CHEMISTRY 1.1



Galway-Mayo Institute of Technology

LibreTexts™

Chemistry 1.1 (GMIT)

This text is disseminated via the Open Education Resource (OER) LibreTexts Project (https://LibreTexts.org) and like the thousands of other texts available within this powerful platform, it is freely available for reading, printing, and "consuming."

The LibreTexts mission is to bring together students, faculty, and scholars in a collaborative effort to provide an accessible, and comprehensive platform that empowers our community to develop, curate, adapt, and adopt openly licensed resources and technologies; through these efforts we can reduce the financial burden born from traditional educational resource costs, ensuring education is more accessible for students and communities worldwide.

Most, but not all, pages in the library have licenses that may allow individuals to make changes, save, and print this book. Carefully consult the applicable license(s) before pursuing such effects. Instructors can adopt existing LibreTexts texts or Remix them to quickly build course-specific resources to meet the needs of their students. Unlike traditional textbooks, LibreTexts' web based origins allow powerful integration of advanced features and new technologies to support learning.



LibreTexts is the adaptable, user-friendly non-profit open education resource platform that educators trust for creating, customizing, and sharing accessible, interactive textbooks, adaptive homework, and ancillary materials. We collaborate with individuals and organizations to champion open education initiatives, support institutional publishing programs, drive curriculum development projects, and more.

The LibreTexts libraries are Powered by NICE CXone Expert and was supported by the Department of Education Open Textbook Pilot Project, the California Education Learning Lab, the UC Davis Office of the Provost, the UC Davis Library, the California State University Affordable Learning Solutions Program, and Merlot. This material is based upon work supported by the National Science Foundation under Grant No. 1246120, 1525057, and 1413739.

Any opinions, findings, and conclusions or recommendations expressed in this material are those of the author(s) and do not necessarily reflect the views of the National Science Foundation nor the US Department of Education.

Have questions or comments? For information about adoptions or adaptions contact info@LibreTexts.org or visit our main website at https://LibreTexts.org.

This text was compiled on 01/11/2026

TABLE OF CONTENTS

Licensing

1: Atoms and Elements

- 1.1: 2.5 The Structure of The Atom
- 1.2: Protons, Neutrons, and Electrons in Atoms
- 1.3: Finding Patterns - The Periodic Law and the Periodic Table
- 1.4: The Average Mass of an Element's Atoms
- 1.5: Molar Mass - Counting Atoms by Weighing Them

2: Molecules, Compounds and Chemical Equations

- 2.1: Chemical Bonds
- 2.2: Representing Compounds- Chemical Formulas and Molecular Models
- 2.3: An Atomic-Level Perspective of Elements and Compounds
- 2.4: Ionic Compounds- Formulas and Names
- 2.5: Molecular Compounds- Formulas and Names
- 2.6: Summary of Inorganic Nomenclature
- 2.7: Composition of Compounds
- 2.8: Determining a Chemical Formula from Experimental Data
- 2.9: Writing and Balancing Chemical Equations

3: Calculations with Chemical Equations and Solution Concentrations

- 3.1: How Much Carbon Dioxide?
- 3.2: 4.3 Limiting Reactant, Theoretical Yield, and Percent Yield
- 3.3: Solution Concentration and Solution Stoichiomentry

4: Quantum Numbers

- 4.1: Quantum Mechanics and The Atom

5: Electron Configurations

- 5.1: Electron Configurations- How Electrons Occupy Orbitals
- 5.2: Electron Configurations, Valence Electrons, and the Periodic Table

6: Lewis Structures

- 6.1: Types of Chemical Bonds
- 6.2: Representing Valance Electrons with Dots
- 6.3: Ionic Bonding
- 6.4: Covalent Bonding- Lewis Structure
- 6.5: Electronegativity and Bond Polarity

7: Chemical Kinetics

- 7.1: Rate of a Chemical Reaction
- 7.2: The Rate Law- The Effect of Concentration on Reaction Rate

8: Chemical Equilibrium

- 8.1: The Equilibrium Constant (K)
- 8.2: Expressing the Equilibrium Constant in Terms of Pressure
- 8.3: Calculating the Equilibrium Constant From Measured Equilibrium Concentrations
- 8.4: Heterogenous Equilibria - Reactions Involving Solids and Liquids
- 8.5: Le Châtelier's Principle- How a System at Equilibrium Responds to Disturbances

9: Organic Chemistry

- 9.1: Alkanes- Saturated Hydrocarbons
- 9.2: Alkenes and Alkynes
- 9.3: Hydrocarbon Reactions
- 9.4: Aromatic Hydrocarbons
- 9.5: Functional Groups
- 9.6: Alcohols
- 9.7: Aldehydes and Ketones
- 9.8: Carboxylic Acids and Esters
- 9.9: Amines

Index

Glossary

Detailed Licensing

Licensing

*A detailed breakdown of this resource's licensing can be found in **Back Matter/Detailed Licensing**.*

CHAPTER OVERVIEW

1: Atoms and Elements

Template:HideTOC

1.1: 2.5 The Structure of The Atom

1.2: Protons, Neutrons, and Electrons in Atoms

1.3: Finding Patterns - The Periodic Law and the Periodic Table

1.4: The Average Mass of an Element’s Atoms

1.5: Molar Mass - Counting Atoms by Weighing Them

1: Atoms and Elements is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

1.1: 2.5 The Structure of The Atom

Learning Objectives

- Write and interpret symbols that depict the atomic number, mass number, and charge of an atom or ion
- Define the atomic mass unit and average atomic mass
- Calculate average atomic mass and isotopic abundance

The development of modern atomic theory revealed much about the inner structure of atoms. It was learned that an atom contains a very small nucleus composed of positively charged protons and uncharged neutrons, surrounded by a much larger volume of space containing negatively charged electrons. The nucleus contains the majority of an atom's mass because protons and neutrons are much heavier than electrons, whereas electrons occupy almost all of an atom's volume. The diameter of an atom is on the order of 10^{-10} m, whereas the diameter of the nucleus is roughly 10^{-15} m—about 100,000 times smaller. For a perspective about their relative sizes, consider this: If the nucleus were the size of a blueberry, the atom would be about the size of a football stadium (Figure **1.1.1**).



Figure **1.1.1**: If an atom could be expanded to the size of a football stadium, the nucleus would be the size of a single blueberry. (credit middle: modification of work by "babyknight"/Wikimedia Commons; credit right: modification of work by Paxson Woelber).

The diagram on the left shows a picture of an atom with a nucleus. The central figure shows a photograph of an American football stadium. The figure on the right shows a photograph of a handful of blueberries.

Atoms—and the protons, neutrons, and electrons that compose them—are extremely small. For example, a carbon atom weighs less than 2×10^{-23} g, and an electron has a charge of less than 2×10^{-19} C (coulomb). When describing the properties of tiny objects such as atoms, we use appropriately small units of measure, such as the atomic mass unit (amu) and the fundamental unit of charge (e). The amu was originally defined based on hydrogen, the lightest element, then later in terms of oxygen. Since 1961, it has been defined with regard to the most abundant isotope of carbon, atoms of which are assigned masses of exactly 12 amu. (This isotope is known as "carbon-12" as will be discussed later in this module.) Thus, one amu is exactly $\mathbf{1/12}$ of the mass of one carbon-12 atom: 1 amu = 1.6605×10^{-24} g. (The Dalton (Da) and the unified atomic mass unit (u) are alternative units that are equivalent to the amu.) The fundamental unit of charge (also called the elementary charge) equals the magnitude of the charge of an electron (e) with e = 1.602×10^{-19} C.

A proton has a mass of 1.0073 amu and a charge of 1+. A neutron is a slightly heavier particle with a mass 1.0087 amu and a charge of zero; as its name suggests, it is neutral. The electron has a charge of 1− and is a much lighter particle with a mass of about 0.00055 amu (it would take about 1800 electrons to equal the mass of one proton. The properties of these fundamental particles are summarized in Table **1.1.1**. (An observant student might notice that the sum of an atom's subatomic particles does not equal the atom's actual mass: The total mass of six protons, six neutrons, and six electrons is 12.0993 amu, slightly larger than the 12.00 amu of an actual carbon-12 atom. This "missing" mass is known as the mass defect, and you will learn about it in the chapter on nuclear chemistry.)

Table **1.1.1**: Properties of Subatomic Particles

Name	Location	Charge (C)	Unit Charge	Mass (amu)	Mass (g)
electron	outside nucleus	-1.602×10^{-19}	1−	0.00055	0.00091×10^{-24}
proton	nucleus	1.602×10^{-19}	1+	1.00727	1.67262×10^{-24}
neutron	nucleus	0	0	1.00866	1.67493×10^{-24}

The number of protons in the nucleus of an atom is its **atomic number** (Z). This is the defining trait of an element: Its value determines the identity of the atom. For example, any atom that contains six protons is the element carbon and has the atomic number 6, regardless of how many neutrons or electrons it may have. A neutral atom must contain the same number of positive and negative charges, so the number of protons equals the number of electrons. Therefore, the atomic number also indicates the number of electrons in an atom. The total number of protons and neutrons in an atom is called its mass number (A). The number of neutrons is therefore the difference between the mass number and the atomic number: A – Z = number of neutrons.

$$\begin{aligned} \text{atomic number (Z)} &= \text{number of protons} \\ \text{mass number (A)} &= \text{number of protons} + \text{number of neutrons} \\ \text{A} - \text{Z} &= \text{number of neutrons} \end{aligned}$$

Atoms are electrically neutral if they contain the same number of positively charged protons and negatively charged electrons. When the numbers of these subatomic particles are *not* equal, the atom is electrically charged and is called an ion. The charge of an atom is defined as follows:

$$\text{Atomic charge} = \text{number of protons} - \text{number of electrons}$$

As will be discussed in more detail later in this chapter, atoms (and molecules) typically acquire charge by gaining or losing electrons. An atom that gains one or more electrons will exhibit a negative charge and is called an anion. Positively charged atoms called cations are formed when an atom loses one or more electrons. For example, a neutral sodium atom (Z = 11) has 11 electrons. If this atom loses one electron, it will become a cation with a 1+ charge (11 − 10 = 1+). A neutral oxygen atom (Z = 8) has eight electrons, and if it gains two electrons it will become an anion with a 2− charge (8 − 10 = 2−).

Example 1.1.1: Composition of an Atom

Iodine is an essential trace element in our diet; it is needed to produce thyroid hormone. Insufficient iodine in the diet can lead to the development of a goiter, an enlargement of the thyroid gland (Figure 1.1.2).



(a)



(b)

Figure **1.1.2**: (a) Insufficient iodine in the diet can cause an enlargement of the thyroid gland called a goiter. (b) The addition of small amounts of iodine to salt, which prevents the formation of goiters, has helped eliminate this concern in the US where salt consumption is high. (credit a: modification of work by "Almazi"/Wikimedia Commons; credit b: modification of work by Mike Mozart)

Figure A shows a photo of a person who has a very swollen thyroid in his or her neck. Figure B shows a photo of a canister of Morton iodized salt.

The addition of small amounts of iodine to table salt (iodized salt) has essentially eliminated this health concern in the United States, but as much as 40% of the world's population is still at risk of iodine deficiency. The iodine atoms are added as anions, and each has a 1− charge and a mass number of 127. Determine the numbers of protons, neutrons, and electrons in one of these iodine anions.

Solution

The atomic number of iodine (53) tells us that a neutral iodine atom contains 53 protons in its nucleus and 53 electrons outside its nucleus. Because the sum of the numbers of protons and neutrons equals the mass number, 127, the number of neutrons is 74 (127 − 53 = 74). Since the iodine is added as a 1− anion, the number of electrons is 54 [53 – (1–) = 54].

? Exercise 1.1.1

An ion of platinum has a mass number of 195 and contains 74 electrons. How many protons and neutrons does it contain, and what is its charge?

Answer

78 protons; 117 neutrons; charge is 4+

Chemical Symbols

A chemical symbol is an abbreviation that we use to indicate an element or an atom of an element. For example, the symbol for mercury is Hg (Figure **1.1.3**). We use the same symbol to indicate one atom of mercury (microscopic domain) or to label a container of many atoms of the element mercury (macroscopic domain).



Figure **1.1.3**: The symbol Hg represents the element mercury regardless of the amount; it could represent one atom of mercury or a large amount of mercury. from Wikipedia (user: Materialscientist).

The symbols for several common elements and their atoms are listed in Table **1.1.2**. Some symbols are derived from the common name of the element; others are abbreviations of the name in another language. Symbols have one or two letters, for example, H for hydrogen and Cl for chlorine. To avoid confusion with other notations, only the first letter of a symbol is capitalized. For example, Co is the symbol for the element cobalt, but CO is the notation for the compound carbon monoxide, which contains atoms of the elements carbon (C) and oxygen (O). All known elements and their symbols are in the periodic table.

Table **1.1.2**: Some Common Elements and Their Symbols

Element	Symbol	Element	Symbol
aluminum	Al	iron	Fe (from *ferrum*)
bromine	Br	lead	Pb (from *plumbum*)
calcium	Ca	magnesium	Mg
carbon	C	mercury	Hg (from *hydrargyrum*)
chlorine	Cl	nitrogen	N
chromium	Cr	oxygen	O
cobalt	Co	potassium	K (from *kalium*)
copper	Cu (from *cuprum*)	silicon	Si
fluorine	F	silver	Ag (from *argentum*)
gold	Au (from *aurum*)	sodium	Na (from *natrium*)
helium	He	sulfur	S
hydrogen	H	tin	Sn (from *stannum*)
iodine	I	zinc	Zn

Traditionally, the discoverer (or discoverers) of a new element names the element. However, until the name is recognized by the International Union of Pure and Applied Chemistry (IUPAC), the recommended name of the new element is based on the Latin word(s) for its atomic number. For example, element 106 was called unnilhexium (Unh), element 107 was called unnilseptium (Uns), and element 108 was called unniloctium (Uno) for several years. These elements are now named after scientists or locations; for example, element 106 is now known as *seaborgium* (Sg) in honor of Glenn Seaborg, a Nobel Prize winner who was active in the discovery of several heavy elements.

Isotopes

The symbol for a specific isotope of any element is written by placing the mass number as a superscript to the left of the element symbol (Figure **1.1.4**). The atomic number is sometimes written as a subscript preceding the symbol, but since this number defines the element's identity, as does its symbol, it is often omitted. For example, magnesium exists as a mixture of three isotopes, each with an atomic number of 12 and with mass numbers of 24, 25, and 26, respectively. These isotopes can be identified as ^{24}Mg, ^{25}Mg, and ^{26}Mg. These isotope symbols are read as "element, mass number" and can be symbolized consistent with this reading. For instance, ^{24}Mg is read as "magnesium 24," and can be written as "magnesium-24" or "Mg-24." ^{25}Mg is read as "magnesium 25," and can be written as "magnesium-25" or "Mg-25." All magnesium atoms have 12 protons in their nucleus. They differ only because a ^{24}Mg atom has 12 neutrons in its nucleus, a ^{25}Mg atom has 13 neutrons, and a ^{26}Mg has 14 neutrons.




Figure **1.1.4**: The symbol for an atom indicates the element via its usual two-letter symbol, the mass number as a left superscript, the atomic number as a left subscript (sometimes omitted), and the charge as a right superscript.

This diagram shows the symbol for helium, "H e." The number to the upper left of the symbol is the mass number, which is 4. The number to the upper right of the symbol is the charge which is positive 2. The number to the lower left of the symbol is the atomic number, which is 2. This number is often omitted. Also shown is "M g" which stands for magnesium It has a mass number of 24, a charge of positive 2, and an atomic number of 12.

Information about the naturally occurring isotopes of elements with atomic numbers 1 through 10 is given in Table **1.1.2**. Note that in addition to standard names and symbols, the isotopes of hydrogen are often referred to using common names and accompanying symbols. Hydrogen-2, symbolized ^{2}H, is also called deuterium and sometimes symbolized D. Hydrogen-3, symbolized ^{3}H, is also called tritium and sometimes symbolized T.

Table **1.1.2**: Nuclear Compositions of Atoms of the Very Light Elements

Element	Symbol	Atomic Number	Number of Protons	Number of Neutrons	Mass (amu)	% Natural Abundance
hydrogen	$^{1}_{1}\mathrm{H}$ (protium)	1	1	0	1.0078	99.989
	$^{2}_{1}\mathrm{H}$ (deuterium)	1	1	1	2.0141	0.0115
	$^{3}_{1}\mathrm{H}$ (tritium)	1	1	2	3.01605	— (trace)
helium	$^{3}_{2}\mathrm{He}$	2	2	1	3.01603	0.00013
	$^{4}_{2}\mathrm{He}$	2	2	2	4.0026	100
lithium	$^{6}_{3}\mathrm{Li}$	3	3	3	6.0151	7.59
	$^{7}_{3}\mathrm{Li}$	3	3	4	7.0160	92.41
beryllium	$^{9}_{4}\mathrm{Be}$	4	4	5	9.0122	100
boron	$^{10}_{5}\mathrm{B}$	5	5	5	10.0129	19.9
	$^{11}_{5}\mathrm{B}$	5	5	6	11.0093	80.1
carbon	$^{12}_{6}\mathrm{C}$	6	6	6	12.0000	98.89
	$^{13}_{6}\mathrm{C}$	6	6	7	13.0034	1.11
	$^{14}_{6}\mathrm{C}$	6	6	8	14.0032	— (trace)
nitrogen	$^{14}_{7}\mathrm{N}$	7	7	7	14.0031	99.63
	$^{15}_{7}\mathrm{N}$	7	7	8	15.0001	0.37
oxygen	$^{16}_{8}\mathrm{O}$	8	8	8	15.9949	99.757
	$^{17}_{8}\mathrm{O}$	8	8	9	16.9991	0.038
	$^{18}_{8}\mathrm{O}$	8	8	10	17.9992	0.205
fluorine	$^{19}_{9}\mathrm{F}$	9	9	10	18.9984	100
neon	$^{20}_{10}\mathrm{Ne}$	10	10	10	19.9924	90.48
	$^{21}_{10}\mathrm{Ne}$	10	10	11	20.9938	0.27
	$^{22}_{10}\mathrm{Ne}$	10	10	12	21.9914	9.25

Atomic Mass

Because each proton and each neutron contribute approximately one amu to the mass of an atom, and each electron contributes far less, the atomic mass of a single atom is approximately equal to its mass number (a whole number). However, the average masses of atoms of most elements are not whole numbers because most elements exist naturally as mixtures of two or more isotopes.

The mass of an element shown in a periodic table or listed in a table of atomic masses is a weighted, average mass of all the isotopes present in a naturally occurring sample of that element. This is equal to the sum of each individual isotope's mass multiplied by its fractional abundance.

$$\text{average mass} = \sum_i (\text{fractional abundance} \times \text{isotopic mass})_i$$

For example, the element boron is composed of two isotopes: About 19.9% of all boron atoms are ^{10}B with a mass of 10.0129 amu, and the remaining 80.1% are ^{11}B with a mass of 11.0093 amu. The average atomic mass for boron is calculated to be:

$$\begin{aligned}\text{boron average mass} &= (0.199 \times 10.0129\ \text{amu}) + (0.801 \times 11.0093\ \text{amu}) \\ &= 1.99\ \text{amu} + 8.82\ \text{amu} \\ &= 10.81\ \text{amu}\end{aligned}$$

It is important to understand that no single boron atom weighs exactly 10.8 amu; 10.8 amu is the average mass of all boron atoms, and individual boron atoms weigh either approximately 10 amu or 11 amu.

✔ Example 1.1.2: Calculation of Average Atomic Mass

A meteorite found in central Indiana contains traces of the noble gas neon picked up from the solar wind during the meteorite's trip through the solar system. Analysis of a sample of the gas showed that it consisted of 91.84% ^{20}Ne (mass 19.9924 amu), 0.47% ^{21}Ne (mass 20.9940 amu), and 7.69% ^{22}Ne (mass 21.9914 amu). What is the average mass of the neon in the solar wind?

Solution

$$\begin{aligned}\text{average mass} &= (0.9184 \times 19.9924\ \text{amu}) + (0.0047 \times 20.9940\ \text{amu}) + (0.0769 \times 21.9914\ \text{amu}) \\ &= (18.36 + 0.099 + 1.69)\ \text{amu} \\ &= 20.15\ \text{amu}\end{aligned}$$

The average mass of a neon atom in the solar wind is 20.15 amu. (The average mass of a terrestrial neon atom is 20.1796 amu. This result demonstrates that we may find slight differences in the natural abundance of isotopes, depending on their origin.)

? Exercise 1.1.2

A sample of magnesium is found to contain 78.70% of ^{24}Mg atoms (mass 23.98 amu), 10.13% of ^{25}Mg atoms (mass 24.99 amu), and 11.17% of ^{26}Mg atoms (mass 25.98 amu). Calculate the average mass of a Mg atom.

Answer

24.31 amu

We can also do variations of this type of calculation, as shown in the next example.

✔ Example 1.1.3: Calculation of Percent Abundance

Naturally occurring chlorine consists of ^{35}Cl (mass 34.96885 amu) and ^{37}Cl (mass 36.96590 amu), with an average mass of 35.453 amu. What is the percent composition of Cl in terms of these two isotopes?

Solution

The average mass of chlorine is the fraction that is ^{35}Cl times the mass of ^{35}Cl plus the fraction that is ^{37}Cl times the mass of ^{37}Cl.

$$\text{average mass} = (\text{fraction of } ^{35}\text{Cl} \times \text{mass of } ^{35}\text{Cl}) + (\text{fraction of } ^{37}\text{Cl} \times \text{mass of } ^{37}\text{Cl})$$

If we let x represent the fraction that is ^{35}Cl, then the fraction that is ^{37}Cl is represented by $1.00 - x$.

(The fraction that is ^{35}Cl + the fraction that is ^{37}Cl must add up to 1, so the fraction of ^{37}Cl must equal 1.00 − the fraction of ^{35}Cl.)

Substituting this into the average mass equation, we have:

$$\begin{aligned}35.453\ \text{amu} &= (x \times 34.96885\ \text{amu}) + [(1.00 - x) \times 36.96590\ \text{amu}] \\ 35.453 &= 34.96885x + 36.96590 - 36.96590x \\ 1.99705x &= 1.513 \\ x &= \frac{1.513}{1.99705} = 0.7576\end{aligned}$$

So solving yields: $x = 0.7576$, which means that $1.00 - 0.7576 = 0.2424$. Therefore, chlorine consists of 75.76% ^{35}Cl and 24.24% ^{37}Cl.

? Exercise 1.1.3

Naturally occurring copper consists of ^{63}Cu (mass 62.9296 amu) and ^{65}Cu (mass 64.9278 amu), with an average mass of 63.546 amu. What is the percent composition of Cu in terms of these two isotopes?

Answer

69.15% Cu-63 and 30.85% Cu-65




Figure **1.1.5**: Analysis of zirconium in a mass spectrometer produces a mass spectrum with peaks showing the different isotopes of Zr.

The left diagram shows how a mass spectrometer works. The graph to the right of the spectrometer shows a mass spectrum of zirconium. The relative abundance, as a percentage from 0 to 100, is graphed on the y axis, and the mass to charge ratio is graphed on the x axis. The sample contains five different isomers of zirconium.

The occurrence and natural abundances of isotopes can be experimentally determined using an instrument called a mass spectrometer. Mass spectrometry (MS) is widely used in chemistry, forensics, medicine, environmental science, and many other fields to analyze and help identify the substances in a sample of material. In a typical mass spectrometer (Figure **1.1.5**), the sample is vaporized and exposed to a high-energy electron beam that causes the sample's atoms (or molecules) to become electrically charged, typically by losing one or more electrons. These cations then pass through a (variable) electric or magnetic field that deflects each cation's path to an extent that depends on both its mass and charge (similar to how the path of a large steel ball bearing rolling past a magnet is deflected to a lesser extent that that of a small steel BB). The ions are detected, and a plot of the relative number of ions generated versus their mass-to-charge ratios (a *mass spectrum*) is made. The height of each vertical feature or peak in a mass spectrum is proportional to the fraction of cations with the specified mass-to-charge ratio. Since its initial use during the development of modern atomic theory, MS has evolved to become a powerful tool for chemical analysis in a wide range of applications.



Video* 1.1.1: Watch this video from the Royal Society for Chemistry for a brief description of the rudiments of mass spectrometry.*

Summary

An atom consists of a small, positively charged nucleus surrounded by electrons. The nucleus contains protons and neutrons; its diameter is about 100,000 times smaller than that of the atom. The mass of one atom is usually expressed in atomic mass units (amu), which is referred to as the atomic mass. An amu is defined as exactly $\mathbf{1/12}$ of the mass of a carbon-12 atom and is equal to 1.6605×10^{-24} g.

Protons are relatively heavy particles with a charge of 1+ and a mass of 1.0073 amu. Neutrons are relatively heavy particles with no charge and a mass of 1.0087 amu. Electrons are light particles with a charge of 1− and a mass of 0.00055 amu. The number of protons in the nucleus is called the atomic number (Z) and is the property that defines an atom's elemental identity. The sum of the numbers of protons and neutrons in the nucleus is called the mass number and, expressed in amu, is approximately equal to the mass of the atom. An atom is neutral when it contains equal numbers of electrons and protons.

Isotopes of an element are atoms with the same atomic number but different mass numbers; isotopes of an element, therefore, differ from each other only in the number of neutrons within the nucleus. When a naturally occurring element is composed of several isotopes, the atomic mass of the element represents the average of the masses of the isotopes involved. A chemical symbol identifies the atoms in a substance using symbols, which are one-, two-, or three-letter abbreviations for the atoms.

Key Equations

- $\mathbf{\text{average mass} = \sum_i (\text{fractional abundance} \times \text{isotopic mass})_i}$

Glossary

anion
negatively charged atom or molecule (contains more electrons than protons)

atomic mass
average mass of atoms of an element, expressed in amu

atomic mass unit (amu)
(also, unified atomic mass unit, u, or Dalton, Da) unit of mass equal to $\frac{1}{12}$ of the mass of a ^{12}C atom

atomic number (Z)
number of protons in the nucleus of an atom

cation
positively charged atom or molecule (contains fewer electrons than protons)

chemical symbol

one-, two-, or three-letter abbreviation used to represent an element or its atoms

Dalton (Da)

alternative unit equivalent to the atomic mass unit

fundamental unit of charge

(also called the elementary charge) equals the magnitude of the charge of an electron (e) with $e = 1.602 \times 10^{-19}$ C

ion

electrically charged atom or molecule (contains unequal numbers of protons and electrons)

mass number (A)

sum of the numbers of neutrons and protons in the nucleus of an atom

unified atomic mass unit (u)

alternative unit equivalent to the atomic mass unit

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

1.1: 2.5 The Structure of The Atom is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.4: Atomic Structure and Symbolism** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

1.2: Protons, Neutrons, and Electrons in Atoms

1.2: Protons, Neutrons, and Electrons in Atoms is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

1.3: Finding Patterns - The Periodic Law and the Periodic Table

Learning Objectives

- To become familiar with the organization of the periodic table.

Rutherford's nuclear model of the atom helped explain why atoms of different elements exhibit different chemical behavior. The identity of an element is defined by its *atomic number (Z)*, the number of protons in the nucleus of an atom of the element. The atomic number is therefore different for each element. The known elements are arranged in order of increasing Z in the *periodic table* (Figure **1.3.1**). The rationale for the peculiar format of the periodic table is explained later. Each element is assigned a unique one-, two-, or three-letter symbol. The names of the elements are listed in the periodic table, along with their symbols, atomic numbers, and atomic masses. The chemistry of each element is determined by its number of protons and electrons. In a neutral atom, the number of electrons equals the number of protons.




Figure **1.3.1**: The Periodic Table Showing the Elements in Order of Increasing Z. The metals are on the bottom left in the periodic table, and the nonmetals are at the top right. The semimetals lie along a diagonal line separating the metals and nonmetals. An interactive Periodic table can be found Periodic Table of the Elements, LibreTexts. (CC-BY-SA-NC 3.0; Anonymous via LibreTexts)

The elements are arranged in a periodic table, which is probably the single most important learning aid in chemistry. It summarizes huge amounts of information about the elements in a way that facilitates the prediction of many of their properties and chemical reactions. The elements are arranged in seven horizontal rows, in order of increasing atomic number from left to right and top to bottom. The rows are called periods, and they are numbered from 1 to 7. The elements are stacked in such a way that elements with similar chemical properties form vertical columns, called groups, numbered from 1 to 18 (older periodic tables use a system based on roman numerals). Groups 1, 2, and 13–18 are the main group elements, listed as A in older tables. Groups 3–12 are in the middle of the periodic table and are the transition elements, listed as B in older tables. The two rows of 14 elements at the bottom of the periodic table are the lanthanides and the actinides, whose positions in the periodic table are indicated in group 3.

Metals, Nonmetals, and Semimetals

The heavy orange zigzag line running diagonally from the upper left to the lower right through groups 13–16 in Figure **1.3.1** divides the elements into metals (in blue, below and to the left of the line) and nonmetals (in bronze, above and to the right of the line).

Gold-colored lements that lie along the diagonal line exhibit properties intermediate between metals and nonmetals; they are called semimetals.

The distinction between metals and nonmetals is one of the most fundamental in chemistry. Metals—such as copper or gold—are good conductors of electricity and heat; they can be pulled into wires because they are ductile; they can be hammered or pressed into thin sheets or foils because they are malleable; and most have a shiny appearance, so they are lustrous. The vast majority of the known elements are metals. Of the metals, only mercury is a liquid at room temperature and pressure; all the rest are solids.

Nonmetals, in contrast, are generally poor conductors of heat and electricity and are not lustrous. Nonmetals can be gases (such as chlorine), liquids (such as bromine), or solids (such as iodine) at room temperature and pressure. Most solid nonmetals are brittle, so they break into small pieces when hit with a hammer or pulled into a wire. As expected, semimetals exhibit properties intermediate between metals and nonmetals.

✔ Example 1.3.1: Classifying Elements

Based on its position in the periodic table, do you expect selenium to be a metal, a nonmetal, or a semimetal?

Given: element

Asked for: classification

Strategy:

Find selenium in the periodic table shown in Figure **1.3.1** and then classify the element according to its location.

Solution:

The atomic number of selenium is 34, which places it in period 4 and group 16. In Figure **1.3.1**, selenium lies above and to the right of the diagonal line marking the boundary between metals and nonmetals, so it should be a nonmetal. Note, however, that because selenium is close to the metal-nonmetal dividing line, it would not be surprising if selenium were similar to a semimetal in some of its properties.

? Exercise 1.3.1

Based on its location in the periodic table, do you expect indium to be a nonmetal, a metal, or a semimetal?

Answer

metal

As previously noted, the periodic table is arranged so that elements with similar chemical behaviors are in the same group. Chemists often make general statements about the properties of the elements in a group using descriptive names with historical origins. For example, the elements of Group 1 are known as the alkali metals, Group 2 are the alkaline earth metals, Group 17 are the halogens, and Group 18 are the noble gases.

Group 1: The Alkali Metals

The alkali metals are lithium, sodium, potassium, rubidium, cesium, and francium. Hydrogen is unique in that it is generally placed in Group 1, but it is not a metal. The compounds of the alkali metals are common in nature and daily life. One example is table salt (sodium chloride); lithium compounds are used in greases, in batteries, and as drugs to treat patients who exhibit manic-depressive, or bipolar, behavior. Although lithium, rubidium, and cesium are relatively rare in nature, and francium is so unstable and highly radioactive that it exists in only trace amounts, sodium and potassium are the seventh and eighth most abundant elements in Earth's crust, respectively.

Group 2: The Alkaline Earth Metals

The alkaline earth metals are beryllium, magnesium, calcium, strontium, barium, and radium. Beryllium, strontium, and barium are rare, and radium is unstable and highly radioactive. In contrast, calcium and magnesium are the fifth and sixth most abundant elements on Earth, respectively; they are found in huge deposits of limestone and other minerals.

Group 17: The Halogens

The halogens are fluorine, chlorine, bromine, iodine, and astatine. The name halogen is derived from the Greek words for “salt forming,” which reflects that all the halogens react readily with metals to form compounds, such as sodium chloride and calcium chloride (used in some areas as road salt).

Compounds that contain the fluoride ion are added to toothpaste and the water supply to prevent dental cavities. Fluorine is also found in Teflon coatings on kitchen utensils. Although chlorofluorocarbon propellants and refrigerants are believed to lead to the depletion of Earth’s ozone layer and contain both fluorine and chlorine, the latter is responsible for the adverse effect on the ozone layer. Bromine and iodine are less abundant than chlorine, and astatine is so radioactive that it exists in only negligible amounts in nature.

Group 18: The Noble Gases

The noble gases are helium, neon, argon, krypton, xenon, and radon. Because the noble gases are composed of only single atoms, they are called monatomic. At room temperature and pressure, they are unreactive gases. Because of their lack of reactivity, for many years they were called inert gases or rare gases. However, the first chemical compounds containing the noble gases were prepared in 1962. Although the noble gases are relatively minor constituents of the atmosphere, natural gas contains substantial amounts of helium. Because of its low reactivity, argon is often used as an unreactive (inert) atmosphere for welding and in light bulbs. The red light emitted by neon in a gas discharge tube is used in neon lights.

> *The noble gases are unreactive at room temperature and pressure.*

Summary

The periodic table is used as a predictive tool. It arranges of the elements in order of increasing atomic number. Elements that exhibit similar chemistry appear in vertical columns called groups (numbered 1–18 from left to right); the seven horizontal rows are called periods. Some of the groups have widely-used common names, including the alkali metals (Group 1) and the alkaline earth metals (Group 2) on the far left, and the halogens (Group 17) and the noble gases (Group 18) on the far right. The elements can be broadly divided into metals, nonmetals, and semimetals. Semimetals exhibit properties intermediate between those of metals and nonmetals. Metals are located on the left of the periodic table, and nonmetals are located on the upper right. They are separated by a diagonal band of semimetals. Metals are lustrous, good conductors of electricity, and readily shaped (they are ductile and malleable), whereas solid nonmetals are generally brittle and poor electrical conductors. Other important groupings of elements in the periodic table are the main group elements, the transition metals, the lanthanides, and the actinides.

1.3: Finding Patterns - The Periodic Law and the Periodic Table is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.5: The Periodic Table** is licensed CC BY-NC-SA 3.0.

1.4: The Average Mass of an Element's Atoms

Learning Objectives

- to know the meaning of isotopes and atomic masses.

Atomic and Molecular Weights

The subscripts in chemical formulas, and the coefficients in chemical equations represent *exact* quantities. $\mathbf{H_2O}$, for example, indicates that a water molecule comprises exactly **two** atoms of hydrogen and **one** atom of oxygen. The following equation:

$$\mathrm{C_3H_8\,(g) + 5\,O_2\,(g) \rightarrow 3\,CO_2\,(g) + 4\,H_2O\,(l)} \tag{1.4.1}$$

not only tells us that propane reacts with oxygen to produce carbon dioxide and water, but that ***1*** molecule of propane reacts with ***5*** molecules of oxygen to produce ***3*** molecules of carbon dioxide and ***4*** molecules of water. Since counting individual atoms or molecules is a little difficult, quantitative aspects of chemistry rely on knowing the *masses* of the compounds involved.

Atoms of different elements have different masses. Early work on the separation of water into its constituent elements (hydrogen and oxygen) indicated that 100 grams of water contained 11.1 grams of hydrogen and 88.9 grams of oxygen:

$$\mathrm{100\ grams\ Water \rightarrow 11.1\ grams\ Hydrogen + 88.9\ grams\ Oxygen} \tag{1.4.2}$$

Later, scientists discovered that water was composed of ***two atoms*** of hydrogen ***for each atom*** of oxygen. Therefore, in the above analysis, *in the 11.1 grams of hydrogen there were twice as many atoms as in the 88.9 grams of oxygen.* Therefore, an oxygen atom must weigh about 16 times as much as a hydrogen atom:

$$\frac{\frac{88.9\ g\ Oxygen}{1\ atom}}{\frac{111\ g\ Hydrogen}{2\ atoms}} = 16 \tag{1.4.3}$$

Hydrogen, the lightest element, was assigned a relative mass of '1', and the other elements were assigned 'atomic masses' relative to this value for hydrogen. Thus, oxygen was assigned an atomic mass of 16. We now know that a **hydrogen** atom has a mass of **1.6735 x 10^{-24}** grams, and that the **oxygen** atom has a mass of **2.6561 X 10^{-23}** grams. As we saw earlier, it is convenient to use a reference unit when dealing with such small numbers: the **atomic mass unit**. The atomic mass unit (***amu***) was not standardized against hydrogen, but rather, against the ^{12}C isotope of **carbon** (***amu*** = **12**).

Thus, the mass of the **hydrogen atom** (^{1}H) is 1.0080 *amu*, and the mass of **an oxygen atom** (^{16}O) is 15.995 *amu*. Once the masses of atoms were determined, the ***amu*** could be assigned an actual value:

1 ***amu*** = 1.66054 x 10^{-24} **grams** conversely: 1 **gram** = 6.02214 x 10^{23} ***amu***



Mass Numbers and Atomic Mass of Elements: Mass Numbers and Atomic Mass of Elements, YouTube(opens in new window) [youtu.be]

Average Atomic Mass

Although the masses of the electron, the proton, and the neutron are known to a high degree of precision (Table 2.3.1), the mass of any given atom is not simply the sum of the masses of its electrons, protons, and neutrons. For example, the ratio of the masses of ^{1}H (hydrogen) and ^{2}H (deuterium) is actually 0.500384, rather than 0.49979 as predicted from the numbers of neutrons and protons present. Although the difference in mass is small, it is extremely important because it is the source of the huge amounts of energy released in nuclear reactions.

Because atoms are much too small to measure individually and do not have charges, there is no convenient way to accurately measure absolute atomic masses. Scientists can measure relative atomic masses very accurately, however, using an instrument called a mass spectrometer. The technique is conceptually similar to the one Thomson used to determine the mass-to-charge ratio of the electron. First, electrons are removed from or added to atoms or molecules, thus producing charged particles called ions. When an electric field is applied, the ions are accelerated into a separate chamber where they are deflected from their initial trajectory by a magnetic field, like the electrons in Thomson's experiment. The extent of the deflection depends on the mass-to-charge ratio of the ion. By measuring the relative deflection of ions that have the same charge, scientists can determine their relative masses (Figure **1.4.1**). Thus it is not possible to calculate absolute atomic masses accurately by simply adding together the masses of the electrons, the protons, and the neutrons, and absolute atomic masses cannot be measured, but relative masses can be measured very accurately. It is actually rather common in chemistry to encounter a quantity whose magnitude can be measured only relative to some other quantity, rather than absolutely. We will encounter many other examples later in this text. In such cases, chemists usually define a standard by arbitrarily assigning a numerical value to one of the quantities, which allows them to calculate numerical values for the rest.




Figure **1.4.1**: Determining Relative Atomic Masses Using a Mass Spectrometer. Chlorine consists of two isotopes, ^{35}Cl and ^{37}Cl, in approximately a 3:1 ratio. (a) When a sample of elemental chlorine is injected into the mass spectrometer, electrical energy is used to dissociate the Cl_2 molecules into chlorine atoms and convert the chlorine atoms to Cl^+ ions. The ions are then accelerated into a magnetic field. The extent to which the ions are deflected by the magnetic field depends on their relative mass-to-charge ratios. Note that the lighter $^{35}Cl^+$ ions are deflected more than the heavier $^{37}Cl^+$ ions. By measuring the relative deflections of the ions, chemists can determine their mass-to-charge ratios and thus their masses. (b) Each peak in the mass spectrum corresponds to an ion with a particular mass-to-charge ratio. The abundance of the two isotopes can be determined from the heights of the peaks.

A: Diagram of a mass spectrometer, showing analysis of gaseous chlorine. B: Mass spectrum of chlorine.

The arbitrary standard that has been established for describing atomic mass is the atomic mass unit (amu or u), defined as one-twelfth of the mass of one atom of ^{12}C. Because the masses of all other atoms are calculated relative to the ^{12}C standard, ^{12}C is the only atom listed in Table 2.3.2 whose exact atomic mass is equal to the mass number. Experiments have shown that 1 amu = 1.66×10^{-24} g.

Mass spectrometric experiments give a value of 0.167842 for the ratio of the mass of ^{2}H to the mass of ^{12}C, so the **absolute mass** of ^{2}H is

$$\frac{\text{mass of } ^{2}\text{H}}{\text{mass of } ^{12}\text{C}} \times \text{mass of } ^{12}\text{C} = 0.167842 \times 12 \text{ amu} = 2.104104 \text{ amu} \tag{1.4.4}$$

The masses of the other elements are determined in a similar way.

The periodic table lists the atomic masses of all the elements. Comparing these values with those given for some of the isotopes in Table 2.3.2 reveals that the atomic masses given in the periodic table never correspond exactly to those of any of the isotopes. Because most elements exist as mixtures of several stable isotopes, the atomic mass of an element is defined as the weighted average of the masses of the isotopes. For example, naturally occurring carbon is largely a mixture of two isotopes: 98.89% ^{12}C (mass = 12 amu by definition) and 1.11% ^{13}C (mass = 13.003355 amu). The percent abundance of ^{14}C is so low that it can be ignored in this calculation. The average atomic mass of carbon is then calculated as follows:

$$(0.9889 \times 12 \text{ amu}) + (0.0111 \times 13.003355 \text{ amu}) = 12.01 \text{ amu} \quad (1.4.5)$$

Carbon is predominantly ^{12}C, so its average atomic mass should be close to 12 amu, which is in agreement with this calculation.

The value of 12.01 is shown under the symbol for C in the periodic table, although without the abbreviation amu, which is customarily omitted. Thus the tabulated atomic mass of carbon or any other element is the weighted average of the masses of the naturally occurring isotopes.

Example 1.4.1: Bromine

Naturally occurring bromine consists of the two isotopes listed in the following table:

Solutions to Example 2.4.1

Isotope	Exact Mass (amu)	Percent Abundance (%)
^{79}Br	78.9183	50.69
^{81}Br	80.9163	49.31

Calculate the atomic mass of bromine.

Given: exact mass and percent abundance

Asked for: atomic mass

Strategy:

A. Convert the percent abundances to decimal form to obtain the mass fraction of each isotope.
B. Multiply the exact mass of each isotope by its corresponding mass fraction (percent abundance ÷ 100) to obtain its weighted mass.
C. Add together the weighted masses to obtain the atomic mass of the element.
D. Check to make sure that your answer makes sense.

Solution:

A The atomic mass is the weighted average of the masses of the isotopes. In general, we can write

atomic mass of element = [(mass of isotope 1 in amu) (mass fraction of isotope 1)] + [(mass of isotope 2) (mass fraction of isotope 2)] + …

Bromine has only two isotopes. Converting the percent abundances to mass fractions gives

$$^{79}\text{Br}: \frac{50.69}{100} = 0.5069$$

$$^{81}\text{Br}: \frac{49.31}{100} = 0.4931$$

B Multiplying the exact mass of each isotope by the corresponding mass fraction gives the isotope's weighted mass:

$$^{79}\text{Br}: 79.9183\ amu \times 0.5069 = 40.00\ amu$$

$$^{81}\text{Br}: 80.9163\ amu \times 0.4931 = 39.90\ amu$$

C The sum of the weighted masses is the atomic mass of bromine is

40.00 amu + 39.90 amu = 79.90 amu

D This value is about halfway between the masses of the two isotopes, which is expected because the percent abundance of each is approximately 50%.

Exercise 1.4.1

Magnesium has the three isotopes listed in the following table:

Solutions to Example 2.4.1

Isotope	Exact Mass (amu)	Percent Abundance (%)
^{24}Mg	23.98504	78.70
^{25}Mg	24.98584	10.13
^{26}Mg	25.98259	11.17

Use these data to calculate the atomic mass of magnesium.

Answer

24.31 amu



Finding the Averaged Atomic Weight of an Element: Finding the Averaged Atomic Weight of an Element(opens in new window) [youtu.be]

Summary

The mass of an atom is a weighted average that is largely determined by the number of its protons and neutrons, whereas the number of protons and electrons determines its charge. Each atom of an element contains the same number of protons, known as the atomic number (Z). Neutral atoms have the same number of electrons and protons. Atoms of an element that contain different numbers of neutrons are called isotopes. Each isotope of a given element has the same atomic number but a different mass number (A), which is the sum of the numbers of protons and neutrons. The relative masses of atoms are reported using the atomic mass unit (amu), which is defined as one-twelfth of the mass of one atom of carbon-12, with 6 protons, 6 neutrons, and 6 electrons. The atomic mass of an element is the weighted average of the masses of the naturally occurring isotopes. When one or more electrons are added to or removed from an atom or molecule, a charged particle called an ion is produced, whose charge is indicated by a superscript after the symbol.

1.4: The Average Mass of an Element's Atoms is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.4: Atomic Mass** is licensed CC BY-NC-SA 3.0.

1.5: Molar Mass - Counting Atoms by Weighing Them

Learning Objectives

Make sure you thoroughly understand the following essential ideas:

- Define *Avogadro's number* and explain why it is important to know.
- Define the *mole*. Be able to calculate the number of moles in a given mass of a substance, or the mass corresponding to a given number of moles.
- Define *molecular weight*, *formula weight*, and *molar mass*; explain how the latter differs from the first two.
- Be able to find the number of atoms or molecules in a given weight of a substance.
- Find the *molar volume* of a solid or liquid, given its density and molar mass.
- Explain how the molar volume of a metallic solid can lead to an estimate of atomic diameter.

The chemical changes we observe always involve *discrete numbers of atoms* that rearrange themselves into new configurations. These numbers are HUGE— far too large in magnitude for us to count or even visualize, but they are still *numbers*, and we need to have a way to deal with them. We also need a bridge between these numbers, which we are unable to measure directly, and the weights of substances, which we do measure and observe. The *mole concept* provides this bridge, and is central to all of quantitative chemistry.

Counting Atoms: Avogadro's Number

Owing to their tiny size, atoms and molecules cannot be counted by direct observation. But much as we do when "counting" beans in a jar, we can estimate the number of particles in a sample of an element or compound if we have some idea of the volume occupied by each particle and the volume of the container. Once this has been done, we know the number of formula units (to use the most general term for any combination of atoms we wish to define) in any arbitrary weight of the substance. The number will of course depend both on the formula of the substance and on the weight of the sample. However, if we consider a weight of substance that is the same as its formula (molecular) weight expressed in grams, we have only one number to know: **Avogadro's number**.

Avogadro's number is known to ten significant digits:

$$N_A = 6.022141527 \times 10^{23}. \tag{1.5.1}$$

However, you only need to know it to three significant figures:

$$N_A \approx 6.02 \times 10^{23}. \tag{1.5.2}$$

So 6.02×10^{23} of *what*? Well, of anything you like: apples, stars in the sky, burritos. However, the only *practical* use for N_A is to have a more convenient way of expressing the huge numbers of the tiny particles such as atoms or molecules that we deal with in chemistry. Avogadro's number is a *collective number*, just like a dozen. Students can think of 6.02×10^{23} as the "chemist's dozen".

Before getting into the use of Avogadro's number in problems, take a moment to convince yourself of the reasoning embodied in the following examples.

Example 1.5.1: Mass ratio from atomic weights

The atomic weights of oxygen and carbon are 16.0 and 12.0 atomic mass units (u), respectively. How much heavier is the oxygen atom in relation to carbon?

Solution

Atomic weights represent the relative masses of different kinds of atoms. This means that the atom of oxygen has a mass that is

$$\frac{16\,\cancel{u}}{12\,\cancel{u}} = \frac{4}{3} \approx 1.33$$

as great as the mass of a carbon atom.

Example 1.5.2: Mass of a single atom

The absolute mass of a carbon atom is 12.0 unified atomic mass units (u). How many grams will a single oxygen atom weigh?

Solution

The absolute mass of a carbon atom is 12.0 u or

$$12 \cancel{u} \times \frac{1.6605 \times 10^{-24} g}{1 \cancel{u}} = 1.99 \times 10^{-23} g \text{ (per carbon atom)}$$

The mass of the oxygen atom will be 4/3 greater (from Example 1.5.1):

$$\left(\frac{4}{3}\right) 1.99 \times 10^{-23} g = 2.66 \times 10^{-23} g \text{ (per oxygen atom)}$$

Alternatively we can do the calculation directly like with carbon:

$$16 \cancel{u} \times \frac{1.6605 \times 10^{-24} g}{1 \cancel{u}} = 2.66 \times 10^{-23} g \text{ (per oxygen atom)}$$

Example 1.5.3: Relative masses from atomic weights

Suppose that we have N carbon atoms, where N is a number large enough to give us a pile of carbon atoms whose mass is 12.0 grams. How much would the same number, N, of oxygen atoms weigh?

Solution

We use the results from Example 1.5.1 again. The collection of N oxygen atoms would have a mass of

$$\frac{4}{3} \times 12 g = 16.0 g.$$

Exercise 1.5.1

What is the numerical value of N in Example 1.5.3?

Answer

Using the results of Examples 1.5.2 and 1.5.3.

$$N \times 1.99 \times 10^{-23} g \text{ (per carbon atom)} = 12 g$$

or

$$N = \frac{12 \cancel{g}}{1.99 \times 10^{-23} \cancel{g} \text{ (per carbon atom)}} = 6.03 \times 10^{23} \text{atoms}$$

There are a lot of atoms in 12 g of carbon.

- It is a *number*, just as is "dozen", and thus is *dimensionless*.
- It is a *huge* number, far greater in magnitude than we can visualize
- Its practical use is limited to counting tiny things like atoms, molecules, "formula units", electrons, or photons.
- The value of N_A can be known only to the precision that the number of atoms in a measurable weight of a substance can be estimated. Because large numbers of atoms cannot be counted directly, a variety of ingenious indirect measurements have been made involving such things as Brownian motion and X-ray scattering.

- The current value was determined by measuring the distances between the atoms of silicon in an ultrapure crystal of this element that was shaped into a perfect sphere. (The measurement was made by X-ray scattering.) When combined with the measured mass of this sphere, it yields Avogadro's number. However, there are two problems with this:
  - The silicon sphere is an artifact, rather than being something that occurs in nature, and thus may not be perfectly reproducible.
  - The standard of mass, the kilogram, is not precisely known, and its value appears to be changing. For these reasons, there are proposals to revise the definitions of both N_A and the kilogram.

Moles and their Uses

The *mole* (abbreviated mol) is the the SI measure of *quantity of a "chemical entity"*, which can be an atom, molecule, formula unit, electron or photon. One mole of anything is just Avogadro's number of that something. Or, if you think like a lawyer, you might prefer the official SI definition:

Definition: The Mole

The mole is the amount of substance of a system which contains as many elementary entities as there are atoms in 0.012 kilogram of carbon 12

Avogadro's number (Equation 1.5.2) like any pure number, is dimensionless. However, it also defines the mole, so we can also express N_A as 6.02×10^{23} mol^{-1}; in this form, it is properly known as ***Avogadro's constant***. This construction emphasizes the role of Avogadro's number as a *conversion factor* between number of moles and number of "entities".

Example 1.5.4: number of moles in N particles

How many moles of nickel atoms are there in 80 nickel atoms?

Solution

$$\frac{80\ atoms}{6.02 \times 10^{23}\ atoms\ mol^{-1}} = 1.33 \times 10^{-22} mol$$

Is this answer reasonable? Yes, because 80 is an extremely small fraction of N_A.

Molar Mass

The atomic weight, molecular weight, or formula weight of one mole of the fundamental units (atoms, molecules, or groups of atoms that correspond to the formula of a pure substance) is the ratio of its mass to 1/12 the mass of one mole of C^{12} atoms, and being a ratio, is dimensionless. But at the same time, this *molar mass* (as many now prefer to call it) is also the observable mass of one mole (N_A) of the substance, so we frequently emphasize this by stating it explicitly as so many grams (or kilograms) per mole: g mol^{-1}.

> *It is important always to bear in mind that the mole is a number and not a mass. But each individual particle has a mass of its own, so a mole of any specific substance will always correspond to a certain mass of that substance.*

Example 1.5.5: Boron content of borax

Borax is the common name of sodium tetraborate, $Na_2B_4O_7$.

a. how many moles of boron are present in 20.0 g of borax?
b. how many grams of boron are present in 20.0 g of borax?

Solution

The formula weight of $Na_2B_4O_7$ so the molecular weight is:

$$(2 \times 23.0) + (4 \times 10.8) + (7 \times 16.0) = 201.2$$

a. 20 g of borax contains (20.0 g) ÷ (201 g mol^{-1}) = 0.10 mol of borax, and thus **0.40 mol** of B.
b. 0.40 mol of boron has a mass of (0.40 mol) × (10.8 g mol^{-1}) = **4.3 g**.

Example 1.5.6: Magnesium in chlorophyll

The plant photosynthetic pigment chlorophyll contains 2.68 percent magnesium by weight. How many atoms of Mg will there be in 1.00 g of chlorophyll?

Solution

Each gram of chlorophyll contains 0.0268 g of Mg, atomic weight 24.3.

- Number of moles in this weight of Mg: (.0268 g) / (24.2 g mol^{-1}) = 0.00110 mol
- Number of atoms: (0.00110 mol) × (6.02E23 mol^{-1}) = $\mathbf{6.64 \times 10^{20}}$

Is this answer reasonable? (Always be suspicious of huge-number answers!) Yes, because we would expect to have huge numbers of atoms in any observable quantity of a substance.

Molar Volume

This is the volume occupied by one mole of a pure substance. Molar volume depends on the density of a substance and, like density, varies with temperature owing to thermal expansion, and also with the pressure. For solids and liquids, these variables ordinarily have little practical effect, so the values quoted for 1 atm pressure and 25°C are generally useful over a fairly wide range of conditions. This is definitely **not** the case with gases, whose molar volumes must be calculated for a specific temperature and pressure.

Example 1.5.7: Molar Volume of a Liquid


Methanol, CH_3OH, is a liquid having a density of 0.79 g per milliliter. Calculate the molar volume of methanol.

Solution

The molar volume will be the volume occupied by one molar mass (32 g) of the liquid. Expressing the density in liters instead of mL, we have

$$V_M = \frac{32\ g\ mol^{-1}}{790\ g\ L^{-1}} = 0.0405\ L\ mol^{-1}$$

The molar volume of a metallic element allows one to estimate the size of the atom. The idea is to mentally divide a piece of the metal into as many little cubic boxes as there are atoms, and then calculate the length of each box. Assuming that an atom sits in the center of each box and that each atom is in direct contact with its six neighbors (two along each dimension), this gives the diameter of the atom. The manner in which atoms pack together in actual metallic crystals is usually more complicated than this and it varies from metal to metal, so this calculation only provides an approximate value.



Example 1.5.8: Radius of a Strontium Atom

The density of metallic strontium is 2.60 g cm^{-3}. Use this value to estimate the radius of the atom of Sr, whose atomic weight is 87.6.

Solution

The molar volume of Sr is:

$$\frac{87.6\ g\ mol^{-1}}{2.60\ g\ cm^{-3}} = 33.7\ cm^3\ mol^{-1} \tag{1.5.3}$$

The volume of each "box" is"

$$\frac{33.7\ cm^3 mol^{-1}}{6.02 \times 10^{23}\ mol^{-1}} = 5.48 \times 10^{-23}\ cm^3 \tag{1.5.4}$$

The side length of each box will be the cube root of this value, $3.79 \times 10^{-8}\ cm$. The atomic radius will be half this value, or

$$1.9 \times 10^{-8}\ cm = 1.9 \times 10^{-10}\ m = 190pm \tag{1.5.5}$$

Note: Your calculator probably has no cube root button, but you *are* expected to be able to find cube roots; you can usually use the x^y button with y=0.333. You should also be able estimate the magnitude of this value for checking. The easiest way is to express the number so that the exponent is a multiple of 3. Take 54×10^{-24}, for example. Since 3^3=27 and 4^3 = 64, you know that the cube root of 55 will be between 3 and 4, so the cube root should be a bit less than 4×10^{-8}.

So how good is our atomic radius? Standard tables give the atomic radius of strontium is in the range 192-220 pm.

1.5: Molar Mass - Counting Atoms by Weighing Them is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.2: Avogadro's Number and the Mole** by Stephen Lower is licensed CC BY 3.0. Original source: http://www.chem1.com/acad/webtext/virtualtextbook.html.

CHAPTER OVERVIEW

2: Molecules, Compounds and Chemical Equations

Template:HideTOC

2.1: Chemical Bonds
2.2: Representing Compounds- Chemical Formulas and Molecular Models
2.3: An Atomic-Level Perspective of Elements and Compounds
2.4: Ionic Compounds- Formulas and Names
2.5: Molecular Compounds- Formulas and Names
2.6: Summary of Inorganic Nomenclature
2.7: Composition of Compounds
2.8: Determining a Chemical Formula from Experimental Data
2.9: Writing and Balancing Chemical Equations

2: Molecules, Compounds and Chemical Equations is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

2.1: Chemical Bonds

Chemical bonds form when electrons can be simultaneously close to two or more nuclei, but beyond this, there is no simple, easily understood theory that would not only explain why atoms bind together to form molecules, but would also predict the three-dimensional structures of the resulting compounds as well as the energies and other properties of the bonds themselves. Unfortunately, no one theory exists that accomplishes these goals in a satisfactory way for all of the many categories of compounds that are known. Moreover, it seems likely that if such a theory does ever come into being, it will be far from simple.

When we are faced with a scientific problem of this complexity, experience has shown that it is often more useful to concentrate instead on developing **models**. A scientific model is something like a theory in that it should be able to explain observed phenomena and to make useful predictions. But whereas a theory can be discredited by a single contradictory case, a model can be useful even if it does not encompass all instances of the phenomena it attempts to explain. We do not even require that a model be a credible representation of reality; all we ask is that be able to explain the behavior of those cases to which it is applicable in terms that are consistent with the model itself. An example of a model that you may already know about is the kinetic molecular theory of gases. Despite its name, this is really a model (at least at the level that beginning students use it) because it does not even try to explain the observed behavior of real gases. Nevertheless, it serves as a tool for developing our understanding of gases, and as a starting point for more elaborate treatments.

Given the extraordinary variety of ways in which atoms combine into aggregates, it should come as no surprise that a number of useful bonding models have been developed. Most of them apply only to certain classes of compounds, or attempt to explain only a restricted range of phenomena. In this section we will provide brief descriptions of some of the bonding models; the more important of these will be treated in much more detail in later parts of this chapter.


Ionic Bonding

Ever since the discovery early in the 19th century that solutions of salts and other electrolytes conduct electric current, there has been general agreement that the forces that hold atoms together must be electrical in nature. Electrolytic solutions contain ions having opposite electrical charges, opposite charges attract, so perhaps the substances from which these ions come consist of positive and negatively charged atoms held together by electrostatic attraction.

It turns out that this is not true generally, but a model built on this assumption does a fairly good job of explaining a rather small but important class of compounds that are called ionic solids. The most well known example of such a compound is sodium chloride, which consists of two interpenetrating lattices of Na^+ and Cl^- ions arranged in such as way that every ion of one type is surrounded (in three dimensional space) by six ions of opposite charge.

The main limitation of this model is that it applies really well only to the small class of solids composed of Group 1 and 2 elements with highly electronegative elements such as the halogens. Although compounds such as $CuCl_2$ dissociate into ions when they dissolve in water, the fundamental units making up the solid are more like polymeric chains of covalently-bound $CuCl_2$ molecules that have little ionic character.

According to the ionic electrostatic model, solids such as NaCl consist of positive and negative ions arranged in a crystal lattice. Each ion is attracted to neighboring ions of opposite charge, and is repelled by ions of like charge; this combination of attractions and repulsions, acting in all directions, causes the ion to be tightly fixed in its own location in the crystal lattice.



Since electrostatic forces are nondirectional, the structure of an ionic solid is determined purely by geometry: two kinds of ions, each with its own radius, will fall into whatever repeating pattern will achieve the lowest possible potential energy. Surprisingly, there are only a small number of possible structures

Covalent Bonding

This model originated with the theory developed by G.N. Lewis in 1916, and it remains the most widely-used model of chemical bonding. The essential element s of this model can best be understood by examining the simplest possible molecule. This is the **hydrogen molecule ion** H_2^+, which consists of two nuclei and one electron.

First, however, think what would happen if we tried to make the even simpler molecule H_2^{2+}. Since this would consist only of two protons whose electrostatic charges would repel each other at all distances, it is clear that such a molecule cannot exist; something more than two nuclei are required for bonding to occur.

In the hydrogen molecule ion H_2^+ we have a third particle, an electron. The effect of this electron will depend on its location with respect to the two nuclei. If the electron is in the space between the two nuclei, it will attract both protons toward itself, and thus toward each other. If the total attraction energy exceeds the internuclear repulsion, there will be a net bonding effect and the molecule will be stable. If, on the other hand, the electron is off to one side, it will attract both nuclei, but it will attract the closer one much more strongly, owing to the inverse-square nature of Coulomb's law. As a consequence, the electron will now help the electrostatic repulsion to push the two nuclei apart.


We see, then, that the electron is an essential component of a chemical bond, but that it must be in the right place: between the two nuclei. Coulomb's law can be used to calculate the forces experienced by the two nuclei for various positions of the electron. This allows us to define two regions of space about the nuclei, as shown in the figure. One region, the binding region, depicts locations at which the electron exerts a net binding effect on the new nuclei. Outside of this, in the antibinding region, the electron will actually work against binding.

This simple picture illustrates the number one rule of chemical bonding: chemical bonds form when electrons can be simultaneously close to two or more nuclei. It should be pointed out that this principle applies also to the ionic model; as will be explained later in this chapter, the electron that is "lost" by a positive ion ends up being closer to more nuclei (including the one from whose electron cloud it came) in the compound.


- **The polar covalent model**: A purely covalent bond can only be guaranteed when the electronegativities (electron-attracting powers) of the two atoms are identical. When atoms having different electronegativities are joined, the electrons shared between them will be displaced toward the more electronegative atom, conferring a polarity on the bond which can be described in terms of percent ionic character. The polar covalent model is thus an generalization of covalent bonding to include a very wide range of behavior.
- **The Coulombic model**: This is an extension of the ionic model to compounds that are ordinarily considered to be non-ionic. Combined hydrogen is always considered to exist as the **hydride ion** H^-, so that methane can be treated as if it were $C^{4+}\ H^{-4}$. This is not as bizarre as it might seem at first if you recall that the proton has almost no significant size, so that it is essentially embedded in an electron pair when it is joined to another atom in a covalent bond. This model, which is not as well known as it deserves to be, has considerable predictive power, both as to bond energies and structures.
- **The VSEPR model**: The "valence shell electron repulsion" model is not so much a model of chemical bonding as a scheme for explaining the shapes of molecules. It is based on the quantum mechanical view that bonds represent electron clouds- physical regions of negative electric charge that repel each other and thus try to stay as far apart as possible.

Summary

The covalent bond is formed when two atoms are able to share electrons:



whereas the ionic bond is formed when the "sharing" is so unequal that an electron from atom A is completely lost to atom B, resulting in a pair of ions:



The two extremes of electron sharing represented by the covalent and ionic models appear to be generally consistent with the observed properties of molecular and ionic solids and liquids. But does this mean that there are really two kinds of chemical bonds, ionic and covalent?

Contributors and Attributions

- Stephen Lower, Professor Emeritus (Simon Fraser U.) Chem1 Virtual Textbook

---

2.1: Chemical Bonds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

2.2: Representing Compounds- Chemical Formulas and Molecular Models


Chemistry is the experimental and theoretical study of materials on their properties at both the macroscopic and microscopic levels. Understanding the relationship between properties and structures/bonding is also a hot pursuit. Chemistry is traditionally divided into organic and inorganic chemistry. The former is the study of compounds containing at least one carbon-hydrogen bonds. By default, the chemical study of all other substances is called inorganic chemistry, a less well defined subject.

However, the boundary between organic and inorganic compounds is not always well defined. For example, oxalic acid, $H_2C_2O_4$, is a compound formed in plants, and it is generally considered an organic acid, but it does not contain any C-H bond. Inorganic chemistry is also closely related to other disciplines such as materials sciences, physical chemistry, thermodynamics, earth sciences, mineralogy, crystallography, spectroscopy etc.

A chemical formula is a format used to express the structure of atoms. The formula tells which elements and how many of each element are present in a compound. Formulas are written using the elemental symbol of each atom and a subscript to denote the number of elements. This notation can be accredited to Swedish chemist Jons Jakob Berzeliu. The most common elements present in organic compounds are carbon, hydrogen, oxygen, and nitrogen. With carbon and hydrogen present, other elements, such as phosphorous, sulfur, silicon, and the halogens, may exist in organic compounds. Compounds that do not pertain to this rule are called inorganic compounds.

Molecular Geometry and Structural Formula


Understanding how atoms in a molecules are arranged and how they are bonded together is very important in giving the molecule its identity. Isomers are compounds in which two molecules can have the same number of atoms, and thus the same molecular formula, but can have completely different physical and chemical properties because of differences in structural formula.



Methylpropane and butane have the same molecular formula of C_4H_{10}, but are structurally different (methylpropane on the left, butane on the right).

Polymers

A polymer is formed when small molecules of identical structure, monomers, combine into a large cluster. The monomers are joined together by covalent bonds. When monomers repeat and bind, they form a polymer. While they can be comprised of natural or synthetic molecules, polymers often include plastics and rubber. When a molecule has more than one of these polymers, square parenthesis are used to show that all the elements within the polymer are multiplied by the subscript outside of the parenthesis. The subscript (shown as n in the example below) denotes the number of monomers present in the macromolecule (or polymer).



Ethylene becomes the polymer polyethylene.

Molecular Formula

The molecular formula is based on the actual makeup of the compound. Although the molecular formula can sometimes be the same as the empirical formula, molecular compounds tend to be more helpful. However, they do not describe how the atoms are

put together. Molecular compounds are also misleading when dealing with isomers, which have the same number and types of atoms (see above in molecular geometry and structural formula).

Ex. Molecular Formula for Ethanol: C_2H_6O.

Empirical Formula


An empirical formula shows the most basic form of a compound. Empirical formulas show the number of atoms of each element in a compound in the most simplified state using whole numbers. Empirical formulas tend to tell us very little about a compound because one cannot determine the structure, shape, or properties of the compound without knowing the molecular formula. Usefulness of the empirical formula is decreased because many chemical compounds can have the same empirical formula.

Ex. Find the empirical formula for $C_8H_{16}O_2$.

Answer: C_4H_8O (divide all subscripts by 2 to get the smallest, whole number ratio).

Structural Formula

A structural formula displays the atoms of the molecule in the order they are bonded. It also depicts how the atoms are bonded to one another, for example single, double, and triple covalent bond. Covalent bonds are shown using lines. The number of dashes indicate whether the bond is a single, double, or triple covalent bond. Structural formulas are helpful because they explain the properties and structure of the compound which empirical and molecular formulas cannot always represent.

Ex. Structural Formula for Ethanol: 


Condensed Structural Formula

Condensed structural formulas show the order of atoms like a structural formula but are written in a single line to save space and make it more convenient and faster to write out. Condensed structural formulas are also helpful when showing that a group of atoms is connected to a single atom in a compound. When this happens, parenthesis are used around the group of atoms to show they are together.

Ex. Condensed Structural Formula for Ethanol: CH_3CH_2OH (Molecular Formula for Ethanol C_2H_6O).

Line-Angle Formula

Because organic compounds can be complex at times, line-angle formulas are used to write carbon and hydrogen atoms more efficiently by replacing the letters with lines. A carbon atom is present wherever a line intersects another line. Hydrogen atoms are then assumed to complete each of carbon's four bonds. All other atoms that are connected to carbon atoms are written out. Line angle formulas help show structure and order of the atoms in a compound making the advantages and disadvantages similar to structural formulas.

Ex. Line-Angle Formula for Ethanol: 

Formulas of Inorganic Compounds

Inorganic compounds are typically not of biological origin. Inorganic compounds are made up of atoms connected using ionic bonds. These inorganic compounds can be binary compounds, binary acids, or polyatomic ions.

Binary compounds

Binary compounds are formed between two elements, either a metal paired with a nonmetal or two nonmetals paired together. When a metal is paired with a nonmetal, they form ionic compounds in which one is a negatively charged ion and the other is positvely charged. The net charge of the compound must then become neutral. Transition metals have different charges; therefore, it is important to specify what type of ion it is during the naming of the compound. When two nonmetals are paired together, the compound is a molecular compound. When writing out the formula, the element with a positive oxidation state is placed first.

Ex. Ionic Compound: $BaBr_2$(Barium Bromide)

Ex. Molecular Compound: N_2O_4 (Dinitrogen Tetroxide)

Binary acids

Binary acids are binary compounds in which hydrogen bonds with a nonmetal forming an acid. However, there are exceptions such as NH_3, which is a base. This is because it shows no tendency to produce a H^+. Because hydrogen is positively charged, it is placed first when writing out these binary acids.

Ex. HBr (Hydrobromic Acid)

Polyatomic ions

Polyatomic ions is formed when two or more atoms are connected with covalent bonds. Cations are ions that have are postively charged, while anions are negatively charged ions. The most common polyatomic ions that exists are those of anions. The two main polyatomic cations are Ammonium and Mercury (I). Many polyatomic ions are typically paired with metals using ionic bonds to form chemical compounds.

Ex. MnO_4^- (Polyatomic ion); $NaMnO_4$ (Chemical Compound)

Oxoacids

Many acids have three different elements to form ternary compounds. When one of those three elements is oxygen, the acid is known as a oxoacid. In other words, oxacids are compounds that contain hydrogen, oxgygen, and one other element.

Ex. HNO_3 (Nitric Acid)

Complex Compounds

Certain compounds can appear in multiple forms yet mean the same thing. A common example is hydrates: water molecules bond to another compound or element. When this happens, a dot is shown between H_2O and the other part of the compound. Because the H_2O molecules are embedded within the compound, the compound is not necessarily "wet". When hydrates are heated, the water in the compound evaporates and the compound becomes anhydrous. These compounds can be used to attract water such as $CoCl_2$. When $CoCl_2$ is dry, $CoCl_2$ is a blue color wherease the hexahydrate (written below) is pink in color.


Ex. $CoCl_2 \cdot 6\ H_2O$

Formulas of Organic Compounds

Organic compounds contain a combination carbon and hydrogen or carbon and hydrogen with nitrogen and a few other elements, such as phosphorous, sulfur, silicon, and the halogens. Most organic compounds are seen in biological origin, as they are found in nature.

Hydrocarbons

Hydrocarbons are compounds that consist of only carbon and hydrogen atoms. Hydrocarbons that are bonded together with only single bonds are alkanes. The simplest example is methane (shown below). When hydrocarbons have one or more double bonds, they are called alkenes. The simplest alkene is Ethene (C_2H_4) which contains a double bond between the two carbon atoms.




Ex. Methane on left, Ethene on right

Functional Groups

Functional groups are atoms connected to carbon chains or rings of organic molecules. Compounds that are within a functional group tend to have similar properties and characteristics. Two common functional groups are hydroxyl groups and carboxyl groups.

Hydroxyl groups end in -OH and are alcohols. Carboxyl groups end in -COOH, making compounds containing -COOH carboxylic acids. Functional groups also help with nomenclature by using prefixes to help name the compounds that have similar chemical properties.




Ex. Hydroxyl Group on top; Carboxyl Group on bottom

References


1. Miessler, Gary L. Inorganic Chemistry. 2nd. Upper Saddle River: Prentince Hall, 1999.
2. Munowitz, Michael. Principles of Chemistry. Norton & Company: New York, 2000.
3. Pettrucci, Ralph H. General Chemistry: Principles and Modern Applications. 9th. Upper Saddle River: Pearson Prentice Hall, 2007.

Problems

1. Which of the following formulas are organic?
    a. HClO
    b. C_5H_{10}
    c. CO_2
2. What is the name of the following formula?



3. Classify the following formulas into their appropriate functional group
    a. Acetic acid
    b. Butanol
    c. Oxalic acid
4. What are the empirical formulas for the following compounds?
    a. $C_{12}H_{10}O_6$
    b. $CH_3CH_2CH_2CH_2CH_2CH_2CH_3$
    c. H_3O
5. What is the name of the following figure and what is the molecular formula of the following figure?



Answer Key:

1. b and c. 2. Propane. 3. a. carboxyl group, b. hydroxyl group, c. carboxyl group. 4. a. $C_6H_5O_3$, b. C_7H_{16}, c. H_3O. 5. Methylbutane, C_5H_{12}

Contributors and Attributions

- Jean Kim (UCD), Kristina Bonnett (UCD)

2.2: Representing Compounds- Chemical Formulas and Molecular Models is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **Formulas of Inorganic and Organic Compounds** is licensed CC BY-NC-SA 4.0.

2.3: An Atomic-Level Perspective of Elements and Compounds

Learning Objectives

- Define ionic and molecular (covalent) compounds
- Predict the type of compound formed from elements based on their location within the periodic table
- Determine formulas for simple ionic compounds

In ordinary chemical reactions, the nucleus of each atom (and thus the identity of the element) remains unchanged. Electrons, however, can be added to atoms by transfer from other atoms, lost by transfer to other atoms, or shared with other atoms. The transfer and sharing of electrons among atoms govern the chemistry of the elements. During the formation of some compounds, atoms gain or lose electrons, and form electrically charged particles called ions (Figure **2.3.1**).




Figure **2.3.1**: (a) A sodium atom (Na) has equal numbers of protons and electrons (11) and is uncharged. (b) A sodium cation (Na^+) has lost an electron, so it has one more proton (11) than electrons (10), giving it an overall positive charge, signified by a superscripted plus sign.

Figure A shows a sodium atom which has a nucleus containing 11 protons, 12 neutrons, and 11 electrons. Figure B shows a sodium ion. Its nucleus contains 11 protons, 12 neutrons, and 11 electrons.

You can use the periodic table to predict whether an atom will form an anion or a cation, and you can often predict the charge of the resulting ion. Atoms of many main-group metals lose enough electrons to leave them with the same number of electrons as an atom of the preceding noble gas. To illustrate, an atom of an alkali metal (group 1) loses one electron and forms a cation with a 1+ charge; an alkaline earth metal (group 2) loses two electrons and forms a cation with a 2+ charge, and so on. For example, a neutral calcium atom, with 20 protons and 20 electrons, readily loses two electrons. This results in a cation with 20 protons, 18 electrons, and a 2+ charge. It has the same number of electrons as atoms of the preceding noble gas, argon, and is symbolized Ca^{2+}. The name of a metal ion is the same as the name of the metal atom from which it forms, so Ca^{2+} is called a calcium ion.

When atoms of nonmetal elements form ions, they generally gain enough electrons to give them the same number of electrons as an atom of the next noble gas in the periodic table. Atoms of group 17 gain one electron and form anions with a 1− charge; atoms of group 16 gain two electrons and form ions with a 2− charge, and so on. For example, the neutral bromine atom, with 35 protons and 35 electrons, can gain one electron to provide it with 36 electrons. This results in an anion with 35 protons, 36 electrons, and a 1− charge. It has the same number of electrons as atoms of the next noble gas, krypton, and is symbolized Br^-. (A discussion of the theory supporting the favored status of noble gas electron numbers reflected in these predictive rules for ion formation is provided in a later chapter of this text.)

Note the usefulness of the periodic table in predicting likely ion formation and charge (Figure **2.3.2**). Moving from the far left to the right on the periodic table, main-group elements tend to form cations with a charge equal to the group number. That is, group 1 elements form 1+ ions; group 2 elements form 2+ ions, and so on. Moving from the far right to the left on the periodic table, elements often form anions with a negative charge equal to the number of groups moved left from the noble gases. For example, group 17 elements (one group left of the noble gases) form 1− ions; group 16 elements (two groups left) form 2− ions, and so on. This trend can be used as a guide in many cases, but its predictive value decreases when moving toward the center of the periodic

table. In fact, transition metals and some other metals often exhibit variable charges that are not predictable by their location in the table. For example, copper can form ions with a 1+ or 2+ charge, and iron can form ions with a 2+ or 3+ charge.




Figure **2.3.2**: Some elements exhibit a regular pattern of ionic charge when they form ions.

This periodic table shows the charges of ions corresponding with the group number. Starting with a charge of positive one for group 1, positive 2 for group 2, and negative 4, 3, 2, and 1 for groups 14, 15, 16, and 17 respectively. Noble gases on the far right do not have any charges. Some of the ions of transition metals are shown, with multiple charges existing for certain metals.

✔ Example 2.3.1: Composition of Ions

An ion found in some compounds used as antiperspirants contains 13 protons and 10 electrons. What is its symbol?

Solution

Because the number of protons remains unchanged when an atom forms an ion, the atomic number of the element must be 13. Knowing this lets us use the periodic table to identify the element as Al (aluminum). The Al atom has lost three electrons and thus has three more positive charges (13) than it has electrons (10). This is the aluminum cation, Al^{3+}.

? Exercise 2.3.1

Give the symbol and name for the ion with 34 protons and 36 electrons.

Answer

Se^{2-}, the selenide ion

✔ Example 2.3.2: Formation of Ions

Magnesium and nitrogen react to form an ionic compound. Predict which forms an anion, which forms a cation, and the charges of each ion. Write the symbol for each ion and name them.

Solution

Magnesium's position in the periodic table (group 2) tells us that it is a metal. Metals form positive ions (cations). A magnesium atom must lose two electrons to have the same number electrons as an atom of the previous noble gas, neon. Thus, a magnesium atom will form a cation with two fewer electrons than protons and a charge of 2+. The symbol for the ion is Mg^{2+}, and it is called a magnesium ion.

Nitrogen's position in the periodic table (group 15) reveals that it is a nonmetal. Nonmetals form negative ions (anions). A nitrogen atom must gain three electrons to have the same number of electrons as an atom of the following noble gas, neon. Thus, a nitrogen atom will form an anion with three more electrons than protons and a charge of 3−. The symbol for the ion is N^{3-}, and it is called a nitride ion.

? Exercise 2.3.2

Aluminum and carbon react to form an ionic compound. Predict which forms an anion, which forms a cation, and the charges of each ion. Write the symbol for each ion and name them.

Answer

Al will form a cation with a charge of 3+: Al^{3+}, an aluminum ion. Carbon will form an anion with a charge of 4−: C^{4-}, a carbide ion.

The ions that we have discussed so far are called monatomic ions, that is, they are ions formed from only one atom. We also find many polyatomic ions. These ions, which act as discrete units, are electrically charged molecules (a group of bonded atoms with an overall charge). Some of the more important polyatomic ions are listed in Table **2.3.1**. Oxyanions are polyatomic ions that contain one or more oxygen atoms. At this point in your study of chemistry, you should memorize the names, formulas, and charges of the most common polyatomic ions. Because you will use them repeatedly, they will soon become familiar.

Table **2.3.1**: Common Polyatomic Ions

Name	Formula	Related Acid	Formula
ammonium	NH_4^+		
hydronium	H_3O^+		
oxide	O^{2-}		
peroxide	O_2^{2-}		
hydroxide	OH^-		
acetate	CH_3COO^-	acetic acid	CH_3COOH
cyanide	CN^-	hydrocyanic acid	HCN
azide	N_3^-	hydrazoic acid	HN_3
carbonate	CO_3^{2-}	carbonic acid	H_2CO_3
bicarbonate	HCO_3^-		
nitrate	NO_3^-	nitric acid	HNO_3
nitrite	NO_2^-	nitrous acid	HNO_2
sulfate	SO_4^{2-}	sulfuric acid	H_2SO_4
hydrogen sulfate	HSO_4^-		
sulfite	SO_3^{2-}	sulfurous acid	H_2SO_3
hydrogen sulfite	HSO_3^-		
phosphate	PO_4^{3-}	phosphoric acid	H_3PO_4
hydrogen phosphate	HPO_4^{2-}		
dihydrogen phosphate	$H_2PO_4^-$		
perchlorate	ClO_4^-	perchloric acid	$HClO_4$
chlorate	ClO_3^-	chloric acid	$HClO_3$
chlorite	ClO_2^-	chlorous acid	$HClO_2$
hypochlorite	ClO^-	hypochlorous acid	$HClO$
chromate	CrO_4^{2-}	chromic acid	H_2CrO_4
dichromate	$Cr_2O_7^{2-}$	dichromic acid	$H_2Cr_2O_7$
permanganate	MnO_4^-	permanganic acid	$HMnO_4$

Note that there is a system for naming some polyatomic ions; *-ate* and *-ite* are suffixes designating polyatomic ions containing more or fewer oxygen atoms. *Per-* (short for “hyper”) and *hypo-* (meaning “under”) are prefixes meaning more oxygen atoms than *-ate* and fewer oxygen atoms than *-ite*, respectively. For example, perchlorate is ClO_4^-, chlorate is ClO_3^-, chlorite is ClO_2^- and hypochlorite is ClO^-. Unfortunately, the number of oxygen atoms corresponding to a given suffix or prefix is not consistent; for example, nitrate is NO_3^- while sulfate is SO_4^{2-}. This will be covered in more detail in the next module on nomenclature.

The nature of the attractive forces that hold atoms or ions together within a compound is the basis for classifying chemical bonding. When electrons are transferred and ions form, ionic bonds result. Ionic bonds are electrostatic forces of attraction, that is, the attractive forces experienced between objects of opposite electrical charge (in this case, cations and anions). When electrons are “shared” and molecules form, covalent bonds result. Covalent bonds are the attractive forces between the positively charged nuclei

of the bonded atoms and one or more pairs of electrons that are located between the atoms. Compounds are classified as ionic or molecular (covalent) on the basis of the bonds present in them.

Ionic Compounds

When an element composed of atoms that readily lose electrons (a metal) reacts with an element composed of atoms that readily gain electrons (a nonmetal), a transfer of electrons usually occurs, producing ions. The compound formed by this transfer is stabilized by the electrostatic attractions (ionic bonds) between the ions of opposite charge present in the compound. For example, when each sodium atom in a sample of sodium metal (group 1) gives up one electron to form a sodium cation, Na^+, and each chlorine atom in a sample of chlorine gas (group 17) accepts one electron to form a chloride anion, Cl^-, the resulting compound, NaCl, is composed of sodium ions and chloride ions in the ratio of one Na^+ ion for each Cl^- ion. Similarly, each calcium atom (group 2) can give up two electrons and transfer one to each of two chlorine atoms to form $CaCl_2$, which is composed of Ca^{2+} and Cl^- ions in the ratio of one Ca^{2+} ion to two Cl^- ions.

A compound that contains ions and is held together by ionic bonds is called an ionic compound. The periodic table can help us recognize many of the compounds that are ionic: When a metal is combined with one or more nonmetals, the compound is usually ionic. This guideline works well for predicting ionic compound formation for most of the compounds typically encountered in an introductory chemistry course. However, it is not always true (for example, aluminum chloride, $AlCl_3$, is not ionic).

You can often recognize ionic compounds because of their properties. Ionic compounds are solids that typically melt at high temperatures and boil at even higher temperatures. For example, sodium chloride melts at 801 °C and boils at 1413 °C. (As a comparison, the molecular compound water melts at 0 °C and boils at 100 °C.) In solid form, an ionic compound is not electrically conductive because its ions are unable to flow (“electricity” is the flow of charged particles). When molten, however, it can conduct electricity because its ions are able to move freely through the liquid (Figure **2.3.3**).




Figure **2.3.3**: Sodium chloride melts at 801 °C and conducts electricity when molten. (credit: modification of work by Mark Blaser and Matt Evans)

This figure shows three photos connected by right-facing arrows. The first shows a light bulb as part of a complex lab equipment setup. The light bulb is not lit. The second photo shows a substances being heated or set on fire. The third shows the light bulb again which is lit.

In every ionic compound, the total number of positive charges of the cations equals the total number of negative charges of the anions. Thus, ionic compounds are electrically neutral overall, even though they contain positive and negative ions. We can use this observation to help us write the formula of an ionic compound. The formula of an ionic compound must have a ratio of ions such that the numbers of positive and negative charges are equal.

✔ Example **2.3.3**: Predicting the Formula of an Ionic Compound

The gemstone sapphire (Figure **2.3.4**) is mostly a compound of aluminum and oxygen that contains aluminum cations, Al^{3+}, and oxygen anions, O^{2-}. What is the formula of this compound?



Figure **2.3.4**: Although pure aluminum oxide is colorless, trace amounts of iron and titanium give blue sapphire its characteristic color. (credit: modification of work by Stanislav Doronenko)

Solution Because the ionic compound must be electrically neutral, it must have the same number of positive and negative charges. Two aluminum ions, each with a charge of 3+, would give us six positive charges, and three oxide ions, each with a charge of 2−, would give us six negative charges. The formula would be Al_2O_3.

? Exercise 2.3.3

Predict the formula of the ionic compound formed between the sodium cation, Na^+, and the sulfide anion, S^{2-}.

Answer

Na_2S

Many ionic compounds contain polyatomic ions (Table **2.3.1**) as the cation, the anion, or both. As with simple ionic compounds, these compounds must also be electrically neutral, so their formulas can be predicted by treating the polyatomic ions as discrete units. We use parentheses in a formula to indicate a group of atoms that behave as a unit. For example, the formula for calcium phosphate, one of the minerals in our bones, is $Ca_3(PO_4)_2$. This formula indicates that there are three calcium ions (Ca^{2+}) for every two phosphate ($\mathbf{PO_4^{3-}}$) groups. The $\mathbf{PO_4^{3-}}$ groups are discrete units, each consisting of one phosphorus atom and four oxygen atoms, and having an overall charge of 3−. The compound is electrically neutral, and its formula shows a total count of three Ca, two P, and eight O atoms.

✓ Example 2.3.4: Predicting the Formula of a Compound with a Polyatomic Anion

Baking powder contains calcium dihydrogen phosphate, an ionic compound composed of the ions Ca^{2+} and $\mathbf{H_2PO_4^-}$. What is the formula of this compound?

Solution

The positive and negative charges must balance, and this ionic compound must be electrically neutral. Thus, we must have two negative charges to balance the 2+ charge of the calcium ion. This requires a ratio of one Ca^{2+} ion to two $\mathbf{H_2PO_4^-}$ ions. We designate this by enclosing the formula for the dihydrogen phosphate ion in parentheses and adding a subscript 2. The formula is $Ca(H_2PO_4)_2$.

? Exercise 2.3.4

Predict the formula of the ionic compound formed between the lithium ion and the peroxide ion, $\mathbf{O_2^{2-}}$ (Hint: Use the periodic table to predict the sign and the charge on the lithium ion.)

Answer

Li_2O_2

Because an ionic compound is not made up of single, discrete molecules, it may not be properly symbolized using a *molecular* formula. Instead, ionic compounds must be symbolized by a formula indicating the *relative numbers* of its constituent ions. For compounds containing only monatomic ions (such as NaCl) and for many compounds containing polyatomic ions (such as $CaSO_4$), these formulas are just the empirical formulas introduced earlier in this chapter. However, the formulas for some ionic compounds containing polyatomic ions are not empirical formulas. For example, the ionic compound sodium oxalate is comprised of Na^+ and

$C_2O_4^{2-}$ ions combined in a 2:1 ratio, and its formula is written as $Na_2C_2O_4$. The subscripts in this formula are not the smallest-possible whole numbers, as each can be divided by 2 to yield the empirical formula, $NaCO_2$. This is not the accepted formula for sodium oxalate, however, as it does not accurately represent the compound's polyatomic anion, $C_2O_4^{2-}$.

Molecular Compounds

Many compounds do not contain ions but instead consist solely of discrete, neutral molecules. These molecular compounds (covalent compounds) result when atoms share, rather than transfer (gain or lose), electrons. Covalent bonding is an important and extensive concept in chemistry, and it will be treated in considerable detail in a later chapter of this text. We can often identify molecular compounds on the basis of their physical properties. Under normal conditions, molecular compounds often exist as gases, low-boiling liquids, and low-melting solids, although many important exceptions exist.

Whereas ionic compounds are usually formed when a metal and a nonmetal combine, covalent compounds are usually formed by a combination of nonmetals. Thus, the periodic table can help us recognize many of the compounds that are covalent. While we can use the positions of a compound's elements in the periodic table to predict whether it is ionic or covalent at this point in our study of chemistry, you should be aware that this is a very simplistic approach that does not account for a number of interesting exceptions. Shades of gray exist between ionic and molecular compounds, and you'll learn more about those later.

✔ Example 2.3.5: Predicting the Type of Bonding in Compounds

Predict whether the following compounds are ionic or molecular:

a. KI, the compound used as a source of iodine in table salt
b. H_2O_2, the bleach and disinfectant hydrogen peroxide
c. $CHCl_3$, the anesthetic chloroform
d. Li_2CO_3, a source of lithium in antidepressants

Solution

a. Potassium (group 1) is a metal, and iodine (group 17) is a nonmetal; KI is predicted to be ionic.
b. Hydrogen (group 1) is a nonmetal, and oxygen (group 16) is a nonmetal; H_2O_2 is predicted to be molecular.
c. Carbon (group 14) is a nonmetal, hydrogen (group 1) is a nonmetal, and chlorine (group 17) is a nonmetal; $CHCl_3$ is predicted to be molecular.
d. Lithium (group 1) is a metal, and carbonate is a polyatomic ion; Li_2CO_3 is predicted to be ionic.

? Exercise 2.3.5

Using the periodic table, predict whether the following compounds are ionic or covalent:

a. SO_2
b. CaF_2
c. N_2H_4
d. $Al_2(SO_4)_3$

Answer a

molecular

Answer b

ionic

Answer c

molecular

Answer d

ionic

Summary

Metals (particularly those in groups 1 and 2) tend to lose the number of electrons that would leave them with the same number of electrons as in the preceding noble gas in the periodic table. By this means, a positively charged ion is formed. Similarly, nonmetals (especially those in groups 16 and 17, and, to a lesser extent, those in Group 15) can gain the number of electrons needed to provide atoms with the same number of electrons as in the next noble gas in the periodic table. Thus, nonmetals tend to form negative ions. Positively charged ions are called cations, and negatively charged ions are called anions. Ions can be either monatomic (containing only one atom) or polyatomic (containing more than one atom).

Compounds that contain ions are called ionic compounds. Ionic compounds generally form from metals and nonmetals. Compounds that do not contain ions, but instead consist of atoms bonded tightly together in molecules (uncharged groups of atoms that behave as a single unit), are called covalent compounds. Covalent compounds usually form from two or more nonmetals.

Glossary

covalent bond
attractive force between the nuclei of a molecule’s atoms and pairs of electrons between the atoms

covalent compound
(also, molecular compound) composed of molecules formed by atoms of two or more different elements

ionic bond
electrostatic forces of attraction between the oppositely charged ions of an ionic compound

ionic compound
compound composed of cations and anions combined in ratios, yielding an electrically neutral substance

molecular compound
(also, covalent compound) composed of molecules formed by atoms of two or more different elements

monatomic ion
ion composed of a single atom

polyatomic ion
ion composed of more than one atom

oxyanion
polyatomic anion composed of a central atom bonded to oxygen atoms

---

2.3: An Atomic-Level Perspective of Elements and Compounds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.7: Molecular and Ionic Compounds** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

2.4: Ionic Compounds- Formulas and Names

6.9: Binary Ionic Compounds and Their Properties

6.18: Ionic Compounds Containing Polyatomic Ions

Learning Objectives

- Derive names for common types of inorganic compounds using a systematic approach

Nomenclature, a collection of rules for naming things, is important in science and in many other situations. This module describes an approach that is used to name simple ionic and molecular compounds, such as NaCl, $CaCO_3$, and N_2O_4. The simplest of these are binary compounds, those containing only two elements, but we will also consider how to name ionic compounds containing polyatomic ions, and one specific, very important class of compounds known as acids (subsequent chapters in this text will focus on these compounds in great detail). We will limit our attention here to inorganic compounds, compounds that are composed principally of elements other than carbon, and will follow the nomenclature guidelines proposed by IUPAC. The rules for organic compounds, in which carbon is the principle element, will be treated in a later chapter on organic chemistry.

Ionic Compounds

To name an inorganic compound, we need to consider the answers to several questions. First, is the compound ionic or molecular? If the compound is ionic, does the metal form ions of only one type (fixed charge) or more than one type (variable charge)? Are the ions monatomic or polyatomic? If the compound is molecular, does it contain hydrogen? If so, does it also contain oxygen? From the answers we derive, we place the compound in an appropriate category and then name it accordingly.

Compounds Containing Only Monatomic Ions

The name of a binary compound containing monatomic ions consists of the name of the cation (the name of the metal) followed by the name of the anion (the name of the nonmetallic element with its ending replaced by the suffix *–ide*). Some examples are given in Table **2.4.2**.

Table **2.4.1**: Names of Some Ionic Compounds

NaCl, sodium chloride	Na_2O, sodium oxide
KBr, potassium bromide	CdS, cadmium sulfide
CaI_2, calcium iodide	Mg_3N_2, magnesium nitride
CsF, cesium fluoride	Ca_3P_2, calcium phosphide
LiCl, lithium chloride	Al_4C_3, aluminum carbide

Compounds Containing Polyatomic Ions

Compounds containing polyatomic ions are named similarly to those containing only monatomic ions, except there is no need to change to an *–ide* ending, since the suffix is already present in the name of the anion. Examples are shown in Table **2.4.2**.

CL, ammonium chloride, C a S O subscript 4 calcium sulfate, and M g subscript 3 (P O subscript 4) subscript 2 magnesium phosphate." data-quail-id="56" data-mt-width="1071">

Table **2.4.2**: Names of Some Polyatomic Ionic Compounds

$KC_2H_3O_2$, potassium acetate	$(NH_4)Cl$, ammonium chloride
$NaHCO_3$, sodium bicarbonate	$CaSO_4$, calcium sulfate
$Al_2(CO_3)_3$, aluminum carbonate	$Mg_3(PO_4)_2$, magnesium phosphate

Ionic Compounds in Your Cabinets

Every day you encounter and use a large number of ionic compounds. Some of these compounds, where they are found, and what they are used for are listed in Table. Look at the label or ingredients list on the various products that you use during the next few days, and see if you run into any of those in this table, or find other ionic compounds that you could now name or write as a formula.

Everyday Ionic Compounds

Ionic Compound	Use
NaCl, sodium chloride	ordinary table salt
KI, potassium iodide	added to “iodized” salt for thyroid health
NaF, sodium fluoride	ingredient in toothpaste
$NaHCO_3$, sodium bicarbonate	baking soda; used in cooking (and as antacid)
Na_2CO_3, sodium carbonate	washing soda; used in cleaning agents
NaOCl, sodium hypochlorite	active ingredient in household bleach
$CaCO_3$ calcium carbonate	ingredient in antacids
$Mg(OH)_2$, magnesium hydroxide	ingredient in antacids
$Al(OH)_3$, aluminum hydroxide	ingredient in antacids
NaOH, sodium hydroxide	lye; used as drain cleaner
K_3PO_4, potassium phosphate	food additive (many purposes)
$MgSO_4$, magnesium sulfate	added to purified water
Na_2HPO_4, sodium hydrogen phosphate	anti-caking agent; used in powdered products
Na_2SO_3, sodium sulfite	preservative

Compounds Containing a Metal Ion with a Variable Charge

Most of the transition metals can form two or more cations with different charges. Compounds of these metals with nonmetals are named with the same method as compounds in the first category, except the charge of the metal ion is specified by a Roman numeral in parentheses after the name of the metal. The charge of the metal ion is determined from the formula of the compound and the charge of the anion. For example, consider binary ionic compounds of iron and chlorine. Iron typically exhibits a charge of either 2+ or 3+ (see [link]), and the two corresponding compound formulas are $FeCl_2$ and $FeCl_3$. The simplest name, “iron chloride,” will, in this case, be ambiguous, as it does not distinguish between these two compounds. In cases like this, the charge of the metal ion is included as a Roman numeral in parentheses immediately following the metal name. These two compounds are then unambiguously named iron(II) chloride and iron(III) chloride, respectively. Other examples are provided in Table **2.4.3**.

Table **2.4.3**: Names of Some Transition Metal Ionic Compounds

Transition Metal Ionic Compound	Name
$FeCl_3$	iron(III) chloride
Hg_2O	mercury(I) oxide
HgO	mercury(II) oxide
$Cu_3(PO_4)_2$	copper(II) phosphate

Out-of-date nomenclature used the suffixes *–ic* and *–ous* to designate metals with higher and lower charges, respectively: Iron(III) chloride, $FeCl_3$, was previously called ferric chloride, and iron(II) chloride, $FeCl_2$, was known as ferrous chloride. Though this naming convention has been largely abandoned by the scientific community, it remains in use by some segments of industry. For example, you may see the words *stannous fluoride* on a tube of toothpaste. This represents the formula SnF_2, which is more properly named tin(II) fluoride. The other fluoride of tin is SnF_4, which was previously called stannic fluoride but is now named tin(IV) fluoride.

Naming Ionic Compounds

Name the following ionic compounds, which contain a metal that can have more than one ionic charge:

a. Fe_2S_3
b. CuSe
c. GaN
d. $CrCl_3$
e. $Ti_2(SO_4)_3$

Solution

The anions in these compounds have a fixed negative charge (S^{2-}, Se^{2-} , N^{3-}, Cl^-, and $\mathbf{SO_4^{2-}}$), and the compounds must be neutral. Because the total number of positive charges in each compound must equal the total number of negative charges, the positive ions must be Fe^{3+}, Cu^{2+}, Ga^{3+}, Cr^{4+}, and Ti^{3+}. These charges are used in the names of the metal ions:

a. iron(III) sulfide
b. copper(II) selenide
c. gallium(III) nitride
d. chromium(III) chloride
e. titanium(III) sulfate

Exercise 2.4.1

Write the formulas of the following ionic compounds:

1. (a) chromium(III) phosphide
2. (b) mercury(II) sulfide
3. (c) manganese(II) phosphate
4. (d) copper(I) oxide
5. (e) chromium(VI) fluoride

Answer

(a) CrP; (b) HgS; (c) $Mn_3(PO_4)_2$; (d) Cu_2O; (e) CrF_6

Summary

Chemists use nomenclature rules to clearly name compounds. Ionic and molecular compounds are named using somewhat-different methods. Binary ionic compounds typically consist of a metal and a nonmetal. The name of the metal is written first, followed by the name of the nonmetal with its ending changed to *–ide*. For example, K_2O is called potassium oxide. If the metal can form ions with different charges, a Roman numeral in parentheses follows the name of the metal to specify its charge. Thus, $FeCl_2$ is iron(II) chloride and $FeCl_3$ is iron(III) chloride. Some compounds contain polyatomic ions; the names of common polyatomic ions should be memorized. Molecular compounds can form compounds with different ratios of their elements, so prefixes are used to specify the numbers of atoms of each element in a molecule of the compound. Examples include SF_6, sulfur hexafluoride, and N_2O_4, dinitrogen tetroxide. Acids are an important class of compounds containing hydrogen and having special nomenclature rules. Binary acids are named using the prefix *hydro-*, changing the *–ide* suffix to *–ic*, and adding “acid;” HCl is hydrochloric acid. Oxyacids are named by changing the ending of the anion to *–ic*, and adding “acid;” H_2CO_3 is carbonic acid.

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

2.4: Ionic Compounds- Formulas and Names is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

2.5: Molecular Compounds- Formulas and Names

Learning Objectives

- Derive names for common types of inorganic compounds using a systematic approach

The bonding characteristics of inorganic molecular compounds are different from ionic compounds, and they are named using a different system as well. The charges of cations and anions dictate their ratios in ionic compounds, so specifying the names of the ions provides sufficient information to determine chemical formulas. However, because covalent bonding allows for significant variation in the combination ratios of the atoms in a molecule, the names for molecular compounds must explicitly identify these ratios.

Compounds Composed of Two Elements

When two nonmetallic elements form a molecular compound, several combination ratios are often possible. For example, carbon and oxygen can form the compounds CO and CO_2. Since these are different substances with different properties, they cannot both have the same name (they cannot both be called carbon oxide). To deal with this situation, we use a naming method that is somewhat similar to that used for ionic compounds, but with added prefixes to specify the numbers of atoms of each element. The name of the more metallic element (the one farther to the left and/or bottom of the periodic table) is first, followed by the name of the more nonmetallic element (the one farther to the right and/or top) with its ending changed to the suffix *–ide*. The numbers of atoms of each element are designated by the Greek prefixes shown in Table **2.5.3**.

Table **2.5.3**: Nomenclature Prefixes

Number	Prefix	Number	Prefix
1 (sometimes omitted)	mono-	6	hexa-
2	di-	7	hepta-
3	tri-	8	octa-
4	tetra-	9	nona-
5	penta-	10	deca-

When only one atom of the first element is present, the prefix *mono-* is usually deleted from that part. Thus, CO is named carbon monoxide, and CO_2 is called carbon dioxide. When two vowels are adjacent, the *a* in the Greek prefix is usually dropped. Some other examples are shown in Table **2.5.4**.

Table **2.5.4**: Names of Some Molecular Compounds Composed of Two Elements

Compound	Name		Compound	Name
SO_2	sulfur dioxide		BCl_3	boron trichloride
SO_3	sulfur trioxide		SF_6	sulfur hexafluoride
NO_2	nitrogen dioxide		PF_5	phosphoru

Compound	Name	Compound	Name
			sentafluoride
N_2O_4	dinitrogen tetroxide	P_4O_{10}	tetraphosphorusdecaoxide
N_2O_5	dinitrogen pentoxide	IF_7	iodin

Compound	Name	Compound	Name
			heptafluoride

There are a few common names that you will encounter as you continue your study of chemistry. For example, although NO is often called nitric oxide, its proper name is nitrogen monoxide. Similarly, N_2O is known as nitrous oxide even though our rules would specify the name dinitrogen monoxide. (And H_2O is usually called water, not dihydrogen monoxide.) You should commit to memory the common names of compounds as you encounter them.

Naming Covalent Compounds

Name the following covalent compounds:

a. SF_6
b. N_2O_3
c. Cl_2O_7
d. P_4O_6

Solution

Because these compounds consist solely of nonmetals, we use prefixes to designate the number of atoms of each element:

a. sulfur hexafluoride
b. dinitrogen trioxide
c. dichlorine heptoxide
d. tetraphosphorus hexoxide

Exercise 2.5.2

Write the formulas for the following compounds:

a. phosphorus pentachloride
b. dinitrogen monoxide
c. iodine heptafluoride
d. carbon tetrachloride

Answer:

(a) PCl_5; (b) N_2O; (c) IF_7; (d) CCl_4

Binary Acids

Some compounds containing hydrogen are members of an important class of substances known as acids. The chemistry of these compounds is explored in more detail in later chapters of this text, but for now, it will suffice to note that many acids release hydrogen ions, H^+, when dissolved in water. To denote this distinct chemical property, a mixture of water with an acid is given a name derived from the compound's name. If the compound is a binary acid (comprised of hydrogen and one other nonmetallic element):

1. The word "hydrogen" is changed to the prefix *hydro-*
2. The other nonmetallic element name is modified by adding the suffix *-ic*
3. The word "acid" is added as a second word

For example, when the gas HCl (hydrogen chloride) is dissolved in water, the solution is called *hydrochloric acid*. Several other examples of this nomenclature are shown in Table **2.5.5**.

Table **2.5.5**: Names of Some Simple Acids

Name of Gas	Name of Acid
HF(*g*), hydrogen fluoride	HF(*aq*), hydrofluoric acid
HCl(*g*), hydrogen chloride	HCl(*aq*), hydrochloric acid
HBr(*g*), hydrogen bromide	HBr(*aq*), hydrobromic acid
HI(*g*), hydrogen iodide	HI(*aq*), hydroiodic acid
H_2S(*g*), hydrogen sulfide	H_2S(*aq*), hydrosulfuric acid

Oxyacids

Many compounds containing three or more elements (such as organic compounds or coordination compounds) are subject to specialized nomenclature rules that you will learn later. However, we will briefly discuss the important compounds known as oxyacids, compounds that contain hydrogen, oxygen, and at least one other element, and are bonded in such a way as to impart acidic properties to the compound (you will learn the details of this in a later chapter). Typical oxyacids consist of hydrogen combined with a polyatomic, oxygen-containing ion. To name oxyacids:

1. Omit "hydrogen"
2. Start with the root name of the anion
3. Replace *–ate* with *–ic*, or *–ite* with *–ous*
4. Add "acid"

For example, consider H_2CO_3 (which you might be tempted to call "hydrogen carbonate"). To name this correctly, "hydrogen" is omitted; the *–ate* of carbonate is replace with *–ic*; and acid is added—so its name is carbonic acid. Other examples are given in Table **2.5.6**. There are some exceptions to the general naming method (e.g., H_2SO_4 is called sulfuric acid, not sulfic acid, and H_2SO_3 is sulfurous, not sulfous, acid).

Table **2.5.6**: Names of Common Oxyacids

Formula	Anion Name	Acid Name
$HC_2H_3O_2$	acetate	acetic acid
HNO_3	nitrate	nitric acid
HNO_2	nitrite	nitrous acid
$HClO_4$	perchlorate	perchloric acid
H_2CO_3	carbonate	carbonic acid
H_2SO_4	sulfate	sulfuric acid
H_2SO_3	sulfite	sulfurous acid
H_3PO_4	phosphate	phosphoric acid

Summary

Chemists use nomenclature rules to clearly name compounds. Ionic and molecular compounds are named using somewhat-different methods. Binary ionic compounds typically consist of a metal and a nonmetal. The name of the metal is written first, followed by the name of the nonmetal with its ending changed to *–ide*. For example, K_2O is called potassium oxide. If the metal can form ions with different charges, a Roman numeral in parentheses follows the name of the metal to specify its charge. Thus, $FeCl_2$ is iron(II) chloride and $FeCl_3$ is iron(III) chloride. Some compounds contain polyatomic ions; the names of common polyatomic ions should be memorized. Molecular compounds can form compounds with different ratios of their elements, so prefixes are used to specify the numbers of atoms of each element in a molecule of the compound. Examples include SF_6, sulfur hexafluoride, and N_2O_4, dinitrogen tetroxide. Acids are an important class of compounds containing hydrogen and having special nomenclature rules. Binary acids are named using the prefix *hydro-*, changing the *–ide* suffix to *–ic*, and adding "acid;" HCl is hydrochloric acid. Oxyacids are named by changing the ending of the anion to *–ic*, and adding "acid;" H_2CO_3 is carbonic acid.

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

2.5: Molecular Compounds- Formulas and Names is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

2.6: Summary of Inorganic Nomenclature

Chemical **nomenclature** is the names we use for chemicals. For instance, H_2O is called "water", and CH_4 (the gas you burn in a stove) is called "methane." You should learn the chemical nomenclature here on this page now, so that you will be able to understand when it is used.

The Basics

Here is some important info about how we write chemicals.


1. Elements have symbols of one or two letters. The first is a capital letter (ABC). If there is a second letter, it is a lower-case letter (abc). For instance, "m" is one unit, and "M" is a different unit. "K" is the symbol for one type of constant, and "k" is the symbol for a different type. You need to remember that capital letter symbols are usually different from lower-case symbols. For instance, Co is cobalt, a metal element next to iron, and CO is carbon monoxide, a poisonous gas made of one carbon atom and one oxygen atom.



2. We write the charge of a chemical using a superscript, which looks like this: H^+or H^-. If we write just H, that means an H atom, which is one proton and one electron. H^+ means 1 H atom – 1 electron, so it means just one proton, also called hydrogen ion. If we write H^- this means one hydrogen atom + one electron, so a proton and 2 electrons, also called hydride ion. If there's an number in the superscript, that says how many electrons are added or removed. For instance, Ca^{2+} is a calcium atom – 2 electrons, or calcium ion. S^{2-} is sulfide, or sulfur + 2 electrons.



3. We indicate the number of atoms of a particular type using a subscript, like this: CO_2. This means one carbon atom and 2 oxygen atoms. If we write O_2 that means the oxygen molecule, which is two atoms of oxygen connected together. Sometimes people might write O2 to mean the same thing. If the number comes first, though, it has a different meaning. 2 O means 2 atoms of oxygen that aren't connected to anything.



1 ball is used to show atomic oxygen. 2 conjoined ball is used to show diatomic oxygen and 3 conjoined ball represents ozone.

4. If we want to show how many protons and neutrons are present in an atom, we can use the mass number, as a superscript *before* the element symbol, such as^{13}C. This means carbon with (protons + neutrons) = 13. You can tell that this is different from the charge, because the charge will always include + or – and come after the symbol.

5. Most molecules or ions that are stable have an even number of electrons. If they have an odd number of electrons, this is called a radical. For instance, H is a radical, because it has one electron. Because this is unusual, it might be indicated with a dot, like this: $H^{\bullet}$. For instance, water is H_2O, and if you remove hydrogen ion, you are left with hydroxide ion, OH^-. If you remove $H^{\bullet}$ from water, you are left with OH molecule, which is neutral. This is also called hydroxyl radical, written $OH^{\bullet}$.



6. The phase of a substance is often indicated by a letter in () after the symbol. For instance, He is almost always a gas, written He(g). If it's a liquid (4.2K or below, less than -269° C) that is written He(l). You'll probably never hear about He(s), since it would be very hard to make it a solid. You might also see something written with (aq), which means "dissolved in water." For instance, NaCl(aq) means salt dissolved in water so there is no solid left. Or you might just see K^+(aq), meaning potassium ions dissolved in water.



Elements

There are lots of elements and you don't need to memorize them all. Here are a few that you should learn right now, though, because they are common or important, so that you won't be confused when they are mentioned later. They are organized by their type.

1. Non-metals

- Light elements: the elements with smallest mass
  - Hydrogen (H): exists as H_2 or in combination with other elements, such as in water
  - Helium (He): named after the sun, because it was discovered in the sun before being discovered on Earth (we'll explain how later); it doesn't react with anything
- Major gases in air
  - Oxygen (O): we get most of our energy from reactions with oxygen, when we breathe or when we burn fuel; O_2 is 21% of air
  - Nitrogen (N): often the limiting factor for agriculture or population growth, even though N_2 is 78% of air, because it only reacts under special circumstances.
- Halogens: reactive elements that make salts; common negative ions
  - Fluorine (F): the lightest halogen and most reactive element in the periodic table, people say that it killed the first two chemists who tried to isolate F_2
  - Chlorine (Cl): part of normal salt, NaCl, it is common in the ocean and in your body
  - Bromine (Br): one of only two elements that are liquid at room temperature, bromine is also found in salts and minerals
  - Iodine (I): a soft, shiny silver solid that easily evaporates to a purple gas, iodine can be used to disinfect cuts and is essential for human brains, suggesting that humans may have evolved to live near the ocean, which provides sources of iodine in fish and seaweed
- Main group solid non-metals: non-conductive and usually soft materials
  - Carbon (C): the element on which biology is based, also found in diamond, graphite, coal, and charcoal
  - Silicon (Si): the basis of the electronics industry; also a main component of sand, glass, and most rocks
  - Sulfur (S): a smelly yellow solid, used to make strong acid in industry, also common in minerals and essential to life
  - Phosphorus (P): first isolated from urine, although common in minerals; essential for life, often glows

2. Metals: soft or hard, light or heavy, usually solid electric conductors

- Alkali metals: soft, light, common soluble positive ions
  - Lithium (Li): the lightest alkali, used in batteries and anti-depressants
  - Sodium (Na, you may know it as natrium): common in the ocean and salt
  - Potassium (K, you may know it as kalium): also common, high concentration inside cells
- Alkaline Earth metals: like alkalis, but less so, less reactive, less soluble, positive ions more common in rocks, but also abundant in ocean
  - Magnesium (Mg): common in rocks, essential for life, especially photosynthesis
  - Calcium (Ca): common in biomaterials such as bone, tooth, and shells, also essential for muscles
- Main group metals

- Aluminum (Al, also called aluminium): requires lots of energy to produce the metal from the mineral sources, but very common and useful metal
- Tin (Sn, from Latin stannum): used since ancient times, especially in alloys such as bronze; still used in solder and many other applications
- Lead (Pb, from Latin plumbum): very heavy, soft, sweet-tasting toxic metal, commonly used since ancient times, now used to shield radiation and in bullets, among many other uses

- Transition Metals: a widely varied group, often characterized by complex chemical properties
  - Iron (Fe, from Latin ferrum): most abundant element on earth, essential in steel, with complex reaction properties essential to life
  - Copper (Cu, from Latin cuprum): less reactive metal, with characteristic colors, commonly used in coins and electronics
  - Silver (Ag, from Latin argentum): used in jewelry, coins and other ornaments and utensils since ancient times, it didn't tarnish until after the industrial revolution, and now also used in electronics
  - Gold (Au, from Latin aurum): used since ancient times in coins and jewelry, to color stained glass, also in dentistry and other applications
  - Mercury (Hg, from Latin hydrargyrum): also called quicksilver, because it is a silver liquid, it is toxic but very important in the history of science; it may be familiar from thermometers

Common Positive Ions (Cations)

"[element name](charge in Roman numerals if needed) ion"

Cation is another word for positive ion. The common positive ions are the ions of the alkali and alkaline earth metals and ammonium, NH_4^+. The alkali metals form +1 cations, such as Na^+ and K^+. The alkaline earth metals form +2 cations, such as Ca^{2+} and Mg^{2+}. The hydrogen ion, H^+ is a very common cation. For these cations, you can call them "[element name] ion", such as sodium ion or calcium ion.

You'll also see transition metal cations or main group metal cations, but it is harder to predict what charge they will have, especially because some of them can have different charges, like iron, which is commonly Fe^{2+} or Fe^{3+}. The charge on a transition metal cation can also be indicated using Roman numerals in parentheses, which looks like Fe(II) or Fe(III). The Roman numerals you will need to know for chemistry are:

1	2	3	3	5	6	7	8	9	10
I	II	III	IV	V	VI	VII	VIII	IX	X

For cations that have uncertain charge, you should call them "[element name](charge in Roman numerals) ion." For instance, iron(II) ion or sometimes just Fe(II).

Sometimes people use special names for these ions, in which the higher charge ion is called "[name]-ic ion" and the lower charge ion is called "[name]-ous ion," such as ferrous for Fe(II) and ferric for Fe(III), or cuprous ion for Cu(I) and cupric ion for Cu(II). I think this is most common for Fe, and I've never heard anyone call nickel(II) nickelous ion because that sounds ridiculous.



Table 5.2 Common Type II Cations

Ion	Systematic Name	Older Name
Fe^{3+}	iron(III)	ferric
Fe^{2+}	iron(II)	ferrous
Cu^{2+}	copper(II)	cupric
Cu^{+}	copper(I)	cuprous
Co^{3+}	cobalt(III)	cobaltic
Co^{2+}	cobalt(II)	cobaltous
Sn^{4+}	tin(IV)	stannic
Sn^{2+}	tin(II)	stannous
Pb^{4+}	lead(IV)	plumbic
Pb^{2+}	lead(II)	plumbous
Hg^{2+}	mercury(II)	mercuric
Hg_2^{2+}*	mercury(I)	mercurous

*Mercury(I) ions always occur bound together in pairs to form Hg_2^{2+}.

Here's a list of common cations with less predictable charges:

• Ag^{+}	• Cu^{+}	• Cu^{2+}	• Fe^{2+}	• Fe^{3+}	• Hg_2^{2+}	• Hg^{2+}	• Pb^{2+}	• Sn^{2+}	• Al^{3+}

Elements not on the list above, that you may see soon anyway: zinc(II): Zn^{2+}, cadmium(II): Cd^{2+}, cobalt(II): Co^{2+}, manganese(II): Mn^{2+}, nickel(II): Ni^{2+}, chromium(III): Cr^{3+}.

Common Negative Ions (Anions)

"[base name] + (-ide,-ate, or -ite)"

Anion is another word for negative ion. Common negative ions are the halide ions, formed from the halogen elements: fluoride, F^{-}; chloride, Cl^{-}; bromide, Br^{-}; and iodide, I^{-}. As you may have noticed, the names of anions have "-ide" at the end when they are formed from elements. Other examples include oxide, O^{2-}, sulfide, S^{2-}, and nitride, N^{3-}.

Common Anions

Charge	Formula	Name
1−	H^{-}	Hydride ion
	F^{-}	Fluoride ion
	Cl^{-}	Chloride ion
	Br^{-}	Bromide ion
	I^{-}	Iodide ion
	CN^{-}	Cyanide ion
	OH^{-}	Hydroxide ion
2−	O^{2-}	Oxide ion
	O_2^{2-}	Peroxide ion
	S^{2-}	Sulfide ion
3−	N^{3-}	Nitride ion

There are also many important polyatomic anions, which means anions that include more than one atom. These include toxic cyanide ion, CN^{-}, common hydroxide ion, OH^{-}, and peroxide ion, O_2^{2-}. Other important anions include acetate ion ($C_2H_3O_2^{-}$), which is in vinegar, the chlorate ion (ClO_3^{-}), the perchlorate ion (ClO_4^{-}) which is often explosive, the nitrate ion (NO_3^{-}), the carbonate ion (CO_3^{2-}) found in shells, the sulfate ion (SO_4^{2-}), and the phosphate ion (PO_4^{3-}). All of these end in "-ate", which means that they have more oxygen. Also, notice that "per-___-ate" means more oxygen than just "-ate", as in perchlorate.

Less common but still important are some "-ite" anions, which have less oxygen, such as nitrite (NO_2^{-}), sulfite (SO_3^{2-}), chlorite (ClO_2^{-}) and hypochlorite (ClO^{-}). Notice that "hypo-___-ite" means less oxygen than just "-ite" as in hypochlorite. Sulfite and nitrite are used to preserve foods. Sulfite salts are used in wine, dried fruit and preserved radish (mu). Nitrite salts are used in preserved meats.

One more rule says that if you take an anion like carbonate or sulfate and add one hydrogen ion, then you call that "bicarbonate" (HCO_3^{-}) or "bisulfate" (HSO_4^{-}). Or you might see it called "hydrogen carbonate" or "hydrogen sulfate." Note that because we added a hydrogen ion, the charge on the bicarbonate ion is one less than the charge on the carbonate ion. Also, note that "disulfate" is $S_2O_7^{2-}$, quite different from bisulfate.

Chemical Nomenclature for Ionic Compounds

"[cation name] + [anion name]"

Ionic compounds are compounds that include at least two components, a positive ion and a negative ion. Often the positive ion is a metal element ion and the negative ion is a non-metal ion. To name an ionic compound, you usually just give the cation followed by the anion, such as "sodium chloride" or "ammonium nitrate." If the cation is the type that could have different charges, than you should say what the charge is, such as "mercury(I) iodide" or "cupric sulfate."

Chemical Nomenclature for Acids

"(hydro if -ide)[anion base name] + (-ic if -ide, -ate; -ous if -ite) + acid"

Acid usually means an anion combined with the hydrogen ion as the cation. For instance, HCl is a common acid, which is the hydrogen ion and the chloride anion. If the anion ends in "-ide" then usually the acid is called "hydro-___-ic acid" such as "hydrochloric acid" for HCl. You'll see this for all the "hydrohalic acids" which are H + a halogen, such as "hydrofluoric acid" or "hydroiodic acid." You might also see "hydrocyanic acid" for HCN. If the anion ends in "-ate" than you call the acid "___-ic acid," such as "sulfuric acid," which is H_2SO_4, or "nitric acid." HNO_3. If the anion ends in "-ite" than the acid name is "___-ous acid." such as "hypochlorous acid" for HClO. Notice that earlier "-ic" and "-ous" meant more and less charge for cations, such as ferric and ferrous ions of iron. Now it also means more and less oxygen in acids.



Chemical Nomenclature for Non-metal Compounds

"(prefix, not mono)[less anion-like atom name] + (prefix)[more anion-like atom name]-ide"

Non-metal compounds are often called covalent compounds. They are named following a different rule from ionic compounds. You will need these "prefixes" which indicate how many of each type of atom are present:

1	2	3	3	5	6	7	8	9	10
mono	di	tri	tetra	penta	hexa	hepta	octa	nona	deca

The prefixes come from Greek. You will put the element that is more left on the periodic table first, unless it is oxygen, which is always last unless it is in a compound with fluorine. This follows the same pattern as ionic compounds. In ionic compounds, the cation is written first, and you will notice that it is usually more to the left in the periodic table than the anion, which is written last. When you name covalent compounds, the atom that's more like an anion is written last. Fluorine is always most "anionic," and oxygen is next most "anionic," so they will always be last. (Fluorine is actually most electronegative, but we will study this concept much later, which is why right now I'm calling it "anion-like.") If both atoms are in the same group (same column of the periodic table) then the lower one is named first. Notice that the two most "anion-like," F and O, are in the upper right of the periodic table. The atom written second, that's more "anion-like" is named like an anion, with the "-ide" ending. For example, CO: carbon is on the left, so we can write "monocarbon monoxide." Actually people usually just call it "carbon monoxide." You can skip "mono" for the first element. For instance, SO_3 is called "sulfur trioxide" and N_2O_4 is called "dinitrogen tetroxide." XeO_2 is xenon dioxide, even though xenon is more to the right than oxygen, because oxygen is more like an anion than anything except fluorine. If the compound involves hydrogen, then you can leave out the prefixes, such as "hydrogen chloride" for HCl or "hydrogen sulfide" for H_2S, because the numbers of each atom can be predicted as if it were an ionic substance. But actually many compounds of hydrogen have special names, such as "ammonia" for NH_3, "methane" for CH_4, "borane" for BH_3, "silane" for SiH_4 and "phosphine" for PH_3. You should learn the first two of these now.



Summary

Key Info for Common Elements

Element name	Symbol	Atomic number	Commonly found as...
Hydrogen	H	1	H_2(g), water (H_2O), acid (H^+(aq))
Helium	He	2	He(g), He(l) if you want to make things very cold
Lithium	Li	3	Li^+ always, (aq) or in solids with anions, lithium metal Li(s) only in chem class
Carbon	C	6	Covalent compounds, making 4 bonds
Nitrogen	N	7	N_2(g) in air, in ammonia (NH_3(g or l)), in basic covalent compounds, in proteins
Oxygen	O	8	O_2(g) in air, in water, in rock and glass, usually combined with Si
Fluorine	F	9	F^-(aq) or with cations in rock, in covalent compounds with carbon (non-stick pans)
Sodium (Natrium)	Na	11	Na^+(aq) or with anions in salts, sodium metal (Na(s)) only in chem class
Magnesium	Mg	12	Mg^{2+}(aq) or with anions in salts and rocks
Aluminum (Aluminium)	Al	13	Al^{3+} with anions in rocks and salts, industrially made Al(s) metal
Silicon	Si	14	Industrially made Si(s) in computer chips, Si(IV) oxides in sand, glass, most rocks
Phosphorus	P	15	Phosphates: PO_4^{3-}, $P_2O_7^{4-}$, etc. in rock, DNA
Sulfur	S	16	S_8(s), S^{2-} or sulfate (SO_4^{2-}) in salts or rocks
Chlorine	Cl	17	Cl^-(aq) or with cations in salts, Cl_2(g) or ClO^-(aq) in disinfectants
Potassium (kalium)	K	19	K^+(aq) or with anions in salts, potassium metal (K(s)) only in chem class
Calcium	Ca	20	Ca^{2+}(aq) or with anions in salts and rocks
Iron	Fe	26	Fe(s) metal industrially made, Fe(II) or Fe(III) oxides or

Element name	Symbol	Atomic number	Commonly found as...
			sulfides and other minerals
Copper	Cu	29	Natural Cu(s) metal, Cu(I) or Cu(II) salts or minerals, usually blue or green
Bromine	Br	35	Br^-(aq) or with cations in salts
Silver	Ag	47	Natural Ag(s) metal, Ag(I) or Ag(II) in salts or sulfide minerals
Tin	Sn	50	Industrially made Sn(s) in alloys, Sn(II) or Sn(IV) salts and oxide or sulfide minerals
Iodine	I	53	I^-(aq) or with cations in salts
Gold	Au	79	Natural Au(s) metal, rarely Au(I) or Au(III) salts
Mercury	Hg	80	Natural (but rare) metal Hg(l), Hg(II) sulfides and halides, Hg(I) exists as Hg_2^{2+}
Lead	Pb	82	Pb(s) in alloys, Pb(II) sulfide, carbonate and sulfate minerals, sometimes Pb(IV) salts or minerals

Common Polyatomic Ions

Name	Formula	Where you find it
Ammonium	NH_4^+	Soluble salts, fertilizer
Cyanide	CN^-	Toxic, in some plant products and dyes
Hydroxide	OH^-	In bases and some minerals
Peroxide	O_2^{2-}	In bleaches and disinfectants
Acetate	$C_2H_3O_2^-$	In vinegar
Perchlorate	ClO_4^-	Soluble salts and explosives, a strong acid
Chlorate	ClO_3^-	Similar to perchlorates but less stable
Chlorite	ClO_2^-	Disinfectants and bleaches, some explosive salts
Hypochlorite	ClO^-	Disinfectants and bleaches, most salts unstable
Nitrate	NO_3^-	Soluble salts, fertilizer, explosives, a strong acid
Nitrite	NO_2^-	Preservatives for food
Carbonate	CO_3^{2-}	In rock, seashells, cement; a base
Bicarbonate	HCO_3^-	A base (baking soda), in soda, in blood
Sulfate	SO_4^{2-}	In salts, plaster, detergent, a strong acid
Bisulfate	HSO_4^-	Food additives
Sulfite	SO_3^{2-}	Salts, food preservatives
Phosphate	PO_4^{3-}	Salts, rock, fertilizers, a strong acid, in ATP and DNA

Outside Link

- CrashCourse Chemistry: How to Speak Chemistrian (11 min)

Contributors and Attributions

- Emily V Eames (City College of San Francisco)

2.6: Summary of Inorganic Nomenclature is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

2.7: Composition of Compounds

Learning Objectives

- To understand the definition and difference between empirical formulas and chemical formulas
- To understand how combustion analysis can be used to identify chemical formulas

Chemical formulas tell you how many atoms of each element are in a compound, and empirical formulas tell you the simplest or most reduced ratio of elements in a compound. If a compound's chemical formula cannot be reduced any more, then the empirical formula is the same as the chemical formula. Combustion analysis can determine the empirical formula of a compound, but cannot determine the chemical formula (other techniques can though). Once known, the chemical formula can be calculated from the empirical formula.

Empirical Formulas

An empirical formula tells us the relative ratios of different atoms in a compound. The ratios hold true on the *molar* level as well. Thus, H_2O is composed of two atoms of hydrogen and 1 atom of oxygen. Likewise, **1.0 mole of H_2O** is composed **of 2.0 moles of hydrogen** and **1.0 mole of oxygen**. We can also work backwards from molar ratios since *if we know the molar amounts of each element in a compound we can determine the empirical formula*.

Example 2.7.1: Mercury Chloride

Mercury forms a compound with chlorine that is 73.9% mercury and 26.1% chlorine by mass. What is the empirical formula?

Solution

Let's say we had a 100 gram sample of this compound. The sample would therefore contain 73.9 grams of mercury and 26.1 grams of chlorine. How many moles of each atom do the individual masses represent?

For Mercury:

$$(73.9\ g) \times \left(\frac{1\ mol}{200.59\ g}\right) = 0.368\ moles$$

For Chlorine:

$$(26.1\ g) \times \left(\frac{1\ mol}{35.45\ g}\right) = 0.736\ mol$$

What is the molar ratio between the two elements?

$$\frac{0.736\ mol\ Cl}{0.368\ mol\ Hg} = 2.0$$

Thus, we have twice as many moles (i.e. atoms) of **Cl** as **Hg**. The empirical formula would thus be (remember to list cation first, anion last):

$$\mathbf{HgCl_2}$$

Chemical Formula from Empirical Formula

The chemical formula for a compound obtained by composition analysis is always the empirical formula. We can obtain the chemical formula from the empirical formula if we know the molecular weight of the compound. The chemical formula will always be some *integer multiple* of the empirical formula (i.e. integer multiples of the subscripts of the empirical formula). The general flow for this approach is shown in Figure **2.7.1** and demonstrated in Example **2.7.2**.




Figure **2.7.1**: The general flow chart for solving empirical formulas from known mass percentages.

Flowchart. From mass % elements, calculate the grams of each element. Then, use atomic weights to calculate the moles of each element. Then, assign empirical formula by calculating the molar ratio for each element.

Example 2.7.2: Ascorbic Acid

Vitamin C (ascorbic acid) contains 40.92 % C, 4.58 % H, and 54.50 % O, by mass. The experimentally determined molecular mass is 176 amu. What is the empirical and chemical formula for ascorbic acid?

Solution

Consider an arbitrary amount of 100 grams of ascorbic acid, so we would have:

- 40.92 grams C
- 4.58 grams H
- 54.50 grams O

This would give us how many moles of each element?

- Carbon

$$(40.92\ \cancel{g\,C}) \times \left(\frac{1\ mol\ C}{12.011\ \cancel{g\,C}}\right) = 3.407\ mol\ C$$

- Hydrogen

$$(4.58\ \cancel{g\,H}) \times \left(\frac{1\ mol\ H}{1.008\ \cancel{g\,H}}\right) = 4.544\ mol\ H$$

- Oxygen

$$(54.50\ \cancel{g\,O}) \times \left(\frac{1\ mol\ O}{15.999\ \cancel{g\,O}}\right) = 3.406\ mol\ O$$

Determine the simplest whole number ratio by dividing by the smallest molar amount (3.406 moles in this case - see oxygen):

- Carbon

$$C = \frac{3.407\ mol}{3.406\ mol} \approx 1.0$$

- Hydrogen

$$C = \frac{4.544\ mol}{3.406\ mol} = 1.333$$

- Oxygen

$$C = \frac{3.406\ mol}{3.406\ mol} = 1.0$$

The relative molar amounts of carbon and oxygen appear to be equal, but the relative molar amount of hydrogen is higher. Since we cannot have "fractional" atoms in a compound, we need to normalize the relative amount of hydrogen to be equal to an integer. 1.333 would appear to be 1 and 1/3, so if we multiply the relative amounts of each atom by '3', we should be able to get integer values for each atom.

C = (1.0)*3 = 3

H = (1.333)*3 = 4

O = (1.0)*3 = 3

or

$$\mathbf{C_3H_4O_3}$$

This is our ***empirical formula*** for ascorbic acid.

What about the chemical formula? We are told that the experimentally determined molecular mass is **176 *amu***. What is the molecular mass of our empirical formula?

(3*12.011) + (4*1.008) + (3*15.999) = 88.062 *amu*

The molecular mass from our empirical formula is significantly lower than the experimentally determined value. What is the ratio between the two values?

(176 *amu*/88.062 *amu*) = 2.0

Thus, it would appear that our empirical formula is essentially one half the mass of the actual molecular mass. If we multiplied our empirical formula by '2', then the molecular mass would be correct. Thus, the actual chemical formula is:

2* $C_3H_4O_3$ = **$C_6H_8O_6$**



Empirical Formulas: Empirical Formulas, YouTube(opens in new window) [youtu.be]

Combustion Analysis

When a compound containing carbon and hydrogen is subject to combustion with oxygen in a special combustion apparatus all the carbon is converted to CO_2 and the hydrogen to H_2O (Figure **2.7.2**). The amount of carbon produced can be determined by measuring the amount of CO_2 produced. This is trapped by the sodium hydroxide, and thus we can monitor the mass of CO_2

produced by determining the increase in mass of the CO_2 trap. Likewise, we can determine the amount of H produced by the amount of H_2O trapped by the magnesium perchlorate.




Figure **2.7.2**: Combustion analysis apparatus

Diagram of a combustion chamber. O 2 enters the furnace and combusts the sample. All carbon is converted to C O 2 and all hydrogen is converted to H 2 O in the presence of C u O in the next chamber. The next chamber is an H 2 O trap with M g (C l O 4) 2 inside. The next chamber is a C O 2 trap with N a O H inside.

One of the most common ways to determine the elemental composition of an unknown hydrocarbon is an analytical procedure called combustion analysis. A small, carefully weighed sample of an unknown compound that may contain carbon, hydrogen, nitrogen, and/or sulfur is burned in an oxygen atmosphere,Other elements, such as metals, can be determined by other methods. and the quantities of the resulting gaseous products (CO_2, H_2O, N_2, and SO_2, respectively) are determined by one of several possible methods. One procedure used in combustion analysis is outlined schematically in Figure **2.7.3** and a typical combustion analysis is illustrated in Examples **2.7.3** and **2.7.4**.




Figure **2.7.3**: Steps for Obtaining an Empirical Formula from Combustion Analysis. (CC BY-NC-SA; anonymous)

✔ Example **2.7.3**: Combustion of Isopropyl Alcohol

What is the empirical formulate for isopropyl alcohol (which contains only C, H and O) if the combustion of a 0.255 grams isopropyl alcohol sample produces 0.561 grams of CO_2 and 0.306 grams of H_2O?

Solution

From this information quantitate the amount of C and H in the sample.

$$(0.561\ \cancel{g\ CO_2})\left(\frac{1\ mol\ CO_2}{44.0\ \cancel{g\ CO_2}}\right) = 0.0128\ mol\ CO_2$$

Since one mole of CO_2 is made up of one mole of C and two moles of O, if we have 0.0128 moles of CO_2 in our sample, then we know we have 0.0128 moles of C in the sample. How many grams of C is this?

$$(0.0128\ \cancel{mol\ C})\left(\frac{12.011\ g\ C}{1\ \cancel{mol\ C}}\right) = 0.154\ g\ C$$

How about the hydrogen?

$$(0.306\ \cancel{g\ H_2O})\left(\frac{1\ mol\ H_2O}{18.0\ \cancel{g\ H_2O}}\right) = 0.017\ mol\ H_2O$$

Since one mole of H_2O is made up of one mole of oxygen and ***two*** moles of hydrogen, if we have 0.017 moles of H_2O, then we have 2*(0.017) = 0.034 moles of hydrogen. Since hydrogen is about 1 gram/mole, we must have **0.034 grams of hydrogen** in our original sample.

When we add our carbon and hydrogen together we get:

0.154 grams (C) + 0.034 grams (H) = **0.188 grams**

But we know we combusted *0.255 grams* of isopropyl alcohol. The 'missing' mass must be from the oxygen atoms in the isopropyl alcohol:

0.255 grams - 0.188 grams = 0.067 grams oxygen

This much oxygen is how many moles?

$$(0.067\ \cancel{g\ O})\left(\frac{1\ mol\ O}{15.994\ \cancel{g\ O}}\right) = 0.0042\ mol\ O$$

Overall therefore, we have:

- 0.0128 moles Carbon
- 0.0340 moles Hydrogen
- 0.0042 moles Oxygen

Divide by the smallest molar amount to normalize:

- C = 3.05 atoms
- H = 8.1 atoms
- O = 1 atom

Within experimental error, the most likely empirical formula for propanol would be C_3H_8O

Example 2.7.4: Combustion of Naphalene

Naphthalene, the active ingredient in one variety of mothballs, is an organic compound that contains carbon and hydrogen only. Complete combustion of a 20.10 mg sample of naphthalene in oxygen yielded 69.00 mg of CO_2 and 11.30 mg of H_2O. Determine the empirical formula of naphthalene.

Given: mass of sample and mass of combustion products

Asked for: empirical formula

Strategy:

A. Use the masses and molar masses of the combustion products, CO_2 and H_2O, to calculate the masses of carbon and hydrogen present in the original sample of naphthalene.
B. Use those masses and the molar masses of the elements to calculate the empirical formula of naphthalene.

Solution:

A Upon combustion, 1 mol of $\mathbf{CO_2}$ is produced for each mole of carbon atoms in the original sample. Similarly, 1 mol of H_2O is produced for every 2 mol of hydrogen atoms present in the sample. The masses of carbon and hydrogen in the original sample can be calculated from these ratios, the masses of CO_2 and H_2O, and their molar masses. Because the units of molar mass are grams per mole, we must first convert the masses from milligrams to grams:

$$mass\ of\ C = 69.00\,mg\,CO_2 \times \frac{1\,g}{1000\,mg} \times \frac{1\,mol\,CO_2}{44.010\,g\,CO_2} \times \frac{1\,mol C}{1\,mol\,CO_2} \times \frac{12.011\,g}{1\,mol\,C}$$

$$= 1.883 \times 10^{-2}\,g\,C$$

$$mass\ of\ H = 11.30\,mg\,H_2O \times \frac{1\,g}{1000\,mg} \times \frac{1\,mol\,H_2O}{18.015\,g\,H_2O} \times \frac{2\,mol H}{1\,mol\,H_2O} \times \frac{1.0079\,g}{1\,mol\,H}$$

$$= 1.264 \times 10^{-3}\,g\,H$$

B To obtain the relative numbers of atoms of both elements present, we need to calculate the number of moles of each and divide by the number of moles of the element present in the smallest amount:

$$moles\,C = 1.883 \times 10^{-2}\,g\,C \times \frac{1\,mol\,C}{12.011\,g\,C} = 1.568 \times 10^{-3}\,molC$$

$$moles\,H = 1.264 \times 10^{-3}\,g\,H \times \frac{1\,mol\,H}{1.0079\,g\,H} = 1.254 \times 10^{-3}\,molH$$

Dividing each number by the number of moles of the element present in the smaller amount gives

$$H: \frac{1.254 \times 10^{-3}}{1.254 \times 10^{-3}} = 1.000 \quad C: \frac{1.568 \times 10^{-3}}{1.254 \times 10^{-3}} = 1.250$$

Thus naphthalene contains a 1.25:1 ratio of moles of carbon to moles of hydrogen: $C_{1.25}H_{1.0}$. Because the ratios of the elements in the empirical formula must be expressed as small whole numbers, multiply both subscripts by 4, which gives C_5H_4 as the empirical formula of naphthalene. In fact, the chemical formula of naphthalene is $C_{10}H_8$, which is consistent with our results.

? Exercise 2.7.4

a. Xylene, an organic compound that is a major component of many gasoline blends, contains carbon and hydrogen only. Complete combustion of a 17.12 mg sample of xylene in oxygen yielded 56.77 mg of CO_2 and 14.53 mg of H_2O. Determine the empirical formula of xylene.
b. The empirical formula of benzene is CH (its chemical formula is C_6H_6). If 10.00 mg of benzene is subjected to combustion analysis, what mass of CO_2 and H_2O will be produced?

Answer a

The empirical formula is C_4H_5. (The chemical formula of xylene is actually C_8H_{10}.)

Answer b

33.81 mg of CO_2; 6.92 mg of H_2O



Combustion Analysis: Combustion Analysis, YouTube(opens in new window) [youtu.be]

2.7: Composition of Compounds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.5: Empirical Formulas from Analysis** by Micheal Blaber is licensed CC BY-NC-SA 3.0. Original source: https://archive.cnx.org/contents/09bb192b-eeee-4363-9c97-ee6653400cd61/introduction-to-combustion-analysis.

2.8: Determining a Chemical Formula from Experimental Data

In the previous section, we discussed the relationship between the bulk mass of a substance and the number of atoms or molecules it contains (moles). Given the chemical formula of the substance, we were able to determine the amount of the substance (moles) from its mass, and vice versa. But what if the chemical formula of a substance is unknown? In this section, we will explore how to apply these very same principles in order to derive the chemical formulas of unknown substances from experimental mass measurements.

Derivation of Molecular Formulas

Recall that empirical formulas are symbols representing the *relative* numbers of a compound's elements. Determining the *absolute* numbers of atoms that compose a single molecule of a covalent compound requires knowledge of both its empirical formula and its molecular mass or molar mass. These quantities may be determined experimentally by various measurement techniques. Molecular mass, for example, is often derived from the mass spectrum of the compound (see discussion of this technique in the previous chapter on atoms and molecules). Molar mass can be measured by a number of experimental methods, many of which will be introduced in later chapters of this text.

Molecular formulas are derived by comparing the compound's molecular or molar mass to its empirical formula mass. As the name suggests, an empirical formula mass is the sum of the average atomic masses of all the atoms represented in an empirical formula. If we know the molecular (or molar) mass of the substance, we can divide this by the empirical formula mass in order to identify the number of empirical formula units per molecule, which we designate as n:

$$\frac{\text{molecular or molar mass}\left(\text{amu or }\frac{\text{g}}{\text{mol}}\right)}{\text{empirical formula mass}\left(\text{amu or }\frac{\text{g}}{\text{mol}}\right)} = n\ \text{formula units/molecule} \tag{2.8.1}$$

The molecular formula is then obtained by multiplying each subscript in the empirical formula by n, as shown by the generic empirical formula A_xB_y:

Double subscripts: use braces to clarify

For example, consider a covalent compound whose empirical formula is determined to be CH_2O. The empirical formula mass for this compound is approximately 30 amu (the sum of 12 amu for one C atom, 2 amu for two H atoms, and 16 amu for one O atom). If the compound's molecular mass is determined to be 180 amu, this indicates that molecules of this compound contain six times the number of atoms represented in the empirical formula:

$$\frac{180\ \text{amu/molecule}}{30\ \frac{\text{amu}}{\text{formula unit}}} = 6\ \text{formula units/molecule} \tag{2.8.2}$$

Molecules of this compound are then represented by molecular formulas whose subscripts are six times greater than those in the empirical formula:

$$(CH_2O)_6 = C_6H_{12}O_6 \tag{2.8.3}$$

Note that this same approach may be used when the molar mass (g/mol) instead of the molecular mass (amu) is used. In this case, we are merely considering one mole of empirical formula units and molecules, as opposed to single units and molecules.

Determination of the Molecular Formula for Nicotine

Nicotine, an alkaloid in the nightshade family of plants that is mainly responsible for the addictive nature of cigarettes, contains 74.02% C, 8.710% H, and 17.27% N. If 40.57 g of nicotine contains 0.2500 mol nicotine, what is the molecular formula?

Solution

Determining the molecular formula from the provided data will require comparison of the compound's empirical formula mass to its molar mass. As the first step, use the percent composition to derive the compound's empirical formula. Assuming a convenient, a 100-g sample of nicotine yields the following molar amounts of its elements:

$$(74.02\ \text{g C})\left(\frac{1\ \text{mol C}}{12.01\ \text{g C}}\right) = 6.163\ \text{mol C} \tag{2.8.4}$$

$$(8.710\ \text{g H})\left(\frac{1\ \text{mol H}}{1.01\ \text{g H}}\right) = 8.624\ \text{mol H} \tag{2.8.5}$$

$$(17.27\ \text{g N})\left(\frac{1\ \text{mol N}}{14.01\ \text{g N}}\right) = 1.233\ \text{mol N} \tag{2.8.6}$$

Next, we calculate the molar ratios of these elements.

The C-to-N and H-to-N molar ratios are adequately close to whole numbers, and so the empirical formula is C_5H_7N. The empirical formula mass for this compound is therefore 81.13 amu/formula unit, or 81.13 g/mol formula unit.

We calculate the molar mass for nicotine from the given mass and molar amount of compound:

$$\frac{40.57\ \text{g nicotine}}{0.2500\ \text{mol nicotine}} = \frac{162.3\ \text{g}}{\text{mol}}$$

Comparing the molar mass and empirical formula mass indicates that each nicotine molecule contains two formula units:

$$\frac{162.3\ \text{g/mol}}{81.13\ \frac{\text{g}}{\text{formula unit}}} = 2\ \text{formula units/molecule}$$

Thus, we can derive the molecular formula for nicotine from the empirical formula by multiplying each subscript by two:

$$(C_5H_7N)_6 = C_{10}H_{14}N_2$$

Exercise 2.8.5

What is the molecular formula of a compound with a percent composition of 49.47% C, 5.201% H, 28.84% N, and 16.48% O, and a molecular mass of 194.2 amu?

Answer

$C_8H_{10}N_4O_2$

Summary

The chemical identity of a substance is defined by the types and relative numbers of atoms composing its fundamental entities (molecules in the case of covalent compounds, ions in the case of ionic compounds). A compound's percent composition provides the mass percentage of each element in the compound, and it is often experimentally determined and used to derive the compound's empirical formula. The empirical formula mass of a covalent compound may be compared to the compound's molecular or molar mass to derive a molecular formula.

Combustion Analysis

When a compound containing carbon and hydrogen is subject to combustion with oxygen in a special combustion apparatus all the carbon is converted to CO_2 and the hydrogen to H_2O (Figure 2.8.2). The amount of carbon produced can be determined by measuring the amount of CO_2 produced. This is trapped by the sodium hydroxide, and thus we can monitor the mass of CO_2 produced by determining the increase in mass of the CO_2 trap. Likewise, we can determine the amount of H produced by the amount of H_2O trapped by the magnesium perchlorate.




***Figure* 2.8.2:** *Combustion analysis apparatus*

One of the most common ways to determine the elemental composition of an unknown hydrocarbon is an analytical procedure called combustion analysis. A small, carefully weighed sample of an unknown compound that may contain carbon, hydrogen, nitrogen, and/or sulfur is burned in an oxygen atmosphere,Other elements, such as metals, can be determined by other methods. and the quantities of the resulting gaseous products (CO_2, H_2O, N_2, and SO_2, respectively) are determined by one of several possible methods. One procedure used in combustion analysis is outlined schematically in Figure **2.8.3** and a typical combustion analysis is illustrated in Examples **2.8.3** and **2.8.4**.




Figure **2.8.3**: Steps for Obtaining an Empirical Formula from Combustion Analysis

Example 2.8.3: Combustion of Isopropyl Alcohol

What is the empirical formulate for isopropyl alcohol (which contains only C, H and O) if the combustion of a 0.255 grams isopropyl alcohol sample produces 0.561 grams of CO_2 and 0.306 grams of H_2O?

Solution

From this information quantitate the amount of C and H in the sample.

$$(0.561\ \cancel{g\ CO_2})\left(\frac{1\ mol\ CO_2}{44.0\ \cancel{g\ CO_2}}\right) = 0.0128\ mol\ CO_2 \tag{2.8.7}$$

Since one mole of CO_2 is made up of one mole of C and two moles of O, if we have 0.0128 moles of CO_2 in our sample, then we know we have 0.0128 moles of C in the sample. How many grams of C is this?

$$(0.0128\ \cancel{mol\ C})\left(\frac{12.011\ g\ C}{1\ \cancel{mol\ C}}\right) = 0.154\ g\ C \tag{2.8.8}$$

How about the hydrogen?

$$(0.306\ \cancel{g\ H_2O})\left(\frac{1\ mol\ H_2O}{18.0\ \cancel{g\ H_2O}}\right) = 0.017\ mol\ H_2O \tag{2.8.9}$$

Since one mole of H_2O is made up of one mole of oxygen and ***two*** moles of hydrogen, if we have 0.017 moles of H_2O, then we have 2*(0.017) = 0.034 moles of hydrogen. Since hydrogen is about 1 gram/mole, we must have **0.034 grams of hydrogen** in our original sample.

When we add our carbon and hydrogen together we get:

0.154 grams (C) + 0.034 grams (H) = **0.188 grams**

But we know we combusted *0.255 grams* of isopropyl alcohol. The 'missing' mass must be from the oxygen atoms in the isopropyl alcohol:

0.255 grams - 0.188 grams = 0.067 grams oxygen

This much oxygen is how many moles?

$$(0.067\ \cancel{g\ O})\left(\frac{1\ mol\ O}{15.994\ \cancel{g\ O}}\right) = 0.0042\ mol\ O \tag{2.8.10}$$

Overall therefore, we have:

- 0.0128 moles Carbon
- 0.0340 moles Hydrogen
- 0.0042 moles Oxygen

Divide by the smallest molar amount to normalize:

- C = 3.05 atoms
- H = 8.1 atoms
- O = 1 atom

Within experimental error, the most likely empirical formula for propanol would be C_3H_8O

Example 2.8.4: Combustion of Naphalene

Naphthalene, the active ingredient in one variety of mothballs, is an organic compound that contains carbon and hydrogen only. Complete combustion of a 20.10 mg sample of naphthalene in oxygen yielded 69.00 mg of CO_2 and 11.30 mg of H_2O. Determine the empirical formula of naphthalene.

Given: mass of sample and mass of combustion products

Asked for: empirical formula

Strategy:

A. Use the masses and molar masses of the combustion products, CO_2 and H_2O, to calculate the masses of carbon and hydrogen present in the original sample of naphthalene.
B. Use those masses and the molar masses of the elements to calculate the empirical formula of naphthalene.

Solution:

A Upon combustion, 1 mol of CO**2** is produced for each mole of carbon atoms in the original sample. Similarly, 1 mol of H_2O is produced for every 2 mol of hydrogen atoms present in the sample. The masses of carbon and hydrogen in the original

sample can be calculated from these ratios, the masses of CO_2 and H_2O, and their molar masses. Because the units of molar mass are grams per mole, we must first convert the masses from milligrams to grams:

$$\underset{mass\ of\ C}{} = 69.00\,mg\,CO_2 \times \frac{1\,g}{1000\,mg} \times \frac{1\,mol\,CO_2}{44.010\,g\,CO_2} \times \frac{1\,molC}{1\,mol\,CO_2} \times \frac{12.011\,g}{1\,mol\,C} \tag{2.8.11}$$

$$= 1.883 \times 10^{-2}\,g\,C \tag{2.8.12}$$

$$\underset{mass\ of\ H}{} = 11.30\,mg\,H_2O \times \frac{1\,g}{1000\,mg} \times \frac{1\,mol\,H_2O}{18.015\,g\,H_2O} \times \frac{2\,molH}{1\,mol\,H_2O} \times \frac{1.0079\,g}{1\,mol\,H} \tag{2.8.13}$$

$$= 1.264 \times 10^{-3}\,g\,H \tag{2.8.14}$$

B To obtain the relative numbers of atoms of both elements present, we need to calculate the number of moles of each and divide by the number of moles of the element present in the smallest amount:

$$moles\,C = 1.883 \times 10^{-2}\,g\,C \times \frac{1\,mol\,C}{12.011\,g\,C} = 1.568 \times 10^{-3}\,molC \tag{2.8.15}$$

$$moles\,H = 1.264 \times 10^{-3}\,g\,H \times \frac{1\,mol\,H}{1.0079\,g\,H} = 1.254 \times 10^{-3}\,molH \tag{2.8.16}$$

Dividing each number by the number of moles of the element present in the smaller amount gives

$$H: \frac{1.254 \times 10^{-3}}{1.254 \times 10^{-3}} = 1.000 \quad C: \frac{1.568 \times 10^{-3}}{1.254 \times 10^{-3}} = 1.250 \tag{2.8.17}$$

Thus naphthalene contains a 1.25:1 ratio of moles of carbon to moles of hydrogen: $C_{1.25}H_{1.0}$. Because the ratios of the elements in the empirical formula must be expressed as small whole numbers, multiply both subscripts by 4, which gives C_5H_4 as the empirical formula of naphthalene. In fact, the molecular formula of naphthalene is $C_{10}H_8$, which is consistent with our results.

Exercise 2.8.4

a. Xylene, an organic compound that is a major component of many gasoline blends, contains carbon and hydrogen only. Complete combustion of a 17.12 mg sample of xylene in oxygen yielded 56.77 mg of CO_2 and 14.53 mg of H_2O. Determine the empirical formula of xylene.

b. The empirical formula of benzene is CH (its molecular formula is C_6H_6). If 10.00 mg of benzene is subjected to combustion analysis, what mass of CO_2 and H_2O will be produced?

Answer a

The empirical formula is C_4H_5. (The molecular formula of xylene is actually C_8H_{10}.)

Answer b

33.81 mg of CO_2; 6.92 mg of H_2O

Contributors and Attributions

- Mike Blaber (Florida State University)
- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

2.8: Determining a Chemical Formula from Experimental Data is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

2.9: Writing and Balancing Chemical Equations

Learning Objectives

- To describe a chemical reaction.
- To calculate the quantities of compounds produced or consumed in a chemical reaction

What happens to matter when it undergoes chemical changes? The Law of conservation of mass says that "***Atoms are neither created, nor destroyed, during any chemical reaction***." Thus, the same collection of atoms is present after a reaction as before the reaction. The changes that occur during a reaction just involve the *rearrangement* of atoms. In this section we will discuss ***stoichiometry*** (the "measurement of elements").

Chemical Equations

As shown in Figure **2.9.1**, applying a small amount of heat to a pile of orange ammonium dichromate powder results in a vigorous reaction known as the ammonium dichromate volcano. Heat, light, and gas are produced as a large pile of fluffy green chromium(III) oxide forms. This reaction is described with a chemical equation, an expression that gives the identities and quantities of the substances in a chemical reaction.



Figure **2.9.1**: An Ammonium Dichromate Volcano: Change during a Chemical Reaction. The starting material is solid ammonium dichromate. A chemical reaction transforms it to solid chromium(III) oxide, depicted showing a portion of its chained structure, nitrogen gas, and water vapor (in addition, energy in the form of heat and light is released). During the reaction, the distribution of atoms changes, but the number of atoms of each element does not change. Because the numbers of each type of atom are the same in the reactants and the products, the chemical equation is balanced. (CC BY-SA 3.0; Mikk Mihkel Vaabel via Wikipedia). See video here: www.youtube.com/watch?v=CW4hN0dYnkM

Chemical reactions are represented on paper by ***chemical equations***. For example, hydrogen gas (H_2) can react (burn) with oxygen gas (O_2) to form water (H_2O). The *chemical equation* for this *reaction* is written as:

$$2\,H_2 + O_2 \rightarrow 2\,H_2O$$

Chemical formulas and other symbols are used to indicate the starting materials, or reactants, which by convention are written on the left side of the equation, and the final compounds, or products, which are written on the right. An arrow points from the reactant to the products. The chemical reaction for the ammonium dichromate volcano in Figure **2.9.1** is

$$\underbrace{(NH_4)_2Cr_2O_7}_{reactant} \rightarrow \underbrace{Cr_2O_3 + N_2 + 4\,H_2O}_{products} \tag{2.9.1}$$

The arrow is read as “yields” or “reacts to form.” Equation 2.9.1 indicates that ammonium dichromate (the reactant) yields chromium(III) oxide, nitrogen, and water (the products). The equation for this reaction is even more informative when written as follows:

$$(NH_4)_2Cr_2O_7\,(s) \rightarrow Cr_2O_3\,(s) + N_2\,(g) + 4\,H_2O\,(g) \tag{2.9.2}$$

Equation 2.9.2 is identical to Equation 2.9.1 except for the addition of abbreviations in parentheses to indicate the physical state of each species. The abbreviations are (s) for solid, (l) for liquid, (g) for gas, and (aq) for an aqueous solution, a solution of the substance in water.

Consistent with the law of conservation of mass, the numbers of each type of atom are the same on both sides of Equations 2.9.1 and 2.9.2. Each side of the reaction has two chromium atoms, seven oxygen atoms, two nitrogen atoms, and eight hydrogen atoms.

In a balanced chemical equation, both the numbers of each type of atom and the total charge are the same on both sides. Equations 2.9.1 and 2.9.2 are balanced chemical equations. What is different on each side of the equation is how the atoms are arranged to make molecules or ions. A chemical reaction represents a change in the distribution of atoms, but not in the number of atoms. In this reaction, and in most chemical reactions, bonds are broken in the reactants (here, Cr–O and N–H bonds), and new bonds are formed to create the products (here, O–H and N≡N bonds). If the numbers of each type of atom are different on the two sides of a chemical equation, then the equation is unbalanced, and it cannot correctly describe what happens during the reaction. To proceed, the equation must first be balanced.

A chemical reaction changes only the distribution of atoms, not the number of atoms.



Introduction to Chemical Reaction Equations: Introduction to Chemical Reaction Equations, YouTube(opens in new window) [youtu.be]

Balancing Simple Chemical Equations

When a chemist encounters a new reaction, it does not usually come with a label that shows the balanced chemical equation. Instead, the chemist must identify the reactants and products and then write them in the form of a chemical equation that may or may not be balanced as first written. Consider, for example, the combustion of n-heptane (C_7H_{16}), an important component of gasoline:

$$\mathrm{C_7H_{16}\,(l) + O_2\,(g) \rightarrow CO_2\,(g) + H_2O\,(g)} \tag{2.9.3}$$

The complete combustion of any hydrocarbon with sufficient oxygen always yields carbon dioxide and water.



Figure 2.9.2: An Example of a Combustion Reaction. The wax in a candle is a high-molecular-mass hydrocarbon, which produces gaseous carbon dioxide and water vapor in a combustion reaction (Equation 2.9.3).

Equation 2.9.3 is not balanced: the numbers of each type of atom on the reactant side of the equation (7 carbon atoms, 16 hydrogen atoms, and 2 oxygen atoms) is not the same as the numbers of each type of atom on the product side (1 carbon atom, 2 hydrogen atoms, and 3 oxygen atoms). Consequently, the coefficients of the reactants and products must be adjusted to give the same numbers of atoms of each type on both sides of the equation. Because the identities of the reactants and products are fixed, the equation cannot be balanced by changing the subscripts of the reactants or the products. To do so would change the chemical identity of the species being described, as illustrated in Figure 2.9.3.




Figure **2.9.3**: Balancing Equations. You cannot change subscripts in a chemical formula to balance a chemical equation; you can change only the coefficients. Changing subscripts changes the ratios of atoms in the molecule and the resulting chemical properties. For example, water (H_2O) and hydrogen peroxide (H_2O_2) are chemically distinct substances. H_2O_2 decomposes to H_2O and O_2 gas when it comes in contact with the metal platinum, whereas no such reaction occurs between water and platinum.

Left: Example of changing coefficients or subscripts. Right: Platinum dissolving in hydrogen peroxide.



Balancing Combustion Reactions: Balancing Combustions Reactions, YouTube(opens in new window) [youtu.be]

The simplest and most generally useful method for balancing chemical equations is “inspection,” better known as trial and error. The following is an efficient approach to balancing a chemical equation using this method.

Steps in Balancing a Chemical Equation

1. Identify the most complex substance.
2. Beginning with that substance, choose an element that appears in only one reactant and one product, if possible. Adjust the coefficients to obtain the same number of atoms of this element on both sides.
3. Balance polyatomic ions (if present) as a unit.
4. Balance the remaining atoms, usually ending with the least complex substance and using fractional coefficients if necessary. If a fractional coefficient has been used, multiply both sides of the equation by the denominator to obtain whole numbers for the coefficients.
5. Check your work by counting the numbers of atoms of each kind on both sides of the equation to be sure that the chemical equation is balanced.

Example 2.9.1A: Combustion of Heptane

To demonstrate this approach, let’s use the combustion of n-heptane (Equation **2.9.3**) as an example.

1. **Identify the most complex substance**. The most complex substance is the one with the largest number of different atoms, which is C_7H_{16}. We will assume initially that the final balanced chemical equation contains 1 molecule or formula unit of this substance.

2. **Adjust the coefficients**. Try to adjust the coefficients of the molecules on the other side of the equation to obtain the same numbers of atoms on both sides. Because one molecule of n-heptane contains 7 carbon atoms, we need 7 CO_2 molecules, each of which contains 1 carbon atom, on the right side:

$$\mathrm{C_7H_{16} + O_2 \rightarrow 7\,CO_2 + H_2O} \tag{2.9.4}$$

3. **Balance polyatomic ions as a unit**. There are no polyatomic ions to be considered in this reaction.
4. **Balance the remaining atoms**. Because one molecule of n-heptane contains 16 hydrogen atoms, we need 8 H2O molecules, each of which contains 2 hydrogen atoms, on the right side:

$$\mathrm{C_7H_{16} + O_2 \rightarrow 7\,CO_2 + 8\,H_2O} \tag{2.9.5}$$

The carbon and hydrogen atoms are now balanced, but we have 22 oxygen atoms on the right side and only 2 oxygen atoms on the left. We can balance the oxygen atoms by adjusting the coefficient in front of the least complex substance, O_2, on the reactant side:

$$\mathrm{C_7H_{16}\,(l) + 11\,O_2\,(g) \rightarrow 7\,CO_2\,(g) + 8\,H_2O\,(g)} \tag{2.9.6}$$

5. **Check your work**. The equation is now balanced, and there are no fractional coefficients: there are 7 carbon atoms, 16 hydrogen atoms, and 22 oxygen atoms on each side. Always check to be sure that a chemical equation is balanced.The assumption that the final balanced chemical equation contains only one molecule or formula unit of the most complex substance is not always valid, but it is a good place to start.

✔ Example 2.9.1*B*: Combustion of Isooctane

Consider, for example, a similar reaction, the combustion of isooctane ($\mathrm{C_8H_{18}}$). Because the combustion of any hydrocarbon with oxygen produces carbon dioxide and water, the unbalanced chemical equation is as follows:

$$\mathrm{C_8H_{18}\,(l) + O_2\,(g) \rightarrow CO_2\,(g) + H_2O\,(g)} \tag{2.9.7}$$

1. **Identify the most complex substance**. Begin the balancing process by assuming that the final balanced chemical equation contains a single molecule of isooctane.
2. **Adjust the coefficients**. The first element that appears only once in the reactants is carbon: 8 carbon atoms in isooctane means that there must be 8 CO_2 molecules in the products:

$$\mathrm{C_8H_{18} + O_2 \rightarrow 8\,CO_2 + H_2O} \tag{2.9.8}$$

3. **Balance polyatomic ions as a unit**. This step does not apply to this equation.
4. **Balance the remaining atoms**. Eighteen hydrogen atoms in isooctane means that there must be 9 H_2O molecules in the products:

$$\mathrm{C_8H_{18} + O_2 \rightarrow 8\,CO_2 + 9\,H_2O} \tag{2.9.9}$$

The carbon and hydrogen atoms are now balanced, but we have 25 oxygen atoms on the right side and only 2 oxygen atoms on the left. We can balance the least complex substance, O_2, but because there are 2 oxygen atoms per O_2 molecule, we must use a fractional coefficient (25/2) to balance the oxygen atoms:

$$\mathrm{C_8H_{18} + \tfrac{25}{2}\,O_2 \rightarrow 8\,CO_2 + 9\,H_2O} \tag{2.9.10}$$

Equation 2.9.10 is now balanced, but we usually write equations with whole-number coefficients. We can eliminate the fractional coefficient by multiplying all coefficients on both sides of the chemical equation by 2:

$$\mathrm{2\,C_8H_{18}\,(l) + 25\,O_2\,(g) \rightarrow 16\,CO_2\,(g) + 18\,H_2O\,(g)} \tag{2.9.11}$$

5. **Check your work**. The balanced chemical equation has 16 carbon atoms, 36 hydrogen atoms, and 50 oxygen atoms on each side.



Balancing Complex Chemical Equations: Balancing Complex Chemical Equations, YouTube(opens in new window) [youtu.be]

Balancing equations requires some practice on your part as well as some common sense. If you find yourself using very large coefficients or if you have spent several minutes without success, go back and make sure that you have written the formulas of the reactants and products correctly.

Example 2.9.1C: Hydroxyapatite

The reaction of the mineral hydroxyapatite ($Ca_5(PO_4)_3(OH)$) with phosphoric acid and water gives $Ca(H_2PO_4)_2 \cdot H_2O$ (calcium dihydrogen phosphate monohydrate). Write and balance the equation for this reaction.



Hydroxyapatite (Extra close brace or missing open brace) crystal

Given: reactants and product

Asked for: balanced chemical equation

Strategy:

A. Identify the product and the reactants and then write the unbalanced chemical equation.
B. Follow the steps for balancing a chemical equation.

Solution:

A We must first identify the product and reactants and write an equation for the reaction. The formulas for hydroxyapatite and calcium dihydrogen phosphate monohydrate are given in the problem (recall that phosphoric acid is H_3PO_4). The initial (unbalanced) equation is as follows:

$$Ca_5(PO_4)_3(OH)\,(s) + H_3PO_4\,(aq) + H_2O_{(l)} \rightarrow Ca(H_2PO_4)_2 \cdot H_2O_{(s)}$$

1. **B Identify the most complex substance**. We start by assuming that only one molecule or formula unit of the most complex substance, $Ca_5(PO_4)_3(OH)$, appears in the balanced chemical equation.

2. **Adjust the coefficients**. Because calcium is present in only one reactant and one product, we begin with it. One formula unit of $Ca_5(PO_4)_3(OH)$ contains 5 calcium atoms, so we need 5 $Ca(H_2PO_4)_2$•H_2O on the right side:

$$Ca_5(PO_4)_3(OH) + H_3PO_4 + H_2O \rightarrow 5\,Ca(H_2PO_4)_2 \cdot H_2O$$

3. **Balance polyatomic ions as a unit**. It is usually easier to balance an equation if we recognize that certain combinations of atoms occur on both sides. In this equation, the polyatomic phosphate ion (PO_4^{3-}), shows up in three places. In H_3PO_4, the phosphate ion is combined with three H^+ ions to make phosphoric acid (H_3PO_4), whereas in $Ca(H_2PO_4)_2 \cdot H_2O$ it is combined with two H^+ ions to give the dihydrogen phosphate ion. Thus it is easier to balance PO_4 as a unit rather than counting individual phosphorus and oxygen atoms. There are 10 PO_4 units on the right side but only 4 on the left. The simplest way to balance the PO_4 units is to place a coefficient of 7 in front of H_3PO_4:

$$\mathrm{Ca_5(PO_4)_3(OH) + 7\,H_3PO_4 + H_2O \rightarrow 5\,Ca(H_2PO_4)_2 \cdot H_2O}$$

Although OH^- is also a polyatomic ion, it does not appear on both sides of the equation. So oxygen and hydrogen must be balanced separately.

4. **Balance the remaining atoms**. We now have 30 hydrogen atoms on the right side but only 24 on the left. We can balance the hydrogen atoms using the least complex substance, H_2O, by placing a coefficient of 4 in front of H_2O on the left side, giving a total of 4 H_2O molecules:

$$\mathrm{Ca_5(PO_4)_3(OH)\,(s) + 7\,H_3PO_4\,(aq) + 4\,H_2O\,(l) \rightarrow 5\,Ca(H_2PO_4)_2 \cdot H_2O\,(s)}$$

The equation is now balanced. Even though we have not explicitly balanced the oxygen atoms, there are 41 oxygen atoms on each side.

5. **Check your work**. Both sides of the equation contain 5 calcium atoms, 10 phosphorus atoms, 30 hydrogen atoms, and 41 oxygen atoms.

? Exercise 2.9.1: Fermentation

Fermentation is a biochemical process that enables yeast cells to live in the absence of oxygen. Humans have exploited it for centuries to produce wine and beer and make bread rise. In fermentation, sugars such as glucose are converted to ethanol (CH_3CH_2OH and carbon dioxide CO_2. Write a balanced chemical reaction for the fermentation of glucose.



Commercial use of fermentation. *(a) Microbrewery vats are used to prepare beer. (b) The fermentation of glucose by yeast cells is the reaction that makes beer production possible.*

Answer

$$C_6H_{12}O_6(s) \rightarrow 2C_2H_5OH(l) + 2CO_2(g)$$



Balancing Reactions Which Contain Polyatomics: Balancing Reactions Which Contain Polyatomics, YouTube(opens in new window) [youtu.be]

Interpreting Chemical Equations

In addition to providing qualitative information about the identities and physical states of the reactants and products, a balanced chemical equation provides quantitative information. Specifically, it gives the relative amounts of reactants and products consumed or produced in a reaction. The number of atoms, molecules, or formula units of a reactant or a product in a balanced chemical equation is the coefficient of that species (e.g., the 4 preceding H_2O in Equation 2.9.1). When no coefficient is written in front of a species, the coefficient is assumed to be 1. As illustrated in Figure **2.9.4**, the coefficients allow Equation 2.9.1 to be interpreted in any of the following ways:

- Two NH_4^+ ions and one $Cr_2O_7^{2-}$ ion yield 1 formula unit of Cr_2O_3, 1 N_2 molecule, and 4 H_2O molecules.
- One mole of $(NH_4)_2Cr_2O_7$ yields 1 mol of Cr_2O_3, 1 mol of N_2, and 4 mol of H_2O.
- A mass of 252 g of $(NH_4)_2Cr_2O_7$ yields 152 g of Cr_2O_3, 28 g of N_2, and 72 g of H_2O.
- A total of 6.022×10^{23} formula units of $(NH_4)_2Cr_2O_7$ yields 6.022×10^{23} formula units of Cr_2O_3, 6.022×10^{23} molecules of N_2, and 24.09×10^{23} molecules of H_2O.




Figure **2.9.4**: The Relationships among Moles, Masses, and Formula Units of Compounds in the Balanced Chemical Reaction for the Ammonium Dichromate Volcano

Chemical equation: (N H 4) 2 C r 2 O 7 dissociates into C r 2 O 3, N 2, and H 2 O. Conversions are given between moles, mass, and molecules.

These are all chemically equivalent ways of stating the information given in the balanced chemical equation, using the concepts of the mole, molar or formula mass, and Avogadro's number. The ratio of the number of moles of one substance to the number of moles of another is called the mole ratio. For example, the mole ratio of H_2O to N_2 in Equation 2.9.1 is 4:1. The total mass of reactants equals the total mass of products, as predicted by Dalton's law of conservation of mass:

$$252\ g\ \text{of}\ (NH_4)_2Cr_2O_7$$

yield

$$152 + 28 + 72 = 252\ g \text{ of products.}$$

The chemical equation does not, however, show the rate of the reaction (rapidly, slowly, or not at all) or whether energy in the form of heat or light is given off. These issues are considered in more detail in later chapters.

An important chemical reaction was analyzed by Antoine Lavoisier, an 18th-century French chemist, who was interested in the chemistry of living organisms as well as simple chemical systems. In a classic series of experiments, he measured the carbon dioxide and heat produced by a guinea pig during respiration, in which organic compounds are used as fuel to produce energy, carbon dioxide, and water. Lavoisier found that the ratio of heat produced to carbon dioxide exhaled was similar to the ratio observed for the reaction of charcoal with oxygen in the air to produce carbon dioxide—a process chemists call combustion. Based on these experiments, he proposed that "Respiration is a combustion, slow it is true, but otherwise perfectly similar to that of charcoal." Lavoisier was correct, although the organic compounds consumed in respiration are substantially different from those found in charcoal. One of the most important fuels in the human body is glucose ($C_6H_{12}O_6$), which is virtually the only fuel used in the brain. Thus combustion and respiration are examples of chemical reactions.


Example 2.9.2: Combustion of Glucose

The balanced chemical equation for the combustion of glucose in the laboratory (or in the brain) is as follows:

$$\mathrm{C_6H_{12}O_6\,(s) + 6\,O_2\,(g) \rightarrow 6\,CO_2\,(g) + 6\,H_2O\,(l)}$$

Construct a table showing how to interpret the information in this equation in terms of

a. a single molecule of glucose.
b. moles of reactants and products.
c. grams of reactants and products represented by 1 mol of glucose.
d. numbers of molecules of reactants and products represented by 1 mol of glucose.



The combustion of a sugar cube consisting of sucrose with a similar reaction to the combustion of glucose. from Wikipedia.

Given: balanced chemical equation

Asked for: molecule, mole, and mass relationships

Strategy:

A. Use the coefficients from the balanced chemical equation to determine both the molecular and mole ratios.
B. Use the molar masses of the reactants and products to convert from moles to grams.
C. Use Avogadro's number to convert from moles to the number of molecules.

Solution:

This equation is balanced as written: each side has 6 carbon atoms, 18 oxygen atoms, and 12 hydrogen atoms. We can therefore use the coefficients directly to obtain the desired information.

a. One molecule of glucose reacts with 6 molecules of O_2 to yield 6 molecules of CO_2 and 6 molecules of H_2O.
b. One mole of glucose reacts with 6 mol of O_2 to yield 6 mol of CO_2 and 6 mol of H_2O.

c. To interpret the equation in terms of masses of reactants and products, we need their molar masses and the mole ratios from part b. The molar masses in grams per mole are as follows: glucose, 180.16; O_2, 31.9988; CO_2, 44.010; and H_2O, 18.015.

$$\textbf{mass of reactants} = \textbf{mass of products}$$

$$g\,glucose + g\,O_2 = g\,CO_2 + g\,H_2O$$

$$1\,mol\,glucose\left(\frac{180.16\,g}{1\,mol\,glucose}\right) + 6\,mol\,O_2\left(\frac{31.9988\,g}{1\,mol\,O_2}\right)$$

$$= 6\,mol\,CO_2\left(\frac{44.010\,g}{1\,mol\,CO_2}\right) + 6\,mol\,H_2O\left(\frac{18.015\,g}{1\,mol\,H_2O}\right)$$

$$372.15\,g = 372.15\,g$$

C One mole of glucose contains Avogadro's number (6.022×10^{23}) of glucose molecules. Thus 6.022×10^{23} glucose molecules react with ($6 \times 6.022 \times 10^{23}$) = 3.613×10^{24} oxygen molecules to yield ($6 \times 6.022 \times 10^{23}$) = 3.613×10^{24} molecules each of CO_2 and H_2O.

In tabular form:

Solution to Example 3.1.2

	$C_6H_{12}O_{6\,(s)}$	+	$6O_{2\,(g)}$	→	$6CO_{2\,(g)}$		$6H_2O_{(l)}$
a.	1 molecule		6 molecules		6 molecules		6 molecules
b.	1 mol		6 mol		6 mol		6 mol
c.	180.16 g		191.9928 g		264.06 g		108.09 g
d.	6.022×10^{23} molecules		3.613×10^{24} molecules		3.613×10^{24} molecules		3.613×10^{24} molecule

? Exercise 2.9.2: Ammonium Nitrate Explosion

Ammonium nitrate is a common fertilizer, but under the wrong conditions it can be hazardous. In 1947, a ship loaded with ammonium nitrate caught fire during unloading and exploded, destroying the town of Texas City, Texas.



Ammonium nitrate can be hazardous. This aerial photograph of Texas City, Texas, shows the devastation caused by the explosion of a shipload of ammonium nitrate on April 16, 1947. For a video click here.

The explosion resulted from the following reaction:

$$2NH_4NO_{3\,(s)} \rightarrow 2N_{2\,(g)} + 4H_2O_{(g)} + O_{2\,(g)}$$

Construct a table showing how to interpret the information in the equation in terms of

a. individual molecules and ions.
b. moles of reactants and products.
c. grams of reactants and products given 2 mol of ammonium nitrate.
d. numbers of molecules or formula units of reactants and products given 2 mol of ammonium nitrate.

Answer:

Answer to Exercise 3.1.2

	$2NH_4NO_{3\,(s)}$	→	$2N_{2\,(g)}$	+	$4H_2O_{(g)}$	+	$O_{2\,(g)}$
a.	$2NH_4^+$ ions and $2NO_3^-$ ions		2 molecules		4 molecules		1 molecule
b.	2 mol		2 mol		4 mol		1 mol
c.	160.0864 g		56.0268 g		72.0608 g		31.9988 g
d.	1.204×10^{24} formula units		1.204×10^{24} molecules		2.409×10^{24} molecules		6.022×10^{23} molecules



Finding Mols and Masses of Reactants and Products Using Stoichiometric Factors (Mol Ratios): Finding Mols and Masses of Reactants and Products Using Stoichiometric Factors, YouTube(opens in new window) [youtu.be]

Summary

A chemical reaction is described by a chemical equation that gives the identities and quantities of the reactants and the products. In a chemical reaction, one or more substances are transformed to new substances. A chemical reaction is described by a **chemical equation**, an expression that gives the identities and quantities of the substances involved in a reaction. A chemical equation shows the starting compound(s)—the **reactants**—on the left and the final compound(s)—the **products**—on the right, separated by an arrow. In a balanced chemical equation, the numbers of atoms of each element and the total charge are the same on both sides of the equation. The number of atoms, molecules, or formula units of a reactant or product in a balanced chemical equation is the **coefficient** of that species. The **mole ratio** of two substances in a chemical reaction is the ratio of their coefficients in the balanced chemical equation.

2.9: Writing and Balancing Chemical Equations is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.1: Chemical Equations** by Anonymous is licensed CC BY-NC-SA 3.0.

CHAPTER OVERVIEW

3: Calculations with Chemical Equations and Solution Concentrations

Template:HideTOC

3.1: How Much Carbon Dioxide?

3.2: 4.3 Limiting Reactant, Theoretical Yield, and Percent Yield

3.3: Solution Concentration and Solution Stoichiomentry

Thumbnail: Copper from a wire is displaced by silver in a silver nitrate solution it is dipped into, and solid silver precipitates out. (CC BY-SA 3.0 au; Toby Hudson via Wikipedia).

3: Calculations with Chemical Equations and Solution Concentrations is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

3.1: How Much Carbon Dioxide?

Learning Objectives

- Explain the concept of stoichiometry as it pertains to chemical reactions
- Use balanced chemical equations to derive stoichiometric factors relating amounts of reactants and products
- Perform stoichiometric calculations involving mass, moles, and solution molarity

A balanced chemical equation provides a great deal of information in a very succinct format. Chemical formulas provide the identities of the reactants and products involved in the chemical change, allowing classification of the reaction. Coefficients provide the relative numbers of these chemical species, allowing a quantitative assessment of the relationships between the amounts of substances consumed and produced by the reaction. These quantitative relationships are known as the reaction's stoichiometry, a term derived from the Greek words *stoicheion* (meaning "element") and *metron* (meaning "measure"). In this module, the use of balanced chemical equations for various stoichiometric applications is explored.

The general approach to using stoichiometric relationships is similar in concept to the way people go about many common activities. Cooking, for example, offers an appropriate comparison. Suppose a recipe for making eight pancakes calls for 1 cup pancake mix, $\frac{3}{4}$ cup milk, and one egg. The "equation" representing the preparation of pancakes per this recipe is

$$\mathrm{1\ cup\ mix} + \frac{3}{4}\ \mathrm{cup\ milk} + \mathrm{1\ egg} \rightarrow \mathrm{8\ pancakes} \tag{3.1.1}$$

If two dozen pancakes are needed for a big family breakfast, the ingredient amounts must be increased proportionally according to the amounts given in the recipe. For example, the number of eggs required to make 24 pancakes is

$$24\ \cancel{\mathrm{pancakes}} \times \frac{1\ \mathrm{egg}}{8\ \cancel{\mathrm{pancakes}}} = 3\ \mathrm{eggs} \tag{3.1.2}$$

Balanced chemical equations are used in much the same fashion to determine the amount of one reactant required to react with a given amount of another reactant, or to yield a given amount of product, and so forth. The coefficients in the balanced equation are used to derive stoichiometric factors that permit computation of the desired quantity. To illustrate this idea, consider the production of ammonia by reaction of hydrogen and nitrogen:

$$\mathrm{N_2}(g) + 3\,\mathrm{H_2}(g) \rightarrow 2\,\mathrm{NH_3}(g) \tag{3.1.3}$$

This equation shows that ammonia molecules are produced from hydrogen molecules in a 2:3 ratio, and stoichiometric factors may be derived using any amount (number) unit:

$$\frac{2\,NH3\ molecules}{3H2\ molecules} \text{ or } \frac{2\ doz\ NH3\ molecules}{3\ doz\ H2\ molecules} \text{ or } \frac{2\ mol\ NH3\ molecules}{3\ mol\ H2\ molecules} \tag{3.1.4}$$

These stoichiometric factors can be used to compute the number of ammonia molecules produced from a given number of hydrogen molecules, or the number of hydrogen molecules required to produce a given number of ammonia molecules. Similar factors may be derived for any pair of substances in any chemical equation.

Example 3.1.1: Moles of Reactant Required in a Reaction

How many moles of I_2 are required to react with 0.429 mol of Al according to the following equation (see Figure 3.1.2)?

$$2\,\mathrm{Al} + 3\,\mathrm{I_2} \rightarrow 2\,\mathrm{AlI_3} \tag{3.1.5}$$





Figure 3.1.1: Aluminum and iodine react to produce aluminum iodide. The heat of the reaction vaporizes some of the solid iodine as a purple vapor. (credit: modification of work by Mark Ott)

Three pictures showing the progression of the reaction between iodine and aluminum. The first diagram shows only a pile of silver powder while the second diagram shows small amount of vapor forming. The final picture shows a large release of purple vapor.

Solution

Referring to the balanced chemical equation, the stoichiometric factor relating the two substances of interest is $\frac{3\ mol\ I2}{2\ mol\ Al}$. The molar amount of iodine is derived by multiplying the provided molar amount of aluminum by this factor:



$$\text{mol I}_2 = 0.429\ \cancel{\text{mol Al}} \times \frac{3\ \text{mol I}_2}{2\ \cancel{\text{mol Al}}}$$

$$= 0.644\ \text{mol I}_2$$

Exercise 3.1.1

How many moles of $Ca(OH)_2$ are required to react with 1.36 mol of H_3PO_4 to produce $Ca_3(PO_4)_2$ according to the equation $3\,Ca(OH)_2 + 2\,H_3PO_4 \rightarrow Ca_3(PO_4)_2 + 6\,H_2O$?

Answer

2.04 mol

Example 3.1.2: Number of Product Molecules Generated by a Reaction

How many carbon dioxide molecules are produced when 0.75 mol of propane is combusted according to this equation?

$$C_3H_8 + 5\,O_2 \rightarrow 3\,CO_2 + 4\,H_2O \tag{3.1.6}$$


Solution

The approach here is the same as for Example 3.1.1, though the absolute number of molecules is requested, not the number of moles of molecules. This will simply require use of the moles-to-numbers conversion factor, Avogadro's number.

The balanced equation shows that carbon dioxide is produced from propane in a 3:1 ratio:

\[\ce{\dfrac{3\: mol\: CO2}{1\: mol\: C3H8}} \label{4.4.7} \]

Using this stoichiometric factor, the provided molar amount of propane, and Avogadro's number,



$$0.75\ \cancel{\text{mol C}_3\text{H}_8} \times \frac{3\ \cancel{\text{mol CO}_2}}{1\ \cancel{\text{mol C}_3\text{H}_8}} \times \frac{6.022 \times 10^{23}\ \text{CO}_2\ \text{molecules}}{\cancel{\text{mol CO}_2}} \tag{3.1.7}$$

$$= 1.4 \times 10^{24}\ \text{CO}_2\ \text{molecules}$$

? Exercise 3.1.1

How many NH_3 molecules are produced by the reaction of 4.0 mol of $Ca(OH)_2$ according to the following equation:

$$(NH_4)_2SO_4 + Ca(OH)_2 \rightarrow 2\,NH_3 + CaSO_4 + 2\,H_2O \tag{3.1.8}$$

Answer

4.8×10^{24} NH_3 molecules

These examples illustrate the ease with which the amounts of substances involved in a chemical reaction of known stoichiometry may be related. Directly measuring numbers of atoms and molecules is, however, not an easy task, and the practical application of stoichiometry requires that we use the more readily measured property of mass.


✓ Example 3.1.3: Relating Masses of Reactants and Products

What mass of sodium hydroxide, NaOH, would be required to produce 16 g of the antacid milk of magnesia [magnesium hydroxide, $Mg(OH)_2$] by the following reaction?

$$MgCl_2(aq) + 2\,NaOH(aq) \rightarrow Mg(OH)_2(s) + 2\,NaCl(aq)$$

Solution

The approach used previously in Examples **3.1.1** and **3.1.2** is likewise used here; that is, we must derive an appropriate stoichiometric factor from the balanced chemical equation and use it to relate the amounts of the two substances of interest. In this case, however, masses (not molar amounts) are provided and requested, so additional steps of the sort learned in the previous chapter are required. The calculations required are outlined in this flowchart:



$$16\ \cancel{g\ Mg(OH)_2} \times \frac{1\ \cancel{mol\ Mg(OH)_2}}{58.3\ \cancel{g\ Mg(OH)_2}} \times \frac{2\ \cancel{mol\ NaOH}}{1\ \cancel{mol\ Mg(OH)_2}} \times \frac{40.0\ g\ NaOH}{\cancel{mol\ NaOH}} = 22\ g\ NaOH$$

? Exercise 3.1.3

What mass of gallium oxide, Ga_2O_3, can be prepared from 29.0 g of gallium metal? The equation for the reaction is $4\,Ga + 3\,O_2 \rightarrow 2\,Ga_2O_3$.

Answer

39.0 g


✓ Example 3.1.4: Relating Masses of Reactants

What mass of oxygen gas, O_2, from the air is consumed in the combustion of 702 g of octane, C_8H_{18}, one of the principal components of gasoline?

$$2\,C_8H_{18} + 25\,O_2 \rightarrow 16\,CO_2 + 18\,H_2O$$

Solution

The approach required here is the same as for the Example **3.1.3**, differing only in that the provided and requested masses are both for reactant species.



$$702\ \cancel{\text{g C}_8\text{H}_{18}} \times \frac{1\ \cancel{\text{mol C}_8\text{H}_{18}}}{114.23\ \cancel{\text{g C}_8\text{H}_{18}}} \times \frac{25\ \cancel{\text{mol O}_2}}{2\ \cancel{\text{mol C}_8\text{H}_{18}}} \times \frac{32.00\ \text{g O}_2}{\cancel{\text{mol O}_2}} = 2.46 \times 10^3\ \text{g O}_2$$

? Exercise 3.1.4

What mass of CO is required to react with 25.13 g of Fe_2O_3 according to the equation $\mathbf{Fe_2O_3 + 3\,CO \rightarrow 2\,Fe + 3\,CO_2}$?

Answer

13.22 g

These examples illustrate just a few instances of reaction stoichiometry calculations. Numerous variations on the beginning and ending computational steps are possible depending upon what particular quantities are provided and sought (volumes, solution concentrations, and so forth). Regardless of the details, all these calculations share a common essential component: the use of stoichiometric factors derived from balanced chemical equations. Figure **3.1.2** provides a general outline of the various computational steps associated with many reaction stoichiometry calculations.




Figure **3.1.2**: The flowchart depicts the various computational steps involved in most reaction stoichiometry calculations.

Schematic flowchart showing how density is used for converting volume of pure substance to mass, molar mass for mass and moles, molarity for moles and volume of solution, Avogadro's number for moles and number of particles, and stoichiometric factor for relating moles of one substance to another.

Airbags

Airbags (Figure **3.1.3**) are a safety feature provided in most automobiles since the 1990s. The effective operation of an airbag requires that it be rapidly inflated with an appropriate amount (volume) of gas when the vehicle is involved in a collision. This requirement is satisfied in many automotive airbag systems through use of explosive chemical reactions, one common choice being the decomposition of sodium azide, NaN_3. When sensors in the vehicle detect a collision, an electrical current is passed through a carefully measured amount of NaN_3 to initiate its decomposition:

$$\mathbf{2\,NaN_3}(s) \rightarrow \mathbf{3\,N_2}(g) + \mathbf{2\,Na}(s)$$

This reaction is very rapid, generating gaseous nitrogen that can deploy and fully inflate a typical airbag in a fraction of a second (~0.03–0.1 s). Among many engineering considerations, the amount of sodium azide used must be appropriate for generating enough nitrogen gas to fully inflate the air bag and ensure its proper function. For example, a small mass (~100 g) of NaN_3 will generate approximately 50 L of N_2.



Figure **3.1.3**: Airbags deploy upon impact to minimize serious injuries to passengers. (credit: Jon Seidman)

Summary

A balanced chemical equation may be used to describe a reaction's stoichiometry (the relationships between amounts of reactants and products). Coefficients from the equation are used to derive stoichiometric factors that subsequently may be used for computations relating reactant and product masses, molar amounts, and other quantitative properties.

Glossary

stoichiometric factor

ratio of coefficients in a balanced chemical equation, used in computations relating amounts of reactants and products

stoichiometry

relationships between the amounts of reactants and products of a chemical reaction

---

3.1: How Much Carbon Dioxide? is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.4: Reaction Stoichiometry** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

3.2: 4.3 Limiting Reactant, Theoretical Yield, and Percent Yield

Learning Objectives

- To understand the concept of limiting reactants and quantify incomplete reactions

In all the examples discussed thus far, the reactants were assumed to be present in stoichiometric quantities. Consequently, none of the reactants was left over at the end of the reaction. This is often desirable, as in the case of a space shuttle, where excess oxygen or hydrogen was not only extra freight to be hauled into orbit but also an explosion hazard. More often, however, reactants are present in mole ratios that are not the same as the ratio of the coefficients in the balanced chemical equation. As a result, one or more of them will not be used up completely but will be left over when the reaction is completed. In this situation, the amount of product that can be obtained is limited by the amount of only one of the reactants. The reactant that restricts the amount of product obtained is called the limiting reactant. The reactant that remains after a reaction has gone to completion is in excess.

Consider a nonchemical example. Assume you have invited some friends for dinner and want to bake brownies for dessert. You find two boxes of brownie mix in your pantry and see that each package requires two eggs. The balanced equation for brownie preparation is thus

$$\text{1 box mix} + \text{2 eggs} \rightarrow \text{1 batch brownies} \tag{3.2.1}$$

If you have a dozen eggs, which ingredient will determine the number of batches of brownies that you can prepare? Because each box of brownie mix requires two eggs and you have two boxes, you need four eggs. Twelve eggs is eight more eggs than you need. Although the ratio of eggs to boxes in is 2:1, the ratio in your possession is 6:1. Hence the eggs are the ingredient (reactant) present in excess, and the brownie mix is the limiting reactant. Even if you had a refrigerator full of eggs, you could make only two batches of brownies.




Figure **3.2.1**: The Concept of a Limiting Reactant in the Preparation of Brownies

Reactants: 2 boxes of brownie mix + 12 eggs produces 2 batches of brownies + 8 eggs. Brownie mix is the limiting reactant. Eggs are the reactant present in excess.



Introduction to Limiting Reactant Problems: Introduction to Limiting Reactant Problems, YouTube(opens in new window) [youtu.be]

Now consider a chemical example of a limiting reactant: the production of pure titanium. This metal is fairly light (45% lighter than steel and only 60% heavier than aluminum) and has great mechanical strength (as strong as steel and twice as strong as aluminum). Because it is also highly resistant to corrosion and can withstand extreme temperatures, titanium has many applications in the aerospace industry. Titanium is also used in medical implants and portable computer housings because it is light and resistant to corrosion. Although titanium is the ninth most common element in Earth's crust, it is relatively difficult to extract from its ores. In the first step of the extraction process, titanium-containing oxide minerals react with solid carbon and chlorine gas to form titanium tetrachloride ($\mathbf{TiCl_4}$) and carbon dioxide.

$$\mathrm{TiO_2(s) + Cl_2(g) \rightarrow TiCl_4(g) + CO_2(g)}$$

Titanium tetrachloride is then converted to metallic titanium by reaction with molten magnesium metal at high temperature:

$$\mathrm{TiCl_4(g) + 2\ Mg(l) \rightarrow Ti(s) + 2\ MgCl_2(l)} \tag{3.2.2}$$

Because titanium ores, carbon, and chlorine are all rather inexpensive, the high price of titanium (about $100 per kilogram) is largely due to the high cost of magnesium metal. Under these circumstances, magnesium metal is the limiting reactant in the production of metallic titanium.



Figure **3.2.2**: Medical use of titanium. Here is an example of its successful use in joint replacement implants. An A-P X-ray of a pelvis showing a total hip joint replacement. The right hip joint (on the left in the photograph) has been replaced. A metal prostheses is cemented in the top of the right femur and the head of the femur has been replaced by the rounded head of the prosthesis. Figure courtesy of NIH (NIADDK) 9AO4 (Connie Raab)

With 1.00 kg of titanium tetrachloride and 200 g of magnesium metal, how much titanium metal can be produced according to Equation 3.2.2?

Solving this type of problem requires that you carry out the following steps

1. Determine the number of moles of each reactant.
2. Compare the mole ratio of the reactants with the ratio in the balanced chemical equation to determine which reactant is limiting.
3. Calculate the number of moles of product that can be obtained from the limiting reactant.
4. Convert the number of moles of product to mass of product.

Step 1: To determine the number of moles of reactants present, calculate or look up their molar masses: 189.679 g/mol for titanium tetrachloride and 24.305 g/mol for magnesium. The number of moles of each is calculated as follows:

$$\begin{aligned}\text{moles } TiCl_4 &= \frac{\text{mass } TiCl_4}{\text{molar mass } TiCl_4} \\ &= 1000 \cancel{g} \text{ } TiCl_4 \times \frac{1 \, mol \, TiCl_4}{189.679 \cancel{g} \text{ } TiCl_4} \\ &= 5.272 \, mol \text{ } TiCl_4 \end{aligned} \tag{3.2.3}$$

$$\begin{aligned}\text{moles Mg} &= \frac{\text{mass Mg}}{\text{molar mass Mg}} \\ &= 200 \cancel{g} \text{ Mg} \times \frac{1 \, mol \, \text{Mg}}{24.305 \cancel{g} \text{ Mg}} \\ &= 8.23 \, \text{mol Mg} \end{aligned} \tag{3.2.4}$$

Step 2: There are more moles of magnesium than of titanium tetrachloride, but the ratio is only the following:

$$\frac{mol \, \text{Mg}}{mol \, TiCl_4} = \frac{8.23 \, mol}{5.272 \, mol} = 1.56$$

Because the ratio of the coefficients in the balanced chemical equation is,

$$\frac{2 \, mol \, \text{Mg}}{1 \, mol \, TiCl_4} = 2$$

there is not have enough magnesium to react with all the titanium tetrachloride. If this point is not clear from the mole ratio, calculate the number of moles of one reactant that is required for complete reaction of the other reactant. For example, there are 8.23 mol of **Mg**, so (8.23 ÷ 2) = 4.12 mol of $TiCl_4$ are required for complete reaction. Because there are 5.272 mol of $TiCl_4$, titanium tetrachloride is present in excess. Conversely, 5.272 mol of $TiCl_4$ requires 2 × 5.272 = 10.54 mol of Mg, but there are only 8.23 mol. Therefore, magnesium is the limiting reactant.

Step 3: Because magnesium is the limiting reactant, the number of moles of magnesium determines the number of moles of titanium that can be formed:

$$mol \text{ Ti} = 8.23 \, mol \text{ Mg} = \frac{1 \, mol \text{ Ti}}{2 \, mol \text{ Mg}} = 4.12 \, mol \text{ Ti}$$

Thus only 4.12 mol of Ti can be formed.

Step 4. To calculate the mass of titanium metal that can obtain, multiply the number of moles of titanium by the molar mass of titanium (47.867 g/mol):

$$\begin{aligned}\text{moles Ti} &= \text{mass Ti} \times \text{molar mass Ti} \\ &= 4.12 \, mol \text{ Ti} \times \frac{47.867 \, g \text{ Ti}}{1 \, mol \text{ Ti}} \\ &= 197 \, g \text{ Ti} \end{aligned}$$

Here is a simple and reliable way to identify the limiting reactant in any problem of this sort:

1. Calculate the number of moles of each reactant present: 5.272 mol of $TiCl_4$ and 8.23 mol of Mg.
2. Divide the actual number of moles of each reactant by its stoichiometric coefficient in the balanced chemical equation:

$$TiCl_4 : \frac{5.272 \, mol \, (actual)}{1 \, mol \, (stoich)} = 5.272$$


$$Mg : \frac{8.23 \, mol \, (actual)}{2 \, mol \, (stoich)} = 4.12$$

3. The reactant with the smallest mole ratio is limiting. Magnesium, with a calculated stoichiometric mole ratio of 4.12, is the limiting reactant.

Density is the mass per unit volume of a substance. If we are given the density of a substance, we can use it in stoichiometric calculations involving liquid reactants and/or products, as Example **3.2.1** demonstrates.

Example 3.2.1: Fingernail Polish Remover

Ethyl acetate ($CH_3CO_2C_2H_5$) is the solvent in many fingernail polish removers and is used to decaffeinate coffee beans and tea leaves. It is prepared by reacting ethanol (C_2H_5OH) with acetic acid (CH_3CO_2H); the other product is water. A small amount of sulfuric acid is used to accelerate the reaction, but the sulfuric acid is not consumed and does not appear in the balanced chemical equation. Given 10.0 mL each of acetic acid and ethanol, how many grams of ethyl acetate can be prepared from this reaction? The densities of acetic acid and ethanol are 1.0492 g/mL and 0.7893 g/mL, respectively.



Ethyl acetate

Given: reactants, products, and volumes and densities of reactants

Asked for: mass of product

Strategy:

A. Balance the chemical equation for the reaction.
B. Use the given densities to convert from volume to mass. Then use each molar mass to convert from mass to moles.
C. Using mole ratios, determine which substance is the limiting reactant. After identifying the limiting reactant, use mole ratios based on the number of moles of limiting reactant to determine the number of moles of product.
D. Convert from moles of product to mass of product.

Solution:

A Always begin by writing the balanced chemical equation for the reaction:

$$C_2H_5OH\,(l) + CH_3CO_2H\,(aq) \rightarrow CH_3CO_2C_2H_5\,(aq) + H_2O\,(l)$$

B We need to calculate the number of moles of ethanol and acetic acid that are present in 10.0 mL of each. Recall that the density of a substance is the mass divided by the volume:

$$\text{density} = \frac{\text{mass}}{\text{volume}}$$

Rearranging this expression gives mass = (density)(volume). We can replace mass by the product of the density and the volume to calculate the number of moles of each substance in 10.0 mL (remember, 1 mL = 1 cm^3):

$$\begin{aligned}\text{moles } C_2H_5OH &= \frac{\text{mass } C_2H_5OH}{\text{molar mass } C_2H_5OH}\\ &= \frac{(\text{volume } C_2H_5OH) \times (\text{density } C_2H_5OH)}{\text{molar mass } C_2H_5OH}\\ &= 10.0 \cancel{ml}\ C_2H_5OH \times \frac{0.7893 \cancel{g}\ C_2H_5OH}{1 \cancel{ml}\ C_2H_5OH} \times \frac{1\,mol\ C_2H_5OH}{46.07 \cancel{g}\ C_2H_5OH}\\ &= 0.171\,mol\ C_2H_5OH\end{aligned}$$

$$\begin{aligned}\text{moles } CH_3CO_2H &= \frac{\text{mass } CH_3CO_2H}{\text{molar mass } CH_3CO_2H}\\ &= \frac{(\text{volume } CH_3CO_2H) \times (\text{density } CH_3CO_2H)}{\text{molar mass } CH_3CO_2H}\\ &= 10.0 \cancel{ml}\ CH_3CO_2H \times \frac{1.0492 \cancel{g}\ CH_3CO_2H}{1 \cancel{ml}\ CH_3CO_2H} \times \frac{1\,mol\ CH_3CO_2H}{60.05 \cancel{g}\ CH_3CO_2H}\\ &= 0.175\,mol\ CH_3CO_2H\end{aligned}$$

C The number of moles of acetic acid exceeds the number of moles of ethanol. Because the reactants both have coefficients of 1 in the balanced chemical equation, the mole ratio is 1:1. We have 0.171 mol of ethanol and 0.175 mol of acetic acid, so ethanol is the limiting reactant and acetic acid is in excess. The coefficient in the balanced chemical equation for the product (ethyl acetate) is also 1, so the mole ratio of ethanol and ethyl acetate is also 1:1. This means that given 0.171 mol of ethanol, the amount of ethyl acetate produced must also be 0.171 mol:

$$\begin{aligned}moles\ \text{ethyl acetate} &= mol\,\text{ethanol} \times \frac{1\,mol\ \text{ethyl acetate}}{1\,mol\ \text{ethanol}}\\ &= 0.171\,mol\ C_2H_5OH \times \frac{1\,mol\ CH_3CO_2C_2H_5}{1\,mol\ C_2H_5OH}\\ &= 0.171\,mol\ CH_3CO_2C_2H_5\end{aligned}$$

D The final step is to determine the mass of ethyl acetate that can be formed, which we do by multiplying the number of moles by the molar mass:

$$\begin{aligned}\text{mass of ethyl acetate} &= mol\ \text{ethyl acetate} \times \text{molar mass ethyl acetate}\\ &= 0.171\,mol\,CH_3CO_2C_2H_5 \times \frac{88.11\,g\,CH_3CO_2C_2H_5}{1\,mol\,CH_3CO_2C_2H_5}\\ &= 15.1\,g\,CH_3CO_2C_2H_5\end{aligned}$$

Thus 15.1 g of ethyl acetate can be prepared in this reaction. If necessary, you could use the density of ethyl acetate (0.9003 g/cm3) to determine the volume of ethyl acetate that could be produced:

$$\begin{aligned}\text{volume of ethyl acetate} &= 15.1\,g\,CH_3CO_2C_2H_5 \times \frac{1\,ml\ CH_3CO_2C_2H_5}{0.9003\,g\ CH_3CO_2C_2H_5}\\ &= 16.8\,ml\,CH_3CO_2C_2H_5\end{aligned}$$

? Exercise 3.2.1

Under appropriate conditions, the reaction of elemental phosphorus and elemental sulfur produces the compound P_4S_{10}. How much P_4S_{10} can be prepared starting with 10.0 g of P_4 and 30.0 g of S_8?

Answer

35.9 g



Determining the Limiting Reactant and Theoretical Yield for a Reaction: Determining the Limiting Reactant and Theoretical Yield for a Reaction, YouTube(opens in new window) [youtu.be]

Limiting Reactants in Solutions


The concept of limiting reactants applies to reactions carried out in solution as well as to reactions involving pure substances. If all the reactants but one are present in excess, then the amount of the limiting reactant may be calculated as illustrated in Example **3.2.2**.

Example 3.2.2: Breathalyzer reaction

Because the consumption of alcoholic beverages adversely affects the performance of tasks that require skill and judgment, in most countries it is illegal to drive while under the influence of alcohol. In almost all US states, a blood alcohol level of 0.08% by volume is considered legally drunk. Higher levels cause acute intoxication (0.20%), unconsciousness (about 0.30%), and even death (about 0.50%). The Breathalyzer is a portable device that measures the ethanol concentration in a person's breath, which is directly proportional to the blood alcohol level. The reaction used in the Breathalyzer is the oxidation of ethanol by the dichromate ion:

$$3\,\mathrm{CH_3\ CH_2\ OH\,(aq)} + 2\underset{yellow-orange}{\mathrm{Cr_2\ O_7^{2-}}}(aq) + 16\,\mathrm{H^+\,(aq)} \xrightarrow[\mathrm{H_2SO_4\,(aq)}]{\mathrm{Ag^+}} 3\,\mathrm{CH_3CO_2H\,(aq)} + 4\underset{green}{\mathrm{Cr^{3+}}}(aq) + 11\,\mathrm{H_2O\,(l)}$$

When a measured volume (52.5 mL) of a suspect's breath is bubbled through a solution of excess potassium dichromate in dilute sulfuric acid, the ethanol is rapidly absorbed and oxidized to acetic acid by the dichromate ions. In the process, the chromium atoms in some of the $\mathrm{Cr_2O_7^{2-}}$ ions are reduced from Cr^{6+} to Cr^{3+}. In the presence of Ag^+ ions that act as a catalyst, the reaction is complete in less than a minute. Because the $\mathrm{Cr_2O_7^{2-}}$ ion (the reactant) is yellow-orange and the Cr^{3+} ion (the product) forms a green solution, the amount of ethanol in the person's breath (the limiting reactant) can be determined quite accurately by comparing the color of the final solution with the colors of standard solutions prepared with known amounts of ethanol.



A Breathalyzer reaction with a test tube before (a) and after (b) ethanol is added. When a measured volume of a suspect's breath is bubbled through the solution, the ethanol is oxidized to acetic acid, and the solution changes color from yellow-orange to green. The intensity of the green color indicates the amount of ethanol in the sample.

A typical Breathalyzer ampul contains 3.0 mL of a 0.25 mg/mL solution of $K_2Cr_2O_7$ in 50% H_2SO_4 as well as a fixed concentration of $AgNO_3$ (typically 0.25 mg/mL is used for this purpose). How many grams of ethanol must be present in 52.5 mL of a person's breath to convert all the Cr^{6+} to Cr^{3+}?

Given: volume and concentration of one reactant

Asked for: mass of other reactant needed for complete reaction

Strategy:

A. Calculate the number of moles of $Cr_2O_7^{2-}$ ion in 1 mL of the Breathalyzer solution by dividing the mass of $K_2Cr_2O_7$ by its molar mass.

B. Find the total number of moles of $Cr_2O_7^{2-}$ ion in the Breathalyzer ampul by multiplying the number of moles contained in 1 mL by the total volume of the Breathalyzer solution (3.0 mL).

C. Use the mole ratios from the balanced chemical equation to calculate the number of moles of C_2H_5OH needed to react completely with the number of moles of $Cr_2O_7^{2-}$ ions present. Then find the mass of C_2H_5OH needed by multiplying the number of moles of C_2H_5OH by its molar mass.

Solution:

A In any stoichiometry problem, the first step is always to calculate the number of moles of each reactant present. In this case, we are given the mass of $K_2Cr_2O_7$ in 1 mL of solution, which can be used to calculate the number of moles of $K_2Cr_2O_7$ contained in 1 mL:

$$\frac{moles\ K_2Cr_2O_7}{1\ mL} = \frac{(0.25\ \cancel{mg}\ K_2Cr_2O_7)}{mL}\left(\frac{1\ \cancel{g}}{1000\ \cancel{mg}}\right)\left(\frac{1\ mol}{294.18\ \cancel{g}\ K_2Cr_2O_7}\right) = 8.5 \times 10^{-7}\ moles$$

B Because 1 mol of $K_2Cr_2O_7$ produces 1 mol of $Cr_2O_7^{2-}$ when it dissolves, each milliliter of solution contains 8.5×10^{-7} mol of $Cr_2O_7^{2-}$. The total number of moles of $Cr_2O_7^{2-}$ in a 3.0 mL Breathalyzer ampul is thus

$$moles\ Cr_2O_7^{2-} = \left(\frac{8.5 \times 10^{-7}\ mol}{1\ \cancel{mL}}\right)(3.0\ \cancel{mL}) = 2.6 \times 10^{-6}\ mol\ Cr_2O_7^{2-}$$

C The balanced chemical equation tells us that 3 mol of C_2H_5OH is needed to consume 2 mol of $Cr_2O_7^{2-}$ ion, so the total number of moles of C_2H_5OH required for complete reaction is

$$moles\ of\ C_2H_5OH = (2.6 \times 10^{-6}\ \cancel{mol\ Cr_2O_7^{2-}})\left(\frac{3\ mol\ C_2H_5OH}{2\ \cancel{mol\ Cr_2O_7^{2-}}}\right)$$
$$= 3.9 \times 10^{-6}\ mol\ C_2H_5OH$$


As indicated in the strategy, this number can be converted to the mass of C_2H_5OH using its molar mass:

$$mass\ C_2H_5OH = (3.9 \times 10^{-6}\ \cancel{mol\ C_2H_5OH}) \left(\frac{46.07\ g}{\cancel{mol\ C_2H_5OH}} \right) = 1.8 \times 10^{-4}\ g\ C_2H_5OH$$

Thus 1.8×10^{-4} g or 0.18 mg of C_2H_5OH must be present. Experimentally, it is found that this value corresponds to a blood alcohol level of 0.7%, which is usually fatal.

Exercise 3.2.2

The compound *para*-nitrophenol (molar mass = 139 g/mol) reacts with sodium hydroxide in aqueous solution to generate a yellow anion via the reaction



para-Nitrophenol **Yellow**

Chemical equation showing conversion of para-nitrophenol to its yellow-colored form with aqueous sodium hydroxide.

Because the amount of *para*-nitrophenol is easily estimated from the intensity of the yellow color that results when excess **NaOH** is added, reactions that produce *para*-nitrophenol are commonly used to measure the activity of enzymes, the catalysts in biological systems. What volume of 0.105 M NaOH must be added to 50.0 mL of a solution containing 7.20×10^{-4} g of *para*-nitrophenol to ensure that formation of the yellow anion is complete?

Answer

4.93×10^{-5} L or 49.3 µL

In Examples **3.2.1** and **3.2.2**, the identities of the limiting reactants are apparent: $[Au(CN)_2]^-$, $LaCl_3$, ethanol, and *para*-nitrophenol. When the limiting reactant is not apparent, it can be determined by comparing the molar amounts of the reactants with their coefficients in the balanced chemical equation. The only difference is that the volumes and concentrations of solutions of reactants, rather than the masses of reactants, are used to calculate the number of moles of reactants, as illustrated in Example **3.2.3**.

Example 3.2.3

When aqueous solutions of silver nitrate and potassium dichromate are mixed, an exchange reaction occurs, and silver dichromate is obtained as a red solid. The overall chemical equation for the reaction is as follows:

$$2\,AgNO_3\,(aq) + K_2Cr_2O_7\,(aq) \rightarrow Ag_2Cr_2O_7\,(s) + 2\,KNO_3\,(aq)$$

What mass of $Ag_2Cr_2O_7$ is formed when 500 mL of 0.17 M $K_2Cr_2O_7$ are mixed with 250 mL of 0.57 M $AgNO_3$?

Given: balanced chemical equation and volume and concentration of each reactant

Asked for: mass of product

Strategy:

A. Calculate the number of moles of each reactant by multiplying the volume of each solution by its molarity.

B. Determine which reactant is limiting by dividing the number of moles of each reactant by its stoichiometric coefficient in the balanced chemical equation.

C. Use mole ratios to calculate the number of moles of product that can be formed from the limiting reactant. Multiply the number of moles of the product by its molar mass to obtain the corresponding mass of product.

Solution:

A The balanced chemical equation tells us that 2 mol of $AgNO_3$(aq) reacts with 1 mol of $K_2Cr_2O_7$(aq) to form 1 mol of $Ag_2Cr_2O_7$(s) (Figure 8.3.2). The first step is to calculate the number of moles of each reactant in the specified volumes:

$$moles\ K_2Cr_2O_7 = 500\ \cancel{mL}\left(\frac{1\ \cancel{L}}{1000\ \cancel{mL}}\right)\left(\frac{0.17\ mol\ K_2Cr_2O_7}{1\ \cancel{L}}\right) = 0.085\ mol\ K_2Cr_2O_7$$

$$moles\ AgNO_3 = 250\ \cancel{mL}\left(\frac{1\ \cancel{L}}{1000\ \cancel{mL}}\right)\left(\frac{0.57\ mol\ AgNO_3}{1\ \cancel{L}}\right) = 0.14\ mol\ AgNO_3$$

B Now determine which reactant is limiting by dividing the number of moles of each reactant by its stoichiometric coefficient:

$$\mathrm{K_2Cr_2O_7}: \frac{0.085\ mol}{1\ mol} = 0.085$$

$$\mathrm{AgNO_3}: \frac{0.14\ mol}{2\ mol} = 0.070$$

Because 0.070 < 0.085, we know that $\mathbf{AgNO_3}$ is the *limiting reactant*.

C Each mole of $\mathbf{Ag_2Cr_2O_7}$ formed requires 2 mol of the limiting reactant ($\mathbf{AgNO_3}$), so we can obtain only 0.14/2 = 0.070 mol of $\mathbf{Ag_2Cr_2O_7}$. Finally, convert the number of moles of $\mathbf{Ag_2Cr_2O_7}$ to the corresponding mass:

$$mass\ of\ Ag_2Cr_2O_7 = 0.070\ \cancel{mol}\left(\frac{431.72\ g}{1\ \cancel{mol}}\right) = 30\ g\ Ag_2Cr_2O_7$$

The Ag^+ and $Cr_2O_7^{2-}$ ions form a red precipitate of solid $\mathbf{Ag_2Cr_2O_7}$, while the $\mathbf{K^+}$ and $\mathbf{NO_3^-}$ ions remain in solution. (Water molecules are omitted from molecular views of the solutions for clarity.)

? Exercise 3.2.3

Aqueous solutions of sodium bicarbonate and sulfuric acid react to produce carbon dioxide according to the following equation:

$$\mathrm{2\,NaHCO_3\,(aq) + H_2SO_4\,(aq) \rightarrow 2\,CO_2\,(g) + Na_2SO_4\,(aq) + 2\,H_2O\,(l)}$$

If 13.0 mL of 3.0 M H_2SO_4 are added to 732 mL of 0.112 M $NaHCO_3$, what mass of CO_2 is produced?

Answer

3.4 g



Limiting Reactant Problems Using Molarities: Limiting Reactant Problems Using Molarities, YouTube(opens in new window) [youtu.be]eOXTliL-gNw (opens in new window)

Theoretical Yields

When reactants are not present in stoichiometric quantities, the limiting reactant determines the maximum amount of product that can be formed from the reactants. The amount of product calculated in this way is the theoretical yield, the amount obtained if the

reaction occurred perfectly and the purification method were 100% efficient.

In reality, less product is always obtained than is theoretically possible because of mechanical losses (such as spilling), separation procedures that are not 100% efficient, competing reactions that form undesired products, and reactions that simply do not run to completion, resulting in a mixture of products and reactants; this last possibility is a common occurrence. Therefore, the actual yield, the measured mass of products obtained from a reaction, is almost always less than the theoretical yield (often much less). The percent yield of a reaction is the ratio of the actual yield to the theoretical yield, multiplied by 100 to give a percentage:

$$\text{percent yield} = \frac{\text{actual yield } (g)}{\text{theoretical yield } (g)} \times 100\% \tag{3.2.5}$$


The method used to calculate the percent yield of a reaction is illustrated in Example **3.2.4**.

Example 3.2.4: Novocain

Procaine is a key component of Novocain, an injectable local anesthetic used in dental work and minor surgery. Procaine can be prepared in the presence of H2SO4 (indicated above the arrow) by the reaction

$$\underset{\text{p-amino benzoic acid}}{C_7H_7NO_2} + \underset{\text{2-diethylaminoethanol}}{C_6H_{15}NO} \xrightarrow{H_2SO_4} \underset{\text{procaine}}{C_{13}H_{20}N_2O_2} + H_2O$$

If this reaction were carried out with 10.0 g of p-aminobenzoic acid and 10.0 g of 2-diethylaminoethanol, and 15.7 g of procaine were isolated, what is the percent yield?



The preparation of procaine. A reaction of p-aminobenzoic acid with 2-diethylaminoethanol yields procaine and water.

Given: masses of reactants and product

Asked for: percent yield

Strategy:

A. Write the balanced chemical equation.
B. Convert from mass of reactants and product to moles using molar masses and then use mole ratios to determine which is the limiting reactant. Based on the number of moles of the limiting reactant, use mole ratios to determine the theoretical yield.
C. Calculate the percent yield by dividing the actual yield by the theoretical yield and multiplying by 100.

Solution:

A From the formulas given for the reactants and the products, we see that the chemical equation is balanced as written. According to the equation, 1 mol of each reactant combines to give 1 mol of product plus 1 mol of water.

B To determine which reactant is limiting, we need to know their molar masses, which are calculated from their structural formulas: p-aminobenzoic acid ($C_7H_7NO_2$), 137.14 g/mol; 2-diethylaminoethanol ($C_6H_{15}NO$), 117.19 g/mol. Thus the reaction used the following numbers of moles of reactants:

$$mol \text{ p-aminobenzoic acid} = 10.0\,g \times \frac{1\,mol}{137.14\,g} = 0.0729\,mol \text{ p-aminbenzoic acid}$$

$$mol \text{ 2-diethylaminoethanol} = 10.0\,g \times \frac{1\,mol}{117.19\,g} = 0.0853\,mol \text{ 2-diethylaminoethanol}$$

The reaction requires a 1:1 mole ratio of the two reactants, so p-aminobenzoic acid is the limiting reactant. Based on the coefficients in the balanced chemical equation, 1 mol of p-aminobenzoic acid yields 1 mol of procaine. We can therefore obtain

only a maximum of 0.0729 mol of procaine. To calculate the corresponding mass of procaine, we use its structural formula ($C_{13}H_{20}N_2O_2$) to calculate its molar mass, which is 236.31 g/mol.

$$\text{theoretical yield of procaine} = 0.0729\,mol \times \frac{236.31\,g}{1\,mol} = 17.2\,g$$

C The actual yield was only 15.7 g of procaine, so the percent yield (via Equation 3.2.5) is

$$\text{percent yield} = \frac{15.7\,g}{17.2\,g} \times 100 = 91.3\%$$

(If the product were pure and dry, this yield would indicate very good lab technique!)

? Exercise 3.2.4: Extraction of Lead

Lead was one of the earliest metals to be isolated in pure form. It occurs as concentrated deposits of a distinctive ore called galena (**PbS**), which is easily converted to lead oxide (**PbO**) in 100% yield by roasting in air via the following reaction:

$$2\,PbS\,(s) + 3\,O_2 \rightarrow 2\,PbO\,(s) + 2\,SO_2\,(g)$$

The resulting **PbO** is then converted to the pure metal by reaction with charcoal. Because lead has such a low melting point (327°C), it runs out of the ore-charcoal mixture as a liquid that is easily collected. The reaction for the conversion of lead oxide to pure lead is as follows:

$$PbO\,(s) + C\,(s) \rightarrow Pb\,(l) + CO\,(g)$$

If 93.3 kg of **PbO** is heated with excess charcoal and 77.3 kg of pure lead is obtained, what is the percent yield?



Electrolytically refined pure (99.989 %) superficially oxidized lead nodules and a high purity (99.989 %) $1\ cm^3$ lead cube for comparison. Figure used with permission from Wikipedia.

Answer

89.2%

Percent yield can range from 0% to 100%. In the laboratory, a student will occasionally obtain a yield that appears to be greater than 100%. This usually happens when the product is impure or is wet with a solvent such as water. If this is not the case, then the student must have made an error in weighing either the reactants or the products. The law of conservation of mass applies even to undergraduate chemistry laboratory experiments. A 100% yield means that everything worked perfectly, and the chemist obtained all the product that could have been produced. Anyone who has tried to do something as simple as fill a salt shaker or add oil to a car's engine without spilling knows the unlikelihood of a 100% yield. At the other extreme, a yield of 0% means that no product was obtained. A percent yield of 80%–90% is usually considered good to excellent; a yield of 50% is only fair. In part because of the problems and costs of waste disposal, industrial production facilities face considerable pressures to optimize the yields of products and make them as close to 100% as possible.

Summary

The stoichiometry of a balanced chemical equation identifies the maximum amount of product that can be obtained. The stoichiometry of a reaction describes the relative amounts of reactants and products in a balanced chemical equation. A stoichiometric quantity of a reactant is the amount necessary to react completely with the other reactant(s). If a quantity of a

reactant remains unconsumed after complete reaction has occurred, it is in excess. The reactant that is consumed first and limits the amount of product(s) that can be obtained is the limiting reactant. To identify the limiting reactant, calculate the number of moles of each reactant present and compare this ratio to the mole ratio of the reactants in the balanced chemical equation. The maximum amount of product(s) that can be obtained in a reaction from a given amount of reactant(s) is the theoretical yield of the reaction. The actual yield is the amount of product(s) actually obtained in the reaction; it cannot exceed the theoretical yield. The percent yield of a reaction is the ratio of the actual yield to the theoretical yield, expressed as a percentage.

3.2: 4.3 Limiting Reactant, Theoretical Yield, and Percent Yield is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.7: Limiting Reactants** is licensed CC BY-NC-SA 3.0.

3.3: Solution Concentration and Solution Stoichiomentry

Learning Objectives

- To describe the concentrations of solutions quantitatively

Many people have a qualitative idea of what is meant by *concentration*. Anyone who has made instant coffee or lemonade knows that too much powder gives a strongly flavored, highly concentrated drink, whereas too little results in a dilute solution that may be hard to distinguish from water. In chemistry, the concentration of a solution is the quantity of a **solute** that is contained in a particular quantity of **solvent** or solution. Knowing the concentration of solutes is important in controlling the stoichiometry of reactants for solution reactions. Chemists use many different methods to define concentrations, some of which are described in this section.

Molarity

The most common unit of concentration is *molarity*, which is also the most useful for calculations involving the stoichiometry of reactions in solution. The molarity (M) is defined as the number of moles of solute present in exactly 1 L of solution. It is, equivalently, the number of millimoles of solute present in exactly 1 mL of solution:

$$molarity = \frac{moles\ of\ solute}{liters\ of\ solution} = \frac{mmoles\ of\ solute}{milliliters\ of\ solution} \tag{3.3.1}$$

The units of molarity are therefore moles per liter of solution (mol/L), abbreviated as M. An aqueous solution that contains 1 mol (342 g) of sucrose in enough water to give a final volume of 1.00 L has a sucrose concentration of 1.00 mol/L or 1.00 M. In chemical notation, square brackets around the name or formula of the solute represent the molar concentration of a solute. Therefore,

$$[\text{sucrose}] = 1.00\ \text{M}$$

is read as “the concentration of sucrose is 1.00 molar.” The relationships between volume, molarity, and moles may be expressed as either

$$V_L M_{mol/L} = \cancel{L}\left(\frac{mol}{\cancel{L}}\right) = moles \tag{3.3.2}$$

or

$$V_{mL} M_{mmol/mL} = \cancel{mL}\left(\frac{mmol}{\cancel{mL}}\right) = mmoles \tag{3.3.3}$$

Figure 3.3.1 illustrates the use of Equations 3.3.2 and 3.3.3.




Figure 3.3.1: Preparation of a Solution of Known Concentration Using a Solid Solute

Example 3.3.1: Calculating Moles from Concentration of NaOH

Calculate the number of moles of sodium hydroxide (NaOH) in 2.50 L of 0.100 M NaOH.

Given: identity of solute and volume and molarity of solution

Asked for: amount of solute in moles

Strategy:

Use either Equation 3.3.2 or Equation 3.3.3, depending on the units given in the problem.

Solution:

Because we are given the volume of the solution in liters and are asked for the number of moles of substance, Equation 3.3.2 is more useful:

$$moles\ NaOH = V_L M_{mol/L} = (2.50\ \cancel{L}) \left(\frac{0.100\ mol}{\cancel{L}} \right) = 0.250\ mol\ NaOH$$

Exercise 3.3.1: Calculating Moles from Concentration of Alanine

Calculate the number of millimoles of alanine, a biologically important molecule, in 27.2 mL of 1.53 M alanine.

Answer

41.6 mmol



Calculations Involving Molarity (M): Calculations Involving Molarity (M), YouTube(opens in new window) [youtu.be]

Concentrations are also often reported on a mass-to-mass (m/m) basis or on a mass-to-volume (m/v) basis, particularly in clinical laboratories and engineering applications. A concentration expressed on an m/m basis is equal to the number of grams of solute per gram of solution; a concentration on an m/v basis is the number of grams of solute per milliliter of solution. Each measurement can be expressed as a percentage by multiplying the ratio by 100; the result is reported as percent m/m or percent m/v. The concentrations of very dilute solutions are often expressed in *parts per million* (*ppm*), which is grams of solute per 10^6 g of solution, or in *parts per billion* (*ppb*), which is grams of solute per 10^9 g of solution. For aqueous solutions at 20°C, 1 ppm corresponds to 1 µg per milliliter, and 1 ppb corresponds to 1 ng per milliliter. These concentrations and their units are summarized in Table **3.3.1**.

Table **3.3.1**: Common Units of Concentration

Concentration	Units
m/m	g of solute/g of solution
m/v	g of solute/mL of solution
ppm	g of solute/10^6 g of solution
	µg/mL
ppb	g of solute/10^9 g of solution
	ng/mL

The Preparation of Solutions

To prepare a solution that contains a specified concentration of a substance, it is necessary to dissolve the desired number of moles of solute in enough solvent to give the desired final volume of solution. Figure **3.3.1** illustrates this procedure for a solution of cobalt(II) chloride dihydrate in ethanol. Note that the volume of the *solvent* is not specified. Because the solute occupies space in the solution, the volume of the solvent needed is almost always *less* than the desired volume of solution. For example, if the desired volume were 1.00 L, it would be incorrect to add 1.00 L of water to 342 g of sucrose because that would produce more than 1.00 L of solution. As shown in Figure **3.3.2**, for some substances this effect can be significant, especially for concentrated solutions.




Figure **3.3.2**: Preparation of 250 mL of a Solution of $(NH_4)_2Cr_2O_7$ in Water. The solute occupies space in the solution, so less than 250 mL of water are needed to make 250 mL of solution.

45 milliliters of water remain in the graduated cylinder even after addition to the mark of the volumetric flask.

✔ Example 3.3.2

The solution contains 10.0 g of cobalt(II) chloride dihydrate, $CoCl_2$•$2H_2O$, in enough ethanol to make exactly 500 mL of solution. What is the molar concentration of $\mathbf{CoCl_2 \cdot 2\,H_2O}$?

Given: mass of solute and volume of solution

Asked for: concentration (M)

Strategy:

To find the number of moles of $\mathbf{CoCl_2 \cdot 2\,H_2O}$, divide the mass of the compound by its molar mass. Calculate the molarity of the solution by dividing the number of moles of solute by the volume of the solution in liters.

Solution:

The molar mass of $CoCl_2$•$2H_2O$ is 165.87 g/mol. Therefore,

$$moles\ CoCl_2 \cdot 2H_2O = \left(\frac{10.0\ \cancel{g}}{165.87\ \cancel{g}/mol}\right) = 0.0603\ mol$$

The volume of the solution in liters is

$$volume = 500\ \cancel{mL}\left(\frac{1\ L}{1000\ \cancel{mL}}\right) = 0.500\ L$$

Molarity is the number of moles of solute per liter of solution, so the molarity of the solution is

$$molarity = \frac{0.0603\ mol}{0.500\ L} = 0.121\ M = CoCl_2 \cdot H_2O$$

Exercise 3.3.2

The solution shown in Figure **3.3.2** contains 90.0 g of $(NH_4)_2Cr_2O_7$ in enough water to give a final volume of exactly 250 mL. What is the molar concentration of ammonium dichromate?

Answer

$$(NH_4)_2Cr_2O_7 = 1.43\ M$$

To prepare a particular volume of a solution that contains a specified concentration of a solute, we first need to calculate the number of moles of solute in the desired volume of solution using the relationship shown in Equation 3.3.2. We then convert the number of moles of solute to the corresponding mass of solute needed. This procedure is illustrated in Example **3.3.3**.

Example 3.3.3: D5W Solution

The so-called D5W solution used for the intravenous replacement of body fluids contains 0.310 M glucose. (D5W is an approximately 5% solution of dextrose [the medical name for glucose] in water.) Calculate the mass of glucose necessary to prepare a 500 mL pouch of D5W. Glucose has a molar mass of 180.16 g/mol.

Given: molarity, volume, and molar mass of solute

Asked for: mass of solute

Strategy:

A. Calculate the number of moles of glucose contained in the specified volume of solution by multiplying the volume of the solution by its molarity.

B. Obtain the mass of glucose needed by multiplying the number of moles of the compound by its molar mass.

Solution:

A We must first calculate the number of moles of glucose contained in 500 mL of a 0.310 M solution:

$$V_L M_{mol/L} = moles$$

$$500\ \cancel{mL}\left(\frac{1\ \cancel{L}}{1000\ \cancel{mL}}\right)\left(\frac{0.310\ mol\ glucose}{1\ \cancel{L}}\right) = 0.155\ mol\ glucose$$

B We then convert the number of moles of glucose to the required mass of glucose:

$$mass\ of\ glucose = 0.155\ \cancel{mol\ glucose}\left(\frac{180.16\ g\ glucose}{1\ \cancel{mol\ glucose}}\right) = 27.9\ g\ glucose$$

Exercise 3.3.3

Another solution commonly used for intravenous injections is normal saline, a 0.16 M solution of sodium chloride in water. Calculate the mass of sodium chloride needed to prepare 250 mL of normal saline solution.

Answer

2.3 g NaCl

A solution of a desired concentration can also be prepared by diluting a small volume of a more concentrated solution with additional solvent. A stock solution is a commercially prepared solution of known concentration and is often used for this purpose. Diluting a stock solution is preferred because the alternative method, weighing out tiny amounts of solute, is difficult to carry out with a high degree of accuracy. Dilution is also used to prepare solutions from substances that are sold as concentrated aqueous solutions, such as strong acids.

The procedure for preparing a solution of known concentration from a stock solution is shown in Figure **3.3.3**. It requires calculating the number of moles of solute desired in the final volume of the more dilute solution and then calculating the volume of the stock solution that contains this amount of solute. Remember that diluting a given quantity of stock solution with solvent does *not* change the number of moles of solute present. The relationship between the volume and concentration of the stock solution and the volume and concentration of the desired diluted solution is therefore

$$(V_s)(M_s) = moles\ of\ solute = (V_d)(M_d) \tag{3.3.4}$$

where the subscripts *s* and *d* indicate the stock and dilute solutions, respectively. Example **3.3.4** demonstrates the calculations involved in diluting a concentrated stock solution.



Figure **3.3.3**: Preparation of a Solution of Known Concentration by Diluting a Stock Solution. (a) A volume (V_s) containing the desired moles of solute (M_s) is measured from a stock solution of known concentration. (b) The measured volume of stock solution is transferred to a second volumetric flask. (c) The measured volume in the second flask is then diluted with solvent up to the volumetric mark [$(V_s)(M_s) = (V_d)(M_d)$].

Example 3.3.4

What volume of a 3.00 M glucose stock solution is necessary to prepare 2500 mL of the D5W solution in Example **3.3.3**?

Given: volume and molarity of dilute solution

Asked for: volume of stock solution

Strategy:

A. Calculate the number of moles of glucose contained in the indicated volume of dilute solution by multiplying the volume of the solution by its molarity.

B. To determine the volume of stock solution needed, divide the number of moles of glucose by the molarity of the stock solution.

Solution:

A The D5W solution in Example 4.5.3 was 0.310 M glucose. We begin by using Equation 4.5.4 to calculate the number of moles of glucose contained in 2500 mL of the solution:

$$\text{moles glucose} = 2500 \cancel{\text{mL}} \left(\frac{1 \cancel{\text{L}}}{1000 \cancel{\text{mL}}} \right) \left(\frac{0.310 \text{ mol glucose}}{1 \cancel{\text{L}}} \right) = 0.775 \text{ mol glucose}$$

B We must now determine the volume of the 3.00 M stock solution that contains this amount of glucose:

$$\text{volume of stock soln} = 0.775 \cancel{\text{ mol glucose}} \left(\frac{1 \text{ L}}{3.00 \cancel{\text{ mol glucose}}} \right) = 0.258 \text{ L or } 258 \text{ mL}$$

In determining the volume of stock solution that was needed, we had to divide the desired number of moles of glucose by the concentration of the stock solution to obtain the appropriate units. Also, the number of moles of solute in 258 mL of the stock solution is the same as the number of moles in 2500 mL of the more dilute solution; *only the amount of solvent has changed*. The answer we obtained makes sense: diluting the stock solution about tenfold increases its volume by about a factor of 10 (258 mL → 2500 mL). Consequently, the concentration of the solute must decrease by about a factor of 10, as it does (3.00 M → 0.310 M).

We could also have solved this problem in a single step by solving Equation 4.5.4 for V_s and substituting the appropriate values:

$$V_s = \frac{(V_d)(M_d)}{M_s} = \frac{(2.500 \text{ L})(0.310 \cancel{M})}{3.00 \cancel{M}} = 0.258 \text{ L}$$

As we have noted, there is often more than one correct way to solve a problem.

? Exercise 3.3.4

What volume of a 5.0 M NaCl stock solution is necessary to prepare 500 mL of normal saline solution (0.16 M NaCl)?

Answer

16 mL

Ion Concentrations in Solution

In Example **3.3.2**, the concentration of a solution containing 90.00 g of ammonium dichromate in a final volume of 250 mL were calculated to be 1.43 M. Let's consider in more detail exactly what that means. Ammonium dichromate is an ionic compound that contains two NH_4^+ ions and one $Cr_2O_7^{2-}$ ion per formula unit. Like other ionic compounds, it is a strong electrolyte that dissociates in aqueous solution to give hydrated NH_4^+ and $Cr_2O_7^{2-}$ ions:

$$(NH_4)_2Cr_2O_7(s) \xrightarrow{H_2O(l)} 2NH_4^+(aq) + Cr_2O_7^{2-}(aq) \tag{3.3.5}$$

Thus 1 mol of ammonium dichromate formula units dissolves in water to produce 1 mol of $Cr_2O_7^{2-}$ anions and 2 mol of NH_4^+ cations (see Figure **3.3.4**).




Figure **3.3.4**: Dissolution of 1 mol of an Ionic Compound. In this case, dissolving 1 mol of $(NH_4)_2Cr_2O_7$ produces a solution that contains 1 mol of $Cr_2O_7^{2-}$ ions and 2 mol of NH_4^+ ions. (Water molecules are omitted from a molecular view of the solution for clarity.)

1 mol of ammonium dichromate is shown in a 1 liter volumetric flask. The resulting volumetric flask on the right contains 1 liter of solution after being dissolved with water. Powdered form of ammonium dichromate is also included in diagram.

When carrying out a chemical reaction using a solution of a salt such as ammonium dichromate, it is important to know the concentration of each ion present in the solution. If a solution contains 1.43 M $(NH_4)_2Cr_2O_7$, then the concentration of $Cr_2O_7^{2-}$ must also be 1.43 M because there is one $Cr_2O_7^{2-}$ ion per formula unit. However, there are two NH_4^+ ions per formula unit, so the concentration of NH_4^+ ions is 2 × 1.43 M = 2.86 M. Because each formula unit of $(NH_4)_2Cr_2O_7$ produces *three* ions when dissolved in water ($2NH_4^+ + 1Cr_2O_7^{2-}$), the *total* concentration of ions in the solution is 3 × 1.43 M = 4.29 M.



Concentration of Ions in Solution from a Soluble Salt: Concentration of Ions in Solution from a Soluble Salt, YouTube(opens in new window) [youtu.be]

Example 3.3.5

What are the concentrations of all species derived from the solutes in these aqueous solutions?

a. 0.21 M NaOH
b. 3.7 M $(CH_3)_2CHOH$
c. 0.032 M $In(NO_3)_3$

Given: molarity

Asked for: concentrations

Strategy:

A Classify each compound as either a strong electrolyte or a nonelectrolyte.

B If the compound is a nonelectrolyte, its concentration is the same as the molarity of the solution. If the compound is a strong electrolyte, determine the number of each ion contained in one formula unit. Find the concentration of each species by

multiplying the number of each ion by the molarity of the solution.

Solution:

1. Sodium hydroxide is an ionic compound that is a strong electrolyte (and a strong base) in aqueous solution:

   $$NaOH(s) \xrightarrow{H_2O(l)} Na^+(aq) + OH^-(aq)$$

   B Because each formula unit of NaOH produces one Na^+ ion and one OH^- ion, the concentration of each ion is the same as the concentration of NaOH: $[Na^+] = 0.21$ M and $[OH^-] = 0.21$ M.

2. **A** The formula $(CH_3)_2CHOH$ represents 2-propanol (isopropyl alcohol) and contains the –OH group, so it is an alcohol. Recall from Section 4.1 that alcohols are covalent compounds that dissolve in water to give solutions of neutral molecules. Thus alcohols are nonelectrolytes.

   B The only solute species in solution is therefore $(CH_3)_2CHOH$ molecules, so $[(CH_3)_2CHOH] = 3.7$ M.

3. **A** Indium nitrate is an ionic compound that contains In^{3+} ions and NO_3^- ions, so we expect it to behave like a strong electrolyte in aqueous solution:


   $$In(NO_3)_3(s) \xrightarrow{H_2O(l)} In^{3+}(aq) + 3NO_3^-(aq)$$

   B One formula unit of $In(NO_3)_3$ produces one In^{3+} ion and three NO_3^- ions, so a 0.032 M $In(NO_3)_3$ solution contains 0.032 M In^{3+} and 3 × 0.032 M = 0.096 M NO_3^-—that is, $[In^{3+}] = 0.032$ M and $[NO_3^-] = 0.096$ M.

? Exercise 3.3.5

What are the concentrations of all species derived from the solutes in these aqueous solutions?

a. 0.0012 M $Ba(OH)_2$
b. 0.17 M Na_2SO_4
c. 0.50 M $(CH_3)_2CO$, commonly known as acetone



Acetone
$(CH_3)_2CO$

Answer a

$[Ba^{2+}] = 0.0012\ M;\ [OH^-] = 0.0024\ M$

Answer b

$[Na^+] = 0.34\ M;\ [SO_4^{2-}] = 0.17\ M$

Answer c

$[(CH_3)_2CO] = 0.50\ M$

Summary

Solution concentrations are typically expressed as molarities and can be prepared by dissolving a known mass of solute in a solvent or diluting a stock solution.

- **definition of molarity:**

$$molarity = \frac{moles\ of\ solute}{liters\ of\ solution} = \frac{mmoles\ of\ solute}{milliliters\ of\ solution}$$

- **relationship among volume, molarity, and moles**:

$$V_L M_{mol/L} = \cancel{L}\left(\frac{mol}{\cancel{L}}\right) = moles$$

- **relationship between volume and concentration of stock and dilute solutions**:

$$(V_s)(M_s) = moles\ of\ solute = (V_d)(M_d)$$

The **concentration** of a substance is the quantity of solute present in a given quantity of solution. Concentrations are usually expressed in terms of **molarity**, defined as the number of moles of solute in 1 L of solution. Solutions of known concentration can be prepared either by dissolving a known mass of solute in a solvent and diluting to a desired final volume or by diluting the appropriate volume of a more concentrated solution (a **stock solution**) to the desired final volume.

Contributors and Attributions

- Modified by Joshua Halpern (Howard University)

3.3: Solution Concentration and Solution Stoichiomentry is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.5: Concentration of Solutions** is licensed CC BY-NC-SA 3.0.

CHAPTER OVERVIEW

4: Quantum Numbers

Template:HideTOC

4.1: Quantum Mechanics and The Atom

4: Quantum Numbers is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

4.1: Quantum Mechanics and The Atom

Learning Objectives

- To apply the results of quantum mechanics to chemistry.

The paradox described by Heisenberg's uncertainty principle and the wavelike nature of subatomic particles such as the electron made it impossible to use the equations of classical physics to describe the motion of electrons in atoms. Scientists needed a new approach that took the wave behavior of the electron into account. In 1926, an Austrian physicist, Erwin Schrödinger (1887–1961; Nobel Prize in Physics, 1933), developed *wave mechanics*, a mathematical technique that describes the relationship between the motion of a particle that exhibits wavelike properties (such as an electron) and its allowed energies.

Erwin Schrödinger (1887–1961)

Schrödinger's unconventional approach to atomic theory was typical of his unconventional approach to life. He was notorious for his intense dislike of memorizing data and learning from books. When Hitler came to power in Germany, Schrödinger escaped to Italy. He then worked at Princeton University in the United States but eventually moved to the Institute for Advanced Studies in Dublin, Ireland, where he remained until his retirement in 1955.

Although quantum mechanics uses sophisticated mathematics, you do not need to understand the mathematical details to follow our discussion of its general conclusions. We focus on the properties of the *wavefunctions* that are the solutions of Schrödinger's equations.

Wavefunctions

A wavefunction (Ψ) is a mathematical function that relates the location of an electron at a given point in space (identified by x, y, and z coordinates) to the amplitude of its wave, which corresponds to its energy. Thus each wavefunction is associated with a particular energy E. The properties of wavefunctions derived from quantum mechanics are summarized here:

- **A wavefunction uses three variables to describe the position of an electron.** A fourth variable is usually required to fully describe the location of objects in motion. Three specify the position in space (as with the Cartesian coordinates x, y, and z), and one specifies the time at which the object is at the specified location. For example, if you were the captain of a ship trying to intercept an enemy submarine, you would need to know its latitude, longitude, and depth, as well as the time at which it was going to be at this position (Figure **4.1.1**). For electrons, we can ignore the time dependence because we will be using standing waves, which by definition do not change with time, to describe the position of an electron.




Figure **4.1.1**: The Four Variables (Latitude, Longitude, Depth, and Time) required to precisely locate an object

- **The magnitude of the wavefunction at a particular point in space is proportional to the amplitude of the wave at that point.** Many wavefunctions are complex functions, which is a mathematical term indicating that they contain $\sqrt{-1}$, represented

as i. Hence the amplitude of the wave has no real physical significance. In contrast, the sign of the wavefunction (either positive or negative) corresponds to the phase of the wave, which will be important in our discussion of chemical bonding. The sign of the wavefunction should *not* be confused with a positive or negative electrical charge.

- **The square of the wavefunction at a given point is proportional to the probability of finding an electron at that point, which leads to a distribution of probabilities in space.** The square of the wavefunction (Ψ^2) is always a real quantity [recall that that $\sqrt{-1}^2 = -1$] and is proportional to the probability of finding an electron at a given point. More accurately, the probability is given by the product of the wavefunction Ψ and its complex conjugate Ψ*, in which all terms that contain *i* are replaced by $-i$. We use probabilities because, according to Heisenberg's uncertainty principle, we cannot precisely specify the position of an electron. The probability of finding an electron at any point in space depends on several factors, including the distance from the nucleus and, in many cases, the atomic equivalent of latitude and longitude. As one way of graphically representing the probability distribution, the probability of finding an electron is indicated by the density of colored dots, as shown for the ground state of the hydrogen atom in Figure **4.1.2**.
- **Describing the electron distribution as a standing wave leads to sets of *quantum numbers* that are characteristic of each wavefunction.** From the patterns of one- and two-dimensional standing waves shown previously, you might expect (correctly) that the patterns of three-dimensional standing waves would be complex. Fortunately, however, in the 18th century, a French mathematician, Adrien Legendre (1752–1783), developed a set of equations to describe the motion of tidal waves on the surface of a flooded planet. Schrödinger incorporated Legendre's equations into his wavefunctions. The requirement that the waves must be in phase with one another to avoid cancellation and produce a standing wave results in a limited number of solutions (wavefunctions), each of which is specified by a set of numbers called quantum numbers.
- **Each wavefunction is associated with a particular energy.** As in Bohr's model, the energy of an electron in an atom is quantized; it can have only certain allowed values. The major difference between Bohr's model and Schrödinger's approach is that Bohr had to impose the idea of quantization arbitrarily, whereas in Schrödinger's approach, quantization is a natural consequence of describing an electron as a standing wave.




Figure **4.1.2**: Probability of Finding the Electron in the Ground State of the Hydrogen Atom at Different Points in Space. (a) The density of the dots shows electron probability. (b) In this plot of Ψ^2 versus *r* for the ground state of the hydrogen atom, the electron probability density is greatest at $r = 0$ (the nucleus) and falls off with increasing *r*. Because the line never actually reaches the horizontal axis, the probability of finding the electron at very large values of *r* is very small but *not* zero.

Quantum Numbers

Schrödinger's approach uses three quantum numbers (*n*, *l*, and m_l) to specify any wavefunction. The quantum numbers provide information about the spatial distribution of an electron. Although *n* can be any positive integer, only certain values of *l* and m_l are allowed for a given value of *n*.

The Principal Quantum Number

The **principal quantum number** (n) tells the average relative distance of an electron from the nucleus:

$$n = 1, 2, 3, 4, \ldots \tag{4.1.1}$$

As *n* increases for a given atom, so does the average distance of an electron from the nucleus. A negatively charged electron that is, on average, closer to the positively charged nucleus is attracted to the nucleus more strongly than an electron that is farther out in space. This means that electrons with higher values of *n* are easier to remove from an atom. All wavefunctions that have the same value of *n* are said to constitute a principal shell because those electrons have similar average distances from the nucleus. As you will see, the principal quantum number *n* corresponds to the *n* used by Bohr to describe electron orbits and by Rydberg to describe atomic energy levels.

The Azimuthal Quantum Number

The second quantum number is often called the **azimuthal quantum number (l)**. The value of *l* describes the *shape* of the region of space occupied by the electron. The allowed values of *l* depend on the value of *n* and can range from 0 to $n - 1$:

$$l = 0, 1, 2, \ldots, n - 1 \tag{4.1.2}$$

For example, if $n = 1$, *l* can be only 0; if $n = 2$, *l* can be 0 or 1; and so forth. For a given atom, all wavefunctions that have the same values of both *n* and *l* form a subshell. The regions of space occupied by electrons in the same subshell usually have the same shape, but they are oriented differently in space.



Principal quantum number (n) & Orbital angular momentum (l): The Orbital Subshell:

Principal quantum number (n) & Orbital angular momentum (l): The Orbital Subshell, YouTube(opens in new window) [youtu.be]

The Magnetic Quantum Number

The third quantum number is the magnetic quantum number (m_l). The value of m_l describes the *orientation* of the region in space occupied by an electron with respect to an applied magnetic field. The allowed values of m_l depend on the value of *l*: m_l can range from $-l$ to *l* in integral steps:

$$m_l = -l, -l + 1, \ldots, 0, \ldots, l - 1, l \tag{4.1.3}$$

For example, if $l = 0$, m_l can be only 0; if $l = 1$, m_l can be −1, 0, or +1; and if $l = 2$, m_l can be −2, −1, 0, +1, or +2.

Each wavefunction with an allowed combination of *n*, *l*, and m_l values describes an atomic **orbital**, a particular spatial distribution for an electron. For a given set of quantum numbers, each principal shell has a fixed number of subshells, and each subshell has a fixed number of orbitals.

Example 4.1.1: n=4 Shell Structure

How many subshells and orbitals are contained within the principal shell with $n = 4$?

Given: value of n

Asked for: number of subshells and orbitals in the principal shell

Strategy:

A. Given $n = 4$, calculate the allowed values of l. From these allowed values, count the number of subshells.

B. For each allowed value of l, calculate the allowed values of m_l. The sum of the number of orbitals in each subshell is the number of orbitals in the principal shell.

Solution:

A We know that l can have all integral values from 0 to $n − 1$. If $n = 4$, then l can equal 0, 1, 2, or 3. Because the shell has four values of l, it has four subshells, each of which will contain a different number of orbitals, depending on the allowed values of m_l.

B For $l = 0$, m_l can be only 0, and thus the $l = 0$ subshell has only one orbital. For $l = 1$, m_l can be 0 or ±1; thus the $l = 1$ subshell has three orbitals. For $l = 2$, m_l can be 0, ±1, or ±2, so there are five orbitals in the $l = 2$ subshell. The last allowed value of l is $l = 3$, for which m_l can be 0, ±1, ±2, or ±3, resulting in seven orbitals in the $l = 3$ subshell. The total number of orbitals in the $n = 4$ principal shell is the sum of the number of orbitals in each subshell and is equal to $n^2 = 16$

Exercise 4.1.1: n=3 Shell Structure

How many subshells and orbitals are in the principal shell with $n = 3$?

Answer

three subshells; nine orbitals

Rather than specifying all the values of n and l every time we refer to a subshell or an orbital, chemists use an abbreviated system with lowercase letters to denote the value of l for a particular subshell or orbital:

abbreviated system with lowercase letters to denote the value of l for a particular subshell or orbital

l =	0	1	2	3
Designation	*s*	*p*	*d*	*f*

The principal quantum number is named first, followed by the letter *s*, *p*, *d*, or *f* as appropriate. (These orbital designations are derived from historical terms for corresponding spectroscopic characteristics: sharp, *p*rinciple, *d*iffuse, and *f*undamental.) A 1*s* orbital has $n = 1$ and $l = 0$; a 2*p* subshell has $n = 2$ and $l = 1$ (and has three 2*p* orbitals, corresponding to $m_l = −1$, 0, and +1); a 3*d* subshell has $n = 3$ and $l = 2$ (and has five 3*d* orbitals, corresponding to $m_l = −2$, −1, 0, +1, and +2); and so forth.

We can summarize the relationships between the quantum numbers and the number of subshells and orbitals as follows (Table 6.5.1):

- Each principal shell has n subshells. For $n = 1$, only a single subshell is possible (1*s*); for $n = 2$, there are two subshells (2*s* and 2*p*); for $n = 3$, there are three subshells (3*s*, 3*p*, and 3*d*); and so forth. Every shell has an *ns* subshell, any shell with $n \geq 2$ also has an *np* subshell, and any shell with $n \geq 3$ also has an *nd* subshell. Because a 2*d* subshell would require both $n = 2$ and $l = 2$, which is not an allowed value of l for $n = 2$, a 2*d* subshell does not exist.
- Each subshell has $2l + 1$ orbitals. This means that all *ns* subshells contain a single *s* orbital, all *np* subshells contain three *p* orbitals, all *nd* subshells contain five *d* orbitals, and all *nf* subshells contain seven *f* orbitals.

> *Each principal shell has n subshells, and each subshell has 2l + 1 orbitals.*

Table 4.1.1: Values of n, l, and ml through n = 4

n	l	Subshell Designation	m_l	Number of Orbitals in Subshell	Number of Orbitals in Shell
1	0	1*s*	0	1	1
2	0	2*s*	0	1	4
	1	2*p*	−1, 0, 1	3	
3	0	3*s*	0	1	9
	1	3*p*	−1, 0, 1	3	
	2	3*d*	−2, −1, 0, 1, 2	5	
4	0	4*s*	0	1	16
	1	4*p*	−1, 0, 1	3	
	2	4*d*	−2, −1, 0, 1, 2	5	
	3	4*f*	−3, −2, −1, 0, 1, 2, 3	7	



Magnetic Quantum Number (ml) & Spin Quantum Number (ms): Magnetic Quantum Number (ml) & Spin Quantum Number (ms) YouTube(opens in new window) [youtu.be] (opens in new window)

Summary

There is a relationship between the motions of electrons in atoms and molecules and their energies that is described by quantum mechanics. Because of wave–particle duality, scientists must deal with the probability of an electron being at a particular point in space. To do so required the development of **quantum mechanics**, which uses **wavefunctions (Ψ)** to describe the mathematical relationship between the motion of electrons in atoms and molecules and their energies. Wavefunctions have five important properties:

1. the wavefunction uses three variables (Cartesian axes *x*, *y*, and *z*) to describe the position of an electron;
2. the magnitude of the wavefunction is proportional to the intensity of the wave;
3. the probability of finding an electron at a given point is proportional to the square of the wavefunction at that point, leading to a distribution of probabilities in space that is often portrayed as an **electron density** plot;
4. describing electron distributions as standing waves leads naturally to the existence of sets of **quantum numbers** characteristic of each wavefunction; and
5. each spatial distribution of the electron described by a wavefunction with a given set of quantum numbers has a particular energy.

Quantum numbers provide important information about the energy and spatial distribution of an electron. The **principal quantum number** n can be any positive integer; as n increases for an atom, the average distance of the electron from the nucleus also increases. All wavefunctions with the same value of n constitute a **principal shell** in which the electrons have similar average distances from the nucleus. The **azimuthal quantum number** l can have integral values between 0 and $n - 1$; it describes the shape of the electron distribution. Wavefunctions that have the same values of both n and l constitute a **subshell**, corresponding to electron distributions that usually differ in orientation rather than in shape or average distance from the nucleus. The **magnetic quantum number** m_l can have $2l + 1$ integral values, ranging from $-l$ to $+l$, and describes the orientation of the electron distribution. Each wavefunction with a given set of values of n, l, and m_l describes a particular spatial distribution of an electron in an atom, an **atomic orbital**.

4.1: Quantum Mechanics and The Atom is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **6.5: Quantum Mechanics and Atomic Orbitals** is licensed CC BY-NC-SA 3.0.

CHAPTER OVERVIEW

5: Electron Configurations

Template:HideTOC

5.1: Electron Configurations- How Electrons Occupy Orbitals

5.2: Electron Configurations, Valence Electrons, and the Periodic Table

---

5: Electron Configurations is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

5.1: Electron Configurations- How Electrons Occupy Orbitals

Learning Objectives

- Derive the predicted ground-state electron configurations of atoms
- Identify and explain exceptions to predicted electron configurations for atoms and ions
- Relate electron configurations to element classifications in the periodic table

Having introduced the basics of atomic structure and quantum mechanics, we can use our understanding of quantum numbers to determine how atomic orbitals relate to one another. This allows us to determine which orbitals are occupied by electrons in each atom. The specific arrangement of electrons in orbitals of an atom determines many of the chemical properties of that atom.

Orbital Energies and Atomic Structure

The energy of atomic orbitals increases as the principal quantum number, n, increases. In any atom with two or more electrons, the repulsion between the electrons makes energies of subshells with different values of l differ so that the energy of the orbitals increases within a shell in the order $s < p < d < f$. Figure 5.1.1 depicts how these two trends in increasing energy relate. The 1*s* orbital at the bottom of the diagram is the orbital with electrons of lowest energy. The energy increases as we move up to the 2*s* and then 2*p*, 3*s*, and 3*p* orbitals, showing that the increasing *n* value has more influence on energy than the increasing *l* value for small atoms. However, this pattern does not hold for larger atoms. The 3*d* orbital is higher in energy than the 4*s* orbital. Such overlaps continue to occur frequently as we move up the chart.




Figure 5.1.1: Generalized energy-level diagram for atomic orbitals in an atom with two or more electrons (not to scale).

Electrons in successive atoms on the periodic table tend to fill low-energy orbitals first. Thus, many students find it confusing that, for example, the 5*p* orbitals fill immediately after the 4*d*, and immediately before the 6*s*. The filling order is based on observed experimental results, and has been confirmed by theoretical calculations. As the principal quantum number, *n*, increases, the size of the orbital increases and the electrons spend more time farther from the nucleus. Thus, the attraction to the nucleus is weaker and the energy associated with the orbital is higher (less stabilized). But this is not the only effect we have to take into account. Within each shell, as the value of *l* increases, the electrons are less penetrating (meaning there is less electron density found close to the nucleus), in the order $s > p > d > f$. Electrons that are closer to the nucleus slightly repel electrons that are farther out, offsetting the more dominant electron–nucleus attractions slightly (recall that all electrons have −1 charges, but nuclei have +*Z* charges). This phenomenon is called shielding and will be discussed in more detail in the next section. Electrons in orbitals that experience more shielding are less stabilized and thus higher in energy. For small orbitals (1*s* through 3*p*), the increase in energy due to *n* is more significant than the increase due to *l*; however, for larger orbitals the two trends are comparable and cannot be simply predicted. We will discuss methods for remembering the observed order.

The arrangement of electrons in the orbitals of an atom is called the electron configuration of the atom. We describe an electron configuration with a symbol that contains three pieces of information (Figure 5.1.2):

1. The number of the principal quantum shell, n,
2. The letter that designates the orbital type (the subshell, l), and
3. A superscript number that designates the number of electrons in that particular subshell.

For example, the notation $2p^4$ (read "two–p–four") indicates four electrons in a p subshell (l = 1) with a principal quantum number (n) of 2. The notation $3d^8$ (read "three–d–eight") indicates eight electrons in the d subshell (i.e., l = 2) of the principal shell for which n = 3.




Figure **5.1.2**: The diagram of an electron configuration specifies the subshell (n and l value, with letter symbol) and superscript number of electrons.

The Aufbau Principle

To determine the electron configuration for any particular atom, we can “build” the structures in the order of atomic numbers. Beginning with hydrogen, and continuing across the periods of the periodic table, we add one proton at a time to the nucleus and one electron to the proper subshell until we have described the electron configurations of all the elements. This procedure is called the Aufbau principle, from the German word *Aufbau* (“to build up”). Each added electron occupies the subshell of lowest energy available (in the order shown in Figure **5.1.3**), subject to the limitations imposed by the allowed quantum numbers according to the Pauli exclusion principle. Electrons enter higher-energy subshells only after lower-energy subshells have been filled to capacity. Figure **5.1.3** illustrates the traditional way to remember the filling order for atomic orbitals.




Figure **5.1.3**: The arrow leads through each subshell in the appropriate filling order for electron configurations. This chart is straightforward to construct. Simply make a column for all the s orbitals with each n shell on a separate row. Repeat for p, d, and f. Be sure to only include orbitals allowed by the quantum numbers (no 1p or 2d, and so forth). Finally, draw diagonal lines from top to bottom as shown.

Since the arrangement of the periodic table is based on the electron configurations, Figure **5.1.4** provides an alternative method for determining the electron configuration. The filling order simply begins at hydrogen and includes each subshell as you proceed in increasing Z order. For example, after filling the 3p block up to Ar, we see the orbital will be 4s (K, Ca), followed by the 3d orbitals.






Figure 5.1.4: This periodic table shows the electron configuration for each subshell. By "building up" from hydrogen, this table can be used to determine the electron configuration for any atom on the periodic table.

We will now construct the ground-state electron configuration and orbital diagram for a selection of atoms in the first and second periods of the periodic table. Orbital diagrams are pictorial representations of the electron configuration, showing the individual orbitals and the pairing arrangement of electrons. We start with a single hydrogen atom (atomic number 1), which consists of one proton and one electron. Referring to either Figure 5.1.3 or 5.1.4, we would expect to find the electron in the 1*s* orbital. By convention, the $m_s = +\frac{1}{2}$ value is usually filled first. The electron configuration and the orbital diagram are:




Following hydrogen is the noble gas helium, which has an atomic number of 2. The helium atom contains two protons and two electrons. The first electron has the same four quantum numbers as the hydrogen atom electron (n = 1, l = 0, m_l = 0, $m_s = +\frac{1}{2}$). The second electron also goes into the 1*s* orbital and fills that orbital. The second electron has the same n, l, and m_l quantum numbers, but must have the opposite spin quantum number, $m_s = -\frac{1}{2}$. This is in accord with the Pauli exclusion principle: No two electrons in the same atom can have the same set of four quantum numbers. For orbital diagrams, this means two arrows go in each box (representing two electrons in each orbital) and the arrows must point in opposite directions (representing paired spins). The electron configuration and orbital diagram of helium are:




The n = 1 shell is completely filled in a helium atom.


The next atom is the alkali metal lithium with an atomic number of 3. The first two electrons in lithium fill the 1*s* orbital and have the same sets of four quantum numbers as the two electrons in helium. The remaining electron must occupy the orbital of next lowest energy, the 2*s* orbital (Figure **5.1.3** or **5.1.4**). Thus, the electron configuration and orbital diagram of lithium are:




An atom of the alkaline earth metal beryllium, with an atomic number of 4, contains four protons in the nucleus and four electrons surrounding the nucleus. The fourth electron fills the remaining space in the 2*s* orbital.



An atom of boron (atomic number 5) contains five electrons. The $n = 1$ shell is filled with two electrons and three electrons will occupy the $n = 2$ shell. Because any *s* subshell can contain only two electrons, the fifth electron must occupy the next energy level, which will be a 2*p* orbital. There are three degenerate 2*p* orbitals ($m_l = -1, 0, +1$) and the electron can occupy any one of these *p* orbitals. When drawing orbital diagrams, we include empty boxes to depict any empty orbitals in the same subshell that we are filling.



Carbon (atomic number 6) has six electrons. Four of them fill the 1*s* and 2*s* orbitals. The remaining two electrons occupy the 2*p* subshell. We now have a choice of filling one of the 2*p* orbitals and pairing the electrons or of leaving the electrons unpaired in two different, but degenerate, *p* orbitals. The orbitals are filled as described by Hund's rule: the lowest-energy configuration for an atom with electrons within a set of degenerate orbitals is that having the maximum number of unpaired electrons. Thus, the two electrons in the carbon 2*p* orbitals have identical *n*, *l*, and m_s quantum numbers and differ in their m_l quantum number (in accord with the Pauli exclusion principle). The electron configuration and orbital diagram for carbon are:



Nitrogen (atomic number 7) fills the 1*s* and 2*s* subshells and has one electron in each of the three 2*p* orbitals, in accordance with Hund's rule. These three electrons have unpaired spins. Oxygen (atomic number 8) has a pair of electrons in any one of the 2*p* orbitals (the electrons have opposite spins) and a single electron in each of the other two. Fluorine (atomic number 9) has only one 2*p* orbital containing an unpaired electron. All of the electrons in the noble gas neon (atomic number 10) are paired, and all of the orbitals in the $n = 1$ and the $n = 2$ shells are filled. The electron configurations and orbital diagrams of these four elements are:




Figure 5.1.5: Since the core electron shells correspond to noble gas electron configurations, we can abbreviate electron configurations by writing the noble gas that matches the core electron configuration, along with the valence electrons in a condensed format. For our sodium example, the symbol [Ne] represents core electrons, ($1s^2 2s^2 2p^6$) and our abbreviated or condensed configuration is [Ne]$3s^1$.

The alkali metal sodium (atomic number 11) has one more electron than the neon atom. This electron must go into the lowest-energy subshell available, the 3*s* orbital, giving a $1s^2 2s^2 2p^6 3s^1$ configuration. The electrons occupying the outermost shell orbital(s) (highest value of *n*) are called valence electrons, and those occupying the inner shell orbitals are called core electrons (Figure \PageIndex5\PageIndex5). Since the core electron shells correspond to noble gas electron configurations, we can abbreviate electron configurations by writing the noble gas that matches the core electron configuration, along with the valence electrons in a condensed format. For our sodium example, the symbol [Ne] represents core electrons, ($1s^2 2s^2 2p^6$) and our abbreviated or condensed configuration is [Ne]$3s^1$.




Figure 5.1.5: A core-abbreviated electron configuration (right) replaces the core electrons with the noble gas symbol whose configuration matches the core electron configuration of the other element.

Similarly, the abbreviated configuration of lithium can be represented as [He]$2s^1$, where [He] represents the configuration of the helium atom, which is identical to that of the filled inner shell of lithium. Writing the configurations in this way emphasizes the similarity of the configurations of lithium and sodium. Both atoms, which are in the alkali metal family, have only one electron in a valence *s* subshell outside a filled set of inner shells.

$$\textbf{Li : [He]}\ 2s^1$$
$$\textbf{Na : [Ne]}\ 3s^1$$

The alkaline earth metal magnesium (atomic number 12), with its 12 electrons in a [Ne]$3s^2$ configuration, is analogous to its family member beryllium, [He]$2s^2$. Both atoms have a filled *s* subshell outside their filled inner shells. Aluminum (atomic number 13), with 13 electrons and the electron configuration [Ne]$3s^2 3p^1$, is analogous to its family member boron, [He]$2s^2 2p^1$.

The electron configurations of silicon (14 electrons), phosphorus (15 electrons), sulfur (16 electrons), chlorine (17 electrons), and argon (18 electrons) are analogous in the electron configurations of their outer shells to their corresponding family members carbon, nitrogen, oxygen, fluorine, and neon, respectively, except that the principal quantum number of the outer shell of the heavier elements has increased by one to $n = 3$. Figure **5.1.6** shows the lowest energy, or ground-state, electron configuration for these elements as well as that for atoms of each of the known elements.




Figure **5.1.6**: This version of the periodic table shows the outer-shell electron configuration of each element. Note that down each group, the configuration is often similar.

When we come to the next element in the periodic table, the alkali metal potassium (atomic number 19), we might expect that we would begin to add electrons to the 3*d* subshell. However, all available chemical and physical evidence indicates that potassium is like lithium and sodium, and that the next electron is not added to the 3*d* level but is, instead, added to the 4*s* level (Figure **5.1.3** or **5.1.4**). As discussed previously, the 3*d* orbital with no radial nodes is higher in energy because it is less penetrating and more shielded from the nucleus than the 4*s*, which has three radial nodes. Thus, potassium has an electron configuration of $[Ar]4s^1$. Hence, potassium corresponds to Li and Na in its valence shell configuration. The next electron is added to complete the 4*s* subshell and calcium has an electron configuration of $[Ar]4s^2$. This gives calcium an outer-shell electron configuration corresponding to that of beryllium and magnesium.

Beginning with the transition metal scandium (atomic number 21), additional electrons are added successively to the 3*d* subshell. This subshell is filled to its capacity with 10 electrons (remember that for $l = 2$ [*d* orbitals], there are $2l + 1 = 5$ values of m_l, meaning that there are five *d* orbitals that have a combined capacity of 10 electrons). The 4*p* subshell fills next. Note that for three series of elements, scandium (Sc) through copper (Cu), yttrium (Y) through silver (Ag), and lutetium (Lu) through gold (Au), a total of 10 *d* electrons are successively added to the $(n - 1)$ shell next to the *n* shell to bring that $(n - 1)$ shell from 8 to 18 electrons. For two series, lanthanum (La) through lutetium (Lu) and actinium (Ac) through lawrencium (Lr), 14 *f* electrons ($l = 3$, $2l + 1 = 7$ m_l values; thus, seven orbitals with a combined capacity of 14 electrons) are successively added to the $(n - 2)$ shell to bring that shell from 18 electrons to a total of 32 electrons.


Example 5.1.1: Quantum Numbers and Electron Configurations

What is the electron configuration and orbital diagram for a phosphorus atom? What are the four quantum numbers for the last electron added?

Solution

The atomic number of phosphorus is 15. Thus, a phosphorus atom contains 15 electrons. The order of filling of the energy levels is 1*s*, 2*s*, 2*p*, 3*s*, 3*p*, 4*s*, . . . The 15 electrons of the phosphorus atom will fill up to the 3*p* orbital, which will contain three electrons:

P $1s^2 2s^2 2p^6 3s^2 3p^3$



The last electron added is a 3*p* electron. Therefore, $n = 3$ and, for a *p*-type orbital, $l = 1$. The m_l value could be –1, 0, or +1. The three *p* orbitals are degenerate, so any of these m_l values is correct. For unpaired electrons, convention assigns the value of $+\frac{1}{2}$ for the spin quantum number; thus, $m_s = +\frac{1}{2}$.

Exercise 5.1.1

Identify the atoms from the electron configurations given:

a. $[Ar]4s^2 3d^5$
b. $[Kr]5s^2 4d^{10} 5p^6$

Answer a

Mn

Answer b

Xe

The periodic table can be a powerful tool in predicting the electron configuration of an element. However, we do find exceptions to the order of filling of orbitals that are shown in Figure **5.1.3** or **5.1.4**. For instance, the electron configurations of the transition metals chromium (Cr; atomic number 24) and copper (Cu; atomic number 29), among others, are not those we would expect. In general, such exceptions involve subshells with very similar energy, and small effects can lead to changes in the order of filling.

In the case of Cr and Cu, we find that half-filled and completely filled subshells apparently represent conditions of preferred stability. This stability is such that an electron shifts from the 4*s* into the 3*d* orbital to gain the extra stability of a half-filled 3*d* subshell (in Cr) or a filled 3*d* subshell (in Cu). Other exceptions also occur. For example, niobium (Nb, atomic number 41) is predicted to have the electron configuration $[Kr]5s^2 4d^3$. Experimentally, we observe that its ground-state electron configuration is actually $[Kr]5s^1 4d^4$. We can rationalize this observation by saying that the electron–electron repulsions experienced by pairing the electrons in the 5*s* orbital are larger than the gap in energy between the 5*s* and 4*d* orbitals. There is no simple method to predict the exceptions for atoms where the magnitude of the repulsions between electrons is greater than the small differences in energy between subshells.

Electron Configurations and the Periodic Table

As described earlier, the periodic table arranges atoms based on increasing atomic number so that elements with the same chemical properties recur periodically. When their electron configurations are added to the table (Figure **5.1.6**), we also see a periodic recurrence of similar electron configurations in the outer shells of these elements. Because they are in the outer shells of an atom, valence electrons play the most important role in chemical reactions. The outer electrons have the highest energy of the electrons in

an atom and are more easily lost or shared than the core electrons. Valence electrons are also the determining factor in some physical properties of the elements.

Elements in any one group (or column) have the same number of valence electrons; the alkali metals lithium and sodium each have only one valence electron, the alkaline earth metals beryllium and magnesium each have two, and the halogens fluorine and chlorine each have seven valence electrons. The similarity in chemical properties among elements of the same group occurs because they have the same number of valence electrons. It is the loss, gain, or sharing of valence electrons that defines how elements react.

It is important to remember that the periodic table was developed on the basis of the chemical behavior of the elements, well before any idea of their atomic structure was available. Now we can understand why the periodic table has the arrangement it has—the arrangement puts elements whose atoms have the same number of valence electrons in the same group. This arrangement is emphasized in Figure **5.1.6**, which shows in periodic-table form the electron configuration of the last subshell to be filled by the Aufbau principle. The colored sections of Figure **5.1.6** show the three categories of elements classified by the orbitals being filled: main group, transition, and inner transition elements. These classifications determine which orbitals are counted in the valence shell, or highest energy level orbitals of an atom.

1. **Main group elements** (sometimes called **representative elements**) are those in which the last electron added enters an *s* or a *p* orbital in the outermost shell, shown in blue and red in Figure **5.1.6**. This category includes all the nonmetallic elements, as well as many metals and the intermediate semimetallic elements. The valence electrons for main group elements are those with the highest *n* level. For example, gallium (Ga, atomic number 31) has the electron configuration [Ar]$\underline{4s^2}3d^{10}\underline{4p^1}$, which contains three valence electrons (underlined). The completely filled *d* orbitals count as core, not valence, electrons.
2. **Transition elements or transition metals**. These are metallic elements in which the last electron added enters a *d* orbital. The valence electrons (those added after the last noble gas configuration) in these elements include the *ns* and $(n - 1)$ *d* electrons. The official IUPAC definition of transition elements specifies those with partially filled *d* orbitals. Thus, the elements with completely filled orbitals (Zn, Cd, Hg, as well as Cu, Ag, and Au in Figure **5.1.6**) are not technically transition elements. However, the term is frequently used to refer to the entire *d* block (colored yellow in Figure **5.1.6**), and we will adopt this usage in this textbook.
3. **Inner transition elements** are metallic elements in which the last electron added occupies an *f* orbital. They are shown in green in Figure **5.1.6**. The valence shells of the inner transition elements consist of the $(n - 2)f$, the $(n - 1)d$, and the *ns* subshells. There are two inner transition series:
    1. The lanthanide series: lanthanide (La) through lutetium (Lu)
    2. The actinide series: actinide (Ac) through lawrencium (Lr)

Lanthanum and actinium, because of their similarities to the other members of the series, are included and used to name the series, even though they are transition metals with no *f* electrons.

Electron Configurations of Ions

We have seen that ions are formed when atoms gain or lose electrons. A cation (positively charged ion) forms when one or more electrons are removed from a parent atom. For main group elements, the electrons that were added last are the first electrons removed. For transition metals and inner transition metals, however, electrons in the *s* orbital are easier to remove than the *d* or *f* electrons, and so the highest *ns* electrons are lost, and then the $(n - 1)d$ or $(n - 2)f$ electrons are removed. An anion (negatively charged ion) forms when one or more electrons are added to a parent atom. The added electrons fill in the order predicted by the Aufbau principle.

✔ Example **5.1.2**: Predicting Electron Configurations of Ions

What is the electron configuration and orbital diagram of:

a. Na^+
b. P^{3-}
c. Al^{2+}
d. Fe^{2+}

e. Sm^{3+}

Solution

First, write out the electron configuration for each parent atom. We have chosen to show the full, unabbreviated configurations to provide more practice for students who want it, but listing the core-abbreviated electron configurations is also acceptable.

Next, determine whether an electron is gained or lost. Remember electrons are negatively charged, so ions with a positive charge have *lost* an electron. For main group elements, the last orbital gains or loses the electron. For transition metals, the last *s* orbital loses an electron before the *d* orbitals.

a. Na: $1s^2 2s^2 2p^6 3s^1$. Sodium cation loses one electron, so Na^+: $1s^2 2s^2 2p^6 3s^1 = Na^+$: $1s^2 2s^2 2p^6$.
b. P: $1s^2 2s^2 2p^6 3s^2 3p^3$. Phosphorus trianion gains three electrons, so P^{3-}: $1s^2 2s^2 2p^6 3s^2 3p^6$.
c. Al: $1s^2 2s^2 2p^6 3s^2 3p^1$. Aluminum dication loses two electrons Al^{2+}: $1s^2 2s^2 2p^6 3s^2 3p^1 = Al^{2+}$: $1s^2 2s^2 2p^6 3s^1$.
d. Fe: $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^6$. Iron(II) loses two electrons and, since it is a transition metal, they are removed from the 4*s* orbital Fe^{2+}: $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^6 = 1s^2 2s^2 2p^6 3s^2 3p^6 3d^6$.
e. Sm: $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10} 4p^6 5s^2 4d^{10} 5p^6 6s^2 4f^6$. Samarium trication loses three electrons. The first two will be lost from the 6*s* orbital, and the final one is removed from the 4*f* orbital. Sm^{3+}: $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10} 4p^6 5s^2 4d^{10} 5p^6 6s^2 4f^6 = 1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10} 4p^6 5s^2 4d^{10} 5p^6 4f^5$.

? Exercise 5.1.2

a. Which ion with a +2 charge has the electron configuration $1s^2 2s^2 2p^6 3s^2 3p^6 3d^{10} 4s^2 4p^6 4d^5$?
b. Which ion with a +3 charge has this configuration?

Answer a

Tc^{2+}

Answer b

Ru^{3+}

Summary

The relative energy of the subshells determine the order in which atomic orbitals are filled (1*s*, 2*s*, 2*p*, 3*s*, 3*p*, 4*s*, 3*d*, 4*p*, and so on). Electron configurations and orbital diagrams can be determined by applying the Pauli exclusion principle (no two electrons can have the same set of four quantum numbers) and Hund's rule (whenever possible, electrons retain unpaired spins in degenerate orbitals).

Electrons in the outermost orbitals, called valence electrons, are responsible for most of the chemical behavior of elements. In the periodic table, elements with analogous valence electron configurations usually occur within the same group. There are some exceptions to the predicted filling order, particularly when half-filled or completely filled orbitals can be formed. The periodic table can be divided into three categories based on the orbital in which the last electron to be added is placed: main group elements (*s* and *p* orbitals), transition elements (*d* orbitals), and inner transition elements (*f* orbitals).

Glossary

Aufbau principle
procedure in which the electron configuration of the elements is determined by "building" them in order of atomic numbers, adding one proton to the nucleus and one electron to the proper subshell at a time

core electron
electron in an atom that occupies the orbitals of the inner shells

electron configuration

electronic structure of an atom in its ground state given as a listing of the orbitals occupied by the electrons

Hund's rule

every orbital in a subshell is singly occupied with one electron before any one orbital is doubly occupied, and all electrons in singly occupied orbitals have the same spin

orbital diagram

pictorial representation of the electron configuration showing each orbital as a box and each electron as an arrow

valence electrons

electrons in the outermost or valence shell (highest value of *n*) of a ground-state atom; determine how an element reacts

valence shell

outermost shell of electrons in a ground-state atom; for main group elements, the orbitals with the highest *n* level (*s* and *p* subshells) are in the valence shell, while for transition metals, the highest energy *s* and *d* subshells make up the valence shell and for inner transition elements, the highest *s*, *d*, and *f* subshells are included

---

5.1: Electron Configurations- How Electrons Occupy Orbitals is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **6.4: Electronic Structure of Atoms (Electron Configurations)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

5.2: Electron Configurations, Valence Electrons, and the Periodic Table

Learning Objectives


- Describe and explain the observed trends in atomic size, ionization energy, and electron affinity of the elements

The elements in groups (vertical columns) of the periodic table exhibit similar chemical behavior. This similarity occurs because the members of a group have the same number and distribution of electrons in their valence shells. However, there are also other patterns in chemical properties on the periodic table. For example, as we move down a group, the metallic character of the atoms increases. Oxygen, at the top of Group 16 (6A), is a colorless gas; in the middle of the group, selenium is a semiconducting solid; and, toward the bottom, polonium is a silver-grey solid that conducts electricity.


As we go across a period from left to right, we add a proton to the nucleus and an electron to the valence shell with each successive element. As we go down the elements in a group, the number of electrons in the valence shell remains constant, but the principal quantum number increases by one each time. An understanding of the electronic structure of the elements allows us to examine some of the properties that govern their chemical behavior. These properties vary periodically as the electronic structure of the elements changes. They are (1) size (radius) of atoms and ions, (2) ionization energies, and (3) electron affinities.

Variation in Covalent Radius

The quantum mechanical picture makes it difficult to establish a definite size of an atom. However, there are several practical ways to define the radius of atoms and, thus, to determine their relative sizes that give roughly similar values. We will use the covalent radius (Figure **5.2.1**), which is defined as one-half the distance between the nuclei of two identical atoms when they are joined by a covalent bond (this measurement is possible because atoms within molecules still retain much of their atomic identity).



(a)



(b)

Figure **5.2.1**: (a) The radius of an atom is defined as one-half the distance between the nuclei in a molecule consisting of two identical atoms joined by a covalent bond. The atomic radius for the halogens increases down the group as n increases. (b) Covalent radii of the elements are shown to scale. The general trend is that radii increase down a group and decrease across a period.

This figure has two parts: a and b. In figure a, 4 diatomic molecules are shown to illustrate the method of determining the atomic radius of an atom. The first model, in light green, is used to find the F atom radius. Two spheres are pushed very tightly together. The distance between the centers of the two atoms is indicated above the diagram with a double headed arrow labeled, “128 p m.” The endpoints of this arrow connect to line segments that extend to the atomic radii below. Beneath the molecule is the label, “F radius equals 128 p m divided by 2 equals 64 p m.” The next three models are similarly used to show the atomic radii of additional atoms. The second diatomic molecule is in a darker shade of green. The distance between the radii is 198 p m. Beneath the molecule is the label, “C l radius equals 198 p m divided by 2 equals 99 pm.” The third diatomic molecule is in red. The distance between the radii is 228 p m. Beneath the molecule is the label, “B r radius equals 228 p m divided by 2 equals 114 pm.” The fourth diatomic molecule is in purple. The distance between the radii is 266 p m. Beneath the molecule is the label, “I radius equals 266 p m divided by 2 equals 133 p m.” In figure b, a periodic table layout is used to compare relative sizes of atoms using green spheres. No spheres are provided for the noble or inert gas, group 18 elements. General trends noted are increasing circle size moving from top to bottom in a group, with a general tendency toward increasing atomic radii toward the lower left corner of the periodic table.

We know that as we scan down a group, the principal quantum number, *n*, increases by one for each element. Thus, the electrons are being added to a region of space that is increasingly distant from the nucleus. Consequently, the size of the atom (and its covalent radius) must increase as we increase the distance of the outermost electrons from the nucleus. This trend is illustrated for the covalent radii of the halogens in Table **5.2.1** and Figure **5.2.1**. The trends for the entire periodic table can be seen in Figure **5.2.2**.

Table **5.2.1**: Covalent Radii of the Halogen Group Elements

Atom	Covalent radius (pm)	Nuclear charge
F	64	+9
Cl	99	+17
Br	114	+35
I	133	+53
At	148	+85

As shown in Figure **5.2.2**, as we move across a period from left to right, we generally find that each element has a smaller covalent radius than the element preceding it. This might seem counterintuitive because it implies that atoms with more electrons have a smaller atomic radius. This can be explained with the concept of effective nuclear charge, Z_{eff}. This is the pull exerted on a specific electron by the nucleus, taking into account any electron–electron repulsions. For hydrogen, there is only one electron and so the nuclear charge (Z) and the effective nuclear charge (Z_{eff}) are equal. For all other atoms, the inner electrons partially *shield* the outer electrons from the pull of the nucleus, and thus:

$$Z_{\text{eff}} = Z - shielding$$

Shielding is determined by the probability of another electron being between the electron of interest and the nucleus, as well as by the electron–electron repulsions the electron of interest encounters. Core electrons are adept at shielding, while electrons in the same valence shell do not block the nuclear attraction experienced by each other as efficiently. Thus, each time we move from one element to the next across a period, Z increases by one, but the shielding increases only slightly. Thus, Z_{eff} increases as we move from left to right across a period. The stronger pull (higher effective nuclear charge) experienced by electrons on the right side of the periodic table draws them closer to the nucleus, making the covalent radii smaller.




Figure **5.2.2**: Within each period, the trend in atomic radius decreases as Z increases; for example, from K to Kr. Within each group (e.g., the alkali metals shown in purple), the trend is that atomic radius increases as Z increases.

This graph is labeled Atomic Number on the horizontal axis and Radius (p m) on the vertical axis. A black jagged line connects the radii values for elements with atomic numbers 1 through 60 on the graph. Peaks are evident at the locations of the alkali metals: L i, N a, K, R b, and C s. Similarly, minima exist at the locations of noble or inert gases: H e, N e, A r, K r, X e, and R n. The locations of period 4 and period 5 transition elements are provided with green dots.

Thus, as we would expect, the outermost or valence electrons are easiest to remove because they have the highest energies, are shielded more, and are farthest from the nucleus. As a general rule, when the representative elements form cations, they do so by the loss of the *ns* or *np* electrons that were added last in the Aufbau process. The transition elements, on the other hand, lose the *ns* electrons before they begin to lose the $(n - 1)d$ electrons, even though the *ns* electrons are added first, according to the Aufbau principle.

✔ Example **5.2.1**: Sorting Atomic Radii

Predict the order of increasing covalent radius for Ge, Fl, Br, Kr.

Solution

Radius increases as we move down a group, so Ge < Fl (Note: Fl is the symbol for flerovium, element 114, NOT fluorine). Radius decreases as we move across a period, so Kr < Br < Ge. Putting the trends together, we obtain Kr < Br < Ge < Fl.

? Exercise 5.2.1

Give an example of an atom whose size is smaller than fluorine.

Answer

Ne or He

Variation in Ionic Radii

Ionic radius is the measure used to describe the size of an ion. A cation always has fewer electrons and the same number of protons as the parent atom; it is smaller than the atom from which it is derived (Figure **5.2.3**). For example, the covalent radius of an aluminum atom ($1s^2 2s^2 2p^6 3s^2 3p^1$) is 118 pm, whereas the ionic radius of an Al^{3+} ($1s^2 2s^2 2p^6$) is 68 pm. As electrons are removed from the outer valence shell, the remaining core electrons occupying smaller shells experience a greater effective nuclear charge Z_{eff} (as discussed) and are drawn even closer to the nucleus.



Figure **5.2.3**: The radius for a cation is smaller than the parent atom (Al), due to the lost electrons; the radius for an anion is larger than the parent (S), due to the gained electrons.

The figure includes spheres in green to represent the relative sizes of A l and S atoms. Beneath each of these spheres is a red sphere. The red sphere represents the ionic states of aluminum and sulfur respectively. While radius for the aluminum cation is smaller than aluminum, the sulfur anion has a greater radius than sulfur.

Cations with larger charges are smaller than cations with smaller charges (e.g., V^{2+} has an ionic radius of 79 pm, while that of V^{3+} is 64 pm). Proceeding down the groups of the periodic table, we find that cations of successive elements with the same charge generally have larger radii, corresponding to an increase in the principal quantum number, *n*.

An anion (negative ion) is formed by the addition of one or more electrons to the valence shell of an atom. This results in a greater repulsion among the electrons and a decrease in Z_{eff} per electron. Both effects (the increased number of electrons and the decreased Z_{eff}) cause the radius of an anion to be larger than that of the parent atom (Figure **5.2.3**). For example, a sulfur atom ($[Ne]3s^2 3p^4$) has a covalent radius of 104 pm, whereas the ionic radius of the sulfide anion ($[Ne]3s^2 3p^6$) is 170 pm. For consecutive elements proceeding down any group, anions have larger principal quantum numbers and, thus, larger radii.

Atoms and ions that have the same electron configuration are said to be isoelectronic. Examples of isoelectronic species are N^{3-}, O^{2-}, F^-, Ne, Na^+, Mg^{2+}, and Al^{3+} ($1s^2 2s^2 2p^6$). Another isoelectronic series is P^{3-}, S^{2-}, Cl^-, Ar, K^+, Ca^{2+}, and Sc^{3+} ($[Ne]3s^2 3p^6$). For atoms or ions that are isoelectronic, the number of protons determines the size. The greater the nuclear charge, the smaller the radius in a series of isoelectronic ions and atoms.

Variation in Ionization Energies

The amount of energy required to remove the most loosely bound electron from a gaseous atom in its ground state is called its first ionization energy (IE_1). The first ionization energy for an element, X, is the energy required to form a cation with +1 charge:

$$\mathbf{X}(g) \longrightarrow \mathbf{X}^+(g) + \mathbf{e}^- \quad \mathbf{IE}_1$$

The energy required to remove the second most loosely bound electron is called the second ionization energy (IE_2).

$$\mathbf{X}^+(g) \longrightarrow \mathbf{X}^{2+}(g) + \mathbf{e}^- \quad \mathbf{IE}_2$$

The energy required to remove the third electron is the third ionization energy, and so on. Energy is always required to remove electrons from atoms or ions, so ionization processes are endothermic and IE values are always positive. For larger atoms, the most loosely bound electron is located farther from the nucleus and so is easier to remove. Thus, as size (atomic radius) increases, the

ionization energy should decrease. Relating this logic to what we have just learned about radii, we would expect first ionization energies to decrease down a group and to increase across a period.




Figure 5.2.4: The first ionization energy of the elements in the first five periods are plotted against their atomic number.

This figure includes Atomic Number on the horizontal axis and, Ionization Energy (k J divided by mol) on the vertical axis. A red jagged line connects the ionization energies for elements with atomic numbers 1 through 86 on the graph. Peaks are evident at the locations of the noble or inert gases: H e, N e, A r, K r, X e, and R n. Similarly, minima exist at the locations of the alkali metals: L i, N a, K, R b, and C s.

Figure 5.2.4 graphs the relationship between the first ionization energy and the atomic number of several elements. Within a period, the values of first ionization energy for the elements (IE_1) generally increases with increasing Z. Down a group, the IE_1 value generally decreases with increasing Z. There are some systematic deviations from this trend, however. Note that the ionization energy of boron (atomic number 5) is less than that of beryllium (atomic number 4) even though the nuclear charge of boron is greater by one proton. This can be explained because the energy of the subshells increases as l increases, due to penetration and shielding (as discussed previously in this chapter). Within any one shell, the s electrons are lower in energy than the p electrons. This means that an s electron is harder to remove from an atom than a p electron in the same shell. The electron removed during the ionization of beryllium ($[He]2s^2$) is an s electron, whereas the electron removed during the ionization of boron ($[He]2s^22p^1$) is a p electron; this results in a lower first ionization energy for boron, even though its nuclear charge is greater by one proton. Thus, we see a small deviation from the predicted trend occurring each time a new subshell begins.





Figure 5.2.5: This version of the periodic table shows the first ionization energy of (IE: $_1$), in kJ/mol, of selected elements.

The trends for first ionization energies across periods and down groups are shown in this version of the periodic table.

Another deviation occurs as orbitals become more than one-half filled. The first ionization energy for oxygen is slightly less than that for nitrogen, despite the trend in increasing IE_1 values across a period. Looking at the orbital diagram of oxygen, we can see that removing one electron will eliminate the electron–electron repulsion caused by pairing the electrons in the 2*p* orbital and will result in a half-filled orbital (which is energetically favorable). Analogous changes occur in succeeding periods (note the dip for sulfur after phosphorus in Figure **5.2.4**.



The electronic configuration for oxygen is 1s superscript 2, 2s superscript, 2p superscript 4. An orbital diagram shows 2 squares each filled with a pair of opposite pointing arrows to represent the 1s ans 2s orbitals. Each of the three connected square which represents the 2p orbitals are filled with one arrow respectively with the addition of 1 red arrow in the first of the three squares.

Removing an electron from a cation is more difficult than removing an electron from a neutral atom because of the greater electrostatic attraction to the cation. Likewise, removing an electron from a cation with a higher positive charge is more difficult than removing an electron from an ion with a lower charge. Thus, successive ionization energies for one element always increase. As seen in Table **5.2.2**, there is a large increase in the ionization energies (color change) for each element. This jump corresponds to removal of the core electrons, which are harder to remove than the valence electrons. For example, Sc and Ga both have three valence electrons, so the rapid increase in ionization energy occurs after the third ionization.

Table 5.2.2: Successive Ionization Energies for Selected Elements (kJ/mol)

Element	IE_1	IE_2	IE_3	IE_4	IE_5	IE_6	IE_7
K	418.8	3051.8	4419.6	5876.9	7975.5	9590.6	11343
Ca	589.8	1145.4	4912.4	6490.6	8153.0	10495.7	12272.9
Sc	633.1	1235.0	2388.7	7090.6	8842.9	10679.0	13315.0
Ga	578.8	1979.4	2964.6	6180	8298.7	10873.9	13594.8
Ge	762.2	1537.5	3302.1	4410.6	9021.4	Not available	Not available
As	944.5	1793.6	2735.5	4836.8	6042.9	12311.5	Not available

✔ Example 5.2.2: Ranking Ionization Energies

Predict the order of increasing energy for the following processes: IE_1 for Al, IE_1 for Tl, IE_2 for Na, IE_3 for Al.

Solution

Removing the $6p^1$ electron from Tl is easier than removing the $3p^1$ electron from Al because the higher *n* orbital is farther from the nucleus, so $IE_1(Tl) < IE_1(Al)$. Ionizing the third electron from

$$\mathbf{Al} \quad (\mathbf{Al^{2+}} \longrightarrow \mathbf{Al^{3+}} + \mathbf{e^-})$$

requires more energy because the cation Al^{2+} exerts a stronger pull on the electron than the neutral Al atom, so $IE_1(Al) < IE_3(Al)$. The second ionization energy for sodium removes a core electron, which is a much higher energy process than removing valence electrons. Putting this all together, we obtain:

$$IE_1(Tl) < IE_1(Al) < IE_3(Al) < IE_2(Na).$$

? Exercise 5.2.2

Which has the lowest value for IE_1: O, Po, Pb, or Ba?

Answer

Ba

Variation in Electron Affinities

The electron affinity [EA] is the energy change for the process of adding an electron to a gaseous atom to form an anion (negative ion).

$$X(g) + e^- \longrightarrow X^-(g) \quad EA_1$$

This process can be either endothermic or exothermic, depending on the element. The EA of some of the elements is given in Figure 5.2.6. You can see that many of these elements have negative values of EA, which means that energy is released when the gaseous atom accepts an electron. However, for some elements, energy is required for the atom to become negatively charged and the value of their EA is positive. Just as with ionization energy, subsequent EA values are associated with forming ions with more charge. The second EA is the energy associated with adding an electron to an anion to form a –2 ion, and so on.




Figure 5.2.6: This version of the periodic table displays the electron affinity values (in kJ/mol) for selected elements.:
The trend for electron affinity values across periods and down groups is shown in this version of the periodic table. Values are not shown for groups 3 to 12 as well as period 7.

As we might predict, it becomes easier to add an electron across a series of atoms as the effective nuclear charge of the atoms increases. We find, as we go from left to right across a period, EAs tend to become more negative. The exceptions found among the elements of group 2 (2A), group 15 (5A), and group 18 (8A) can be understood based on the electronic structure of these groups. The noble gases, group 18 (8A), have a completely filled shell and the incoming electron must be added to a higher *n* level, which is more difficult to do. Group 2 (2A) has a filled *ns* subshell, and so the next electron added goes into the higher energy *np*, so, again, the observed EA value is not as the trend would predict. Finally, group 15 (5A) has a half-filled *np* subshell and the next electron must be paired with an existing *np* electron. In all of these cases, the initial relative stability of the electron configuration disrupts the trend in EA.

We also might expect the atom at the top of each group to have the largest EA; their first ionization potentials suggest that these atoms have the largest effective nuclear charges. However, as we move down a group, we see that the second element in the group most often has the greatest EA. The reduction of the EA of the first member can be attributed to the small size of the $n = 2$ shell and the resulting large electron–electron repulsions. For example, chlorine, with an EA value of –348 kJ/mol, has the highest value of any element in the periodic table. The EA of fluorine is –322 kJ/mol. When we add an electron to a fluorine atom to form a fluoride anion (F^-), we add an electron to the $n = 2$ shell. The electron is attracted to the nucleus, but there is also significant repulsion from the other electrons already present in this small valence shell. The chlorine atom has the same electron configuration in the valence shell, but because the entering electron is going into the $n = 3$ shell, it occupies a considerably larger region of space and the

electron–electron repulsions are reduced. The entering electron does not experience as much repulsion and the chlorine atom accepts an additional electron more readily.

The properties discussed in this section (size of atoms and ions, effective nuclear charge, ionization energies, and electron affinities) are central to understanding chemical reactivity. For example, because fluorine has an energetically favorable EA and a large energy barrier to ionization (IE), it is much easier to form fluorine anions than cations. Metallic properties including conductivity and malleability (the ability to be formed into sheets) depend on having electrons that can be removed easily. Thus, metallic character increases as we move down a group and decreases across a period in the same trend observed for atomic size because it is easier to remove an electron that is farther away from the nucleus.

Summary

Electron configurations allow us to understand many periodic trends. Covalent radius increases as we move down a group because the *n* level (orbital size) increases. Covalent radius mostly decreases as we move left to right across a period because the effective nuclear charge experienced by the electrons increases, and the electrons are pulled in tighter to the nucleus. Anionic radii are larger than the parent atom, while cationic radii are smaller, because the number of valence electrons has changed while the nuclear charge has remained constant. Ionization energy (the energy associated with forming a cation) decreases down a group and mostly increases across a period because it is easier to remove an electron from a larger, higher energy orbital. Electron affinity (the energy associated with forming an anion) is more favorable (exothermic) when electrons are placed into lower energy orbitals, closer to the nucleus. Therefore, electron affinity becomes increasingly negative as we move left to right across the periodic table and decreases as we move down a group. For both IE and electron affinity data, there are exceptions to the trends when dealing with completely filled or half-filled subshells.

Glossary

covalent radius
: one-half the distance between the nuclei of two identical atoms when they are joined by a covalent bond

effective nuclear charge
: charge that leads to the Coulomb force exerted by the nucleus on an electron, calculated as the nuclear charge minus shielding

electron affinity
: energy required to add an electron to a gaseous atom to form an anion

ionization energy
: energy required to remove an electron from a gaseous atom or ion. The associated number (e.g., second ionization energy) corresponds to the charge of the ion produced (X^{2+})

isoelectronic
: group of ions or atoms that have identical electron configurations

---

5.2: Electron Configurations, Valence Electrons, and the Periodic Table is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **6.5: Periodic Variations in Element Properties** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

CHAPTER OVERVIEW

6: Lewis Structures

Template:HideTOC

6.1: Types of Chemical Bonds

6.2: Representing Valance Electrons with Dots

6.3: Ionic Bonding

6.4: Covalent Bonding- Lewis Structure

6.5: Electronegativity and Bond Polarity

Thumbnail: Ball and Stick model for Methane (CH_4). (CC BY-SA-NC; anonymous by request).

6: Lewis Structures is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

6.1: Types of Chemical Bonds

Learning Objectives

- To quantitatively describe the energetic factors involved in the formation of an ionic bond.

Chemical bonds form when electrons can be simultaneously close to two or more nuclei, but beyond this, there is no simple, easily understood theory that would not only explain why atoms bind together to form molecules, but would also predict the three-dimensional structures of the resulting compounds as well as the energies and other properties of the bonds themselves. Unfortunately, no one theory exists that accomplishes these goals in a satisfactory way for all of the many categories of compounds that are known. Moreover, it seems likely that if such a theory does ever come into being, it will be far from simple.

When we are faced with a scientific problem of this complexity, experience has shown that it is often more useful to concentrate instead on developing **models**. A scientific model is something like a theory in that it should be able to explain observed phenomena and to make useful predictions. But whereas a theory can be discredited by a single contradictory case, a model can be useful even if it does not encompass all instances of the phenomena it attempts to explain. We do not even require that a model be a credible representation of reality; all we ask is that be able to explain the behavior of those cases to which it is applicable in terms that are consistent with the model itself. An example of a model that you may already know about is the kinetic molecular theory of gases. Despite its name, this is really a model (at least at the level that beginning students use it) because it does not even try to explain the observed behavior of real gases. Nevertheless, it serves as a tool for developing our understanding of gases, and as a starting point for more elaborate treatments.Given the extraordinary variety of ways in which atoms combine into aggregates, it should come as no surprise that a number of useful bonding models have been developed. Most of them apply only to certain classes of compounds, or attempt to explain only a restricted range of phenomena. In this section we will provide brief descriptions of some of the bonding models; the more important of these will be treated in much more detail in later parts of this chapter.

Ionic Bonding

Ions are atoms or molecules which are electrically charged. **Cations** are positively charged and **anions** carry a negative charge. Ions form when atoms gain or lose electrons. Since electrons are negatively charged, an atom that loses one or more electrons will become positively charged; an atom that gains one or more electrons becomes negatively charged. Ionic bonding is the attraction between positively- and negatively-charged **ions**. These oppositely charged ions attract each other to form ionic networks (or lattices). Electrostatics explains why this happens: opposite charges attract and like charges repel. When many ions attract each other, they form large, ordered, crystal lattices in which each ion is surrounded by ions of the opposite charge. Generally, when metals react with non-metals, electrons are transferred from the metals to the non-metals. The metals form positively-charged ions and the non-metals form negatively-charged ions.


Ionic bonds form when metals and non-metals chemically react. By definition, a metal is relatively stable if it loses electrons to form a complete valence shell and becomes positively charged. Likewise, a non-metal becomes stable by gaining electrons to complete its valence shell and become negatively charged. When metals and non-metals react, the metals lose electrons by transferring them to the non-metals, which gain them. Consequently, ions are formed, which instantly attract each other—ionic bonding.

Example 6.1.1: Sodium Chloride

For example, in the reaction of Na (sodium) and Cl (chlorine), each Cl atom takes one electron from a Na atom. Therefore each Na becomes a Na^+ cation and each Cl atom becomes a Cl^- anion. Due to their opposite charges, they attract each other to form an ionic lattice. The formula (ratio of positive to negative ions) in the lattice is **NaCl**.


$$2Na_{(s)} + Cl_{2(g)} \rightarrow 2NaCl_{(s)} \tag{6.1.1}$$

These ions are arranged in solid NaCl in a regular three-dimensional arrangement (or lattice):



NaCl lattice. (left) 3-D structure and (right) simple 2D slice through lattes. Images used with permission from Wikipedia and Mike Blaber.

The chlorine has a high affinity for electrons, and the sodium has a low ionization potential. Thus the chlorine gains an electron from the sodium atom. This can be represented using ***electron-dot symbols*** (here we will consider one chlorine atom, rather than Cl_2):



The arrow indicates the transfer of the electron from sodium to chlorine to form the Na^+ metal ion and the Cl^- chloride ion. Each ion now has an **octet** of electrons in its valence shell:

- Na^+: $2s^2 2p^6$
- Cl^-: $3s^2 3p^6$

Covalent Bonding

Formation of an ionic bond by complete transfer of an electron from one atom to another is possible only for a fairly restricted set of elements. Covalent bonding, in which neither atom loses complete control over its valence electrons, is much more common. In a **covalent bond** the electrons occupy a region of space *between* the two nuclei and are said to be *shared* by them. This model originated with the theory developed by G.N. Lewis in 1916, and it remains the most widely-used model of chemical bonding. The essential element s of this model can best be understood by examining the simplest possible molecule. This is the **hydrogen molecule ion** H_2^+, which consists of two nuclei and one electron. First, however, think what would happen if we tried to make the even simpler molecule H_2^{2+}. Since this would consist only of two protons whose electrostatic charges would repel each other at all distances, it is clear that such a molecule cannot exist; something more than two nuclei are required for bonding to occur.

In the hydrogen molecule ion H_2^+ we have a third particle, an electron. The effect of this electron will depend on its location with respect to the two nuclei. If the electron is in the space between the two nuclei, it will attract both protons toward itself, and thus toward each other. If the total attraction energy exceeds the internuclear repulsion, there will be a net bonding effect and the molecule will be stable. If, on the other hand, the electron is off to one side, it will attract both nuclei, but it will attract the closer one much more strongly, owing to the inverse-square nature of Coulomb's law. As a consequence, the electron will now help the electrostatic repulsion to push the two nuclei apart.

We see, then, that the electron is an essential component of a chemical bond, but that it must be in the right place: between the two nuclei. Coulomb's law can be used to calculate the forces experienced by the two nuclei for various positions of the electron. This allows us to define two regions of space about the nuclei, as shown in the figure. One region, the binding region, depicts locations at which the electron exerts a net binding effect on the new nuclei. Outside of this, in the antibinding region, the electron will actually work against binding.Summary


The amount of energy needed to separate a gaseous ion pair is its bond energy. The formation of ionic compounds are usually ***extremely exothermic***. The strength of the electrostatic attraction between ions with opposite charges is directly proportional to the magnitude of the charges on the ions and inversely proportional to the internuclear distance. The total energy of the system is a balance between the repulsive interactions between electrons on adjacent ions and the attractive interactions between ions with opposite charges.

Metallic Bonding

Metals have several qualities that are unique, such as the ability to conduct electricity, a low ionization energy, and a low electronegativity (so they will give up electrons easily, i.e., they are cations). **Metallic bonding** is sort of like covalent bonding, because it involves sharing electrons. The simplest model of metallic bonding is the "sea of electrons" model, which imagines that the atoms sit in a sea of valence electrons that are delocalized over all the atoms. Because there are not specific bonds between individual atoms, metals are more flexible. The atoms can move around and the electron sea will keep holding them together. Some metals are very hard and have very high melting points, while others are soft and have low melting points. This depends roughly on the number of valence electrons that form the sea.

A False Dichotomy: The Ionic vs. Colvalent

The covalent-ionic continuum described above is certainly an improvement over the old covalent -*versus* - ionic dichotomy that existed only in the textbook and classroom, but it is still only a one-dimensional view of a multidimensional world, and thus a view that hides more than it reveals. The main thing missing is any allowance for the type of bonding that occurs between more pairs of elements than any other: metallic bonding. Intermetallic compounds are rarely even mentioned in introductory courses, but since most of the elements are metals, there are a lot of them, and many play an important role in metallurgy. In metallic bonding, the valence electrons lose their association with individual atoms; they form what amounts to a mobile "electron fluid" that fills the space between the crystal lattice positions occupied by the atoms, (now essentially positive ions.) The more readily this electron delocalization occurs, the more "metallic" the element.



A triangular diagram whose corners are labeled metallic, covalent, and ionic. The chemical formula of some elements and compounds are listed inside the triangle.

Thus instead of the one-dimension chart shown above, we can construct a triangular diagram whose corners represent the three extremes of "pure" covalent, ionic, and metallic bonding.

Contributors

- Mike Blaber (Florida State University)
- Modified by Joshua Halpern (Howard University)

6.1: Types of Chemical Bonds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

6.2: Representing Valance Electrons with Dots

Learning Objectives

- To use Lewis electron dot symbols to predict the number of bonds an element will form.

Why are some substances chemically bonded molecules and others are an association of ions? The answer to this question depends upon the electronic structures of the atoms and nature of the chemical forces within the compounds. Although there are no sharply defined boundaries, chemical bonds are typically classified into three main types: ionic bonds, covalent bonds, and metallic bonds. In this chapter, each type of bond wil be discussed and the general properties found in typical substances in which the bond type occurs

1. Ionic bonds results from ***electrostatic forces that exist between ions of opposite charge***. These bonds typically involves a metal with a nonmetal
2. Covalent bonds ***result from the sharing of electrons between two atoms***. The bonds typically involves one nonmetallic element with another
3. Metallic bonds These bonds are found in solid metals (copper, iron, aluminum) with each metal bonded to several neighboring groups and bonding electrons free to move throughout the 3-dimensional structure.

Each bond classification is discussed in detail in subsequent sections of the chapter. Let's look at the preferred arrangements of electrons in atoms when they form chemical compounds.




Figure **6.2.1**: G. N. Lewis and the Octet Rule. (a) Lewis is working in the laboratory. (b) In Lewis's original sketch for the octet rule, he initially placed the electrons at the corners of a cube rather than placing them as we do now.

Lewis Symbols

At the beginning of the 20th century, the American chemist G. N. Lewis (1875–1946) devised a system of symbols—now called *Lewis electron dot symbols* (often shortened to *Lewis dot symbols*) that can be used for predicting the number of bonds formed by most elements in their compounds. Each Lewis dot symbol consists of the chemical symbol for an element surrounded by dots that represent its valence electrons.

Lewis Dot symbols:

- convenient representation of valence electrons
- allows you to keep track of valence electrons during bond formation
- consists of the chemical symbol for the element plus a dot for each valence electron

To write an element's Lewis dot symbol, we place dots representing its valence electrons, one at a time, around the element's chemical symbol. Up to four dots are placed above, below, to the left, and to the right of the symbol (in any order, as long as elements with four or fewer valence electrons have no more than one dot in each position). The next dots, for elements with more than four valence electrons, are again distributed one at a time, each paired with one of the first four. For example, the electron configuration for atomic sulfur is [Ne]3s^{2}3p^4, thus there are ***six*** valence electrons. Its Lewis symbol would therefore be:



Fluorine, for example, with the electron configuration [He]$2s^2 2p^5$, has seven valence electrons, so its Lewis dot symbol is constructed as follows:




Figure 8.1.2.

Lewis used the unpaired dots to predict the number of bonds that an element will form in a compound. Consider the symbol for nitrogen in Figure 8.1.2. The Lewis dot symbol explains why nitrogen, with three unpaired valence electrons, tends to form compounds in which it shares the unpaired electrons to form three bonds. Boron, which also has three unpaired valence electrons in its Lewis dot symbol, also tends to form compounds with three bonds, whereas carbon, with four unpaired valence electrons in its Lewis dot symbol, tends to share all of its unpaired valence electrons by forming compounds in which it has four bonds.

Element	Electron config.	Electron dot symbol
Li	[He]$2s^1$	
Be	[He]$2s^2$	
B	[He]$2s^2 2p^1$	
C	[He]$2s^2 2p^2$	
N	[He]$2s^2 2p^3$	
O	[He]$2s^2 2p^4$	
F	[He]$2s^2 2p^5$	
Ne	[He]$2s^2 2p^6$	

Figure **6.2.2**: Lewis Dot Symbols for the Elements in Period 2

L i has one dot on the right, B e has one dot on the left and right, B has one dot on the left, right, and above. C has one dot above, below, on the left and on the right. N has one dot above, below, on the left and two dots on the right. O has two dots on the left and right and one dot above and below. F has two dots above, on the left, on the right and on dot below. N e has two dots above, below, on the right, and on the left.



The Octet Rule

In 1904, Richard Abegg formulated what is now known as *Abegg's rule*, which states that the difference between the maximum positive and negative valences of an element is frequently eight. This rule was used later in 1916 when Gilbert N. Lewis formulated the "octet rule" in his cubical atom theory. The **octet rule** refers to the tendency of atoms to prefer to have eight electrons in the *valence shell*. When atoms have fewer than eight electrons, they tend to react and form more stable compounds. Atoms will react to get in the most stable state possible. A complete octet is very stable because all orbitals will be full. Atoms with greater stability

have less energy, so a reaction that increases the stability of the atoms will release energy in the form of heat or light ;reactions that decrease stability must absorb energy, getting colder.

When discussing the octet rule, we do not consider *d* or *f* electrons. Only the s and p electrons are involved in the octet rule, making it a useful rule for the *main group elements* (elements not in the transition metal or inner-transition metal blocks); an octet in these atoms corresponds to an electron configurations ending with s^2p^6.

Definition: Octet Rule

A stable arrangement is attended when the atom is surrounded by eight electrons. This octet can be made up by own electrons and some electrons which are shared. Thus, an atom continues to form bonds until an octet of electrons is made. This is known as octet rule by Lewis.

1. Normally two electrons pairs up and forms a bond, e.g., $\mathbf{H_2}$
2. For most atoms there will be a maximum of eight electrons in the valence shell (octet structure), e.g., $\mathbf{CH_4}$




Figure 1: Bonding in $\boldsymbol{H_2}$ and methane ($\boldsymbol{CH_4}$)

A hydrogen bonds with each of the four valence electrons of a carbon meaning that four hydrogens can bond with one carbon.

The other tendency of atoms is to maintain a neutral charge. Only the noble gases (the elements on the right-most column of the periodic table) have zero charge with filled valence octets. All of the other elements have a charge when they have eight electrons all to themselves. The result of these two guiding principles is the explanation for much of the reactivity and bonding that is observed within atoms: atoms seek to share electrons in a way that minimizes charge while fulfilling an octet in the valence shell.

The noble gases rarely form compounds. They have the most stable configuration (full octet, no charge), so they have no reason to react and change their configuration. All other elements attempt to gain, lose, or share electrons to achieve a noble gas configuration.

Example 6.2.1: Salt

The formula for table salt is NaCl. It is the result of Na^+ ions and Cl^- ions bonding together. If sodium metal and chlorine gas mix under the right conditions, they will form salt. The sodium loses an electron, and the chlorine gains that electron. In the process, a great amount of light and heat is released. The resulting salt is mostly unreactive — it is stable. It will not undergo any explosive reactions, unlike the sodium and chlorine that it is made of. Why?

Solution

Referring to the octet rule, atoms attempt to get a noble gas electron configuration, which is eight valence electrons. Sodium has one valence electron, so giving it up would result in the same electron configuration as neon. Chlorine has seven valence electrons, so if it takes one it will have eight (an octet). Chlorine has the electron configuration of argon when it gains an electron.

The octet rule could have been satisfied if chlorine gave up all seven of its valence electrons and sodium took them. In that case, both would have the electron configurations of noble gasses, with a full valence shell. However, their charges would be

much higher. It would be Na^{7-} and Cl^{7+}, which is much less stable than Na^+ and Cl^-. Atoms are more stable when they have no charge, or a small charge.

Lewis dot symbols can also be used to represent the ions in ionic compounds. The reaction of cesium with fluorine, for example, to produce the ionic compound CsF can be written as follows:



No dots are shown on Cs^+ in the product because cesium has lost its single valence electron to fluorine. The transfer of this electron produces the Cs^+ ion, which has the valence electron configuration of Xe, and the F^- ion, which has a total of eight valence electrons (an octet) and the Ne electron configuration. This description is consistent with the statement that among the main group elements, ions in simple binary ionic compounds generally have the electron configurations of the nearest noble gas. The charge of each ion is written in the product, and the anion and its electrons are enclosed in brackets. This notation emphasizes that the ions are associated electrostatically; no electrons are shared between the two elements.

> *Atoms often gain, lose, or share electrons to achieve the same number of electrons as the noble gas closest to them in the periodic table.*

As you might expect for such a qualitative approach to bonding, there are exceptions to the octet rule, which we describe elsewhere. These include molecules in which one or more atoms contain fewer or more than eight electrons.

Summary

Lewis dot symbols can be used to predict the number of bonds formed by most elements in their compounds. One convenient way to predict the number and basic arrangement of bonds in compounds is by using **Lewis electron dot symbols**, which consist of the chemical symbol for an element surrounded by dots that represent its valence electrons, grouped into pairs often placed above, below, and to the left and right of the symbol. The structures reflect the fact that the elements in period 2 and beyond tend to gain, lose, or share electrons to reach a total of eight valence electrons in their compounds, the so-called **octet rule**. Hydrogen, with only two valence electrons, does not obey the octet rule.

Contributors and Attributions

- Mike Blaber (Florida State University)
- Wikipedia
- National Programme on Technology Enhanced Learning (India)

6.2: Representing Valance Electrons with Dots is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **8.1: Chemical Bonds, Lewis Symbols, and the Octet Rule** is licensed CC BY-NC-SA 3.0.

6.3: Ionic Bonding

Learning Objectives

- To describe the characteristics of ionic bonding.
- To quantitatively describe the energetic factors involved in the formation of an ionic bond.

Ions are atoms or molecules which are electrically charged. **Cations** are positively charged and **anions** carry a negative charge. Ions form when atoms gain or lose electrons. Since electrons are negatively charged, an atom that loses one or more electrons will become positively charged; an atom that gains one or more electrons becomes negatively charged. **Ionic bonding** is the attraction between positively- and negatively-charged ions. These oppositely charged ions attract each other to form ionic networks (or **lattices**). Electrostatics explains why this happens: opposite charges attract and like charges repel. When many ions attract each other, they form large, ordered, crystal lattices in which each ion is surrounded by ions of the opposite charge. Generally, when metals react with non-metals, electrons are transferred from the metals to the non-metals. The metals form positively-charged ions and the non-metals form negatively-charged ions.

Generating Ionic Bonds

Ionic bonds form when metals and non-metals chemically react. By definition, a metal is relatively stable if it loses electrons to form a complete valence shell and becomes positively charged. Likewise, a non-metal becomes stable by gaining electrons to complete its valence shell and become negatively charged. When metals and non-metals react, the metals lose electrons by transferring them to the non-metals, which gain them. Consequently, ions are formed, which instantly attract each other—ionic bonding.


In the overall ionic compound, positive and negative charges must be balanced, because electrons cannot be created or destroyed, only transferred. Thus, the total number of electrons lost by the cationic species must equal the total number of electrons gained by the anionic species.

Example 6.3.1: Sodium Chloride

For example, in the reaction of Na (sodium) and Cl (chlorine), each Cl atom takes one electron from a Na atom. Therefore each Na becomes a Na^+ cation and each Cl atom becomes a Cl^- anion. Due to their opposite charges, they attract each other to form an ionic lattice. The formula (ratio of positive to negative ions) in the lattice is **NaCl**.


$$2\,Na\,(s) + Cl\,2\,(g) \rightarrow 2\,NaCl\,(s)$$

These ions are arranged in solid NaCl in a regular three-dimensional arrangement (or lattice):



NaCl lattice. (left) 3-D structure and (right) simple 2D slice through lattes. Images used with permission from Wikipedia and Mike Blaber.

The chlorine has a high affinity for electrons, and the sodium has a low ionization energy. Thus the chlorine gains an electron from the sodium atom. This can be represented using ewis dot symbols (here we will consider one chlorine atom, rather than Cl_2):



Chlorine becomes more negative when it takes the one valence electron from sodium when it makes an octet.

The arrow indicates the transfer of the electron from sodium to chlorine to form the Na^+ metal ion and the Cl^- chloride ion. Each ion now has an **octet** of electrons in its valence shell:

- $Na^{+:}$ $2s^22p^6$
- Cl^-: $3s^23p^6$

Energetics of Ionic Bond Formation

Ionic bonds are formed when positively and negatively charged ions are held together by electrostatic forces. Consider a single pair of ions, one cation and one anion. How strong will the force of their attraction be? According to **Coulomb's Law**, the energy of the electrostatic attraction (E) between two charged particles is proportional to the magnitude of the charges and inversely proportional to the internuclear distance between the particles (r):

$$E \propto \frac{Q_1 Q_2}{r} \tag{6.3.1}$$

$$E = k\frac{Q_1 Q_2}{r} \tag{6.3.2}$$

where each ion's charge is represented by the symbol Q. The proportionality constant k is equal to 2.31×10^{-28} J·m. This value of k includes the charge of a single electron (1.6022×10^{-19} C) for each ion. The equation can also be written using the charge of each ion, expressed in coulombs (C), incorporated in the constant. In this case, the proportionality constant, k, equals 8.999 × 109 J·m/C^2. In the example given, $Q_1 = +1(1.6022 \times 10^{-19}$ C) and $Q_2 = -1(1.6022 \times 10^{-19}$ C). If Q_1 and Q_2 have opposite signs (as in NaCl, for example, where Q_1 is +1 for Na^+ and Q_2 is −1 for Cl^-), then E is negative, which means that energy is *released* when oppositely charged ions are brought together from an infinite distance to form an isolated ion pair.

> *Energy is always released when a bond is formed and correspondingly, it always requires energy to break a bond.*

As shown by the green curve in the lower half of Figure **6.3.1**, the maximum energy would be released when the ions are infinitely close to each other, at $r = 0$. Because ions occupy space and have a structure with the positive nucleus being surrounded by electrons, however, they cannot be infinitely close together. At very short distances, repulsive electron–electron interactions between electrons on adjacent ions become stronger than the attractive interactions between ions with opposite charges, as shown by the red curve in the upper half of Figure **6.3.1**. The total energy of the system is a balance between the attractive and repulsive interactions. The purple curve in Figure **6.3.1** shows that the total energy of the system reaches a minimum at r_0, the point where the electrostatic repulsions and attractions are exactly balanced. This distance is the same as the experimentally measured **bond distance**.




Figure 6.3.1: A Plot of Potential Energy versus Internuclear Distance for the Interaction between a Gaseous Na^+ Ion and a Gaseous Cl^- Ion. The energy of the system reaches a minimum at a particular distance (r_0) when the attractive and repulsive interactions are balanced.

Consider the energy released when a gaseous Na^+ ion and a gaseous Cl^- ion are brought together from $r = \infty$ to $r = r_0$. Given that the observed gas-phase internuclear distance is 236 pm, the energy change associated with the formation of an ion pair from an $Na^+_{(g)}$ ion and a $Cl^-_{(g)}$ ion is as follows:

$$\begin{aligned} E &= k\frac{Q_1Q_2}{r_0} \\ &= (2.31 \times 10^{-28}\text{J} \cdot \cancel{\text{m}}) \left(\frac{(+1)(-1)}{236\ \cancel{\text{pm}} \times 10^{-12}\ \cancel{\text{m/pm}}} \right) \\ &= -9.79 \times 10^{-19}\ J/ion\ pair \end{aligned}$$

The negative value indicates that energy is released. Our convention is that if a chemical process provides energy to the outside world, the energy change is negative. If it requires energy, the energy change is positive. To calculate the energy change in the formation of a mole of NaCl pairs, we need to multiply the energy per ion pair by Avogadro's number:

$$E = \left(-9.79 \times 10^{-19}\ J/\cancel{ionpair}\right)\left(6.022 \times 10^{23}\ \cancel{ion\ pair}/mol\right) = -589\ kJ/mol \tag{6.3.3}$$

This is the energy released when 1 mol of gaseous ion pairs is formed, *not* when 1 mol of positive and negative ions condenses to form a crystalline lattice. Because of long-range interactions in the lattice structure, this energy does not correspond directly to the **lattice energy** of the crystalline solid. However, the large negative value indicates that bringing positive and negative ions together is energetically very favorable, whether an ion pair or a crystalline lattice is formed.

We summarize the important points about ionic bonding:

- At r_0, the ions are more stable (have a lower potential energy) than they are at an infinite internuclear distance. When oppositely charged ions are brought together from $r = \infty$ to $r = r_0$, the energy of the system is lowered (energy is released).
- Because of the low potential energy at r_0, energy must be added to the system to separate the ions. The amount of energy needed is the bond energy.
- The energy of the system reaches a minimum at a particular internuclear distance (the bond distance).

✔ Example 6.3.2: LiF

Calculate the amount of energy released when 1 mol of gaseous Li^+F^- ion pairs is formed from the separated ions. The observed internuclear distance in the gas phase is 156 pm.

Given: cation and anion, amount, and internuclear distance

Asked for: energy released from formation of gaseous ion pairs

Strategy:

Substitute the appropriate values into Equation 6.3.2 to obtain the energy released in the formation of a single ion pair and then multiply this value by Avogadro's number to obtain the energy released per mole.

Solution:

Inserting the values for Li^+F^- into Equation 6.3.2 (where $Q_1 = +1$, $Q_2 = -1$, and $r = 156$ pm), we find that the energy associated with the formation of a single pair of Li^+F^- ions is

$$\begin{aligned} E &= k\frac{Q_1Q_2}{r_0} \\ &= \left(2.31 \times 10^{-28}\, J \cdot \cancel{m}\right)\left(\frac{(+1)(-1)}{156\, \cancel{pm} \times 10^{-12}\, \cancel{m/pm}}\right) \\ &= -1.48 \times 10^{-18} \end{aligned}$$

Then the energy released per mole of Li^+F^- ion pairs is

$$\begin{aligned} E &= \left(-1.48 \times 10^{-18}\, J/\cancel{\text{ion pair}}\right)\left(6.022 \times 10^{23}\, \cancel{\text{ion pair}}/mol\right) \\ &- 891\ kJ/mol \end{aligned}$$

Because Li^+ and F^- are smaller than Na^+ and Cl^- (see Section 7.3), the internuclear distance in LiF is shorter than in NaCl. Consequently, in accordance with Equation 6.3.2, much more energy is released when 1 mol of gaseous Li^+F^- ion pairs is formed (−891 kJ/mol) than when 1 mol of gaseous Na^+Cl^- ion pairs is formed (−589 kJ/mol).

? Exercise 6.3.2: Magnesium oxide

Calculate the amount of energy released when 1 mol of gaseous **MgO** ion pairs is formed from the separated ions. The internuclear distance in the gas phase is 175 pm.

Answer

−3180 kJ/mol = -3.18×10^3 kJ/mol

Electron Configuration of Ions

How does the energy released in lattice formation compare to the energy required to strip away a second electron from the Na^+ ion? Since the Na^+ ion has a noble gas electron configuration, stripping away the next electron from this stable arrangement would require more energy than what is released during lattice formation (Sodium I_2 = 4,560 kJ/mol). Thus, sodium is present in ionic compounds as Na^+ and not Na^{2+}. Likewise, adding an electron to fill a valence shell (and achieve noble gas electron configuration) is exothermic or only slightly endothermic. To add an additional electron into a ***new*** subshell requires tremendous energy - more than the lattice energy. Thus, we find Cl^- in ionic compounds, but not Cl^{2-}.

Table **6.3.1**: Lattice energies range from around 700 kJ/mol to 4000 kJ/mol:

Compound	Lattice Energy (kJ/mol)
LiF	1024
LiI	744
NaF	911
NaCl	788
NaI	693
KF	815
KBr	682
KI	641
MgF_2	2910
$SrCl_2$	2130
MgO	3938

This amount of energy can compensate for values as large as I_3 for valence electrons (i.e. can strip away up to 3 valence electrons). Because most transition metals would require the removal of more than 3 electrons to attain a noble gas core, they are not found in ionic compounds with a noble gas core. A transition metal always loses electrons first from the higher 's' subshell, before losing from the underlying 'd' subshell. (The remaining electrons in the unfilled d subshell are the reason for the bright colors observed in many transition metal compounds!) For example, iron ions will **not** form a noble gas core:

- Fe: [Ar]$4s^2 3d^6$
- Fe^{2+}: [Ar] $3d^6$
- Fe^{3+}: [Ar] $3d^5$

Some metal ions can form a pseudo noble gas core (and be colorless), for example:

- Ag: [Kr]$5s^1 4d^{10}$ Ag^+ [Kr]$4d^{10}$ Compound: AgCl
- Cd: [Kr]$5s^2 4d^{10}$ Cd^{2+} [Kr]$4d^{10}$ Compound: CdS

The valence electrons do not adhere to the "octet rule" in this case (a limitation of the usefulness of this rule). Note: The silver and cadmium atoms lost the 5s electrons in achieving the ionic state.

> *When a positive ion is formed from an atom, electrons are **always** lost first from the subshell with the largest principle quantum number*

Polyatomic Ions

Not all ionic compounds are formed from only two elements. Many **polyatomic ions** exist, in which two or more atoms are bound together by covalent bonds. They form a stable grouping which carries a charge (positive or negative). The group of atoms as a whole acts as a charged species in forming an ionic compound with an oppositely charged ion. Polyatomic ions may be either positive or negative, for example:

- NH_4^+ (ammonium) = cation
- SO_4^{2-} (sulfate) = anion

The principles of ionic bonding with polyatomic ions are the same as those with monatomic ions. Oppositely charged ions come together to form a crystalline lattice, releasing a lattice energy. Based on the shapes and charges of the polyatomic ions, these compounds may form crystalline lattices with interesting and complex structures.

Summary

The amount of energy needed to separate a gaseous ion pair is its bond energy. The formation of ionic compounds are usually ***extremely exothermic***. The strength of the electrostatic attraction between ions with opposite charges is directly proportional to the magnitude of the charges on the ions and inversely proportional to the internuclear distance. The total energy of the system is a balance between the repulsive interactions between electrons on adjacent ions and the attractive interactions between ions with opposite charges.

Contributors and Attributions

- Wikibooks [en.wikibooks.org]
- Mike Blaber (Florida State University)
- Modified by Joshua Halpern (Howard University)

6.3: Ionic Bonding is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **8.2: Ionic Bonding** is licensed CC BY-NC-SA 3.0.

6.4: Covalent Bonding- Lewis Structure

Learning Objectives

- To use Lewis dot symbols to explain the stoichiometry of a compound

We begin our discussion of the relationship between structure and bonding in covalent compounds by describing the interaction between two identical neutral atoms—for example, the H_2 molecule, which contains a purely covalent bond. Each hydrogen atom in H_2 contains one electron and one proton, with the electron attracted to the proton by electrostatic forces. As the two hydrogen atoms are brought together, additional interactions must be considered (Figure **6.4.1**):

- The electrons in the two atoms repel each other because they have the same charge (
- *The electrons in the two atoms repel each other because they have the same charge (E > 0).*
- *Similarly, the protons in adjacent atoms repel each other (E > 0).*
- *The electron in one atom is attracted to the oppositely charged proton in the other atom and vice versa (E < 0). Recall that it is impossible to specify precisely the position of the electron in either hydrogen atom. Hence the quantum mechanical probability distributions must be used.*




Figure **6.4.1**: Attractive and Repulsive Interactions between Electrons and Nuclei in the Hydrogen Molecule. Electron–electron and proton–proton interactions are repulsive; electron–proton interactions are attractive. At the observed bond distance, the repulsive and attractive interactions are balanced.

A plot of the potential energy of the system as a function of the internuclear distance (Figure **6.4.2**) shows that the system becomes more stable (the energy of the system decreases) as two hydrogen atoms move toward each other from $r = \infty$, until the energy reaches a minimum at $r = r_0$ (the observed internuclear distance in H_2 is 74 pm). Thus at intermediate distances, proton–electron attractive interactions dominate, but as the distance becomes very short, electron–electron and proton–proton repulsive interactions cause the energy of the system to increase rapidly. Notice the similarity between Figures **6.4.1** and **6.4.2**, which described a system containing two oppositely charged *ions*. The shapes of the energy versus distance curves in the two figures are similar because they both result from attractive and repulsive forces between charged entities.





Figure **6.4.2**: A Plot of Potential Energy versus Internuclear Distance for the Interaction between Two Gaseous Hydrogen Atoms.

At long distances, both attractive and repulsive interactions are small. As the distance between the atoms decreases, the attractive electron–proton interactions dominate, and the energy of the system decreases. At the observed bond distance, the repulsive electron–electron and proton–proton interactions just balance the attractive interactions, preventing a further decrease in the

internuclear distance. At very short internuclear distances, the repulsive interactions dominate, making the system less stable than the isolated atoms.


Using Lewis Dot Symbols to Describe Covalent Bonding

The valence electron configurations of the constituent atoms of a covalent compound are important factors in determining its structure, stoichiometry, and properties. For example, chlorine, with seven valence electrons, is one electron short of an octet. If two chlorine atoms share their unpaired electrons by making a covalent bond and forming Cl_2, they can each complete their valence shell:




Each chlorine atom now has an octet. The electron pair being shared by the atoms is called a bonding pair; the other three pairs of electrons on each chlorine atom are called lone pairs. Lone pairs are not involved in covalent bonding. If both electrons in a covalent bond come from the same atom, the bond is called a coordinate covalent bond. Examples of this type of bonding are presented in Section 8.6 when we discuss atoms with less than an octet of electrons.

We can illustrate the formation of a water molecule from two hydrogen atoms and an oxygen atom using Lewis dot symbols:



The structure on the right is the *Lewis electron structure*, or *Lewis structure*, for H_2O. With two bonding pairs and two lone pairs, the oxygen atom has now completed its octet. Moreover, by sharing a bonding pair with oxygen, each hydrogen atom now has a full valence shell of two electrons. Chemists usually indicate a bonding pair by a single line, as shown here for our two examples:



The following procedure can be used to construct Lewis electron structures for more complex molecules and ions:

1. **Arrange the atoms to show specific connections.** When there is a central atom, it is usually the least electronegative element in the compound. Chemists usually list this central atom first in the chemical formula (as in CCl_4 and CO_3^{2-}, which both have C as the central atom), which is another clue to the compound's structure. Hydrogen and the halogens are almost always connected to only one other atom, so they are usually *terminal* rather than central.
2. **Determine the total number of valence electrons in the molecule or ion.** Add together the valence electrons from each atom. (Recall that the number of valence electrons is indicated by the position of the element in the periodic table.) If the species is a polyatomic ion, remember to add or subtract the number of electrons necessary to give the total charge on the ion. For CO_3^{2-}, for example, we add two electrons to the total because of the −2 charge.
3. **Place a bonding pair of electrons between each pair of adjacent atoms to give a single bond.** In H_2O, for example, there is a bonding pair of electrons between oxygen and each hydrogen.
4. **Beginning with the terminal atoms, add enough electrons to each atom to give each atom an octet (two for hydrogen).** These electrons will usually be lone pairs.
5. **If any electrons are left over, place them on the central atom.** We will explain later that some atoms are able to accommodate more than eight electrons.
6. **If the central atom has fewer electrons than an octet, use lone pairs from terminal atoms to form multiple (double or triple) bonds to the central atom to achieve an octet.** This will not change the number of electrons on the terminal atoms.

Now let's apply this procedure to some particular compounds, beginning with one we have already discussed.

> The central atom is usually the least electronegative element in the molecule or ion; hydrogen and the halogens are usually terminal.

The H_2O Molecule

1. Because H atoms are almost always terminal, the arrangement within the molecule must be HOH.


2. Each H atom (group 1) has 1 valence electron, and the O atom (group 16) has 6 valence electrons, for a total of 8 valence electrons.
3. Placing one bonding pair of electrons between the O atom and each H atom gives H:O:H, with 4 electrons left over.
4. Each H atom has a full valence shell of 2 electrons.
5. Adding the remaining 4 electrons to the oxygen (as two lone pairs) gives the following structure:



This is the Lewis structure we drew earlier. Because it gives oxygen an octet and each hydrogen two electrons, we do not need to use step 6.

The OCl^- Ion

1. With only two atoms in the molecule, there is no central atom.
2. Oxygen (group 16) has 6 valence electrons, and chlorine (group 17) has 7 valence electrons; we must add one more for the negative charge on the ion, giving a total of 14 valence electrons.
3. Placing a bonding pair of electrons between O and Cl gives O:Cl, with 12 electrons left over.
4. If we place six electrons (as three lone pairs) on each atom, we obtain the following structure:



Both the oxygen and chlorine have 3 electron pairs drawn around them with a bond drawn between them. The molecule has square brackets placed around it and has a negative charge.

Each atom now has an octet of electrons, so steps 5 and 6 are not needed. The Lewis electron structure is drawn within brackets as is customary for an ion, with the overall charge indicated outside the brackets, and the bonding pair of electrons is indicated by a solid line. OCl^- is the hypochlorite ion, the active ingredient in chlorine laundry bleach and swimming pool disinfectant.


The CH_2O Molecule

1. Because carbon is less electronegative than oxygen and hydrogen is normally terminal, C must be the central atom. One possible arrangement is as follows:




2. Each hydrogen atom (group 1) has one valence electron, carbon (group 14) has 4 valence electrons, and oxygen (group 16) has 6 valence electrons, for a total of [(2)(1) + 4 + 6] = 12 valence electrons.

3. Placing a bonding pair of electrons between each pair of bonded atoms gives the following:



Six electrons are used, and 6 are left over.


4. Adding all 6 remaining electrons to oxygen (as three lone pairs) gives the following:



Although oxygen now has an octet and each hydrogen has 2 electrons, carbon has only 6 electrons.

5. There are no electrons left to place on the central atom.

6. To give carbon an octet of electrons, we use one of the lone pairs of electrons on oxygen to form a carbon–oxygen double bond:



The bond between the oxygen and carbon is replaced with a double bond. The oxygen also has two lone pairs drawn.

Both the oxygen and the carbon now have an octet of electrons, so this is an acceptable Lewis electron structure. The O has two bonding pairs and two lone pairs, and C has four bonding pairs. This is the structure of formaldehyde, which is used in embalming fluid.

An alternative structure can be drawn with one H bonded to O. *Formal charges*, discussed later in this section, suggest that such a structure is less stable than that shown previously.

Example 6.4.1

Write the Lewis electron structure for each species.

a. NCl_3
b. S_2^{2-}
c. NOCl

Given: chemical species


Asked for: Lewis electron structures

Strategy:


Use the six-step procedure to write the Lewis electron structure for each species.

Solution:

a. Nitrogen is less electronegative than chlorine, and halogen atoms are usually terminal, so nitrogen is the central atom. The nitrogen atom (group 15) has 5 valence electrons and each chlorine atom (group 17) has 7 valence electrons, for a total of 26 valence electrons. Using 2 electrons for each N–Cl bond and adding three lone pairs to each Cl account for (3 × 2) + (3 × 2 × 3) = 24 electrons. Rule 5 leads us to place the remaining 2 electrons on the central N:




Nitrogen trichloride is an unstable oily liquid once used to bleach flour; this use is now prohibited in the United States.




Nitrogen trichloride


b. In a diatomic molecule or ion, we do not need to worry about a central atom. Each sulfur atom (group 16) contains 6 valence electrons, and we need to add 2 electrons for the −2 charge, giving a total of 14 valence electrons. Using 2 electrons for the S–S bond, we arrange the remaining 12 electrons as three lone pairs on each sulfur, giving each S atom an octet of electrons:




c. Because nitrogen is less electronegative than oxygen or chlorine, it is the central atom. The N atom (group 15) has 5 valence electrons, the O atom (group 16) has 6 valence electrons, and the Cl atom (group 17) has 7 valence electrons, giving a total of 18 valence electrons. Placing one bonding pair of electrons between each pair of bonded atoms uses 4 electrons and gives the following:




Adding three lone pairs each to oxygen and to chlorine uses 12 more electrons, leaving 2 electrons to place as a lone pair on nitrogen:



Because this Lewis structure has only 6 electrons around the central nitrogen, a lone pair of electrons on a terminal atom must be used to form a bonding pair. We could use a lone pair on either O or Cl. Because we have seen many structures in which O forms a double bond but none with a double bond to Cl, it is reasonable to select a lone pair from O to give the following:




All atoms now have octet configurations. This is the Lewis electron structure of nitrosyl chloride, a highly corrosive, reddish-orange gas.




? Exercise 6.4.1

Write Lewis electron structures for CO_2 and SCl_2, a vile-smelling, unstable red liquid that is used in the manufacture of rubber.


Answer

1. 




2. 

Two chlorines are bonded to a sulfur. The sulfur has 2 lone pairs while the chlorines have 3 lone pairs each.




Using Lewis Electron Structures to Explain Stoichiometry

Lewis dot symbols provide a simple rationalization of why elements form compounds with the observed stoichiometries. In the Lewis model, the number of bonds formed by an element in a neutral compound is the same as the number of unpaired electrons it must share with other atoms to complete its octet of electrons. For the elements of Group 17 (the halogens), this number is one; for the elements of Group 16 (the chalcogens), it is two; for Group 15 elements, three; and for Group 14 elements four. These requirements are illustrated by the following Lewis structures for the hydrides of the lightest members of each group:



Elements may form multiple bonds to complete an octet. In ethylene, for example, each carbon contributes two electrons to the double bond, giving each carbon an octet (two electrons/bond × four bonds = eight electrons). Neutral structures with fewer or more bonds exist, but they are unusual and violate the octet rule.



Allotropes of an element can have very different physical and chemical properties because of different three-dimensional arrangements of the atoms; the number of bonds formed by the component atoms, however, is always the same. As noted at the beginning of the chapter, diamond is a hard, transparent solid; graphite is a soft, black solid; and the fullerenes have open cage structures. Despite these differences, the carbon atoms in all three allotropes form four bonds, in accordance with the octet rule.

> Lewis structures explain why the elements of groups 14–17 form neutral compounds with four, three, two, and one bonded atom(s), respectively.

Elemental phosphorus also exists in three forms: white phosphorus, a toxic, waxy substance that initially glows and then spontaneously ignites on contact with air; red phosphorus, an amorphous substance that is used commercially in safety matches, fireworks, and smoke bombs; and black phosphorus, an unreactive crystalline solid with a texture similar to graphite (Figure **6.4.3**). Nonetheless, the phosphorus atoms in all three forms obey the octet rule and form three bonds per phosphorus atom.




Figure **6.4.3**: The Three Allotropes of Phosphorus: White, Red, and Black. ll three forms contain only phosphorus atoms, but they differ in the arrangement and connectivity of their atoms. White phosphorus contains P_4 tetrahedra, red phosphorus is a network of linked P_8 and P_9 units, and black phosphorus forms sheets of six-membered rings. As a result, their physical and chemical properties differ dramatically.

Formal Charges

It is sometimes possible to write more than one Lewis structure for a substance that does not violate the octet rule, as we saw for CH_2O, but not every Lewis structure may be equally reasonable. In these situations, we can choose the most stable Lewis structure

by considering the formal charge on the atoms, which is the difference between the number of valence electrons in the free atom and the number assigned to it in the Lewis electron structure. The formal charge is a way of computing the charge distribution within a Lewis structure; the sum of the formal charges on the atoms within a molecule or an ion must equal the overall charge on the molecule or ion. A formal charge does *not* represent a true charge on an atom in a covalent bond but is simply used to predict the most likely structure when a compound has more than one valid Lewis structure.


To calculate formal charges, we assign electrons in the molecule to individual atoms according to these rules:

- Nonbonding electrons are assigned to the atom on which they are located.
- Bonding electrons are divided equally between the bonded atoms.

For each atom, we then compute a formal charge:

$$\textit{formal charge} = \underset{(\textit{free atom})}{\textit{valence } e^-} - \underset{(\textit{atom in Lewis structure})}{\left(\textit{non} - \textit{bonding } e^- + \frac{\textit{bonding } e^-}{2}\right)} \text{ (atom in Lewis structure)}$$

To illustrate this method, let's calculate the formal charge on the atoms in ammonia (NH_3) whose Lewis electron structure is as follows:



Ammonia

A neutral nitrogen atom has five valence electrons (it is in group 15). From its Lewis electron structure, the nitrogen atom in ammonia has one lone pair and shares three bonding pairs with hydrogen atoms, so nitrogen itself is assigned a total of five electrons [2 nonbonding e^- + (6 bonding e^-/2)]. Substituting into Equation 6.4.1, we obtain

$$\textit{formal charge}\,(N) = 5\ \textit{valence } e^- - \left(2\ \textit{non} - \textit{bonding } e^- + \frac{6\ \textit{bonding } e^-}{2}\right) = 0 \tag{6.4.1}$$

A neutral hydrogen atom has one valence electron. Each hydrogen atom in the molecule shares one pair of bonding electrons and is therefore assigned one electron [0 nonbonding e^- + (2 bonding e^-/2)]. Using Equation 6.4.1 to calculate the formal charge on hydrogen, we obtain

$$\textit{formal charge}\,(H) = 1\ \textit{valence } e^- - \left(0\ \textit{non} - \textit{bonding } e^- + \frac{2\ \textit{bonding } e^-}{2}\right) = 0 \tag{6.4.2}$$

The hydrogen atoms in ammonia have the same number of electrons as neutral hydrogen atoms, and so their formal charge is also zero. Adding together the formal charges should give us the overall charge on the molecule or ion. In this example, the nitrogen and each hydrogen has a formal charge of zero. When summed the overall charge is zero, which is consistent with the overall charge on the NH_3 molecule.

> An atom, molecule, or ion has a formal charge of zero if it has the number of bonds that is typical for that species.

Typically, the structure with the most charges on the atoms closest to zero is the more stable Lewis structure. In cases where there are positive or negative formal charges on various atoms, stable structures generally have negative formal charges on the more electronegative atoms and positive formal charges on the less electronegative atoms. The next example further demonstrates how to calculate formal charges.



Example 6.4.2: The Ammonium Ion

Calculate the formal charges on each atom in the NH_4^+ ion.

Given: chemical species


Asked for: formal charges

Strategy:

Identify the number of valence electrons in each atom in the NH_4^+ ion. Use the Lewis electron structure of NH_4^+ to identify the number of bonding and nonbonding electrons associated with each atom and then use Equation 6.4.1 to calculate the formal charge on each atom.

Solution:

The Lewis electron structure for the NH_4^+ ion is as follows:



The central nitrogen is bonded to four hydrogens. The molecule is surrounded by square brackets. Outside the bracket is where the positive charge is placed.


The nitrogen atom shares four bonding pairs of electrons, and a neutral nitrogen atom has five valence electrons. Using Equation ???, the formal charge on the nitrogen atom is therefore

$$formal\ charge\,(N) = 5 - \left(0 + \frac{8}{2}\right) = 0$$

Each hydrogen atom in has one bonding pair. The formal charge on each hydrogen atom is therefore

$$formal\ charge\,(H) = 1 - \left(0 + \frac{2}{2}\right) = 0$$

The formal charges on the atoms in the NH_4^+ ion are thus




In the Lewis structure, each hydrogen has a zero placed nearby while the nitrogen has a +1 placed nearby.

Adding together the formal charges on the atoms should give us the total charge on the molecule or ion. In this case, the sum of the formal charges is 0 + 1 + 0 + 0 + 0 = +1.

Exercise 6.4.2

Write the formal charges on all atoms in BH_4^-.

Answer



Four hydrogens are bonded to a central boron. Each hydrogen has a zero placed nearby while the boron has a -1. The molecule is surrounded by square brackets. Outside of the brackets is a negative charge.

If an atom in a molecule or ion has the number of bonds that is typical for that atom (e.g., four bonds for carbon), its formal charge is zero.

Using Formal Charges to Distinguish Viable Lewis Structures

6.4: Covalent Bonding- Lewis Structure is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **8.5: Drawing Lewis Structures** is licensed CC BY-NC-SA 3.0.

6.5: Electronegativity and Bond Polarity

Learning Objectives

- To define electronegativity and bond polarity
- To calculate the percent ionic character of a covalent polar bond

The electron pairs shared between two atoms ***are not necessarily shared equally.*** For example, while the bonding electron pair is shared equally in the covalent bond in Cl_2, in $NaCl$ the 3s electron is stripped from the Na atom and is incorporated into the electronic structure of the Cl atom - and the compound is most accurately described as consisting of individual Na^+ and Cl^- ions (ionic bonding). For most covalent substances, their bond character falls **between** these two extremes. As demonstrated below, the **bond polarity** is a useful concept for describing the sharing of electrons between atoms within a covalent bond:

- A ***nonpolar covalent bond*** is one in which the electrons are shared *equally* between two atoms.
- A ***polar covalent bond*** is one in which ***one atom has a greater attraction for the electrons than the other atom***. If this relative attraction is great enough, then the bond is an ***ionic bond.***

Electronegativity

The elements with the highest ionization energies are generally those with the most negative electron affinities, which are located toward the upper right corner of the periodic table. Conversely, the elements with the lowest ionization energies are generally those with the least negative electron affinities and are located in the lower left corner of the periodic table.

Because the tendency of an element to gain or lose electrons is so important in determining its chemistry, various methods have been developed to quantitatively describe this tendency. The most important method uses a measurement called **electronegativity** (represented by the Greek letter *chi*, χ, pronounced “ky” as in “sky”), defined as the *relative* ability of an atom to attract electrons to itself *in a chemical compound*. Elements with high electronegativities tend to acquire electrons in chemical reactions and are found in the upper right corner of the periodic table. Elements with low electronegativities tend to lose electrons in chemical reactions and are found in the lower left corner of the periodic table.

Unlike ionization energy or electron affinity, the electronegativity of an atom is not a simple, fixed property that can be directly measured in a single experiment. In fact, an atom’s electronegativity should depend to some extent on its chemical environment because the properties of an atom are influenced by its neighbors in a chemical compound. Nevertheless, when different methods for measuring the electronegativity of an atom are compared, they all tend to assign similar relative values to a given element. For example, all scales predict that fluorine has the highest electronegativity and cesium the lowest of the stable elements, which suggests that all the methods are measuring the same fundamental property.

> *Electronegativity is defined as the ability of an atom in a particular molecule to attract electrons to itself. The greater the value, the greater the attractiveness for electrons.*

Electronegativity is a function of:

1. the atom's ***ionization energy*** (how strongly the atom holds on to its own electrons) and
2. the atom's ***electron affinity*** (how strongly the atom attracts other electrons).

Both of these are properties of the *isolated* atom. An element will be *highly electronegative* if it has a large (negative) electron affinity and a high ionization energy (always endothermic, or positive for neutral atoms). Thus, it will attract electrons from other atoms and resist having its own electrons attracted away.

The Pauling Electronegativity Scale

The original electronegativity scale, developed in the 1930s by Linus Pauling (1901– 1994) was based on measurements of the strengths of covalent bonds between different elements. Pauling arbitrarily set the electronegativity of fluorine at 4.0 (although today it has been refined to 3.98), thereby creating a scale in which all elements have values between 0 and 4.0.





Figure **6.5.1**: A Plot of Periodic Variation of Electronegativity with Atomic Number for the First Six Rows of the Periodic Table
The main groups 1 and 2 are purple, the main groups 13 through 18 are green, the transition metals are red, and the lanthanides are blue.

Periodic variations in Pauling's electronegativity values are illustrated in Figures **6.5.1** and **6.5.2**. If we ignore the inert gases and elements for which no stable isotopes are known, we see that fluorine ($\chi = 3.98$) is the most electronegative element and cesium is the least electronegative nonradioactive element ($\chi = 0.79$). Because electronegativities generally increase diagonally from the lower left to the upper right of the periodic table, elements lying on diagonal lines running from upper left to lower right tend to have comparable values (e.g., O and Cl and N, S, and Br).




The s blocks are purple, the p blocks are green, the d blocks are red, and the f blocks are blue. Electronegativity increase from bottom to top and left to right.

Figure* 6.5.2*: *Pauling Electronegativity Values of the s-, p-, d-, and f-Block Elements. Values for most of the actinides are approximate. Elements for which no data are available are shown in gray. Source: Data from L. Pauling, The Nature of the Chemical Bond, 3rd ed. (1960).*

Linus Pauling (1901-1994)

When he was nine, Pauling's father died, and his mother tried to convince him to quit school to support the family. He did not quit school, but was later denied a high school degree, and had to work several jobs to put himself through college. Pauling would go on to become one of the most influential chemists of the century if not all time. He won two Nobel Prizes, one for chemistry in 1954 and one for peace in 1962.



Pauling's method is limited by the fact that many elements do not form stable covalent compounds with other elements; hence their electronegativities cannot be measured by his method. Other definitions have since been developed that address this problem, e.g., the Mulliken, Allred-Rochow, and Allen electronegativity scales. The Mulliken electronegativity of an element is the average of its first ionization energy and the absolute value of its electron affinity, showing the relationship between electronegativity and these other periodic properties.



Electronegativity Differences between Metals and Nonmetals

An element's electronegativity provides us with a single value that we can use to characterize the chemistry of an element. Elements with a high electronegativity ($\chi \geq 2.2$ in Figure **6.5.2**) have very negative affinities and large ionization potentials, so they are generally nonmetals and electrical insulators that tend to gain electrons in chemical reactions (i.e., they are *oxidants*). In contrast, elements with a low electronegativity ($\chi \leq 1.8$) have electron affinities that have either positive or small negative values and small ionization potentials, so they are generally metals and good electrical conductors that tend to lose their valence electrons in chemical reactions (i.e., they are *reductants*). In between the metals and nonmetals, along the heavy diagonal line running from B to At is a group of elements with intermediate electronegativities ($\chi \sim 2.0$). These are the **metalloids** (or semimetals), elements that have some of the chemical properties of both nonmetals and metals. The distinction between metals and nonmetals is one of the most fundamental we can make in categorizing the elements and predicting their chemical behavior. Figure **6.5.3** shows the strong correlation between electronegativity values, metallic versus nonmetallic character, and location in the periodic table.




Figure **6.5.3**: Three-Dimensional Plots Demonstrating the Relationship between Electronegativity and the Metallic/Nonmetallic Character of the Elements. (a) A plot of electrical resistivity (measured resistivity to electron flow) at or near room temperature shows that substances with high resistivity (little to no measured electron flow) are electrical insulators, whereas substances with low resistivity (high measured electron flow) are metals. (b) A plot of Pauling electronegativities for a like set of elements shows that high electronegativity values (≥ about 2.2) correlate with high electrical resistivities (insulators). Low electronegativity values (≤ about 2.2) correlate with low resistivities (metals). Because electrical resistivity is typically measured only for solids and liquids, the gaseous elements do not appear in part (a).

Metals are blue, semimetals are yellow, nonmetals are gray, gaseous at 20 degrees C are gray with dashed lines.

Electronegativity values *increase* from lower left to upper right in the periodic table.

The rules for assigning oxidation states(opens in new window) are based on the relative electronegativities of the elements; the more electronegative element in a binary compound is assigned a negative oxidation state. As we shall see, electronegativity values are also used to predict bond energies, bond polarities, and the kinds of reactions that compounds undergo.

✔ Example 6.5.1: Increasing Electronegativity

On the basis of their positions in the periodic table, arrange Cl, Se, Si, and Sr in order of increasing electronegativity and classify each as a metal, a nonmetal, or a metalloid.

Given: four elements

Asked for: order by increasing electronegativity and classification

Strategy:

A. Locate the elements in the periodic table. From their diagonal positions from lower left to upper right, predict their relative electronegativities.
B. Arrange the elements in order of increasing electronegativity.
C. Classify each element as a metal, a nonmetal, or a metalloid according to its location about the diagonal belt of metalloids running from B to At.

Solution:

A Electronegativity increases from lower left to upper right in the periodic table (Figure 8.4.2). Because Sr lies far to the left of the other elements given, we can predict that it will have the lowest electronegativity. Because Cl lies above and to the right of Se, we can predict that $\chi_{Cl} > \chi_{Se}$. Because Si is located farther from the upper right corner than Se or Cl, its electronegativity should be lower than those of Se and Cl but greater than that of Sr. **B** The overall order is therefore $\chi_{Sr} < \chi_{Si} < \chi_{Se} < \chi_{Cl}$.

C To classify the elements, we note that Sr lies well to the left of the diagonal belt of metalloids running from B to At; while Se and Cl lie to the right and Si lies in the middle. We can predict that Sr is a metal, Si is a metalloid, and Se and Cl are nonmetals.

? Exercise 6.5.1

On the basis of their positions in the periodic table, arrange Ge, N, O, Rb, and Zr in order of increasing electronegativity and classify each as a metal, a nonmetal, or a metalloid.

Answer

Rb < Zr < Ge < N < O; metals (Rb, Zr); metalloid (Ge); nonmetal (N, O)

Percent Ionic Character of a Covalent polar bond

The two idealized extremes of chemical bonding: (1) ionic bonding—in which one or more electrons are transferred completely from one atom to another, and the resulting ions are held together by purely electrostatic forces—and (2) covalent bonding, in which electrons are shared equally between two atoms. Most compounds, however, have polar covalent bonds, which means that electrons are shared unequally between the bonded atoms. Figure **6.5.4** compares the electron distribution in a polar covalent bond with those in an ideally covalent and an ideally ionic bond. Recall that a lowercase Greek delta (δ) is used to indicate that a bonded atom possesses a partial positive charge, indicated by δ^+, or a partial negative charge, indicated by δ^-, and a bond between two atoms that possess partial charges is a polar bond.




Figure **6.5.4**: The Electron Distribution in a Nonpolar Covalent Bond, a Polar Covalent Bond, and an Ionic Bond Using Lewis Electron Structures. In a purely covalent bond (a), the bonding electrons are shared equally between the atoms. In a purely ionic bond (c), an electron has been transferred completely from one atom to the other. A polar covalent bond (b) is intermediate between the two extremes: the bonding electrons are shared unequally between the two atoms, and the electron distribution is asymmetrical with the electron density being greater around the more electronegative atom. Electron-rich (negatively charged) regions are shown in blue; electron-poor (positively charged) regions are shown in red.

Bond Polarity

The polarity of a bond—the extent to which it is polar—is determined largely by the relative electronegativities of the bonded atoms. Electronegativity (χ) was defined as the ability of an atom in a molecule or an ion to attract electrons to itself. Thus there is a direct correlation between electronegativity and bond polarity. A bond is *nonpolar* if the bonded atoms have equal electronegativities. If the electronegativities of the bonded atoms are not equal, however, the bond is *polarized* toward the more electronegative atom. A bond in which the electronegativity of B (χ_B) is greater than the electronegativity of A (χ_A), for example, is indicated with the partial negative charge on the more electronegative atom:

$$\underset{\delta^+}{\underset{\textit{less electronegative}}{A}} - \underset{\delta^-}{\underset{\textit{more electronegative}}{B}} \tag{6.5.1}$$

One way of estimating the ionic character of a bond—that is, the magnitude of the charge separation in a polar covalent bond—is to calculate the difference in electronegativity between the two atoms: $\Delta\chi = \chi_B - \chi_A$.

To predict the polarity of the bonds in Cl_2, HCl, and NaCl, for example, we look at the electronegativities of the relevant atoms: χ_{Cl} = 3.16, χ_H = 2.20, and χ_{Na} = 0.93. Cl_2 must be nonpolar because the electronegativity difference ($\Delta\chi$) is zero; hence the two chlorine atoms share the bonding electrons equally. In NaCl, $\Delta\chi$ is 2.23. This high value is typical of an ionic compound ($\Delta\chi \geq \approx 1.5$) and means that the valence electron of sodium has been completely transferred to chlorine to form Na^+ and Cl^- ions. In HCl, however, $\Delta\chi$ is only 0.96. The bonding electrons are more strongly attracted to the more electronegative chlorine atom, and so the charge distribution is

$$\overset{\delta+}{H} - \overset{\delta-}{Cl}$$

Remember that electronegativities are difficult to measure precisely and different definitions produce slightly different numbers. In practice, the polarity of a bond is usually estimated rather than calculated.

> Bond polarity and ionic character **increase** with an increasing difference in electronegativity.

As with bond energies, the electronegativity of an atom depends to some extent on its chemical environment. It is therefore unlikely that the reported electronegativities of a chlorine atom in NaCl, Cl_2, ClF_5, and $HClO_4$ would be exactly the same.

Dipole Moments

The asymmetrical charge distribution in a polar substance such as HCl produces a **dipole moment** where Qr in meters (m). is abbreviated by the Greek letter mu (μ). The dipole moment is defined as the product of the partial charge Q on the bonded atoms and the distance r between the partial charges:

$$\mu = Qr \tag{6.5.2}$$

where Q is measured in coulombs (C) and r in meters. The unit for dipole moments is the debye (D):

$$1\ D = 3.3356 \times 10^{-30}\ C \cdot m \tag{6.5.3}$$

When a molecule with a dipole moment is placed in an electric field, it tends to orient itself with the electric field because of its asymmetrical charge distribution (Figure **6.5.4**).




Figure **6.5.5**: Molecules That Possess a Dipole Moment Partially Align Themselves with an Applied Electric Field. In the absence of a field (a), the HCl molecules are randomly oriented. When an electric field is applied (b), the molecules tend to align themselves with the field, such that the positive end of the molecular dipole points toward the negative terminal and vice versa.

We can measure the partial charges on the atoms in a molecule such as HCl using Equation 6.5.2. If the bonding in HCl were purely ionic, an electron would be transferred from H to Cl, so there would be a full +1 charge on the H atom and a full −1 charge on the Cl atom. The dipole moment of HCl is 1.109 D, as determined by measuring the extent of its alignment in an electric field, and the reported gas-phase H–Cl distance is 127.5 pm. Hence the charge on each atom is

$$Q = \frac{\mu}{r} = 1.109\ \cancel{D}\left(\frac{3.3356 \times 10^{-30}\ C \cdot \cancel{m}}{1\ \cancel{D}}\right)\left(\frac{1}{127.8\ \cancel{pm}}\right)\left(\frac{1\ \cancel{pm}}{10^{-12}\ \cancel{m}}\right) = 2.901 \times 10^{-20}\ C \tag{6.5.4}$$

By dividing this calculated value by the charge on a single electron (1.6022×10^{-19} C), we find that the electron distribution in HCl is asymmetric and that effectively it appears that there is a net negative charge on the Cl of about −0.18, effectively corresponding to about 0.18 e^-. This certainly does not mean that there is a fraction of an electron on the Cl atom, but that the distribution of electron probability favors the Cl atom side of the molecule by about this amount.

$$\frac{2.901 \times 10^{-20} \cancel{C}}{1.6022 \times 10^{-19} \cancel{C}} = 0.1811\ e^- \tag{6.5.5}$$

To form a neutral compound, the charge on the H atom must be equal but opposite. Thus the measured dipole moment of HCl indicates that the H–Cl bond has approximately 18% ionic character (0.1811 × 100), or 82% covalent character. Instead of writing HCl as

$$\overset{\delta+}{H} - \overset{\delta-}{Cl}$$

we can therefore indicate the charge separation quantitatively as

$$\overset{0.18\delta+}{H} - \overset{0.18\delta-}{Cl}$$

Our calculated results are in agreement with the electronegativity difference between hydrogen and chlorine $\chi_H = 2.20$; $\chi_{Cl} = 3.16$, $\chi_{Cl} - \chi_H = 0.96$), a value well within the range for polar covalent bonds. We indicate the dipole moment by writing an arrow above the molecule. Mathematically, dipole moments are vectors, and they possess both a magnitude and a direction. The dipole moment of a molecule is the vector sum of the dipoles of the individual bonds. In HCl, for example, the dipole moment is indicated as follows:



The arrow shows the direction of electron flow by pointing toward the more electronegative atom.

The charge on the atoms of many substances in the gas phase can be calculated using measured dipole moments and bond distances. Figure **6.5.6** shows a plot of the percent ionic character versus the difference in electronegativity of the bonded atoms for several substances. According to the graph, the bonding in species such as NaCl(g) and CsF(g) is substantially less than 100% ionic in character. As the gas condenses into a solid, however, dipole–dipole interactions between polarized species increase the charge separations. In the crystal, therefore, an electron is transferred from the metal to the nonmetal, and these substances behave like classic ionic compounds. The data in Figure **6.5.6** show that diatomic species with an electronegativity difference of less than 1.5 are less than 50% ionic in character, which is consistent with our earlier description of these species as containing polar covalent bonds. The use of dipole moments to determine the ionic character of a polar bond is illustrated in Example **6.5.2**.




Figure **6.5.6**: A Plot of the Percent Ionic Character of a Bond as Determined from Measured Dipole Moments versus the Difference in Electronegativity of the Bonded Atoms.In the gas phase, even CsF, which has the largest possible difference in electronegativity between atoms, is not 100% ionic. Solid CsF, however, is best viewed as 100% ionic because of the additional electrostatic interactions in the lattice.

Example 6.5.2

In the gas phase, NaCl has a dipole moment of 9.001 D and an Na–Cl distance of 236.1 pm. Calculate the percent ionic character in NaCl.

Given: chemical species, dipole moment, and internuclear distance

Asked for: percent ionic character

Strategy:

A Compute the charge on each atom using the information given and Equation 6.5.2.

B Find the percent ionic character from the ratio of the actual charge to the charge of a single electron.

Solution:

A The charge on each atom is given by

$$Q = \frac{\mu}{r}$$

$$= 9.001 \cancel{D} \left(\frac{3.3356 \times 10^{-30}\ C \cdot \cancel{m}}{1\ \cancel{D}} \right) \left(\frac{1}{236.1\ \cancel{pm}} \right) \left(\frac{1\ \cancel{pm}}{10^{-12}\ \cancel{m}} \right) = 1.272 \times 10^{-19}\ C$$

Thus NaCl behaves as if it had charges of 1.272×10^{-19} C on each atom separated by 236.1 pm.

B The percent ionic character is given by the ratio of the actual charge to the charge of a single electron (the charge expected for the complete transfer of one electron):

$$\%\ ionic\ character = \left(\frac{1.272 \times 10^{-19}\ \cancel{C}}{1.6022 \times 10^{-19}\ \cancel{C}} \right) (100) = 79.39\% \simeq 79\%$$

? Exercise 6.5.2

In the gas phase, silver chloride (AgCl) has a dipole moment of 6.08 D and an Ag–Cl distance of 228.1 pm. What is the percent ionic character in silver chloride?

Answer

55.5%

Summary

Bond polarity and ionic character increase with an increasing difference in electronegativity. The **electronegativity (χ)** of an element is the relative ability of an atom to attract electrons to itself in a chemical compound and increases diagonally from the lower left of the periodic table to the upper right. The Pauling electronegativity scale is based on measurements of the strengths of covalent bonds between different atoms, whereas the Mulliken electronegativity of an element is the average of its first ionization energy and the absolute value of its electron affinity. Elements with a high electronegativity are generally nonmetals and electrical insulators and tend to behave as oxidants in chemical reactions. Conversely, elements with a low electronegativity are generally metals and good electrical conductors and tend to behave as reductants in chemical reactions.

Compounds with **polar covalent bonds** have electrons that are shared unequally between the bonded atoms. The polarity of such a bond is determined largely by the relative electronegativites of the bonded atoms. The asymmetrical charge distribution in a polar substance produces a **dipole moment**, which is the product of the partial charges on the bonded atoms and the distance between them.

6.5: Electronegativity and Bond Polarity is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **8.4: Bond Polarity and Electronegativity** is licensed CC BY-NC-SA 3.0.

CHAPTER OVERVIEW

7: Chemical Kinetics

Template:HideTOC

7.1: Rate of a Chemical Reaction

7.2: The Rate Law- The Effect of Concentration on Reaction Rate

---

7: Chemical Kinetics is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

7.1: Rate of a Chemical Reaction

Learning Objectives

- To determine the reaction rate of a reaction.

Reaction rates are usually expressed as the concentration of reactant consumed or the concentration of product formed per unit time. The units are thus moles per liter per unit time, written as M/s, M/min, or M/h. To measure reaction rates, chemists initiate the reaction, measure the concentration of the reactant or product at different times as the reaction progresses, perhaps plot the concentration as a function of time on a graph, and then calculate the change in the concentration per unit time.




Figure **7.1.1**: The Progress of a Simple Reaction (A → B). The mixture initially contains only A molecules (purple). Over time, the number of A molecules decreases and more B molecules (green) are formed (top). The graph shows the change in the number of A and B molecules in the reaction as a function of time over a 1 min period (bottom).

The progress of a simple reaction (A → B) is shown in Figure **7.1.1**; the beakers are snapshots of the composition of the solution at 10 s intervals. The number of molecules of reactant (A) and product (B) are plotted as a function of time in the graph. Each point in the graph corresponds to one beaker in Figure **7.1.1**. The reaction rate is the change in the concentration of either the reactant or the product over a period of time. The concentration of A decreases with time, while the concentration of B increases with time.

$$\text{rate} = \frac{\Delta[\text{B}]}{\Delta t} = -\frac{\Delta[\text{A}]}{\Delta t} \tag{7.1.1}$$

Square brackets indicate molar concentrations, and the capital Greek delta (Δ) means “change in.” Because chemists follow the convention of expressing all reaction rates as positive numbers, however, a negative sign is inserted in front of Δ[A]/Δt to convert that expression to a positive number. The reaction rate calculated for the reaction A → B using Equation 7.1.1 is different for each interval (this is not true for every reaction, as shown below). A greater change occurs in [A] and [B] during the first 10 s interval, for example, than during the last, meaning that the reaction rate is greatest at first.

> *Reaction rates generally decrease with time as reactant concentrations decrease.*



A Video Discussing Average Reaction Rates. Video Link: Introduction to Chemical Reaction Kinetics(opens in new window) [youtu.be] (opens in new window)

Determining the Reaction Rate of Hydrolysis of Aspirin

We can use Equation 7.1.1 to determine the reaction rate of hydrolysis of aspirin, probably the most commonly used drug in the world (more than 25,000,000 kg are produced annually worldwide). Aspirin (acetylsalicylic acid) reacts with water (such as water in body fluids) to give salicylic acid and acetic acid, as shown in Figure **7.1.2**.




Figure **7.1.2**: Hydrolysis of Aspirin reaction.

Because salicylic acid is the actual substance that relieves pain and reduces fever and inflammation, a great deal of research has focused on understanding this reaction and the factors that affect its rate. Data for the hydrolysis of a sample of aspirin are in Table **7.1.1** and are shown in the graph in Figure **7.1.3**.

Table **7.1.1**: Data for Aspirin Hydrolysis in Aqueous Solution at pH 7.0 and 37°C*

Time (h)	[Aspirin] (M)	[Salicylic Acid] (M)
0	5.55×10^{-3}	0
2.0	5.51×10^{-3}	0.040×10^{-3}
5.0	5.45×10^{-3}	0.10×10^{-3}
10	5.35×10^{-3}	0.20×10^{-3}
20	5.15×10^{-3}	0.40×10^{-3}
30	4.96×10^{-3}	0.59×10^{-3}
40	4.78×10^{-3}	0.77×10^{-3}
50	4.61×10^{-3}	0.94×10^{-3}
100	3.83×10^{-3}	1.72×10^{-3}
200	2.64×10^{-3}	2.91×10^{-3}
300	1.82×10^{-3}	3.73×10^{-3}

*The reaction at pH 7.0 is very slow. It is much faster under acidic conditions, such as those found in the stomach.

The data in Table 7.1.1 were obtained by removing samples of the reaction mixture at the indicated times and analyzing them for the concentrations of the reactant (aspirin) and one of the products (salicylic acid).




Figure 7.1.3: The Hydrolysis of Aspirin. This graph shows the concentrations of aspirin and salicylic acid as a function of time, based on the hydrolysis data in Table 14.1. The time dependence of the concentration of the other product, acetate, is not shown, but based on the stoichiometry of the reaction, it is identical to the data for salicylic acid.

Graph of concentration against time in hours. The purple line is aspirin. The green line is salicylic acid.

The **average reaction rate** for a given time interval can be calculated from the concentrations of either the reactant or one of the products at the beginning of the interval (time = t_0) and at the end of the interval (t_1). Using salicylic acid, the reaction rate for the interval between t = 0 h and t = 2.0 h (recall that change is always calculated as final minus initial) is calculated as follows:

$$\begin{aligned}\text{rate}_{(t=0-2.0\text{ h})} &= \frac{[\text{salicyclic acid}]_2 - [\text{salicyclic acid}]_0}{2.0\text{ h} - 0\text{ h}} \\ &= \frac{0.040 \times 10^{-3}\text{ M} - 0\text{ M}}{2.0\text{ h}} = 2.0 \times 10^{-5}\text{ M/h}\end{aligned}$$

The reaction rate can also be calculated from the concentrations of aspirin at the beginning and the end of the same interval, remembering to insert a negative sign, because its concentration decreases:

$$\begin{aligned}\text{rate}_{(t=0-2.0\text{ h})} &= -\frac{[\text{aspirin}]_2 - [\text{aspirin}]_0}{2.0\text{ h} - 0\text{ h}} \\ &= -\frac{(5.51 \times 10^{-3}\text{ M}) - (5.55 \times 10^{-3}\text{ M})}{2.0\text{ h}} \\ &= 2 \times 10^{-5}\text{ M/h}\end{aligned}$$

If the reaction rate is calculated during the last interval given in Table 7.1.1(the interval between 200 h and 300 h after the start of the reaction), the reaction rate is significantly slower than it was during the first interval (t = 0–2.0 h):

$$\begin{aligned}\text{rate}_{(t=200-300\text{h})} &= \frac{[\text{salicyclic acid}]_{300} - [\text{salicyclic acid}]_{200}}{300\text{ h} - 200\text{ h}} \\ &= -\frac{(3.73 \times 10^{-3}\text{ M}) - (2.91 \times 10^{-3}\text{ M})}{100\text{ h}} \\ &= 8.2 \times 10^{-6}\text{ M/h}\end{aligned}$$

Calculating the Reaction Rate of Fermentation of Sucrose

In the preceding example, the stoichiometric coefficients in the balanced chemical equation are the same for all reactants and products; that is, the reactants and products all have the coefficient 1. Consider a reaction in which the coefficients are not all the same, the fermentation of sucrose to ethanol and carbon dioxide:

$$\underset{\text{sucrose}}{C_{12}H_{22}O_{11}(aq)} + H_2O(l) \rightarrow 4C_2H_5OH(aq) + 4CO_2(g) \tag{7.1.2}$$

The coefficients indicate that the reaction produces four molecules of ethanol and four molecules of carbon dioxide for every one molecule of sucrose consumed. As before, the reaction rate can be found from the change in the concentration of any reactant or product. In this particular case, however, a chemist would probably use the concentration of either sucrose or ethanol because gases are usually measured as volumes and, as explained in Chapter 10, the volume of CO_2 gas formed depends on the total volume of the solution being studied and the solubility of the gas in the solution, not just the concentration of sucrose. The coefficients in the balanced chemical equation tell us that the reaction rate at which ethanol is formed is always four times faster than the reaction rate at which sucrose is consumed:

$$\frac{\Delta[C_2H_5OH]}{\Delta t} = -\frac{4\Delta[\text{sucrose}]}{\Delta t} \tag{7.1.3}$$

The concentration of the reactant—in this case sucrose—*decreases* with time, so the value of Δ[sucrose] is negative. Consequently, a minus sign is inserted in front of Δ[sucrose] in Equation 7.1.3 so the rate of change of the sucrose concentration is expressed as a positive value. Conversely, the ethanol concentration *increases* with time, so its rate of change is automatically expressed as a positive value.

Often the reaction rate is expressed in terms of the reactant or product with the smallest coefficient in the balanced chemical equation. The smallest coefficient in the sucrose fermentation reaction (Equation 7.1.2) corresponds to sucrose, so the reaction rate is generally defined as follows:

$$\text{rate} = -\frac{\Delta[\text{sucrose}]}{\Delta t} = \frac{1}{4}\left(\frac{\Delta[C_2H_5OH]}{\Delta t}\right) \tag{7.1.4}$$

Example 7.1.1: Decomposition Reaction I

Consider the thermal decomposition of gaseous N_2O_5 to NO_2 and O_2 via the following equation:

$$2N_2O_5(g) \xrightarrow{\Delta} 4NO_2(g) + O_2(g)$$

Write expressions for the reaction rate in terms of the rates of change in the concentrations of the reactant and each product with time.

Given: balanced chemical equation

Asked for: reaction rate expressions

Strategy:

A. Choose the species in the equation that has the smallest coefficient. Then write an expression for the rate of change of that species with time.

B. For the remaining species in the equation, use molar ratios to obtain equivalent expressions for the reaction rate.

Solution

A Because O_2 has the smallest coefficient in the balanced chemical equation for the reaction, define the reaction rate as the rate of change in the concentration of O_2 and write that expression.

B The balanced chemical equation shows that 2 mol of N_2O_5 must decompose for each 1 mol of O_2 produced and that 4 mol of NO_2 are produced for every 1 mol of O_2 produced. The molar ratios of O_2 to N_2O_5 and to NO_2 are thus 1:2 and 1:4, respectively. This means that the rate of change of $[N_2O_5]$ and $[NO_2]$ must be divided by its stoichiometric coefficient to obtain equivalent expressions for the reaction rate. For example, because NO_2 is produced at four times the rate of O_2, the rate of production of NO_2 is divided by 4. The reaction rate expressions are as follows:

$$\text{rate} = \frac{\Delta[O_2]}{\Delta t} = \frac{\Delta[NO_2]}{4\Delta t} = -\frac{\Delta[N_2O_5]}{2\Delta t}$$

Exercise 7.1.1: Contact Process I

The contact process is used in the manufacture of sulfuric acid. A key step in this process is the reaction of SO_2 with O_2 to produce SO_3.

$$2SO_{2(g)} + O_{2(g)} \rightarrow 2SO_{3(g)}$$

Write expressions for the reaction rate in terms of the rate of change of the concentration of each species.

Answer

$$\text{rate} = -\frac{\Delta[O_2]}{\Delta t} = -\frac{\Delta[SO_2]}{2\Delta t} = \frac{\Delta[SO_3]}{2\Delta t}$$

Instantaneous Rates of Reaction

The **instantaneous rate** of a reaction is the reaction rate at any given point in time. As the period of time used to calculate an average rate of a reaction becomes shorter and shorter, the average rate approaches the instantaneous rate. Comparing this to calculus, the instantaneous rate of a reaction at a given time corresponds to the slope of a line tangent to the concentration-versus-time curve at that point—that is, the derivative of concentration with respect to time.

The distinction between the instantaneous and average rates of a reaction is similar to the distinction between the actual speed of a car at any given time on a trip and the average speed of the car for the entire trip. Although the car may travel for an extended period at 65 mph on an interstate highway during a long trip, there may be times when it travels only 25 mph in construction zones or 0 mph if you stop for meals or gas. The average speed on the trip may be only 50 mph, whereas the instantaneous speed on the interstate at a given moment may be 65 mph. Whether the car can be stopped in time to avoid an accident depends on its instantaneous speed, not its average speed. There are important differences between the speed of a car during a trip and the speed of a chemical reaction, however. The speed of a car may vary unpredictably over the length of a trip, and the initial part of a trip is often one of the slowest. In a chemical reaction, the initial interval typically has the fastest rate (though this is not always the case), and the reaction rate generally changes smoothly over time.

> *Chemical kinetics generally focuses on one particular instantaneous rate, which is the initial reaction rate, t = 0. Initial rates are determined by measuring the reaction rate at various times and then extrapolating a plot of rate versus time to t = 0.*



Example 7.1.2: Decomposition Reaction II

Using the reaction shown in Example 7.1.1, calculate the reaction rate from the following data taken at 56°C:

$$2N_2O_{5(g)} \rightarrow 4NO_{2(g)} + O_{2(g)}$$

calculate the reaction rate from the following data taken at 56°C:

Time (s)	$[N_2O_5]$ (M)	$[NO_2]$ (M)	$[O_2]$ (M)
240	0.0388	0.0314	0.00792
600	0.0197	0.0699	0.0175

Given: balanced chemical equation and concentrations at specific times

Asked for: reaction rate

Strategy:

A. Using the equations in Example **7.1.1**, subtract the initial concentration of a species from its final concentration and substitute that value into the equation for that species.

B. Substitute the value for the time interval into the equation. Make sure your units are consistent.

Solution

A Calculate the reaction rate in the interval between t_1 = 240 s and t_2 = 600 s. From Example **7.1.1**, the reaction rate can be evaluated using any of three expressions:

$$\text{rate} = \frac{\Delta[O_2]}{\Delta t} = \frac{\Delta[NO_2]}{4\Delta t} = -\frac{\Delta[N_2O_5]}{2\Delta t}$$

Subtracting the initial concentration from the final concentration of N_2O_5 and inserting the corresponding time interval into the rate expression for N_2O_5,

$$\text{rate} = -\frac{\Delta[N_2O_5]}{2\Delta t} = -\frac{[N_2O_5]_{600} - [N_2O_5]_{240}}{2(600\text{ s} - 240\text{ s})}$$

B Substituting actual values into the expression,

$$\text{rate} = -\frac{0.0197\text{ M} - 0.0388\text{ M}}{2(360\text{ s})} = 2.65 \times 10^{-5}\text{ M/s}$$

Similarly, NO_2 can be used to calculate the reaction rate:

$$\text{rate} = \frac{\Delta[NO_2]}{4\Delta t} = \frac{[NO_2]_{600} - [NO_2]_{240}}{4(600\text{ s} - 240\text{ s})} = \frac{0.0699\text{ M} - 0.0314\text{ M}}{4(360\text{ s})} = 2.67 \times 10^{-5}\text{ M/s}$$

Allowing for experimental error, this is the same rate obtained using the data for N_2O_5. The data for O_2 can also be used:

$$\text{rate} = \frac{\Delta[O_2]}{\Delta t} = \frac{[O_2]_{600} - [O_2]_{240}}{600\text{ s} - 240\text{ s}} = \frac{0.0175\text{ M} - 0.00792\text{ M}}{360\text{ s}} = 2.66 \times 10^{-5}\text{ M/s}$$

Again, this is the same value obtained from the N_2O_5 and NO_2 data. Thus, the reaction rate does not depend on which reactant or product is used to measure it.

? Exercise 7.1.2: Contact Process II

Using the data in the following table, calculate the reaction rate of $SO_2(g)$ with $O_2(g)$ to give $SO_3(g)$.

$$2SO_{2(g)} + O_{2(g)} \rightarrow 2SO_{3(g)}$$

calculate the reaction rate of $SO_2(g)$ with $O_2(g)$ to give $SO_3(g)$.

Time (s)	$[SO_2]$ (M)	$[O_2]$ (M)	$[SO_3]$ (M)
300	0.0270	0.0500	0.0072
720	0.0194	0.0462	0.0148

Answer:

9.0×10^{-6} M/s

Summary

In this Module, the quantitative determination of a reaction rate is demonstrated. Reaction rates can be determined over particular time intervals or at a given point in time. A rate law describes the relationship between reactant rates and reactant concentrations. Reaction rates are reported as either the average rate over a period of time or as the instantaneous rate at a single time. Reaction rates can be determined over particular time intervals or at a given point in time.

- General definition of rate for A → B:

$$\text{rate} = \frac{\Delta[\text{B}]}{\Delta t} = -\frac{\Delta[\text{A}]}{\Delta t}$$

7.1: Rate of a Chemical Reaction is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **14.2: Reaction Rates** is licensed CC BY-NC-SA 3.0.

7.2: The Rate Law- The Effect of Concentration on Reaction Rate

Learning Objectives

- To understand the meaning of the rate law.

The factors that affect the reaction rate of a chemical reaction, which may determine whether a desired product is formed. In this section, we will show you how to quantitatively determine the reaction rate.

Rate Laws

Typically, reaction rates decrease with time because reactant concentrations decrease as reactants are converted to products. Reaction rates generally increase when reactant concentrations are increased. This section examines mathematical expressions called **rate laws**, which describe the relationships between reactant rates and reactant concentrations. Rate laws are mathematical descriptions of experimentally verifiable data.

Rate laws may be written from either of two different but related perspectives. A **differential rate law** expresses the reaction rate in terms of changes in the concentration of one or more reactants (Δ[R]) over a specific time interval (Δt). In contrast, an **integrated rate law** describes the reaction rate in terms of the initial concentration ($[R]_0$) and the measured concentration of one or more reactants ([R]) after a given amount of time (t); integrated rate laws are discussed in more detail later. The integrated rate law is derived by using calculus to integrate the differential rate law. Whether using a differential rate law or integrated rate law, always make sure that the rate law gives the proper units for the reaction rate, usually moles per liter per second (M/s).

Reaction Orders

For a reaction with the general equation:

$$aA + bB \rightarrow cC + dD \tag{7.2.1}$$

the experimentally determined rate law usually has the following form:

$$\text{rate} = k[A]^m[B]^n \tag{7.2.2}$$


The proportionality constant (k) is called the **rate constant**, and its value is characteristic of the reaction and the reaction conditions. A given reaction has a particular rate constant value under a given set of conditions, such as temperature, pressure, and solvent; varying the temperature or the solvent usually changes the value of the rate constant. The numerical value of k, however, does not change as the reaction progresses under a given set of conditions.

> *Under a given set of conditions, the value of the rate constant does **not** change as the reaction progresses.*

The reaction rate thus depends on the rate constant for the given set of reaction conditions and the concentration of A and B raised to the powers m and n, respectively. The values of m and n are derived from experimental measurements of the changes in reactant concentrations over time and indicate the **reaction order**, the degree to which the reaction rate depends on the concentration of each reactant; m and n need not be integers. For example, Equation 7.2.2 tells us that Equation 7.2.1 is m^{th} order in reactant A and n^{th} order in reactant B. It is important to remember that n and m are not related to the stoichiometric coefficients a and b in the balanced chemical equation and must be determined **experimentally**. The overall reaction order is the sum of all the exponents in the rate law: $m + n$.

> *The orders of the reactions (e.g. n and m) are **not** related to the stoichiometric coefficients in the balanced chemical (e.g., a and b).*

To illustrate how chemists interpret a differential rate law, consider the experimentally derived rate law for the hydrolysis of *t*-butyl bromide in 70% aqueous acetone.



t-butanol methyl bromide

This reaction produces *t*-butanol according to the following equation:

$$(CH_3)_3CBr_{(soln)} + H_2O_{(soln)} \rightarrow (CH_3)_3COH_{(soln)} + HBr_{(soln)} \tag{7.2.3}$$

Combining the rate expression in Equation 7.2.2 with the definition of average reaction rate

$$\text{rate} = -\frac{\Delta[\text{A}]}{\Delta t}$$

gives a general expression for the differential rate law:

$$\text{rate} = -\frac{\Delta[\text{A}]}{\Delta t} = k[\text{A}]^m[\text{B}]^n \tag{7.2.4}$$

Inserting the identities of the reactants into Equation 7.2.4 gives the following expression for the differential rate law for the reaction:

$$\text{rate} = -\frac{\Delta[(\text{CH}_3)_3\text{CBr}]}{\Delta t} = k[(\text{CH}_3)_3\text{CBr}]^m[\text{H}_2\text{O}]^n \tag{7.2.5}$$

Experiments to determine the rate law for the hydrolysis of *t*-butyl bromide show that the reaction rate is directly proportional to the concentration of $(CH_3)_3CBr$ but is independent of the concentration of water. Therefore, m and n in Equation 7.2.4 are 1 and 0, respectively, and,

$$\text{rate} = k[(CH_3)_3CBr]^1[H_2O]^0 = k[(CH_3)_3CBr] \tag{7.2.6}$$

Because the exponent for the reactant is 1, the reaction is first order in $(CH_3)_3CBr$. It is zeroth order in water because the exponent for $[H_2O]$ is 0. (Recall that anything raised to the zeroth power equals 1.) Thus, the overall reaction order is 1 + 0 = 1. The reaction orders state in practical terms that doubling the concentration of $(CH_3)_3CBr$ doubles the reaction rate of the hydrolysis reaction, halving the concentration of $(CH_3)_3CBr$ halves the reaction rate, and so on. Conversely, increasing or decreasing the concentration of water has no effect on the reaction rate. (Again, when working with rate laws, there is no simple correlation between the stoichiometry of the reaction and the rate law. The values of *k*, *m*, and *n* in the rate law must be determined experimentally.) Experimental data show that *k* has the value 5.15×10^{-4} s^{-1} at 25°C. The rate constant has units of reciprocal seconds (s^{-1}) because the reaction rate is defined in units of concentration per unit time (M/s). The units of a rate constant depend on the rate law for a particular reaction.

Under conditions identical to those for the *t*-butyl bromide reaction, the experimentally derived differential rate law for the hydrolysis of methyl bromide (CH_3Br) is as follows:

$$\text{rate} = -\frac{\Delta[\text{CH}_3\text{Br}]}{\Delta t} = k'[\text{CH}_3\text{Br}] \tag{7.2.7}$$

This reaction also has an overall reaction order of 1, but the rate constant in Equation 7.2.7 is approximately 10^6 times smaller than that for *t*-butyl bromide. Thus, methyl bromide hydrolyzes about 1 million times more slowly than *t*-butyl bromide, and this information tells chemists how the reactions differ on a molecular level.

Frequently, changes in reaction conditions also produce changes in a rate law. In fact, chemists often alter reaction conditions to study the mechanics of a reaction. For example, when *t*-butyl bromide is hydrolyzed in an aqueous acetone solution containing OH^- ions rather than in aqueous acetone alone, the differential rate law for the hydrolysis reaction does not change. In contrast, for methyl bromide, the differential rate law becomes

$$\text{rate} = k''[CH_3Br][OH^-]$$

with an overall reaction order of 2. Although the two reactions proceed similarly in neutral solution, they proceed very differently in the presence of a base, providing clues as to how the reactions differ on a molecular level.

Example 7.2.1: Writing Rate Laws from Reaction Orders

An experiment shows that the reaction of nitrogen dioxide with carbon monoxide:

$$NO_2(g) + CO(g) \longrightarrow NO(g) + CO_2(g)$$

is second order in NO_2 and zero order in CO at 100 °C. What is the rate law for the reaction?

Solution

The reaction will have the form:

$$\text{rate} = k[NO_2]^m[CO]^n$$

The reaction is second order in NO_2; thus $m = 2$. The reaction is zero order in CO; thus $n = 0$. The rate law is:

$$\text{rate} = k[NO_2]^2[CO]^0 = k[NO_2]^2$$

Remember that a number raised to the zero power is equal to 1, thus $[CO]^0 = 1$, which is why we can simply drop the concentration of CO from the rate equation: the rate of reaction is solely dependent on the concentration of NO_2. When we consider rate mechanisms later in this chapter, we will explain how a reactant's concentration can have no effect on a reaction despite being involved in the reaction.

Exercise 7.2.1A

The rate law for the reaction:

$$H_2(g) + 2\,NO(g) \longrightarrow N_2O(g) + H_2O(g)$$

has been experimentally determined to be $rate = k[NO]^2[H_2]$. What are the orders with respect to each reactant, and what is the overall order of the reaction?

Answer

- order in NO = 2
- order in H_2 = 1
- overall order = 3

Exercise 7.2.1B

In a transesterification reaction, a triglyceride reacts with an alcohol to form an ester and glycerol. Many students learn about the reaction between methanol (CH_3OH) and ethyl acetate ($CH_3CH_2OCOCH_3$) as a sample reaction before studying the chemical reactions that produce biodiesel:

$$CH_3OH + CH_3CH_2OCOCH_3 \longrightarrow CH_3OCOCH_3 + CH_3CH_2OH$$

The rate law for the reaction between methanol and ethyl acetate is, under certain conditions, experimentally determined to be:

$$\text{rate} = k[CH_3OH]$$

What is the order of reaction with respect to methanol and ethyl acetate, and what is the overall order of reaction?

Answer

- order in CH_3OH = 1
- order in $CH_3CH_2OCOCH_3$ = 0
- overall order = 1

Example 7.2.2: Differential Rate Laws

Below are three reactions and their experimentally determined differential rate laws. For each reaction, give the units of the rate constant, give the reaction order with respect to each reactant, give the overall reaction order, and predict what happens to the reaction rate when the concentration of the first species in each chemical equation is doubled.

a.
$$2\text{HI}(g) \xrightarrow{\text{Pt}} \text{H}_2(g) + \text{I}_2(g)$$
$$\text{rate} = -\frac{1}{2}\left(\frac{\Delta[\text{HI}]}{\Delta t}\right) = k[\text{HI}]^2$$

b.
$$2\text{N}_2\text{O}(g) \xrightarrow{\Delta} 2\text{N}_2(g) + \text{O}_2(g)$$
$$\text{rate} = -\frac{1}{2}\left(\frac{\Delta[\text{N}_2\text{O}]}{\Delta t}\right) = k$$

c.
$$\text{cyclopropane}(g) \rightarrow \text{propane}(g)$$
$$\text{rate} = -\frac{\Delta[\text{cyclopropane}]}{\Delta t} = k[\text{cyclopropane}]$$

Given: balanced chemical equations and differential rate laws

Asked for: units of rate constant, reaction orders, and effect of doubling reactant concentration

Strategy:

A. Express the reaction rate as moles per liter per second [mol/(L·s), or M/s]. Then determine the units of each chemical species in the rate law. Divide the units for the reaction rate by the units for all species in the rate law to obtain the units for the rate constant.

B. Identify the exponent of each species in the rate law to determine the reaction order with respect to that species. Add all exponents to obtain the overall reaction order.

C. Use the mathematical relationships as expressed in the rate law to determine the effect of doubling the concentration of a single species on the reaction rate.

Solution

1. **A** $[\text{HI}]^2$ will give units of (moles per liter)^2. For the reaction rate to have units of moles per liter per second, the rate constant must have reciprocal units [1/(M·s)]:

$$k\text{M}^2 = \frac{\text{M}}{\text{s}}k = \frac{\text{M/s}}{\text{M}^2} = \frac{1}{\text{M}\cdot\text{s}} = \text{M}^{-1}\cdot\text{s}^{-1}$$

B The exponent in the rate law is 2, so the reaction is second order in HI. Because HI is the only reactant and the only species that appears in the rate law, the reaction is also second order overall.

C If the concentration of HI is doubled, the reaction rate will increase from $k[\text{HI}]_0^2$ to $k(2[\text{HI}])_0^2 = 4k[\text{HI}]_0^2$. The reaction rate will therefore quadruple.

2. **A** Because no concentration term appears in the rate law, the rate constant must have M/s units for the reaction rate to have M/s units.

B The rate law tells us that the reaction rate is constant and independent of the N_2O concentration. That is, the reaction is zeroth order in N_2O and zeroth order overall.

C Because the reaction rate is independent of the N_2O concentration, doubling the concentration will have no effect on the reaction rate.

3. **A** The rate law contains only one concentration term raised to the first power. Hence the rate constant must have units of reciprocal seconds (s^{-1}) to have units of moles per liter per second for the reaction rate: $M\cdot s^{-1} = M/s$.

B The only concentration in the rate law is that of cyclopropane, and its exponent is 1. This means that the reaction is first order in cyclopropane. Cyclopropane is the only species that appears in the rate law, so the reaction is also first order overall.

C Doubling the initial cyclopropane concentration will increase the reaction rate from $k[\text{cyclopropane}]_0$ to $2k[\text{cyclopropane}]_0$. This doubles the reaction rate.

? Exercise 7.2.2

Given the following two reactions and their experimentally determined differential rate laws: determine the units of the rate constant if time is in seconds, determine the reaction order with respect to each reactant, give the overall reaction order, and predict what will happen to the reaction rate when the concentration of the first species in each equation is doubled.

a. $\mathrm{CH_3N{=}NCH_3(g) \rightarrow C_2H_6(g) + N_2(g)} \quad \text{rate} = -\dfrac{\Delta[\mathrm{CH_3N{=}NCH_3}]}{\Delta t}$ (7.2.8)

$= k[\mathrm{CH_3N{=}NCH_3}]$ (7.2.9)

b. $\mathrm{2NO_2(g) + F_2(g) \rightarrow 2NO_2F(g)} \quad \text{rate} = -\dfrac{\Delta[\mathrm{F_2}]}{\Delta t} = -\dfrac{1}{2}\left(\dfrac{\Delta[\mathrm{NO_2}]}{\Delta t}\right)$ (7.2.10)

$= k[\mathrm{NO_2}][\mathrm{F_2}]$ (7.2.11)

Answer a

s^{-1}; first order in $CH_3N{=}NCH_3$; first order overall; doubling $[CH_3N{=}NCH_3]$ will double the reaction rate.

Answer b

$M^{-1}{\cdot}s^{-1}$; first order in NO_2, first order in F_2; second order overall; doubling $[NO_2]$ will double the reaction rate.

Determining the Rate Law of a Reaction

The number of fundamentally different mechanisms (sets of steps in a reaction) is actually rather small compared to the large number of chemical reactions that can occur. Thus understanding **reaction mechanisms** can simplify what might seem to be a confusing variety of chemical reactions. The first step in discovering the reaction mechanism is to determine the reaction's rate law. This can be done by designing experiments that measure the concentration(s) of one or more reactants or products as a function of time. For the reaction $A + B \rightarrow \textit{products}$, for example, we need to determine k and the exponents m and n in the following equation:

$$\text{rate} = k[A]^m[B]^n \tag{7.2.12}$$

To do this, we might keep the initial concentration of B constant while varying the initial concentration of A and calculating the initial reaction rate. This information would permit us to deduce the reaction order with respect to A. Similarly, we could determine the reaction order with respect to B by studying the initial reaction rate when the initial concentration of A is kept constant while the initial concentration of B is varied. In earlier examples, we determined the reaction order with respect to a given reactant by comparing the different rates obtained when only the concentration of the reactant in question was changed. An alternative way of determining reaction orders is to set up a proportion using the rate laws for two different experiments. Rate data for a hypothetical reaction of the type $A + B \rightarrow \textit{products}$ are given in Table **7.2.1**.

Table **7.2.1**: Rate Data for a Hypothetical Reaction of the Form $A + B \rightarrow \textit{products}$

Experiment	[A] (M)	[B] (M)	Initial Rate (M/min)
1	0.50	0.50	8.5×10^{-3}
2	0.75	0.50	19×10^{-3}
3	1.00	0.50	34×10^{-3}
4	0.50	0.75	8.5×10^{-3}
5	0.50	1.00	8.5×10^{-3}

The general rate law for the reaction is given in Equation 7.2.12. We can obtain m or n directly by using a proportion of the rate laws for two experiments in which the concentration of one reactant is the same, such as Experiments 1 and 3 in Table **7.2.3**.

$$\frac{\text{rate}_1}{\text{rate}_3} = \frac{k[\mathrm{A_1}]^m[\mathrm{B_1}]^n}{k[\mathrm{A_3}]^m[\mathrm{B_3}]^n}$$

Inserting the appropriate values from Table **7.2.3**,

$$\frac{8.5 \times 10^{-3}\ \text{M/min}}{34 \times 10^{-3}\ \text{M/min}} = \frac{k[0.50\ \text{M}]^m[0.50\ \text{M}]^n}{k[1.00\ \text{M}]^m[0.50\ \text{M}]^n}$$

Because 1.00 to any power is 1, $[1.00\ \text{M}]^m = 1.00\ \text{M}$. We can cancel like terms to give $0.25 = [0.50]^m$, which can also be written as $1/4 = [1/2]^m$. Thus we can conclude that $m = 2$ and that the reaction is second order in A. By selecting two experiments in which the concentration of B is the same, we were able to solve for m.

Conversely, by selecting two experiments in which the concentration of A is the same (e.g., Experiments 5 and 1), we can solve for n.

$$\frac{\text{rate}_1}{\text{rate}_5} = \frac{k[\text{A}_1]^m[\text{B}_1]^n}{k[\text{A}_5]^m[\text{B}_5]^n}$$

Substituting the appropriate values from Table **7.2.3**,

$$\frac{8.5 \times 10^{-3}\ \text{M/min}}{8.5 \times 10^{-3}\ \text{M/min}} = \frac{k[0.50\ \text{M}]^m[0.50\ \text{M}]^n}{k[0.50\ \text{M}]^m[1.00\ \text{M}]^n}$$

Canceling leaves $1.0 = [0.50]^n$, which gives $\boldsymbol{n = 0}$; that is, the reaction is zeroth order in $\boldsymbol{B}$. The experimentally determined rate law is therefore

$$\text{rate} = k[\text{A}]^2[\text{B}]^0 = k[\text{A}]^2$$

We can now calculate the rate constant by inserting the data from any row of Table **7.2.3** into the experimentally determined rate law and solving for $\boldsymbol{k}$. Using Experiment 2, we obtain

$$19 \times 10^{-3}\ \text{M/min} = k(0.75\ \text{M})^2$$

$$3.4 \times 10^{-2}\ \text{M}^{-1}\cdot\text{min}^{-1} = \text{k}$$

You should verify that using data from any other row of Table **7.2.1** gives the same rate constant. This must be true as long as the experimental conditions, such as temperature and solvent, are the same.

Example 7.2.3

Nitric oxide is produced in the body by several different enzymes and acts as a signal that controls blood pressure, long-term memory, and other critical functions. The major route for removing NO from biological fluids is via reaction with $\boldsymbol{O_2}$ to give $\boldsymbol{NO_2}$, which then reacts rapidly with water to give nitrous acid and nitric acid:

$$2\text{NO} + \text{O}_2 \longrightarrow 2\text{NO}_2 \xrightarrow{\text{H}_2\text{O}} \text{HNO}_2 + \text{HNO}_3$$

These reactions are important in maintaining steady levels of NO. The following table lists kinetics data for the reaction of NO with O_2 at 25°C:

$$2NO(g) + O_2(g) \rightarrow 2NO_2(g)$$

Determine the rate law for the reaction and calculate the rate constant.

rate law for the reaction and calculate the rate constant.

Experiment	$[NO]_0$ (M)	$[O_2]_0$ (M)	Initial Rate (M/s)
1	0.0235	0.0125	7.98×10^{-3}
2	0.0235	0.0250	15.9×10^{-3}
3	0.0470	0.0125	32.0×10^{-3}
4	0.0470	0.0250	63.5×10^{-3}

Given: balanced chemical equation, initial concentrations, and initial rates

Asked for: rate law and rate constant

Strategy:

A. Compare the changes in initial concentrations with the corresponding changes in rates of reaction to determine the reaction order for each species. Write the rate law for the reaction.

B. Using data from any experiment, substitute appropriate values into the rate law. Solve the rate equation for *k*.

Solution

A Comparing Experiments 1 and 2 shows that as $[O_2]$ is doubled at a constant value of $[NO_2]$, the reaction rate approximately doubles. Thus the reaction rate is proportional to $[O_2]^1$, so the reaction is first order in O_2. Comparing Experiments 1 and 3 shows that the reaction rate essentially quadruples when [NO] is doubled and $[O_2]$ is held constant. That is, the reaction rate is proportional to $[NO]^2$, which indicates that the reaction is second order in NO. Using these relationships, we can write the rate law for the reaction:

$$\text{rate} = k[NO]^2[O_2]$$

B The data in any row can be used to calculate the rate constant. Using Experiment 1, for example, gives

$$k = \frac{\text{rate}}{[NO]^2[O_2]} = \frac{7.98 \times 10^{-3}\ \text{M/s}}{(0.0235\ \text{M})^2(0.0125\ \text{M})} = 1.16 \times 10^3\ \text{M}^{-2} \cdot \text{s}^{-1}$$

Alternatively, using Experiment 2 gives

$$k = \frac{\text{rate}}{[NO]^2[O_2]} = \frac{15.9 \times 10^{-3}\ \text{M/s}}{(0.0235\ \text{M})^2(0.0250\ \text{M})} = 1.15 \times 10^3\ \text{M}^{-2} \cdot \text{s}^{-1}$$

The difference is minor and associated with significant digits and likely experimental error in making the table.

The overall reaction order $(m + n) = 3$, so this is a third-order reaction whose rate is determined by three reactants. The units of the rate constant become more complex as the overall reaction order increases.

? Exercise 7.2.3

The peroxydisulfate ion ($S_2O_8^{2-}$) is a potent oxidizing agent that reacts rapidly with iodide ion in water:

$$S_2O^{2-}_{8(aq)} + 3I^-_{(aq)} \rightarrow 2SO^{2-}_{4(aq)} + I^-_{3(aq)}$$

The following table lists kinetics data for this reaction at 25°C. Determine the rate law and calculate the rate constant.

kinetics data for this reaction at 25°C.

Experiment	$[S_2O_8^{2-}]_0$ (M)	$[I^-]_0$ (M)	Initial Rate (M/s)
1	0.27	0.38	2.05
2	0.40	0.38	3.06
3	0.40	0.22	1.76

Answer:

rate = $k[S_2O_8^{2-}][I^-]$; $k = 20\ \text{M}^{-1}\cdot\text{s}^{-1}$



A Video Discussing Initial Rates and Rate Law Expressions. Video Link: Initial Rates and Rate Law Expressions(opens in new window) [youtu.be]

Summary

The rate law for a reaction is a mathematical relationship between the reaction rate and the concentrations of species in solution. Rate laws can be expressed either as a differential rate law, describing the change in reactant or product concentrations as a function of time, or as an integrated rate law, describing the actual concentrations of reactants or products as a function of time. The rate constant (k) of a rate law is a constant of proportionality between the reaction rate and the reactant concentration. The exponent to which a concentration is raised in a rate law indicates the reaction order, the degree to which the reaction rate depends on the concentration of a particular reactant.

7.2: The Rate Law- The Effect of Concentration on Reaction Rate is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **14.3: Concentration and Rates (Differential Rate Laws)** is licensed CC BY-NC-SA 3.0.

CHAPTER OVERVIEW

8: Chemical Equilibrium

Template:HideTOC

8.1: The Equilibrium Constant (K)

8.2: Expressing the Equilibrium Constant in Terms of Pressure

8.3: Calculating the Equilibrium Constant From Measured Equilibrium Concentrations

8.4: Heterogenous Equilibria - Reactions Involving Solids and Liquids

8.5: Le Châtelier’s Principle- How a System at Equilibrium Responds to Disturbances

---

8: Chemical Equilibrium is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

8.1: The Equilibrium Constant (K)

Learning Objectives

- To know the relationship between the equilibrium constant and the rate constants for the forward and reverse reactions.
- To write an equilibrium constant expression for any reaction.

Because an equilibrium state is achieved when the forward reaction rate equals the reverse reaction rate, under a given set of conditions there must be a relationship between the composition of the system at equilibrium and the kinetics of a reaction (represented by rate constants). We can show this relationship using the decomposition reaction of $\mathbf{N_2O_4}$ to $\mathbf{NO_2}$. Both the forward and reverse reactions for this system consist of a single elementary reaction, so the reaction rates are as follows:

$$\text{forward rate} = k_f[\mathrm{N_2O_4}]$$

and

$$\text{reverse rate} = k_r[\mathrm{NO_2}]^2$$

At equilibrium, the forward rate equals the reverse rate (definition of equilibrium):

$$k_f[\mathrm{N_2O_4}] = k_r[\mathrm{NO_2}]^2 \tag{8.1.1}$$

so

$$\frac{k_f}{k_r} = \frac{[\mathrm{NO_2}]^2}{[\mathrm{N_2O_4}]} \tag{8.1.2}$$

The ratio of the rate constants gives us a new constant, the equilibrium constant (K), which is defined as follows:

$$K = \frac{k_f}{k_r} \tag{8.1.3}$$

Hence there is a fundamental relationship between chemical kinetics and chemical equilibrium: under a given set of conditions, the composition of the equilibrium mixture is determined by the magnitudes of the rate constants for the forward and the reverse reactions.

> *The equilibrium constant is equal to the rate constant for the forward reaction divided by the rate constant for the reverse reaction.*



A Video for Determining the Equilibrium Expression: Determining the Equilibrium Expression(opens in new window) [youtu.be]

Table 8.1.1 lists the initial and equilibrium concentrations from five different experiments using the reaction system described by Equation 8.1.1. At equilibrium the magnitude of the quantity $[\mathrm{NO_2}]^2/[\mathrm{N_2O_4}]$ is essentially the same for all five experiments. In fact, no matter what the initial concentrations of $\mathbf{NO_2}$ and $\mathbf{N_2O_4}$ are, at equilibrium the quantity $[\mathrm{NO_2}]^2/[\mathrm{N_2O_4}]$ will always be 6.53 ± 0.03

$\times 10^{-3}$ at 25°C, which corresponds to the ratio of the rate constants for the forward and reverse reactions. That is, at a given temperature, the equilibrium constant for a reaction always has the same value, even though the specific concentrations of the reactants and products vary depending on their initial concentrations.

Table 8.1.1: Initial and Equilibrium Concentrations for $NO_2 : N_2O_4$ Mixtures at 25°C

[\(\ce{NO2}\)] (M)	Initial Concentrations [\(\ce{NO2}\)] (M)		Concentrations at Equilibrium		
Experiment	$[N_2O_4]$ (M)	$[NO_2]$ (M)	$[N_2O_4]$ (M)	$[NO_2]$ (M)	$K = [NO_2]^2/[N_2O_4]$
1	0.0500	0.0000	0.0417	0.0165	6.54×10^{-3}
2	0.0000	0.1000	0.0417	0.0165	6.54×10^{-3}
3	0.0750	0.0000	0.0647	0.0206	6.56×10^{-3}
4	0.0000	0.0750	0.0304	0.0141	6.54×10^{-3}
5	0.0250	0.0750	0.0532	0.0186	6.50×10^{-3}

Developing an Equilibrium Constant Expression

In 1864, the Norwegian chemists Cato Guldberg (1836–1902) and Peter Waage (1833–1900) carefully measured the compositions of many reaction systems at equilibrium. They discovered that for any reversible reaction of the general form

$$aA + bB \rightleftharpoons cC + dD \tag{8.1.4}$$

where A and B are reactants, C and D are products, and a, b, c, and d are the stoichiometric coefficients in the balanced chemical equation for the reaction, the ratio of the product of the equilibrium concentrations of the products (raised to their coefficients in the balanced chemical equation) to the product of the equilibrium concentrations of the reactants (raised to their coefficients in the balanced chemical equation) is always a constant under a given set of conditions. This relationship is known as the law of mass action (or law of chemical equilibrium) and can be stated as follows:

$$K = \frac{[C]^c[D]^d}{[A]^a[B]^b} \tag{8.1.5}$$

where K is the equilibrium constant for the reaction. Equation 8.1.4 is called the equilibrium equation, and the right side of Equation 8.1.5 is called the equilibrium constant expression. The relationship shown in Equation 8.1.5 is true for any pair of opposing reactions regardless of the mechanism of the reaction or the number of steps in the mechanism.

The equilibrium constant can vary over a wide range of values. The values of K shown in Table 8.1.2, for example, vary by 60 orders of magnitude. Because products are in the numerator of the equilibrium constant expression and reactants are in the denominator, values of K greater than 10^3 indicate a strong tendency for reactants to form products. In this case, chemists say that equilibrium lies to the right as written, favoring the formation of products. An example is the reaction between H_2 and Cl_2 to produce HCl, which has an equilibrium constant of 1.6×10^{33} at 300 K. Because H_2 is a good reductant and Cl_2 is a good oxidant, the reaction proceeds essentially to completion. In contrast, values of K less than 10^{-3} indicate that the ratio of products to reactants at equilibrium is very small. That is, reactants do not tend to form products readily, and the equilibrium lies to the left as written, favoring the formation of reactants.

Table 8.1.2: Equilibrium Constants for Selected Reactions*

Reaction	Temperature (K)	Equilibrium Constant (K)
$S_{(s)} + O_{2(g)} \rightleftharpoons SO_{2(g)}$	300	4.4×10^{53}
$2H_{2(g)} + O_{2(g)} \rightleftharpoons 2H2O_{(g)}$	500	2.4×10^{47}
$H_{2(g)} + Cl_{2(g)} \rightleftharpoons 2HCl_{(g)}$	300	1.6×10^{33}
$H_{2(g)} + Br_{2(g)} \rightleftharpoons 2HBr_{(g)}$	300	4.1×10^{18}
$2NO_{(g)} + O_{2(g)} \rightleftharpoons 2NO_{2(g)}$	300	4.2×10^{13}
$3H_{2(g)} + N_{2(g)} \rightleftharpoons 2NH_{3(g)}$	300	2.7×10^{8}
$H_{2(g)} + D_{2(g)} \rightleftharpoons 2HD_{(g)}$	100	1.92
$H_{2(g)} + I_{2(g)} \rightleftharpoons 2HI_{(g)}$	300	2.9×10^{-1}
$I_{2(g)} \rightleftharpoons 2I_{(g)}$	800	4.6×10^{-7}
$Br_{2(g)} \rightleftharpoons 2Br_{(g)}$	1000	4.0×10^{-7}
$Cl_{2(g)} \rightleftharpoons 2Cl_{(g)}$	1000	1.8×10^{-9}
$F_{2(g)} \rightleftharpoons 2F_{(g)}$	500	7.4×10^{-13}

*Equilibrium constants vary with temperature. The K values shown are for systems at the indicated temperatures.

Effective vs. True Concentrations

You will also notice in Table **8.1.2** that equilibrium constants have no units, even though Equation 8.1.5 suggests that the units of concentration might not always cancel because the exponents may vary. **In fact, equilibrium constants are calculated using "effective concentrations," or activities, of reactants and products, which are the ratios of the measured concentrations to a standard state of 1 M.** As shown in Equation 8.1.6, the units of concentration cancel, which makes K unitless as well:

$$\frac{[A]_{measured}}{[A]_{standard\ state}} = \frac{\cancel{M}}{\cancel{M}} = \frac{\frac{\cancel{mol}}{\cancel{L}}}{\frac{\cancel{mol}}{\cancel{L}}} \tag{8.1.6}$$

Because equilibrium constants are calculated using "effective concentrations" relative to a standard state of 1 M, values of K are unitless.

Many reactions have equilibrium constants between 1000 and 0.001 ($10^3 \geq K \geq 10^{-3}$), neither very large nor very small. At equilibrium, these systems tend to contain significant amounts of both products and reactants, indicating that there is not a strong tendency to form either products from reactants or reactants from products. An example of this type of system is the reaction of gaseous hydrogen and deuterium, a component of high-stability fiber-optic light sources used in ocean studies, to form **HD**:

$$\mathrm{H_2\,(g) + D_2\,(g) \rightleftharpoons 2\,HD\,(g)}$$

The equilibrium constant expression for this reaction is

$$K = \frac{[HD]^2}{[H_2][D_2]}$$

with K varying between 1.9 and 4 over a wide temperature range (100–1000 K). Thus an equilibrium mixture of H_2, D_2, and HD contains significant concentrations of both product and reactants.

Figure **8.1.3** summarizes the relationship between the magnitude of K and the relative concentrations of reactants and products at equilibrium for a general reaction, written as reactants ⇌ products. Because there is a direct relationship between the kinetics of a reaction and the equilibrium concentrations of products and reactants (Equations 8.1.6 and 8.1.5), when $k_f \gg k_r$, K is a **large**

number, and the concentration of products at equilibrium predominate. This corresponds to an essentially irreversible reaction. Conversely, when $k_f \ll k_r$, K is a very **small** number, and the reaction produces almost no products as written. Systems for which $k_f \approx k_r$ have significant concentrations of both reactants and products at equilibrium.




Figure **8.1.3**: The Relationship between the Composition of the Mixture at Equilibrium and the Magnitude of the Equilibrium Constant. The larger the K, the farther the reaction proceeds to the right before equilibrium is reached, and the greater the ratio of products to reactants at equilibrium.

If K is less than 0.001, it is considered small and it will be mostly reactants. If K is greater than 1000, it is considered large and it will be mostly products. If K is greater than or equal to 0.001 and less than or equal to 1000, it is considered intermediate. there will be significant amounts or reactants and products.

> *A large value of the equilibrium constant K means that products predominate at equilibrium; a small value means that reactants predominate at equilibrium.*

✔ Example 8.1.1: Equilibrium Constant Expressions

Write the equilibrium constant expression for each reaction.

- $\mathrm{N_2(g) + 3\,H_2(g) \rightleftharpoons 2\,NH_3(g)}$
- $\mathrm{CO(g) + \tfrac{1}{2}\,O_2(g) \rightleftharpoons CO_2(g)}$
- $\mathrm{2\,CO_2(g) \rightleftharpoons 2\,CO(g) + O_2(g)}$

Given: balanced chemical equations

Asked for: equilibrium constant expressions

Strategy:

Refer to Equation 8.1.5. Place the arithmetic product of the concentrations of the products (raised to their stoichiometric coefficients) in the numerator and the product of the concentrations of the reactants (raised to their stoichiometric coefficients) in the denominator.

Solution:

The only product is ammonia, which has a coefficient of 2. For the reactants, $\mathrm{N_2}$ has a coefficient of 1 and $\mathrm{H_2}$ has a coefficient of 3. The equilibrium constant expression is as follows:

$$\frac{[\mathrm{NH_3}]^2}{[\mathrm{N_2}][\mathrm{H_2}]^3}$$

The only product is carbon dioxide, which has a coefficient of 1. The reactants are CO, with a coefficient of 1, and $\mathrm{O_2}$, with a coefficient of $\frac{1}{2}$. Thus the equilibrium constant expression is as follows:

$$\frac{[\mathrm{CO_2}]}{[\mathrm{CO}][\mathrm{O_2}]^{1/2}}$$

This reaction is the reverse of the reaction in part b, with all coefficients multiplied by 2 to remove the fractional coefficient for $\mathrm{O_2}$. The equilibrium constant expression is therefore the inverse of the expression in part b, with all exponents multiplied by 2

$$\frac{[CO]^2[O_2]}{[CO_2]^2}$$

Exercise 8.1.1

Write the equilibrium constant expression for each reaction.

a. $\mathrm{N_2O\,(g)} \rightleftharpoons \mathrm{N_2\,(g)} + \frac{1}{2}\,\mathrm{O_2\,(g)}$
b. $\mathrm{2\,C_8H_{18}\,(g) + 25\,O_2\,(g)} \rightleftharpoons \mathrm{16\,CO_2\,(g) + 18\,H_2O\,(g)}$
c. $\mathrm{H_2\,(g) + I_2\,(g)} \rightleftharpoons \mathrm{2\,HI\,(g)}$

Answer a

$$K = \frac{[N_2][O_2]^{1/2}}{[N_2O]}$$

Answer b

$$K = \frac{[CO_2]^{16}[H_2O]^{18}}{[C_8H_{18}]^2[O_2]^{25}}$$

Answer c

$$K = \frac{[HI]^2}{[H_2][I_2]}$$

Example 8.1.2

Predict which systems at equilibrium will (a) contain essentially only products, (b) contain essentially only reactants, and (c) contain appreciable amounts of both products and reactants.

1. $H_{2(g)} + I_{2(g)} \rightleftharpoons 2HI_{(g)} \qquad K_{(700K)} = 54$
2. $2CO_{2(g)} \rightleftharpoons 2CO_{(g)} + O_{2(g)} \qquad K_{(1200K)} = 3.1 \times 10^{-18}$
3. $PCl_{5(g)} \rightleftharpoons PCl_{3(g)} + Cl_{2(g)} \qquad K_{(613K)} = 97$
4. $2O_{3(g)} \rightleftharpoons 3O_{2(g)} \qquad K_{(298K)} = 5.9 \times 10^{55}$

Given: systems and values of K

Asked for: composition of systems at equilibrium

Strategy:

Use the value of the equilibrium constant to determine whether the equilibrium mixture will contain essentially only products, essentially only reactants, or significant amounts of both.

Solution:

a. Only system 4 has $K \gg 10^3$, so at equilibrium it will consist of essentially only products.
b. System 2 has $K \ll 10^{-3}$, so the reactants have little tendency to form products under the conditions specified; thus, at equilibrium the system will contain essentially only reactants.
c. Both systems 1 and 3 have equilibrium constants in the range $10^3 \geq K \geq 10^{-3}$, indicating that the equilibrium mixtures will contain appreciable amounts of both products and reactants.

Exercise 8.1.2

Hydrogen and nitrogen react to form ammonia according to the following balanced chemical equation:

$$\mathrm{3\,H_2\,(g) + N_2\,(g)} \rightleftharpoons \mathrm{2\,NH_3\,(g)}$$

Values of the equilibrium constant at various temperatures were reported as

- $K_{25°C} = 3.3 \times 10^8$,

- $K_{177°C} = 2.6 \times 10^3$, and
- $K_{327°C} = 4.1$.

a. At which temperature would you expect to find the highest proportion of H_2 and N_2 in the equilibrium mixture?
b. Assuming that the reaction rates are fast enough so that equilibrium is reached quickly, at what temperature would you design a commercial reactor to operate to maximize the yield of ammonia?

Answer a

327°C, where K is smallest

Answer b

25°C



Video which Discusses What Does K Tell us About a Reaction?: What Does K Tell us About a Reaction?(opens in new window) [youtu.be]

Variations in the Form of the Equilibrium Constant Expression

Because equilibrium can be approached from either direction in a chemical reaction, the equilibrium constant expression and thus the magnitude of the equilibrium constant depend on the form in which the chemical reaction is written. For example, if we write the reaction described in Equation 8.1.4 in reverse, we obtain the following:

$$cC + dD \rightleftharpoons aA + bB \tag{8.1.7}$$

The corresponding equilibrium constant K' is as follows:

$$K' = \frac{[A]^a[B]^b}{[C]^c[D]^d} \tag{8.1.8}$$

This expression is the inverse of the expression for the original equilibrium constant, so $K' = 1/K$. That is, when we write a reaction in the reverse direction, the equilibrium constant expression is inverted. For instance, the equilibrium constant for the reaction $\mathrm{N_2O_4} \rightleftharpoons \mathrm{2\,NO_2}$ is as follows:

$$K = \frac{[\mathrm{NO_2}]^2}{[\mathrm{N_2O_4}]} \tag{8.1.9}$$

but for the opposite reaction, $2NO_2 \rightleftharpoons N_2O_4$, the equilibrium constant K′ is given by the inverse expression:

$$K' = \frac{[\mathrm{N_2O_4}]}{[\mathrm{NO_2}]^2} \tag{8.1.10}$$

Consider another example, the formation of water:

$$\mathrm{2\,H_2\,(g) + O_2\,(g) \rightleftharpoons 2\,H_2O\,(g)}.$$

Because H_2 is a good reductant and O_2 is a good oxidant, this reaction has a very large equilibrium constant ($K = 2.4 \times 10^{47}$ at 500 K). Consequently, the equilibrium constant for the reverse reaction, the decomposition of water to form O_2 and H_2, is very small: $K' = 1/K = 1/(2.4 \times 10^{47}) = 4.2 \times 10^{-48}$. As suggested by the very small equilibrium constant, and fortunately for life as we know it, a substantial amount of energy is indeed needed to dissociate water into H_2 and O_2.

> *The equilibrium constant for a reaction written in reverse is the inverse of the equilibrium constant for the reaction as written originally.*

Writing an equation in different but chemically equivalent forms also causes both the equilibrium constant expression and the magnitude of the equilibrium constant to be different. For example, we could write the equation for the reaction

$$2\,NO_2 \rightleftharpoons N_2O_4$$

as

$$NO_2 \rightleftharpoons \tfrac{1}{2}\,N_2O_4$$

with the equilibrium constant K″ is as follows:

$$K'' = \frac{[N_2O_4]^{1/2}}{[NO_2]} \tag{8.1.11}$$

The values for K′ (Equation 8.1.10) and K″ are related as follows:

$$K'' = (K')^{1/2} = \sqrt{K'} \tag{8.1.12}$$

In general, if all the coefficients in a balanced chemical equation were subsequently multiplied by n, then the new equilibrium constant is the original equilibrium constant raised to the n^{th} power.



A Video Discussing Relationships Involving Equilibrium Constants: Relationships Involving Equilibrium Constants(opens in new window) [youtu.be] (opens in new window)

Example 8.1.3: The Haber Process

At 745 K, K is 0.118 for the following reaction:

$$N_2\,(g) + 3\,H_2\,(g) \rightleftharpoons 2\,NH_3\,(g)$$

What is the equilibrium constant for each related reaction at 745 K?

a. $2\,NH_3\,(g) \rightleftharpoons N_2\,(g) + 3\,H_2\,(g)$
b. $\tfrac{1}{2}\,N_2\,(g) + \tfrac{3}{2}\,H_2\,(g) \rightleftharpoons NH_3\,(g)$

Given: balanced equilibrium equation, K at a given temperature, and equations of related reactions

Asked for: values of K for related reactions

Strategy:

Write the equilibrium constant expression for the given reaction and for each related reaction. From these expressions, calculate K for each reaction.

Solution:

The equilibrium constant expression for the given reaction of $N_{2(g)}$ with $H_{2(g)}$ to produce $NH_{3(g)}$ at 745 K is as follows:

$$K = \frac{[NH_3]^2}{[N_2][H_2]^3} = 0.118$$

This reaction is the reverse of the one given, so its equilibrium constant expression is as follows:

$$K' = \frac{1}{K} = \frac{[N_2][H_2]^3}{[NH_3]^2} = \frac{1}{0.118} = 8.47$$

In this reaction, the stoichiometric coefficients of the given reaction are divided by 2, so the equilibrium constant is calculated as follows:

$$K'' = \frac{[NH_3]}{[N_2]^{1/2}[H_2]^{3/2}} = K^{1/2} = \sqrt{K} = \sqrt{0.118} = 0.344$$

? Exercise

At 527°C, the equilibrium constant for the reaction

$$2\,SO_2\,(g) + O_2\,(g) \rightleftharpoons 2\,SO_3\,(g)$$

is 7.9×10^4. Calculate the equilibrium constant for the following reaction at the same temperature:

$$SO_3\,(g) \rightleftharpoons SO_2\,(g) + \tfrac{1}{2}\,O_2\,(g)$$

Answer

3.6×10^{-3}

Equilibrium Constant Expressions for Systems that Contain Gases

For reactions that involve species in solution, the concentrations used in equilibrium calculations are usually expressed in moles/liter. For gases, however, the concentrations are usually expressed in terms of partial pressures rather than molarity, where the standard state is 1 atm of pressure. The symbol K_p is used to denote equilibrium constants calculated from partial pressures. For the general reaction $aA + bB \rightleftharpoons cC + dD$, in which all the components are gases, the equilibrium constant expression can be written as the ratio of the partial pressures of the products and reactants (each raised to its coefficient in the chemical equation):

$$K_p = \frac{(P_C)^c(P_D)^d}{(P_A)^a(P_B)^b} \tag{8.1.13}$$

Thus K_p for the decomposition of N_2O_4 (Equation 15.1) is as follows:

$$K_p = \frac{(P_{NO_2})^2}{P_{N_2O_4}} \tag{8.1.14}$$

Like K, K_p is a unitless quantity because the quantity that is actually used to calculate it is an “effective pressure,” the ratio of the measured pressure to a standard state of 1 bar (approximately 1 atm), which produces a unitless quantity. The “effective pressure” is called the fugacity, just as activity is the effective concentration.

Because partial pressures are usually expressed in atmospheres or mmHg, the molar concentration of a gas and its partial pressure do not have the same numerical value. Consequently, the numerical values of K and K_p are usually different. They are, however, related by the ideal gas constant (R) and the absolute temperature (T):

$$K_p = K(RT)^{\Delta n} \tag{8.1.15}$$

where K is the equilibrium constant expressed in units of concentration and Δn is the difference between the numbers of moles of **gaseous** products and **gaseous** reactants ($n_p - n_r$). The temperature is expressed as the absolute temperature in Kelvin. According to Equation 8.1.15, $K_p = K$ only if the moles of gaseous products and gaseous reactants are the same (i.e., $\Delta n = 0$). For the decomposition of N_2O_4, there are 2 mol of gaseous product and 1 mol of gaseous reactant, so $\Delta n = 1$. Thus, for this reaction,

\[K_p = K(RT)^1 = KRT \nonumber \]

Example 8.1.4: The Haber Process (again)

The equilibrium constant for the reaction of nitrogen and hydrogen to give ammonia is 0.118 at 745 K. The balanced equilibrium equation is as follows:

$$\mathrm{N_2(g) + 3\,H_2(g) \rightleftharpoons 2\,NH_3(g)}$$

What is K_p for this reaction at the same temperature?

Given: equilibrium equation, equilibrium constant, and temperature

Asked for: K_p

Strategy:

Use the coefficients in the balanced chemical equation to calculate Δn. Then use Equation 8.1.15 to calculate K from K_p.

Solution:

This reaction has 2 mol of gaseous product and 4 mol of gaseous reactants, so $\Delta n = (2 - 4) = -2$. We know K, and $T = 745\ K$. Thus, from Equation 8.1.12, we have the following:

$$\begin{aligned} K_p &= K(RT)^{-2} \\ &= \frac{K}{(RT)^2} \\ &= \frac{0.118}{\{[0.08206(L \cdot atm)/(mol \cdot K)][745\ K]\}^2} \\ &= 3.16 \times 10^{-5} \end{aligned}$$

Because K_p is a unitless quantity, the answer is $K_p = 3.16 \times 10^{-5}$.

Exercise 8.1.4

Calculate K_p for the reaction

$$\mathrm{2\,SO_2(g) + O_2(g) \rightleftharpoons 2\,SO_3(g)}$$

at 527°C, if $K = 7.9 \times 10^4$ at this temperature.

Answer

$K_p = 1.2 \times 10^3$



Video Discussing Converting Kc to Kp: Converting Kc to Kp(opens in new window) [youtu.be]

Equilibrium Constant Expressions for the Sums of Reactions

Chemists frequently need to know the equilibrium constant for a reaction that has not been previously studied. In such cases, the desired reaction can often be written as the sum of other reactions for which the equilibrium constants are known. The equilibrium constant for the unknown reaction can then be calculated from the tabulated values for the other reactions.

To illustrate this procedure, let's consider the reaction of $\mathbf{N_2}$ with $\mathbf{O_2}$ to give $\mathbf{NO_2}$. This reaction is an important source of the $\mathbf{NO_2}$ that gives urban smog its typical brown color. The reaction normally occurs in two distinct steps. In the first reaction (step 1), $\mathbf{N_2}$ reacts with $\mathbf{O_2}$ at the high temperatures inside an internal combustion engine to give $\mathbf{NO}$. The released $\mathbf{NO}$ then reacts with additional $\mathbf{O_2}$ to give $\mathbf{NO_2}$ (step 2). The equilibrium constant for each reaction at 100°C is also given.

$$\mathrm{N_2(g) + O_2(g) \rightleftharpoons 2NO(g)} \qquad K_1 = 2.0 \times 10^{-25}$$

$$\mathrm{2NO(g) + O_2(g) \rightleftharpoons 2NO_2(g)} \quad K_2 = 6.4 \times 10^{9}$$

Summing reactions (step 1) and (step 2) gives the overall reaction of N_2 with O_2:

$$\mathrm{N_2(g) + 2O_2(g) \rightleftharpoons 2NO_2(g)} \qquad K_3 = ?$$

The equilibrium constant expressions for the reactions are as follows:

$$K_1 = \frac{[NO]^2}{[N_2][O_2]} \qquad K_2 = \frac{[NO_2]^2}{[NO]^2[O_2]} \qquad K_3 = \frac{[NO_2]^2}{[N_2][O_2]^2}$$

What is the relationship between K_1, K_2, and K_3, all at 100°C? The expression for K_1 has $[NO]^2$ in the numerator, the expression for K_2 has $[NO]^2$ in the denominator, and $[NO]^2$ does not appear in the expression for K_3. Multiplying K_1 by K_2 and canceling the $[NO]^2$ terms,

$$K_1K_2 = \frac{\cancel{[NO]^2}}{[N_2][O_2]} \times \frac{[NO_2]^2}{\cancel{[NO]^2}\,[O_2]} = \frac{[NO_2]^2}{[N_2][O_2]^2} = K_3$$

Thus the product of the equilibrium constant expressions for K_1 and K_2 is the same as the equilibrium constant expression for K_3:

$$K_3 = K_1K_2 = (2.0 \times 10^{-25})(6.4 \times 10^{9}) = 1.3 \times 10^{-15}$$

The equilibrium constant for a reaction that is the sum of two or more reactions is equal to the product of the equilibrium constants for the individual reactions. In contrast, recall that according to Hess's Law, ΔH for the sum of two or more reactions is the sum of the ΔH values for the individual reactions.

> *To determine K for a reaction that is the sum of two or more reactions, add the reactions but multiply the equilibrium constants.*

Example 8.1.6

The following reactions occur at 1200°C:

1. $CO_{(g)} + 3H_{2(g)} \rightleftharpoons CH_{4(g)} + H_2O_{(g)} \qquad K_1 = 9.17 \times 10^{-2}$
2. $CH_{4(g)} + 2H_2S_{(g)} \rightleftharpoons CS_{2(g)} + 4H_{2(g)} \qquad K_2 = 3.3 \times 10^{4}$

Calculate the equilibrium constant for the following reaction at the same temperature.

3. $CO_{(g)} + 2H_2S_{(g)} \rightleftharpoons CS_{2(g)} + H_2O_{(g)} + H_{2(g)} \qquad K_3 = ?$

Given: two balanced equilibrium equations, values of K, and an equilibrium equation for the overall reaction

Asked for: equilibrium constant for the overall reaction

Strategy:

Arrange the equations so that their sum produces the overall equation. If an equation had to be reversed, invert the value of K for that equation. Calculate K for the overall equation by multiplying the equilibrium constants for the individual equations.

Solution:

The key to solving this problem is to recognize that reaction 3 is the sum of reactions 1 and 2:

$$CO_{(g)} + \cancel{3H_{2(g)}} \rightleftharpoons \cancel{CH_{4(g)}} + H_2O_{(g)}$$

$$\cancel{CH_{4(g)}} + 2H_2S_{(g)} \rightleftharpoons CS_{2(g)} + \cancel{3H_{2(g)}} + H_{2(g)}$$

$$CO_{(g)} + 3H_{2(g)} \rightleftharpoons CS_{2(g)} + H_2O_{(g)} + H_{2(g)}$$

The values for K_1 and K_2 are given, so it is straightforward to calculate K_3:

$$K_3 = K_1K_2 = (9.17 \times 10^{-2})(3.3 \times 10^{4}) = 3.03 \times 10^{3}$$

Exercise 8.1.6

In the first of two steps in the industrial synthesis of sulfuric acid, elemental sulfur reacts with oxygen to produce sulfur dioxide. In the second step, sulfur dioxide reacts with additional oxygen to form sulfur trioxide. The reaction for each step is shown, as is the value of the corresponding equilibrium constant at 25°C. Calculate the equilibrium constant for the overall reaction at this same temperature.

1. $\frac{1}{8}S_{8(s)} + O_{2(g)} \rightleftharpoons SO_{2(g)} \qquad K_1 = 4.4 \times 10^{53}$
2. $SO_{2(g)} + \frac{1}{2}O_{2(g)} \rightleftharpoons SO_{3(g)} \qquad K_2 = 2.6 \times 10^{12}$
3. $\frac{1}{8}S_{8(s)} + \frac{3}{2}O_{2(g)} \rightleftharpoons SO_{3(g)} \qquad K_3 = ?$

Answer

$K_3 = 1.1 \times 10^{66}$

Summary

The ratio of the rate constants for the forward and reverse reactions at equilibrium is the equilibrium constant (K), a unitless quantity. The composition of the equilibrium mixture is therefore determined by the magnitudes of the forward and reverse rate constants at equilibrium. Under a given set of conditions, a reaction will always have the same K. For a system at equilibrium, the law of mass action relates K to the ratio of the equilibrium concentrations of the products to the concentrations of the reactants raised to their respective powers to match the coefficients in the equilibrium equation. The ratio is called the equilibrium constant expression. When a reaction is written in the reverse direction, K and the equilibrium constant expression are inverted. For gases, the equilibrium constant expression can be written as the ratio of the partial pressures of the products to the partial pressures of the reactants, each raised to a power matching its coefficient in the chemical equation. An equilibrium constant calculated from partial pressures (K_p) is related to K by the ideal gas constant (R), the temperature (T), and the change in the number of moles of gas

during the reaction. An equilibrium system that contains products and reactants in a single phase is a homogeneous equilibrium; a system whose reactants, products, or both are in more than one phase is a heterogeneous equilibrium. When a reaction can be expressed as the sum of two or more reactions, its equilibrium constant is equal to the product of the equilibrium constants for the individual reactions.

- The law of mass action describes a system at equilibrium in terms of the concentrations of the products and the reactants.
- For a system involving one or more gases, either the molar concentrations of the gases or their partial pressures can be used.
- Definition of equilibrium constant in terms of forward and reverse rate constants:

$$K = \frac{k_f}{k_r}$$

- Equilibrium constant expression (law of mass action):

$$K = \frac{[C]^c[D]^d}{[A]^a[B]^b}$$

- Equilibrium constant expression for reactions involving gases using partial pressures:

$$K_p = \frac{(P_C)^c(P_D)^d}{(P_A)^a(P_B)^b}$$

- Relationship between K_p and K:

$$K_p = K(RT)^{\Delta n}$$

8.1: The Equilibrium Constant (K) is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **15.2: The Equilibrium Constant** is licensed CC BY-NC-SA 3.0.

8.2: Expressing the Equilibrium Constant in Terms of Pressure

Learning Objectives

- To understand how different phases affect equilibria.

When the products and reactants of an equilibrium reaction form a single phase, whether gas or liquid, the system is a homogeneous equilibrium. In such situations, the concentrations of the reactants and products can vary over a wide range. In contrast, a system whose reactants, products, or both are in more than one phase is a heterogeneous equilibrium, such as the reaction of a gas with a solid or liquid.

As noted in the previous section, the equilibrium constant expression is actually a ratio of activities. To simplify the calculations in general chemistry courses, the activity of each substance in the reaction is often approximated using a ratio of the molarity of a substance compared to the standard state of that substance. For substances that are liquids or solids, the standard state is just the concentration of the substance within the liquid or solid. Because the molar concentrations of pure liquids and solids normally do not vary greatly with temperature, the ratio of the molarity to the standard state for substances that are liquids or solids always has a value of 1. For example, for a compound such as $CaF_2(s)$, the term going into the equilibrium expression is $[CaF_2]/[CaF_2]$ which cancels to unity. Thus, when the activities of the solids and liquids (including solvents) are incorporated into the equilibrium expression, they do not change the value.

Consider the following reaction, which is used in the final firing of some types of pottery to produce brilliant metallic glazes:

$$\mathrm{CO_2(g) + C(s) \rightleftharpoons 2\,CO(g)} \tag{8.2.1}$$

The glaze is created when metal oxides are reduced to metals by the product, carbon monoxide. The equilibrium constant expression for this reaction is as follows:


$$K = \frac{a_{CO}^2}{a_{CO_2} a_C} = \frac{[CO]^2}{[CO_2][1]} = \frac{[CO]^2}{[CO_2]} \tag{8.2.2}$$

The equilibrium constant for this reaction can also be written in terms of the partial pressures of the gases:

$$K_p = \frac{(P_{CO})^2}{P_{CO_2}} \tag{8.2.3}$$

Incorporating all the constant values into K' or K_p allows us to focus on the substances whose concentrations change during the reaction.

Although the activities of pure liquids or solids are not written explicitly in the equilibrium constant expression, these substances must be present in the reaction mixture for chemical equilibrium to occur. Whatever the concentrations of CO and CO_2, the system described in Equation 8.2.1 will reach chemical equilibrium only if a stoichiometric amount of solid carbon or excess solid carbon has been added so that some is still present once the system has reached equilibrium. As shown in Figure 8.2.1, it does not matter whether 1 g or 100 g of solid carbon is present; in either case, the composition of the gaseous components of the system will be the same at equilibrium.



$$CO_2(g) + C(s) \rightleftharpoons 2CO(g)$$

Figure 8.2.2: Effect of the Amount of Solid Present on Equilibrium in a Heterogeneous Solid–Gas System. In the system, the equilibrium composition of the gas phase at a given temperature, 1000 K in this case, is the same whether a small amount of solid carbon (left) or a large amount (right) is present.

Example 8.2.1

Write each expression for K, incorporating all constants, and K_p for the following equilibrium reactions.

a. $\mathrm{PCl_3(l) + Cl_2(g) \rightleftharpoons PCl_5(s)}$
b. $\mathrm{Fe_3O_4(s) + 4H_2(g) \rightleftharpoons 3Fe(s) + 4H_2O(g)}$

Given: balanced equilibrium equations.

Asked for: expressions for K and K_p.

Strategy:

Find K by writing each equilibrium constant expression as the ratio of the concentrations of the products and reactants, each raised to its coefficient in the chemical equation. Then express K_p as the ratio of the partial pressures of the products and reactants, each also raised to its coefficient in the chemical equation.

Solution

This reaction contains a pure solid (PCl_5) and a pure liquid (PCl_3). Their activities are equal to 1, so when incorporated into the equilibrium constant expression, they do not change the value. So

$$K = \frac{1}{(1)[Cl_2]}$$

and

$$K_p = \frac{1}{(1)P_{Cl_2}}$$

This reaction contains two pure solids (Fe_3O_4 and Fe), which are each assigned a value of 1 in the equilibrium constant expressions:

$$K = \frac{(1)[H_2O]^4}{(1)[H_2]^4}$$

and

$$K_p = \frac{(1)(P_{H_2O})^4}{(1)(P_{H_2})^4}$$

? Exercise 8.2.1

Write the expressions for K and K_p for the following reactions.

a. $\mathrm{CaCO_3\,(s) \rightleftharpoons CaO\,(s) + CO_2\,(g)}$

b. $\underset{\textit{glucose}}{\mathrm{C_6H_{12}O_6\,(s)}} + \mathrm{6\,O_2\,(g) \rightleftharpoons 6\,CO_2\,(g) + 6\,H_2O\,(g)}$

Answer a

$K = [\mathrm{CO_2}]$ and $K_p = P_{\mathrm{CO_2}}$

Answer b

$K = \frac{[CO_2]^6[H_2O]^6}{[O_2]^6}$ and $K_p = \frac{(P_{CO_2})^6(P_{H_2O})^6}{(P_{O_2})^6}$

For reactions carried out in solution, the solvent is assumed to be pure, and therefore is assigned an activity equal to 1 in the equilibrium constant expression. The activities of the solutes are approximated by their molarities. The result is that the equilibrium constant expressions appear to only depend upon the concentrations of the solutes.

> *The activities of pure solids, pure liquids, and solvents are defined as having a value of '1'. Often, it is said that these activities are "left out" of equilibrium constant expressions. This is an unfortunate use of words. The activities are not "left out" of equilibrium constant expressions. Rather, because they have a value of '1', they do not change the value of the equilibrium constant when they are multiplied together with the other terms. The activities of the solutes are approximated by their molarities.*

Summary

An equilibrated system that contains products and reactants in a single phase is a homogeneous equilibrium; a system whose reactants, products, or both are in more than one phase is a heterogeneous equilibrium.

Contributors and Attributions

- Anonymous
- Modified by Tom Neils (Grand Rapids Community College)

8.2: Expressing the Equilibrium Constant in Terms of Pressure is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **15.4: Heterogeneous Equilibria** is licensed CC BY-NC-SA 3.0.

8.3: Calculating the Equilibrium Constant From Measured Equilibrium Concentrations

Learning Objectives

- To solve quantitative problems involving chemical equilibriums.


There are two fundamental kinds of equilibrium problems:

1. those in which we are given the concentrations of the reactants and the products at equilibrium (or, more often, information that allows us to calculate these concentrations), and we are asked to calculate the equilibrium constant for the reaction; and
2. those in which we are given the equilibrium constant and the initial concentrations of reactants, and we are asked to calculate the concentration of one or more substances at equilibrium. In this section, we describe methods for solving both kinds of problems.

Calculating an Equilibrium Constant from Equilibrium Concentrations

We saw in the exercise in Example 6 in Section 15.2 that the equilibrium constant for the decomposition of $CaCO_{3(s)}$ to $CaO_{(s)}$ and $CO_{2(g)}$ is $K = [CO_2]$. At 800°C, the concentration of CO_2 in equilibrium with solid $CaCO_3$ and CaO is $2.5 \times 10^{-3}\ M$. Thus K at 800°C is 2.5×10^{-3}. (Remember that equilibrium constants are unitless.)

A more complex example of this type of problem is the conversion of n-butane, an additive used to increase the volatility of gasoline, into isobutane (2-methylpropane).



n-butane isobutane (2-methylpropane)

This reaction can be written as follows:

$$n\text{-butane}_{(g)} \rightleftharpoons \text{isobutane}_{(g)} \tag{8.3.1}$$

and the equilibrium constant $K = [\text{isobutane}]/[\text{n-butane}]$. At equilibrium, a mixture of n-butane and isobutane at room temperature was found to contain 0.041 M isobutane and 0.016 M n-butane. Substituting these concentrations into the equilibrium constant expression,

$$K = \frac{[isobutane]}{[n\text{-}butane]} = 0.041\ M = 2.6 \tag{8.3.2}$$

Thus the equilibrium constant for the reaction as written is 2.6.

Example 8.3.1

The reaction between gaseous sulfur dioxide and oxygen is a key step in the industrial synthesis of sulfuric acid:

$$2SO_{2(g)} + O_{2(g)} \rightleftharpoons 2SO_{3(g)}$$

A mixture of SO_2 and O_2 was maintained at 800 K until the system reached equilibrium. The equilibrium mixture contained

- $5.0 \times 10^{-2}\ M\ SO_3$,
- $3.5 \times 10^{-3}\ M\ O_2$, and
- $3.0 \times 10^{-3}\ M\ SO_2$.

Calculate K and K_p at this temperature.

Given: balanced equilibrium equation and composition of equilibrium mixture

Asked for: equilibrium constant

Strategy

Write the equilibrium constant expression for the reaction. Then substitute the appropriate equilibrium concentrations into this equation to obtain K.

Solution

Substituting the appropriate equilibrium concentrations into the equilibrium constant expression,

$$K = \frac{[SO_3]^2}{[SO_2]^2[O_2]} = \frac{(5.0 \times 10^{-2})^2}{(3.0 \times 10^{-3})^2(3.5 \times 10^{-3})} = 7.9 \times 10^4$$

To solve for K_p, we use the relationship derived previously

$$K_p = K(RT)^{\Delta n}$$

where $\Delta n = 2 - 3 = -1$:

$$K_p = K(RT)^{\Delta n}$$

$$K_p = 7.9 \times 10^4[(0.08206\ L \cdot atm/mol \cdot K)(800K)]^{-1}$$

$$K_p = 1.2 \times 10^3$$

? Exercise 8.3.1

Hydrogen gas and iodine react to form hydrogen iodide via the reaction

$$2NOCl_{(g)} \leftrightharpoons 2NO_{(g)} + Cl_{2(g)}$$

A mixture of H_2 and I_2 was maintained at 740 K until the system reached equilibrium. The equilibrium mixture contained

- $1.37 \times 10^{-2}\ M\ HI$,
- $6.47 \times 10^{-3}\ M\ H_2$, and
- $5.94 \times 10^{-4}\ M\ I_2$.

Calculate K and K_p for this reaction.

Answer

$K = 48.8$ and $K_p = 48.8$

Chemists are not often given the concentrations of all the substances, and they are not likely to measure the equilibrium concentrations of all the relevant substances for a particular system. In such cases, we can obtain the equilibrium concentrations from the initial concentrations of the reactants and the balanced chemical equation for the reaction, as long as the equilibrium concentration of one of the substances is known. Example **8.3.2** shows one way to do this.

✔ Example 8.3.2

A 1.00 mol sample of $NOCl$ was placed in a 2.00 L reactor and heated to 227°C until the system reached equilibrium. The contents of the reactor were then analyzed and found to contain 0.056 mol of Cl_2. Calculate K at this temperature. The equation for the decomposition of $NOCl$ to NO and Cl_2 is as follows:

\[2 NOCl_{(g)} \rightleftharpoons 2NO_{(g)}+Cl_{2(g)}\nonumber \]

Given: balanced equilibrium equation, amount of reactant, volume, and amount of one product at equilibrium

Asked for: K

Strategy:

A. Write the equilibrium constant expression for the reaction. Construct a table showing the initial concentrations, the changes in concentrations, and the final concentrations (as initial concentrations plus changes in concentrations).

B. Calculate all possible initial concentrations from the data given and insert them in the table.

C. Use the coefficients in the balanced chemical equation to obtain the changes in concentration of all other substances in the reaction. Insert those concentration changes in the table.

D. Obtain the final concentrations by summing the columns. Calculate the equilibrium constant for the reaction.

Solution

A The first step in any such problem is to balance the chemical equation for the reaction (if it is not already balanced) and use it to derive the equilibrium constant expression. In this case, the equation is already balanced, and the equilibrium constant expression is as follows:

$$K = \frac{[NO]^2[Cl_2]}{[NOCl]^2}$$

To obtain the concentrations of $NOCl$, NO, and Cl_2 at equilibrium, we construct a table showing what is known and what needs to be calculated. We begin by writing the balanced chemical equation at the top of the table, followed by three lines corresponding to the initial concentrations, the changes in concentrations required to get from the initial to the final state, and the final concentrations.

$$2NOCl_{(g)} \rightleftharpoons 2NO_{(g)} + Cl_{2(g)}$$

ICE	$[NOCl]$	$[NO]$	$[Cl_2]$
Initial			
Change			
Final			

B Initially, the system contains 1.00 mol of $NOCl$ in a 2.00 L container. Thus $[NOCl]_i = 1.00\ mol/2.00\ L = 0.500\ M$. The initial concentrations of NO and Cl_2 are $0\ M$ because initially no products are present. Moreover, we are told that at equilibrium the system contains 0.056 mol of Cl_2 in a 2.00 L container, so $[Cl_2]_f = 0.056\ mol/2.00\ L = 0.028\ M$. We insert these values into the following table:

$$2NOCl_{(g)} \rightleftharpoons 2NO_{(g)} + Cl_{2(g)}$$

ICE	$[NOCl]$	$[NO]$	$[Cl_2]$
Initial	0.500	0	0
Change			
Final			0.028

C We use the stoichiometric relationships given in the balanced chemical equation to find the change in the concentration of Cl_2, the substance for which initial and final concentrations are known:

$$\Delta[Cl_2] = 0.028\ M_{(final)} - 0.00\ M_{(initial)}] = +0.028\ M$$

According to the coefficients in the balanced chemical equation, 2 mol of NO are produced for every 1 mol of Cl_2, so the change in the NO concentration is as follows:

$$\Delta[NO] = \left(\frac{0.028\ \cancel{mol\ Cl_2}}{L}\right)\left(\frac{2\ mol\ NO}{1\ \cancel{mol\ Cl_2}}\right) = 0.056\ M$$

Similarly, 2 mol of $NOCl$ are consumed for every 1 mol of Cl_2 produced, so the change in the $NOCl$ concentration is as follows:

$$\Delta[NOCl] = \left(\frac{0.028\ \cancel{mol\ Cl_2}}{L}\right)\left(\frac{-2\ mol\ NOCl}{1\ \cancel{mol\ Cl_2}}\right) = -0.056\ M$$

We insert these values into our table:

$$2NOCl_{(g)} \rightleftharpoons 2NO_{(g)} + Cl_{2(g)}$$

ICE	$[NOCl]$	$[NO]$	$[Cl_2]$
Initial	0.500	0	0
Change	−0.056	+0.056	+0.028
Final			0.028

D We sum the numbers in the $[NOCl]$ and $[NO]$ columns to obtain the final concentrations of NO and $NOCl$:

$$[NO]_f = 0.000\ M + 0.056\ M = 0.056\ M$$

$$[NOCl]_f = 0.500\ M + (-0.056\ M) = 0.444M$$

We can now complete the table:

$$2NOCl_{(g)} \rightleftharpoons 2NO_{(g)} + Cl_{2(g)}$$

ICE	\([NOCl]	$[NO]$	$[Cl_2]$
initial	0.500	0	0
change	−0.056	+0.056	+0.028
final	0.444	0.056	0.028

We can now calculate the equilibrium constant for the reaction:

$$K = \frac{[NO]^2[Cl_2]}{[NOCl]^2} = \frac{(0.056)^2(0.028)}{(0.444)^2} = 4.5 \times 10^{-4}$$

? Exercise 8.3.2

The German chemist Fritz Haber (1868–1934; Nobel Prize in Chemistry 1918) was able to synthesize ammonia (NH_3) by reacting $0.1248\ M\ H_2$ and $0.0416\ M\ N_2$ at about 500°C. At equilibrium, the mixture contained 0.00272 M NH_3. What is K for the reaction

$$N_2 + 3H_2 \rightleftharpoons 2NH_3$$

at this temperature? What is K_p?

Answer

$K = 0.105$ and $K_p = 2.61 \times 10^{-5}$



A Video Disucssing Using ICE Tables to find Kc: Using ICE Tables to find Kc(opens in new window) [youtu.be]

Calculating Equilibrium Concentrations from the Equilibrium Constant

To describe how to calculate equilibrium concentrations from an equilibrium constant, we first consider a system that contains only a single product and a single reactant, the conversion of n-butane to isobutane (Equation 8.3.1), for which K = 2.6 at 25°C. If we begin with a 1.00 M sample of n-butane, we can determine the concentration of n-butane and isobutane at equilibrium by constructing a table showing what is known and what needs to be calculated, just as we did in Example 8.3.2.

$$\text{n-butane}_{(g)} \rightleftharpoons \text{isobutane}_{(g)}$$

ICE	$[\text{n-butane}_{(g)}]$	$[\text{isobutane}_{(g)}]$
Initial		
Change		
Final		

The initial concentrations of the reactant and product are both known: [n-butane]i = 1.00 M and [isobutane]i = 0 M. We need to calculate the equilibrium concentrations of both n-butane and isobutane. Because it is generally difficult to calculate final concentrations directly, we focus on the change in the concentrations of the substances between the initial and the final (equilibrium) conditions. If, for example, we define the change in the concentration of isobutane (Δ[isobutane]) as $+x$, then the change in the concentration of n-butane is Δ[n-butane] = $-x$. This is because the balanced chemical equation for the reaction tells us that 1 mol of n-butane is consumed for every 1 mol of isobutane produced. We can then express the final concentrations in terms of the initial concentrations and the changes they have undergone.

$$\text{n-butane}_{(g)} \rightleftharpoons \text{isobutane}_{(g)}$$

ICE	$[\text{n-butane}_{(g)}]$	$[\text{isobutane}_{(g)}]$
Initial	1.00	0
Change	$-x$	$+x$
Final	$(1.00 - x)$	$(0 + x) = x$

Substituting the expressions for the final concentrations of n-butane and isobutane from the table into the equilibrium equation,

$$K = \frac{[\text{isobutane}]}{[\text{n-butane}]} = \frac{x}{1.00 - x} = 2.6$$

Rearranging and solving for x,

$$x = 2.6(1.00 - x) = 2.6 - 2.6x$$

$$x + 2.6x = 2.6$$

$$x = 0.72$$

We obtain the final concentrations by substituting this x value into the expressions for the final concentrations of n-butane and isobutane listed in the table:

$$[\text{n-butane}]_f = (1.00 - x)M = (1.00 - 0.72)M = 0.28\ M$$

$$[\text{isobutane}]_f = (0.00 + x)M = (0.00 + 0.72)M = 0.72\ M$$

We can check the results by substituting them back into the equilibrium constant expression to see whether they give the same K that we used in the calculation:

$$K = \frac{[\text{isobutane}]}{[\text{n-butane}]} = \left(\frac{0.72\ \cancel{M}}{0.28\ \cancel{M}}\right) = 2.6$$

This is the same K we were given, so we can be confident of our results.

Example **8.3.3** illustrates a common type of equilibrium problem that you are likely to encounter.

Example 8.3.3: The water–gas shift reaction

The water–gas shift reaction is important in several chemical processes, such as the production of H_2 for fuel cells. This reaction can be written as follows:

$$H_{2(g)} + CO_{2(g)} \rightleftharpoons H_2O_{(g)} + CO_{(g)}$$

$K = 0.106$ at 700 K. If a mixture of gases that initially contains 0.0150 M H_2 and 0.0150 M CO_2 is allowed to equilibrate at 700 K, what are the final concentrations of all substances present?

Given: balanced equilibrium equation, K, and initial concentrations

Asked for: final concentrations

Strategy:

A. Construct a table showing what is known and what needs to be calculated. Define x as the change in the concentration of one substance. Then use the reaction stoichiometry to express the changes in the concentrations of the other substances in terms of x. From the values in the table, calculate the final concentrations.
B. Write the equilibrium equation for the reaction. Substitute appropriate values from the ICE table to obtain x.
C. Calculate the final concentrations of all species present. Check your answers by substituting these values into the equilibrium constant expression to obtain K.

Solution

A The initial concentrations of the reactants are $[H_2]_i = [CO_2]_i = 0.0150\ M$. Just as before, we will focus on the change in the concentrations of the various substances between the initial and final states. If we define the change in the concentration of H_2O as x, then $\Delta[H_2O] = +x$. We can use the stoichiometry of the reaction to express the changes in the concentrations of the other substances in terms of x. For example, 1 mol of CO is produced for every 1 mol of H_2O, so the change in the CO concentration can be expressed as $\Delta[CO] = +x$. Similarly, for every 1 mol of H_2O produced, 1 mol each of H_2 and CO_2 are consumed, so the change in the concentration of the reactants is $\Delta[H_2] = \Delta[CO_2] = -x$. We enter the values in the following table and calculate the final concentrations.

$$H_{2(g)} + CO_{2(g)} \rightleftharpoons H_2O_{(g)} + CO_{(g)}$$

ICE	$[H_2]$	$[CO_2]$	$[H_2O]$	$[CO]$
Initial	0.0150	0.0150	0	0
Change	$-x$	$-x$	$+x$	$+x$
Final	$(0.0150-x)$	$(0.0150-x)$	x	x

B We can now use the equilibrium equation and the given K to solve for x:

$$K=\frac{[H_2O][CO]}{[H_2][CO_2]}=\frac{(x)(x)}{(0.0150-x)(0.0150-x}=\frac{x^2}{(0.0150-x)^2}=0.106$$

We could solve this equation with the quadratic formula, but it is far easier to solve for x by recognizing that the left side of the equation is a perfect square; that is,

$$\frac{x^2}{(0.0150-x)^2}=\left(\frac{x}{0.0150-x}\right)^2=0.106$$

Taking the square root of the middle and right terms,

$$\frac{x}{(0.0150-x)}=(0.106)^{1/2}=0.326$$

$$x=(0.326)(0.0150)-0.326x$$

$$1.326x=0.00489$$

$$x=0.00369=3.69\times10^{-3}$$

C The final concentrations of all species in the reaction mixture are as follows:

- $[H_2]_f=[H_2]_i+\Delta[H_2]=(0.0150-0.00369)\ M=0.0113\ M$
- $[CO_2]_f=[CO_2]_i+\Delta[CO_2]=(0.0150-0.00369)\ M=0.0113\ M$
- $[H_2O]_f=[H_2O]_i+\Delta[H_2O]=(0+0.00369)\ M=0.00369\ M$
- $[CO]_f=[CO]_i+\Delta[CO]=(0+0.00369)\ M=0.00369\ M$

We can check our work by inserting the calculated values back into the equilibrium constant expression:

$$K=\frac{[H_2O][CO]}{[H_2][CO_2]}=\frac{(0.00369)^2}{(0.0113)^2}=0.107$$

To two significant figures, this K is the same as the value given in the problem, so our answer is confirmed.

? Exercise 8.3.3

Hydrogen gas reacts with iodine vapor to give hydrogen iodide according to the following chemical equation:

$$H_{2(g)}+I_{2(g)}\rightleftharpoons 2HI_{(g)}$$

$K=54$ at 425°C. If 0.172 M H_2 and I_2 are injected into a reactor and maintained at 425°C until the system equilibrates, what is the final concentration of each substance in the reaction mixture?

Answer

- $[HI]_f=0.270\ M$
- $[H_2]_f=[I_2]_f=0.037\ M$

In Example **8.3.3**, the initial concentrations of the reactants were the same, which gave us an equation that was a perfect square and simplified our calculations. Often, however, the initial concentrations of the reactants are not the same, and/or one or more of the

products may be present when the reaction starts. Under these conditions, there is usually no way to simplify the problem, and we must determine the equilibrium concentrations with other means. Such a case is described in Example **8.3.4**.

Example 8.3.4

In the water–gas shift reaction shown in Example **8.3.3**, a sample containing 0.632 M CO2 and 0.570 M H_2 is allowed to equilibrate at 700 K. At this temperature, $K = 0.106$. What is the composition of the reaction mixture at equilibrium?

Given: balanced equilibrium equation, concentrations of reactants, and K

Asked for: composition of reaction mixture at equilibrium

Strategy:

A. Write the equilibrium equation. Construct a table showing the initial concentrations of all substances in the mixture. Complete the table showing the changes in the concentrations (\(x) and the final concentrations.
B. Write the equilibrium constant expression for the reaction. Substitute the known K value and the final concentrations to solve for x.
C. Calculate the final concentration of each substance in the reaction mixture. Check your answers by substituting these values into the equilibrium constant expression to obtain K.

Solution

A $[CO_2]_i = 0.632\ M$ and $[H_2]_i = 0.570\ M$. Again, x is defined as the change in the concentration of H_2O: $\Delta[H_2O] = +x$. Because 1 mol of CO is produced for every 1 mol of H_2O, the change in the concentration of CO is the same as the change in the concentration of H2O, so Δ[CO] = +x. Similarly, because 1 mol each of H_2 and CO_2 are consumed for every 1 mol of H_2O produced, $\Delta[H_2] = \Delta[CO_2] = -x$. The final concentrations are the sums of the initial concentrations and the changes in concentrations at equilibrium.

$$H_{2(g)} + CO_{2(g)} \rightleftharpoons H_2O_{(g)} + CO_{(g)}$$

ICE	$H_{2(g)}$	$CO_{2(g)}$	$H_2O_{(g)}$	$CO_{(g)}$
Initial	0.570	0.632	0	0
Change	$-x$	$-x$	$+x$	$+x$
Final	$(0.570 - x)$	$(0.632 - x)$	x	x

B We can now use the equilibrium equation and the known K value to solve for x:

$$K = \frac{[H_2O][CO]}{[H_2][CO_2]} = \frac{x^2}{(0.570 - x)(0.632 - x)} = 0.106$$

In contrast to Example **8.3.3**, however, there is no obvious way to simplify this expression. Thus we must expand the expression and multiply both sides by the denominator:

$$x^2 = 0.106(0.360 - 1.202x + x^2)$$

Collecting terms on one side of the equation,

$$0.894x^2 + 0.127x - 0.0382 = 0$$

This equation can be solved using the quadratic formula:

$$x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a} = \frac{-0.127 \pm \sqrt{(0.127)^2 - 4(0.894)(-0.0382)}}{2(0.894)}$$

$$x = 0.148 \text{ and } -0.290$$

Only the answer with the positive value has any physical significance, so $\Delta[H_2O] = \Delta[CO] = +0.148M$, and $\Delta[H_2] = \Delta[CO_2] = -0.148\ M$.

C The final concentrations of all species in the reaction mixture are as follows:

- $[H_2]_f[=[H_2]_i+\Delta[H_2]=0.570\ M-0.148\ M=0.422M$
- $[CO_2]_f=[CO_2]_i+\Delta[CO_2]=0.632\ M-0.148\ M=0.484M$
- $[H_2O]_f=[H_2O]_i+\Delta[H_2O]=0\ M+0.148\ M=0.148\ M$
- $[CO]_f=[CO]_i+\Delta[CO]=0M+0.148\ M=0.148M$

We can check our work by substituting these values into the equilibrium constant expression:

$$K=\frac{[H_2O][CO]}{[H_2][CO_2]}=\frac{(0.148)^2}{(0.422)(0.484)}=0.107$$

Because K is essentially the same as the value given in the problem, our calculations are confirmed.

? Exercise 8.3.4

The exercise in Example 8.3.1 showed the reaction of hydrogen and iodine vapor to form hydrogen iodide, for which $K=54$ at 425°C. If a sample containing 0.200 M H_2 and 0.0450 M I_2 is allowed to equilibrate at 425°C, what is the final concentration of each substance in the reaction mixture?

Answer

- $[H_I]_f=0.0882\ M$
- $[H_2]_f=0.156\ M$
- $[I_2]_f=9.2\times10^{-4}M$

In many situations it is not necessary to solve a quadratic (or higher-order) equation. Most of these cases involve reactions for which the equilibrium constant is either very small ($K\le10^{-3}$) or very large ($K\ge10^{3}$), which means that the change in the concentration (defined as x) is essentially negligible compared with the initial concentration of a substance. Knowing this simplifies the calculations dramatically, as illustrated in Example 8.3.5.

✔ Example 8.3.5

Atmospheric nitrogen and oxygen react to form nitric oxide:

$$N_{2(g)}+O_{2(g)}\rightleftharpoons2NO_{(g)}$$

with $K_p=2.0\times10^{-31}$ at 25°C.

What is the partial pressure of NO in equilibrium with N_2 and O_2 in the atmosphere (at 1 atm, $P_{N_2}=0.78\ atm$ and $P_{O_2}=0.21\ atm$?

Given: balanced equilibrium equation and values of K_p, P_{O_2}, and P_{N_2}

Asked for: partial pressure of NO

Strategy:

A. Construct a table and enter the initial partial pressures, the changes in the partial pressures that occur during the course of the reaction, and the final partial pressures of all substances.
B. Write the equilibrium equation for the reaction. Then substitute values from the table to solve for the change in concentration (\(x).
C. Calculate the partial pressure of NO. Check your answer by substituting values into the equilibrium equation and solving for K.

Solution

A Because we are given Kp and partial pressures are reported in atmospheres, we will use partial pressures. The initial partial pressure of O_2 is 0.21 atm and that of N_2 is 0.78 atm. If we define the change in the partial pressure of NO as $2x$, then the change in the partial pressure of O_2 and of N_2 is $-x$ because 1 mol each of N_2 and of O_2 is consumed for every 2 mol of NO

produced. Each substance has a final partial pressure equal to the sum of the initial pressure and the change in that pressure at equilibrium.

$$N_{2(g)} + O_{2(g)} \rightleftharpoons 2NO_{(g)}$$

ICE	P_{N_2}	P_{O_2}	P_{NO}
Initial	0.78	0.21	0
Change	$-x$	$-x$	$+2x$
Final	$(0.78-x)$	$(0.21-x)$	$2x$

B Substituting these values into the equation for the equilibrium constant,

$$K_p = \frac{(P_{NO})^2}{(P_{N_2})(P_{O_2})} = \frac{(2x)^2}{(0.78-x)(0.21-x)} = 2.0 \times 10^{-31}$$

In principle, we could multiply out the terms in the denominator, rearrange, and solve the resulting quadratic equation. In practice, it is far easier to recognize that an equilibrium constant of this magnitude means that the extent of the reaction will be very small; therefore, the x value will be negligible compared with the initial concentrations. If this assumption is correct, then to two significant figures, $(0.78-x) = 0.78$ and $(0.21-x) = 0.21$. Substituting these expressions into our original equation,

$$\frac{(2x)^2}{(0.78)(0.21)} = 2.0 \times 10^{-31}$$

$$\frac{4x^2}{0.16} = 2.0 \times 10^{-31}$$

$$x^2 = \frac{0.33 \times 10^{-31}}{4}$$

$$x = 9.1 \times 10^{-17}$$

C Substituting this value of x into our expressions for the final partial pressures of the substances,

- $P_{NO} = 2x\ atm = 1.8 \times 10^{-16}\ atm$
- $P_{N_2} = (0.78-x)\ atm = 0.78\ atm$
- $P_{O_2} = (0.21-x)\ atm = 0.21\ atm$

From these calculations, we see that our initial assumption regarding x was correct: given two significant figures, 2.0×10^{-16} is certainly negligible compared with 0.78 and 0.21. When can we make such an assumption? As a general rule, if x is less than about 5% of the total, or $10^{-3} > K > 10^{3}$, then the assumption is justified. Otherwise, we must use the quadratic formula or some other approach. The results we have obtained agree with the general observation that toxic NO, an ingredient of smog, does not form from atmospheric concentrations of N_2 and O_2 to a substantial degree at 25°C. We can verify our results by substituting them into the original equilibrium equation:

$$K_p = \frac{(P_{NO})^2}{(P_{N_2})(P_{O_2})} = \frac{(1.8 \times 10^{-16})^2}{(0.78)(0.21)} = 2.0 \times 10^{-31}$$

The final K_p agrees with the value given at the beginning of this example.

? Exercise 8.3.5

Under certain conditions, oxygen will react to form ozone, as shown in the following equation:

$$3O_{2(g)} \rightleftharpoons 2O_{3(g)}$$

with $K_p = 2.5 \times 10^{-59}$ at 25°C. What ozone partial pressure is in equilibrium with oxygen in the atmosphere ($P_{O_2} = 0.21\ atm$)?

Answer

$4.8 \times 10^{-31}\ atm$

Another type of problem that can be simplified by assuming that changes in concentration are negligible is one in which the equilibrium constant is very large ($K \geq 10^3$). A large equilibrium constant implies that the reactants are converted almost entirely to products, so we can assume that the reaction proceeds 100% to completion. When we solve this type of problem, we view the system as equilibrating from the products side of the reaction rather than the reactants side. This approach is illustrated in Example 8.3.6.

Example 8.3.6

The chemical equation for the reaction of hydrogen with ethylene (C_2H_4) to give ethane (C_2H_6) is as follows:

$$H_{2(g)} + C_2H_{4(g)} \overset{Ni}{\rightleftharpoons} C_2H_{6(g)}$$

with $K = 9.6 \times 10^{18}$ at 25°C. If a mixture of 0.200 M H_2 and 0.155 M C_2H_4 is maintained at 25°C in the presence of a powdered nickel catalyst, what is the equilibrium concentration of each substance in the mixture?

Given: balanced chemical equation, K, and initial concentrations of reactants

Asked for: equilibrium concentrations

Strategy:

A. Construct a table showing initial concentrations, concentrations that would be present if the reaction were to go to completion, changes in concentrations, and final concentrations.
B. Write the equilibrium constant expression for the reaction. Then substitute values from the table into the expression to solve for x (the change in concentration).
C. Calculate the equilibrium concentrations. Check your answers by substituting these values into the equilibrium equation.

Solution:

A From the magnitude of the equilibrium constant, we see that the reaction goes essentially to completion. Because the initial concentration of ethylene (0.155 M) is less than the concentration of hydrogen (0.200 M), ethylene is the limiting reactant; that is, no more than 0.155 M ethane can be formed from 0.155 M ethylene. If the reaction were to go to completion, the concentration of ethane would be 0.155 M and the concentration of ethylene would be 0 M. Because the concentration of hydrogen is greater than what is needed for complete reaction, the concentration of unreacted hydrogen in the reaction mixture would be 0.200 M − 0.155 M = 0.045 M. The equilibrium constant for the forward reaction is very large, so the equilibrium constant for the reverse reaction must be very small. The problem then is identical to that in Example 8.3.5. If we define $-x$ as the change in the ethane concentration for the reverse reaction, then the change in the ethylene and hydrogen concentrations is $+x$. The final equilibrium concentrations are the sums of the concentrations for the forward and reverse reactions.

$$H_{2(g)} + C_2H_{4(g)} \overset{Ni}{\rightleftharpoons} C_2H_{6(g)}$$

IACE	$[H_{2(g)}]$	$[C_2H_{4(g)}]$	$[C_2H_{6(g)}]$
Initial	0.200	0.155	0
Assuming 100% reaction	0.045	0	0.155
Change	$+x$	$+x$	$-x$
Final	$(0.045 + x)$	$(0 + x)$	$(0.155 - x)$

B Substituting values into the equilibrium constant expression,

$$K = \frac{[C_2H_6]}{[H_2][C_2H_4]} = \frac{0.155 - x}{(0.045 + x)x} = 9.6 \times 10^{18}$$

Once again, the magnitude of the equilibrium constant tells us that the equilibrium will lie far to the right as written, so the reverse reaction is negligible. Thus x is likely to be very small compared with either 0.155 M or 0.045 M, and the equation can be simplified ($(0.045 + x)$ = 0.045 and $(0.155 - x) = 0.155$) as follows:

$$K = \frac{0.155}{0.045x} = 9.6 \times 10^{18}$$

$$x = 3.6 \times 10^{-19}$$

C The small x value indicates that our assumption concerning the reverse reaction is correct, and we can therefore calculate the final concentrations by evaluating the expressions from the last line of the table:

- $[C_2H_6]_f = (0.155 - x)\ M = 0.155\ M$
- $[C_2H_4]_f = x\ M = 3.6 \times 10^{-19} M$
- $[H_2]_f = (0.045 + x)\ M = 0.045\ M$

We can verify our calculations by substituting the final concentrations into the equilibrium constant expression:

$$K = \frac{[C_2H_6]}{[H_2][C_2H_4]} = \frac{0.155}{(0.045)(3.6 \times 10^{-19})} = 9.6 \times 10^{18}$$

This K value agrees with our initial value at the beginning of the example.

? Exercise 8.3.6

Hydrogen reacts with chlorine gas to form hydrogen chloride:

$$H_{2(g)} + Cl_{2(g)} \rightleftharpoons 2HCl_{(g)}$$

with $K_p = 4.0 \times 10^{31}$ at 47°C. If a mixture of 0.257 M H_2 and 0.392 M Cl_2 is allowed to equilibrate at 47°C, what is the equilibrium composition of the mixture?

Answer

$[H_2]_f = 4.8 \times 10^{-32}\ M\ [Cl_2]_f = 0.135\ M\ [HCl]_f = 0.514\ M$



A Video Discussing Using ICE Tables to find Eq. Concentrations & Kc: Using ICE Tables to find Eq. Concentrations & Kc(opens in new window) [youtu.be]

Summary

Various methods can be used to solve the two fundamental types of equilibrium problems: (1) those in which we calculate the concentrations of reactants and products at equilibrium and (2) those in which we use the equilibrium constant and the initial concentrations of reactants to determine the composition of the equilibrium mixture. When an equilibrium constant is calculated

from equilibrium concentrations, molar concentrations or partial pressures are substituted into the equilibrium constant expression for the reaction. Equilibrium constants can be used to calculate the equilibrium concentrations of reactants and products by using the quantities or concentrations of the reactants, the stoichiometry of the balanced chemical equation for the reaction, and a tabular format to obtain the final concentrations of all species at equilibrium.

8.3: Calculating the Equilibrium Constant From Measured Equilibrium Concentrations is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **15.5: Calculating Equilibrium Constants** is licensed CC BY-NC-SA 3.0.

8.4: Heterogenous Equilibria - Reactions Involving Solids and Liquids

Learning Objectives

- To understand how different phases affect equilibria.

When the products and reactants of an equilibrium reaction form a single phase, whether gas or liquid, the system is a homogeneous equilibrium. In such situations, the concentrations of the reactants and products can vary over a wide range. In contrast, a system whose reactants, products, or both are in more than one phase is a heterogeneous equilibrium, such as the reaction of a gas with a solid or liquid.

As noted in the previous section, the equilibrium constant expression is actually a ratio of activities. To simplify the calculations in general chemistry courses, the activity of each substance in the reaction is often approximated using a ratio of the molarity of a substance compared to the standard state of that substance. For substances that are liquids or solids, the standard state is just the concentration of the substance within the liquid or solid. Because the molar concentrations of pure liquids and solids normally do not vary greatly with temperature, the ratio of the molarity to the standard state for substances that are liquids or solids always has a value of 1. For example, for a compound such as $CaF_2(s)$, the term going into the equilibrium expression is $[CaF_2]/[CaF_2]$ which cancels to unity. Thus, when the activities of the solids and liquids (including solvents) are incorporated into the equilibrium expression, they do not change the value.

Consider the following reaction, which is used in the final firing of some types of pottery to produce brilliant metallic glazes:

$$\mathrm{CO_2(g) + C(s) \rightleftharpoons 2\,CO(g)} \tag{8.4.1}$$

The glaze is created when metal oxides are reduced to metals by the product, carbon monoxide. The equilibrium constant expression for this reaction is as follows:

$$K = \frac{a_{CO}^2}{a_{CO_2} a_C} = \frac{[CO]^2}{[CO_2][1]} = \frac{[CO]^2}{[CO_2]} \tag{8.4.2}$$

The equilibrium constant for this reaction can also be written in terms of the partial pressures of the gases:

$$K_p = \frac{(P_{CO})^2}{P_{CO_2}} \tag{8.4.3}$$

Incorporating all the constant values into K' or K_p allows us to focus on the substances whose concentrations change during the reaction.

Although the activities of pure liquids or solids are not written explicitly in the equilibrium constant expression, these substances must be present in the reaction mixture for chemical equilibrium to occur. Whatever the concentrations of CO and CO_2, the system described in Equation 8.4.1 will reach chemical equilibrium only if a stoichiometric amount of solid carbon or excess solid carbon has been added so that some is still present once the system has reached equilibrium. As shown in Figure 8.4.1, it does not matter whether 1 g or 100 g of solid carbon is present; in either case, the composition of the gaseous components of the system will be the same at equilibrium.




Figure 8.4.2: Effect of the Amount of Solid Present on Equilibrium in a Heterogeneous Solid–Gas System. In the system, the equilibrium composition of the gas phase at a given temperature, 1000 K in this case, is the same whether a small amount of solid carbon (left) or a large amount (right) is present.

Example 8.4.1

Write each expression for K, incorporating all constants, and K_p for the following equilibrium reactions.

a. $\mathrm{PCl_3(l) + Cl_2(g) \rightleftharpoons PCl_5(s)}$
b. $\mathrm{Fe_3O_4(s) + 4H_2(g) \rightleftharpoons 3Fe(s) + 4H_2O(g)}$

Given: balanced equilibrium equations.

Asked for: expressions for K and K_p.

Strategy:

Find K by writing each equilibrium constant expression as the ratio of the concentrations of the products and reactants, each raised to its coefficient in the chemical equation. Then express K_p as the ratio of the partial pressures of the products and reactants, each also raised to its coefficient in the chemical equation.

Solution

This reaction contains a pure solid (PCl_5) and a pure liquid (PCl_3). Their activities are equal to 1, so when incorporated into the equilibrium constant expression, they do not change the value. So

$$K = \frac{1}{(1)[Cl_2]}$$

and

$$K_p = \frac{1}{(1)P_{Cl_2}}$$

This reaction contains two pure solids (Fe_3O_4 and Fe), which are each assigned a value of 1 in the equilibrium constant expressions:

$$K = \frac{(1)[H_2O]^4}{(1)[H_2]^4}$$

and

$$K_p = \frac{(1)(P_{H_2O})^4}{(1)(P_{H_2})^4}$$

? Exercise 8.4.1

Write the expressions for K and K_p for the following reactions.

a. $\mathrm{CaCO_3(s) \rightleftharpoons CaO(s) + CO_2(g)}$

b. $\underset{\textit{glucose}}{\mathrm{C_6H_{12}O_6(s)}} + \mathrm{6\,O_2(g) \rightleftharpoons 6\,CO_2(g) + 6\,H_2O(g)}$

Answer a

$K = [\mathrm{CO_2}]$ and $K_p = P_{\mathrm{CO_2}}$

Answer b

$K = \frac{[CO_2]^6[H_2O]^6}{[O_2]^6}$ and $K_p = \frac{(P_{CO_2})^6(P_{H_2O})^6}{(P_{O_2})^6}$

For reactions carried out in solution, the solvent is assumed to be pure, and therefore is assigned an activity equal to 1 in the equilibrium constant expression. The activities of the solutes are approximated by their molarities. The result is that the equilibrium constant expressions appear to only depend upon the concentrations of the solutes.

> *The activities of pure solids, pure liquids, and solvents are defined as having a value of '1'. Often, it is said that these activities are "left out" of equilibrium constant expressions. This is an unfortunate use of words. The activities are not "left out" of equilibrium constant expressions. Rather, because they have a value of '1', they do not change the value of the equilibrium constant when they are multiplied together with the other terms. The activities of the solutes are approximated by their molarities.*

Summary

An equilibrated system that contains products and reactants in a single phase is a homogeneous equilibrium; a system whose reactants, products, or both are in more than one phase is a heterogeneous equilibrium.

Contributors and Attributions

- Anonymous
- Modified by Tom Neils (Grand Rapids Community College)

8.4: Heterogenous Equilibria - Reactions Involving Solids and Liquids is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **15.4: Heterogeneous Equilibria** is licensed CC BY-NC-SA 3.0.

8.5: Le Châtelier's Principle- How a System at Equilibrium Responds to Disturbances

Learning Objectives

- Describe the ways in which an equilibrium system can be stressed
- Predict the response of a stressed equilibrium using Le Chatelier's principle

As we saw in the previous section, reactions proceed in both directions (reactants go to products and products go to reactants). We can tell a reaction is at equilibrium if the reaction quotient (Q) is equal to the equilibrium constant (K). We next address what happens when a system at equilibrium is disturbed so that Q is no longer equal to K. If a system at equilibrium is subjected to a perturbance or stress (such as a change in concentration) the position of equilibrium changes. Since this stress affects the concentrations of the reactants and the products, the value of Q will no longer equal the value of K. To re-establish equilibrium, the system will either shift toward the products (if ($Q \leq K$) or the reactants (if ($Q \geq K$) until Q returns to the same value as K. This process is described by Le Chatelier's principle.

Le Chatelier's principle

When a chemical system at equilibrium is disturbed, it returns to equilibrium by counteracting the disturbance. As described in the previous paragraph, the disturbance causes a change in Q; the reaction will shift to re-establish $Q = K$.

Predicting the Direction of a Reversible Reaction

Le Chatelier's principle can be used to predict changes in equilibrium concentrations when a system that is at equilibrium is subjected to a stress. However, if we have a mixture of reactants and products that have not yet reached equilibrium, the changes necessary to reach equilibrium may not be so obvious. In such a case, we can compare the values of Q and K for the system to predict the changes.

> *A chemical system at equilibrium can be **temporarily** shifted out of equilibrium by adding or removing one or more of the reactants or products. The concentrations of both reactants and products then undergo additional changes to return the system to equilibrium.*

The stress on the system in Figure **8.5.1** is the reduction of the equilibrium concentration of SCN^- (lowering the concentration of one of the reactants would cause Q to be larger than K). As a consequence, Le Chatelier's principle leads us to predict that the concentration of $Fe(SCN)^{2+}$ should decrease, increasing the concentration of SCN^- part way back to its original concentration, and increasing the concentration of Fe^{3+} above its initial equilibrium concentration.



Figure **8.5.1**: (a) The test tube contains 0.1 M Fe^{3+}. (b) Thiocyanate ion has been added to solution in (a), forming the red $Fe(SCN)^{2+}$ ion. $\mathbf{Fe^{3+}(aq) + SCN^-(aq) \rightleftharpoons Fe(SCN)^{2+}(aq)}$. (c) Silver nitrate has been added to the solution in (b), precipitating some of the SCN− as the white solid AgSCN. $\mathbf{Ag^+(aq) + SCN^-(aq) \rightleftharpoons AgSCN(s)}$. The decrease in the SCN− concentration shifts the first equilibrium in the solution to the left, decreasing the concentration (and lightening color) of the $Fe(SCN)^{2+}$. (credit: modification of work by Mark Ott).

The effect of a change in concentration on a system at equilibrium is illustrated further by the equilibrium of this chemical reaction:

$$\mathrm{H_2(g) + I_2(g) \rightleftharpoons 2\,HI(g)} \tag{8.5.1}$$

$$K_c = 50.0 \text{ at } 400^\circ\mathrm{C} \tag{8.5.2}$$

The numeric values for this example have been determined experimentally. A mixture of gases at 400 °C with $[\mathrm{H_2}] = [\mathrm{I_2}] = 0.221\ M$ and $[\mathrm{HI}] = 1.563\ M$ is at equilibrium; for this mixture, $Q_c = K_c = 50.0$. If $\mathrm{H_2}$ is introduced into the system so quickly that its concentration doubles before it begins to react (new $[\mathrm{H_2}] = 0.442\ M$), the reaction will shift so that a new equilibrium is reached, at which

- $[\mathrm{H_2}] = 0.374\ M$,
- $[\mathrm{I_2}] = 0.153\ M$, and
- $[\mathrm{HI}] = 1.692\ M$.

This gives:

$$\begin{aligned} Q_c &= \frac{[\mathrm{HI}]^2}{[\mathrm{H_2}][\mathrm{I_2}]} \\ &= \frac{(1.692)^2}{(0.374)(0.153)} \\ &= 50.0 = K_c \end{aligned}$$

We have stressed this system by introducing additional $\mathrm{H_2}$. The stress is relieved when the reaction shifts to the right, using up some (but not all) of the excess $\mathrm{H_2}$, reducing the amount of uncombined $\mathrm{I_2}$, and forming additional HI. **Le Chatelier's Principle (Changing Concentrations):** Le Chatelier's Principle (Changing Concentrations)(opens in new window) [youtu.be]



A Video Discussing Le Chatelier's Principle (Changing Concentrations): Le Chatelier's Principle (Changing Concentrations)(opens in new window) [youtu.be] (opens in new window)

Effect of Change in Pressure on Equilibrium

Sometimes we can change the position of equilibrium by changing the pressure of a system. However, changes in pressure have a measurable effect only in systems in which gases are involved, and then only when the chemical reaction produces a change in the total number of gas molecules in the system. An easy way to recognize such a system is to look for different numbers of moles of gas on the reactant and product sides of the equilibrium. While evaluating pressure (as well as related factors like volume), it is important to remember that equilibrium constants are defined with regard to concentration (for K_c) or partial pressure (for K_P). Some changes to total pressure, like adding an inert gas that is not part of the equilibrium, will change the total pressure but not the partial pressures of the gases in the equilibrium constant expression. Thus, addition of a gas not involved in the equilibrium will not perturb the equilibrium.

As we increase the pressure of a gaseous system at equilibrium, either by decreasing the volume of the system or by adding more of one of the components of the equilibrium mixture, we introduce a stress by increasing the partial pressures of one or more of the components. In accordance with Le Chatelier's principle, a shift in the equilibrium that reduces the total number of molecules per unit of volume will be favored because this relieves the stress. The reverse reaction would be favored by a decrease in pressure.

Consider what happens when we increase the pressure on a system in which $\mathbf{NO}$, $\mathbf{O_2}$, and $\mathbf{NO_2}$ are at equilibrium:

$$\mathbf{2\,NO\,(g) + O_2\,(g) \rightleftharpoons 2\,NO_2\,(g)} \tag{8.5.3}$$

The formation of additional amounts of $\mathbf{NO_2}$ decreases the total number of molecules in the system because each time two molecules of $\mathbf{NO_2}$ form, a total of three molecules of $\mathbf{NO}$ and $\mathbf{O_2}$ are consumed. This reduces the total pressure exerted by the system and reduces, but does not completely relieve, the stress of the increased pressure. On the other hand, a decrease in the pressure on the system favors decomposition of $\mathbf{NO_2}$ into $\mathbf{NO}$ and $\mathbf{O_2}$, which tends to restore the pressure.

Now consider this reaction:

$$\mathbf{N_2\,(g) + O_2\,(g) \rightleftharpoons 2\,NO\,(g)} \tag{8.5.4}$$

Because there is no change in the total number of molecules in the system during reaction, a change in pressure does not favor either formation or decomposition of gaseous nitrogen monoxide.



Le Chatelier’s Principle (Changes in Pressure or Volume):

Le Chatelier’s Principle (Changes in Pressure or Volume)(opens in new window) [youtu.be]

Effect of Change in Temperature on Equilibrium

Changing concentration or pressure perturbs an equilibrium because the reaction quotient is shifted away from the equilibrium value. Changing the temperature of a system at equilibrium has a different effect: A change in temperature actually changes the value of the equilibrium constant. However, we can qualitatively predict the effect of the temperature change by treating it as a stress on the system and applying Le Chatelier's principle.

When hydrogen reacts with gaseous iodine, heat is evolved.

$$\mathbf{H_2\,(g) + I_2\,(g) \rightleftharpoons 2\,HI\,(g)} \quad \Delta H = -9.4\ \text{kJ (exothermic)} \tag{8.5.5}$$

Because this reaction is exothermic, we can write it with heat as a product.

$$\mathbf{H_2\,(g) + I_2\,(g) \rightleftharpoons 2\,HI\,(g) + heat} \tag{8.5.6}$$

Increasing the temperature of the reaction increases the internal energy of the system. Thus, increasing the temperature has the effect of increasing the amount of one of the products of this reaction. The reaction shifts to the left to relieve the stress, and there is an increase in the concentration of H_2 and I_2 and a reduction in the concentration of HI. Lowering the temperature of this system reduces the amount of energy present, favors the production of heat, and favors the formation of hydrogen iodide.

When we change the temperature of a system at equilibrium, the equilibrium constant for the reaction changes. Lowering the temperature in the HI system increases the equilibrium constant: At the new equilibrium the concentration of HI has increased and the concentrations of H_2 and I_2 decreased. Raising the temperature decreases the value of the equilibrium constant, from 67.5 at 357 °C to 50.0 at 400 °C.

Temperature affects the equilibrium between $\mathbf{NO_2}$ and $\mathbf{N_2O_4}$ in this reaction

$$\mathbf{N_2O_4\,(g)} \rightleftharpoons \mathbf{2\,NO_2\,(g)} \quad \Delta H = 57.20\ \mathbf{kJ} \tag{8.5.7}$$

The positive ΔH value tells us that the reaction is endothermic and could be written

$$\mathbf{heat + N_2O_4\,(g)} \rightleftharpoons \mathbf{2\,NO_2\,(g)} \tag{8.5.8}$$

At higher temperatures, the gas mixture has a deep brown color, indicative of a significant amount of brown $\mathbf{NO_2}$ molecules. If, however, we put a stress on the system by cooling the mixture (withdrawing energy), the equilibrium shifts to the left to supply some of the energy lost by cooling. The concentration of colorless $\mathbf{N_2O_4}$ increases, and the concentration of brown $\mathbf{NO_2}$ decreases, causing the brown color to fade.

The overview of how different disturbances affect the reaction equilibrium properties is tabulated in Table 8.5.1.

Table 8.5.1: Effects of Disturbances of Equilibrium and K

Disturbance	Observed Change as Equilibrium is Restored	Direction of Shift	Effect on K
reactant added	added reactant is partially consumed	toward products	none
product added	added product is partially consumed	toward reactants	none
decrease in volume/increase in gas pressure	pressure decreases	toward side with fewer moles of gas	none
increase in volume/decrease in gas pressure	pressure increases	toward side with more moles of gas	none
temperature increase	heat is absorbed	toward products for endothermic, toward reactants for exothermic	changes
temperature decrease	heat is given off	toward reactants for endothermic, toward products for exothermic	changes

Example 8.5.1

Write an equilibrium constant expression for each reaction and use this expression to predict what will happen to the concentration of the substance in bold when the indicated change is made if the system is to maintain equilibrium.

a. $\mathbf{2}HgO_{(s)} \rightleftharpoons \mathbf{2}Hg_{(l)} + \mathbf{O_{2(g)}}$: the amount of HgO is doubled.
b. $NH_4HS_{(s)} \rightleftharpoons \mathbf{NH_{3(g)}} + H_2S_{(g)}$: the concentration of H_2S is tripled.
c. $\mathbf{n\text{-}butane_{(g)}} \rightleftharpoons isobutane_{(g)}$: the concentration of isobutane is halved.

Given: equilibrium systems and changes

Asked for: equilibrium constant expressions and effects of changes

Strategy:

Write the equilibrium constant expression, remembering that pure liquids and solids do not appear in the expression. From this expression, predict the change that must occur to maintain equilibrium when the indicated changes are made.

Solution:

Because $HgO_{(s)}$ and $Hg_{(l)}$ are pure substances, they do not appear in the equilibrium constant expression. Thus, for this reaction, $K = [O_2]$. The equilibrium concentration of O_2 is a constant and does not depend on the amount of HgO present. Hence adding more HgO will not affect the equilibrium concentration of O_2, so no compensatory change is necessary.

NH_4HS does not appear in the equilibrium constant expression because it is a solid. Thus $K = [NH_3][H_2S]$, which means that the concentrations of the products are inversely proportional. If adding H_2S triples the H_2S concentration, for example, then the NH_3 concentration must decrease by about a factor of 3 for the system to remain at equilibrium so that the product of the concentrations equals K.

For this reaction, $K = \frac{[isobutane]}{[n\text{-}butane]}$, so halving the concentration of isobutane means that the n-butane concentration must also decrease by about half if the system is to maintain equilibrium.

Exercise 8.5.1

Write an equilibrium constant expression for each reaction. What must happen to the concentration of the substance in bold when the indicated change occurs if the system is to maintain equilibrium?

a. $\mathbf{HBr}(g) + NaH(s) \rightleftharpoons NaBr(s) + \mathbf{H_2}(g)$: the concentration of **HBr** is decreased by a factor of 3.
b. $6\,Li(s) + \mathbf{N_2}(g) \rightleftharpoons 2\,Li_3N(s)$: the amount of **Li** is tripled.
c. $\mathbf{SO_2}(g) + Cl_2(g) \rightleftharpoons SO_2Cl_2(l)$: the concentration of $\mathbf{Cl_2}$ is doubled.

Answer a

$K = \frac{[H_2]}{[HBr]}$; $[H_2]$ must decrease by about a factor of 3.

Answer b

$K = \frac{1}{[N_2]}$; solid lithium does not appear in the equilibrium constant expression, so no compensatory change is necessary.

Answer c

$K = \frac{1}{[SO_2][Cl_2]}$; $[SO_2]$ must decrease by about half.



Le Chatelier's Principle (Changes in Temperature):

Le Chatelier's Principle (Changes in Temperature)(opens in new window) [youtu.be]

Catalysts Do Not Affect Equilibrium

As we learned during our study of kinetics, a catalyst can speed up the rate of a reaction. Though this increase in reaction rate may cause a system to reach equilibrium more quickly (by speeding up the forward and reverse reactions), a catalyst has no effect on the

value of an equilibrium constant nor on equilibrium concentrations. The interplay of changes in concentration or pressure, temperature, and the lack of an influence of a catalyst on a chemical equilibrium is illustrated in the industrial synthesis of ammonia from nitrogen and hydrogen according to the equation

$$N_2(g) + 3H_2(g) \rightleftharpoons 2NH_3(g) \tag{8.5.9}$$

A large quantity of ammonia is manufactured by this reaction. Each year, ammonia is among the top 10 chemicals, by mass, manufactured in the world. About 2 billion pounds are manufactured in the United States each year. Ammonia plays a vital role in our global economy. It is used in the production of fertilizers and is, itself, an important fertilizer for the growth of corn, cotton, and other crops. Large quantities of ammonia are converted to nitric acid, which plays an important role in the production of fertilizers, explosives, plastics, dyes, and fibers, and is also used in the steel industry.

Fritz Haber

Haber was born in Breslau, Prussia (presently Wroclaw, Poland) in December 1868. He went on to study chemistry and, while at the University of Karlsruhe, he developed what would later be known as the Haber process: the catalytic formation of ammonia from hydrogen and atmospheric nitrogen under high temperatures and pressures. For this work, Haber was awarded the 1918 Nobel Prize in Chemistry for synthesis of ammonia from its elements (Equation 8.5.9). The Haber process was a boon to agriculture, as it allowed the production of fertilizers to no longer be dependent on mined feed stocks such as sodium nitrate.



Figure 8.5.1: The work of Nobel Prize recipient Fritz Haber revolutionized agricultural practices in the early 20th century. His work also affected wartime strategies, adding chemical weapons to the artillery.

Currently, the annual production of synthetic nitrogen fertilizers exceeds 100 million tons and synthetic fertilizer production has increased the number of humans that arable land can support from 1.9 persons per hectare in 1908 to 4.3 in 2008. The availability of nitrogen is a strong limiting factor to the growth of plants. Despite accounting for 78% of air, diatomic nitrogen (N_2) is nutritionally unavailable to a majority of plants due the tremendous stability of the nitrogen-nitrogen triple bond. Therefore, the nitrogen must be converted to a more bioavailable form (this conversion is called nitrogen fixation). Legumes achieve this conversion at ambient temperature by exploiting bacteria equipped with suitable enzymes.

In addition to his work in ammonia production, Haber is also remembered by history as one of the fathers of chemical warfare. During World War I, he played a major role in the development of poisonous gases used for trench warfare. Regarding his role in these developments, Haber said, “During peace time a scientist belongs to the World, but during war time he belongs to his country.”[1] Haber defended the use of gas warfare against accusations that it was inhumane, saying that death was death, by whatever means it was inflicted. He stands as an example of the ethical dilemmas that face scientists in times of war and the double-edged nature of the sword of science.

Like Haber, the products made from ammonia can be multifaceted. In addition to their value for agriculture, nitrogen compounds can also be used to achieve destructive ends. Ammonium nitrate has also been used in explosives, including improvised explosive devices. Ammonium nitrate was one of the components of the bomb used in the attack on the Alfred P. Murrah Federal Building in downtown Oklahoma City on April 19, 1995.

Summary

Systems at equilibrium can be disturbed by changes to temperature, concentration, and, in some cases, volume and pressure; volume and pressure changes will disturb equilibrium if the number of moles of gas is different on the reactant and product sides of the reaction. The system's response to these disturbances is described by Le Chatelier's principle: The system will respond in a way

that counteracts the disturbance. Not all changes to the system result in a disturbance of the equilibrium. Adding a catalyst affects the rates of the reactions but does not alter the equilibrium, and changing pressure or volume will not significantly disturb systems with no gases or with equal numbers of moles of gas on the reactant and product side.

Footnotes

1. 1 Herrlich, P. “The Responsibility of the Scientist: What Can History Teach Us About How Scientists Should Handle Research That Has the Potential to Create Harm?” *EMBO Reports* 14 (2013): 759–764.

Glossary

Le Chatelier's principle

when a chemical system at equilibrium is disturbed, it returns to equilibrium by counteracting the disturbance

position of equilibrium

concentrations or partial pressures of components of a reaction at equilibrium (commonly used to describe conditions before a disturbance)

stress

change to a reaction's conditions that may cause a shift in the equilibrium

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

8.5: Le Châtelier’s Principle- How a System at Equilibrium Responds to Disturbances is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **15.7: Le Chatelier's Principle** is licensed CC BY-NC-SA 3.0.

CHAPTER OVERVIEW

9: Organic Chemistry

Template:HideTOC

9.1: Alkanes- Saturated Hydrocarbons
9.2: Alkenes and Alkynes
9.3: Hydrocarbon Reactions
9.4: Aromatic Hydrocarbons
9.5: Functional Groups
9.6: Alcohols
9.7: Aldehydes and Ketones
9.8: Carboxylic Acids and Esters
9.9: Amines

9: Organic Chemistry is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

9.1: Alkanes- Saturated Hydrocarbons

Learning Objectives

- To identify and name simple (straight-chain) alkanes given formulas and write formulas for straight-chain alkanes given their names.

We begin our study of organic chemistry with the hydrocarbons, the simplest organic compounds, which are composed of carbon and hydrogen atoms only. As we noted, there are several different kinds of hydrocarbons. They are distinguished by the types of bonding between carbon atoms and the properties that result from that bonding. Hydrocarbons with only carbon-to-carbon single bonds (C–C) and existing as a continuous chain of carbon atoms also bonded to hydrogen atoms are called alkanes (or saturated hydrocarbons). *Saturated*, in this case, means that each carbon atom is bonded to four other atoms (hydrogen or carbon)—the most possible; there are no double or triple bonds in the molecules.

> The word *saturated* has the same meaning for hydrocarbons as it does for the dietary fats and oils: the molecule has no carbon-to-carbon double bonds (C=C).

We previously introduced the three simplest alkanes—methane (CH_4), ethane (C_2H_6), and propane (C_3H_8) and they are shown again in Figure **9.1.1**.




Figure **9.1.1**: The Three Simplest Alkanes

The flat representations shown do not accurately portray bond angles or molecular geometry. Methane has a tetrahedral shape that chemists often portray with wedges indicating bonds coming out toward you and dashed lines indicating bonds that go back away from you. An ordinary solid line indicates a bond in the plane of the page. Recall that the VSEPR theory correctly predicts a tetrahedral shape for the methane molecule (Figure **9.1.2**).




Figure **9.1.2**: The Tetrahedral Methane Molecule

Methane (CH_4), ethane (C_2H_6), and propane (C_3H_8) are the beginning of a series of compounds in which any two members in a sequence differ by one carbon atom and two hydrogen atoms—namely, a CH_2 unit. The first 10 members of this series are given in Table **9.1.1**.

Table **9.1.1**: The First 10 Straight-Chain Alkanes

Name	Molecular Formula (C_nH_{2n+2})	Condensed Structural Formula	Number of Possible Isomers
methane	CH_4	CH_4	—
ethane	C_2H_6	CH_3CH_3	—
propane	C_3H_8	$CH_3CH_2CH_3$	—
butane	C_4H_{10}	$CH_3CH_2CH_2CH_3$	2
pentane	C_5H_{12}	$CH_3CH_2CH_2CH_2CH_3$	3
hexane	C_6H_{14}	$CH_3CH_2CH_2CH_2CH_2CH_3$	5
heptane	C_7H_{16}	$CH_3CH_2CH_2CH_2CH_2CH_2CH_3$	9
octane	C_8H_{18}	$CH_3CH_2CH_2CH_2CH_2CH_2CH_2CH_3$	18
nonane	C_9H_{20}	$CH_3CH_2CH_2CH_2CH_2CH_2CH_2CH_2CH_3$	35
decane	$C_{10}H_{22}$	$CH_3CH_2CH_2CH_2CH_2CH_2CH_2CH_2CH_2CH_3$	75

Consider the series in Figure **9.1.3**. The sequence starts with C_3H_8, and a CH_2 unit is added in each step moving up the series. Any family of compounds in which adjacent members differ from each other by a definite factor (here a CH_2 group) is called a homologous series. The members of such a series, called *homologs*, have properties that vary in a regular and predictable manner. The principle of *homology* gives organization to organic chemistry in much the same way that the periodic table gives organization to inorganic chemistry. Instead of a bewildering array of individual carbon compounds, we can study a few members of a homologous series and from them deduce some of the properties of other compounds in the series.




Figure **9.1.3**: Members of a Homologous Series. Each succeeding formula incorporates one carbon atom and two hydrogen atoms more than the previous formula.

The principle of homology allows us to write a general formula for alkanes: C_nH_{2n+2}. Using this formula, we can write a molecular formula for any alkane with a given number of carbon atoms. For example, an alkane with eight carbon atoms has the molecular formula $C_8H_{(2\times 8)+2} = C_8H_{18}$.

Key Takeaway

- Simple alkanes exist as a homologous series, in which adjacent members differ by a CH_2 unit.

9.1: Alkanes- Saturated Hydrocarbons is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.


- **12.2: Structures and Names of Alkanes** by Anonymous is licensed CC BY-NC-SA 3.0. Original source: https://2012books.lardbucket.org/books/introduction-to-chemistry-general-organic-and-biological.

9.2: Alkenes and Alkynes

Learning Objectives

- To name alkenes given formulas and write formulas for alkenes given names.

As noted before, alkenes are hydrocarbons with carbon-to-carbon double bonds ($R_2C{=}CR_2$) and alkynes are hydrocarbons with carbon-to-carbon triple bonds (R–C≡C–R). Collectively, they are called unsaturated hydrocarbons because they have fewer hydrogen atoms than does an alkane with the same number of carbon atoms, as is indicated in the following general formulas:




Some representative alkenes—their names, structures, and physical properties—are given in Table **9.2.1**.

Table **9.2.1**: Physical Properties of Some Selected Alkenes

IUPAC Name	Molecular Formula	Condensed Structural Formula	Melting Point (°C)	Boiling Point (°C)
ethene	C_2H_4	$CH_2{=}CH_2$	–169	–104
propene	C_3H_6	$CH_2{=}CHCH_3$	–185	–47
1-butene	C_4H_8	$CH_2{=}CHCH_2CH_3$	–185	–6
1-pentene	C_5H_{10}	$CH_2{=}CH(CH_2)_2CH_3$	–138	30
1-hexene	C_6H_{12}	$CH_2{=}CH(CH_2)_3CH_3$	–140	63
1-heptene	C_7H_{14}	$CH_2{=}CH(CH_2)_4CH_3$	–119	94
1-octene	C_8H_{16}	$CH_2{=}CH(CH_2)_5CH_3$	–102	121

We used only condensed structural formulas in Table **9.2.1**. Thus, $CH_2{=}CH_2$ stands for



The double bond is shared by the two carbons and does not involve the hydrogen atoms, although the condensed formula does not make this point obvious. Note that the molecular formula for ethene is C_2H_4, whereas that for ethane is C_2H_6.

The first two alkenes in Table **9.2.1**, ethene and propene, are most often called by their common names—ethylene and propylene, respectively (Figure **9.2.1**). Ethylene is a major commercial chemical. The US chemical industry produces about 25 billion kilograms of ethylene annually, more than any other synthetic organic chemical. More than half of this ethylene goes into the manufacture of polyethylene, one of the most familiar plastics. Propylene is also an important industrial chemical. It is converted to plastics, isopropyl alcohol, and a variety of other products.





Figure **9.2.1**: Ethene and Propene. The ball-and-spring models of ethene/ethylene (a) and propene/propylene (b) show their respective shapes, especially bond angles.

Although there is only one alkene with the formula C_2H_4 (ethene) and only one with the formula C_3H_6 (propene), there are several alkenes with the formula C_4H_8.


Here are some basic rules for naming alkenes from the International Union of Pure and Applied Chemistry (IUPAC):


1. The longest chain of carbon atoms *containing the double bond* is considered the parent chain. It is named using the same stem as the alkane having the same number of carbon atoms but ends in *-ene* to identify it as an alkene. Thus the compound CH_2=$CHCH_3$ is *propene*.
2. If there are four or more carbon atoms in a chain, we must indicate the position of the double bond. The carbons atoms are numbered so that the first of the two that are doubly bonded is given the lower of the two possible numbers.The compound CH_3CH=$CHCH_2CH_3$, for example, has the double bond between the second and third carbon atoms. Its name is 2-pentene (not 3-pentene).
3. Substituent groups are named as with alkanes, and their position is indicated by a number. Thus, the structure below is 5-methyl-2-hexene. Note that the numbering of the parent chain is always done in such a way as to give the double bond the lowest number, even if that causes a substituent to have a higher number. *The double bond always has priority in numbering.*



Example 9.2.1

Name each compound.

a. 

b. 

Solution


a. The longest chain containing the double bond has five carbon atoms, so the compound is a *pentene* (rule 1). To give the first carbon atom of the double bond the lowest number (rule 2), we number from the left, so the compound is a 2-pentene. There is a methyl group on the fourth carbon atom (rule 3), so the compound's name is 4-methyl-2-pentene.

b. The longest chain containing the double bond has five carbon atoms, so the parent compound is a *pentene* (rule 1). To give the first carbon atom of the double bond the lowest number (rule 2), we number from the left, so the compound is a 2-pentene. There is a methyl group on the third carbon atom (rule 3), so the compound's name is 3-methyl-2-pentene.

Exercise 9.2.1

Name each compound.

a. $CH_3CH_2CH_2CH_2CH_2CH{=}CHCH_3$

b. 

Answer

Just as there are cycloalkanes, there are *cycloalkenes*. These compounds are named like alkenes, but with the prefix *cyclo-* attached to the beginning of the parent alkene name.

Example 9.2.2


Draw the structure for each compound.

a. 3-methyl-2-pentene
b. cyclohexene


Solution

a.

First write the parent chain of five carbon atoms: C–C–C–C–C. Then add the double bond between the second and third carbon atoms:




Now place the methyl group on the third carbon atom and add enough hydrogen atoms to give each carbon atom a total of four bonds.



b

First, consider what each of the three parts of the name means. *Cyclo* means a ring compound, *hex* means 6 carbon atoms, and *-ene* means a double bond.



Exercise 9.2.2

Draw the structure for each compound.

a. 2-ethyl-1-hexene
b. cyclopentene

Key Takeaway

- Alkenes are hydrocarbons with a carbon-to-carbon double bond.

9.2: Alkenes and Alkynes is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.


- **13.1: Alkenes- Structures and Names** by Anonymous is licensed CC BY-NC-SA 3.0. Original source: https://2012books.lardbucket.org/books/introduction-to-chemistry-general-organic-and-biological.

9.3: Hydrocarbon Reactions

Learning Objectives

- To identify the main chemical properties of alkanes.

Alkane molecules are nonpolar and therefore generally do not react with ionic compounds such as most laboratory acids, bases, oxidizing agents, or reducing agents. Consider butane as an example:



Butane plus O H superscript negative sign yields no reaction. There is also no reaction of butane with H superscript positive sign and Mn O subscript 4 superscript negative sign.

Neither positive ions nor negative ions are attracted to a nonpolar molecule. In fact, the alkanes undergo so few reactions that they are sometimes called *paraffins*, from the Latin *parum affinis*, meaning "little affinity."

Two important reactions that the alkanes do undergo are combustion and halogenation. Nothing happens when alkanes are merely mixed with oxygen (O_2) at room temperature, but when a flame or spark provides the activation energy, a highly exothermic combustion reaction proceeds vigorously. For methane (CH_4), the reaction is as follows:

$$CH_4 + 2\,O_2 \rightarrow CO_2 + 2\,H_2O + \text{heat}$$

If the reactants are adequately mixed and there is sufficient oxygen, the only products are carbon dioxide (CO_2), water (H_2O), and heat—heat for cooking foods, heating homes, and drying clothes. Because conditions are rarely ideal, however, other products are frequently formed. When the oxygen supply is limited, carbon monoxide (CO) is a by-product:

$$2\,CH_4 + 3\,O_2 \rightarrow 2\,CO + 4\,H_2O$$

This reaction is responsible for dozens of deaths each year from unventilated or improperly adjusted gas heaters. (Similar reactions with similar results occur with kerosene heaters.)

Alkanes also react with the halogens chlorine (Cl_2) and bromine (Br_2) in the presence of ultraviolet light or at high temperatures to yield chlorinated and brominated alkanes. For example, chlorine reacts with excess methane (CH_4) to give methyl chloride (CH_3Cl).

$$CH_4 + Cl_2 \rightarrow CH_3Cl + HCl$$

With more chlorine, a mixture of products is obtained: CH_3Cl, CH_2Cl_2, $CHCl_3$, and CCl_4. Fluorine (F_2), the lightest halogen, combines explosively with most hydrocarbons. Iodine (I_2) is relatively unreactive. Fluorinated and iodinated alkanes are produced by indirect methods.

Key Takeaway

- Alkanes react with oxygen (combustion) and with halogens (halogenation).

9.3: Hydrocarbon Reactions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.


- **12.7: Chemical Properties of Alkanes** by Anonymous is licensed CC BY-NC-SA 3.0. Original source: https://2012books.lardbucket.org/books/introduction-to-chemistry-general-organic-and-biological.

9.4: Aromatic Hydrocarbons

Textbook, Hydrocarbons

Textbook, Hydrocarbons

Benzene, C_6H_6, is the simplest member of a large family of hydrocarbons, called aromatic hydrocarbons. These compounds contain ring structures and exhibit bonding that must be described using the resonance hybrid concept of valence bond theory or the delocalization concept of molecular orbital theory. (To review these concepts, refer to the earlier chapters on chemical bonding). The resonance structures for benzene, C_6H_6, are:



Benzene is shown as a hexagonal ring. There are three double bonds in total. The left structure shows double bonds occupying three sides of the hexagon. A double sided arrow points to the right structure which has three double bonds which occupy the three previously unoccupied sides on the left.

Valence bond theory describes the benzene molecule and other planar aromatic hydrocarbon molecules as hexagonal rings of sp^2-hybridized carbon atoms with the unhybridized p orbital of each carbon atom perpendicular to the plane of the ring. Three valence electrons in the sp^2 hybrid orbitals of each carbon atom and the valence electron of each hydrogen atom form the framework of σ bonds in the benzene molecule. The fourth valence electron of each carbon atom is shared with an adjacent carbon atom in their unhybridized p orbitals to yield the π bonds. Benzene does not, however, exhibit the characteristics typical of an alkene. Each of the six bonds between its carbon atoms is equivalent and exhibits properties that are intermediate between those of a C–C single bond and a C = C double bond. To represent this unique bonding, structural formulas for benzene and its derivatives are typically drawn with single bonds between the carbon atoms and a circle within the ring as shown in Figure **9.4.10**.





Figure **9.4.10**: This condensed formula shows the unique bonding structure of benzene.
A six carbon hexagonal ring structural formula is shown. Each C has an H atom beside it. A circle is at the center of the ring.

There are many derivatives of benzene. The hydrogen atoms can be replaced by many different substituents. Aromatic compounds more readily undergo substitution reactions than addition reactions; replacement of one of the hydrogen atoms with another substituent will leave the delocalized double bonds intact. The following are typical examples of substituted benzene derivatives:




Toluene has one of the H replaced by C H subscript 3 molecule. Xylene has 2 of the H atoms replaced by two C H subscript 3 molecules respectively. Styrene has one of the H atom replaced C H double bond C H subscript 2.

Toluene and xylene are important solvents and raw materials in the chemical industry. Styrene is used to produce the polymer polystyrene.

Structure of Aromatic Hydrocarbons


One possible isomer created by a substitution reaction that replaces a hydrogen atom attached to the aromatic ring of toluene with a chlorine atom is shown here. Draw two other possible isomers in which the chlorine atom replaces a different hydrogen atom attached to the aromatic ring:



A hexagonal structure of benzene is shown with one of the H replaced by a chlorine atom and another H replaced by C H subscript 3. These two substitutions are apart by 1 carbon atom. Two structures are shown, one shows all the C and H in the ring written out, while the other omits it.

Solution

Since the six-carbon ring with alternating double bonds is necessary for the molecule to be classified as aromatic, appropriate isomers can be produced only by changing the positions of the chloro-substituent relative to the methyl-substituent:




A hexagonal structure of benzene is shown with one of the H replaced by a chlorine atom and another H replaced by C H subscript 3. There are two of these isomers. The first isomer has these two substitutions adjacent to one another while the other are apart by 2 carbons. Two structures are shown for each isomer, one shows all the C and H in the ring written out, while the other omits it.

Exercise 9.4.7

Draw three isomers of a six-membered aromatic ring compound substituted with two bromines.

Answer



A hexagonal structure of benzene is shown with two of the H replaced by two bromine atoms. Three of these isomers are shown. The first isomer has these two substitutions adjacent to one another, the next isomer has these two bromines 1 carbon apart and the final isomer has two bromines that are two carbons apart. Two structures are shown for each isomer, one shows all the C and H in the ring written out, while the other omits it.

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).




9.4: Aromatic Hydrocarbons is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

9.5: Functional Groups

Learning Objectives

- To know the major classes of organic compounds and identify important functional groups.

You were previously introduced to several structural units that chemists use to classify organic compounds and predict their reactivities. These functional groups, which determine the chemical reactivity of a molecule under a given set of conditions, can consist of a single atom (such as Cl) or a group of atoms (such as CO_2H). The major families of organic compounds are characterized by their functional groups. Figure **9.5.1** summarizes five families introduced in earlier chapters, gives examples of compounds that contain each functional group, and lists the suffix or prefix used in the systematic nomenclature of compounds that contain each functional group.


Class	General Formula	Example	Common Name (Systematic Name)	Common Suffix/Prefix (Systematic)
Hydrocarbons				
Alkanes	RH	CH_3CH_3	ethane	-ane
Alkenes	$RR'C{=}CR''R'''$	$H_2C{=}CH_2$	ethylene (ethene)	-ene
Alkynes	$RC{\equiv}CR'$	$HC{\equiv}CH$	acetylene (ethyne)	(-yne)
Arenes	ArH[a]		benzene	-ene
Halogen-Containing Compounds				
Alkyl halides	RX	CH_3CH_2Cl	ethyl chloride (chloroethane)	halide (halo-)
Aryl halides	ArX[a]		chlorobenzene	halo-
Oxygen-Containing Compounds				
Alcohols	ROH[a]	CH_3CH_2OH	ethyl alcohol (ethanol)	-ol
Phenols	ArOH[b]		phenol	-ol
Ethers	ROR′	$H_3CH_2COCH_2CH_3$	diethyl ether	ether
Aldehydes	RCHO	$CH_3\overset{O}{\overset{\|}{C}}H$	acetaldehyde (ethanal)	-aldehyde (-al)
Ketones	RR′C=O	$CH_3\overset{O}{\overset{\|}{C}}CH_3$	acetone (2-propanone)	-one
Carboxylic acids	RCO_2H	$CH_3\overset{O}{\overset{\|}{C}}OH$	acetic acid (ethanoic acid)	-ic acid (-oic acid)
Carboxylic Acid Derivatives				
Esters	RCO_2R'	$CH_3\overset{O}{\overset{\|}{C}}OCH_3$	methyl acetate (methyl ethanoate)	-ate (-oate)
Amides	RCONHR′	$CH_3\overset{O}{\overset{\|}{C}}NHCH_3$	*N*-methylacetamide	-amide
Nitrogen-Containing Compounds				
Amines	RNH_2, RNHR′, RNR′R″	$CH_3CH_2NH_2$	ethylamine	-amine
Nitriles	$RC{\equiv}N$	$H_3CC{\equiv}N$	acetonitrile	-nitrile
Nitro compounds	$ArNO_2$[a]		nitrobenzene	nitro-

[a] R indicates an alkyl group [b] Ar indicates an aryl group

Figure 9.5.1: Major Classes of Organic Compounds

The first family listed in Figure 9.5.1 is the hydrocarbons. These include alkanes, with the general molecular formula C_nH_{2n+2} where n is an integer; alkenes, represented by C_nH_{2n}; alkynes, represented by C_nH_{2n-2}; and arenes. Halogen-substituted alkanes, alkenes, and arenes form a second major family of organic compounds, which include the alkyl halides and the aryl halides. Oxygen-containing organic compounds, a third family, may be divided into two main types: those that contain at least one C–O bond, which include alcohols, phenols (derivatives of benzene), and ethers, and those that contain a carbonyl group (C=O), which include aldehydes, ketones, and carboxylic acids. Carboxylic acid derivatives, the fourth family listed, are compounds in which the OH of the $–CO_2H$ functional group is replaced by either an alkoxy (–OR) group, producing an ester, or by an amido (–NRR′, where R and R′ can be H and/or alkyl groups), forming an amide. Nitrogen-containing organic compounds, the fifth family, include amines; nitriles, which have a C≡N bond; and nitro compounds, which contain the $–NO_2$ group.

The systematic nomenclature of organic compounds indicates the positions of substituents using the lowest numbers possible to identify their locations in the carbon chain of the parent compound. If two compounds have the same systematic name, then they are the same compound. Although systematic names are preferred because they are unambiguous, many organic compounds are known by their common names rather than their systematic names. Common nomenclature uses the prefix form—for a compound that contains no carbons other than those in the functional group, and acet—for those that have one carbon atom in addition [two in the case of acetone, $(CH_3)_2C=O$]. Thus methanal and ethanal, respectively, are the systematic names for formaldehyde and acetaldehyde.



Recall that in the systematic nomenclature of aromatic compounds, the positions of groups attached to the aromatic ring are indicated by numbers, starting with 1 and proceeding around the ring in the direction that produces the lowest possible numbers. For example, the position of the first CH_3 group in dimethyl benzene is indicated with a 1, but the second CH_3 group, which can be placed in any one of three positions, produces 1,2-dimethylbenzene, 1,3-dimethylbenzene, or 1,4-dimethylbenzene (Figure 9.5.2). In common nomenclature, in contrast, the prefixes ortho-, meta-, and para- are used to describe the relative positions of groups attached to an aromatic ring. If the CH_3 groups in dimethylbenzene, whose common name is xylene, are adjacent to each other, the compound is commonly called ortho-xylene, abbreviated o-xylene. If they are across from each other on the ring, the compound is commonly called para-xylene or p-xylene. When the arrangement is intermediate between those of ortho- and para- compounds, the name is meta-xylene or m-xylene.




Prefix	Positions of Methyl Groups	Example	Common Name (Systematic Name)
ortho-	1,2		*o*-xylene (1,2-dimethylbenzene)
meta-	1,3		*m*-xylene (1,3-dimethylbenzene)
para-	1,4		*p*-xylene (1,4-dimethylbenzene)

Figure 9.5.2: Common Nomenclature for Aromatic Ring Substitutions

We begin our discussion of the structure and reactivity of organic compounds by exploring structural variations in the simple saturated hydrocarbons known as alkanes. These compounds serve as the scaffolding to which the various functional groups are most often attached.

Summary

Functional groups determine the chemical reactivity of an organic molecule. Functional groups are structural units that determine the chemical reactivity of a molecule under a given set of conditions. Organic compounds are classified into several major categories based on the functional groups they contain. In the systematic names of organic compounds, numbers indicate the positions of functional groups in the basic hydrocarbon framework. Many organic compounds also have common names, which use the prefix form—for a compound that contains no carbons other than those in the functional group and acet—for those that have one additional carbon atom.

Conceptual Problems

1. Can two substances have the same systematic name and be different compounds?
2. Is a carbon–carbon multiple bond considered a functional group?

9.5: Functional Groups is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **23.2: Functional Groups and Classes of Organic Compounds** by Anonymous is licensed CC BY-NC-SA 3.0.

9.6: Alcohols


Learning Objectives

- Identify the general structure for an alcohol.
- Identify the structural feature that classifies alcohols as primary, secondary, or tertiary.
- Name alcohols with both common names and IUPAC names

An alcohol is an organic compound with a hydroxyl (OH) functional group on an aliphatic carbon atom. Because OH is the functional group of all alcohols, we often represent alcohols by the general formula ROH, where R is an alkyl group. Alcohols are common in nature. Most people are familiar with ethyl alcohol (ethanol), the active ingredient in alcoholic beverages, but this compound is only one of a family of organic compounds known as alcohols. The family also includes such familiar substances as cholesterol and the carbohydrates. Methanol (CH_3OH) and ethanol (CH_3CH_2OH) are the first two members of the homologous series of alcohols.

Nomenclature of Alcohols

Alcohols with one to four carbon atoms are frequently called by common names, in which the name of the alkyl group is followed by the word *alcohol*:



Structural formula of methyl alcohol, ethyl alcohol, propyl alcohol, and isopropyl alcohol with the methyl, ethyl propyl, and isopropyl groups highlighted in green.

According to the International Union of Pure and Applied Chemistry (IUPAC), alcohols are named by changing the ending of the parent alkane name to *-ol*. Here are some basic IUPAC rules for naming alcohols:


1. The longest continuous chain (LCC) of carbon atoms containing the OH group is taken as the parent compound—an alkane with the same number of carbon atoms. The chain is numbered from the end nearest the OH group.
2. The number that indicates the position of the OH group is prefixed to the name of the parent hydrocarbon, and the *-e* ending of the parent alkane is replaced by the suffix *-ol*. (In cyclic alcohols, the carbon atom bearing the OH group is designated C1, but the 1 is not used in the name.) Substituents are named and numbered as in alkanes.
3. If more than one OH group appears in the same molecule (polyhydroxy alcohols), suffixes such as *-diol* and *-triol* are used. In these cases, the *-e* ending of the parent alkane is retained.

Figure **9.6.1** shows some examples of the application of these rules.

Structures of 2 methylbutan-2-ol, 3 5-dimethylhexan-1-ol, 6 methylheptan-3-ol, 2 bromo 5 chlorocyclopentanol are shown to highlight rules 1 and 2. 1 2 ethanediol and propane 1 2 3 triol are shown to highlight rule 3
Figure **9.6.1**: IUPAC Rules for Alcohols. The names and structures of some alcohols demonstrate the use of IUPAC rules.

Example 9.6.1

Give the IUPAC name for each compound.


a. 

From left to right, there are ten carbon on the alkane straight chain with methyl groups emerging from carbon 3 and 5 and a hydroxyl group on carbon 8.

- $HOCH_2CH_2CH_2CH_2CH_2OH$


Solution

a. Ten carbon atoms in the LCC makes the compound a derivative of decane (rule 1), and the OH on the third carbon atom makes it a 3-decanol (rule 2).




The carbon atoms are numbered from the end closest to the OH group. That fixes the two methyl (CH_3) groups at the sixth and eighth positions. The name is 6,8-dimethyl-3-decanol (not 3,5-dimethyl-8-decanol).


b. Five carbon atoms in the LCC make the compound a derivative of pentane. Two OH groups on the first and fifth carbon atoms make the compound a diol and give the name 1,5-pentanediol (rule 3).



? Exercise 9.6.1

Give the IUPAC name for each compound.

a. 

- 

✔ Example 9.6.2


Draw the structure for each compound.

a. 2-hexanol
b. 3-methyl-2-pentanol


Solution

a. The ending *-ol* indicates an alcohol (the OH functional group), and the *hex-* stem tells us that there are six carbon atoms in the LCC. We start by drawing a chain of six carbon atoms: –C–C–C–C–C–C–.


The 2 indicates that the OH group is attached to the second carbon atom.



Finally, we add enough hydrogen atoms to give each carbon atom four bonds.



- The numbers indicate that there is a methyl (CH_3) group on the third carbon atom and an OH group on the second carbon atom.



? Exercise 9.6.2

Draw the structure for each compound.

a. 3-heptanol

- 2-methyl-3-hexanol

Classification of Alcohols

Some of the properties of alcohols depend on the number of carbon atoms attached to the specific carbon atom that is attached to the OH group. Alcohols can be grouped into three classes on this basis.

- A primary (1°) alcohol is one in which the carbon atom (in red) with the OH group is attached to *one* other carbon atom (in blue). Its general formula is RCH_2OH.



- A secondary (2°) alcohol is one in which the carbon atom (in red) with the OH group is attached to *two* other carbon atoms (in blue). Its general formula is R_2CHOH.



- A tertiary (3°) alcohol is one in which the carbon atom (in red) with the OH group is attached to *three* other carbon atoms (in blue). Its general formula is R_3COH.





Table **9.6.1** names and classifies some of the simpler alcohols. Some of the common names reflect a compound's classification as secondary (*sec*-) or tertiary (*tert*-). These designations are not used in the IUPAC nomenclature system for alcohols. Note that there are four butyl alcohols in the table, corresponding to the four butyl groups: the butyl group ($CH_3CH_2CH_2CH_2$) discussed before, and three others:



Table **9.6.1**: Classification and Nomenclature of Some Alcohols

Condensed Structural Formula	Class of Alcohol	Common Name	IUPAC Name
CH_3OH	—	methyl alcohol	methanol
CH_3CH_2OH	primary	ethyl alcohol	ethanol
$CH_3CH_2CH_2OH$	primary	propyl alcohol	1-propanol
$(CH_3)_2CHOH$	secondary	isopropyl alcohol	2-propanol
$CH_3CH_2CH_2CH_2OH$	primary	butyl alcohol	1-butanol
$CH_3CH_2CHOHCH_3$	secondary	*sec*-butyl alcohol	2-butanol
$(CH_3)_2CHCH_2OH$	primary	isobutyl alcohol	2-methyl-1-propanol
$(CH_3)_3COH$	tertiary	*tert*-butyl alcohol	2-methyl-2-propanol
	secondary	cyclohexyl alcohol	cyclohexanol

Summary

In the IUPAC system, alcohols are named by changing the ending of the parent alkane name to *-ol*. Alcohols are classified according to the number of carbon atoms attached to the carbon atom that is attached to the OH group.

Learning Objectives

- Explain why the boiling points of alcohols are higher than those of ethers and alkanes of similar molar masses.
- Explain why alcohols and ethers of four or fewer carbon atoms are soluble in water while comparable alkanes are not soluble.

Alcohols can be considered derivatives of water (H_2O; also written as HOH).



Like the H–O–H bond in water, the R–O–H bond is bent, and alcohol molecules are polar. This relationship is particularly apparent in small molecules and reflected in the physical and chemical properties of alcohols with low molar mass. Replacing a hydrogen atom from an alkane with an OH group allows the molecules to associate through hydrogen bonding (Figure **9.6.1**).




Figure **9.6.1**: Intermolecular Hydrogen Bonding in Methanol. The OH groups of alcohol molecules make hydrogen bonding possible.

Recall that physical properties are determined to a large extent by the type of intermolecular forces. Table **9.6.1** lists the molar masses and the boiling points of some common compounds. The table shows that substances with similar molar masses can have quite different boiling points.

Table **9.6.1**: Comparison of Boiling Points and Molar Masses

Formula	Name	Molar Mass	Boiling Point (°C)
CH_4	methane	16	–164
HOH	water	18	100
C_2H_6	ethane	30	–89
CH_3OH	methanol	32	65
C_3H_8	propane	44	–42
CH_3CH_2OH	ethanol	46	78
C_4H_{10}	butane	58	–1
$CH_3CH_2CH_2OH$	1-propanol	60	97

Alkanes are nonpolar and are thus associated only through relatively weak dispersion forces. Alkanes with one to four carbon atoms are gases at room temperature. In contrast, even methanol (with one carbon atom) is a liquid at room temperature. Hydrogen bonding greatly increases the boiling points of alcohols compared to hydrocarbons of comparable molar mass. The boiling point is a rough measure of the amount of energy necessary to separate a liquid molecule from its nearest neighbors. If the molecules interact through hydrogen bonding, a relatively large quantity of energy must be supplied to break those intermolecular attractions. Only then can the molecule escape from the liquid into the gaseous state.

Alcohols can also engage in hydrogen bonding with water molecules (Figure **9.6.2**). Thus, whereas the hydrocarbons are insoluble in water, alcohols with one to three carbon atoms are completely soluble. As the length of the chain increases, however, the solubility of alcohols in water decreases; the molecules become more like hydrocarbons and less like water. The alcohol 1-decanol ($CH_3CH_2CH_2CH_2CH_2CH_2CH_2CH_2CH_2OH$) is essentially insoluble in water. We frequently find that the borderline of solubility in a family of organic compounds occurs at four or five carbon atoms.




Figure **9.6.2**: Hydrogen Bonding between Methanol Molecules and Water Molecules. Hydrogen bonding between the OH of methanol and water molecules accounts for the solubility of methanol in water.

Summary

Alcohols have higher boiling points than do ethers and alkanes of similar molar masses because the OH group allows alcohol molecules to engage in hydrogen bonding. Alcohols of four or fewer carbon atoms are soluble in water because the alcohol molecules engage in hydrogen bonding with water molecules; comparable alkane molecules cannot engage in hydrogen bonding.

Learning Objectives

1. Give two major types of reactions of alcohols.
2. Describe the result of the oxidation of a primary alcohol.
3. Describe the result of the oxidation of a secondary alcohol.

Chemical reactions in alcohols occur mainly at the functional group, but some involve hydrogen atoms attached to the OH-bearing carbon atom or to an adjacent carbon atom. Of the three major kinds of alcohol reactions, which are summarized in Figure **9.6.1**, two—dehydration and oxidation—are considered here. The third reaction type—esterification—is covered elsewhere.





Figure **9.6.1**: Reactions of Alcohols. Oxidation and dehydration of alcohols are considered here.
A flow diagram of three possible reactions of an alcohol. The final products of the reactions are also shown at the end of the flow diagram.

Dehydration


As noted in Figure **9.6.1**, an alcohol undergoes dehydration in the presence of a catalyst to form an alkene and water. The reaction removes the OH group from the alcohol carbon atom and a hydrogen atom from an adjacent carbon atom in the same molecule:



Ethanol Ethylene

Structural formula of ethanol dehydrating under excess concentrated sulfuric acid at 180 degrees celsius. The products are ethylene and a side product of a water molecule.


Under the proper conditions, it is possible for the dehydration to occur between *two* alcohol molecules. The entire OH group of one molecule and only the hydrogen atom of the OH group of the second molecule are removed. The two ethyl groups attached to an oxygen atom form an ether molecule.



Two molecules of ethanol are dehydrated under concentrated sulfuric acid at 140 degrees celsius and excess ethanol to give a diethyl ether and a water molecule.

(Ethers are discussed in elsewhere) Thus, depending on conditions, one can prepare either alkenes or ethers by the dehydration of alcohols.

Both dehydration and hydration reactions occur continuously in cellular metabolism, with enzymes serving as catalysts and at a temperature of about 37°C. The following reaction occurs in the "Embden–Meyerhof" pathway




Structural formula of 2 phosphoglycerate forming phosphoenolpyruvate and a water molecule with the aid of enzymes.

Although the participating compounds are complex, the reaction is the same: elimination of water from the starting material. The idea is that if you know the chemistry of a particular functional group, you know the chemistry of hundreds of different compounds.


Oxidation

Primary and secondary alcohols are readily oxidized. We saw earlier how methanol and ethanol are oxidized by liver enzymes to form aldehydes. Because a variety of oxidizing agents can bring about oxidation, we can indicate an oxidizing agent without specifying a particular one by writing an equation with the symbol [O] above the arrow. For example, we write the oxidation of ethanol—a primary alcohol—to form acetaldehyde—an aldehyde—as follows:



Formula of ethanol reacting to form acetaldehyde with an O in a bracket above the right pointing arrow.

We shall see that aldehydes are even more easily oxidized than alcohols and yield carboxylic acids. Secondary alcohols are oxidized to *ketones*. The oxidation of isopropyl alcohol by potassium dichromate ($K_2Cr_2O_7$) gives acetone, the simplest ketone:




Unlike aldehydes, ketones are relatively resistant to further oxidation, so no special precautions are required to isolate them as they form. Note that in oxidation of both primary (RCH_2OH) and secondary (R_2CHOH) alcohols, two hydrogen atoms are removed from the alcohol molecule, one from the OH group and other from the carbon atom that bears the OH group.

These reactions can also be carried out in the laboratory with chemical oxidizing agents. One such oxidizing agent is potassium dichromate. The balanced equation (showing only the species involved in the reaction) in this case is as follows:

$$8\,H^{=} + Cr_2O_7^{2-} + 3\,CH_3CH_2OH \longrightarrow 3\,CH_3CHO + 2\,Cr^{3+} + 7\,H_2O$$

Alcohol oxidation is important in living organisms. Enzyme-controlled oxidation reactions provide the energy cells need to do useful work. One step in the metabolism of carbohydrates involves the oxidation of the secondary alcohol group in isocitric acid to a ketone group:



Isocitrate Oxalosuccinate


The overall type of reaction is the same as that in the conversion of isopropyl alcohol to acetone.

Tertiary alcohols (R_3COH) are resistant to oxidation because the carbon atom that carries the OH group does not have a hydrogen atom attached but is instead bonded to other carbon atoms. The oxidation reactions we have described involve the formation of a carbon-to-oxygen double bond. Thus, the carbon atom bearing the OH group must be able to release one of its attached atoms to form the double bond. The carbon-to-hydrogen bonding is easily broken under oxidative conditions, but carbon-to-carbon bonds are not. Therefore tertiary alcohols are not easily oxidized.


Example 9.6.1

Write an equation for the oxidation of each alcohol. Use [O] above the arrow to indicate an oxidizing agent. If no reaction occurs, write "no reaction" after the arrow.

a. $CH_3CH_2CH_2CH_2CH_2OH$

b. 

From left to right, there are four carbons on the alkane straight chain with a methyl and hydroxyl group on carbon 2.


c. 

From left to right, there are six carbons on the alkane straight chain with a hydroxyl group on carbon 2.


Solution

The first step is to recognize the class of each alcohol as primary, secondary, or tertiary.


a. This alcohol has the OH group on a carbon atom that is attached to only *one* other carbon atom, so it is a primary alcohol. Oxidation forms first an aldehyde and further oxidation forms a carboxylic acid.



b. This alcohol has the OH group on a carbon atom that is attached to three other carbon atoms, so it is a tertiary alcohol. No reaction occurs.




c. This alcohol has the OH group on a carbon atom that is attached to two other carbon atoms, so it is a secondary alcohol; oxidation gives a ketone.



? Exercise 9.6.1


Write an equation for the oxidation of each alcohol. Use [O] above the arrow to indicate an oxidizing agent. If no reaction occurs, write “no reaction” after the arrow.

a.




From left to right, there are six carbons on the alkane straight chain with a hydroxyl group and methyl group on carbon 3.

b.



From left to right, there are four carbons on the alkane straight chain with a methyl group on carbon 3 as well as a hydroxyl group on carbon 4.

c.



From left to right, there are six carbons on the alkane straight chain with a methyl group on carbon 2 and a hydroxyl group on carbon 3.

Summary

Alcohols can be dehydrated to form either alkenes (higher temperature, excess acid) or ethers (lower temperature, excess alcohol). Primary alcohols are oxidized to form aldehydes. Secondary alcohols are oxidized to form ketones. Tertiary alcohols are not readily oxidized.

9.6: Alcohols is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **14.2: Alcohols - Nomenclature and Classification** by Anonymous is licensed CC BY-NC-SA 3.0. Original source: https://2012books.lardbucket.org/books/introduction-to-chemistry-general-organic-and-biological.
- **14.3: Physical Properties of Alcohols** by Anonymous is licensed CC BY-NC-SA 3.0. Original source: https://2012books.lardbucket.org/books/introduction-to-chemistry-general-organic-and-biological.
- **14.5: Reactions of Alcohols** by Anonymous is licensed CC BY-NC-SA 3.0. Original source: https://2012books.lardbucket.org/books/introduction-to-chemistry-general-organic-and-biological.

9.7: Aldehydes and Ketones

Learning Objectives

- Identify the general structure for an aldehyde and a ketone.
- Use common names to name aldehydes and ketones.
- Use the IUPAC system to name aldehydes and ketones.


The next functional group we consider, the carbonyl group, has a carbon-to-oxygen double bond.




Carbonyl groups define two related families of organic compounds: the aldehydes and the ketones.

> *The carbonyl group is ubiquitous in biological compounds. It is found in carbohydrates, fats, proteins, nucleic acids, hormones, and vitamins—organic compounds critical to living systems.*

In a ketone, two carbon groups are attached to the carbonyl carbon atom. The following general formulas, in which R represents an alkyl group and Ar stands for an aryl group, represent ketones.



In an aldehyde, at least one of the attached groups must be a hydrogen atom. The following compounds are aldehydes:



In condensed formulas, we use CHO to identify an aldehyde rather than COH, which might be confused with an alcohol. This follows the general rule that in condensed structural formulas H comes after the atom it is attached to (usually C, N, or O).



An aldehyde




A ketone

The carbon-to-oxygen double bond is not shown but understood to be present. Because they contain the same functional group, aldehydes and ketones share many common properties, but they still differ enough to warrant their classification into two families.

Naming Aldehydes and Ketones

Both common and International Union of Pure and Applied Chemistry (IUPAC) names are frequently used for aldehydes and ketones, with common names predominating for the lower homologs. The common names of aldehydes are taken from the names of the acids into which the aldehydes can be converted by *oxidation*.




The stems for the common names of the first four aldehydes are as follows:

- 1 carbon atom: *form-*
- 2 carbon atoms: *acet-*
- 3 carbon atoms: *propion-*
- 4 carbon atoms: *butyr-*

Because the carbonyl group in a ketone must be attached to two carbon groups, the simplest ketone has three carbon atoms. It is widely known as *acetone*, a unique name unrelated to other common names for ketones.





Generally, the common names of ketones consist of the names of the groups attached to the carbonyl group, followed by the word *ketone*. (Note the similarity to the naming of ethers.) Another name for acetone, then, is *dimethyl ketone*. The ketone with four carbon atoms is ethyl methyl ketone.




Example 9.7.1

Classify each compound as an aldehyde or a ketone. Give the common name for each ketone.

a. 

b. 

c. 

Solution




a. This compound has the carbonyl group on an end carbon atom, so it is an aldehyde.

b. This compound has the carbonyl group on an interior carbon atom, so it is a ketone. Both alkyl groups are propyl groups. The name is therefore dipropyl ketone.

c. This compound has the carbonyl group between two alkyl groups, so it is a ketone. One alkyl group has three carbon atoms and is attached by the middle carbon atom; it is an isopropyl group. A group with one carbon atom is a methyl group. The name is therefore isopropyl methyl ketone.

? Exercise 9.7.1

Classify each compound as an aldehyde or a ketone. Give the common name for each ketone.


1. 
2. 
3. 


Here are some simple IUPAC rules for naming aldehydes and ketones:


- The stem names of aldehydes and ketones are derived from those of the parent alkanes, defined by the longest continuous chain (LCC) of carbon atoms that contains the functional group.
- For an aldehyde, drop the *-e* from the alkane name and add the ending *-al*. Methanal is the IUPAC name for formaldehyde, and ethanal is the name for acetaldehyde.
- For a ketone, drop the *-e* from the alkane name and add the ending *-one*. Propanone is the IUPAC name for acetone, and butanone is the name for ethyl methyl ketone.
- To indicate the position of a substituent on an aldehyde, the carbonyl carbon atom is always considered to be C1; it is unnecessary to designate this group by number.
- To indicate the position of a substituent on a ketone, number the chain in the manner that gives the carbonyl carbon atom the lowest possible number. In cyclic ketones, it is understood that the carbonyl carbon atom is C1.

✓ Example 9.7.2

Give the IUPAC name for each compound.

a. 

b. 

c. 

Solution


a. There are five carbon atoms in the LCC. The methyl group (CH_3) is a substituent on the second carbon atom of the chain; the aldehyde carbon atom is always C1. The name is derived from pentane. Dropping the *-e* and adding the ending *-al* gives pentanal. The methyl group on the second carbon atom makes the name 2-methylpentanal.


b. There are five carbon atoms in the LCC. The carbonyl carbon atom is C3, and there are methyl groups on C2 and C4. The IUPAC name is 2,4-dimethyl-3-pentanone.


c. There are six carbon atoms in the ring. The compound is cyclohexanone. No number is needed to indicate the position of the carbonyl group because all six carbon atoms are equivalent.

Exercise

Give the IUPAC name for each compound.

a. 

b. 

c. 


Example 9.7.3

Draw the structure for each compound.


a. 7-chlorooctanal
b. 4-methyl–3-hexanone

Solution

a. The *octan-* part of the name tells us that the LCC has eight carbon atoms. There is a chlorine (Cl) atom on the seventh carbon atom; numbering from the carbonyl group and counting the carbonyl carbon atom as C1, we place the Cl atom on the seventh carbon atom.



b. The *hexan-* part of the name tells us that the LCC has six carbon atoms. The 3 means that the carbonyl carbon atom is C3 in this chain, and the 4 tells us that there is a methyl (CH_3) group at C4:



Exercise 9.7.3

Draw the structure for each compound.

a. 5-bromo-3-iodoheptanal
b. 5-bromo-4-ethyl-2-heptanone


Summary

The common names of aldehydes are taken from the names of the corresponding carboxylic acids: formaldehyde, acetaldehyde, and so on. The common names of ketones, like those of ethers, consist of the names of the groups attached to the carbonyl group, followed by the word *ketone*. Stem names of aldehydes and ketones are derived from those of the parent alkanes, using an *-al* ending for an aldehydes and an *-one* ending for a ketone.

Learning Objectives

- Explain why the boiling points of aldehydes and ketones are higher than those of ethers and alkanes of similar molar masses but lower than those of comparable alcohols.
- Compare the solubilities in water of aldehydes and ketones of four or fewer carbon atoms with the solubilities of comparable alkanes and alcohols.
- Name the typical reactions take place with aldehydes and ketones.
- Describe some of the uses of common aldehydes and ketones.

The carbon-to-oxygen double bond is quite polar, more polar than a carbon-to-oxygen single bond. The electronegative oxygen atom has a much greater attraction for the bonding electron pairs than does the carbon atom. The carbon atom has a partial positive charge, and the oxygen atom has a partial negative charge:



In aldehydes and ketones, this charge separation leads to dipole-dipole interactions that are great enough to significantly affect the boiling points. Table **9.7.1** shows that the polar single bonds in ethers have little such effect, whereas hydrogen bonding between alcohol molecules is even stronger.


Table **9.7.1**: Boiling Points of Compounds Having Similar Molar Masses but Different Types of Intermolecular Forces

Compound	Family	Molar Mass	Type of Intermolecular Forces	Boiling Point (°C)
$CH_3CH_2CH_2CH_3$	alkane	58	dispersion only	–1
$CH_3OCH_2CH_3$	ether	60	weak dipole	6
CH_3CH_2CHO	aldehyde	58	strong dipole	49
$CH_3CH_2CH_2OH$	alcohol	60	hydrogen bonding	97

Formaldehyde is a gas at room temperature. Acetaldehyde boils at 20°C; in an open vessel, it boils away in a warm room. Most other common aldehydes are liquids at room temperature.

Although the lower members of the homologous series have pungent odors, many higher aldehydes have pleasant odors and are used in perfumes and artificial flavorings. As for the ketones, acetone has a pleasant odor, but most of the higher homologs have rather bland odors.


The oxygen atom of the carbonyl group engages in hydrogen bonding with a water molecule.



The solubility of aldehydes is therefore about the same as that of alcohols and ethers. Formaldehyde, acetaldehyde, and acetone are soluble in water. As the carbon chain increases in length, solubility in water decreases. The borderline of solubility occurs at about four carbon atoms per oxygen atom. All aldehydes and ketones are soluble in organic solvents and, in general, are less dense than water.

Oxidation of Aldehydes and Ketones

Aldehydes and ketones are much alike in many of their reactions, owing to the presence of the carbonyl functional group in both. They differ greatly, however, in one most important type of reaction: oxidation. Aldehydes are readily oxidized to carboxylic acids, whereas ketones resist oxidation.



The aldehydes are, in fact, among the most easily oxidized of organic compounds. They are oxidized by oxygen (O_2) in air to carboxylic acids.

$$2\,RCHO + O_2 \longrightarrow 2\,RCOOH$$

The ease of oxidation helps chemists identify aldehydes. A sufficiently mild oxidizing agent can distinguish aldehydes not only from ketones but also from alcohols. Tollens' reagent, for example, is an alkaline solution of silver (Ag^+) ion complexed with ammonia (NH_3), which keeps the Ag^+ ion in solution.

$$H_3N{-}Ag^+{-}NH_3$$

When Tollens' reagent oxidizes an aldehyde, the Ag^+ ion is reduced to free silver (Ag).

$$\underbrace{RCHO\,(aq)}_{\text{an aldehyde}} + 2\,Ag(NH_3)_2^+\,(aq) \longrightarrow RCOO^- + \underbrace{2\,Ag\,(s)}_{\text{free silver}} + 4\,NH_3\,(aq) + 2\,H_2O$$

Deposited on a clean glass surface, the silver produces a mirror (Figure 9.7.1). Ordinary ketones do not react with Tollens' reagent.



Figure 9.7.1: Aldehyde Reactions. A reaction related to the Tollens' reaction is often used to silver mirrors. These ornaments were silvered by such a reaction. Glucose, a simple sugar with an aldehyde functional group, is used as the reducing agent. Source: Photo courtesy of Krebs Glas Lauscha, commons.wikimedia.org/wiki/File:Silvering.jpg.

A person wearing gloves is holding a bunch of ornaments that she has just lifted from a basin containing a solution.

Although ketones resist oxidation by ordinary laboratory oxidizing agents, they undergo combustion, as do aldehydes.

Some Common Carbonyl Compounds

Formaldehyde has an irritating odor. Because of its reactivity, it is difficult to handle in the gaseous state. For many uses, it is therefore dissolved in water and sold as a 37% to 40% aqueous solution called *formalin*. Formaldehyde denatures proteins, rendering them insoluble in water and resistant to bacterial decay. For this reason, formalin is used in embalming solutions and in preserving biological specimens.

Aldehydes are the active components in many other familiar substances. Large quantities of formaldehyde are used to make phenol-formaldehyde resins for gluing the wood sheets in plywood and as adhesives in other building materials. Sometimes the formaldehyde escapes from the materials and causes health problems in some people. While some people seem unaffected, others experience coughing, wheezing, eye irritation, and other symptoms.

> *The odor of green leaves is due in part to a carbonyl compound, cis-3-hexenal, which with related compounds is used to impart a "green" herbal odor to shampoos and other products.*

Acetaldehyde is an extremely volatile, colorless liquid. It is a starting material for the preparation of many other organic compounds. Acetaldehyde is formed as a metabolite in the fermentation of sugars and in the detoxification of alcohol in the liver. Aldehydes are the active components of many other familiar materials (Figure **9.7.2**).





Figure **9.7.2** Some Interesting Aldehydes. (a) Benzaldehyde is an oil found in almonds; (b) cinnamaldehyde is oil of cinnamon; (c) vanillin gives vanilla its flavor; (d) *cis*-3-hexenal provides an herbal odor; and (e) *trans*-2-*cis*-6-nonadienal gives a cucumber odor.

Acetone is the simplest and most important ketone. Because it is miscible with water as well as with most organic solvents, its chief use is as an industrial solvent (for example, for paints and lacquers). It is also the chief ingredient in some brands of nail polish remover.

To Your Health: Acetone in Blood, Urine, and Breath

Acetone is formed in the human body as a by-product of lipid metabolism. Normally, acetone does not accumulate to an appreciable extent because it is oxidized to carbon dioxide and water. The normal concentration of acetone in the human body is less than 1 mg/100 mL of blood. In certain disease states, such as uncontrolled diabetes mellitus, the acetone concentration rises to higher levels. It is then excreted in the urine, where it is easily detected. In severe cases, its odor can be noted on the breath.

Ketones are also the active components of other familiar substances, some of which are noted in the accompanying figure.



Some ketones have interesting properties: (a) Butter flavoring comes from 2,3-butanedione; (b) β-ionone is responsible for the odor of violets; (c) muscone is musk oil, an ingredient in perfumes; and (d) camphor is used in some insect repellents.

Certain steroid hormones have the ketone functional group as a part of their structure. Two examples are progesterone, a hormone secreted by the ovaries that stimulates the growth of cells in the uterine wall and prepares it for attachment of a fertilized egg, and testosterone, the main male sex hormone. These and other sex hormones affect our development and our lives in fundamental ways.

Summary

The polar carbon-to-oxygen double bond causes aldehydes and ketones to have higher boiling points than those of ethers and alkanes of similar molar masses but lower than those of comparable alcohols that engage in intermolecular hydrogen bonding. Aldehydes are readily oxidized to carboxylic acids, whereas ketones resist oxidation.


9.7: Aldehydes and Ketones is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **14.9: Aldehydes and Ketones- Structure and Names** by Anonymous is licensed CC BY-NC-SA 3.0. Original source: https://2012books.lardbucket.org/books/introduction-to-chemistry-general-organic-and-biological.
- **14.10: Properties of Aldehydes and Ketones** by Anonymous is licensed CC BY-NC-SA 3.0. Original source: https://2012books.lardbucket.org/books/introduction-to-chemistry-general-organic-and-biological.


9.8: Carboxylic Acids and Esters

Aldehydes and Ketones

There are a number of functional groups that contain a carbon-oxygen double bond, which is commonly referred to as a **carbonyl**. **Ketones** and **aldehydes** are two closely related carbonyl-based functional groups that react in very similar ways. In a ketone, the carbon atom of a carbonyl is bonded to two other carbons. In an aldehyde, the carbonyl carbon is bonded on one side to a hydrogen, and on the other side to a carbon. The exception to this definition is formaldehyde, in which the carbonyl carbon has bonds to two hydrogens.




Molecules with carbon-nitrogen double bonds are called **imines**, or **Schiff bases**.




Carboxylic acids and acid derivatives


If a carbonyl carbon is bonded on one side to a carbon (or hydrogen) and on the other side to a **heteroatom** (in organic chemistry, this term generally refers to oxygen, nitrogen, sulfur, or one of the halogens), the functional group is considered to be one of the '**carboxylic acid derivatives'**, a designation that describes a grouping of several functional groups. The eponymous member of this grouping is the **carboxylic acid** functional group, in which the carbonyl is bonded to a hydroxyl (OH) group.




As the name implies, carboxylic acids are acidic, meaning that they are readily deprotonated to form the conjugate base form, called a **carboxylate** (much more about carboxylic acids in the acid-base chapter!).




In **amides**, the carbonyl carbon is bonded to a nitrogen. The nitrogen in an amide can be bonded either to hydrogens, to carbons, or to both. Another way of thinking of an amide is that it is a carbonyl bonded to an amine.




In **esters**, the carbonyl carbon is bonded to an oxygen which is itself bonded to another carbon. Another way of thinking of an ester is that it is a carbonyl bonded to an alcohol. **Thioesters** are similar to esters, except a sulfur is in place of the oxygen.




In an **acyl phosphate**, the carbonyl carbon is bonded to the oxygen of a phosphate, and in an **acid chloride**, the carbonyl carbon is bonded to a chlorine.



an acyl phosphate



an acid chloride

Finally, in a **nitrile** group, a carbon is triple-bonded to a nitrogen. Nitriles are also often referred to as **cyano** groups.



a nitrile

A single compound often contains several functional groups. The six-carbon sugar molecules glucose and fructose, for example, contain aldehyde and ketone groups, respectively, and both contain five alcohol groups (a compound with several alcohol groups is often referred to as a '**polyol**').



glucose



fructose

Capsaicin, the compound responsible for the heat in hot peppers, contains phenol, ether, amide, and alkene functional groups.


capsiacin

The male sex hormone testosterone contains ketone, alkene, and secondary alcohol groups, while acetylsalicylic acid (aspirin) contains aromatic, carboxylic acid, and ester groups.


testosterone


acetylsalicylic acid
(aspirin)

While not in any way a complete list, this section has covered most of the important functional groups that we will encounter in biological and laboratory organic chemistry. The table on the inside back cover provides a summary of all of the groups listed in this section, plus a few more that will be introduced later in the text.

9.8: Carboxylic Acids and Esters is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **24.6: Compounds with a Carbonyl Group** is licensed CC BY-NC-SA 3.0.


9.9: Amines

15.11: Amines - Structures and Names
15.12: Physical Properties of Amines

Learning Objectives

- Name the typical reactions that take place with amines.
- Describe heterocyclic amines.

Recall that ammonia (NH_3) acts as a base because the nitrogen atom has a lone pair of electrons that can accept a proton. Amines also have a lone electron pair on their nitrogen atoms and can accept a proton from water to form substituted ammonium (NH_4^+) ions and hydroxide (OH^-) ions:



As a specific example, methylamine reacts with water to form the methylammonium ion and the OH^- ion.

$$\underset{\text{Methylamine}}{CH_3NH_2(aq)} + H_2O \rightleftharpoons \underset{\text{Methylammonium ion}}{CH_3NH_3^+(aq)} + OH^-(aq)$$

Nearly all amines, including those that are not very soluble in water, will react with strong acids to form salts soluble in water.

$$\underset{\text{Octylamine (insoluble)}}{CH_3(CH_2)_6NH_2(l)} + HNO_3(aq) \longrightarrow \underset{\text{Octylammonium nitrate (soluble)}}{CH_3(CH_2)_6NH_3{}^+NO_3^-(aq)}$$

Amine salts are named like other salts: the name of the cation is followed by the name of the anion.

Example 9.9.1

What are the formulas of the acid and base that react to form $[CH_3NH_2CH_2CH_3]^+CH_3COO^-$?

Solution

The cation has two groups—methyl and ethyl—attached to the nitrogen atom. It comes from ethylmethylamine ($CH_3NHCH_2CH_3$). The anion is the acetate ion. It comes from acetic acid (CH_3COOH).

Exercise 9.9.1

What are the formulas of the acid and base that react to form $(CH_3CH_2CH_2)_3NH^+I^-$?

To Your Health: Amine Salts as Drugs

Salts of aniline are properly named as *anilinium* compounds, but an older system, still in use for naming drugs, identifies the salt of aniline and hydrochloric acid as “aniline hydrochloride.” These compounds are ionic—they are salts—and the properties of the compounds (solubility, for example) are those characteristic of salts. Many drugs that are amines are converted to hydrochloride salts to increase their solubility in aqueous solution.

Heterocyclic Amines


Looking back at the various cyclic hydrocarbons discussed previously, we see that all the atoms in the rings of these compounds are carbon atoms. In other cyclic compounds, called **heterocyclic compounds** (Greek *heteros*, meaning “other”), nitrogen, oxygen,

sulfur, or some other atom is incorporated in the ring. Many heterocyclic compounds are important in medicine and biochemistry. Some compose part of the structure of the nucleic acids, which in turn compose the genetic material of cells and direct protein synthesis.

Many heterocyclic amines occur naturally in plants. Like other amines, these compounds are basic. Such a compound is an **alkaloid**, a name that means "like alkalis." Many alkaloids are physiologically active, including the familiar drugs caffeine, nicotine, and cocaine.


To Your Health: Three Well-Known Alkaloids

Caffeine is a stimulant found in coffee, tea, and some soft drinks. Its mechanism of action is not well understood, but it is thought to block the activity of adenosine, a heterocyclic base that acts as a neurotransmitter, a substance that carries messages across a tiny gap (synapse) from one nerve cell (neuron) to another cell. The effective dose of caffeine is about 200 mg, corresponding to about two cups of strong coffee or tea.




Caffeine

Nicotine acts as a stimulant by a different mechanism; it probably mimics the action of the neurotransmitter acetylcholine. People ingest this drug by smoking or chewing tobacco. Its stimulant effect seems transient, as this initial response is followed by depression. Nicotine is highly toxic to animals. It is especially deadly when injected; the lethal dose for a human is estimated to be about 50 mg. Nicotine has also been used in agriculture as a contact insecticide.



Nicotine

Cocaine acts as a stimulant by preventing nerve cells from taking up dopamine, another neurotransmitter, from the synapse. High levels of dopamine are therefore available to stimulate the pleasure centers of the brain. The enhancement of dopamine action is thought to be responsible for cocaine's "high" and its addictive properties. After the binge, dopamine is depleted in less than an hour. This leaves the user in a pleasureless state and (often) craving more cocaine.



Cocaine

Cocaine is used as the salt cocaine hydrochloride and in the form of broken lumps of the free (unneutralized) base, which is called *crack cocaine*.

$$\underbrace{C_{17}H_{21}O_4N}_{\text{cocaine (freebase)}} + HCl \longrightarrow \underbrace{C_{17}H_{21}O_4NH^+Cl^-}_{\text{cocaine hydrochloride}}$$

Because it is soluble in water, cocaine hydrochloride is readily absorbed through the watery mucous membranes of the nose when it is snorted. Crack cocaine is more volatile than cocaine hydrochloride. It vaporizes at the temperature of a burning cigarette. When smoked, cocaine reaches the brain in 15 s.

Summary

Amines are bases; they react with acids to form salts. Salts of aniline are properly named as *anilinium* compounds, but an older system is used to name drugs: the salts of amine drugs and hydrochloric acid are called “hydrochlorides.” Heterocyclic amines are cyclic compounds with one or more nitrogen atoms in the ring.

9.9: Amines is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **15.12: Amines as Bases** by Anonymous is licensed CC BY-NC-SA 3.0. Original source: https://2012books.lardbucket.org/books/introduction-to-chemistry-general-organic-and-biological.

Index

H

Heterogenous Equilibria

8.4: Heterogenous Equilibria - Reactions Involving Solids and Liquids

Glossary

Sample Word 1 | Sample Definition 1

Detailed Licensing

Overview

Title: Chemistry 1.1 (GMIT)

Webpages: 60

All licenses found:

- Undeclared: 100% (60 pages)

By Page

- Chemistry 1.1 (GMIT) - *Undeclared*
  - Front Matter - *Undeclared*
    - TitlePage - *Undeclared*
    - InfoPage - *Undeclared*
    - Table of Contents - *Undeclared*
    - Licensing - *Undeclared*
  - 1: Atoms and Elements - *Undeclared*
    - 1.1: 2.5 The Structure of The Atom - *Undeclared*
    - 1.2: Protons, Neutrons, and Electrons in Atoms - *Undeclared*
    - 1.3: Finding Patterns - The Periodic Law and the Periodic Table - *Undeclared*
    - 1.4: The Average Mass of an Element's Atoms - *Undeclared*
    - 1.5: Molar Mass - Counting Atoms by Weighing Them - *Undeclared*
  - 2: Molecules, Compounds and Chemical Equations - *Undeclared*
    - 2.1: Chemical Bonds - *Undeclared*
    - 2.2: Representing Compounds- Chemical Formulas and Molecular Models - *Undeclared*
    - 2.3: An Atomic-Level Perspective of Elements and Compounds - *Undeclared*
    - 2.4: Ionic Compounds- Formulas and Names - *Undeclared*
    - 2.5: Molecular Compounds- Formulas and Names - *Undeclared*
    - 2.6: Summary of Inorganic Nomenclature - *Undeclared*
    - 2.7: Composition of Compounds - *Undeclared*
    - 2.8: Determining a Chemical Formula from Experimental Data - *Undeclared*
    - 2.9: Writing and Balancing Chemical Equations - *Undeclared*
  - 3: Calculations with Chemical Equations and Solution Concentrations - *Undeclared*
    - 3.1: How Much Carbon Dioxide? - *Undeclared*
    - 3.2: 4.3 Limiting Reactant, Theoretical Yield, and Percent Yield - *Undeclared*
    - 3.3: Solution Concentration and Solution Stoichiomentry - *Undeclared*
  - 4: Quantum Numbers - *Undeclared*
    - 4.1: Quantum Mechanics and The Atom - *Undeclared*
  - 5: Electron Configurations - *Undeclared*
    - 5.1: Electron Configurations- How Electrons Occupy Orbitals - *Undeclared*
    - 5.2: Electron Configurations, Valence Electrons, and the Periodic Table - *Undeclared*
  - 6: Lewis Structures - *Undeclared*
    - 6.1: Types of Chemical Bonds - *Undeclared*
    - 6.2: Representing Valance Electrons with Dots - *Undeclared*
    - 6.3: Ionic Bonding - *Undeclared*
    - 6.4: Covalent Bonding- Lewis Structure - *Undeclared*
    - 6.5: Electronegativity and Bond Polarity - *Undeclared*
  - 7: Chemical Kinetics - *Undeclared*
    - 7.1: Rate of a Chemical Reaction - *Undeclared*
    - 7.2: The Rate Law- The Effect of Concentration on Reaction Rate - *Undeclared*
  - 8: Chemical Equilibrium - *Undeclared*
    - 8.1: The Equilibrium Constant (K) - *Undeclared*
    - 8.2: Expressing the Equilibrium Constant in Terms of Pressure - *Undeclared*
    - 8.3: Calculating the Equilibrium Constant From Measured Equilibrium Concentrations - *Undeclared*
    - 8.4: Heterogenous Equilibria - Reactions Involving Solids and Liquids - *Undeclared*
    - 8.5: Le Châtelier's Principle- How a System at Equilibrium Responds to Disturbances - *Undeclared*
  - 9: Organic Chemistry - *Undeclared*
    - 9.1: Alkanes- Saturated Hydrocarbons - *Undeclared*
    - 9.2: Alkenes and Alkynes - *Undeclared*

- 9.3: Hydrocarbon Reactions - *Undeclared*
- 9.4: Aromatic Hydrocarbons - *Undeclared*
- 9.5: Functional Groups - *Undeclared*
- 9.6: Alcohols - *Undeclared*
- 9.7: Aldehydes and Ketones - *Undeclared*
- 9.8: Carboxylic Acids and Esters - *Undeclared*
- 9.9: Amines - *Undeclared*

Back Matter - *Undeclared*

- Index - *Undeclared*
- Glossary - *Undeclared*
- Detailed Licensing - *Undeclared*