CHEM 201: GENERAL CHEMISTRY I OER



Rana Akiel
College of the Canyons

LibreTexts™

Chem 201: General Chemistry I OER

This text is disseminated via the Open Education Resource (OER) LibreTexts Project (https://LibreTexts.org) and like the thousands of other texts available within this powerful platform, it is freely available for reading, printing, and "consuming."

The LibreTexts mission is to bring together students, faculty, and scholars in a collaborative effort to provide an accessible, and comprehensive platform that empowers our community to develop, curate, adapt, and adopt openly licensed resources and technologies; through these efforts we can reduce the financial burden born from traditional educational resource costs, ensuring education is more accessible for students and communities worldwide.

Most, but not all, pages in the library have licenses that may allow individuals to make changes, save, and print this book. Carefully consult the applicable license(s) before pursuing such effects. Instructors can adopt existing LibreTexts texts or Remix them to quickly build course-specific resources to meet the needs of their students. Unlike traditional textbooks, LibreTexts' web based origins allow powerful integration of advanced features and new technologies to support learning.



LibreTexts is the adaptable, user-friendly non-profit open education resource platform that educators trust for creating, customizing, and sharing accessible, interactive textbooks, adaptive homework, and ancillary materials. We collaborate with individuals and organizations to champion open education initiatives, support institutional publishing programs, drive curriculum development projects, and more.

The LibreTexts libraries are Powered by NICE CXone Expert and was supported by the Department of Education Open Textbook Pilot Project, the California Education Learning Lab, the UC Davis Office of the Provost, the UC Davis Library, the California State University Affordable Learning Solutions Program, and Merlot. This material is based upon work supported by the National Science Foundation under Grant No. 1246120, 1525057, and 1413739.

Any opinions, findings, and conclusions or recommendations expressed in this material are those of the author(s) and do not necessarily reflect the views of the National Science Foundation nor the US Department of Education.

Have questions or comments? For information about adoptions or adaptions contact info@LibreTexts.org or visit our main website at https://LibreTexts.org.

This text was compiled on 01/11/2026

TABLE OF CONTENTS

Licensing

1: Matter and Measurements

- 1.1: Chemistry- The Central science
- 1.2: Scientific Approach for Solving Problems
- 1.3: Classification of Matter
- 1.4: Properties of Matter
- 1.5: Units of Measurements
- 1.6: Uncertainty in Measurements
- 1.7: Dimensional Analysis- a Problem Solving Method Used in Chemistry
- 1.8: End of Chapter Problems

2: Atoms and Elements

- 2.1: Early Ideas of Atomic Theories
- 2.2: Development of Modern Atomic Tehory
- 2.3: Atomic Structure, Names/Symbols of Atoms, and Ions
- 2.4: Periodic Table
- 2.5: Isotopes and Average Atomic Mass
- 2.6: Molar Mass of Elements
- 2.7: End of Chapter Problems

3: Molecules and Compounds

- 3.1: Ionic and Molecular Compounds
- 3.2: Representation of Chemical Compounds
- 3.3: Types of ions
- 3.4: Formulas and names of ionic compounds
- 3.5: Formulas and Names of Covalent Compounds
- 3.6: Formula Mass and Molar Mass of Compounds
- 3.7: Percent Composition, Emperical Formulas, and Molecular Fromulas
- 3.8: Determine Empirical Formula from Combustion Analysis
- 3.9: End of Chapter Problems

4: Introduction to Solutions

- 4.1: Introduction to solutions
- 4.2: Solution Concentration
- 4.3: Solution Dilution
- 4.4: Hydration of Ions in Aqueous Solutions
- 4.5: Solubility of Ionic Compounds
- 4.6: Introduction to Acids and Bases
- 4.7: End of Chapter Problems

5: Chemical reactions

- 5.1: Writing and Balancing Chemical Reactions
- 5.2: Precipitation Reactions

- 5.3: Representing aqueous reaction- Molecular, complete ionic, and net ionic equations
- 5.4: Neutralization Reactions and Gas Evolution
- 5.5: Oxidation-Reduction reactions
- 5.6: Balancing Redox Reactions
- 5.7: End of Chapter Problems

6: Reaction Stoichiometry

- 6.1: Reaction Stoichiometry
- 6.2: Limiting reactant, theoretical yield, and percent yield
- 6.3: solution stoichiometry
- 6.4: Quantitative Analysis-Titration and Gravimetric Analysis
- 6.5: End of Chapter Problems

7: Gases

- 7.1: Pressure of the Gas
- 7.2: simple Gas Laws
- 7.3: Ideal Gas Law
- 7.4: Applying the Ideal Gas Law
- 7.5: Mixture of Gases
- 7.6: Gas Stoichiometry
- 7.7: Effusion and Diffusion of Gases
- 7.8: Kinetic Molecular Theory
- 7.9: Non Ideal Gas Behavior
- 7.10: End of Chapter Problems

8: Thermochemistry

- 8.1: Types of Energy
- 8.2: Internal Energy and First Law of Thermodynamics
- 8.3: Quantifying Heat and Work
- 8.4: Constant Volume Calorimeter
- 8.5: Enthalpy of reactions
- 8.6: Constant Pressure Calorimeter
- 8.7: Standard Enthalpy of formation
- 8.8: Calculating Enthalpy of Reactions Using Hess's Law
- 8.9: End of Chapter Problems

9: Electronic Structure and Periodic Table

- 9.1: The Nature of Light
- 9.2: Line Spectra and Bohr Model of Atoms
- 9.3: Wave Nature of Matter
- 9.4: The Quantum-Mechanical Model of an Atom
- 9.5: Electron Configuration of Atoms
- 9.6: Electron Configurations of Ions
- 9.7: Periodic Trends
- 9.8: End of Chapter Problems

10: Lewis Structure and Bond Energy

- 10.3: Covalent Bonding and Electronegativity
- 10.7: Formal Charges
- 10.1: Lewis Symbol of Atoms
- 10.2: Ionic Bonding
- 10.4: Lewis Structures of Molecular Compounds
- 10.5: Exceptions to the Octet Rule
- 10.6: Resonance Strucutres
- 10.8: Strengths of Ionic and Covalent Bonds
- 10.9: End of Chapter Problems

11: Theories of Chemical Bonding

- 11.1: VSEPR Theory
- 11.2: Polarity of Molecules
- 11.3: Valence Bond theory
- 11.4: Hybrid Atomic Orbitals
- 11.5: Overlap of Hybrid Orbitals
- 11.6: Molecular Orbital Theory
- 11.7: End of Chapter Problems

12: Liquids and Solids

- 12.1: Intermolecular forces
- 12.2: Properties of Liquids
- 12.3: Phase Changes
- 12.4: Phase diagram
- 12.5: The Solid State of Matter
- 12.6: Lattice Structure in Crystalline Solids
- 12.7: End of Chapter Problems

13: Solution

- 13.1: How Do Solutions Form?
- 13.2: Electrolytes
- 13.3: Factors Affecting Solubility
- 13.4: Solution Concentration
- 13.5: Colligative Properties
- 13.6: Colloids
- 13.7: End of Chapter Problems

Index

Glossary

Detailed Licensing

Licensing

*A detailed breakdown of this resource's licensing can be found in **Back Matter/Detailed Licensing**.*

CHAPTER OVERVIEW

1: Matter and Measurements

1.1: Chemistry- The Central science
1.2: Scientific Approach for Solving Problems
1.3: Classification of Matter
1.4: Properties of Matter
1.5: Units of Measurements
1.6: Uncertainty in Measurements
1.7: Dimensional Analysis- a Problem Solving Method Used in Chemistry
1.8: End of Chapter Problems

1: Matter and Measurements is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

1.1: Chemistry- The Central science

Learning Objectives

- Outline the historical development of chemistry
- Provide examples of the importance of chemistry in everyday life
- Provide examples illustrating macroscopic, microscopic, and symbolic domains

Throughout human history, people have tried to convert matter into more useful forms. Our Stone Age ancestors chipped pieces of flint into useful tools and carved wood into statues and toys. These endeavors involved changing the shape of a substance without changing the substance itself. But as our knowledge increased, humans began to change the composition of the substances as well—clay was converted into pottery, hides were cured to make garments, copper ores were transformed into copper tools and weapons, and grain was made into bread.

Humans began to practice chemistry when they learned to control fire and use it to cook, make pottery, and smelt metals. Subsequently, they began to separate and use specific components of matter. A variety of drugs such as aloe, myrrh, and opium were isolated from plants. Dyes, such as indigo and Tyrian purple, were extracted from plant and animal matter. Metals were combined to form alloys—for example, copper and tin were mixed together to make bronze—and more elaborate smelting techniques produced iron. Alkalis were extracted from ashes, and soaps were prepared by combining these alkalis with fats. Alcohol was produced by fermentation and purified by distillation.

Attempts to understand the behavior of matter extend back for more than 2500 years. As early as the sixth century BC, Greek philosophers discussed a system in which water was the basis of all things. You may have heard of the Greek postulate that matter consists of four elements: earth, air, fire, and water. Subsequently, an amalgamation of chemical technologies and philosophical speculations were spread from Egypt, China, and the eastern Mediterranean by alchemists, who endeavored to transform “base metals” such as lead into “noble metals” like gold, and to create elixirs to cure disease and extend life (Figure **1.1.1**).



Figure **1.1.1**: This portrayal shows an alchemist’s workshop circa 1580. Although alchemy made some useful contributions to how to manipulate matter, it was not scientific by modern standards. (credit: Chemical Heritage Foundation).

From alchemy came the historical progressions that led to modern chemistry: the isolation of drugs from natural sources, metallurgy, and the dye industry. Today, chemistry continues to deepen our understanding and improve our ability to harness and control the behavior of matter. This effort has been so successful that many people do not realize either the central position of chemistry among the sciences or the importance and universality of chemistry in daily life.

Chemistry: The Central Science

Chemistry is sometimes referred to as “the central science” due to its interconnectedness with a vast array of other STEM disciplines (STEM stands for areas of study in the science, technology, engineering, and math fields). Chemistry and the language of chemists play vital roles in biology, medicine, materials science, forensics, environmental science, and many other fields (Figure **1.1.2**). The basic principles of physics are essential for understanding many aspects of chemistry, and there is extensive overlap between many subdisciplines within the two fields, such as chemical physics and nuclear chemistry. Mathematics, computer science, and information theory provide important tools that help us calculate, interpret, describe, and generally make sense of the chemical world. Biology and chemistry converge in biochemistry, which is crucial to understanding the many complex factors and processes that keep living organisms (such as us) alive. Chemical engineering, materials science, and nanotechnology combine

chemical principles and empirical findings to produce useful substances, ranging from gasoline to fabrics to electronics. Agriculture, food science, veterinary science, and brewing and wine making help provide sustenance in the form of food and drink to the world's population. Medicine, pharmacology, biotechnology, and botany identify and produce substances that help keep us healthy. Environmental science, geology, oceanography, and atmospheric science incorporate many chemical ideas to help us better understand and protect our physical world. Chemical ideas are used to help understand the universe in astronomy and cosmology.




Figure 1.1.2: Knowledge of chemistry is central to understanding a wide range of scientific disciplines. This diagram shows just some of the interrelationships between chemistry and other fields.

What are some changes in matter that are essential to daily life? Digesting and assimilating food, synthesizing polymers that are used to make clothing, containers, cookware, and credit cards, and refining crude oil into gasoline and other products are just a few examples. As you proceed through this course, you will discover many different examples of changes in the composition and structure of matter, how to classify these changes and how they occurred, their causes, the changes in energy that accompany them, and the principles and laws involved. As you learn about these things, you will be learning chemistry, the study of the composition, properties, and interactions of matter. The practice of chemistry is not limited to chemistry books or laboratories: It happens whenever someone is involved in changes in matter or in conditions that may lead to such changes.

The Domains of Chemistry

Chemists study and describe the behavior of matter and energy in three different domains: macroscopic, microscopic, and symbolic. These domains provide different ways of considering and describing chemical behavior.

Macro is a Greek word that means "large." The macroscopic domain is familiar to us: It is the realm of everyday things that are large enough to be sensed directly by human sight or touch. In daily life, this includes the food you eat and the breeze you feel on your face. The macroscopic domain includes everyday and laboratory chemistry, where we observe and measure physical and chemical properties, or changes such as density, solubility, and flammability.

The microscopic domain of chemistry is almost always visited in the imagination. *Micro* also comes from Greek and means "small." Some aspects of the microscopic domains are visible through a microscope, such as a magnified image of graphite or bacteria. Viruses, for instance, are too small to be seen with the naked eye, but when we're suffering from a cold, we're reminded of how real they are.

However, most of the subjects in the microscopic domain of chemistry—such as atoms and molecules—are too small to be seen even with standard microscopes and often must be pictured in the mind. Other components of the microscopic domain include ions and electrons, protons and neutrons, and chemical bonds, each of which is far too small to see. This domain includes the individual metal atoms in a wire, the ions that compose a salt crystal, the changes in individual molecules that result in a color change, the conversion of nutrient molecules into tissue and energy, and the evolution of heat as bonds that hold atoms together are created.

The symbolic domain contains the specialized language used to represent components of the macroscopic and microscopic domains. Chemical symbols (such as those used in the periodic table), chemical formulas, and chemical equations are part of the symbolic domain, as are graphs and drawings. We can also consider calculations as part of the symbolic domain. These symbols play an important role in chemistry because they help interpret the behavior of the macroscopic domain in terms of the components

of the microscopic domain. One of the challenges for students learning chemistry is recognizing that the same symbols can represent different things in the macroscopic and microscopic domains, and one of the features that makes chemistry fascinating is the use of a domain that must be imagined to explain behavior in a domain that can be observed.

A helpful way to understand the three domains is via the essential and ubiquitous substance of water. That water is a liquid at moderate temperatures, will freeze to form a solid at lower temperatures, and boil to form a gas at higher temperatures (Figure **1.1.3**) are macroscopic observations. But some properties of water fall into the microscopic domain—what we cannot observe with the naked eye. The description of water as comprised of two hydrogen atoms and one oxygen atom, and the explanation of freezing and boiling in terms of attractions between these molecules, is within the microscopic arena. The formula H_2O, which can describe water at either the macroscopic or microscopic levels, is an example of the symbolic domain. The abbreviations (*g*) for gas, (*s*) for solid, and (*l*) for liquid are also symbolic.




Figure **1.1.3**: (a) Moisture in the air, icebergs, and the ocean represent water in the macroscopic domain. (b) At the molecular level (microscopic domain), gas molecules are far apart and disorganized, solid water molecules are close together and organized, and liquid molecules are close together and disorganized. (c) The formula H_2O symbolizes water, and (g), (s), and (l) symbolize its phases. Note that clouds are actually comprised of either very small liquid water droplets or solid water crystals; gaseous water in our atmosphere is not visible to the naked eye, although it may be sensed as humidity. (credit a: modification of work by "Gorkaazk"/Wikimedia Commons).

Summary

Chemistry deals with the composition, structure, and properties of matter, and the ways by which various forms of matter may be interconverted. Thus, it occupies a central place in the study and practice of science and technology. Chemists use the scientific method to perform experiments, pose hypotheses, and formulate laws and develop theories, so that they can better understand the behavior of the natural world. To do so, they operate in the macroscopic, microscopic, and symbolic domains. Chemists measure, analyze, purify, and synthesize a wide variety of substances that are important to our lives.

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

1.1: Chemistry- The Central science is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **11.6: Colloids** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

1.2: Scientific Approach for Solving Problems

Learning Objectives

- To identify the components of the scientific method

Scientists search for answers to questions and solutions to problems by using a procedure called the **scientific method**. This procedure consists of making observations, formulating hypotheses, and designing experiments, which in turn lead to additional observations, hypotheses, and experiments in repeated cycles (Figure **1.2.1**).




Figure **1.2.1**: The Scientific Method. As depicted in this flowchart, the scientific method consists of making observations, formulating hypotheses, and designing experiments. A scientist may enter the cycle at any point.

Observations can be qualitative or quantitative. Qualitative observations describe properties or occurrences in ways that do not rely on numbers. Examples of qualitative observations include the following: the outside air temperature is cooler during the winter season, table salt is a crystalline solid, sulfur crystals are yellow, and dissolving a penny in dilute nitric acid forms a blue solution and a brown gas. Quantitative observations are measurements, which by definition consist of both a number and a unit. Examples of quantitative observations include the following: the melting point of crystalline sulfur is 115.21 °C, and 35.9 grams of table salt—whose chemical name is sodium chloride—dissolve in 100 grams of water at 20 °C. An example of a quantitative observation was the initial observation leading to the modern theory of the dinosaurs' extinction: iridium concentrations in sediments dating to 66 million years ago were found to be 20–160 times higher than normal. The development of this theory is a good exemplar of the scientific method in action (see Figure **1.2.2** below).

After deciding to learn more about an observation or a set of observations, scientists generally begin an investigation by forming a **hypothesis**, a tentative explanation for the observation(s). The hypothesis may not be correct, but it puts the scientist's understanding of the system being studied into a form that can be tested. For example, the observation that we experience alternating periods of light and darkness corresponding to observed movements of the sun, moon, clouds, and shadows is consistent with either of two hypotheses:

1. Earth rotates on its axis every 24 hours, alternately exposing one side to the sun, or
2. The sun revolves around Earth every 24 hours.

Suitable experiments can be designed to choose between these two alternatives. For the disappearance of the dinosaurs, the hypothesis was that the impact of a large extraterrestrial object caused their extinction. Unfortunately (or perhaps fortunately), this hypothesis does not lend itself to direct testing by any obvious experiment, but scientists collected additional data that either support or refute it.

After a hypothesis has been formed, scientists conduct experiments to test its validity. **Experiments** are systematic observations or measurements, preferably made under controlled conditions—that is, under conditions in which a single variable changes. For example, in the dinosaur extinction scenario, iridium concentrations were measured worldwide and compared. A properly designed

and executed experiment enables a scientist to determine whether the original hypothesis is valid. Experiments often demonstrate that the hypothesis is incorrect or that it must be modified. More experimental data are then collected and analyzed, at which point a scientist may begin to think that the results are sufficiently reproducible (i.e., dependable) to merit being summarized in a **law**, a verbal or mathematical description of a phenomenon that allows for general predictions. A law simply says what happens; it does not address the question of why.

One example of a law, the Law of Definite Proportions, which was discovered by the French scientist Joseph Proust (1754–1826), states that a chemical substance always contains the same proportions of elements by mass. Thus sodium chloride (table salt) always contains the same proportion by mass of sodium to chlorine, in this case 39.34% sodium and 60.66% chlorine by mass, and sucrose (table sugar) is always 42.11% carbon, 6.48% hydrogen, and 51.41% oxygen by mass. Some solid compounds do not strictly obey the law of definite proportions. The law of definite proportions should seem obvious—we would expect the composition of sodium chloride to be consistent—but the head of the US Patent Office did not accept it as a fact until the early 20th century.

Whereas a law states only what happens, a **theory** attempts to explain why nature behaves as it does. Laws are unlikely to change greatly over time unless a major experimental error is discovered. In contrast, a theory, by definition, is incomplete and imperfect, evolving with time to explain new facts as they are discovered. The theory developed to explain the extinction of the dinosaurs, for example, is that Earth occasionally encounters small- to medium-sized asteroids, and these encounters may have unfortunate implications for the continued existence of most species. This theory is by no means proven, but it is consistent with the bulk of evidence amassed to date. Figure 1.2.2 summarizes the application of the scientific method in this case.




Figure 1.2.2: A Summary of How the Scientific Method Was Used in Developing the Asteroid Impact Theory to Explain the Disappearance of the Dinosaurs from Earth

Example 1.2.1

Classify each statement as a law, a theory, an experiment, a hypothesis, a qualitative observation, or a quantitative observation.

a. Ice always floats on liquid water.
b. Birds evolved from dinosaurs.
c. Hot air is less dense than cold air, probably because the components of hot air are moving more rapidly.
d. When 10 g of ice were added to 100 mL of water at 25 °C, the temperature of the water decreased to 15.5 °C after the ice melted.
e. The ingredients of Ivory soap were analyzed to see whether it really is 99.44% pure, as advertised.

Given: components of the scientific method

Asked for: statement classification

Strategy: Refer to the definitions in this section to determine which category best describes each statement.

Solution

a. This is a general statement of a relationship between the properties of liquid and solid water, so it is a law.
b. This is a possible explanation for the origin of birds, so it is a hypothesis.
c. This is a statement that tries to explain the relationship between the temperature and the density of air based on fundamental principles, so it is a theory.
d. The temperature is measured before and after a change is made in a system, so these are quantitative observations.
e. This is an analysis designed to test a hypothesis (in this case, the manufacturer's claim of purity), so it is an experiment.

Exercise 1.2.1

Classify each statement as a law, a theory, an experiment, a hypothesis, a qualitative observation, or a quantitative observation.

a. Measured amounts of acid were added to a Rolaids tablet to see whether it really "consumes 47 times its weight in excess stomach acid."
b. Heat always flows from hot objects to cooler ones, not in the opposite direction.
c. The universe was formed by a massive explosion that propelled matter into a vacuum.
d. Michael Jordan is the greatest pure shooter ever to play professional basketball.
e. Limestone is relatively insoluble in water but dissolves readily in dilute acid with the evolution of a gas.
f. Gas mixtures that contain more than 4% hydrogen in air are potentially explosive.

Answer a

experiment

Answer b

law

Answer c

theory

Answer d

hypothesis

Answer e

qualitative observation

Answer f

quantitative observation

Because scientists can enter the cycle shown in Figure **1.2.1** at any point, the actual application of the scientific method to different topics can take many different forms. For example, a scientist may start with a hypothesis formed by reading about work done by others in the field, rather than by making direct observations.

It is important to remember that scientists have a tendency to formulate hypotheses in familiar terms simply because it is difficult to propose something that has never been encountered or imagined before. As a result, scientists sometimes discount or overlook unexpected findings that disagree with the basic assumptions behind the hypothesis or theory being tested. Fortunately, truly important findings are immediately subject to independent verification by scientists in other laboratories, so science is a self-correcting discipline. When the Alvarezes originally suggested that an extraterrestrial impact caused the extinction of the dinosaurs, the response was almost universal skepticism and scorn. In only 20 years, however, the persuasive nature of the evidence overcame the skepticism of many scientists, and their initial hypothesis has now evolved into a theory that has revolutionized paleontology and geology.

Summary

Chemists expand their knowledge by making observations, carrying out experiments, and testing hypotheses to develop laws to summarize their results and theories to explain them. In doing so, they are using the scientific method.

1.2: Scientific Approach for Solving Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **11.6: Colloids** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

1.3: Classification of Matter

Learning Objectives

- To classify matter according to their states.
- To classify matter according to composition.

Chemists study the structures, physical properties, and chemical properties of material substances. These consist of **matter**, which is anything that occupies space and has mass. Gold and iridium are matter, as are peanuts, people, and postage stamps. Smoke, smog, and laughing gas are matter. Energy, light, and sound, however, are not matter; ideas and emotions are also not matter.

The **mass** of an object is the quantity of matter it contains. Do not confuse an object's mass with its **weight**, which is a force caused by the gravitational attraction that operates on the object. Mass is a fundamental property of an object that does not depend on its location.In physical terms, the mass of an object is directly proportional to the force required to change its speed or direction. A more detailed discussion of the differences between weight and mass and the units used to measure them is included in Essential Skills 1 (Section 1.9). Weight, on the other hand, depends on the location of an object. An astronaut whose mass is 95 kg weighs about 210 lb on Earth but only about 35 lb on the moon because the gravitational force he or she experiences on the moon is approximately one-sixth the force experienced on Earth. For practical purposes, weight and mass are often used interchangeably in laboratories. Because the force of gravity is considered to be the same everywhere on Earth's surface, 2.2 lb (a weight) equals 1.0 kg (a mass), regardless of the location of the laboratory on Earth.

Classification of matter Accroding to States

Under normal conditions, there are three distinct states of matter: solids, liquids, and gases. **Solids** are relatively rigid and have fixed shapes and volumes. A rock, for example, is a solid. In contrast, **liquids** have fixed volumes but flow to assume the shape of their containers, such as a beverage in a can. **Gases**, such as air in an automobile tire, have neither fixed shapes nor fixed volumes and expand to completely fill their containers. Whereas the volume of gases strongly depends on their temperature and **pressure** (the amount of force exerted on a given area), the volumes of liquids and solids are virtually independent of temperature and pressure. Matter can often change from one physical state to another in a process called a **physical change**. For example, liquid water can be heated to form a gas called steam, or steam can be cooled to form liquid water. However, such changes of state do not affect the chemical composition of the substance.




Figure **1.3.1**: The Three States of Matter. Solids have a defined shape and volume. Liquids have a fixed volume but flow to assume the shape of their containers. Gases completely fill their containers, regardless of volume. Figure used with permission from Wikipedia

Classification of Matter According to Composition: Pure Substances and Mixtures

A pure chemical substance is any matter that has a fixed chemical composition and characteristic properties. Oxygen, for example, is a pure chemical substance that is a colorless, odorless gas at 25°C. Very few samples of matter consist of pure substances; instead, most are mixtures, which are combinations of two or more pure substances in variable proportions in which the individual substances retain their identity. Air, tap water, milk, blue cheese, bread, and dirt are all mixtures. If all portions of a material are in the same state, have no visible boundaries, and are uniform throughout, then the material is **homogeneous**. Examples of homogeneous mixtures are the air we breathe and the tap water we drink. Homogeneous mixtures are also called solutions. Thus air is a solution of nitrogen, oxygen, water vapor, carbon dioxide, and several other gases; tap water is a solution of small amounts of several substances in water. The specific compositions of both of these solutions are not fixed, however, but depend on both source and location; for example, the composition of tap water in Boise, Idaho, is not the same as the composition of tap water in Buffalo,

New York. Although most solutions we encounter are liquid, solutions can also be solid. The gray substance still used by some dentists to fill tooth cavities is a complex solid solution that contains 50% mercury and 50% of a powder that contains mostly silver, tin, and copper, with small amounts of zinc and mercury. Solid solutions of two or more metals are commonly called alloys.

If the composition of a material is not completely uniform, then it is **heterogeneous** (e.g., chocolate chip cookie dough, blue cheese, and dirt). Mixtures that appear to be homogeneous are often found to be heterogeneous after microscopic examination. Milk, for example, appears to be homogeneous, but when examined under a microscope, it clearly consists of tiny globules of fat and protein dispersed in water. The components of heterogeneous mixtures can usually be separated by simple means. Solid-liquid mixtures such as sand in water or tea leaves in tea are readily separated by filtration, which consists of passing the mixture through a barrier, such as a strainer, with holes or pores that are smaller than the solid particles. In principle, mixtures of two or more solids, such as sugar and salt, can be separated by microscopic inspection and sorting. More complex operations are usually necessary, though, such as when separating gold nuggets from river gravel by panning. First solid material is filtered from river water; then the solids are separated by inspection. If gold is embedded in rock, it may have to be isolated using chemical methods.



Figure 1.3.2: A Heterogeneous Mixture. Under a microscope, whole milk is actually a heterogeneous mixture composed of globules of fat and protein dispersed in water. Figure used with permission from Wikipedia

Homogeneous mixtures (solutions) can be separated into their component substances by physical processes that rely on differences in some physical property, such as differences in their boiling points. Two of these separation methods are distillation and crystallization. **Distillation** makes use of differences in volatility, a measure of how easily a substance is converted to a gas at a given temperature. A simple distillation apparatus for separating a mixture of substances, at least one of which is a liquid. The most volatile component boils first and is condensed back to a liquid in the water-cooled condenser, from which it flows into the receiving flask. If a solution of salt and water is distilled, for example, the more volatile component, pure water, collects in the receiving flask, while the salt remains in the distillation flask.




Figure 1.3.3: The Distillation of a Solution of Table Salt in Water. The solution of salt in water is heated in the distilling flask until it boils. The resulting vapor is enriched in the more volatile component (water), which condenses to a liquid in the cold condenser and is then collected in the receiving flask.

Mixtures of two or more liquids with different boiling points can be separated with a more complex distillation apparatus. One example is the refining of crude petroleum into a range of useful products: aviation fuel, gasoline, kerosene, diesel fuel, and lubricating oil (in the approximate order of decreasing volatility). Another example is the distillation of alcoholic spirits such as brandy or whiskey. (This relatively simple procedure caused more than a few headaches for federal authorities in the 1920s during the era of Prohibition, when illegal stills proliferated in remote regions of the United States!)

Crystallization separates mixtures based on differences in solubility, a measure of how much solid substance remains dissolved in a given amount of a specified liquid. Most substances are more soluble at higher temperatures, so a mixture of two or more substances can be dissolved at an elevated temperature and then allowed to cool slowly. Alternatively, the liquid, called the solvent, may be allowed to evaporate. In either case, the least soluble of the dissolved substances, the one that is least likely to remain in solution, usually forms crystals first, and these crystals can be removed from the remaining solution by filtration.



Figure **1.3.4**: The Crystallization of Sodium Acetate from a Concentrated Solution of Sodium Acetate in Water. The addition of a small "seed" crystal (a) causes the compound to form white crystals, which grow and eventually occupy most of the flask. Video can be found here: www.youtube.com/watch?v=BLq5NibwV5g

Most mixtures can be separated into pure substances, which may be either elements or compounds. An **element**, such as gray, metallic sodium, is a substance that cannot be broken down into simpler ones by chemical changes; a **compound**, such as white, crystalline sodium chloride, contains two or more elements and has chemical and physical properties that are usually different from those of the elements of which it is composed. With only a few exceptions, a particular compound has the same elemental composition (the same elements in the same proportions) regardless of its source or history. The chemical composition of a substance is altered in a process called a **chemical change**. The conversion of two or more elements, such as sodium and chlorine, to a chemical compound, sodium chloride, is an example of a chemical change, often called a chemical reaction. Currently, about 118 elements are known, but millions of chemical compounds have been prepared from these 118 elements. The known elements are listed in the periodic table.




Figure **1.3.5**: The Decomposition of Water to Hydrogen and Oxygen by Electrolysis. Water is a chemical compound; hydrogen and oxygen are elements.



Different Definitions of Matter: https://youtu.be/qi_qLHc8wLk

In general, a reverse chemical process breaks down compounds into their elements. For example, water (a compound) can be decomposed into hydrogen and oxygen (both elements) by a process called electrolysis. In electrolysis, electricity provides the energy needed to separate a compound into its constituent elements (Figure **1.3.5**). A similar technique is used on a vast scale to obtain pure aluminum, an element, from its ores, which are mixtures of compounds. Because a great deal of energy is required for electrolysis, the cost of electricity is by far the greatest expense incurred in manufacturing pure aluminum. Thus recycling aluminum is both cost-effective and ecologically sound.

The overall organization of matter and the methods used to separate mixtures are summarized in Figure **1.3.6**.




Figure **1.3.6**: Relationships between the Types of Matter and the Methods Used to Separate Mixtures

Example 1.3.1

Identify each substance as a compound, an element, a heterogeneous mixture, or a homogeneous mixture (solution).

a. filtered tea
b. freshly squeezed orange juice
c. a compact disc
d. aluminum oxide, a white powder that contains a 2:3 ratio of aluminum and oxygen atoms
e. selenium

Given: a chemical substance

Asked for: its classification

Strategy:

A. Decide whether a substance is chemically pure. If it is pure, the substance is either an element or a compound. If a substance can be separated into its elements, it is a compound.
B. If a substance is not chemically pure, it is either a heterogeneous mixture or a homogeneous mixture. If its composition is uniform throughout, it is a homogeneous mixture.

Solution

a. **A** Tea is a solution of compounds in water, so it is not chemically pure. It is usually separated from tea leaves by filtration. **B** Because the composition of the solution is uniform throughout, it is a homogeneous mixture.
b. **A** Orange juice contains particles of solid (pulp) as well as liquid; it is not chemically pure. B Because its composition is not uniform throughout, orange juice is a heterogeneous mixture.
c. **A** A compact disc is a solid material that contains more than one element, with regions of different compositions visible along its edge. Hence a compact disc is not chemically pure. **B** The regions of different composition indicate that a compact disc is a heterogeneous mixture.
d. **A** Aluminum oxide is a single, chemically pure compound.
e. **A** Selenium is one of the known elements.

? Exercise 1.3.1

Identify each substance as a compound, an element, a heterogeneous mixture, or a homogeneous mixture (solution).

a. white wine
b. mercury
c. ranch-style salad dressing
d. table sugar (sucrose)

Answer A

solution

Answer B

element

Answer C

heterogeneous mixture

Answer D

compound



Different Definitions of Changes: https://youtu.be/OiLaMHigCuo

Summary

Matter can be classified according to physical and chemical properties. Matter is anything that occupies space and has mass. The three states of matter are solid, liquid, and gas. A physical change involves the conversion of a substance from one state of matter to another, without changing its chemical composition. Most matter consists of mixtures of pure substances, which can be homogeneous (uniform in composition) or heterogeneous (different regions possess different compositions and properties). Pure substances can be either chemical compounds or elements. Compounds can be broken down into elements by chemical reactions, but elements cannot be separated into simpler substances by chemical means. The properties of substances can be classified as either physical or chemical. Scientists can observe physical properties without changing the composition of the substance, whereas chemical properties describe the tendency of a substance to undergo chemical changes (chemical reactions) that change its chemical composition. Physical properties can be intensive or extensive. Intensive properties are the same for all samples; do not depend on sample size; and include, for example, color, physical state, and melting and boiling points. Extensive properties depend on the amount of material and include mass and volume. The ratio of two extensive properties, mass and volume, is an important intensive property called density.

Contributors and Attributions

- Modified by Joshua Halpern (Howard University)

1.3: Classification of Matter is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **11.6: Colloids** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **1.2: Classification of Matter** is licensed CC BY-NC-SA 3.0.

1.4: Properties of Matter

Learning Objectives

- To separate physical from chemical properties and changes

All matter has physical and chemical properties. **Physical properties** are characteristics that scientists can measure without changing the composition of the sample under study, such as mass, color, and volume (the amount of space occupied by a sample). **Chemical properties** describe the characteristic ability of a substance to react to form new substances; they include its flammability and susceptibility to corrosion. All samples of a pure substance have the same chemical and physical properties. For example, pure copper is always a reddish-brown solid (a physical property) and always dissolves in dilute nitric acid to produce a blue solution and a brown gas (a chemical property).

Physical properties can be extensive or intensive. **Extensive properties** vary with the amount of the substance and include mass, weight, and volume. **Intensive properties**, in contrast, do not depend on the amount of the substance; they include color, melting point, boiling point, electrical conductivity, and physical state at a given temperature. For example, elemental sulfur is a yellow crystalline solid that does not conduct electricity and has a melting point of 115.2 °C, no matter what amount is examined (Figure 1.4.1). Scientists commonly measure intensive properties to determine a substance's identity, whereas extensive properties convey information about the amount of the substance in a sample.




Figure 1.4.1: The Difference between Extensive and Intensive Properties of Matter. Because they differ in size, the two samples of sulfur have different extensive properties, such as mass and volume. In contrast, their intensive properties, including color, melting point, and electrical conductivity, are identical.

Although mass and volume are both extensive properties, their ratio is an important intensive property called **density** (ρ). Density is defined as mass per unit volume and is usually expressed in grams per cubic centimeter (g/cm^3). As mass increases in a given volume, density also increases. For example, lead, with its greater mass, has a far greater density than the same volume of air, just as a brick has a greater density than the same volume of Styrofoam. At a given temperature and pressure, the density of a pure substance is a constant:

$$\text{density} = \frac{\text{mass}}{\text{volume}}$$

$$\rho = \frac{m}{V}$$

Pure water, for example, has a density of 0.998 g/cm^3 at 25 °C. The average densities of some common substances are in Table 1.4.1. Notice that corn oil has a lower mass to volume ratio than water. This means that when added to water, corn oil will "float" (Figure 1.4.2).

Table 1.4.1: Densities of Common Substances

Substance	Density at 25 °C (g/cm^3)	Substance	Density at 25 °C (g/cm^3)
blood	1.035	corn oil	0.922
body fat	0.918	mayonnaise	0.910
whole milk	1.030	honey	1.420



Figure 1.4.2: Water and oil. Since the oil has a lower density than water, it floats on top. (CC-BY SA 3.0; Victor Blacus).

Physical Property and Change

Physical changes are changes in which no chemical bonds are broken or formed. This means that the same types of compounds or elements that were there at the beginning of the change are there at the end of the change. Because the ending materials are the same as the beginning materials, the properties (such as color, boiling point, etc) will also be the same. Physical changes involve moving molecules around, but not changing them. Some types of physical changes include:

- Changes of state (changes from a solid to a liquid or a gas and vice versa)
- Separation of a mixture
- Physical deformation (cutting, denting, stretching)
- Making solutions (special kinds of mixtures) .

As an ice cube melts, its shape changes as it acquires the ability to flow. However, its composition does not change. **Melting** is an example of a **physical change** (Figure 1.4.3), since some properties of the material change, but the identity of the matter does not. Physical changes can further be classified as reversible or irreversible. The melted ice cube may be refrozen, so melting is a reversible physical change. Physical changes that involve a change of state are all reversible. Other changes of state include **vaporization** (liquid to gas), **freezing** (liquid to solid), and **condensation** (gas to liquid). Dissolving is also a reversible physical change. When salt is dissolved into water, the salt is said to have entered the aqueous state. The salt may be regained by boiling off the water, leaving the salt behind.



Figure 1.4.3: Ice Melting is a physical change. When solid water (H_2O) as ice melts into a liquid (water), it appears changed. However, this change is only physical as the the composition of the constituent molecules is the same: 11.19% hydrogen and 88.81% oxygen by mass.

Chemical Properties and Change

Chemical changes occur when bonds are broken and/or formed between molecules or atoms. This means that one substance with a certain set of properties (such as melting point, color, taste, etc) is turned into a different substance with different properties. Chemical changes are frequently harder to reverse than physical changes.

One good example of a chemical change is burning paper. In contrast to the act of ripping paper, the act of burning paper actually results in the formation of new chemicals (carbon dioxide and water, to be exact). Another example of chemical change occurs when water is formed. Each molecule contains two atoms of hydrogen and one atom of oxygen chemically bonded.

Another example of a chemical change is what occurs when natural gas is burned in your furnace. This time, before the reaction we have a molecule of methane, CH_4, and two molecules of oxygen, O_2, while after the reaction we have two molecules of water, H_2O, and one molecule of carbon dioxide, CO_2. In this case, not only has the appearance changed, but the structure of the molecules has also changed. The new substances do not have the same chemical properties as the original ones. Therefore, this is a chemical change.

The combustion of magnesium metal is also chemical change (Magnesium + Oxygen → Magnesium Oxide):

$$2\,Mg + O_2 \rightarrow 2\,MgO$$


as is the rusting of iron (Iron + Oxygen → Iron Oxide/ Rust):

$$4\,Fe + 3\,O_2 \rightarrow 2\,Fe_2O_3$$

Using the components of composition and properties, we have the ability to distinguish one sample of matter from the others.



Different Definitions of Changes: https://youtu.be/OiLaMHigCuo



Different Definitions of Properties: https://youtu.be/n7UwjQJGh9Y

References

1. Petrucci, Bissonnette, Herring, Madura. General Chemistry: Principles and Modern Applications. Tenth ed. Upper Saddle River, NJ 07458: Pearson Education Inc., 2011.
2. Cracolice, Peters. Basics of introductory Chemistry An active Learning Approach. Second ed. Belmont, CA 94001:Brooks/Cole, 2007.

Contributors and Attributions

- Samantha Ma (UC Davis)

1.4: Properties of Matter is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **11.6: Colloids** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **1.3: Properties of Matter** is licensed CC BY-NC-SA 3.0.

1.5: Units of Measurements

Learning Objectives

- Explain the process of measurement and describe the three basic parts of a quantity.
- Describe the properties and units of length, mass, volume, density, temperature, and time.
- Recognize the common unit prefixes and use them to describe the magnitude of a measurement.
- Describe and calculate the density of a substance.
- Perform basic unit calculations and conversions in the metric and other unit systems.

Measurements provide the macroscopic information that is the basis of most of the hypotheses, theories, and laws that describe the behavior of matter and energy in both the macroscopic and microscopic domains of chemistry. Every measurement provides three kinds of information: the size or magnitude of the measurement (a number); a standard of comparison for the measurement (a unit); and an indication of the uncertainty of the measurement. While the number and unit are explicitly represented when a quantity is written, the uncertainty is an aspect of the measurement result that is more implicitly represented and will be discussed later.

The number in the measurement can be represented in different ways, including decimal form and scientific notation. For example, the maximum takeoff weight of a Boeing 777-200ER airliner is 298,000 kilograms, which can also be written as 2.98×10^5 kg. The mass of the average mosquito is about 0.0000025 kilograms, which can be written as 2.5×10^{-6} kg.

Units, such as liters, pounds, and centimeters, are standards of comparison for measurements. When we buy a 2-liter bottle of a soft drink, we expect that the volume of the drink was measured, so it is two times larger than the volume that everyone agrees to be 1 liter. The meat used to prepare a 0.25-pound hamburger is measured so it weighs one-fourth as much as 1 pound. Without units, a number can be meaningless, confusing, or possibly life threatening. Suppose a doctor prescribes phenobarbital to control a patient's seizures and states a dosage of "100" without specifying units. Not only will this be confusing to the medical professional giving the dose, but the consequences can be dire: 100 mg given three times per day can be effective as an anticonvulsant, but a single dose of 100 g is more than 10 times the lethal amount.

We usually report the results of scientific measurements in SI units, an updated version of the metric system, using the units listed in Table 1.5.1. Other units can be derived from these base units. The standards for these units are fixed by international agreement, and they are called the International System of Units or SI Units (from the French, *Le Système International d'Unités*). SI units have been used by the United States National Institute of Standards and Technology (NIST) since 1964.

Table 1.5.1: Base Units of the SI System

Property Measured	Name of Unit	Symbol of Unit
length	meter	m
mass	kilogram	kg
time	second	s
temperature	kelvin	K
electric current	ampere	A
amount of substance	mole	mol
luminous intensity	candela	cd

Sometimes we use units that are fractions or multiples of a base unit. Ice cream is sold in quarts (a familiar, non-SI base unit), pints (0.5 quart), or gallons (4 quarts). We also use fractions or multiples of units in the SI system, but these fractions or multiples are always powers of 10. Fractional or multiple SI units are named using a prefix and the name of the base unit. For example, a length of 1000 meters is also called a kilometer because the prefix *kilo* means "one thousand," which in scientific notation is 10^3 (1 kilometer = 1000 m = 10^3 m). The prefixes used and the powers to which 10 are raised are listed in Table 1.5.2.

Table 1.5.2: Common Unit Prefixes

Prefix	Symbol	Factor	Example
femto	f	10^{-15}	1 femtosecond (fs) = 1×10^{-15} s (0.000000000000001 s)
pico	p	10^{-12}	1 picometer (pm) = 1×10^{-12} m (0.000000000001 m)
nano	n	10^{-9}	4 nanograms (ng) = 4×10^{-9} g (0.000000004 g)
micro	µ	10^{-6}	1 microliter (µL) = 1×10^{-6} L (0.000001 L)
milli	m	10^{-3}	2 millimoles (mmol) = 2×10^{-3} mol (0.002 mol)
centi	c	10^{-2}	7 centimeters (cm) = 7×10^{-2} m (0.07 m)
deci	d	10^{-1}	1 deciliter (dL) = 1×10^{-1} L (0.1 L)
kilo	k	10^{3}	1 kilometer (km) = 1×10^{3} m (1000 m)
mega	M	10^{6}	3 megahertz (MHz) = 3×10^{6} Hz (3,000,000 Hz)
giga	G	10^{9}	8 gigayears (Gyr) = 8×10^{9} yr (8,000,000,000 Gyr)
tera	T	10^{12}	5 terawatts (TW) = 5×10^{12} W (5,000,000,000,000 W)

SI Base Units

The initial units of the metric system, which eventually evolved into the SI system, were established in France during the French Revolution. The original standards for the meter and the kilogram were adopted there in 1799 and eventually by other countries. This section introduces four of the SI base units commonly used in chemistry. Other SI units will be introduced in subsequent chapters.

Length

The standard unit of length in both the SI and original metric systems is the meter (m). A meter was originally specified as 1/10,000,000 of the distance from the North Pole to the equator. It is now defined as the distance light in a vacuum travels in 1/299,792,458 of a second. A meter is about 3 inches longer than a yard (Figure 1.5.1); one meter is about 39.37 inches or 1.094 yards. Longer distances are often reported in kilometers (1 km = 1000 m = 10^3 m), whereas shorter distances can be reported in centimeters (1 cm = 0.01 m = 10^{-2} m) or millimeters (1 mm = 0.001 m = 10^{-3} m).




Figure **1.5.1**: The relative lengths of 1 m, 1 yd, 1 cm, and 1 in. are shown (not actual size), as well as comparisons of 2.54 cm and 1 in., and of 1 m and 1.094 yd.

Mass

The standard unit of mass in the SI system is the kilogram (kg). A kilogram was originally defined as the mass of a liter of water (a cube of water with an edge length of exactly 0.1 meter). It is now defined by a certain cylinder of platinum-iridium alloy, which is kept in France (Figure **1.5.2**). Any object with the same mass as this cylinder is said to have a mass of 1 kilogram. One kilogram is about 2.2 pounds. The gram (g) is exactly equal to 1/1000 of the mass of the kilogram (10^{-3} kg).



Figure **1.5.2**: This replica prototype kilogram is housed at the National Institute of Standards and Technology (NIST) in Maryland. (credit: National Institutes of Standards and Technology).

Temperature

Temperature is an intensive property. The SI unit of temperature is the kelvin (K). The IUPAC convention is to use kelvin (all lowercase) for the word, K (uppercase) for the unit symbol, and neither the word “degree” nor the degree symbol (°). The degree Celsius (°C) is also allowed in the SI system, with both the word “degree” and the degree symbol used for Celsius measurements. Celsius degrees are the same magnitude as those of kelvin, but the two scales place their zeros in different places. Water freezes at 273.15 K (0 °C) and boils at 373.15 K (100 °C) by definition, and normal human body temperature is approximately 310 K (37 °C). The conversion between these two units and the Fahrenheit scale will be discussed later in this chapter.

Time

The SI base unit of time is the second (s). Small and large time intervals can be expressed with the appropriate prefixes; for example, 3 microseconds = 0.000003 s = 3×10^{-6} and 5 megaseconds = 5,000,000 s = 5×10^{6} s. Alternatively, hours, days, and years can be used.

Derived SI Units

We can derive many units from the seven SI base units. For example, we can use the base unit of length to define a unit of volume, and the base units of mass and length to define a unit of density.

Volume

Volume is the measure of the amount of space occupied by an object. The standard SI unit of volume is defined by the base unit of length (Figure **1.5.3**). The standard volume is a cubic meter (m^3), a cube with an edge length of exactly one meter. To dispense a cubic meter of water, we could build a cubic box with edge lengths of exactly one meter. This box would hold a cubic meter of water or any other substance.




Figure **1.5.3**: (a) The relative volumes are shown for cubes of 1 m^3, 1 dm^3 (1 L), and 1 cm^3 (1 mL) (not to scale). (b) The diameter of a dime is compared relative to the edge length of a 1-cm^3 (1-mL) cube.

A more commonly used unit of volume is derived from the decimeter (0.1 m, or 10 cm). A cube with edge lengths of exactly one decimeter contains a volume of one cubic decimeter (dm^3). A liter (L) is the more common name for the cubic decimeter. One liter is about 1.06 quarts. A cubic centimeter (cm^3) is the volume of a cube with an edge length of exactly one centimeter. The abbreviation **cc** (for **c**ubic **c**entimeter) is often used by health professionals. A cubic centimeter is also called a milliliter (mL) and is 1/1000 of a liter.

Density

We use the mass and volume of a substance to determine its density. Thus, the units of density are defined by the base units of mass and length.

The density of a substance is the ratio of the mass of a sample of the substance to its volume. The SI unit for density is the kilogram per cubic meter (kg/m^3). For many situations, however, this as an inconvenient unit, and we often use grams per cubic centimeter (g/cm^3) for the densities of solids and liquids, and grams per liter (g/L) for gases. Although there are exceptions, most liquids and solids have densities that range from about 0.7 g/cm^3 (the density of gasoline) to 19 g/cm^3 (the density of gold). The density of air is about 1.2 g/L. Table **1.5.3** shows the densities of some common substances.

Table **1.5.3**: Densities of Common Substances

Solids	Liquids	Gases (at 25 °C and 1 atm)
ice (at 0 °C) 0.92 g/cm^3	water 1.0 g/cm^3	dry air 1.20 g/L
oak (wood) 0.60–0.90 g/cm^3	ethanol 0.79 g/cm^3	oxygen 1.31 g/L
iron 7.9 g/cm^3	acetone 0.79 g/cm^3	nitrogen 1.14 g/L
copper 9.0 g/cm^3	glycerin 1.26 g/cm^3	carbon dioxide 1.80 g/L
lead 11.3 g/cm^3	olive oil 0.92 g/cm^3	helium 0.16 g/L
silver 10.5 g/cm^3	gasoline 0.70–0.77 g/cm^3	neon 0.83 g/L
gold 19.3 g/cm^3	mercury 13.6 g/cm^3	radon 9.1 g/L

While there are many ways to determine the density of an object, perhaps the most straightforward method involves separately finding the mass and volume of the object, and then dividing the mass of the sample by its volume. In the following example, the

mass is found directly by weighing, but the volume is found indirectly through length measurements.

$$\text{density} = \frac{\text{mass}}{\text{volume}} \tag{1.5.1}$$

Example 1.5.1

Calculation of Density Gold—in bricks, bars, and coins—has been a form of currency for centuries. In order to swindle people into paying for a brick of gold without actually investing in a brick of gold, people have considered filling the centers of hollow gold bricks with lead to fool buyers into thinking that the entire brick is gold. It does not work: Lead is a dense substance, but its density is not as great as that of gold, 19.3 g/cm^3. What is the density of lead if a cube of lead has an edge length of 2.00 cm and a mass of 90.7 g?

Solution

The density of a substance can be calculated by dividing its mass by its volume. The volume of a cube is calculated by cubing the edge length.

$$\text{volume of lead cube} = 2.00\ \text{cm} \times 2.00\ \text{cm} \times 2.00\ \text{cm} = 8.00\ \text{cm}^3$$

$$\text{density} = \frac{\text{mass}}{\text{volume}} = \frac{90.7\ \text{g}}{8.00\ \text{cm}^3} = \frac{11.3\ \text{g}}{1.00\ \text{cm}^3} = 11.3\ \text{g/cm}^3$$

(We will discuss the reason for rounding to the first decimal place in the next section.)

Exercise 1.5.1

a. To three decimal places, what is the volume of a cube (cm^3) with an edge length of 0.843 cm?
b. If the cube in part (a) is copper and has a mass of 5.34 g, what is the density of copper to two decimal places?

Answer a

0.599 cm^3;

Answer b

8.91 g/cm^3

Example 1.5.2: Using Displacement of Water to Determine Density

This PhET simulation illustrates another way to determine density, using displacement of water. Determine the density of the red and yellow blocks.

Solution

When you open the density simulation and select Same Mass, you can choose from several 5.00-kg colored blocks that you can drop into a tank containing 100.00 L water. The yellow block floats (it is less dense than water), and the water level rises to 105.00 L. While floating, the yellow block displaces 5.00 L water, an amount equal to the weight of the block. The red block sinks (it is more dense than water, which has density = 1.00 kg/L), and the water level rises to 101.25 L.

The red block therefore displaces 1.25 L water, an amount equal to the volume of the block. The density of the red block is:

$$\text{density} = \frac{\text{mass}}{\text{volume}} = \frac{5.00\ \text{kg}}{1.25\ \text{L}} = 4.00\ \text{kg/L}$$

Note that since the yellow block is not completely submerged, you cannot determine its density from this information. But if you hold the yellow block on the bottom of the tank, the water level rises to 110.00 L, which means that it now displaces 10.00 L water, and its density can be found:

$$\text{density} = \frac{\text{mass}}{\text{volume}} = \frac{5.00\ \text{kg}}{10.00\ \text{L}} = 0.500\ \text{kg/L}$$

? Exercise 1.5.2

Remove all of the blocks from the water and add the green block to the tank of water, placing it approximately in the middle of the tank. Determine the density of the green block.

Answer

2.00 kg/L

Summary

Measurements provide quantitative information that is critical in studying and practicing chemistry. Each measurement has an amount, a unit for comparison, and an uncertainty. Measurements can be represented in either decimal or scientific notation. Scientists primarily use the SI (International System) or metric systems. We use base SI units such as meters, seconds, and kilograms, as well as derived units, such as liters (for volume) and g/cm^3 (for density). In many cases, we find it convenient to use unit prefixes that yield fractional and multiple units, such as microseconds (10^{-6} seconds) and megahertz (10^6 hertz), respectively.

Key Equations

- $\text{density} = \dfrac{\text{mass}}{\text{volume}}$

Glossary

Celsius (°C)
unit of temperature; water freezes at 0 °C and boils at 100 °C on this scale

cubic centimeter (cm^3 or cc)
volume of a cube with an edge length of exactly 1 cm

cubic meter (m^3)
SI unit of volume

density
ratio of mass to volume for a substance or object

kelvin (K)
SI unit of temperature; 273.15 K = 0 ºC

kilogram (kg)
standard SI unit of mass; 1 kg = approximately 2.2 pounds

length
measure of one dimension of an object

liter (L)
(also, cubic decimeter) unit of volume; 1 L = 1,000 cm^3

meter (m)
standard metric and SI unit of length; 1 m = approximately 1.094 yards

milliliter (mL)
1/1,000 of a liter; equal to 1 cm^3

second (s)
SI unit of time

SI units (International System of Units)

standards fixed by international agreement in the International System of Units (*Le Système International d'Unités*)

unit

standard of comparison for measurements

volume

amount of space occupied by an object

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

1.5: Units of Measurements is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **11.6: Colloids** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **1.4: Measurements** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

1.6: Uncertainty in Measurements

Learning Objectives

- Compare and contrast exact and uncertain numbers.
- Correctly represent uncertainty in quantities using significant figures.
- Identify the number of significant figures in value.
- Solve problems that involve various calculations and report the results with the appropriate number of significant figures.
- Apply proper rounding rules to computed quantities
- Define accuracy and precision, and use accuracy and precision to describe data sets.

Counting is the only type of measurement that is free from uncertainty, provided the number of objects being counted does not change while the counting process is underway. The result of such a counting measurement is an example of an exact number. If we count eggs in a carton, we know *exactly* how many eggs the carton contains. The numbers of defined quantities are also exact. By definition, 1 foot is exactly 12 inches, 1 inch is exactly 2.54 centimeters, and 1 gram is exactly 0.001 kilogram. Quantities derived from measurements other than counting, however, are uncertain to varying extents due to practical limitations of the measurement process used.

Significant Figures in Measurement

The numbers of measured quantities, unlike defined or directly counted quantities, are not exact. To measure the volume of liquid in a graduated cylinder, you should make a reading at the bottom of the meniscus, the lowest point on the curved surface of the liquid.





Figure 1.6.1: To measure the volume of liquid in this graduated cylinder, you must mentally subdivide the distance between the 21 and 22 mL marks into tenths of a milliliter, and then make a reading (estimate) at the bottom of the meniscus.


Refer to the illustration in Figure 1.6.1. The bottom of the meniscus in this case clearly lies between the 21 and 22 markings, meaning the liquid volume is *certainly* greater than 21 mL but less than 22 mL. The meniscus appears to be a bit closer to the 22-mL mark than to the 21-mL mark, and so a reasonable estimate of the liquid's volume would be 21.6 mL. In the number 21.6, then, the digits 2 and 1 are certain, but the 6 is an estimate. Some people might estimate the meniscus position to be equally distant from each of the markings and estimate the tenth-place digit as 5, while others may think it to be even closer to the 22-mL mark and estimate this digit to be 7. Note that it would be pointless to attempt to estimate a digit for the hundredths place, given that the tenths-place digit is uncertain. In general, numerical scales such as the one on this graduated cylinder will permit measurements to one-tenth of the smallest scale division. The scale in this case has 1-mL divisions, and so volumes may be measured to the nearest 0.1 mL.

This concept holds true for all measurements, even if you do not actively make an estimate. If you place a quarter on a standard electronic balance, you may obtain a reading of 6.72 g. The digits 6 and 7 are certain, and the 2 indicates that the mass of the quarter is likely between 6.71 and 6.73 grams. The quarter weighs *about* 6.72 grams, with a nominal uncertainty in the measurement of ± 0.01 gram. If we weigh the quarter on a more sensitive balance, we may find that its mass is 6.723 g. This means its mass lies between 6.722 and 6.724 grams, an uncertainty of 0.001 gram. Every measurement has some uncertainty, which depends on the device used (and the user's ability). All of the digits in a measurement, including the uncertain last digit, are called significant figures or significant digits. Note that zero may be a measured value; for example, if you stand on a scale that shows weight to the nearest pound and it shows "120," then the 1 (hundreds), 2 (tens) and 0 (ones) are all significant (measured) values.

Whenever you make a measurement properly, all the digits in the result are significant. But what if you were analyzing a reported value and trying to determine what is significant and what is not? Well, for starters, all nonzero digits are significant, and it is only zeros that require some thought. We will use the terms "leading," "trailing," and "captive" for the zeros and will consider how to deal with them.



Starting with the first nonzero digit on the left, count this digit and all remaining digits to the right. This is the number of significant figures in the measurement unless the last digit is a trailing zero lying to the left of the decimal point.




Captive zeros result from measurement and are therefore always significant. Leading zeros, however, are never significant—they merely tell us where the decimal point is located.



The leading zeros in this example are not significant. We could use exponential notation (as described in Appendix B) and express the number as 8.32407×10^{-3}; then the number 8.32407 contains all of the significant figures, and 10^{-3} locates the decimal point.

The number of significant figures is uncertain in a number that ends with a zero to the left of the decimal point location. The zeros in the measurement 1,300 grams could be significant or they could simply indicate where the decimal point is located. The ambiguity can be resolved with the use of exponential notation: 1.3×10^3 (two significant figures), 1.30×10^3 (three significant figures, if the tens place was measured), or 1.300×10^3 (four significant figures, if the ones place was also measured). In cases where only the decimal-formatted number is available, it is prudent to assume that all trailing zeros are not significant.



When determining significant figures, be sure to pay attention to reported values and think about the measurement and significant figures in terms of what is reasonable or likely—that is, whether the value makes sense. For example, the official January 2014 census reported the resident population of the US as 317,297,725. Do you think the US population was correctly determined to the reported nine significant figures, that is, to the exact number of people? People are constantly being born, dying, or moving into or out of the country, and assumptions are made to account for the large number of people who are not actually counted. Because of

these uncertainties, it might be more reasonable to expect that we know the population to within perhaps a million or so, in which case the population should be reported as 317 million, or 3.17×10^8 people.

Significant Figures in Calculations

A second important principle of uncertainty is that results calculated from a measurement are at least as uncertain as the measurement itself. We must take the uncertainty in our measurements into account to avoid misrepresenting the uncertainty in calculated results. One way to do this is to report the result of a calculation with the correct number of significant figures, which is determined by the following three rules for rounding numbers:

1. When we add or subtract numbers, we should round the result to the same number of decimal places as the number with the least number of decimal places (the least precise value in terms of addition and subtraction).
2. When we multiply or divide numbers, we should round the result to the same number of digits as the number with the least number of significant figures (the least precise value in terms of multiplication and division).
3. If the digit to be dropped (the one immediately to the right of the digit to be retained) is less than 5, we "round down" and leave the retained digit unchanged; if it is more than 5, we "round up" and increase the retained digit by 1; if the dropped digit *is* 5, we round up or down, whichever yields an even value for the retained digit. (The last part of this rule may strike you as a bit odd, but it's based on reliable statistics and is aimed at avoiding any bias when dropping the digit "5," since it is equally close to both possible values of the retained digit.)

The following examples illustrate the application of this rule in rounding a few different numbers to three significant figures:

- 0.028675 rounds "up" to 0.0287 (the dropped digit, 7, is greater than 5)
- 18.3384 rounds "down" to 18.3 (the dropped digit, 3, is less than 5)
- 6.8752 rounds "up" to 6.88 (the dropped digit is 5, and the retained digit is even)
- 92.85 rounds "down" to 92.8 (the dropped digit is 5, and the retained digit is even)

Let's work through these rules with a few examples.

✔ Example 1.6.1: Rounding Numbers

Round the following to the indicated number of significant figures:

a. 31.57 (to two significant figures)
b. 8.1649 (to three significant figures)
c. 0.051065 (to four significant figures)
d. 0.90275 (to four significant figures)

Solution

a. 31.57 rounds "up" to 32 (the dropped digit is 5, and the retained digit is even)
b. 8.1649 rounds "down" to 8.16 (the dropped digit, 4, is less than 5)
c. 0.051065 rounds "down" to 0.05106 (the dropped digit is 5, and the retained digit is even)
d. 0.90275 rounds "up" to 0.9028 (the dropped digit is 5, and the retained digit is even)

? Exercise 1.6.1

Round the following to the indicated number of significant figures:

a. 0.424 (to two significant figures)
b. 0.0038661 (to three significant figures)
c. 421.25 (to four significant figures)
d. 28,683.5 (to five significant figures)

Answer a

0.42

Answer b

0.00387

Answer c

421.2

Answer d

28,684

Example 1.6.2: Addition and Subtraction with Significant Figures Rule:

When we add or subtract numbers, we should round the result to the same number of decimal places as the number with the least number of decimal places (i.e., the least precise value in terms of addition and subtraction).

a. Add 1.0023 g and 4.383 g.
b. Subtract 421.23 g from 486 g.

Solution

(a)


$$\begin{array}{r} 1.0023\ \text{g} \\ +\ 4.383\ \text{g} \\ \hline 5.3853\ \text{g} \end{array}$$

Answer is 5.385 g (round to the thousandths place; three decimal places)

(b)

$$\begin{array}{r} 486\ \text{g} \\ -\ 421.23\ \text{g} \\ \hline 64.77\ \text{g} \end{array}$$

Answer is 65 g (round to the ones place; no decimal places)



Exercise 1.6.2

a. Add 2.334 mL and 0.31 mL.
b. Subtract 55.8752 m from 56.533 m.

Answer a

2.64 mL

Answer b

0.658 m

Example 1.6.3: Multiplication and Division with Significant Figures

Rule: When we multiply or divide numbers, we should round the result to the same number of digits as the number with the least number of significant figures (the least precise value in terms of multiplication and division).

a. Multiply 0.6238 cm by 6.6 cm.
b. Divide 421.23 g by 486 mL.

Solution

(a)

$$0.6238\ \text{cm} \times 6.6\ \text{cm} = 4.11708\ \text{cm}^2 \rightarrow \text{result is } 4.1\ \text{cm}^2 \quad (1.6.1)$$
$$\text{(round to two significant figures)}$$

$$\text{four significant figures} \times \text{two significant figures} \rightarrow \text{two significant figures answer} \quad (1.6.2)$$

(b)

$$\frac{421.23\ \text{g}}{486\ \text{mL}} = 0.86728...\ \text{g/mL} \rightarrow \text{result is } 0.867\ \text{g/mL} \quad (1.6.3)$$
$$\text{(round to three significant figures)}$$

$$\frac{\text{five significant figures}}{\text{three significant figures}} \rightarrow \text{three significant figures answer} \quad (1.6.4)$$

Exercise 1.6.3

a. Multiply 2.334 cm and 0.320 cm.
b. Divide 55.8752 m by 56.53 s.

Answer a

0.747 cm^2

Answer b

0.9884 m/s

In the midst of all these technicalities, it is important to keep in mind the reason why we use significant figures and rounding rules—to correctly represent the certainty of the values we report and to ensure that a calculated result is not represented as being more certain than the least certain value used in the calculation.

Example 1.6.4: Calculation with Significant Figures

One common bathtub is 13.44 dm long, 5.920 dm wide, and 2.54 dm deep. Assume that the tub is rectangular and calculate its approximate volume in liters.

Solution

$$\begin{aligned} V &= l \times w \times d \\ &= 13.44\ \text{dm} \times 5.920\ \text{dm} \times 2.54\ \text{dm} \\ &= 202.09459...\text{dm}^3\ \text{(value from calculator)} \\ &= 202\ \text{dm}^3\text{, or } 202\ \text{L (answer rounded to three significant figures)} \end{aligned}$$

Exercise 1.6.4: Determination of Density Using Water Displacement


What is the density of a liquid with a mass of 31.1415 g and a volume of 30.13 cm^3?

Answer

1.034 g/mL

Example 1.6.5

A piece of rebar is weighed and then submerged in a graduated cylinder partially filled with water, with results as shown.



a. Use these values to determine the density of this piece of rebar.
b. Rebar is mostly iron. Does your result in (a) support this statement? How?

Solution

The volume of the piece of rebar is equal to the volume of the water displaced:

$$\text{volume} = 22.4\ \text{mL} - 13.5\ \text{mL} = 8.9\ \text{mL} = 8.9\ \text{cm}^3$$

(rounded to the nearest 0.1 mL, per the rule for addition and subtraction)

The density is the mass-to-volume ratio:

$$\text{density} = \frac{\text{mass}}{\text{volume}} = \frac{69.658\ \text{g}}{8.9\ \text{cm}^3} = 7.8\ \text{g/cm}^3$$

(rounded to two significant figures, per the rule for multiplication and division)

The density of iron is 7.9 g/cm^3, very close to that of rebar, which lends some support to the fact that rebar is mostly iron.

Exercise 1.6.5

An irregularly shaped piece of a shiny yellowish material is weighed and then submerged in a graduated cylinder, with results as shown.



a. Use these values to determine the density of this material.
b. Do you have any reasonable guesses as to the identity of this material? Explain your reasoning.

Answer a

19 g/cm^3

Answer b

It is likely gold; it has the right appearance for gold and very close to the density given for gold.

Accuracy and Precision

Scientists typically make repeated measurements of a quantity to ensure the quality of their findings and to know both the precision and the accuracy of their results. Measurements are said to be precise if they yield very similar results when repeated in the same manner. A measurement is considered accurate if it yields a result that is very close to the true or accepted value. Precise values agree with each other; accurate values agree with a true value. These characterizations can be extended to other contexts, such as the results of an archery competition (Figure **1.6.2**).




Figure **1.6.2**: (a) These arrows are close to both the bull's eye and one another, so they are both accurate and precise. (b) These arrows are close to one another but not on target, so they are precise but not accurate. (c) These arrows are neither on target nor close to one another, so they are neither accurate nor precise.

Suppose a quality control chemist at a pharmaceutical company is tasked with checking the accuracy and precision of three different machines that are meant to dispense 10 ounces (296 mL) of cough syrup into storage bottles. She proceeds to use each machine to fill five bottles and then carefully determines the actual volume dispensed, obtaining the results tabulated in Table **1.6.2**.

Table **1.6.2**: Volume (mL) of Cough Medicine Delivered by 10-oz (296 mL) Dispensers

Dispenser #1	Dispenser #2	Dispenser #3
283.3	298.3	296.1
284.1	294.2	295.9
283.9	296.0	296.1
284.0	297.8	296.0
284.1	293.9	296.1

Considering these results, she will report that dispenser #1 is precise (values all close to one another, within a few tenths of a milliliter) but not accurate (none of the values are close to the target value of 296 mL, each being more than 10 mL too low). Results for dispenser #2 represent improved accuracy (each volume is less than 3 mL away from 296 mL) but worse precision (volumes vary by more than 4 mL). Finally, she can report that dispenser #3 is working well, dispensing cough syrup both accurately (all volumes within 0.1 mL of the target volume) and precisely (volumes differing from each other by no more than 0.2 mL).

Summary

Quantities can be exact or measured. Measured quantities have an associated uncertainty that is represented by the number of significant figures in the measurement. The uncertainty of a calculated value depends on the uncertainties in the values used in the calculation and is reflected in how the value is rounded. Measured values can be accurate (close to the true value) and/or precise (showing little variation when measured repeatedly).

Glossary

uncertainty
estimate of amount by which measurement differs from true value

significant figures
(also, significant digits) all of the measured digits in a determination, including the uncertain last digit

rounding
procedure used to ensure that calculated results properly reflect the uncertainty in the measurements used in the calculation

precision
how closely a measurement matches the same measurement when repeated

exact number
number derived by counting or by definition

accuracy
how closely a measurement aligns with a correct value

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

1.6: Uncertainty in Measurements is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **1.5: Measurement Uncertainty, Accuracy, and Precision** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

1.7: Dimensional Analysis- a Problem Solving Method Used in Chemistry

Learning Objectives

- Explain the dimensional analysis (factor label) approach to mathematical calculations involving quantities.
- Describe how to use dimensional analysis to carry out unit conversions for a given property and computations involving two or more properties.
- Convert between the three main temperature units: Fahrenheit, Celsius, and Kelvin.

It is often the case that a quantity of interest may not be easy (or even possible) to measure directly but instead must be calculated from other directly measured properties and appropriate mathematical relationships. For example, consider measuring the average speed of an athlete running sprints. This is typically accomplished by measuring the *time* required for the athlete to run from the starting line to the finish line, and the *distance* between these two lines, and then computing *speed* from the equation that relates these three properties:

$$\text{speed} = \frac{\text{distance}}{\text{time}} \tag{1.7.1}$$

An Olympic-quality sprinter can run 100 m in approximately 10 s, corresponding to an average speed of

$$\frac{100\ \text{m}}{10\ \text{s}} = 10\ \text{m/s} \tag{1.7.2}$$

Note that this simple arithmetic involves dividing the numbers of each measured quantity to yield the number of the computed quantity (100/10 = 10) *and likewise* dividing the units of each measured quantity to yield the unit of the computed quantity (m/s = m/s). Now, consider using this same relation to predict the time required for a person running at this speed to travel a distance of 25 m. The same relation between the three properties is used, but in this case, the two quantities provided are a speed (10 m/s) and a distance (25 m). To yield the sought property, time, the equation must be rearranged appropriately:

$$\text{time} = \frac{\text{distance}}{\text{speed}} \tag{1.7.3}$$

The time can then be computed as:

$$\frac{25\ \text{m}}{10\ \text{m/s}} = 2.5\ \text{s} \tag{1.7.4}$$

Again, arithmetic on the numbers (25/10 = 2.5) was accompanied by the same arithmetic on the units (m/m/s = s) to yield the number and unit of the result, 2.5 s. Note that, just as for numbers, when a unit is divided by an identical unit (in this case, m/m), the result is “1”—or, as commonly phrased, the units “cancel.”

These calculations are examples of a versatile mathematical approach known as dimensional analysis (or the factor-label method). Dimensional analysis is based on this premise: *the units of quantities must be subjected to the same mathematical operations as their associated numbers*. This method can be applied to computations ranging from simple unit conversions to more complex, multi-step calculations involving several different quantities.

Conversion Factors and Dimensional Analysis

A ratio of two equivalent quantities expressed with different measurement units can be used as a unit conversion factor. For example, the lengths of 2.54 cm and 1 in. are equivalent (by definition), and so a unit conversion factor may be derived from the ratio,

$$\frac{2.54\ \text{cm}}{1\ \text{in.}}\ (2.54\ \text{cm} = 1\ \text{in.})\ \text{or}\ 2.54\ \frac{\text{cm}}{\text{in.}} \tag{1.7.5}$$

Several other commonly used conversion factors are given in Table 1.7.1.

Table 1.7.1: Common Conversion Factors

Length	Volume	Mass
1 m = 1.0936 yd	1 L = 1.0567 qt	1 kg = 2.2046 lb
1 in. = 2.54 cm (exact)	1 qt = 0.94635 L	1 lb = 453.59 g
1 km = 0.62137 mi	1 ft^3 = 28.317 L	1 (avoirdupois) oz = 28.349 g
1 mi = 1609.3 m	1 tbsp = 14.787 mL	1 (troy) oz = 31.103 g

When we multiply a quantity (such as distance given in inches) by an appropriate unit conversion factor, we convert the quantity to an equivalent value with different units (such as distance in centimeters). For example, a basketball player's vertical jump of 34 inches can be converted to centimeters by:

$$34 \cancel{\text{in.}} \times \frac{2.54 \text{ cm}}{1 \cancel{\text{in.}}} = 86 \text{ cm} \tag{1.7.6}$$

Since this simple arithmetic involves *quantities*, the premise of dimensional analysis requires that we multiply both *numbers and units*. The numbers of these two quantities are multiplied to yield the number of the product quantity, 86, whereas the units are multiplied to yield

$$\frac{\text{in.} \times \text{cm}}{\text{in.}}. \tag{1.7.7}$$

Just as for numbers, a ratio of identical units is also numerically equal to one,

$$\frac{\text{in.}}{\text{in.}} = 1 \tag{1.7.8}$$

and the unit product thus simplifies to *cm*. (When identical units divide to yield a factor of 1, they are said to "cancel.") Using dimensional analysis, we can determine that a unit conversion factor has been set up correctly by checking to confirm that the original unit will cancel, and the result will contain the sought (converted) unit.

Example 1.7.1: Using a Unit Conversion Factor

The mass of a competition Frisbee is 125 g. Convert its mass to ounces using the unit conversion factor derived from the relationship 1 oz = 28.349 g (Table 1.7.1).

Solution

If we have the conversion factor, we can determine the mass in kilograms using an equation similar the one used for converting length from inches to centimeters.

$$x \text{ oz} = 125 \text{ g} \times \text{unit conversion factor}$$

We write the unit conversion factor in its two forms:

$$\frac{1 \text{ oz}}{28.349 \text{ g}} \text{ and } \frac{28.349 \text{ g}}{1 \text{ oz}}$$

The correct unit conversion factor is the ratio that cancels the units of grams and leaves ounces.

$$\begin{aligned} x \text{ oz} &= 125 \cancel{\text{g}} \times \frac{1 \text{ oz}}{28.349 \cancel{\text{g}}} \\ &= \left(\frac{125}{28.349}\right) \text{ oz} \\ &= 4.41 \text{ oz (three significant figures)} \end{aligned}$$

? Exercise 1.7.1

Convert a volume of 9.345 qt to liters.

Answer

8.844 L

Beyond simple unit conversions, the factor-label method can be used to solve more complex problems involving computations. Regardless of the details, the basic approach is the same—all the *factors* involved in the calculation must be appropriately oriented to insure that their *labels* (units) will appropriately cancel and/or combine to yield the desired unit in the result. This is why it is referred to as the factor-label method. As your study of chemistry continues, you will encounter many opportunities to apply this approach.

✓ Example 1.7.2: Computing Quantities from Measurement Results

What is the density of common antifreeze in units of g/mL? A 4.00-qt sample of the antifreeze weighs 9.26 lb.

Solution

Since $\text{density} = \dfrac{\text{mass}}{\text{volume}}$, we need to divide the mass in grams by the volume in milliliters. In general: the number of units of B = the number of units of A × unit conversion factor. The necessary conversion factors are given in Table 1.7.1: 1 lb = 453.59 g; 1 L = 1.0567 qt; 1 L = 1,000 mL. We can convert mass from pounds to grams in one step:

$$9.26 \cancel{\text{lb}} \times \frac{453.59\ \text{g}}{1\ \cancel{\text{lb}}} = 4.20 \times 10^3\ \text{g}$$

We need to use two steps to convert volume from quarts to milliliters.

1. *Convert quarts to liters.*

$$4.00\ \cancel{\text{qt}} \times \frac{1\ \text{L}}{1.0567\ \cancel{\text{qt}}} = 3.78\ \text{L}$$

2. *Convert liters to milliliters.*

$$3.78\ \cancel{\text{L}} \times \frac{1000\ \text{mL}}{1\ \cancel{\text{L}}} = 3.78 \times 10^3\ \text{mL}$$

Then,

$$\text{density} = \frac{4.20 \times 10^3\ \text{g}}{3.78 \times 10^3\ \text{mL}} = 1.11\ \text{g/mL}$$

Alternatively, the calculation could be set up in a way that uses three unit conversion factors sequentially as follows:

$$\frac{9.26\ \cancel{\text{lb}}}{4.00\ \cancel{\text{qt}}} \times \frac{453.59\ \text{g}}{1\ \cancel{\text{lb}}} \times \frac{1.0567\ \cancel{\text{qt}}}{1\ \cancel{\text{L}}} \times \frac{1\ \cancel{\text{L}}}{1000\ \text{mL}} = 1.11\ \text{g/mL}$$

? Exercise 1.7.2

What is the volume in liters of 1.000 oz, given that 1 L = 1.0567 qt and 1 qt = 32 oz (exactly)?

Answer

2.956×10^{-2} L

Example 1.7.3: Computing Quantities from Measurement Results

While being driven from Philadelphia to Atlanta, a distance of about 1250 km, a 2014 Lamborghini Aventador Roadster uses 213 L gasoline.

a. What (average) fuel economy, in miles per gallon, did the Roadster get during this trip?
b. If gasoline costs $3.80 per gallon, what was the fuel cost for this trip?

Solution

(a) We first convert distance from kilometers to miles:

$$1250\ \text{km} \times \frac{0.62137\ \text{mi}}{1\ \text{km}} = 777\ \text{mi}$$

and then convert volume from liters to gallons:

$$213\ \cancel{\text{L}} \times \frac{1.0567\ \cancel{\text{qt}}}{1\ \cancel{\text{L}}} \times \frac{1\ \text{gal}}{4\ \cancel{\text{qt}}} = 56.3\ \text{gal}$$

Then,

$$\text{(average) mileage} = \frac{777\ \text{mi}}{56.3\ \text{gal}} = 13.8\ \text{miles/gallon} = 13.8\ \text{mpg}$$

Alternatively, the calculation could be set up in a way that uses all the conversion factors sequentially, as follows:

$$\frac{1250\ \cancel{\text{km}}}{213\ \cancel{\text{L}}} \times \frac{0.62137\ \text{mi}}{1\ \cancel{\text{km}}} \times \frac{1\ \cancel{\text{L}}}{1.0567\ \cancel{\text{qt}}} \times \frac{4\ \cancel{\text{qt}}}{1\ \text{gal}} = 13.8\ \text{mpg}$$

(b) Using the previously calculated volume in gallons, we find:

$$56.3\ \text{gal} \times \frac{\$3.80}{1\ \text{gal}} = \$214$$

Exercise 1.7.3

A Toyota Prius Hybrid uses 59.7 L gasoline to drive from San Francisco to Seattle, a distance of 1300 km (two significant digits).

a. What (average) fuel economy, in miles per gallon, did the Prius get during this trip?
b. If gasoline costs $3.90 per gallon, what was the fuel cost for this trip?

Answer a

51 mpg

Answer b

$62

Conversion of Temperature Units

We use the word temperature to refer to the hotness or coldness of a substance. One way we measure a change in temperature is to use the fact that most substances expand when their temperature increases and contract when their temperature decreases. The mercury or alcohol in a common glass thermometer changes its volume as the temperature changes. Because the volume of the liquid changes more than the volume of the glass, we can see the liquid expand when it gets warmer and contract when it gets cooler.

To mark a scale on a thermometer, we need a set of reference values: Two of the most commonly used are the freezing and boiling temperatures of water at a specified atmospheric pressure. On the Celsius scale, 0 °C is defined as the freezing temperature of water and 100 °C as the boiling temperature of water. The space between the two temperatures is divided into 100 equal intervals, which

we call degrees. On the Fahrenheit scale, the freezing point of water is defined as 32 °F and the boiling temperature as 212 °F. The space between these two points on a Fahrenheit thermometer is divided into 180 equal parts (degrees).

Defining the Celsius and Fahrenheit temperature scales as described in the previous paragraph results in a slightly more complex relationship between temperature values on these two scales than for different units of measure for other properties. Most measurement units for a given property are directly proportional to one another (y = mx). Using familiar length units as one example:

$$\text{length in feet} = \left(\frac{1\ \text{ft}}{12\ \text{in.}}\right) \times \text{length in inches} \tag{1.7.9}$$

where

- y = length in feet,
- x = length in inches, and
- the proportionality constant, m, is the conversion factor.

The Celsius and Fahrenheit temperature scales, however, do not share a common zero point, and so the relationship between these two scales is a linear one rather than a proportional one ($y = mx + b$). Consequently, converting a temperature from one of these scales into the other requires more than simple multiplication by a conversion factor, m, it also must take into account differences in the scales' zero points (b).

The linear equation relating Celsius and Fahrenheit temperatures is easily derived from the two temperatures used to define each scale. Representing the Celsius temperature as x and the Fahrenheit temperature as y, the slope, m, is computed to be:

$$\begin{aligned} m &= \frac{\Delta y}{\Delta x} \\ &= \frac{212\ ^\circ\text{F} - 32\ ^\circ\text{F}}{100\ ^\circ\text{C} - 0\ ^\circ\text{C}} \\ &= \frac{180\ ^\circ\text{F}}{100\ ^\circ\text{C}} \\ &= \frac{9\ ^\circ\text{F}}{5\ ^\circ\text{C}} \end{aligned}$$

The y-intercept of the equation, b, is then calculated using either of the equivalent temperature pairs, (100 °C, 212 °F) or (0 °C, 32 °F), as:

$$\begin{aligned} b &= y - mx \\ &= 32\ ^\circ\text{F} - \frac{9\ ^\circ\text{F}}{5\ ^\circ\text{C}} \times 0\ ^\circ\text{C} \\ &= 32\ ^\circ\text{F} \end{aligned}$$

The equation relating the temperature scales is then:

$$T_{^\circ\text{F}} = \left(\frac{9\ ^\circ\text{F}}{5\ ^\circ\text{C}} \times T_{^\circ\text{C}}\right) + 32\ ^\circ\text{C} \tag{1.7.10}$$

An abbreviated form of this equation that omits the measurement units is:

$$T_{^\circ\text{F}} = \frac{9}{5} \times T_{^\circ\text{C}} + 32 \tag{1.7.11}$$

Rearrangement of this equation yields the form useful for converting from Fahrenheit to Celsius:

$$T_{^\circ\text{C}} = \frac{5}{9}(T_{^\circ\text{F}} + 32) \tag{1.7.12}$$

As mentioned earlier in this chapter, the SI unit of temperature is the kelvin (K). Unlike the Celsius and Fahrenheit scales, the kelvin scale is an absolute temperature scale in which 0 (zero) K corresponds to the lowest temperature that can theoretically be achieved. The early 19th-century discovery of the relationship between a gas's volume and temperature suggested that the volume of a gas would be zero at −273.15 °C. In 1848, British physicist William Thompson, who later adopted the title of Lord Kelvin,

proposed an absolute temperature scale based on this concept (further treatment of this topic is provided in this text's chapter on gases).

The freezing temperature of water on this scale is 273.15 K and its boiling temperature 373.15 K. Notice the numerical difference in these two reference temperatures is 100, the same as for the Celsius scale, and so the linear relation between these two temperature scales will exhibit a slope of $1\ \frac{\text{K}}{^\circ\text{C}}$. Following the same approach, the equations for converting between the kelvin and Celsius temperature scales are derived to be:

$$T_{\text{K}} = T_{^\circ\text{C}} + 273.15 \tag{1.7.13}$$

$$T_{^\circ\text{C}} = T_{\text{K}} - 273.15 \tag{1.7.14}$$

The 273.15 in these equations has been determined experimentally, so it is not exact. Figure 1.7.1 shows the relationship among the three temperature scales. Recall that we do not use the degree sign with temperatures on the kelvin scale.




Figure 1.7.1: The Fahrenheit, Celsius, and kelvin temperature scales are compared.

Although the kelvin (absolute) temperature scale is the official SI temperature scale, Celsius is commonly used in many scientific contexts and is the scale of choice for nonscience contexts in almost all areas of the world. Very few countries (the U.S. and its territories, the Bahamas, Belize, Cayman Islands, and Palau) still use Fahrenheit for weather, medicine, and cooking.

✔ Example 1.7.4: Conversion from Celsius

Normal body temperature has been commonly accepted as 37.0 °C (although it varies depending on time of day and method of measurement, as well as among individuals). What is this temperature on the kelvin scale and on the Fahrenheit scale?

Solution

$$\text{K} = {}^\circ\text{C} + 273.15 = 37.0 + 273.2 = 310.2\ \text{K}$$

$${}^\circ\text{F} = \frac{9}{5}\ {}^\circ\text{C} + 32.0 = \left(\frac{9}{5} \times 37.0\right) + 32.0 = 66.6 + 32.0 = 98.6\ {}^\circ\text{F}$$

? Exercise 1.7.4

Convert 80.92 °C to K and °F.

Answer

354.07 K, 177.7 °F

Example 1.7.5: Conversion from Fahrenheit

Baking a ready-made pizza calls for an oven temperature of 450 °F. If you are in Europe, and your oven thermometer uses the Celsius scale, what is the setting? What is the kelvin temperature?

Solution

$$°\mathrm{C} = \frac{5}{9}(°\mathrm{F} - 32) = \frac{5}{9}(450 - 32) = \frac{5}{9} \times 418 = 232°\mathrm{C} \rightarrow \text{set oven to } 230°\mathrm{C}$$
$$\text{(two significant figures)}$$

$$\mathrm{K} = °\mathrm{C} + 273.15 = 230 + 273 = 503\ \mathrm{K} \rightarrow 5.0 \times 10^2\ \mathrm{K} \quad \text{(two significant figures)}$$

Exercise 1.7.5

Convert 50 °F to °C and K.

Answer

10 °C, 280 K

Summary

Measurements are made using a variety of units. It is often useful or necessary to convert a measured quantity from one unit into another. These conversions are accomplished using unit conversion factors, which are derived by simple applications of a mathematical approach called the factor-label method or dimensional analysis. This strategy is also employed to calculate sought quantities using measured quantities and appropriate mathematical relations.

Key Equations

- $T_{°\mathrm{C}} = \frac{5}{9} \times T_{°\mathrm{F}} - 32$
- $T_{°\mathrm{F}} = \frac{9}{5} \times T_{°\mathrm{C}} + 32$
- $T_{\mathrm{K}} = °\mathrm{C} + 273.15$
- $T_{°\mathrm{C}} = \mathrm{K} - 273.15$

Glossary

dimensional analysis
(also, factor-label method) versatile mathematical approach that can be applied to computations ranging from simple unit conversions to more complex, multi-step calculations involving several different quantities

Fahrenheit
unit of temperature; water freezes at 32 °F and boils at 212 °F on this scale

unit conversion factor
ratio of equivalent quantities expressed with different units; used to convert from one unit to a different unit

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

1.7: Dimensional Analysis- a Problem Solving Method Used in Chemistry is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **1.6: Mathematical Treatment of Measurement Results** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

1.8: End of Chapter Problems

1. dentify each of the following statements as being most similar to a hypothesis, a law, or a theory. Explain your reasoning.
    a. Falling barometric pressure precedes the onset of bad weather.
    b. All life on earth has evolved from a common, primitive organism through the process of natural selection.
    c. My truck's gas mileage has dropped significantly, probably because it's due for a tune-up.
2. Identify each of the following statements as being most similar to a hypothesis, a law, or a theory. Explain your reasoning.
    a. The pressure of a sample of gas is directly proportional to the temperature of the gas.
    b. Matter consists of tiny particles that can combine in specific ratios to form substances with specific properties.
    c. At a higher temperature, solids (such as salt or sugar) will dissolve better in water.

Answer

a. law (states a consistently observed phenomenon, can be used for prediction); b. theory (a widely accepted explanation of the behavior of matter); c. hypothesis (a tentative explanation, can be investigated by experimentation)

3. Identify each of the underlined items as a part of either the macroscopic domain, the microscopic domain, or the symbolic domain of chemistry. For any in the symbolic domain, indicate whether they are symbols for a macroscopic or a microscopic feature.
    a. The mass of a lead pipe is 14 lb.
    b. The mass of a certain chlorine atom is 35 amu.
    c. A bottle with a label that reads Al contains aluminum metal.
    d. Al is the symbol for an aluminum atom.
4. Identify each of the underlined items as a part of either the macroscopic domain, the microscopic domain, or the symbolic domain of chemistry. For those in the symbolic domain, indicate whether they are symbols for a macroscopic or a microscopic feature.
    a. A certain molecule contains one H atom and one Cl atom.
    b. Copper wire has a density of about 8 g/cm^3.
    c. The bottle contains 15 grams of Ni powder.
    d. A sulfur molecule is composed of eight sulfur atoms.

Answer

a. symbolic, microscopic; b. macroscopic; c. symbolic, macroscopic; d. microscopic

5. Why do we use an object's mass, rather than its weight, to indicate the amount of matter it contains?
6. What properties distinguish solids from liquids? Liquids from gases? Solids from gases?

Answer

Liquids can change their shape (flow); solids can't. Gases can undergo large volume changes as pressure changes; liquids do not. Gases flow and change volume; solids do not.

7. How does a heterogeneous mixture differ from a homogeneous mixture? How are they similar?
8. How does a homogeneous mixture differ from a pure substance? How are they similar?

Answer

The mixture can have a variety of compositions; a pure substance has a definite composition. Both have the same composition from point to point.

9. How does an element differ from a compound? How are they similar?
10. How do molecules of elements and molecules of compounds differ? In what ways are they similar?

Answer

Molecules of elements contain only one type of atom; molecules of compounds contain two or more types of atoms. They are similar in that both are comprised of two or more atoms chemically bonded together.

11. How does an atom differ from a molecule? In what ways are they similar?
12. Many of the items you purchase are mixtures of pure compounds. Select three of these commercial products and prepare a list of the ingredients that are pure compounds.Classify each of the following as an element, a compound, or a mixture:
    a. copper
    b. water
    c. nitrogen
    d. sulfur
    e. air
    f. sucrose
    g. a substance composed of molecules each of which contains two iodine atoms
13. Classify each of the following as an element, a compound, or a mixture:
    a. iron
    b. oxygen
    c. mercury oxide
    d. pancake syrup
    e. carbon dioxide
    f. a substance composed of molecules each of which contains one hydrogen atom and one chlorine atom
    g. baking soda
    h. baking powder

Answer

a. (a) element; (b) element; (c) compound; (d) mixture, (e) compound; (f) compound; (g) compound; (h) mixture

14. A sulfur atom and a sulfur molecule are not identical. What is the difference?
15. How are the molecules in oxygen gas, the molecules in hydrogen gas, and water molecules similar? How do they differ?

Answer

a. In each case, a molecule consists of two or more combined atoms. They differ in that the types of atoms change from one substance to the next.

16. We refer to astronauts in space as weightless, but not without mass. Why?
17. As we drive an automobile, we don't think about the chemicals consumed and produced. Prepare a list of the principal chemicals consumed and produced during the operation of an automobile.

Answer

Gasoline (a mixture of compounds), oxygen, and to a lesser extent, nitrogen are consumed. Carbon dioxide and water are the principal products. Carbon monoxide and nitrogen oxides are produced in lesser amounts.

18. Matter is everywhere around us. Make a list by name of fifteen different kinds of matter that you encounter every day. Your list should include (and label at least one example of each) the following: a solid, a liquid, a gas, an element, a compound, a homogenous mixture, a heterogeneous mixture, and a pure substance.
19. When elemental iron corrodes it combines with oxygen in the air to ultimately form red brown iron(III) oxide which we call rust. (a) If a shiny iron nail with an initial mass of 23.2 g is weighed after being coated in a layer of rust, would you expect the mass to have increased, decreased, or remained the same? Explain. (b) If the mass of the iron nail increases to 24.1 g, what mass of oxygen combined with the iron?

Answer

(a) Increased as it would have combined with oxygen in the air thus increasing the amount of matter and therefore the mass. (b) 0.9 g

20. As stated in the text, convincing examples that demonstrate the law of conservation of matter outside of the laboratory are few and far between. Indicate whether the mass would increase, decrease, or stay the same for the following scenarios where chemical reactions take place:
    a. Exactly one pound of bread dough is placed in a baking tin. The dough is cooked in an oven at 350 °F releasing a wonderful aroma of freshly baked bread during the cooking process. Is the mass of the baked loaf less than, greater than, or the same as the one pound of original dough? Explain.
    b. When magnesium burns in air a white flaky ash of magnesium oxide is produced. Is the mass of magnesium oxide less than, greater than, or the same as the original piece of magnesium? Explain.
    c. Antoine Lavoisier, the French scientist credited with first stating the law of conservation of matter, heated a mixture of tin and air in a sealed flask to produce tin oxide. Did the mass of the sealed flask and contents decrease, increase, or remain the same after the heating?
21. Yeast converts glucose to ethanol and carbon dioxide during anaerobic fermentation as depicted in the simple chemical equation here:

$$\text{glucose} \rightarrow \text{ethanol} + \text{carbon dioxide} \tag{1.8.1}$$

    a. If 200.0 g of glucose is fully converted, what will be the total mass of ethanol and carbon dioxide produced?
    b. If the fermentation is carried out in an open container, would you expect the mass of the container and contents after fermentation to be less than, greater than, or the same as the mass of the container and contents before fermentation? Explain.
    c. If 97.7 g of carbon dioxide is produced, what mass of ethanol is produced?

Answer

a. 200.0 g; b. The mass of the container and contents would decrease as carbon dioxide is a gaseous product and would leave the container; c. 102.3 g

22. Classify the six underlined properties in the following paragraph as chemical or physical:

    Fluorine is a pale yellow gas that reacts with most substances. The free element melts at −220 °C and boils at −188 °C. Finely divided metals burn in fluorine with a bright flame. Nineteen grams of fluorine will react with 1.0 gram of hydrogen.

23. Classify each of the following changes as physical or chemical:
    a. condensation of steam
    b. burning of gasoline
    c. souring of milk
    d. dissolving of sugar in water
    e. melting of gold

Answer

a. a physical; b. chemical; c. chemical; d. physical; e. physical

24. Classify each of the following changes as physical or chemical:
    a. coal burning
    b. ice melting
    c. mixing chocolate syrup with milk
    d. explosion of a firecracker
    e. magnetizing of a screwdriver
25. The volume of a sample of oxygen gas changed from 10 mL to 11 mL as the temperature changed. Is this a chemical or physical change?

Answer

physical

26. A 2.0-liter volume of hydrogen gas combined with 1.0 liter of oxygen gas to produce 2.0 liters of water vapor. Does oxygen undergo a chemical or physical change? Explain the difference between extensive properties and intensive properties.
27. The value of an extensive property depends upon the amount of matter being considered, whereas the value of an intensive property is the same regardless of the amount of matter being considered. Identify the following properties as either extensive or intensive.
    a. volume
    b. temperature
    c. humidity
    d. heat
    e. boiling point
28. The density (d) of a substance is an intensive property that is defined as the ratio of its mass (m) to its volume (V).

$$\text{density} = \frac{\text{mass}}{\text{volume}} \quad \text{d} = \frac{\text{m}}{\text{V}}$$

Answer

a. Being extensive properties, both mass and volume are directly proportional to the amount of substance under study. Dividing one extensive property by another will in effect “cancel” this dependence on amount, yielding a ratio that is independent of amount (an intensive property).

29. Is one liter about an ounce, a pint, a quart, or a gallon?
30. Is a meter about an inch, a foot, a yard, or a mile?
31. Indicate the SI base units or derived units that are appropriate for the following measurements:
    a. the length of a marathon race (26 miles 385 yards)
    b. the mass of an automobile
    c. the volume of a swimming pool
    d. the speed of an airplane
    e. the density of gold
    f. the area of a football field
    g. the maximum temperature at the South Pole on April 1, 1913
32. Indicate the SI base units or derived units that are appropriate for the following measurements:
    a. the mass of the moon
    b. the distance from Dallas to Oklahoma City
    c. the speed of sound
    d. the density of air
    e. the temperature at which alcohol boils
    f. the area of the state of Delaware
    g. the volume of a flu shot or a measles vaccination

Answer

a.kilograms; b. meters; c. kilometers/second; d. kilograms/cubic meter; e. kelvin; f. square meters; g. cubic meters

33. Give the name and symbol of the prefixes used with SI units to indicate multiplication by the following exact quantities.
    a. 10^3
    b. 0^{-2}
    c. 0.1
    d. 10^{-3}
    e. 1,000,000

f. 0.000001

34. Give the name of the prefix and the quantity indicated by the following symbols that are used with SI base units.

a. c
b. d
c. G
d. k
e. m
f. n
g. p
h. T

Answer

a. centi-, $\times\times 10^{-2}$; b. deci-, $\times\times 10^{-1}$; c. Giga-, $\times\times 10^{9}$; d. kilo-, $\times\times 10^{3}$; e. milli-, $\times\times 10^{-3}$; f.nano-, $\times\times 10^{-9}$; g. pico-, $\times\times 10^{-12}$; h. tera-, $\times\times 10^{12}$

35. A large piece of jewelry has a mass of 132.6 g. A graduated cylinder initially contains 48.6 mL water. When the jewelry is submerged in the graduated cylinder, the total volume increases to 61.2 mL.

a. Determine the density of this piece of jewelry.
b. Assuming that the jewelry is made from only one substance, what substance is it likely to be? Explain

36. Express each of the following numbers in scientific notation with correct significant figures:

a. 711.0
b. 0.239
c. 90743
d. 134.2
e. 0.05499
f. 10000.0
g. 0.000000738592

37. Express each of the following numbers in exponential notation with correct significant figures:

a. 704
b. 0.03344
c. 547.9
d. 22086
e. 1000.00
f. 0.0000000651
g. 0.007157

Answer

a. $7.04 \times\times 10^{2}$; b. $3.344 \times\times 10^{-2}$; c. $5.479 \times\times 10^{2}$; d. $2.2086 \times\times 10^{4}$; e. $1.00000 \times\times 10^{3}$; f. $6.51 \times\times 10^{-8}$; g. $7.157 \times\times 10^{-3}$

38. Indicate whether each of the following can be determined exactly or must be measured with some degree of uncertainty:

a. the number of eggs in a basket
b. the mass of a dozen eggs
c. the number of gallons of gasoline necessary to fill an automobile gas tank
d. the number of cm in 2 m
e. the mass of a textbook
f. the time required to drive from San Francisco to Kansas City at an average speed of 53 mi/h

39. Indicate whether each of the following can be determined exactly or must be measured with some degree of uncertainty:

a. the number of seconds in an hour
b. the number of pages in this book

c. the number of grams in your weight
d. the number of grams in 3 kilograms
e. the volume of water you drink in one day
f. the distance from San Francisco to Kansas City

Answer

a. exact; b. exact; c. uncertain; d. exact; e. uncertain; f. uncertain

40. How many significant figures are contained in each of the following measurements?

a. 38.7 g
b. 2×10^{18} m
c. 3,486,002 kg
d. 9.74150×10^{-4} J
e. 0.0613 cm^3
f. 17.0 kg
g. 0.01400 g/mL

41. How many significant figures are contained in each of the following measurements?

a. 53 cm
b. 2.05×10^{8} m
c. 86,002 J
d. 9.740×10^{4} m/s
e. 10.0613 m^3
f. 0.17 g/mL
g. 0.88400 s

Answer

a. two; b. three; c. five; d. four; e. six; f. two; g. five

42. The following quantities were reported on the labels of commercial products. Determine the number of significant figures in each.

a. 0.0055 g active ingredients
b. 12 tablets
c. 3% hydrogen peroxide
d. 5.5 ounces
e. 473 mL
f. 1.75% bismuth
g. 0.001% phosphoric acid
h. 99.80% inert ingredients

43. Round off each of the following numbers to two significant figures:

a. 0.436
b. 9.000
c. 27.2
d. 135
e. 1.497×10^{-3}
f. 0.445

Answer

a. 0.44; b. 9.0; c. 27; d. 140; e. $1.5 \times\times 10^{-3}$; f. 0.44

44. Round off each of the following numbers to two significant figures:

a. 517
b. 86.3
c. 6.382×10^3
d. 5.0008
e. 22.497
f. 0.885

45. Perform the following calculations and report each answer with the correct number of significant figures.

a. 628×342
b. $(5.63 \times 10^2) \times (7.4 \times 10^3)$
c. $\frac{28.0}{13.483}$
d. 8119×0.000023
e. 14.98 + 27,340 + 84.7593
f. 42.7 + 0.259

Answer


a. $2.15 \times\times 10^5$; b. $4.2 \times\times 10^6$; c. 2.08; d. 0.19; e. 27,440; f. 43.0

46. Perform the following calculations and report each answer with the correct number of significant figures.

a. 62.8×34
b. 0.147 + 0.0066 + 0.012
c. $38 \times 95 \times 1.792$
d. 15 – 0.15 – 0.6155
e. $8.78 \times \left(\frac{0.0500}{0.478}\right)$
f. 140 + 7.68 + 0.014
g. 28.7 – 0.0483
h. $\frac{(88.5 - 87.57)}{45.13}$

47. Consider the results of the archery contest shown in this figure.

a. Which archer is most precise?
b. Which archer is most accurate?
c. Who is both least precise and least accurate?


4 targets are shown each with 4 holes indicating where the arrows hit the targets. Archer W put all 4 arrows closely around the center of the target. Archer X put all 4 arrows in a tight cluster but far to the lower right of the target. Archer Y put all 4 arrows at different corners of the target. All 4 arrows are very far from the center of the target. Archer Z put 2 arrows close to the target and 2 other arrows far outside of the target.

Answer

a. Archer X; b. Archer W; c. Archer Y

48. Classify the following sets of measurements as accurate, precise, both, or neither.

a. Checking for consistency in the weight of chocolate chip cookies: 17.27 g, 13.05 g, 19.46 g, 16.92 g
b. Testing the volume of a batch of 25-mL pipettes: 27.02 mL, 26.99 mL, 26.97 mL, 27.01 mL
c. Determining the purity of gold: 99.9999%, 99.9998%, 99.9998%, 99.9999%

49. Write conversion factors (as ratios) for the number of:

a. yards in 1 meter
b. liters in 1 liquid quart
c. pounds in 1 kilogram

Answer

a. $\frac{1.0936\ \text{yd}}{1\ \text{m}}$; b. $\frac{0.94635\ \text{L}}{1\ \text{qt}}$; c. $\frac{2.2046\ \text{lb}}{1\ \text{kg}}$

50. Write conversion factors (as ratios) for the number of:
    a. kilometers in 1 mile
    b. liters in 1 cubic foot
    c. grams in 1 ounce
51. The label on a soft drink bottle gives the volume in two units: 2.0 L and 67.6 fl oz. Use this information to derive a conversion factor between the English and metric units. How many significant figures can you justify in your conversion factor?

Answer

Only two significant figures are justified.

52. The label on a box of cereal gives the mass of cereal in two units: 978 grams and 34.5 oz. Use this information to find a conversion factor between the English and metric units. How many significant figures can you justify in your conversion factor?
53. Soccer is played with a round ball having a circumference between 27 and 28 in. and a weight between 14 and 16 oz. What are these specifications in units of centimeters and grams?

Answer

68–71 cm; 400–450 g

54. A woman's basketball has a circumference between 28.5 and 29.0 inches and a maximum weight of 20 ounces (two significant figures). What are these specifications in units of centimeters and grams?
55. How many milliliters of a soft drink are contained in a 12.0-oz can?

Answer

355 mL

56. A barrel of oil is exactly 42 gal. How many liters of oil are in a barrel?
57. The diameter of a red blood cell is about 3×10^{-4} in. What is its diameter in centimeters?

Answer

$8 \times\times 10^{-4}$ cm

58. The distance between the centers of the two oxygen atoms in an oxygen molecule is 1.21×10^{-8} cm. What is this distance in inches?
59. Is a 197-lb weight lifter light enough to compete in a class limited to those weighing 90 kg or less?

Answer

yes; weight = 89.4 kg

60. A very good 197-lb weight lifter lifted 192 kg in a move called the clean and jerk. What was the mass of the weight lifted in pounds?
61. Many medical laboratory tests are run using 5.0 µL blood serum. What is this volume in milliliters?

Answer

$5.0 \times\times 10^{-3}$ mL

62. If an aspirin tablet contains 325 mg aspirin, how many grams of aspirin does it contain?
63. Use scientific (exponential) notation to express the following quantities in terms of the SI base units in [link]:
    a. 0.13 g
    b. 232 Gg
    c. 5.23 pm
    d. 86.3 mg

e. 37.6 cm
f. 54 μm
g. 1 Ts
h. 27 ps
i. 0.15 mK

Answer

a. $1.3 \times\times 10^{-4}$ kg; b. $2.32 \times\times 10^{8}$ kg; c. $5.23 \times\times 10^{-12}$ m; d. $8.63 \times\times 10^{-5}$ kg; e. $3.76 \times\times 10^{-1}$ m; f. $5.4 \times\times 10^{-5}$ m; g. $1 \times\times 10^{12}$ s; h. $2.7 \times\times 10^{-11}$ s; i. $1.5 \times\times 10^{-4}$ K

64. Complete the following conversions between SI units.

a. 612 g = _____ mg
b. 8.160 m = _____ cm
c. 3779 μg = _____ g
d. 781 mL = _____ L
e. 4.18 kg = _____ g
f. 27.8 m = _____ km
g. 0.13 mL = _____ L
h. 1738 km = _____ m
i. 1.9 Gg = _____ g

65. Gasoline is sold by the liter in many countries. How many liters are required to fill a 12.0-gal gas tank?

Answer

45.4 L

66. Milk is sold by the liter in many countries. What is the volume of exactly 1/2 gal of milk in liters?
67. A long ton is defined as exactly 2240 lb. What is this mass in kilograms?

Answer

$1.0160 \times\times 10^{3}$ kg

68. Make the conversion indicated in each of the following:

a. the men's world record long jump, 29 ft 4¼ in., to meters
b. the greatest depth of the ocean, about 6.5 mi, to kilometers
c. the area of the state of Oregon, 96,981 mi^2, to square kilometers
d. the volume of 1 gill (exactly 4 oz) to milliliters
e. the estimated volume of the oceans, 330,000,000 mi^3, to cubic kilometers.
f. the mass of a 3525-lb car to kilograms
g. the mass of a 2.3-oz egg to grams

69. Make the conversion indicated in each of the following:

a. the length of a soccer field, 120 m (three significant figures), to feet
b. the height of Mt. Kilimanjaro, at 19,565 ft the highest mountain in Africa, to kilometers
c. the area of an 8.5 t 11-inch sheet of paper in cm^2
d. the displacement volume of an automobile engine, 161 $in.^3$, to liters
e. the estimated mass of the atmosphere, 5.6 t 10^{15} tons, to kilograms
f. the mass of a bushel of rye, 32.0 lb, to kilograms
g. the mass of a 5.00-grain aspirin tablet to milligrams (1 grain = 0.00229 oz)

Answer

a. 394 ft; b. 5.9634 km; c. $6.0 \times\times 10^{2}$; d. 2.64 L; e. $5.1 \times\times 10^{18}$ kg; f. 14.5 kg; g. 324 mg

70. The gas tank of a certain luxury automobile holds 22.3 gallons according to the owner's manual. If the density of gasoline is 0.8206 g/mL, determine the mass in kilograms and pounds of the fuel in a full tank.
71. As an instructor is preparing for an experiment, he requires 225 g phosphoric acid. The only container readily available is a 150-mL Erlenmeyer flask. Is it large enough to contain the acid, whose density is 1.83 g/mL?

Answer

Yes, the acid's volume is 123 mL.

72. To prepare for a laboratory period, a student lab assistant needs 125 g of a compound. A bottle containing 1/4 lb is available. Did the student have enough of the compound?
73. A chemistry student is 159 cm tall and weighs 45.8 kg. What is her height in inches and weight in pounds?

Answer

62.6 in (about 5 ft 3 in.) and 101 lb

74. In a recent Grand Prix, the winner completed the race with an average speed of 229.8 km/h. What was his speed in miles per hour, meters per second, and feet per second?
75. Solve these problems about lumber dimensions.
    a. To describe to a European how houses are constructed in the US, the dimensions of "two-by-four" lumber must be converted into metric units. The thickness × width × length dimensions are 1.50 in. × 3.50 in. × 8.00 ft in the US. What are the dimensions in cm × cm × m?
    b. (b) This lumber can be used as vertical studs, which are typically placed 16.0 in. apart. What is that distance in centimeters?

Answer

a. 3.81 cm ×× 8.89 cm ×× 2.44 m; b. 40.6 cm

76. The mercury content of a stream was believed to be above the minimum considered safe—1 part per billion (ppb) by weight. An analysis indicated that the concentration was 0.68 parts per billion. What quantity of mercury in grams was present in 15.0 L of the water, the density of which is 0.998 g/ml? $\left(1\text{ ppb Hg} = \frac{1\text{ ng Hg}}{1\text{ g water}}\right)$
77. Calculate the density of aluminum if 27.6 cm^3 has a mass of 74.6 g.

Answer

2.70 g/cm^3

78. Osmium is one of the densest elements known. What is its density if 2.72 g has a volume of 0.121 cm^3?
79. Calculate these masses.
    a. What is the mass of 6.00 cm^3 of mercury, density = 13.5939 g/cm^3?
    b. What is the mass of 25.0 mL octane, density = 0.702 g/cm^3?

Answer

a. 81.6 g; b. 17.6 g

80. Calculate these masses.
    a. What is the mass of 4.00 cm^3 of sodium, density = 0.97 g/cm?
    b. What is the mass of 125 mL gaseous chlorine, density = 3.16 g/L?
81. Calculate these volumes.
    a. What is the volume of 25 g iodine, density = 4.93 g/cm^3?
    b. What is the volume of 3.28 g gaseous hydrogen, density = 0.089 g/L?

Answer

a. 5.1 mL; b. 37 L

82. Calculate these volumes.
    a. What is the volume of 11.3 g graphite, density = 2.25 g/cm^3?
    b. What is the volume of 39.657 g bromine, density = 2.928 g/cm^3?
83. Convert the boiling temperature of gold, 2966 °C, into degrees Fahrenheit and kelvin.

Answer

5371 °F, 3239 K

84. Convert the temperature of scalding water, 54 °C, into degrees Fahrenheit and kelvin.
85. Convert the temperature of the coldest area in a freezer, −10 °F, to degrees Celsius and kelvin.

Answer

−23 °C, 250 K

86. Convert the temperature of dry ice, −77 °C, into degrees Fahrenheit and kelvin.
87. Convert the boiling temperature of liquid ammonia, −28.1 °F, into degrees Celsius and kelvin.

Answer

−33.4 °C, 239.8 K

88. The label on a pressurized can of spray disinfectant warns against heating the can above 130 °F. What are the corresponding temperatures on the Celsius and kelvin temperature scales? >
89. The weather in Europe was unusually warm during the summer of 1995. The TV news reported temperatures as high as 45 °C. What was the temperature on the Fahrenheit scale?

Answer

113 °F

1.8: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

2: Atoms and Elements

2.1: Early Ideas of Atomic Theories
2.2: Development of Modern Atomic Tehory
2.3: Atomic Structure, Names/Symbols of Atoms, and Ions
2.4: Periodic Table
2.5: Isotopes and Average Atomic Mass
2.6: Molar Mass of Elements
2.7: End of Chapter Problems

2: Atoms and Elements is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

2.1: Early Ideas of Atomic Theories

Learning Objectives

- State the postulates of Dalton's atomic theory
- Use postulates of Dalton's atomic theory to explain the laws of definite and multiple proportions

The earliest recorded discussion of the basic structure of matter comes from ancient Greek philosophers, the scientists of their day. In the fifth century BC, Leucippus and Democritus argued that all matter was composed of small, finite particles that they called *atomos*, a term derived from the Greek word for "indivisible." They thought of atoms as moving particles that differed in shape and size, and which could join together. Later, Aristotle and others came to the conclusion that matter consisted of various combinations of the four "elements"—fire, earth, air, and water—and could be infinitely divided. Interestingly, these philosophers thought about atoms and "elements" as philosophical concepts, but apparently never considered performing experiments to test their ideas.

Atomic Theory through the Nineteenth Century

The Aristotelian view of the composition of matter held sway for over two thousand years, until English schoolteacher John Dalton helped to revolutionize chemistry with his hypothesis that the behavior of matter could be explained using an atomic theory. First published in 1807, many of Dalton's hypotheses about the microscopic features of matter are still valid in modern atomic theory. Here are the postulates of Dalton's atomic theory.

1. Matter is composed of exceedingly small particles called atoms. An atom is the smallest unit of an element that can participate in a chemical change.
2. An element consists of only one type of atom, which has a mass that is characteristic of the element and is the same for all atoms of that element (Figure **2.1.1**). A macroscopic sample of an element contains an incredibly large number of atoms, all of which have identical chemical properties.




Figure **2.1.1**: A pre-1982 copper penny (left) contains approximately 3×10^{22} copper atoms (several dozen are represented as brown spheres at the right), each of which has the same chemical properties. (credit: modification of work by "slgckgc"/Flickr)

3. Atoms of one element differ in properties from atoms of all other elements.
4. A compound consists of atoms of two or more elements combined in a small, whole-number ratio. In a given compound, the numbers of atoms of each of its elements are always present in the same ratio (Figure **2.1.2**).




Figure **2.1.2**: Copper(II) oxide, a powdery, black compound, results from the combination of two types of atoms—copper (brown spheres) and oxygen (red spheres)—in a 1:1 ratio. (credit: modification of work by "Chemicalinterest"/Wikimedia Commons)

5. *Atoms are neither created nor destroyed during a chemical change, but are instead rearranged to yield substances that are different from those present before the change (Figure* **2.1.3***).*




Figure 2.1.3: When the elements copper (a shiny, red-brown solid, shown here as brown spheres) and oxygen (a clear and colorless gas, shown here as red spheres) react, their atoms rearrange to form a compound containing copper and oxygen (a powdery, black solid). (credit copper: modification of work by http://images-of-elements.com/copper.php).

Dalton's atomic theory provides a microscopic explanation of the many macroscopic properties of matter that you've learned about. For example, if an element such as copper consists of only one kind of atom, then it cannot be broken down into simpler substances, that is, into substances composed of fewer types of atoms. And if atoms are neither created nor destroyed during a chemical change, then the total mass of matter present when matter changes from one type to another will remain constant (the law of conservation of matter).

✔ Example 2.1.1: Testing Dalton's Atomic Theory

In the following drawing, the green spheres represent atoms of a certain element. The purple spheres represent atoms of another element. If the spheres touch, they are part of a single unit of a compound. Does the following chemical change represented by these symbols violate any of the ideas of Dalton's atomic theory? If so, which one?



Solution

The starting materials consist of two green spheres and two purple spheres. The products consist of only one green sphere and one purple sphere. This violates Dalton's postulate that atoms are neither created nor destroyed during a chemical change, but are merely redistributed. (In this case, atoms appear to have been destroyed.)

? Exercise 2.1.1

In the following drawing, the green spheres represent atoms of a certain element. The purple spheres represent atoms of another element. If the spheres touch, they are part of a single unit of a compound. Does the following chemical change represented by these symbols violate any of the ideas of Dalton's atomic theory? If so, which one



Answer

The starting materials consist of four green spheres and two purple spheres. The products consist of four green spheres and two purple spheres. This does not violate any of Dalton's postulates: Atoms are neither created nor destroyed, but are

redistributed in small, whole-number ratios.

Dalton knew of the experiments of French chemist Joseph Proust, who demonstrated that *all samples of a pure compound contain the same elements in the same proportion by mass*. This statement is known as the law of definite proportions or the law of constant composition. The suggestion that the numbers of atoms of the elements in a given compound always exist in the same ratio is consistent with these observations. For example, when different samples of isooctane (a component of gasoline and one of the standards used in the octane rating system) are analyzed, they are found to have a carbon-to-hydrogen mass ratio of 5.33:1, as shown in Table **2.1.1**.

Table **2.1.1**: Constant Composition of Isooctane

Sample	Carbon	Hydrogen	Mass Ratio
A	14.82 g	2.78 g	$\frac{14.82\text{ g carbon}}{2.78\text{ g hydrogen}} = \frac{5.33\text{ g carbon}}{1.00\text{ g hydrogen}}$
B	22.33 g	4.19 g	$\frac{22.33\text{ g carbon}}{4.19\text{ g hydrogen}} = \frac{5.33\text{ g carbon}}{1.00\text{ g hydrogen}}$
C	19.40 g	3.64 g	$\frac{19.40\text{ g carbon}}{3.63\text{ g hydrogen}} = \frac{5.33\text{ g carbon}}{1.00\text{ g hydrogen}}$

It is worth noting that although all samples of a particular compound have the same mass ratio, the converse is not true in general. That is, samples that have the same mass ratio are not necessarily the same substance. For example, there are many compounds other than isooctane that also have a carbon-to-hydrogen mass ratio of 5.33:1.00.

Dalton also used data from Proust, as well as results from his own experiments, to formulate another interesting law. The law of multiple proportions states that *when two elements react to form more than one compound, a fixed mass of one element will react with masses of the other element in a ratio of small, whole numbers*. For example, copper and chlorine can form a green, crystalline solid with a mass ratio of 0.558 g chlorine to 1 g copper, as well as a brown crystalline solid with a mass ratio of 1.116 g chlorine to 1 g copper. These ratios by themselves may not seem particularly interesting or informative; however, if we take a ratio of these ratios, we obtain a useful and possibly surprising result: a small, whole-number ratio.

$$\frac{\frac{1.116\text{ g Cl}}{1\text{ g Cu}}}{\frac{0.558\text{ g Cl}}{1\text{ g Cu}}} = \frac{2}{1} \tag{2.1.1}$$

This 2-to-1 ratio means that the brown compound has twice the amount of chlorine per amount of copper as the green compound.

This can be explained by atomic theory if the copper-to-chlorine ratio in the brown compound is 1 copper atom to 2 chlorine atoms, and the ratio in the green compound is 1 copper atom to 1 chlorine atom. The ratio of chlorine atoms (and thus the ratio of their masses) is therefore 2 to 1 (Figure **2.1.4**).




Figure **2.1.4**: Compared to the copper chlorine compound in (a), where copper is represented by brown spheres and chlorine by green spheres, the copper chlorine compound in (b) has twice as many chlorine atoms per copper atom. (credit a: modification of work by “Benjah-bmm27”/Wikimedia Commons; credit b: modification of work by “Walkerma”/Wikimedia Commons)

Example 2.1.2: Laws of Definite and Multiple Proportions

A sample of compound A (a clear, colorless gas) is analyzed and found to contain 4.27 g carbon and 5.69 g oxygen. A sample of compound B (also a clear, colorless gas) is analyzed and found to contain 5.19 g carbon and 13.84 g oxygen. Are these data an example of the law of definite proportions, the law of multiple proportions, or neither? What do these data tell you about substances A and B?

Solution

In compound A, the mass ratio of carbon to oxygen is:

$$\frac{1.33\ \text{g O}}{1\ \text{g C}}$$

In compound B, the mass ratio of carbon to oxygen is:

$$\frac{2.67\ \text{g O}}{1\ \text{g C}}$$

The ratio of these ratios is:

$$\frac{\frac{1.33\ \text{g O}}{1\ \text{g C}}}{\frac{2.67\ \text{g O}}{1\ \text{g C}}} = \frac{1}{2}$$

This supports the law of multiple proportions. This means that A and B are different compounds, with A having one-half as much carbon per amount of oxygen (or twice as much oxygen per amount of carbon) as B. A possible pair of compounds that would fit this relationship would be A = CO_2 and B = CO.

Exercise 2.1.2

A sample of compound X (a clear, colorless, combustible liquid with a noticeable odor) is analyzed and found to contain 14.13 g carbon and 2.96 g hydrogen. A sample of compound Y (a clear, colorless, combustible liquid with a noticeable odor that is slightly different from X's odor) is analyzed and found to contain 19.91 g carbon and 3.34 g hydrogen. Are these data an example of the law of definite proportions, the law of multiple proportions, or neither? What do these data tell you about substances X and Y?

Answer

In compound X, the mass ratio of carbon to hydrogen is $\frac{14.13\ \text{g C}}{2.96\ \text{g H}}$.

In compound Y, the mass ratio of carbon to oxygen is $\frac{19.91\ \text{g C}}{3.34\ \text{g H}}$.

The ratio of these ratios is

$$\frac{\frac{14.13\ \text{g C}}{2.96\ \text{g H}}}{\frac{19.91\ \text{g C}}{3.34\ \text{g H}}} = \frac{4.77\ \text{g C/g H}}{5.96\ \text{g C/g H}} = 0.800 = \frac{4}{5}.$$

This small, whole-number ratio supports the law of multiple proportions. This means that X and Y are different compounds.

Summary

The ancient Greeks proposed that matter consists of extremely small particles called atoms. Dalton postulated that each element has a characteristic type of atom that differs in properties from atoms of all other elements, and that atoms of different elements can combine in fixed, small, whole-number ratios to form compounds. Samples of a particular compound all have the same elemental

proportions by mass. When two elements form different compounds, a given mass of one element will combine with masses of the other element in a small, whole-number ratio. During any chemical change, atoms are neither created nor destroyed.

Glossary

Dalton's atomic theory

set of postulates that established the fundamental properties of atoms

law of constant composition

(also, law of definite proportions) all samples of a pure compound contain the same elements in the same proportions by mass

law of multiple proportions

when two elements react to form more than one compound, a fixed mass of one element will react with masses of the other element in a ratio of small whole numbers

law of definite proportions

(also, law of constant composition) all samples of a pure compound contain the same elements in the same proportions by mass

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

2.1: Early Ideas of Atomic Theories is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.2: Early Ideas in Atomic Theory** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

2.2: Development of Modern Atomic Tehory

Learning Objectives

- To become familiar with the components and structure of the atom.

Long before the end of the 19th century, it was well known that applying a high voltage to a gas contained at low pressure in a sealed tube (called a gas discharge tube) caused electricity to flow through the gas, which then emitted light (Figure **2.2.1**). Researchers trying to understand this phenomenon found that an unusual form of energy was also emitted from the cathode, or negatively charged electrode; this form of energy was called a cathode ray.




Figure **2.2.1**: A Gas Discharge Tube Producing Cathode Rays. When a high voltage is applied to a gas contained at low pressure in a gas discharge tube, electricity flows through the gas, and energy is emitted in the form of light. Image used with Permission (CC BY-SA-NC).

In 1897, the British physicist J. J. Thomson (1856–1940) proved that atoms were not the most basic form of matter. He demonstrated that cathode rays could be deflected, or bent, by magnetic or electric fields, which indicated that cathode rays consist of charged particles (Figure **2.2.2**). More important, by measuring the extent of the deflection of the cathode rays in magnetic or electric fields of various strengths, Thomson was able to calculate the mass-to-charge ratio of the particles. These particles were emitted by the negatively charged cathode and repelled by the negative terminal of an electric field. Because like charges repel each other and opposite charges attract, Thomson concluded that the particles had a net negative charge; these particles are now called electrons. Most relevant to the field of chemistry, Thomson found that the mass-to-charge ratio of cathode rays is independent of the nature of the metal electrodes or the gas, which suggested that electrons were fundamental components of all atoms.




Figure **2.2.2**: Deflection of Cathode Rays by an Electric Field. As the cathode rays travel toward the right, they are deflected toward the positive electrode (+), demonstrating that they are negatively charged. Image used with Permission (CC BY-SA-NC).

Subsequently, the American scientist Robert Millikan (1868–1953) carried out a series of experiments using electrically charged oil droplets, which allowed him to calculate the charge on a single electron. With this information and Thomson's mass-to-charge ratio, Millikan determined the mass of an electron:

$$\frac{mass}{charge} \times charge = mass \tag{2.2.1}$$

It was at this point that two separate lines of investigation began to converge, both aimed at determining how and why matter emits energy. The video below shows how JJ Thompson used such a tube to measure the ratio of charge over mass of an electron



Measuring e/m For an Electron. Video from Davidson College demonstrating Thompson's e/m experiment.

Radioactivity

The second line of investigation began in 1896, when the French physicist Henri Becquerel (1852–1908) discovered that certain minerals, such as uranium salts, emitted a new form of energy. Becquerel's work was greatly extended by Marie Curie (1867–1934) and her husband, Pierre (1854–1906); all three shared the Nobel Prize in Physics in 1903. Marie Curie coined the term radioactivity (from the Latin *radius*, meaning "ray") to describe the emission of energy rays by matter. She found that one particular uranium ore, pitchblende, was substantially more radioactive than most, which suggested that it contained one or more highly radioactive impurities. Starting with several tons of pitchblende, the Curies isolated two new radioactive elements after months of work: polonium, which was named for Marie's native Poland, and radium, which was named for its intense radioactivity. Pierre Curie carried a vial of radium in his coat pocket to demonstrate its greenish glow, a habit that caused him to become ill from radiation poisoning well before he was run over by a horse-drawn wagon and killed instantly in 1906. Marie Curie, in turn, died of what was almost certainly radiation poisoning.



Figure **2.2.3**: Radium bromide illuminated by its own radioactive glow. This 1922 photo was taken in the dark in the Curie laboratory.

Building on the Curies' work, the British physicist Ernest Rutherford (1871–1937) performed decisive experiments that led to the modern view of the structure of the atom. While working in Thomson's laboratory shortly after Thomson discovered the electron, Rutherford showed that compounds of uranium and other elements emitted at least two distinct types of radiation. One was readily absorbed by matter and seemed to consist of particles that had a positive charge and were massive compared to electrons. Because it was the first kind of radiation to be discovered, Rutherford called these substances α particles. Rutherford also showed that the particles in the second type of radiation, β particles, had the same charge and mass-to-charge ratio as Thomson's electrons; they are now known to be high-speed electrons. A third type of radiation, γ rays, was discovered somewhat later and found to be similar to the lower-energy form of radiation called x-rays, now used to produce images of bones and teeth.




Figure 2.2.4: Effect of an Electric Field on α Particles, β Particles, and γ Rays. A negative electrode deflects negatively charged β particles, whereas a positive electrode deflects positively charged α particles. Uncharged γ rays are unaffected by an electric field. (Relative deflections are not shown to scale.) Image used with Permission (CC BY-SA-NC).

These three kinds of radiation—α particles, β particles, and γ rays—are readily distinguished by the way they are deflected by an electric field and by the degree to which they penetrate matter. As Figure 2.2.4 illustrates, α particles and β particles are deflected in opposite directions; α particles are deflected to a much lesser extent because of their higher mass-to-charge ratio. In contrast, γ rays have no charge, so they are not deflected by electric or magnetic fields. Figure 2.2.5 shows that α particles have the least penetrating power and are stopped by a sheet of paper, whereas β particles can pass through thin sheets of metal but are absorbed by lead foil or even thick glass. In contrast, γ-rays can readily penetrate matter; thick blocks of lead or concrete are needed to stop them.




Figure 2.2.5: Relative Penetrating Power of the Three Types of Radiation. A sheet of paper stops comparatively massive α particles, whereas β particles easily penetrate paper but are stopped by a thin piece of lead foil. Uncharged γ rays penetrate the paper and lead foil; a much thicker piece of lead or concrete is needed to absorb them. Image used with Permission (CC BY-SA-NC).

The Atomic Model

Once scientists concluded that all matter contains negatively charged electrons, it became clear that atoms, which are electrically neutral, must also contain positive charges to balance the negative ones. Thomson proposed that the electrons were embedded in a uniform sphere that contained both the positive charge and most of the mass of the atom, much like raisins in plum pudding or chocolate chips in a cookie (Figure 2.2.6).




Figure 2.2.6: Thomson's Plum Pudding or Chocolate Chip Cookie Model of the Atom. In this model, the electrons are embedded in a uniform sphere of positive charge. Image used with Permission (CC BY-SA-NC).

In a single famous experiment, however, Rutherford showed unambiguously that Thomson's model of the atom was incorrect. Rutherford aimed a stream of α particles at a very thin gold foil target (Figure **2.2.7*a***) and examined how the α particles were scattered by the foil. Gold was chosen because it could be easily hammered into extremely thin sheets, minimizing the number of atoms in the target. If Thomson's model of the atom were correct, the positively-charged α particles should crash through the uniformly distributed mass of the gold target like cannonballs through the side of a wooden house. They might be moving a little slower when they emerged, but they should pass essentially straight through the target (Figure **2.2.7*b***). To Rutherford's amazement, a small fraction of the α particles were deflected at large angles, and some were reflected directly back at the source (Figure **2.2.7*c***). According to Rutherford, "It was almost as incredible as if you fired a 15-inch shell at a piece of tissue paper and it came back and hit you."




Figure **2.2.7**: A Summary of Rutherford's Experiments. (a) A representation of the apparatus Rutherford used to detect deflections in a stream of α particles aimed at a thin gold foil target. The particles were produced by a sample of radium. (b) If Thomson's model of the atom were correct, the α particles should have passed straight through the gold foil. (c) However, a small number of α particles were deflected in various directions, including right back at the source. This could be true only if the positive charge were much more massive than the α particle. It suggested that the mass of the gold atom is concentrated in a very small region of space, which he called the nucleus. Image used with Permission (CC BY-SA-NC).



The Nuclear Atom: https://youtu.be/eqoyZuv1tWA

Rutherford's results were not consistent with a model in which the mass and positive charge are distributed uniformly throughout the volume of an atom. Instead, they strongly suggested that both the mass and positive charge are concentrated in a tiny fraction of the volume of an atom, which Rutherford called the nucleus. It made sense that a small fraction of the α particles collided with the

dense, positively charged nuclei in either a glancing fashion, resulting in large deflections, or almost head-on, causing them to be reflected straight back at the source.

Although Rutherford could not explain why repulsions between the positive charges in nuclei that contained more than one positive charge did not cause the nucleus to disintegrate, he reasoned that repulsions between negatively charged electrons would cause the electrons to be uniformly distributed throughout the atom's volume.Today it is known that strong nuclear forces, which are much stronger than electrostatic interactions, hold the protons and the neutrons together in the nucleus. For this and other insights, Rutherford was awarded the Nobel Prize in Chemistry in 1908. Unfortunately, Rutherford would have preferred to receive the Nobel Prize in Physics because he considered physics superior to chemistry. In his opinion, "All science is either physics or stamp collecting."




Figure **2.2.8**: A Summary of the Historical Development of Models of the Components and Structure of the Atom. The dates in parentheses are the years in which the key experiments were performed. Image used with Permission (CC BY-SA-NC).

The historical development of the different models of the atom's structure is summarized in Figure **2.2.8**. Rutherford established that the nucleus of the hydrogen atom was a positively charged particle, for which he coined the name proton in 1920. He also suggested that the nuclei of elements other than hydrogen must contain electrically neutral particles with approximately the same mass as the proton. The neutron, however, was not discovered until 1932, when James Chadwick (1891–1974, a student of Rutherford; Nobel Prize in Physics, 1935) discovered it. As a result of Rutherford's work, it became clear that an α particle contains two protons and neutrons, and is therefore the nucleus of a helium atom.




Figure 2.2.9: The Evolution of Atomic Theory, as Illustrated by Models of the Oxygen Atom. Bohr's model and the current model are described in Chapter 6, "The Structure of Atoms." Image used with Permission (CC BY-SA-NC).

Rutherford's model of the atom is essentially the same as the modern model, except that it is now known that electrons are not uniformly distributed throughout an atom's volume. Instead, they are distributed according to a set of principles described by Quantum Mechanics. Figure 2.2.9 shows how the model of the atom has evolved over time from the indivisible unit of Dalton to the modern view taught today.

Summary

Atoms are the ultimate building blocks of all matter. The modern atomic theory establishes the concepts of atoms and how they compose matter. Atoms, the smallest particles of an element that exhibit the properties of that element, consist of negatively charged electrons around a central nucleus composed of more massive positively charged protons and electrically neutral neutrons. Radioactivity is the emission of energetic particles and rays (radiation) by some substances. Three important kinds of radiation are α particles (helium nuclei), β particles (electrons traveling at high speed), and γ rays (similar to x-rays but higher in energy).

2.2: Development of Modern Atomic Tehory is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.2: The Discovery of Atomic Structure** is licensed CC BY-NC-SA 3.0.

2.3: Atomic Structure, Names/Symbols of Atoms, and Ions

Learning Objectives

- Define electron, protons, and neutrons.
- Name elements and give their symbols.
- Define ions, cations, and anions.

Electrons, Protons, and Neutrons

The development of modern atomic theory revealed much about the inner structure of atoms. It was learned that an atom contains a very small nucleus composed of positively charged protons and uncharged neutrons, surrounded by a much larger volume of space containing negatively charged electrons. The nucleus contains the majority of an atom's mass because protons and neutrons are much heavier than electrons, whereas electrons occupy almost all of an atom's volume. The diameter of an atom is on the order of 10^{-10} m, whereas the diameter of the nucleus is roughly 10^{-15} m—about 100,000 times smaller. For a perspective about their relative sizes, consider this: If the nucleus were the size of a blueberry, the atom would be about the size of a football stadium (Figure **2.3.1**).



Figure **2.3.1**: If an atom could be expanded to the size of a football stadium, the nucleus would be the size of a single blueberry. (credit middle: modification of work by "babyknight"/Wikimedia Commons; credit right: modification of work by Paxson Woelber).

Atoms—and the protons, neutrons, and electrons that compose them—are extremely small. For example, a carbon atom weighs less than 2×10^{-23} g, and an electron has a charge of less than 2×10^{-19} C (coulomb). When describing the properties of tiny objects such as atoms, we use appropriately small units of measure, such as the atomic mass unit (amu) and the fundamental unit of charge (e). The amu was originally defined based on hydrogen, the lightest element, then later in terms of oxygen. Since 1961, it has been defined with regard to the most abundant isotope of carbon, atoms of which are assigned masses of exactly 12 amu. (This isotope is known as "carbon-12" as will be discussed later in this module.) Thus, one amu is exactly **1/12** of the mass of one carbon-12 atom: 1 amu = 1.6605×10^{-24} g. (The Dalton (Da) and the unified atomic mass unit (u) are alternative units that are equivalent to the amu.) The fundamental unit of charge (also called the elementary charge) equals the magnitude of the charge of an electron (e) with e = 1.602×10^{-19} C.

A proton has a mass of 1.0073 amu and a charge of 1+. A neutron is a slightly heavier particle with a mass 1.0087 amu and a charge of zero; as its name suggests, it is neutral. The electron has a charge of 1− and is a much lighter particle with a mass of about 0.00055 amu (it would take about 1800 electrons to equal the mass of one proton. The properties of these fundamental particles are summarized in Table **2.3.1**. (An observant student might notice that the sum of an atom's subatomic particles does not equal the atom's actual mass: The total mass of six protons, six neutrons, and six electrons is 12.0993 amu, slightly larger than the 12.00 amu of an actual carbon-12 atom. This "missing" mass is known as the mass defect, and you will learn about it in the chapter on nuclear chemistry.)

Table **2.3.1**: Properties of Subatomic Particles

Name	Location	Charge (C)	Unit Charge	Mass (amu)	Mass (g)
electron	outside nucleus	-1.602×10^{-19}	1−	0.00055	0.00091×10^{-24}
proton	nucleus	1.602×10^{-19}	1+	1.00727	1.67262×10^{-24}
neutron	nucleus	0	0	1.00866	1.67493×10^{-24}

The number of protons in the nucleus of an atom is its **atomic number** (Z). This is the defining trait of an element: Its value determines the identity of the atom. For example, any atom that contains six protons is the element carbon and has the atomic number 6, regardless of how many neutrons or electrons it may have. A neutral atom must contain the same number of positive and negative charges, so the number of protons equals the number of electrons. Therefore, the atomic number also indicates the number of electrons in an atom. The total number of protons and neutrons in an atom is called its mass number (A). The number of neutrons is therefore the difference between the mass number and the atomic number: A – Z = number of neutrons.

$$\begin{aligned} \text{atomic number (Z)} &= \text{number of protons} \\ \text{mass number (A)} &= \text{number of protons} + \text{number of neutrons} \\ \text{A} - \text{Z} &= \text{number of neutrons} \end{aligned}$$

Chemical Symbols

A chemical symbol is an abbreviation that we use to indicate an element or an atom of an element. For example, the symbol for mercury is Hg (Figure 2.3.3). We use the same symbol to indicate one atom of mercury (microscopic domain) or to label a container of many atoms of the element mercury (macroscopic domain).



Figure 2.3.3: The symbol Hg represents the element mercury regardless of the amount; it could represent one atom of mercury or a large amount of mercury. from Wikipedia (user: Materialscientist).

The symbols for several common elements and their atoms are listed in Table 2.3.2. Some symbols are derived from the common name of the element; others are abbreviations of the name in another language. Symbols have one or two letters, for example, H for hydrogen and Cl for chlorine. To avoid confusion with other notations, only the first letter of a symbol is capitalized. For example, Co is the symbol for the element cobalt, but CO is the notation for the compound carbon monoxide, which contains atoms of the elements carbon (C) and oxygen (O). All known elements and their symbols are in the periodic table.

Table 2.3.2: Some Common Elements and Their Symbols

Element	Symbol	Element	Symbol
aluminum	Al	iron	Fe (from *ferrum*)
bromine	Br	lead	Pb (from *plumbum*)
calcium	Ca	magnesium	Mg
carbon	C	mercury	Hg (from *hydrargyrum*)
chlorine	Cl	nitrogen	N
chromium	Cr	oxygen	O
cobalt	Co	potassium	K (from *kalium*)
copper	Cu (from *cuprum*)	silicon	Si
fluorine	F	silver	Ag (from *argentum*)
gold	Au (from *aurum*)	sodium	Na (from *natrium*)
helium	He	sulfur	S
hydrogen	H	tin	Sn (from *stannum*)
iodine	I	zinc	Zn

Traditionally, the discoverer (or discoverers) of a new element names the element. However, until the name is recognized by the International Union of Pure and Applied Chemistry (IUPAC), the recommended name of the new element is based on the Latin word(s) for its atomic number. For example, element 106 was called unnilhexium (Unh), element 107 was called unnilseptium (Uns), and element 108 was called unniloctium (Uno) for several years. These elements are now named after scientists or locations; for example, element 106 is now known as *seaborgium* (Sg) in honor of Glenn Seaborg, a Nobel Prize winner who was active in the discovery of several heavy elements.

Ions

Ions are electrically charged elements. As we will discuss in more detail in a later chapter, atoms typically acquire a charge by gaining or loosing electrons. An atom that gains one or more electrons will exhibit a negative charge and is called an **anion**. Positively charged atoms called cations are formed when an atom loses one or more electrons. For example, a neutral sodium atom (Z = 11) has 11 electrons. If this atom loses one electron, it will become a cation with a 1+ charge (11 − 10 = 1+). A neutral oxygen atom (Z = 8) has eight electrons, and if it gains two electrons it will become an anion with a 2− charge (8 − 10 = 2−).Atoms are electrically neutral if they contain the same number of positively charged protons and negatively charged electrons. When the numbers of these subatomic particles are *not* equal, the atom is electrically charged and is called an ion. The charge of an atom is defined as follows:

$$\text{Atomic charge} = \text{number of protons} - \text{number of electrons}$$

Example 2.3.1: Composition of an Atom

Iodine is an essential trace element in our diet; it is needed to produce thyroid hormone. Insufficient iodine in the diet can lead to the development of a goiter, an enlargement of the thyroid gland (Figure **2.3.2**).



(a)



(b)

Figure **2.3.2**: (a) Insufficient iodine in the diet can cause an enlargement of the thyroid gland called a goiter. (b) The addition of small amounts of iodine to salt, which prevents the formation of goiters, has helped eliminate this concern in the US where salt consumption is high. (credit a: modification of work by "Almazi"/Wikimedia Commons; credit b: modification of work by Mike Mozart)

The addition of small amounts of iodine to table salt (iodized salt) has essentially eliminated this health concern in the United States, but as much as 40% of the world's population is still at risk of iodine deficiency. The iodine atoms are added as anions, and each has a 1− charge and a mass number of 127. Determine the numbers of protons, neutrons, and electrons in one of these iodine anions.

Solution

The atomic number of iodine (53) tells us that a neutral iodine atom contains 53 protons in its nucleus and 53 electrons outside its nucleus. Because the sum of the numbers of protons and neutrons equals the mass number, 127, the number of neutrons is 74 (127 − 53 = 74). Since the iodine is added as a 1− anion, the number of electrons is 54 [53 – (1–) = 54].

? Exercise 2.3.1

An ion of platinum has a mass number of 195 and contains 74 electrons. How many protons and neutrons does it contain, and what is its charge?

Answer

78 protons; 117 neutrons; charge is 4+

Glossary

anion

negatively charged atom or molecule (contains more electrons than protons)

atomic mass unit (amu)

(also, unified atomic mass unit, u, or Dalton, Da) unit of mass equal to $\frac{1}{12}$ of the mass of a ^{12}C atom

atomic number (Z)

number of protons in the nucleus of an atom

cation

positively charged atom or molecule (contains fewer electrons than protons)

chemical symbol

one-, two-, or three-letter abbreviation used to represent an element or its atoms

Dalton (Da)

alternative unit equivalent to the atomic mass unit

fundamental unit of charge

(also called the elementary charge) equals the magnitude of the charge of an electron (e) with $e = 1.602 \times 10^{-19}$ C

ion

electrically charged atom or molecule (contains unequal numbers of protons and electrons)

unified atomic mass unit (u)

alternative unit equivalent to the atomic mass unit

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

2.3: Atomic Structure, Names/Symbols of Atoms, and Ions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.4: Atomic Structure and Symbolism** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.


2.4: Periodic Table

Learning Objectives

- State the periodic law and explain the organization of elements in the periodic table
- Predict the general properties of elements based on their location within the periodic table
- Identify metals, nonmetals, and metalloids by their properties and/or location on the periodic table

As early chemists worked to purify ores and discovered more elements, they realized that various elements could be grouped together by their similar chemical behaviors. One such grouping includes lithium (Li), sodium (Na), and potassium (K): These elements all are shiny, conduct heat and electricity well, and have similar chemical properties. A second grouping includes calcium (Ca), strontium (Sr), and barium (Ba), which also are shiny, good conductors of heat and electricity, and have chemical properties in common. However, the specific properties of these two groupings are notably different from each other. For example: Li, Na, and K are much more reactive than are Ca, Sr, and Ba; Li, Na, and K form compounds with oxygen in a ratio of two of their atoms to one oxygen atom, whereas Ca, Sr, and Ba form compounds with one of their atoms to one oxygen atom. Fluorine (F), chlorine (Cl), bromine (Br), and iodine (I) also exhibit similar properties to each other, but these properties are drastically different from those of any of the elements above.

Dimitri Mendeleev in Russia (1869) and Lothar Meyer in Germany (1870) independently recognized that there was a periodic relationship among the properties of the elements known at that time. Both published tables with the elements arranged according to increasing atomic mass. But Mendeleev went one step further than Meyer: He used his table to predict the existence of elements that would have the properties similar to aluminum and silicon, but were yet unknown. The discoveries of gallium (1875) and germanium (1886) provided great support for Mendeleev's work. Although Mendeleev and Meyer had a long dispute over priority, Mendeleev's contributions to the development of the periodic table are now more widely recognized (Figure **2.4.1**).



Reihen	Gruppe I. — R^1O	Gruppe II. — RO	Gruppe III. — R^2O^3	Gruppe IV. RH^4 RO^2	Gruppe V. RH^3 R^2O^5	Gruppe VI. RH^2 RO^3	Gruppe VII. RH R^2O^7	Gruppe VIII. — RO^4
1	H=1							
2	Li=7	Be=9,4	B=11	C=12	N=14	O=16	F=19	
3	Na=23	Mg=24	Al=27,3	Si=28	P=31	S=32	Cl=35,5	
4	K=39	Ca=40	—=44	Ti=48	V=51	Cr=52	Mn=55	Fe=56, Co=59, Ni=59, Cu=63.
5	(Cu=63)	Zn=65	—=68	—=72	As=75	Se=78	Br=80	
6	Rb=85	Sr=87	?Yt=88	Zr=90	Nb=94	Mo=96	—=100	Ru=104, Rh=104, Pd=106, Ag=108.
7	(Ag=108)	Cd=112	In=113	Sn=118	Sb=122	Te=125	J=127	
8	Cs=133	Ba=137	?Di=138	?Ce=140	—	—	—	— — — —
9	(—)	—	—	—	—	—	—	
10	—	—	?Er=178	?La=180	Ta=182	W=184	—	Os=195, Ir=197, Pt=198, Au=199.
11	(Au=199)	Hg=200	Tl=204	Pb=207	Bi=208	—	—	
12	—	—	—	Th=231	—	U=240	—	— — — —

(a) (b)

Figure **2.4.1**: (a) Dimitri Mendeleev is widely credited with creating (b) the first periodic table of the elements. (credit a: modification of work by Serge Lachinov; credit b: modification of work by "Den fjättrade ankan"/Wikimedia Commons)

By the twentieth century, it became apparent that the periodic relationship involved atomic numbers rather than atomic masses. The modern statement of this relationship, the periodic law, is as follows: *the properties of the elements are periodic functions of their atomic numbers*. A modern periodic table arranges the elements in increasing order of their atomic numbers and groups atoms with similar properties in the same vertical column (Figure **2.4.2**). Each box represents an element and contains its atomic number, symbol, average atomic mass, and (sometimes) name. The elements are arranged in seven horizontal rows, called periods or series, and 18 vertical columns, called groups. Groups are labeled at the top of each column. In the United States, the labels traditionally were numerals with capital letters. However, IUPAC recommends that the numbers 1 through 18 be used, and these labels are more common. For the table to fit on a single page, parts of two of the rows, a total of 14 columns, are usually written below the main body of the table.




Figure **2.4.2**: Elements in the periodic table are organized according to their properties.

Many elements differ dramatically in their chemical and physical properties, but some elements are similar in their behaviors. For example, many elements appear shiny, are malleable (able to be deformed without breaking) and ductile (can be drawn into wires), and conduct heat and electricity well. Other elements are not shiny, malleable, or ductile, and are poor conductors of heat and electricity. We can sort the elements into large classes with common properties: metals (elements that are shiny, malleable, good conductors of heat and electricity—shaded yellow); nonmetals (elements that appear dull, poor conductors of heat and electricity—shaded green); and metalloids (elements that conduct heat and electricity moderately well, and possess some properties of metals and some properties of nonmetals—shaded purple).

The elements can also be classified into the main-group elements (or representative elements) in the columns labeled 1, 2, and 13–18; the transition metals in the columns labeled 3–12; and inner transition metals in the two rows at the bottom of the table (the top-row elements are called lanthanides and the bottom-row elements are actinides; Figure **2.4.3**). The elements can be subdivided further by more specific properties, such as the composition of the compounds they form. For example, the elements in group 1 (the first column) form compounds that consist of one atom of the element and one atom of hydrogen. These elements (except hydrogen) are known as alkali metals, and they all have similar chemical properties. The elements in group 2 (the second column) form compounds consisting of one atom of the element and two atoms of hydrogen: These are called alkaline earth metals, with similar properties among members of that group. Other groups with specific names are the pnictogens (group 15), chalcogens (group 16), halogens (group 17), and the noble gases (group 18, also known as inert gases). The groups can also be referred to by the first element of the group: For example, the chalcogens can be called the oxygen group or oxygen family. Hydrogen is a unique, nonmetallic element with properties similar to both group 1 and group 17 elements. For that reason, hydrogen may be shown at the top of both groups, or by itself.




Figure 2.4.3: The periodic table organizes elements with similar properties into groups.

Example 2.4.1: Naming Groups of Elements

Atoms of each of the following elements are essential for life. Give the group name for the following elements:

a. chlorine
b. calcium
c. sodium
d. sulfur

Solution

The family names are as follows:

a. halogen
b. alkaline earth metal
c. alkali metal
d. chalcogen

Exercise 2.4.1

Give the group name for each of the following elements:

a. krypton
b. selenium
c. barium
d. lithium

Answer a

noble gas

Answer b

chalcogen

Answer c

alkaline earth metal

Answer d

alkali metal

In studying the periodic table, you might have noticed something about the atomic masses of some of the elements. Element 43 (technetium), element 61 (promethium), and most of the elements with atomic number 84 (polonium) and higher have their atomic mass given in square brackets. This is done for elements that consist entirely of unstable, radioactive isotopes (you will learn more about radioactivity in the nuclear chemistry chapter). An average atomic weight cannot be determined for these elements because their radioisotopes may vary significantly in relative abundance, depending on the source, or may not even exist in nature. The number in square brackets is the atomic mass number (and approximate atomic mass) of the most stable isotope of that element.

Summary

The discovery of the periodic recurrence of similar properties among the elements led to the formulation of the periodic table, in which the elements are arranged in order of increasing atomic number in rows known as periods and columns known as groups. Elements in the same group of the periodic table have similar chemical properties. Elements can be classified as metals, metalloids, and nonmetals, or as a main-group elements, transition metals, and inner transition metals. Groups are numbered 1–18 from left to right. The elements in group 1 are known as the alkali metals; those in group 2 are the alkaline earth metals; those in 15 are the pnictogens; those in 16 are the chalcogens; those in 17 are the halogens; and those in 18 are the noble gases.

Glossary

actinide
inner transition metal in the bottom of the bottom two rows of the periodic table

alkali metal
element in group 1

alkaline earth metal
element in group 2

chalcogen
element in group 16

group
vertical column of the periodic table

halogen
element in group 17

inert gas
(also, noble gas) element in group 18

inner transition metal
(also, lanthanide or actinide) element in the bottom two rows; if in the first row, also called lanthanide, or if in the second row, also called actinide

lanthanide
inner transition metal in the top of the bottom two rows of the periodic table

main-group element
(also, representative element) element in columns 1, 2, and 12–18

metal

element that is shiny, malleable, good conductor of heat and electricity

metalloid

element that conducts heat and electricity moderately well, and possesses some properties of metals and some properties of nonmetals

noble gas

(also, inert gas) element in group 18

nonmetal

element that appears dull, poor conductor of heat and electricity

period

(also, series) horizontal row of the periodic table

periodic law

properties of the elements are periodic function of their atomic numbers.

periodic table

table of the elements that places elements with similar chemical properties close together

pnictogen

element in group 15

representative element

(also, main-group element) element in columns 1, 2, and 12–18

transition metal

element in columns 3–11

series

(also, period) horizontal row of the period table

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

2.4: Periodic Table is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.6: The Periodic Table** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

2.5: Isotopes and Average Atomic Mass

Learning Objectives

- Write and interpret symbols that depict the atomic number, mass number, and charge of an atom or ion
- Define the atomic mass unit and average atomic mass
- Calculate average atomic mass and isotopic abundance

Isotopes are atoms of the same element that have the same number of protons but different number of neutrons, therefore they have different masses. The symbol for a specific isotope of any element is written by placing the mass number as a superscript to the left of the element symbol (Figure **2.5.4**). The atomic number is sometimes written as a subscript preceding the symbol, but since this number defines the element's identity, as does its symbol, it is often omitted. For example, magnesium exists as a mixture of three isotopes, each with an atomic number of 12 and with mass numbers of 24, 25, and 26, respectively. These isotopes can be identified as ^{24}Mg, ^{25}Mg, and ^{26}Mg. These isotope symbols are read as "element, mass number" and can be symbolized consistent with this reading. For instance, ^{24}Mg is read as "magnesium 24," and can be written as "magnesium-24" or "Mg-24." ^{25}Mg is read as "magnesium 25," and can be written as "magnesium-25" or "Mg-25." All magnesium atoms have 12 protons in their nucleus. They differ only because a ^{24}Mg atom has 12 neutrons in its nucleus, a ^{25}Mg atom has 13 neutrons, and a ^{26}Mg has 14 neutrons.




Figure **2.5.4**: The symbol for an atom indicates the element via its usual two-letter symbol, the mass number as a left superscript, the atomic number as a left subscript (sometimes omitted), and the charge as a right superscript.

Information about the naturally occurring isotopes of elements with atomic numbers 1 through 10 is given in Table **2.5.2**. Note that in addition to standard names and symbols, the isotopes of hydrogen are often referred to using common names and accompanying symbols. Hydrogen-2, symbolized ^{2}H, is also called deuterium and sometimes symbolized D. Hydrogen-3, symbolized ^{3}H, is also called tritium and sometimes symbolized T.

Table **2.5.2**: Nuclear Compositions of Atoms of the Very Light Elements

Element	Symbol	Atomic Number	Number of Protons	Number of Neutrons	Mass (amu)	% Natural Abundance
hydrogen	$^{1}_{1}\mathrm{H}$ (protium)	1	1	0	1.0078	99.989
	$^{2}_{1}\mathrm{H}$ (deuterium)	1	1	1	2.0141	0.0115
	$^{3}_{1}\mathrm{H}$ (tritium)	1	1	2	3.01605	— (trace)
helium	$^{3}_{2}\mathrm{He}$	2	2	1	3.01603	0.00013
	$^{4}_{2}\mathrm{He}$	2	2	2	4.0026	100
lithium	$^{6}_{3}\mathrm{Li}$	3	3	3	6.0151	7.59
	$^{7}_{3}\mathrm{Li}$	3	3	4	7.0160	92.41
beryllium	$^{9}_{4}\mathrm{Be}$	4	4	5	9.0122	100
boron	$^{10}_{5}\mathrm{B}$	5	5	5	10.0129	19.9
	$^{11}_{5}\mathrm{B}$	5	5	6	11.0093	80.1
carbon	$^{12}_{6}\mathrm{C}$	6	6	6	12.0000	98.89
	$^{13}_{6}\mathrm{C}$	6	6	7	13.0034	1.11
	$^{14}_{6}\mathrm{C}$	6	6	8	14.0032	— (trace)
nitrogen	$^{14}_{7}\mathrm{N}$	7	7	7	14.0031	99.63
	$^{15}_{7}\mathrm{N}$	7	7	8	15.0001	0.37
oxygen	$^{16}_{8}\mathrm{O}$	8	8	8	15.9949	99.757
	$^{17}_{8}\mathrm{O}$	8	8	9	16.9991	0.038
	$^{18}_{8}\mathrm{O}$	8	8	10	17.9992	0.205
fluorine	$^{19}_{9}\mathrm{F}$	9	9	10	18.9984	100
neon	$^{20}_{10}\mathrm{Ne}$	10	10	10	19.9924	90.48
	$^{21}_{10}\mathrm{Ne}$	10	10	11	20.9938	0.27
	$^{22}_{10}\mathrm{Ne}$	10	10	12	21.9914	9.25

Atomic Mass

Because each proton and each neutron contribute approximately one amu to the mass of an atom, and each electron contributes far less, the atomic mass of a single atom is approximately equal to its mass number (a whole number). However, the average masses of atoms of most elements are not whole numbers because most elements exist naturally as mixtures of two or more isotopes.

The mass of an element shown in a periodic table or listed in a table of atomic masses is a weighted, average mass of all the isotopes present in a naturally occurring sample of that element. This is equal to the sum of each individual isotope's mass multiplied by its fractional abundance.

$$\text{average mass} = \sum_i (\text{fractional abundance} \times \text{isotopic mass})_i \tag{2.5.1}$$

For example, the element boron is composed of two isotopes: About 19.9% of all boron atoms are ^{10}B with a mass of 10.0129 amu, and the remaining 80.1% are ^{11}B with a mass of 11.0093 amu. The average atomic mass for boron is calculated to be:

$$\begin{aligned}\text{boron average mass} &= (0.199 \times 10.0129\ \text{amu}) + (0.801 \times 11.0093\ \text{amu}) \\ &= 1.99\ \text{amu} + 8.82\ \text{amu} \\ &= 10.81\ \text{amu}\end{aligned}$$

It is important to understand that no single boron atom weighs exactly 10.8 amu; 10.8 amu is the average mass of all boron atoms, and individual boron atoms weigh either approximately 10 amu or 11 amu.

✔ Example 2.5.1: Calculation of Average Atomic Mass

A meteorite found in central Indiana contains traces of the noble gas neon picked up from the solar wind during the meteorite's trip through the solar system. Analysis of a sample of the gas showed that it consisted of 91.84% ^{20}Ne (mass 19.9924 amu), 0.47% ^{21}Ne (mass 20.9940 amu), and 7.69% ^{22}Ne (mass 21.9914 amu). What is the average mass of the neon in the solar wind?

Solution

$$\begin{aligned}\text{average mass} &= (0.9184 \times 19.9924\ \text{amu}) + (0.0047 \times 20.9940\ \text{amu}) + (0.0769 \times 21.9914\ \text{amu}) \\ &= (18.36 + 0.099 + 1.69)\ \text{amu} \\ &= 20.15\ \text{amu}\end{aligned}$$

The average mass of a neon atom in the solar wind is 20.15 amu. (The average mass of a terrestrial neon atom is 20.1796 amu. This result demonstrates that we may find slight differences in the natural abundance of isotopes, depending on their origin.)

? Exercise 2.5.1

A sample of magnesium is found to contain 78.70% of ^{24}Mg atoms (mass 23.98 amu), 10.13% of ^{25}Mg atoms (mass 24.99 amu), and 11.17% of ^{26}Mg atoms (mass 25.98 amu). Calculate the average mass of a Mg atom.

Answer

24.31 amu

We can also do variations of this type of calculation, as shown in the next example.

✔ Example 2.5.2: Calculation of Percent Abundance

Naturally occurring chlorine consists of ^{35}Cl (mass 34.96885 amu) and ^{37}Cl (mass 36.96590 amu), with an average mass of 35.453 amu. What is the percent composition of Cl in terms of these two isotopes?

Solution

The average mass of chlorine is the fraction that is ^{35}Cl times the mass of ^{35}Cl plus the fraction that is ^{37}Cl times the mass of ^{37}Cl.

$$\text{average mass} = (\text{fraction of } ^{35}\text{Cl} \times \text{mass of } ^{35}\text{Cl}) + (\text{fraction of } ^{37}\text{Cl} \times \text{mass of } ^{37}\text{Cl}) \tag{2.5.2}$$

If we let x represent the fraction that is ^{35}Cl, then the fraction that is ^{37}Cl is represented by $1.00 - x$.

(The fraction that is ^{35}Cl + the fraction that is ^{37}Cl must add up to 1, so the fraction of ^{37}Cl must equal 1.00 − the fraction of ^{35}Cl.)

Substituting this into the average mass equation, we have:

$$\begin{aligned}35.453\ \text{amu} &= (x \times 34.96885\ \text{amu}) + [(1.00 - x) \times 36.96590\ \text{amu}] \\ 35.453 &= 34.96885x + 36.96590 - 36.96590x \\ 1.99705x &= 1.513 \\ x &= \frac{1.513}{1.99705} = 0.7576\end{aligned}$$

So solving yields: $x = 0.7576$, which means that $1.00 - 0.7576 = 0.2424$. Therefore, chlorine consists of 75.76% ^{35}Cl and 24.24% ^{37}Cl.

? Exercise 2.5.2

Naturally occurring copper consists of ^{63}Cu (mass 62.9296 amu) and ^{65}Cu (mass 64.9278 amu), with an average mass of 63.546 amu. What is the percent composition of Cu in terms of these two isotopes?

Answer

69.15% Cu-63 and 30.85% Cu-65




Figure 2.5.5: Analysis of zirconium in a mass spectrometer produces a mass spectrum with peaks showing the different isotopes of Zr.

The occurrence and natural abundances of isotopes can be experimentally determined using an instrument called a mass spectrometer. Mass spectrometry (MS) is widely used in chemistry, forensics, medicine, environmental science, and many other fields to analyze and help identify the substances in a sample of material. In a typical mass spectrometer (Figure 2.5.5), the sample is vaporized and exposed to a high-energy electron beam that causes the sample's atoms (or molecules) to become electrically charged, typically by losing one or more electrons. These cations then pass through a (variable) electric or magnetic field that deflects each cation's path to an extent that depends on both its mass and charge (similar to how the path of a large steel ball bearing rolling past a magnet is deflected to a lesser extent that that of a small steel BB). The ions are detected, and a plot of the relative number of ions generated versus their mass-to-charge ratios (a *mass spectrum*) is made. The height of each vertical feature or peak in a mass spectrum is proportional to the fraction of cations with the specified mass-to-charge ratio. Since its initial use during the development of modern atomic theory, MS has evolved to become a powerful tool for chemical analysis in a wide range of applications.



Video* 2.5.1: Watch this video from the Royal Society for Chemistry for a brief description of the rudiments of mass spectrometry.*

Summary

Isotopes of an element are atoms with the same atomic number but different mass numbers; isotopes of an element, therefore, differ from each other only in the number of neutrons within the nucleus. When a naturally occurring element is composed of several isotopes, the atomic mass of the element represents the average of the masses of the isotopes involved. A chemical symbol identifies the atoms in a substance using symbols, which are one-, two-, or three-letter abbreviations for the atoms.

Key Equations

- $\text{average mass} = \sum_i (\text{fractional abundance} \times \text{isotopic mass})_i$

Glossary

atomic mass
average mass of atoms of an element, expressed in amu

atomic mass unit (amu)
(also, unified atomic mass unit, u, or Dalton, Da) unit of mass equal to $\frac{1}{12}$ of the mass of a ^{12}C atom

atomic number (Z)
number of protons in the nucleus of an atom

Dalton (Da)
alternative unit equivalent to the atomic mass unit

mass number (A)
sum of the numbers of neutrons and protons in the nucleus of an atom

unified atomic mass unit (u)
alternative unit equivalent to the atomic mass unit

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

2.5: Isotopes and Average Atomic Mass is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.4: Atomic Structure and Symbolism** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

2.6: Molar Mass of Elements

Learning Objectives

- Define *Avogadro's number* and explain why it is important to know.
- Define the *mole*. Be able to calculate the number of moles in a given mass of a substance, or the mass corresponding to a given number of moles.
- Define *molecular weight*, *formula weight*, and *molar mass*; explain how the latter differs from the first two.
- Be able to find the number of atoms or molecules in a given weight of a substance.

The chemical changes we observe always involve *discrete numbers of atoms* that rearrange themselves into new configurations. These numbers are HUGE— far too large in magnitude for us to count or even visualize, but they are still *numbers*, and we need to have a way to deal with them. We also need a bridge between these numbers, which we are unable to measure directly, and the weights of substances, which we do measure and observe. The *mole concept* provides this bridge, and is central to all of quantitative chemistry.

Counting Atoms by the the moles

The mole is an amount unit similar to familiar units like pair, dozen, gross, etc. It provides a specific measure of *the number* of atoms or molecules in a bulk sample of matter. A mole is defined as the amount of substance containing the same number of discrete entities (such as atoms, molecules, and ions) as the number of atoms in a sample of pure ^{12}C weighing exactly 12 g. One Latin connotation for the word “mole” is “large mass” or “bulk,” which is consistent with its use as the name for this unit. The mole provides a link between an easily measured macroscopic property, bulk mass, and an extremely important fundamental property, number of atoms, molecules, and so forth.

The number of entities composing a mole has been experimentally determined to be $6.02214179 \times 10^{23}$, a fundamental constant named **Avogadro’s number** (N_A) or the Avogadro constant in honor of Italian scientist Amedeo Avogadro. This constant is properly reported with an explicit unit of “per mole,” a conveniently rounded version being $6.022 \times 10^{23}/\text{mol}$.

Consistent with its definition as an amount unit, 1 mole of any element contains the same number of atoms as 1 mole of any other element. The masses of 1 mole of different elements, however, are different, since the masses of the individual atoms are drastically different. The molar mass of an element (or compound) is the mass in grams of 1 mole of that substance, a property expressed in units of grams per mole (g/mol) (Figure 2.6.1).




Figure 2.6.1: Each sample contains 6.022×10^{23} atoms —1.00 mol of atoms. From left to right (top row): 65.4 g zinc, 12.0 g carbon, 24.3 g magnesium, and 63.5 g copper. From left to right (bottom row): 32.1 g sulfur, 28.1 g silicon, 207 g lead, and 118.7 g tin. (credit: modification of work by Mark Ott).

Because the definitions of both the mole and the atomic mass unit are based on the same reference substance, ^{12}C, the molar mass of any substance is numerically equivalent to its atomic or formula weight in amu. Per the amu definition, a single ^{12}C atom weighs 12 amu (its atomic mass is 12 amu). According to the definition of the mole, 12 g of ^{12}C contains 1 mole of ^{12}C atoms (its molar mass is 12 g/mol). This relationship holds for all elements, since their atomic masses are measured relative to that of the amu-reference substance, ^{12}C. Extending this principle, the molar mass of a compound in grams is likewise numerically equivalent to its formula mass in amu.

Table **2.6.1**: Mass of one mole of elements

Element	Average Atomic Mass (amu)	Molar Mass (g/mol)	Atoms/Mole
C	12.01	12.01	6.022×10^{23}
H	1.008	1.008	6.022×10^{23}
O	16.00	16.00	6.022×10^{23}
Na	22.99	22.99	6.022×10^{23}
Cl	33.45	35.45	6.022×10^{23}

While atomic mass and molar mass are numerically equivalent, keep in mind that they are vastly different in terms of scale, as represented by the vast difference in the magnitudes of their respective units (amu versus g).



Video **2.6.1**: The mole is used in chemistry to represent 6.022×10^{23} of something, but it can be difficult to conceptualize such a large number. Watch this video and then complete the "Think" questions that follow. Explore more about the mole by reviewing the information under "Dig Deeper."

The relationships between formula mass, the mole, and Avogadro's number can be applied to compute various quantities that describe the composition of substances and compounds. For example, if we know the mass and chemical composition of a substance, we can determine the number of moles and calculate number of atoms or molecules in the sample. Likewise, if we know the number of moles of a substance, we can derive the number of atoms or molecules and calculate the substance's mass.


Example **2.6.1**: Deriving Moles from Grams for an Element

According to nutritional guidelines from the US Department of Agriculture, the estimated average requirement for dietary potassium is 4.7 g. What is the estimated average requirement of potassium in moles?

Solution

The mass of K is provided, and the corresponding amount of K in moles is requested. Referring to the periodic table, the atomic mass of K is 39.10 amu, and so its molar mass is 39.10 g/mol. The given mass of K (4.7 g) is a bit more than one-tenth the molar mass (39.10 g), so a reasonable "ballpark" estimate of the number of moles would be slightly greater than 0.1 mol.

The molar amount of a substance may be calculated by dividing its mass (g) by its molar mass (g/mol):



The factor-label method supports this mathematical approach since the unit “g” cancels and the answer has units of “mol:”

$$4.7\ \cancel{g}\,\text{K}\left(\frac{\text{mol K}}{39.10\ \cancel{g}}\right) = 0.12\ \text{mol K}$$

The calculated magnitude (0.12 mol K) is consistent with our ballpark expectation, since it is a bit greater than 0.1 mol.

? Exercise 2.6.1: Beryllium

Beryllium is a light metal used to fabricate transparent X-ray windows for medical imaging instruments. How many moles of Be are in a thin-foil window weighing 3.24 g?

Answer


0.360 mol

✓ Example 2.6.2: Deriving Grams from Moles for an Element

A liter of air contains 9.2×10^{-4} mol argon. What is the mass of Ar in a liter of air?

Solution

The molar amount of Ar is provided and must be used to derive the corresponding mass in grams. Since the amount of Ar is less than 1 mole, the mass will be less than the mass of 1 mole of Ar, approximately 40 g. The molar amount in question is approximately one-one thousandth (~10^{-3}) of a mole, and so the corresponding mass should be roughly one-one thousandth of the molar mass (~0.04 g):



In this case, logic dictates (and the factor-label method supports) multiplying the provided amount (mol) by the molar mass (g/mol):

$$9.2 \times 10^{-4}\ \cancel{\text{mol}}\ \text{Ar}\left(\frac{39.95\ \text{g}}{\cancel{\text{mol}}\ \text{Ar}}\right) = 0.037\ \text{g Ar}$$

The result is in agreement with our expectations, around 0.04 g Ar.

? Exercise 2.6.2

What is the mass of 2.561 mol of gold?

Answer

504.4 g

✓ Example 2.6.3: Deriving Number of Atoms from Mass for an Element


Copper is commonly used to fabricate electrical wire (Figure 2.6.2). How many copper atoms are in 5.00 g of copper wire?



Figure **2.6.2**: Copper wire is composed of many, many atoms of Cu. (credit: Emilian Robert Vicol)

Solution

The number of Cu atoms in the wire may be conveniently derived from its mass by a two-step computation: first calculating the molar amount of Cu, and then using Avogadro's number (N_A) to convert this molar amount to number of Cu atoms:



Considering that the provided sample mass (5.00 g) is a little less than one-tenth the mass of 1 mole of Cu (~64 g), a reasonable estimate for the number of atoms in the sample would be on the order of one-tenth N_A, or approximately 10^{22} Cu atoms. Carrying out the two-step computation yields:

$$5.00\ \cancel{\text{g}}\ \text{Cu}\left(\frac{\cancel{\text{mol}}\ \text{Cu}}{63.55\ \cancel{\text{g}}}\right)\left(\frac{6.022\times10^{23}\ \text{atoms}}{\cancel{\text{mol}}}\right)=4.74\times10^{22}\ \text{atoms of copper} \tag{2.6.1}$$

The factor-label method yields the desired cancellation of units, and the computed result is on the order of 10^{22} as expected.

? Exercise 2.6.3

A prospector panning for gold in a river collects 15.00 g of pure gold. How many Au atoms are in this quantity of gold?

Answer

4.586×10^{22} *Au* atoms

Summary

The formula mass of a substance is the sum of the average atomic masses of each atom represented in the chemical formula and is expressed in atomic mass units. The formula mass of a covalent compound is also called the molecular mass. A convenient amount unit for expressing very large numbers of atoms or molecules is the mole. Experimental measurements have determined the number of entities composing 1 mole of substance to be 6.022×10^{23}, a quantity called Avogadro's number. The mass in grams of 1 mole of substance is its molar mass. Due to the use of the same reference substance in defining the atomic mass unit and the mole, the formula mass (amu) and molar mass (g/mol) for any substance are numerically equivalent (for example, one H_2O molecule weighs approximately18 amu and 1 mole of H_2O molecules weighs approximately 18 g).

Glossary

Avogadro's number (N_A)

experimentally determined value of the number of entities comprising 1 mole of substance, equal to 6.022×10^{23} mol^{-1}

formula mass

sum of the average masses for all atoms represented in a chemical formula; for covalent compounds, this is also the molecular mass

mole

amount of substance containing the same number of atoms, molecules, ions, or other entities as the number of atoms in exactly 12 grams of ^{12}C

molar mass

mass in grams of 1 mole of a substance

2.6: Molar Mass of Elements is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.4: Atomic Structure and Symbolism** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **4.2: Avogadro's Number and the Mole** by Stephen Lower is licensed CC BY 3.0. Original source: http://www.chem1.com/acad/webtext/virtualtextbook.html.
- **3.1: Formula Mass and the Mole Concept** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

2.7: End of Chapter Problems

Exercises

1. In the following drawing, the green spheres represent atoms of a certain element. The purple spheres represent atoms of another element. If the spheres of different elements touch, they are part of a single unit of a compound. The following chemical change represented by these spheres may violate one of the ideas of Dalton's atomic theory. Which one?



This equation contains the starting materials of a single, green sphere plus two smaller, purple spheres bonded together. When the starting materials are added together the products of the change are one purple sphere bonded with one green sphere plus one purple sphere bonded with one green sphere.

2. Which postulate of Dalton's theory is consistent with the following observation concerning the weights of reactants and products? When 100 grams of solid calcium carbonate is heated, 44 grams of carbon dioxide and 56 grams of calcium oxide are produced.
3. Identify the postulate of Dalton's theory that is violated by the following observations: 59.95% of one sample of titanium dioxide is titanium; 60.10% of a different sample of titanium dioxide is titanium.
4. Samples of compound X, Y, and Z are analyzed, with results shown here. Do these data provide example(s) of the law of definite proportions, the law of multiple proportions, neither, or both? What do these data tell you about compounds X, Y, and Z?

Compound	Description	Mass of Carbon	Mass of Hydrogen
X	clear, colorless, liquid with strong odor	1.776 g	0.148 g
Y	clear, colorless, liquid with strong odor	1.974 g	0.329 g
Z	clear, colorless, liquid with strong odor	7.812 g	0.651 g

5. The existence of isotopes violates one of the original ideas of Dalton's atomic theory. Which one?

Answer

Dalton originally thought that all atoms of a particular element had identical properties, including mass. Thus, the concept of isotopes, in which an element has different masses, was a violation of the original idea. To account for the existence of isotopes, the second postulate of his atomic theory was modified to state that atoms of the same element must have identical chemical properties.

6. How are electrons and protons similar? How are they different?

Answer

Both are subatomic particles that reside in an atom's nucleus. Both have approximately the same mass. Protons are positively charged, whereas neutrons are uncharged.

7. How are protons and neutrons similar? How are they different?

Answer

Both are subatomic particles that reside in an atom's nucleus. Both have approximately the same mass. Protons are positively charged, whereas neutrons are uncharged.

8. Predict and test the behavior of α particles fired at a "plum pudding" model atom.
   a. Predict the paths taken by α particles that are fired at atoms with a Thomson's plum pudding model structure. Explain why you expect the α particles to take these paths.

b. If α particles of higher energy than those in (a) are fired at plum pudding atoms, predict how their paths will differ from the lower-energy α particle paths. Explain your reasoning.
c. Now test your predictions from (a) and (b). Open the Rutherford Scattering simulation and select the "Plum Pudding Atom" tab. Set "Alpha Particles Energy" to "min," and select "show traces." Click on the gun to start firing α particles. Does this match your prediction from (a)? If not, explain why the actual path would be that shown in the simulation. Hit the pause button, or "Reset All." Set "Alpha Particles Energy" to "max," and start firing α particles. Does this match your prediction from (b)? If not, explain the effect of increased energy on the actual paths as shown in the simulation.

Answer

a.The plum pudding model indicates that the positive charge is spread uniformly throughout the atom, so we expect the α particles to (perhaps) be slowed somewhat by the positive-positive repulsion, but to follow straight-line paths (i.e., not to be deflected) as they pass through the atoms. b. Higher-energy α particles will be traveling faster (and perhaps slowed less) and will also follow straight-line paths through the atoms. c. The α particles followed straight-line paths through the plum pudding atom. There was no apparent slowing of the α particles as they passed through the atoms.

9. Predict and test the behavior of α particles fired at a Rutherford atom model.
   a. Predict the paths taken by α particles that are fired at atoms with a Rutherford atom model structure. Explain why you expect the α particles to take these paths.
   b. If α particles of higher energy than those in (a) are fired at Rutherford atoms, predict how their paths will differ from the lower-energy α particle paths. Explain your reasoning.
   c. Predict how the paths taken by the α particles will differ if they are fired at Rutherford atoms of elements other than gold. What factor do you expect to cause this difference in paths, and why?
   d. Now test your predictions from (a), (b), and (c). Open the Rutherford Scattering simulation and select the "Rutherford Atom" tab. Due to the scale of the simulation, it is best to start with a small nucleus, so select "20" for both protons and neutrons, "min" for energy, show traces, and then start firing α particles. Does this match your prediction from (a)? If not, explain why the actual path would be that shown in the simulation. Pause or reset, set energy to "max," and start firing α particles. Does this match your prediction from (b)? If not, explain the effect of increased energy on the actual path as shown in the simulation. Pause or reset, select "40" for both protons and neutrons, "min" for energy, show traces, and fire away. Does this match your prediction from (c)? If not, explain why the actual path would be that shown in the simulation. Repeat this with larger numbers of protons and neutrons. What generalization can you make regarding the type of atom and effect on the path of α particles? Be clear and specific.

Answer

a. The Rutherford atom has a small, positively charged nucleus, so most α particles will pass through empty space far from the nucleus and be undeflected. Those α particles that pass near the nucleus will be deflected from their paths due to positive-positive repulsion. The more directly toward the nucleus the α particles are headed, the larger the deflection angle will be. b. Higher-energy α particles that pass near the nucleus will still undergo deflection, but the faster they travel, the less the expected angle of deflection. c. If the nucleus is smaller, the positive charge is smaller and the expected deflections are smaller—both in terms of how closely the α particles pass by the nucleus undeflected and the angle of deflection. If the nucleus is larger, the positive charge is larger and the expected deflections are larger—more α particles will be deflected, and the deflection angles will be larger. d. The paths followed by the α particles match the predictions from (a), (b), and (c).

10. In what way are isotopes of a given element always different? In what way(s) are they always the same?
11. Write the symbol for each of the following ions:
    a. the ion with a 1+ charge, atomic number 55, and mass number 133.
    b. the ion with 54 electrons, 53 protons, and 74 neutrons
    c. the ion with atomic number 15, mass number 31, and a 3− charge
    d. the ion with 24 electrons, 30 neutrons, and a 3+ charge

Answer

a. $^{133}Cs^{+}$; b. $^{127}I^{-}$; c. $^{31}P^{3-}$; d. $^{57}Co^{3+}$

12. Write the symbol for each of the following ions
    a. the ion with a 3+ charge, 28 electrons, and a mass number of 71
    b. the ion with 36 electrons, 35 protons, and 45 neutrons
    c. the ion with 86 electrons, 142 neutrons, and a 4+ charge
    d. the ion with a 2+ charge, atomic number 38, and mass number 87
13. Determine the number of protons, neutrons, and electrons in the following isotopes that are used in medical diagnoses:
    a. atomic number 9, mass number 18, charge of 1−
    b. atomic number 43, mass number 99, charge of 7+
    c. atomic number 53, atomic mass number 131, charge of 1−
    d. atomic number 81, atomic mass number 201, charge of 1+
    e. Name the elements in parts (a), (b), (c), and (d).
14. The following are properties of isotopes of two elements that are essential in our diet. Determine the number of protons, neutrons and electrons in each and name them.
    a. atomic number 26, mass number 58, charge of 2+
    b. atomic number 53, mass number 127, charge of 1−

Answer

a. Iron, 26 protons, 24 electrons, and 32 neutrons; b. iodine, 53 protons, 54 electrons, and 74 neutrons

15. Give the number of protons, electrons, and neutrons in neutral atoms of each of the following isotopes:
    a. $^{10}_{5}\mathrm{B}$
    b. $^{199}_{80}\mathrm{Hg}$
    c. $^{63}_{29}\mathrm{Cu}$
    d. $^{13}_{6}\mathrm{C}$
    e. $^{77}_{34}\mathrm{Se}$
16. Give the number of protons, electrons, and neutrons in neutral atoms of each of the following isotopes:
    a. $^{7}_{3}\mathrm{Li}$
    b. $^{125}_{52}\mathrm{Te}$
    c. $^{109}_{47}\mathrm{Ag}$
    d. $^{15}_{7}\mathrm{N}$
    e. $^{31}_{15}\mathrm{P}$

Answer

a. 3 protons, 3 electrons, 4 neutrons; b. 52 protons, 52 electrons, 73 neutrons; c. 47 protons, 47 electrons, 62 neutrons; d. 7 protons, 7 electrons, 8 neutrons; e. 15 protons, 15 electrons, 16 neutrons

17. Click on the site and select the “Mix Isotopes” tab, hide the “Percent Composition” and “Average Atomic Mass” boxes, and then select the element boron.
    a. atomic number 26, mass number 58, charge of 2+
    b. atomic number 53, mass number 127, charge of 1−
18. Click on the site and select the “Mix Isotopes” tab, hide the “Percent Composition” and “Average Atomic Mass” boxes, and then select the element boron.
    a. Write the symbols of the isotopes of boron that are shown as naturally occurring in significant amounts.
    b. Predict the relative amounts (percentages) of these boron isotopes found in nature. Explain the reasoning behind your choice.
    c. Add isotopes to the black box to make a mixture that matches your prediction in (b). You may drag isotopes from their bins or click on “More” and then move the sliders to the appropriate amounts.

d. Reveal the “Percent Composition” and “Average Atomic Mass” boxes. How well does your mixture match with your prediction? If necessary, adjust the isotope amounts to match your prediction.
e. Select “Nature’s” mix of isotopes and compare it to your prediction. How well does your prediction compare with the naturally occurring mixture? Explain. If necessary, adjust your amounts to make them match “Nature’s” amounts as closely as possible.
f. Repeat Exercise using an element that has three naturally occurring isotopes.

2.7: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

3: Molecules and Compounds

3.1: Ionic and Molecular Compounds
3.2: Representation of Chemical Compounds
3.3: Types of ions
3.4: Formulas and names of ionic compounds
3.5: Formulas and Names of Covalent Compounds
3.6: Formula Mass and Molar Mass of Compounds
3.7: Percent Composition, Emperical Formulas, and Molecular Fromulas
3.8: Determine Empirical Formula from Combustion Analysis
3.9: End of Chapter Problems

3: Molecules and Compounds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

3.1: Ionic and Molecular Compounds

Learning Objectives

- Define ionic and molecular (covalent) compounds
- Predict the type of compound formed from elements based on their location within the periodic table
- Determine formulas for simple ionic compounds

The nature of the attractive forces that hold atoms or ions together within a compound is the basis for classifying chemical bonding. When electrons are transferred and ions form, ionic bonds result. Ionic bonds are electrostatic forces of attraction, that is, the attractive forces experienced between objects of opposite electrical charge (in this case, cations and anions). When electrons are "shared" and molecules form, covalent bonds result. Covalent bonds are the attractive forces between the positively charged nuclei of the bonded atoms and one or more pairs of electrons that are located between the atoms. Compounds are classified as ionic or molecular (covalent) on the basis of the bonds present in them.

Ionic compounds and Ionic Bond

When an element composed of atoms that readily lose electrons (a metal) reacts with an element composed of atoms that readily gain electrons (a nonmetal), a transfer of electrons usually occurs, producing ions. The compound formed by this transfer is stabilized by the electrostatic attractions (ionic bonds) between the ions of opposite charge present in the compound. For example, when each sodium atom in a sample of sodium metal (group 1) gives up one electron to form a sodium cation, Na^+, and each chlorine atom in a sample of chlorine gas (group 17) accepts one electron to form a chloride anion, Cl^-, the resulting compound, NaCl, is composed of sodium ions and chloride ions in the ratio of one Na^+ ion for each Cl^- ion. Similarly, each calcium atom (group 2) can give up two electrons and transfer one to each of two chlorine atoms to form $CaCl_2$, which is composed of Ca^{2+} and Cl^- ions in the ratio of one Ca^{2+} ion to two Cl^- ions.

A compound that contains ions and is held together by ionic bonds is called an ionic compound. The periodic table can help us recognize many of the compounds that are ionic: When a metal is combined with one or more nonmetals, the compound is usually ionic. This guideline works well for predicting ionic compound formation for most of the compounds typically encountered in an introductory chemistry course. However, it is not always true (for example, aluminum chloride, $AlCl_3$, is not ionic).

You can often recognize ionic compounds because of their properties. Ionic compounds are solids that typically melt at high temperatures and boil at even higher temperatures. For example, sodium chloride melts at 801 °C and boils at 1413 °C. (As a comparison, the molecular compound water melts at 0 °C and boils at 100 °C.) In solid form, an ionic compound is not electrically conductive because its ions are unable to flow ("electricity" is the flow of charged particles). When molten, however, it can conduct electricity because its ions are able to move freely through the liquid (Figure **3.1.1**).




Figure **3.1.1**: Sodium chloride melts at 801 °C and conducts electricity when molten. (credit: modification of work by Mark Blaser and Matt Evans)

In every ionic compound, the total number of positive charges of the cations equals the total number of negative charges of the anions. Thus, ionic compounds are electrically neutral overall, even though they contain positive and negative ions. We can use this

observation to help us write the formula of an ionic compound. The formula of an ionic compound must have a ratio of ions such that the numbers of positive and negative charges are equal.

Example 3.1.1: Predicting the Formula of an Ionic Compound

The gemstone sapphire (Figure **3.1.2**) is mostly a compound of aluminum and oxygen that contains aluminum cations, Al^{3+}, and oxygen anions, O^{2-}. What is the formula of this compound?



Figure **3.1.2**: Although pure aluminum oxide is colorless, trace amounts of iron and titanium give blue sapphire its characteristic color. (credit: modification of work by Stanislav Doronenko)

Solution Because the ionic compound must be electrically neutral, it must have the same number of positive and negative charges. Two aluminum ions, each with a charge of 3+, would give us six positive charges, and three oxide ions, each with a charge of 2−, would give us six negative charges. The formula would be Al_2O_3.

Exercise 3.1.1

Predict the formula of the ionic compound formed between the sodium cation, Na^+, and the sulfide anion, S^{2-}.

Answer

Na_2S

Many ionic compounds contain polyatomic ions (will be covered in later section) as the cation, the anion, or both. As with simple ionic compounds, these compounds must also be electrically neutral, so their formulas can be predicted by treating the polyatomic ions as discrete units. We use parentheses in a formula to indicate a group of atoms that behave as a unit. For example, the formula for calcium phosphate, one of the minerals in our bones, is $Ca_3(PO_4)_2$. This formula indicates that there are three calcium ions (Ca^{2+}) for every two phosphate ($\mathbf{PO_4^{3-}}$) groups. The $\mathbf{PO_4^{3-}}$ groups are discrete units, each consisting of one phosphorus atom and four oxygen atoms, and having an overall charge of 3−. The compound is electrically neutral, and its formula shows a total count of three Ca, two P, and eight O atoms.

Example 3.1.2: Predicting the Formula of a Compound with a Polyatomic Anion

Baking powder contains calcium dihydrogen phosphate, an ionic compound composed of the ions Ca^{2+} and $\mathbf{H_2PO_4^-}$. What is the formula of this compound?

Solution

The positive and negative charges must balance, and this ionic compound must be electrically neutral. Thus, we must have two negative charges to balance the 2+ charge of the calcium ion. This requires a ratio of one Ca^{2+} ion to two $\mathbf{H_2PO_4^-}$ ions. We designate this by enclosing the formula for the dihydrogen phosphate ion in parentheses and adding a subscript 2. The formula is $Ca(H_2PO_4)_2$.

Exercise 3.1.2

Predict the formula of the ionic compound formed between the lithium ion and the peroxide ion, $\mathbf{O_2^{2-}}$ (Hint: Use the periodic table to predict the sign and the charge on the lithium ion.)

Answer

Li_2O_2

Because an ionic compound is not made up of single, discrete molecules, it may not be properly symbolized using a *molecular* formula. Instead, ionic compounds must be symbolized by a formula indicating the *relative numbers* of its constituent ions. For compounds containing only monatomic ions (such as NaCl) and for many compounds containing polyatomic ions (such as $CaSO_4$), these formulas are just the empirical formulas introduced earlier in this chapter. However, the formulas for some ionic compounds containing polyatomic ions are not empirical formulas. For example, the ionic compound sodium oxalate is comprised of Na^+ and $C_2O_4^{2-}$ ions combined in a 2:1 ratio, and its formula is written as $Na_2C_2O_4$. The subscripts in this formula are not the smallest-possible whole numbers, as each can be divided by 2 to yield the empirical formula, $NaCO_2$. This is not the accepted formula for sodium oxalate, however, as it does not accurately represent the compound's polyatomic anion, $C_2O_4^{2-}$

Molecular Compounds and Covalent Bond

Many compounds do not contain ions but instead consist solely of discrete, neutral molecules. These molecular compounds (covalent compounds) result when atoms share, rather than transfer (gain or lose), electrons. Covalent bonding is an important and extensive concept in chemistry, and it will be treated in considerable detail in a later chapter of this text. We can often identify molecular compounds on the basis of their physical properties. Under normal conditions, molecular compounds often exist as gases, low-boiling liquids, and low-melting solids, although many important exceptions exist.

Whereas ionic compounds are usually formed when a metal and a nonmetal combine, covalent compounds are usually formed by a combination of nonmetals. Thus, the periodic table can help us recognize many of the compounds that are covalent. While we can use the positions of a compound's elements in the periodic table to predict whether it is ionic or covalent at this point in our study of chemistry, you should be aware that this is a very simplistic approach that does not account for a number of interesting exceptions. Shades of gray exist between ionic and molecular compounds, and you'll learn more about those later.

✔ Example 3.1.1: Predicting the Type of Bonding in Compounds

Predict whether the following compounds are ionic or molecular:

a. KI, the compound used as a source of iodine in table salt
b. H_2O_2, the bleach and disinfectant hydrogen peroxide
c. $CHCl_3$, the anesthetic chloroform
d. Li_2CO_3, a source of lithium in antidepressants

Solution

a. Potassium (group 1) is a metal, and iodine (group 17) is a nonmetal; KI is predicted to be ionic.
b. Hydrogen (group 1) is a nonmetal, and oxygen (group 16) is a nonmetal; H_2O_2 is predicted to be molecular.
c. Carbon (group 14) is a nonmetal, hydrogen (group 1) is a nonmetal, and chlorine (group 17) is a nonmetal; $CHCl_3$ is predicted to be molecular.
d. Lithium (group 1) is a metal, and carbonate is a polyatomic ion; Li_2CO_3 is predicted to be ionic.

? Exercise 3.1.1

Using the periodic table, predict whether the following compounds are ionic or covalent:

a. SO_2
b. CaF_2
c. N_2H_4
d. $Al_2(SO_4)_3$

Answer a

molecular

Answer b

ionic

Answer c

molecular

Answer d

ionic

Summary

Compounds that contain ions are called ionic compounds. Ionic compounds generally form from metals and nonmetals. Compounds that do not contain ions, but instead consist of atoms bonded tightly together in molecules (uncharged groups of atoms that behave as a single unit), are called covalent compounds. Covalent compounds usually form from two or more nonmetals.

Glossary

covalent bond

attractive force between the nuclei of a molecule's atoms and pairs of electrons between the atoms

covalent compound

(also, molecular compound) composed of molecules formed by atoms of two or more different elements

ionic bond

electrostatic forces of attraction between the oppositely charged ions of an ionic compound

ionic compound

compound composed of cations and anions combined in ratios, yielding an electrically neutral substance

molecular compound

(also, covalent compound) composed of molecules formed by atoms of two or more different elements

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

3.1: Ionic and Molecular Compounds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.7: Molecular and Ionic Compounds** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

3.2: Representation of Chemical Compounds

Learning Objectives

- Symbolize the composition of molecules using molecular formulas and empirical formulas
- Represent the bonding arrangement of atoms within molecules using structural formulas

A molecular formula is a representation of a molecule that uses chemical symbols to indicate the types of atoms followed by subscripts to show the number of atoms of each type in the molecule. (A subscript is used only when more than one atom of a given type is present.) Molecular formulas are also used as abbreviations for the names of compounds.

The structural formula for a compound gives the same information as its molecular formula (the types and numbers of atoms in the molecule) but also shows how the atoms are connected in the molecule. The structural formula for methane contains symbols for one C atom and four H atoms, indicating the number of atoms in the molecule (Figure **3.2.1**). The lines represent bonds that hold the atoms together. (A chemical bond is an attraction between atoms or ions that holds them together in a molecule or a crystal.) We will discuss chemical bonds and see how to predict the arrangement of atoms in a molecule later. For now, simply know that the lines are an indication of how the atoms are connected in a molecule. A ball-and-stick model shows the geometric arrangement of the atoms with atomic sizes not to scale, and a space-filling model shows the relative sizes of the atoms.




Figure **3.2.1**: A methane molecule can be represented as (a) a molecular formula, (b) a structural formula, (c) a ball-and-stick model, and (d) a space-filling model. Carbon and hydrogen atoms are represented by black and white spheres, respectively.

Although many elements consist of discrete, individual atoms, some exist as molecules made up of two or more atoms of the element chemically bonded together. For example, most samples of the elements hydrogen, oxygen, and nitrogen are composed of molecules that contain two atoms each (called diatomic molecules) and thus have the molecular formulas H_2, O_2, and N_2, respectively. Other elements commonly found as diatomic molecules are fluorine (F_2), chlorine (Cl_2), bromine (Br_2), and iodine (I_2). The most common form of the element sulfur is composed of molecules that consist of eight atoms of sulfur; its molecular formula is S_8 (Figure **3.2.2**).




Figure **3.2.2**: A molecule of sulfur is composed of eight sulfur atoms and is therefore written as S_8. It can be represented as (a) a structural formula, (b) a ball-and-stick model, and (c) a space-filling model. Sulfur atoms are represented by yellow spheres.

It is important to note that a subscript following a symbol and a number in front of a symbol do not represent the same thing; for example, H_2 and 2H represent distinctly different species. H_2 is a molecular formula; it represents a diatomic molecule of hydrogen, consisting of two atoms of the element that are chemically bonded together. The expression 2H, on the other hand, indicates two separate hydrogen atoms that are not combined as a unit. The expression $2H_2$ represents two molecules of diatomic hydrogen (Figure **3.2.3**).




Figure **3.2.3**: The symbols H, 2H, H_2, and $2H_2$ represent very different entities.

Compounds are formed when two or more elements chemically combine, resulting in the formation of bonds. For example, hydrogen and oxygen can react to form water, and sodium and chlorine can react to form table salt. We sometimes describe the composition of these compounds with an empirical formula, which indicates the types of atoms present and *the simplest whole-number ratio of the number of atoms (or ions) in the compound*. For example, titanium dioxide (used as pigment in white paint and in the thick, white, blocking type of sunscreen) has an empirical formula of TiO_2. This identifies the elements titanium (Ti) and oxygen (O) as the constituents of titanium dioxide, and indicates the presence of twice as many atoms of the element oxygen as atoms of the element titanium (Figure **3.2.4**).




Figure **3.2.4**: (a) The white compound titanium dioxide provides effective protection from the sun. (b) A crystal of titanium dioxide, TiO_2, contains titanium and oxygen in a ratio of 1 to 2. The titanium atoms are gray and the oxygen atoms are red. (credit a: modification of work by "osseous"/Flickr).

As discussed previously, we can describe a compound with a molecular formula, in which the subscripts indicate the *actual numbers of atoms* of each element in a molecule of the compound. In many cases, the molecular formula of a substance is derived from experimental determination of both its empirical formula and its molecular mass (the sum of atomic masses for all atoms composing the molecule). For example, it can be determined experimentally that benzene contains two elements, carbon (C) and hydrogen (H), and that for every carbon atom in benzene, there is one hydrogen atom. Thus, the empirical formula is CH. An experimental determination of the molecular mass reveals that a molecule of benzene contains six carbon atoms and six hydrogen atoms, so the molecular formula for benzene is C_6H_6 (Figure **3.2.5**).




Figure **3.2.5**: Benzene, C_6H_6, is produced during oil refining and has many industrial uses. A benzene molecule can be represented as (a) a structural formula, (b) a ball-and-stick model, and (c) a space-filling model. (d) Benzene is a clear liquid. (credit d: modification of work by Sahar Atwa).

If we know a compound's formula, we can easily determine the empirical formula. (This is somewhat of an academic exercise; the reverse chronology is generally followed in actual practice.) For example, the molecular formula for acetic acid, the component that gives vinegar its sharp taste, is $C_2H_4O_2$. This formula indicates that a molecule of acetic acid (Figure **3.2.6**) contains two carbon atoms, four hydrogen atoms, and two oxygen atoms. The ratio of atoms is 2:4:2. Dividing by the lowest common

denominator (2) gives the simplest, whole-number ratio of atoms, 1:2:1, so the empirical formula is CH_2O. Note that a molecular formula is always a whole-number multiple of an empirical formula.




Figure **3.2.6**: (a) Vinegar contains acetic acid, $C_2H_4O_2$, which has an empirical formula of CH_2O. It can be represented as (b) a structural formula and (c) as a ball-and-stick model. (credit a: modification of work by "HomeSpot HQ"/Flickr)

Example 3.2.1: Empirical and Molecular Formulas

Molecules of glucose (blood sugar) contain 6 carbon atoms, 12 hydrogen atoms, and 6 oxygen atoms. What are the molecular and empirical formulas of glucose?

Solution

The molecular formula is $C_6H_{12}O_6$ because one molecule actually contains 6 C, 12 H, and 6 O atoms. The simplest whole-number ratio of C to H to O atoms in glucose is 1:2:1, so the empirical formula is CH_2O.

Exercise 3.2.1

A molecule of metaldehyde (a pesticide used for snails and slugs) contains 8 carbon atoms, 16 hydrogen atoms, and 4 oxygen atoms. What are the molecular and empirical formulas of metaldehyde?

Answer

Molecular formula, $C_8H_{16}O_4$; empirical formula, C_2H_4O

It is important to be aware that it may be possible for the same atoms to be arranged in different ways: Compounds with the same molecular formula may have different atom-to-atom bonding and therefore different structures. For example, could there be another compound with the same formula as acetic acid, $C_2H_4O_2$? And if so, what would be the structure of its molecules?

If you predict that another compound with the formula $C_2H_4O_2$ could exist, then you demonstrated good chemical insight and are correct. Two C atoms, four H atoms, and two O atoms can also be arranged to form methyl formate, which is used in manufacturing, as an insecticide, and for quick-drying finishes. Methyl formate molecules have one of the oxygen atoms between the two carbon atoms, differing from the arrangement in acetic acid molecules. Acetic acid and methyl formate are examples of isomers—compounds with the same chemical formula but different molecular structures (Figure **3.2.7**). Note that this small difference in the arrangement of the atoms has a major effect on their respective chemical properties. You would certainly not want to use a solution of methyl formate as a substitute for a solution of acetic acid (vinegar) when you make salad dressing.




Figure **3.2.7**: Molecules of (a) acetic acid and methyl formate (b) are structural isomers; they have the same formula ($C_2H_4O_2$) but different structures (and therefore different chemical properties).

Many types of isomers exist (Figure **3.2.8**). Acetic acid and methyl formate are structural isomers, compounds in which the molecules differ in how the atoms are connected to each other. There are also various types of spatial isomers, in which the relative orientations of the atoms in space can be different. For example, the compound carvone (found in caraway seeds, spearmint, and mandarin orange peels) consists of two isomers that are mirror images of each other. *S*-(+)-carvone smells like caraway, and *R*-(−)-carvone smells like spearmint.




Figure **3.2.8**: Molecules of carvone are spatial isomers; they only differ in the relative orientations of the atoms in space. (credit bottom left: modification of work by "Miansari66"/Wikimedia Commons; credit bottom right: modification of work by Forest & Kim Starr)

Summary

A molecular formula uses chemical symbols and subscripts to indicate the exact numbers of different atoms in a molecule or compound. An empirical formula gives the simplest, whole-number ratio of atoms in a compound. A structural formula indicates the bonding arrangement of the atoms in the molecule. Ball-and-stick and space-filling models show the geometric arrangement of atoms in a molecule. Isomers are compounds with the same molecular formula but different arrangements of atoms.

Glossary

empirical formula
formula showing the composition of a compound given as the simplest whole-number ratio of atoms

isomers
compounds with the same chemical formula but different structures

molecular formula
formula indicating the composition of a molecule of a compound and giving the actual number of atoms of each element in a molecule of the compound.

spatial isomers
compounds in which the relative orientations of the atoms in space differ

structural isomer

one of two substances that have the same molecular formula but different physical and chemical properties because their atoms are bonded differently

structural formula

shows the atoms in a molecule and how they are connected

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

3.2: Representation of Chemical Compounds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.5: Chemical Formulas** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

3.3: Types of ions

In ordinary chemical reactions, the nucleus of each atom (and thus the identity of the element) remains unchanged. Electrons, however, can be added to atoms by transfer from other atoms, lost by transfer to other atoms, or shared with other atoms. The transfer and sharing of electrons among atoms govern the chemistry of the elements. During the formation of some compounds, atoms gain or lose electrons, and form electrically charged particles called ions (Figure **3.3.1**).




Figure **3.3.1**: (a) A sodium atom (Na) has equal numbers of protons and electrons (11) and is uncharged. (b) A sodium cation (Na^+) has lost an electron, so it has one more proton (11) than electrons (10), giving it an overall positive charge, signified by a superscripted plus sign.

You can use the periodic table to predict whether an atom will form an anion or a cation, and you can often predict the charge of the resulting ion. Atoms of many main-group metals lose enough electrons to leave them with the same number of electrons as an atom of the preceding noble gas. To illustrate, an atom of an alkali metal (group 1) loses one electron and forms a cation with a 1+ charge; an alkaline earth metal (group 2) loses two electrons and forms a cation with a 2+ charge, and so on. For example, a neutral calcium atom, with 20 protons and 20 electrons, readily loses two electrons. This results in a cation with 20 protons, 18 electrons, and a 2+ charge. It has the same number of electrons as atoms of the preceding noble gas, argon, and is symbolized Ca^{2+}. The name of a metal ion is the same as the name of the metal atom from which it forms, so Ca^{2+} is called a calcium ion.

When atoms of nonmetal elements form ions, they generally gain enough electrons to give them the same number of electrons as an atom of the next noble gas in the periodic table. Atoms of group 17 gain one electron and form anions with a 1− charge; atoms of group 16 gain two electrons and form ions with a 2− charge, and so on. For example, the neutral bromine atom, with 35 protons and 35 electrons, can gain one electron to provide it with 36 electrons. This results in an anion with 35 protons, 36 electrons, and a 1− charge. It has the same number of electrons as atoms of the next noble gas, krypton, and is symbolized Br^-. (A discussion of the theory supporting the favored status of noble gas electron numbers reflected in these predictive rules for ion formation is provided in a later chapter of this text.)

Note the usefulness of the periodic table in predicting likely ion formation and charge (Figure **3.3.2**). Moving from the far left to the right on the periodic table, main-group elements tend to form cations with a charge equal to the group number. That is, group 1 elements form 1+ ions; group 2 elements form 2+ ions, and so on. Moving from the far right to the left on the periodic table, elements often form anions with a negative charge equal to the number of groups moved left from the noble gases. For example, group 17 elements (one group left of the noble gases) form 1− ions; group 16 elements (two groups left) form 2− ions, and so on. This trend can be used as a guide in many cases, but its predictive value decreases when moving toward the center of the periodic table. In fact, transition metals and some other metals often exhibit variable charges that are not predictable by their location in the table. For example, copper can form ions with a 1+ or 2+ charge, and iron can form ions with a 2+ or 3+ charge.




Figure **3.3.2**: Some elements exhibit a regular pattern of ionic charge when they form ions.

✔ Example 3.3.1: Composition of Ions

An ion found in some compounds used as antiperspirants contains 13 protons and 10 electrons. What is its symbol?

Solution

Because the number of protons remains unchanged when an atom forms an ion, the atomic number of the element must be 13. Knowing this lets us use the periodic table to identify the element as Al (aluminum). The Al atom has lost three electrons and thus has three more positive charges (13) than it has electrons (10). This is the aluminum cation, Al^{3+}.

? Exercise 3.3.1

Give the symbol and name for the ion with 34 protons and 36 electrons.

Answer

Se^{2-}, the selenide ion

✔ Example 3.3.2: Formation of Ions

Magnesium and nitrogen react to form an ionic compound. Predict which forms an anion, which forms a cation, and the charges of each ion. Write the symbol for each ion and name them.

Solution

Magnesium's position in the periodic table (group 2) tells us that it is a metal. Metals form positive ions (cations). A magnesium atom must lose two electrons to have the same number electrons as an atom of the previous noble gas, neon. Thus, a magnesium atom will form a cation with two fewer electrons than protons and a charge of 2+. The symbol for the ion is Mg^{2+}, and it is called a magnesium ion.

Nitrogen's position in the periodic table (group 15) reveals that it is a nonmetal. Nonmetals form negative ions (anions). A nitrogen atom must gain three electrons to have the same number of electrons as an atom of the following noble gas, neon. Thus, a nitrogen atom will form an anion with three more electrons than protons and a charge of 3−. The symbol for the ion is N^{3-}, and it is called a nitride ion.

? Exercise 3.3.2

Aluminum and carbon react to form an ionic compound. Predict which forms an anion, which forms a cation, and the charges of each ion. Write the symbol for each ion and name them.

Answer

Al will form a cation with a charge of 3+: Al^{3+}, an aluminum ion. Carbon will form an anion with a charge of 4−: C^{4-}, a carbide ion.

The ions that we have discussed so far are called monatomic ions, that is, they are ions formed from only one atom. We also find many polyatomic ions. These ions, which act as discrete units, are electrically charged molecules (a group of bonded atoms with an overall charge). Some of the more important polyatomic ions are listed in Table **3.3.1**. Oxyanions are polyatomic ions that contain one or more oxygen atoms. At this point in your study of chemistry, you should memorize the names, formulas, and charges of the most common polyatomic ions. Because you will use them repeatedly, they will soon become familiar.

Table **3.3.1**: Common Polyatomic Ions

Name	Formula	Related Acid	Formula
ammonium	NH_4^+		
hydronium	H_3O^+		
oxide	O^{2-}		
peroxide	O_2^{2-}		
hydroxide	OH^-		
acetate	CH_3COO^-	acetic acid	CH_3COOH
cyanide	CN^-	hydrocyanic acid	HCN
azide	N_3^-	hydrazoic acid	HN_3
carbonate	CO_3^{2-}	carbonic acid	H_2CO_3
bicarbonate	HCO_3^-		
nitrate	NO_3^-	nitric acid	HNO_3
nitrite	NO_2^-	nitrous acid	HNO_2
sulfate	SO_4^{2-}	sulfuric acid	H_2SO_4
hydrogen sulfate	HSO_4^-		
sulfite	SO_3^{2-}	sulfurous acid	H_2SO_3
hydrogen sulfite	HSO_3^-		
phosphate	PO_4^{3-}	phosphoric acid	H_3PO_4
hydrogen phosphate	HPO_4^{2-}		
dihydrogen phosphate	$H_2PO_4^-$		
perchlorate	ClO_4^-	perchloric acid	$HClO_4$
chlorate	ClO_3^-	chloric acid	$HClO_3$
chlorite	ClO_2^-	chlorous acid	$HClO_2$
hypochlorite	ClO^-	hypochlorous acid	$HClO$
chromate	CrO_4^{2-}	chromic acid	H_2CrO_4
dichromate	$Cr_2O_7^{2-}$	dichromic acid	$H_2Cr_2O_7$
permanganate	MnO_4^-	permanganic acid	$HMnO_4$

Note that there is a system for naming some polyatomic ions; *-ate* and *-ite* are suffixes designating polyatomic ions containing more or fewer oxygen atoms. *Per-* (short for “hyper”) and *hypo-* (meaning “under”) are prefixes meaning more oxygen atoms than *-ate* and fewer oxygen atoms than *-ite*, respectively. For example, perchlorate is ClO_4^-, chlorate is ClO_3^-, chlorite is ClO_2^- and hypochlorite is ClO^-. Unfortunately, the number of oxygen atoms corresponding to a given suffix or prefix is not consistent; for example, nitrate is NO_3^- while sulfate is SO_4^{2-}. This will be covered in more detail in the next module on nomenclature.

Summary

Metals (particularly those in groups 1 and 2) tend to lose the number of electrons that would leave them with the same number of electrons as in the preceding noble gas in the periodic table. By this means, a positively charged ion is formed. Similarly, nonmetals

(especially those in groups 16 and 17, and, to a lesser extent, those in Group 15) can gain the number of electrons needed to provide atoms with the same number of electrons as in the next noble gas in the periodic table. Thus, nonmetals tend to form negative ions. Positively charged ions are called cations, and negatively charged ions are called anions. Ions can be either monatomic (containing only one atom) or polyatomic (containing more than one atom).

Glossary

monatomic ion
ion composed of a single atom

polyatomic ion
ion composed of more than one atom

Contributors and Attributions

oxyanion
polyatomic anion composed of a central atom bonded to oxygen atoms

Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

3.3: Types of ions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.7: Molecular and Ionic Compounds** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **2.5: Chemical Formulas** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

3.4: Formulas and names of ionic compounds

Learning Objectives

- Derive names for common types of ionic compounds using a systematic approach

Nomenclature, a collection of rules for naming things, is important in science and in many other situations. This section describes an approach that is used to name simple ionic such as NaCl, and $CaCO_3$. The simplest of these are binary compounds, those containing only two elements, but we will also consider how to name ionic compounds containing polyatomic ions. We will follow the nomenclature guidelines proposed by IUPAC.

To name an inorganic compound, we need to consider the answers to several questions. First, is the compound ionic or molecular? If the compound is ionic, does the metal form ions of only one type (fixed charge) or more than one type (variable charge)? Are the ions monatomic or polyatomic?

Compounds Containing Only Monatomic Ions

The name of a binary compound containing monatomic ions consists of the name of the cation (the name of the metal) followed by the name of the anion (the name of the nonmetallic element with its ending replaced by the suffix *–ide*). Some examples are given in Table **3.4.1**.

Table **3.4.1**: Names of Some Ionic Compounds

NaCl, sodium chloride	Na_2O, sodium oxide
KBr, potassium bromide	CdS, cadmium sulfide
CaI_2, calcium iodide	Mg_3N_2, magnesium nitride
CsF, cesium fluoride	Ca_3P_2, calcium phosphide
LiCl, lithium chloride	Al_4C_3, aluminum carbide

Compounds Containing Polyatomic Ions

Compounds containing polyatomic ions are named similarly to those containing only monatomic ions, except there is no need to change to an *–ide* ending, since the suffix is already present in the name of the anion. Examples are shown in Table **3.4.2**.

Table **3.4.2**: Names of Some Polyatomic Ionic Compounds

$KC_2H_3O_2$, potassium acetate	$(NH_4)Cl$, ammonium chloride
$NaHCO_3$, sodium bicarbonate	$CaSO_4$, calcium sulfate
$Al_2(CO_3)_3$, aluminum carbonate	$Mg_3(PO_4)_2$, magnesium phosphate

Ionic Compounds in Your Cabinets

Every day you encounter and use a large number of ionic compounds. Some of these compounds, where they are found, and what they are used for are listed in Table. Look at the label or ingredients list on the various products that you use during the next few days, and see if you run into any of those in this table, or find other ionic compounds that you could now name or write as a formula.

Ionic Compound	Use
NaCl, sodium chloride	ordinary table salt
KI, potassium iodide	added to “iodized” salt for thyroid health
NaF, sodium fluoride	ingredient in toothpaste
$NaHCO_3$, sodium bicarbonate	baking soda; used in cooking (and as antacid)
Na_2CO_3, sodium carbonate	washing soda; used in cleaning agents
NaOCl, sodium hypochlorite	active ingredient in household bleach
$CaCO_3$ calcium carbonate	ingredient in antacids
$Mg(OH)_2$, magnesium hydroxide	ingredient in antacids
$Al(OH)_3$, aluminum hydroxide	ingredient in antacids
NaOH, sodium hydroxide	lye; used as drain cleaner
K_3PO_4, potassium phosphate	food additive (many purposes)
$MgSO_4$, magnesium sulfate	added to purified water
Na_2HPO_4, sodium hydrogen phosphate	anti-caking agent; used in powdered products
Na_2SO_3, sodium sulfite	preservative

Compounds Containing a Metal Ion with a Variable Charge

Most of the transition metals can form two or more cations with different charges. Compounds of these metals with nonmetals are named with the same method as compounds in the first category, except the charge of the metal ion is specified by a Roman numeral in parentheses after the name of the metal. The charge of the metal ion is determined from the formula of the compound and the charge of the anion. For example, consider binary ionic compounds of iron and chlorine. Iron typically exhibits a charge of either 2+ or 3+ (see [link]), and the two corresponding compound formulas are $FeCl_2$ and $FeCl_3$. The simplest name, “iron chloride,” will, in this case, be ambiguous, as it does not distinguish between these two compounds. In cases like this, the charge of the metal ion is included as a Roman numeral in parentheses immediately following the metal name. These two compounds are then unambiguously named iron(II) chloride and iron(III) chloride, respectively. Other examples are provided in Table **3.4.3**.

Table **3.4.3**: Names of Some Transition Metal Ionic Compounds

Transition Metal Ionic Compound	Name
$FeCl_3$	iron(III) chloride
Hg_2O	mercury(I) oxide
HgO	mercury(II) oxide
$Cu_3(PO_4)_2$	copper(II) phosphate

Out-of-date nomenclature used the suffixes *–ic* and *–ous* to designate metals with higher and lower charges, respectively: Iron(III) chloride, $FeCl_3$, was previously called ferric chloride, and iron(II) chloride, $FeCl_2$, was known as ferrous chloride. Though this naming convention has been largely abandoned by the scientific community, it remains in use by some segments of industry. For example, you may see the words *stannous fluoride* on a tube of toothpaste. This represents the formula SnF_2, which is more properly named tin(II) fluoride. The other fluoride of tin is SnF_4, which was previously called stannic fluoride but is now named tin(IV) fluoride.

Naming Ionic Compounds

Name the following ionic compounds, which contain a metal that can have more than one ionic charge:

a. Fe_2S_3
b. CuSe
c. GaN
d. $CrCl_3$
e. $Ti_2(SO_4)_3$

Solution

The anions in these compounds have a fixed negative charge (S^{2-}, Se^{2-} , N^{3-}, Cl^-, and SO_4^{2-}), and the compounds must be neutral. Because the total number of positive charges in each compound must equal the total number of negative charges, the positive ions must be Fe^{3+}, Cu^{2+}, Ga^{3+}, Cr^{4+}, and Ti^{3+}. These charges are used in the names of the metal ions:

a. iron(III) sulfide
b. copper(II) selenide
c. gallium(III) nitride
d. chromium(III) chloride
e. titanium(III) sulfate

Exercise 3.4.1

Write the formulas of the following ionic compounds:

a. chromium(III) phosphide
b. mercury(II) sulfide
c. manganese(II) phosphate
d. copper(I) oxide
e. chromium(VI) fluoride
f. **Answer**

Summary

Chemists use nomenclature rules to clearly name compounds. Ionic and molecular compounds are named using somewhat-different methods. Binary ionic compounds typically consist of a metal and a nonmetal. The name of the metal is written first, followed by the name of the nonmetal with its ending changed to *–ide*. For example, K_2O is called potassium oxide. If the metal can form ions with different charges, a Roman numeral in parentheses follows the name of the metal to specify its charge. Thus, $FeCl_2$ is iron(II) chloride and $FeCl_3$ is iron(III) chloride. Some compounds contain polyatomic ions; the names of common polyatomic ions should be memorized.

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

3.4: Formulas and names of ionic compounds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

3.5: Formulas and Names of Covalent Compounds

Learning Objectives

- Derive names for common types of molecular compounds using a systematic approach

The bonding characteristics of inorganic molecular compounds are different from ionic compounds, and they are named using a different system as well. The charges of cations and anions dictate their ratios in ionic compounds, so specifying the names of the ions provides sufficient information to determine chemical formulas. However, because covalent bonding allows for significant variation in the combination ratios of the atoms in a molecule, the names for molecular compounds must explicitly identify these ratios.

Compounds Composed of Two Elements

When two nonmetallic elements form a molecular compound, several combination ratios are often possible. For example, carbon and oxygen can form the compounds CO and CO_2. Since these are different substances with different properties, they cannot both have the same name (they cannot both be called carbon oxide). To deal with this situation, we use a naming method that is somewhat similar to that used for ionic compounds, but with added prefixes to specify the numbers of atoms of each element. The name of the more metallic element (the one farther to the left and/or bottom of the periodic table) is first, followed by the name of the more nonmetallic element (the one farther to the right and/or top) with its ending changed to the suffix *–ide*. The numbers of atoms of each element are designated by the Greek prefixes shown in Table **3.5.1**.

Table **3.5.1**: Nomenclature Prefixes

Number	Prefix		Number	Prefix
1 (sometimes omitted)	mono-		6	hexa-
2	di-		7	hepta-
3	tri-		8	octa-
4	tetra-		9	nona-
5	penta-		10	deca-

When only one atom of the first element is present, the prefix *mono-* is usually deleted from that part. Thus, CO is named carbon monoxide, and CO_2 is called carbon dioxide. When two vowels are adjacent, the *a* in the Greek prefix is usually dropped. Some other examples are shown in Table **3.5.2**.

Table **3.5.2**: Names of Some Molecular Compounds Composed of Two Elements

Compound	Name		Compound	Name
SO_2	sulfur dioxide		BCl_3	boron trichloride
SO_3	sulfur trioxide		SF_6	sulfur hexafluoride
NO_2	nitrogen dioxide		PF_5	phosphorus pentafluoride
N_2O_4	dinitrogen tetroxide		P_4O_{10}	tetraphosphorus decaoxide
N_2O_5	dinitrogen pentoxide		IF_7	iodine heptafluoride

There are a few common names that you will encounter as you continue your study of chemistry. For example, although NO is often called nitric oxide, its proper name is nitrogen monoxide. Similarly, N_2O is known as nitrous oxide even though our rules would specify the name dinitrogen monoxide. (And H_2O is usually called water, not dihydrogen monoxide.) You should commit to memory the common names of compounds as you encounter them.

Naming Covalent Compounds

Name the following covalent compounds:

a. SF_6
b. N_2O_3
c. Cl_2O_7
d. P_4O_6

Solution

Because these compounds consist solely of nonmetals, we use prefixes to designate the number of atoms of each element:

a. sulfur hexafluoride
b. dinitrogen trioxide
c. dichlorine heptoxide
d. tetraphosphorus hexoxide

Exercise 3.5.1

Write the formulas for the following compounds:

a. phosphorus pentachloride
b. dinitrogen monoxide
c. iodine heptafluoride
d. carbon tetrachloride

Answer

(a) PCl_5; (b) N_2O; (c) IF_7; (d) CCl_4

Binary Acids

Some compounds containing hydrogen are members of an important class of substances known as acids. The chemistry of these compounds is explored in more detail in later chapters of this text, but for now, it will suffice to note that many acids release hydrogen ions, H^+, when dissolved in water. To denote this distinct chemical property, a mixture of water with an acid is given a name derived from the compound's name. If the compound is a binary acid (comprised of hydrogen and one other nonmetallic element):

1. The word "hydrogen" is changed to the prefix *hydro-*
2. The other nonmetallic element name is modified by adding the suffix *-ic*
3. The word "acid" is added as a second word

For example, when the gas HCl (hydrogen chloride) is dissolved in water, the solution is called *hydrochloric acid*. Several other examples of this nomenclature are shown in Table **3.5.3**.

Table **3.5.3**: Names of Some Simple Acids

Name of Gas	Name of Acid
HF(*g*), hydrogen fluoride	HF(*aq*), hydrofluoric acid
HCl(*g*), hydrogen chloride	HCl(*aq*), hydrochloric acid
HBr(*g*), hydrogen bromide	HBr(*aq*), hydrobromic acid
HI(*g*), hydrogen iodide	HI(*aq*), hydroiodic acid
H_2S(*g*), hydrogen sulfide	H_2S(*aq*), hydrosulfuric acid

Oxyacids

Many compounds containing three or more elements (such as organic compounds or coordination compounds) are subject to specialized nomenclature rules that you will learn later. However, we will briefly discuss the important compounds known as oxyacids, compounds that contain hydrogen, oxygen, and at least one other element, and are bonded in such a way as to impart acidic properties to the compound (you will learn the details of this in a later chapter). Typical oxyacids consist of hydrogen combined with a polyatomic, oxygen-containing ion. To name oxyacids:

1. Omit “hydrogen”
2. Start with the root name of the anion
3. Replace *–ate* with *–ic*, or *–ite* with *–ous*
4. Add “acid”

For example, consider H_2CO_3 (which you might be tempted to call “hydrogen carbonate”). To name this correctly, “hydrogen” is omitted; the *–ate* of carbonate is replace with *–ic*; and acid is added—so its name is carbonic acid. Other examples are given in Table **3.5.4**. There are some exceptions to the general naming method (e.g., H_2SO_4 is called sulfuric acid, not sulfic acid, and H_2SO_3 is sulfurous, not sulfous, acid).

Table **3.5.4**: Names of Common Oxyacids

Formula	Anion Name	Acid Name
$HC_2H_3O_2$	acetate	acetic acid
HNO_3	nitrate	nitric acid
HNO_2	nitrite	nitrous acid
$HClO_4$	perchlorate	perchloric acid
H_2CO_3	carbonate	carbonic acid
H_2SO_4	sulfate	sulfuric acid
H_2SO_3	sulfite	sulfurous acid
H_3PO_4	phosphate	phosphoric acid

Summary

Molecular compounds can form compounds with different ratios of their elements, so prefixes are used to specify the numbers of atoms of each element in a molecule of the compound. Examples include SF_6, sulfur hexafluoride, and N_2O_4, dinitrogen tetroxide. Acids are an important class of compounds containing hydrogen and having special nomenclature rules. Binary acids are named using the prefix *hydro-*, changing the *–ide* suffix to *–ic*, and adding “acid;” HCl is hydrochloric acid. Oxyacids are named by changing the ending of the anion to *–ic*, and adding “acid;” H_2CO_3 is carbonic acid.

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

3.5: Formulas and Names of Covalent Compounds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

3.6: Formula Mass and Molar Mass of Compounds

Learning Objectives

- Calculate formula masses for covalent and ionic compounds
- Define the amount unit mole and the related quantity Avogadro's number
- Explain the relation between mass, moles, and numbers of atoms or molecules, and perform calculations deriving these quantities from one another

We can argue that modern chemical science began when scientists started exploring the quantitative as well as the qualitative aspects of chemistry. For example, Dalton's atomic theory was an attempt to explain the results of measurements that allowed him to calculate the relative masses of elements combined in various compounds. Understanding the relationship between the masses of atoms and the chemical formulas of compounds allows us to quantitatively describe the composition of substances.

Formula Mass

In an earlier chapter, we described the development of the atomic mass unit, the concept of average atomic masses, and the use of chemical formulas to represent the elemental makeup of substances. These ideas can be extended to calculate the formula mass of a substance by summing the average atomic masses of all the atoms represented in the substance's formula.

Formula Mass for Covalent Substances

For covalent substances, the formula represents the numbers and types of atoms composing a single molecule of the substance; therefore, the formula mass may be correctly referred to as a molecular mass. Consider chloroform ($CHCl_3$), a covalent compound once used as a surgical anesthetic and now primarily used in the production of tetrafluoroethylene, the building block for the "anti-stick" polymer, Teflon. The molecular formula of chloroform indicates that a single molecule contains one carbon atom, one hydrogen atom, and three chlorine atoms. The average molecular mass of a chloroform molecule is therefore equal to the sum of the average atomic masses of these atoms. Figure **3.6.1** outlines the calculations used to derive the molecular mass of chloroform, which is 119.37 amu.

Element	Quantity		Average atomic mass (amu)		Subtotal (amu)
C	1	×	12.01	=	12.01
H	1	×	1.008	=	1.008
Cl	3	×	35.45	=	106.35
				Molecular mass	119.37




Figure **3.6.1**: The average mass of a chloroform molecule, $CHCl_3$, is 119.37 amu, which is the sum of the average atomic masses of each of its constituent atoms. The model shows the molecular structure of chloroform.

Likewise, the molecular mass of an aspirin molecule, $C_9H_8O_4$, is the sum of the atomic masses of nine carbon atoms, eight hydrogen atoms, and four oxygen atoms, which amounts to 180.15 amu (Figure **3.6.2**).

Element	Quantity		Average atomic mass (amu)		Subtotal (amu)
C	9	×	12.01	=	108.09
H	8	×	1.008	=	8.064
O	4	×	16.00	=	64.00
				Molecular mass	180.15



Figure **3.6.2**: The average mass of an aspirin molecule is 180.15 amu. The model shows the molecular structure of aspirin, $C_9H_8O_4$.


Example 3.6.1: Computing Molecular Mass for a Covalent Compound

Ibuprofen, $C_{13}H_{18}O_2$, is a covalent compound and the active ingredient in several popular nonprescription pain medications, such as Advil and Motrin. What is the molecular mass (amu) for this compound?

Solution

Molecules of this compound are comprised of 13 carbon atoms, 18 hydrogen atoms, and 2 oxygen atoms. Following the approach described above, the average molecular mass for this compound is therefore:

Element	Quantity		Average atomic mass (amu)		Subtotal (amu)
C	13	×	12.01	=	156.13
H	18	×	1.008	=	18.114
O	2	×	16.00	=	32.00
				Molecular mass	206.27



Exercise 3.6.1

Acetaminophen, $C_8H_9NO_2$, is a covalent compound and the active ingredient in several popular nonprescription pain medications, such as Tylenol. What is the molecular mass (amu) for this compound?

Answer

151.16 amu

Formula Mass for Ionic Compounds

Ionic compounds are composed of discrete cations and anions combined in ratios to yield electrically neutral bulk matter. The formula mass for an ionic compound is calculated in the same way as the formula mass for covalent compounds: by summing the average atomic masses of all the atoms in the compound's formula. Keep in mind, however, that the formula for an ionic compound does not represent the composition of a discrete molecule, so it may not correctly be referred to as the "molecular mass."

As an example, consider sodium chloride, NaCl, the chemical name for common table salt. Sodium chloride is an ionic compound composed of sodium cations, Na^+, and chloride anions, Cl^-, combined in a 1:1 ratio. The formula mass for this compound is computed as 58.44 amu (Figure **3.6.3**).

Element	Quantity		Average atomic mass (amu)		Subtotal
Na	1	×	22.99	=	22.99
Cl	1	×	35.45	=	35.45
				Formula mass	58.44




Figure **3.6.3**: Table salt, NaCl, contains an array of sodium and chloride ions combined in a 1:1 ratio. Its formula mass is 58.44 amu.

Note that the average masses of neutral sodium and chlorine atoms were used in this computation, rather than the masses for sodium cations and chlorine anions. This approach is perfectly acceptable when computing the formula mass of an ionic compound. Even though a sodium cation has a slightly smaller mass than a sodium atom (since it is missing an electron), this difference will be offset by the fact that a chloride anion is slightly more massive than a chloride atom (due to the extra electron). Moreover, the mass of an electron is negligibly small with respect to the mass of a typical atom. Even when calculating the mass of an isolated ion, the missing or additional electrons can generally be ignored, since their contribution to the overall mass is negligible, reflected only in the nonsignificant digits that will be lost when the computed mass is properly rounded. The few exceptions to this guideline are very light ions derived from elements with precisely known atomic masses.

Example 3.6.2: Computing Formula Mass for an Ionic Compound

Aluminum sulfate, $Al_2(SO_4)_3$, is an ionic compound that is used in the manufacture of paper and in various water purification processes. What is the formula mass (amu) of this compound?

Solution

The formula for this compound indicates it contains Al^{3+} and SO_4^{2-} ions combined in a 2:3 ratio. For purposes of computing a formula mass, it is helpful to rewrite the formula in the simpler format, $Al_2S_3O_{12}$. Following the approach outlined above, the formula mass for this compound is calculated as follows:



" style="width: 791px; height: 210px;" width="791px" height="210px" src="/@api/deki/files/56171/CNX_Chem_03_01_alsulfatemass_img.jpg">

Exercise 3.6.2

Calcium phosphate, $Ca_3(PO_4)_2$, is an ionic compound and a common anti-caking agent added to food products. What is the formula mass (amu) of calcium phosphate?

Answer

310.18 amu

Molar Mass of compounds

The identity of a substance is defined not only by the types of atoms or ions it contains, but by the quantity of each type of atom or ion. For example, water, H_2O, and hydrogen peroxide, H_2O_2, are alike in that their respective molecules are composed of hydrogen and oxygen atoms. However, because a hydrogen peroxide molecule contains two oxygen atoms, as opposed to the water molecule, which has only one, the two substances exhibit very different properties. Today, we possess sophisticated instruments that allow the direct measurement of these defining microscopic traits; however, the same traits were originally derived from the measurement of macroscopic properties (the masses and volumes of bulk quantities of matter) using relatively simple tools (balances and volumetric glassware). This experimental approach required the introduction of a new unit for amount of substances, the *mole*, which remains indispensable in modern chemical science.

Remember from Chapter 2, the mole is an amount unit similar to familiar units like pair, dozen, gross, etc. It provides a specific measure of *the number* of atoms or molecules in a bulk sample of matter. The number of entities composing a mole has been experimentally determined to be $6.02214179 \times 10^{23}$, a fundamental constant named **Avogadro's number** (N_A) or the Avogadro constant in honor of Italian scientist Amedeo Avogadro. This constant is properly reported with an explicit unit of "per mole," a conveniently rounded version being $6.022 \times 10^{23}/\text{mol}$.

Similar to atoms, 1 mole of any compound contains the same number of molecules as 1 mole of any other compund. The masses of 1 mole of different compunds, however, are different, since the masses of the individual molecules are drastically different. The molar mass of a compound is the mass in grams of 1 mole of that substance, a property expressed in units of grams per mole (g/mol)

Because the definitions of both the mole and the formula mass are based on the same reference substance, ^{12}C, the molar mass of any compound is numerically equivalent to its formula weight in amu.



Molar Masses of Compounds: https://youtu.be/PhOqgNNv78s


The relationships between formula mass, the mole, and Avogadro's number can be applied to compute various quantities that describe the composition of compounds. For example, if we know the mass and chemical composition of a compound, we can determine the number of moles and calculate number of molecules in the sample. Likewise, if we know the number of moles of a compound, we can derive the number of molecules and calculate the compound's mass.

Example 3.6.3: Deriving Moles from Grams for a Compound

Our bodies synthesize protein from amino acids. One of these amino acids is glycine, which has the molecular formula $C_2H_5O_2N$. How many moles of glycine molecules are contained in 28.35 g of glycine?


Solution

We can derive the number of moles of a compound from its mass following the same procedure we used for an element in Example **3.6.6**:



The molar mass of glycine is required for this calculation, and it is computed in the same fashion as its molecular mass. One mole of glycine, $C_2H_5O_2N$, contains 2 moles of carbon, 5 moles of hydrogen, 2 moles of oxygen, and 1 mole of nitrogen:

Element	Quantity (mol element/ mol compound)		Molar mass (g/mol element)		Subtotal (g/mol compound)
C	2	×	12.01	=	24.02
H	5	×	1.008	=	5.040
O	2	×	16.00	=	32.00
N	1	×	14.007	=	14.007
Molecular mass (g/mol compound)					75.07



The provided mass of glycine (~28 g) is a bit more than one-third the molar mass (~75 g/mol), so we would expect the computed result to be a bit greater than one-third of a mole (~0.33 mol). Dividing the compound's mass by its molar mass yields:

$$28.35\ \cancel{g}\ \text{glycine}\left(\frac{\text{mol glycine}}{75.07\ \cancel{g}}\right) = 0.378\ \text{mol glycine}$$

This result is consistent with our rough estimate.

Exercise 3.6.3

How many moles of sucrose, $C_{12}H_{22}O_{11}$, are in a 25-g sample of sucrose?

Answer


0.073 mol

Example 3.6.4: Deriving Grams from Moles for a Compound

Vitamin C is a covalent compound with the molecular formula $C_6H_8O_6$. The recommended daily dietary allowance of vitamin C for children aged 4–8 years is 1.42×10^{-4} mol. What is the mass of this allowance in grams?

Solution

As for elements, the mass of a compound can be derived from its molar amount as shown:



The molar mass for this compound is computed to be 176.124 g/mol. The given number of moles is a very small fraction of a mole (~10^{-4} or one-ten thousandth); therefore, we would expect the corresponding mass to be about one-ten thousandth of the molar mass (~0.02 g). Performing the calculation, we get:

$$1.42 \times 10^{-4} \cancel{\text{mol}}\ \text{vitamin C} \left(\frac{176.124\ \text{g}}{\cancel{\text{mol}}\ \text{vitamin C}} \right) = 0.0250\ \text{g vitamin C}$$

This is consistent with the anticipated result.

Exercise 3.6.4


What is the mass of 0.443 mol of hydrazine, N_2H_4?

Answer

14.2 g

Example 3.6.5: Deriving the Number of Molecules from the Compound Mass


A packet of an artificial sweetener contains 40.0 mg of saccharin ($C_7H_5NO_3S$), which has the structural formula:



Given that saccharin has a molar mass of 183.18 g/mol, how many saccharin molecules are in a 40.0-mg (0.0400-g) sample of saccharin? How many carbon atoms are in the same sample?

Solution

The number of molecules in a given mass of compound is computed by first deriving the number of moles, as demonstrated in Example **3.6.8**, and then multiplying by Avogadro's number:



Using the provided mass and molar mass for saccharin yields:

$$0.0400\ \cancel{g}\ C_7H_5NO_3S\left(\frac{\cancel{mol}\ C_7H_5NO_3S}{183.18\ \cancel{g}\ C_7H_5NO_3S}\right)\left(\frac{6.022\times10^{23}\ C_7H_5NO_3S\ molecules}{1\ \cancel{mol}\ C_7H_5NO_3S}\right)$$
$$=1.31\times10^{20}\ C_7H_5NO_3S\ molecules \tag{3.6.1}$$

The compound's formula shows that each molecule contains seven carbon atoms, and so the number of C atoms in the provided sample is:

$$1.31\times10^{20}\ C_7H_5NO_3S\ molecules\left(\frac{7\ C\ atoms}{1\ C_7H_5NO_3S\ molecule}\right)=9.20\times10^{21}\ C\ atoms$$

? Exercise 3.6.5

How many C_4H_{10} molecules are contained in 9.213 g of this compound? How many hydrogen atoms?

Answer

- 9.545×10^{22} molecules C_4H_{10}
- 9.545×10^{23} atoms H

Summary

The formula mass of a substance is the sum of the average atomic masses of each atom represented in the chemical formula and is expressed in atomic mass units. The formula mass of a covalent compound is also called the molecular mass. A convenient amount unit for expressing very large numbers of atoms or molecules is the mole. Experimental measurements have determined the number of entities composing 1 mole of substance to be 6.022×10^{23}, a quantity called Avogadro's number. The mass in grams of 1 mole of substance is its molar mass. Due to the use of the same reference substance in defining the atomic mass unit and the mole, the formula mass (amu) and molar mass (g/mol) for any substance are numerically equivalent (for example, one H_2O molecule weighs approximately18 amu and 1 mole of H_2O molecules weighs approximately 18 g).

Footnotes

1. 1 Omiatek, Donna M., Amanda J. Bressler, Ann-Sofie Cans, Anne M. Andrews, Michael L. Heien, and Andrew G. Ewing. "The Real Catecholamine Content of Secretory Vesicles in the CNS Revealed by Electrochemical Cytometry." *Scientific Report* 3 (2013): 1447, accessed January 14, 2015, doi:10.1038/srep01447.

Glossary

Avogadro's number (N_A)
experimentally determined value of the number of entities comprising 1 mole of substance, equal to $6.022\times10^{23}\ mol^{-1}$

formula mass
sum of the average masses for all atoms represented in a chemical formula; for covalent compounds, this is also the molecular mass

mole

amount of substance containing the same number of atoms, molecules, ions, or other entities as the number of atoms in exactly 12 grams of ^{12}C

molar mass

mass in grams of 1 mole of a substance

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

3.6: Formula Mass and Molar Mass of Compounds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.1: Formula Mass and the Mole Concept** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

3.7: Percent Composition, Emperical Formulas, and Molecular Fromulas

Learning Objectives

- Compute the percent composition of a compound
- Determine the empirical formula of a compound
- Determine the molecular formula of a compound

In the previous section, we discussed the relationship between the bulk mass of a substance and the number of atoms or molecules it contains (moles). Given the chemical formula of the substance, we were able to determine the amount of the substance (moles) from its mass, and vice versa. But what if the chemical formula of a substance is unknown? In this section, we will explore how to apply these very same principles in order to derive the chemical formulas of unknown substances from experimental mass measurements.

Percent Composition

The elemental makeup of a compound defines its chemical identity, and chemical formulas are the most succinct way of representing this elemental makeup. When a compound's formula is unknown, measuring the mass of each of its constituent elements is often the first step in the process of determining the formula experimentally. The results of these measurements permit the calculation of the compound's percent composition, defined as the percentage by mass of each element in the compound. For example, consider a gaseous compound composed solely of carbon and hydrogen. The percent composition of this compound could be represented as follows:

$$\%\mathrm{H} = \frac{\text{mass H}}{\text{mass compound}} \times 100\% \tag{3.7.1}$$

$$\%\mathrm{C} = \frac{\text{mass C}}{\text{mass compound}} \times 100\% \tag{3.7.2}$$

If analysis of a 10.0-g sample of this gas showed it to contain 2.5 g H and 7.5 g C, the percent composition would be calculated to be 25% H and 75% C:

$$\%\mathrm{H} = \frac{2.5\ \text{g H}}{10.0\ \text{g compound}} \times 100\% = 25\% \tag{3.7.3}$$

$$\%\mathrm{C} = \frac{7.5\ \text{g C}}{10.0\ \text{g compound}} \times 100\% = 75\% \tag{3.7.4}$$

Example 3.7.1: Calculation of Percent Composition

Analysis of a 12.04-g sample of a liquid compound composed of carbon, hydrogen, and nitrogen showed it to contain 7.34 g C, 1.85 g H, and 2.85 g N. What is the percent composition of this compound?

Solution

To calculate percent composition, we divide the experimentally derived mass of each element by the overall mass of the compound, and then convert to a percentage:

$$\%\mathrm{C} = \frac{7.34\ \text{g C}}{12.04\ \text{g compound}} \times 100\% = 61.0\%$$

$$\%\mathrm{H} = \frac{1.85\ \text{g H}}{12.04\ \text{g compound}} \times 100\% = 15.4\%$$

$$\%\mathrm{N} = \frac{2.85\ \text{g N}}{12.04\ \text{g compound}} \times 100\% = 23.7\%$$

The analysis results indicate that the compound is 61.0% C, 15.4% H, and 23.7% N by mass.

? Exercise 3.7.1

A 24.81-g sample of a gaseous compound containing only carbon, oxygen, and chlorine is determined to contain 3.01 g C, 4.00 g O, and 17.81 g Cl. What is this compound's percent composition?

Answer

12.1% C, 16.1% O, 71.8% Cl

Determining Percent Composition from Formula Mass

Percent composition is also useful for evaluating the relative abundance of a given element in different compounds of known formulas. As one example, consider the common nitrogen-containing fertilizers ammonia (NH_3), ammonium nitrate (NH_4NO_3), and urea (CH_4N_2O). The element nitrogen is the active ingredient for agricultural purposes, so the mass percentage of nitrogen in the compound is a practical and economic concern for consumers choosing among these fertilizers. For these sorts of applications, the percent composition of a compound is easily derived from its formula mass and the atomic masses of its constituent elements. A molecule of NH_3 contains one N atom weighing 14.01 amu and three H atoms weighing a total of (3 × 1.008 amu) = 3.024 amu. The formula mass of ammonia is therefore (14.01 amu + 3.024 amu) = 17.03 amu, and its percent composition is:

$$\%\mathrm{N} = \frac{14.01\ \text{amu N}}{17.03\ \text{amu NH}_3} \times 100\% = 82.27\% \tag{3.7.5}$$

$$\%\mathrm{H} = \frac{3.024\ \text{amu N}}{17.03\ \text{amu NH}_3} \times 100\% = 17.76\% \tag{3.7.6}$$

This same approach may be taken considering a pair of molecules, a dozen molecules, or a mole of molecules, etc. The latter amount is most convenient and would simply involve the use of molar masses instead of atomic and formula masses, as demonstrated Example **3.7.2**. As long as we know the chemical formula of the substance in question, we can easily derive percent composition from the formula mass or molar mass.

✓ Example 3.7.2: Determining Percent Composition from a Molecular Formula

Aspirin is a compound with the molecular formula $C_9H_8O_4$. What is its percent composition?

Solution

To calculate the percent composition, we need to know the masses of C, H, and O in a known mass of $C_9H_8O_4$. It is convenient to consider 1 mol of $C_9H_8O_4$ and use its molar mass (180.159 g/mole, determined from the chemical formula) to calculate the percentages of each of its elements:

$$\%\mathrm{C} = \frac{9\ \text{mol C} \times \text{molar mass C}}{\text{molar mass } C_9H_{18}O_4} \times 100$$
$$= \frac{9 \times 12.01\ \text{g/mol}}{180.159\ \text{g/mol}} \times 100 = \frac{108.09\ \text{g/mol}}{180.159\ \text{g/mol}} \times 100$$
$$\%\mathrm{C} = 60.00\,\%\,\mathrm{C}$$

$$\%\mathrm{H} = \frac{8\ \text{mol H} \times \text{molar mass H}}{\text{molar mass } C_9H_{18}O_4} \times 100$$
$$= \frac{8 \times 1.008\ \text{g/mol}}{180.159\ \text{g/mol}} \times 100 = \frac{8.064\ \text{g/mol}}{180.159\ \text{g/mol}} \times 100$$
$$\%\mathrm{H} = 4.476\,\%\,\mathrm{H}$$

$$\%\mathrm{O} = \frac{4\ \text{mol O} \times \text{molar mass O}}{\text{molar mass } C_9H_{18}O_4} \times 100$$
$$= \frac{4 \times 16.00\ \text{g/mol}}{180.159\ \text{g/mol}} \times 100 = \frac{64.00\ \text{g/mol}}{180.159\ \text{g/mol}} \times 100$$
$$\%\mathrm{O} = 35.52\%$$

Note that these percentages sum to equal 100.00% when appropriately rounded.

? Exercise 3.7.2

To three significant digits, what is the mass percentage of iron in the compound Fe_2O_3?

Answer

69.9% Fe



Determination of Empirical Formulas

As previously mentioned, the most common approach to determining a compound's chemical formula is to first measure the masses of its constituent elements. However, we must keep in mind that chemical formulas represent the relative *numbers*, not masses, of atoms in the substance. Therefore, any experimentally derived data involving mass must be used to derive the corresponding numbers of atoms in the compound. To accomplish this, we can use molar masses to convert the mass of each element to a number of moles. We then consider the moles of each element relative to each other, converting these numbers into a whole-number ratio that can be used to derive the empirical formula of the substance. Consider a sample of compound determined to contain 1.71 g C and 0.287 g H. The corresponding numbers of atoms (in moles) are:

$$1.71\ \text{g C} \times \frac{1\ \text{mol C}}{12.01\ \text{g C}} = 0.142\ \text{mol C} \tag{3.7.7}$$

$$0.287\ \text{g H} \times \frac{1\ \text{mol H}}{1.008\ \text{g H}} = 0.284\ \text{mol H} \tag{3.7.8}$$

Thus, we can accurately represent this compound with the formula $C_{0.142}H_{0.284}$. Of course, per accepted convention, formulas contain whole-number subscripts, which can be achieved by dividing each subscript by the smaller subscript:

$$\text{C}_{\frac{0.142}{0.142}}\ \text{H}_{\frac{0.284}{0.142}}\ \text{or}\ \text{CH}_2 \tag{3.7.9}$$

(Recall that subscripts of "1" are not written, but rather assumed if no other number is present.)

The empirical formula for this compound is thus CH_2. This may or not be the compound's *molecular formula* as well; however, we would need additional information to make that determination (as discussed later in this section).

Consider as another example a sample of compound determined to contain 5.31 g Cl and 8.40 g O. Following the same approach yields a tentative empirical formula of:

$$\text{Cl}_{0.150}\text{O}_{0.525} = \text{Cl}_{\frac{0.150}{0.150}}\ \text{O}_{\frac{0.525}{0.150}} = \text{ClO}_{3.5} \tag{3.7.10}$$

In this case, dividing by the smallest subscript still leaves us with a decimal subscript in the empirical formula. To convert this into a whole number, we must multiply each of the subscripts by two, retaining the same atom ratio and yielding Cl_2O_7 as the final empirical formula.

Procedure

In summary, empirical formulas are derived from experimentally measured element masses by:

1. Deriving the number of moles of each element from its mass
2. Dividing each element's molar amount by the smallest molar amount to yield subscripts for a tentative empirical formula
3. Multiplying all coefficients by an integer, if necessary, to ensure that the smallest whole-number ratio of subscripts is obtained

Figure **3.7.1** outlines this procedure in flow chart fashion for a substance containing elements A and X.




Figure **3.7.1**: The empirical formula of a compound can be derived from the masses of all elements in the sample.

Example 3.7.3: Determining an Empirical Formula from Masses of Elements

A sample of the black mineral hematite (Figure **3.7.2**), an oxide of iron found in many iron ores, contains 34.97 g of iron and 15.03 g of oxygen. What is the empirical formula of hematite?



Figure **3.7.2**: Hematite is an iron oxide that is used in jewelry. (credit: Mauro Cateb)

Solution

For this problem, we are given the mass in grams of each element. Begin by finding the moles of each:

$$34.97\ \text{g Fe}\left(\frac{\text{mol Fe}}{55.85\ \text{g}}\right) = 0.6261\ \text{mol Fe}$$

$$15.03\ \text{g O}\left(\frac{\text{mol O}}{16.00\ \text{g}}\right) = 0.9394\ \text{mol O}$$

Next, derive the iron-to-oxygen molar ratio by dividing by the lesser number of moles:

$$\frac{0.6261}{0.6261} = 1.000\ \text{mol Fe}$$

$$\frac{0.9394}{0.6261} = 1.500\ \text{mol O}$$

The ratio is 1.000 mol of iron to 1.500 mol of oxygen ($Fe_1O_{1.5}$). Finally, multiply the ratio by two to get the smallest possible whole number subscripts while still maintaining the correct iron-to-oxygen ratio:

$$2(Fe_1O_{1.5}) = Fe_2O_3$$

The empirical formula is Fe_2O_3.

? Exercise 3.7.3

What is the empirical formula of a compound if a sample contains 0.130 g of nitrogen and 0.370 g of oxygen?

Answer

N_2O_5

***Video* 3.7.1**: *Additional worked examples illustrating the derivation of empirical formulas are presented in the brief video clip.*

Deriving Empirical Formulas from Percent Composition

Finally, with regard to deriving empirical formulas, consider instances in which a compound's percent composition is available rather than the absolute masses of the compound's constituent elements. In such cases, the percent composition can be used to calculate the masses of elements present in any convenient mass of compound; these masses can then be used to derive the empirical formula in the usual fashion.

✓ Example 3.7.4: Determining an Empirical Formula from Percent Composition

The bacterial fermentation of grain to produce ethanol forms a gas with a percent composition of 27.29% C and 72.71% O (Figure **3.7.3**). What is the empirical formula for this gas?



Figure **3.7.3**: An oxide of carbon is removed from these fermentation tanks through the large copper pipes at the top. (credit: "Dual Freq"/Wikimedia Commons)

Solution

Since the scale for percentages is 100, it is most convenient to calculate the mass of elements present in a sample weighing 100 g. The calculation is "most convenient" because, per the definition for percent composition, the mass of a given element in grams is numerically equivalent to the element's mass percentage. This numerical equivalence results from the definition of the "percentage" unit, whose name is derived from the Latin phrase *per centum* meaning "by the hundred." Considering this definition, the mass percentages provided may be more conveniently expressed as fractions:

$$27.29\,\%\,\mathrm{C} = \frac{27.29\ \mathrm{g\ C}}{100\ \mathrm{g\ compound}}$$

$$72.71\,\%\,\mathrm{O} = \frac{72.71\ \mathrm{g\ O}}{100\ \mathrm{g\ compound}}$$

The molar amounts of carbon and hydrogen in a 100-g sample are calculated by dividing each element's mass by its molar mass:

$$27.29\ \text{g C}\left(\frac{\text{mol C}}{12.01\ \text{g}}\right) = 2.272\ \text{mol C}$$

$$72.71\ \text{g O}\left(\frac{\text{mol O}}{16.00\ \text{g}}\right) = 4.544\ \text{mol O}$$

Coefficients for the tentative empirical formula are derived by dividing each molar amount by the lesser of the two:

$$\frac{2.272\ \text{mol C}}{2.272} = 1$$

$$\frac{4.544\ \text{mol O}}{2.272} = 2$$

Since the resulting ratio is one carbon to two oxygen atoms, the empirical formula is CO_2.

? Exercise 3.7.4

What is the empirical formula of a compound containing 40.0% C, 6.71% H, and 53.28% O?

Answer

CH_2O

Derivation of Molecular Formulas

Recall that empirical formulas are symbols representing the *relative* numbers of a compound's elements. Determining the *absolute* numbers of atoms that compose a single molecule of a covalent compound requires knowledge of both its empirical formula and its molecular mass or molar mass. These quantities may be determined experimentally by various measurement techniques. Molecular mass, for example, is often derived from the mass spectrum of the compound (see discussion of this technique in the previous chapter on atoms and molecules). Molar mass can be measured by a number of experimental methods, many of which will be introduced in later chapters of this text.

Molecular formulas are derived by comparing the compound's molecular or molar mass to its empirical formula mass. As the name suggests, an empirical formula mass is the sum of the average atomic masses of all the atoms represented in an empirical formula. If we know the molecular (or molar) mass of the substance, we can divide this by the empirical formula mass in order to identify the number of empirical formula units per molecule, which we designate as *n*:

$$\frac{\text{molecular or molar mass}\left(\text{amu or }\frac{\text{g}}{\text{mol}}\right)}{\text{empirical formula mass}\left(\text{amu or }\frac{\text{g}}{\text{mol}}\right)} = n\ \text{formula units/molecule} \tag{3.7.11}$$

The molecular formula is then obtained by multiplying each subscript in the empirical formula by *n*, as shown by the generic empirical formula A_xB_y:

Double subscripts: use braces to clarify

For example, consider a covalent compound whose empirical formula is determined to be CH_2O. The empirical formula mass for this compound is approximately 30 amu (the sum of 12 amu for one C atom, 2 amu for two H atoms, and 16 amu for one O atom). If the compound's molecular mass is determined to be 180 amu, this indicates that molecules of this compound contain six times the number of atoms represented in the empirical formula:

$$\frac{180\ \text{amu/molecule}}{30\ \frac{\text{amu}}{\text{formula unit}}} = 6\ \text{formula units/molecule} \tag{3.7.12}$$

Molecules of this compound are then represented by molecular formulas whose subscripts are six times greater than those in the empirical formula:

$$(CH_2O)_6 = C_6H_{12}O_6 \tag{3.7.13}$$

Note that this same approach may be used when the molar mass (g/mol) instead of the molecular mass (amu) is used. In this case, we are merely considering one mole of empirical formula units and molecules, as opposed to single units and molecules.

Example 3.7.5: Determination of the Molecular Formula for Nicotine

Nicotine, an alkaloid in the nightshade family of plants that is mainly responsible for the addictive nature of cigarettes, contains 74.02% C, 8.710% H, and 17.27% N. If 40.57 g of nicotine contains 0.2500 mol nicotine, what is the molecular formula?

Solution

Determining the molecular formula from the provided data will require comparison of the compound's empirical formula mass to its molar mass. As the first step, use the percent composition to derive the compound's empirical formula. Assuming a convenient, a 100-g sample of nicotine yields the following molar amounts of its elements:

$$(74.02\ \text{g C})\left(\frac{1\ \text{mol C}}{12.01\ \text{g C}}\right) = 6.163\ \text{mol C} \tag{3.7.14}$$

$$(8.710\ \text{g H})\left(\frac{1\ \text{mol H}}{1.01\ \text{g H}}\right) = 8.624\ \text{mol H} \tag{3.7.15}$$

$$(17.27\ \text{g N})\left(\frac{1\ \text{mol N}}{14.01\ \text{g N}}\right) = 1.233\ \text{mol N} \tag{3.7.16}$$

Next, we calculate the molar ratios of these elements relative to the least abundant element, **N**.

$$6.163\ \text{mol C} / 1.233\ \text{mol N} = 5$$

$$8.264\ \text{mol H} / 1.233\ \text{mol N} = 7$$

$$1.233\ \text{mol N} / 1.233\ \text{mol N} = 1$$

$$1.233/1.233 = 1.000\ \text{mol N}$$

$$6.163/1.233 = 4.998\ \text{mol C}$$

$$8.624/1.233 = 6.994\ \text{mol H}$$

The C-to-N and H-to-N molar ratios are adequately close to whole numbers, and so the empirical formula is C_5H_7N. The empirical formula mass for this compound is therefore 81.13 amu/formula unit, or 81.13 g/mol formula unit.

We calculate the molar mass for nicotine from the given mass and molar amount of compound:

$$\frac{40.57\ \text{g nicotine}}{0.2500\ \text{mol nicotine}} = \frac{162.3\ \text{g}}{\text{mol}}$$

Comparing the molar mass and empirical formula mass indicates that each nicotine molecule contains two formula units:

$$\frac{162.3\ \text{g/mol}}{81.13\ \frac{\text{g}}{\text{formula unit}}} = 2\ \text{formula units/molecule}$$

Thus, we can derive the molecular formula for nicotine from the empirical formula by multiplying each subscript by two:

$$(C_5H_7N)_2 = C_{10}H_{14}N_2$$

Exercise 3.7.5

What is the molecular formula of a compound with a percent composition of 49.47% C, 5.201% H, 28.84% N, and 16.48% O, and a molecular mass of 194.2 amu?

Answer

$C_8H_{10}N_4O_2$

Summary

The chemical identity of a substance is defined by the types and relative numbers of atoms composing its fundamental entities (molecules in the case of covalent compounds, ions in the case of ionic compounds). A compound's percent composition provides the mass percentage of each element in the compound, and it is often experimentally determined and used to derive the compound's empirical formula. The empirical formula mass of a covalent compound may be compared to the compound's molecular or molar mass to derive a molecular formula.

Key Equations

- $\%\mathrm{X} = \dfrac{\text{mass X}}{\text{mass compound}} \times 100\%$
- $\dfrac{\text{molecular or molar mass}\left(\text{amu or } \dfrac{\text{g}}{\text{mol}}\right)}{\text{empirical formula mass}\left(\text{amu or } \dfrac{\text{g}}{\text{mol}}\right)} = n \text{ formula units/molecule}$
- $(A_xB_y)_n = A_{nx}B_{ny}$

Glossary

percent composition

percentage by mass of the various elements in a compound

empirical formula mass

sum of average atomic masses for all atoms represented in an empirical formula

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

3.7: Percent Composition, Emperical Formulas, and Molecular Fromulas is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.2: Determining Empirical and Molecular Formulas** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

3.8: Determine Empirical Formula from Combustion Analysis

Learning Objectives

- Determine the empirical formula of a compound using combustion analysis.

When a compound containing carbon and hydrogen is subject to combustion with oxygen in a special combustion apparatus all the carbon is converted to CO_2 and the hydrogen to H_2O (Figure 3.8.1). The amount of carbon produced can be determined by measuring the amount of CO_2 produced. This is trapped by the sodium hydroxide, and thus we can monitor the mass of CO_2 produced by determining the increase in mass of the CO_2 trap. Likewise, we can determine the amount of H produced by the amount of H_2O trapped by the magnesium perchlorate.




Figure* 3.8.1*: *Combustion analysis apparatus*

One of the most common ways to determine the elemental composition of an unknown hydrocarbon is an analytical procedure called combustion analysis. A small, carefully weighed sample of an unknown compound that may contain carbon, hydrogen, nitrogen, and/or sulfur is burned in an oxygen atmosphere,Other elements, such as metals, can be determined by other methods. and the quantities of the resulting gaseous products (CO_2, H_2O, N_2, and SO_2, respectively) are determined by one of several possible methods. One procedure used in combustion analysis is outlined schematically in Figure 3.8.2 and a typical combustion analysis is illustrated in Examples 3.8.1 and 3.8.2.




Figure **3.8.2**: Steps for Obtaining an Empirical Formula from Combustion Analysis

Example 3.8.1: Combustion of Isopropyl Alcohol

What is the empirical formulate for isopropyl alcohol (which contains only C, H and O) if the combustion of a 0.255 grams isopropyl alcohol sample produces 0.561 grams of CO_2 and 0.306 grams of H_2O?

Solution

From this information quantitate the amount of C and H in the sample.

$$(0.561\ \cancel{g\ CO_2}) \left(\frac{1\ mol\ CO_2}{44.0\ \cancel{g\ CO_2}} \right) = 0.0128\ mol\ CO_2 \tag{3.8.1}$$

Since one mole of CO_2 is made up of one mole of C and two moles of O, if we have 0.0128 moles of CO_2 in our sample, then we know we have 0.0128 moles of C in the sample. How many grams of C is this?

$$(0.0128\ \cancel{mol\ C}) \left(\frac{12.011\ g\ C}{1\ \cancel{mol\ C}} \right) = 0.154\ g\ C \tag{3.8.2}$$

How about the hydrogen?

$$(0.306\ \cancel{g\ H_2O}) \left(\frac{1\ mol\ H_2O}{18.0\ \cancel{g\ H_2O}} \right) = 0.017\ mol\ H_2O \tag{3.8.3}$$

Since one mole of H_2O is made up of one mole of oxygen and ***two*** moles of hydrogen, if we have 0.017 moles of H_2O, then we have 2*(0.017) = 0.034 moles of hydrogen. Since hydrogen is about 1 gram/mole, we must have **0.034 grams of hydrogen** in our original sample.

When we add our carbon and hydrogen together we get:

0.154 grams (C) + 0.034 grams (H) = **0.188 grams**

But we know we combusted *0.255 grams* of isopropyl alcohol. The 'missing' mass must be from the oxygen atoms in the isopropyl alcohol:

0.255 grams - 0.188 grams = 0.067 grams oxygen

This much oxygen is how many moles?

$$(0.067\ \cancel{g\,O})\left(\frac{1\ mol\ O}{15.994\ \cancel{g\,O}}\right) = 0.0042\ mol\ O \tag{3.8.4}$$

Overall therefore, we have:

- 0.0128 moles Carbon
- 0.0340 moles Hydrogen
- 0.0042 moles Oxygen

Divide by the smallest molar amount to normalize:

- C = 3.05 atoms
- H = 8.1 atoms
- O = 1 atom

Within experimental error, the most likely empirical formula for propanol would be C_3H_8O

Example 3.8.2: Combustion of Naphalene

Naphthalene, the active ingredient in one variety of mothballs, is an organic compound that contains carbon and hydrogen only. Complete combustion of a 20.10 mg sample of naphthalene in oxygen yielded 69.00 mg of CO_2 and 11.30 mg of H_2O. Determine the empirical formula of naphthalene.

Given: mass of sample and mass of combustion products

Asked for: empirical formula

Strategy:

A. Use the masses and molar masses of the combustion products, CO_2 and H_2O, to calculate the masses of carbon and hydrogen present in the original sample of naphthalene.
B. Use those masses and the molar masses of the elements to calculate the empirical formula of naphthalene.

Solution:

A Upon combustion, 1 mol of CO**2** is produced for each mole of carbon atoms in the original sample. Similarly, 1 mol of H_2O is produced for every 2 mol of hydrogen atoms present in the sample. The masses of carbon and hydrogen in the original sample can be calculated from these ratios, the masses of CO_2 and H_2O, and their molar masses. Because the units of molar mass are grams per mole, we must first convert the masses from milligrams to grams:

$$mass\ of\ C = 69.00\,mg\,CO_2 \times \frac{1\,g}{1000\,mg} \times \frac{1\,mol\,CO_2}{44.010\,g\,CO_2} \times \frac{1\,mol C}{1\,mol\,CO_2} \times \frac{12.011\,g}{1\,mol\,C} \tag{3.8.5}$$

$$= 1.883 \times 10^{-2}\,g\,C \tag{3.8.6}$$

$$mass\ of\ H = 11.30\,mg\,H_2O \times \frac{1\,g}{1000\,mg} \times \frac{1\,mol\,H_2O}{18.015\,g\,H_2O} \times \frac{2\,mol H}{1\,mol\,H_2O} \times \frac{1.0079\,g}{1\,mol\,H} \tag{3.8.7}$$

$$= 1.264 \times 10^{-3}\,g\,H \tag{3.8.8}$$

B To obtain the relative numbers of atoms of both elements present, we need to calculate the number of moles of each and divide by the number of moles of the element present in the smallest amount:

$$moles\,C = 1.883 \times 10^{-2}\,g\,C \times \frac{1\,mol\,C}{12.011\,g\,C} = 1.568 \times 10^{-3}\,molC \tag{3.8.9}$$

$$moles\,H = 1.264 \times 10^{-3}\,g\,H \times \frac{1\,mol\,H}{1.0079\,g\,H} = 1.254 \times 10^{-3}\,molH \tag{3.8.10}$$

Dividing each number by the number of moles of the element present in the smaller amount gives

$$H: \frac{1.254 \times 10^{-3}}{1.254 \times 10^{-3}} = 1.000 \;\; C: \frac{1.568 \times 10^{-3}}{1.254 \times 10^{-3}} = 1.250 \tag{3.8.11}$$

Thus naphthalene contains a 1.25:1 ratio of moles of carbon to moles of hydrogen: $C_{1.25}H_{1.0}$. Because the ratios of the elements in the empirical formula must be expressed as small whole numbers, multiply both subscripts by 4, which gives C_5H_4 as the empirical formula of naphthalene. In fact, the molecular formula of naphthalene is $C_{10}H_8$, which is consistent with our results.

? Exercise 3.8.1

a. Xylene, an organic compound that is a major component of many gasoline blends, contains carbon and hydrogen only. Complete combustion of a 17.12 mg sample of xylene in oxygen yielded 56.77 mg of CO_2 and 14.53 mg of H_2O. Determine the empirical formula of xylene.

b. The empirical formula of benzene is CH (its molecular formula is C_6H_6). If 10.00 mg of benzene is subjected to combustion analysis, what mass of CO_2 and H_2O will be produced?

Answer a

The empirical formula is C_4H_5. (The molecular formula of xylene is actually C_8H_{10}.)

Answer b

33.81 mg of CO_2; 6.92 mg of H_2O

Contributors and Attributions

- Mike Blaber (Florida State University)
- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).


3.8: Determine Empirical Formula from Combustion Analysis is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.6: The Periodic Table** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.


3.9: End of Chapter Problems

1. Explain why the symbol for an atom of the element oxygen and the formula for a molecule of oxygen differ.
2. Explain why the symbol for the element sulfur and the formula for a molecule of sulfur differ.
3. Write the molecular and empirical formulas of the following compounds:

a.


Figure A shows a carbon atom that forms two, separate double bonds with two oxygen atoms.


b.


Figure B shows a hydrogen atom which forms a single bond with a carbon atom. The carbon atom forms a triple bond with another carbon atom. The second carbon atom forms a single bond with a hydrogen atom.

c.


Figure C shows a carbon atom forming a double bond with another carbon atom. Each carbon atom forms a single bond with two hydrogen atoms.

d.



Figure D shows a sulfur atom forming single bonds with four oxygen atoms. Two of the oxygen atoms form a single bond with a hydrogen atom.

Answer


a. molecular CO_2, empirical CO_2; b. molecular C_2H_2, empirical CH; c. molecular C_2H_4, empirical CH_2; d. molecular H_2SO_4, empirical H_2SO_4

4. Write the molecular and empirical formulas of the following compounds:


a.


Figure A shows a structural diagram of four carbon atoms bonded together into a chain. The two carbon atoms on the left form a double bond with each other. All of the remaining carbon atoms form single bonds with each other. The leftmost carbon also forms single bonds with two hydrogen. The second carbon in the chain forms a single bond with a hydrogen atom. The third carbon in the chain forms a single bond with two hydrogen atoms each. The rightmost carbon forms a single bond with three hydrogen atoms each.


b.


Figure B shows a structural diagram of a molecule that has a chain of four carbon atoms. The leftmost carbon atom forms a single bond with three hydrogen atoms each and single bond with the second carbon atom. The second carbon atom forms a triple bond with the third carbon atom. The third carbon atom forms a single bond to the fourth carbon atom. The fourth carbon atom forms a single bond to three hydrogen atoms each.

c.


Figure C shows a structural diagram of two silicon atoms are bonded together with a single bond. Each of the silicon atoms form single bonds to two chlorine atoms each and one hydrogen atom.

d.


Figure D shows a structural diagram of a phosphorus atom that forms a single bond to four oxygen atoms each. Three of the oxygen atoms each have a single bond to a hydrogen atom.

5. Determine the empirical formulas for the following compounds:

a. caffeine, $C_8H_{10}N_4O_2$
b. fructose, $C_{12}H_{22}O_{11}$
c. hydrogen peroxide, H_2O_2
d. glucose, $C_6H_{12}O_6$
e. ascorbic acid (vitamin C), $C_6H_8O_6$

Answer

a. $C_4H_5N_2O$; b. $C_{12}H_{22}O_{11}$; c. HO; d. CH_2O; e. $C_3H_4O_3$


6. Determine the empirical formulas for the following compounds:

a. acetic acid, $C_2H_4O_2$
b. citric acid, $C_6H_8O_7$


c. hydrazine, N_2H_4
d. nicotine, $C_{10}H_{14}N_2$
e. butane, C_4H_{10}

7. Write the empirical formulas for the following compounds:

a.


Figure A shows a structural diagram of two carbon atoms that form a single bond with each other. The left carbon atom forms single bonds with hydrogen atoms each. The right carbon forms a double bond to an oxygen atom. The right carbon also forms a single bonded to another oxygen atom. This oxygen atom also forms a single bond to a hydrogen atom.

b.


Figure B shows a structural diagram containing a leftmost carbon that forms single bonds to three hydrogen atoms each. This leftmost carbon also forms a single bond to a second carbon atom. The second carbon atom forms a double bond with an oxygen atom. The second carbon also forms a single bond to a second oxygen atom. This oxygen atom forms a single bond to a third carbon atom. This third carbon atom forms single bonds with two hydrogen atoms each as well as a single bond with another carbon atom. The rightmost carbon atom forms a single bond with three hydrogen atoms each.

Answer

a. CH_2O; b. C_2H_4O

8. Open the Build a Molecule simulation and select the “Larger Molecules” tab. Select an appropriate atoms “Kit” to build a molecule with two carbon and six hydrogen atoms. Drag atoms into the space above the “Kit” to make a molecule. A name will appear when you have made an actual molecule that exists (even if it is not the one you want). You can use the scissors tool to separate atoms if you would like to change the connections. Click on “3D” to see the molecule, and look at both the space-filling and ball-and-stick possibilities.


a. Draw the structural formula of this molecule and state its name.
b. Can you arrange these atoms in any way to make a different compound?

9. Use the Build a Molecule simulation to repeat Exercise, but build a molecule with two carbons, six hydrogens, and one oxygen.


a. Draw the structural formula of this molecule and state its name.
b. Can you arrange these atoms to make a different molecule? If so, draw its structural formula and state its name.
c. How are the molecules drawn in (a) and (b) the same? How do they differ? What are they called (the type of relationship between these molecules, not their names).

Answer

a. ethanol


A Lewis Structure is shown. An oxygen atom is bonded to a hydrogen atom and a carbon atom. The carbon atom is bonded to two hydrogen atoms and another carbon atom. That carbon atom is bonded to three more hydrogen atoms. There are a total of two carbon atoms, six hydrogen atoms, and one oxygen atoms.

b. methoxymethane, more commonly known as dimethyl ether


A Lewis Structure is shown. An oxygen atom is bonded to two carbon atoms. Each carbon atom is bonded to three different hydrogen atoms. There are a total of two carbon atoms, six hydrogen atoms, and one oxygen atom.

c. These molecules have the same chemical composition (types and number of atoms) but different chemical structures. They are structural isomers.1

10. Use the Build a Molecule simulation to repeat Exercise, but build a molecule with three carbons, seven hydrogens, and one chlorine.

a. Draw the structural formula of this molecule and state its name.
b. Can you arrange these atoms to make a different molecule? If so, draw its structural formula and state its name.
c. How are the molecules drawn in (a) and (b) the same? How do they differ? What are they called (the type of relationship between these molecules, not their names)?

11. Using the periodic table, predict whether the following chlorides are ionic or covalent: KCl, NCl_3, ICl, $MgCl_2$, PCl_5, and CCl_4.

Answer

Ionic: KCl, $MgCl_2$; Covalent: NCl_3, ICl, PCl_5, $CCl_4$15. (a) CaS; (b) $(NH_4)_2CO_3$; (c) $AlBr_3$; (d) Na_2HPO_4; (e) $Mg_3 (PO_4)_2$

12. Using the periodic table, predict whether the following chlorides are ionic or covalent: $SiCl_4$, PCl_3, $CaCl_2$, CsCl, $CuCl_2$, and $CrCl_3$.
13. For each of the following compounds, state whether it is ionic or covalent. If it is ionic, write the symbols for the ions involved:

a. NF_3
b. BaO,
c. $(NH_4)_2CO_3$
d. $Sr(H_2PO_4)_2$
e. IBr
f. Na_2O

Answer

a. covalent; b. ionic, Ba^{2+}, O^{2-}; c. ionic, $\mathbf{NH_4^+}$, $\mathbf{CO_3^{2-}}$; d. ionic, Sr^{2+}, $\mathbf{H_2PO_4^-}$; e. covalent; f. ionic, Na^+, O^{2-}

14. For each of the following compounds, state whether it is ionic or covalent, and if it is ionic, write the symbols for the ions involved:

a. $KClO_4$
b. $MgC_2H_3O_2$
c. H_2S
d. Ag_2S
e. N_2Cl_4
f. $Co(NO_3)_2$

15. For each of the following pairs of ions, write the symbol for the formula of the compound they will form:

a. Ca^{2+}, S^{2-}
b. $\mathbf{NH_4^+}$, $\mathbf{SO_4^{2-}}$
c. Al^{3+}, Br^-
d. Na^+, $\mathbf{HPO_4^{2-}}$
e. Mg^{2+}, $\mathbf{PO_4^{3-}}$

16. For each of the following pairs of ions, write the symbol for the formula of the compound they will form:

a. K^+, O^{2-}
b. $\mathbf{NH_4^+}$, $\mathbf{PO_4^{3-}}$
c. Al^{3+}, O^{2-}
d. Na^+, $\mathbf{CO_3^{2-}}$
e. Ba^{2+}, $\mathbf{PO_4^{3-}}$

17. Name the following compounds:

a. CsCl
b. BaO
c. K_2S
d. $BeCl_2$
e. HBr
f. AlF_3

Answer

a. cesium chloride; b. barium oxide; c. potassium sulfide; d. beryllium chloride; e. hydrogen bromide; f. aluminum fluoride

18. Name the following compounds:

19. NaF
20. Rb_2O
21. BCl_3
22. H_2Se
23. P_4O_6
24. ICl_3

19. Write the formulas of the following compounds:

a. rubidium bromide
b. magnesium selenide
c. sodium oxide
d. calcium chloride
e. hydrogen fluoride
f. gallium phosphide
g. aluminum bromide
h. ammonium sulfate

Answer

a. RbBr; b. MgSe; c. Na_2O; d. $CaCl_2$; e. HF; f. GaP; g. $AlBr_3$; h. $(NH_4)_2SO_4$

20. Write the formulas of the following compounds:

a. lithium carbonate
b. sodium perchlorate
c. barium hydroxide
d. ammonium carbonate
e. sulfuric acid
f. calcium acetate
g. magnesium phosphate
h. sodium sulfite

21. Write the formulas of the following compounds:

a. chlorine dioxide
b. dinitrogen tetraoxide
c. potassium phosphide
d. silver(I) sulfide
e. aluminum nitride
f. silicon dioxide

Answer

a. ClO_2; b. N_2O_4; c. K_3P; d. Ag_2S; e. AlN; f. SiO_2

22. Write the formulas of the following compounds:

a. barium chloride
b. magnesium nitride
c. sulfur dioxide
d. nitrogen trichloride
e. dinitrogen trioxide
f. tin(IV) chloride

23. Each of the following compounds contains a metal that can exhibit more than one ionic charge. Name these compounds:

a. Cr_2O_3

b. $FeCl_2$
c. CrO_3
d. $TiCl_4$
e. CoO
f. MoS_2

Answer

a. chromium(III) oxide; b. iron(II) chloride; c. chromium(VI) oxide; d. titanium(IV) chloride; e. cobalt(II) oxide; f. molybdenum(IV) sulfide

24. Each of the following compounds contains a metal that can exhibit more than one ionic charge. Name these compounds:

a. $NiCO_3$
b. MoO_3
c. $Co(NO_3)_2$
d. V_2O_5
e. MnO_2
f. Fe_2O_3

25. The following ionic compounds are found in common household products. Write the formulas for each compound:

a. potassium phosphate
b. copper(II) sulfate
c. calcium chloride
d. titanium dioxide
e. ammonium nitrate
f. sodium bisulfate (the common name for sodium hydrogen sulfate)

Answer

a. K_3PO_4; b. $CuSO_4$; c. $CaCl_2$; d. TiO_2; e. NH_4NO_3; f. $NaHSO_4$

26. The following ionic compounds are found in common household products. Name each of the compounds:

a. $Ca(H_2PO_4)_2$
b. $FeSO_4$
c. $CaCO_3$
d. MgO
e. $NaNO_2$
f. KI

27. What are the IUPAC names of the following compounds?

a. manganese dioxide
b. mercurous chloride (Hg_2Cl_2)
c. ferric nitrate [$Fe(NO_3)_3$]
d. titanium tetrachloride
e. cupric bromide ($CuBr_2$)

Answer

a. manganese(IV) oxide; b. mercury(I) chloride; c. iron(III) nitrate; d. titanium(IV) chloride; e. copper(II) bromide

28. Find the amount of moles contained in each specimen.

a. 7.87 kg H_2O_2
b. 2.34 kg NaCl
c. 12.5 g C_2H_6O

d. 85.72 g NH_3

Answer

A. First, determine the units that are given for each sample. In order to convert these measurements to moles, each sample should first be written in grams. Two of the given samples are measured in kilograms. Use the following conversion factor to convert kilograms to grams, with x representing the given mass:

$$x\,kg \cdot \frac{1000\,g}{1\,kg} \tag{3.9.1}$$

B. Next, find the atomic masses of all the atoms in each compound by using the Periodic Table. Then, add these atomic masses together for each compound. The resulting value will be the number of grams of each sample that make up one mole.

C. Convert the mass in grams of each sample to moles by multiplying it by the following conversion factor, called the molar mass, with *x* representing the mass of the given specimen and y representing the calculated atomic mass found in step B:

$$x\,g \cdot \frac{1\,mole}{y\,g} \tag{3.9.2}$$

A Numbers 1 and 2 first need to be converted into grams.

a.

$$7.87\,kg\,H_2O_2 \cdot \frac{1000\,g}{1\,kg} = 7,870\,g\,H_2O_2 \tag{3.9.3}$$

b.

$$2.34\,kg\,NaCl \cdot \frac{1000\,g}{1\,kg} = 2,340\,g\,NaCl \tag{3.9.4}$$

B The following are the calculated molar masses of each of the given compounds. The atomic mass of each element has been rounded to 4 significant figures in these calculations.

a. H_2O_2:

$$2\,(1.008\,g\,H) + 2\,(16.00\,g\,O) = \frac{34.02\,g}{1\,mole}\,H_2O_2 \tag{3.9.5}$$

b. NaCl:

$$(22.99\,g\,Na) + (35.45\,g\,Cl) = \frac{58.44\,g}{1\,mole}\,NaCl \tag{3.9.6}$$

c. C_2H_6O:

$$2\,(12.01\,g\,C) + 6\,(1.008\,g\,H) + (16.00\,g\,O) = \frac{46.07\,g}{1\,mole}\,C_2H_6O \tag{3.9.7}$$

d. NH_3:

$$(14.01\,g\,N) + 3\,(1.008\,g\,H) = \frac{17.03\,g}{1\,mole}\,NH_3 \tag{3.9.8}$$

C The number of moles in each specimen can now be calculated by multiplying the mass in grams of each sample by its molarity.

a.

$$7,870\,g\,H_2O_2 \cdot \frac{1\,mole\,H_2O_2}{34.02\,g\,H_2O_2} = 231\,moles\,H_2O_2 \tag{3.9.9}$$

b.

$$2,340\,g\,NaCl \cdot \frac{1\,mole\,NaCl}{58.44\,g\,NaCl} = 40.0\,moles\,NaCl \tag{3.9.10}$$

c.

$$12.5\,g\,C_2H_6O \cdot \frac{1\,mole\,C_2H_6O}{46.07\,g\,C_2H_6O} = 0.271\,moles\,C_2H_6O \tag{3.9.11}$$

d.

$$85.72\,g\,NH_3 \cdot \frac{1\,mole\,NH_3}{17.03\,g\,NH_3} = 5.033\,moles\,NH_3 \tag{3.9.12}$$

29. Calculate the number of moles in each of the following examples.

a. 402.5 mg of NO_2
b. 2.7 kg of H_2O
c. 323 g of CBr_4
d. 2.9 kg of CaO

Answer

a) First, calculate the molar mass of NO_2.

14.007g/mol N + 2 (15.999 g/mol O) = ***46.0055 g/mol***

Now, convert the sample from mg to g.

402.5 ~~mg~~ NO_2	1 g	**0.4025 g NO_2**
	1000 ~~mg~~	

Finally, use the molar mass to determine how many moles your sample size contains.

0.4025 g NO_2	1 mol	**0.0087 moles of NO_2**
	46.0055 g	

This gives us the final answer, **0.0087 moles of NO_2**.

From this, we can deduce that:

$$\text{Moles of substance} = \text{Mass of substance (g)} Molar mass of substance \tag{3.9.13}$$

b) 150 moles of H_2O

c) 0.974 moles of CBr_4

d) 52 moles of CaO

30. For each substance, convert the given molecules to mass in grams:

a. 3.2 x 10^{24} Cl_2 molecules
b. 8.25 x 10^{18} CH_2O molecules
c. 1 carbon dioxide molecule

Answer

Step 1: Convert the given molecules to moles by dividing by Avogadro's number.

Step 2: Multiply the number of moles by the Molar Mass of the substance to determine the grams.

Step 3: Through correct Dimensional Analysis, the molecules and moles will cancel to leave grams.

$$\frac{molecules}{Avogadro's} \rightarrow moles \rightarrow moles \cdot MM \rightarrow grams \tag{3.9.14}$$

Helpful Hints:

Avogadro's number: 6.022 x 10^{23} mol of a substance Molar mass (MM): the weight of a substance in the units g/mol, found by adding the atomic masses of each element.

- Example: MM of H_2O --> H(1.008 x 2) + O(15.999)= 18 g/mol

c) 7.31 x 10^{25} grams

Solution

a) 3.8 x 10^{51} grams

b) 4.11 x 10^{45} grams

31. Write the empirical formula and molecular formula for the compound with the given percent composition and molecular weight.

- 40.0% Carbon
- 6.70% Hydrogen
- 53.3% Oxygen

Molecular Weight ≈ 240 g/mol

Answer

Calculate amount of grams of each element we have. Convert amount of grams into number of moles of each element. Obtain molecular formula. Find the common factor among the number of atoms each elements has, then obtain the empirical formula.

Solution:

1. Calculate amount of grams in each element:

$$Carbon = .40 \cdot 240g = 96g$$

$$Hydrogen = .067 \cdot 240g = 16.1g$$

$$Oxygen = .533 \cdot 240g = 127.9g$$

2. Convert amount of grams into number of moles of each elements:

Carbon-

$$96g \cdot \frac{1mol}{12.001g} = 8.00mols$$

Hydrogen-

$$16.1g \cdot \frac{1mol}{1.008g} = 16.0mols$$

Oxygen-

$$127.9g \cdot \frac{1mol}{16.0g} = 8mols$$

3. Obtain molecular formula:

$$C_8H_{16}O_8 \tag{3.9.15}$$

4. Find common factor and obtain empirical formula:

Common factor is 8

Empirical formula is

$$CH_2O \tag{3.9.16}$$

32. For several compounds both the molar mass and and empirical formulas are listed. What is the molecular formula for each compound.

a. C_2OH_4, 88 g/mol
b. C_2H_8N, 46 g/mol
c. NH_2, 32 g/mol

Answer

Find the empirical formula mass of the compound B. Determine the ratio between the empirical formula mass and the molar mass of the compound C.Multiply the empirical formula by the factor found in part B.

Solution:

C_2OH_4, 88 g/mol

A.

Carbon: 2(12.0g/mol)

Oxygen: 1(16.0g/mol)

Hydrogen: 4(1.0g/mol)

=44.0 g/mol

B.

$$\frac{88.0g/mol}{44.0g/mol} = 2 \tag{3.9.17}$$

C.

2(C_2OH_4)= $C_4O_2H_8$

C_2H_8N, 46 g/mol

A.

Carbon: 2(12.0g/mol)

Hydrogen: 8(1.0g/mol)

Nitrogen: 1(14.0g/mol)

=46.0 g/mol

B.

$$\frac{46.0g/mol}{46.0g/mol} = 1.0 \tag{3.9.18}$$

C.

1(C_2H_8N)=C_2H_8N

NH_2

A.

Nitrogen: 1(14.0g/mol)

Hydrogen: 2(1.0g/mol)

=16.0g/mol

B.

$$\frac{32.0g/mol}{16.0g/mol} = 2 \tag{3.9.19}$$

C.

$2(NH_2)=N_2H_4$

33. After the combustion of a hydrocarbon, we find 66.02g of CO_2 and 27.02g of H_2O. What is the empirical formula of this hydrocarbon?

Answer

66.02 x 1 mol/ 44.0 g= 1.500 mol CO2= 1.5 mol C

27.02 x 1 mol/ 18g = 1.501 mol H20= 3 mol H

C1.5 H3= C3 H6

You start by taking both, divide by the molar mass, use the mol ratio of the compound and multiple to get rid of decimals.

Additional Question

Additional Questions 1. For the following molecules; write the chemical formula, determine how many atoms are present in one molecule, determine the molecular weight, determine the number of moles in exactly 1 gram, and the number of moles in exactly 10-6 gram. a. carbon dioxide b. iron (II) chloride c. dinitrogen pentoxide d. iron (III) sulfate 2. Name the following compounds, determine the molecular weight, determine the percent composition, and determine how many moles in 8.35 grams of the compound. a. KI b. CaF2 c. Cu2SO4 d. N2O e. LiOH 3. Give the chemical formula (or atomic symbol), molecular (or atomic) weight, and charge for the following ions: a. sulfate b. sulfite c. nitrate d. chloride e. nitride f. acetate g. carbonate 4. Calculate the number of moles in: a. 20.1797 g of Ne b. 45.3594 g of Ne c. 0.198669 g of Ne 5. Calculate the mass of: a. 2.00 mole of Fe b. 4.362 x 10-5 mol of Fe c. 4.362 x 10-5 mol of Li

---

3.9: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

4: Introduction to Solutions

4.1: Introduction to solutions
4.2: Solution Concentration
4.3: Solution Dilution
4.4: Hydration of Ions in Aqueous Solutions
4.5: Solubility of Ionic Compounds
4.6: Introduction to Acids and Bases
4.7: End of Chapter Problems

4: Introduction to Solutions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

4.1: Introduction to solutions

Learning Objectives

- Describe the fundamental properties of solutions

In the previous chapter, we focused on the composition of substances: samples of matter that contain only one type of element or compound. However, mixtures—samples of matter containing two or more substances physically combined—are more commonly encountered in nature than are pure substances. Similar to a pure substance, the relative composition of a mixture plays an important role in determining its properties. The relative amount of oxygen in a planet's atmosphere determines its ability to sustain aerobic life. The relative amounts of iron, carbon, nickel, and other elements in steel (a mixture known as an "alloy") determine its physical strength and resistance to corrosion. The relative amount of the active ingredient in a medicine determines its effectiveness in achieving the desired pharmacological effect. The relative amount of sugar in a beverage determines its sweetness (Figure **4.1.1**). In this section, we will describe one of the most common ways in which the relative compositions of mixtures may be quantified.



Figure **4.1.1**: Sugar is one of many components in the complex mixture known as coffee. The amount of sugar in a given amount of coffee is an important determinant of the beverage's sweetness. (credit: Jane Whitney)

Solutions are homogeneous mixture, meaning that the composition of the mixture (and therefore its properties) is uniform throughout its entire volume. Solutions occur frequently in nature and have also been implemented in many forms of manmade technology. We will explore a more thorough treatment of solution properties in the chapter on solutions and colloids, but here we will introduce some of the basic properties of solutions.

The relative amount of a given solution component is known as its concentration. Often, though not always, a solution contains one component with a concentration that is significantly greater than that of all other components. This component is called the solvent and may be viewed as the medium in which the other components are dispersed, or dissolved. Solutions in which water is the solvent are, of course, very common on our planet. A solution in which water is the solvent is called an aqueous solution.

A solute is a component of a solution that is typically present at a much lower concentration than the solvent. Solute concentrations are often described with qualitative terms such as dilute (of relatively low concentration) and concentrated (of relatively high concentration).Concentrations may be quantitatively assessed using a wide variety of measurement units, each convenient for particular applications. In this chapter we will introduce the Molarity (*M*) Molarity (*M*) is a useful concentration unit for many applications in chemistry.

Glossary

aqueous solution

solution for which water is the solvent

concentrated

qualitative term for a solution containing solute at a relatively high concentration

concentration

quantitative measure of the relative amounts of solute and solvent present in a solution

dilute

qualitative term for a solution containing solute at a relatively low concentration

Dissolved

describes the process by which solute components are dispersed in a solvent

solute

solution component present in a concentration less than that of the solvent

solvent

solution component present in a concentration that is higher relative to other components

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

4.1: Introduction to solutions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.3: Molarity** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

4.2: Solution Concentration

Learning Objectives

- To describe the concentrations of solutions quantitatively

Many people have a qualitative idea of what is meant by *concentration*. Anyone who has made instant coffee or lemonade knows that too much powder gives a strongly flavored, highly concentrated drink, whereas too little results in a dilute solution that may be hard to distinguish from water. In chemistry, the concentration of a solution is the quantity of a **solute** that is contained in a particular quantity of **solvent** or solution. Knowing the concentration of solutes is important in controlling the stoichiometry of reactants for solution reactions. Chemists use many different methods to define concentrations. In this section, we will focus on a unit of concentration called molarity which is a useful unit for many applications in chemistry. In addition, concentrations are often reported on a mass-to-mass (m/m) basis or on a mass-to-volume (m/v) basis, particularly in clinical laboratories and engineering applications. A concentration expressed on an m/m basis is equal to the number of grams of solute per gram of solution; a concentration on an m/v basis is the number of grams of solute per milliliter of solution. Each measurement can be expressed as a percentage by multiplying the ratio by 100; the result is reported as percent m/m or percent m/v. The concentrations of very dilute solutions are often expressed in *parts per million* (*ppm*), which is grams of solute per 10^6 g of solution, or in *parts per billion* (*ppb*), which is grams of solute per 10^9 g of solution. For aqueous solutions at 20°C, 1 ppm corresponds to 1 µg per milliliter, and 1 ppb corresponds to 1 ng per milliliter. These concentrations and their units are summarized in Table **4.2.1** and will be discussed in detail in chapter 13.

Table **4.2.1**: Common Units of Concentration

Concentration	Units
m/m	g of solute/g of solution
m/v	g of solute/mL of solution
ppm	g of solute/10^6 g of solution
	µg/mL
ppb	g of solute/10^9 g of solution
	ng/mL

Molarity

The most common unit of concentration is *molarity (M)*. It is defined as the number of moles of solute present in exactly 1 L of solution. It is, equivalently, the number of millimoles of solute present in exactly 1 mL of solution:

$$M = \frac{\text{mol solute}}{\text{L solution}} \tag{4.2.1}$$

Example 4.2.1: Calculating Molar Concentrations

A 355-mL soft drink sample contains 0.133 mol of sucrose (table sugar). What is the molar concentration of sucrose in the beverage?

Solution

Since the molar amount of solute and the volume of solution are both given, the molarity can be calculated using the definition of molarity. Per this definition, the solution volume must be converted from mL to L:

$$M = \frac{mol\ solute}{L\ solution}$$
$$= \frac{0.133\ mol}{355\ mL \times \frac{1\ L}{1000\ mL}}$$
$$= 0.375\ M$$

Exercise 4.2.1

A teaspoon of table sugar contains about 0.01 mol sucrose. What is the molarity of sucrose if a teaspoon of sugar has been dissolved in a cup of tea with a volume of 200 mL?

Answer

0.05 M

Example 4.2.2: Deriving Moles and Volumes from Molar Concentrations

How much sugar (mol) is contained in a modest sip (~10 mL) of the soft drink from Example **4.2.1**?

Solution

In this case, we can rearrange the definition of molarity to isolate the quantity sought, moles of sugar. We then substitute the value for molarity that we derived in Example 3.4.2, 0.375 *M*:

$$M = \frac{\text{mol solute}}{\text{L solution}}$$

Multiple \label

Exercise 4.2.2

What volume (mL) of the sweetened tea described in Example **4.2.1** contains the same amount of sugar (mol) as 10 mL of the soft drink in this example?

Answer

80 mL

Example 4.2.3: Calculating Molar Concentrations from the Mass of Solute

Distilled white vinegar (Figure **4.2.1**) is a solution of acetic acid, CH_3CO_2H, in water. A 0.500-L vinegar solution contains 25.2 g of acetic acid. What is the concentration of the acetic acid solution in units of molarity?



Figure **4.2.1**: Distilled white vinegar is a solution of acetic acid in water.

Solution

As in previous examples, the definition of molarity is the primary equation used to calculate the quantity sought. In this case, the mass of solute is provided instead of its molar amount, so we must use the solute's molar mass to obtain the amount of solute in moles:

$$M = \frac{\text{mol solute}}{\text{L solution}} = \frac{25.2\ \text{g}\ \text{CH}_3\text{CO}_2\text{H} \times \frac{1\ \text{mol}\ \text{CH}_3\text{CO}_2\text{H}}{60.052\ \text{g}\ \text{CH}_3\text{CO}_2\text{H}}}{0.500\ \text{L solution}} = 0.839\ M$$

$$M = \frac{0.839\ \text{mol solute}}{1.00\ \text{L solution}}$$

Exercise 4.2.3

Calculate the molarity of 6.52 g of $CoCl_2$ (128.9 g/mol) dissolved in an aqueous solution with a total volume of 75.0 mL.

Answer

0.674 M

Example 4.2.4: Determining the Mass of Solute in a Given Volume of Solution

How many grams of NaCl are contained in 0.250 L of a 5.30-*M* solution?

Solution

The volume and molarity of the solution are specified, so the amount (mol) of solute is easily computed as demonstrated in Example **4.2.3**:

$$M = \frac{\text{mol solute}}{\text{L solution}} \tag{4.2.2}$$

$$\text{mol solute} = M \times \text{L solution} \tag{4.2.3}$$

$$\text{mol solute} = 5.30\ \frac{\text{mol NaCl}}{\text{L}} \times 0.250\ \text{L} = 1.325\ \text{mol NaCl} \tag{4.2.4}$$

Finally, this molar amount is used to derive the mass of NaCl:

$$1.325\ \text{mol NaCl} \times \frac{58.44\ \text{g NaCl}}{\text{mol NaCl}} = 77.4\ \text{g NaCl} \tag{4.2.5}$$

Exercise 4.2.4

How many grams of $CaCl_2$ (110.98 g/mol) are contained in 250.0 mL of a 0.200-M solution of calcium chloride?

Answer

5.55 g $CaCl_2$

When performing calculations stepwise, as in Example **4.2.3**, it is important to refrain from rounding any intermediate calculation results, which can lead to rounding errors in the final result. In Example **4.2.4**, the molar amount of NaCl computed in the first step, 1.325 mol, would be properly rounded to 1.32 mol if it were to be reported; however, although the last digit (5) is not significant, it must be retained as a guard digit in the intermediate calculation. If we had not retained this guard digit, the final calculation for the mass of NaCl would have been 77.1 g, a difference of 0.3 g.

In addition to retaining a guard digit for intermediate calculations, we can also avoid rounding errors by performing computations in a single step (Example **4.2.5**). This eliminates intermediate steps so that only the final result is rounded.

Example 4.2.5: Determining the Volume of Solution

In Example **4.2.3**, we found the typical concentration of vinegar to be 0.839 *M*. What volume of vinegar contains 75.6 g of acetic acid?

Solution

First, use the molar mass to calculate moles of acetic acid from the given mass:

$$\text{g solute} \times \frac{\text{mol solute}}{\text{g solute}} = \text{mol solute} \tag{4.2.6}$$

Then, use the molarity of the solution to calculate the volume of solution containing this molar amount of solute:

$$\text{mol solute} \times \frac{\text{L solution}}{\text{mol solute}} = \text{L solution} \tag{4.2.7}$$

Combining these two steps into one yields:

$$\text{g solute} \times \frac{\text{mol solute}}{\text{g solute}} \times \frac{\text{L solution}}{\text{mol solute}} = \text{L solution} \tag{4.2.8}$$

$$75.6\ \text{g}\ CH_3CO_2H \left(\frac{\text{mol}\ CH_3CO_2H}{60.05\ \text{g}}\right)\left(\frac{\text{L solution}}{0.839\ \text{mol}\ CH_3CO_2H}\right) = 1.50\ \text{L solution} \tag{4.2.9}$$

Exercise 4.2.5:

What volume of a 1.50-M KBr solution contains 66.0 g KBr?

Answer

0.370 L

The Preparation of Solutions

To prepare a solution that contains a specified concentration of a substance, it is necessary to dissolve the desired number of moles of solute in enough solvent to give the desired final volume of solution. Figure **4.2.1** illustrates this procedure for a solution of cobalt(II) chloride dihydrate in ethanol. Note that the volume of the *solvent* is not specified. Because the solute occupies space in the solution, the volume of the solvent needed is almost always *less* than the desired volume of solution. For example, if the desired volume were 1.00 L, it would be incorrect to add 1.00 L of water to 342 g of sucrose because that would produce more than 1.00 L of solution. As shown in Figure **4.2.2**, for some substances this effect can be significant, especially for concentrated solutions.




Figure **4.2.2**: Preparation of 250 mL of a Solution of $(NH_4)_2Cr_2O_7$ in Water. The solute occupies space in the solution, so less than 250 mL of water are needed to make 250 mL of solution.

Example 4.2.6

The solution contains 10.0 g of cobalt(II) chloride dihydrate, $CoCl_2$•$2H_2O$, in enough ethanol to make exactly 500 mL of solution. What is the molar concentration of $\mathbf{CoCl_2 \cdot 2H_2O}$?

Given: mass of solute and volume of solution

Asked for: concentration (M)

Strategy:

To find the number of moles of $\mathbf{CoCl_2 \cdot 2H_2O}$, divide the mass of the compound by its molar mass. Calculate the molarity of the solution by dividing the number of moles of solute by the volume of the solution in liters.

Solution:

The molar mass of $CoCl_2$•$2H_2O$ is 165.87 g/mol. Therefore,

$$moles\ CoCl_2 \cdot 2H_2O = \left(\frac{10.0\ \cancel{g}}{165.87\ \cancel{g}/mol}\right) = 0.0603\ mol$$

The volume of the solution in liters is

$$volume = 500\ \cancel{mL}\left(\frac{1\ L}{1000\ \cancel{mL}}\right) = 0.500\ L$$

Molarity is the number of moles of solute per liter of solution, so the molarity of the solution is

$$molarity = \frac{0.0603\ mol}{0.500\ L} = 0.121\ M = CoCl_2 \cdot H_2O$$

Exercise 4.2.6

The solution shown in Figure **4.2.2** contains 90.0 g of $(NH_4)_2Cr_2O_7$ in enough water to give a final volume of exactly 250 mL. What is the molar concentration of ammonium dichromate?

Answer

$$(NH_4)_2Cr_2O_7 = 1.43\ M$$

To prepare a particular volume of a solution that contains a specified concentration of a solute, we first need to calculate the number of moles of solute in the desired volume of solution using the relationship shown in Equation ???. We then convert the number of moles of solute to the corresponding mass of solute needed. This procedure is illustrated in Example **4.2.3**.

Example 4.2.7: D5W Solution

The so-called D5W solution used for the intravenous replacement of body fluids contains 0.310 M glucose. (D5W is an approximately 5% solution of dextrose [the medical name for glucose] in water.) Calculate the mass of glucose necessary to prepare a 500 mL pouch of D5W. Glucose has a molar mass of 180.16 g/mol.

Given: molarity, volume, and molar mass of solute

Asked for: mass of solute

Strategy:

A. Calculate the number of moles of glucose contained in the specified volume of solution by multiplying the volume of the solution by its molarity.
B. Obtain the mass of glucose needed by multiplying the number of moles of the compound by its molar mass.

Solution:

A We must first calculate the number of moles of glucose contained in 500 mL of a 0.310 M solution:

$$V_L M_{mol/L} = moles$$

$$500\ \cancel{mL}\left(\frac{1\ \cancel{L}}{1000\ \cancel{mL}}\right)\left(\frac{0.310\ mol\ glucose}{1\ \cancel{L}}\right) = 0.155\ mol\ glucose$$

B We then convert the number of moles of glucose to the required mass of glucose:

$$mass\ of\ glucose = 0.155\ \cancel{mol\ glucose}\left(\frac{180.16\ g\ glucose}{1\ \cancel{mol\ glucose}}\right) = 27.9\ g\ glucose$$

? Exercise 4.2.7

Another solution commonly used for intravenous injections is normal saline, a 0.16 M solution of sodium chloride in water. Calculate the mass of sodium chloride needed to prepare 250 mL of normal saline solution.

Answer

2.3 g NaCl

Summary

The concentration of a solution is a measure of the relative amount of solute in a given amount of solution. Concentrations may be measured using various units, with one very useful unit being molarity, defined as the number of moles of solute per liter of solution. The solute concentration of a solution may be decreased by adding solvent, a process referred to as dilution. The dilution equation is a simple relation between concentrations and volumes of a solution before and after dilution.

Key Equations

- $M = \frac{\text{mol solute}}{\text{L solution}}$

Glossary

molarity (M)

unit of concentration, defined as the number of moles of solute dissolved in 1 liter of solution

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

4.2: Solution Concentration is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.3: Molarity** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **4.5: Concentration of Solutions** is licensed CC BY-NC-SA 3.0.

4.3: Solution Dilution

Learning Objectives

- Perform dilution calculations using the dilution equation

Dilution is the process whereby the concentration of a solution is lessened by the addition of solvent. For example, we might say that a glass of iced tea becomes increasingly diluted as the ice melts. The water from the melting ice increases the volume of the solvent (water) and the overall volume of the solution (iced tea), thereby reducing the relative concentrations of the solutes that give the beverage its taste (Figure **4.3.1**).




Figure **4.3.1**: Both solutions contain the same mass of copper nitrate. The solution on the right is more dilute because the copper nitrate is dissolved in more solvent. (credit: Mark Ott).

Dilution is also a common means of preparing solutions of a desired concentration. By adding solvent to a measured portion of a more concentrated *stock solution*, we can achieve a particular concentration. The procedure for preparing a solution of known concentration from a stock solution is shown in Figure **4.3.2**. It requires calculating the number of moles of solute desired in the final volume of the more dilute solution and then calculating the volume of the stock solution that contains this amount of solute. Remember that diluting a given quantity of stock solution with solvent does *not* change the number of moles of solute present.




Figure **4.3.2**: Preparation of a Solution of Known Concentration by Diluting a Stock Solution. (a) A volume (V_s) containing the desired moles of solute (M_s) is measured from a stock solution of known concentration. (b) The measured volume of stock solution is transferred to a second volumetric flask. (c) The measured volume in the second flask is then diluted with solvent up to the volumetric mark [$(V_s)(M_s) = (V_d)(M_d)$].

A simple mathematical relationship can be used to relate the volumes and concentrations of a solution before and after the dilution process. According to the definition of molarity, the molar amount of solute in a solution is equal to the product of the solution's

molarity and its volume in liters:

$$n = ML \tag{4.3.1}$$

Expressions like these may be written for a solution before and after it is diluted:

$$n_1 = M_1L_1 \tag{4.3.2}$$

$$n_2 = M_2L_2 \tag{4.3.3}$$

where the subscripts "1" and "2" refer to the solution before and after the dilution, respectively. Since the dilution process *does not change the amount of solute in the solution*,$n_1 = n_2$. Thus, these two equations may be set equal to one another:

$$M_1L_1 = M_2L_2 \tag{4.3.4}$$

This relation is commonly referred to as the dilution equation. Although we derived this equation using molarity as the unit of concentration and liters as the unit of volume, other units of concentration and volume may be used, so long as the units properly cancel per the factor-label method. Reflecting this versatility, the dilution equation is often written in the more general form:

$$C_1V_1 = C_2V_2 \tag{4.3.5}$$

where C and V are concentration and volume, respectively.

✔ Example 4.3.1: Determining the Concentration of a Diluted Solution

If 0.850 L of a 5.00-*M* solution of copper nitrate, $Cu(NO_3)_2$, is diluted to a volume of 1.80 L by the addition of water, what is the molarity of the diluted solution?

Solution

We are given the volume and concentration of a stock solution, V_1 and C_1, and the volume of the resultant diluted solution, V_2. We need to find the concentration of the diluted solution, C_2. We thus rearrange the dilution equation in order to isolate C_2:

$$C_1V_1 = C_2V_2$$

$$C_2 = \frac{C_1V_1}{V_2}$$

Since the stock solution is being diluted by more than two-fold (volume is increased from 0.85 L to 1.80 L), we would expect the diluted solution's concentration to be less than one-half 5 *M*. We will compare this ballpark estimate to the calculated result to check for any gross errors in computation (for example, such as an improper substitution of the given quantities). Substituting the given values for the terms on the right side of this equation yields:

$$C_2 = \frac{0.850\ \text{L} \times 5.00\ \frac{\text{mol}}{\text{L}}}{1.80\ \text{L}} = 2.36\ M$$

This result compares well to our ballpark estimate (it's a bit less than one-half the stock concentration, 5 *M*).

? Exercise 4.3.1

What is the concentration of the solution that results from diluting 25.0 mL of a 2.04-M solution of CH3OH to 500.0 mL?

Answer

0.102 M CH_3OH

Example 4.3.2: Volume of a Diluted Solution

What volume of 0.12 *M* HBr can be prepared from 11 mL (0.011 L) of 0.45 *M* HBr?

Solution

We are given the volume and concentration of a stock solution, V_1 and C_1, and the concentration of the resultant diluted solution, C_2. We need to find the volume of the diluted solution, V_2. We thus rearrange the dilution equation in order to isolate V_2:

$$C_1V_1 = C_2V_2$$

$$V_2 = \frac{C_1V_1}{C_2}$$

Since the diluted concentration (0.12 *M*) is slightly more than one-fourth the original concentration (0.45 *M*), we would expect the volume of the diluted solution to be roughly four times the original volume, or around 44 mL. Substituting the given values and solving for the unknown volume yields:

$$V_2 = \frac{(0.45\ M)(0.011\ \text{L})}{(0.12\ M)}$$

$$V_2 = 0.041\ \text{L}$$

The volume of the 0.12-*M* solution is 0.041 L (41 mL). The result is reasonable and compares well with our rough estimate.

Exercise 4.3.2

A laboratory experiment calls for 0.125 M HNO_3. What volume of 0.125 M HNO_3 can be prepared from 0.250 L of 1.88 M HNO_3?

Answer

3.76 L

Example 4.3.3: Volume of a Concentrated Solution Needed for Dilution

What volume of 1.59 *M* KOH is required to prepare 5.00 L of 0.100 *M* KOH?

Solution

We are given the concentration of a stock solution, C_1, and the volume and concentration of the resultant diluted solution, V_2 and C_2. We need to find the volume of the stock solution, V_1. We thus rearrange the dilution equation in order to isolate V_1:

$$C_1V_1 = C_2V_2$$

$$V_1 = \frac{C_2V_2}{C_1}$$

Since the concentration of the diluted solution 0.100 *M* is roughly one-sixteenth that of the stock solution (1.59 *M*), we would expect the volume of the stock solution to be about one-sixteenth that of the diluted solution, or around 0.3 liters. Substituting the given values and solving for the unknown volume yields:

$$V_1 = \frac{(0.100\ M)(5.00\ \text{L})}{1.59\ M}$$

$$V_1 = 0.314\ \text{L}$$

Thus, we would need 0.314 L of the 1.59-*M* solution to prepare the desired solution. This result is consistent with our rough estimate.

? Exercise 4.3.3

What volume of a 0.575-M solution of glucose, $C_6H_{12}O_6$, can be prepared from 50.00 mL of a 3.00-M glucose solution?

Answer

0.261 L

Summary

The dilution equation is a simple relation between concentrations and volumes of a solution before and after dilution.

Key Equations

- $M = \frac{\text{mol solute}}{\text{L solution}}$
- $C_1V_1 = C_2V_2$

Glossary

dilution

process of adding solvent to a solution in order to lower the concentration of solutes

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

4.3: Solution Dilution is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.3: Molarity** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

4.4: Hydration of Ions in Aqueous Solutions

Learning Objectives

- To understand how and why solutions form

The solvent in aqueous solutions is water, which makes up about 70% of the mass of the human body and is essential for life. Many of the chemical reactions that keep us alive depend on the interaction of water molecules with dissolved compounds. Moreover, the presence of large amounts of water on Earth's surface helps maintain its surface temperature in a range suitable for life. In this section, we describe some of the interactions of water with various substances and introduce you to the characteristics of aqueous solutions.

As shown in Figure **4.4.1**, the individual water molecule consists of two hydrogen atoms bonded to an oxygen atom in a bent (V-shaped) structure. As is typical of group 16 elements, the oxygen atom in each O–H covalent bond attracts electrons more strongly than the hydrogen atom does. Consequently, the oxygen and hydrogen nuclei do not equally share electrons. Instead, hydrogen atoms are electron poor compared with a neutral hydrogen atom and have a partial positive charge, which is indicated by δ^+. The oxygen atom, in contrast, is more electron rich than a neutral oxygen atom, so it has a partial negative charge. This charge must be twice as large as the partial positive charge on each hydrogen for the molecule to have a net charge of zero. Thus its charge is indicated by $2\delta^-$. This unequal distribution of charge creates a polar bond in which one portion of the molecule carries a partial negative charge, while the other portion carries a partial positive charge (Figure **4.4.1**). Because of the arrangement of polar bonds in a water molecule, water is described as a polar substance.




Figure **4.4.1**: The Polar Nature of Water. Each water molecule consists of two hydrogen atoms bonded to an oxygen atom in a bent (V-shaped) structure. Because the oxygen atom attracts electrons more strongly than the hydrogen atoms do, the oxygen atom is partially negatively charged ($2\delta^-$; blue) and the hydrogen atoms are partially positively charged (δ^+; red). For the molecule to have a net charge of zero, the partial negative charge on oxygen must be twice as large as the partial positive charge on each hydrogen.

Because of the asymmetric charge distribution in the water molecule, adjacent water molecules are held together by attractive electrostatic ($\delta^+ \ldots \delta^-$) interactions between the partially negatively charged oxygen atom of one molecule and the partially positively charged hydrogen atoms of adjacent molecules (Figure **4.4.2**). Energy is needed to overcome these electrostatic attractions. In fact, without them, water would evaporate at a much lower temperature, and neither Earth's oceans nor we would exist!




Figure **4.4.2**: The Structure of Liquid Water. Two views of a water molecule are shown: (a) a ball-and-stick structure and (b) a space-filling model. Water molecules are held together by electrostatic attractions (dotted lines) between the partially negatively charged oxygen atom of one molecule and the partially positively charged hydrogen atoms on adjacent molecules. As a result, the water molecules in liquid water form transient networks with structures similar to that shown. Because the interactions between water molecules are continually breaking and reforming, liquid water does not have a single fixed structure.

As you learned previously, ionic compounds such as sodium chloride (NaCl) are also held together by electrostatic interactions—in this case, between oppositely charged ions in the highly ordered solid, where each ion is surrounded by ions of the opposite charge in a fixed arrangement. In contrast to an ionic solid, the structure of liquid water is not completely ordered because the interactions between molecules in a liquid are constantly breaking and reforming.

The unequal charge distribution in polar liquids such as water makes them good solvents for ionic compounds. When an ionic solid dissolves in water, the ions *dissociate*. That is, the partially negatively charged oxygen atoms of the H_2O molecules surround the cations (Na^+ in the case of NaCl), and the partially positively charged hydrogen atoms in H_2O surround the anions (Cl^-; Figure **4.4.3**). Individual cations and anions that are each surrounded by their own shell of water molecules are called hydrated ions. We can describe the dissolution of NaCl in water as

$$NaCl(s) \xrightarrow{H_2O(l)} Na^+(aq) + Cl^-(aq) \tag{4.4.1}$$

where (aq) indicates that Na^+ and Cl^- are hydrated ions.




Figure **4.4.3**: The Dissolution of Sodium Chloride in Water. An ionic solid such as sodium chloride dissolves in water because of the electrostatic attraction between the cations (Na^+) and the partially negatively charged oxygen atoms of water molecules, and between the anions (Cl^-) and the partially positively charged hydrogen atoms of water.

> *Polar liquids are good solvents for ionic compounds.*

Summary

Aqueous solutions can be classified as polar or nonpolar depending on how well they conduct electricity. Most chemical reactions are carried out in *solutions*, which are homogeneous mixtures of two or more substances. In a solution, a *solute* (the substance present in the lesser amount) is dispersed in a *solvent* (the substance present in the greater amount). *Aqueous solutions* contain water as the solvent, whereas *nonaqueous solutions* have solvents other than water. Polar substances, such as water, contain

asymmetric arrangements of **polar bonds**, in which electrons are shared unequally between bonded atoms. Polar substances and ionic compounds tend to be most soluble in water because they interact favorably with its structure. In aqueous solution, dissolved ions become **hydrated**; that is, a shell of water molecules surrounds them.

Glossary

dissociation

physical process accompanying the dissolution of an ionic compound in which the compound's constituent ions are solvated and dispersed throughout the solution

Contributors and Attributions

- Modified by Joshua Halpern (Howard University)

4.4: Hydration of Ions in Aqueous Solutions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.3: Molarity** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **4.1: General Properties of Aqueous Solutions** by Anonymous is licensed CC BY-NC-SA 3.0.

4.5: Solubility of Ionic Compounds

Learning Objectives

- Predict solubilities of ionic compounds in water using the solubility rules.

The extent to which a substance may be dissolved in water, or any solvent, is quantitatively expressed as its solubility, defined as the maximum concentration of a substance that can be achieved under specified conditions. Substances with relatively large solubilities are said to be soluble. A substance will precipitate when solution conditions are such that its concentration exceeds its solubility. Substances with relatively low solubilities are said to be insoluble, and these are the substances that readily precipitate from solution. More information on these important concepts is provided in the text chapter on solutions. For purposes of predicting the identities of solids formed by precipitation reactions, one may simply refer to patterns of solubility that have been observed for many ionic compounds (Table **4.5.1**).

Table **4.5.1**: Solubilities of Common Ionic Compounds in Water

Soluble compounds contain	**Exceptions** to these solubility rules include
• group 1 metal cations (Li^+, Na^+, K^+, Rb^+, and Cs^+) and ammonium ion (NH_4^+) • the halide ions (Cl^-, Br^-, and I^-) • the acetate ($C_2H_3O_2^-$), bicarbonate (HCO_3^-), nitrate (NO_3^-), and chlorate (ClO_3^-) ions • the sulfate (SO_4^-) ion	• halides of Ag^+, Hg_2^{2+}, and Pb^{2+} • sulfates of Ag^+, Ba^{2+}, Ca^{2+}, Hg_2^{2+}, Pb^{2+}, and Sr^{2+}
Insoluble compounds contain	**Exceptions** to these insolubility rules include
• carbonate (CO_3^{2-}), chromate (CrO_4^{2-}), phosphate (PO_4^{3-}), and sulfide (S^{2-}) ions • hydroxide ion (OH^-)	• compounds of these anions with group 1 metal cations and ammonium ion • hydroxides of group 1 metal cations and Ba^{2+}

Example 4.5.1: Predicting Precipitation Reactions

Use table **4.5.1** to predict the solubility of each of the following ionic compounds.

a. barium sulfate
b. silver chloride
c. lead(II) nitrate

Solution

(a) According to the solubility table the presence of SO_4^{2-} renders the compound soluble except when SO_4^{2-} is combined with Ag^+, Ba^{2+}, Ca^{2+}, Hg_2^{2+}, Pb^{2+}, and Sr^{2+}. Since $BaSO_4$ has Ba^{2+}, it is insoluble.

(b) According to the solubility table the presence of Cl^- renders the compound soluble except when Cl^- is combined Ag^+, Hg_2^{2+}, and Pb^{2+}. Since AgCl has Ag^+, it is insoluble.

(c) According to the solubility table the presence of NO_3^- renders the compund soluble with no exception. Therefore, $Pb(NO_3)_2$ is soluble.


Exercise 4.5.1

Use table **4.5.1** to predict the solubility of each of the following ionic compounds.

a. calcium hydroxide
b. ammonium carbonate
c. mercury(I) bromide

Answer

(a) insoluble; (b) soluble; (c) insoluble



Predicting the Solubility of Ionic Compounds: https://youtu.be/U3QNwnfmvGU

Summary

Solubility is the maximum amount of solute that can dissolve in specific amount of solvent. Not all ionic compounds are able soluble in water. We use the solubility rules to predict whether an ionic compound dissolves in water or not.

Glossary

Solubility

Solubility is the maximum amount of solute that can dissolve in specific amount of solvent

---

4.5: Solubility of Ionic Compounds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.3: Molarity** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **4.2: Precipitation Reactions** is licensed CC BY-NC-SA 3.0.
- **4.3: Classifying Chemical Reactions** is licensed CC BY 4.0.

4.6: Introduction to Acids and Bases


Learning Objectives

- To know the characteristic properties of acids and bases.

Acid–base reactions are essential in both biochemistry and industrial chemistry. Moreover, many of the substances we encounter in our homes, the supermarket, and the pharmacy are acids or bases. For example, aspirin is an acid (acetylsalicylic acid), and antacids are bases. In fact, every amateur chef who has prepared mayonnaise or squeezed a wedge of lemon to marinate a piece of fish has carried out an acid–base reaction. Before we discuss the characteristics of such reactions, let's first describe some of the properties of acids and bases.

Definitions of Acids and Bases

We can define **acids** as substances that dissolve in water to produce H^+ ions, whereas **bases** are defined as substances that dissolve in water to produce OH^- ions. In fact, this is only one possible set of definitions. Although the general properties of acids and bases have been known for more than a thousand years, the definitions of *acid* and *base* have changed dramatically as scientists have learned more about them. In ancient times, an acid was any substance that had a sour taste (e.g., vinegar or lemon juice), caused consistent color changes in dyes derived from plants (e.g., turning blue litmus paper red), reacted with certain metals to produce hydrogen gas and a solution of a salt containing a metal cation, and dissolved carbonate salts such as limestone ($CaCO_3$) with the evolution of carbon dioxide. In contrast, a base was any substance that had a bitter taste, felt slippery to the touch, and caused color changes in plant dyes that differed diametrically from the changes caused by acids (e.g., turning red litmus paper blue). Although these definitions were useful, they were entirely descriptive.



The Arrhenius Definition of Acids and Bases

The first person to define acids and bases in detail was the Swedish chemist Svante Arrhenius (1859–1927; Nobel Prize in Chemistry, 1903). According to the *Arrhenius definition*, an acid is a substance like hydrochloric acid that dissolves in water to produce H^+ ions (protons; Equation 4.6.1), and a base is a substance like sodium hydroxide that dissolves in water to produce hydroxide (OH^-) ions (Equation 4.6.2):

$$\underset{\text{an Arrhenius acid}}{HCl_{(g)}} \xrightarrow{H_2O_{(l)}} H^+_{(aq)} + Cl^-_{(aq)} \tag{4.6.1}$$

$$\underset{\text{an Arrhenius base}}{NaOH_{(s)}} \xrightarrow{H_2O_{(l)}} Na^+_{(aq)} + OH^-_{(aq)} \tag{4.6.2}$$

According to Arrhenius, the characteristic properties of acids and bases are due exclusively to the presence of H^+ and OH^- ions, respectively, in solution. Although Arrhenius's ideas were widely accepted, his definition of acids and bases had two major limitations:

1. First, because acids and bases were defined in terms of ions obtained from water, the Arrhenius concept applied only to substances in aqueous solution.
2. Second, and more important, the Arrhenius definition predicted that *only* substances that dissolve in water to produce H^+ and OH^- ions should exhibit the properties of acids and bases, respectively. For example, according to the Arrhenius definition, the reaction of ammonia (a base) with gaseous HCl (an acid) to give ammonium chloride (Equation 4.6.3) is not an acid–base reaction because it does not involve H^+ and OH^-:

$$NH_{3\,(g)} + HCl_{(g)} \rightarrow NH_4Cl_{(s)} \tag{4.6.3}$$

The Brønsted–Lowry Definition of Acids and Bases

Because of the limitations of the Arrhenius definition, a more general definition of acids and bases was needed. One was proposed independently in 1923 by the Danish chemist J. N. Brønsted (1879–1947) and the British chemist T. M. Lowry (1874–1936), who defined acid–base reactions in terms of the transfer of a proton (H^+ ion) from one substance to another.

According to Brønsted and Lowry, an acid (A substance with at least one hydrogen atom that can dissociate to form an anion and an H^+ ion (a proton) in aqueous solution, thereby forming an acidic solution) is any substance that can donate a proton, and a base (a substance that produces one or more hydroxide ions (OH^- and a cation when dissolved in aqueous solution, thereby forming a basic solution) is any substance that can accept a proton. The Brønsted–Lowry definition of an acid is essentially the same as the Arrhenius definition, except that it is not restricted to aqueous solutions. The Brønsted–Lowry definition of a base, however, is far more general because the hydroxide ion is just one of many substances that can accept a proton. Ammonia, for example, reacts with a proton to form NH_4^+, so in Equation 4.6.3, NH_3 is a Brønsted–Lowry base and HCl is a Brønsted–Lowry acid. Because of its more general nature, the Brønsted–Lowry definition is used throughout this text unless otherwise specified.

Polyprotic Acids


Acids differ in the number of protons they can donate. For example, monoprotic acids (a compound that is capable of donating one proton per molecule) are compounds that are capable of donating a single proton per molecule. Monoprotic acids include HF, HCl, HBr, HI, HNO_3, and HNO_2. All carboxylic acids that contain a single $-CO_2H$ group, such as acetic acid (CH_3CO_2H), are monoprotic acids, dissociating to form RCO_2^- and H^+. A compound that can donate more than one proton per molecule is known as a **polyprotic acid**. For example, H_2SO_4 can donate two H^+ ions in separate steps, so it is a diprotic acid (a compound that can donate two protons per molecule in separate steps) and H_3PO_4, which is capable of donating three protons in successive steps, is a triprotic acid (a compound that can donate three protons per molecule in separate steps), (Equation 4.6.4, Equation 4.6.5, and Equation 4.6.6):

$$H_3PO_4(l) \overset{H_2O(l)}{\rightleftharpoons} H^+(aq) + H_2PO_4^-(aq) \tag{4.6.4}$$

$$H_2PO_4^-(aq) \rightleftharpoons H^+(aq) + HPO_4^{2-}(aq) \tag{4.6.5}$$

$$HPO_4^{2-}(aq) \rightleftharpoons H^+(aq) + PO_4^{3-}(aq) \tag{4.6.6}$$

In chemical equations such as these, a double arrow is used to indicate that both the forward and reverse reactions occur simultaneously, so the forward reaction does not go to completion. Instead, the solution contains significant amounts of both reactants and products. Over time, the reaction reaches a state in which the concentration of each species in solution remains constant. The reaction is then said to be in **equilibrium** (the point at which the rates of the forward and reverse reactions become the same, so that the net composition of the system no longer changes with time).



Strengths of Acids and Bases

We will not discuss the strengths of acids and bases quantitatively until next semester. Qualitatively, however, we can state that **strong acids** react essentially completely with water to give H^+ and the corresponding anion. Similarly, **strong bases** dissociate essentially completely in water to give OH^- and the corresponding cation. Strong acids and strong bases are both strong electrolytes. In contrast, only a fraction of the molecules of weak acids and weak bases react with water to produce ions, so weak

acids and weak bases are also weak electrolytes. Typically less than 5% of a weak electrolyte dissociates into ions in solution, whereas more than 95% is present in undissociated form.

In practice, only a few strong acids are commonly encountered: HCl, HBr, HI, HNO_3, $HClO_4$, and H_2SO_4 (H_3PO_4 is only moderately strong). The most common strong bases are ionic compounds that contain the hydroxide ion as the anion; three examples are NaOH, KOH, and $Ca(OH)_2$. Common weak acids include HCN, H_2S, HF, oxoacids such as HNO_2 and HClO, and carboxylic acids such as acetic acid. The ionization reaction of acetic acid is as follows:

$$CH_3CO_2H(l) \overset{H_2O(l)}{\rightleftharpoons} H^+(aq) + CH_3CO_2^-(aq) \tag{4.6.7}$$

Although acetic acid is *very* soluble in water, almost all of the acetic acid in solution exists in the form of neutral molecules (less than 1% dissociates). Sulfuric acid is unusual in that it is a strong acid when it donates its first proton (Equation 4.6.8) but a weak acid when it donates its second proton (Equation 4.6.9) as indicated by the single and double arrows, respectively:

$$\underset{\text{strong acid}}{H_2SO_4(l)} \xrightarrow{H_2O(l)} H^+(aq) + HSO_4^-(aq) \tag{4.6.8}$$

$$\underset{\text{weak acid}}{HSO_4^-(aq)} \rightleftharpoons H^+(aq) + SO_4^{2-}(aq) \tag{4.6.9}$$

Consequently, an aqueous solution of sulfuric acid contains $H^+_{(aq)}$ ions and a mixture of $HSO^-_{4\,(aq)}$ and $SO^{2-}_{4\,(aq)}$ ions, but no H_2SO_4 molecules. All other polyprotic acids, such as H_3PO_4, are weak acids.

The most common weak base is ammonia, which reacts with water to form small amounts of hydroxide ion:

$$NH_3(g) + H_2O(l) \rightleftharpoons NH_4^+(aq) + OH^-(aq) \tag{4.6.10}$$

Most of the ammonia (>99%) is present in the form of $NH_3(g)$. Amines, which are organic analogues of ammonia, are also weak bases, as are ionic compounds that contain anions derived from weak acids (such as S^{2-}).

> *There is no correlation between the solubility of a substance and whether it is a strong electrolyte, a weak electrolyte, or a nonelectrolyte.*



Definition of Strong/Weak Acids & Bases: https://youtu.be/gN2l8H_AWGU

Table **4.6.1** lists some common strong acids and bases. Acids other than the six common strong acids are almost invariably weak acids. The only common strong bases are the hydroxides of the alkali metals and the heavier alkaline earths (Ca, Sr, and Ba); any other bases you encounter are most likely weak. Remember that *there is no correlation between solubility and whether a substance is a strong or a weak electrolyte!* Many weak acids and bases are extremely soluble in water.

Table **4.6.1**: Common Strong Acids and Bases

Strong Acids		Strong Bases	
Hydrogen Halides	Oxoacids	Group 1 Hydroxides	Hydroxides of Heavy Group 2 Elements
HCl	HNO_3	LiOH	$Ca(OH)_2$
HBr	H_2SO_4	NaOH	$Sr(OH)_2$
HI	$HClO_4$	KOH	$Ba(OH)_2$
		RbOH	
		CsOH	

Example 4.6.1: Acid Strength

Classify each compound as a strong acid, a weak acid, a strong base, a weak base, or none of these.

a. $CH_3CH_2CO_2H$
b. CH_3OH
c. $Sr(OH)_2$
d. $CH_3CH_2NH_2$
e. $HBrO_4$

Given: compound

Asked for: acid or base strength

Strategy:

A Determine whether the compound is organic or inorganic.

B If inorganic, determine whether the compound is acidic or basic by the presence of dissociable H^+ or OH^- ions, respectively. If organic, identify the compound as a weak base or a weak acid by the presence of an amine or a carboxylic acid group, respectively. Recall that all polyprotic acids except H_2SO_4 are weak acids.

Solution:

a. **A** This compound is propionic acid, which is organic. **B** It contains a carboxylic acid group analogous to that in acetic acid, so it must be a weak acid.
b. **A** CH_3OH is methanol, an organic compound that contains the −OH group. **B** As a covalent compound, it does not dissociate to form the OH^- ion. Because it does not contain a carboxylic acid ($-CO_2H$) group, methanol also cannot dissociate to form $H^+(aq)$ ions. Thus we predict that in aqueous solution methanol is neither an acid nor a base.
c. **A** $Sr(OH)_2$ is an inorganic compound that contains one Sr^{2+} and two OH^- ions per formula unit. **B** We therefore expect it to be a strong base, similar to $Ca(OH)_2$.
d. **A** $CH_3CH_2NH_2$ is an amine (ethylamine), an organic compound in which one hydrogen of ammonia has been replaced by an R group. **B** Consequently, we expect it to behave similarly to ammonia (Equation 4.6.7), reacting with water to produce small amounts of the OH^- ion. Ethylamine is therefore a weak base.
e. **A** $HBrO_4$ is perbromic acid, an inorganic compound. **B** It is not listed in Table **4.6.1** as one of the common strong acids, but that does not necessarily mean that it is a weak acid. If you examine the periodic table, you can see that Br lies directly below Cl in group 17. We might therefore expect that $HBrO_4$ is chemically similar to $HClO_4$, a strong acid—and, in fact, it is.

Exercise 4.6.1: Acid Strength

Classify each compound as a strong acid, a weak acid, a strong base, a weak base, or none of these.

a. $Ba(OH)_2$
b. HIO_4
c. $CH_3CH_2CH_2CO_2H$
d. $(CH_3)_2NH$
e. CH_2O

Answer a

strong base

Answer b

strong acid

Answer c

weak acid

Answer d

weak base

Answer e

none of these; formaldehyde is a neutral molecule

Summary

According to Arrhenius, an acid is compound that produces H^+ in an aqueous solution, and a base is a compound that produces OH^- in an aqueous solution. According to Brønsted-Lowry definition, a compound that can donate a H^+ to another compound is called a Brønsted-Lowry acid. The compound that accepts the H^+ is called a Brønsted-Lowry base. The species remaining after a Brønsted-Lowry acid has lost a proton is the conjugate base of the acid. A polyprotyic acid is a compound that can donate more than none proton. Strong acids completely ionize in water. Weak acids only partially ionize.

Glossary

diprotic acid
acid containing two ionizable hydrogen atoms per molecule. A diprotic acid ionizes in two steps

triprotic acid
acid that contains three ionizable hydrogen atoms per molecule; ionization of triprotic acids occurs in three steps

successive ionization
process in which an acid is ionized by losing protons sequentially

monoprotic acid
acid containing one ionizable hydrogen atom per molecule

diprotic base
base capable of accepting two protons. The protons are accepted in two steps

4.6: Introduction to Acids and Bases is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.3: Molarity** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **4.3: Acid-Base Reactions** is licensed CC BY-NC-SA 3.0.

4.7: End of Chapter Problems

1. Explain what changes and what stays the same when 1.00 L of a solution of NaCl is diluted to 1.80 L.
2. What information do we need to calculate the molarity of a sulfuric acid solution?
3. What does it mean when we say that a 200-mL sample and a 400-mL sample of a solution of salt have the same molarity? In what ways are the two samples identical? In what ways are these two samples different?
4. Determine the molarity for each of the following solutions:
    a. 0.444 mol of $CoCl_2$ in 0.654 L of solution
    b. 98.0 g of phosphoric acid, H_3PO_4, in 1.00 L of solution
    c. 0.2074 g of calcium hydroxide, $Ca(OH)_2$, in 40.00 mL of solution
    d. 10.5 kg of $Na_2SO_4 \cdot 10H_2O$ in 18.60 L of solution
    e. 7.0×10^{-3} mol of I_2 in 100.0 mL of solution
    f. 1.8×10^4 mg of HCl in 0.075 L of solution

Answer

a. 0.679 *M*; b. 1.00 *M*; c. 0.06998 *M*; d. 1.75 *M*; e. 0.070 *M*; f. 6.6 *M*

5. Determine the molarity of each of the following solutions:
    a. 1.457 mol KCl in 1.500 L of solution
    b. 0.515 g of H_2SO_4 in 1.00 L of solution
    c. 20.54 g of $Al(NO_3)_3$ in 1575 mL of solution
    d. 2.76 kg of $CuSO_4 \cdot 5H_2O$ in 1.45 L of solution
    e. 0.005653 mol of Br_2 in 10.00 mL of solution
    f. 0.000889 g of glycine, $C_2H_5NO_2$, in 1.05 mL of solution

Answer

a. a. 0.9713 M; b. 5.25×10^{-3} M; c. 6.122×10^{-2} M; d. 7.62 M; e. 0.5653 M; f. 1.13×10^{-2} M

6. Consider this question: What is the mass of the solute in 0.500 L of 0.30 *M* glucose, $C_6H_{12}O_6$, used for intravenous injection?
    a. Outline the steps necessary to answer the question.
    b. Answer the question.

Answer

a. determine the number of moles of glucose in 0.500 L of solution; determine the molar mass of glucose; determine the mass of glucose from the number of moles and its molar mass; b. 27 g

7. Consider this question: What is the mass of solute in 200.0 L of a 1.556-*M* solution of KBr?
    a. Outline the steps necessary to answer the question.
    b. Answer the question.

Answer

a. Calculate to moles of KBr by multiplying the Molarity by the amount of solution (200.0 L); then, Find the Molar Mass of KBr and convert moles of solute to grams; b. 37.03 kg

8. Calculate the number of moles and the mass of the solute in each of the following solutions:
    a. 2.00 L of 18.5 *M* H_2SO_4, concentrated sulfuric acid
    b. 100.0 mL of 3.8×10^{-5} *M* NaCN, the minimum lethal concentration of sodium cyanide in blood serum
    c. 5.50 L of 13.3 *M* H_2CO, the formaldehyde used to “fix” tissue samples
    d. 325 mL of 1.8×10^{-6} *M* $FeSO_4$, the minimum concentration of iron sulfate detectable by taste in drinking water

Answer

a. 37.0 mol H_2SO_4; 3.63 × 10^3 g H_2SO_4; (b) 3.8 × 10^{-6} mol NaCN; 1.9 × 10^{-4} g NaCN; (c) 73.2 mol H_2CO; 2.20 kg H_2CO; (d) 5.9 × 10^{-7} mol $FeSO_4$; 8.9 × 10^{-5} g $FeSO_4$

9. Calculate the number of moles and the mass of the solute in each of the following solutions:
   a. 325 mL of 8.23 × 10^{-5} *M* KI, a source of iodine in the diet
   b. 75.0 mL of 2.2 × 10^{-5} *M* H_2SO_4, a sample of acid rain
   c. 0.2500 L of 0.1135 *M* K_2CrO_4, an analytical reagent used in iron assays
   d. 10.5 L of 3.716 *M* $(NH_4)_2SO_4$, a liquid fertilizer

Answer

a. 2.67x10^{-5} moles KI; 4.44x10^{-3}g KI; b. 1.7x10^{-6} moles H_2SO_4 ; 1.6x10^{-4} g H_2SO_4; c. 2.838x10^{-2} moles K_2CrO_4 ; 5.510g K_2CrO_4; d. 39.0 moles $(NH_4)_2SO_4$; 5,160 g $(NH_4)_2SO_4$

10. Consider this question: What is the molarity of $KMnO_4$ in a solution of 0.0908 g of $KMnO_4$ in 0.500 L of solution?
    a. Outline the steps necessary to answer the question.
    b. Answer the question.

Answer

a. Determine the molar mass of $KMnO_4$; determine the number of moles of $KMnO_4$ in the solution; from the number of moles and the volume of solution, determine the molarity; b. 1.15 × 10^{-3} *M*

11. Consider this question: What is the molarity of HCl if 35.23 mL of a solution of HCl contain 0.3366 g of HCl?
    a. Outline the steps necessary to answer the question.
    b. Answer the question.

Answer

a. Convert g of HCl to moles of HCl and convert mL of solution to L of solution, Divide moles of HCl by L of solution; b. 0.2621 M ;

12. Calculate the molarity of each of the following solutions:
    a. 0.195 g of cholesterol, $C_{27}H_{46}O$, in 0.100 L of serum, the average concentration of cholesterol in human serum
    b. 4.25 g of NH_3 in 0.500 L of solution, the concentration of NH_3 in household ammonia
    c. 1.49 kg of isopropyl alcohol, C_3H_7OH, in 2.50 L of solution, the concentration of isopropyl alcohol in rubbing alcohol
    d. 0.029 g of I_2 in 0.100 L of solution, the solubility of I_2 in water at 20 °C

Answer

a. 5.04 × 10^{-3} *M*; b. 0.499 *M*; c. 9.92 *M*; d. 1.1 × 10^{-3} *M*

13. Calculate the molarity of each of the following solutions:
    a. 293 g HCl in 666 mL of solution, a concentrated HCl solution
    b. 2.026 g $FeCl_3$ in 0.1250 L of a solution used as an unknown in general chemistry laboratories
    c. 0.001 mg Cd^{2+} in 0.100 L, the maximum permissible concentration of cadmium in drinking water
    d. 0.0079 g $C_7H_5SNO_3$ in one ounce (29.6 mL), the concentration of saccharin in a diet soft drink.
14. There is about 1.0 g of calcium, as Ca^{2+}, in 1.0 L of milk. What is the molarity of Ca^{2+} in milk? Answer: 0.025 *M*
15. What volume of a 1.00-*M* $Fe(NO_3)_3$ solution can be diluted to prepare 1.00 L of a solution with a concentration of 0.250 *M*?
16. If 0.1718 L of a 0.3556-*M* C_3H_7OH solution is diluted to a concentration of 0.1222 *M*, what is the volume of the resulting solution? Answer: 0.5000 L
17. If 4.12 L of a 0.850 *M*-H_3PO_4 solution is be diluted to a volume of 10.00 L, what is the concentration the resulting solution?
18. What volume of a 0.33-*M* $C_{12}H_{22}O_{11}$ solution can be diluted to prepare 25 mL of a solution with a concentration of 0.025 *M*? Answer: 1.9 mL

19. What is the concentration of the NaCl solution that results when 0.150 L of a 0.556-*M* solution is allowed to evaporate until the volume is reduced to 0.105 L?
20. What is the molarity of the diluted solution when each of the following solutions is diluted to the given final volume?
    a. 1.00 L of a 0.250-*M* solution of $Fe(NO_3)_3$ is diluted to a final volume of 2.00 L
    b. 0.5000 L of a 0.1222-*M* solution of C_3H_7OH is diluted to a final volume of 1.250 L
    c. 2.35 L of a 0.350-*M* solution of H_3PO_4 is diluted to a final volume of 4.00 L
    d. 22.50 mL of a 0.025-*M* solution of $C_{12}H_{22}O_{11}$ is diluted to 100.0 mL

Answer

a. 0.125 *M*; b. 0.04888 *M;* c. 0.206 *M*; d. 0.0056 *M*

21. What is the final concentration of the solution produced when 225.5 mL of a 0.09988-*M* solution of Na_2CO_3 is allowed to evaporate until the solution volume is reduced to 45.00 mL?
22. A 2.00-L bottle of a solution of concentrated HCl was purchased for the general chemistry laboratory. The solution contained 868.8 g of HCl. What is the molarity of the solution? Answer: 11.9 *M*
23. An experiment in a general chemistry laboratory calls for a 2.00-*M* solution of HCl. How many mL of 11.9 *M* HCl would be required to make 250 mL of 2.00 *M* HCl?
24. What volume of a 0.20-*M* K_2SO_4 solution contains 57 g of K_2SO_4? Answer: 1.6 L
25. The US Environmental Protection Agency (EPA) places limits on the quantities of toxic substances that may be discharged into the sewer system. Limits have been established for a variety of substances, including hexavalent chromium, which is limited to 0.50 mg/L. If an industry is discharging hexavalent chromium as potassium dichromate ($K_2Cr_2O_7$), what is the maximum permissible molarity of that substance?

4.7: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

5: Chemical reactions

5.1: Writing and Balancing Chemical Reactions
5.2: Precipitation Reactions
5.3: Representing aqueous reaction- Molecular, complete ionic, and net ionic equations
5.4: Neutralization Reactions and Gas Evolution
5.5: Oxidation-Reduction reactions
5.6: Balancing Redox Reactions
5.7: End of Chapter Problems

5: Chemical reactions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

5.1: Writing and Balancing Chemical Reactions

Learning Objectives

- Derive chemical equations from narrative descriptions of chemical reactions.
- Write and balance chemical equations in molecular, total ionic, and net ionic formats.

The preceding chapter introduced the use of element symbols to represent individual atoms. When atoms gain or lose electrons to yield ions, or combine with other atoms to form molecules, their symbols are modified or combined to generate chemical formulas that appropriately represent these species. Extending this symbolism to represent both the identities and the relative quantities of substances undergoing a chemical (or physical) change involves writing and balancing a chemical equation. Consider as an example the reaction between one methane molecule (CH_4) and two diatomic oxygen molecules (O_2) to produce one carbon dioxide molecule (CO_2) and two water molecules (H_2O). The chemical equation representing this process is provided in the upper half of Figure **5.1.1**, with space-filling molecular models shown in the lower half of the figure.




Figure **5.1.1**: The reaction between methane and oxygen to yield carbon dioxide and water (shown at bottom) may be represented by a chemical equation using formulas (top).

This example illustrates the fundamental aspects of any chemical equation:

1. The substances undergoing reaction are called reactants, and their formulas are placed on the left side of the equation.
2. The substances generated by the reaction are called products, and their formulas are placed on the right sight of the equation.
3. Plus signs (+) separate individual reactant and product formulas, and an arrow (⟶) separates the reactant and product (left and right) sides of the equation.
4. The relative numbers of reactant and product species are represented by coefficients (numbers placed immediately to the left of each formula). A coefficient of 1 is typically omitted.

It is common practice to use the smallest possible whole-number coefficients in a chemical equation, as is done in this example. Realize, however, that these coefficients represent the *relative* numbers of reactants and products, and, therefore, they may be correctly interpreted as ratios. Methane and oxygen react to yield carbon dioxide and water in a 1:2:1:2 ratio. This ratio is satisfied if the numbers of these molecules are, respectively, 1-2-1-2, or 2-4-2-4, or 3-6-3-6, and so on (Figure **5.1.2**). Likewise, these coefficients may be interpreted with regard to any amount (number) unit, and so this equation may be correctly read in many ways, including:

- *One* methane molecule and *two* oxygen molecules react to yield *one* carbon dioxide molecule and *two* water molecules.
- *One dozen* methane molecules and *two dozen* oxygen molecules react to yield *one dozen* carbon dioxide molecules and *two dozen* water molecules.
- *One mole* of methane molecules and *2 moles* of oxygen molecules react to yield *1 mole* of carbon dioxide molecules and *2 moles* of water molecules.




Figure **5.1.2**: Regardless of the absolute number of molecules involved, the ratios between numbers of molecules of each species that react (the reactants) and molecules of each species that form (the products) are the same and are given in the chemical equation.

Balancing Equations

When a chemical equation is balanced it means that equal numbers of atoms for each element involved in the reaction are represented on the reactant and product sides. This is a requirement the equation must satisfy to be consistent with the law of conservation of matter. It may be confirmed by simply summing the numbers of atoms on either side of the arrow and comparing these sums to ensure they are equal. Note that the number of atoms for a given element is calculated by multiplying the coefficient of any formula containing that element by the element's subscript in the formula. If an element appears in more than one formula on a given side of the equation, the number of atoms represented in each must be computed and then added together. For example, both product species in the example reaction, $\mathbf{CO_2}$ and $\mathbf{H_2O}$, contain the element oxygen, and so the number of oxygen atoms on the product side of the equation is

$$\left(1\ \cancel{\mathrm{CO_2\ molecule}} \times \frac{2\ \mathrm{O\ atoms}}{\cancel{\mathrm{CO_2\ molecule}}}\right) + \left(\cancel{2\,\mathrm{H_2O\ molecule}} \times \frac{1\ \mathrm{O\ atom}}{\cancel{\mathrm{H_2O\ molecule}}}\right) = 4\ \mathrm{O\ atoms} \tag{5.1.1}$$

The equation for the reaction between methane and oxygen to yield carbon dioxide and water is confirmed to be balanced per this approach, as shown here:

$$\mathbf{CH_4 + 2\,O_2 \rightarrow CO_2 + 2\,H_2O} \tag{5.1.2}$$

Element	Reactants	Products	Balanced?
C	1 × 1 = 1	1 × 1 = 1	1 = 1, yes
H	4 × 1 = 4	2 × 2 = 4	4 = 4, yes
O	2 × 2 = 4	(1 × 2) + (2 × 1) = 4	4 = 4, yes

A balanced chemical equation often may be derived from a qualitative description of some chemical reaction by a fairly simple approach known as balancing by inspection. Consider as an example the decomposition of water to yield molecular hydrogen and oxygen. This process is represented qualitatively by an *unbalanced* chemical equation:

$$\mathbf{H_2O \rightarrow H_2 + O_2} \qquad \textbf{(unbalanced)}$$

Comparing the number of H and O atoms on either side of this equation confirms its imbalance:

Element	Reactants	Products	Balanced?
H	1 × 2 = 2	1 × 2 = 2	2 = 2, yes
O	1 × 1 = 1	1 × 2 = 2	1 ≠ 2, no

The numbers of H atoms on the reactant and product sides of the equation are equal, but the numbers of O atoms are not. To achieve balance, the *coefficients* of the equation may be changed as needed. Keep in mind, of course, that the *formula subscripts* define, in part, the identity of the substance, and so these cannot be changed without altering the qualitative meaning of the equation. For example, changing the reactant formula from H_2O to H_2O_2 would yield balance in the number of atoms, but doing so also changes the reactant's identity (it's now hydrogen peroxide and not water). The O atom balance may be achieved by changing the coefficient for H_2O to 2.

$$2\,H_2O \rightarrow H_2 + O_2 \qquad \text{(unbalanced)}$$

Element	Reactants	Products	Balanced?
H	**2** × 2 = 4	1 × 2 = 2	4 ≠ 2, no
O	2 × 1 = 2	1 × 2 = 2	2 = 2, yes

The H atom balance was upset by this change, but it is easily reestablished by changing the coefficient for the H_2 product to 2.

$$2\,H_2O \rightarrow 2\,H_2 + O_2 \qquad \text{(balanced)}$$

Element	Reactants	Products	Balanced?
H	2 × 2 = 4	**2** × 2 = 2	4 = 4, yes
O	2 × 1 = 2	1 × 2 = 2	2 = 2, yes

These coefficients yield equal numbers of both H and O atoms on the reactant and product sides, and the balanced equation is, therefore:

$$2\,H_2O \rightarrow 2\,H_2 + O_2 \qquad (5.1.3)$$

Example 5.1.1: Balancing Chemical Equations

Write a balanced equation for the reaction of molecular nitrogen (N_2) and oxygen (O_2) to form dinitrogen pentoxide.

Solution

First, write the unbalanced equation.

$$N_2 + O_2 \rightarrow N_2O_5 \qquad \text{(unbalanced)}$$

Next, count the number of each type of atom present in the unbalanced equation.

Element	Reactants	Products	Balanced?
N	1 × 2 = 2	1 × 2 = 2	2 = 2, yes
O	1 × 2 = 2	1 × 5 = 5	2 ≠ 5, no

Though nitrogen is balanced, changes in coefficients are needed to balance the number of oxygen atoms. To balance the number of oxygen atoms, a reasonable first attempt would be to change the coefficients for the O_2 and N_2O_5 to integers that will yield 10 O atoms (the least common multiple for the O atom subscripts in these two formulas).

$$N_2 + 5\,O_2 \rightarrow 2\,N_2O_5 \qquad \text{(unbalanced)}$$

Element	Reactants	Products	Balanced?
N	1 × 2 = 2	**2** × 2 = 4	2 ≠ 4, no
O	**5** × 2 = 10	**2** × 5 = 10	10 = 10, yes

The N atom balance has been upset by this change; it is restored by changing the coefficient for the reactant N_2 to 2.

$$2\,N_2 + 5\,O_2 \rightarrow 2\,N_2O_5 \tag{5.1.4}$$

Element	Reactants	Products	Balanced?
N	**2** × 2 = 4	2 × 2 = 4	4 = 4, yes
O	5 × 2 = 10	2 × 5 = 10	10 = 10, yes

The numbers of N and O atoms on either side of the equation are now equal, and so the equation is balanced.

? Exercise 5.1.1

Write a balanced equation for the decomposition of ammonium nitrate to form molecular nitrogen, molecular oxygen, and water. (Hint: Balance oxygen last, since it is present in more than one molecule on the right side of the equation.)

Answer

$$2\,NH_4NO_3 \rightarrow 2\,N_2 + O_2 + 4\,H_2O$$

It is sometimes convenient to use fractions instead of integers as intermediate coefficients in the process of balancing a chemical equation. When balance is achieved, all the equation's coefficients may then be multiplied by a whole number to convert the fractional coefficients to integers without upsetting the atom balance. For example, consider the reaction of ethane (C_2H_6) with oxygen to yield H_2O and CO_2, represented by the unbalanced equation:

$$C_2H_6 + O_2 \rightarrow H_2O + CO_2 \qquad \text{(unbalanced)}$$

Following the usual inspection approach, one might first balance C and H atoms by changing the coefficients for the two product species, as shown:

$$C_2H_6 + O_2 \rightarrow 3\,H_2O + 2\,CO_2 \qquad \text{(unbalanced)}$$

This results in seven O atoms on the product side of the equation, an odd number—no integer coefficient can be used with the O_2 reactant to yield an odd number, so a fractional coefficient, $\frac{7}{2}$, is used instead to yield a provisional balanced equation:

$$C_2H_6 + \tfrac{7}{2}\,O_2 \rightarrow 3\,H_2O + 2\,CO_2$$

A conventional balanced equation with integer-only coefficients is derived by multiplying each coefficient by 2:

$$2\,C_2H_6 + 7\,O_2 \rightarrow 6\,H_2O + 4\,CO_2 \tag{5.1.5}$$

Finally with regard to balanced equations, recall that convention dictates use of the *smallest whole-number coefficients*. Although the equation for the reaction between molecular nitrogen and molecular hydrogen to produce ammonia is, indeed, balanced,

$$3\,N_2 + 9\,H_2 \rightarrow 6\,NH_3 \tag{5.1.6}$$

the coefficients are not the smallest possible integers representing the relative numbers of reactant and product molecules. Dividing each coefficient by the greatest common factor, 3, gives the preferred equation:

$$N_2 + 3\,H_2 \rightarrow 2\,NH_3 \tag{5.1.7}$$

Additional Information in Chemical Equations

The physical states of reactants and products in chemical equations very often are indicated with a parenthetical abbreviation following the formulas. Common abbreviations include *s* for solids, *l* for liquids, *g* for gases, and *aq* for substances dissolved in water (*aqueous solutions*, as introduced in the preceding chapter). These notations are illustrated in the example equation here:

$$2\,Na\,(s) + 2\,H_2O\,(l) \rightarrow 2\,NaOH\,(aq) + H_2\,(g) \tag{5.1.8}$$

This equation represents the reaction that takes place when sodium metal is placed in water. The solid sodium reacts with liquid water to produce molecular hydrogen gas and the ionic compound sodium hydroxide (a solid in pure form, but readily dissolved in water).

Special conditions necessary for a reaction are sometimes designated by writing a word or symbol above or below the equation's arrow. For example, a reaction carried out by heating may be indicated by the uppercase Greek letter delta (Δ) over the arrow.

$$CaCO_3(s) \xrightarrow{\Delta} CaO(s) + CO_2(g) \tag{5.1.9}$$

Other examples of these special conditions will be encountered in more depth in later chapters.

Key Concepts and Summary

Chemical equations are symbolic representations of chemical and physical changes. Formulas for the substances undergoing the change (reactants) and substances generated by the change (products) are separated by an arrow and preceded by integer coefficients indicating their relative numbers. Balanced equations are those whose coefficients result in equal numbers of atoms for each element in the reactants and products. Chemical reactions in aqueous solution that involve ionic reactants or products may be represented more realistically by complete ionic equations and, more succinctly, by net ionic equations.

Glossary

balanced equation
chemical equation with equal numbers of atoms for each element in the reactant and product

chemical equation
symbolic representation of a chemical reaction

coefficient
number placed in front of symbols or formulas in a chemical equation to indicate their relative amount

complete ionic equation
chemical equation in which all dissolved ionic reactants and products, including spectator ions, are explicitly represented by formulas for their dissociated ions

molecular equation
chemical equation in which all reactants and products are represented as neutral substances

net ionic equation
chemical equation in which only those dissolved ionic reactants and products that undergo a chemical or physical change are represented (excludes spectator ions)

product
substance formed by a chemical or physical change; shown on the right side of the arrow in a chemical equation

reactant
substance undergoing a chemical or physical change; shown on the left side of the arrow in a chemical equation

spectator ion
ion that does not undergo a chemical or physical change during a reaction, but its presence is required to maintain charge neutrality

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

5.1: Writing and Balancing Chemical Reactions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.2: Writing and Balancing Chemical Equations** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

5.2: Precipitation Reactions

Learning Objectives

- Classify chemical reactions as precipitation reactions
- Predict the the products of precipitation reactions

Humans interact with one another in various and complex ways, and we classify these interactions according to common patterns of behavior. When two humans exchange information, we say they are communicating. When they exchange blows with their fists or feet, we say they are fighting. Faced with a wide range of varied interactions between chemical substances, scientists have likewise found it convenient (or even necessary) to classify chemical interactions by identifying common patterns of reactivity. This module will provide an introduction to three of the most prevalent types of chemical reactions: precipitation, acid-base, and oxidation-reduction.

Precipitation Reactions and Solubility Rules

A precipitation reaction is one in which dissolved substances react to form one (or more) solid products. Many reactions of this type involve the exchange of ions between ionic compounds in aqueous solution and are sometimes referred to as *double displacement*, *double replacement*, or *metathesis* reactions. These reactions are common in nature and are responsible for the formation of coral reefs in ocean waters and kidney stones in animals. They are used widely in industry for production of a number of commodity and specialty chemicals. Precipitation reactions also play a central role in many chemical analysis techniques, including spot tests used to identify metal ions and *gravimetric methods* for determining the composition of matter (see the last module of this chapter).

This unbalanced equation of a precipitation reaction has the general form of a double displacement:

$$\overset{\text{soluble}}{\widehat{\text{AC}}} + \overset{\text{soluble}}{\widehat{\text{BD}}} \rightarrow \underbrace{\text{AD}}_{\text{insoluble}} + \overset{\text{soluble}}{\widehat{\text{BC}}} \tag{5.2.1}$$

A vivid example of precipitation is observed when solutions of potassium iodide and lead nitrate are mixed, resulting in the formation of solid lead iodide:

$$2\,\text{KI}(aq) + \text{Pb}(\text{NO}_3)_2(aq) \rightarrow \text{PbI}_2(s) + 2\,\text{KNO}_3(aq) \tag{5.2.2}$$

This observation is consistent with the solubility guidelines in Table 4.5.1: The only insoluble compound among all those involved is lead iodide, one of the exceptions to the general solubility of iodide salts.

Lead iodide is a bright yellow solid that was formerly used as an artist's pigment known as iodine yellow (Figure 5.2.1). The properties of pure PbI_2 crystals make them useful for fabrication of X-ray and gamma ray detectors.



Figure 5.2.1: A precipitate of PbI_2 forms when solutions containing Pb^{2+} and I^- are mixed. (credit: Der Kreole/Wikimedia Commons)

The solubility guidelines in Table 4.5.1 may be used to predict whether a precipitation reaction will occur when solutions of soluble ionic compounds are mixed together. One merely needs to identify all the ions present in the solution and then consider if possible cation/anion pairing could result in an insoluble compound. For example, mixing solutions of silver nitrate and sodium fluoride will yield a solution containing Ag^+, NO_3^-, Na^+, and F^- ions. Aside from the two ionic compounds originally present in the solutions, $AgNO_3$ and NaF, two additional ionic compounds may be derived from this collection of ions: $NaNO_3$ and AgF. The solubility guidelines indicate all nitrate salts are soluble but that AgF is one of the exceptions to the general solubility of fluoride salts. A precipitation reaction, therefore, is predicted to occur, as described by the following equations:

$$\mathrm{NaF}(aq) + \mathrm{AgNO_3}(aq) \rightarrow \mathrm{AgF}(s) + \mathrm{NaNO_3}(aq) \quad \text{(molecular)} \tag{5.2.3}$$



Determining the Products for Precipitation Reactions: https://youtu.be/r0kYeZVuTAM

Example 5.2.1: Predicting Precipitation Reactions

Predict the result of mixing reasonably concentrated solutions of the following ionic compounds. If precipitation is expected, write a balanced equation for the reaction.

a. potassium sulfate and barium nitrate
b. lithium chloride and silver acetate
c. lead nitrate and ammonium carbonate

Solution

(a) The two possible products for this combination are KNO_3 and $BaSO_4$. The solubility guidelines indicate $BaSO_4$ is insoluble, and so a precipitation reaction is expected. The balance chemical reaction is,

$$K_2SO_4(aq) + Ba(NO_3)_2(aq) \rightarrow BaSO_4(s) + 2\,KNO_3(aq) \quad (5.2.4)$$

(b) The two possible products for this combination are $LiC_2H_3O_2$ and AgCl. The solubility guidelines indicate AgCl is insoluble, and so a precipitation reaction is expected. The balance chemical reaction is,

$$LiCl(aq) + AgC_2H_3O_2(aq) \rightarrow AgCl(s) + LiC_2H_3O_2(aq) \quad (5.2.5)$$

(c) The two possible products for this combination are $PbCO_3$ and NH_4NO_3. The solubility guidelines indicate $PbCO_3$ is insoluble, and so a precipitation reaction is expected. The balance chemical reaction is,

$$Pd(NO_3)_2(aq) + (NH_4)_2CO_3(aq) \rightarrow PbCO_3(s) + 2\,NH_4NO_3(aq) \quad (5.2.6)$$

? Exercise 5.2.1

Which solution could be used to precipitate the barium ion, Ba^{2+}, in a water sample: sodium chloride, sodium hydroxide, or sodium sulfate? What is the formula for the expected precipitate?

Answer

sodium sulfate, $BaSO_4$

Summary

A precipitation reaction is one in which dissolved substances react to form one (or more) solid products. Many reactions of this type involve the exchange of ions between ionic compounds in aqueous solution and are sometimes referred to as *double displacement*, *double replacement*, or *metathesis* reactions.

Glossary

precipitate

insoluble product that forms from reaction of soluble reactants

precipitation reaction

reaction that produces one or more insoluble products; when reactants are ionic compounds, sometimes called double-displacement or metathesis

soluble

of relatively high solubility; dissolving to a relatively large extent

solubility

the extent to which a substance may be dissolved in water, or any solvent

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

5.2: Precipitation Reactions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.3: Classifying Chemical Reactions** is licensed CC BY 4.0.
- **4.2: Precipitation Reactions** is licensed CC BY-NC-SA 3.0.

5.3: Representing aqueous reaction- Molecular, complete ionic, and net ionic equations

Learning

- Write and balance chemical equations in molecular, total ionic, and net ionic formats.

Given the abundance of water on earth, it stands to reason that a great many chemical reactions take place in aqueous media. When ions are involved in these reactions, the chemical equations may be written with various levels of detail appropriate to their intended use. To illustrate this, consider a reaction between ionic compounds taking place in an aqueous solution. When aqueous solutions of $\mathrm{CaCl_2}$ and $\mathrm{AgNO_3}$ are mixed, a reaction takes place producing aqueous $\mathrm{Ca(NO_3)_2}$ and solid AgCl:

$$\mathrm{CaCl_2}(aq) + 2\,\mathrm{AgNO_3}(aq) \rightarrow \mathrm{Ca(NO_3)_2}(aq) + 2\,\mathrm{AgCl}(s) \tag{5.3.1}$$

This balanced equation, derived in the usual fashion, is called a molecular equation because it doesn't explicitly represent the ionic species that are present in solution. When ionic compounds dissolve in water, they may *dissociate* into their constituent ions, which are subsequently dispersed homogenously throughout the resulting solution (a thorough discussion of this important process is provided in the chapter on solutions). Ionic compounds dissolved in water are, therefore, more realistically represented as dissociated ions, in this case:

$$\mathrm{CaCl_2}(aq) \rightarrow \mathrm{Ca^{2+}}(aq) + 2\,\mathrm{Cl^-}(aq) \tag{5.3.2}$$

$$2\,\mathrm{AgNO_3}(aq) \rightarrow 2\,\mathrm{Ag^+}(aq) + 2\,\mathrm{NO_3^-}(aq) \tag{5.3.3}$$

$$\mathrm{Ca(NO_3)_2}(aq) \rightarrow \mathrm{Ca^{2+}}(aq) + 2\,\mathrm{NO_3^-}(aq) \tag{5.3.4}$$

Unlike these three ionic compounds, AgCl does not dissolve in water to a significant extent, as signified by its physical state notation, *(s)*.

Explicitly representing all dissolved ions results in a complete ionic equation. In this particular case, the formulas for the dissolved ionic compounds are replaced by formulas for their dissociated ions:

$$\begin{aligned}\mathrm{Ca^{2+}}(aq) + 2\,\mathrm{Cl^-}(aq) + 2\,\mathrm{Ag^+}(aq) + 2\,\mathrm{NO_3^-}(aq) \\ \rightarrow \mathrm{Ca^{2+}}(aq) + 2\,\mathrm{NO_3^-}(aq) + 2\,\mathrm{AgCl}(s)\end{aligned} \tag{5.3.5}$$

Examining this equation shows that two chemical species are present in identical form on both sides of the arrow, $\mathrm{Ca^{2+}(aq)}$ and $\mathrm{NO_3^-}(aq)$. These spectator ions—ions whose presence is required to maintain charge neutrality—are neither chemically nor physically changed by the process, and so they may be eliminated from the equation to yield a more succinct representation called a net ionic equation:

$$\begin{aligned}\cancel{\mathrm{Ca^{2+}}(aq)} + 2\,\mathrm{Cl^-}(aq) + 2\,\mathrm{Ag^+}(aq) + \cancel{2\,\mathrm{NO_3^-}(aq)} \\ \rightarrow \cancel{\mathrm{Ca^{2+}}(aq)} + \cancel{2\,\mathrm{NO_3^-}(aq)} + 2\,\mathrm{AgCl}(s)\end{aligned} \tag{5.3.6}$$

$$2\,\mathrm{Cl^-}(aq) + 2\,\mathrm{Ag^+}(aq) \rightarrow 2\,\mathrm{AgCl}(s) \tag{5.3.7}$$

Following the convention of using the smallest possible integers as coefficients, this equation is then written:

$$\mathrm{Cl^-}(aq) + \mathrm{Ag^+}(aq) \rightarrow \mathrm{AgCl}(s) \tag{5.3.8}$$

This net ionic equation indicates that solid silver chloride may be produced from dissolved chloride and silver(I) ions, regardless of the source of these ions. These molecular and complete ionic equations provide additional information, namely, the ionic compounds used as sources of $\mathrm{Cl^-}$ and $\mathrm{Ag^+}$.

Example 5.3.1: Molecular and Ionic Equations

When carbon dioxide is dissolved in an aqueous solution of sodium hydroxide, the mixture reacts to yield aqueous sodium carbonate and liquid water. Write balanced molecular, complete ionic, and net ionic equations for this process.

Solution

Begin by identifying formulas for the reactants and products and arranging them properly in chemical equation form:

$$\mathrm{CO_2\,(aq) + NaOH\,(aq) \rightarrow Na_2CO_3\,(aq) + H_2O\,(l)} \qquad \textbf{(unbalanced)}$$

Balance is achieved easily in this case by changing the coefficient for NaOH to 2, resulting in the molecular equation for this reaction:

$$\mathrm{CO_2(aq) + 2\,NaOH(aq) \rightarrow Na_2CO_3\,(aq) + H_2O(\mathit{l})}$$

The two dissolved ionic compounds, NaOH and Na_2CO_3, can be represented as dissociated ions to yield the complete ionic equation:

$$\mathrm{CO_2\,(aq) + 2\,Na^+\,(aq) + 2\,OH^-\,(aq) \rightarrow 2\,Na^+\,(aq) + CO_3{}^{2-}\,(aq) + H_2O\,(l)}$$

Finally, identify the spectator ion(s), in this case $Na^+(aq)$, and remove it from each side of the equation to generate the net ionic equation:

$$\mathrm{CO_2(\mathit{aq}) + \cancel{2\,Na^+(\mathit{aq})} + 2\,OH^-(\mathit{aq}) \rightarrow \cancel{2\,Na^+(\mathit{aq})} + CO_3{}^{2-}(\mathit{aq}) + H_2O(\mathit{l})}$$
$$\mathrm{CO_2(\mathit{aq}) + 2\,OH^-(\mathit{aq}) \rightarrow CO_3{}^{2-}(\mathit{aq}) + H_2O(\mathit{l})}$$

? Exercise 5.3.1

Diatomic chlorine and sodium hydroxide (lye) are commodity chemicals produced in large quantities, along with diatomic hydrogen, via the electrolysis of brine, according to the following unbalanced equation:

$$\mathrm{NaCl\,(aq) + H_2O\,(l) \xrightarrow{electricity} NaOH\,(aq) + H_2\,(g) + Cl_2\,(g)}$$

Write balanced molecular, complete ionic, and net ionic equations for this process.

Answer

Balanced molecular equation:

Extra close brace or missing open brace

Balanced ionic equation:

Extra close brace or missing open brace

Balanced net ionic equation:

Extra close brace or missing open brace



Determining the Net Ionic Equation for a Precipitation Reaction: https://youtu.be/AMJz1Sdz8IA

Key Concepts and Summary

Chemical equations are symbolic representations of chemical and physical changes. Formulas for the substances undergoing the change (reactants) and substances generated by the change (products) are separated by an arrow and preceded by integer coefficients indicating their relative numbers. Balanced equations are those whose coefficients result in equal numbers of atoms for each element in the reactants and products. Chemical reactions in aqueous solution that involve ionic reactants or products may be represented more realistically by complete ionic equations and, more succinctly, by net ionic equations.

Glossary

Complete ionic equation

chemical equation in which all dissolved ionic reactants and products, including spectator ions, are explicitly represented by formulas for their dissociated ions

molecular equation

chemical equation in which all reactants and products are represented as neutral substances

net ionic equation

chemical equation in which only those dissolved ionic reactants and products that undergo a chemical or physical change are represented (excludes spectator ions)

spectator ion

ion that does not undergo a chemical or physical change during a reaction, but its presence is required to maintain charge neutrality

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

5.3: Representing aqueous reaction- Molecular, complete ionic, and net ionic equations is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.2: Writing and Balancing Chemical Equations** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

5.4: Neutralization Reactions and Gas Evolution

Learning Objectives

- Predict the products of an acid base reaction
- Write the net ionic equation of neutralization reaction

An acid-base reaction is one in which a hydrogen ion, H^+, is transferred from one chemical species to another. Such reactions are of central importance to numerous natural and technological processes, ranging from the chemical transformations that take place within cells and the lakes and oceans, to the industrial-scale production of fertilizers, pharmaceuticals, and other substances essential to society. The subject of acid-base chemistry, therefore, is worthy of thorough discussion, and a full chapter is devoted to this topic later in the text.

A **neutralization** reaction is a type of double displacement reaction where an acid reacts with a base to form water and salt. If the base is a metal hydroxide, then the general formula for the reaction of an acid with a base is described as follows:

$$acid + base \rightarrow salt + water \tag{5.4.1}$$

For example, the reaction of equimolar amounts of HBr and NaOH to give water and a salt (NaBr) is a neutralization reaction:

$$\underset{acid}{HBr(aq)} + \underset{base}{NaOH(aq)} \rightarrow \underset{water}{H_2O(l)} + \underset{salt}{NaBr(aq)} \tag{5.4.2}$$

Note that in addition to water, this reaction produces a salt, sodium bromide.

If we write the complete ionic equation for the reaction in Equation 5.4.1, we see that $Na^+_{(aq)}$ and $Br^-_{(aq)}$ are spectator ions and are not involved in the reaction:

$$H^+(aq) + \cancel{Br^-(aq)} + \cancel{Na^+(aq)} + OH^-(aq) \rightarrow H_2O(l) + \cancel{Na^+(aq)} + \cancel{Br^-(aq)}$$

The overall reaction is therefore simply the combination of H^+(aq) and OH^-(aq) to produce H_2O, as shown in the net ionic equation:

$$H^+(aq) + OH^-(aq) \rightarrow H_2O(l)$$

The net ionic equation for the reaction of any strong acid with any strong base is identical to Equation 5.4.4.



Acid/Base Neutralization Reactions & Net Ionic Equations: https://youtu.be/gDS93ySeF80

The strengths of the acid and the base generally determine whether the reaction goes to completion. The reaction of *any* strong acid with *any* strong base goes essentially to completion, as does the reaction of a strong acid with a weak base, and a weak acid with a strong base. Examples of the last two are as follows:

$$\underset{\text{strong acid}}{HCl(aq)} + \underset{\text{weak base}}{NH_3(aq)} \rightarrow \underset{\text{salt}}{NH_4Cl(aq)}$$

$$\underset{\text{weak acid}}{CH_3CO_2H(aq)} + \underset{\text{strong base}}{NaOH(aq)} \rightarrow \underset{\text{salt}}{CH_3CO_2Na(aq)} + H_2O(l)$$

Sodium acetate is written with the organic component first followed by the cation, as is usual for organic salts. Most reactions of a weak acid with a weak base also go essentially to completion. One example is the reaction of acetic acid with ammonia:

$$\underset{\text{weak acid}}{CH_3CO_2H(aq)} + \underset{\text{weak base}}{NH_3(aq)} \rightarrow \underset{\text{salt}}{CH_3CO_2NH_4(aq)}$$

An example of an acid–base reaction that does not go to completion is the reaction of a weak acid or a weak base with water, which is both an extremely weak acid and an extremely weak base.

In some cases, the reaction of an acid with an anion derived from a weak acid (such as HS^-) produces a gas (in this case, H_2S). Because the gaseous product escapes from solution in the form of bubbles, the reverse reaction cannot occur. Therefore, these reactions tend to be forced, or driven, to completion. Examples include reactions in which an acid is added to ionic compounds that contain the HCO_3^-, CN^-, or S^{2-} anions, all of which are driven to completion:

$$HCO_3^-(aq) + H^+(aq) \rightarrow H_2CO_3(aq)$$

$$H_2CO_3(aq) \rightarrow CO_2(g) + H_2O(l)$$

$$CN^-(aq) + H^+(aq) \rightarrow HCN(g)$$

$$S^{2-}(aq) + H^+(aq) \rightarrow HS^-(aq)$$

$$HS^-(aq) + H^+(aq) \rightarrow H_2S(g)$$

Example 5.4.1: Writing Equations for Acid-Base Reactions

Calcium propionate is used to inhibit the growth of molds in foods, tobacco, and some medicines. Write a balanced chemical equation for the reaction of aqueous propionic acid ($CH_3CH_2CO_2H$) with aqueous calcium hydroxide [$Ca(OH)_2$] to give calcium propionate. Do you expect this reaction to go to completion, making it a feasible method for the preparation of calcium propionate?

Solution

Given: reactants and product

Asked for: balanced chemical equation and whether the reaction will go to completion

Strategy:

Write the balanced chemical equation for the reaction of propionic acid with calcium hydroxide. Based on their acid and base strengths, predict whether the reaction will go to completion.

Solution:

Propionic acid is an organic compound that is a weak acid, and calcium hydroxide is an inorganic compound that is a strong base. The balanced chemical equation is as follows:

$$2CH_3CH_2CO_2H(aq) + Ca(OH)_2(aq) \rightarrow (CH_3CH_2CO_2)_2Ca(aq) + 2H_2O(l)$$

The reaction of a weak acid and a strong base will go to completion, so it is reasonable to prepare calcium propionate by mixing solutions of propionic acid and calcium hydroxide in a 2:1 mole ratio.

Exercise

Write a balanced chemical equation for the reaction of solid sodium acetate with dilute sulfuric acid to give sodium sulfate.

Answer: $2CH_3CO_2Na(s) + H_2SO_4(aq) \rightarrow Na_2SO_4(aq) + 2CH_3CO_2H(aq)$

? Exercise 5.4.1

Write balanced chemical equations for the acid-base reactions when a solution of barium hydroxide is neutralized with a solution of nitric acid

Answer

Ba(OH)2(aq)+2HNO3(aq)→Ba(NO3)2(aq)+2H2O(l)

Summary

Acid-base reactions involve the transfer of hydrogen ions between reactants.

Glossary

acid-base reaction

reaction involving the transfer of a hydrogen ion between reactant species

Neutralization reaction

reaction between an acid and a base to produce salt and water

salt

ionic compound that can be formed by the reaction of an acid with a base that contains a cation and an anion other than hydroxide or oxide

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).
- Anonymous

  Modified by Joshua Halpern (Howard University)

5.4: Neutralization Reactions and Gas Evolution is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.3: Classifying Chemical Reactions** is licensed CC BY 4.0.

5.5: Oxidation-Reduction reactions

Learning Objectives

- Predict the products of an oxidation reduction reaction.
- Assign the oxidation states for elements in compounds

Earth's atmosphere contains about 20% molecular oxygen, O_2, a chemically reactive gas that plays an essential role in the metabolism of aerobic organisms and in many environmental processes that shape the world. The term oxidation was originally used to describe chemical reactions involving O_2, but its meaning has evolved to refer to a broad and important reaction class known as *oxidation-reduction (redox) reactions*. A few examples of such reactions will be used to develop a clear picture of this classification.

Some redox reactions involve the transfer of electrons between reactant species to yield ionic products, such as the reaction between sodium and chlorine to yield sodium chloride:

$$2\,\mathrm{Na}(s) + \mathrm{Cl_2}(g) \rightarrow 2\,\mathrm{NaCl}(s) \tag{5.5.1}$$

It is helpful to view the process with regard to each individual reactant, that is, to represent the fate of each reactant in the form of an equation called a half-reaction:

$$2\,\mathrm{Na}(s) \rightarrow 2\,\mathrm{Na^+}(s) + 2\,\mathrm{e^-}$$
$$\mathrm{Cl_2}(g) + 2\,\mathrm{e^-} \rightarrow 2\,\mathrm{Cl^-}(s)$$

These equations show that Na atoms *lose electrons* while Cl atoms (in the Cl_2 molecule) *gain electrons*, the "*s*" subscripts for the resulting ions signifying they are present in the form of a solid ionic compound. For redox reactions of this sort, the loss and gain of electrons define the complementary processes that occur:

$$\textbf{oxidation} = \text{loss of electrons} \tag{5.5.2}$$
$$\textbf{reduction} = \text{gain of electrons} \tag{5.5.3}$$

In this reaction, then, sodium is *oxidized* and chlorine undergoes reduction. Viewed from a more active perspective, sodium functions as a reducing agent (reductant), since it provides electrons to (or reduces) chlorine. Likewise, chlorine functions as an oxidizing agent (oxidant), as it effectively removes electrons from (oxidizes) sodium.

$$\textbf{reducing agent} = \text{species that is oxidized} \tag{5.5.4}$$
$$\textbf{oxidizing agent} = \text{species that is reduced} \tag{5.5.5}$$

Some redox processes, however, do not involve the transfer of electrons. Consider, for example, a reaction similar to the one yielding NaCl:

$$\mathrm{H_2}(g) + \mathrm{Cl_2}(g) \rightarrow 2\,\mathrm{HCl}(g) \tag{5.5.6}$$

The product of this reaction is a covalent compound, so transfer of electrons in the explicit sense is not involved. To clarify the similarity of this reaction to the previous one and permit an unambiguous definition of redox reactions, a property called *oxidation number* has been defined. The oxidation number (or oxidation state) of an element in a compound is the charge its atoms would possess *if the compound was ionic*. The following guidelines are used to assign oxidation numbers to each element in a molecule or ion.

1. The oxidation number of an atom in an elemental substance is zero.
2. The oxidation number of a monatomic ion is equal to the ion's charge.
3. Oxidation numbers for common nonmetals are usually assigned as follows:
   - Hydrogen: +1 when combined with nonmetals, −1 when combined with metals
   - Oxygen: −2 in most compounds, sometimes −1 (so-called peroxides, $\mathrm{O_2^{2-}}$), very rarely $-\frac{1}{2}$ (so-called superoxides, $\mathrm{O_2^-}$), positive values when combined with F (values vary)
   - Halogens: −1 for F always, −1 for other halogens except when combined with oxygen or other halogens (positive oxidation numbers in these cases, varying values)

4. The sum of oxidation numbers for all atoms in a molecule or polyatomic ion equals the charge on the molecule or ion.

Note: The proper convention for reporting charge is to write the number first, followed by the sign (e.g., 2+), while oxidation number is written with the reversed sequence, sign followed by number (e.g., +2). This convention aims to emphasize the distinction between these two related properties.

Example 5.5.1: Assigning Oxidation Numbers

Follow the guidelines in this section of the text to assign oxidation numbers to all the elements in the following species:

a. H_2S
b. SO_3^{2-}
c. Na_2SO_4

Solution

(a) According to guideline 1, the oxidation number for H is +1.

Using this oxidation number and the compound's formula, guideline 4 may then be used to calculate the oxidation number for sulfur:

$$\text{charge on } H_2S = 0 = (2 \times +1) + (1 \times x)$$

$$x = 0 - (2 \times +1) = -2$$

(b) Guideline 3 suggests the oxidation number for oxygen is −2.

Using this oxidation number and the ion's formula, guideline 4 may then be used to calculate the oxidation number for sulfur:

$$\text{charge on } SO_3^{2-} = -2 = (3 \times -2) + (1 \times x)$$

$$x = -2 - (3 \times -2) = +4$$

(c) For ionic compounds, it's convenient to assign oxidation numbers for the cation and anion separately.

According to guideline 2, the oxidation number for sodium is +1.

Assuming the usual oxidation number for oxygen (−2 per guideline 3), the oxidation number for sulfur is calculated as directed by guideline 4:

$$\text{charge on } SO_4^{2-} = -2 = (4 \times -2) + (1 \times x)$$

$$x = -2 - (4 \times -2) = +6$$

Exercise 5.5.1

Assign oxidation states to the elements whose atoms are underlined in each of the following compounds or ions:

a. $K\underline{N}O_3$
b. $\underline{Al}H_3$
c. $\underline{N}H_4^+$
d. msubsup

Answer a

N, +5

Answer b

Al, +3

Answer c

N, −3

Answer d

P, +5

Using the oxidation number concept, an all-inclusive definition of redox reaction has been established. Oxidation-reduction (redox) reactions are those in which one or more elements involved undergo a change in oxidation number. While the vast majority of redox reactions involve changes in oxidation number for two or more elements, a few interesting exceptions to this rule do exist as shown below\). Definitions for the complementary processes of this reaction class are correspondingly revised as shown here:

$$\textbf{oxidation} = \textbf{increase in oxidation number} \tag{5.5.7}$$

$$\textbf{reduction} = \textbf{decrease in oxidation number} \tag{5.5.8}$$

Returning to the reactions used to introduce this topic, they may now both be identified as redox processes. In the reaction between sodium and chlorine to yield sodium chloride, sodium is oxidized (its oxidation number increases from 0 in Na to +1 in NaCl) and chlorine is reduced (its oxidation number decreases from 0 in Cl_2 to −1 in NaCl). In the reaction between molecular hydrogen and chlorine, hydrogen is oxidized (its oxidation number increases from 0 in H_2 to +1 in HCl) and chlorine is reduced (its oxidation number decreases from 0 in Cl_2 to −1 in HCl).

Several subclasses of redox reactions are recognized, including combustion reactions in which the reductant (also called a *fuel*) and oxidant (often, but not necessarily, molecular oxygen) react vigorously and produce significant amounts of heat, and often light, in the form of a flame. Solid rocket-fuel reactions such as the one depicted below are combustion processes. A typical propellant reaction in which solid aluminum is oxidized by ammonium perchlorate is represented by this equation:

$$10\,Al(s) + 6\,NH_4ClO_4(s) \rightarrow 4\,Al_2O_3(s) + 2\,AlCl_3(s) + 12\,H_2O(g) + 3\,N_2(g) \tag{5.5.9}$$

Watch a brief video showing the test firing of a small-scale, prototype, hybrid rocket engine planned for use in the new Space Launch System being developed by NASA. The first engines firing at 3 s (green flame) use a liquid fuel/oxidant mixture, and the second, more powerful engines firing at 4 s (yellow flame) use a solid mixture.



Single-displacement (replacement) reactions are redox reactions in which an ion in solution is displaced (or replaced) via the oxidation of a metallic element. One common example of this type of reaction is the acid oxidation of certain metals:

$$Zn(s) + 2\,HCl(aq) \rightarrow ZnCl_2(aq) + H_2(g) \tag{5.5.10}$$

Metallic elements may also be oxidized by solutions of other metal salts; for example:

$$Cu(s) + 2\,AgNO_3(aq) \rightarrow Cu(NO_3)_2(aq) + 2\,Ag(s) \tag{5.5.11}$$

This reaction may be observed by placing copper wire in a solution containing a dissolved silver salt. Silver ions in solution are reduced to elemental silver at the surface of the copper wire, and the resulting Cu^{2+} ions dissolve in the solution to yield a characteristic blue color (Figure **5.5.1**).




Figure 5.5.1: (a) A copper wire is shown next to a solution containing silver(I) ions. (b) Displacement of dissolved silver ions by copper ions results in (c) accumulation of gray-colored silver metal on the wire and development of a blue color in the solution, due to dissolved copper ions. (credit: modification of work by Mark Ott)

Example 5.5.1: Describing Redox Reactions

Identify which equations represent redox reactions, providing a name for the reaction if appropriate. For those reactions identified as redox, name the oxidant and reductant.

a. $\mathrm{ZnCO_3}(s) \rightarrow \mathrm{ZnO}(s) + \mathrm{CO_2}(g)$
b. $2\,\mathrm{Ga}(l) + 3\,\mathrm{Br_2}(l) \rightarrow 2\,\mathrm{GaBr_3}(s)$
c. $2\,\mathrm{H_2O_2}(aq) \rightarrow 2\,\mathrm{H_2O}(l) + \mathrm{O_2}(g)$
d. $\mathrm{BaCl_2}(aq) + \mathrm{K_2SO_4}(aq) \rightarrow \mathrm{BaSO_4}(s) + 2\,\mathrm{KCl}(aq)$
e. $\mathrm{C_2H_4}(g) + 3\,\mathrm{O_2}(g) \rightarrow 2\,\mathrm{CO_2}(g) + 2\,\mathrm{H_2O}(l)$

Solution

Redox reactions are identified per definition if one or more elements undergo a change in oxidation number.

a. This is not a redox reaction, since oxidation numbers remain unchanged for all elements.
b. This is a redox reaction. Gallium is oxidized, its oxidation number increasing from 0 in Ga(l) to +3 in $GaBr_3$(s). The reducing agent is Ga(l). Bromine is reduced, its oxidation number decreasing from 0 in Br_2(l) to −1 in $GaBr_3$(s). The oxidizing agent is Br_2(l).
c. This is a redox reaction. It is a particularly interesting process, as it involves the same element, oxygen, undergoing both oxidation and reduction (a so-called *disproportionation reaction)*. Oxygen is oxidized, its oxidation number increasing from −1 in H_2O_2(aq) to 0 in O_2(g). Oxygen is also reduced, its oxidation number decreasing from −1 in H_2O_2(aq) to −2 in H_2O(l). For disproportionation reactions, the same substance functions as an oxidant and a reductant.
d. This is not a redox reaction, since oxidation numbers remain unchanged for all elements.
e. This is a redox reaction (combustion). Carbon is oxidized, its oxidation number increasing from −2 in C_2H_4(g) to +4 in CO_2(g). The reducing agent (fuel) is C_2H_4(g). Oxygen is reduced, its oxidation number decreasing from 0 in O_2(g) to −2 in H_2O(l). The oxidizing agent is O_2(g).

Exercise 5.5.1

This equation describes the production of tin(II) chloride:

$$\mathrm{Sn}(s) + 2\,\mathrm{HCl}(g) \rightarrow \mathrm{SnCl_2}(s) + \mathrm{H_2}(g)$$

Is this a redox reaction? If so, provide a more specific name for the reaction if appropriate, and identify the oxidant and reductant.

Answer

Yes, a single-replacement reaction. Sn(s) is the reductant, HCl(g) is the oxidant.



Redox Reactions: https://youtu.be/1v3yaaR_nHc

Summary

The term oxidation was originally used to describe chemical reactions involving O2, but its meaning has evolved to refer to a broad and important reaction class known as oxidation-reduction (redox) reactions. A few examples of such reactions will be used to develop a clear picture of this classification.

Glossary

oxidation

process in which an element's oxidation number is increased by loss of electrons

oxidation-reduction reaction

(also, redox reaction) reaction involving a change in oxidation number for one or more reactant elements

oxidation number

(also, oxidation state) the charge each atom of an element would have in a compound if the compound were ionic

oxidizing agent

(also, oxidant) substance that brings about the oxidation of another substance, and in the process becomes reduced

reduction

process in which an element's oxidation number is decreased by gain of electrons

reducing agent

(also, reductant) substance that brings about the reduction of another substance, and in the process becomes oxidized

single-displacement reaction

(also, replacement) redox reaction involving the oxidation of an elemental substance by an ionic species

---

5.5: Oxidation-Reduction reactions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.3: Classifying Chemical Reactions** is licensed CC BY 4.0.

5.6: Balancing Redox Reactions

Learning Objectives

- Balance redox reaction using half-reaction

Redox reactions that take place in aqueous media often involve water, hydronium ions, and hydroxide ions as reactants or products. Although these species are not oxidized or reduced, they do participate in chemical change in other ways (e.g., by providing the elements required to form oxyanions). Equations representing these reactions are sometimes very difficult to balance by inspection, so systematic approaches have been developed to assist in the process. One very useful approach is to use the method of half-reactions, which involves the following steps:

1. Write the two half-reactions representing the redox process.
2. Balance all elements except oxygen and hydrogen.
3. Balance oxygen atoms by adding H_2O molecules.
4. Balance hydrogen atoms by adding H^+ ions.
5. Balance charge by adding electrons.
6. If necessary, multiply each half-reaction's coefficients by the smallest possible integers to yield equal numbers of electrons in each.
7. Add the balanced half-reactions together and simplify by removing species that appear on both sides of the equation.
8. For reactions occurring in basic media (excess hydroxide ions), carry out these additional steps:
   - Add OH^- ions to both sides of the equation in numbers equal to the number of H^+ ions.
   - On the side of the equation containing both H^+ and OH^- ions, combine these ions to yield water molecules.
   - Simplify the equation by removing any redundant water molecules.
9. Finally, check to see that both the number of atoms and the total charges are balanced.

Example 5.6.1: Balancing Redox Reactions in Acidic Solution

Write a balanced equation for the reaction between dichromate ion and iron(II) to yield iron(III) and chromium(III) in acidic solution.

$$\mathrm{Cr_2O_7^{2-} + Fe^{2+} \rightarrow Cr^{3+} + Fe^{3+}}$$

Solution

Write the two half-reactions.

Each half-reaction will contain one reactant and one product with one element in common.

$$\mathrm{Fe^{2+} \rightarrow Fe^{3+}}$$
$$\mathrm{Cr_2O_7^{2-} \rightarrow Cr^{3+}}$$

Balance all elements except oxygen and hydrogen. The iron half-reaction is already balanced, but the chromium half-reaction shows two Cr atoms on the left and one Cr atom on the right. Changing the coefficient on the right side of the equation to 2 achieves balance with regard to Cr atoms.

$$\mathrm{Fe^{2+} \rightarrow Fe^{3+}}$$
$$\mathrm{Cr_2O_7^{2-} \rightarrow 2\,Cr^{3+}}$$

Balance oxygen atoms by adding H_2O *molecules.* The iron half-reaction does not contain O atoms. The chromium half-reaction shows seven O atoms on the left and none on the right, so seven water molecules are added to the right side.

$$\mathrm{Fe^{2+} \rightarrow Fe^{3+}}$$
$$\mathrm{Cr_2O_7^{2-} \rightarrow 2\,Cr^{3+} + 7\,H_2O}$$

Balance hydrogen atoms by adding H^+*ions.* The iron half-reaction does not contain H atoms. The chromium half-reaction shows 14 H atoms on the right and none on the left, so 14 hydrogen ions are added to the left side.

$$\mathrm{Fe^{2+} \rightarrow Fe^{3+}}$$
$$\mathrm{Cr_2O_7^{2-} + 14\,H^+ \rightarrow 2\,Cr^{3+} + 7\,H_2O}$$

Balance charge by adding electrons. The iron half-reaction shows a total charge of 2+ on the left side (1 Fe^{2+} ion) and 3+ on the right side (1 Fe^{3+} ion). Adding one electron to the right side bring that side's total charge to (3+) + (1−) = 2+, and charge balance is achieved.

The chromium half-reaction shows a total charge of (1 × 2−) + (14 × 1+) = 12+ on the left side ($1\,Cr_2O_7^{2-}$ ion and 14 H^+ ions). The total charge on the right side is (2 × 3+) = 6 + (2 Cr^{3+} ions). Adding six electrons to the left side will bring that side's total charge to (12+ + 6−) = 6+, and charge balance is achieved.

$$\mathrm{Fe^{2+} \rightarrow Fe^{3+} + e^-}$$
$$\mathrm{Cr_2O_7^{2-} + 14\,H^+ + 6\,e^- \rightarrow 2\,Cr^{3+} + 7\,H_2O}$$

Multiply the two half-reactions so the number of electrons in one reaction equals the number of electrons in the other reaction. To be consistent with mass conservation, and the idea that redox reactions involve the transfer (not creation or destruction) of electrons, the iron half-reaction's coefficient must be multiplied by 6.

$$\mathrm{6\,Fe^{2+} \rightarrow 6\,Fe^{3+} + 6\,e^-}$$
$$\mathrm{Cr_2O_7^{2-} + 6\,e^- + 14\,H^+ \rightarrow 2\,Cr^{3+} + 7\,H_2O}$$

Add the balanced half-reactions and cancel species that appear on both sides of the equation.

$$\mathrm{6\,Fe^{2+} + Cr_2O_7^{2-} + 6\,e^- + 14\,H^+ \rightarrow 6\,Fe^{3+} + 6\,e^- + 2\,Cr^{3+} + 7\,H_2O} \quad (5.6.1)$$

Only the six electrons are redundant species. Removing them from each side of the equation yields the simplified, balanced equation here:

$$\mathrm{6\,Fe^{2+} + Cr_2O_7^{2-} + 14\,H^+ \rightarrow 6\,Fe^{3+} + 2\,Cr^{3+} + 7\,H_2O} \quad (5.6.2)$$

A final check of atom and charge balance confirms the equation is balanced.

	Reactants	Products
Fe	6	6
Cr	2	2
O	7	7
H	14	14
charge	24+	24+

? Exercise 5.6.1

In acidic solution, hydrogen peroxide reacts with Fe^{2+} to produce Fe^{3+} and H_2O. Write a balanced equation for this reaction.

Answer

$$\mathrm{H_2O_2}(aq) + \mathrm{2\,H^+}(aq) + \mathrm{2\,Fe^{2+} \rightarrow 2\,H_2O}(l) + \mathrm{2\,Fe^{3+}}$$



Balancing a Redox Reaction in Acidic Conditions: https://youtu.be/IB-fWLsI0lc

Summary

Chemical reactions are classified according to similar patterns of behavior. A large number of important reactions are included in three categories: precipitation, acid-base, and oxidation-reduction (redox). Precipitation reactions involve the formation of one or more insoluble products. Acid-base reactions involve the transfer of hydrogen ions between reactants. Redox reactions involve a change in oxidation number for one or more reactant elements. Writing balanced equations for some redox reactions that occur in aqueous solutions is simplified by using a systematic approach called the half-reaction method.

Glossary

half-reaction

an equation that shows whether each reactant loses or gains electrons in a reaction.

5.6: Balancing Redox Reactions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.3: Classifying Chemical Reactions** is licensed CC BY 4.0.

5.7: End of Chapter Problems

1. What does it mean to say an equation is balanced? Why is it important for an equation to be balanced?

Answer

An equation is balanced when the same number of each element is represented on the reactant and product sides. Equations must be balanced to accurately reflect the law of conservation of matter.

2. Consider molecular, complete ionic, and net ionic equations. What is the difference between these types of equations? In what circumstance would the complete and net ionic equations for a reaction be identical?
3. Balance the following equations:
   a. $\mathrm{PCl_5}(s) + \mathrm{H_2O}(l) \rightarrow \mathrm{POCl_3}(l) + \mathrm{HCl}(aq)$
   b. $\mathrm{Cu}(s) + \mathrm{HNO_3}(aq) \rightarrow \mathrm{Cu(NO_3)_2}(aq) + \mathrm{H_2O}(l) + \mathrm{NO}(g)$
   c. $\mathrm{H_2}(g) + \mathrm{I_2}(s) \rightarrow \mathrm{HI}(s)$
   d. $\mathrm{Fe}(s) + \mathrm{O_2}(g) \rightarrow \mathrm{Fe_2O_3}(s)$
   e. $\mathrm{Na}(s) + \mathrm{H_2O}(l) \rightarrow \mathrm{NaOH}(aq) + \mathrm{H_2}(g)$
   f. $\mathrm{(NH_4)_2Cr_2O_7}(s) \rightarrow \mathrm{Cr_2O_3}(s) + \mathrm{N_2}(g) + \mathrm{H_2O}(g)$
   g. $\mathrm{P_4}(s) + \mathrm{Cl_2}(g) \rightarrow \mathrm{PCl_3}(l)$
   h. $\mathrm{PtCl_4}(s) \rightarrow \mathrm{Pt}(s) + \mathrm{Cl_2}(g)$

Answer

a. $\mathrm{PCl_5}(s) + \mathrm{H_2O}(l) \rightarrow \mathrm{POCl_3}(l) + 2\,\mathrm{HCl}(aq)$;b. $3\,\mathrm{Cu}(s) + 8\,\mathrm{HNO_3}(aq) \rightarrow 3\,\mathrm{Cu(NO_3)_2}(aq) + 4\,\mathrm{H_2O}(l) + 2\,\mathrm{NO}(g)$; c. $\mathrm{H_2}(g) + \mathrm{I_2}(s) \rightarrow 2\,\mathrm{HI}(s)$; d. $4\,\mathrm{Fe}(s) + 3\,\mathrm{O_2}(g) \rightarrow 2\,\mathrm{Fe_2O_3}(s)$; e. $2\,\mathrm{Na}(s) + 2\,\mathrm{H_2O}(l) \rightarrow 2\,\mathrm{NaOH}(aq) + \mathrm{H_2}(g)$; f. $\mathrm{(NH_4)_2Cr_{52}O_7}(s) \rightarrow \mathrm{Cr_2O_3}(s) + \mathrm{N_2}(g) + 4\,\mathrm{H_2O}(g)$; g. $\mathrm{P_4}(s) + 6\,\mathrm{Cl_2}(g) \rightarrow 4\,\mathrm{PCl_3}(l)$; h. $\mathrm{PtCl_4}(s) \rightarrow \mathrm{Pt}(s) + 2\,\mathrm{Cl_2}(g)$

4. Balance the following equations:
   a. $\mathrm{Ag}(s) + \mathrm{H_2S}(g) + \mathrm{O_2}(g) \rightarrow \mathrm{Ag_2S}(s) + \mathrm{H_2O}(l)$
   b. $\mathrm{P_4}(s) + \mathrm{O_2}(g) \rightarrow \mathrm{P_4O_{10}}(s)$
   c. $\mathrm{Pb}(s) + \mathrm{H_2O}(l) + \mathrm{O_2}(g) \rightarrow \mathrm{Pb(OH)_2}(s)$
   d. $\mathrm{Fe}(s) + \mathrm{H_2O}(l) \rightarrow \mathrm{Fe_3O_4}(s) + \mathrm{H_2}(g)$
   e. $\mathrm{Sc_2O_3}(s) + \mathrm{SO_3}(l) \rightarrow \mathrm{Sc_2(SO_4)_3}(s)$
   f. $\mathrm{Ca_3(PO_4)_2}(aq) + \mathrm{H_3PO_4}(aq) \rightarrow \mathrm{Ca(H_2PO_4)_2}(aq)$
   g. $\mathrm{Al}(s) + \mathrm{H_2SO_4}(aq) \rightarrow \mathrm{Al_2(SO_4)_3}(s) + \mathrm{H_2}(g)$
   h. $\mathrm{TiCl_4}(s) + \mathrm{H_2O}(g) \rightarrow \mathrm{TiO_2}(s) + \mathrm{HCl}(g)$

Answer

a. $4\,\mathrm{Ag}(s) + 2\,\mathrm{H_2S}(g) + \mathrm{O_2}(g) \rightarrow 2\,\mathrm{Ag_2S}(s) + 2\,\mathrm{H_2O}(l)$; b. $\mathrm{P_4}(s) + 5\,\mathrm{O_2}(g) \rightarrow \mathrm{P_4O_{10}}(s)$; c. $2\,\mathrm{Pb}(s) + 2\,\mathrm{H_2O}(l) + \mathrm{O_2}(g) \rightarrow 2\,\mathrm{Pb(OH)_2}(s)$; d. $3\,\mathrm{Fe}(s) + 4\,\mathrm{H_2O}(l) \rightarrow \mathrm{Fe_3O_4}(s) + 4\,\mathrm{H_2}(g)$; e. $\mathrm{Sc_2O_3}(s) + 3\,\mathrm{SO_3}(l) \rightarrow \mathrm{Sc_2(SO_4)_3}(s)$; f. $\mathrm{Ca_3(PO_4)_2}(aq) + 4\,\mathrm{H_3PO_4}(aq) \rightarrow 3\,\mathrm{Ca(H_2PO_4)_2}(aq)$; g. $2\,\mathrm{Al}(s) + 3\,\mathrm{H_2SO_4}(aq) \rightarrow \mathrm{Al_2(SO_4)_3}(s) + 3\,\mathrm{H_2}(g)$; h. $\mathrm{TiCl_4}(s) + 2\,\mathrm{H_2O}(g) \rightarrow \mathrm{TiO_2}(s) + 4\,\mathrm{HCl}(g)$

5. Write a balanced molecular equation describing each of the following chemical reactions.
   a. Solid calcium carbonate is heated and decomposes to solid calcium oxide and carbon dioxide gas.
   b. Gaseous butane, $\mathrm{C_4H_{10}}$, reacts with diatomic oxygen gas to yield gaseous carbon dioxide and water vapor.
   c. Aqueous solutions of magnesium chloride and sodium hydroxide react to produce solid magnesium hydroxide and aqueous sodium chloride.
   d. Water vapor reacts with sodium metal to produce solid sodium hydroxide and hydrogen gas.

Answer

a. $\mathrm{CaCO_3}(s) \rightarrow \mathrm{CaO}(s) + \mathrm{CO_2}(g)$; b. $2\,\mathrm{C_4H_{10}}(g) + 13\,\mathrm{O_2}(g) \rightarrow 8\,\mathrm{CO_2}(g) + 10\,\mathrm{H_2O}(g)$; c. $\mathrm{MgCl_2}(aq) + 2\,\mathrm{NaOH}(aq) \rightarrow \mathrm{Mg(OH)_2}(s) + 2\,\mathrm{NaCl}(aq)$; d. $2\,\mathrm{H_2O}(g) + 2\,\mathrm{Na}(s) \rightarrow 2\,\mathrm{NaOH}(s) + \mathrm{H_2}(g)$


6. Write a balanced equation describing each of the following chemical reactions.
   a. Solid potassium chlorate, $KClO_3$, decomposes to form solid potassium chloride and diatomic oxygen gas.
   b. Solid aluminum metal reacts with solid diatomic iodine to form solid Al_2I_6.
   c. When solid sodium chloride is added to aqueous sulfuric acid, hydrogen chloride gas and aqueous sodium sulfate are produced.
   d. Aqueous solutions of phosphoric acid and potassium hydroxide react to produce aqueous potassium dihydrogen phosphate and liquid water.

7. Colorful fireworks often involve the decomposition of barium nitrate and potassium chlorate and the reaction of the metals magnesium, aluminum, and iron with oxygen.
   a. Write the formulas of barium nitrate and potassium chlorate.
   b. The decomposition of solid potassium chlorate leads to the formation of solid potassium chloride and diatomic oxygen gas. Write an equation for the reaction.
   c. The decomposition of solid barium nitrate leads to the formation of solid barium oxide, diatomic nitrogen gas, and diatomic oxygen gas. Write an equation for the reaction.
   d. Write separate equations for the reactions of the solid metals magnesium, aluminum, and iron with diatomic oxygen gas to yield the corresponding metal oxides. (Assume the iron oxide contains Fe^{3+} ions.)

Answer

a. $Ba(NO_3)_2$, $KClO_3$; b. $\mathbf{2\,KClO_3(s) \rightarrow 2\,KCl(s) + 3\,O_2(g)}$; c. $\mathbf{2\,Ba(NO_3)_2(s) \rightarrow 2\,BaO(s) + 2\,N_2(g) + 5\,O_2(g)}$; d. $\mathbf{2\,Mg(s) + O_2(g) \rightarrow 2\,MgO(s)}$; $\mathbf{4\,Al(s) + 3\,O_2(g) \rightarrow 2\,Al_2O_3(g)}$; $\mathbf{4\,Fe(s) + 3\,O_2(g) \rightarrow 2\,Fe_2O_3(s)}$

8. Fill in the blank with a single chemical formula for a covalent compound that will balance the equation:



9. Aqueous hydrogen fluoride (hydrofluoric acid) is used to etch glass and to analyze minerals for their silicon content. Hydrogen fluoride will also react with sand (silicon dioxide).
   a. Write an equation for the reaction of solid silicon dioxide with hydrofluoric acid to yield gaseous silicon tetrafluoride and liquid water.
   b. The mineral fluorite (calcium fluoride) occurs extensively in Illinois. Solid calcium fluoride can also be prepared by the reaction of aqueous solutions of calcium chloride and sodium fluoride, yielding aqueous sodium chloride as the other product. Write complete and net ionic equations for this reaction.

Answer

a. 4HF(aq)+SiO2(s)→SiF4(g)+2H2O(l)4HF(aq)+SiO2(s)→SiF4(g)+2H2O(l); b. complete ionic equation: 2Na+(aq)+2F−(aq)+Ca2+(aq)+2Cl−(aq)→CaF2(s)+2Na+(aq)+2Cl−(aq)2Na+(aq)+2F−(aq)+Ca2+(aq)+2Cl−(aq)→CaF2(s)+2Na+(aq)+2Cl−(aq), net ionic equation: 2F−(aq)+Ca2+(aq)→CaF2(s)

10. $\mathbf{4\,HF(aq) + SiO_2(s) \rightarrow SiF_4(g) + 2\,H_2O(l)}$;
    a. complete ionic equation: $\mathbf{2\,Na^+(aq) + 2\,F^-(aq) + Ca^{2+}(aq) + 2\,Cl^-(aq) \rightarrow CaF_2(s) + 2\,Na^+(aq) + 2\,Cl^-(aq)}$, net ionic equation: $\mathbf{2\,F^-(aq) + Ca^{2+}(aq) \rightarrow CaF_2(s)}$
    b. A novel process for obtaining magnesium from sea water involves several reactions. Write a balanced chemical equation for each step of the process.
    c. The first step is the decomposition of solid calcium carbonate from seashells to form solid calcium oxide and gaseous carbon dioxide.
    d. The second step is the formation of solid calcium hydroxide as the only product from the reaction of the solid calcium oxide with liquid water.

e. Solid calcium hydroxide is then added to the seawater, reacting with dissolved magnesium chloride to yield solid magnesium hydroxide and aqueous calcium chloride.
f. The solid magnesium hydroxide is added to a hydrochloric acid solution, producing dissolved magnesium chloride and liquid water.
g. Finally, the magnesium chloride is melted and electrolyzed to yield liquid magnesium metal and diatomic chlorine gas.

11. From the balanced molecular equations, write the complete ionic and net ionic equations for the following:

a. $\mathrm{K_2C_2O_4}(aq) + \mathrm{Ba(OH)_2}(aq) \rightarrow 2\,\mathrm{KOH}(aq) + \mathrm{BaC_2O_2}(s)$
b. $\mathrm{Pb(NO_3)_2}(aq) + \mathrm{H_2SO_4}(aq) \rightarrow \mathrm{PbSO_4}(s) + 2\,\mathrm{HNO_3}(aq)$
c. $\mathrm{CaCO_3}(s) + \mathrm{H_2SO_4}(aq) \rightarrow \mathrm{CaSO_4}(s) + \mathrm{CO_2}(g) + \mathrm{H_2O}(l)$

Answer

a.

$$2\,\mathrm{K^+}(aq) + \mathrm{C_2O_4^{2-}}(aq) + \mathrm{Ba^{2+}}(aq) + 2\,\mathrm{OH^-}(aq) \rightarrow 2\,\mathrm{K^+}(aq) + 2\,\mathrm{OH^-}(aq) + \mathrm{BaC_2O_4}(s) \quad \text{(complete)} \tag{5.7.1}$$

$$\mathrm{Ba^{2+}}(aq) + \mathrm{C_2O_4^{2-}}(aq) \rightarrow \mathrm{BaC_2O_4}(s) \quad \text{(net)} \tag{5.7.2}$$

; b.

$$\mathrm{Pb^{2+}}(aq) + 2\,\mathrm{NO_3^-}(aq) + 2\,\mathrm{H^+}(aq) + \mathrm{SO_4^{2-}}(aq) \rightarrow \mathrm{PbSO_4}(s) + 2\,\mathrm{H^+}(aq) + 2\,\mathrm{NO_3^-}(aq) \quad \text{(complete)} \tag{5.7.3}$$

$$\mathrm{Pb^{2+}}(aq) + \mathrm{SO_4^{2-}}(aq) \rightarrow \mathrm{PbSO_4}(s) \quad \text{(net)} \tag{5.7.4}$$

; c.

$$\mathrm{CaCO_3}(s) + 2\,\mathrm{H^+}(aq) + \mathrm{SO_4^{2-}}(aq) \rightarrow \mathrm{CaSO_4}(s) + \mathrm{CO_2}(g) + \mathrm{H_2O}(l) \quad \text{(complete)} \tag{5.7.5}$$

$$\mathrm{CaCO_3}(s) + 2\,\mathrm{H^+}(aq) + \mathrm{SO_4^{2-}}(aq) \rightarrow \mathrm{CaSO_4}(s) + \mathrm{CO_2}(g) + \mathrm{H_2O}(l) \quad \text{(net)} \tag{5.7.6}$$

;

12. Use the following equations to answer the next five questions:

i. $\mathrm{H_2O}(s) \rightarrow \mathrm{H_2O}(l)$
ii. $\mathrm{Na^+}(aq) + \mathrm{Cl^-}(aq)\mathrm{Ag^+}(aq) + \mathrm{NO_3^-}(aq) \rightarrow \mathrm{AgCl}(s) + \mathrm{Na^+}(aq) + \mathrm{NO_3^-}(aq)$
iii. $\mathrm{CH_3OH}(g) + \mathrm{O_2}(g) \rightarrow \mathrm{CO_2}(g) + \mathrm{H_2O}(g)$
iv. $2\,\mathrm{H_2O}(l) \rightarrow 2\,\mathrm{H_2}(g) + \mathrm{O_2}(g)$
v. $\mathrm{H^+}(aq) + \mathrm{OH^-}(aq) \rightarrow \mathrm{H_2O}(l)$

a. Which equation describes a physical change?
b. Which equation identifies the reactants and products of a combustion reaction?
c. Which equation is not balanced?
d. Which is a net ionic equation?

Answer

a.) **i**; b.) **iii**; c.) **iii**; d.) **v**

13. Indicate what type, or types, of reaction each of the following represents:

a. $\mathrm{Ca}(s) + \mathrm{Br_2}(l) \rightarrow \mathrm{CaBr_2}(s)$
b. $\mathrm{Ca(OH)_2}(aq) + 2\,\mathrm{HBr}(aq) \rightarrow \mathrm{CaBr_2}(aq) + 2\,\mathrm{H_2O}(l)$
c. $\mathrm{C_6H_{12}}(l) + 9\,\mathrm{O_2}(g) \rightarrow 6\,\mathrm{CO_2}(g) + 6\,\mathrm{H_2O}(g)$

Answer

a. oxidation-reduction (addition); b. acid-base (neutralization); c.oxidation-reduction (combustion)

14. Indicate what type, or types, of reaction each of the following represents:

a. $H_2O(g) + C(s) \rightarrow CO(g) + H_2(g)$
b. $2\,KClO_3(s) \rightarrow 2\,KCl(s) + 3\,O_2(g)$
c. $Al(OH)_3(aq) + 3\,HCl(aq) \rightarrow AlBr_3(aq) + 3\,H_2O(l)$
d. $Pb(NO_3)_2(aq) + H_2SO_4(aq) \rightarrow PbSO_4(s) + 2\,HNO_3(aq)$

15. Silver can be separated from gold because silver dissolves in nitric acid while gold does not. Is the dissolution of silver in nitric acid an acid-base reaction or an oxidation-reduction reaction? Explain your answer.

Answer

It is an oxidation-reduction reaction because the oxidation state of the silver changes during the reaction.

16. Determine the oxidation states of the elements in the following compounds:

a. NaI
b. $GdCl_3$
c. $LiNO_3$
d. H_2Se
e. Mg_2Si
f. RbO_2, rubidium superoxide
g. HF

17. Determine the oxidation states of the elements in the compounds listed. None of the oxygen-containing compounds are peroxides or superoxides.

a. H_3PO_4
b. $Al(OH)_3$
c. SeO_2
d. KNO_2
e. In_2S_3
f. P_4O_6

Answer

a. H +1, P +5, O −2; b. Al +3, H +1, O −2; c. Se +4, O −2; d. K +1, N +3, O −2; e. In +3, S −2; f. P +3, O −2

18. Determine the oxidation states of the elements in the compounds listed. None of the oxygen-containing compounds are peroxides or superoxides.

a. H_2SO_4
b. $Ca(OH)_2$
c. BrOH
d. $ClNO_2$
e. $TiCl_4$
f. NaH

Answer

a. H^{1+}, O^{2-}, S^{6+}; b. H^{1+}, O^{2-}, Ca^{+2} ; c. H^{1+}, O^{2-}, Br^{1+} ;d. O^{2-}, Cl^{1-}, N^{5+} ;e. Cl^{1-}, Ti^{4+} ; f. H^{1+}, Na^{1-}

19. Classify the following as acid-base reactions or oxidation-reduction reactions:

a. $Na_2S(aq) + 2\,HCl(aq) \rightarrow 2\,NaCl(aq) + H_2S(g)$
b. $2\,Na(s) + 2\,HCl(aq) \rightarrow 2\,NaCl(aq) + H_2(g)$
c. $Mg(s) + Cl_2(g) \rightarrow MgCl_2(s)$
d. $MgO(s) + 2\,HCl(aq) \rightarrow MgCl_2(aq) + H_2O(l)$
e. $K_3P(s) + 2\,O_2(g) \rightarrow K_3PO_4(s)$
f. $3\,KOH(aq) + H_3PO_4(aq) \rightarrow K_3PO_4(aq) + 3\,H_2O(l)$

Answer

a. acid-base; b. oxidation-reduction: Na is oxidized, H^+ is reduced; c. oxidation-reduction: Mg is oxidized, Cl_2 is reduced; d. acid-base; e. oxidation-reduction: P^{3-} is oxidized, O_2 is reduced; f. acid-base

20. Identify the atoms that are oxidized and reduced, the change in oxidation state for each, and the oxidizing and reducing agents in each of the following equations:

    a. $\mathrm{Mg}(s) + \mathrm{NiCl_2}(aq) \rightarrow \mathrm{MgCl_2}(aq) + \mathrm{Ni}(s)$
    b. $\mathrm{PCl_3}(l) + \mathrm{Cl_2}(g) \rightarrow \mathrm{PCl_5}(s)$
    c. $\mathrm{C_2H_4}(g) + 3\,\mathrm{O_2}(g) \rightarrow 2\,\mathrm{CO_2}(g) + 2\,\mathrm{H_2O}(g)$
    d. $\mathrm{Zn}(s) + \mathrm{H_2SO_4}(aq) \rightarrow \mathrm{ZnSO_4}(aq) + \mathrm{H_2}(g)$
    e. $2\,\mathrm{K_2S_2O_3}(s) + \mathrm{I_2}(s) \rightarrow \mathrm{K_2S_4O_6}(s) + 2\,\mathrm{KI}(s)$
    f. $3\,\mathrm{Cu}(s) + 8\,\mathrm{HNO_3}(aq) \rightarrow 3\,\mathrm{Cu(NO_3)_2}(aq) + 2\,\mathrm{NO}(g) + 4\,\mathrm{H_2O}(l)$

21. Complete and balance the following acid-base equations:

    a. HCl gas reacts with solid $Ca(OH)_2(s)$.
    b. A solution of $Sr(OH)_2$ is added to a solution of HNO_3.

Answer

a. $2\,\mathrm{HCl}(g) + \mathrm{Ca(OH)_2}(s) \rightarrow \mathrm{CaCl_2}(s) + 2\,\mathrm{H_2O}(l)$; b. $\mathrm{Sr(OH)_2}(aq) + 2\,\mathrm{HNO_3}(aq) \rightarrow \mathrm{Sr(NO_3)_2}(aq) + 2\,\mathrm{H_2O}(l)$

22. Complete and balance the following acid-base equations:

    a. A solution of $HClO_4$ is added to a solution of LiOH.
    b. Aqueous H_2SO_4 reacts with NaOH.
    c. $Ba(OH)_2$ reacts with HF gas.

23. Complete and balance the following oxidation-reduction reactions, which give the highest possible oxidation state for the oxidized atoms.

    a. $\mathrm{Al}(s) + \mathrm{F_2}(g) \rightarrow$
    b. $\mathrm{Al}(s) + \mathrm{CuBr_2}(aq) \rightarrow$ (single displacement)
    c. $\mathrm{P_4}(s) + \mathrm{O_2}(g) \rightarrow$
    d. $\mathrm{Ca}(s) + \mathrm{H_2O}(l) \rightarrow$ (products are a strong base and a diatomic gas)

Answer

a. $2\,\mathrm{Al}(s) + 3\,\mathrm{F_2}(g) \rightarrow 2\,\mathrm{AlF_3}(s)$; b. $2\,\mathrm{Al}(s) + 3\,\mathrm{CuBr_2}(aq) \rightarrow 3\,\mathrm{Cu}(s) + 2\,\mathrm{AlBr_3}(aq)$; c. $\mathrm{P_4}(s) + 5\,\mathrm{O_2}(g) \rightarrow \mathrm{P_4O_{10}}(s)$; d. $\mathrm{Ca}(s) + 2\,\mathrm{H_2O}(l) \rightarrow \mathrm{Ca(OH)_2}(aq) + \mathrm{H_2}(g)$

24. Complete and balance the following oxidation-reduction reactions, which give the highest possible oxidation state for the oxidized atoms.

    a. $\mathrm{K}(s) + \mathrm{H_2O}(l) \rightarrow$
    b. $\mathrm{Ba}(s) + \mathrm{HBr}(aq) \rightarrow$
    c. $\mathrm{Sn}(s) + \mathrm{I_2}(s) \rightarrow$

25. Complete and balance the equations for the following acid-base neutralization reactions. If water is used as a solvent, write the reactants and products as aqueous ions. In some cases, there may be more than one correct answer, depending on the amounts of reactants used.

    a. $\mathrm{Mg(OH)_2}(s) + \mathrm{HClO_4}(aq) \rightarrow$
    b. $\mathrm{SO_3}(g) + \mathrm{H_2O}(l) \rightarrow$ (assume an excess of water and that the product dissolves)
    c. $\mathrm{SrO}(s) + \mathrm{H_2SO_4}(l) \rightarrow$

Answer

a. $Mg(OH)_2(s) + 2\,HClO_4(aq) \rightarrow Mg^{2+}(aq) + 2\,ClO_4^-(aq) + 2\,H_2O(l)$; b. $SO_3(g) + 2\,H_2O(l) \rightarrow H_3O^+(aq) + HSO_4^-(aq)$, (a solution of H_2SO_4); c. $SrO(s) + H_2SO_4(l) \rightarrow SrSO_4(s) + H_2O$

26. When heated to 700–800 °C, diamonds, which are pure carbon, are oxidized by atmospheric oxygen. (They burn!) Write the balanced equation for this reaction.

27. The military has experimented with lasers that produce very intense light when fluorine combines explosively with hydrogen. What is the balanced equation for this reaction?

Answer

$H_2(g) + F_2(g) \rightarrow 2\,HF(g)$

28. Write the molecular, total ionic, and net ionic equations for the following reactions:
    a. $Ca(OH)_2(aq) + HC_2H_3O_2(aq) \rightarrow$
    b. $H_3PO_4(aq) + CaCl_2(aq) \rightarrow$

29. Great Lakes Chemical Company produces bromine, Br_2, from bromide salts such as NaBr, in Arkansas brine by treating the brine with chlorine gas. Write a balanced equation for the reaction of NaBr with Cl_2.

Answer

$2\,NaBr(aq) + Cl_2(g) \rightarrow 2\,NaCl(aq) + Br_2(l)$

30. In a common experiment in the general chemistry laboratory, magnesium metal is heated in air to produce MgO. MgO is a white solid, but in these experiments it often looks gray, due to small amounts of Mg_3N_2, a compound formed as some of the magnesium reacts with nitrogen. Write a balanced equation for each reaction.

31. Lithium hydroxide may be used to absorb carbon dioxide in enclosed environments, such as manned spacecraft and submarines. Write an equation for the reaction that involves 2 mol of LiOH per 1 mol of CO_2. (Hint: Water is one of the products.)

Answer

$2\,LiOH(aq) + CO_2(g) \rightarrow Li_2CO_3(aq) + H_2O(l)$

32. Calcium propionate is sometimes added to bread to retard spoilage. This compound can be prepared by the reaction of calcium carbonate, $CaCO_3$, with propionic acid, $C_2H_5CO_2H$, which has properties similar to those of acetic acid. Write the balanced equation for the formation of calcium propionate.

33. Complete and balance the equations of the following reactions, each of which could be used to remove hydrogen sulfide from natural gas:
    a. $Ca(OH)_2(s) + H_2S(g) \rightarrow$
    b. $Na_2CO_3(aq) + H_2S(g) \rightarrow$

Answer

a. $Ca(OH)_2(s) + H_2S(g) \rightarrow CaS(s) + 2\,H_2O(l)$; b. $Na_2CO_3(aq) + H_2S(g) \rightarrow Na_2S(aq) + CO_2(g) + H_2O(l)$

34. Copper(II) sulfide is oxidized by molecular oxygen to produce gaseous sulfur trioxide and solid copper(II) oxide. The gaseous product then reacts with liquid water to produce liquid hydrogen sulfate as the only product. Write the two equations which represent these reactions.

35. Write balanced chemical equations for the reactions used to prepare each of the following compounds from the given starting material(s). In some cases, additional reactants may be required.
    a. solid ammonium nitrate from gaseous molecular nitrogen via a two-step process (first reduce the nitrogen to ammonia, then neutralize the ammonia with an appropriate acid)
    b. gaseous hydrogen bromide from liquid molecular bromine via a one-step redox reaction
    c. gaseous H_2S from solid Zn and S via a two-step process (first a redox reaction between the starting materials, then reaction of the product with a strong acid)

Answer

a. step 1: $N_2(g) + 3\,H_2(g) \rightarrow 2\,NH_3(g)$, step 2: $NH_3(g) + HNO_3(aq) \rightarrow NH_4NO_3(aq) \rightarrow NH_4NO_3(s)(\text{after drying})$; b. $H_2(g) + Br_2(l) \rightarrow 2\,HBr(g)$; c. $Zn(s) + S(s) \rightarrow ZnS(s)$ and $ZnS(s) + 2\,HCl(aq) \rightarrow ZnCl_2(aq) + H_2S(g)$

36. Calcium cyclamate $Ca(C_6H_{11}NHSO_3)_2$ is an artificial sweetener used in many countries around the world but is banned in the United States. It can be purified industrially by converting it to the barium salt through reaction of the acid $C_6H_{11}NHSO_3H$ with barium carbonate, treatment with sulfuric acid (barium sulfate is very insoluble), and then neutralization with calcium hydroxide. Write the balanced equations for these reactions.

37. Complete and balance each of the following half-reactions (steps 2–5 in half-reaction method):

a. $Sn^{4+}(aq) \rightarrow Sn^{2+}(aq)$
b. $[Ag(NH_3)_2]^+(aq) \rightarrow Ag(s) + NH_3(aq)$
c. $Hg_2Cl_2(s) \rightarrow Hg(l) + Cl^-(aq)$
d. $H_2O(l) \rightarrow O_2(g)\ (\text{in acidic solution})$
e. $IO_3^-(aq) \rightarrow I_2(s)$
f. $SO_3^{2-}(aq) \rightarrow SO_4^{2-}(aq)\ (\text{in acidic solution})$
g. $MnO_4^-(aq) \rightarrow Mn^{2+}(aq)\ (\text{in acidic solution})$
h. $Cl^-(aq) \rightarrow ClO_3^-(aq)\ (\text{in basic solution})$

Answer

a. $Sn^{4+}(aq) + 2\,e^- \rightarrow Sn^{2+}(aq)$; b. $[Ag(NH_3)_2]^+(aq) + e^- \rightarrow Ag(s) + 2\,NH_3(aq)$; c. $Hg_2Cl_2(s) + 2\,e^- \rightarrow 2\,Hg(l) + 2\,Cl^-(aq)$;d. $2\,H_2O(l) \rightarrow O_2(g) + 4\,H^+(aq) + 4\,e^-$; e. $6\,H_2O(l) + 2\,IO_3^-(aq) + 10\,e^- \rightarrow I_2(s) + 12\,OH^-(aq)$; f. $H_2O(l) + SO_3^{2-}(aq) \rightarrow SO_4^{2-}(aq) + 2\,H^+(aq) + 2\,e^-$; g. $8\,H^+(aq) + MnO_4^-(aq) + 5\,e^- \rightarrow Mn^{2+}(aq) + 4\,H_2O(l)$; h. $Cl^-(aq) + 6\,OH^-(aq) \rightarrow ClO_3^-(aq) + 3\,H_2O(l) + 6\,e^-$

38. Complete and balance each of the following half-reactions (steps 2–5 in half-reaction method):

a. $Cr^{2+}(aq) \rightarrow Cr^{3+}(aq)$
b. $Hg(l) + Br^-(aq) \rightarrow HgBr_4^{2-}(aq)$
c. $ZnS(s) \rightarrow Zn(s) + S^{2-}(aq)$
d. $H_2(g) \rightarrow H_2O(l)\ (\text{in basic solution})$
e. $H_2(g) \rightarrow H_3O^+(aq)\ (\text{in acidic solution})$
f. $NO_3^-(aq) \rightarrow HNO_2(aq)\ (\text{in acidic solution})$
g. $MnO_2(s) \rightarrow MnO_4^-(aq)\ (\text{in basic solution})$
h. $Cl^-(aq) \rightarrow ClO_3^-(aq)\ (\text{in acidic solution})$

39. Balance each of the following equations according to the half-reaction method:

a. $Sn^{2+}(aq) + Cu^{2+}(aq) \rightarrow Sn^{4+}(aq) + Cu^+(aq)$
b. $H_2S(g) + Hg_2^{2+}(aq) \rightarrow Hg(l) + S(s)\ (\text{in acid})$
c. $CN^-(aq) + ClO_2(aq) \rightarrow CNO^-(aq) + Cl^-(aq)\ (\text{in acid})$
d. $Fe^{2+}(aq) + Ce^{4+}(aq) \rightarrow Fe^{3+}(aq) + Ce^{3+}(aq)$
e. $HBrO(aq) \rightarrow Br^-(aq) + O_2(g)\ (\text{in acid})$

Answer

a. $Sn^{2+}(aq) + 2\,Cu^{2+}(aq) \rightarrow Sn^{4+}(aq) + 2\,Cu^+(aq)$;

b. $H_2S(g) + Hg_2^{2+}(aq) + 2\,H_2O(l) \rightarrow 2\,Hg(l) + S(s) + 2\,H_3O^+(aq)$;

c. $5\,CN^-(aq) + 2\,ClO_2(aq) + 3\,H_2O(l) \rightarrow 5\,CNO^-(aq) + 2\,Cl^-(aq) + 2\,H_3O^+(aq)$;

d. $Fe^{2+}(aq) + Ce^{4+}(aq) \rightarrow Fe^{3+}(aq) + Ce^{3+}(aq)$;

e. $2\,HBrO(aq) + 2\,H_2O(l) \rightarrow 2\,H_3O^+(aq) + 2\,Br^-(aq) + O_2(g)$

40. Balance each of the following equations according to the half-reaction method:

a. $Zn(s) + NO_3^-(aq) \rightarrow Zn^{2+}(aq) + N_2(g)$ (in acid)
b. $Zn(s) + NO_3^-(aq) \rightarrow Zn^{2+}(aq) + NH_3(aq)$ (in base)
c. $CuS(s) + NO_3^-(aq) \rightarrow Cu^{2+}(aq) + S(s) + NO(g)$ (in acid)
d. $NH_3(aq) + O_2(g) \rightarrow NO_2(g)$ (gas phase)
e. $Cl_2(g) + OH^-(aq) \rightarrow Cl^-(aq) + ClO_3^-(aq)$ (in base)
f. $H_2O_2(aq) + MnO_4^-(aq) \rightarrow Mn^{2+}(aq) + O_2(g)$ (in acid)
g. $NO_2(g) \rightarrow NO_3^-(aq) + NO_2^-(aq)$ (in base)
h. $Fe^{3+}(aq) + I^-(aq) \rightarrow Fe^{2+}(aq) + I_2(aq)$

41. Balance each of the following equations according to the half-reaction method:

a. $MnO_4^-(aq) + NO_2^-(aq) \rightarrow MnO_2(s) + NO_3^-(aq)$ (in base)
b. $MnO_4^{2-}(aq) \rightarrow MnO_4^-(aq) + MnO_2(s)$ (in base)
c. $Br_2(l) + SO_2(g) \rightarrow Br^-(aq) + SO_4^{2-}(aq)$ (in acid)

Answer

a. $2\,MnO_4^-(aq) + 3\,NO_2^-(aq) + H_2O(l) \rightarrow 2\,MnO_2(s) + 3\,NO_3^-(aq) + 2\,OH^-(aq)$;

b. $3\,MnO_4^{2-}(aq) + 2\,H_2O(l) \rightarrow 2\,MnO_4^-(aq) + 4\,OH^-(aq) + MnO_2(s)$ (in base);

c. $Br_2(l) + SO_2(g) + 2\,H_2O(l) \rightarrow 4\,H^+(aq) + 2\,Br^-(aq) + SO_4^{2-}(aq)$

5.7: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

6: Reaction Stoichiometry

6.1: Reaction Stoichiometry

6.2: Limiting reactant, theoretical yield, and percent yield

6.3: solution stoichiometry

6.4: Quantitative Analysis-Titration and Gravimetric Analysis

6.5: End of Chapter Problems

6: Reaction Stoichiometry is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

6.1: Reaction Stoichiometry

Learning Objectives

- Explain the concept of stoichiometry as it pertains to chemical reactions
- Use balanced chemical equations to derive stoichiometric factors relating amounts of reactants and products
- Perform stoichiometric calculations involving mass, moles, and solution molarity

A balanced chemical equation provides a great deal of information in a very succinct format. Chemical formulas provide the identities of the reactants and products involved in the chemical change, allowing classification of the reaction. Coefficients provide the relative numbers of these chemical species, allowing a quantitative assessment of the relationships between the amounts of substances consumed and produced by the reaction. These quantitative relationships are known as the reaction's stoichiometry, a term derived from the Greek words *stoicheion* (meaning "element") and *metron* (meaning "measure"). In this module, the use of balanced chemical equations for various stoichiometric applications is explored.

The general approach to using stoichiometric relationships is similar in concept to the way people go about many common activities. Cooking, for example, offers an appropriate comparison. Suppose a recipe for making eight pancakes calls for 1 cup pancake mix, $\frac{3}{4}$ cup milk, and one egg. The "equation" representing the preparation of pancakes per this recipe is

$$\text{1 cup mix} + \frac{3}{4}\ \text{cup milk} + \text{1 egg} \rightarrow \text{8 pancakes} \tag{6.1.1}$$

If two dozen pancakes are needed for a big family breakfast, the ingredient amounts must be increased proportionally according to the amounts given in the recipe. For example, the number of eggs required to make 24 pancakes is

$$24\ \cancel{\text{pancakes}} \times \frac{1\ \text{egg}}{8\ \cancel{\text{pancakes}}} = 3\ \text{eggs} \tag{6.1.2}$$

Balanced chemical equations are used in much the same fashion to determine the amount of one reactant required to react with a given amount of another reactant, or to yield a given amount of product, and so forth. The coefficients in the balanced equation are used to derive stoichiometric factors that permit computation of the desired quantity. To illustrate this idea, consider the production of ammonia by reaction of hydrogen and nitrogen:

$$\mathrm{N_2}(g) + 3\,\mathrm{H_2}(g) \rightarrow 2\,\mathrm{NH_3}(g) \tag{6.1.3}$$

This equation shows that ammonia molecules are produced from hydrogen molecules in a 2:3 ratio, and stoichiometric factors may be derived using any amount (number) unit:

$$\frac{2\,NH3\ molecules}{3H2\ molecules} \text{ or } \frac{2\ doz\ NH3\ molecules}{3\ doz\ H2\ molecules} \text{ or } \frac{2\ mol\ NH3\ molecules}{3\ mol\ H2\ molecules} \tag{6.1.4}$$

These stoichiometric factors can be used to compute the number of ammonia molecules produced from a given number of hydrogen molecules, or the number of hydrogen molecules required to produce a given number of ammonia molecules. Similar factors may be derived for any pair of substances in any chemical equation.



Finding Mols and Masses of Reactants and Products Using Stoichiometric Factors (Mol Ratios): https://youtu.be/74mHV0CZcjw

Example 6.1.1: Moles of Reactant Required in a Reaction

How many moles of I_2 are required to react with 0.429 mol of Al according to the following equation (see Figure 6.1.2)?

$$2\,Al + 3\,I_2 \rightarrow 2\,AlI_3 \tag{6.1.5}$$





Figure 6.1.1: Aluminum and iodine react to produce aluminum iodide. The heat of the reaction vaporizes some of the solid iodine as a purple vapor. (credit: modification of work by Mark Ott)

Solution

Referring to the balanced chemical equation, the stoichiometric factor relating the two substances of interest is $\frac{3\ mol\ I2}{2\ mol\ Al}$. The molar amount of iodine is derived by multiplying the provided molar amount of aluminum by this factor:



$$\text{mol } I_2 = 0.429\ \cancel{\text{mol Al}} \times \frac{3\ \text{mol } I_2}{2\ \cancel{\text{mol Al}}}$$

$$= 0.644\ \text{mol } I_2$$

Exercise 6.1.1

How many moles of $Ca(OH)_2$ are required to react with 1.36 mol of H_3PO_4 to produce $Ca_3(PO_4)_2$ according to the equation $3\,Ca(OH)_2 + 2\,H_3PO_4 \rightarrow Ca_3(PO_4)_2 + 6\,H_2O$?

Answer

2.04 mol

Example 6.1.2: Number of Product Molecules Generated by a Reaction

How many carbon dioxide molecules are produced when 0.75 mol of propane is combusted according to this equation?

$$\mathrm{C_3H_8 + 5\,O_2 \rightarrow 3\,CO_2 + 4\,H_2O} \tag{6.1.6}$$


Solution

The approach here is the same as for Example **6.1.1**, though the absolute number of molecules is requested, not the number of moles of molecules. This will simply require use of the moles-to-numbers conversion factor, Avogadro's number.

The balanced equation shows that carbon dioxide is produced from propane in a 3:1 ratio:

$$\frac{3\ mol\ CO2}{1\ mol\ C3H8} \tag{6.1.7}$$

Using this stoichiometric factor, the provided molar amount of propane, and Avogadro's number,



$$0.75\ \cancel{\mathrm{mol\ C_3H_8}} \times \frac{3\ \cancel{\mathrm{mol\ CO_2}}}{1\ \cancel{\mathrm{mol\ C_3H_8}}} \times \frac{6.022 \times 10^{23}\ \mathrm{CO_2\ molecules}}{\cancel{\mathrm{mol\ CO_2}}} = 1.4 \times 10^{24}\ \mathrm{CO_2\ molecules} \tag{6.1.8}$$

Exercise 6.1.2

How many NH_3 molecules are produced by the reaction of 4.0 mol of $Ca(OH)_2$ according to the following equation:

$$\mathrm{(NH_4)_2SO_4 + Ca(OH)_2 \rightarrow 2\,NH_3 + CaSO_4 + 2\,H_2O}$$

Answer

4.8×10^{24} NH_3 molecules

These examples illustrate the ease with which the amounts of substances involved in a chemical reaction of known stoichiometry may be related. Directly measuring numbers of atoms and molecules is, however, not an easy task, and the practical application of stoichiometry requires that we use the more readily measured property of mass.


Example 6.1.3: Relating Masses of Reactants and Products

What mass of sodium hydroxide, NaOH, would be required to produce 16 g of the antacid milk of magnesia [magnesium hydroxide, $Mg(OH)_2$] by the following reaction?

$$\mathrm{MgCl_2}(aq) + 2\,\mathrm{NaOH}(aq) \rightarrow \mathrm{Mg(OH)_2}(s) + 2\,\mathrm{NaCl}(aq)$$

Solution

The approach used previously in Examples **6.1.1** and **6.1.2** is likewise used here; that is, we must derive an appropriate stoichiometric factor from the balanced chemical equation and use it to relate the amounts of the two substances of interest. In this case, however, masses (not molar amounts) are provided and requested, so additional steps of the sort learned in the previous chapter are required. The calculations required are outlined in this flowchart:



$$16\ \text{g}\ \text{Mg(OH)}_2 \times \frac{1\ \text{mol}\ \text{Mg(OH)}_2}{58.3\ \text{g}\ \text{Mg(OH)}_2} \times \frac{2\ \text{mol NaOH}}{1\ \text{mol}\ \text{Mg(OH)}_2} \times \frac{40.0\ \text{g NaOH}}{\text{mol NaOH}} = 22\ \text{g NaOH} \tag{6.1.9}$$

Exercise 6.1.3

What mass of gallium oxide, Ga_2O_3, can be prepared from 29.0 g of gallium metal? The equation for the reaction is $4\,Ga + 3\,O_2 \rightarrow 2\,Ga_2O_3$.

Answer

39.0 g


Example 6.1.4: Relating Masses of Reactants

What mass of oxygen gas, O_2, from the air is consumed in the combustion of 702 g of octane, C_8H_{18}, one of the principal components of gasoline?

$$2\,C_8H_{18} + 25\,O_2 \rightarrow 16\,CO_2 + 18\,H_2O$$

Solution

The approach required here is the same as for the Example **6.1.3**, differing only in that the provided and requested masses are both for reactant species.



$$702\ \text{g}\ \text{C}_8\text{H}_{18} \times \frac{1\ \text{mol}\ \text{C}_8\text{H}_{18}}{114.23\ \text{g}\ \text{C}_8\text{H}_{18}} \times \frac{25\ \text{mol}\ \text{O}_2}{2\ \text{mol}\ \text{C}_8\text{H}_{18}} \times \frac{32.00\ \text{g}\ \text{O}_2}{\text{mol}\ \text{O}_2} = 2.46 \times 10^3\ \text{g}\ \text{O}_2$$

Exercise 6.1.4

What mass of CO is required to react with 25.13 g of Fe_2O_3 according to the equation $Fe_2O_3 + 3\,CO \rightarrow 2\,Fe + 3\,CO_2$?

Answer

13.22 g

These examples illustrate just a few instances of reaction stoichiometry calculations. Numerous variations on the beginning and ending computational steps are possible depending upon what particular quantities are provided and sought (volumes, solution concentrations, and so forth). Regardless of the details, all these calculations share a common essential component: the use of stoichiometric factors derived from balanced chemical equations. Figure **6.1.2** provides a general outline of the various computational steps associated with many reaction stoichiometry calculations.




Figure **6.1.2**: The flowchart depicts the various computational steps involved in most reaction stoichiometry calculations.

Airbags

Airbags (Figure **6.1.3**) are a safety feature provided in most automobiles since the 1990s. The effective operation of an airbag requires that it be rapidly inflated with an appropriate amount (volume) of gas when the vehicle is involved in a collision. This requirement is satisfied in many automotive airbag systems through use of explosive chemical reactions, one common choice being the decomposition of sodium azide, NaN_3. When sensors in the vehicle detect a collision, an electrical current is passed through a carefully measured amount of NaN_3 to initiate its decomposition:

$$2\,NaN_3(s) \rightarrow 3\,N_2(g) + 2\,Na(s) \tag{6.1.10}$$

This reaction is very rapid, generating gaseous nitrogen that can deploy and fully inflate a typical airbag in a fraction of a second (~0.03–0.1 s). Among many engineering considerations, the amount of sodium azide used must be appropriate for generating enough nitrogen gas to fully inflate the air bag and ensure its proper function. For example, a small mass (~100 g) of NaN_3 will generate approximately 50 L of N_2.



Figure **6.1.3**: Airbags deploy upon impact to minimize serious injuries to passengers. (credit: Jon Seidman)

Summary

A balanced chemical equation may be used to describe a reaction's stoichiometry (the relationships between amounts of reactants and products). Coefficients from the equation are used to derive stoichiometric factors that subsequently may be used for computations relating reactant and product masses, molar amounts, and other quantitative properties.

Glossary

stoichiometric factor
: ratio of coefficients in a balanced chemical equation, used in computations relating amounts of reactants and products

stoichiometry
: relationships between the amounts of reactants and products of a chemical reaction

---

6.1: Reaction Stoichiometry is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.4: Reaction Stoichiometry** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

6.2: Limiting reactant, theoretical yield, and percent yield

Learning Objectives

- Explain the concepts of theoretical yield and limiting reactants/reagents.
- Derive the theoretical yield for a reaction under specified conditions.
- Calculate the percent yield for a reaction.

The relative amounts of reactants and products represented in a balanced chemical equation are often referred to as *stoichiometric amounts*. All the exercises of the preceding module involved stoichiometric amounts of reactants. For example, when calculating the amount of product generated from a given amount of reactant, it was assumed that any other reactants required were available in stoichiometric amounts (or greater). In this module, more realistic situations are considered, in which reactants are not present in stoichiometric amounts.

Limiting Reactant

Consider another food analogy, making grilled cheese sandwiches (Figure **6.2.1**):

$$\textbf{1 slice of cheese} + \textbf{2 slices of bread} \rightarrow \textbf{1 sandwich} \tag{6.2.1}$$

Stoichiometric amounts of sandwich ingredients for this recipe are bread and cheese slices in a 2:1 ratio. Provided with 28 slices of bread and 11 slices of cheese, one may prepare 11 sandwiches per the provided recipe, using all the provided cheese and having six slices of bread left over. In this scenario, the number of sandwiches prepared has been *limited* by the number of cheese slices, and the bread slices have been provided in *excess*.




Figure **6.2.1**: Sandwich making can illustrate the concepts of limiting and excess reactants.

Consider this concept now with regard to a chemical process, the reaction of hydrogen with chlorine to yield hydrogen chloride:

$$\mathrm{Cl_2}(g) \rightarrow 2\,\mathrm{HCl}(g) \tag{6.2.2}$$

The balanced equation shows the hydrogen and chlorine react in a 1:1 stoichiometric ratio. If these reactants are provided in any other amounts, one of the reactants will nearly always be entirely consumed, thus limiting the amount of product that may be generated. This substance is the limiting reactant, and the other substance is the excess reactant. Identifying the limiting and excess reactants for a given situation requires computing the molar amounts of each reactant provided and comparing them to the stoichiometric amounts represented in the balanced chemical equation. For example, imagine combining 3 moles of H_2 and 2 moles of Cl_2. This represents a 3:2 (or 1.5:1) ratio of hydrogen to chlorine present for reaction, which is greater than the stoichiometric ratio of 1:1. Hydrogen, therefore, is present in excess, and chlorine is the limiting reactant. Reaction of all the provided chlorine (2 mol) will consume 2 mol of the 3 mol of hydrogen provided, leaving 1 mol of hydrogen nonreacted.

An alternative approach to identifying the limiting reactant involves comparing the amount of product expected for the complete reaction of each reactant. Each reactant amount is used to separately calculate the amount of product that would be formed per the

reaction's stoichiometry. The reactant yielding the lesser amount of product is the limiting reactant. For the example in the previous paragraph, complete reaction of the hydrogen would yield

$$\text{mol HCl produced} = 3\ \text{mol } H_2 \times \frac{2\ \text{mol HCl}}{1\ \text{mol } H_2} = 6\ \text{mol HCl} \tag{6.2.3}$$

Complete reaction of the provided chlorine would produce

$$\text{mol HCl produced} = 2\ \text{mol } Cl_2 \times \frac{2\ \text{mol HCl}}{1\ \text{mol } Cl_2} = 4\ \text{mol HCl} \tag{6.2.4}$$

The chlorine will be completely consumed once 4 moles of HCl have been produced. Since enough hydrogen was provided to yield 6 moles of HCl, there will be non-reacted hydrogen remaining once this reaction is complete. Chlorine, therefore, is the limiting reactant and hydrogen is the excess reactant (Figure **6.2.2**).




Figure **6.2.2**: When H_2 and Cl_2 are combined in nonstoichiometric amounts, one of these reactants will limit the amount of HCl that can be produced. This illustration shows a reaction in which hydrogen is present in excess and chlorine is the limiting reactant.

Example 6.2.1: Identifying the Limiting Reactant

Silicon nitride is a very hard, high-temperature-resistant ceramic used as a component of turbine blades in jet engines. It is prepared according to the following equation:

$$3\,Si(s) + 2\,N_2(g) \rightarrow Si_3N_4(s) \tag{6.2.5}$$

Which is the limiting reactant when 2.00 g of Si and 1.50 g of N_2 react?

Solution

Compute the provided molar amounts of reactants, and then compare these amounts to the balanced equation to identify the limiting reactant.

$$\text{mol Si} = 2.00\ \cancel{\text{g Si}} \times \frac{1\ \text{mol Si}}{28.09\ \cancel{\text{g Si}}} = 0.0712\ \text{mol Si} \tag{6.2.6}$$

$$\text{mol } N_2 = 1.50\ \cancel{\text{g } N_2} \times \frac{1\ \text{mol } N_2}{28.02\ \cancel{\text{g } N_2}} = 0.0535\ \text{mol } N_2 \tag{6.2.7}$$

The provided Si:N_2 molar ratio is:

$$\frac{0.0712\ \text{mol Si}}{0.0535\ \text{mol } N_2} = \frac{1.33\ \text{mol Si}}{1\ \text{mol } N_2} \tag{6.2.8}$$

The stoichiometric Si:N_2 ratio is:

$$\frac{3\ \text{mol Si}}{2\ \text{mol } N_2} = \frac{1.5\ \text{mol Si}}{1\ \text{mol } N_2} \tag{6.2.9}$$

Comparing these ratios shows that Si is provided in a less-than-stoichiometric amount, and so is the limiting reactant.

Alternatively, compute the amount of product expected for complete reaction of each of the provided reactants. The 0.0712 moles of silicon would yield

$$\text{mol Si}_3\text{N}_4 \text{ produced} = 0.0712 \text{ mol Si} \times \frac{1 \text{ mol Si}_3\text{N}_4}{3 \text{ mol Si}} = 0.0237 \text{ mol Si}_3\text{N}_4 \tag{6.2.10}$$

while the 0.0535 moles of nitrogen would produce

$$\text{mol Si}_3\text{N}_4 \text{ produced} = 0.0535 \text{ mol N}_2 \times \frac{1 \text{ mol Si}_3\text{N}_4}{2 \text{ mol N}_2} = 0.0268 \text{ mol Si}_3\text{N}_4 \tag{6.2.11}$$

Since silicon yields the lesser amount of product, it is the limiting reactant.

? Exercise 6.2.1

Which is the limiting reactant when 5.00 g of H_2 and 10.0 g of O_2 react and form water?

Answer

O_2

Percent Yield

The amount of product that *may be* produced by a reaction under specified conditions, as calculated per the stoichiometry of an appropriate balanced chemical equation, is called the theoretical yield of the reaction. In practice, the amount of product obtained is called the actual yield, and it is often less than the theoretical yield for a number of reasons. Some reactions are inherently inefficient, being accompanied by *side reactions* that generate other products. Others are, by nature, incomplete (consider the partial reactions of weak acids and bases discussed earlier in this text). Some products are difficult to collect without some loss, and so less than perfect recovery will reduce the actual yield. The extent to which a reaction's theoretical yield is achieved is commonly expressed as its percent yield:

$$\text{percent yield} = \frac{\text{actual yield}}{\text{theoretical yield}} \times 100\% \tag{6.2.12}$$

Actual and theoretical yields may be expressed as masses or molar amounts (or any other appropriate property; e.g., volume, if the product is a gas). As long as both yields are expressed using the same units, these units will cancel when percent yield is calculated.

✓ Example 6.2.2: Calculation of Percent Yield

Upon reaction of 1.274 g of copper sulfate with excess zinc metal, 0.392 g copper metal was obtained according to the equation:

$$\text{CuSO}_4(aq) + \text{Zn}(s) \rightarrow \text{Cu}(s) + \text{ZnSO}_4(aq)$$

What is the percent yield?

Solution

The provided information identifies copper sulfate as the limiting reactant, and so the theoretical yield is found by the approach illustrated in the previous module, as shown here:

Double subscripts: use braces to clarify

Using this theoretical yield and the provided value for actual yield, the percent yield is calculated to be

$$\text{percent yield} = \left(\frac{\text{actual yield}}{\text{theoretical yield}}\right) \times 100$$

$$\text{percent yield} = \left(\frac{0.392 \text{ g Cu}}{0.5072 \text{ g Cu}}\right) \times 100$$
$$= 77.3\%$$

Exercise 6.2.2

What is the percent yield of a reaction that produces 12.5 g of the gas Freon CF_2Cl_2 from 32.9 g of CCl_4 and excess HF?

$$CCl_4 + 2\,HF \rightarrow CF_2Cl_2 + 2\,HCl$$

Answer

48.3%



Determining the Limiting Reactant and Theoretical Yield for a Reaction: https://youtu.be/HmDm1qpNUD0

Green Chemistry and Atom Economy

The purposeful design of chemical products and processes that minimize the use of environmentally hazardous substances and the generation of waste is known as *green chemistry*. Green chemistry is a philosophical approach that is being applied to many areas of science and technology, and its practice is summarized by guidelines known as the "Twelve Principles of Green Chemistry". One of the 12 principles is aimed specifically at maximizing the efficiency of processes for synthesizing chemical products. The *atom economy* of a process is a measure of this efficiency, defined as the percentage by mass of the final product of a synthesis relative to the masses of *all* the reactants used:

$$\text{atom economy} = \frac{\text{mass of product}}{\text{mass of reactants}} \times 100\% \tag{6.2.13}$$

Though the definition of atom economy at first glance appears very similar to that for percent yield, be aware that this property represents a difference in the *theoretical* efficiencies of *different* chemical processes. The percent yield of a given chemical process, on the other hand, evaluates the efficiency of a process by comparing the yield of product actually obtained to the maximum yield predicted by stoichiometry.

The synthesis of the common nonprescription pain medication, ibuprofen, nicely illustrates the success of a green chemistry approach (Figure **6.2.3**). First marketed in the early 1960s, ibuprofen was produced using a six-step synthesis that required 514 g of reactants to generate each mole (206 g) of ibuprofen, an atom economy of 40%. In the 1990s, an alternative process was developed by the BHC Company (now BASF Corporation) that requires only three steps and has an atom economy of ~80%, nearly twice that of the original process. The BHC process generates significantly less chemical waste; uses less-hazardous and recyclable materials; and provides significant cost-savings to the manufacturer (and, subsequently, the consumer). In recognition of the positive environmental impact of the BHC process, the company received the Environmental Protection Agency's Greener Synthetic Pathways Award in 1997.




Figure **6.2.3**: (a) Ibuprofen is a popular nonprescription pain medication commonly sold as 200 mg tablets. (b) The BHC process for synthesizing ibuprofen requires only three steps and exhibits an impressive atom economy. (credit a: modification of work by Derrick Coetzee)

Summary

When reactions are carried out using less-than-stoichiometric quantities of reactants, the amount of product generated will be determined by the limiting reactant. The amount of product generated by a chemical reaction is its actual yield. This yield is often less than the amount of product predicted by the stoichiometry of the balanced chemical equation representing the reaction (its theoretical yield). The extent to which a reaction generates the theoretical amount of product is expressed as its percent yield.

Key Equations

- $\text{percent yield} = \left(\frac{\text{actual yield}}{\text{theoretical yield}}\right) \times 100$

Glossary

actual yield
amount of product formed in a reaction

excess reactant
reactant present in an amount greater than required by the reaction stoichiometry

limiting reactant
reactant present in an amount lower than required by the reaction stoichiometry, thus limiting the amount of product generated

percent yield
measure of the efficiency of a reaction, expressed as a percentage of the theoretical yield

theoretical yield
amount of product that may be produced from a given amount of reactant(s) according to the reaction stoichiometry

---

6.2: Limiting reactant, theoretical yield, and percent yield is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.5: Reaction Yields** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

6.3: solution stoichiometry

Learning Objectives

- To solve quantitative problems involving the stoichiometry of reactions in solution.

Quantitative calculations involving reactions in solution are carried out with *masses*, however, *volumes* of solutions of known concentration are used to determine the number of moles of reactants. Whether dealing with volumes of solutions of reactants or masses of reactants, the coefficients in the balanced chemical equation give the number of moles of each reactant needed and the number of moles of each product that can be produced. An expanded version of the flowchart for stoichiometric calculations is shown in Figure **6.3.1**. The balanced chemical equation for the reaction and *either* the masses of solid reactants and products *or* the volumes of solutions of reactants and products can be used to determine the amounts of other species, as illustrated in the following examples.




Figure **6.3.1**: An Expanded Flowchart for Stoichiometric Calculations. Either the masses or the volumes of solutions of reactants and products can be used to determine the amounts of other species in a balanced chemical equation.

The balanced chemical equation for a reaction and either the masses of solid reactants and products or the volumes of solutions of reactants and products can be used in stoichiometric calculations.

Example 6.3.1 : Extraction of Gold

Gold is extracted from its ores by treatment with an aqueous cyanide solution, which causes a reaction that forms the soluble $[Au(CN)_2]^-$ ion. Gold is then recovered by reduction with metallic zinc according to the following equation:

$$Zn(s) + 2[Au(CN)_2]^-(aq) \rightarrow [Zn(CN)_4]^{2-}(aq) + 2Au(s) \tag{6.3.1}$$

What mass of gold can be recovered from 400.0 L of a 3.30×10^{-4} M solution of $[Au(CN)_2]^-$?

Given: chemical equation and molarity and volume of reactant

Asked for: mass of product


Strategy:

A. Check the chemical equation to make sure it is balanced as written; balance if necessary. Then calculate the number of moles of $[Au(CN)_2]^-$ present by multiplying the volume of the solution by its concentration.

B. From the balanced chemical equation, use a mole ratio to calculate the number of moles of gold that can be obtained from the reaction. To calculate the mass of gold recovered, multiply the number of moles of gold by its molar mass.

Solution:

A The equation is balanced as written; proceed to the stoichiometric calculation. Figure **6.3.2** is adapted for this particular problem as follows:



As indicated in the strategy, start by calculating the number of moles of $[Au(CN)_2]^-$ present in the solution from the volume and concentration of the $[Au(CN)_2]^-$ solution:

$$moles\ [Au(CN)_2]^- = V_L M_{mol/L} \tag{6.3.2}$$

$$= 400.0\ \cancel{L}\left(\frac{3.30 \times 10^{-4}\ mol\ [Au(CN)_2]^-}{1\ \cancel{L}}\right) = 0.132\ mol\ [Au(CN)_2]^- \tag{6.3.3}$$

B Because the coefficients of gold and the $[Au(CN)_2]^-$ ion are the same in the balanced chemical equation, assuming that Zn(s) is present in excess, the number of moles of gold produced is the same as the number of moles of $[Au(CN)_2]^-$ (i.e., 0.132 mol of Au). The problem asks for the mass of gold that can be obtained, so the number of moles of gold must be converted to the corresponding mass using the molar mass of gold:

$$mass\ of\ Au = (moles\ Au)(molar\ mass\ Au) \tag{6.3.4}$$

$$= 0.132\ \cancel{mol\ Au}\left(\frac{196.97\ g\ Au}{1\ \cancel{mol\ Au}}\right) = 26.0\ g\ Au \tag{6.3.5}$$

At a 2011 market price of over $1400 per troy ounce (31.10 g), this amount of gold is worth $1170.

$$26.0\ \cancel{g\ Au} \times \frac{1\ \cancel{troy\ oz}}{31.10\ \cancel{g}} \times \frac{\$1400}{1\ \cancel{troy\ oz\ Au}} = \$1170$$

? Exercise 6.3.1 : Lanthanum Oxalate

What mass of solid lanthanum(III) oxalate nonahydrate $[La_2(C_2O_4)_3{\cdot}9H_2O]$ can be obtained from 650 mL of a 0.0170 M aqueous solution of $LaCl_3$ by adding a stoichiometric amount of sodium oxalate?

Answer

3.89 g

Summary

Either the masses or the volumes of solutions of reactants and products can be used to determine the amounts of other species in the balanced chemical equation. Quantitative calculations that involve the stoichiometry of reactions in solution use volumes of solutions of known concentration instead of masses of reactants or products. The coefficients in the balanced chemical equation tell how many moles of reactants are needed and how many moles of product can be produced.

6.3: solution stoichiometry is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **2.4: Atomic Structure and Symbolism** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **3.6: Quantitative Information from Balanced Equations** is licensed CC BY-NC-SA 3.0.

6.4: Quantitative Analysis-Titration and Gravimetric Analysis

Learning Objectives

- Describe the fundamental aspects of titrations and gravimetric analysis.
- Perform stoichiometric calculations using typical titration and gravimetric data.

In the 18th century, the strength (actually the concentration) of vinegar samples was determined by noting the amount of potassium carbonate, K_2CO_3, which had to be added, a little at a time, before bubbling ceased. The greater the weight of potassium carbonate added to reach the point where the bubbling ended, the more concentrated the vinegar.

We now know that the effervescence that occurred during this process was due to reaction with acetic acid, CH_3CO_2H, the compound primarily responsible for the odor and taste of vinegar. Acetic acid reacts with potassium carbonate according to the following equation:


$$2\,CH_3CO_2H(aq) + K_2CO_3(s) \rightarrow 2KCH_3CO_3(aq) + CO_2(g) + H_2O(l) \tag{6.4.1}$$

The bubbling was due to the production of CO_2.

The test of vinegar with potassium carbonate is one type of quantitative analysis—the determination of the amount or concentration of a substance in a sample. In the analysis of vinegar, the concentration of the solute (acetic acid) was determined from the amount of reactant that combined with the solute present in a known volume of the solution. In other types of chemical analyses, the amount of a substance present in a sample is determined by measuring the amount of product that results.

Titration

The described approach to measuring vinegar strength was an early version of the analytical technique known as titration analysis. A typical titration analysis involves the use of a buret (Figure **6.4.1**) to make incremental additions of a solution containing a known concentration of some substance (the titrant) to a sample solution containing the substance whose concentration is to be measured (the analyte). The titrant and analyte undergo a chemical reaction of known stoichiometry, and so measuring the volume of titrant solution required for complete reaction with the analyte (the equivalence point of the titration) allows calculation of the analyte concentration. The equivalence point of a titration may be detected visually if a distinct change in the appearance of the sample solution accompanies the completion of the reaction. The halt of bubble formation in the classic vinegar analysis is one such example, though, more commonly, special dyes called indicators are added to the sample solutions to impart a change in color at or very near the equivalence point of the titration. Equivalence points may also be detected by measuring some solution property that changes in a predictable way during the course of the titration. Regardless of the approach taken to detect a titration's equivalence point, the volume of titrant actually measured is called the end point. Properly designed titration methods typically ensure that the difference between the equivalence and end points is negligible. Though any type of chemical reaction may serve as the basis for a titration analysis, the three described in this chapter (precipitation, acid-base, and redox) are most common. Additional details regarding titration analysis are provided in the chapter on acid-base equilibria.



(a) (b)

Figure 6.4.1: (a) A student fills a buret in preparation for a titration analysis. (b) A typical buret permits volume measurements to the nearest 0.1 mL. (credit a: modification of work by Mark Blaser and Matt Evans; credit b: modification of work by Mark Blaser and Matt Evans)

Example 6.4.1: Titration Analysis

The end point in a titration of a 50.00-mL sample of aqueous HCl was reached by addition of 35.23 mL of 0.250 M NaOH titrant. The titration reaction is:


$$\mathrm{HCl}(aq) + \mathrm{NaOH}(aq) \rightarrow \mathrm{NaCl}(aq) + \mathrm{H_2O}(l) \tag{6.4.2}$$

What is the molarity of the HCl?

Solution

As for all reaction stoichiometry calculations, the key issue is the relation between the molar amounts of the chemical species of interest as depicted in the balanced chemical equation. The approach outlined in previous modules of this chapter is followed, with additional considerations required, since the amounts of reactants provided and requested are expressed as solution concentrations.

For this exercise, the calculation will follow the following outlined steps:



The molar amount of HCl is calculated to be:

$$35.23\ \cancel{\text{mL NaOH}} \times \frac{1\ \cancel{L}}{1000\ \cancel{\text{mL}}} \times \frac{0.250\ \cancel{\text{mol NaOH}}}{1\ \cancel{L}} \times \frac{1\ \text{mol HCl}}{1\ \cancel{\text{mol NaOH}}} = 8.81 \times 10^{-3}\ \text{mol HCl} \tag{6.4.3}$$

Using the provided volume of HCl solution and the definition of molarity, the HCl concentration is:

$$M = \frac{\text{mol HCl}}{\text{L solution}}$$
$$M = \frac{8.81 \times 10^{-3}\ \text{mol HCl}}{50.00\ \text{mL} \times \frac{1\ \text{L}}{1000\ \text{mL}}}$$
$$M = 0.176\ M$$

Note: For these types of titration calculations, it is convenient to recognize that solution molarity is also equal to the number of *milli*moles of solute per *milli*liter of solution:

$$M = \frac{\text{mol solute}}{\text{L solution}} \times \frac{\frac{10^3\ \text{mmol}}{\text{mol}}}{\frac{10^3\ \text{mL}}{\text{L}}} = \frac{\text{mmol solute}}{\text{mL solution}} \tag{6.4.4}$$

Using this version of the molarity unit will shorten the calculation by eliminating two conversion factors:

$$\frac{35.23\ \text{mL NaOH} \times \frac{0.250\ \text{mmol NaOH}}{\text{mL NaOH}} \times \frac{1\ \text{mmol HCl}}{1\ \text{mmol NaOH}}}{50.00\ \text{mL solution}} = 0.176\ M\ \text{HCl} \tag{6.4.5}$$

Exercise 6.4.1

A 20.00-mL sample of aqueous oxalic acid, $H_2C_2O_4$, was titrated with a 0.09113-*M* solution of potassium permanganate, $KMnO_4$.

$$2\,MnO_4^-(aq) + 5\,H_2C_2O_4(aq) + 6\,H^+(aq) \rightarrow 10\,CO_2(g) + 2\,Mn^{2+}(aq) + 8\,H_2O(l) \tag{6.4.6}$$

A volume of 23.24 mL was required to reach the end point. What is the oxalic acid molarity?

Answer

0.2648 *M*



Calculations Involving Titrations: https://youtu.be/GuGusTXmEbE

Gravimetric Analysis

A gravimetric analysis is one in which a sample is subjected to some treatment that causes a change in the physical state of the analyte that permits its separation from the other components of the sample. Mass measurements of the sample, the isolated analyte, or some other component of the analysis system, used along with the known stoichiometry of the compounds involved, permit calculation of the analyte concentration. Gravimetric methods were the first techniques used for quantitative chemical analysis, and they remain important tools in the modern chemistry laboratory.

The required change of state in a gravimetric analysis may be achieved by various physical and chemical processes. For example, the moisture (water) content of a sample is routinely determined by measuring the mass of a sample before and after it is subjected to a controlled heating process that evaporates the water. Also common are gravimetric techniques in which the analyte is subjected to a precipitation reaction of the sort described earlier in this chapter. The precipitate is typically isolated from the reaction mixture by filtration, carefully dried, and then weighed (Figure **6.4.2**). The mass of the precipitate may then be used, along with relevant stoichiometric relationships, to calculate analyte concentration.



Figure **6.4.2**: Precipitate may be removed from a reaction mixture by filtration.

Example 6.4.2: Gravimetric Analysis


A 0.4550-g solid mixture containing $MgSO_4$ is dissolved in water and treated with an excess of $Ba(NO_3)_2$, resulting in the precipitation of 0.6168 g of $BaSO_4$.

$$MgSO_4(aq) + Ba(NO_3)_2(aq) \rightarrow BaSO_4(s) + Mg(NO_3)_2(aq) \tag{6.4.7}$$

What is the concentration (percent) of $MgSO_4$ in the mixture?

Solution

The plan for this calculation is similar to others used in stoichiometric calculations, the central step being the connection between the moles of $BaSO_4$ and $MgSO_4$ through their stoichiometric factor. Once the mass of $MgSO_4$ is computed, it may be used along with the mass of the sample mixture to calculate the requested percentage concentration.



The mass of $MgSO_4$ that would yield the provided precipitate mass is

$$0.6168\ \cancel{\text{g BaSO}_4} \times \frac{1\ \cancel{\text{mol BaSO}_4}}{233.43\ \cancel{\text{g BaSO}_4}} \times \frac{1\ \cancel{\text{mol MgSO}_4}}{1\ \cancel{\text{mol BaSO}_4}} \times \frac{120.37\ \text{g MgSO}_4}{1\ \cancel{\text{mol MgSO}_4}} = 0.3181\ \text{g MgSO}_4 \tag{6.4.8}$$

The concentration of $MgSO_4$ in the sample mixture is then calculated to be

$$\text{percent MgSO}_4 = \frac{mass\ MgSO4}{mass\ sample} \times 100\%$$

$$\frac{0.3181\ \text{g}}{0.4550\ \text{g}} \times 100\% = 69.91\%$$

? Exercise 6.4.2

What is the percent of chloride ion in a sample if 1.1324 g of the sample produces 1.0881 g of AgCl when treated with excess Ag^+?

$$Ag^+(aq) + Cl^-(aq) \rightarrow AgCl(s)$$

Answer

23.76%

Summary

The stoichiometry of chemical reactions may serve as the basis for quantitative chemical analysis methods. Titrations involve measuring the volume of a titrant solution required to completely react with a sample solution. This volume is then used to calculate the concentration of analyte in the sample using the stoichiometry of the titration reaction. Gravimetric analysis involves separating the analyte from the sample by a physical or chemical process, determining its mass, and then calculating its concentration in the sample based on the stoichiometry of the relevant process. Combustion analysis is a gravimetric method used to determine the elemental composition of a compound by collecting and weighing the gaseous products of its combustion.

Glossary

analyte
chemical species of interest

buret
device used for the precise delivery of variable liquid volumes, such as in a titration analysis

combustion analysis
gravimetric technique used to determine the elemental composition of a compound via the collection and weighing of its gaseous combustion products

end point
measured volume of titrant solution that yields the change in sample solution appearance or other property expected for stoichiometric equivalence (see *equivalence point*)

equivalence point
volume of titrant solution required to react completely with the analyte in a titration analysis; provides a stoichiometric amount of titrant for the sample's analyte according to the titration reaction

gravimetric analysis
quantitative chemical analysis method involving the separation of an analyte from a sample by a physical or chemical process and subsequent mass measurements of the analyte, reaction product, and/or sample

indicator

substance added to the sample in a titration analysis to permit visual detection of the end point

quantitative analysis

the determination of the amount or concentration of a substance in a sample

titrant

solution containing a known concentration of substance that will react with the analyte in a titration analysis

titration analysis


quantitative chemical analysis method that involves measuring the volume of a reactant solution required to completely react with the analyte in a sample

---

6.4: Quantitative Analysis-Titration and Gravimetric Analysis is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **4.6: Quantitative Chemical Analysis** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

6.5: End of Chapter Problems

1. Write the balanced equation, then outline the steps necessary to determine the information requested in each of the following:
    a. The number of moles and the mass of chlorine, Cl_2, required to react with 10.0 g of sodium metal, Na, to produce sodium chloride, NaCl.
    b. The number of moles and the mass of oxygen formed by the decomposition of 1.252 g of mercury(II) oxide.
    c. The number of moles and the mass of sodium nitrate, $NaNO_3$, required to produce 128 g of oxygen. ($NaNO_2$ is the other product.)
    d. The number of moles and the mass of carbon dioxide formed by the combustion of 20.0 kg of carbon in an excess of oxygen.
    e. The number of moles and the mass of copper(II) carbonate needed to produce 1.500 kg of copper(II) oxide. (CO_2 is the other product.)
    f. 

2. Write the balanced equation, then outline the steps necessary to determine the information requested in each of the following:
    a. The number of moles and the mass of Mg required to react with 5.00 g of HCl and produce $MgCl_2$ and H_2.
    b. The number of moles and the mass of oxygen formed by the decomposition of 1.252 g of silver(I) oxide.
    c. The number of moles and the mass of magnesium carbonate, $MgCO_3$, required to produce 283 g of carbon dioxide. (MgO is the other product.)
    d. The number of moles and the mass of water formed by the combustion of 20.0 kg of acetylene, C_2H_2, in an excess of oxygen.
    e. The number of moles and the mass of barium peroxide, BaO_2, needed to produce 2.500 kg of barium oxide, BaO (O_2 is the other product.)

Answer

a. 0.0686 mol Mg, 1.67 g Mg; b. 2.701×10^{-3} mol O_2, 0.08644 g O_2; c. 6.43 mol $MgCO_3$, 542 g $MgCO_3$; d. 713 mol H_2O, 12.8 kg H_2O; e. 16.31 mol BaO_2, 2762 g BaO_2

3. H_2 is produced by the reaction of 118.5 mL of a 0.8775-M solution of H_3PO_4 according to the following equation:
$\mathbf{2\,Cr + 2\,H_3PO_4 \rightarrow 3\,H_2 + 2\,CrPO_4}$.
    a. Outline the steps necessary to determine the number of moles and mass of H_2.
    b. Perform the calculations outlined.

Answer

a.)

Convert mL to L Multiply L by the molarity to determine moles of H_3PO_4 Convert moles of H_3PO_4 to moles of H_2 Multiply moles of H_2 by the molar mass of H_2 to get the answer in grams

b.)

1. $\mathbf{118.5\,mL \times \dfrac{1\,L}{1000\,mL} = 0.1185\,L}$
2. $\mathbf{0.1185\,L \times \dfrac{0.8775\,moles\,H_3PO_4}{1\,L} = 0.1040\,moles\,H_3PO_4}$
3. $\mathbf{0.1040\,moles\,H_3PO_4 \times \dfrac{3\,moles\,H_2}{2\,moles\,H_3PO_4} = 0.1560\,moles\,H_2}$
4. $\mathbf{0.1560\,moles\,H_2 \times \dfrac{2.02g}{1\,mole} = 0.3151g\,H_2}$

4. Gallium chloride is formed by the reaction of 2.6 L of a 1.44 M solution of HCl according to the following equation: $2\,Ga + 6\,HCl \rightarrow 2\,GaCl_3 + 3\,H_2$.

    a. Outline the steps necessary to determine the number of moles and mass of gallium chloride.
    b. Perform the calculations outlined.

Answer

$\text{volume HCl solution} \rightarrow \text{mol HCl} \rightarrow \text{mol } GaCl_3$; 1.25 mol $GaCl_3$, 2.2×10^2 g $GaCl_3$

5. I_2 is produced by the reaction of 0.4235 mol of $CuCl_2$ according to the following equation: $2\,CuCl_2 + 4\,KI \rightarrow 2\,CuI + 4\,KCl + I_2$.

    a. How many molecules of I_2 are produced?
    b. What mass of I_2 is produced?

6. Silver is often extracted from ores as $K[Ag(CN)_2]$ and then recovered by the reaction

$$2\,K[Ag(CN)_2](aq) + Zn(s) \rightarrow 2\,Ag(s) + Zn(CN)_2(aq) + 2\,KCN(aq)$$

    a. How many molecules of $Zn(CN)_2$ are produced by the reaction of 35.27 g of $K[Ag(CN)_2]$?
    b. What mass of $Zn(CN)_2$ is produced?

Answer

5.337×10^{22} molecules; 10.41 g $Zn(CN)_2$

7. What mass of silver oxide, Ag_2O, is required to produce 25.0 g of silver sulfadiazine, $AgC_{10}H_9N_4SO_2$, from the reaction of silver oxide and sulfadiazine?

$$2\,C_{10}H_{10}N_4SO_2 + Ag_2O \rightarrow 2\,AgC_{10}H_9N_4SO_2 + H_2O$$

8. Carborundum is silicon carbide, SiC, a very hard material used as an abrasive on sandpaper and in other applications. It is prepared by the reaction of pure sand, SiO_2, with carbon at high temperature. Carbon monoxide, CO, is the other product of this reaction. Write the balanced equation for the reaction, and calculate how much SiO_2 is required to produce 3.00 kg of SiC.

Answer

$SiO_2 + 3\,C \rightarrow SiC + 2\,CO$, 4.50 kg SiO_2

9. Automotive air bags inflate when a sample of sodium azide, NaN_3, is very rapidly decomposed.

$$2\,NaN_3(s) \rightarrow 2\,Na(s) + 3\,N_2(g)$$

What mass of sodium azide is required to produce 2.6 ft^3 (73.6 L) of nitrogen gas with a density of 1.25 g/L?

Answer

142g NaN_3

10. Urea, $CO(NH_2)_2$, is manufactured on a large scale for use in producing urea-formaldehyde plastics and as a fertilizer. What is the maximum mass of urea that can be manufactured from the CO_2 produced by combustion of 1.00×10^3 kg of carbon followed by the reaction?

$$CO_2(g) + 2\,NH_3(g) \rightarrow CO(NH_2)_2(s) + H_2O(l) \tag{6.5.1}$$

Answer

5.00×10^3 kg

11. In an accident, a solution containing 2.5 kg of nitric acid was spilled. Two kilograms of Na_2CO_3 was quickly spread on the area and CO_2 was released by the reaction. Was sufficient Na_2CO_3 used to neutralize all of the acid?
12. A compact car gets 37.5 miles per gallon on the highway. If gasoline contains 84.2% carbon by mass and has a density of 0.8205 g/mL, determine the mass of carbon dioxide produced during a 500-mile trip (3.785 liters per gallon).

Answer

1.28×10^5 g CO_2

13. What volume of a 0.750 M solution of hydrochloric acid, a solution of HCl, can be prepared from the HCl produced by the reaction of 25.0 g of NaCl with an excess of sulfuric acid?

$$\mathrm{NaCl}(s) + \mathrm{H_2SO_4}(l) \rightarrow \mathrm{HCl}(g) + \mathrm{NaHSO_4}(s) \tag{6.5.2}$$

14. What volume of a 0.2089 *M* KI solution contains enough KI to react exactly with the $Cu(NO_3)_2$ in 43.88 mL of a 0.3842 *M* solution of $Cu(NO_3)_2$?

$$\mathrm{2\,Cu(NO_3)_2 + 4\,KI \rightarrow 2\,CuI + I_2 + 4\,KNO_3} \tag{6.5.3}$$

Answer

161.40 mL KI solution

15. A mordant is a substance that combines with a dye to produce a stable fixed color in a dyed fabric. Calcium acetate is used as a mordant. It is prepared by the reaction of acetic acid with calcium hydroxide.

$$\mathrm{2\,CH_3CO_2H + Ca(OH)_2 \rightarrow Ca(CH_3CO_2)_2 + 2\,H_2O} \tag{6.5.4}$$

What mass of $Ca(OH)_2$ is required to react with the acetic acid in 25.0 mL of a solution having a density of 1.065 g/mL and containing 58.0% acetic acid by mass?

16. The toxic pigment called white lead, $Pb_3(OH)_2(CO_3)_2$, has been replaced in white paints by rutile, TiO_2. How much rutile (g) can be prepared from 379 g of an ore that contains 88.3% ilmenite ($FeTiO_3$) by mass?

$$\mathrm{2\,FeTiO_3 + 4\,HCl + Cl_2 \rightarrow 2\,FeCl_3 + 2\,TiO_2 + 2\,H_2O} \tag{6.5.5}$$

Answer

176 g TiO_2

17. The following quantities are placed in a container: 1.5×10^{24} atoms of hydrogen, 1.0 mol of sulfur, and 88.0 g of diatomic oxygen.
    a. What is the total mass in grams for the collection of all three elements?
    b. What is the total number of moles of atoms for the three elements?
    c. If the mixture of the three elements formed a compound with molecules that contain two hydrogen atoms, one sulfur atom, and four oxygen atoms, which substance is consumed first?
    d. How many atoms of each remaining element would remain unreacted in the change described in ?
18. What is the limiting reactant in a reaction that produces sodium chloride from 8 g of sodium and 8 g of diatomic chlorine?

Answer

The limiting reactant is Cl_2.

19. Which of the postulates of Dalton's atomic theory explains why we can calculate a theoretical yield for a chemical reaction?
20. A student isolated 25 g of a compound following a procedure that would theoretically yield 81 g. What was his percent yield?

Answer

$\mathbf{\text{Percent yield} = 31\%}$

21. A sample of 0.53 g of carbon dioxide was obtained by heating 1.31 g of calcium carbonate. What is the percent yield for this reaction?

$$\mathrm{CaCO_3}(s) \rightarrow \mathrm{CaO}(s) + \mathrm{CO_2}(s) \tag{6.5.6}$$

22. Freon-12, CCl_2F_2, is prepared from CCl_4 by reaction with HF. The other product of this reaction is HCl. Outline the steps needed to determine the percent yield of a reaction that produces 12.5 g of CCl_2F_2 from 32.9 g of CCl_4. Freon-12 has been

banned and is no longer used as a refrigerant because it catalyzes the decomposition of ozone and has a very long lifetime in the atmosphere. Determine the percent yield.

Answer

$\text{g } CCl_4 \rightarrow \text{mol } CCl_4 \rightarrow \text{mol } CCl_2F_2 \rightarrow \text{g } CCl_2F_2$, percent yield = 48.3%

23. Citric acid, $C_6H_8O_7$, a component of jams, jellies, and fruity soft drinks, is prepared industrially via fermentation of sucrose by the mold *Aspergillus niger*. The equation representing this reaction is

$$C_{12}H_{22}O_{11} + H_2O + 3\,O_2 \rightarrow 2\,C_6H_8O_7 + 4\,H_2O \tag{6.5.7}$$

What mass of citric acid is produced from exactly 1 metric ton (1.000×10^3 kg) of sucrose if the yield is 92.30%?

24. Toluene, $C_6H_5CH_3$, is oxidized by air under carefully controlled conditions to benzoic acid, $C_6H_5CO_2H$, which is used to prepare the food preservative sodium benzoate, $C_6H_5CO_2Na$. What is the percent yield of a reaction that converts 1.000 kg of toluene to 1.21 kg of benzoic acid?

$$2\,C_6H_5CH_3 + 3\,O_2 \rightarrow 2\,C_6H_5CO_2H + 2\,H_2O \tag{6.5.8}$$

Answer

percent yield = 91.3%

25. In a laboratory experiment, the reaction of 3.0 mol of H_2 with 2.0 mol of I_2 produced 1.0 mol of HI. Determine the theoretical yield in grams and the percent yield for this reaction.

26. Outline the steps needed to solve the following problem, then do the calculations. Ether, $(C_2H_5)_2O$, which was originally used as an anesthetic but has been replaced by safer and more effective medications, is prepared by the reaction of ethanol with sulfuric acid.

$$2C_2H_5OH + H_2SO_4 \longrightarrow (C_2H_5)_2 + H_2SO_4{\cdot}H_2O$$

27. What is the percent yield of ether if 1.17 L (d = 0.7134 g/mL) is isolated from the reaction of 1.500 L of C_2H_5OH (d = 0.7894 g/mL)?

Answer

Convert mass of ethanol to moles of ethanol; relate the moles of ethanol to the moles of ether produced using the stoichiometry of the balanced equation. Convert moles of ether to grams; divide the actual grams of ether (determined through the density) by the theoretical mass to determine the percent yield; 87.6%

28. Outline the steps needed to determine the limiting reactant when 30.0 g of propane, C_3H_8, is burned with 75.0 g of oxygen.

$$\text{percent yield} = \frac{0.8347\ \cancel{g}}{0.9525\ \cancel{g}} \times 100\% = 87.6\% \tag{6.5.9}$$

Determine the limiting reactant.

29. Outline the steps needed to determine the limiting reactant when 0.50 g of Cr and 0.75 g of H_3PO_4 react according to the following chemical equation?

$$2\,Cr + 2\,H_3PO_4 \rightarrow 2\,CrPO_4 + 3\,H_2 \tag{6.5.10}$$

Determine the limiting reactant.

Answer

The conversion needed is $\text{mol Cr} \rightarrow \text{mol } H_2PO_4$. Then compare the amount of Cr to the amount of acid present. Cr is the limiting reactant.

Q4.4.14

30. What is the limiting reactant when 1.50 g of lithium and 1.50 g of nitrogen combine to form lithium nitride, a component of advanced batteries, according to the following unbalanced equation?

$$\mathrm{Li} + \mathrm{N_2} \rightarrow \mathrm{Li_3N} \tag{6.5.11}$$

Answer

$$6\,\mathrm{Li} + \mathrm{N_2} \rightarrow 2\,\mathrm{Li_3N} \tag{6.5.12}$$

$$1.50 g\,\mathrm{Li} \times \frac{1\ mole\ \mathrm{Li}}{6.94 g\ \mathrm{Li}} \times \frac{2\ mole\ \mathrm{Li_3N}}{6\ mole\ \mathrm{Li}} = 0.0720\ moles\ \mathrm{Li_3N} \tag{6.5.13}$$

$$1.50 g\,\mathrm{N_2} \times \frac{1\ mole\ \mathrm{N_2}}{28.02 g\ \mathrm{N_2}} \times \frac{2\ mole\ \mathrm{Li_3N}}{1\ mole\ \mathrm{N_2}} = 0.107\ moles\ \mathrm{Li_3N} \tag{6.5.14}$$

Li is the limiting reactant

31. Uranium can be isolated from its ores by dissolving it as $UO_2(NO_3)_2$, then separating it as solid $UO_2(C_2O_4)\cdot 3H_2O$. Addition of 0.4031 g of sodium oxalate, $Na_2C_2O_4$, to a solution containing 1.481 g of uranyl nitrate, $UO_2(NO_2)_2$, yields 1.073 g of solid $UO_2(C_2O_4)\cdot 3H_2O$.

$$\mathrm{Na_2C_2O_4 + UO_2(NO_3)_2 + 3\,H_2O \longrightarrow UO_2(C_2O_4)\cdot 3\,H_2O + 2\,NaNO_3} \tag{6.5.15}$$


Determine the limiting reactant and the percent yield of this reaction.

Answer

$Na_2C_2O_4$ is the limiting reactant. percent yield = 86.6%

32. How many molecules of $C_2H_4Cl_2$ can be prepared from 15 C_2H_4 molecules and 8 Cl_2 molecules?

33. How many molecules of the sweetener saccharin can be prepared from 30 C atoms, 25 H atoms, 12 O atoms, 8 S atoms, and 14 N atoms?



Answer

Only four molecules can be made.

34. The phosphorus pentoxide used to produce phosphoric acid for cola soft drinks is prepared by burning phosphorus in oxygen.

    a. What is the limiting reactant when 0.200 mol of P_4 and 0.200 mol of O_2 react according to

$$\mathrm{P_4 + 5\,O_2 \rightarrow P_4O_{10}} \tag{6.5.16}$$

    b. Calculate the percent yield if 10.0 g of P_4O_{10} is isolated from the reaction.

Would you agree to buy 1 trillion (1,000,000,000,000) gold atoms for $5? Explain why or why not. Find the current price of gold at http://money.cnn.com/data/commodities/ **(1 troy ounce = 31.1 g)**

Answer

This amount cannot be weighted by ordinary balances and is worthless.

4.5: Quantitative Chemical Analysis

35. What volume of 0.0105-M HBr solution is be required to titrate 125 mL of a 0.0100-*M* $Ca(OH)_2$ solution?

$$Ca(OH)_2(aq) + 2\,HBr(aq) \rightarrow CaBr_2(aq) + 2\,H_2O(l) \tag{6.5.17}$$

36. Titration of a 20.0-mL sample of acid rain required 1.7 mL of 0.0811 *M* NaOH to reach the end point. If we assume that the acidity of the rain is due to the presence of sulfuric acid, what was the concentration of sulfuric acid in this sample of rain?

Answer

3.4×10^{-3} *M* H_2SO_4

37. What is the concentration of NaCl in a solution if titration of 15.00 mL of the solution with 0.2503 *M* $AgNO_3$ requires 20.22 mL of the $AgNO_3$ solution to reach the end point?

$$AgNO_3(aq) + NaCl(aq) \rightarrow AgCl(s) + NaNO_3(aq) \tag{6.5.18}$$

38. In a common medical laboratory determination of the concentration of free chloride ion in blood serum, a serum sample is titrated with a $Hg(NO_3)_2$ solution.

$$2\,Cl^-(aq) + Hg(NO_3)_2(aq) \rightarrow 2\,NO_3{}^-(aq) + HgCl_2(s) \tag{6.5.19}$$

What is the Cl^- concentration in a 0.25-mL sample of normal serum that requires 1.46 mL of 5.25×10^{-4} *M* $Hg(NO_3)_2(aq)$ to reach the end point?

Answer

9.6×10^{-3} *M* Cl^-

39. Potatoes can be peeled commercially by soaking them in a 3-M to 6-M solution of sodium hydroxide, then removing the loosened skins by spraying them with water. Does a sodium hydroxide solution have a suitable concentration if titration of 12.00 mL of the solution requires 30.6 mL of 1.65 M HCI to reach the end point?
40. A sample of gallium bromide, $GaBr_2$, weighing 0.165 g was dissolved in water and treated with silver nitrate, $AgNO_3$, resulting in the precipitation of 0.299 g AgBr. Use these data to compute the %Ga (by mass) $GaBr_2$.

Answer

22.4%

41. The principal component of mothballs is naphthalene, a compound with a molecular mass of about 130 amu, containing only carbon and hydrogen. A 3.000-mg sample of naphthalene burns to give 10.3 mg of CO_2. Determine its empirical and molecular formulas.
42. A 0.025-g sample of a compound composed of boron and hydrogen, with a molecular mass of ~28 amu, burns spontaneously when exposed to air, producing 0.063 g of B_2O_3. What are the empirical and molecular formulas of the compound.

Answer

The empirical formula is BH_3. The molecular formula is B_2H_6.

43. Sodium bicarbonate (baking soda), $NaHCO_3$, can be purified by dissolving it in hot water (60 °C), filtering to remove insoluble impurities, cooling to 0 °C to precipitate solid $NaHCO_3$, and then filtering to remove the solid, leaving soluble impurities in solution. Any $NaHCO_3$ that remains in solution is not recovered. The solubility of $NaHCO_3$ in hot water of 60 °C is 164 g L. Its solubility in cold water of 0 °C is 69 g/L. What is the percent yield of $NaHCO_3$ when it is purified by this method?
44. What volume of 0.600 *M* HCl is required to react completely with 2.50 g of sodium hydrogen carbonate?

$$NaHCO_3(aq) + HCl(aq) \rightarrow NaCl(aq) + CO_2(g) + H_2O(l) \tag{6.5.20}$$

Answer

49.6 mL

45. What volume of 0.08892 *M* HNO_3 is required to react completely with 0.2352 g of potassium hydrogen phosphate?

$$2\,HNO_3(aq) + K_2HPO_4(aq) \rightarrow H_2PO_4(aq) + 2\,KNO_3(aq) \tag{6.5.21}$$

46. What volume of a 0.3300-*M* solution of sodium hydroxide would be required to titrate 15.00 mL of 0.1500 *M* oxalic acid?

$$C_2O_4H_2(aq) + 2\,NaOH(aq) \rightarrow Na_2C_2O_4(aq) + 2\,H_2O(l) \tag{6.5.22}$$

Answer

13.64 mL

47. What volume of a 0.00945-*M* solution of potassium hydroxide would be required to titrate 50.00 mL of a sample of acid rain with a H_2SO_4 concentration of 1.23×10^{-4} *M*.

$$H_2SO_4(aq) + 2\,KOH(aq) \rightarrow K_2SO_4(aq) + 2\,H_2O(l) \tag{6.5.23}$$

Answer

1.30 mL

48. A sample of solid calcium hydroxide, $Ca(OH)_2$, is allowed to stand in water until a saturated solution is formed. A titration of 75.00 mL of this solution with 5.00×10^{-2} *M* HCl requires 36.6 mL of the acid to reach the end point.


$$Ca(OH)_2(aq) + 2\,HCl(aq) \rightarrow CaCl_2(aq) + 2\,H_2O(l) \tag{6.5.24}$$

What is the molarity?

Answer

1.22 *M*

49. What mass of $Ca(OH)_2$ will react with 25.0 g of propionic acid to form the preservative calcium propionate according to the equation?



50. How many milliliters of a 0.1500-*M* solution of KOH will be required to titrate 40.00 mL of a 0.0656-*M* solution of H_3PO_4?

$$H_3PO_4(aq) + 2\,KOH(aq) \rightarrow K_2HPO_4(aq) + 2\,H_2O(l) \tag{6.5.25}$$

Answer

34.99 mL KOH

51. Potassium acid phthalate, $KHC_6H_4O_4$, or KHP, is used in many laboratories, including general chemistry laboratories, to standardize solutions of base. KHP is one of only a few stable solid acids that can be dried by warming and weighed. A 0.3420-g sample of $KHC_6H_4O_4$ reacts with 35.73 mL of a NaOH solution in a titration. What is the molar concentration of the NaOH?

$$KHC_6H_4O_4(aq) + NaOH(aq) \rightarrow KNaC_6H_4O_4(aq) + H_2O(aq) \tag{6.5.26}$$

52. The reaction of WCl_6 with Al at ~400 °C gives black crystals of a compound containing only tungsten and chlorine. A sample of this compound, when reduced with hydrogen, gives 0.2232 g of tungsten metal and hydrogen chloride, which is absorbed in water. Titration of the hydrochloric acid thus produced requires 46.2 mL of 0.1051 *M* NaOH to reach the end point. What is the empirical formula of the black tungsten chloride?

Answer

The empirical formula is WCl_4.

6.5: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

7: Gases

7.1: Pressure of the Gas
7.2: simple Gas Laws
7.3: Ideal Gas Law
7.4: Applying the Ideal Gas Law
7.5: Mixture of Gases
7.6: Gas Stoichiometry
7.7: Effusion and Diffusion of Gases
7.8: Kinetic Molecular Theory
7.9: Non Ideal Gas Behavior
7.10: End of Chapter Problems

7: Gases is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

7.1: Pressure of the Gas

Learning Objectives

- Define the property of pressure
- Define and convert among the units of pressure measurements
- Describe the operation of common tools for measuring gas pressure
- Calculate pressure from manometer data

The earth's atmosphere exerts a pressure, as does any other gas. Although we do not normally notice atmospheric pressure, we are sensitive to pressure changes—for example, when your ears "pop" during take-off and landing while flying, or when you dive underwater. Gas pressure is caused by the force exerted by gas molecules colliding with the surfaces of objects (Figure **7.1.1**). Although the force of each collision is very small, any surface of appreciable area experiences a large number of collisions in a short time, which can result in a high pressure. In fact, normal air pressure is strong enough to crush a metal container when not balanced by equal pressure from inside the container.




Figure **7.1.1**: The atmosphere above us exerts a large pressure on objects at the surface of the earth, roughly equal to the weight of a bowling ball pressing on an area the size of a human thumbnail.

Atmospheric pressure is caused by the weight of the column of air molecules in the atmosphere above an object, such as the tanker car. At sea level, this pressure is roughly the same as that exerted by a full-grown African elephant standing on a doormat, or a typical bowling ball resting on your thumbnail. These may seem like huge amounts, and they are, but life on earth has evolved under such atmospheric pressure. If you actually perch a bowling ball on your thumbnail, the pressure experienced is twice the usual pressure, and the sensation is unpleasant.



A dramatic illustration of atmospheric pressure is provided in this brief video, which shows a railway tanker car imploding when its internal pressure is decreased.

Pressure is defined as the force exerted on a given area:

$$P = \frac{F}{A} \tag{7.1.1}$$

Since pressure is directly proportional to force and inversely proportional to area (Equation 7.1.1), pressure can be increased either by either **increasing** the amount of force or by **decreasing** the area over which it is applied. Correspondingly, pressure can be decreased by either **decreasing** the force or **increasing** the area.

Let's apply the definition of pressure (Equation 7.1.1) to determine which would be more likely to fall through thin ice in Figure **7.1.2**.—the elephant or the figure skater?



Figure **7.1.2**: Although (a) an elephant's weight is large, creating a very large force on the ground, (b) the figure skater exerts a much higher pressure on the ice due to the small surface area of her skates. (credit a: modification of work by Guido da Rozze; credit b: modification of work by Ryosuke Yagi).

A large African elephant can weigh 7 tons, supported on four feet, each with a diameter of about 1.5 ft (footprint area of 250 in^2), so the pressure exerted by each foot is about 14 lb/in^2:

$$\text{pressure per elephant foot} = 14,000\frac{\text{lb}}{\text{elephant}} \times \frac{1\text{ elephant}}{4\text{ feet}} \times \frac{1\text{ foot}}{250\text{ in}^2} = 14\text{ lb/in}^2 \tag{7.1.2}$$

The figure skater weighs about 120 lbs, supported on two skate blades, each with an area of about 2 in^2, so the pressure exerted by each blade is about 30 lb/in^2:

$$\text{pressure per skate blade} = 120\frac{\text{lb}}{\text{skater}} \times \frac{1\text{ skater}}{2\text{ blades}} \times \frac{1\text{ blade}}{2\text{ in}^2} = 30\text{ lb/in}^2 \tag{7.1.3}$$

Even though the elephant is more than one hundred times heavier than the skater, it exerts less than one-half of the pressure and would therefore be less likely to fall through thin ice. On the other hand, if the skater removes her skates and stands with bare feet (or regular footwear) on the ice, the larger area over which her weight is applied greatly reduces the pressure exerted:

$$\text{pressure per human foot} = 120\frac{\text{lb}}{\text{skater}} \times \frac{1\text{ skater}}{2\text{ feet}} \times \frac{1\text{ foot}}{30\text{ in}^2} = 2\text{ lb/in}^2 \tag{7.1.4}$$

The SI unit of pressure is the pascal (Pa), with 1 Pa = 1 N/m^2, where N is the newton, a unit of force defined as 1 kg m/s^2. One pascal is a small pressure; in many cases, it is more convenient to use units of kilopascal (1 kPa = 1000 Pa) or bar (1 bar = 100,000 Pa). In the United States, pressure is often measured in pounds of force on an area of one square inch—pounds per square inch (psi)—for example, in car tires. Pressure can also be measured using the unit atmosphere (atm), which originally represented the average sea level air pressure at the approximate latitude of Paris (45°). Table **7.1.1** provides some information on these and a few other common units for pressure measurements

Table **7.1.1**: Pressure Units

Unit Name and Abbreviation	Definition or Relation to Other Unit	Comment
pascal (Pa)	1 Pa = 1 N/m^2	recommended IUPAC unit
kilopascal (kPa)	1 kPa = 1000 Pa	
pounds per square inch (psi)	air pressure at sea level is ~14.7 psi	
atmosphere (atm)	1 atm = 101,325 Pa	air pressure at sea level is ~1 atm
bar (bar, or b)	1 bar = 100,000 Pa (exactly)	commonly used in meteorology
millibar (mbar, or mb)	1000 mbar = 1 bar	
inches of mercury (in. Hg)	1 in. Hg = 3386 Pa	used by aviation industry, also some weather reports
torr	$1\ \text{torr} = \frac{1}{760}\ \text{atm}$	named after Evangelista Torricelli, inventor of the barometer
millimeters of mercury (mm Hg)	1 mm Hg ~1 torr	

Example 7.1.1: Conversion of Pressure Units

The United States National Weather Service reports pressure in both inches of Hg and millibars. Convert a pressure of 29.2 in. Hg into:

a. torr
b. atm
c. kPa
d. mbar

Solution

This is a unit conversion problem. The relationships between the various pressure units are given in Table 9.2.1.

a. $29.2\ \cancel{\text{in Hg}} \times \frac{25.4\ \cancel{\text{mm}}}{1\ \cancel{\text{in}}} \times \frac{1\ \text{torr}}{1\ \cancel{\text{mm Hg}}} = 742\ \text{torr}$

b. $742\ \cancel{\text{torr}} \times \frac{1\ \text{atm}}{760\ \cancel{\text{torr}}} = 0.976\ \text{atm}$

c. $742\ \cancel{\text{torr}} \times \frac{101.325\ \text{kPa}}{760\ \cancel{\text{torr}}} = 98.9\ \text{kPa}$

d. $98.9\ \cancel{\text{kPa}} \times \frac{1000\ \cancel{\text{Pa}}}{1\ \cancel{\text{kPa}}} \times \frac{1\ \cancel{\text{bar}}}{100,000\ \cancel{\text{Pa}}} \times \frac{1000\ \text{mbar}}{1\ \cancel{\text{bar}}} = 989\ \text{mbar}$

Exercise 7.1.1

A typical barometric pressure in Kansas City is 740 torr. What is this pressure in atmospheres, in millimeters of mercury, in kilopascals, and in bar?

Answer

0.974 atm; 740 mm Hg; 98.7 kPa; 0.987 bar

We can measure atmospheric pressure, the force exerted by the atmosphere on the earth's surface, with a barometer (Figure **7.1.3**). A barometer is a glass tube that is closed at one end, filled with a nonvolatile liquid such as mercury, and then inverted and immersed in a container of that liquid. The atmosphere exerts pressure on the liquid outside the tube, the column of liquid exerts

pressure inside the tube, and the pressure at the liquid surface is the same inside and outside the tube. The height of the liquid in the tube is therefore proportional to the pressure exerted by the atmosphere.




Figure 7.1.3: In a barometer, the height, h, of the column of liquid is used as a measurement of the air pressure. Using very dense liquid mercury (left) permits the construction of reasonably sized barometers, whereas using water (right) would require a barometer more than 30 feet tall.

If the liquid is water, normal atmospheric pressure will support a column of water over 10 meters high, which is rather inconvenient for making (and reading) a barometer. Because mercury (Hg) is about 13.6-times denser than water, a mercury barometer only needs to be $\frac{1}{13.6}$ as tall as a water barometer—a more suitable size. Standard atmospheric pressure of 1 atm at sea level (101,325 Pa) corresponds to a column of mercury that is about 760 mm (29.92 in.) high. The torr was originally intended to be a unit equal to one millimeter of mercury, but it no longer corresponds exactly. The pressure exerted by a fluid due to gravity is known as hydrostatic pressure, p:

$$p = h\rho g \tag{7.1.5}$$

where

- h is the height of the fluid,
- ρ is the density of the fluid, and
- g is acceleration due to gravity.

Example 7.1.2: Calculation of Barometric Pressure

Show the calculation supporting the claim that atmospheric pressure near sea level corresponds to the pressure exerted by a column of mercury that is about 760 mm high. The density of mercury = $13.6\,g/cm^3$.

Solution

The hydrostatic pressure is given by Equation 7.1.5, with $h = 760\,mm$, $\rho = 13.6\,g/cm^3$, and $g = 9.81\,m/s^2$. Plugging these values into the Equation 7.1.5 and doing the necessary unit conversions will give us the value we seek. (Note: We are expecting to find a pressure of ~101,325 Pa:)

$$101,325\ N/\mathrm{m}^2 = 101,325\ \frac{\mathrm{kg}\cdot\mathrm{m/s}^2}{\mathrm{m}^2} = 101,325\ \frac{\mathrm{kg}}{\mathrm{m}\cdot\mathrm{s}^2}$$

$$\begin{aligned} p &= \left(760\ \mathrm{mm}\times\frac{1\ \mathrm{m}}{1000\ \mathrm{mm}}\right)\times\left(\frac{13.6\ \mathrm{g}}{1\ \mathrm{cm}^3}\times\frac{1\ \mathrm{kg}}{1000\ \mathrm{g}}\times\frac{(100\ \mathrm{cm})^3}{(1\ \mathrm{m})^3}\right)\times\left(\frac{9.81\ \mathrm{m}}{1\ \mathrm{s}^2}\right) \\ &= (0.760\ \mathrm{m})(13,600\ \mathrm{kg/m}^3)(9.81\ \mathrm{m/s}^2) = 1.01\times10^5\ \mathrm{kg/ms}^2 = 1.01\times10^5 N/\mathrm{m}^2 \\ &= 1.01\times10^5\ \mathrm{Pa} \end{aligned}$$

Exercise 7.1.2

Calculate the height of a column of water at 25 °C that corresponds to normal atmospheric pressure. The density of water at this temperature is 1.0 g/cm^3.

Answer

10.3 m

A manometer is a device similar to a barometer that can be used to measure the pressure of a gas trapped in a container. A closed-end manometer is a U-shaped tube with one closed arm, one arm that connects to the gas to be measured, and a nonvolatile liquid (usually mercury) in between. As with a barometer, the distance between the liquid levels in the two arms of the tube (*h* in the diagram) is proportional to the pressure of the gas in the container. An open-end manometer (Figure **7.1.3**) is the same as a closed-end manometer, but one of its arms is open to the atmosphere. In this case, the distance between the liquid levels corresponds to the difference in pressure between the gas in the container and the atmosphere.





Figure **7.1.4**: A manometer can be used to measure the pressure of a gas. The (difference in) height between the liquid levels (h) is a measure of the pressure. Mercury is usually used because of its large density.

Example 7.1.3: Calculation of Pressure Using an Open-End Manometer

The pressure of a sample of gas is measured at sea level with an open-end Hg (mercury) manometer, as shown below. Determine the pressure of the gas in:

a. mm Hg
b. atm
c. kPa



Solution

The pressure of the gas equals the hydrostatic pressure due to a column of mercury of height 13.7 cm plus the pressure of the atmosphere at sea level. (The pressure at the bottom horizontal line is equal on both sides of the tube. The pressure on the left

is due to the gas and the pressure on the right is due to 13.7 cm of Hg plus atmospheric pressure.)

a. In mm Hg, this is: 137 mm Hg + 760 mm Hg = 897 mm Hg


b. $897 \cancel{\text{ mmHg}} \times \dfrac{1 \text{ atm}}{760 \cancel{\text{ mmHg}}} = 1.18 \text{ atm}$

c. $1.18 \cancel{\text{ atm}} \times \dfrac{101.325 \text{ kPa}}{1 \cancel{\text{ atm}}} = 1.20 \times 10^2 \text{ kPa}$

Exercise 7.1.3

The pressure of a sample of gas is measured at sea level with an open-end Hg manometer, as shown below Determine the pressure of the gas in:

a. mm Hg
b. atm
c. kPa



Answer a

642 mm Hg

Answer b

0.845 atm

Answer c

85.6 kPa

Application: Measuring Blood Pressure

Blood pressure is measured using a device called a sphygmomanometer (Greek *sphygmos* = “pulse”). It consists of an inflatable cuff to restrict blood flow, a manometer to measure the pressure, and a method of determining when blood flow begins and when it becomes impeded (Figure **7.1.5**). Since its invention in 1881, it has been an essential medical device. There are many types of sphygmomanometers: manual ones that require a stethoscope and are used by medical professionals; mercury ones, used when the most accuracy is required; less accurate mechanical ones; and digital ones that can be used with little training but that have limitations. When using a sphygmomanometer, the cuff is placed around the upper arm and inflated until blood flow is completely blocked, then slowly released. As the heart beats, blood forced through the arteries causes a rise in pressure. This rise in pressure at which blood flow begins is the *systolic pressure*—the peak pressure in the cardiac cycle. When the cuff’s pressure equals the arterial systolic pressure, blood flows past the cuff, creating audible sounds that can be heard using a stethoscope. This is followed by a decrease in pressure as the heart’s ventricles prepare for another beat. As cuff pressure continues to decrease, eventually sound is no longer heard; this is the *diastolic pressure*—the lowest pressure (resting phase) in the cardiac cycle. Blood pressure units from a sphygmomanometer are in terms of millimeters of mercury (mm Hg).



Figure 7.1.5: (a) A medical technician prepares to measure a patient's blood pressure with a sphygmomanometer. (b) A typical sphygmomanometer uses a valved rubber bulb to inflate the cuff and a diaphragm gauge to measure pressure. (credit a: modification of work by Master Sgt. Jeffrey Allen)



Defining Gas Pressure: https://youtu.be/_CRn3cFs2CI

Meteorology, Climatology, and Atmospheric Science

Throughout the ages, people have observed clouds, winds, and precipitation, trying to discern patterns and make predictions: when it is best to plant and harvest; whether it is safe to set out on a sea voyage; and much more. We now face complex weather and atmosphere-related challenges that will have a major impact on our civilization and the ecosystem. Several different scientific disciplines use chemical principles to help us better understand weather, the atmosphere, and climate. These are meteorology, climatology, and atmospheric science. Meteorology is the study of the atmosphere, atmospheric phenomena, and atmospheric effects on earth's weather. Meteorologists seek to understand and predict the weather in the short term, which can save lives and benefit the economy. Weather forecasts (Figure 7.1.5) are the result of thousands of measurements of air pressure, temperature, and the like, which are compiled, modeled, and analyzed in weather centers worldwide.




Figure **7.1.6**: Meteorologists use weather maps to describe and predict weather. Regions of high (H) and low (L) pressure have large effects on weather conditions. The gray lines represent locations of constant pressure known as isobars. (credit: modification of work by National Oceanic and Atmospheric Administration)

In terms of weather, low-pressure systems occur when the earth's surface atmospheric pressure is lower than the surrounding environment: Moist air rises and condenses, producing clouds. Movement of moisture and air within various weather fronts instigates most weather events.

The atmosphere is the gaseous layer that surrounds a planet. Earth's atmosphere, which is roughly 100–125 km thick, consists of roughly 78.1% nitrogen and 21.0% oxygen, and can be subdivided further into the regions shown in Figure **7.1.7**: the exosphere (furthest from earth, > 700 km above sea level), the thermosphere (80–700 km), the mesosphere (50–80 km), the stratosphere (second lowest level of our atmosphere, 12–50 km above sea level), and the troposphere (up to 12 km above sea level, roughly 80% of the earth's atmosphere by mass and the layer where most weather events originate). As you go higher in the troposphere, air density and temperature both decrease.




Figure **7.1.7**: Earth's atmosphere has five layers: the troposphere, the stratosphere, the mesosphere, the thermosphere, and the exosphere.

Climatology is the study of the climate, averaged weather conditions over long time periods, using atmospheric data. However, climatologists study patterns and effects that occur over decades, centuries, and millennia, rather than shorter time frames of hours, days, and weeks like meteorologists. Atmospheric science is an even broader field, combining meteorology, climatology, and other scientific disciplines that study the atmosphere.

Summary

Gases exert pressure, which is force per unit area. The pressure of a gas may be expressed in the SI unit of pascal or kilopascal, as well as in many other units including torr, atmosphere, and bar. Atmospheric pressure is measured using a barometer; other gas pressures can be measured using one of several types of manometers.

Key Equations

- $P = \frac{F}{A}$
- $p = h\rho g$

Glossary

atmosphere (atm)
unit of pressure; 1 atm = 101,325 Pa

bar
(bar or b) unit of pressure; 1 bar = 100,000 Pa

barometer
device used to measure atmospheric pressure

hydrostatic pressure
pressure exerted by a fluid due to gravity

manometer
device used to measure the pressure of a gas trapped in a container

pascal (Pa)
SI unit of pressure; 1 Pa = 1 N/m^2

pounds per square inch (psi)
unit of pressure common in the US

pressure
force exerted per unit area

torr
unit of pressure; $1\ \text{torr} = \frac{1}{760}\ \text{atm}$

7.1: Pressure of the Gas is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **9.1: Gas Pressure** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

7.2: simple Gas Laws

Learning Objectives

- Identify the mathematical relationships between the various properties of gases

During the seventeenth and especially eighteenth centuries, driven both by a desire to understand nature and a quest to make balloons in which they could fly (Figure **7.2.1**), a number of scientists established the relationships between the macroscopic physical properties of gases, that is, pressure, volume, temperature, and amount of gas. Although their measurements were not precise by today's standards, they were able to determine the mathematical relationships between pairs of these variables (e.g., pressure and temperature, pressure and volume) that hold for an *ideal* gas—a hypothetical construct that real gases approximate under certain conditions. Eventually, these individual laws were combined into a single equation—the *ideal gas law*—that relates gas quantities for gases and is quite accurate for low pressures and moderate temperatures. We will consider the key developments in individual relationships (for pedagogical reasons not quite in historical order), then put them together in the ideal gas law.




Figure **7.2.1**: In 1783, the first (a) hydrogen-filled balloon flight, (b) manned hot air balloon flight, and (c) manned hydrogen-filled balloon flight occurred. When the hydrogen-filled balloon depicted in (a) landed, the frightened villagers of Gonesse reportedly destroyed it with pitchforks and knives. The launch of the latter was reportedly viewed by 400,000 people in Paris.

Pressure and Temperature: Amontons's Law

Imagine filling a rigid container attached to a pressure gauge with gas and then sealing the container so that no gas may escape. If the container is cooled, the gas inside likewise gets colder and its pressure is observed to decrease. Since the container is rigid and tightly sealed, both the volume and number of moles of gas remain constant. If we heat the sphere, the gas inside gets hotter (Figure **7.2.2**) and the pressure increases.




Figure **7.2.2**: The effect of temperature on gas pressure: When the hot plate is off, the pressure of the gas in the sphere is relatively low. As the gas is heated, the pressure of the gas in the sphere increases.

This relationship between temperature and pressure is observed for any sample of gas confined to a constant volume. An example of experimental pressure-temperature data is shown for a sample of air under these conditions in Figure **7.2.3**. We find that temperature and pressure are linearly related, and if the temperature is on the kelvin scale, then P and T are directly proportional

(again, when *volume and moles of gas are held constant*); if the temperature on the kelvin scale increases by a certain factor, the gas pressure increases by the same factor.

Temperature (°C)	Temperature (K)	Pressure (kPa)
–150	173	36.0
–100	223	46.4
–50	273	56.7
0	323	67.1
50	373	77.5
100	423	88.0




Figure **7.2.3**: For a constant volume and amount of air, the pressure and temperature are directly proportional, provided the temperature is in kelvin. (Measurements cannot be made at lower temperatures because of the condensation of the gas.) When this line is extrapolated to lower pressures, it reaches a pressure of 0 at –273 °C, which is 0 on the kelvin scale and the lowest possible temperature, called absolute zero.

Guillaume Amontons was the first to empirically establish the relationship between the pressure and the temperature of a gas (~1700), and Joseph Louis Gay-Lussac determined the relationship more precisely (~1800). Because of this, the *P*-*T* relationship for gases is known as either Amontons's law or Gay-Lussac's law. Under either name, it states that *the pressure of a given amount of gas is directly proportional to its temperature on the kelvin scale when the volume is held constant*. Mathematically, this can be written:

$$P \propto T \text{ or } P = \text{constant} \times T \text{ or } P = k \times T \tag{7.2.1}$$

where ∝ means "is proportional to," and *k* is a proportionality constant that depends on the identity, amount, and volume of the gas.

For a confined, constant volume of gas, the ratio $\frac{P}{T}$ is therefore constant (i.e., $\frac{P}{T} = k$). If the gas is initially in "Condition 1" (with $P = P_1$ and $T = T_1$), and then changes to "Condition 2" (with $P = P_2$ and $T = T_2$), we have that $\frac{P_1}{T_1} = k$ and $\frac{P_2}{T_2} = k$, which reduces to $\frac{P_1}{T_1} = \frac{P_2}{T_2}$. This equation is useful for pressure-temperature calculations for a confined gas at constant volume. Note that temperatures must be on the kelvin scale for any gas law calculations (0 on the kelvin scale and the lowest possible temperature is called absolute zero). (Also note that there are at least three ways we can describe how the pressure of a gas changes as its temperature changes: We can use a table of values, a graph, or a mathematical equation.)

✔ Example 7.2.1: Predicting Change in Pressure with Temperature

A can of hair spray is used until it is empty except for the propellant, isobutane gas.

a. On the can is the warning "Store only at temperatures below 120 °F (48.8 °C). Do not incinerate." Why?
b. The gas in the can is initially at 24 °C and 360 kPa, and the can has a volume of 350 mL. If the can is left in a car that reaches 50 °C on a hot day, what is the new pressure in the can?

Solution

a. The can contains an amount of isobutane gas at a constant volume, so if the temperature is increased by heating, the pressure will increase proportionately. High temperature could lead to high pressure, causing the can to burst. (Also, isobutane is combustible, so incineration could cause the can to explode.)
b. We are looking for a pressure change due to a temperature change at constant volume, so we will use Amontons's/Gay-Lussac's law. Taking P_1 and T_1 as the initial values, T_2 as the temperature where the pressure is unknown and P_2 as the unknown pressure, and converting °C to K, we have:

$$\frac{P_1}{T_1} = \frac{P_2}{T_2} \text{ which means that } \frac{360\ k\text{Pa}}{297\ \text{K}} = \frac{P_2}{323\ \text{K}}$$

Rearranging and solving gives:

$$P_2 = \frac{360\ \text{kPa} \times 323\ \cancel{\text{K}}}{297\ \cancel{\text{K}}} = 390\ \text{kPa}$$

? Exercise 7.2.1

A sample of nitrogen, N_2, occupies 45.0 mL at 27 °C and 600 torr. What pressure will it have if cooled to –73 °C while the volume remains constant?

Answer

400 torr

Volume and Temperature: Charles's Law


If we fill a balloon with air and seal it, the balloon contains a specific amount of air at atmospheric pressure, let's say 1 atm. If we put the balloon in a refrigerator, the gas inside gets cold and the balloon shrinks (although both the amount of gas and its pressure remain constant). If we make the balloon very cold, it will shrink a great deal, and it expands again when it warms up.



Video **7.2.1**: This video shows how cooling and heating a gas causes its volume to decrease or increase, respectively.

These examples of the effect of temperature on the volume of a given amount of a confined gas at constant pressure are true in general: The volume increases as the temperature increases, and decreases as the temperature decreases. Volume-temperature data for a 1-mole sample of methane gas at 1 atm are listed and graphed in Figure **7.2.4**.

Temperature (°C)	Temperature (K)	Volume (L)
–3	270	22
–23	250	21
–53	220	18
–162	111	9



Figuire **7.2.4**: The volume and temperature are linearly related for 1 mole of methane gas at a constant pressure of 1 atm. If the temperature is in kelvin, volume and temperature are directly proportional. The line stops at 111 K because methane liquefies at this temperature; when extrapolated, it intersects the graph's origin, representing a temperature of absolute zero.

The relationship between the volume and temperature of a given amount of gas at constant pressure is known as Charles's law in recognition of the French scientist and balloon flight pioneer Jacques Alexandre César Charles. Charles's law states that *the volume of a given amount of gas is directly proportional to its temperature on the kelvin scale when the pressure is held constant.*

Mathematically, this can be written as:

$$V \alpha T \text{ or } V = \text{constant} \cdot T \text{ or } V = k \cdot T \tag{7.2.2}$$

with k being a proportionality constant that depends on the amount and pressure of the gas.

For a confined, constant pressure gas sample, $\frac{V}{T}$ is constant (i.e., the ratio = k), and as seen with the P-T relationship, this leads to another form of Charles's law: $\frac{V_1}{T_1} = \frac{V_2}{T_2}$.

Example 7.2.2: Predicting Change in Volume with Temperature

A sample of carbon dioxide, CO_2, occupies 0.300 L at 10 °C and 750 torr. What volume will the gas have at 30 °C and 750 torr?

Solution

Because we are looking for the volume change caused by a temperature change at constant pressure, this is a job for Charles's law. Taking V_1 and T_1 as the initial values, T_2 as the temperature at which the volume is unknown and V_2 as the unknown volume, and converting °C into K we have:

$$\frac{V_1}{T_1} = \frac{V_2}{T_2} \text{ which means that } \frac{0.300\ \text{L}}{283\ \text{K}} = \frac{V_2}{303\ \text{K}}$$

Rearranging and solving gives: $V_2 = \frac{0.300\ \text{L} \times 303\ \cancel{\text{K}}}{283\ \cancel{\text{K}}} = 0.321\ \text{L}$

This answer supports our expectation from Charles's law, namely, that raising the gas temperature (from 283 K to 303 K) at a constant pressure will yield an increase in its volume (from 0.300 L to 0.321 L).

Exercise 7.2.2

A sample of oxygen, O_2, occupies 32.2 mL at 30 °C and 452 torr. What volume will it occupy at –70 °C and the same pressure?

Answer

21.6 mL

Example 7.2.3: Measuring Temperature with a Volume

Change Temperature is sometimes measured with a gas thermometer by observing the change in the volume of the gas as the temperature changes at constant pressure. The hydrogen in a particular hydrogen gas thermometer has a volume of 150.0 cm^3 when immersed in a mixture of ice and water (0.00 °C). When immersed in boiling liquid ammonia, the volume of the hydrogen, at the same pressure, is 131.7 cm^3. Find the temperature of boiling ammonia on the kelvin and Celsius scales.

Solution

A volume change caused by a temperature change at constant pressure means we should use Charles's law. Taking V_1 and T_1 as the initial values, T_2 as the temperature at which the volume is unknown and V_2 as the unknown volume, and converting °C into K we have:

$$\frac{V_1}{T_1} = \frac{V_2}{T_2} \text{ which means that } \frac{150.0\ \text{cm}^3}{273.15\ \text{K}} = \frac{131.7\ \text{cm}^3}{T_2} \tag{7.2.3}$$

Rearrangement gives $T_2 = \frac{131.7\ \cancel{\text{cm}^3} \times 273.15\ \text{K}}{150.0\ \text{cm}^3} = 239.8\ \text{K}$

Subtracting 273.15 from 239.8 K, we find that the temperature of the boiling ammonia on the Celsius scale is –33.4 °C.

Exercise 7.2.3

What is the volume of a sample of ethane at 467 K and 1.1 atm if it occupies 405 mL at 298 K and 1.1 atm?

Answer

635 mL



Charles's Law: https://youtu.be/NBf510ZnlR0

Volume and Pressure: Boyle's Law

If we partially fill an airtight syringe with air, the syringe contains a specific amount of air at constant temperature, say 25 °C. If we slowly push in the plunger while keeping temperature constant, the gas in the syringe is compressed into a smaller volume and its pressure increases; if we pull out the plunger, the volume increases and the pressure decreases. This example of the effect of volume on the pressure of a given amount of a confined gas is true in general. Decreasing the volume of a contained gas will increase its pressure, and increasing its volume will decrease its pressure. In fact, if the volume increases by a certain factor, the pressure decreases by the same factor, and vice versa. Volume-pressure data for an air sample at room temperature are graphed in Figure 7.2.5.




Figure 7.2.5: When a gas occupies a smaller volume, it exerts a higher pressure; when it occupies a larger volume, it exerts a lower pressure (assuming the amount of gas and the temperature do not change). Since P and V are inversely proportional, a graph of $\frac{1}{P}$ vs. V is linear.

Unlike the *P*-*T* and *V*-*T* relationships, pressure and volume are not directly proportional to each other. Instead, P and V exhibit inverse proportionality: Increasing the pressure results in a decrease of the volume of the gas. Mathematically this can be written:

$$P \propto \frac{1}{V} \tag{7.2.4}$$

or

$$P = k \cdot \frac{1}{V} \tag{7.2.5}$$

or

$$PV = k \tag{7.2.6}$$

or

$$P_1V_1 = P_2V_2 \tag{7.2.7}$$

with k being a constant. Graphically, this relationship is shown by the straight line that results when plotting the inverse of the pressure $\left(\frac{1}{P}\right)$ versus the volume (V), or the inverse of volume $\left(\frac{1}{V}\right)$ versus the pressure (P). Graphs with curved lines are difficult to read accurately at low or high values of the variables, and they are more difficult to use in fitting theoretical equations and parameters to experimental data. For those reasons, scientists often try to find a way to "linearize" their data. If we plot P versus V, we obtain a hyperbola (Figure 7.2.6).



This diagram shows two graphs. In a, a graph is shown with volume on the horizontal axis and pressure on the vertical axis. A curved line is shown on the graph showing a decreasing trend with a decreasing rate of change. In b, a graph is shown with volume on the horizontal axis and one divided by pressure on the vertical axis. A line segment, beginning at the origin of the graph, shows a positive, linear trend.

Figure 7.2.6: The relationship between pressure and volume is inversely proportional. (a) The graph of P vs. V is a hyperbola, whereas (b) the graph of $\left(\frac{1}{P}\right)$ vs. V is linear.

The relationship between the volume and pressure of a given amount of gas at constant temperature was first published by the English natural philosopher Robert Boyle over 300 years ago. It is summarized in the statement now known as **Boyle's law**: *The volume of a given amount of gas held at constant temperature is inversely proportional to the pressure under which it is measured.*

Example 7.2.4: Volume of a Gas Sample

The sample of gas has a volume of 15.0 mL at a pressure of 13.0 psi. Determine the pressure of the gas at a volume of 7.5 mL, using:

a. the P-V graph in Figure 7.2.6*a*
b. the $\frac{1}{P}$ vs. V graph in Figure 7.2.6*b*
c. the Boyle's law equation

Comment on the likely accuracy of each method.

Solution

a. Estimating from the P-V graph gives a value for P somewhere around 27 psi.
b. Estimating from the $\frac{1}{P}$ versus V graph give a value of about 26 psi.
c. From Boyle's law, we know that the product of pressure and volume (PV) for a given sample of gas at a constant temperature is always equal to the same value. Therefore we have $P_1V_1 = k$ and $P_2V_2 = k$ which means that $P_1V_1 = P_2V_2$.

Using P_1 and V_1 as the known values 13.0 psi and 15.0 mL, P_2 as the pressure at which the volume is unknown, and V_2 as the unknown volume, we have:

$$P_1V_1 = P_2V_2 \text{ or } 13.0 \text{ psi} \times 15.0 \text{ mL} = P_2 \times 7.5 \, m\text{L}$$

Solving:

$$P_2 = \frac{13.0 \text{ psi} \times 15.0 \cancel{\text{mL}}}{7.5 \cancel{\text{mL}}} = 26 \text{ psi}$$

It was more difficult to estimate well from the P-V graph, so (a) is likely more inaccurate than (b) or (c). The calculation will be as accurate as the equation and measurements allow.

Exercise 7.2.4

The sample of gas has a volume of 30.0 mL at a pressure of 6.5 psi. Determine the volume of the gas at a pressure of 11.0 psi, using:

a. the P-V graph in Figure 7.2.6*a*
b. the $\frac{1}{P}$ vs. V graph in Figure 7.2.6*b*
c. the Boyle's law equation

Comment on the likely accuracy of each method.

Answer a

about 17–18 mL

Answer b

~18 mL

Answer c

17.7 mL; it was more difficult to estimate well from the *P*-*V* graph, so (a) is likely more inaccurate than (b); the calculation will be as accurate as the equation and measurements allow

Breathing and Boyle's Law

What do you do about 20 times per minute for your whole life, without break, and often without even being aware of it? The answer, of course, is respiration, or breathing. How does it work? It turns out that the gas laws apply here. Your lungs take in gas that your body needs (oxygen) and get rid of waste gas (carbon dioxide). Lungs are made of spongy, stretchy tissue that expands and contracts while you breathe. When you inhale, your diaphragm and intercostal muscles (the muscles between your ribs) contract, expanding your chest cavity and making your lung volume larger. The increase in volume leads to a decrease in pressure (Boyle's law). This causes air to flow into the lungs (from high pressure to low pressure). When you exhale, the process reverses: Your diaphragm and rib muscles relax, your chest cavity contracts, and your lung volume decreases, causing the pressure to increase (Boyle's law again), and air flows out of the lungs (from high pressure to low pressure). You then breathe in and out again, and again, repeating this Boyle's law cycle for the rest of your life (Figure **7.2.7**).




Figure **7.2.7**: Breathing occurs because expanding and contracting lung volume creates small pressure differences between your lungs and your surroundings, causing air to be drawn into and forced out of your lungs.



Boyle's Law: https://youtu.be/lu86VSupPO4

Moles of Gas and Volume: Avogadro's Law

The Italian scientist Amedeo Avogadro advanced a hypothesis in 1811 to account for the behavior of gases, stating that equal volumes of all gases, measured under the same conditions of temperature and pressure, contain the same number of molecules. Over time, this relationship was supported by many experimental observations as expressed by Avogadro's law: *For a confined gas, the volume (V) and number of moles (n) are directly proportional if the pressure and temperature both remain constant*.

In equation form, this is written as:

$$V \propto n \text{ or } V = k \times n \text{ or } \frac{V_1}{n_1} = \frac{V_2}{n_2} \tag{7.2.8}$$

Mathematical relationships can also be determined for the other variable pairs, such as *P* versus *n*, and *n* versus *T*.

> *Visit this interactive PhET simulation to investigate the relationships between pressure, volume, temperature, and amount of gas. Use the simulation to examine the effect of changing one parameter on another while holding the other parameters constant (as described in the preceding sections on the various gas laws).*



Avogadro's Law: https://youtu.be/dRY3Trl4T24

Summary

The behavior of gases can be described by several laws based on experimental observations of their properties. The pressure of a given amount of gas is directly proportional to its absolute temperature, provided that the volume does not change (Amontons's law). The volume of a given gas sample is directly proportional to its absolute temperature at constant pressure (Charles's law). The

volume of a given amount of gas is inversely proportional to its pressure when temperature is held constant (Boyle's law). Under the same conditions of temperature and pressure, equal volumes of all gases contain the same number of molecules (Avogadro's law).

The equations describing these laws are special cases of the ideal gas law, $PV = nRT$, where P is the pressure of the gas, V is its volume, n is the number of moles of the gas, T is its kelvin temperature, and R is the ideal (universal) gas constant.

Key Equations

- $PV = nRT$

Summary

absolute zero

temperature at which the volume of a gas would be zero according to Charles's law.

Amontons's law

(also, Gay-Lussac's law) pressure of a given number of moles of gas is directly proportional to its kelvin temperature when the volume is held constant

Avogadro's law

volume of a gas at constant temperature and pressure is proportional to the number of gas molecules

Boyle's law

volume of a given number of moles of gas held at constant temperature is inversely proportional to the pressure under which it is measured

Charles's law

volume of a given number of moles of gas is directly proportional to its kelvin temperature when the pressure is held constan

---

7.2: simple Gas Laws is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **9.2: Relating Pressure, Volume, Amount, and Temperature - The Ideal Gas Law** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

7.3: Ideal Gas Law

Learning Objectives

- Derive the ideal gas law from the constituent gas laws
- To use the ideal gas law to describe the behavior of a gas.

In this module, the relationship between pressure, temperature, volume, and amount of a gas are described and how these relationships can be combined to give a general expression that describes the behavior of a gas.

Deriving the Ideal Gas Law

Any set of relationships between a single quantity (such as V) and several other variables (P, T, and n) can be combined into a single expression that describes all the relationships simultaneously. The three individual expressions were derived previously:

- **Boyle's law**

$$V \propto \frac{1}{P} \text{ @ constant n and T} \tag{7.3.1}$$

- **Charles's law**

$$V \propto T \text{ @ constant n and P} \tag{7.3.2}$$

- **Avogadro's law**

$$V \propto n \text{ @ constant T and P} \tag{7.3.3}$$

Combining these three expressions gives

$$V \propto \frac{nT}{P} \tag{7.3.4}$$

which shows that the volume of a gas is proportional to the number of moles and the temperature and inversely proportional to the pressure. This expression can also be written as

$$V = \text{Cons.} \left(\frac{nT}{P}\right) \tag{7.3.5}$$

By convention, the proportionality constant in Equation 7.3.4 is called the gas constant, which is represented by the letter R. Inserting R into Equation 7.3.5 gives

$$V = \frac{RnT}{P} = \frac{nRT}{P} \tag{7.3.6}$$

Clearing the fractions by multiplying both sides of Equation 7.3.7 by P gives

$$PV = nRT \tag{7.3.7}$$

This equation is known as the **ideal gas law**.

An ideal gas is defined as a hypothetical gaseous substance whose behavior is independent of attractive and repulsive forces and can be completely described by the ideal gas law. In reality, there is no such thing as an ideal gas, but an ideal gas is a useful conceptual model that allows us to understand how gases respond to changing conditions. As we shall see, under many conditions, most real gases exhibit behavior that closely approximates that of an ideal gas. The ideal gas law can therefore be used to predict the behavior of real gases under most conditions. The ideal gas law does not work well at very low temperatures or very high pressures, where deviations from ideal behavior are most commonly observed.

> *Significant deviations from ideal gas behavior commonly occur at low temperatures and very high pressures.*

Before we can use the ideal gas law, however, we need to know the value of the gas constant R. Its form depends on the units used for the other quantities in the expression. If V is expressed in liters (L), P in atmospheres (atm), T in kelvins (K), and n in moles (mol), then

$$R = 0.08206 \frac{\text{L} \cdot \text{atm}}{\text{K} \cdot \text{mol}} \tag{7.3.8}$$

Because the product PV has the units of energy, R can also have units of J/(K•mol):

$$R = 8.3145 \frac{\text{J}}{\text{K} \cdot \text{mol}} \tag{7.3.9}$$

Standard Conditions of Temperature and Pressure

Scientists have chosen a particular set of conditions to use as a reference: 0°C (273.15 K) and $1 \text{ bar} = 100 \text{ kPa} = 10^5 \text{ Pa}$ pressure, referred to as standard temperature and pressure (**STP**).

$$\text{STP:} \qquad T = 273.15 \text{ K and } P = 1 \text{ bar} = 10^5 \text{ Pa} \tag{7.3.10}$$

Please note that STP was defined differently in the past. The old definition was based on a standard pressure of 1 atm.

We can calculate the volume of 1.000 mol of an ideal gas under standard conditions using the variant of the ideal gas law given in Equation 7.3.7:

$$V = \frac{nRT}{P} \tag{7.3.11}$$

Thus the volume of 1 mol of an ideal gas is **22.71 L at STP** and **22.41 L at 0°C and 1 atm**, approximately equivalent to the volume of three basketballs. The molar volumes of several real gases at 0°C and 1 atm are given in Table 10.3, which shows that the deviations from ideal gas behavior are quite small. Thus the ideal gas law does a good job of approximating the behavior of real gases at 0°C and 1 atm. The relationships described in Section 10.3 as Boyle's, Charles's, and Avogadro's laws are simply special cases of the ideal gas law in which two of the four parameters (P, V, T, and n) are held fixed.

Table **7.3.1**: Molar Volumes of Selected Gases at 0°C and 1 atm

Gas	Molar Volume (L)
He	22.434
Ar	22.397
H_2	22.433
N_2	22.402
O_2	22.397
CO_2	22.260
NH_3	22.079

Summary

The ideal gas law is derived from empirical relationships among the pressure, the volume, the temperature, and the number of moles of a gas; it can be used to calculate any of the four properties if the other three are known.

Ideal gas equation: $PV = nRT$,

where $R = 0.08206 \frac{\text{L} \cdot \text{atm}}{\text{K} \cdot \text{mol}} = 8.3145 \frac{\text{J}}{\text{K} \cdot \text{mol}}$

The empirical relationships among the volume, the temperature, the pressure, and the amount of a gas can be combined into the **ideal gas law**, *PV* = *nRT*. The proportionality constant, *R*, is called the **gas constant** and has the value 0.08206 (L•atm)/(K•mol), 8.3145 J/(K•mol), or 1.9872 cal/(K•mol), depending on the units used. The ideal gas law describes the behavior of an **ideal gas**, a

hypothetical substance whose behavior can be explained quantitatively by the ideal gas law and the kinetic molecular theory of gases. **Standard temperature and pressure (STP)** is 0°C and 1 atm. The volume of 1 mol of an ideal gas at STP is 22.41 L, the **standard molar volume**.

7.3: Ideal Gas Law is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **10.4: The Ideal Gas Equation** is licensed CC BY-NC-SA 3.0.

7.4: Applying the Ideal Gas Law

Learning Objectives

- To use the ideal gas law to describe the behavior of a gas.

The ideal gas law allows us to calculate the value of the fourth variable for a gaseous sample if we know the values of any three of the four variables (*P*, *V*, *T*, and *n*). It also allows us to predict the *final state* of a sample of a gas (i.e., its final temperature, pressure, volume, and amount) following any changes in conditions if the parameters (*P*, *V*, *T*, and *n*) are specified for an *initial state*. Some applications are illustrated in the following examples. The approach used throughout is always to start with the same equation—the ideal gas law—and then determine which quantities are given and which need to be calculated. Let's begin with simple cases in which we are given three of the four parameters needed for a complete physical description of a gaseous sample.

Example 7.4.1

The balloon that Charles used for his initial flight in 1783 was destroyed, but we can estimate that its volume was 31,150 L (1100 ft^3), given the dimensions recorded at the time. If the temperature at ground level was 86°F (30°C) and the atmospheric pressure was 745 mmHg, how many moles of hydrogen gas were needed to fill the balloon?

Given: volume, temperature, and pressure

Asked for: amount of gas

Strategy:

A. Solve the ideal gas law for the unknown quantity, in this case *n*.
B. Make sure that all quantities are given in units that are compatible with the units of the gas constant. If necessary, convert them to the appropriate units, insert them into the equation you have derived, and then calculate the number of moles of hydrogen gas needed.

Solution:

A We are given values for *P*, *T*, and *V* and asked to calculate *n*. If we solve the ideal gas law (Equation ???) for n, we obtain

$$745\ \text{mmHg} \times \frac{1\ \text{atm}}{760\ \text{mmHg}} = 0.980\ \text{atm}$$

B *P* and *T* are given in units that are not compatible with the units of the gas constant [*R* = 0.08206 (L•atm)/(K•mol)]. We must therefore convert the temperature to kelvins and the pressure to atmospheres:

$$T = 273 + 30 = 303\text{K}$$

Substituting these values into the expression we derived for *n*, we obtain

$$\begin{aligned} n &= \frac{PV}{RT} \\ &= \frac{0.980\ \text{atm} \times 31150\ \text{L}}{0.08206 \frac{\text{atm} \cdot \text{L}}{\text{mol} \cdot \text{K}} \times 303\ \text{K}} \\ &= 1.23 \times 10^3\ mol \end{aligned}$$

Exercise 7.4.1

Suppose that an "empty" aerosol spray-paint can has a volume of 0.406 L and contains 0.025 mol of a propellant gas such as CO_2. What is the pressure of the gas at 25°C?

Answer

1.5 atm

In Example **7.4.1**, we were given three of the four parameters needed to describe a gas under a particular set of conditions, and we were asked to calculate the fourth. We can also use the ideal gas law to calculate the effect of *changes* in any of the specified conditions on any of the other parameters, as shown in Example **7.4.5**.

General Gas Equation

When a gas is described under two different conditions, the ideal gas equation must be applied twice - to an initial condition and a final condition. This is:

$$\underset{P_iV_i = n_iRT_i}{\text{Initial condition } (i)} \qquad \underset{P_fV_f = n_fRT_f}{\text{Final condition}(f)} \tag{7.4.1}$$

Both equations can be rearranged to give:

$$R = \frac{P_iV_i}{n_iT_i} \qquad R = \frac{P_fV_f}{n_fT_f} \tag{7.4.2}$$

The two equations are equal to each other since each is equal to the same constant R. Therefore, we have:

$$\frac{P_iV_i}{n_iT_i} = \frac{P_fV_f}{n_fT_f} \tag{7.4.3}$$

The equation is called the **general gas equation**. The equation is particularly useful when one or two of the gas properties are held constant between the two conditions. In such cases, the equation can be simplified by eliminating these constant gas properties.



Example 7.4.2

Suppose that Charles had changed his plans and carried out his initial flight not in August but on a cold day in January, when the temperature at ground level was −10°C (14°F). How large a balloon would he have needed to contain the same amount of hydrogen gas at the same pressure as in Example **7.4.1**?

Given: temperature, pressure, amount, and volume in August; temperature in January

Asked for: volume in January

Strategy:

A. Use the results from Example **7.4.1** for August as the initial conditions and then calculate the *change in volume* due to the change in temperature from 30°C to −10°C. Begin by constructing a table showing the initial and final conditions.
B. Simplify the general gas equation by eliminating the quantities that are held constant between the initial and final conditions, in this case P and n.
C. Solve for the unknown parameter.

Solution:

A To see exactly which parameters have changed and which are constant, prepare a table of the initial and final conditions:

Initial (August)	Final (January)
$T_i = 30\,°C = 303\,K$	$T_f = -10°C = 263\,K$
$P_i = 0.980\,atm$	$P_f = 0.980\,atm$
$n_i = 1.23 \times 10^3\,mol$	$n_f = 1.23 \times 10^3\,mol$
$V_i = 31150\,L$	$V_f = ?$

B Both n and P are the same in both cases ($n_i = n_f, P_i = P_f$). Therefore, Equation 7.4.3 can be simplified to:

$$\frac{V_i}{T_i} = \frac{V_f}{T_f}$$

This is the relationship first noted by Charles.

C Solving the equation for V_f, we get:

$$\begin{aligned} V_f &= V_i \times \frac{T_f}{T_i} \\ &= 31150\ \text{L} \times \frac{263\ \text{K}}{303\ \text{K}} \\ &= 2.70 \times 10^4\ L \end{aligned}$$

It is important to check your answer to be sure that it makes sense, just in case you have accidentally inverted a quantity or multiplied rather than divided. In this case, the temperature of the gas decreases. Because we know that gas volume decreases with decreasing temperature, the final volume must be less than the initial volume, so the answer makes sense. We could have calculated the new volume by plugging all the given numbers into the ideal gas law, but it is generally much easier and faster to focus on only the quantities that change.

? Exercise 7.4.2

At a laboratory party, a helium-filled balloon with a volume of 2.00 L at 22°C is dropped into a large container of liquid nitrogen (T = −196°C). What is the final volume of the gas in the balloon?

Answer

0.52 L

Example **7.4.1** illustrates the relationship originally observed by Charles. We could work through similar examples illustrating the inverse relationship between pressure and volume noted by Boyle (*PV* = constant) and the relationship between volume and amount observed by Avogadro (*V*/*n* = constant). We will not do so, however, because it is more important to note that the historically important gas laws are only special cases of the ideal gas law in which two quantities are varied while the other two remain fixed. The method used in Example **7.4.1** can be applied in *any* such case, as we demonstrate in Example **7.4.2** (which also shows why heating a closed container of a gas, such as a butane lighter cartridge or an aerosol can, may cause an explosion).

✔ Example 7.4.3

Aerosol cans are prominently labeled with a warning such as “Do not incinerate this container when empty.” Assume that you did not notice this warning and tossed the “empty” aerosol can in Exercise **7.4.1** (0.025 mol in 0.406 L, initially at 25°C and 1.5 atm internal pressure) into a fire at 750°C. What would be the pressure inside the can (if it did not explode)?

Given: initial volume, amount, temperature, and pressure; final temperature

Asked for: final pressure

Strategy:

Follow the strategy outlined in Example **7.4.2**.

Solution:

Prepare a table to determine which parameters change and which are held constant:

Initial	Final
$V_i = 0.406\ \text{L}$	$V_f = 0.406\ \text{L}$
$n_i = 0.025\ \text{mol}$	$n_f = 0.025\ \text{mol}$
$T_i = 25\ ^\circ\text{C} = 298\ \text{K}$	$T_i = 750\ ^\circ\text{C} = 1023\ \text{K}$
$P_i = 1.5\ \text{atm}$	$P_f = ?$

Both V and n are the same in both cases ($V_i = V_f, n_i = n_f$). Therefore, Equation can be simplified to:

$$\frac{P_i}{T_i} = \frac{P_f}{T_f} \tag{7.4.4}$$

By solving the equation for P_f, we get:

$$\begin{aligned} P_f &= P_i \times \frac{T_f}{T_i} \\ &= 1.5\ \text{atm} \times \frac{1023\ \text{K}}{298\ \text{K}} \\ &= 5.1\ atm \end{aligned}$$

This pressure is more than enough to rupture a thin sheet metal container and cause an explosion!

? Exercise 7.4.3

Suppose that a fire extinguisher, filled with CO_2 to a pressure of 20.0 atm at 21°C at the factory, is accidentally left in the sun in a closed automobile in Tucson, Arizona, in July. The interior temperature of the car rises to 160°F (71.1°C). What is the internal pressure in the fire extinguisher?

Answer

23.4 atm

In Examples **7.4.1** and **7.4.2**, two of the four parameters (*P*, *V*, *T*, and *n*) were fixed while one was allowed to vary, and we were interested in the effect on the value of the fourth. In fact, we often encounter cases where two of the variables *P*, *V*, and *T* are allowed to vary for a given sample of gas (hence *n* is constant), and we are interested in the change in the value of the third under the new conditions.



Example 7.4.4

We saw in Example **7.4.1** that Charles used a balloon with a volume of 31,150 L for his initial ascent and that the balloon contained 1.23×10^3 mol of H_2 gas initially at 30°C and 745 mmHg. Suppose that Gay-Lussac had also used this balloon for his record-breaking ascent to 23,000 ft and that the pressure and temperature at that altitude were 312 mmHg and −30°C, respectively. To what volume would the balloon have had to expand to hold the same amount of hydrogen gas at the higher altitude?

Given: initial pressure, temperature, amount, and volume; final pressure and temperature

Asked for: final volume

Strategy:

Follow the strategy outlined in Example **7.4.3**.

Solution:

Begin by setting up a table of the two sets of conditions:

Initial	Final
$P_i = 745\ \text{mmHg} = 0.980\ \text{atm}$	$P_f = 312\ \text{mmHg} = 0.411\ \text{atm}$
$T_i = 30\ ^\circ\text{C} = 303\ \text{K}$	$T_f = 750 - 30\ ^\circ\text{C} = 243\ \text{K}$
$n_i = 1.2 \times 10^3\ \text{mol}$	$n_i = 1.2 \times 10^3\ \text{mol}$
$V_i = 31150\ \text{L}$	$V_f = ?$

By eliminating the constant property (n) of the gas, Equation 7.4.3 is simplified to:

$$\frac{P_i V_i}{T_i} = \frac{P_f V_f}{T_f} \tag{7.4.5}$$

By solving the equation for V_f, we get:

$$\begin{aligned} V_f &= V_i \times \frac{P_i}{P_f}\frac{T_f}{T_i} \\ &= 3.115 \times 10^4\ \text{L} \times \frac{0.980\ \text{atm}}{0.411\ \text{atm}}\frac{243\ \text{K}}{303\ \text{K}} \\ &= 5.96 \times 10^4\ L \end{aligned}$$

Does this answer make sense? Two opposing factors are at work in this problem: decreasing the pressure tends to *increase* the volume of the gas, while decreasing the temperature tends to *decrease* the volume of the gas. Which do we expect to

predominate? The pressure drops by more than a factor of two, while the absolute temperature drops by only about 20%. Because the volume of a gas sample is directly proportional to both T and $1/P$, the variable that changes the most will have the greatest effect on V. In this case, the effect of decreasing pressure predominates, and we expect the volume of the gas to increase, as we found in our calculation.

We could also have solved this problem by solving the ideal gas law for V and then substituting the relevant parameters for an altitude of 23,000 ft:

Except for a difference caused by rounding to the last significant figure, this is the same result we obtained previously. *There is often more than one "right" way to solve chemical problems.*

? Exercise 7.4.4

A steel cylinder of compressed argon with a volume of 0.400 L was filled to a pressure of 145 atm at 10°C. At 1.00 atm pressure and 25°C, how many 15.0 mL incandescent light bulbs could be filled from this cylinder? (Hint: find the number of moles of argon in each container.)

Answer

4.07×10^3

Using the Ideal Gas Law to Calculate Gas Densities

The ideal gas law can also be used to calculate molar masses of gases from experimentally measured gas densities. To see how this is possible, we first rearrange the ideal gas law to obtain

$$\frac{n}{V} = \frac{P}{RT} \tag{7.4.6}$$

The left side has the units of moles per unit volume (mol/L). The number of moles of a substance equals its mass (m, in grams) divided by its molar mass (M, in grams per mole):

$$n = \frac{m}{M} \tag{7.4.7}$$

Substituting this expression for n into Equation 7.4.6 gives

$$\frac{m}{MV} = \frac{P}{RT} \tag{7.4.8}$$

Because m/V is the density d of a substance, we can replace m/V by d and rearrange to give

$$\rho = \frac{m}{V} = \frac{MP}{RT} \tag{7.4.9}$$

The distance between particles in gases is large compared to the size of the particles, so their densities are much lower than the densities of liquids and solids. Consequently, gas density is usually measured in grams per liter (g/L) rather than grams per milliliter (g/mL).



Example 7.4.5

Calculate the density of butane at 25°C and a pressure of 750 mmHg.

Given: compound, temperature, and pressure

Asked for: density

Strategy:

A. Calculate the molar mass of butane and convert all quantities to appropriate units for the value of the gas constant.
B. Substitute these values into Equation 7.4.9 to obtain the density.

Solution:

A The molar mass of butane (C_4H_{10}) is

$$M = (4)(12.011) + (10)(1.0079) = 58.123 \text{g/mol}$$

Using 0.08206 (L•atm)/(K•mol) for R means that we need to convert the temperature from degrees Celsius to kelvins (T = 25 + 273 = 298 K) and the pressure from millimeters of mercury to atmospheres:

$$P = 750 \text{ mmHg} \times \frac{1 \text{ atm}}{760 \text{ mmHg}} = 0.987 \text{ atm}$$

B Substituting these values into Equation 7.4.9 gives

$$\rho = \frac{58.123 \text{ g/mol} \times 0.987 \text{ atm}}{0.08206 \frac{\text{L} \cdot \text{atm}}{\text{K} \cdot \text{mol}} \times 298 \text{ K}} = 2.35 \text{ g/L}$$

Exercise 7.4.5: Density of Radon

Radon (Rn) is a radioactive gas formed by the decay of naturally occurring uranium in rocks such as granite. It tends to collect in the basements of houses and poses a significant health risk if present in indoor air. Many states now require that houses be tested for radon before they are sold. Calculate the density of radon at 1.00 atm pressure and 20°C and compare it with the density of nitrogen gas, which constitutes 80% of the atmosphere, under the same conditions to see why radon is found in basements rather than in attics.

Answer

radon, 9.23 g/L; N_2, 1.17 g/L

Using the Ideal Gas Law to Calculate the Molar Mass of a Gas

Another useful application of the ideal gas law involves the determination of molar mass. By definition, the molar mass of a substance is the ratio of its mass in grams, *m*, to its amount in moles, *n*:

$$\mathcal{M} = \frac{\text{grams of substance}}{\text{moles of substance}} = \frac{m}{n} \tag{7.4.10}$$

The ideal gas equation can be rearranged to isolate n:

$$n = \frac{PV}{RT} \tag{7.4.11}$$

and then combined with the molar mass equation to yield:

$$\mathcal{M} = \frac{mRT}{PV} \tag{7.4.12}$$

This equation can be used to derive the molar mass of a gas from measurements of its pressure, volume, temperature, and mass.

Example 7.4.6: Determining the Molar Mass of a Volatile Liquid

The approximate molar mass of a volatile liquid can be determined by:

1. Heating a sample of the liquid in a flask with a tiny hole at the top, which converts the liquid into gas that may escape through the hole
2. Removing the flask from heat at the instant when the last bit of liquid becomes gas, at which time the flask will be filled with only gaseous sample at ambient pressure
3. Sealing the flask and permitting the gaseous sample to condense to liquid, and then weighing the flask to determine the sample's mass (Figure 7.4.1)




Figure 7.4.1: When the volatile liquid in the flask is heated past its boiling point, it becomes gas and drives air out of the flask. At $t_{l \longrightarrow g}$, *the flask is filled with volatile liquid gas at the same pressure as the atmosphere. If the flask is then cooled to room temperature, the gas condenses and the mass of the gas that filled the flask, and is now liquid, can be measured. (credit: modification of work by Mark Ott)*

Using this procedure, a sample of chloroform gas weighing 0.494 g is collected in a flask with a volume of 129 cm^3 at 99.6 °C when the atmospheric pressure is 742.1 mm Hg. What is the approximate molar mass of chloroform?

Solution

Since

$$\mathcal{M} = \frac{m}{n} \tag{7.4.13}$$

and

$$n = \frac{PV}{RT} \tag{7.4.14}$$

substituting and rearranging gives

$$\mathcal{M} = \frac{mRT}{PV} \tag{7.4.15}$$

then

$$\mathcal{M} = \frac{mRT}{PV} = \frac{(0.494\ \text{g}) \times 0.08206\ \text{L} \cdot \text{atm/mol K} \times 372.8\ \text{K}}{0.976\ \text{atm} \times 0.129\ \text{L}} = 120\ \text{g/mol} \tag{7.4.16}$$

Summary

General gas equation: $\frac{P_i V_i}{n_i T_i} = \frac{P_f V_f}{n_f T_f}$

Density of a gas: $\rho = \frac{MP}{RT}$

All of the empirical gas relationships are special cases of the ideal gas law in which two of the four parameters are held constant. The ideal gas law allows us to calculate the value of the fourth quantity (*P*, *V*, *T*, or *n*) needed to describe a gaseous sample when the others are known and also predict the value of these quantities following a change in conditions if the original conditions (values of *P*, *V*, *T*, and *n*) are known. The ideal gas law can also be used to calculate the density of a gas if its molar mass is known or, conversely, the molar mass of an unknown gas sample if its density is measured.

7.4: Applying the Ideal Gas Law is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **10.4: The Ideal Gas Equation** is licensed CC BY-NC-SA 3.0.
- **9.3: Stoichiometry of Gaseous Substances, Mixtures, and Reactions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

7.5: Mixture of Gases

Learning Objectives

- To determine the contribution of each component gas to the total pressure of a mixture of gases

In our use of the ideal gas law thus far, we have focused entirely on the properties of pure gases with only a single chemical species. But what happens when two or more gases are mixed? In this section, we describe how to determine the contribution of each gas present to the total pressure of the mixture.

Partial Pressures

The ideal gas law *assumes* that all gases behave identically and that their behavior is independent of attractive and repulsive forces. If volume and temperature are held constant, the ideal gas equation can be rearranged to show that the pressure of a sample of gas is directly proportional to the number of moles of gas present:

$$P = n\left(\frac{RT}{V}\right) = n \times \text{const.} \tag{7.5.1}$$

Nothing in the equation depends on the *nature* of the gas—only the amount.

With this assumption, let's suppose we have a mixture of two ideal gases that are present in equal amounts. What is the total pressure of the mixture? Because the pressure depends on only the total number of particles of gas present, the total pressure of the mixture will simply be twice the pressure of either component. More generally, the total pressure exerted by a mixture of gases at a given temperature and volume is the sum of the pressures exerted by each gas alone. Furthermore, if we know the volume, the temperature, and the number of moles of each gas in a mixture, then we can calculate the pressure exerted by each gas individually, which is its partial pressure, the pressure the gas would exert if it were the only one present (at the same temperature and volume).

To summarize, ***the total pressure exerted by a mixture of gases is the sum of the partial pressures of component gases***. This law was first discovered by John Dalton, the father of the atomic theory of matter. It is now known as *Dalton's law of partial pressures*. We can write it mathematically as

$$P_{tot} = P_1 + P_2 + P_3 + P_4 \ldots \tag{7.5.2}$$

$$= \sum_{i=1}^{n} P_i \tag{7.5.3}$$

where P_{tot} is the total pressure and the other terms are the partial pressures of the individual gases (up to n component gases).




Figure **7.5.1**: Dalton's Law. The total pressure of a mixture of gases is the sum of the partial pressures of the individual gases.

For a mixture of two ideal gases, A and B, we can write an expression for the total pressure:

$$P_{tot} = P_A + P_B \tag{7.5.4}$$

$$= n_A\left(\frac{RT}{V}\right) + n_B\left(\frac{RT}{V}\right) \tag{7.5.5}$$

$$= (n_A + n_B)\left(\frac{RT}{V}\right) \tag{7.5.6}$$

More generally, for a mixture of n component gases, the total pressure is given by

$$P_{tot} = (P_1 + P_2 + P_3 + \cdots + P_n)\left(\frac{RT}{V}\right) \tag{7.5.7}$$

$$= \sum_{i=1}^{n} P_i\left(\frac{RT}{V}\right) \tag{7.5.8}$$

Equation 7.5.8 restates Equation 7.5.6 in a more general form and makes it explicitly clear that, at constant temperature and volume, the pressure exerted by a gas depends on only the total number of moles of gas present, whether the gas is a single chemical species or a mixture of dozens or even hundreds of gaseous species. For Equation 7.5.8 to be valid, the identity of the particles present cannot have an effect. Thus an ideal gas must be one whose properties are not affected by either the size of the particles or their intermolecular interactions because both will vary from one gas to another. The calculation of total and partial pressures for mixtures of gases is illustrated in Example 7.5.1.

Example 7.5.1: The Bends

Deep-sea divers must use special gas mixtures in their tanks, rather than compressed air, to avoid serious problems, most notably a condition called “the bends.” At depths of about 350 ft, divers are subject to a pressure of approximately 10 atm. A typical gas cylinder used for such depths contains 51.2 g of O_2 and 326.4 g of He and has a volume of 10.0 L. What is the partial pressure of each gas at 20.00°C, and what is the total pressure in the cylinder at this temperature?

Given: masses of components, total volume, and temperature

Asked for: partial pressures and total pressure

Strategy:

A. Calculate the number of moles of **He** and $\mathbf{O_2}$ present.
B. Use the ideal gas law to calculate the partial pressure of each gas. Then add together the partial pressures to obtain the total pressure of the gaseous mixture.

Solution:

A The number of moles of **He** is

$$n_{\mathrm{He}} = \frac{326.4\ \mathrm{g}}{4.003\ \mathrm{g/mol}} = 81.54\ \mathrm{mol}$$

The number of moles of $\mathbf{O_2}$ is

$$n_{\mathrm{O_2}} = \frac{51.2\ \mathrm{g}}{32.00\ \mathrm{g/mol}} = 1.60\ \mathrm{mol}$$

B We can now use the ideal gas law to calculate the partial pressure of each:

$$P_{\mathrm{He}} = \frac{n_{\mathrm{He}}RT}{V} = \frac{81.54\ \mathrm{mol} \times 0.08206\ \frac{\mathrm{atm \cdot L}}{\mathrm{mol \cdot K}} \times 293.15\ \mathrm{K}}{10.0\ \mathrm{L}} = 196.2\ \mathrm{atm}$$

$$P_{\mathrm{O_2}} = \frac{n_{\mathrm{O_2}}RT}{V} = \frac{1.60\ \mathrm{mol} \times 0.08206\ \frac{\mathrm{atm \cdot L}}{\mathrm{mol \cdot K}} \times 293.15\ \mathrm{K}}{10.0\ \mathrm{L}} = 3.85\ \mathrm{atm}$$

The total pressure is the sum of the two partial pressures:

$$P_{\mathrm{tot}} = P_{\mathrm{He}} + P_{\mathrm{O_2}} = (196.2 + 3.85)\ \mathrm{atm} = 200.1\ \mathrm{atm}$$

? Exercise 7.5.1

A cylinder of compressed natural gas has a volume of 20.0 L and contains 1813 g of methane and 336 g of ethane. Calculate the partial pressure of each gas at 22.0°C and the total pressure in the cylinder.

Answer

$P_{CH_4} = 137\ atm;\ P_{C_2H_6} = 13.4\ atm;\ P_{tot} = 151\ atm$

Mole Fractions of Gas Mixtures

The composition of a gas mixture can be described by the mole fractions of the gases present. The mole fraction (χ) of any component of a mixture is the ratio of the number of moles of that component to the total number of moles of all the species present in the mixture (n_{tot}):

$$\chi_A = \frac{\text{moles of A}}{\text{total moles}} = \frac{n_A}{n_{tot}} = \frac{n_A}{n_A + n_B + \cdots} \tag{7.5.9}$$

The mole fraction is a dimensionless quantity between 0 and 1. If $\chi_A = 1.0$, then the sample is pure A, not a mixture. If $\chi_A = 0$, then no A is present in the mixture. The sum of the mole fractions of all the components present must equal 1.

To see how mole fractions can help us understand the properties of gas mixtures, let's evaluate the ratio of the pressure of a gas A to the total pressure of a gas mixture that contains A. We can use the ideal gas law to describe the pressures of both gas A and the mixture: $P_A = n_A RT/V$ and $P_{tot} = n_t RT/V$. The ratio of the two is thus

$$\frac{P_A}{P_{tot}} = \frac{n_A RT/V}{n_{tot} RT/V} = \frac{n_A}{n_{tot}} = \chi_A \tag{7.5.10}$$

Rearranging this equation gives

$$P_A = \chi_A P_{tot} \tag{7.5.11}$$

That is, the partial pressure of any gas in a mixture is the total pressure multiplied by the mole fraction of that gas. This conclusion is a direct result of the ideal gas law, which assumes that all gas particles behave ideally. Consequently, the pressure of a gas in a mixture depends on only the percentage of particles in the mixture that are of that type, not their specific physical or chemical properties. By volume, Earth's atmosphere is about 78% N_2, 21% O_2, and 0.9% Ar, with trace amounts of gases such as CO_2, H_2O, and others. This means that 78% of the particles present in the atmosphere are N_2; hence the mole fraction of N_2 is 78%/100% = 0.78. Similarly, the mole fractions of O_2 and Ar are 0.21 and 0.009, respectively. Using Equation 7.5.11, we therefore know that the partial pressure of N_2 is 0.78 atm (assuming an atmospheric pressure of exactly 760 mmHg) and, similarly, the partial pressures of O_2 and Ar are 0.21 and 0.009 atm, respectively.



Example 7.5.2: Exhaling Composition

We have just calculated the partial pressures of the major gases in the air we inhale. Experiments that measure the composition of the air we *exhale* yield different results, however. The following table gives the measured pressures of the major gases in both inhaled and exhaled air. Calculate the mole fractions of the gases in exhaled air.

	Inhaled Air / mmHg	Exhaled Air / mmHg
P_{N_2}	597	568
P_{O_2}	158	116
P_{H_2O}	0.3	28
P_{CO_2}	5	48
P_{Ar}	8	8
P_{tot}	767	767

Given: pressures of gases in inhaled and exhaled air

Asked for: mole fractions of gases in exhaled air

Strategy:

Calculate the mole fraction of each gas using Equation 7.5.11.

Solution:

The mole fraction of any gas A is given by

$$\chi_A = \frac{P_A}{P_{tot}}$$

where P_A is the partial pressure of A and P_{tot} is the total pressure. For example, the mole fraction of CO_2 is given as:

$$\chi_{CO_2} = \frac{48\ \text{mmHg}}{767\ \text{mmHg}} = 0.063$$

The following table gives the values of χ_A for the gases in the exhaled air.

Gas	Mole Fraction
N_2	0.741
O_2	0.151
H_2O	0.037
CO_2	0.063
Ar	0.010

Exercise 7.5.2

Venus is an inhospitable place, with a surface temperature of 560°C and a surface pressure of 90 atm. The atmosphere consists of about 96% CO_2 and 3% N_2, with trace amounts of other gases, including water, sulfur dioxide, and sulfuric acid. Calculate the partial pressures of CO_2 and N_2.

Answer

$$P_{CO_2} = 86\ \text{atm}$$

$$P_{N_2} = 2.7 \text{ atm}$$

Collection of Gases over Water

A simple way to collect gases that do not react with water is to capture them in a bottle that has been filled with water and inverted into a dish filled with water. The pressure of the gas inside the bottle can be made equal to the air pressure outside by raising or lowering the bottle. When the water level is the same both inside and outside the bottle (Figure **7.5.3**), the pressure of the gas is equal to the atmospheric pressure, which can be measured with a barometer.




Figure **7.5.3**: When a reaction produces a gas that is collected above water, the trapped gas is a mixture of the gas produced by the reaction and water vapor. If the collection flask is appropriately positioned to equalize the water levels both within and outside the flask, the pressure of the trapped gas mixture will equal the atmospheric pressure outside the flask (see the earlier discussion of manometers).

However, there is another factor we must consider when we measure the pressure of the gas by this method. Water evaporates and there is always gaseous water (water vapor) above a sample of liquid water. As a gas is collected over water, it becomes saturated with water vapor and the total pressure of the mixture equals the partial pressure of the gas plus the partial pressure of the water vapor. The pressure of the pure gas is therefore equal to the total pressure minus the pressure of the water vapor—this is referred to as the "dry" gas pressure, that is, the pressure of the gas only, without water vapor.




Figure **7.5.4**: This graph shows the vapor pressure of water at sea level as a function of temperature.

The vapor pressure of water, which is the pressure exerted by water vapor in equilibrium with liquid water in a closed container, depends on the temperature (Figure **7.5.4**); more detailed information on the temperature dependence of water vapor can be found in Table **7.5.1**, and vapor pressure will be discussed in more detail in the next chapter on liquids.

Table **7.5.1***: Vapor Pressure of Ice and Water in Various Temperatures at Sea Level*

Temperature (°C)	Pressure (torr)	Temperature (°C)	Pressure (torr)	Temperature (°C)	Pressure (torr)
–10	1.95	18	15.5	30	31.8
–5	3.0	19	16.5	35	42.2
–2	3.9	20	17.5	40	55.3
0	4.6	21	18.7	50	92.5
2	5.3	22	19.8	60	149.4
4	6.1	23	21.1	70	233.7
6	7.0	24	22.4	80	355.1
8	8.0	25	23.8	90	525.8
10	9.2	26	25.2	95	633.9
12	10.5	27	26.7	99	733.2
14	12.0	28	28.3	100.0	760.0
16	13.6	29	30.0	101.0	787.6

Example 7.5.3: Pressure of a Gas Collected Over Water

If 0.200 L of argon is collected over water at a temperature of 26 °C and a pressure of 750 torr in a system like that shown in Figure **7.5.3**, what is the partial pressure of argon?

Solution

According to Dalton's law, the total pressure in the bottle (750 torr) is the sum of the partial pressure of argon and the partial pressure of gaseous water:

$$P_T = P_{Ar} + P_{H_2O} \tag{7.5.12}$$

Rearranging this equation to solve for the pressure of argon gives:

$$P_{Ar} = P_T - P_{H_2O} \tag{7.5.13}$$

The pressure of water vapor above a sample of liquid water at 26 °C is 25.2 torr (Appendix E), so:

$$P_{Ar} = 750 \text{ torr} - 25.2 \text{ torr} = 725 \text{ torr} \tag{7.5.14}$$

Exercise 7.5.3

A sample of oxygen collected over water at a temperature of 29.0 °C and a pressure of 764 torr has a volume of 0.560 L. What volume would the dry oxygen have under the same conditions of temperature and pressure?

Answer

0.583 L



Collecting a Product Gas over Water: https://youtu.be/zFuy3t81vjQ

Summary

The partial pressure of each gas in a mixture is proportional to its mole fraction. The pressure exerted by each gas in a gas mixture (its **partial pressure**) is independent of the pressure exerted by all other gases present. Consequently, the total pressure exerted by a mixture of gases is the sum of the partial pressures of the components (**Dalton's law of partial pressures**). The amount of gas present in a mixture may be described by its partial pressure or its mole fraction. The **mole fraction** of any component of a mixture is the ratio of the number of moles of that substance to the total number of moles of all substances present. In a mixture of gases, the partial pressure of each gas is the product of the total pressure and the mole fraction of that gas.

Glossary

Dalton's law of partial pressures
: total pressure of a mixture of ideal gases is equal to the sum of the partial pressures of the component gases.

mole fraction (*X*)
: concentration unit defined as the ratio of the molar amount of a mixture component to the total number of moles of all mixture components

partial pressure
: pressure exerted by an individual gas in a mixture

vapor pressure of water
: pressure exerted by water vapor in equilibrium with liquid water in a closed container at a specific temperature

---

7.5: Mixture of Gases is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **10.6: Gas Mixtures and Partial Pressures** is licensed CC BY-NC-SA 3.0.
- **9.3: Stoichiometry of Gaseous Substances, Mixtures, and Reactions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

7.6: Gas Stoichiometry

Learning Objectives

- Perform stoichiometric calculations involving gaseous substances

Chemical stoichiometry describes the quantitative relationships between reactants and products in chemical reactions. We have previously measured quantities of reactants and products using masses for solids and volumes in conjunction with the molarity for solutions; now we can also use gas volumes to indicate quantities. If we know the volume, pressure, and temperature of a gas, we can use the ideal gas equation to calculate how many moles of the gas are present. If we know how many moles of a gas are involved, we can calculate the volume of a gas at any temperature and pressure.

Avogadro's Law Revisited

Sometimes we can take advantage of a simplifying feature of the stoichiometry of gases that solids and solutions do not exhibit: All gases that show ideal behavior contain the same number of molecules in the same volume (at the same temperature and pressure). Thus, the ratios of volumes of gases involved in a chemical reaction are given by the coefficients in the equation for the reaction, provided that the gas volumes are measured at the same temperature and pressure.

We can extend Avogadro's law (that the volume of a gas is directly proportional to the number of moles of the gas) to chemical reactions with gases: Gases combine, or react, in definite and simple proportions by volume, provided that all gas volumes are measured at the same temperature and pressure. For example, since nitrogen and hydrogen gases react to produce ammonia gas according to

$$\mathrm{N_2}(g) + 3\,\mathrm{H_2}(g) \longrightarrow 2\,\mathrm{NH_3}(g) \tag{7.6.1}$$

a given volume of nitrogen gas reacts with three times that volume of hydrogen gas to produce two times that volume of ammonia gas, if pressure and temperature remain constant.

The explanation for this is illustrated in Figure **7.6.1**. According to Avogadro's law, equal volumes of gaseous N_2, H_2, and NH_3, at the same temperature and pressure, contain the same number of molecules. Because one molecule of N_2 reacts with three molecules of H_2 to produce two molecules of NH_3, the volume of H_2 required is three times the volume of N_2, and the volume of NH_3 produced is two times the volume of N_2.




Figure **7.6.1**: *One volume of N_2 combines with three volumes of H_2 to form two volumes of NH_3.*

Example 7.6.1: Reaction of Gases

Propane, $C_3H_8(g)$, is used in gas grills to provide the heat for cooking. What volume of $O_2(g)$ measured at 25 °C and 760 torr is required to react with 2.7 L of propane measured under the same conditions of temperature and pressure? Assume that the

propane undergoes complete combustion.

Solution

The ratio of the volumes of C_3H_8 and O_2 will be equal to the ratio of their coefficients in the balanced equation for the reaction:

$$\begin{array}{ll} \mathrm{C_3H_8}(g) + 5\,\mathrm{O_2}(g) \longrightarrow & 3\,\mathrm{CO_2}(g) + 4\,\mathrm{H_2O}(l) \quad (7.6.2) \\ 1\ \text{volume} + 5\ \text{volumes} & 3\ \text{volumes} + 4\ \text{volumes} \quad (7.6.3) \end{array}$$

From the equation, we see that one volume of C_3H_8 will react with five volumes of O_2:

$$2.7\ \mathrm{L\ C_3H_8} \times \frac{5\ \mathrm{L\ O_2}}{1\ \mathrm{L\ C_3H_8}} = 13.5\ \mathrm{L\ O_2} \quad (7.6.4)$$

A volume of 13.5 L of O_2 will be required to react with 2.7 L of C_3H_8.

? Exercise 7.6.1

An acetylene tank for an oxyacetylene welding torch provides 9340 L of acetylene gas, C_2H_2, at 0 °C and 1 atm. How many tanks of oxygen, each providing 7.00×10^3 L of O_2 at 0 °C and 1 atm, will be required to burn the acetylene?

$$2\,\mathrm{C_2H_2} + 5\,\mathrm{O_2} \longrightarrow 4\,\mathrm{CO_2} + 2\,\mathrm{H_2O} \quad (7.6.5)$$

Answer

3.34 tanks (2.34×10^4 L)

✓ Example 7.6.2: Volumes of Reacting Gases

Ammonia is an important fertilizer and industrial chemical. Suppose that a volume of 683 billion cubic feet of gaseous ammonia, measured at 25 °C and 1 atm, was manufactured. What volume of $H_2(g)$, measured under the same conditions, was required to prepare this amount of ammonia by reaction with N_2?

$$\mathrm{N_2}(g) + 3\,\mathrm{H_2}(g) \longrightarrow 2\,\mathrm{NH_3}(g) \quad (7.6.6)$$

Solution

Because equal volumes of H_2 and NH_3 contain equal numbers of molecules and each three molecules of H_2 that react produce two molecules of NH_3, the ratio of the volumes of H_2 and NH_3 will be equal to 3:2. Two volumes of NH_3, in this case in units of billion ft^3, will be formed from three volumes of H_2:

$$683\ \mathrm{billion\ ft^3\ NH_3} \times \frac{3\ \mathrm{billion\ ft^3\ H_2}}{2\ \mathrm{billion\ ft^3\ NH_3}} = 1.02 \times 10^3\ \mathrm{billion\ ft^3\ H_2} \quad (7.6.7)$$

The manufacture of 683 billion ft^3 of NH_3 required 1020 billion ft^3 of H_2. (At 25 °C and 1 atm, this is the volume of a cube with an edge length of approximately 1.9 miles.)

? Exercise 7.6.2

What volume of $O_2(g)$ measured at 25 °C and 760 torr is required to react with 17.0 L of ethylene, $C_2H_4(g)$, measured under the same conditions of temperature and pressure? The products are CO_2 and water vapor.

Answer

51.0 L


Example 7.6.3: Volume of Gaseous Product

What volume of hydrogen at 27 °C and 723 torr may be prepared by the reaction of 8.88 g of gallium with an excess of hydrochloric acid?

$$2\,Ga(s) + 6\,HCl(aq) \longrightarrow 2\,GaCl_3(aq) + 3\,H_2(g) \tag{7.6.8}$$

Solution

To convert from the mass of gallium to the volume of $H_2(g)$, we need to do something like this:



The first two conversions are:

$$8.88\ \cancel{g\ Ga} \times \frac{1\ \cancel{mol\ Ga}}{69.723\ \cancel{g\ Ga}} \times \frac{3\ mol\ H_2}{2\ \cancel{mol\ Ga}} = 0.191\ mol\ H_2 \tag{7.6.9}$$

Finally, we can use the ideal gas law:

$$V_{H_2} = \left(\frac{nRT}{P}\right)_{H_2} = \frac{0.191\ \cancel{mol} \times 0.08206\ L\ \cancel{atm\ mol^{-1}\ K^{-1}} \times 300\ K}{0.951\ atm} = 4.94\ L \tag{7.6.10}$$

Exercise 7.6.3

Sulfur dioxide is an intermediate in the preparation of sulfuric acid. What volume of SO_2 at 343 °C and 1.21 atm is produced by burning l.00 kg of sulfur in oxygen?

Answer

1.30×10^3 L

Greenhouse Gases and Climate Change

The thin skin of our atmosphere keeps the earth from being an ice planet and makes it habitable. In fact, this is due to less than 0.5% of the air molecules. Of the energy from the sun that reaches the earth, almost $\frac{1}{3}$ is reflected back into space, with the rest absorbed by the atmosphere and the surface of the earth. Some of the energy that the earth absorbs is re-emitted as infrared (IR) radiation, a portion of which passes back out through the atmosphere into space. However, most of this IR radiation is absorbed by certain substances in the atmosphere, known as greenhouse gases, which re-emit this energy in all directions, trapping some of the heat. This maintains favorable living conditions—without atmosphere, the average global average temperature of 14 °C (57 °F) would be about –19 °C (–2 °F). The major greenhouse gases (GHGs) are water vapor, carbon dioxide, methane, and ozone. Since the Industrial Revolution, human activity has been increasing the concentrations of GHGs, which have changed the energy balance and are significantly altering the earth's climate (Figure 7.6.2).




Figure **7.6.2**: Greenhouse gases trap enough of the sun's energy to make the planet habitable—this is known as the greenhouse effect. Human activities are increasing greenhouse gas levels, warming the planet and causing more extreme weather events.

There is strong evidence from multiple sources that higher atmospheric levels of CO_2 are caused by human activity, with fossil fuel burning accounting for about $\frac{3}{4}$ of the recent increase in CO_2. Reliable data from ice cores reveals that CO_2 concentration in the atmosphere is at the highest level in the past 800,000 years; other evidence indicates that it may be at its highest level in 20 million years. In recent years, the CO_2 concentration has increased from historical levels of below 300 ppm to almost 400 ppm today (Figure **7.6.3**).




Figure **7.6.3**: Figure CO_2 levels over the past 700,000 years were typically from 200–300 ppm, with a steep, unprecedented increase over the past 50 years.



Ideal Gas law Equation and Reaction Stoichiometry: https://youtu.be/8pPlW8MRhgI

Summary

Avogadro’s law may be used in stoichiometric computations for chemical reactions involving gaseous reactants or products.

7.6: Gas Stoichiometry is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **9.3: Stoichiometry of Gaseous Substances, Mixtures, and Reactions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

7.7: Effusion and Diffusion of Gases

Learning Objectives

- Define and explain effusion and diffusion
- State Graham's law and use it to compute relevant gas properties

If you have ever been in a room when a piping hot pizza was delivered, you have been made aware of the fact that gaseous molecules can quickly spread throughout a room, as evidenced by the pleasant aroma that soon reaches your nose. Although gaseous molecules travel at tremendous speeds (hundreds of meters per second), they collide with other gaseous molecules and travel in many different directions before reaching the desired target. At room temperature, a gaseous molecule will experience billions of collisions per second. The mean free path is the average distance a molecule travels between collisions. The mean free path increases with decreasing pressure; in general, the mean free path for a gaseous molecule will be hundreds of times the diameter of the molecule

In general, we know that when a sample of gas is introduced to one part of a closed container, its molecules very quickly disperse throughout the container; this process by which molecules disperse in space in response to differences in concentration is called diffusion (shown in Figure **7.7.1**). The gaseous atoms or molecules are, of course, unaware of any concentration gradient, they simply move randomly—regions of higher concentration have more particles than regions of lower concentrations, and so a net movement of species from high to low concentration areas takes place. In a closed environment, diffusion will ultimately result in equal concentrations of gas throughout, as depicted in Figure **7.7.1**. The gaseous atoms and molecules continue to move, but since their concentrations are the same in both bulbs, the rates of transfer between the bulbs are equal (no *net* transfer of molecules occurs).




Figure **7.7.1**: (a) Two gases, H_2 and O_2, are initially separated. (b) When the stopcock is opened, they mix together. The lighter gas, H_2, passes through the opening faster than O_2, so just after the stopcock is opened, more H_2 molecules move to the O_2 side than O_2 molecules move to the H_2 side. (c) After a short time, both the slower-moving O_2 molecules and the faster-moving H_2 molecules have distributed themselves evenly on both sides of the vessel.

We are often interested in the rate of diffusion, the amount of gas passing through some area per unit time:

$$\text{rate of diffusion} = \frac{\text{amount of gas passing through an area}}{\text{unit of time}} \tag{7.7.1}$$

The diffusion rate depends on several factors: the concentration gradient (the increase or decrease in concentration from one point to another); the amount of surface area available for diffusion; and the distance the gas particles must travel. Note also that the time required for diffusion to occur is inversely proportional to the rate of diffusion, as shown in the rate of diffusion equation.

A process involving movement of gaseous species similar to diffusion is effusion, the escape of gas molecules through a tiny hole such as a pinhole in a balloon into a vacuum (Figure **7.7.1**). Although diffusion and effusion rates both depend on the molar mass of the gas involved, their rates are not equal; however, the ratios of their rates are the same.




Figure 7.7.2: Diffusion occurs when gas molecules disperse throughout a container. Effusion occurs when a gas passes through an opening that is smaller than the mean free path of the particles, that is, the average distance traveled between collisions. Effectively, this means that only one particle passes through at a time.

If a mixture of gases is placed in a container with porous walls, the gases effuse through the small openings in the walls. The lighter gases pass through the small openings more rapidly (at a higher rate) than the heavier ones (Figure 7.7.2). In 1832, Thomas Graham studied the rates of effusion of different gases and formulated Graham's law of effusion: *The rate of effusion of a gas is inversely proportional to the square root of the mass of its particles*:

$$\text{rate of effusion} \propto \frac{1}{\sqrt{\mathcal{M}}} \tag{7.7.2}$$

This means that if two gases A and B are at the same temperature and pressure, the ratio of their effusion rates is inversely proportional to the ratio of the square roots of the masses of their particles:

$$\frac{\text{rate of effusion of B}}{\text{rate of effusion of A}} = \frac{\sqrt{\mathcal{M}_\text{A}}}{\sqrt{\mathcal{M}_\text{B}}} \tag{7.7.3}$$




Figure 7.7.3: A balloon filled with air (the blue one) remains full overnight. A balloon filled with helium (the green one) partially deflates because the smaller, light helium atoms effuse through small holes in the rubber much more readily than the heavier molecules of nitrogen and oxygen found in air. (credit: modification of work by Mark Ott)

Example 7.7.1: Applying Graham's Law to Rates of Effusion

Calculate the ratio of the rate of effusion of hydrogen to the rate of effusion of oxygen.

Solution

From Graham's law, we have:

$$\frac{\text{rate of effusion of hydrogen}}{\text{rate of effusion of oxygen}} = \frac{\sqrt{1.43\ \text{g}\,\text{L}^{-1}}}{\sqrt{0.0899\ \text{g}\,\text{L}^{-1}}} = \frac{1.20}{0.300} = \frac{4}{1}$$

Using molar masses:

$$\frac{\text{rate of effusion of hydrogen}}{\text{rate of effusion of oxygen}} = \frac{32\ \text{g}\,\text{mol}^{-1}}{2\ \text{g}\,\text{mol}^{-1}} = \frac{\sqrt{16}}{\sqrt{1}} = \frac{4}{1}$$

Hydrogen effuses four times as rapidly as oxygen.

Exercise 7.7.1

At a particular pressure and temperature, nitrogen gas effuses at the rate of 79 mL/s. Using the same apparatus at the same temperature and pressure, at what rate will sulfur dioxide effuse?

Answer

52 mL/s

Here's another example, making the point about how determining times differs from determining rates.

Example 7.7.2: Effusion Time Calculations

It takes 243 s for 4.46×10^{-5} mol Xe to effuse through a tiny hole. Under the same conditions, how long will it take 4.46×10^{-5} mol Ne to effuse?

Solution

It is important to resist the temptation to use the times directly, and to remember how rate relates to time as well as how it relates to mass. Recall the definition of rate of effusion:

$$\text{rate of effusion} = \frac{\text{amount of gas transferred}}{\text{time}}$$

and combine it with Graham's law:

$$\frac{\text{rate of effusion of gas Xe}}{\text{rate of effusion of gas Ne}} = \frac{\sqrt{\mathcal{M}_{\text{Ne}}}}{\sqrt{\mathcal{M}_{\text{Xe}}}}$$

To get:

$$\frac{\dfrac{\text{amount of Xe transferred}}{\text{time for Xe}}}{\dfrac{\text{amount of Ne transferred}}{\text{time for Ne}}} = \frac{\sqrt{\mathcal{M}_{\text{Ne}}}}{\sqrt{\mathcal{M}_{\text{Xe}}}}$$

Noting that *amount of A* = *amount of B*, and solving for *time for Ne*:

$$\frac{\dfrac{\cancel{\text{amount of Xe}}}{\text{time for Xe}}}{\dfrac{\cancel{\text{amount of Ne}}}{\text{time for Ne}}} = \frac{\text{time for Ne}}{\text{time for Xe}} = \frac{\sqrt{\mathcal{M}_{\text{Ne}}}}{\sqrt{\mathcal{M}_{\text{Xe}}}} = \frac{\sqrt{\mathcal{M}_{\text{Ne}}}}{\sqrt{\mathcal{M}_{\text{Xe}}}}$$

and substitute values:

$$\frac{\text{time for Ne}}{243\ \text{s}} = \sqrt{\frac{20.2\ \cancel{\text{g mol}}}{131.3\ \cancel{\text{g mol}}}} = 0.392$$

Finally, solve for the desired quantity:

$$\text{time for Ne} = 0.392 \times 243\ \text{s} = 95.3\ \text{s}$$

Note that this answer is reasonable: Since Ne is lighter than Xe, the effusion rate for Ne will be larger than that for Xe, which means the time of effusion for Ne will be smaller than that for Xe.

Exercise 7.7.2

A party balloon filled with helium deflates to $\frac{2}{3}$ of its original volume in 8.0 hours. How long will it take an identical balloon filled with the same number of moles of air ($\mathcal{M}$ = 28.2 g/mol) to deflate to $\frac{1}{2}$ of its original volume?

Answer

32 h

Finally, here is one more example showing how to calculate molar mass from effusion rate data.

Example 7.7.3: Determining Molar Mass Using Graham's Law

An unknown gas effuses 1.66 times more rapidly than CO_2. What is the molar mass of the unknown gas? Can you make a reasonable guess as to its identity?

Solution

From Graham's law, we have:

$$\frac{\text{rate of effusion of Unknown}}{\text{rate of effusion of } CO_2} = \sqrt{\mathcal{M}_{CO_2}}\sqrt{\mathcal{M}_{Unknown}} \tag{7.7.4}$$

Plug in known data:

$$\frac{1.66}{1} = \frac{\sqrt{44.0\ \text{g/mol}}}{\sqrt{\mathcal{M}_{Unknown}}} \tag{7.7.5}$$

Solve:

$$\mathcal{M}_{Unknown} = \frac{44.0\ \text{g/mol}}{(1.66)^2} = 16.0\ \text{g/mol} \tag{7.7.6}$$

The gas could well be CH_4, the only gas with this molar mass.

Exercise 7.7.3

Hydrogen gas effuses through a porous container 8.97-times faster than an unknown gas. Estimate the molar mass of the unknown gas.

Answer

163 g/mol

Application: Use of Diffusion for Uranium Enrichment

Gaseous diffusion has been used to produce enriched uranium for use in nuclear power plants and weapons. Naturally occurring uranium contains only 0.72% of ^{235}U, the kind of uranium that is "fissile," that is, capable of sustaining a nuclear fission chain reaction. Nuclear reactors require fuel that is 2–5% ^{235}U, and nuclear bombs need even higher concentrations. One way to enrich uranium to the desired levels is to take advantage of Graham's law. In a gaseous diffusion enrichment plant, uranium hexafluoride (UF_6, the only uranium compound that is volatile enough to work) is slowly pumped through large cylindrical vessels called diffusers, which contain porous barriers with microscopic openings. The process is one of diffusion because the other side of the barrier is not evacuated. The $^{235}UF_6$ molecules have a higher average speed and diffuse through the barrier a little faster than the heavier $^{238}UF_6$ molecules. The gas that has passed through the barrier is slightly enriched in $^{235}UF_6$ and the residual gas is slightly depleted. The small difference in molecular weights between $^{235}UF_6$ and $^{238}UF_6$ only about 0.4% enrichment, is achieved in one diffuser (Figure **7.7.4**). But by connecting many diffusers in a sequence of stages (called a cascade), the desired level of enrichment can be attained.




Figure **7.7.4**: In a diffuser, gaseous UF_6 is pumped through a porous barrier, which partially separates $^{235}UF_6$ from $^{238}UF_6$ The UF_6 must pass through many large diffuser units to achieve sufficient enrichment in ^{235}U.

The large scale separation of gaseous $^{235}UF_6$ from $^{238}UF_6$ was first done during the World War II, at the atomic energy installation in Oak Ridge, Tennessee, as part of the Manhattan Project (the development of the first atomic bomb). Although the theory is simple, this required surmounting many daunting technical challenges to make it work in practice. The barrier must have tiny, uniform holes (about 10^{-6} cm in diameter) and be porous enough to produce high flow rates. All materials (the barrier, tubing, surface coatings, lubricants, and gaskets) need to be able to contain, but not react with, the highly reactive and corrosive UF_6.

Because gaseous diffusion plants require very large amounts of energy (to compress the gas to the high pressures required and drive it through the diffuser cascade, to remove the heat produced during compression, and so on), it is now being replaced by gas centrifuge technology, which requires far less energy. A current hot political issue is how to deny this technology to Iran, to prevent it from producing enough enriched uranium for them to use to make nuclear weapons.



Graham's law of Diffusion and Effusion: https://youtu.be/9HO-qgh-iGI

Summary

Gaseous atoms and molecules move freely and randomly through space. Diffusion is the process whereby gaseous atoms and molecules are transferred from regions of relatively high concentration to regions of relatively low concentration. Effusion is a similar process in which gaseous species pass from a container to a vacuum through very small orifices. The rates of effusion of gases are inversely proportional to the square roots of their densities or to the square roots of their atoms/molecules' masses (Graham's law).

Key Equations

- $\text{rate of diffusion} = \dfrac{\text{amount of gas passing through an area}}{\text{unit of time}}$

- $\frac{\text{rate of effusion of gas B}}{\text{rate of effusion of gas A}} = \frac{\sqrt{m_B}}{\sqrt{m_A}} = \frac{\sqrt{\mathcal{M}_B}}{\sqrt{\mathcal{M}_A}}$

Summary

diffusion

movement of an atom or molecule from a region of relatively high concentration to one of relatively low concentration (discussed in this chapter with regard to gaseous species, but applicable to species in any phase)

effusion

transfer of gaseous atoms or molecules from a container to a vacuum through very small openings

Graham's law of effusion

rates of diffusion and effusion of gases are inversely proportional to the square roots of their molecular masses

mean free path

average distance a molecule travels between collisions

rate of diffusion

amount of gas diffusing through a given area over a given time

---

7.7: Effusion and Diffusion of Gases is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **9.4: Effusion and Diffusion of Gases** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

7.8: Kinetic Molecular Theory

Learning Objectives

- State the postulates of the kinetic-molecular theory
- Use this theory's postulates to explain the gas laws

The gas laws that we have seen to this point, as well as the ideal gas equation, are empirical, that is, they have been derived from experimental observations. The mathematical forms of these laws closely describe the macroscopic behavior of most gases at pressures less than about 1 or 2 atm. Although the gas laws describe relationships that have been verified by many experiments, they do not tell us why gases follow these relationships.

The kinetic molecular theory (KMT) is a simple microscopic model that effectively explains the gas laws described in previous modules of this chapter. This theory is based on the following five postulates described here. (Note: The term "molecule" will be used to refer to the individual chemical species that compose the gas, although some gases are composed of atomic species, for example, the noble gases.)

1. Gases are composed of molecules that are in continuous motion, travelling in straight lines and changing direction only when they collide with other molecules or with the walls of a container.
2. The molecules composing the gas are negligibly small compared to the distances between them.
3. The pressure exerted by a gas in a container results from collisions between the gas molecules and the container walls.
4. Gas molecules exert no attractive or repulsive forces on each other or the container walls; therefore, their collisions are *elastic* (do not involve a loss of energy).
5. The average kinetic energy of the gas molecules is proportional to the kelvin temperature of the gas.

The test of the KMT and its postulates is its ability to explain and describe the behavior of a gas. The various gas laws can be derived from the assumptions of the KMT, which have led chemists to believe that the assumptions of the theory accurately represent the properties of gas molecules. We will first look at the individual gas laws (Boyle's, Charles's, Amontons's, Avogadro's, and Dalton's laws) conceptually to see how the KMT explains them. Then, we will more carefully consider the relationships between molecular masses, speeds, and kinetic energies with temperature, and explain Graham's law.

The Kinetic-Molecular Theory Explains the Behavior of Gases, Part I

Recalling that gas pressure is exerted by rapidly moving gas molecules and depends directly on the number of molecules hitting a unit area of the wall per unit of time, we see that the KMT conceptually explains the behavior of a gas as follows:

- *Amontons's law.* If the temperature is increased, the average speed and kinetic energy of the gas molecules increase. If the volume is held constant, the increased speed of the gas molecules results in more frequent and more forceful collisions with the walls of the container, therefore increasing the pressure (Figure **7.8.1*a***).
- *Charles's law.* If the temperature of a gas is increased, a constant pressure may be maintained only if the volume occupied by the gas increases. This will result in greater average distances traveled by the molecules to reach the container walls, as well as increased wall surface area. These conditions will decrease both the frequency of molecule-wall collisions and the number of collisions per unit area, the combined effects of which balance the effect of increased collision forces due to the greater kinetic energy at the higher temperature.
- *Boyle's law.* If the gas volume is decreased, the container wall area decreases and the molecule-wall collision frequency increases, both of which increase the pressure exerted by the gas (Figure **7.8.1*b***).
- *Avogadro's law.* At constant pressure and temperature, the frequency and force of molecule-wall collisions are constant. Under such conditions, increasing the number of gaseous molecules will require a proportional increase in the container volume in order to yield a decrease in the number of collisions per unit area to compensate for the increased frequency of collisions (Figure **7.8.1*c***).
- *Dalton's Law.* Because of the large distances between them, the molecules of one gas in a mixture bombard the container walls with the same frequency whether other gases are present or not, and the total pressure of a gas mixture equals the sum of the (partial) pressures of the individual gases.




Figure 7.8.1: (a) When gas temperature increases, gas pressure increases due to increased force and frequency of molecular collisions. (b) When volume decreases, gas pressure increases due to increased frequency of molecular collisions. (c) When the amount of gas increases at a constant pressure, volume increases to yield a constant number of collisions per unit wall area per unit time.

Molecular Velocities and Kinetic Energy

The previous discussion showed that the KMT qualitatively explains the behaviors described by the various gas laws. The postulates of this theory may be applied in a more quantitative fashion to derive these individual laws. To do this, we must first look at velocities and kinetic energies of gas molecules, and the temperature of a gas sample.

In a gas sample, individual molecules have widely varying speeds; however, because of the *vast* number of molecules and collisions involved, the molecular speed distribution and average speed are constant. This molecular speed distribution is known as a Maxwell-Boltzmann distribution, and it depicts the relative numbers of molecules in a bulk sample of gas that possesses a given speed (Figure 7.8.2).




Figure 7.8.2: The molecular speed distribution for oxygen gas at 300 K is shown here. Very few molecules move at either very low or very high speeds. The number of molecules with intermediate speeds increases rapidly up to a maximum, which is the most probable speed, then drops off rapidly. Note that the most probable speed, v_p, is a little less than 400 m/s, while the root mean square speed, u_{rms}, is closer to 500 m/s.

The kinetic energy (KE) of a particle of mass (m) and speed (u) is given by:

$$\mathrm{KE} = \frac{1}{2}mu^2 \tag{7.8.1}$$

Expressing mass in kilograms and speed in meters per second will yield energy values in units of joules (J = kg m^2 s^{-2}). To deal with a large number of gas molecules, we use averages for both speed and kinetic energy. In the KMT, the root mean square velocity of a particle, u_{rms}, is defined as the square root of the average of the squares of the velocities with n = the number of particles:

$$u_{rms} = \sqrt{\overline{u^2}} = \sqrt{\frac{u_1^2 + u_2^2 + u_3^2 + u_4^2 + \ldots}{n}} \tag{7.8.2}$$

The average kinetic energy, KE_{avg}, is then equal to:

$$KE_{avg} = \frac{1}{2} m u_{rms}^2 \tag{7.8.3}$$

The KE_{avg} of a collection of gas molecules is also directly proportional to the temperature of the gas and may be described by the equation:

$$KE_{avg} = \frac{3}{2} RT \tag{7.8.4}$$

where R is the gas constant and T is the kelvin temperature. When used in this equation, the appropriate form of the gas constant is 8.314 J $mol^{-1}K^{-1}$ (8.314 kg $m^2s^{-2}mol^{-1}K^{-1}$). These two separate equations for KE_{avg} may be combined and rearranged to yield a relation between molecular speed and temperature:

$$\frac{1}{2} m u_{rms}^2 = \frac{3}{2} RT \tag{7.8.5}$$

$$u_{rms} = \sqrt{\frac{3RT}{m}} \tag{7.8.6}$$

Example 7.8.1: Calculation of u_{rms}

Calculate the root-mean-square velocity for a nitrogen molecule at 30 °C.

Solution

Convert the temperature into Kelvin:

$$30°C + 273 = 303\ K$$

Determine the mass of a nitrogen molecule in kilograms:

$$\frac{28.0\ \cancel{g}}{1\ \text{mol}} \times \frac{1\ \text{kg}}{1000\ \cancel{g}} = 0.028\ \text{kg/mol}$$

Replace the variables and constants in the root-mean-square velocity formula (Equation 7.8.6), replacing Joules with the equivalent kg m^2s^{-2}:

$$u_{rms} = \sqrt{\frac{3RT}{m}}$$

$$u_{rms} = \sqrt{\frac{3(8.314\ J/mol\ K)(303\ K)}{(0.028\ kg/mol)}}$$

$$= \sqrt{2.70 \times 10^5\ m^2s^{-2}}$$

$$= 519\ m/s$$

Exercise 7.8.1

Calculate the root-mean-square velocity for an oxygen molecule at –23 °C.

Answer

441 m/s

If the temperature of a gas increases, its KE_{avg} increases, more molecules have higher speeds and fewer molecules have lower speeds, and the distribution shifts toward higher speeds overall, that is, to the right. If temperature decreases, KE_{avg} decreases, more

molecules have lower speeds and fewer molecules have higher speeds, and the distribution shifts toward lower speeds overall, that is, to the left. This behavior is illustrated for nitrogen gas in Figure **7.8.3**.




Figure **7.8.3**: The molecular speed distribution for nitrogen gas (N_2) shifts to the right and flattens as the temperature increases; it shifts to the left and heightens as the temperature decreases.

At a given temperature, all gases have the same KE_{avg} for their molecules. Gases composed of lighter molecules have more high-speed particles and a higher u_{rms}, with a speed distribution that peaks at relatively higher velocities. Gases consisting of heavier molecules have more low-speed particles, a lower u_{rms}, and a speed distribution that peaks at relatively lower velocities. This trend is demonstrated by the data for a series of noble gases shown in Figure **7.8.4**.




Figure **7.8.4**: Molecular velocity is directly related to molecular mass. At a given temperature, lighter molecules move faster on average than heavier molecules.

> *The gas simulator may be used to examine the effect of temperature on molecular velocities. Examine the simulator's "energy histograms" (molecular speed distributions) and "species information" (which gives average speed values) for molecules of different masses at various temperatures.*

The Kinetic-Molecular Theory Explains the Behavior of Gases, Part II

According to Graham's law, the molecules of a gas are in rapid motion and the molecules themselves are small. The average distance between the molecules of a gas is large compared to the size of the molecules. As a consequence, gas molecules can move past each other easily and diffuse at relatively fast rates.

The rate of effusion of a gas depends directly on the (average) speed of its molecules:

$$\text{effusion rate} \propto u_{rms} \tag{7.8.7}$$

Using this relation, and the equation relating molecular speed to mass, Graham's law may be easily derived as shown here:

$$u_{\text{rms}} = \sqrt{\frac{3RT}{m}} \tag{7.8.8}$$

$$m = \frac{3RT}{u_{\text{rms}}^2} = \frac{3RT}{\overline{u}^2} \tag{7.8.9}$$

$$\frac{\text{effusion rate A}}{\text{effusion rate B}} = \frac{u_{\text{rms A}}}{u_{\text{rms B}}} = \frac{\sqrt{\frac{3RT}{m_{\text{A}}}}}{\sqrt{\frac{3RT}{m_{\text{B}}}}} = \sqrt{\frac{m_{\text{B}}}{m_{\text{A}}}} \tag{7.8.10}$$

The ratio of the rates of effusion is thus derived to be inversely proportional to the ratio of the square roots of their masses. This is the same relation observed experimentally and expressed as Graham's law.



Kinetic-Molecular Theory of Gases: https://youtu.be/9f83XAYfXAg

Summary

The kinetic molecular theory is a simple but very effective model that effectively explains ideal gas behavior. The theory assumes that gases consist of widely separated molecules of negligible volume that are in constant motion, colliding elastically with one another and the walls of their container with average velocities determined by their absolute temperatures. The individual molecules of a gas exhibit a range of velocities, the distribution of these velocities being dependent on the temperature of the gas and the mass of its molecules.

Key Equations

- $u_{\text{rms}} = \sqrt{\overline{u^2}} = \sqrt{\frac{u_1^2 + u_2^2 + u_3^2 + u_4^2 + \ldots}{n}}$
- $\text{KE}_{\text{avg}} = \frac{3}{2}RT$
- $u_{\text{rms}} = \sqrt{\frac{3RT}{m}}$

Summary

kinetic molecular theory

theory based on simple principles and assumptions that effectively explains ideal gas behavior

root mean square velocity (u_{rms})

measure of average velocity for a group of particles calculated as the square root of the average squared velocity

7.8: Kinetic Molecular Theory is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **9.5: The Kinetic-Molecular Theory** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

7.9: Non Ideal Gas Behavior

Learning Objectives

- Describe the physical factors that lead to deviations from ideal gas behavior
- Explain how these factors are represented in the van der Waals equation
- Define compressibility (Z) and describe how its variation with pressure reflects non-ideal behavior
- Quantify non-ideal behavior by comparing computations of gas properties using the ideal gas law and the van der Waals equation

Thus far, the ideal gas law, $PV = nRT$, has been applied to a variety of different types of problems, ranging from reaction stoichiometry and empirical and molecular formula problems to determining the density and molar mass of a gas. As mentioned in the previous modules of this chapter, however, the behavior of a gas is often non-ideal, meaning that the observed relationships between its pressure, volume, and temperature are not accurately described by the gas laws. In this section, the reasons for these deviations from ideal gas behavior are considered.

One way in which the accuracy of PV = nRT can be judged is by comparing the actual volume of 1 mole of gas (its molar volume, Vm) to the molar volume of an ideal gas at the same temperature and pressure. This ratio is called the compressibility factor (Z) with:

$$\mathrm{Z} = \frac{\text{molar volume of gas at same } T \text{ and } P}{\text{molar volume of ideal gas at same } T \text{ and } P} = \left(\frac{PV_m}{RT}\right)_{\text{measured}} \tag{7.9.1}$$

Ideal gas behavior is therefore indicated when this ratio is equal to 1, and any deviation from 1 is an indication of non-ideal behavior. Figure **7.9.1** shows plots of Z over a large pressure range for several common gases.




Figure **7.9.1**: A graph of the compressibility factor (Z) vs. pressure shows that gases can exhibit significant deviations from the behavior predicted by the ideal gas law.

As is apparent from Figure **7.9.1**, the ideal gas law does not describe gas behavior well at relatively high pressures. To determine why this is, consider the differences between real gas properties and what is expected of a hypothetical ideal gas.

Particles of a hypothetical ideal gas have **no significant volume** and **do not attract or repel each other**. In general, real gases approximate this behavior at relatively low pressures and high temperatures. However, at high pressures, the molecules of a gas are crowded closer together, and the amount of empty space between the molecules is reduced. At these higher pressures, the volume of the gas molecules themselves becomes appreciable relative to the total volume occupied by the gas (Figure **7.9.2**). The gas therefore becomes less compressible at these high pressures, and although its volume continues to decrease with increasing pressure, this decrease is not *proportional* as predicted by Boyle's law.




Figure 7.9.2: Raising the pressure of a gas increases the fraction of its volume that is occupied by the gas molecules and makes the gas less compressible.

At relatively low pressures, gas molecules have practically no attraction for one another because they are (on average) so far apart, and they behave almost like particles of an ideal gas. At higher pressures, however, the force of attraction is also no longer insignificant. This force pulls the molecules a little closer together, slightly decreasing the pressure (if the volume is constant) or decreasing the volume (at constant pressure) (Figure 7.9.3). This change is more pronounced at low temperatures because the molecules have lower KE relative to the attractive forces, and so they are less effective in overcoming these attractions after colliding with one another.




Figure 7.9.3: (a) Attractions between gas molecules serve to decrease the gas volume at constant pressure compared to an ideal gas whose molecules experience no attractive forces. (b) These attractive forces will decrease the force of collisions between the molecules and container walls, therefore reducing the pressure exerted compared to an ideal gas.

There are several different equations that better approximate gas behavior than does the ideal gas law. The first, and simplest, of these was developed by the Dutch scientist Johannes van der Waals in 1879. The van der Waals equation improves upon the ideal gas law by adding two terms: one to account for the volume of the gas molecules and another for the attractive forces between them.

$$PV = nRT \longrightarrow \left(P + \frac{an^2}{V^2}\right)(V - nb) = nRT$$

Correction for molecular attraction

Correction for volume of molecules

The constant a corresponds to the strength of the attraction between molecules of a particular gas, and the constant b corresponds to the size of the molecules of a particular gas. The “correction” to the pressure term in the ideal gas law is $\frac{n^2a}{V^2}$, and the “correction” to the volume is nb. Note that when V is relatively large and n is relatively small, both of these correction terms become negligible, and the van der Waals equation reduces to the ideal gas law, $PV = nRT$. Such a condition corresponds to a gas in which a relatively low number of molecules is occupying a relatively large volume, that is, a gas at a relatively low pressure. Experimental values for the van der Waals constants of some common gases are given in Table 7.9.1.

Table **7.9.1**: Values of van der Waals Constants for Some Common Gases

Gas	a (L^2 atm/mol^2)	b (L/mol)
N_2	1.39	0.0391
O_2	1.36	0.0318
CO_2	3.59	0.0427
H_2O	5.46	0.0305
He	0.0342	0.0237
CCl_4	20.4	0.1383

At low pressures, the correction for intermolecular attraction, *a*, is more important than the one for molecular volume, *b*. At high pressures and small volumes, the correction for the volume of the molecules becomes important because the molecules themselves are incompressible and constitute an appreciable fraction of the total volume. At some intermediate pressure, the two corrections have opposing influences and the gas appears to follow the relationship given by $PV = nRT$ over a small range of pressures. This behavior is reflected by the "dips" in several of the compressibility curves shown in Figure **7.9.1**. The attractive force between molecules initially makes the gas more compressible than an ideal gas, as pressure is raised (Z decreases with increasing *P*). At very high pressures, the gas becomes less compressible (Z increases with *P*), as the gas molecules begin to occupy an increasingly significant fraction of the total gas volume.

Strictly speaking, the ideal gas equation functions well when intermolecular attractions between gas molecules are negligible and the gas molecules themselves do not occupy an appreciable part of the whole volume. These criteria are satisfied under conditions of *low pressure and high temperature*. Under such conditions, the gas is said to behave ideally, and deviations from the gas laws are small enough that they may be disregarded—this is, however, very often not the case.

Example **7.9.1**: Comparison of Ideal Gas Law and van der Waals Equation

A 4.25-L flask contains 3.46 mol CO_2 at 229 °C. Calculate the pressure of this sample of CO_2:

a. from the ideal gas law
b. from the van der Waals equation
c. Explain the reason(s) for the difference.

Solution

(a) From the ideal gas law:

$$P = \frac{nRT}{V} = \frac{3.46\ \cancel{\text{mol}} \times 0.08206\ \cancel{\text{L}}\ \text{atm}\ \cancel{\text{mol}^{-1}}\ \cancel{\text{K}^{-1}} \times 502\ \cancel{\text{K}}}{4.25\ \cancel{\text{L}}} = 33.5\ \text{atm}$$

(b) From the van der Waals equation:

$$\left(P + \frac{n^2a}{V^2}\right) \times (V - nb) = nRT \longrightarrow P = \frac{nRT}{(V - nb)} - \frac{n^2a}{V^2}$$

$$P = \frac{3.46\ \text{mol} \times 0.08206\ \text{L atm mol}^{-1}\ \text{K}^{-1} \times 502\ \text{K}}{(4.25\ \text{L} - 3.46\ \text{mol} \times 0.0427\ \text{L mol}^{-1})} - \frac{(3.46\ \text{mol})^2 \times 3.59\ \text{L}^2\ \text{atm mol}^2}{(4.25\ \text{L})^2}$$

This finally yields *P* = 32.4 atm.

(c) This is not very different from the value from the ideal gas law because the pressure is not very high and the temperature is not very low. The value is somewhat different because CO_2 molecules do have some volume and attractions between molecules, and the ideal gas law assumes they do not have volume or attractions.

? Exercise 7.9.1

A 560-mL flask contains 21.3 g N_2 at 145 °C. Calculate the pressure of N_2:

a. from the ideal gas law
b. from the van der Waals equation
c. Explain the reason(s) for the difference.

Answer a

46.562 atm

Answer b

46.594 atm

Answer c

The van der Waals equation takes into account the volume of the gas molecules themselves as well as intermolecular attractions.

Summary

Gas molecules possess a finite volume and experience forces of attraction for one another. Consequently, gas behavior is not necessarily described well by the ideal gas law. Under conditions of low pressure and high temperature, these factors are negligible, the ideal gas equation is an accurate description of gas behavior, and the gas is said to exhibit ideal behavior. However, at lower temperatures and higher pressures, corrections for molecular volume and molecular attractions are required to account for finite molecular size and attractive forces. The van der Waals equation is a modified version of the ideal gas law that can be used to account for the non-ideal behavior of gases under these conditions.

Key Equations

- $\mathrm{Z} = \dfrac{\text{molar volume of gas at same } T \text{ and } P}{\text{molar volume of ideal gas at same } T \text{ and } P} = \left(\dfrac{P \times V_m}{R \times T}\right)_{\text{measured}}$
- $\left(P + \dfrac{n^2 a}{V^2}\right) \times (V - nb) = nRT$

Glossary

compressibility factor (Z)
ratio of the experimentally measured molar volume for a gas to its molar volume as computed from the ideal gas equation

van der Waals equation
modified version of the ideal gas equation containing additional terms to account for non-ideal gas behavior

7.9: Non Ideal Gas Behavior is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **9.6: Non-Ideal Gas Behavior** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

7.10: End of Chapter Problems

1. Why are sharp knives more effective than dull knives (Hint: think about the definition of pressure)?

Answer

The cutting edge of a knife that has been sharpened has a smaller surface area than a dull knife. Since pressure is force per unit area, a sharp knife will exert a higher pressure with the same amount of force and cut through material more effectively.

2. Why do some small bridges have weight limits that depend on how many wheels or axles the crossing vehicle has?
3. Why should you roll or belly-crawl rather than walk across a thinly-frozen pond?

Answer

Lying down distributes your weight over a larger surface area, exerting less pressure on the ice compared to standing up. If you exert less pressure, you are less likely to break through thin ice.

4. A typical barometric pressure in Redding, California, is about 750 mm Hg. Calculate this pressure in atm and kPa.
5. A typical barometric pressure in Denver, Colorado, is 615 mm Hg. What is this pressure in atmospheres and kilopascals?

Answer

0.809 atm; 82.0 kPa

6. A typical barometric pressure in Kansas City is 740 torr. What is this pressure in atmospheres, in millimeters of mercury, and in kilopascals?
7. Canadian tire pressure gauges are marked in units of kilopascals. What reading on such a gauge corresponds to 32 psi?

Answer

2.2×10^2 kPa

8. During the Viking landings on Mars, the atmospheric pressure was determined to be on the average about 6.50 millibars (1 bar = 0.987 atm). What is that pressure in torr and kPa?
9. The pressure of the atmosphere on the surface of the planet Venus is about 88.8 atm. Compare that pressure in psi to the normal pressure on earth at sea level in psi.

Answer

Earth: 14.7 lb in^{-2}; Venus: 13.1×10^3 lb in^{-2}


10. A medical laboratory catalog describes the pressure in a cylinder of a gas as 14.82 MPa. What is the pressure of this gas in atmospheres and torr?
11. Consider this scenario and answer the following questions: On a mid-August day in the northeastern United States, the following information appeared in the local newspaper: atmospheric pressure at sea level 29.97 in., 1013.9 mbar.
    a. What was the pressure in kPa?
    b. The pressure near the seacoast in the northeastern United States is usually reported near 30.0 in. Hg. During a hurricane, the pressure may fall to near 28.0 in. Hg. Calculate the drop in pressure in torr.

Answer

a. 101.5 kPa; b. 51 torr drop

12. Why is it necessary to use a nonvolatile liquid in a barometer or manometer?
13. The pressure of a sample of gas is measured at sea level with a closed-end manometer. The liquid in the manometer is mercury. Determine the pressure of the gas in:
    a. torr

b. Pa
c. bar




Answer

a. 264 torr; b. 35,200 Pa; c. 0.352 bar


14. The pressure of a sample of gas is measured with an open-end manometer, partially shown to the right. The liquid in the manometer is mercury. Assuming atmospheric pressure is 29.92 in. Hg, determine the pressure of the gas in:

    a. torr
    b. Pa
    c. bar



15. The pressure of a sample of gas is measured at sea level with an open-end mercury manometer. Assuming atmospheric pressure is 760.0 mm Hg, determine the pressure of the gas in:

    a. mm Hg
    b. atm
    c. kPa




Answer

a. 623 mm Hg; b. 0.820 atm; c. 83.1 kPa

16. The pressure of a sample of gas is measured at sea level with an open-end mercury manometer. Assuming atmospheric pressure is 760 mm Hg, determine the pressure of the gas in:

    a. mm Hg
    b. atm
    c. kPa



17. How would the use of a volatile liquid affect the measurement of a gas using open-ended manometers vs. closed-end manometers?

Answer

With a closed-end manometer, no change would be observed, since the vaporized liquid would contribute equal, opposing pressures in both arms of the manometer tube. However, with an open-ended manometer, a higher pressure reading of the gas would be obtained than expected, since $P_{gas} = P_{atm} + P_{vol\ liquid}$.

18. Sometimes leaving a bicycle in the sun on a hot day will cause a blowout. Why?

19. Explain how the volume of the bubbles exhausted by a scuba diver (Figure) change as they rise to the surface, assuming that they remain intact.

Answer

As the bubbles rise, the pressure decreases, so their volume increases as suggested by Boyle's law.

20. One way to state Boyle's law is "All other things being equal, the pressure of a gas is inversely proportional to its volume." (a) What is the meaning of the term "inversely proportional?" (b) What are the "other things" that must be equal?

21. An alternate way to state Avogadro's law is "All other things being equal, the number of molecules in a gas is directly proportional to the volume of the gas."


    a. What is the meaning of the term "directly proportional?"
    b. What are the "other things" that must be equal?

Answer

a. The number of particles in the gas increases as the volume increases. b. temperature, pressure


22. How would the graph in Figure change if the number of moles of gas in the sample used to determine the curve were doubled?


Temperature (°C)	Temperature (K)	Volume (L)
–3	270	22
–23	250	21
–53	220	18
–162	111	9




The volume and temperature are linearly related for 1 mole of methane gas at a constant pressure of 1 atm. If the temperature is in kelvin, volume and temperature are directly proportional. The line stops at 111 K because methane liquefies at this temperature; when extrapolated, it intersects the graph's origin, representing a temperature of absolute zero.

23. How would the graph in Figure change if the number of moles of gas in the sample used to determine the curve were doubled?







When a gas occupies a smaller volume, it exerts a higher pressure; when it occupies a larger volume, it exerts a lower pressure (assuming the amount of gas and the temperature do not change). Since P and V are inversely proportional, a graph of $1/P$ *vs. \ (V\) is linear.*

Answer

The curve would be farther to the right and higher up, but the same basic shape.

24. In addition to the data found in Figure, what other information do we need to find the mass of the sample of air used to determine the graph?

25. Determine the volume of 1 mol of CH_4 gas at 150 K and 1 atm, using Figure.

Answer

16.3 to 16.5 L

26. Determine the pressure of the gas in the syringe shown in Figure when its volume is 12.5 mL, using:
    a. the appropriate graph
    b. Boyle's law

27. A spray can is used until it is empty except for the propellant gas, which has a pressure of 1344 torr at 23 °C. If the can is thrown into a fire (T = 475 °C), what will be the pressure in the hot can?

Answer

3.40×10^3 torr

28. What is the temperature of an 11.2-L sample of carbon monoxide, CO, at 744 torr if it occupies 13.3 L at 55 °C and 744 torr?

Answer

we must use $\frac{P_1V_1}{T_1} = \frac{P_2V_2}{T_2}$ and solve for T_1

$T_1 = \frac{P_1V_1T_2}{P_2V_2}$

Where:

$P_1 = 744\ torr$

$V_1 = 11.2\ L$

$P_2 = 744\ torr$

$V_2 = 13.3\ L$

$T_2 = 328.15°\ K$

$\frac{(744\ torr)(11.2\ L)(328.15°\ K)}{(744\ torr)(13.3\ L)} = 276°\ K$

276°K ; 3°C

29. A 2.50-L volume of hydrogen measured at –196 °C is warmed to 100 °C. Calculate the volume of the gas at the higher temperature, assuming no change in pressure.

Answer

12.1 L

30. A balloon inflated with three breaths of air has a volume of 1.7 L. At the same temperature and pressure, what is the volume of the balloon if five more same-sized breaths are added to the balloon?

31. A weather balloon contains 8.80 moles of helium at a pressure of 0.992 atm and a temperature of 25 °C at ground level. What is the volume of the balloon under these conditions?



Answer

217 L

32. The volume of an automobile air bag was 66.8 L when inflated at 25 °C with 77.8 g of nitrogen gas. What was the pressure in the bag in kPa?

33. How many moles of gaseous boron trifluoride, BF_3, are contained in a 4.3410-L bulb at 788.0 K if the pressure is 1.220 atm? How many grams of BF_3?

Answer

8.190×10^{-2} mol; 5.553 g

34. Iodine, I_2, is a solid at room temperature but sublimes (converts from a solid into a gas) when warmed. What is the temperature in a 73.3-mL bulb that contains 0.292 g of I_2 vapor at a pressure of 0.462 atm?

Answer

1.) Use the equation $PV = nRT$ and solve for T

$$T = \frac{PV}{nR}$$

2.) convert grams of I_2 to moles of I_2 and convert mL to L

$$0.292g\ I_2 \times \frac{1\ mole\ I_2}{253.8g\ I_2} = 1.15 \times 10^{-3}\ moles\ I_2$$

$$73.3\ mL = 0.0733\ L$$

3.) Use these values along with $R = 0.08206\ \frac{atm\ L}{mole\ °K}$ to solve for T

$$T = \frac{(0.462\ \cancel{atm})(0.0733\ \cancel{L})}{(1.15 \times 10^{-3}\ \cancel{moles})(0.08206\ \frac{\cancel{atm}\ \cancel{L}}{\cancel{mole}\ °K})} = 359\ °K$$

359°K ; 86°C

35. How many grams of gas are present in each of the following cases?
    a. 0.100 L of CO_2 at 307 torr and 26 °C
    b. 8.75 L of C_2H_4, at 378.3 kPa and 483 K
    c. 221 mL of Ar at 0.23 torr and –54 °C

Answer

a. 7.24×10^{-2} g; b. 23.1 g; c. 1.5×10^{-4} g

36. A high altitude balloon is filled with 1.41×10^4 L of hydrogen at a temperature of 21 °C and a pressure of 745 torr. What is the volume of the balloon at a height of 20 km, where the temperature is –48 °C and the pressure is 63.1 torr?

37. A cylinder of medical oxygen has a volume of 35.4 L, and contains O_2 at a pressure of 151 atm and a temperature of 25 °C. What volume of O_2 does this correspond to at normal body conditions, that is, 1 atm and 37 °C?

Answer

5561 L

38. A large scuba tank (Figure) with a volume of 18 L is rated for a pressure of 220 bar. The tank is filled at 20 °C and contains enough air to supply 1860 L of air to a diver at a pressure of 2.37 atm (a depth of 45 feet). Was the tank filled to capacity at 20 °C?

39. A 20.0-L cylinder containing 11.34 kg of butane, C_4H_{10}, was opened to the atmosphere. Calculate the mass of the gas remaining in the cylinder if it were opened and the gas escaped until the pressure in the cylinder was equal to the atmospheric pressure,

0.983 atm, and a temperature of 27 °C.


Answer

46.4 g

40. While resting, the average 70-kg human male consumes 14 L of pure O_2 per hour at 25 °C and 100 kPa. How many moles of O_2 are consumed by a 70 kg man while resting for 1.0 h?

41. For a given amount of gas showing ideal behavior, draw labeled graphs of:
    a. the variation of P with V
    b. the variation of V with T
    c. the variation of P with T
    d. the variation of $\frac{1}{P}$ with V

42. For a gas exhibiting ideal behavior:



43. A liter of methane gas, CH_4, at STP contains more atoms of hydrogen than does a liter of pure hydrogen gas, H_2, at STP. Using Avogadro's law as a starting point, explain why.

44. The effect of chlorofluorocarbons (such as CCl_2F_2) on the depletion of the ozone layer is well known. The use of substitutes, such as $CH_3CH_2F(g)$, for the chlorofluorocarbons, has largely corrected the problem. Calculate the volume occupied by 10.0 g of each of these compounds at STP:
    a. $CCl_2F_2(g)$
    b. $CH_3CH_2F(g)$

Answer

a. 1.85 L CCl_2F_2; b. 4.66 L CH_3CH_2F

45. As 1 g of the radioactive element radium decays over 1 year, it produces 1.16×10^{18} alpha particles (helium nuclei). Each alpha particle becomes an atom of helium gas. What is the pressure in pascal of the helium gas produced if it occupies a volume of 125 mL at a temperature of 25 °C?

46. A balloon that is 100.21 L at 21 °C and 0.981 atm is released and just barely clears the top of Mount Crumpet in British Columbia. If the final volume of the balloon is 144.53 L at a temperature of 5.24 °C, what is the pressure experienced by the balloon as it clears Mount Crumpet?

Answer

0.644 atm

47. If the temperature of a fixed amount of a gas is doubled at constant volume, what happens to the pressure?

48. If the volume of a fixed amount of a gas is tripled at constant temperature, what happens to the pressure?

Answer

The pressure decreases by a factor of 3.

49. What is the density of laughing gas, dinitrogen monoxide, N_2O, at a temperature of 325 K and a pressure of 113.0 kPa?

Answer

1.) First convert kPa to atm

$$113.0\ kPa \times \frac{1\ atm}{101.325\ kPa} = 1.115\ atm$$

2.) The use the equation $d = \frac{PM}{RT}$ where d = density in g L^{-1} and M = molar mass in g mol^{-1}

$$d = \frac{(1.115\ atm)(44.02 \frac{g}{\cancel{mol}})}{(0.08206 \frac{\cancel{atm}\ L}{\cancel{mole}\ \cancel{°K}})(325\ \cancel{°K})} = 1.84\ \frac{g}{L}$$

50. Calculate the density of Freon 12, CF_2Cl_2, at 30.0 °C and 0.954 atm.

Answer

4.64 g L^{-1}

51. Which is denser at the same temperature and pressure, dry air or air saturated with water vapor? Explain.

52. A cylinder of $O_2(g)$ used in breathing by emphysema patients has a volume of 3.00 L at a pressure of 10.0 atm. If the temperature of the cylinder is 28.0 °C, what mass of oxygen is in the cylinder?

Answer

38.8 g

53. What is the molar mass of a gas if 0.0494 g of the gas occupies a volume of 0.100 L at a temperature 26 °C and a pressure of 307 torr?

Answer

1.) convert torr to atm and °C to °K

$$307\ torr = 0.404 atm$$

$$26°C = 300.°K$$

2.) Use the equation $PV = nRT$ and solve for n

$$n = \frac{PV}{RT}$$

$$n = \frac{(0.404\ \cancel{atm})(0.100\ \cancel{L})}{(0.08206\frac{\cancel{atm}\ \cancel{L}}{mol\ \cancel{°K}})(300.\ \cancel{°K})} = 0.00165\ moles$$

3.) Then divide grams by the number of moles to obtain the molar mass:

$$\frac{0.0494g}{0.00165\ moles} = 30.0\frac{g}{mole}$$

54. What is the molar mass of a gas if 0.281 g of the gas occupies a volume of 125 mL at a temperature 126 °C and a pressure of 777 torr?

Answer

72.0 g mol^{-1}

55. How could you show experimentally that the molecular formula of propene is C_3H_6, not CH_2?

56. The density of a certain gaseous fluoride of phosphorus is 3.93 g/L at STP. Calculate the molar mass of this fluoride and determine its molecular formula.

Answer

88.1 g mol^{-1}; PF_3

57. Consider this question: What is the molecular formula of a compound that contains 39% C, 45% N, and 16% H if 0.157 g of the compound occupies 125 mL with a pressure of 99.5 kPa at 22 °C?

a. Outline the steps necessary to answer the question.
b. Answer the question.

58. A 36.0–L cylinder of a gas used for calibration of blood gas analyzers in medical laboratories contains 350 g CO_2, 805 g O_2, and 4,880 g N_2. At 25 degrees C, what is the pressure in the cylinder in atmospheres?

Answer

141 atm

59. A cylinder of a gas mixture used for calibration of blood gas analyzers in medical laboratories contains 5.0% CO_2, 12.0% O_2, and the remainder N_2 at a total pressure of 146 atm. What is the partial pressure of each component of this gas? (The percentages given indicate the percent of the total pressure that is due to each component.)

Q9.3.12

60. A sample of gas isolated from unrefined petroleum contains 90.0% CH_4, 8.9% C_2H_6, and 1.1% C_3H_8 at a total pressure of 307.2 kPa. What is the partial pressure of each component of this gas? (The percentages given indicate the percent of the total pressure that is due to each component.)

Answer

CH_4: 276 kPa; C_2H_6: 27 kPa; C_3H_8: 3.4 kPa

61. A mixture of 0.200 g of H_2, 1.00 g of N_2, and 0.820 g of Ar is stored in a closed container at STP. Find the volume of the container, assuming that the gases exhibit ideal behavior.

62. Most mixtures of hydrogen gas with oxygen gas are explosive. However, a mixture that contains less than 3.0 % O_2 is not. If enough O_2 is added to a cylinder of H_2 at 33.2 atm to bring the total pressure to 34.5 atm, is the mixture explosive?

Answer

Yes

63. A commercial mercury vapor analyzer can detect, in air, concentrations of gaseous Hg atoms (which are poisonous) as low as 2 × 10^{-6} mg/L of air. At this concentration, what is the partial pressure of gaseous mercury if the atmospheric pressure is 733 torr

at 26 °C?

64. A sample of carbon monoxide was collected over water at a total pressure of 756 torr and a temperature of 18 °C. What is the pressure of the carbon monoxide? (See Table for the vapor pressure of water.)

Answer

740 torr

65. In an experiment in a general chemistry laboratory, a student collected a sample of a gas over water. The volume of the gas was 265 mL at a pressure of 753 torr and a temperature of 27 °C. The mass of the gas was 0.472 g. What was the molar mass of the gas?

66. Joseph Priestley first prepared pure oxygen by heating mercuric oxide, HgO:

$$2\,HgO(s) \longrightarrow 2\,Hg(l) + O_2(g)$$

a. Outline the steps necessary to answer the following question: What volume of O_2 at 23 °C and 0.975 atm is produced by the decomposition of 5.36 g of HgO?
b. Answer the question.

Answer

a. Determine the moles of HgO that decompose; using the chemical equation, determine the moles of O_2 produced by decomposition of this amount of HgO; and determine the volume of O_2 from the moles of O_2, temperature, and pressure. b. 0.308 L

67. Cavendish prepared hydrogen in 1766 by the novel method of passing steam through a red-hot gun barrel:

$$4\,H_2O(g) + 3\,Fe(s) \longrightarrow Fe_3O_4(s) + 4\,H_2(g) \qquad (7.10.1)$$

a. Outline the steps necessary to answer the following question: What volume of H_2 at a pressure of 745 torr and a temperature of 20 °C can be prepared from the reaction of 15.O g of H_2O?
b. Answer the question.

68. The chlorofluorocarbon CCl_2F_2 can be recycled into a different compound by reaction with hydrogen to produce $CH_2F_2(g)$, a compound useful in chemical manufacturing:

$$CCl_2F_2(g) + 4\,H_2(g) \longrightarrow CH_2F_2(g) + 2\,HCl(g) \qquad (7.10.2)$$

a. Outline the steps necessary to answer the following question: What volume of hydrogen at 225 atm and 35.5 °C would be required to react with 1 ton (1.000×10^3 kg) of CCl_2F_2?
b. Answer the question.

Answer

a. Determine the molar mass of CCl_2F_2. From the balanced equation, calculate the moles of H_2 needed for the complete reaction. From the ideal gas law, convert moles of H_2 into volume. b. 3.72×10^3 L

69. Automobile air bags are inflated with nitrogen gas, which is formed by the decomposition of solid sodium azide (NaN_3). The other product is sodium metal. Calculate the volume of nitrogen gas at 27 °C and 756 torr formed by the decomposition of 125 g of sodium azide.

70. Lime, CaO, is produced by heating calcium carbonate, $CaCO_3$; carbon dioxide is the other product.

a. Outline the steps necessary to answer the following question: What volume of carbon dioxide at 875° and 0.966 atm is produced by the decomposition of 1 ton (1.000×10^3 kg) of calcium carbonate?
b. Answer the question.

Answer

a. Balance the equation. Determine the grams of CO_2 produced and the number of moles. From the ideal gas law, determine the volume of gas. b. 7.43×10^5 L

71. Before small batteries were available, carbide lamps were used for bicycle lights. Acetylene gas, C_2H_2, and solid calcium hydroxide were formed by the reaction of calcium carbide, CaC_2, with water. The ignition of the acetylene gas provided the light. Currently, the same lamps are used by some cavers, and calcium carbide is used to produce acetylene for carbide cannons.
    a. Outline the steps necessary to answer the following question: What volume of C_2H_2 at 1.005 atm and 12.2 °C is formed by the reaction of 15.48 g of CaC_2 with water?
    b. Answer the question.
72. Calculate the volume of oxygen required to burn 12.00 L of ethane gas, C_2H_6, to produce carbon dioxide and water, if the volumes of C_2H_6 and O_2 are measured under the same conditions of temperature and pressure.

Answer

42.00 L

73. What volume of O_2 at STP is required to oxidize 8.0 L of NO at STP to NO_2? What volume of NO_2 is produced at STP?
74. Consider the following questions:
    a. What is the total volume of the $CO_2(g)$ and $H_2O(g)$ at 600 °C and 0.888 atm produced by the combustion of 1.00 L of $C_2H_6(g)$ measured at STP?
    b. What is the partial pressure of H_2O in the product gases?

Answer

a. 18.0 L; b. 0.533 atm

75. Methanol, CH_3OH, is produced industrially by the following reaction:

$$\mathrm{CO}(g) + 2\,\mathrm{H_2}(g) \xrightarrow{\text{copper catalyst 300 °C, 300 atm}} \mathrm{CH_3OH}(g) \tag{7.10.3}$$

Assuming that the gases behave as ideal gases, find the ratio of the total volume of the reactants to the final volume.

76. What volume of oxygen at 423.0 K and a pressure of 127.4 kPa is produced by the decomposition of 129.7 g of BaO_2 to BaO and O_2?

Answer

10.57 L O_2

77. A 2.50-L sample of a colorless gas at STP decomposed to give 2.50 L of N_2 and 1.25 L of O_2 at STP. What is the colorless gas?
78. Ethanol, C_2H_5OH, is produced industrially from ethylene, C_2H_4, by the following sequence of reactions:

$$3\,\mathrm{C_2H_4} + 2\,\mathrm{H_2SO_4} \longrightarrow \mathrm{C_2H_5HSO_4} + (\mathrm{C_2H_5})_2\mathrm{SO_4} \tag{7.10.4}$$

$$\mathrm{C_2H_5HSO_4} + (\mathrm{C_2H_5})_2\mathrm{SO_4} + 3\,\mathrm{H_2O} \longrightarrow 3\,\mathrm{C_2H_5OH} + 2\,\mathrm{H_2SO_4} \tag{7.10.5}$$

What volume of ethylene at STP is required to produce 1.000 metric ton (1000 kg) of ethanol if the overall yield of ethanol is 90.1%?

Answer

5.40×10^5 L

79. One molecule of hemoglobin will combine with four molecules of oxygen. If 1.0 g of hemoglobin combines with 1.53 mL of oxygen at body temperature (37 °C) and a pressure of 743 torr, what is the molar mass of hemoglobin?
80. A sample of a compound of xenon and fluorine was confined in a bulb with a pressure of 18 torr. Hydrogen was added to the bulb until the pressure was 72 torr. Passage of an electric spark through the mixture produced Xe and HF. After the HF was

removed by reaction with solid KOH, the final pressure of xenon and unreacted hydrogen in the bulb was 36 torr. What is the empirical formula of the xenon fluoride in the original sample? (Note: Xenon fluorides contain only one xenon atom per molecule.)

Answer

XeF_2

81. One method of analyzing amino acids is the van Slyke method. The characteristic amino groups ($-NH_2$) in protein material are allowed to react with nitrous acid, HNO_2, to form N_2 gas. From the volume of the gas, the amount of amino acid can be determined. A 0.0604-g sample of a biological sample containing glycine, $CH_2(NH_2)COOH$, was analyzed by the van Slyke method and yielded 3.70 mL of N_2 collected over water at a pressure of 735 torr and 29 °C. What was the percentage of glycine in the sample?

$$\mathbf{CH_2(NH_2)CO_2H + HNO_2 \longrightarrow CH_2(OH)CO_2H + H_2O + N_2}$$

82. A balloon filled with helium gas is found to take 6 hours to deflate to 50% of its original volume. How long will it take for an identical balloon filled with the same volume of hydrogen gas (instead of helium) to decrease its volume by 50%?

Answer

4.2 hours

83. Explain why the numbers of molecules are not identical in the left- and right-hand bulbs shown in the center illustration of Figure.

84. Starting with the definition of rate of effusion and Graham's finding relating rate and molar mass, show how to derive the Graham's law equation, relating the relative rates of effusion for two gases to their molecular masses.

Answer

Effusion can be defined as the process by which a gas escapes through a pinhole into a vacuum. Graham's law states that with a mixture of two gases A and B: $\left(\frac{\text{rate A}}{\text{rate B}}\right) = \left(\frac{\text{molar mass of B}}{\text{molar mass of A}}\right)^{1/2}$. Both A and B are in the same container at the same temperature, and therefore will have the same kinetic energy:

$\mathbf{KE_A = KE_{BKE}} = \frac{1}{2}mv^2$ Therefore, $\frac{1}{2}m_A v_A^2 = \frac{1}{2}m_B v_B^2$ $\frac{v_A^2}{v_B^2} = \frac{m_B}{m_A}$ $\left(\frac{v_A^2}{v_B^2}\right)^{1/2} = \left(\frac{m_B}{m_A}\right)^{1/2}$ $\frac{v_A}{v_B} = \left(\frac{m_B}{m_A}\right)^{1/2}$

85. Heavy water, D_2O (molar mass = 20.03 g mol^{-1}), can be separated from ordinary water, H_2O (molar mass = 18.01), as a result of the difference in the relative rates of diffusion of the molecules in the gas phase. Calculate the relative rates of diffusion of H_2O and D_2O.

86. Which of the following gases diffuse more slowly than oxygen? F_2, Ne, N_2O, C_2H_2, NO, Cl_2, H_2S

Answer

F_2, N_2O, Cl_2, H_2S

87. During the discussion of gaseous diffusion for enriching uranium, it was claimed that $^{235}UF_6$ diffuses 0.4% faster than $^{238}UF_6$. Show the calculation that supports this value. The molar mass of $^{235}UF_6$ = 235.043930 + 6 × 18.998403 = 349.034348 g/mol, and the molar mass of $^{238}UF_6$ = 238.050788 + 6 × 18.998403 = 352.041206 g/mol.

88. Calculate the relative rate of diffusion of $^1H_2$ (molar mass 2.0 g/mol) compared to that of $^2H_2$ (molar mass 4.0 g/mol) and the relative rate of diffusion of O_2 (molar mass 32 g/mol) compared to that of O_3 (molar mass 48 g/mol).

Answer

1.4; 1.2

89. A gas of unknown identity diffuses at a rate of 83.3 mL/s in a diffusion apparatus in which carbon dioxide diffuses at the rate of 102 mL/s. Calculate the molecular mass of the unknown gas.

90. When two cotton plugs, one moistened with ammonia and the other with hydrochloric acid, are simultaneously inserted into opposite ends of a glass tube that is 87.0 cm long, a white ring of NH_4Cl forms where gaseous NH_3 and gaseous HCl first come into contact. (Hint: Calculate the rates of diffusion for both NH_3 and HCl, and find out how much faster NH_3 diffuses than HCl.)

$$\mathbf{NH_3}(g) + \mathbf{HCl}(g) \longrightarrow \mathbf{NH_4Cl}(s) \tag{7.10.6}$$

91. At approximately what distance from the ammonia moistened plug does this occur?

Answer

51.7 cm

92. Using the postulates of the kinetic molecular theory, explain why a gas uniformly fills a container of any shape.

93. Can the speed of a given molecule in a gas double at constant temperature? Explain your answer.

Answer

Yes. At any given instant, there are a range of values of molecular speeds in a sample of gas. Any single molecule can speed up or slow down as it collides with other molecules. The average velocity of all the molecules is constant at constant temperature.

94. Describe what happens to the average kinetic energy of ideal gas molecules when the conditions are changed as follows:

    a. The pressure of the gas is increased by reducing the volume at constant temperature.
    b. The pressure of the gas is increased by increasing the temperature at constant volume.
    c. The average velocity of the molecules is increased by a factor of 2.

95. The distribution of molecular velocities in a sample of helium is shown in Figure. If the sample is cooled, will the distribution of velocities look more like that of H_2 or of H_2O? Explain your answer.

Answer

H_2O. Cooling slows the velocities of the He atoms, causing them to behave as though they were heavier.

96. What is the ratio of the average kinetic energy of a SO_2 molecule to that of an O_2 molecule in a mixture of two gases? What is the ratio of the root mean square speeds, u_{rms}, of the two gases?

97. A 1-L sample of CO initially at STP is heated to 546 °C, and its volume is increased to 2 L.

    a. What effect do these changes have on the number of collisions of the molecules of the gas per unit area of the container wall?
    b. What is the effect on the average kinetic energy of the molecules?
    c. What is the effect on the root mean square speed of the molecules?

Answer

a. The number of collisions per unit area of the container wall is constant. b. The average kinetic energy doubles. c. The root mean square speed increases to $\sqrt{2}$ times its initial value; u_{rms} is proportional to $\mathbf{KE_{avg}}$.

98. The root mean square speed of H_2 molecules at 25 °C is about 1.6 km/s. What is the root mean square speed of a N_2 molecule at 25 °C?

99. Answer the following questions:

    a. Is the pressure of the gas in the hot air balloon shown at the opening of this chapter greater than, less than, or equal to that of the atmosphere outside the balloon?
    b. Is the density of the gas in the hot air balloon shown at the opening of this chapter greater than, less than, or equal to that of the atmosphere outside the balloon?


c. At a pressure of 1 atm and a temperature of 20 °C, dry air has a density of 1.2256 g/L. What is the (average) molar mass of dry air?
d. The average temperature of the gas in a hot air balloon is 1.30×10^2 °F. Calculate its density, assuming the molar mass equals that of dry air.
e. The lifting capacity of a hot air balloon is equal to the difference in the mass of the cool air displaced by the balloon and the mass of the gas in the balloon. What is the difference in the mass of 1.00 L of the cool air in part (c) and the hot air in part (d)?
f. An average balloon has a diameter of 60 feet and a volume of 1.1×10^5 ft^3. What is the lifting power of such a balloon? If the weight of the balloon and its rigging is 500 pounds, what is its capacity for carrying passengers and cargo?
g. A balloon carries 40.0 gallons of liquid propane (density 0.5005 g/L). What volume of CO_2 and H_2O gas is produced by the combustion of this propane?
h. A balloon flight can last about 90 minutes. If all of the fuel is burned during this time, what is the approximate rate of heat loss (in kJ/min) from the hot air in the bag during the flight?

Answer

a. equal; b. less than; c. 29.48 g mol^{-1}; d. 1.0966 g L^{-1}; e. 0.129 g/L; f. 4.01×10^5 g; net lifting capacity = 384 lb; g. 270 L; h. 39.1 kJ min^{-1}

100. Show that the ratio of the rate of diffusion of Gas 1 to the rate of diffusion of Gas 2, $\frac{R_1}{R_2}$, is the same at 0 °C and 100 °C.


101. Graphs showing the behavior of several different gases follow. Which of these gases exhibit behavior significantly different from that expected for ideal gases?



Answer

Gases C, E, and F

102. Explain why the plot of PV for CO_2 differs from that of an ideal gas.



103. Under which of the following sets of conditions does a real gas behave most like an ideal gas, and for which conditions is a real gas expected to deviate from ideal behavior? Explain.

a. high pressure, small volume
b. high temperature, low pressure
c. low temperature, high pressure

Answer

The gas behavior most like an ideal gas will occur under the conditions in (b). Molecules have high speeds and move through greater distances between collision; they also have shorter contact times and interactions are less likely. Deviations occur with the conditions described in (a) and (c). Under conditions of (a), some gases may liquefy. Under conditions of (c), most gases will liquefy.

104. Describe the factors responsible for the deviation of the behavior of real gases from that of an ideal gas.

105. For which of the following gases should the correction for the molecular volume be largest: CO, CO_2, H_2, He, NH_3, SF_6?

Answer

SF_6

106. A 0.245-L flask contains 0.467 mol CO_2 at 159 °C. Calculate the pressure:

a. using the ideal gas law
b. using the van der Waals equation
c. Explain the reason for the difference.
d. Identify which correction (that for P or V) is dominant and why.

107. Answer the following questions:


a. If XX behaved as an ideal gas, what would its graph of Z vs. P look like?
b. For most of this chapter, we performed calculations treating gases as ideal. Was this justified?
c. What is the effect of the volume of gas molecules on Z? Under what conditions is this effect small? When is it large? Explain using an appropriate diagram.
d. What is the effect of intermolecular attractions on the value of Z? Under what conditions is this effect small? When is it large? Explain using an appropriate diagram.

e. In general, under what temperature conditions would you expect Z to have the largest deviations from the Z for an ideal gas?

Answer

a. A straight horizontal line at 1.0; b. When real gases are at low pressures and high temperatures they behave close enough to ideal gases that they are approximated as such, however, in some cases, we see that at a high pressure and temperature, the ideal gas approximation breaks down and is significantly different from the pressure calculated by the van der Waals equation c. The greater the compressibility, the more the volume matters. At low pressures, the correction factor for intermolecular attractions is more significant, and the effect of the volume of the gas molecules on Z would be a small lowering compressibility. At higher pressures, the effect of the volume of the gas molecules themselves on Z would increase compressibility (see Figure) d. Once again, at low pressures, the effect of intermolecular attractions on Z would be more important than the correction factor for the volume of the gas molecules themselves, though perhaps still small. At higher pressures and low temperatures, the effect of intermolecular attractions would be larger. See Figure. e. low temperatures

108. Graphs showing the behavior of several different gases follow. Which of these gases exhibit behavior significantly different from that expected for ideal gases?



Answer

Gases C, E, and F

Explain why the plot of PV for CO_2 differs from that of an ideal gas.

A graph is shown. The horizontal axis is labeled, “P (a t m).” Its scale is marked at 0, 1, and 2. The vertical axis is labeled, “P V (a t m L).” This scale includes markings at 0, 22.4, 22.5, and 22.6. Two curves and two lines are drawn of varying colors. One line is a horizontal, blue line extending right from about 22.42 a t m L on the vertical axis, and is labeled, “Ideal gas.” The remaining two curves and one line start at the same point on the vertical axis. A green line extends up and to the right slightly on the graph, reaching a value of approximately 22.46 a t m L at 2 a t m. This green line is labeled, “H e.” An orange curve dips below the horizontal ideal gas line initially, then increases to cross the line just past 1 a t m. This curve reaches a value of about 22.52 a t m L at 2 a t m. This curve is labeled, “C H subscript 4.” A purple curve dips below the horizontal ideal gas line initially, then increases to cross the line at about 0.8 a t m. This curve reaches a value of nearly 22.62 a t m L at nearly 1.2 a t m. This curve is labeled, “C O subscript 2.”

109. Under which of the following sets of conditions does a real gas behave most like an ideal gas, and for which conditions is a real gas expected to deviate from ideal behavior? Explain.

(a) high pressure, small volume

(b) high temperature, low pressure

(c) low temperature, high pressure

Answer

4The gas behavior most like an ideal gas will occur under the conditions in (b). Molecules have high speeds and move through greater distances between collision; they also have shorter contact times and interactions are less likely. Deviations occur with the conditions described in (a) and (c). Under conditions of (a), some gases may liquefy. Under conditions of (c), most gases will liquefy.

110. Describe the factors responsible for the deviation of the behavior of real gases from that of an ideal gas.

111. For which of the following gases should the correction for the molecular volume be largest:

CO, CO_2, H_2, He, NH_3, SF_6?

Answer

SF_6

112. A 0.245-L flask contains 0.467 mol CO_2 at 159 °C. Calculate the pressure:

(a) using the ideal gas law

(b) using the van der Waals equation

(c) Explain the reason for the difference.

(d) Identify which correction (that for P or V) is dominant and why.

113. Answer the following questions:

(a) If XX behaved as an ideal gas, what would its graph of Z vs. P look like?

(b) For most of this chapter, we performed calculations treating gases as ideal. Was this justified?

(c) What is the effect of the volume of gas molecules on Z? Under what conditions is this effect small? When is it large? Explain using an appropriate diagram.

(d) What is the effect of intermolecular attractions on the value of Z? Under what conditions is this effect small? When is it large? Explain using an appropriate diagram.

(e) In general, under what temperature conditions would you expect Z to have the largest deviations from the Z for an ideal gas?

Answer

(a) A straight horizontal line at 1.0; (b) When real gases are at low pressures and high temperatures they behave close enough to ideal gases that they are approximated as such, however, in some cases, we see that at a high pressure and temperature, the ideal gas approximation breaks down and is significantly different from the pressure calculated by the van der Waals equation (c) The greater the compressibility, the more the volume matters. At low pressures, the correction factor for intermolecular attractions is more significant, and the effect of the volume of the gas molecules on Z would be a small lowering compressibility. At higher pressures, the effect of the volume of the gas molecules themselves on Z would increase compressibility (see Figure) (d) Once again, at low pressures, the effect of intermolecular attractions on Z would be more important than the correction factor for the volume of the gas molecules themselves, though perhaps still small. At higher pressures and low temperatures, the effect of intermolecular attractions would be larger. See Figure. (e) low temperatures

7.10: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

8: Thermochemistry

8.1: Types of Energy
8.2: Internal Energy and First Law of Thermodynamics
8.3: Quantifying Heat and Work
8.4: Constant Volume Calorimeter
8.5: Enthalpy of reactions
8.6: Constant Pressure Calorimeter
8.7: Standard Enthalpy of formation
8.8: Calculating Enthalpy of Reactions Using Hess's Law
8.9: End of Chapter Problems

8: Thermochemistry is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

8.1: Types of Energy

Learning Objectives

- Define energy, distinguish types of energy, and describe the nature of energy changes that accompany chemical and physical changes
- Distinguish the related properties of heat, thermal energy, and temperature

Energy is one of the most fundamental and universal concepts of physical science, but one that is remarkably difficult to define in way that is meaningful to most people. This perhaps reflects the fact that energy is not a “thing” that exists by itself, but is rather an attribute of matter (and also of electromagnetic radiation) that can manifest itself in different ways. It can be observed and measured only indirectly through its effects on matter that acquires, loses, or possesses it. Energy can be defined as the capacity to supply heat or do work. One type of work (w) is the process of causing matter to move against an opposing force. For example, we do work when we inflate a bicycle tire—we move matter (the air in the pump) against the opposing force of the air already in the tire.

History of Energy - "Living Force" vs. "Dead force"

The concept that we call energy was very slow to develop; it took more than a hundred years just to get people to agree on the definitions of many of the terms we use to describe energy and the interconversion between its various forms. But even now, most people have some difficulty in explaining what it is; somehow, the definition we all learned in elementary science ("the capacity to do work") seems less than adequate to convey its meaning.

Although the term "energy" was not used in science prior to 1802, it had long been suggested that certain properties related to the motions of objects exhibit an endurance which is incorporated into the modern concept of "conservation of energy". René Descartes (1596-1650) stated it explicitly: In the 17th Century, the great mathematician Gottfried Leibniz (1646-1716) suggested the distinction between *vis viva* ("life force") and *vis mortua* ("dead force"), which later became known as kinetic energy (1829) and potential energy (1853).

SI Unit of Energy - The joule

The basic unit of energy is the *joule*. One joule is the amount of work done when a force of 1 newton acts over a distance of 1 m; thus 1 J = 1 N-m. The newton is the amount of force required to accelerate a 1-kg mass by 1 m/sec^2, so the basic dimensions of the joule are kg m^2 s^{-2}.

$$1\,J = 1\,kg\,m^2 s^{-2}: \tag{8.1.1}$$

Types of Energy

Energy can be characterized through its observed properties. All the types can be broadly divided into two types principal types: potential and kinetic energy. However, there are additional flavors of both that are commonly discussed in the study of chemistry.

Kinetic Energy

Whatever energy may be, there are basically two kinds. Kinetic energy is associated with the **motion** of an object, and its direct consequences are part of everyone's daily experience; the faster the ball you catch in your hand, and the heavier it is, the more you feel it. Quantitatively, a body with a mass m and moving at a velocity v possesses the kinetic energy

$$KE = \frac{1}{2}mv^2 \tag{8.1.2}$$

Example 8.1.1

What is the kinetic energy of a 4.25 g bullet shot from a rifle a velocity of 965 m s^{-1}.

Solution

This is a direct application of the definition of kinetic energy (Equation 8.1.2):

$$\begin{aligned} KE &= \frac{1}{2}(0.00425\,kg)(965\,m\,s^{-1})^2 \\ &= 1.980\,J \end{aligned}$$

Potential Energy

Potential energy is energy a body has by virtue of its *location, composition, or condition.* However, there is more: the body must be subject to a "restoring force" of some kind that tends to move it to a location of lower potential energy. Think of an arrow that is subjected to the force from a stretched bowstring; the more tightly the arrow is pulled back against the string, the more potential energy it has. More generally, the restoring force comes from what we call a *force field*— a gravitational, electrostatic, or magnetic field. We observe the consequences of *gravitational* potential energy all the time, such as when we walk, but seldom give it any thought.

If an object of mass m is raised off the floor to a height h, its potential energy increases by mgh, where g is a proportionality constant known as the *acceleration of gravity*; its value at the earth's surface is 9.8 m s^{-2}.

$$PE = mpg \tag{8.1.3}$$

Example 8.1.2

Find the change in gravitational potential energy of a 2.6 kg textbook that falls from the 66-cm height of a table top onto the floor.

Solution

This is a direct application of Equation 8.1.3

$$\begin{aligned} PE &= m\,g\,h \\ &= (2.6\,kg)(9.8\,ms^{-2})(0.66m) \\ &= 16.8\,kg\,m^2s^{-2} \\ &= 16.8\,J \end{aligned}$$

Similarly, the potential energy of a particle having an electric charge q depends on its location in an electrostatic field. This would be an electric potential energy. and has a difference functional form that gravitational energy (Equation 8.1.3).

Chemical Energy

Electrostatic potential energy plays a major role in chemistry; the potential energies of electrons in the force field created by atomic nuclei lie at the heart of the chemical behavior of atoms and molecules. "Chemical energy" usually refers to the energy that is stored in the chemical bonds of molecules. These bonds form when electrons are able to respond to the force fields created by two or more atomic nuclei, so they can be regarded as manifestations of electrostatic potential energy. In an exothermic chemical reaction, the electrons and nuclei within the reactants undergo rearrangement into products possessing lower energies, and the difference is released to the environment in the form of heat.

Thermal Energy

Kinetic energy is associated with motion, but in two different ways. For a macroscopic object such as a book or a ball, or a parcel of flowing water, it is simply given by Equation 8.1.2. But as we mentioned above, when an object is dropped onto the floor, or when an exothermic chemical reaction heats surrounding matter, the kinetic energy gets dispersed into the molecular units in the environment. This "microscopic" form of kinetic energy, unlike that of a speeding bullet, is completely random in the kinds of motions it exhibits and in its direction. We refer to this as "thermalized" kinetic energy, or more commonly simply as *thermal*

energy. We observe the effects of this as a rise in the temperature of the surroundings. The temperature of a body is direct measure of the quantity of thermal energy is contains.

Once kinetic energy is thermalized, only a portion of it can be converted back into potential energy. The remainder simply gets dispersed and diluted into the environment, and is effectively lost. To summarize, then:

- Potential energy can be converted entirely into kinetic energy..
- Potential energy can also be converted, with varying degrees of efficiency,into electrical energy.
- The kinetic energy of macroscopic objects can be transferred between objects (barring the effects of friction).

Interconversion of Energies

Like matter, energy comes in different types. Energy can be converted from one form into another, but all of the energy present before a change occurs always exists in some form after the change is completed. This observation is expressed in the law of conservation of energy:

law of conservation of energy

During a chemical or physical change, energy can be neither created nor destroyed, although it can be changed in form.

When one substance is converted into another, there is always an associated conversion of one form of energy into another. Heat is usually released or absorbed, but sometimes the conversion involves light, electrical energy, or some other form of energy. For example, chemical energy (a type of potential energy) is stored in the molecules that compose gasoline. When gasoline is combusted within the cylinders of a car's engine, the rapidly expanding gaseous products of this chemical reaction generate mechanical energy (a type of kinetic energy) when they move the cylinders' pistons. The law of conservation of energy is also one version of the first law of thermodynamics, as you will learn later.

Transitions between potential and kinetic energy are such an intimate part of our daily lives that we hardly give them a thought. It happens in walking as the body moves up and down. Our bodies utilize the chemical energy in glucose to keep us warm and to move our muscles. In fact, life itself depends on the conversion of chemical energy to other forms. So when you go uphill, your kinetic energy is transformed into potential energy, which gets changed back into kinetic energy as you coast down the other side. And where did the kinetic energy you expended in peddling uphill come from? By conversion of some of the chemical potential energy in your breakfast cereal.

Water at the top of a waterfall or dam has potential energy because of its position; when it flows downward through generators, it has kinetic energy that can be used to do work and produce electricity in a hydroelectric plant (Figure 8.1.1). A battery has potential energy because the chemicals within it can produce electricity that can do work.



(a) (b)

Figure 8.1.1: (a) Water that is higher in elevation, for example, at the top of Victoria Falls, has a higher potential energy than water at a lower elevation. As the water falls, some of its potential energy is converted into kinetic energy. (b) If the water flows through generators at the bottom of a dam, such as the Hoover Dam shown here, its kinetic energy is converted into electrical energy. (credit a: modification of work by Steve Jurvetson; credit b: modification of work by "curimedia"/Wikimedia commons).

- When drop a book, its potential energy is transformed into kinetic energy. When it strikes the floor, this transformation is complete. What happens to the energy then? The kinetic energy that at the moment of impact was formerly situated exclusively in the moving book, now becomes shared between the book and the floor, and in the form of randomized thermal motions of the molecular units of which they are made; we can observe this effect as a rise in temperature.
- Much of the potential energy of falling water can be captured by a water wheel or other device that transforms the kinetic energy of the exit water into kinetic energy. The output of a hydroelectric power is directly proportional to its height above the level of the generator turbines in the valley below. At this point, the kinetic energy of the exit water is transferred to that of the turbine, most of which (up to 90 percent in the largest installations) is then converted into electrical energy.
- Will the temperature of the water at the bottom of a water fall be greater than that at the top? James Joule himself predicted that it would be. It has been calculated that at Niagra falls, that complete conversion of the potential energy of 1 kg of water at the top into kinetic energy when it hits the plunge pool 58 meters below will result in a temperature increase of about 0.14 C°. (But there are lots of complications. For example, some of the water breaks up into tiny droplets as it falls, and water evaporates from droplets quite rapidly, producing a cooling effect.)
- Chemical energy can also be converted, at least partially, into electrical energy: this is what happens in a battery. If a highly exothermic reaction also produces gaseous products, the latter may expand so rapidly that the result is an explosion — a net conversion of chemical energy into kinetic energy (including sound).

What is the zero of Energy and does it matter?

You might at first think that a book sitting on the table has zero kinetic energy since it is not moving. But if you think about it, the earth itself is moving; it is spinning on its axis, it is orbiting the sun, and the sun itself is moving away from the other stars in the general expansion of the universe. Since these motions are normally of no interest to us, we are free to adopt an arbitrary scale in which the velocity of the book is measured with respect to the table; on this so-called *laboratory coordinate system*, the kinetic energy of the book can be considered zero.

We do the same thing with potential energy. If the book is on the table, its potential energy with respect to the surface of the table will be zero. If we adopt this as our zero of potential energy, and then push the book off the table, its potential energy will be negative after it reaches the floor.

Summary

Energy is the capacity to do work (applying a force to move matter). Kinetic energy (KE) is the energy of motion; potential energy is energy due to relative position, composition, or condition. When energy is converted from one form into another, energy is neither created nor destroyed (law of conservation of energy or first law of thermodynamics). Matter has thermal energy due to the KE of its molecules and temperature that corresponds to the average KE of its molecules. Heat is energy that is transferred between objects at different temperatures; it flows from a high to a low temperature. Chemical and physical processes can absorb heat (endothermic) or release heat (exothermic). The SI unit of energy, heat, and work is the joule (J).

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).
- Stephen Lower, Professor Emeritus (Simon Fraser U.) Chem1 Virtual Textbook

8.1: Types of Energy is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

8.2: Internal Energy and First Law of Thermodynamics

Learning Objectives

- State the first law of thermodynamics
- To calculate changes in internal energy

To study the flow of energy during a chemical reaction, we need to distinguish between a system, the small, well-defined part of the universe in which we are interested (such as a chemical reaction), and its surroundings, the rest of the universe, including the container in which the reaction is carried out (Figure 8.2.1). In the discussion that follows, the mixture of chemical substances that undergoes a reaction is always the system, and the flow of heat can be from the system to the surroundings or vice versa.




Figure 8.2.1: A System and Its Surroundings. The system is that part of the universe we are interested in studying, such as a chemical reaction inside a flask. The surroundings are the rest of the universe, including the container in which the reaction is carried out.

Three kinds of systems are important in chemistry. An **open system** can exchange both matter and energy with its surroundings. A pot of boiling water is an open system because a burner supplies energy in the form of heat, and matter in the form of water vapor is lost as the water boils. A **closed system** can exchange energy but not matter with its surroundings. The sealed pouch of a ready-made dinner that is dropped into a pot of boiling water is a closed system because thermal energy is transferred to the system from the boiling water but no matter is exchanged (unless the pouch leaks, in which case it is no longer a closed system). An **isolated system** exchanges neither energy nor matter with the surroundings. Energy is always exchanged between a system and its surroundings, although this process may take place very slowly. A truly isolated system does not actually exist. An insulated thermos containing hot coffee approximates an isolated system, but eventually the coffee cools as heat is transferred to the surroundings. In all cases, the amount of heat lost by a system is equal to the amount of heat gained by its surroundings and vice versa. That is, *the total energy of a system plus its surroundings is constant*, which must be true if *energy is conserved*.

The state of a system is a complete description of a system at a given time, including its temperature and pressure, the amount of matter it contains, its chemical composition, and the physical state of the matter. A state function is a property of a system whose magnitude depends on only the present state of the system, not its previous history. Temperature, pressure, volume, and potential energy are all state functions. The temperature of an oven, for example, is independent of however many steps it may have taken for it to reach that temperature. Similarly, the pressure in a tire is independent of how often air is pumped into the tire for it to reach that pressure, as is the final volume of air in the tire. Heat and work, on the other hand, are not state functions because they are *path dependent*. For example, a car sitting on the top level of a parking garage has the same potential energy whether it was lifted by a crane, set there by a helicopter, driven up, or pushed up by a group of students (Figure 8.2.2). The amount of work expended to get it there, however, can differ greatly depending on the path chosen. If the students decided to carry the car to the top of the ramp, they would perform a great deal more work than if they simply pushed the car up the ramp (unless, of course, they neglected to release the parking brake, in which case the work expended would increase substantially!). The potential energy of the car is the same, however, no matter which path they choose.



Figure 8.2.2: Elevation as an Example of a State Function. The change in elevation between state 1 (at the bottom of the parking garage) and state 2 (at the top level of the parking garage) is the same for both paths A and B; it does not depend on which path is taken from the bottom to the top. In contrast, the distance traveled and the work needed to reach the top do depend on which path is taken. Elevation is a state function, but distance and work are *not* state functions.

Direction of Heat Flow

The reaction of powdered aluminum with iron(III) oxide, known as the thermite reaction, generates an enormous amount of heat—enough, in fact, to melt steel (Figure 8.2.3). The balanced chemical equation for the reaction is as follows:

$$2\,Al\,(s) + Fe_2O_3\,(s) \longrightarrow 2\,Fe\,(s) + Al_2O_3\,(s) \tag{8.2.1}$$



Figure 8.2.3: The thermite reaction produces so much heat that the iron it produces comes out molten, a property that makes this reaction useful in welding. Image by Kingfisher [CC BY-SA 3.0 (https://creativecommons.org/licenses/by-sa/3.0)], from Wikimedia Commons.

We can also write this chemical equation as

$$2\,Al\,(s) + Fe_2O_3\,(s) \rightarrow 2\,Fe\,(s) + Al_2O_3\,(s) + heat \tag{8.2.2}$$

to indicate that heat is one of the products. Chemical equations in which heat is shown as either a reactant or a product are called *thermochemical equations*. In this reaction, the system consists of aluminum, iron, and oxygen atoms; everything else, including the container, makes up the surroundings. During the reaction, so much heat is produced that the iron liquefies. Eventually, the system cools; the iron solidifies as heat is transferred to the surroundings. A process in which heat (q) is transferred *from* a system *to* its surroundings is described as exothermic. By convention, $q < 0$ for an exothermic reaction.

When you hold an ice cube in your hand, heat from the surroundings (including your hand) is transferred to the system (the ice), causing the ice to melt and your hand to become cold. We can describe this process by the following thermochemical equation:

$$heat + H_2O\,(s) \rightarrow H_2O\,(l) \tag{8.2.3}$$

When heat is transferred *to* a system *from* its surroundings, the process is endothermic. By convention, $q > 0$ for an endothermic reaction.

Heat is technically not a component in Chemical Reactions

Technically, it is poor form to have a ***heat*** term in the chemical reaction like in Equations 8.2.2 and 8.2.3 since is it not a true species in the reaction. However, this is a convenient approach to represent exothermic and endothermic behavior and is commonly used by chemists.

Internal Energy

Thermochemistry is a branch of chemical thermodynamics, the science that deals with the relationships between heat, work, and other forms of energy in the context of chemical and physical processes. As we concentrate on thermochemistry in this chapter, we need to consider some widely used concepts of thermodynamics.

Substances act as reservoirs of energy, meaning that energy can be added to them or removed from them. Energy is stored in a substance when the kinetic energy of its atoms or molecules is raised. The greater kinetic energy may be in the form of increased translations (travel or straight-line motions), vibrations, or rotations of the atoms or molecules. When thermal energy is lost, the intensities of these motions decrease and the kinetic energy falls. The total of all possible kinds of energy present in a substance is called the internal energy (U), sometimes symbolized as E.

As a system undergoes a change, its internal energy can change, and energy can be transferred from the system to the surroundings, or from the surroundings to the system. Energy is transferred into a system when it absorbs heat (q) from the surroundings or when the surroundings do work (w) on the system. For example, energy is transferred into room-temperature metal wire if it is immersed in hot water (the wire absorbs heat from the water), or if you rapidly bend the wire back and forth (the wire becomes warmer because of the work done on it). Both processes increase the internal energy of the wire, which is reflected in an increase in the wire's temperature. Conversely, energy is transferred out of a system when heat is lost from the system, or when the system does work on the surroundings.

The relationship between internal energy, heat, and work can be represented by the equation:

$$\Delta U = q + w \tag{8.2.4}$$

as shown in Figure 8.2.1. This is one version of the first law of thermodynamics, and it shows that the internal energy of a system changes through heat flow into or out of the system (positive q is heat flow in; negative q is heat flow out) or work done on or by the system. The work, w, is positive if it is done on the system and negative if it is done by the system.




Figure 8.2.1: The internal energy, U, of a system can be changed by heat flow and work. If heat flows into the system, q_{in}, or work is done on the system, w_{on}, its internal energy increases, $\Delta U > 0$. If heat flows out of the system, q_{out}, or work is done by the system, w_{by}, its internal energy decreases, $\Delta U < 0$.

A type of work called expansion work (or pressure-volume work) occurs when a system pushes back the surroundings against a restraining pressure, or when the surroundings compress the system. An example of this occurs during the operation of an internal combustion engine. The reaction of gasoline and oxygen is exothermic. Some of this energy is given off as heat, and some does work pushing the piston in the cylinder. The substances involved in the reaction are the system, and the engine and the rest of the universe are the surroundings. The system loses energy by both heating and doing work on the surroundings, and its internal energy decreases. (The engine is able to keep the car moving because this process is repeated many times per second while the engine is running.) We will consider how to determine the amount of work involved in a chemical or physical change in the chapter on thermodynamics.

As discussed, the relationship between internal energy, heat, and work can be represented as $\Delta U = q + w$. Internal energy is a type of quantity known as a state function (or state variable), whereas heat and work are not state functions. The value of a state function depends only on the state that a system is in, and not on how that state is reached. If a quantity is not a state function, then its value *does* depend on how the state is reached. An example of a state function is altitude or elevation. If you stand on the summit of Mt. Kilimanjaro, you are at an altitude of 5895 m, and it does not matter whether you hiked there or parachuted there. The distance you traveled to the top of Kilimanjaro, however, is not a state function. You could climb to the summit by a direct route or by a more

roundabout, circuitous path (Figure 8.2.2). The distances traveled would differ (distance is not a state function) but the elevation reached would be the same (altitude is a state function).




Figure 8.2.2: Paths X and Y represent two different routes to the summit of Mt. Kilimanjaro. Both have the same change in elevation (altitude or elevation on a mountain is a state function; it does not depend on path), but they have very different distances traveled (distance walked is not a state function; it depends on the path). (credit: modification of work by Paul Shaffner)

The First Law

The relationship between the energy change of a system and that of its surroundings is given by the **first law of thermodynamics**, which states that the energy of the universe is constant. We can express this law mathematically as follows:

$$U_{univ} = \Delta U_{sys} + \Delta U_{surr} = 0 \tag{8.2.5}$$

$$\Delta U_{sys} = -\Delta U_{surr} \tag{8.2.6}$$

where the subscripts univ, sys, and surr refer to the universe, the system, and the surroundings, respectively. Thus the change in energy of a system is identical in magnitude but opposite in sign to the change in energy of its surroundings.

> The tendency of all systems, chemical or otherwise, is to move toward the state with the lowest possible energy.

An important factor that determines the outcome of a chemical reaction is the tendency of all systems, chemical or otherwise, to move toward the lowest possible overall energy state. As a brick dropped from a rooftop falls, its potential energy is converted to kinetic energy; when it reaches ground level, it has achieved a state of lower potential energy. Anyone nearby will notice that energy is transferred to the surroundings as the noise of the impact reverberates and the dust rises when the brick hits the ground. Similarly, if a spark ignites a mixture of isooctane and oxygen in an internal combustion engine, carbon dioxide and water form spontaneously, while potential energy (in the form of the relative positions of atoms in the molecules) is released to the surroundings as heat and work. The internal energy content of the CO_2/H_2O product mixture is less than that of the isooctane/ O_2 reactant mixture. The two cases differ, however, in the form in which the energy is released to the surroundings. In the case of the falling brick, the energy is transferred as work done on whatever happens to be in the path of the brick; in the case of burning isooctane, the energy can be released as solely heat (if the reaction is carried out in an open container) or as a mixture of heat and work (if the reaction is carried out in the cylinder of an internal combustion engine). Because heat and work are the only two ways in which energy can be transferred between a system and its surroundings, any change in the internal energy of the system is the sum of the heat transferred (q) and the work done (w):

$$\Delta U_{sys} = q + w \tag{8.2.7}$$

Although q and w are not state functions on their own, their sum (ΔU_{sys}) is independent of the path taken and is therefore a state function. A major task for the designers of any machine that converts energy to work is to maximize the amount of work obtained and minimize the amount of energy released to the environment as heat. An example is the combustion of coal to produce electricity. Although the maximum amount of energy available from the process is fixed by the energy content of the reactants and the products, the fraction of that energy that can be used to perform useful work is not fixed.

Because we focus almost exclusively on the changes in the energy of a system, we will not use “sys” as a subscript unless we need to distinguish explicitly between a system and its surroundings.

> Although q and w are not state functions, their sum (ΔU_{sys}) is independent of the path taken and therefore is a state function.

Thus, because of the first law, we can determine ΔU for any process if we can measure both q and w. In the next section, we will learn how we can quantify heat and work.

Summary

In chemistry, the small part of the universe that we are studying is the **system**, and the rest of the universe is the **surroundings**. **Open systems** can exchange both matter and energy with their surroundings, **closed systems** can exchange energy but not matter with their surroundings, and **isolated systems** can exchange neither matter nor energy with their surroundings. A **state function** is a property of a system that depends on only its present **state**, not its history. A reaction or process in which heat is transferred from a system to its surroundings is **exothermic**. A reaction or process in which heat is transferred to a system from its surroundings is **endothermic**. The first law of thermodynamics states that the energy of the universe is constant. The change in the internal energy of a system is the sum of the heat transferred and the work done. The heat flow is equal to the change in the internal energy of the system plus the PV work done. When the volume of a system is constant, changes in its internal energy can be calculated by substituting the ideal gas law into the equation for ΔU.

Glossary

chemical thermodynamics
: area of science that deals with the relationships between heat, work, and all forms of energy associated with chemical and physical processes

Expansion work (pressure-volume work)
: work done as a system expands or contracts against external pressure

first law of thermodynamics
: internal energy of a system changes due to heat flow in or out of the system or work done on or by the system

Internal energy (U)
: total of all possible kinds of energy present in a substance or substances

State function
: property depending only on the state of a system, and not the path taken to reach that state

---

8.2: Internal Energy and First Law of Thermodynamics is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **5.2: The First Law of Thermodynamics** is licensed CC BY-NC-SA 3.0.
- **5.4: Enthalpy** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

8.3: Quantifying Heat and Work

Learning Objectives

- Distinguish the related properties of heat, thermal energy, and temperature
- Define and distinguish specific heat and heat capacity, and describe the physical implications of both
- Perform calculations involving heat, specific heat, and temperature change
- Perform Calculation involving work.

Thermal Energy, Temperature, and Heat

Thermal energy is kinetic energy associated with the random motion of atoms and molecules. Temperature is a quantitative measure of “hot” or “cold.” When the atoms and molecules in an object are moving or vibrating quickly, they have a higher average kinetic energy (KE), and we say that the object is “hot.” When the atoms and molecules are moving slowly, they have lower KE, and we say that the object is “cold” (Figure **8.3.1**). Assuming that no chemical reaction or phase change (such as melting or vaporizing) occurs, increasing the amount of thermal energy in a sample of matter will cause its temperature to increase. And, assuming that no chemical reaction or phase change (such as condensation or freezing) occurs, decreasing the amount of thermal energy in a sample of matter will cause its temperature to decrease.




Figure **8.3.1**: (a) The molecules in a sample of hot water move more rapidly than (b) those in a sample of cold water.

Most substances expand as their temperature increases and contract as their temperature decreases. This property can be used to measure temperature changes, as shown in Figure **8.3.2**. The operation of many thermometers depends on the expansion and contraction of substances in response to temperature changes.




Figure **8.3.2**: (a) In an alcohol or mercury thermometer, the liquid (dyed red for visibility) expands when heated and contracts when cooled, much more so than the glass tube that contains the liquid. (b) In a bimetallic thermometer, two different metals (such as brass and steel) form a two-layered strip. When heated or cooled, one of the metals (brass) expands or contracts more than the other metal (steel), causing the strip to coil or uncoil. Both types of thermometers have a calibrated scale that indicates the temperature. (credit a: modification of work by “dwstucke”/Flickr). (c) The demonstration allows one to view the effects of heating and cooling a coiled bimetallic strip.A bimetallic coil from a thermometer reacts to the heat from a lighter, by uncoiling and then coiling back up when the lighter is removed. Animation used with permission from Hustvedt (via Wikipedia).

Heat (q) is the transfer of thermal energy between two bodies at different temperatures. Heat flow (a redundant term, but one commonly used) increases the thermal energy of one body and decreases the thermal energy of the other. Suppose we initially have a high temperature (and high thermal energy) substance (H) and a low temperature (and low thermal energy) substance (L). The atoms and molecules in H have a higher average KE than those in L. If we place substance H in contact with substance L, the thermal energy will flow spontaneously from substance H to substance L. The temperature of substance H will decrease, as will the

average KE of its molecules; the temperature of substance L will increase, along with the average KE of its molecules. Heat flow will continue until the two substances are at the same temperature (Figure **8.3.3**).




Figure **8.3.3**: (a) Substances H and L are initially at different temperatures, and their atoms have different average kinetic energies. (b) When they are put into contact with each other, collisions between the molecules result in the transfer of kinetic (thermal) energy from the hotter to the cooler matter. (c) The two objects reach "thermal equilibrium" when both substances are at the same temperature, and their molecules have the same average kinetic energy.

Matter undergoing chemical reactions and physical changes can release or absorb heat. A change that releases heat is called an exothermic process. For example, the combustion reaction that occurs when using an oxyacetylene torch is an exothermic process—this process also releases energy in the form of light as evidenced by the torch's flame (Figure **8.3.4*a***). A reaction or change that absorbs heat is an endothermic process. The cold pack shown in (Figure **8.3.4*b***)used to treat muscle strains provides an example of an endothermic process. When the substances in the cold pack (water and a salt like ammonium nitrate) are brought together, the resulting process absorbs heat, leading to the sensation of cold.



Figure **8.3.4**: (a) An oxyacetylene torch produces heat by the combustion of acetylene in oxygen. The energy released by this exothermic reaction heats and then melts the metal being cut. The sparks are tiny bits of the molten metal flying away. (b) A cold pack uses an endothermic process to create the sensation of cold. (credit a: modification of work by "Skatebiker"/Wikimedia commons).

Measuring Heat and Heat Capacity

Historically, energy was measured in units of calories (cal). A calorie is the amount of energy required to raise one gram of water by 1 degree C (1 kelvin). However, this quantity depends on the atmospheric pressure and the starting temperature of the water. The ease of measurement of energy changes in calories has meant that the calorie is still frequently used. The Calorie (with a capital C), or large calorie, commonly used in quantifying food energy content, is a kilocalorie. The SI unit of heat, work, and energy is the joule. A joule (J) is defined as the amount of energy used when a force of 1 newton moves an object 1 meter. It is named in honor of the English physicist James Prescott Joule. One joule is equivalent to 1 kg m^2/s^2, which is also called 1 newton–meter. A kilojoule (kJ) is 1000 joules. To standardize its definition, 1 calorie has been set to equal 4.184 joules.

We now introduce two concepts useful in describing heat flow and temperature change. The heat capacity (C) of a body of matter is the quantity of heat (q) it absorbs or releases when it experiences a temperature change (ΔT) of 1 degree Celsius (or equivalently, 1 kelvin)

$$C = \frac{q}{\Delta T} \tag{8.3.1}$$

Heat capacity is determined by both the type and amount of substance that absorbs or releases heat. It is therefore an extensive property—its value is proportional to the amount of the substance.

For example, consider the heat capacities of two cast iron frying pans. The heat capacity of the large pan is five times greater than that of the small pan because, although both are made of the same material, the mass of the large pan is five times greater than the mass of the small pan. More mass means more atoms are present in the larger pan, so it takes more energy to make all of those atoms vibrate faster. The heat capacity of the small cast iron frying pan is found by observing that it takes 18,150 J of energy to raise the temperature of the pan by 50.0 °C

$$C_{\text{small pan}} = \frac{18,140\ \text{J}}{50.0\ \text{°C}} = 363\ \text{J/°C} \tag{8.3.2}$$

The larger cast iron frying pan, while made of the same substance, requires 90,700 J of energy to raise its temperature by 50.0 °C. The larger pan has a (proportionally) larger heat capacity because the larger amount of material requires a (proportionally) larger amount of energy to yield the same temperature change:

$$C_{\text{large pan}} = \frac{90,700\ \text{J}}{50.0\ \text{°C}} = 1814\ \text{J/°C} \tag{8.3.3}$$

The specific heat capacity (c) of a substance, commonly called its "specific heat," is the quantity of heat required to raise the temperature of 1 gram of a substance by 1 degree Celsius (or 1 kelvin):

$$c = \frac{q}{\text{m}\Delta\text{T}} \tag{8.3.4}$$

Specific heat capacity depends only on the kind of substance absorbing or releasing heat. It is an intensive property—the type, but not the amount, of the substance is all that matters. For example, the small cast iron frying pan has a mass of 808 g. The specific heat of iron (the material used to make the pan) is therefore:

$$c_{\text{iron}} = \frac{18,140\ \text{J}}{(808\ \text{g})(50.0\ \text{°C})} = 0.449\ \text{J/g °C} \tag{8.3.5}$$

The large frying pan has a mass of 4040 g. Using the data for this pan, we can also calculate the specific heat of iron:

$$c_{\text{iron}} = \frac{90,700\ \text{J}}{(4,040\ \text{g})(50.0\ \text{°C})} = 0.449\ \text{J/g °C} \tag{8.3.6}$$

Although the large pan is more massive than the small pan, since both are made of the same material, they both yield the same value for specific heat (for the material of construction, iron). Note that specific heat is measured in units of energy per temperature per mass and is an intensive property, being derived from a ratio of two extensive properties (heat and mass). The molar heat capacity, also an intensive property, is the heat capacity per mole of a particular substance and has units of J/mol °C (Figure **8.3.5**).



Figure **8.3.5**: Due to its larger mass, a large frying pan has a larger heat capacity than a small frying pan. Because they are made of the same material, both frying pans have the same specific heat. (credit: Mark Blaser).

Liquid water has a relatively high specific heat (about 4.2 J/g °C); most metals have much lower specific heats (usually less than 1 J/g °C). The specific heat of a substance varies somewhat with temperature. However, this variation is usually small enough that we will treat specific heat as constant over the range of temperatures that will be considered in this chapter. Specific heats of some common substances are listed in Table **8.3.1**.

Table **8.3.1**: Specific Heats of Common Substances at 25 °C and 1 bar

Substance	Symbol (state)	Specific Heat (J/g °C)
helium	$He(g)$	5.193
water	$H_2O(l)$	4.184
ethanol	$C_2H_6O(l)$	2.376
ice	$H_2O(s)$	2.093 (at −10 °C)
water vapor	$H_2O(g)$	1.864
nitrogen	$N_2(g)$	1.040
air		1.007
oxygen	$O_2(g)$	0.918
aluminum	$Al(s)$	0.897
carbon dioxide	$CO_2(g)$	0.853
argon	$Ar(g)$	0.522
iron	$Fe(s)$	0.449
copper	$Cu(s)$	0.385
lead	$Pb(s)$	0.130
gold	$Au(s)$	0.129
silicon	$Si(s)$	0.712

If we know the mass of a substance and its specific heat, we can determine the amount of heat, q, entering or leaving the substance by measuring the temperature change before and after the heat is gained or lost:

$$q = (\text{specific heat}) \times (\text{mass of substance}) \times (\text{temperature change})$$
$$q = c \times m \times \Delta T$$
$$= c \times m \times (T_{\text{final}} - T_{\text{initial}})$$

In this equation, c is the specific heat of the substance, m is its mass, and ΔT (which is read “delta T”) is the temperature change, $T_{\text{final}} - T_{\text{initial}}$. If a substance gains thermal energy, its temperature increases, its final temperature is higher than its initial temperature, $T_{\text{final}} - T_{\text{initial}}$ has a positive value, and the value of q is positive. If a substance loses thermal energy, its temperature decreases, the final temperature is lower than the initial temperature, $T_{\text{final}} - T_{\text{initial}}$ has a negative value, and the value of q is negative.

Example 8.3.1: Measuring Heat

A flask containing 8.0×10^2 g of water is heated, and the temperature of the water increases from 21 °C to 85 °C. How much heat did the water absorb?

Solution

To answer this question, consider these factors:

- the specific heat of the substance being heated (in this case, water)
- the amount of substance being heated (in this case, 800 g)
- the magnitude of the temperature change (in this case, from 21 °C to 85 °C).

The specific heat of water is 4.184 J/g °C, so to heat 1 g of water by 1 °C requires 4.184 J. We note that since 4.184 J is required to heat 1 g of water by 1 °C, we will need 800 times as much to heat 800 g of water by 1 °C. Finally, we observe that

since 4.184 J are required to heat 1 g of water by 1 °C, we will need 64 times as much to heat it by 64 °C (that is, from 21 °C to 85 °C).

This can be summarized using the equation:

$$\begin{aligned} q &= c \times m \times \Delta T \\ &= c \times m \times (T_{\text{final}} - T_{\text{initial}}) \\ &= (4.184\ \text{J/g°C}) \times (800\ \cancel{\text{g}}) \times (85 - 21)\text{°C} \\ &= (4.184\ \text{J/g°}\cancel{\text{C}}) \times (800\ \cancel{\text{g}}) \times (64)\text{°}\cancel{\text{C}} \\ &= 210,000\ \text{J} (= 210\ \text{kJ}) \end{aligned}$$

Because the temperature increased, the water absorbed heat and q is positive.

? Exercise 8.3.1

How much heat, in joules, must be added to a 5.00×10^2 g iron skillet to increase its temperature from 25 °C to 250 °C? The specific heat of iron is 0.451 J/g °C.

Answer

5.05×10^4 J

Note that the relationship between heat, specific heat, mass, and temperature change can be used to determine any of these quantities (not just heat) if the other three are known or can be deduced.

✓ Example 8.3.2: Determining Other Quantities

A piece of unknown metal weighs 348 g. When the metal piece absorbs 6.64 kJ of heat, its temperature increases from 22.4 °C to 43.6 °C. Determine the specific heat of this metal (which might provide a clue to its identity).

Solution

Since mass, heat, and temperature change are known for this metal, we can determine its specific heat using the relationship:

$$\begin{aligned} q &= c \times m \times \Delta T \\ &= c \times m \times (T_{\text{final}} - T_{\text{initial}}) \end{aligned}$$

Substituting the known values:

$$6,640\ \text{J} = c \times (348\ \text{g}) \times (43.6 - 22.4)\ \text{°C}$$

Solving:

$$c = \frac{6,640\ \text{J}}{(348\ \text{g}) \times (21.2\text{°C})} = 0.900\ \text{J/g °C}$$

Comparing this value with the values in Table 8.3.1, this value matches the specific heat of aluminum, which suggests that the unknown metal may be aluminum.

? Exercise 8.3.2

A piece of unknown metal weighs 217 g. When the metal piece absorbs 1.43 kJ of heat, its temperature increases from 24.5 °C to 39.1 °C. Determine the specific heat of this metal, and predict its identity.

Answer

$c = 0.45$ J/g °C; the metal is likely to be iron from checking Table 8.3.1.

Heat exchange between a hot and a cold object

If we place the metal in the water, heat will flow from M to W. The temperature of M will decrease, and the temperature of W will increase, until the two substances have the same temperature—that is, when they reach **thermal equilibrium** (Figure 8.3.6). If this occurs in a calorimeter, ideally all of this heat transfer occurs between the two substances assuming no heat is lost to the surroundings. Under these ideal circumstances, the net heat change is zero:

$$q_{\text{substance M}} + q_{\text{substance W}} = 0 \tag{8.3.7}$$

This relationship can be rearranged to show that the heat gained by substance M is equal to the heat lost by substance W:

$$q_{\text{substance M}} = -q_{\text{substance W}} \tag{8.3.8}$$

The magnitude of the heat (change) is therefore the same for both substances, and the negative sign merely shows that $q_{substance\ M}$ and $q_{substance\ W}$ are opposite in direction of heat flow (gain or loss) but does not indicate the arithmetic sign of either q value (that is determined by whether the matter in question gains or loses heat, per definition). In the specific situation described, $q_{substance\ M}$ is a negative value and $q_{substance\ W}$ is positive, since heat is transferred from M to W.




Figure 8.3.6: In a simple calorimetry process, (a) heat, q, is transferred from the hot metal, M, to the cool water, W, until (b) both are at the same temperature.

Example 8.3.1: Heat Transfer between Substances at Different Temperatures

A hot 360-g piece of rebar (a steel rod used for reinforcing concrete) is dropped into 425 mL of water at 24.0 °C. The final temperature of the water is measured as 42.7 °C. Calculate the initial temperature of the piece of rebar. Assume the specific heat of steel is approximately the same as that for iron (Table T4), and that all heat transfer occurs between the rebar and the water (there is no heat exchange with the surroundings).

Solution

The temperature of the water increases from 24.0 °C to 42.7 °C, so the water absorbs heat. That heat came from the piece of rebar, which initially was at a higher temperature. Assuming that all heat transfer was between the rebar and the water, with no heat "lost" to the surroundings, then heat given off by rebar = − heat taken in by water, or:

$$q_{\text{rebar}} = -q_{\text{water}}$$

Since we know how heat is related to other measurable quantities, we have:

$$(c \times m \times \Delta T)_{\text{rebar}} = -(c \times m \times \Delta T)_{\text{water}}$$

Letting f = final and i = initial, in expanded form, this becomes:

$$c_{\text{rebar}} \times m_{\text{rebar}} \times (T_{\text{f,rebar}} - T_{\text{i,rebar}}) = -c_{\text{water}} \times m_{\text{water}} \times (T_{\text{f,water}} - T_{\text{i,water}})$$

The density of water is 1.0 g/mL, so 425 mL of water = 425 g. Noting that the final temperature of both the rebar and water is 42.7 °C, substituting known values yields:

$$(0.449\ \text{J/g °C})(360\text{g})(42.7\text{°C} - T_{\text{i,rebar}}) = -(4.184\ \text{J/g °C})(425\ \text{g})(42.7\text{°C} - 24.0\text{°C})$$

$$T_{\text{i,rebar}} = \frac{(4.184\ \text{J/g °C})(425\ \text{g})(42.7\text{°C} - 24.0\text{°C})}{(0.449\ \text{J/g °C})(360\ \text{g})} + 42.7\text{°C}$$

Solving this gives Ti,rebar= 248 °C, so the initial temperature of the rebar was 248 °C.

? Exercise 8.3.1*A*

A 248-g piece of copper is dropped into 390 mL of water at 22.6 °C. The final temperature of the water was measured as 39.9 °C. Calculate the initial temperature of the piece of copper. Assume that all heat transfer occurs between the copper and the water.

Answer

The initial temperature of the copper was 335.6 °C.

? Exercise 8.3.1*B*

A 248-g piece of copper initially at 314 °C is dropped into 390 mL of water initially at 22.6 °C. Assuming that all heat transfer occurs between the copper and the water, calculate the final temperature.

Answer

The final temperature (reached by both copper and water) is 38.7 °C.

This method can also be used to determine other quantities, such as the specific heat of an unknown metal.

✔ Example 8.3.2: Identifying a Metal by Measuring Specific Heat

A 59.7 g piece of metal that had been submerged in boiling water was quickly transferred into 60.0 mL of water initially at 22.0 °C. The final temperature is 28.5 °C. Use these data to determine the specific heat of the metal. Use this result to identify the metal.

Solution

Assuming perfect heat transfer, heat given off by metal = −heat taken in by water, or:

$$q_{\text{metal}} = -q_{\text{water}}$$

In expanded form, this is:

$$c_{\text{metal}} \times m_{\text{metal}} \times (T_{\text{f,metal}} - T_{\text{i,metal}}) = -c_{\text{water}} \times m_{\text{water}} \times (T_{\text{f,water}} - T_{\text{i,water}})$$

Noting that since the metal was submerged in boiling water, its initial temperature was 100.0 °C; and that for water, 60.0 mL = 60.0 g; we have:

$$(c_{\text{metal}})(59.7\ \text{g})(28.5\text{°C} - 100.0\text{°C}) = -(4.18\ \text{J/g °C})(60.0\ \text{g})(28.5\text{°C} - 22.0\text{°C})$$

Solving this:

$$c_{\text{metal}} = \frac{-(4.184\ \text{J/g °C})(60.0\ \text{g})(6.5\text{°C})}{(59.7\ \text{g})(-71.5\text{°C})} = 0.38\ \text{J/g °C}$$

Comparing this with values in Table T4, our experimental specific heat is closest to the value for copper (0.39 J/g °C), so we identify the metal as copper.

Exercise 8.3.2

A 92.9-g piece of a silver/gray metal is heated to 178.0 °C, and then quickly transferred into 75.0 mL of water initially at 24.0 °C. After 5 minutes, both the metal and the water have reached the same temperature: 29.7 °C. Determine the specific heat and the identity of the metal. (Note: You should find that the specific heat is close to that of two different metals. Explain how you can confidently determine the identity of the metal).

Answer

$c_{metal} = 0.13\ J/g\,°C$

This specific heat is close to that of either gold or lead. It would be difficult to determine which metal this was based solely on the numerical values. However, the observation that the metal is silver/gray in addition to the value for the specific heat indicates that the metal is lead.



Conservation of Energy: The Movement of Heat between Substances: https://youtu.be/pGEYy-pNHBg

Mechanical Work

One definition of energy is the capacity to do work. There are many kinds of work, including mechanical work, electrical work, and work against a gravitational or a magnetic field. Here we will consider only mechanical work and focus on the work done during changes in the pressure or the volume of a gas.

The easiest form of work to visualize is mechanical work (Figure **8.3.7**), which is the energy required to move an object a distance d when *opposed* by a force F, such as gravity:

$$w = F\,d \tag{8.3.9}$$

with w is work, F is opposing force, and d is distance.




Figure 8.3.7: One form of energy is mechanical work, the energy required to move an object of mass m through distance d when opposed by a force F, i.e., as gravity.

Because the force (F) that opposes the action is equal to the mass (m) of the object times its acceleration (a), Equation 8.3.9 can be rewritten to:

$$w = m\,a\,d \tag{8.3.10}$$

with w is work, m is mass, a is acceleration, and d is distance.

Recall from that weight is a force caused by the gravitational attraction between two masses, such as you and Earth. Hence for works against gravity (on Earth), a can be set to $g = 9.8\ m/s^2$). Consider the mechanical work required for you to travel from the first floor of a building to the second. Whether you take an elevator or an escalator, trudge upstairs, or leap up the stairs two at a time, energy is expended to overcome the opposing force of gravity. The amount of work done (w) and thus the energy required depends on three things:

1. the height of the second floor (the distance d);
2. your mass, which must be raised that distance against the downward acceleration due to gravity; and
3. your path.

Pressure-Volume (PV) Work

To describe this pressure–volume work (PV work), we will use such imaginary oddities as frictionless pistons, which involve no component of resistance, and ideal gases, which have no attractive or repulsive interactions. Imagine, for example, an ideal gas, confined by a frictionless piston, with internal pressure P_{int} and initial volume V_i (Figure 8.3.8). If $P_{ext} = P_{int}$, the system is at equilibrium; the piston does not move, and no work is done. If the external pressure on the piston (P_{ext}) is less than P_{int}, however, then the ideal gas inside the piston will expand, forcing the piston to perform work on its surroundings; that is, the final volume (V_f) will be greater than V_i. If $P_{ext} > P_{int}$, then the gas will be compressed, and the surroundings will perform work on the system.




Figure 8.3.8: PV Work demonstrated with a frictionless piston. (a) if the external pressure is less than P_{int}, the ideal gas inside the piston will expand, forcing the piston to perform work on its surroundings. The final volume (V_f) will be greater than V_i. (b) Alternatively, if the external pressure is greater than P_{int}, the gas will be compressed, and the surroundings will perform work on the system.

If the piston has cross-sectional area A, the external pressure exerted by the piston is, by definition, the force per unit area:

$$P_{ext} = \frac{F}{A} \tag{8.3.11}$$

The volume of any three-dimensional object with parallel sides (such as a cylinder) is the cross-sectional area times the height ($V = Ah$). Rearranging Equation 8.3.11 to give

$$F = P_{ext}A \tag{8.3.12}$$

and defining the distance the piston moves (d) as Δh, we can calculate the magnitude of the work performed by the piston by substituting into Equation 8.3.9:

$$w = Fd = P_{ext}A\Delta h \tag{8.3.13}$$

The change in the volume of the cylinder (ΔV) as the piston moves a distance d is $\Delta V = A\Delta h$, as shown in Figure 8.3.9.




Figure 8.3.9: Work Performed with a change in volume. The change in the volume (ΔV) of the cylinder housing a piston is $\Delta V = A\Delta h$ as the piston moves. The work performed by the surroundings on the system as the piston moves inward is given by

Equation 8.3.14.

The PV work performed is thus

$$w = P_{ext}\Delta V \tag{8.3.14}$$

The units of work obtained using this definition are correct for energy: pressure is force per unit area (newton/m^2) and volume has units of cubic meters, so

$$w = \left(\frac{F}{A}\right)_{ext}(\Delta V) = \frac{\text{newton}}{\text{m}^2} \times \text{m}^3 = \text{newton} \cdot \text{m} = \text{joule} \tag{8.3.15}$$

If we use atmospheres for P and liters for V, we obtain units of L·atm for work. These units correspond to units of energy, as shown in the different values of the ideal gas constant R:

$$R = \frac{0.08206\ \text{L} \cdot \text{atm}}{\text{mol} \cdot \text{K}} = \frac{8.314\ \text{J}}{\text{mol} \cdot \text{K}} \tag{8.3.16}$$

Thus 0.08206 L·atm = 8.314 J and 1 L·atm = 101.3 J.

? Example ? 8.3.3

a. How much work is done by a gas that expands from 2 liters to 5 liters against an external pressure of 750 mmHg?
b. How much work is done by 0.54 moles of a gas that has an initial volume of 8 liters and expands under the following conditions: 30 ^{o}C and 1.3 atm?
c. How much work is done by a gas (P=1.7 atm, V=1.56 L) that expands against an external pressure of 1.8 atm?

Solution a

$$w = -P\Delta V \tag{8.3.17}$$

$$\Delta V = V_{final} - V_{Initial} = 5\,L - 2\,L = 3L \tag{8.3.18}$$

Convert 750 mmHg to atm:

$$750 mmHg * 1/760(atm/mmHg) = 0.9868 atm. \tag{8.3.19}$$

$$W = -p\Delta V = -(.9868\,atm)(3\,L) = -2.96\,L\,atm. \tag{8.3.20}$$

Solution b

First we must find the final volume using the ideal gas law:

$$pV = nRT \tag{8.3.21}$$

or

$$V = \frac{nRT}{P} = \frac{[(0.54\,moles)(0.082057(L\,atm)/(mol\,K))(303\,K)]}{1.3\,atm} = 10.33\,L \tag{8.3.22}$$

$$\Delta V = V_{final} - V_{initial} = 10.3\,L - 8\,L = 2.3\,L \tag{8.3.23}$$

$$w = -p\Delta V = -(1.3\,atm)(2.3\,L) = -3\,L\,atm. \tag{8.3.24}$$

Solution c

$$w = -p * \Delta V\backslash) = -(1.8\,atm)\,\Delta V. \tag{8.3.25}$$

Given p_1, V_1, and p_2, find V_2: $p_1V_1 = p_2V_2$ (at constant T and n)

$V_2 = (V_1 * P_1)/P_2$ = (1.56 L * 1.7 atm) / 1.8 atm = 1.47 L

Now,

$$\Delta V = V_2 - V_1 = 1.47\,L - 1.56\,L = -0.09 \tag{8.3.26}$$

$$w = -(1.8atm) * (-0.09L) = 0.162Latm. \tag{8.3.27}$$

Whether work is defined as having a positive sign or a negative sign is a matter of convention. Heat flow is defined from a system to its surroundings as negative; using that same sign convention, we define work done by a system on its surroundings as having a negative sign because it results in a transfer of energy from a system to its surroundings. This is an arbitrary convention and one that is not universally used. Some engineering disciplines are more interested in the work done on the surroundings than in the work done by the system and therefore use the opposite convention. Because ΔV > 0 for an expansion, Equation 8.3.14 must be written with a negative sign to describe PV work done by the system as negative:

$$w = -P_{ext}\Delta V \tag{8.3.28}$$

The work done by a gas expanding against an external pressure is therefore negative, corresponding to work done by a system on its surroundings. Conversely, when a gas is compressed by an external pressure, ΔV < 0 and the work is positive because work is being done on a system by its surroundings.

A Matter of Convention

- Heat flow is defined from the system to its surroundings as **negative**
- Work is defined as by the system on its surroundings as **negative**

Suppose, for example, that the system under study is a mass of steam heated by the combustion of several hundred pounds of coal and enclosed within a cylinder housing a piston attached to the crankshaft of a large steam engine. The gas is not ideal, and the cylinder is not frictionless. Nonetheless, as steam enters the engine chamber and the expanding gas pushes against the piston, the piston moves, so useful work is performed. In fact, PV work launched the Industrial Revolution of the 19th century and powers the internal combustion engine on which most of us still rely for transportation.




Figure 8.3.10: Work Is Not a State Function. In pathway A, the volume of a gas is initially increased while its pressure stays constant (step 1). Its pressure is then decreased while the volume remains constant (step 2). Pathway B reverses these steps. Although (V_1, P_1) and (V_2, P_2) are identical in both cases, the amount of work done (shaded area) depends on the pathway taken.

In contrast to internal energy, work is not a state function. We can see this by examining Figure 8.3.10, in which two different, two-step pathways take a gaseous system from an initial state to a final state with corresponding changes in temperature. In pathway A, the volume of a gas is initially increased while its pressure stays constant (step 1); then its pressure is decreased while the volume remains constant (step 2). In pathway B, the order of the steps is reversed. The temperatures, pressures, and volumes of the initial and final states are identical in both cases, but the amount of work done, indicated by the shaded areas in the figure, is substantially different. As we can see, the amount of work done depends on the pathway taken from (V_1, P_1) to (V_2, P_2), which means that work is **not** a state function.

> *Internal energy is a state function, whereas work is not.*

Example 8.3.4

A small high-performance internal combustion engine has six cylinders with a total nominal displacement (volume) of 2.40 L and a 10:1 compression ratio (meaning that the volume of each cylinder decreases by a factor of 10 when the piston compresses the air–gas mixture inside the cylinder prior to ignition). How much work in joules is done when a gas in one cylinder of the engine expands at constant temperature against an opposing pressure of 40.0 atm during the engine cycle? Assume that the gas is ideal, the piston is frictionless, and no energy is lost as heat.

Given: final volume, compression ratio, and external pressure

Asked for: work done

Strategy:

Calculate the final volume of gas in a single cylinder. Then compute the initial volume of gas in a single cylinder from the compression ratio. Use Equation 8.3.28 to calculate the work done in liter-atmospheres. Convert from liter-atmospheres to joules.

Solution:

A To calculate the work done, we need to know the initial and final volumes. The final volume is the volume of one of the six cylinders with the piston all the way down: V_f = 2.40 L/6 = 0.400 L. With a 10:1 compression ratio, the volume of the same cylinder with the piston all the way up is V_i = 0.400 L/10 = 0.0400 L. Work is done by the system on its surroundings, so work is negative.

$$\begin{aligned} w &= -P_{ext}\Delta V \\ &= -(40.0\,atm)(0.400\,L - 0.0400\,L) \\ &= -14.4\,L \cdot atm \end{aligned}$$

Converting from liter-atmospheres to joules,

$$\begin{aligned} w &= -(14.4\ \text{L} \cdot \text{atm})[101.3\ \text{J}/(\text{L} \cdot \text{atm})] \\ &= -1.46 \times 10^3\ \text{J} \end{aligned}$$

In the following exercise, you will see that the concept of work is not confined to engines and pistons. It is found in other applications as well.

Exercise 8.3.3

Breathing requires work, even if you are unaware of it. The lung volume of a 70 kg man at rest changed from 2200 mL to 2700 mL when he inhaled, while his lungs maintained a pressure of approximately 1.0 atm. How much work in liter-atmospheres and joules was required to take a single breath? During exercise, his lung volume changed from 2200 mL to 5200 mL on each in-breath. How much additional work in joules did he require to take a breath while exercising?

Answer

−0.500 L·atm, or −50.7 J; −304 J; if he takes a breath every three seconds, this corresponds to 1.4 Calories per minute (1.4 kcal).

Work and Chemical Reactions

We have stated that the change in energy (ΔU) is equal to the sum of the heat produced and the work performed. Work done by an expanding gas is called *pressure-volume work*, (or just *PV work)*. Consider, for example, a reaction that produces a gas, such as dissolving a piece of copper in concentrated nitric acid. The chemical equation for this reaction is as follows:

$$Cu_{(s)} + 4HNO_{3(aq)} \rightarrow Cu(NO_3)_{2(aq)} + 2H_2O_{(l)} + 2NO_{2(g)} \tag{8.3.29}$$

If the reaction is carried out in a closed system that is maintained at constant pressure by a movable piston, the piston will rise as nitrogen dioxide gas is formed (Figure 8.3.11). The system is performing work by lifting the piston against the downward force exerted by the atmosphere (i.e., *atmospheric pressure*). We find the amount of *PV* work done by multiplying the external pressure *P* by the change in volume caused by movement of the piston (ΔV). At a constant external pressure (here, atmospheric pressure)

$$w = -P\Delta V \tag{8.3.30}$$

The negative sign associated with PV work done indicates that the system loses energy. If the volume increases at constant pressure ($\Delta V > 0$), the work done by the system is negative, indicating that a system has lost energy by performing work on its surroundings. Conversely, if the volume decreases ($\Delta V < 0$), the work done by the system is positive, which means that the surroundings have performed work on the system, thereby increasing its energy.




Figure 8.3.11: An Example of Work Performed by a Reaction Carried Out at Constant Pressure. (a) Initially, the system (a copper penny and concentrated nitric acid) is at atmospheric pressure. (b) When the penny is added to the nitric acid, the volume of NO_2 gas that is formed causes the piston to move upward to maintain the system at atmospheric pressure. In doing so, the system is performing work on its surroundings.

The symbol U represents the internal energy of a system, which is the sum of the kinetic energy and potential energy of all its components. It is the change in internal energy that produces heat plus work. To measure the energy changes that occur in chemical reactions, chemists usually use a related thermodynamic quantity called enthalpy (H) (from the Greek *enthalpein*, meaning "to warm"). The enthalpy of a system is defined as the sum of its internal energy U plus the product of its pressure P and volume V:

$$H = U + PV \tag{8.3.31}$$

Because internal energy, pressure, and volume are all state functions, enthalpy is also a state function.

If a chemical change occurs at constant pressure (i.e., for a given *P*, $\Delta P = 0$), the change in enthalpy (ΔH) is

$$\Delta H = \Delta(U + PV) = \Delta U + \Delta PV = \Delta U + P\Delta V \tag{8.3.32}$$

Substituting $q + w$ for ΔU (Equation 8.3.32) and $-w$ for $P\Delta V$ (Equation 8.3.30), we obtain

$$\Delta H = \Delta U + P\Delta V = q_p + w - w = q_p \tag{8.3.33}$$

The subscript p is used here to emphasize that this equation is true only for a process that occurs at constant pressure. From Equation 8.3.33 we see that at constant pressure the change in enthalpy, ΔH of the system, defined as $H_{final} - H_{initial}$, is equal to the heat gained or lost.

$$\Delta H = H_{final} - H_{initial} = q_p \tag{8.3.34}$$

Just as with ΔU, because enthalpy is a state function, the magnitude of ΔH depends on only the initial and final states of the system, not on the path taken. Most important, the enthalpy change is the same even if the process does *not* occur at constant pressure.

> *To find ΔH for a reaction, measure q_p under constant pressure.*

Summary

Energy is the capacity to do work (applying a force to move matter). Kinetic energy (KE) is the energy of motion; potential energy is energy due to relative position, composition, or condition. When energy is converted from one form into another, energy is

neither created nor destroyed (law of conservation of energy or first law of thermodynamics). Matter has thermal energy due to the KE of its molecules and temperature that corresponds to the average KE of its molecules. Heat is energy that is transferred between objects at different temperatures; it flows from a high to a low temperature. Chemical and physical processes can absorb heat (endothermic) or release heat (exothermic). The SI unit of energy, heat, and work is the joule (J). Specific heat and heat capacity are measures of the energy needed to change the temperature of a substance or object. The amount of heat absorbed or released by a substance depends directly on the type of substance, its mass, and the temperature change it undergoes.

Key Equations

- $q = c \times m \times \Delta T = c \times m \times (T_{\text{final}} - T_{\text{initial}})$

Glossary

calorie (cal)
unit of heat or other energy; the amount of energy required to raise 1 gram of water by 1 degree Celsius; 1 cal is defined as 4.184 J

endothermic process
chemical reaction or physical change that absorbs heat

energy
capacity to supply heat or do work

exothermic process
chemical reaction or physical change that releases heat

heat (*q*)
transfer of thermal energy between two bodies

heat capacity (*C*)
extensive property of a body of matter that represents the quantity of heat required to increase its temperature by 1 degree Celsius (or 1 kelvin)

joule (J)
SI unit of energy; 1 joule is the kinetic energy of an object with a mass of 2 kilograms moving with a velocity of 1 meter per second, 1 J = 1 kg m^2/s and 4.184 J = 1 cal

kinetic energy
energy of a moving body, in joules, equal to $\frac{1}{2}mv^2$ (where m = mass and v = velocity)

potential energy
energy of a particle or system of particles derived from relative position, composition, or condition

specific heat capacity (*c*)
intensive property of a substance that represents the quantity of heat required to raise the temperature of 1 gram of the substance by 1 degree Celsius (or 1 kelvin)

temperature
intensive property of matter that is a quantitative measure of “hotness” and “coldness”

thermal energy
kinetic energy associated with the random motion of atoms and molecules

thermochemistry

study of measuring the amount of heat absorbed or released during a chemical reaction or a physical change

Outside Links

Gasparro, Frances P. "Remembering the sign conventions for q and w in deltaU = q - w." J. Chem. Educ. 1976: 53, 389. Koubek, E. "PV work demonstration (TD)." J. Chem. Educ. 1980: 57, 374. '

Contributors and Attributions

work (*w*)

energy transfer due to changes in external, macroscopic variables such as pressure and volume; or causing matter to move against an opposing force

Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

8.3: Quantifying Heat and Work is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **5.2: Energy Basics** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **5.3: Calorimetry** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

8.4: Constant Volume Calorimeter

For reactions in which one or more of the reactants is a gas, such as a combustion reaction, we use constant-volume calorimeter, such as bomb calorimeter shown schematically in Figure **8.4.1**), to measure the internal energy change of the system. The reactant is placed in a steel cup inside a steel vessel with a fixed volume (the "bomb"). The bomb is then sealed, filled with excess oxygen gas, and placed inside an insulated container that holds a known amount of water. Because combustion reactions are exothermic, the temperature of the bath and the calorimeter increases during combustion. If the heat capacity of the bomb and the mass of water are known, the heat released can be calculated.




Figure **8.4.1**: A Bomb Calorimeter. After the temperature of the water in the insulated container has reached a constant value, the combustion reaction is initiated by passing an electric current through a wire embedded in the sample. Because this calorimeter operates at constant volume, the heat released is not precisely the same as the enthalpy change for the reaction.


Because the volume of the system (the inside of the bomb) is fixed, the combustion reaction occurs under conditions in which the volume, but not the pressure, is constant. Since there is no change on the volume, the work done by the system is zero. Therefore, the heat released by a reaction carried out at constant volume is identical to the change in *internal energy* (ΔE). The relationship between the measured temperature change and ΔE_{comb} is given in Equation 8.4.1, where C_{bomb} is the total heat capacity of the steel bomb and the water surrounding it:

$$\Delta E_{comb} = q_{comb} = -q_{calorimater} = -C_{bomb}\Delta T \tag{8.4.1}$$

To measure the heat capacity of the calorimeter, we first burn a carefully weighed mass of a standard compound whose enthalpy of combustion is accurately known. Benzoic acid ($C_6H_5CO_2H$) is often used for this purpose because it is a crystalline solid that can be obtained in high purity. The combustion of benzoic acid in a bomb calorimeter releases 26.38 kJ of heat per gram (i.e., its ΔE_{comb} = −26.38 kJ/g). This value and the measured increase in temperature of the calorimeter can be used in Equation 8.3.1 to determine C_{bomb}. The use of a bomb calorimeter to measure the ΔE_{comb} of a substance is illustrated in Example **8.4.4**.

✔ Example 8.4.1: Combustion of Glucose

The combustion of 0.579 g of benzoic acid in a bomb calorimeter caused a 2.08°C increase in the temperature of the calorimeter. The chamber was then emptied and recharged with 1.732 g of glucose and excess oxygen. Ignition of the glucose resulted in a temperature increase of 3.64°C. What is the ΔE_{comb} of glucose?


Benzoic acid

Given: mass and ΔT for combustion of standard and sample

Asked for: ΔE_{comb} of glucose

Strategy:

A. Calculate the value of q_{rxn} for benzoic acid by multiplying the mass of benzoic acid by its ΔE_{comb}. Then use Equation $ref5.5.9$ to determine the heat capacity of the calorimeter (C_{bomb}) from q_{comb} and ΔT.

B. Calculate the amount of heat released during the combustion of glucose by multiplying the heat capacity of the bomb by the temperature change. Determine the ΔE_{comb} of glucose by multiplying the amount of heat released per gram by the molar mass of glucose.

Solution:

The first step is to use Equation 8.4.1 and the information obtained from the combustion of benzoic acid to calculate C_{bomb}. We are given ΔT, and we can calculate q_{comb} from the mass of benzoic acid:

$$qcomb = \left(0.579\ \cancel{g}\right)\left(-26.38\ kJ/\cancel{g}\right) = -15.3\ kJ \tag{8.4.2}$$

From Equation 8.4.1,

$$-Cbomb = \frac{q_{comb}}{\Delta T} = \frac{-15.3\ kJ}{2.08\ ^oC} = -7.34\ kJ/^oC \tag{8.4.3}$$

B According to the strategy, we can now use the heat capacity of the bomb to calculate the amount of heat released during the combustion of glucose:

$$q_{comb} = -C_{bomb}\Delta T = (-7.34\ kJ/^oC)\,(3.64\ ^oC) = -26.7\ kJ \tag{8.4.4}$$

Because the combustion of 1.732 g of glucose released 26.7 kJ of energy, the ΔE_{comb} of glucose is

$$\Delta E_{comb} = \left(\frac{-26.7\ kJ}{1.732\ \cancel{g}}\right)\left(\frac{180.16\ \cancel{g}}{mol}\right) = -2780\ kJ/mol = 2.78 \times 10^3\ kJ/mol \tag{8.4.5}$$

? Exercise 8.4.1: Combustion of Benzoic Acid

When 2.123 g of benzoic acid is ignited in a bomb calorimeter, a temperature increase of 4.75°C is observed. When 1.932 g of methylhydrazine (CH_3NHNH_2) is ignited in the same calorimeter, the temperature increase is 4.64°C. Calculate the ΔE_{comb} of methylhydrazine, the fuel used in the maneuvering jets of the US space shuttle.


Methylhydrazine

Answer

-1.30×10^3 kJ/mol

8.4: Constant Volume Calorimeter is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

8.5: Enthalpy of reactions

Learning Objectives

- To understand how enthalpy pertains to chemical reactions

We have stated that the change in energy (ΔU) is equal to the sum of the heat produced and the work performed. Work done by an expanding gas is called *pressure-volume work*, (or just *PV work)*. Consider, for example, a reaction that produces a gas, such as dissolving a piece of copper in concentrated nitric acid. The chemical equation for this reaction is as follows:

$$\mathrm{Cu\,(s) + 4\,HNO_3\,(aq)\ \rightarrow Cu(NO_3)_2\,(aq) + 2\,H_2O\,(l) + 2\,NO_2\,(g)}$$

If the reaction is carried out in a closed system that is maintained at constant pressure by a movable piston, the piston will rise as nitrogen dioxide gas is formed (Figure 8.5.1). The system is performing work by lifting the piston against the downward force exerted by the atmosphere (i.e., *atmospheric pressure*). We find the amount of PV work done by multiplying the external pressure P by the change in volume caused by movement of the piston (ΔV). At a constant external pressure (here, atmospheric pressure),

$$w = -P\Delta V \tag{8.5.1}$$

The negative sign associated with PV work done indicates that the system loses energy when the volume increases. If the volume increases at constant pressure ($\Delta V > 0$), the work done by the system is negative, indicating that a system has lost energy by performing work on its surroundings. Conversely, if the volume decreases ($\Delta V < 0$), the work done by the system is positive, which means that the surroundings have performed work on the system, thereby increasing its energy.




Figure 8.5.1: An Example of Work Performed by a Reaction Carried Out at Constant Pressure. (a) Initially, the system (a copper penny and concentrated nitric acid) is at atmospheric pressure. (b) When the penny is added to the nitric acid, the volume of NO_2 gas that is formed causes the piston to move upward to maintain the system at atmospheric pressure. In doing so, the system is performing work on its surroundings. (CC BY-NC-SA; anonymous)

The internal energy U of a system is the sum of the kinetic energy and potential energy of all its components. It is the change in internal energy that produces heat plus work. To measure the energy changes that occur in chemical reactions, chemists usually use a related thermodynamic quantity called **enthalpy** (H) (from the Greek *enthalpein*, meaning "to warm"). The enthalpy of a system is defined as the sum of its internal energy U plus the product of its pressure P and volume V:

$$H = U + PV \tag{8.5.2}$$

Because internal energy, pressure, and volume are all state functions, enthalpy is also a state function. So we can define a change in enthalpy (ΔH) accordingly

$$\Delta H = H_{final} - H_{initial}$$

If a chemical change occurs at constant pressure (i.e., for a given P, $\Delta P = 0$), the change in enthalpy (ΔH) is

$$\Delta H = \Delta(U + PV) \tag{8.5.3}$$
$$= \Delta U + \Delta PV \tag{8.5.4}$$
$$= \Delta U + P\Delta V \tag{8.5.5}$$

Substituting $q + w$ for ΔU (First Law of Thermodynamics) and $-w$ for $P\Delta V$ (Equation 8.5.1) into Equation 8.5.5, we obtain

$$\Delta H = \Delta U + P\Delta V \tag{8.5.6}$$
$$= q_p + \cancel{w} - \cancel{w} \tag{8.5.7}$$
$$= q_p \tag{8.5.8}$$

The subscript p is used here to emphasize that this equation is true only for a process that occurs at constant pressure. From Equation 8.5.8 we see that at constant pressure the change in enthalpy, ΔH of the system, is equal to the heat gained or lost.

$$\Delta H = H_{final} - H_{initial} \tag{8.5.9}$$
$$= q_p \tag{8.5.10}$$

Just as with ΔU, because enthalpy is a state function, the magnitude of ΔH depends on only the initial and final states of the system, not on the path taken. Most important, the enthalpy change is the same even if the process does *not* occur at constant pressure.

> *To find ΔH for a reaction, measure q_p.*

When we study energy changes in chemical reactions, the most important quantity is usually the enthalpy of reaction (ΔH_{rxn}), the change in enthalpy that occurs during a reaction (such as the dissolution of a piece of copper in nitric acid). If heat flows from a system to its surroundings, the enthalpy of the system decreases, so ΔH_{rxn} is negative. Conversely, if heat flows from the surroundings to a system, the enthalpy of the system increases, so ΔH_{rxn} is positive. Thus:

- $\Delta H_{rxn} < 0$ for an *exothermic reaction*, and
- $\Delta H_{rxn} > 0$ for an *endothermic reaction*.

In chemical reactions, bond breaking requires an input of energy and is therefore an endothermic process, whereas bond making releases energy, which is an exothermic process. The sign conventions for heat flow and enthalpy changes are summarized in the following table:

Reaction Type	q	ΔH_{rxn}
exothermic	< 0	< 0 (heat flows from a system to its surroundings)
endothermic	> 0	> 0 (heat flows from the surroundings to a system)

If ΔH_{rxn} is negative, then the enthalpy of the products is less than the enthalpy of the reactants; that is, *an exothermic reaction is energetically downhill* (Figure 8.5.2*a*). Conversely, if ΔH_{rxn} is positive, then the enthalpy of the products is greater than the enthalpy of the reactants; thus, *an endothermic reaction is energetically uphill* (Figure 8.5.2*b*). Two important characteristics of enthalpy and changes in enthalpy are summarized in the following discussion.

> *Bond breaking **ALWAYS** requires an input of energy; bond making **ALWAYS** releases energy.y.*




Figure 8.5.2: The Enthalpy of Reaction. Energy changes in chemical reactions are usually measured as changes in enthalpy. (a) If heat flows from a system to its surroundings, the enthalpy of the system decreases, ΔH_{rxn} is negative, and the reaction is exothermic; it is energetically downhill. (b) Conversely, if heat flows from the surroundings to a system, the enthalpy of the system increases, ΔH_{rxn} is positive, and the reaction is endothermic; it is energetically uphill. (CC BY-NC-SA; anonymous)

- **Reversing a reaction or a process changes the sign of ΔH.** Ice *absorbs* heat when it melts (electrostatic interactions are broken), so liquid water must *release* heat when it freezes (electrostatic interactions are formed):

$$heat + H_2O(s) \rightarrow H_2O(l) \quad \Delta H > 0$$

$$H_2O(l) \rightarrow H_2O(s) + heat \quad \Delta H < 0$$

  In both cases, the *magnitude* of the enthalpy change is the same; only the *sign* is different.

- **Enthalpy is an extensive property (like mass).** The magnitude of ΔH for a reaction is proportional to the amounts of the substances that react. For example, a large fire produces more heat than a single match, even though the chemical reaction—the combustion of wood—is the same in both cases. For this reason, the enthalpy change for a reaction is usually given in kilojoules per mole of a particular reactant or product. Consider Equation 8.5.11, which describes the reaction of aluminum with iron(III) oxide (Fe_2O_3) at constant pressure. According to the reaction stoichiometry, 2 mol of Fe, 1 mol of Al_2O_3, and 851.5 kJ of heat are produced for every 2 mol of Al and 1 mol of Fe_2O_3 consumed:

$$2\,Al(s) + Fe_2O_3(s) \longrightarrow 2\,Fe(s) + Al_2O_3(s) + 815.5\ kJ \tag{8.5.11}$$

  Thus ΔH = −851.5 kJ/mol of Fe_2O_3. We can also describe ΔH for the reaction as −425.8 kJ/mol of Al: because 2 mol of Al are consumed in the balanced chemical equation, we divide −851.5 kJ by 2. When a value for ΔH, in kilojoules rather than kilojoules per mole, is written after the reaction, as in Equation 8.5.12, it is the value of ΔH corresponding to the reaction of the molar quantities of reactants as given in the balanced chemical equation:

$$2\,Al(s) + Fe_2O_3(s) \longrightarrow 2\,Fe(s) + Al_2O_3(s) \quad \Delta H_{rxn} = -851.5\ kJ \tag{8.5.12}$$

  If 4 mol of Al and 2 mol of Fe_2O_3 react, the change in enthalpy is 2 × (−851.5 kJ) = −1703 kJ. We can summarize the relationship between the amount of each substance and the enthalpy change for this reaction as follows:

$$-\frac{851.5\ kJ}{2\ mol\ Al} = -\frac{425.8\ kJ}{1\ mol\ Al} = -\frac{1703\ kJ}{4\ mol\ Al} \tag{8.5.13}$$

The relationship between the magnitude of the enthalpy change and the mass of reactants is illustrated in Example 8.5.1.

Example 8.5.1: Melting Icebergs

Certain parts of the world, such as southern California and Saudi Arabia, are short of freshwater for drinking. One possible solution to the problem is to tow icebergs from Antarctica and then melt them as needed. If ΔH is 6.01 kJ/mol for the reaction at 0°C and constant pressure:

$$\mathrm{H_2O\,(s) \longrightarrow H_2O\,(l)}$$

How much energy would be required to melt a moderately large iceberg with a mass of 1.00 million metric tons (1.00×10^6 metric tons)? (A metric ton is 1000 kg.)

Given: energy per mole of ice and mass of iceberg

Asked for: energy required to melt iceberg

Strategy:

A. Calculate the number of moles of ice contained in 1 million metric tons (1.00×10^6 metric tons) of ice.
B. Calculate the energy needed to melt the ice by multiplying the number of moles of ice in the iceberg by the amount of energy required to melt 1 mol of ice.

Solution:

A Because enthalpy is an extensive property, the amount of energy required to melt ice depends on the amount of ice present. We are given ΔH for the process—that is, the amount of energy needed to melt 1 mol (or 18.015 g) of ice—so we need to calculate the number of moles of ice in the iceberg and multiply that number by ΔH (+6.01 kJ/mol):

$$moles\ H_2O = 1.00 \times 10^6\ \cancel{\text{metric ton}}\ \mathrm{H_2O}\left(\frac{1000\ \cancel{kg}}{1\ \cancel{\text{metric ton}}}\right)\left(\frac{1000\ \cancel{g}}{1\ \cancel{kg}}\right)\left(\frac{1\ mol\ H_2O}{18.015\ \cancel{g\ H_2O}}\right)$$

$$= 5.55 \times 10^{10}\ mol\,\mathrm{H_2O}$$

B The energy needed to melt the iceberg is thus

$$\left(\frac{6.01\ kJ}{\cancel{mol\ H_2O}}\right)\left(5.55 \times 10^{10}\ \cancel{mol\ H_2O}\right) = 3.34 \times 10^{11}\ kJ$$

Because so much energy is needed to melt the iceberg, this plan would require a relatively inexpensive source of energy to be practical. To give you some idea of the scale of such an operation, the amounts of different energy sources equivalent to the amount of energy needed to melt the iceberg are shown below.

Possible sources of the approximately $3.34 \times 10^{11}\ kJ$ needed to melt a 1.00×10^6 metric ton iceberg

- Combustion of 3.8×10^3 ft^3 of natural gas
- Combustion of 68,000 barrels of oil
- Combustion of 15,000 tons of coal
- 1.1×10^8 kilowatt-hours of electricity

Alternatively, we can rely on ambient temperatures to slowly melt the iceberg. The main issue with this idea is the cost of dragging the iceberg to the desired place.

Exercise 8.5.1: Thermite Reaction

If 17.3 g of powdered aluminum are allowed to react with excess $\mathrm{Fe_2O_3}$, how much heat is produced?

Answer

273 kJ

Enthalpies of Reaction

One way to report the heat absorbed or released would be to compile a massive set of reference tables that list the enthalpy changes for all possible chemical reactions, which would require an incredible amount of effort. Fortunately, since enthalpy is a state function, all we have to know is the initial and final states of the reaction. This allows us to calculate the enthalpy change for virtually any conceivable chemical reaction using a relatively small set of tabulated data, such as the following:

- Enthalpy of combustion (ΔH_{comb}) The change in enthalpy that occurs during a combustion reaction. Enthalpy changes have been measured for the combustion of virtually any substance that will burn in oxygen; these values are usually reported as the enthalpy of combustion per mole of substance.
- Enthalpy of fusion (ΔH_{fus}) The enthalpy change that acompanies the melting (fusion) of 1 mol of a substance. The enthalpy change that accompanies the melting, or fusion, of 1 mol of a substance; these values have been measured for almost all the elements and for most simple compounds.
- Enthalpy of vaporization (ΔH_{vap}) The enthalpy change that accompanies the vaporization of 1 mol of a substance. The enthalpy change that accompanies the vaporization of 1 mol of a substance; these values have also been measured for nearly all the elements and for most volatile compounds.
- Enthalpy of solution (ΔH_{soln}) The change in enthalpy that occurs when a specified amount of solute dissolves in a given quantity of solvent. The enthalpy change when a specified amount of solute dissolves in a given quantity of solvent.

Table **8.5.1**: Enthalpies of Vaporization and Fusion for Selected Substances at Their Boiling Points and Melting Points

Substance	ΔH_{vap} (kJ/mol)	ΔH_{fus} (kJ/mol)
argon (Ar)	6.3	1.3
methane (CH_4)	9.2	0.84
ethanol (CH_3CH_2OH)	39.3	7.6
benzene (C_6H_6)	31.0	10.9
water (H_2O)	40.7	6.0
mercury (Hg)	59.0	2.29
iron (Fe)	340	14

> The sign convention is the same for all enthalpy changes: negative if heat is released by the system and positive if heat is absorbed by the system.



Enthalpy of Reaction: https://youtu.be/z2KUaIEF9qI

Enthalpy of Combustion

Standard enthalpy of combustion (ΔH_C°) is the enthalpy change when 1 mole of a substance burns (combines vigorously with oxygen) under standard state conditions; it is sometimes called “heat of combustion.” For example, the enthalpy of combustion of ethanol, −1366.8 kJ/mol, is the amount of heat produced when one mole of ethanol undergoes complete combustion at 25 °C and 1 atmosphere pressure, yielding products also at 25 °C and 1 atm.

Label '5.4.8' multiply defined

Enthalpies of combustion for many substances have been measured; a few of these are listed in Table **8.5.1**. Many readily available substances with large enthalpies of combustion are used as fuels, including hydrogen, carbon (as coal or charcoal), and hydrocarbons (compounds containing only hydrogen and carbon), such as methane, propane, and the major components of gasoline.

Table **8.5.1**: Standard Molar Enthalpies of Combustion

Substance	Combustion Reaction	Enthalpy of Combustion $\Delta H_c^\circ \left(\frac{\text{kJ}}{\text{mol}} \text{ at } 25°\text{C}\right)$
carbon	$\text{C}(s) + \text{O}_2(g) \longrightarrow \text{CO}_2(g)$	−393.5
hydrogen	$\text{H}_2(g) + \frac{1}{2}\text{O}_2(g) \longrightarrow \text{H}_2\text{O}(l)$	−285.8
magnesium	$\text{Mg}(s) + \frac{1}{2}\text{O}_2(g) \longrightarrow \text{MgO}(s)$	−601.6
sulfur	$\text{S}(s) + \text{O}_2(g) \longrightarrow \text{SO}_2(g)$	−296.8
carbon monoxide	$\text{CO}(g) + \frac{1}{2}\text{O}_2(g) \longrightarrow \text{CO}_2(g)$	−283.0
methane	$\text{CH}_4(g) + 2\,\text{O}_2(g) \longrightarrow \text{CO}_2(g) + 2\,\text{H}_2\text{O}(l)$	−890.8
acetylene	$\text{C}_2\text{H}_2(g) + \frac{5}{2}\text{O}_2(g) \longrightarrow 2\,\text{CO}_2(g) + \text{H}_2\text{O}(l)$	−1301.1
ethanol	$\text{C}_2\text{H}_5\text{OH}(l) + 3\,\text{O}_2(g) \longrightarrow \text{CO}_2(g) + 3\,\text{H}_2\text{O}(l)$	−1366.8
methanol	$\text{CH}_3\text{OH}(l) + \frac{3}{2}\text{O}_2(g) \longrightarrow \text{CO}_2(g) + 2\,\text{H}_2\text{O}(l)$	−726.1
isooctane	$\text{C}_8\text{H}_{18}(l) + \frac{25}{2}\text{O}_2(g) \longrightarrow 8\,\text{CO}_2(g) + 9\,\text{H}_2\text{O}(l)$	−5461

Example 8.5.3: Using Enthalpy of Combustion

As Figure **8.5.3** suggests, the combustion of gasoline is a highly exothermic process. Let us determine the approximate amount of heat produced by burning 1.00 L of gasoline, assuming the enthalpy of combustion of gasoline is the same as that of isooctane, a common component of gasoline. The density of isooctane is 0.692 g/mL.



Figure **8.5.3**: The combustion of gasoline is very exothermic. (credit: modification of work by “AlexEagle”/Flickr)

Solution

Starting with a known amount (1.00 L of isooctane), we can perform conversions between units until we arrive at the desired amount of heat or energy. The enthalpy of combustion of isooctane provides one of the necessary conversions. Table **8.5.1** gives

this value as −5460 kJ per 1 mole of isooctane (C_8H_{18}).

Using these data,

$$1.00\ \cancel{\text{L } C_8H_{18}} \times \frac{1000\ \cancel{\text{mL } C_8H_{18}}}{1\ \cancel{\text{L } C_8H_{18}}} \times \frac{0.692\ \cancel{\text{g } C_8H_{18}}}{1\ \cancel{\text{mL } C_8H_{18}}} \times \frac{1\ \cancel{\text{mol } C_8H_{18}}}{114\ \cancel{\text{g } C_8H_{18}}} \times \frac{-5460\ \text{kJ}}{1\ \cancel{\text{mol } C_8H_{18}}} = -3.31 \times 10^4\ \text{kJ}$$

The combustion of 1.00 L of isooctane produces 33,100 kJ of heat. (This amount of energy is enough to melt 99.2 kg, or about 218 lbs, of ice.)

Note: If you do this calculation one step at a time, you would find:

$$1.00\ \text{L } C_8H_{18} \longrightarrow 1.00 \times 10^3\ \text{mL } C_8H_{18}$$
$$1.00 \times 10^3\ \text{mL } C_8H_{18} \longrightarrow 692\ \text{g } C_8H_{18}$$
$$692\ \text{g } C_8H_{18} \longrightarrow 6.07\ \text{mol } C_8H_{18}$$
$$692\ \text{g } C_8H_{18} \longrightarrow -3.31 \times 10^4\ \text{kJ}$$

? Exercise 8.5.3

How much heat is produced by the combustion of 125 g of acetylene?

Answer

6.25×10^3 kJ

Emerging Algae-Based Energy Technologies (Biofuels)

As reserves of fossil fuels diminish and become more costly to extract, the search is ongoing for replacement fuel sources for the future. Among the most promising biofuels are those derived from algae (Figure **8.5.4**). The species of algae used are nontoxic, biodegradable, and among the world's fastest growing organisms. About 50% of algal weight is oil, which can be readily converted into fuel such as biodiesel. Algae can yield 26,000 gallons of biofuel per hectare—much more energy per acre than other crops. Some strains of algae can flourish in brackish water that is not usable for growing other crops. Algae can produce biodiesel, biogasoline, ethanol, butanol, methane, and even jet fuel.



Figure **8.5.4**: (a) Tiny algal organisms can be (b) grown in large quantities and eventually (c) turned into a useful fuel such as biodiesel. (credit a: modification of work by Micah Sittig; credit b: modification of work by Robert Kerton; credit c: modification of work by John F. Williams)

According to the US Department of Energy, only 39,000 square kilometers (about 0.4% of the land mass of the US or less than $\frac{1}{7}$ of the area used to grow corn) can produce enough algal fuel to replace all the petroleum-based fuel used in the US. The cost of algal fuels is becoming more competitive—for instance, the US Air Force is producing jet fuel from algae at a total cost of under $5 per gallon. The process used to produce algal fuel is as follows: grow the algae (which use sunlight as their energy source and CO_2 as a raw material); harvest the algae; extract the fuel compounds (or precursor compounds); process as necessary (e.g., perform a transesterification reaction to make biodiesel); purify; and distribute (Figure **8.5.5**).



Figure 8.5.5: Algae convert sunlight and carbon dioxide into oil that is harvested, extracted, purified, and transformed into a variety of renewable fuels.

Summary

For a chemical reaction, the **enthalpy of reaction** (ΔH_{rxn}) is the difference in enthalpy between products and reactants; the units of ΔH_{rxn} are kilojoules per mole. Reversing a chemical reaction reverses the sign of ΔH_{rxn}.

Contributors and Attributions

- Modified by Joshua Halpern (Howard University)

8.5: Enthalpy of reactions is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **5.4: Enthalpy of Reaction** is licensed CC BY-NC-SA 3.0.
- **5.4: Enthalpy** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

8.6: Constant Pressure Calorimeter

Because ΔH is defined as the heat flow at constant pressure, measurements made using a constant-pressure calorimeter (a device used to measure enthalpy changes in chemical processes at constant pressure) give ΔH values directly. This device is particularly well suited to studying reactions carried out in solution at a constant atmospheric pressure. A "student" version, called a *coffee-cup calorimeter* (Figure **8.6.1**), is often encountered in general chemistry laboratories. Commercial calorimeters operate on the same principle, but they can be used with smaller volumes of solution, have better thermal insulation, and can detect a change in temperature as small as several millionths of a degree (10^{-6} °C). Because the heat released or absorbed at constant pressure is equal to ΔH, the relationship between heat and ΔH_{rxn} is

$$\Delta H_{rxn} = q_{rxn} = -q_{calorimater} = -mc\Delta T \tag{8.6.1}$$

The use of a constant-pressure calorimeter is illustrated in Example **8.6.3**.




Figure **8.6.1**: A Coffee-Cup Calorimeter. This simplified version of a constant-pressure calorimeter consists of two Styrofoam cups nested and sealed with an insulated stopper to thermally isolate the system (the solution being studied) from the surroundings (the air and the laboratory bench). Two holes in the stopper allow the use of a thermometer to measure the temperature and a stirrer to mix the reactants. (CC BY-NC-SA; anonymous)

✔ Example 8.6.1

When 5.03 g of solid potassium hydroxide are dissolved in 100.0 mL of distilled water in a coffee-cup calorimeter, the temperature of the liquid increases from 23.0°C to 34.7°C. The density of water in this temperature range averages 0.9969 g/cm^3. What is ΔH_{soln} (in kilojoules per mole)? Assume that the calorimeter absorbs a negligible amount of heat and, because of the large volume of water, the specific heat of the solution is the same as the specific heat of pure water.

Given: mass of substance, volume of solvent, and initial and final temperatures

Asked for: ΔH_{soln}

Strategy:

A. Calculate the mass of the solution from its volume and density and calculate the temperature change of the solution.
B. Find the heat flow that accompanies the dissolution reaction by substituting the appropriate values into Equation 5.5.8.
C. Use the molar mass of KOH to calculate ΔH_{soln}.

Solution:

A To calculate ΔH_{soln}, we must first determine the amount of heat released in the calorimetry experiment. The mass of the solution is

$$(100.0\ mL\ H2O)\left(0.9969\ g/\cancel{mL}\right) + 5.03\ g\ KOH = 104.72\ g \tag{8.6.2}$$

The temperature change is (34.7°C − 23.0°C) = +11.7°C.

B Because the solution is not very concentrated (approximately 0.9 M), we assume that the specific heat of the solution is the same as that of water. The heat flow that accompanies dissolution is thus

$$q_{calorimater} = mC_s\Delta T = \left(104.72\ \cancel{g}\right)\left(\frac{4.184\ J}{\cancel{g}\cdot\cancel{^\circ C}}\right)(11.7\ ^\circ C) = 5130\ J = 5.13\ lJ \tag{8.6.3}$$

The temperature of the solution increased because heat was absorbed by the solution (q > 0). Where did this heat come from? It was released by KOH dissolving in water. From Equation 8.6.1, we see that

$$\Delta H_{rxn} = -q_{calorimeter} = -5.13\ kJ$$

This experiment tells us that dissolving 5.03 g of KOH in water is accompanied by the *release* of 5.13 kJ of energy. Because the temperature of the solution increased, the dissolution of KOH in water must be exothermic.

C The last step is to use the molar mass of KOH to calculate ΔH_{soln}—the heat released when dissolving 1 mol of KOH:

$$\Delta H_{soln} = \left(\frac{5.13\ kJ}{5.03\ \cancel{g}}\right)\left(\frac{56.11\ \cancel{g}}{1\ mol}\right) = -57.2\ kJ/mol \tag{8.6.4}$$

? Exercise 8.6.1

A coffee-cup calorimeter contains 50.0 mL of distilled water at 22.7°C. Solid ammonium bromide (3.14 g) is added and the solution is stirred, giving a final temperature of 20.3°C. Using the same assumptions as in Example **8.6.1**, find ΔH_{soln} for NH_4Br (in kilojoules per mole).

Answer

16.6 kJ/mol

8.6: Constant Pressure Calorimeter is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

8.7: Standard Enthalpy of formation

Learning Objectives

- To understand Enthalpies of Formation and be able to use them to calculate Enthalpies of Reaction

Standard Enthalpies of Formation

A standard enthalpy of formation ΔH_f° is an enthalpy change for a reaction in which exactly 1 mole of a pure substance is formed from free elements in their most stable states under standard state conditions. These values are especially useful for computing or predicting enthalpy changes for chemical reactions that are impractical or dangerous to carry out, or for processes for which it is difficult to make measurements. If we have values for the appropriate standard enthalpies of formation, we can determine the enthalpy change for any reaction, which we will practice in the next section on Hess's law.

The standard enthalpy of formation of $CO_2(g)$ is −393.5 kJ/mol. This is the enthalpy change for the exothermic reaction:

$$\mathrm{C}(s) + \mathrm{O_2}(g) \longrightarrow \mathrm{CO_2}(g) \quad \Delta H_f^\circ = \Delta H_{298}^\circ = -393.5\ k\mathrm{J} \tag{8.7.1}$$

starting with the reactants at a pressure of 1 atm and 25 °C (with the carbon present as graphite, the most stable form of carbon under these conditions) and ending with one mole of CO_2, also at 1 atm and 25 °C. For nitrogen dioxide, $\mathrm{NO_{2(g)}}$, ΔH_f° is 33.2 kJ/mol. This is the enthalpy change for the reaction:

$$\frac{1}{2}\mathrm{N_2}(g) + \mathrm{O_2}(g) \longrightarrow \mathrm{NO_2}(g) \quad \Delta H_f^\circ = \Delta H_{298}^\circ = +33.2\ k\mathrm{J} \tag{8.7.2}$$

A reaction equation with $\frac{1}{2}$ mole of N_2 and 1 mole of O_2 is correct in this case because the standard enthalpy of formation always refers to 1 mole of product, $NO_2(g)$.

You will find a table of standard enthalpies of formation of many common substances in Tables T1 and T2. These values indicate that formation reactions range from highly exothermic (such as −2984 kJ/mol for the formation of P_4O_{10}) to strongly endothermic (such as +226.7 kJ/mol for the formation of acetylene, C_2H_2). By definition, the standard enthalpy of formation of an element in its most stable form is equal to zero under standard conditions, which is 1 atm for gases and 1 M for solutions.



Definition of Heat of Formation Reactions: https://youtu.be/A20k0CK4doI

Example 8.7.4: Evaluating an Enthalpy of Formation

Ozone, $O_3(g)$, forms from oxygen, $O_2(g)$, by an endothermic process. Ultraviolet radiation is the source of the energy that drives this reaction in the upper atmosphere. Assuming that both the reactants and products of the reaction are in their standard states, determine the standard enthalpy of formation, ΔH_f° of ozone from the following information:

$$3\,\mathrm{O_2}(g) \longrightarrow 2\,\mathrm{O_3}(g) \quad \Delta H_{298}^\circ = +286\ k\mathrm{J}$$

Solution ΔH_f° is the enthalpy change for the formation of one mole of a substance in its standard state from the elements in their standard states. Thus, ΔH_f° for $O_3(g)$ is the enthalpy change for the reaction:

$$\frac{3}{2}O_2(g) \longrightarrow O_3(g)$$

For the formation of 2 mol of $O_3(g)$, $\Delta H_{298}^\circ = +286\ k\text{J}$. This ratio, $\left(\frac{286\ \text{kJ}}{2\ \text{mol}\ O_3}\right)$, can be used as a conversion factor to find the heat produced when 1 mole of $O_3(g)$ is formed, which is the enthalpy of formation for $O_3(g)$:

$$\Delta H^\circ \text{ for 1 mole of } O_3(g) = 1\ \cancel{\text{mol}\ O_3} \times \frac{286\ \text{kJ}}{2\ \cancel{\text{mol}\ O_3}} = 143\ \text{kJ}$$

Therefore, $\Delta H_f^\circ[O_3(g)] = +143\ \ k\text{J/mol}$.

Exercise 8.7.4

Hydrogen gas, H_2, reacts explosively with gaseous chlorine, Cl_2, to form hydrogen chloride, $HCl(g)$. What is the enthalpy change for the reaction of 1 mole of $H_2(g)$ with 1 mole of $Cl_2(g)$ if both the reactants and products are at standard state conditions? The standard enthalpy of formation of $HCl(g)$ is −92.3 kJ/mol.

Answer

For the reaction

$$H_2(g) + Cl_2(g) \longrightarrow 2\,HCl(g) \quad \Delta H_{298}^\circ = -184.6\ \text{kJ}$$

Example 8.7.5: Writing Reaction Equations for ΔH_f°

Write the heat of formation reaction equations for:

a. $C_2H_5OH_{(l)}$
b. $Ca_3(PO_4)_{2(s)}$

Solution

Remembering that ΔH_f° reaction equations are for forming 1 mole of the compound from its constituent elements under standard conditions, we have:

a. $2\,C(s,\ \text{graphite}) + 3\,H_2(g) + \frac{1}{2}O_2(g) \longrightarrow C_2H_5OH(l)$
b. $3\,Ca(s) + \frac{1}{2}P_4(s) + 4\,O_2(g) \longrightarrow Ca_3(PO_4)_2(s)$

Note: The standard state of carbon is graphite, and phosphorus exists as P_4.

Exercise 8.7.5

Write the heat of formation reaction equations for:

a. $C_2H_5OC_2H_{5(l)}$
b. $Na_2CO_{3(s)}$

Answer a

$$4\,C(s,\ \text{graphite}) + 5\,H_2(g) + \tfrac{1}{2}O_2(g) \longrightarrow C_2H_5OC_2H_5(l);$$

Answer b

$$2\,Na(s) + C(s,\ \text{graphite}) + \frac{3}{2}O_2(g) \longrightarrow Na_2CO_3(s)$$



Calculating DH° using DHf°: https://youtu.be/Y3aJJno9W2c

Standard Enthalpies of Reaction

Tabulated values of standard enthalpies of formation can be used to calculate enthalpy changes for *any* reaction involving substances whose ΔH_f^o values are known. The standard enthalpy of reaction ΔH_{rxn}^o is the enthalpy change that occurs when a reaction is carried out with all reactants and products in their standard states. Consider the general reaction

$$aA + bB \rightarrow cC + dD \tag{8.7.3}$$

where A, B, C, and D are chemical substances and a, b, c, and d are their stoichiometric coefficients. The magnitude of ΔH^o is the sum of the standard enthalpies of formation of the products, each multiplied by its appropriate coefficient, minus the sum of the standard enthalpies of formation of the reactants, also multiplied by their coefficients:

$$\Delta H_{rxn}^o = \underbrace{\left[c\Delta H_f^o(C) + d\Delta H_f^o(D)\right]}_{\text{products}} - \underbrace{\left[a\Delta H_f^o(A) + b\Delta H_f^o(B)\right]}_{\text{reactants}} \tag{8.7.4}$$

More generally, we can write

$$\Delta H_{rxn}^o = \sum m\Delta H_f^o\,(products) - \sum n\Delta H_f^o\,(reactants) \tag{8.7.5}$$

where the symbol $\sum$ means "sum of" and m and n are the stoichiometric coefficients of each of the products and the reactants, respectively. "Products minus reactants" summations such as Equation 8.7.5 arise from the fact that enthalpy is a state function. Because many other thermochemical quantities are also state functions, "products minus reactants" summations are very common in chemistry; we will encounter many others in subsequent chapters.

> "Products minus reactants" summations are typical of state functions.

To demonstrate the use of tabulated ΔH^o values, we will use them to calculate ΔH_{rxn} for the combustion of glucose, the reaction that provides energy for your brain:

$$\mathrm{C_6H_{12}O_6\,(s) + 6\,O_2\,(g) \rightarrow 6\,CO_2\,(g) + 6\,H_2O\,(l)} \tag{8.7.6}$$

Using Equation 8.7.5, we write

$$\begin{aligned} &\Delta H_f^o \\ &= \left\{6\Delta H_f^o\left[CO_2\,(g)\right] + 6\Delta H_f^o\left[H_2O\,(g)\right]\right\} - \left\{\Delta H_f^o\left[C_6H_{12}O_6\,(s)\right] + 6\Delta H_f^o\left[O_2\,(g)\right]\right\} \end{aligned} \tag{8.7.7}$$

From Table T1, the relevant ΔH^o_f values are $\Delta H^o_f\,[CO_2(g)]$ = -393.5 kJ/mol, $\Delta H^o_f\,[H_2O(l)]$ = -285.8 kJ/mol, and $\Delta H^o_f\,[C_6H_{12}O_6(s)]$ = -1273.3 kJ/mol. Because $O_2(g)$ is a pure element in its standard state, $\Delta H^o_f\,[O_2(g)]$ = 0 kJ/mol. Inserting these values into Equation 8.7.7 and changing the subscript to indicate that this is a combustion reaction, we obtain

$$\Delta H_{comb}^o = \left[6\,(-393.5\ kJ/mol) + 6\,(-285.8\ kJ/mol)\right] - \left[-1273.3 + 6\,(0\ kJ\ mol)\right] \tag{8.7.8}$$

$$= -2802.5\ kJ/mol \tag{8.7.9}$$

As illustrated in Figure **8.7.2**, we can use Equation 8.7.8 to calculate ΔH_f^o for glucose because enthalpy is a state function. The figure shows two pathways from reactants (middle left) to products (bottom). The more direct pathway is the downward green arrow labeled ΔH_{comb}^o. The alternative hypothetical pathway consists of **four separate reactions** that convert the reactants to the elements in their standard states (upward purple arrow at left) and then convert the elements into the desired products (downward purple arrows at right). The reactions that convert the reactants to the elements are the reverse of the equations that define the ΔH_f^o values of the reactants. Consequently, the enthalpy changes are

$$\begin{aligned}\Delta H_1^o &= \Delta H_f^o\,[glucose\,(s)] \\ &= -1\ \cancel{mol\ glucose}\left(\frac{1273.3\ kJ}{1\ \cancel{mol\ glucose}}\right) \\ &= +1273.3\ kJ \\ \Delta H_2^o &= 6\Delta H_f^o\,[O_2\,(g)] \\ &= 6\ \cancel{mol\ O_2}\left(\frac{0\ kJ}{1\ \cancel{mol\ O_2}}\right) \\ &= 0\ kJ\end{aligned} \tag{8.7.10}$$

> *Recall that when we reverse a reaction, we must also reverse the* ***sign*** *of the accompanying enthalpy change (Equation 8.7.4 since the products are now reactants and vice versa.*

The overall enthalpy change for conversion of the reactants (1 mol of glucose and 6 mol of O_2) to the elements is therefore +1273.3 kJ.




Figure **8.7.1**: A Thermochemical Cycle for the Combustion of Glucose. Two hypothetical pathways are shown from the reactants to the products. The green arrow labeled ΔH^o_{comb} indicates the combustion reaction. Alternatively, we could first convert the reactants to the elements via the reverse of the equations that define their standard enthalpies of formation (the upward arrow, labeled ΔH^o_1 and ΔH^o_2). Then we could convert the elements to the products via the equations used to define their standard enthalpies of formation (the downward arrows, labeled ΔH^o_3 and ΔH^o_4). Because enthalpy is a state function, ΔH^o_{comb} is equal to the sum of the enthalpy changes $\Delta H^o_1 + \Delta H^o_2 + \Delta H^o_3 + \Delta H^o_4$.

The reactions that convert the elements to final products (downward purple arrows in Figure **8.7.2**) are identical to those used to define the ΔH^o_f values of the products. Consequently, the enthalpy changes (from Table T1) are

$$\begin{aligned}\Delta H_3^o &= \Delta H_f^o\,[CO_2\,(g)] = 6\ \cancel{mol\ CO_2}\left(\frac{393.5\ kJ}{1\ \cancel{mol\ CO_2}}\right) = -2361.0\ kJ \\ \Delta H_4^o &= 6\Delta H_f^o\,[H_2O\,(l)] = 6\ \cancel{mol\ H_2O}\left(\frac{-285.8\ kJ}{1\ \cancel{mol\ H_2O}}\right) = -1714.8\ kJ\end{aligned} \tag{8.7.11}$$

The overall enthalpy change for the conversion of the elements to products (6 mol of carbon dioxide and 6 mol of liquid water) is therefore −4075.8 kJ. Because enthalpy is a state function, the difference in enthalpy between an initial state and a final state can be computed using *any* pathway that connects the two. Thus the enthalpy change for the combustion of glucose to carbon dioxide and

water is the sum of the enthalpy changes for the conversion of glucose and oxygen to the elements (+1273.3 kJ) and for the conversion of the elements to carbon dioxide and water (−4075.8 kJ):

$$\Delta H^o_{comb} = +1273.3\ kJ + (-4075.8\ kJ) = -2802.5\ kJ \tag{8.7.12}$$

This is the same result we obtained using the "products minus reactants" rule (Equation 8.7.5) and ΔH^o_f values. The two results must be the same because Equation 8.7.12 is just a more compact way of describing the thermochemical cycle shown in Figure 8.7.1.

Example 8.7.6: Heat of Combustion

Long-chain fatty acids such as palmitic acid ($CH_3(CH_2)_{14}CO_2H$) are one of the two major sources of energy in our diet (ΔH^o_f =−891.5 kJ/mol). Use the data in Table T1 to calculate ΔH^o_{comb} for the combustion of palmitic acid. Based on the energy released in combustion *per gram*, which is the better fuel — glucose or palmitic acid?

Given: compound and ΔH^o_f values

Asked for: ΔH^o_{comb} per mole and per gram

Strategy:

A. After writing the balanced chemical equation for the reaction, use Equation 8.7.5 and the values from Table T1 to calculate ΔH^o_{comb} the energy released by the combustion of 1 mol of palmitic acid.

B. Divide this value by the molar mass of palmitic acid to find the energy released from the combustion of 1 g of palmitic acid. Compare this value with the value calculated in Equation 8.7.8 for the combustion of glucose to determine which is the better fuel.

Solution:

A To determine the energy released by the combustion of palmitic acid, we need to calculate its ΔH^o_f. As always, the first requirement is a balanced chemical equation:

$$C_{16}H_{32}O_{2(s)} + 23O_{2(g)} \rightarrow 16CO_{2(g)} + 16H_2O_{(l)}$$

Using Equation 8.7.5 ("products minus reactants") with ΔH^o_f values from Table T1 (and omitting the physical states of the reactants and products to save space) gives

$$\begin{aligned}\Delta H^o_{comb} &= \sum m\Delta H^o_f\,(products) - \sum n\Delta H^o_f\,(reactants)\\ &= [16\,(-393.5\ kJ/mol\ CO_2) + 16\,(-285.8\ kJ/mol\ H_2O\,)]\\ &\quad - [-891.5\ kJ/mol\ C_{16}H_{32}O_2 + 23\,(0\ kJ/mol\ O_2\,)]\\ &= -9977.3\ kJ/mol\end{aligned}$$

This is the energy released by the combustion of 1 mol of palmitic acid.

B The energy released by the combustion of 1 g of palmitic acid is

$$\Delta H^o_{comb}\ per\ gram = \left(\frac{9977.3\ kJ}{\cancel{1\ mol}}\right)\left(\frac{\cancel{1\ mol}}{256.42\ g}\right) = -38.910\ kJ/g$$

As calculated in Equation 8.7.8, \(ΔH^o_f\) of glucose is −2802.5 kJ/mol. The energy released by the combustion of 1 g of glucose is therefore

$$\Delta H^o_{comb}\ per\ gram = \left(\frac{-2802.5\ kJ}{\cancel{1\ mol}}\right)\left(\frac{\cancel{1\ mol}}{180.16\ g}\right) = -15.556\ kJ/g$$

The combustion of fats such as palmitic acid releases more than twice as much energy per gram as the combustion of sugars such as glucose. This is one reason many people try to minimize the fat content in their diets to lose weight.

Exercise 8.7.7: Water–gas shift reaction

Use Table T1 to calculate ΔH^{o}_{rxn} for the *water–gas shift reaction*, which is used industrially on an enormous scale to obtain $H_2(g)$:

$$\mathrm{CO\ (g) + H_2O\ (g) \longrightarrow CO_2\,(g) + H_2\ (g)}$$


Answer

−41.2 kJ/mol

We can also measure the enthalpy change for another reaction, such as a combustion reaction, and then use it to calculate a compound's ΔH^{o}_{f} which we cannot obtain otherwise. This procedure is illustrated in Example 8.7.3.

Example 8.7.8: Tetraethyllead

Beginning in 1923, tetraethyllead [$(C_2H_5)_4Pb$] was used as an antiknock additive in gasoline in the United States. Its use was completely phased out in 1986 because of the health risks associated with chronic lead exposure. Tetraethyllead is a highly poisonous, colorless liquid that burns in air to give an orange flame with a green halo. The combustion products are $CO_2\,(g)$, $H_2O\,(l)$, and red $PbO\,(s)$. What is the standard enthalpy of formation of tetraethyllead, given that ΔH^{o}_{f} is −19.29 kJ/g for the combustion of tetraethyllead and ΔH^{o}_{f} of red PbO(s) is −219.0 kJ/mol?



Tetraethyllead

Given: reactant, products, and ΔH^{o}_{comb} values

Asked for: ΔH^{o}_{f} of the reactants

Strategy:

A. Write the balanced chemical equation for the combustion of tetraethyl lead. Then insert the appropriate quantities into Equation 8.7.5 to get the equation for ΔH^{o}_{f} of tetraethyl lead.

B. Convert ΔH^{o}_{comb} per gram given in the problem to ΔH^{o}_{comb} per mole by multiplying ΔH^{o}_{comb} per gram by the molar mass of tetraethyllead.

C. Use Table T1 to obtain values of ΔH^{o}_{f} for the other reactants and products. Insert these values into the equation for ΔH^{o}_{f} of tetraethyl lead and solve the equation.

Solution:

A The balanced chemical equation for the combustion reaction is as follows:

$$\mathrm{2\,(C_2H_5)_4Pb\,(l) + 27\,O_2\,(g) \longrightarrow 2\,PbO\,(s) + 16\,CO_2\,(g) + 20\,H_2O\,(l)}$$

Using Equation 8.7.5 gives

$$\Delta H^{o}_{comb} = \left[2\Delta H^{o}_{f}\,(PbO) + 16\Delta H^{o}_{f}\,(CO_2) + 20\Delta H^{o}_{f}\,(H_2O)\right] - \left[2\Delta H^{o}_{f}\,((C_2H_5)_4\,Pb) + 27\Delta H^{o}_{f}\,(O_2)\right]$$

Solving for $\Delta H^{o}_{f}[(C_2H_5)_4Pb]$ gives

$$\Delta H_f^\circ\left((C_2H_5)_4\,Pb\right) = \Delta H_f^\circ\left(PbO\right) + 8\Delta H_f^\circ\left(CO_2\right) + 10\Delta H_f^\circ\left(H_2O\right) - \frac{27}{2}\Delta H_f^\circ\left(O_2\right) - \frac{\Delta H_{comb}^\circ}{2}$$

The values of all terms other than $\Delta H_f^\circ[(C_2H_5)_4Pb]$ are given in Table T1.

B The magnitude of ΔH_{comb}° is given in the problem in kilojoules per *gram* of tetraethyl lead. We must therefore multiply this value by the molar mass of tetraethyl lead (323.44 g/mol) to get ΔH_{comb}° for 1 mol of tetraethyl lead:

$$\begin{aligned}\Delta H_{comb}^\circ &= \left(\frac{-19.29\ kJ}{\cancel{g}}\right)\left(\frac{323.44\ \cancel{g}}{mol}\right)\\ &= -6329\ kJ/mol\end{aligned}$$

Because the balanced chemical equation contains 2 mol of tetraethyllead, ΔH_{rxn}° is

$$\begin{aligned}\Delta H_{rxn}^\circ &= 2\ \cancel{mol\ (C_2H5)_4\,Pb}\left(\frac{-6329\ kJ}{1\ \cancel{mol\ (C_2H5)_4\,Pb}}\right)\\ &= -12,480\ kJ\end{aligned}$$

C Inserting the appropriate values into the equation for $\Delta H_f^\circ[(C_2H_5)_4Pb]$ gives

$$\begin{aligned}\Delta H_f^\circ[&(C_2H_4)_4\\ &Pb] = [1\ mol\ PbO\ \times 219.0\ kJ/mol] + [8\ mol\ CO_2 \times (-393.5\ kJ/mol)]\\ &\quad + [10\ mol\ H_2O \times (-285.8\ kJ/mol)]\\ &\quad + [-27/2\ mol\ O_2) \times 0\ kJ/mol\ O_2]\,[12,480.2\ kJ/mol\ \ (C_2H_5)_4\,Pb]\\ &= -219.0\ kJ - 3148\ kJ - 2858kJ - 0kJ + 6240\ kJ = 15kJ/mol\end{aligned}$$

Exercise 8.7.9

Ammonium sulfate, $(NH_4)_2SO_4$, is used as a fire retardant and wood preservative; it is prepared industrially by the highly exothermic reaction of gaseous ammonia with sulfuric acid:

$$2\,NH_3\,(g) + H_2SO_4\,(aq) \rightarrow (NH_4)_2SO_4\,(s)$$

The value of ΔH_{rxn}° is -179.4 kJ/mole H_2SO_4. Use the data in Table T1 to calculate the standard enthalpy of formation of ammonium sulfate (in kilojoules per mole).

Answer

−1181 kJ/mol

Exercise 8.7.10

Calculate the heat of combustion of 1 mole of ethanol, $C_2H_5OH(l)$, when $H_2O(l)$ and $CO_2(g)$ are formed. Use the following enthalpies of formation: $C_2H_5OH(l)$, −278 kJ/mol; $H_2O(l)$, −286 kJ/mol; and $CO_2(g)$, −394 kJ/mol.

Answer

−1368 kJ/mol

Summary

The standard enthalpy of formation, ΔH_f°, is the enthalpy change accompanying the formation of 1 mole of a substance from the elements in their most stable states at 1 bar (standard state). Many of the processes are carried out at 298.15 K.

Key Equations

- $\Delta U = q + w$
- $\Delta H^\circ_{\text{reaction}} = \sum n \times \Delta H^\circ_f(\text{products}) - \sum n \times \Delta H^\circ_f(\text{reactants})$

Footnotes

1. 1 For more on algal fuel, see www.theguardian.com/environme...n-fuel-problem.

Glossary

standard enthalpy of combustion (ΔH°_c)

heat released when one mole of a compound undergoes complete combustion under standard conditions

standard enthalpy of formation (ΔH°_f)

enthalpy change of a chemical reaction in which 1 mole of a pure substance is formed from its elements in their most stable states under standard state conditions

standard state

set of physical conditions as accepted as common reference conditions for reporting thermodynamic properties; 1 bar of pressure, and solutions at 1 molar concentrations, usually at a temperature of 298.15 K

8.7: Standard Enthalpy of formation is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **5.2: The First Law of Thermodynamics** is licensed CC BY-NC-SA 3.0.
- **5.4: Enthalpy** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **7.8: Standard Enthalpies of Formation** is licensed CC BY-NC-SA 4.0.

8.8: Calculating Enthalpy of Reactions Using Hess's Law

Learning Objectives

- Explain Hess's law and use it to compute reaction enthalpies

There are two ways to determine the amount of heat involved in a chemical change: measure it experimentally, or calculate it from other experimentally determined enthalpy changes. Some reactions are difficult, if not impossible, to investigate and make accurate measurements for experimentally. And even when a reaction is not hard to perform or measure, it is convenient to be able to determine the heat involved in a reaction without having to perform an experiment.

This type of calculation usually involves the use of Hess's law, which states: If a process can be written as the sum of several stepwise processes, the enthalpy change of the total process equals the sum of the enthalpy changes of the various steps. Hess's law is valid because enthalpy is a state function: Enthalpy changes depend only on where a chemical process starts and ends, but not on the path it takes from start to finish. For example, we can think of the reaction of carbon with oxygen to form carbon dioxide as occurring either directly or by a two-step process. The direct process is written:

$$\mathrm{C_{(s)} + O_{2(g)} \longrightarrow CO_{2(g)} \quad \Delta H^\circ_{298} = -394\ kJ} \tag{8.8.1}$$

In the two-step process, first carbon monoxide is formed:

$$\mathrm{C_{(s)} + \frac{1}{2}O_{2(g)} \longrightarrow CO_{(g)} \quad \Delta H^\circ_{298} = -111\ kJ} \tag{8.8.2}$$

Then, carbon monoxide reacts further to form carbon dioxide:

$$\mathrm{CO(g) + \frac{1}{2}O_2(g) \longrightarrow CO_2(g) \quad \Delta H^\circ_{298} = -283\ kJ} \tag{8.8.3}$$

The equation describing the overall reaction is the sum of these two chemical changes:

$$\begin{aligned}
&\text{Step 1: } \mathrm{C(s) + \tfrac{1}{2}O_2(g) \longrightarrow CO(g)}\\
&\underline{\text{Step 2: } \mathrm{CO(g) + \tfrac{1}{2}O_2(g) \longrightarrow CO_2(g)}}\\
&\text{Sum: } \mathrm{C(s) + \tfrac{1}{2}O_2(g) + CO(g) + \tfrac{1}{2}O_2(g) \longrightarrow CO(g) + CO_2(g)}
\end{aligned}$$

Because the CO produced in Step 1 is consumed in Step 2, the net change is:

$$\mathrm{C_{(s)} + O_{2(g)} \longrightarrow CO_{2(g)}} \tag{8.8.4}$$

According to Hess's law, the enthalpy change of the reaction will equal the sum of the enthalpy changes of the steps. We can apply the data from the experimental enthalpies of combustion in Table 8.8.1 to find the enthalpy change of the entire reaction from its two steps:

$$\begin{aligned}
&\mathrm{C(s) + \tfrac{1}{2}O_2(g) \longrightarrow CO(g)} && \Delta H^\circ_{298} = -111\ kJ\\
&\mathrm{CO(g) + \tfrac{1}{2}O_2(g) \longrightarrow CO_2(g)} && \Delta H^\circ_{298} = -283\ kJ\\
&\overline{\mathrm{C(s) + O_2(g) \longrightarrow CO_2(g)}} && \overline{\Delta H^\circ_{298} = -394\ kJ}
\end{aligned}$$

The result is shown in Figure 8.8.6. We see that ΔH of the overall reaction is the same whether it occurs in one step or two. This finding (overall ΔH for the reaction = sum of Δ*H* values for reaction "steps" in the overall reaction) is true in general for chemical and physical processes.




Figure **8.8.6**: The formation of CO_2(g) from its elements can be thought of as occurring in two steps, which sum to the overall reaction, as described by Hess's law. The horizontal blue lines represent enthalpies. For an exothermic process, the products are at lower enthalpy than are the reactants.

Before we further practice using Hess's law, let us recall two important features of ΔH.

1. ΔH is directly proportional to the quantities of reactants or products. For example, the enthalpy change for the reaction forming 1 mole of $NO_2(g)$ is +33.2 kJ:

$$\frac{1}{2}N_2(g) + O_2(g) \longrightarrow NO_2(g) \quad \Delta H = +33.2\,kJ \tag{8.8.5}$$

When 2 moles of NO_2 (twice as much) are formed, the ΔH will be twice as large:

$$N_2(g) + 2\,O_2(g) \longrightarrow 2\,NO_2(g) \quad \Delta H = +66.4\,kJ \tag{8.8.6}$$

In general, if we multiply or divide an equation by a number, then the enthalpy change should also be multiplied or divided by the same number.

2. ΔH for a reaction in one direction is equal in magnitude and opposite in sign to ΔH for the reaction in the reverse direction. For example, given that:

$$H_2(g) + Cl_2(g) \longrightarrow 2\,HCl(g) \quad \Delta H = -184.6\,kJ \tag{8.8.7}$$

Then, for the "reverse" reaction, the enthalpy change is also "reversed":

$$2\,HCl(g) \longrightarrow H_2(g) + Cl_2(g) \quad \Delta H = +184.6\,kJ \tag{8.8.8}$$

✔ Example 8.8.6: Stepwise Calculation of ΔH_f°

Using Hess's Law Determine the enthalpy of formation, ΔH_f°, of $FeCl_3$(s) from the enthalpy changes of the following two-step process that occurs under standard state conditions:

$$Fe(s) + Cl_2(g) \longrightarrow FeCl_2(s) \quad \Delta H^\circ = -341.8\,kJ$$

$$FeCl_2(s) + \frac{1}{2}Cl_2(g) \longrightarrow FeCl_3(s) \quad \Delta H^\circ = -57.7\,kJ$$

Solution

We are trying to find the standard enthalpy of formation of FeCl3(s), which is equal to ΔH° for the reaction:

$$Fe(s) + \frac{3}{2}Cl_2(g) \longrightarrow FeCl_3(s) \quad \Delta H_f^\circ = ?$$

Looking at the reactions, we see that the reaction for which we want to find ΔH° is the sum of the two reactions with known ΔH values, so we must sum their ΔHs:

$$\mathrm{Fe}(s) + \mathrm{Cl_2}(g) \longrightarrow \mathrm{FeCl_2}(s) \qquad \Delta H° = -341.8\ \mathrm{kJ}$$
$$\mathrm{FeCl_2}(s) + \frac{1}{2}\mathrm{Cl_2}(g) \longrightarrow \mathrm{FeCl_3}(s) \qquad \Delta H° = -57.7\ \mathrm{kJ}$$
$$\mathrm{Fe}(s) + \frac{1}{2}\mathrm{Cl_2}(g) \longrightarrow \mathrm{FeCl_3}(s) \qquad \Delta H° = -399.5\ \mathrm{kJ}$$

The enthalpy of formation, ΔH_f°, of $FeCl_3$(s) is −399.5 kJ/mol.

? Exercise 8.8.6

Calculate ΔH for the process:

$$\mathrm{N_2}(g) + 2\,\mathrm{O_2}(g) \longrightarrow 2\,\mathrm{NO_2}(g)$$

from the following information:

$$\mathrm{N_2}(g) + \mathrm{O_2}(g) \longrightarrow 2\,\mathrm{NO}(g) \quad \Delta H = 180.5\ \mathrm{kJ}$$

$$\mathrm{NO}(g) + \frac{1}{2}\mathrm{O_2}(g) \longrightarrow \mathrm{NO_2}(g) \quad \Delta H = -57.06\ \mathrm{kJ}$$

Answer

66.4 kJ

Here is a less straightforward example that illustrates the thought process involved in solving many Hess's law problems. It shows how we can find many standard enthalpies of formation (and other values of Δ*H*) if they are difficult to determine experimentally.

✓ Example 8.8.7: A More Challenging Problem

Using Hess's Law Chlorine monofluoride can react with fluorine to form chlorine trifluoride:

$$\text{(i)}\ \mathrm{ClF}(g) + \mathrm{F_2}(g) \longrightarrow \mathrm{ClF_3}(g) \quad \Delta H° = ?$$

Use the reactions here to determine the ΔH° for reaction (i):

$$\text{(ii)}\ 2\,\mathrm{OF_2}(g) \longrightarrow \mathrm{O_2}(g) + 2\,\mathrm{F_2}(g) \quad \Delta H°_{(ii)} = -49.4\ \mathrm{kJ}$$

$$\text{(iii)}\ 2\,\mathrm{ClF}(g) + \mathrm{O_2}(g) \longrightarrow \mathrm{Cl_2O}(g) + \mathrm{OF_2}(g) \quad \Delta H°_{(iii)} = +205.6\ \mathrm{kJ}$$

$$\text{(iv)}\ \mathrm{ClF_3}(g) + \mathrm{O_2}(g) \longrightarrow \tfrac{1}{2}\mathrm{Cl_2O}(g) + \frac{3}{2}\mathrm{OF_2}(g) \quad \Delta H°_{(iv)} = +266.7\ \mathrm{kJ}$$

Solution

Our goal is to manipulate and combine reactions (ii), (iii), and (iv) such that they add up to reaction (i). Going from left to right in (i), we first see that $\mathrm{ClF}_{(g)}$ is needed as a reactant. This can be obtained by multiplying reaction (iii) by $\frac{1}{2}$, which means that the ΔH° change is also multiplied by $\frac{1}{2}$:

$$\mathrm{ClF}(g) + \frac{1}{2}\mathrm{O_2}(g) \longrightarrow \frac{1}{2}\mathrm{Cl_2O}(g) + \frac{1}{2}\mathrm{OF_2}(g) \quad \Delta H° = \frac{1}{2}(205.6) = +102.8\ k\,\mathrm{J}$$

Next, we see that $\mathrm{F_2}$ is also needed as a reactant. To get this, reverse and halve reaction (ii), which means that the ΔH° changes sign and is halved:

$$\frac{1}{2}\mathrm{O_2}(g) + \mathrm{F_2}(g) \longrightarrow \mathrm{OF_2}(g) \quad \Delta H° = +24.7\ k\,\mathrm{J}$$

To get ClF_3 as a product, reverse (iv), changing the sign of ΔH°:

$$\frac{1}{2}\mathrm{Cl_2O}(g) + \frac{3}{2}\mathrm{OF_2}(g) \longrightarrow \mathrm{ClF_3}(g) + \mathrm{O_2}(g) \quad \Delta H° = -266.7\ \mathrm{kJ}$$

Now check to make sure that these reactions add up to the reaction we want:

$$\begin{aligned}
&\mathrm{ClF}(g) + \frac{1}{2}\mathrm{O_2}(g) \longrightarrow \frac{1}{2}\mathrm{Cl_2O}(g) + \frac{1}{2}\mathrm{OF_2}(g) && \Delta H° = +102.8\ \mathrm{kJ}\\
&\frac{1}{2}\mathrm{O_2}(g) + \mathrm{F_2}(g) \longrightarrow \mathrm{OF_2}(g) && \Delta H° = +24.7\ \mathrm{kJ}\\
&\frac{1}{2}\mathrm{Cl_2O}(g) + \frac{3}{2}\mathrm{OF_2}(g) \longrightarrow \mathrm{ClF_3}(g) + \mathrm{O_2}(g) && \Delta H° = -266.7\ \mathrm{kJ}\\
&\overline{\mathrm{ClF}(g) + \mathrm{F_2} \longrightarrow \mathrm{ClF_3}(g)} && \overline{\Delta H° = -139.2\ \mathrm{kJ}}
\end{aligned}$$

Reactants $\frac{1}{2}\mathrm{O_2}$ and $\frac{1}{2}\mathrm{O_2}$ cancel out product O_2; product $\frac{1}{2}\mathrm{Cl_2O}$ cancels reactant $\frac{1}{2}\mathrm{Cl_2O}$; and reactant $\frac{3}{2}\mathrm{OF_2}$ is cancelled by products $\frac{1}{2}\mathrm{OF_2}$ and OF_2. This leaves only reactants ClF(g) and F_2(g) and product ClF_3(g), which are what we want. Since summing these three modified reactions yields the reaction of interest, summing the three modified ΔH° values will give the desired ΔH°:

$$\Delta H° = (+102.8\ \mathrm{kJ}) + (24.7\ \mathrm{kJ}) + (-266.7\ \mathrm{kJ}) = -139.2\ \mathrm{kJ}$$

? Exercise 8.8.7

Aluminum chloride can be formed from its elements:

$$\text{(i)}\ 2\,\mathrm{Al}(s) + 3\,\mathrm{Cl_2}(g) \longrightarrow 2\,\mathrm{AlCl_3}(s) \quad \Delta H° = ?$$

Use the reactions here to determine the ΔH° for reaction (i):

$$\text{(ii)}\ \mathrm{HCl}(g) \longrightarrow \mathrm{HCl}(aq) \quad \Delta H°_{(ii)} = -74.8\ \mathrm{kJ}$$

$$\text{(iii)}\ \mathrm{H_2}(g) + \mathrm{Cl_2}(g) \longrightarrow 2\,\mathrm{HCl}(g) \quad \Delta H°_{(iii)} = -185\ \mathrm{kJ}$$

$$\text{(iv)}\ \mathrm{AlCl_3}(aq) \longrightarrow \mathrm{AlCl_3}(s) \quad \Delta H°_{(iv)} = +323\ \mathrm{kJ/mol}$$

$$\text{(v)}\ 2\,\mathrm{Al}(s) + 6\,\mathrm{HCl}(aq) \longrightarrow 2\,\mathrm{AlCl_3}(aq) + 3\,\mathrm{H_2}(g) \quad \Delta H°_{(v)} = -1049\ \mathrm{kJ}$$

Answer

−1407 kJ



Hess's Law: https://youtu.be/hisUr1fikFU

We also can use Hess's law to determine the enthalpy change of any reaction if the corresponding enthalpies of formation of the reactants and products are available. The stepwise reactions we consider are: (i) decompositions of the reactants into their component elements (for which the enthalpy changes are proportional to the negative of the enthalpies of formation of the reactants), followed by (ii) re-combinations of the elements to give the products (with the enthalpy changes proportional to the enthalpies of formation of the products). The standard enthalpy change of the overall reaction is therefore equal to: (ii) the sum of the standard enthalpies of formation of all the products plus (i) the sum of the negatives of the standard enthalpies of formation of the reactants. This is usually rearranged slightly to be written as follows, with $\sum$ representing "the sum of" and *n* standing for the stoichiometric coefficients:

$$\Delta H^\circ_{\text{reaction}} = \sum n \times \Delta H^\circ_f(\text{products}) - \sum n \times \Delta H^\circ_f(\text{reactants}) \tag{8.8.9}$$

The following example shows in detail why this equation is valid, and how to use it to calculate the enthalpy change for a reaction of interest.

Example 8.8.8: Using Hess's Law

What is the standard enthalpy change for the reaction:

$$3\,NO_2(g) + H_2O(l) \longrightarrow 2\,HNO_3(aq) + NO(g) \quad \Delta H^\circ = ?$$

Solution 1: Using the Equation

Alternatively, we could use the special form of Hess's law given previously:

$$\Delta H^\circ_{\text{reaction}} = \sum n \times \Delta H^\circ_f(\text{products}) - \sum n \times \Delta H^\circ_f(\text{reactants})$$

$$= \left[2\ \cancel{\text{mol HNO}_3} \times \frac{-207.4\ \text{kJ}}{\cancel{\text{mol HNO}_3\,(aq)}} + 1\ \cancel{\text{mol NO}\,(g)} \times \frac{+90.2\ \text{kJ}}{\cancel{\text{mol NO}\,(g)}}\right]$$

$$- \left[3\ \cancel{\text{mol NO}_2(g)} \times \frac{+33.2\ \text{kJ}}{\cancel{\text{mol NO}_2\,(g)}} + 1\ \cancel{\text{mol H}_2\text{O}\,(l)} \times \frac{-285.8\ \text{kJ}}{\cancel{\text{mol H}_2\text{O}\,(l)}}\right]$$

$$= 2(-207.4\ \text{kJ}) + 1(+90.2\ \text{kJ}) - 3(+33.2\ \text{kJ}) - 1(-285.8\ \text{kJ})$$

$$= -138.4\ \text{kJ}$$

Solution 2: Supporting Why the General Equation Is Valid

We can write this reaction as the sum of the decompositions of $3NO_2(g)$ and $1H_2O(l)$ into their constituent elements, and the formation of 2 $HNO_3(aq)$ and 1 $NO(g)$ from their constituent elements. Writing out these reactions, and noting their relationships to the ΔH°_f values for these compounds (from Tables T1 and T2), we have:

$$3\,NO_2(g) \longrightarrow \frac{3}{2}N_2(g) + 3O_2(g) \quad \Delta H^\circ_1 = -99.6\ \text{kJ}$$

$$H_2O(l) \longrightarrow H_2(g) + \frac{1}{2}O_2(g) \quad \Delta H^\circ_2 = +285.8\ kJ\ [-1 \times \Delta H^\circ_f(H_2O)]$$

$$H_2(g) + N_2(g) + 3O_2(g) \longrightarrow 2\,HNO_3(aq) \quad \Delta H^\circ_3 = -414.8\ kJ\ [2 \times \Delta H^\circ_f(HNO_3)]$$

$$\frac{1}{2}N_2(g) + \frac{1}{2}O_2(g) \longrightarrow NO(g) \quad \Delta H^\circ_4 = +90.2\ kJ\ [1 \times (NO)]$$

Summing these reaction equations gives the reaction we are interested in:

$$3\,NO_2(g) + H_2O(l) \longrightarrow 2\,HNO_3(aq) + NO(g)$$

Summing their enthalpy changes gives the value we want to determine:

$$\Delta H^\circ_{\text{rxn}} = \Delta H^\circ_1 + \Delta H^\circ_2 + \Delta H^\circ_3 + \Delta H^\circ_4 = (-99.6\ \text{kJ}) + (+285.8\ \text{kJ}) + (-414.8\ \text{kJ}) + (+90.2\ \text{kJ})$$
$$= -138.4\ \text{kJ}$$

So the standard enthalpy change for this reaction is $\Delta H^\circ = -138.4$ kJ.

Note that this result was obtained by:

1. multiplying the ΔH°_f of each product by its stoichiometric coefficient and summing those values,
2. multiplying the ΔH°_f of each reactant by its stoichiometric coefficient and summing those values, and then
3. subtracting the result found in step 2 from the result found in step 1.

This is also the procedure in using the general equation, as shown.

Exercise 8.8.8

Calculate the heat of combustion of 1 mole of ethanol, $C_2H_5OH(l)$, when $H_2O(l)$ and $CO_2(g)$ are formed. Use the following enthalpies of formation: $C_2H_5OH(l)$, −278 kJ/mol; $H_2O(l)$, −286 kJ/mol; and $CO_2(g)$, −394 kJ/mol.

Answer

−1368 kJ/mol

Summary

Many of the processes are carried out at 298.15 K. If the enthalpies of formation are available for the reactants and products of a reaction, the enthalpy change can be calculated using Hess's law: If a process can be written as the sum of several stepwise processes, the enthalpy change of the total process equals the sum of the enthalpy changes of the various steps.

Key Equations

- $\Delta U = q + w$
- $\Delta H^\circ_{\text{reaction}} = \sum n \times \Delta H^\circ_f(\text{products}) - \sum n \times \Delta H^\circ_f(\text{reactants})$

Footnotes

1. 1 For more on algal fuel, see www.theguardian.com/environme...n-fuel-problem.

Glossary

Hess's law

if a process can be represented as the sum of several steps, the enthalpy change of the process equals the sum of the enthalpy changes of the steps

---

8.8: Calculating Enthalpy of Reactions Using Hess's Law is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **5.4: Enthalpy** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

8.9: End of Chapter Problems

1. A burning match and a bonfire may have the same temperature, yet you would not sit around a burning match on a fall evening to stay warm. Why not?

Answer

The temperature of 1 gram of burning wood is approximately the same for both a match and a bonfire. This is an intensive property and depends on the material (wood). However, the overall amount of produced heat depends on the amount of material; this is an extensive property. The amount of wood in a bonfire is much greater than that in a match; the total amount of produced heat is also much greater, which is why we can sit around a bonfire to stay warm, but a match would not provide enough heat to keep us from getting cold.

2. Prepare a table identifying several energy transitions that take place during the typical operation of an automobile.
3. Explain the difference between heat capacity and specific heat of a substance.

Answer

Heat capacity refers to the heat required to raise the temperature of the mass of the substance 1 degree; specific heat refers to the heat required to raise the temperature of 1 gram of the substance 1 degree. Thus, heat capacity is an extensive property, and specific heat is an intensive one.

4. Calculate the heat capacity, in joules and in calories per degree, of the following:

    a. 28.4 g of water
    b. 1.00 oz of lead

5. Calculate the heat capacity, in joules and in calories per degree, of the following:

    a. 45.8 g of nitrogen gas
    b. 1.00 pound of aluminum metal

Answer

a. 47.6 J/°C; 11.38 cal $°C^{-1}$; b. 407 J/°C; 97.3 cal $°C^{-1}$

6. How much heat, in joules and in calories, must be added to a 75.0–g iron block with a specific heat of 0.449 J/g °C to increase its temperature from 25 °C to its melting temperature of 1535 °C?

Answer

$q = mC\Delta °T$

$q = (75.0g) \times (\frac{0.449\ J}{g\ °C}) \times (1,510°K) = 50,800J$

50,800J ; 12,200cal

7. How much heat, in joules and in calories, is required to heat a 28.4-g (1-oz) ice cube from −23.0 °C to −1.0 °C?

Answer

1310 J; 313 cal

8. How much would the temperature of 275 g of water increase if 36.5 kJ of heat were added?

Answer

ΔT° = 31.7° C

9. If 14.5 kJ of heat were added to 485 g of liquid water, how much would its temperature increase?

Answer

7.15 °C

10. A piece of unknown substance weighs 44.7 g and requires 2110 J to increase its temperature from 23.2 °C to 89.6 °C.
    a. What is the specific heat of the substance?
    b. If it is one of the substances found in Table, what is its likely identity?

Answer

a.) Solve for the specific heat C and compare the values with the chart

$$q = mC\Delta°T$$

$$2110J = (44.7\,g)(C)(66.4°C)$$

$$C = \frac{2110\,J}{2970\,g\,°C}$$

$$C = \frac{0.711\,J}{g\,°C}$$

b.) Silicon

11. A piece of unknown solid substance weighs 437.2 g, and requires 8460 J to increase its temperature from 19.3 °C to 68.9 °C.

a. What is the specific heat of the substance?
b. If it is one of the substances found in Table, what is its likely identity?

Answer

a. 0.390 J/g °C; b. Copper is a likely candidate.

12. An aluminum kettle weighs 1.05 kg.
    a. What is the heat capacity of the kettle?
    b. How much heat is required to increase the temperature of this kettle from 23.0 °C to 99.0 °C?
    c. How much heat is required to heat this kettle from 23.0 °C to 99.0 °C if it contains 1.25 L of water (density of 0.997 g/mL and a specific heat of 4.184 J/g °C)?

13. Most people find waterbeds uncomfortable unless the water temperature is maintained at about 85 °F. Unless it is heated, a waterbed that contains 892 L of water cools from 85 °F to 72 °F in 24 hours. Estimate the amount of electrical energy required over 24 hours, in kWh, to keep the bed from cooling. Note that 1 kilowatt-hour (kWh) = 3.6×10^6 J, and assume that the density of water is 1.0 g/mL (independent of temperature). What other assumptions did you make? How did they affect your calculated result (i.e., were they likely to yield “positive” or “negative” errors)?

Answer

We assume that the density of water is 1.0 g/cm^3(1 g/mL) and that it takes as much energy to keep the water at 85 °F as to heat it from 72 °F to 85 °F. We also assume that only the water is going to be heated. Energy required = 7.47 kWh

14. A 500-mL bottle of water at room temperature and a 2-L bottle of water at the same temperature were placed in a refrigerator. After 30 minutes, the 500-mL bottle of water had cooled to the temperature of the refrigerator. An hour later, the 2-L of water had cooled to the same temperature. When asked which sample of water lost the most heat, one student replied that both bottles lost the same amount of heat because they started at the same temperature and finished at the same temperature. A second student thought that the 2-L bottle of water lost more heat because there was more water. A third student believed that the 500-mL bottle of water lost more heat because it cooled more quickly. A fourth student thought that it was not possible to tell because we do not know the initial temperature and the final temperature of the water. Indicate which of these answers is correct and describe the error in each of the other answers.
15. Would the amount of heat measured for the reaction in Example be greater, lesser, or remain the same if we used a calorimeter that was a poorer insulator than a coffee cup calorimeter? Explain your answer.

Answer

lesser; more heat would be lost to the coffee cup and the environment and so ΔT for the water would be lesser and the calculated q would be lesser

16. Would the amount of heat absorbed by the dissolution in Example appear greater, lesser, or remain the same if the experimenter used a calorimeter that was a poorer insulator than a coffee cup calorimeter? Explain your answer.
17. Would the amount of heat absorbed by the dissolution in Example appear greater, lesser, or remain the same if the heat capacity of the calorimeter were taken into account? Explain your answer.

Answer

greater, since taking the calorimeter's heat capacity into account will compensate for the thermal energy transferred to the solution from the calorimeter; this approach includes the calorimeter itself, along with the solution, as "surroundings": $q_{rxn} = -(q_{solution} + q_{calorimeter})$; since both $q_{solution}$ and $q_{calorimeter}$ are negative, including the latter term (q_{rxn}) will yield a greater value for the heat of the dissolution

18. How many milliliters of water at 23 °C with a density of 1.00 g/mL must be mixed with 180 mL (about 6 oz) of coffee at 95 °C so that the resulting combination will have a temperature of 60 °C? Assume that coffee and water have the same density and the same specific heat.
19. How much will the temperature of a cup (180 g) of coffee at 95 °C be reduced when a 45 g silver spoon (specific heat 0.24 J/g °C) at 25 °C is placed in the coffee and the two are allowed to reach the same temperature? Assume that the coffee has the same density and specific heat as water.

Answer

The temperature of the coffee will drop 1 degree.

20. A 45-g aluminum spoon (specific heat 0.88 J/g °C) at 24 °C is placed in 180 mL (180 g) of coffee at 85 °C and the temperature of the two become equal.
    a. What is the final temperature when the two become equal? Assume that coffee has the same specific heat as water.
    b. The first time a student solved this problem she got an answer of 88 °C. Explain why this is clearly an incorrect answer.
21. The temperature of the cooling water as it leaves the hot engine of an automobile is 240 °F. After it passes through the radiator it has a temperature of 175 °F. Calculate the amount of heat transferred from the engine to the surroundings by one gallon of water with a specific heat of 4.184 J/g °C.

Answer

$5.7 \times 10^2\ kJ$

22. A 70.0-g piece of metal at 80.0 °C is placed in 100 g of water at 22.0 °C contained in a calorimeter like that shown in Figure. The metal and water come to the same temperature at 24.6 °C. How much heat did the metal give up to the water? What is the specific heat of the metal?
23. If a reaction produces 1.506 kJ of heat, which is trapped in 30.0 g of water initially at 26.5 °C in a calorimeter like that in Figure, what is the resulting temperature of the water?

Answer

38.5 °C

24. A 0.500-g sample of KCl is added to 50.0 g of water in a calorimeter (Figure). If the temperature decreases by 1.05 °C, what is the approximate amount of heat involved in the dissolution of the KCl, assuming the heat capacity of the resulting solution is 4.18 J/g °C? Is the reaction exothermic or endothermic?
25. Dissolving 3.0 g of $CaCl_2(s)$ in 150.0 g of water in a calorimeter (Figure) at 22.4 °C causes the temperature to rise to 25.8 °C. What is the approximate amount of heat involved in the dissolution, assuming the heat capacity of the resulting solution is 4.18 J/g °C? Is the reaction exothermic or endothermic?

Answer

2.2 kJ; The heat produced shows that the reaction is exothermic.

26. When 50.0 g of 0.200 M NaCl(*aq*) at 24.1 °C is added to 100.0 g of 0.100 M $AgNO_3$(*aq*) at 24.1 °C in a calorimeter, the temperature increases to 25.2 °C as AgCl(*s*) forms. Assuming the specific heat of the solution and products is 4.20 J/g °C, calculate the approximate amount of heat in joules produced.

27. The addition of 3.15 g of $Ba(OH)_2$•$8H_2O$ to a solution of 1.52 g of NH_4SCN in 100 g of water in a calorimeter caused the temperature to fall by 3.1 °C. Assuming the specific heat of the solution and products is 4.20 J/g °C, calculate the approximate amount of heat absorbed by the reaction, which can be represented by the following equation:

$$Ba(OH)_2 \cdot 8H_2O_{(s)} + 2NH_4SCN_{(aq)} \rightarrow Ba(SCN)_{2(aq)} + 2NH_{3(aq)} + 10H_2O_{(l)} \tag{8.9.1}$$

Answer

1.4 kJ

28. The reaction of 50 mL of acid and 50 mL of base described in Example increased the temperature of the solution by 6.9 degrees. How much would the temperature have increased if 100 mL of acid and 100 mL of base had been used in the same calorimeter starting at the same temperature of 22.0 °C? Explain your answer.

29. If the 3.21 g of NH_4NO_3 in Example were dissolved in 100.0 g of water under the same conditions, how much would the temperature change? Explain your answer.

Answer

22.6. Since the mass and the heat capacity of the solution is approximately equal to that of the water, the two-fold increase in the amount of water leads to a two-fold decrease of the temperature change.

30. When 1.0 g of fructose, $C_6H_{12}O_6$(*s*), a sugar commonly found in fruits, is burned in oxygen in a bomb calorimeter, the temperature of the calorimeter increases by 1.58 °C. If the heat capacity of the calorimeter and its contents is 9.90 kJ/°C, what is *q* for this combustion?

31. When a 0.740-g sample of trinitrotoluene (TNT), $C_7H_5N_2O_6$, is burned in a bomb calorimeter, the temperature increases from 23.4 °C to 26.9 °C. The heat capacity of the calorimeter is 534 J/°C, and it contains 675 mL of water. How much heat was produced by the combustion of the TNT sample?

Answer

11.7 kJ

32. One method of generating electricity is by burning coal to heat water, which produces steam that drives an electric generator. To determine the rate at which coal is to be fed into the burner in this type of plant, the heat of combustion per ton of coal must be determined using a bomb calorimeter. When 1.00 g of coal is burned in a bomb calorimeter, the temperature increases by 1.48 °C. If the heat capacity of the calorimeter is 21.6 kJ/°C, determine the heat produced by combustion of a ton of coal (2.000×10^3 pounds).

33. The amount of fat recommended for someone with a daily diet of 2000 Calories is 65 g. What percent of the calories in this diet would be supplied by this amount of fat if the average number of Calories for fat is 9.1 Calories/g?

Answer

30%

34. A teaspoon of the carbohydrate sucrose (common sugar) contains 16 Calories (16 kcal). What is the mass of one teaspoon of sucrose if the average number of Calories for carbohydrates is 4.1 Calories/g?

35. What is the maximum mass of carbohydrate in a 6-oz serving of diet soda that contains less than 1 Calorie per can if the average number of Calories for carbohydrates is 4.1 Calories/g?

Answer

0.24 g

36. A pint of premium ice cream can contain 1100 Calories. What mass of fat, in grams and pounds, must be produced in the body to store an extra 1.1×10^3 Calories if the average number of Calories for fat is 9.1 Calories/g?

37. A serving of a breakfast cereal contains 3 g of protein, 18 g of carbohydrates, and 6 g of fat. What is the Calorie content of a serving of this cereal if the average number of Calories for fat is 9.1 Calories/g, for carbohydrates is 4.1 Calories/g, and for protein is 4.1 Calories/g?

Answer

1.4×10^2 Calories

38. Which is the least expensive source of energy in kilojoules per dollar: a box of breakfast cereal that weighs 32 ounces and costs $4.23, or a liter of isooctane (density, 0.6919 g/mL) that costs $0.45? Compare the nutritional value of the cereal with the heat produced by combustion of the isooctane under standard conditions. A 1.0-ounce serving of the cereal provides 130 Calories.

39. Explain how the heat measured in [link] differs from the enthalpy change for the exothermic reaction described by the following equation:

$$\mathrm{HCl}(aq) + \mathrm{NaOH}(aq) \longrightarrow \mathrm{NaCl}(aq) + \mathrm{H_2O}(l) \tag{8.9.2}$$

The enthalpy change of the indicated reaction is for exactly 1 mol HCL and 1 mol NaOH; the heat in the example is produced by 0.0500 mol HCl and 0.0500 mol NaOH. Using the data in the check your learning section of [link], calculate ΔH in kJ/mol of $AgNO_3(aq)$ for the reaction:

$$\mathrm{NaCl}(aq) + \mathrm{AgNO_3}(aq) \longrightarrow \mathrm{AgCl}(s) + \mathrm{NaNO_3}(aq) \tag{8.9.3}$$

40. Calculate the enthalpy of solution (ΔH for the dissolution) per mole of NH_4NO_3 under the conditions described in [link].

Answer

25 kJ mol^{-1}

41. Calculate ΔH for the reaction described by the equation.

$$\mathrm{Ba(OH)_2 \cdot 8\,H_2O}(s) + 2\,\mathrm{NH_4SCN}(aq) \longrightarrow \mathrm{Ba(SCN)_2}(aq) + 2\,\mathrm{NH_3}(aq) + 10\,\mathrm{H_2O}(l)$$

42. Calculate the enthalpy of solution (ΔH for the dissolution) per mole of $CaCl_2$.

Answer

81 kJ mol^{-1}

43. Although the gas used in an oxyacetylene torch is essentially pure acetylene, the heat produced by combustion of one mole of acetylene in such a torch is likely not equal to the enthalpy of combustion of acetylene listed in Table. Considering the conditions for which the tabulated data are reported, suggest an explanation.

44. How much heat is produced by burning 4.00 moles of acetylene under standard state conditions?

Answer

5204.4 kJ

45. How much heat is produced by combustion of 125 g of methanol under standard state conditions?

46. How many moles of isooctane must be burned to produce 100 kJ of heat under standard state conditions?

Answer

1.83×10^{-2} mol

47. What mass of carbon monoxide must be burned to produce 175 kJ of heat under standard state conditions?

48. When 2.50 g of methane burns in oxygen, 125 kJ of heat is produced. What is the enthalpy of combustion per mole of methane under these conditions?

Answer

802 kJ mol^{-1}

49. How much heat is produced when 100 mL of 0.250 M HCl (density, 1.00 g/mL) and 200 mL of 0.150 M NaOH (density, 1.00 g/mL) are mixed?

$$\mathrm{HCl}(aq) + \mathrm{NaOH}(aq) \longrightarrow \mathrm{NaCl}(aq) + \mathrm{H_2O}(l) \quad \Delta H^\circ_{298} = -58\ \mathrm{kJ} \tag{8.9.4}$$

If both solutions are at the same temperature and the heat capacity of the products is 4.19 J/g °C, how much will the temperature increase? What assumption did you make in your calculation?

50. A sample of 0.562 g of carbon is burned in oxygen in a bomb calorimeter, producing carbon dioxide. Assume both the reactants and products are under standard state conditions, and that the heat released is directly proportional to the enthalpy of combustion of graphite. The temperature of the calorimeter increases from 26.74 °C to 27.93 °C. What is the heat capacity of the calorimeter and its contents?

Answer

15.5 kJ/°C

51. Before the introduction of chlorofluorocarbons, sulfur dioxide (enthalpy of vaporization, 6.00 kcal/mol) was used in household refrigerators. What mass of SO_2 must be evaporated to remove as much heat as evaporation of 1.00 kg of CCl_2F_2 (enthalpy of vaporization is 17.4 kJ/mol)?

The vaporization reactions for SO_2 and CCl_2F_2 are

$\mathrm{SO_2}(l) \longrightarrow \mathrm{SO_2}(g)$ and $\mathrm{CCl_2F}(l) \longrightarrow \mathrm{CCl_2F_2}(g)$, respectively.

52. Homes may be heated by pumping hot water through radiators. What mass of water will provide the same amount of heat when cooled from 95.0 to 35.0 °C, as the heat provided when 100 g of steam is cooled from 110 °C to 100 °C.

Answer

7.43 g

53. Which of the enthalpies of combustion in Table the table are also standard enthalpies of formation?

54. Does the standard enthalpy of formation of $H_2O(g)$ differ from $\Delta H°$ for the reaction $\mathrm{2\,H_2}(g) + \mathrm{O_2}(g) \longrightarrow \mathrm{2\,H_2O}(g)$?

Answer

No.

55. Joseph Priestly prepared oxygen in 1774 by heating red mercury(II) oxide with sunlight focused through a lens. How much heat is required to decompose exactly 1 mole of red HgO(*s*) to Hg(*l*) and $O_2(g)$ under standard conditions?

56. How many kilojoules of heat will be released when exactly 1 mole of manganese, Mn, is burned to form $Mn_3O_4(s)$ at standard state conditions?

Answer

459.6 kJ

57. How many kilojoules of heat will be released when exactly 1 mole of iron, Fe, is burned to form Fe_2O_3(s) at standard state conditions?

58. The following sequence of reactions occurs in the commercial production of aqueous nitric acid:

$$\mathrm{4\,NH_3}(g) + \mathrm{5\,O_2}(g) \longrightarrow \mathrm{4\,NO}(g) + \mathrm{6\,H_2O}(l) \quad \Delta H = -907\ \mathrm{kJ}$$

$$2\,NO(g) + O_2(g) \longrightarrow 2\,NO_2(g) \quad \Delta H = -113\,kJ$$

$$3\,NO_2 + H_2O(l) \longrightarrow 2\,HNO_2(aq) + NO(g) \quad \Delta H = -139\,kJ$$

Determine the total energy change for the production of one mole of aqueous nitric acid by this process.

Answer

495 kJ/mol

59. Both graphite and diamond burn.

$$C(s,\ \text{diamond}) + O_2(g) \longrightarrow CO_2(g)$$

For the conversion of graphite to diamond:

$$C(s,\ \text{graphite}) \longrightarrow C(s,\ \text{diamond}) \quad \Delta H^\circ_{298} = 1.90\,kJ$$

Which produces more heat, the combustion of graphite or the combustion of diamond?

60. From the molar heats of formation in Appendix G, determine how much heat is required to evaporate one mole of water: $H_2O(l) \longrightarrow H_2O(g)$

Answer

44.01 kJ/mol

61. Which produces more heat?

$$Os(s) \longrightarrow 2\,O_2(g) \longrightarrow OsO_4(s)$$

or

$$Os(s) \longrightarrow 2\,O_2(g) \longrightarrow OsO_4(g)$$

for the phase change $OsO_4(s) \longrightarrow OsO_4(g) \quad \Delta H = 56.4\,kJ$

62. Calculate ΔH°_{298} for the process

$$Sb(s) + \frac{5}{2}Cl_2(g) \longrightarrow SbCl_5(g)$$

from the following information:

$$Sb(s) + \frac{3}{2}Cl_2(g) \longrightarrow SbCl_3(g) \quad \Delta H^\circ_{298} = -314\,kJ$$

$$SbCl_3(s) + Cl_2(g) \longrightarrow SbCl_5(g) \quad \Delta H^\circ_{298} = -80\,kJ$$

Answer

394 kJ

63. Calculate ΔH°_{298} for the process $Zn(s) + S(s) + 2\,O_2(g) \longrightarrow ZnSO_4(s)$

from the following information:

$$Zn(s) + S(s) \longrightarrow ZnS(s) \quad \Delta H^\circ_{298} = -206.0\,kJ$$

$$ZnS(s) + 2\,O_2(g) \longrightarrow ZnSO_4(s) \quad \Delta H^\circ_{298} = -776.8\,kJ$$

64. Calculate ΔH for the process

$$Hg_2Cl_2(s) \longrightarrow 2\,Hg(l) + Cl_2(g)$$

from the following information:

$Hg(l) + Cl_2(g) \longrightarrow HgCl_2(s) \quad \Delta H = -224\,kJ$

$Hg(l) + HgCl_2(s) \longrightarrow Hg_2Cl_2(s) \quad \Delta H = -41.2\,kJ$

Answer

265 kJ

65. Calculate ΔH°_{298} for the process

$$Co_3O_4(s) \longrightarrow 3\,Co(s) + 2\,O_2(g)$$

from the following information:

$$Co(s) + \frac{1}{2}O_2(g) \longrightarrow CoO(s) \quad \Delta H^\circ_{298} = -237.9\,kJ$$

$$3\,Co(s) + O_2(g) \longrightarrow Co_3O_4(s) \quad \Delta H^\circ_{298} = -177.5\,kJ$$

66. Calculate the standard molar enthalpy of formation of NO(g) from the following data:

$$N_2(g) + 2\,O_2 \longrightarrow 2\,NO_2(g) \quad \Delta H^\circ_{298} = 66.4\,kJ$$

$$2\,NO(g) + O_2 \longrightarrow 2\,NO_2(g) \quad \Delta H^\circ_{298} = -114.1\,kJ$$

Answer

90.3 mol^{-1} of NO

67. Using the data in Appendix G, calculate the standard enthalpy change for each of the following reactions:

a. $N_2(g) + O_2(g) \longrightarrow 2\,NO(g)$
b. $Si(s) + 2\,Cl_2(g) \longrightarrow SiCl_4(g)$
c. $Fe_2O_3(s) + 3\,H_2(g) \longrightarrow 2\,Fe(s) + 3\,H_2O(l)$
d. $2\,LiOH(s) + CO_2(g) \longrightarrow Li_2CO_3(s) + H_2O(g)$

68. Using the data in Appendix G, calculate the standard enthalpy change for each of the following reactions:

a. $Si(s) + 2\,F_2(g) \longrightarrow SiF_4(g)$
b. $2\,C(s) + 2\,H_2(g) + O_2(g) \longrightarrow CH_3CO_2H(l)$
c. $CH_4(g) + N_2(g) \longrightarrow HCN(g) + NH_3(g)$;
d. $CS_2(g) + 3\,Cl_2(g) \longrightarrow CCl_4(g) + S_2Cl_2(g)$

Answer

a. −1615.0 kJ mol^{-1};

b. −484.3 kJ mol^{-1};

c. 164.2 kJ;

d. −232.1 kJ

69. The following reactions can be used to prepare samples of metals. Determine the enthalpy change under standard state conditions for each.

a. $2\,Ag_2O(s) \longrightarrow 4\,Ag(s) + O_2(g)$
b. $SnO(s) + CO(g) \longrightarrow Sn(s) + CO_2(g)$
c. $Cr_2O_3(s) + 3\,H_2(g) \longrightarrow 2\,Cr(s) + 3\,H_2O(l)$
d. $2\,Al(s) + Fe_2O_3(s) \longrightarrow Al_2O_3(s) + 2\,Fe(s)$

70. The decomposition of hydrogen peroxide, H_2O_2, has been used to provide thrust in the control jets of various space vehicles. Using the data in Appendix G, determine how much heat is produced by the decomposition of exactly 1 mole of H_2O_2 under standard conditions.

$$2\,H_2O_2(l) \longrightarrow 2\,H_2O(g) + O_2(g)$$

Answer

−54.04 kJ mol^{-1}

71. Calculate the enthalpy of combustion of propane, $C_3H_8(g)$, for the formation of $H_2O(g)$ and $CO_2(g)$. The enthalpy of formation of propane is −104 kJ/mol.

Q5.3.34

72. Calculate the enthalpy of combustion of butane, $C_4H_{10}(g)$ for the formation of $H_2O(g)$ and $CO_2(g)$. The enthalpy of formation of butane is −126 kJ/mol.

Answer

2660 kJ mol^{-1}

73. Both propane and butane are used as gaseous fuels. Which compound produces more heat per gram when burned?

74. The white pigment TiO_2 is prepared by the reaction of titanium tetrachloride, $TiCl_4$, with water vapor in the gas phase:

$$\mathrm{TiCl_4}(g) + 2\,\mathrm{H_2O}(g) \longrightarrow \mathrm{TiO_2}(s) + 4\,\mathrm{HCl}(g).$$

How much heat is evolved in the production of exactly 1 mole of $TiO_2(s)$ under standard state conditions?

Answer

67.1 kJ

75. Water gas, a mixture of H_2 and CO, is an important industrial fuel produced by the reaction of steam with red hot coke, essentially pure carbon:

$$\mathrm{C}(s) + \mathrm{H_2O}(g) \longrightarrow \mathrm{CO}(g) + \mathrm{H_2}(g).$$

a. Assuming that coke has the same enthalpy of formation as graphite, calculate ΔH°_{298} for this reaction.
b. Methanol, a liquid fuel that could possibly replace gasoline, can be prepared from water gas and additional hydrogen at high temperature and pressure in the presence of a suitable catalyst:

$$2\,\mathrm{H_2}(g) + \mathrm{CO}(g) \longrightarrow \mathrm{CH_3OH}(g). \tag{8.9.5}$$

Under the conditions of the reaction, methanol forms as a gas. Calculate ΔH°_{298} for this reaction and for the condensation of gaseous methanol to liquid methanol.
c. Calculate the heat of combustion of 1 mole of liquid methanol to $H_2O(g)$ and $CO_2(g)$.

76. In the early days of automobiles, illumination at night was provided by burning acetylene, C_2H_2. Though no longer used as auto headlamps, acetylene is still used as a source of light by some cave explorers. The acetylene is (was) prepared in the lamp by the reaction of water with calcium carbide, CaC_2:

$$\mathrm{CaC_2}(s) + \mathrm{H_2O}(l) \longrightarrow \mathrm{Ca(OH)_2}(s) + \mathrm{C_2H_2}(g).$$

Calculate the standard enthalpy of the reaction. The ΔH°_f of CaC_2 is −15.14 kcal/mol.

Answer

122.8 kJ

77. From the data in Table, determine which of the following fuels produces the greatest amount of heat per gram when burned under standard conditions: $CO(g)$, $CH_4(g)$, or $C_2H_2(g)$.

78. The enthalpy of combustion of hard coal averages −35 kJ/g, that of gasoline, 1.28×10^5 kJ/gal. How many kilograms of hard coal provide the same amount of heat as is available from 1.0 gallon of gasoline? Assume that the density of gasoline is 0.692 g/mL (the same as the density of isooctane).

Answer

3.7 kg

79. Ethanol, C_2H_5OH, is used as a fuel for motor vehicles, particularly in Brazil.

a. Write the balanced equation for the combustion of ethanol to $CO_2(g)$ and $H_2O(g)$, and, using the data in Appendix G, calculate the enthalpy of combustion of 1 mole of ethanol.
b. The density of ethanol is 0.7893 g/mL. Calculate the enthalpy of combustion of exactly 1 L of ethanol.
c. Assuming that an automobile's mileage is directly proportional to the heat of combustion of the fuel, calculate how much farther an automobile could be expected to travel on 1 L of gasoline than on 1 L of ethanol. Assume that gasoline has the heat of combustion and the density of n–octane, C_8H_{18} ($\Delta H_f^\circ = -208.4\ \text{kJ/mol}$; density = 0.7025 g/mL).

80. Among the substances that react with oxygen and that have been considered as potential rocket fuels are diborane [B_2H_6, produces $B_2O_3(s)$ and $H_2O(g)$], methane [CH_4, produces $CO_2(g)$ and $H_2O(g)$], and hydrazine [N_2H_4, produces $N_2(g)$ and $H_2O(g)$]. On the basis of the heat released by 1.00 g of each substance in its reaction with oxygen, which of these compounds offers the best possibility as a rocket fuel? The ΔH_f° of $B_2H_6(g)$, $CH_4(g)$, and $N_2H_4(l)$ may be found in Appendix G.

Answer

On the assumption that the best rocket fuel is the one that gives off the most heat, B_2H_6 is the prime candidate.

81. How much heat is produced when 1.25 g of chromium metal reacts with oxygen gas under standard conditions?

Ethylene, C_2H_2, a byproduct from the fractional distillation of petroleum, is fourth among the 50 chemical compounds produced commercially in the largest quantities. About 80% of synthetic ethanol is manufactured from ethylene by its reaction with water in the presence of a suitable catalyst.

$$\mathrm{C_2H_4}(g) + \mathrm{H_2O}(g) \longrightarrow \mathrm{C_2H_5OH}(l)$$

Using the data in the table in Appendix G, calculate ΔH° for the reaction.

Answer

88.2 kJ

82. The oxidation of the sugar glucose, $C_6H_{12}O_6$, is described by the following equation:

$$\mathrm{C_6H_{12}O_6}(s) + 6\,\mathrm{O_2}(g) \longrightarrow 6\,\mathrm{CO_2}(g) + 6\,\mathrm{H_2O}(l) \quad \Delta H = -2816\ \text{kJ}$$

The metabolism of glucose gives the same products, although the glucose reacts with oxygen in a series of steps in the body.

a. How much heat in kilojoules can be produced by the metabolism of 1.0 g of glucose?
b. How many Calories can be produced by the metabolism of 1.0 g of glucose?

83. Propane, C_3H_8, is a hydrocarbon that is commonly used as a fuel.

a. Write a balanced equation for the complete combustion of propane gas.
b. Calculate the volume of air at 25 °C and 1.00 atmosphere that is needed to completely combust 25.0 grams of propane. Assume that air is 21.0 percent O_2 by volume. (Hint: we will see how to do this calculation in a later chapter on gases—for now use the information that 1.00 L of air at 25 °C and 1.00 atm contains 0.275 g of O_2 per liter.)
c. The heat of combustion of propane is −2,219.2 kJ/mol. Calculate the heat of formation, ΔH_f° of propane given that ΔH_f° of $H_2O(l)$ = −285.8 kJ/mol and ΔH_f° of $CO_2(g)$ = −393.5 kJ/mol.
d. Assuming that all of the heat released in burning 25.0 grams of propane is transferred to 4.00 kilograms of water, calculate the increase in temperature of the water.

Answer

a. $\mathrm{C_3H_8}(g) + 5\,\mathrm{O_2}(g) \longrightarrow 3\,\mathrm{CO_2}(g) + 4\,\mathrm{H_2O}(l)$;

b. 330 L;

c. −104.5 kJ mol^{-1};

d. 75.4 °C

84. During a recent winter month in Sheboygan, Wisconsin, it was necessary to obtain 3500 kWh of heat provided by a natural gas furnace with 89% efficiency to keep a small house warm (the efficiency of a gas furnace is the percent of the heat produced by

combustion that is transferred into the house).

a. Assume that natural gas is pure methane and determine the volume of natural gas in cubic feet that was required to heat the house. The average temperature of the natural gas was 56 °F; at this temperature and a pressure of 1 atm, natural gas has a density of 0.681 g/L.
b. How many gallons of LPG (liquefied petroleum gas) would be required to replace the natural gas used? Assume the LPG is liquid propane [C_3H_8: density, 0.5318 g/mL; enthalpy of combustion, 2219 kJ/mol for the formation of $CO_2(g)$ and $H_2O(l)$] and the furnace used to burn the LPG has the same efficiency as the gas furnace.
c. What mass of carbon dioxide is produced by combustion of the methane used to heat the house?
d. What mass of water is produced by combustion of the methane used to heat the house?
e. What volume of air is required to provide the oxygen for the combustion of the methane used to heat the house? Air contains 23% oxygen by mass. The average density of air during the month was 1.22 g/L.
f. How many kilowatt–hours (1 kWh = 3.6×10^6 J) of electricity would be required to provide the heat necessary to heat the house? Note electricity is 100% efficient in producing heat inside a house.
g. Although electricity is 100% efficient in producing heat inside a house, production and distribution of electricity is not 100% efficient. The efficiency of production and distribution of electricity produced in a coal-fired power plant is about 40%. A certain type of coal provides 2.26 kWh per pound upon combustion. What mass of this coal in kilograms will be required to produce the electrical energy necessary to heat the house if the efficiency of generation and distribution is 40%?

8.9: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

9: Electronic Structure and Periodic Table

9.1: The Nature of Light
9.2: Line Spectra and Bohr Model of Atoms
9.3: Wave Nature of Matter
9.4: The Quantum-Mechanical Model of an Atom
9.5: Electron Configuration of Atoms
9.6: Electron Configurations of Ions
9.7: Periodic Trends
9.8: End of Chapter Problems

9: Electronic Structure and Periodic Table is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

9.1: The Nature of Light

Learning Objectives

- Explain the basic behavior of waves, including traveling waves and standing waves
- Describe the wave nature of light
- Use appropriate equations to calculate related light-wave properties such as period, frequency, wavelength, and energy
- Distinguish between line and continuous emission spectra
- Describe the particle nature of light

The nature of light has been a subject of inquiry since antiquity. In the seventeenth century, Isaac Newton performed experiments with lenses and prisms and was able to demonstrate that white light consists of the individual colors of the rainbow combined together. Newton explained his optics findings in terms of a "corpuscular" view of light, in which light was composed of streams of extremely tiny particles traveling at high speeds according to Newton's laws of motion. Others in the seventeenth century, such as Christiaan Huygens, had shown that optical phenomena such as reflection and refraction could be equally well explained in terms of light as waves travelling at high speed through a medium called "luminiferous aether" that was thought to permeate all space. Early in the nineteenth century, Thomas Young demonstrated that light passing through narrow, closely spaced slits produced interference patterns that could not be explained in terms of Newtonian particles but could be easily explained in terms of waves. Later in the nineteenth century, after James Clerk Maxwell developed his theory of electromagnetic radiation and showed that light was the visible part of a vast spectrum of electromagnetic waves, the particle view of light became thoroughly discredited. By the end of the nineteenth century, scientists viewed the physical universe as roughly comprising two separate domains: matter composed of particles moving according to Newton's laws of motion, and electromagnetic radiation consisting of waves governed by Maxwell's equations. Today, these domains are referred to as classical mechanics and classical electrodynamics (or classical electromagnetism). Although there were a few physical phenomena that could not be explained within this framework, scientists at that time were so confident of the overall soundness of this framework that they viewed these aberrations as puzzling paradoxes that would ultimately be resolved somehow within this framework. As we shall see, these paradoxes led to a contemporary framework that intimately connects particles and waves at a fundamental level called wave-particle duality, which has superseded the classical view.

Visible light and other forms of electromagnetic radiation play important roles in chemistry, since they can be used to infer the energies of electrons within atoms and molecules. Much of modern technology is based on electromagnetic radiation. For example, radio waves from a mobile phone, X-rays used by dentists, the energy used to cook food in your microwave, the radiant heat from red-hot objects, and the light from your television screen are forms of electromagnetic radiation that all exhibit wavelike behavior.

Waves

A wave is an oscillation or periodic movement that can transport energy from one point in space to another. Common examples of waves are all around us. Shaking the end of a rope transfers energy from your hand to the other end of the rope, dropping a pebble into a pond causes waves to ripple outward along the water's surface, and the expansion of air that accompanies a lightning strike generates sound waves (thunder) that can travel outward for several miles. In each of these cases, kinetic energy is transferred through matter (the rope, water, or air) while the matter remains essentially in place. An insightful example of a wave occurs in sports stadiums when fans in a narrow region of seats rise simultaneously and stand with their arms raised up for a few seconds before sitting down again while the fans in neighboring sections likewise stand up and sit down in sequence. While this wave can quickly encircle a large stadium in a few seconds, none of the fans actually travel with the wave-they all stay in or above their seats.

Waves need not be restricted to travel through matter. As Maxwell showed, electromagnetic waves consist of an electric field oscillating in step with a perpendicular magnetic field, both of which are perpendicular to the direction of travel. These waves can travel through a vacuum at a constant speed of 2.998×10^8 m/s, the speed of light (denoted by c).

All waves, including forms of electromagnetic radiation, are characterized by, a wavelength (denoted by λ, the lowercase Greek letter lambda), a frequency (denoted by ν, the lowercase Greek letter nu), and an amplitude. As can be seen in Figure **9.1.1**, the wavelength is the distance between two consecutive peaks or troughs in a wave (measured in meters in the SI system).

Electromagnetic waves have wavelengths that fall within an enormous range-wavelengths of kilometers (10^3 m) to picometers (10^{-12} m) have been observed. The frequency is the number of wave cycles that pass a specified point in space in a specified amount of time (in the SI system, this is measured in seconds). A cycle corresponds to one complete wavelength. The unit for frequency, expressed as cycles per second [s^{-1}], is the hertz (Hz). Common multiples of this unit are megahertz, (1 MHz = 1×10^6 Hz) and gigahertz (1 GHz = 1×10^9 Hz). The amplitude corresponds to the magnitude of the wave's displacement and so, in Figure, this corresponds to one-half the height between the peaks and troughs. The amplitude is related to the intensity of the wave, which for light is the brightness, and for sound is the loudness.




Figure **9.1.1**: One-dimensional sinusoidal waves show the relationship among wavelength, frequency, and speed. The wave with the shortest wavelength has the highest frequency. Amplitude is one-half the height of the wave from peak to trough. (CC BY 4.0; OpenStax)

The product of a wave's wavelength (λ) and its frequency (ν), $\lambda\nu$, is the speed of the wave. Thus, for electromagnetic radiation in a vacuum:

$$c = 2.998 \times 10^8 \,\mathrm{ms}^{-1} = \lambda\nu \tag{9.1.1}$$

Wavelength and frequency are inversely proportional: As the wavelength increases, the frequency decreases. The inverse proportionality is illustrated in Figure **9.1.2**. This figure also shows the electromagnetic spectrum, the range of all types of electromagnetic radiation. Each of the various colors of visible light has specific frequencies and wavelengths associated with them, and you can see that visible light makes up only a small portion of the electromagnetic spectrum. Because the technologies developed to work in various parts of the electromagnetic spectrum are different, for reasons of convenience and historical legacies, different units are typically used for different parts of the spectrum. For example, radio waves are usually specified as frequencies (typically in units of MHz), while the visible region is usually specified in wavelengths (typically in units of nm or angstroms).




Figure 9.1.2: Portions of the electromagnetic spectrum are shown in order of decreasing frequency and increasing wavelength. Examples of some applications for various wavelengths include positron emission tomography (PET) scans, X-ray imaging, remote controls, wireless Internet, cellular telephones, and radios. (credit “Cosmic ray": modification of work by NASA; credit “PET scan": modification of work by the National Institute of Health; credit “X-ray": modification of work by Dr. Jochen Lengerke; credit “Dental curing": modification of work by the Department of the Navy; credit “Night vision": modification of work by the Department of the Army; credit “Remote": modification of work by Emilian Robert Vicol; credit “Cell phone": modification of work by Brett Jordan; credit “Microwave oven": modification of work by Billy Mabray; credit “Ultrasound": modification of work by Jane Whitney; credit “AM radio": modification of work by Dave Clausen)

Example 9.1.1: Determining the Frequency and Wavelength of Radiation

A sodium streetlight gives off yellow light that has a wavelength of 589 nm (1 nm = 1×10^{-9} m). What is the frequency of this light?

Solution

We can rearrange the Equation 9.1.1 to solve for the frequency:

$$\nu = \frac{c}{\lambda}$$

Since c is expressed in meters per second, we must also convert 589 nm to meters.

$$\nu = \left(\frac{2.998 \times 10^{8}\ \cancel{\text{m}}\ \text{s}^{-1}}{589\ \cancel{\text{nm}}}\right)\left(\frac{1 \times 10^{9}\ \cancel{\text{nm}}}{1\ \cancel{\text{m}}}\right) = 5.09 \times 10^{14}\ \text{s}^{-1}$$

Exercise 9.1.1

One of the frequencies used to transmit and receive cellular telephone signals in the United States is 850 MHz. What is the wavelength in meters of these radio waves?

Answer

0.353 m = 35.3 cm

An Important Wave Property: Phase And Interference

A wave is a disturbance that travels in space. The magnitude of the wave at any point in space and time varies sinusoidally. While the absolute value of the magnitude of one wave at any point is not very important, the *relative* displacement of two waves, called the phase difference, is vitally important because it determines whether the waves reinforce or interfere with each other. Figure 9.1.3*a* shows an arbitrary phase difference between two wave and Figure 9.1.3*b* shows what happens when the two waves are 180 degrees out of phase. The green line is their sum. Figure 9.1.3*c* shows what happens when the two lines are in phase, exactly superimposed on each other. Again, the green line is the sum of the intensities. A pattern of constructive and

destructive interference is obtained when two (or more) diffracting waves interact with each other. This principle of diffraction and interference was used to prove the wave properties of electrons and is the basis for how electron microscopes work.





Figure 9.1.3: Phase. Two waves traveling together are displaced by a phase difference. If the phase difference is 0° then they lay on top of each other and reinforce. If the phase difference is 180° they completely cancel each other out.



Photograph of an interference pattern produced by circular water waves in a ripple tank.

For a mathematical analysis of phase aspects in sinusoids, check the math Libretexts library.

Wireless Communication

Many valuable technologies operate in the radio (3 kHz-300 GHz) frequency region of the electromagnetic spectrum. At the low frequency (low energy, long wavelength) end of this region are AM (amplitude modulation) radio signals (540-2830 kHz) that can travel long distances. FM (frequency modulation) radio signals are used at higher frequencies (87.5-108.0 MHz). In AM radio, the information is transmitted by varying the amplitude of the wave (Figure 9.1.5). In FM radio, by contrast, the amplitude is constant and the instantaneous frequency varies.



Figure 9.1.4: Radio and cell towers are typically used to transmit long-wavelength electromagnetic radiation. Increasingly, cell towers are designed to blend in with the landscape, as with the Tucson, Arizona, cell tower (right) disguised as a palm tree. (credit left: modification of work by Sir Mildred Pierce; credit middle: modification of work by M.O. Stevens)

Other technologies also operate in the radio-wave portion of the electromagnetic spectrum. For example, 4G cellular telephone signals are approximately 880 MHz, while Global Positioning System (GPS) signals operate at 1.228 and 1.575 GHz, local area

wireless technology (Wi-Fi) networks operate at 2.4 to 5 GHz, and highway toll sensors operate at 5.8 GHz. The frequencies associated with these applications are convenient because such waves tend not to be absorbed much by common building materials.




Figure **9.1.5**: This schematic depicts how amplitude modulation (AM) and frequency modulation (FM) can be used to transmit a radio wave.

One particularly characteristic phenomenon of waves results when two or more waves come into contact: They interfere with each other. Figure **9.1.6** shows the interference patterns that arise when light passes through narrow slits closely spaced about a wavelength apart. The fringe patterns produced depend on the wavelength, with the fringes being more closely spaced for shorter wavelength light passing through a given set of slits. When the light passes through the two slits, each slit effectively acts as a new source, resulting in two closely spaced waves coming into contact at the detector (the camera in this case). The dark regions in Figure **9.1.5** correspond to regions where the peaks for the wave from one slit happen to coincide with the troughs for the wave from the other slit (destructive interference), while the brightest regions correspond to the regions where the peaks for the two waves (or their two troughs) happen to coincide (constructive interference). Likewise, when two stones are tossed close together into a pond, interference patterns are visible in the interactions between the waves produced by the stones. Such interference patterns cannot be explained by particles moving according to the laws of classical mechanics.




Figure **9.1.6**: Interference fringe patterns are shown for light passing through two closely spaced, narrow slits. The spacing of the fringes depends on the wavelength, with the fringes being more closely spaced for the shorter-wavelength blue light. (credit: PASCO)

Dorothy Hodgkin

Because the wavelengths of X-rays (10-10,000 picometers [pm]) are comparable to the size of atoms, X-rays can be used to determine the structure of molecules. When a beam of X-rays is passed through molecules packed together in a crystal, the X-rays collide with the electrons and scatter. Constructive and destructive interference of these scattered X-rays creates a specific diffraction pattern. Calculating backward from this pattern, the positions of each of the atoms in the molecule can be determined very precisely. One of the pioneers who helped create this technology was Dorothy Crowfoot Hodgkin.

She was born in Cairo, Egypt, in 1910, where her British parents were studying archeology. Even as a young girl, she was fascinated with minerals and crystals. When she was a student at Oxford University, she began researching how X-ray crystallography could be used to determine the structure of biomolecules. She invented new techniques that allowed her and her students to determine the structures of vitamin B_{12}, penicillin, and many other important molecules. Diabetes, a disease that affects 382 million people worldwide, involves the hormone insulin. Hodgkin began studying the structure of insulin in 1934, but it required several decades of advances in the field before she finally reported the structure in 1969. Understanding the structure has led to better understanding of the disease and treatment options.

Not all waves are travelling waves. Standing waves (also known as stationary waves) remain constrained within some region of space. As we shall see, standing waves play an important role in our understanding of the electronic structure of atoms and molecules. The simplest example of a standing wave is a one-dimensional wave associated with a vibrating string that is held fixed at its two end points. Figure **9.1.6** shows the four lowest-energy standing waves (the fundamental wave and the lowest three harmonics) for a vibrating string at a particular amplitude. Although the string's motion lies mostly within a plane, the wave itself is considered to be one dimensional, since it lies along the length of the string. The motion of string segments in a direction perpendicular to the string length generates the waves and so the amplitude of the waves is visible as the maximum displacement of the curves seen in Figure **9.1.7**. The key observation from the figure is that only those waves having an integer number, n, of half-wavelengths between the end points can form. A system with fixed end points such as this restricts the number and type of the possible waveforms. This is an example of quantization, in which only discrete values from a more general set of continuous values of some property are observed. Another important observation is that the harmonic waves (those waves displaying more than one-half wavelength) all have one or more points between the two end points that are not in motion. These special points are nodes. The energies of the standing waves with a given amplitude in a vibrating string increase with the number of half-wavelengths *n*. Since the number of nodes is $n - 1$, the energy can also be said to depend on the number of nodes, generally increasing as the number of nodes increases.




Figure **9.1.7**: A vibrating string shows some one-dimensional standing waves. Since the two end points of the string are held fixed, only waves having an integer number of half-wavelengths can form. The points on the string between the end points that are not moving are called the nodes.

An example of two-dimensional standing waves is shown in Figure **9.1.8** which shows the vibrational patterns on a flat surface. Although the vibrational amplitudes cannot be seen like they could in the vibrating string, the nodes have been made visible by sprinkling the drum surface with a powder that collects on the areas of the surface that have minimal displacement. For one-dimensional standing waves, the nodes were points on the line, but for two-dimensional standing waves, the nodes are lines on the surface (for three-dimensional standing waves, the nodes are two-dimensional surfaces within the three-dimensional volume). Because of the circular symmetry of the drum surface, its boundary conditions (the drum surface being tightly constrained to the circumference of the drum) result in two types of nodes: radial nodes that sweep out all angles at constant radii and, thus, are seen as circles about the center, and angular nodes that sweep out all radii at constant angles and, thus, are seen as lines passing through the center. The upper left image in Figure **9.1.8** shows two radial nodes, while the image in the lower right shows the vibrational pattern associated with three radial nodes and two angular nodes.




Figure **9.1.8**: *Two-dimensional standing waves can be visualized on a vibrating surface. The surface has been sprinkled with a powder that collects near the nodal lines. There are two types of nodes visible: radial nodes (circles) and angular nodes (radii). For a more animated video, check this link out.*



Electromagnetic Radiation: https://youtu.be/TZy7a69pP-w

Blackbody Radiation and the Ultraviolet Catastrophe

The last few decades of the nineteenth century witnessed intense research activity in commercializing newly discovered electric lighting. This required obtaining a better understanding of the distributions of light emitted from various sources being considered. Artificial lighting is usually designed to mimic natural sunlight within the limitations of the underlying technology. Such lighting consists of a range of broadly distributed frequencies that form a continuous spectrum. Figure **9.1.9** shows the wavelength distribution for sunlight. The most intense radiation is in the visible region, with the intensity dropping off rapidly for shorter wavelength ultraviolet (UV) light, and more slowly for longer wavelength infrared (IR) light.




Figure **9.1.9**: The spectral distribution (light intensity vs. wavelength) of sunlight reaches the Earth's atmosphere as UV light, visible light, and IR light. The unabsorbed sunlight at the top of the atmosphere has a distribution that approximately matches the theoretical distribution of a blackbody at 5250 °C, represented by the blue curve. (credit: modification of work by American Society for Testing and Materials (ASTM) Terrestrial Reference Spectra for Photovoltaic Performance Evaluation)

In Figure **9.1.9**, the solar distribution is compared to a representative distribution, called a blackbody spectrum, that corresponds to a temperature of 5250 °C. The blackbody spectrum matches the solar spectrum quite well. A blackbody is a convenient, ideal emitter that approximates the behavior of many materials when heated. It is “ideal” in the same sense that an ideal gas is a convenient, simple representation of real gases that works well, provided that the pressure is not too high nor the temperature too low. A good approximation of a blackbody that can be used to observe blackbody radiation is a metal oven that can be heated to very high temperatures. The oven has a small hole allowing for the light being emitted within the oven to be observed with a spectrometer so that the wavelengths and their intensities can be measured. Figure **9.1.8** shows the resulting curves for some representative temperatures. Each distribution depends only on a single parameter: the temperature. The maxima in the blackbody curves, λ_{max}, shift to shorter wavelengths as the temperature increases, reflecting the observation that metals being heated to high temperatures begin to glow a darker red that becomes brighter as the temperature increases, eventually becoming white hot at very high temperatures as the intensities of all of the visible wavelengths become appreciable. This common observation was at the heart of the first paradox that showed the fundamental limitations of classical physics that we will examine.

Physicists derived mathematical expressions for the blackbody curves using well-accepted concepts from the theories of classical mechanics and classical electromagnetism. The theoretical expressions as functions of temperature fit the observed experimental blackbody curves well at longer wavelengths, but showed significant discrepancies at shorter wavelengths. Not only did the theoretical curves not show a peak, they absurdly showed the intensity becoming infinitely large as the wavelength became smaller, which would imply that everyday objects at room temperature should be emitting large amounts of UV light. This became known as the “ultraviolet catastrophe” because no one could find any problems with the theoretical treatment that could lead to such unrealistic short-wavelength behavior. Finally, around 1900, Max Planck derived a theoretical expression for blackbody radiation that fit the experimental observations exactly (within experimental error). Planck developed his theoretical treatment by extending the earlier work that had been based on the premise that the atoms composing the oven vibrated at increasing frequencies (or decreasing wavelengths) as the temperature increased, with these vibrations being the source of the emitted electromagnetic radiation. But where the earlier treatments had allowed the vibrating atoms to have any energy values obtained from a continuous set of energies (perfectly reasonable, according to classical physics), Planck found that by restricting the vibrational energies to discrete values for each frequency, he could derive an expression for blackbody radiation that correctly had the intensity dropping rapidly for the short wavelengths in the UV region.

$$E = nh\nu,\ n = 1, 2, 3,\ \ldots \tag{9.1.2}$$

The quantity h is a constant now known as Planck's constant, in his honor. Although Planck was pleased he had resolved the blackbody radiation paradox, he was disturbed that to do so, he needed to assume the vibrating atoms required quantized energies, which he was unable to explain. The value of Planck's constant is very small, 6.626×10^{-34} joule seconds (J s), which helps explain why energy quantization had not been observed previously in macroscopic phenomena.




Figure **9.1.10**: Blackbody spectral distribution curves are shown for some representative temperatures.

The Photoelectric Effect

The next paradox in the classical theory to be resolved concerned the photoelectric effect (Figure **9.1.11**). It had been observed that electrons could be ejected from the clean surface of a metal when light having a frequency greater than some threshold frequency was shone on it. Surprisingly, the kinetic energy of the ejected electrons did not depend on the brightness of the light, but increased with increasing frequency of the light. Since the electrons in the metal had a certain amount of binding energy keeping them there, the incident light needed to have more energy to free the electrons. According to classical wave theory, a wave's energy depends on its intensity (which depends on its amplitude), not its frequency. One part of these observations was that the number of electrons ejected within in a given time period was seen to increase as the brightness increased. In 1905, Albert Einstein was able to resolve the paradox by incorporating Planck's quantization findings into the discredited particle view of light (Einstein actually won his Nobel prize for this work, and not for his theories of relativity for which he is most famous).

Einstein argued that the quantized energies that Planck had postulated in his treatment of blackbody radiation could be applied to the light in the photoelectric effect so that the light striking the metal surface should not be viewed as a wave, but instead as a stream of particles (later called photons) whose energy depended on their frequency, according to Planck's formula, $E = h\nu$ (or, in terms of wavelength using $c = \nu\lambda$, $\boldsymbol{E = \frac{hc}{\lambda}}$). Electrons were ejected when hit by photons having sufficient energy (a frequency greater than the threshold). The greater the frequency, the greater the kinetic energy imparted to the escaping electrons by the collisions. Einstein also argued that the light intensity did not depend on the amplitude of the incoming wave, but instead corresponded to the number of photons striking the surface within a given time period. This explains why the number of ejected electrons increased with increasing brightness, since the greater the number of incoming photons, the greater the likelihood that they would collide with some of the electrons.

With Einstein's findings, the nature of light took on a new air of mystery. Although many light phenomena could be explained either in terms of waves or particles, certain phenomena, such as the interference patterns obtained when light passed through a double slit, were completely contrary to a particle view of light, while other phenomena, such as the photoelectric effect, were completely contrary to a wave view of light. Somehow, at a deep fundamental level still not fully understood, light is both wavelike and particle-like. This is known as wave-particle duality.




Figure **9.1.11**: Photons with low frequencies do not have enough energy to cause electrons to be ejected via the photoelectric effect. For any frequency of light above the threshold frequency, the kinetic energy of an ejected electron will increase linearly with the energy of the incoming photon.

✔ Example 9.1.2: Calculating the Energy of Radiation

When we see light from a neon sign, we are observing radiation from excited neon atoms. If this radiation has a wavelength of 640 nm, what is the energy of the photon being emitted?

Solution

We use the part of Planck's equation that includes the wavelength, λ, and convert units of nanometers to meters so that the units of λ and c are the same.

$$\begin{aligned} E &= \frac{hc}{\lambda} \\ &= \frac{(6.626 \times 10^{-34}\ \text{J}\,\cancel{\text{s}})(2.998 \times 10^{8}\ \text{m}\,\cancel{\text{s}^{-1}})}{(640\ \cancel{\text{nm}})\left(\frac{1\ \text{m}}{10^{9}\ \cancel{\text{nm}}}\right)} \\ &= 3.10 \times 10^{-19}\ \text{J} \end{aligned}$$

? Exercise 9.1.2

The microwaves in an oven are of a specific frequency that will heat the water molecules contained in food. (This is why most plastics and glass do not become hot in a microwave oven-they do not contain water molecules.) This frequency is about 3×10^9 Hz. What is the energy of one photon in these microwaves?

Answer

2×10^{-24} J

✔ Example 9.1.3: Photoelectric Effect

Identify which of the following statements are false and, where necessary, change the italicized word or phrase to make them true, consistent with Einstein's explanation of the photoelectric effect.

a. Increasing the brightness of incoming light *increases* the kinetic energy of the ejected electrons.
b. Increasing the *wavelength* of incoming light increases the kinetic energy of the ejected electrons.
c. Increasing the brightness of incoming light *increases* the number of ejected electrons.
d. Increasing the *frequency* of incoming light can increase the number of ejected electrons.

Solution

a. False. Increasing the brightness of incoming light *has no effect* on the kinetic energy of the ejected electrons. Only energy, not the number or amplitude, of the photons influences the kinetic energy of the electrons.

b. False. Increasing the *frequency* of incoming light increases the kinetic energy of the ejected electrons. Frequency is proportional to energy and inversely proportional to wavelength. Frequencies above the threshold value transfer the excess energy into the kinetic energy of the electrons.
c. True. Because the number of collisions with photons increases with brighter light, the number of ejected electrons increases.
d. True with regard to the threshold energy binding the electrons to the metal. Below this threshold, electrons are not emitted and above it they are. Once over the threshold value, further increasing the frequency does not increase the number of ejected electrons

? Exercise 9.1.3


Calculate the threshold energy in kJ/mol of electrons in aluminum, given that the lowest frequency photon for which the photoelectric effect is observed is $9.87 \times 10^{14}\ Hz$.

Answer

$3.94\ kJ/mol$



The Photoelectric Effect: https://youtu.be/mxBMxJLauQk



Energy of a Photon: https://youtu.be/6swES9-eAAE

Summary

Light and other forms of electromagnetic radiation move through a vacuum with a constant speed, c, of 2.998×10^8 m s^{-1}. This radiation shows wavelike behavior, which can be characterized by a frequency, ν, and a wavelength, λ, such that $c = \lambda\nu$. Light is an

example of a travelling wave. Other important wave phenomena include standing waves, periodic oscillations, and vibrations. Standing waves exhibit quantization, since their wavelengths are limited to discrete integer multiples of some characteristic lengths. Electromagnetic radiation that passes through two closely spaced narrow slits having dimensions roughly similar to the wavelength will show an interference pattern that is a result of constructive and destructive interference of the waves. Electromagnetic radiation also demonstrates properties of particles called photons. The energy of a photon is related to the frequency (or alternatively, the wavelength) of the radiation as $E = h\nu$ (or $E = \frac{hc}{\lambda}$), where h is Planck's constant. That light demonstrates both wavelike and particle-like behavior is known as wave-particle duality. All forms of electromagnetic radiation share these properties, although various forms including X-rays, visible light, microwaves, and radio waves interact differently with matter and have very different practical applications.

Key Equations

- $c = \lambda\nu$
- $E = h\nu = \frac{hc}{\lambda}$, where $h = 6.626 \times 10^{-34}$ J s
- $\frac{1}{\lambda} = R_\infty \left(\frac{1}{n_1^2} - \frac{1}{n_2^2} \right)$

Glossary

amplitude
extent of the displacement caused by a wave (for sinusoidal waves, it is one-half the difference from the peak height to the trough depth, and the intensity is proportional to the square of the amplitude)

blackbody
idealized perfect absorber of all incident electromagnetic radiation; such bodies emit electromagnetic radiation in characteristic continuous spectra called blackbody radiation

electromagnetic radiation
energy transmitted by waves that have an electric-field component and a magnetic-field component

electromagnetic spectrum
range of energies that electromagnetic radiation can comprise, including radio, microwaves, infrared, visible, ultraviolet, X-rays, and gamma rays; since electromagnetic radiation energy is proportional to the frequency and inversely proportional to the wavelength, the spectrum can also be specified by ranges of frequencies or wavelengths

frequency (ν)
number of wave cycles (peaks or troughs) that pass a specified point in space per unit time

hertz (Hz)
the unit of frequency, which is the number of cycles per second, s^{-1}

intensity
property of wave-propagated energy related to the amplitude of the wave, such as brightness of light or loudness of sound

interference pattern
pattern typically consisting of alternating bright and dark fringes; it results from constructive and destructive interference of waves

Node
any point of a standing wave with zero amplitude

photon
smallest possible packet of electromagnetic radiation, a particle of light

quantization

occurring only in specific discrete values, not continuous

standing wave

(also, stationary wave) localized wave phenomenon characterized by discrete wavelengths determined by the boundary conditions used to generate the waves; standing waves are inherently quantized

wave

oscillation that can transport energy from one point to another in space

wavelength (λ)

distance between two consecutive peaks or troughs in a wave

wave-particle duality

term used to describe the fact that elementary particles including matter exhibit properties of both particles (including localized position, momentum) and waves (including nonlocalization, wavelength, frequency)

9.1: The Nature of Light is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **6.1: Electromagnetic Energy** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **6.4: The Wave Behavior of Matter** is licensed CC BY-NC-SA 3.0.

9.2: Line Spectra and Bohr Model of Atoms

Learning Objectives

- Describe the Bohr model of the hydrogen atom
- Use the Rydberg equation to calculate energies of light emitted or absorbed by hydrogen atoms

Line Spectra

Another paradox within the classical electromagnetic theory that scientists in the late nineteenth century struggled with concerned the light emitted from atoms and molecules. When solids, liquids, or condensed gases are heated sufficiently, they radiate some of the excess energy as light. Photons produced in this manner have a range of energies, and thereby produce a continuous spectrum in which an unbroken series of wavelengths is present. Most of the light generated from stars (including our sun) is produced in this fashion. You can see all the visible wavelengths of light present in sunlight by using a prism to separate them. The sunlight also contains UV light (shorter wavelengths) and IR light (longer wavelengths) that can be detected using instruments but that are invisible to the human eye. Incandescent (glowing) solids such as tungsten filaments in incandescent lights also give off light that contains all wavelengths of visible light. These continuous spectra can often be approximated by blackbody radiation curves at some appropriate temperature.

In contrast to continuous spectra, light can also occur as discrete or line spectra having very narrow line widths interspersed throughout the spectral regions. Exciting a gas at low partial pressure using an electrical current, or heating it, will produce line spectra. Fluorescent light bulbs and neon signs operate in this way (Figure **9.2.1**). Each element displays its own characteristic set of lines, as do molecules, although their spectra are generally much more complicated.



Figure **9.2.1**: Neon signs operate by exciting a gas at low partial pressure using an electrical current. This sign shows the elaborate artistic effects that can be achieved. (credit: Dave Shaver)

Each emission line consists of a single wavelength of light, which implies that the light emitted by a gas consists of a set of discrete energies. For example, when an electric discharge passes through a tube containing hydrogen gas at low pressure, the H_2 molecules are broken apart into separate H atoms, and we see a blue-pink color. Passing the light through a prism produces a line spectrum, indicating that this light is composed of photons of four visible wavelengths, as shown in Figure **9.2.2**.




Figure 9.2.2: Line spectra of select gas. Compare the two types of emission spectra: continuous spectrum of white light (top) and the line spectra of the light from excited sodium, hydrogen, calcium, and mercury atoms.

The origin of discrete spectra in atoms and molecules was extremely puzzling to scientists in the late nineteenth century, since according to classical electromagnetic theory, only continuous spectra should be observed. Even more puzzling, in 1885, Johann Balmer was able to derive an empirical equation that related the four visible wavelengths of light emitted by hydrogen atoms to whole integers. That equation is the following one, in which k is a constant:

$$\frac{1}{\lambda} = k\left(\frac{1}{4} - \frac{1}{n^2}\right), \; n = 3,\, 4,\, 5,\, 6 \tag{9.2.1}$$

Other discrete lines for the hydrogen atom were found in the UV and IR regions. Johannes Rydberg generalized Balmer's work and developed an empirical formula that predicted all of hydrogen's emission lines, not just those restricted to the visible range, where, n_1 and n_2 are integers, $n_1 < n_2$, and R_∞ is the Rydberg constant (1.097×10^7 m^{-1}).

$$\frac{1}{\lambda} = R_\infty\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right) \tag{9.2.2}$$

Even in the late nineteenth century, spectroscopy was a very precise science, and so the wavelengths of hydrogen were measured to very high accuracy, which implied that the Rydberg constant could be determined very precisely as well. That such a simple formula as the Rydberg formula could account for such precise measurements seemed astounding at the time, but it was the eventual explanation for emission spectra by Neils Bohr in 1913 that ultimately convinced scientists to abandon classical physics and spurred the development of modern quantum mechanics.

Bohr Model of Atoms

Following the work of Ernest Rutherford and his colleagues in the early twentieth century, the picture of atoms consisting of tiny dense nuclei surrounded by lighter and even tinier electrons continually moving about the nucleus was well established. This picture was called the planetary model, since it pictured the atom as a miniature “solar system” with the electrons orbiting the nucleus like planets orbiting the sun. The simplest atom is hydrogen, consisting of a single proton as the nucleus about which a single electron moves. The electrostatic force attracting the electron to the proton depends only on the distance between the two particles.

$$F_{gravity} = G\frac{m_1 m_2}{r^2} \tag{9.2.3}$$

with

- G is a gravitational constant
- m_1 and m_2 are the masses of particle 1 and 2, respectively
- r is the distance between the two particles

The electrostatic force has the same form as the gravitational force between two mass particles except that the electrostatic force depends on the magnitudes of the charges on the particles (+1 for the proton and −1 for the electron) instead of the magnitudes of the particle masses that govern the gravitational force.

$$F_{electrostatic} = k\frac{m_1 m_2}{r^2} \tag{9.2.4}$$

with

- k is a constant
- m_1 and m_2 are the masses of particle 1 and 2, respectively
- r is the distance between the two particles

Since forces can be derived from potentials, it is convenient to work with potentials instead, since they are forms of energy. The electrostatic potential is also called the *Coulomb potential*. Because the electrostatic potential has the same form as the gravitational potential, according to classical mechanics, the equations of motion should be similar, with the electron moving around the nucleus in circular or elliptical orbits (hence the label "planetary" model of the atom). Potentials of the form $V(r)$ that depend only on the radial distance r are known as central potentials. Central potentials have spherical symmetry, and so rather than specifying the position of the electron in the usual Cartesian coordinates (x, y, z), it is more convenient to use polar spherical coordinates centered at the nucleus, consisting of a linear coordinate r and two angular coordinates, usually specified by the Greek letters theta (θ) and phi (Φ). These coordinates are similar to the ones used in GPS devices and most smart phones that track positions on our (nearly) spherical earth, with the two angular coordinates specified by the latitude and longitude, and the linear coordinate specified by sea-level elevation. Because of the spherical symmetry of central potentials, the energy and angular momentum of the classical hydrogen atom are constants, and the orbits are constrained to lie in a plane like the planets orbiting the sun. This classical mechanics description of the atom is incomplete, however, since an electron moving in an elliptical orbit would be accelerating (by changing direction) and, according to classical electromagnetism, it should continuously emit electromagnetic radiation. This loss in orbital energy should result in the electron's orbit getting continually smaller until it spirals into the nucleus, implying that atoms are inherently unstable.

In 1913, Niels Bohr attempted to resolve the atomic paradox by ignoring classical electromagnetism's prediction that the orbiting electron in hydrogen would continuously emit light. Instead, he incorporated into the classical mechanics description of the atom Planck's ideas of quantization and Einstein's finding that light consists of photons whose energy is proportional to their frequency. Bohr assumed that the electron orbiting the nucleus would not normally emit any radiation (the stationary state hypothesis), but it would emit or absorb a photon if it moved to a different orbit. The energy absorbed or emitted would reflect differences in the orbital energies according to this equation:

$$|\Delta E| = |E_f - E_i| = hu = \frac{hc}{\lambda} \tag{9.2.5}$$

In this equation, h is Planck's constant and E_i and E_f are the initial and final orbital energies, respectively. The absolute value of the energy difference is used, since frequencies and wavelengths are always positive. Instead of allowing for continuous values for the angular momentum, energy, and orbit radius, Bohr assumed that only discrete values for these could occur (actually, quantizing any one of these would imply that the other two are also quantized). Bohr's expression for the quantized energies is:

$$E_n = -\frac{k}{n^2} \tag{9.2.6}$$

with $n = 1, 2, 3, ...$

In this expression, k is a constant comprising fundamental constants such as the electron mass and charge and Planck's constant. Inserting the expression for the orbit energies into the equation for ΔE gives

$$\Delta E = k\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right) = \frac{hc}{\lambda} \tag{9.2.7}$$

or

$$\frac{1}{\lambda} = \frac{k}{hc}\left(\frac{1}{n_1^2} - \frac{1}{n_2^2}\right) \tag{9.2.8}$$

The lowest few energy levels are shown in Figure 9.2.3. One of the fundamental laws of physics is that matter is most stable with the lowest possible energy. Thus, the electron in a hydrogen atom usually moves in the $n = 1$ orbit, the orbit in which it has the lowest energy. When the electron is in this lowest energy orbit, the atom is said to be in its ground electronic state (or simply ground state). If the atom receives energy from an outside source, it is possible for the electron to move to an orbit with a higher n value and the atom is now in an excited electronic state (or simply an excited state) with a higher energy. When an electron transitions from an excited state (higher energy orbit) to a less excited state, or ground state, the difference in energy is emitted as a photon. Similarly, if a photon is absorbed by an atom, the energy of the photon moves an electron from a lower energy orbit up to a more excited one.




Figure 9.2.3: Quantum numbers and energy levels in a hydrogen atom. The more negative the calculated value, the lower the energy.

We can relate the energy of electrons in atoms to what we learned previously about energy. The law of conservation of energy says that we can neither create nor destroy energy. Thus, if a certain amount of external energy is required to excite an electron from one energy level to another, that same amount of energy will be liberated when the electron returns to its initial state (Figure 9.2.4). In effect, an atom can "store" energy by using it to promote an electron to a state with a higher energy and release it when the electron returns to a lower state. The energy can be released as one quantum of energy, as the electron returns to its ground state (say, from $n = 5$ to $n = 1$), or it can be released as two or more smaller quanta as the electron falls to an intermediate state, then to the ground state (say, from $n = 5$ to $n = 4$, emitting one quantum, then to $n = 1$, emitting a second quantum).




Figure 9.2.4: The horizontal lines show the relative energy of orbits in the Bohr model of the hydrogen atom, and the vertical arrows depict the energy of photons absorbed (left) or emitted (right) as electrons move between these orbits.

Since Bohr's model involved only a single electron, it could also be applied to the single electron ions He^{+}, Li^{2+}, Be^{3+}, and so forth, which differ from hydrogen only in their nuclear charges, and so one-electron atoms and ions are collectively referred to as *hydrogen-like* or *hydrogenic* atoms. The energy expression for hydrogen-like atoms is a generalization of the hydrogen atom energy, in which Z is the nuclear charge (+1 for hydrogen, +2 for He, +3 for Li, and so on) and k has a value of $2.179 \times 10^{-18}\ J$.

$$E_n = -\frac{kZ^2}{n^2} \tag{9.2.9}$$

The sizes of the circular orbits for hydrogen-like atoms are given in terms of their radii by the following expression, in which a_o is a constant called the Bohr radius, with a value of $5.292 \times 10^{-11}\ m$:

$$r = \frac{n^2}{Z} a_0 \tag{9.2.10}$$

The equation also shows us that as the electron's energy increases (as n increases), the electron is found at greater distances from the nucleus. This is implied by the inverse dependence on r in the Coulomb potential, since, as the electron moves away from the nucleus, the electrostatic attraction between it and the nucleus decreases, and it is held less tightly in the atom. Note that as n gets larger and the orbits get larger, their energies get closer to zero, and so the limits $n \longrightarrow \infty$ and $r \longrightarrow \infty$ imply that $E = 0$ corresponds to the ionization limit where the electron is completely removed from the nucleus. Thus, for hydrogen in the ground state $n = 1$, the ionization energy would be:

$$\Delta E = E_{n \longrightarrow \infty} - E_1 = 0 + k = k \tag{9.2.11}$$

With three extremely puzzling paradoxes now solved (blackbody radiation, the photoelectric effect, and the hydrogen atom), and all involving Planck's constant in a fundamental manner, it became clear to most physicists at that time that the classical theories that worked so well in the macroscopic world were fundamentally flawed and could not be extended down into the microscopic domain of atoms and molecules. Unfortunately, despite Bohr's remarkable achievement in deriving a theoretical expression for the Rydberg constant, he was unable to extend his theory to the next simplest atom, He, which only has two electrons. Bohr's model was severely flawed, since it was still based on the classical mechanics notion of precise orbits, a concept that was later found to be untenable in the microscopic domain, when a proper model of quantum mechanics was developed to supersede classical mechanics.

Example 9.2.1: Calculating the Energy of an Electron in a Bohr Orbit

Early researchers were very excited when they were able to predict the energy of an electron at a particular distance from the nucleus in a hydrogen atom. If a spark promotes the electron in a hydrogen atom into an orbit with $n = 3$, what is the calculated energy, in joules, of the electron?

Solution

The energy of the electron is given by Equation 9.2.9:

$$E = \frac{-kZ^2}{n^2} \tag{9.2.12}$$

The atomic number, Z, of hydrogen is 1; $k = 2.179 \times 10^{-18}\ J$; and the electron is characterized by an n value of 3. Thus,

$$E = \frac{-(2.179 \times 10^{-18}\ J) \times (1)^2}{(3)^2} = -2.421 \times 10^{-19}\ J \tag{9.2.13}$$

Exercise 9.2.1

The electron in Example 9.2.1 in the $n = 3$ state is promoted even further to an orbit with $n = 6$. What is its new energy?

Answer

TBD

Example 9.2.2: Calculating Electron Transitions in a One–electron System

What is the energy (in joules) and the wavelength (in meters) of the line in the spectrum of hydrogen that represents the movement of an electron from Bohr orbit with n = 4 to the orbit with n = 6? In what part of the electromagnetic spectrum do we find this radiation?

Solution

In this case, the electron starts out with $n = 4$, so $n_1 = 4$. It comes to rest in the $n = 6$ orbit, so $n_2 = 6$. The difference in energy between the two states is given by this expression:

$$\Delta E = E_1 - E_2 = 2.179 \times 10^{-18} \left(\frac{1}{n_1^2} - \frac{1}{n_2^2} \right) \tag{9.2.14}$$

$$\Delta E = 2.179 \times 10^{-18} \left(\frac{1}{4^2} - \frac{1}{6^2} \right) J \tag{9.2.15}$$

$$\Delta E = 2.179 \times 10^{-18} \left(\frac{1}{16} - \frac{1}{36} \right) J \tag{9.2.16}$$

$$\Delta E = 7.566 \times 10^{-20}\ J \tag{9.2.17}$$

This energy difference is *positive*, indicating a photon enters the system (is absorbed) to excite the electron from the n = 4 orbit up to the $n = 6$ orbit. The wavelength of a photon with this energy is found by the expression $E = hc\lambda$. Rearrangement gives:

$$\lambda = \frac{hc}{E} \tag{9.2.18}$$

From the figure of electromagnetic radiation, we can see that this wavelength is found in the infrared portion of the electromagnetic spectrum.

? Exercise 9.2.2

What is the energy in joules and the wavelength in meters of the photon produced when an electron falls from the $n = 5$ to the $n = 3$ level in a He^+ ion ($Z = 2$ for He^+)?

Answer

$6.198 \times 10^{-19}\ J$ and $3.205 \times 10^{-7}\ m$

Bohr's model of the hydrogen atom provides insight into the behavior of matter at the microscopic level, but it is does not account for electron–electron interactions in atoms with more than one electron. It does introduce several important features of all models used to describe the distribution of electrons in an atom. These features include the following:

- The energies of electrons (energy levels) in an atom are quantized, described by quantum numbers: integer numbers having only specific allowed value and used to characterize the arrangement of electrons in an atom.
- An electron's energy increases with increasing distance from the nucleus.
- The discrete energies (lines) in the spectra of the elements result from quantized electronic energies.

Of these features, the most important is the postulate of quantized energy levels for an electron in an atom. As a consequence, the model laid the foundation for the quantum mechanical model of the atom. Bohr won a Nobel Prize in Physics for his contributions to our understanding of the structure of atoms and how that is related to line spectra emissions.



The Bohr Atom: https://youtu.be/GuFQEOzFOgA

Summary

Electromagnetic radiation can be generated by exciting matter to higher energies, such as by heating it. The emitted light can be either continuous (incandescent sources like the sun) or discrete (from specific types of excited atoms). Continuous spectra often have distributions that can be approximated as blackbody radiation at some appropriate temperature. The line spectrum of hydrogen can be obtained by passing the light from an electrified tube of hydrogen gas through a prism. This line spectrum was simple enough that an empirical formula called the Rydberg formula could be derived from the spectrum. Three historically important paradoxes from the late 19th and early 20th centuries that could not be explained within the existing framework of classical mechanics and classical electromagnetism were the blackbody problem, the photoelectric effect, and the discrete spectra of atoms. The resolution of these paradoxes ultimately led to quantum theories that superseded the classical theories. Bohr incorporated Planck's and Einstein's quantization ideas into a model of the hydrogen atom that resolved the paradox of atom stability and discrete spectra. The Bohr model of the hydrogen atom explains the connection between the quantization of photons and the quantized emission from atoms. Bohr described the hydrogen atom in terms of an electron moving in a circular orbit about a nucleus. He postulated that the electron was restricted to certain orbits characterized by discrete energies. Transitions between these allowed orbits result in the absorption or emission of photons. When an electron moves from a higher-energy orbit to a more stable one, energy is emitted in the form of a photon. To move an electron from a stable orbit to a more excited one, a photon of energy

must be absorbed. Using the Bohr model, we can calculate the energy of an electron and the radius of its orbit in any one-electron system.

Glossary

Bohr's model of the hydrogen atom
: structural model in which an electron moves around the nucleus only in circular orbits, each with a specific allowed radius; the orbiting electron does not normally emit electromagnetic radiation, but does so when changing from one orbit to another.

continuous spectrum
: electromagnetic radiation given off in an unbroken series of wavelengths (e.g., white light from the sun

excited state
: state having an energy greater than the ground-state energy

ground state
: state in which the electrons in an atom, ion, or molecule have the lowest energy possible

quantum number
: integer number having only specific allowed values and used to characterize the arrangement of electrons in an atom

line spectrum
: electromagnetic radiation emitted at discrete wavelengths by a specific atom (or atoms) in an excited state

---

9.2: Line Spectra and Bohr Model of Atoms is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **6.2: The Bohr Model** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **6.1: Electromagnetic Energy** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

9.3: Wave Nature of Matter

Learning Objectives

- Extend the concept of wave–particle duality that was observed in electromagnetic radiation to matter as well

Bohr's model explained the experimental data for the hydrogen atom and was widely accepted, but it also raised many questions. Why did electrons orbit at only fixed distances defined by a single quantum number n = 1, 2, 3, and so on, but never in between? Why did the model work so well describing hydrogen and one-electron ions, but could not correctly predict the emission spectrum for helium or any larger atoms? To answer these questions, scientists needed to completely revise the way they thought about matter.

Behavior in the Microscopic World

We know how matter behaves in the macroscopic world—objects that are large enough to be seen by the naked eye follow the rules of classical physics. A billiard ball moving on a table will behave like a particle: It will continue in a straight line unless it collides with another ball or the table cushion, or is acted on by some other force (such as friction). The ball has a well-defined position and velocity (or a well-defined momentum, $p = mv$, defined by mass m and velocity v) at any given moment. In other words, the ball is moving in a classical trajectory. This is the typical behavior of a classical object.

When waves interact with each other, they show interference patterns that are not displayed by macroscopic particles such as the billiard ball. For example, interacting waves on the surface of water can produce interference patters similar to those shown on Figure **9.3.1**. This is a case of wave behavior on the macroscopic scale, and it is clear that particles and waves are very different phenomena in the macroscopic realm.




Figure **9.3.1**: An interference pattern on the water surface is formed by interacting waves. The waves are caused by reflection of water from the rocks. (credit: modification of work by Sukanto Debnath)

As technological improvements allowed scientists to probe the microscopic world in greater detail, it became increasingly clear by the 1920s that very small pieces of matter follow a different set of rules from those we observe for large objects. The unquestionable separation of waves and particles was no longer the case for the microscopic world.

One of the first people to pay attention to the special behavior of the microscopic world was Louis de Broglie. He asked the question: If electromagnetic radiation can have particle-like character, can electrons and other submicroscopic particles exhibit wavelike character? In his 1925 doctoral dissertation, de Broglie extended the wave–particle duality of light that Einstein used to resolve the photoelectric-effect paradox to material particles. He predicted that a particle with mass m and velocity v (that is, with linear momentum p) should also exhibit the behavior of a wave with a wavelength value λ, given by this expression in which h is the familiar Planck's constant

$$\lambda = \frac{h}{mv} = \frac{h}{p} \tag{9.3.1}$$

This is called the *de Broglie wavelength*. Unlike the other values of λ discussed in this chapter, the de Broglie wavelength is a characteristic of particles and other bodies, not electromagnetic radiation (note that this equation involves velocity [v, m/s], not frequency [v, Hz]. Although these two symbols are identical, they mean very different things). Where Bohr had postulated the electron as being a particle orbiting the nucleus in quantized orbits, de Broglie argued that Bohr's assumption of quantization can

be explained if the electron is considered not as a particle, but rather as a circular standing wave such that only an integer number of wavelengths could fit exactly within the orbit (Figure **9.3.2**).




Figure **9.3.2**: If an electron is viewed as a wave circling around the nucleus, an integer number of wavelengths must fit into the orbit for this standing wave behavior to be possible.

For a circular orbit of radius r, the circumference is 2πr, and so de Broglie's condition is:

$$2\pi r = n\lambda \tag{9.3.2}$$

with $n = 1, 2, 3, ...$

Since the de Broglie expression relates the wavelength to the momentum and, hence, velocity, this implies:

$$2\pi r = n\lambda = \frac{nh}{p} = \frac{nh}{mv} = \frac{nhr}{mvr} = \frac{nhr}{L} \tag{9.3.3}$$

This expression can be rearranged to give Bohr's formula for the quantization of the angular momentum:

$$L = \frac{nh}{2\pi} = n\hbar \tag{9.3.4}$$

Classical angular momentum L for a circular motion is equal to the product of the radius of the circle and the momentum of the moving particle p.

$$L = rp = rmv \quad \text{(for a circular motion)} \tag{9.3.5}$$




Figure **9.3.3**: The diagram shows angular momentum for a circular motion.

Shortly after de Broglie proposed the wave nature of matter, two scientists at Bell Laboratories, C. J. Davisson and L. H. Germer, demonstrated experimentally that electrons can exhibit wavelike behavior by showing an interference pattern for electrons travelling through a regular atomic pattern in a crystal. The regularly spaced atomic layers served as slits, as used in other interference experiments. Since the spacing between the layers serving as slits needs to be similar in size to the wavelength of the tested wave for an interference pattern to form, Davisson and Germer used a crystalline nickel target for their "slits," since the spacing of the atoms within the lattice was approximately the same as the de Broglie wavelengths of the electrons that they used. Figure **9.3.4** shows an interference pattern.




Figure 9.3.4: (a) The interference pattern for electrons passing through very closely spaced slits demonstrates that quantum particles such as electrons can exhibit wavelike behavior. (b) The experimental results illustrated here demonstrate the wave–particle duality in electrons. The electrons pass through very closely spaced slits, forming an interference pattern, with increasing numbers of electrons being recorded from the left image to the right. With only a few electrons recorded, it is clear that the electrons arrive as individual localized "particles," but in a seemingly random pattern. As more electrons arrive, a wavelike interference pattern begins to emerge. Note that the probability of the final electron location is still governed by the wave-type distribution, even for a single electron, but it can be observed more easily if many electron collisions have been recorded.

The wave–particle duality of matter can be seen by observing what happens if electron collisions are recorded over a long period of time. Initially, when only a few electrons have been recorded, they show clear particle-like behavior, having arrived in small localized packets that appear to be random. As more and more electrons arrived and were recorded, a clear interference pattern that is the hallmark of wavelike behavior emerged. Thus, it appears that while electrons are small localized particles, their motion does not follow the equations of motion implied by classical mechanics, but instead it is governed by some type of a wave equation that governs a probability distribution even for a single electron's motion. Thus the wave–particle duality first observed with photons is actually a fundamental behavior intrinsic to all quantum particles.



Video 9.3.1: View the Dr. Quantum – Double Slit Experiment cartoon for an easy-to-understand description of wave–particle duality and the associated experiments.

Example 9.3.1: Calculating the Wavelength of a Particle

If an electron travels at a velocity of 1.000×10^{7} m s^{-1} and has a mass of 9.109×10^{-28} g, what is its wavelength?

Solution

We can use de Broglie's equation to solve this problem, but we first must do a unit conversion of Planck's constant. You learned earlier that 1 J = 1 kg m^2/s^2. Thus, we can write $h = 6.626 \times 10^{-34}$ J s as 6.626×10^{-34} kg m^2/s.

$$\begin{aligned}\lambda &= \frac{h}{mv} \\ &= \frac{6.626 \times 10^{-34}\ \text{kg m}^2/\text{s}}{(9.109 \times 10^{-31}\ \text{kg})(1.000 \times 10^{7}\ \text{m/s})} \\ &= 7.274 \times 10^{-11}\ \text{m}\end{aligned}$$

This is a small value, but it is significantly larger than the size of an electron in the classical (particle) view. This size is the same order of magnitude as the size of an atom. This means that electron wavelike behavior is going to be noticeable in an atom.

? Exercise 9.3.1

Calculate the wavelength of a softball with a mass of 100 g traveling at a velocity of 35 m s^{-1}, assuming that it can be modeled as a single particle.

Answer

1.9×10^{-34} m.

We never think of a thrown softball having a wavelength, since this wavelength is so small it is impossible for our senses or any known instrument to detect (strictly speaking, the wavelength of a real baseball would correspond to the wavelengths of its constituent atoms and molecules, which, while much larger than this value, would still be microscopically tiny). The de Broglie wavelength is only appreciable for matter that has a very small mass and/or a very high velocity.

Werner Heisenberg considered the limits of how accurately we can measure properties of an electron or other microscopic particles. He determined that there is a fundamental limit to how accurately one can measure both a particle's position and its momentum simultaneously. The more accurately we measure the momentum of a particle, the less accurately we can determine its position at that time, and vice versa. This is summed up in what we now call the Heisenberg uncertainty principle: *It is fundamentally impossible to determine simultaneously and exactly both the momentum and the position of a particle*. For a particle of mass m moving with velocity v_x in the x direction (or equivalently with momentum p_x), the product of the uncertainty in the position, Δx, and the uncertainty in the momentum, Δp_x , must be greater than or equal to $\frac{\hbar}{2}$ (recall that $\hbar = \frac{h}{2\pi}$, the value of Planck's constant divided by 2π).

$$\Delta x \times \Delta p_x = (\Delta x)(m\Delta v) \geq \frac{\hbar}{2} \tag{9.3.6}$$

This equation allows us to calculate the limit to how precisely we can know both the simultaneous position of an object and its momentum. For example, if we improve our measurement of an electron's position so that the uncertainty in the position (Δx) has a value of, say, 1 pm (10^{-12} m, about 1% of the diameter of a hydrogen atom), then our determination of its momentum must have an uncertainty with a value of at least

$$\left[\Delta p = m\Delta v = \frac{h}{(2\Delta x)}\right] = \frac{(1.055 \times 10^{-34}\ \text{kg m}^2/\text{s})}{(2 \times 1 \times 10^{-12}\ \text{m})} = 5 \times 10^{-23}\ \text{kg m/s}. \tag{9.3.7}$$

The value of $\hbar$ is not large, so the uncertainty in the position or momentum of a macroscopic object like a baseball is too insignificant to observe. However, the mass of a microscopic object such as an electron is small enough that the uncertainty can be large and significant.

It should be noted that Heisenberg's uncertainty principle is not just limited to uncertainties in position and momentum, but it also links other dynamical variables. For example, when an atom absorbs a photon and makes a transition from one energy state to another, the uncertainty in the energy and the uncertainty in the time required for the transition are similarly related, as $\Delta E\ \Delta t \geq \frac{\hbar}{2}$. As will be discussed later, even the vector components of angular momentum cannot all be specified exactly simultaneously.

Heisenberg's principle imposes ultimate limits on what is knowable in science. The uncertainty principle can be shown to be a consequence of wave–particle duality, which lies at the heart of what distinguishes modern quantum theory from classical mechanics. Recall that the equations of motion obtained from classical mechanics are trajectories where, at any given instant in time, both the position and the momentum of a particle can be determined exactly. Heisenberg's uncertainty principle implies that such a view is untenable in the microscopic domain and that there are fundamental limitations governing the motion of quantum particles. This does not mean that microscopic particles do not move in trajectories, it is just that measurements of trajectories are limited in their precision. In the realm of quantum mechanics, measurements introduce changes into the system that is being observed.



The de Broglie Equation: https://youtu.be/pz0zMHWtK7Q

Summary

An electron possesses both particle and wave properties. The modern model for the electronic structure of the atom is based on recognizing that an electron possesses particle and wave properties, the so-called **wave–particle duality**. Louis de Broglie showed that the wavelength of a particle is equal to Planck's constant divided by the mass times the velocity of the particle. values for all the four quantum numbers.

Glossary

angular momentum quantum number (*l*)
: quantum number distinguishing the different shapes of orbitals; it is also a measure of the orbital angular momentum

atomic orbital
: mathematical function that describes the behavior of an electron in an atom (also called the wavefunction), it can be used to find the probability of locating an electron in a specific region around the nucleus, as well as other dynamical variables

***d* orbital**
: region of space with high electron density that is either four lobed or contains a dumbbell and torus shape; describes orbitals with $l = 2$. An electron in this orbital is called a *d* electron

electron density
: a measure of the probability of locating an electron in a particular region of space, it is equal to the squared absolute value of the wave function ψ

***f* orbital**
: multilobed region of space with high electron density, describes orbitals with $l = 3$. An electron in this orbital is called an *f* electron

Heisenberg uncertainty principle

rule stating that it is impossible to exactly determine both certain conjugate dynamical properties such as the momentum and the position of a particle at the same time. The uncertainty principle is a consequence of quantum particles exhibiting wave–particle duality

magnetic quantum number (m_l)
quantum number signifying the orientation of an atomic orbital around the nucleus; orbitals having different values of m_l but the same subshell value of l have the same energy (are degenerate), but this degeneracy can be removed by application of an external magnetic field

***p* orbital**
dumbbell-shaped region of space with high electron density, describes orbitals with $l = 1$. An electron in this orbital is called a *p* electron

Pauli exclusion principle
specifies that no two electrons in an atom can have the same value for all four quantum numbers

principal quantum number (n)
quantum number specifying the shell an electron occupies in an atom

quantum mechanics
field of study that includes quantization of energy, wave-particle duality, and the Heisenberg uncertainty principle to describe matter

***s* orbital**
spherical region of space with high electron density, describes orbitals with $l = 0$. An electron in this orbital is called an *s* electron

shell
set of orbitals with the same principal quantum number, n

spin quantum number (m_s)
number specifying the electron spin direction, either $+\frac{1}{2}$ or $-\frac{1}{2}$

subshell
set of orbitals in an atom with the same values of n and l

wavefunction (ψ)
mathematical description of an atomic orbital that describes the shape of the orbital; it can be used to calculate the probability of finding the electron at any given location in the orbital, as well as dynamical variables such as the energy and the angular momentum

---

9.3: Wave Nature of Matter is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **6.3: Development of Quantum Theory** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

9.4: The Quantum-Mechanical Model of an Atom

Learning Objectives

- Understand the general idea of the quantum mechanical description of electrons in an atom, and that it uses the notion of three-dimensional wave functions, or orbitals, that define the distribution of probability to find an electron in a particular part of space
- List and describe traits of the four quantum numbers that form the basis for completely specifying the state of an electron in an atom

Shortly after de Broglie published his ideas that the electron in a hydrogen atom could be better thought of as being a circular standing wave instead of a particle moving in quantized circular orbits, as Bohr had argued, Erwin Schrödinger extended de Broglie's work by incorporating the de Broglie relation into a wave equation, deriving what is today known as the Schrödinger equation. When Schrödinger applied his equation to hydrogen-like atoms, he was able to reproduce Bohr's expression for the energy and, thus, the Rydberg formula governing hydrogen spectra, and he did so without having to invoke Bohr's assumptions of stationary states and quantized orbits, angular momenta, and energies; quantization in Schrödinger's theory was a natural consequence of the underlying mathematics of the wave equation. Like de Broglie, Schrödinger initially viewed the electron in hydrogen as being a physical wave instead of a particle, but where de Broglie thought of the electron in terms of circular stationary waves, Schrödinger properly thought in terms of three-dimensional stationary waves, or wavefunctions, represented by the Greek letter psi, ψ. A few years later, Max Born proposed an interpretation of the wavefunction ψ that is still accepted today: Electrons are still particles, and so the waves represented by ψ are not physical waves but, instead, are complex probability amplitudes. The square of the magnitude of a wavefunction $|\psi|^2$ describes the probability of the quantum particle being present near a certain location in space. This means that wavefunctions can be used to determine the distribution of the electron's density with respect to the nucleus in an atom. In the most general form, the Schrödinger equation can be written as:

$$\hat{H}\psi = E\psi \tag{9.4.1}$$

$\hat{H}$ is the Hamiltonian operator, a set of mathematical operations representing the total energy of the quantum particle (such as an electron in an atom), ψ is the wavefunction of this particle that can be used to find the special distribution of the probability of finding the particle, and E is the actual value of the total energy of the particle.

Schrödinger's work, as well as that of Heisenberg and many other scientists following in their footsteps, is generally referred to as quantum mechanics.



Video **9.4.1**: You may also have heard of Schrödinger because of his famous thought experiment. This story explains the concepts of superposition and entanglement as related to a cat in a box with poison (https://www.youtube.com/watch?v=IOYy...eature=youtube).

Understanding Quantum Theory of Electrons in Atoms

The goal of this section is to understand the electron orbitals (location of electrons in atoms), their different energies, and other properties. The use of quantum theory provides the best understanding to these topics. This knowledge is a precursor to chemical bonding.

As was described previously, electrons in atoms can exist only on discrete energy levels but not between them. It is said that the energy of an electron in an atom is quantized, that is, it can be equal only to certain specific values and can jump from one energy level to another but not transition smoothly or stay between these levels.

The energy levels are labeled with an n value, where n = 1, 2, 3, …. Generally speaking, the energy of an electron in an atom is greater for greater values of n. This number, n, is referred to as the principal quantum number. The principal quantum number defines the location of the energy level. It is essentially the same concept as the n in the Bohr atom description. Another name for the principal quantum number is the shell number. The shells of an atom can be thought of concentric circles radiating out from the nucleus. The electrons that belong to a specific shell are most likely to be found within the corresponding circular area. The further we proceed from the nucleus, the higher the shell number, and so the higher the energy level (Figure **9.4.1**). The positively charged protons in the nucleus stabilize the electronic orbitals by electrostatic attraction between the positive charges of the protons and the negative charges of the electrons. So the further away the electron is from the nucleus, the greater the energy it has.




Figure **9.4.1**: Different shells are numbered by principal quantum numbers.

This quantum mechanical model for where electrons reside in an atom can be used to look at electronic transitions, the events when an electron moves from one energy level to another. If the transition is to a higher energy level, energy is absorbed, and the energy change has a positive value. To obtain the amount of energy necessary for the transition to a higher energy level, a photon is absorbed by the atom. A transition to a lower energy level involves a release of energy, and the energy change is negative. This process is accompanied by emission of a photon by the atom. The following equation summarizes these relationships and is based on the hydrogen atom:

$$\begin{aligned}\Delta E &= E_{\text{final}} - E_{\text{initial}} \\ &= -2.18 \times 10^{-18} \left(\frac{1}{n_{\text{f}}^2} - \frac{1}{n_{\text{i}}^2} \right) \text{ J}\end{aligned}$$

The values n_{f} and n_{i} are the final and initial energy states of the electron.

The principal quantum number is one of three quantum numbers used to characterize an orbital. An atomic orbital, which is distinct from an *orbit*, is a general region in an atom within which an electron is most probable to reside. The quantum mechanical model specifies the probability of finding an electron in the three-dimensional space around the nucleus and is based on solutions of the Schrödinger equation. In addition, the principal quantum number defines the energy of an electron in a hydrogen or hydrogen-like atom or an ion (an atom or an ion with only one electron) and the general region in which discrete energy levels of electrons in a multi-electron atoms and ions are located.

Another quantum number is l, the angular momentum quantum number. It is an integer that defines the shape of the orbital, and takes on the values, l = 0, 1, 2, …, n – 1. This means that an orbital with n = 1 can have only one value of l, l = 0, whereas n = 2 permits l = 0 and l = 1, and so on. The principal quantum number defines the general size and energy of the orbital. The l value specifies the shape of the orbital. Orbitals with the same value of l form a subshell. In addition, the greater the angular momentum quantum number, the greater is the angular momentum of an electron at this orbital.

Orbitals with $l = 0$ are called *s* orbitals (or the *s* subshells). The value $l = 1$ corresponds to the *p* orbitals. For a given *n*, *p* orbitals constitute a *p* subshell (e.g., 3*p* if $n = 3$). The orbitals with $l = 2$ are called the *d* orbitals, followed by the *f*-, *g*-, *and h*-orbitals for $l = 3, 4, 5$, and there are higher values we will not consider.

There are certain distances from the nucleus at which the probability density of finding an electron located at a particular orbital is zero. In other words, the value of the wavefunction ψ is zero at this distance for this orbital. Such a value of radius *r* is called a radial node. The number of radial nodes in an orbital is $n - l - 1$.




Figure 9.4.2: The graphs show the probability (y axis) of finding an electron for the 1s, 2s, 3s orbitals as a function of distance from the nucleus.

Consider the examples in Figure 9.4.2. The orbitals depicted are of the *s* type, thus $l = 0$ for all of them. It can be seen from the graphs of the probability densities that there are $1 - 0 - 1 = 0$ places where the density is zero (nodes) for 1*s* ($n = 1$), $2 - 0 - 1 = 1$ node for 2*s*, and $3 - 0 - 1 = 2$ nodes for the 3*s* orbitals.

The *s* subshell electron density distribution is spherical and the *p* subshell has a dumbbell shape. The *d* and *f* orbitals are more complex. These shapes represent the three-dimensional regions within which the electron is likely to be found.




Figure **9.4.3**: Shapes of s, p, d, and f orbitals.

Principal quantum number (n) & Orbital angular momentum (l): The Orbital Subshell: https://youtu.be/ms7WR149fAY

If an electron has an angular momentum ($l \neq 0$), then this vector can point in different directions. In addition, the z component of the angular momentum can have more than one value. This means that if a magnetic field is applied in the z direction, orbitals with different values of the z component of the angular momentum will have different energies resulting from interacting with the field. The magnetic quantum number, called m_l, specifies the z component of the angular momentum for a particular orbital. For example, for an s orbital, $l = 0$, and the only value of m_l is zero. For p orbitals, $l = 1$, and m_l can be equal to –1, 0, or +1. Generally speaking, m_l can be equal to $-l$, $-(l - 1)$, …, –1, 0, +1, …, $(l - 1)$, l. The total number of possible orbitals with the same value of l (a subshell)

is $2l + 1$. Thus, there is one *s*-orbital for $ml = 0$, there are three *p*-orbitals for $ml = 1$, five *d*-orbitals for $ml = 2$, seven *f*-orbitals for $ml = 3$, and so forth. The principal quantum number defines the general value of the electronic energy. The angular momentum quantum number determines the shape of the orbital. And the magnetic quantum number specifies orientation of the orbital in space, as can be seen in Figure **9.4.3**.




Figure **9.4.4**: *The chart shows the energies of electron orbitals in a multi-electron atom.*

Figure **9.4.4** illustrates the energy levels for various orbitals. The number before the orbital name (such as 2*s*, 3*p*, and so forth) stands for the principal quantum number, *n*. The letter in the orbital name defines the subshell with a specific angular momentum quantum number $l = 0$ for *s* orbitals, 1 for *p* orbitals, 2 for *d* orbitals. Finally, there are more than one possible orbitals for $l \geq 1$, each corresponding to a specific value of m_l. In the case of a hydrogen atom or a one-electron ion (such as He^+, Li^{2+}, and so on), energies of all the orbitals with the same *n* are the same. This is called a degeneracy, and the energy levels for the same principal quantum number, *n*, are called degenerate energy levels. However, in atoms with more than one electron, this degeneracy is eliminated by the electron–electron interactions, and orbitals that belong to different subshells have different energies. Orbitals within the same subshell (for example *ns*, *np*, *nd*, *nf*, such as 2*p*, 3*s*) are still degenerate and have the same energy.

While the three quantum numbers discussed in the previous paragraphs work well for describing electron orbitals, some experiments showed that they were not sufficient to explain all observed results. It was demonstrated in the 1920s that when hydrogen-line spectra are examined at extremely high resolution, some lines are actually not single peaks but, rather, pairs of closely spaced lines. This is the so-called fine structure of the spectrum, and it implies that there are additional small differences in energies of electrons even when they are located in the same orbital. These observations led Samuel Goudsmit and George Uhlenbeck to propose that electrons have a fourth quantum number. They called this the spin quantum number, or m_s.

The other three quantum numbers, *n*, *l*, and m_l, are properties of specific atomic orbitals that also define in what part of the space an electron is most likely to be located. Orbitals are a result of solving the Schrödinger equation for electrons in atoms. The electron spin is a different kind of property. It is a completely quantum phenomenon with no analogues in the classical realm. In addition, it cannot be derived from solving the Schrödinger equation and is not related to the normal spatial coordinates (such as the Cartesian *x*, *y*, and *z*). Electron spin describes an intrinsic electron "rotation" or "spinning." Each electron acts as a tiny magnet or a tiny rotating object with an angular momentum, even though this rotation cannot be observed in terms of the spatial coordinates.

The magnitude of the overall electron spin can only have one value, and an electron can only "spin" in one of two quantized states. One is termed the α state, with the *z* component of the spin being in the positive direction of the *z* axis. This corresponds to the spin quantum number $m_s = \frac{1}{2}$. The other is called the β state, with the *z* component of the spin being negative and $m_s = -\frac{1}{2}$. Any electron, regardless of the atomic orbital it is located in, can only have one of those two values of the spin quantum number. The energies of electrons having $m_s = -\frac{1}{2}$ and $m_s = \frac{1}{2}$ are different if an external magnetic field is applied.




Figure **9.4.5**: Electrons with spin values \(±\ce{1/2}\) *in an external magnetic field.*

Figure **9.4.5** illustrates this phenomenon. An electron acts like a tiny magnet. Its moment is directed up (in the positive direction of the *z* axis) for the $\frac{1}{2}$ spin quantum number and down (in the negative *z* direction) for the spin quantum number of $-\frac{1}{2}$. A magnet has a lower energy if its magnetic moment is aligned with the external magnetic field (the left electron) and a higher energy for the magnetic moment being opposite to the applied field. This is why an electron with $m_s = \frac{1}{2}$ has a slightly lower energy in an external field in the positive *z* direction, and an electron with $m_s = -\frac{1}{2}$ has a slightly higher energy in the same field. This is true even for an electron occupying the same orbital in an atom. A spectral line corresponding to a transition for electrons from the same orbital but with different spin quantum numbers has two possible values of energy; thus, the line in the spectrum will show a fine structure splitting.



Magnetic Quantum Number (ml) & Spin Quantum Number (ms): https://youtu.be/gbmGVUXBOBk

The Pauli Exclusion Principle

An electron in an atom is completely described by four quantum numbers: *n*, *l*, m_l, and m_s. The first three quantum numbers define the orbital and the fourth quantum number describes the intrinsic electron property called spin. An Austrian physicist Wolfgang Pauli formulated a general principle that gives the last piece of information that we need to understand the general behavior of electrons in atoms. The Pauli exclusion principle can be formulated as follows: No two electrons in the same atom can have exactly the same set of all the four quantum numbers. What this means is that electrons can share the same orbital (the same set of the quantum numbers *n*, *l*, and m_l), but only if their spin quantum numbers m_s have different values. Since the spin quantum number can only have two values $\left(\pm\frac{1}{2}\right)$, no more than two electrons can occupy the same orbital (and if two electrons are located in the same orbital, they must have opposite spins). Therefore, any atomic orbital can be populated by only zero, one, or two electrons. The properties and meaning of the quantum numbers of electrons in atoms are briefly summarized in Table **9.4.1**.

Table **9.4.1***: Quantum Numbers, Their Properties, and Significance*

Name	Symbol	Allowed values	Physical meaning
principal quantum number	n	1, 2, 3, 4, ….	shell, the general region for the value of energy for an electron on the orbital
angular momentum or azimuthal quantum number	l	$0 \le l \le n-1$	subshell, the shape of the orbital
magnetic quantum number	m_l	$-l \le m_l \le l$	orientation of the orbital
spin quantum number	m_s	$\frac{1}{2}, -\frac{1}{2}$	direction of the intrinsic quantum "spinning" of the electron

Example 9.4.1: Working with Shells and Subshells

Indicate the number of subshells, the number of orbitals in each subshell, and the values of l and m_l for the orbitals in the $n = 4$ shell of an atom.

Solution

For $n = 4$, l can have values of 0, 1, 2, and 3. Thus, *s*, *p*, *d*, and *f* subshells are found in the $n = 4$ shell of an atom. For $l = 0$ (the *s* subshell), m_l can only be 0. Thus, there is only one 4*s* orbital. For $l = 1$ (*p*-type orbitals), m can have values of –1, 0, +1, so we find three 4*p* orbitals. For $l = 2$ (*d*-type orbitals), m_l can have values of –2, –1, 0, +1, +2, so we have five 4*d* orbitals. When $l = 3$ (*f*-type orbitals), m_l can have values of –3, –2, –1, 0, +1, +2, +3, and we can have seven 4*f* orbitals. Thus, we find a total of 16 orbitals in the $n = 4$ shell of an atom.

Exercise 9.4.1

Identify the subshell in which electrons with the following quantum numbers are found:

a. $n = 3$, $l = 1$;
b. $n = 5$, $l = 3$;
c. $n = 2$, $l = 0$.

Answer a

3*p*

Answer b

5*f*

Answer c

2s

Example 9.4.2: Maximum Number of Electrons

Calculate the maximum number of electrons that can occupy a shell with (a) $n = 2$, (b) $n = 5$, and (c) n as a variable. Note you are only looking at the orbitals with the specified n value, not those at lower energies.

Solution

(a) When $n = 2$, there are four orbitals (a single 2*s* orbital, and three orbitals labeled 2*p*). These four orbitals can contain eight electrons.

(b) When $n = 5$, there are five subshells of orbitals that we need to sum:

1 orbital labeled 5*s*
3 orbitals labeled 5*p*
5 orbitals labeled 5*d*
7 orbitals labeled 5*f*
+9 orbitals labeled 5*g*
25 orbitals total

Again, each orbital holds two electrons, so 50 electrons can fit in this shell.

(c) The number of orbitals in any shell n will equal n^2. There can be up to two electrons in each orbital, so the maximum number of electrons will be $2 \times n^2$

Exercise 9.4.2

If a shell contains a maximum of 32 electrons, what is the principal quantum number, n?

Answer

$n = 4$

Example 9.4.3: Working with Quantum Numbers

Complete the following table for atomic orbitals:

Orbital	n	l	m_l degeneracy	Radial nodes (no.)
4*f*				
	4	1		
	7		7	3
5*d*				

Solution

The table can be completed using the following rules:

- The orbital designation is nl, where $l = 0, 1, 2, 3, 4, 5, \ldots$ is mapped to the letter sequence s, *p*, *d*, *f*, *g*, *h*, …,
- The m_l degeneracy is the number of orbitals within an l subshell, and so is $2l + 1$ (there is one *s* orbital, three *p* orbitals, five *d* orbitals, seven *f* orbitals, and so forth).
- The number of radial nodes is equal to $n - l - 1$.

Orbital	n	l	m_l **degeneracy**	**Radial nodes (no.)**
4*f*	4	3	7	0
4*p*	4	1	3	2
7*f*	7	3	7	3
5*d*	5	2	5	2



Summary of the Rules for Quantum Numbers: https://youtu.be/nRsRZUsOBzE

? Exercise 9.4.3

How many orbitals have $l = 2$ and $n = 3$?

Answer

The five degenerate 3*d* orbitals

Summary

The quantum mechanical model of atoms describes the three-dimensional position of the electron in a *probabilistic* manner according to a mathematical function called a wavefunction, often denoted as ψ. Atomic wavefunctions are also called orbitals. The squared magnitude of the wavefunction describes the distribution of the probability of finding the electron in a particular region in space. Therefore, atomic orbitals describe the areas in an atom where electrons are most likely to be found.

An atomic orbital is characterized by three quantum numbers. The principal quantum number, n, can be any positive integer. The general region for value of energy of the orbital and the average distance of an electron from the nucleus are related to n. Orbitals having the same value of n are said to be in the same shell. The angular momentum quantum number, l, can have any integer value from 0 to $n – 1$. This quantum number describes the shape or type of the orbital. Orbitals with the same principal quantum number and the same l value belong to the same subshell. The magnetic quantum number, m_l, with $2l + 1$ values ranging from $–l$ to $+l$, describes the orientation of the orbital in space. In addition, each electron has a spin quantum number, m_s, that can be equal to $\pm\frac{1}{2}$. No two electrons in the same atom can have the same set of values for all the four quantum numbers.

Glossary

angular momentum quantum number (*l*)

quantum number distinguishing the different shapes of orbitals; it is also a measure of the orbital angular momentum

atomic orbital

mathematical function that describes the behavior of an electron in an atom (also called the wavefunction), it can be used to find the probability of locating an electron in a specific region around the nucleus, as well as other dynamical variables

***d* orbital**

region of space with high electron density that is either four lobed or contains a dumbbell and torus shape; describes orbitals with $l = 2$. An electron in this orbital is called a *d* electron

electron density

a measure of the probability of locating an electron in a particular region of space, it is equal to the squared absolute value of the wave function ψ

_f_ orbital

multilobed region of space with high electron density, describes orbitals with $l = 3$. An electron in this orbital is called an *f* electron

magnetic quantum number (m_l)

quantum number signifying the orientation of an atomic orbital around the nucleus; orbitals having different values of m_l but the same subshell value of l have the same energy (are degenerate), but this degeneracy can be removed by application of an external magnetic field

***p* orbital**

dumbbell-shaped region of space with high electron density, describes orbitals with $l = 1$. An electron in this orbital is called a *p* electron

Pauli exclusion principle

specifies that no two electrons in an atom can have the same value for all four quantum numbers

principal quantum number (n)

quantum number specifying the shell an electron occupies in an atom

quantum mechanics

field of study that includes quantization of energy, wave-particle duality, and the Heisenberg uncertainty principle to describe matter

***s* orbital**

spherical region of space with high electron density, describes orbitals with $l = 0$. An electron in this orbital is called an *s* electron

shell

set of orbitals with the same principal quantum number, n

spin quantum number (m_s)

number specifying the electron spin direction, either $+\frac{1}{2}$ or $-\frac{1}{2}$

subshell

set of orbitals in an atom with the same values of n and l

wavefunction (ψ)

mathematical description of an atomic orbital that describes the shape of the orbital; it can be used to calculate the probability of finding the electron at any given location in the orbital, as well as dynamical variables such as the energy and the angular momentum

---

9.4: The Quantum-Mechanical Model of an Atom is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **6.3: Development of Quantum Theory** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

9.5: Electron Configuration of Atoms

Learning Objectives

- Derive the predicted ground-state electron configurations of atoms
- Identify and explain exceptions to predicted electron configurations for atoms and ions
- Relate electron configurations to element classifications in the periodic table

Having introduced the basics of atomic structure and quantum mechanics, we can use our understanding of quantum numbers to determine how atomic orbitals relate to one another. This allows us to determine which orbitals are occupied by electrons in each atom. The specific arrangement of electrons in orbitals of an atom determines many of the chemical properties of that atom.

Orbital Energies and Atomic Structure

The energy of atomic orbitals increases as the principal quantum number, n, increases. In any atom with two or more electrons, the repulsion between the electrons makes energies of subshells with different values of l differ so that the energy of the orbitals increases within a shell in the order $s < p < d < f$. Figure **9.5.1** depicts how these two trends in increasing energy relate. The 1*s* orbital at the bottom of the diagram is the orbital with electrons of lowest energy. The energy increases as we move up to the 2*s* and then 2*p*, 3*s*, and 3*p* orbitals, showing that the increasing *n* value has more influence on energy than the increasing *l* value for small atoms. However, this pattern does not hold for larger atoms. The 3*d* orbital is higher in energy than the 4*s* orbital. Such overlaps continue to occur frequently as we move up the chart.




Figure **9.5.1**: Generalized energy-level diagram for atomic orbitals in an atom with two or more electrons (not to scale).

Electrons in successive atoms on the periodic table tend to fill low-energy orbitals first. Thus, many students find it confusing that, for example, the 5*p* orbitals fill immediately after the 4*d*, and immediately before the 6*s*. The filling order is based on observed experimental results, and has been confirmed by theoretical calculations. As the principal quantum number, *n*, increases, the size of the orbital increases and the electrons spend more time farther from the nucleus. Thus, the attraction to the nucleus is weaker and the energy associated with the orbital is higher (less stabilized). But this is not the only effect we have to take into account. Within each shell, as the value of *l* increases, the electrons are less penetrating (meaning there is less electron density found close to the nucleus), in the order $s > p > d > f$. Electrons that are closer to the nucleus slightly repel electrons that are farther out, offsetting the more dominant electron–nucleus attractions slightly (recall that all electrons have −1 charges, but nuclei have $+Z$ charges). This phenomenon is called shielding and will be discussed in more detail in the next section. Electrons in orbitals that experience more shielding are less stabilized and thus higher in energy. For small orbitals (1*s* through 3*p*), the increase in energy due to *n* is more significant than the increase due to *l*; however, for larger orbitals the two trends are comparable and cannot be simply predicted. We will discuss methods for remembering the observed order.

The arrangement of electrons in the orbitals of an atom is called the electron configuration of the atom. We describe an electron configuration with a symbol that contains three pieces of information (Figure **9.5.2**):

1. The number of the principal quantum shell, n,
2. The letter that designates the orbital type (the subshell, l), and
3. A superscript number that designates the number of electrons in that particular subshell.

For example, the notation $2p^4$ (read "two–p–four") indicates four electrons in a p subshell (l = 1) with a principal quantum number (n) of 2. The notation $3d^8$ (read "three–d–eight") indicates eight electrons in the d subshell (i.e., l = 2) of the principal shell for which n = 3.




Figure **9.5.2**: The diagram of an electron configuration specifies the subshell (n and l value, with letter symbol) and superscript number of electrons.

The Aufbau Principle

To determine the electron configuration for any particular atom, we can “build” the structures in the order of atomic numbers. Beginning with hydrogen, and continuing across the periods of the periodic table, we add one proton at a time to the nucleus and one electron to the proper subshell until we have described the electron configurations of all the elements. This procedure is called the Aufbau principle, from the German word *Aufbau* (“to build up”). Each added electron occupies the subshell of lowest energy available (in the order shown in Figure **9.5.3**), subject to the limitations imposed by the allowed quantum numbers according to the Pauli exclusion principle. Electrons enter higher-energy subshells only after lower-energy subshells have been filled to capacity. Figure **9.5.3** illustrates the traditional way to remember the filling order for atomic orbitals.




Figure **9.5.3**: The arrow leads through each subshell in the appropriate filling order for electron configurations. This chart is straightforward to construct. Simply make a column for all the s orbitals with each n shell on a separate row. Repeat for p, d, and f. Be sure to only include orbitals allowed by the quantum numbers (no 1p or 2d, and so forth). Finally, draw diagonal lines from top to bottom as shown.

Since the arrangement of the periodic table is based on the electron configurations, Figure **9.5.4** provides an alternative method for determining the electron configuration. The filling order simply begins at hydrogen and includes each subshell as you proceed in increasing Z order. For example, after filling the 3p block up to Ar, we see the orbital will be 4s (K, Ca), followed by the 3d orbitals.





Figure 9.5.4: This periodic table shows the electron configuration for each subshell. By “building up” from hydrogen, this table can be used to determine the electron configuration for any atom on the periodic table.




Electron Configuration of Atoms: https://youtu.be/LlY-O3-bfnk

We will now construct the ground-state electron configuration and orbital diagram for a selection of atoms in the first and second periods of the periodic table. Orbital diagrams are pictorial representations of the electron configuration, showing the individual orbitals and the pairing arrangement of electrons. We start with a single hydrogen atom (atomic number 1), which consists of one proton and one electron. Referring to either Figure 9.5.3 or 9.5.4, we would expect to find the electron in the 1*s* orbital. By convention, the $m_s = +\frac{1}{2}$ value is usually filled first. The electron configuration and the orbital diagram are:


H $1s^1$ 

Following hydrogen is the noble gas helium, which has an atomic number of 2. The helium atom contains two protons and two electrons. The first electron has the same four quantum numbers as the hydrogen atom electron (n = 1, l = 0, m_l = 0, $m_s = +\frac{1}{2}$). The second electron also goes into the 1*s* orbital and fills that orbital. The second electron has the same n, l, and m_l quantum numbers, but must have the opposite spin quantum number, $m_s = -\frac{1}{2}$. This is in accord with the Pauli exclusion principle: No two electrons in the same atom can have the same set of four quantum numbers. For orbital diagrams, this means two arrows go in each box (representing two electrons in each orbital) and the arrows must point in opposite directions (representing paired spins). The electron configuration and orbital diagram of helium are:




The n = 1 shell is completely filled in a helium atom.


The next atom is the alkali metal lithium with an atomic number of 3. The first two electrons in lithium fill the 1*s* orbital and have the same sets of four quantum numbers as the two electrons in helium. The remaining electron must occupy the orbital of next lowest energy, the 2*s* orbital (Figure **9.5.3** or **9.5.4**). Thus, the electron configuration and orbital diagram of lithium are:




An atom of the alkaline earth metal beryllium, with an atomic number of 4, contains four protons in the nucleus and four electrons surrounding the nucleus. The fourth electron fills the remaining space in the 2*s* orbital.



An atom of boron (atomic number 5) contains five electrons. The n = 1 shell is filled with two electrons and three electrons will occupy the n = 2 shell. Because any *s* subshell can contain only two electrons, the fifth electron must occupy the next energy level, which will be a 2*p* orbital. There are three degenerate 2*p* orbitals (m_l = −1, 0, +1) and the electron can occupy any one of these *p* orbitals. When drawing orbital diagrams, we include empty boxes to depict any empty orbitals in the same subshell that we are filling.



Carbon (atomic number 6) has six electrons. Four of them fill the 1*s* and 2*s* orbitals. The remaining two electrons occupy the 2*p* subshell. We now have a choice of filling one of the 2*p* orbitals and pairing the electrons or of leaving the electrons unpaired in two different, but degenerate, *p* orbitals. The orbitals are filled as described by Hund's rule: the lowest-energy configuration for an atom with electrons within a set of degenerate orbitals is that having the maximum number of unpaired electrons. Thus, the two electrons in the carbon 2*p* orbitals have identical n, l, and m_s quantum numbers and differ in their m_l quantum number (in accord with the Pauli exclusion principle). The electron configuration and orbital diagram for carbon are:



Nitrogen (atomic number 7) fills the 1*s* and 2*s* subshells and has one electron in each of the three 2*p* orbitals, in accordance with Hund's rule. These three electrons have unpaired spins. Oxygen (atomic number 8) has a pair of electrons in any one of the 2*p* orbitals (the electrons have opposite spins) and a single electron in each of the other two. Fluorine (atomic number 9) has only one 2*p* orbital containing an unpaired electron. All of the electrons in the noble gas neon (atomic number 10) are paired, and all of the orbitals in the $n = 1$ and the $n = 2$ shells are filled. The electron configurations and orbital diagrams of these four elements are:




Figure **9.5.5**: Since the core electron shells correspond to noble gas electron configurations, we can abbreviate electron configurations by writing the noble gas that matches the core electron configuration, along with the valence electrons in a condensed format. For our sodium example, the symbol [Ne] represents core electrons, ($1s^2 2s^2 2p^6$) and our abbreviated or condensed configuration is [Ne]$3s^1$.

The alkali metal sodium (atomic number 11) has one more electron than the neon atom. This electron must go into the lowest-energy subshell available, the 3*s* orbital, giving a $1s^2 2s^2 2p^6 3s^1$ configuration. The electrons occupying the outermost shell orbital(s) (highest value of *n*) are called valence electrons, and those occupying the inner shell orbitals are called core electrons (Figure \PageIndex5\PageIndex5). Since the core electron shells correspond to noble gas electron configurations, we can abbreviate electron configurations by writing the noble gas that matches the core electron configuration, along with the valence electrons in a condensed format. For our sodium example, the symbol [Ne] represents core electrons, ($1s^2 2s^2 2p^6$) and our abbreviated or condensed configuration is [Ne]$3s^1$.




Figure **9.5.5**: A core-abbreviated electron configuration (right) replaces the core electrons with the noble gas symbol whose configuration matches the core electron configuration of the other element.



Definition of Valence Electrons: https://youtu.be/_ldxOYwM2VM

Similarly, the abbreviated configuration of lithium can be represented as [He]$2s^1$, where [He] represents the configuration of the helium atom, which is identical to that of the filled inner shell of lithium. Writing the configurations in this way emphasizes the similarity of the configurations of lithium and sodium. Both atoms, which are in the alkali metal family, have only one electron in a valence *s* subshell outside a filled set of inner shells.

$$\begin{aligned} \mathbf{Li:[He]}\,\mathbf{2}s^{\mathbf{1}} \\ \mathbf{Na:[Ne]}\,\mathbf{3}s^{\mathbf{1}} \end{aligned} \tag{9.5.1}$$

The alkaline earth metal magnesium (atomic number 12), with its 12 electrons in a [Ne]$3s^2$ configuration, is analogous to its family member beryllium, [He]$2s^2$. Both atoms have a filled *s* subshell outside their filled inner shells. Aluminum (atomic number 13), with 13 electrons and the electron configuration [Ne]$3s^23p^1$, is analogous to its family member boron, [He]$2s^22p^1$.

The electron configurations of silicon (14 electrons), phosphorus (15 electrons), sulfur (16 electrons), chlorine (17 electrons), and argon (18 electrons) are analogous in the electron configurations of their outer shells to their corresponding family members carbon, nitrogen, oxygen, fluorine, and neon, respectively, except that the principal quantum number of the outer shell of the heavier elements has increased by one to $n = 3$. Figure **9.5.6** shows the lowest energy, or ground-state, electron configuration for these elements as well as that for atoms of each of the known elements.




Figure **9.5.6**: This version of the periodic table shows the outer-shell electron configuration of each element. Note that down each group, the configuration is often similar.

When we come to the next element in the periodic table, the alkali metal potassium (atomic number 19), we might expect that we would begin to add electrons to the 3*d* subshell. However, all available chemical and physical evidence indicates that potassium is like lithium and sodium, and that the next electron is not added to the 3*d* level but is, instead, added to the 4*s* level (Figure **9.5.3** or **9.5.4**). As discussed previously, the 3*d* orbital with no radial nodes is higher in energy because it is less penetrating and more shielded from the nucleus than the 4*s*, which has three radial nodes. Thus, potassium has an electron configuration of [Ar]$4s^1$. Hence, potassium corresponds to Li and Na in its valence shell configuration. The next electron is added to complete the 4*s* subshell and calcium has an electron configuration of [Ar]$4s^2$. This gives calcium an outer-shell electron configuration corresponding to that of beryllium and magnesium.

Beginning with the transition metal scandium (atomic number 21), additional electrons are added successively to the 3*d* subshell. This subshell is filled to its capacity with 10 electrons (remember that for $l = 2$ [*d* orbitals], there are $2l + 1 = 5$ values of m_l, meaning that there are five *d* orbitals that have a combined capacity of 10 electrons). The 4*p* subshell fills next. Note that for three series of elements, scandium (Sc) through copper (Cu), yttrium (Y) through silver (Ag), and lutetium (Lu) through gold (Au), a total of 10 *d* electrons are successively added to the $(n - 1)$ shell next to the *n* shell to bring that $(n - 1)$ shell from 8 to 18 electrons. For two series, lanthanum (La) through lutetium (Lu) and actinium (Ac) through lawrencium (Lr), 14 *f* electrons ($l = 3$, $2l + 1 = 7$ m_l values; thus, seven orbitals with a combined capacity of 14 electrons) are successively added to the $(n - 2)$ shell to bring that shell from 18 electrons to a total of 32 electrons.



Electron Configuration of Transition Metals: https://youtu.be/HzpfE0fk_E0


Example 9.5.1: Quantum Numbers and Electron Configurations

What is the electron configuration and orbital diagram for a phosphorus atom? What are the four quantum numbers for the last electron added?

Solution

The atomic number of phosphorus is 15. Thus, a phosphorus atom contains 15 electrons. The order of filling of the energy levels is 1*s*, 2*s*, 2*p*, 3*s*, 3*p*, 4*s*, . . . The 15 electrons of the phosphorus atom will fill up to the 3*p* orbital, which will contain three electrons:

P $1s^2 2s^2 2p^6 3s^2 3p^3$



The last electron added is a 3*p* electron. Therefore, $n = 3$ and, for a *p*-type orbital, $l = 1$. The m_l value could be –1, 0, or +1. The three *p* orbitals are degenerate, so any of these m_l values is correct. For unpaired electrons, convention assigns the value of $+\frac{1}{2}$ for the spin quantum number; thus, $m_s = +\frac{1}{2}$.

Exercise 9.5.1

Identify the atoms from the electron configurations given:

a. [Ar]$4s^2 3d^5$
b. [Kr]$5s^2 4d^{10} 5p^6$

Answer a

Mn

Answer b

Xe



Writing Quantum Number from Electron Configurations: https://youtu.be/SoUhs2_YnKU

The periodic table can be a powerful tool in predicting the electron configuration of an element. However, we do find exceptions to the order of filling of orbitals that are shown in Figure **9.5.3** or **9.5.4**. For instance, the electron configurations of the transition metals chromium (Cr; atomic number 24) and copper (Cu; atomic number 29), among others, are not those we would expect. In general, such exceptions involve subshells with very similar energy, and small effects can lead to changes in the order of filling.

In the case of Cr and Cu, we find that half-filled and completely filled subshells apparently represent conditions of preferred stability. This stability is such that an electron shifts from the 4*s* into the 3*d* orbital to gain the extra stability of a half-filled 3*d* subshell (in Cr) or a filled 3*d* subshell (in Cu). Other exceptions also occur. For example, niobium (Nb, atomic number 41) is predicted to have the electron configuration [Kr]$5s^2 4d^3$. Experimentally, we observe that its ground-state electron configuration is actually [Kr]$5s^1 4d^4$. We can rationalize this observation by saying that the electron–electron repulsions experienced by pairing the electrons in the 5*s* orbital are larger than the gap in energy between the 5*s* and 4*d* orbitals. There is no simple method to predict the exceptions for atoms where the magnitude of the repulsions between electrons is greater than the small differences in energy between subshells.

Electron Configurations and the Periodic Table

As described earlier, the periodic table arranges atoms based on increasing atomic number so that elements with the same chemical properties recur periodically. When their electron configurations are added to the table (Figure **9.5.6**), we also see a periodic recurrence of similar electron configurations in the outer shells of these elements. Because they are in the outer shells of an atom, valence electrons play the most important role in chemical reactions. The outer electrons have the highest energy of the electrons in an atom and are more easily lost or shared than the core electrons. Valence electrons are also the determining factor in some physical properties of the elements.

Elements in any one group (or column) have the same number of valence electrons; the alkali metals lithium and sodium each have only one valence electron, the alkaline earth metals beryllium and magnesium each have two, and the halogens fluorine and chlorine each have seven valence electrons. The similarity in chemical properties among elements of the same group occurs because they have the same number of valence electrons. It is the loss, gain, or sharing of valence electrons that defines how elements react.

It is important to remember that the periodic table was developed on the basis of the chemical behavior of the elements, well before any idea of their atomic structure was available. Now we can understand why the periodic table has the arrangement it has—the arrangement puts elements whose atoms have the same number of valence electrons in the same group. This arrangement is emphasized in Figure **9.5.6**, which shows in periodic-table form the electron configuration of the last subshell to be filled by the Aufbau principle. The colored sections of Figure **9.5.6** show the three categories of elements classified by the orbitals being filled: main group, transition, and inner transition elements. These classifications determine which orbitals are counted in the valence shell, or highest energy level orbitals of an atom.

1. **Main group elements** (sometimes called **representative elements**) are those in which the last electron added enters an *s* or a *p* orbital in the outermost shell, shown in blue and red in Figure **9.5.6**. This category includes all the nonmetallic elements, as well

as many metals and the intermediate semimetallic elements. The valence electrons for main group elements are those with the highest *n* level. For example, gallium (Ga, atomic number 31) has the electron configuration [Ar]$\underline{4s^2}3d^{10}\underline{4p^1}$, which contains three valence electrons (underlined). The completely filled *d* orbitals count as core, not valence, electrons.

2. **Transition elements or transition metals**. These are metallic elements in which the last electron added enters a *d* orbital. The valence electrons (those added after the last noble gas configuration) in these elements include the *ns* and (*n* – 1) *d* electrons. The official IUPAC definition of transition elements specifies those with partially filled *d* orbitals. Thus, the elements with completely filled orbitals (Zn, Cd, Hg, as well as Cu, Ag, and Au in Figure **9.5.6**) are not technically transition elements. However, the term is frequently used to refer to the entire *d* block (colored yellow in Figure **9.5.6**), and we will adopt this usage in this textbook.
3. **Inner transition elements** are metallic elements in which the last electron added occupies an *f* orbital. They are shown in green in Figure **9.5.6**. The valence shells of the inner transition elements consist of the (*n* – 2)*f*, the (*n* – 1)*d*, and the *ns* subshells. There are two inner transition series:
    1. The lanthanide series: lanthanide (La) through lutetium (Lu)
    2. The actinide series: actinide (Ac) through lawrencium (Lr)

Lanthanum and actinium, because of their similarities to the other members of the series, are included and used to name the series, even though they are transition metals with no *f* electrons.

Summary

The relative energy of the subshells determine the order in which atomic orbitals are filled (1*s*, 2*s*, 2*p*, 3*s*, 3*p*, 4*s*, 3*d*, 4*p*, and so on). Electron configurations and orbital diagrams can be determined by applying the Pauli exclusion principle (no two electrons can have the same set of four quantum numbers) and Hund's rule (whenever possible, electrons retain unpaired spins in degenerate orbitals).

Electrons in the outermost orbitals, called valence electrons, are responsible for most of the chemical behavior of elements. In the periodic table, elements with analogous valence electron configurations usually occur within the same group. There are some exceptions to the predicted filling order, particularly when half-filled or completely filled orbitals can be formed. The periodic table can be divided into three categories based on the orbital in which the last electron to be added is placed: main group elements (*s* and *p* orbitals), transition elements (*d* orbitals), and inner transition elements (*f* orbitals).

Glossary

Aufbau principle
: procedure in which the electron configuration of the elements is determined by "building" them in order of atomic numbers, adding one proton to the nucleus and one electron to the proper subshell at a time

core electron
: electron in an atom that occupies the orbitals of the inner shells

electron configuration
: electronic structure of an atom in its ground state given as a listing of the orbitals occupied by the electrons

Hund's rule
: every orbital in a subshell is singly occupied with one electron before any one orbital is doubly occupied, and all electrons in singly occupied orbitals have the same spin

orbital diagram
: pictorial representation of the electron configuration showing each orbital as a box and each electron as an arrow

valence electrons
: electrons in the outermost or valence shell (highest value of *n*) of a ground-state atom; determine how an element reacts

valence shell

outermost shell of electrons in a ground-state atom; for main group elements, the orbitals with the highest *n* level (*s* and *p* subshells) are in the valence shell, while for transition metals, the highest energy *s* and *d* subshells make up the valence shell and for inner transition elements, the highest *s*, *d*, and *f* subshells are included

---

9.5: Electron Configuration of Atoms is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **6.4: Electronic Structure of Atoms (Electron Configurations)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

9.6: Electron Configurations of Ions

Learning Objectives

- Identify and explain exceptions to predicted electron configurations for atoms and ions

We have seen that ions are formed when atoms gain or lose electrons. A cation (positively charged ion) forms when one or more electrons are removed from a parent atom. For main group elements, the electrons that were added last are the first electrons removed. For transition metals and inner transition metals, however, electrons in the *s* orbital are easier to remove than the *d* or *f* electrons, and so the highest *ns* electrons are lost, and then the $(n-1)d$ or $(n-2)f$ electrons are removed. An anion (negatively charged ion) forms when one or more electrons are added to a parent atom. The added electrons fill in the order predicted by the Aufbau principle.

Example 9.6.2: Predicting Electron Configurations of Ions

What is the electron configuration and orbital diagram of:

a. Na^+
b. P^{3-}
c. Al^{2+}
d. Fe^{2+}
e. Sm^{3+}

Solution

First, write out the electron configuration for each parent atom. We have chosen to show the full, unabbreviated configurations to provide more practice for students who want it, but listing the core-abbreviated electron configurations is also acceptable.

Next, determine whether an electron is gained or lost. Remember electrons are negatively charged, so ions with a positive charge have *lost* an electron. For main group elements, the last orbital gains or loses the electron. For transition metals, the last *s* orbital loses an electron before the *d* orbitals.

a. Na: $1s^2 2s^2 2p^6 3s^1$. Sodium cation loses one electron, so Na^+: $1s^2 2s^2 2p^6 3s^1 = Na^+$: $1s^2 2s^2 2p^6$.
b. P: $1s^2 2s^2 2p^6 3s^2 3p^3$. Phosphorus trianion gains three electrons, so P^{3-}: $1s^2 2s^2 2p^6 3s^2 3p^6$.
c. Al: $1s^2 2s^2 2p^6 3s^2 3p^1$. Aluminum dication loses two electrons Al^{2+}: $1s^2 2s^2 2p^6 3s^2 3p^1 = Al^{2+}$: $1s^2 2s^2 2p^6 3s^1$.
d. Fe: $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^6$. Iron(II) loses two electrons and, since it is a transition metal, they are removed from the 4*s* orbital Fe^{2+}: $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^6 = 1s^2 2s^2 2p^6 3s^2 3p^6 3d^6$.
e. Sm: $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10} 4p^6 5s^2 4d^{10} 5p^6 6s^2 4f^6$. Samarium trication loses three electrons. The first two will be lost from the 6*s* orbital, and the final one is removed from the 4*f* orbital. Sm^{3+}: $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10} 4p^6 5s^2 4d^{10} 5p^6 6s^2 4f^6 = 1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10} 4p^6 5s^2 4d^{10} 5p^6 4f^5$.

Exercise 9.6.2

a. Which ion with a +2 charge has the electron configuration $1s^2 2s^2 2p^6 3s^2 3p^6 3d^{10} 4s^2 4p^6 4d^5$?
b. Which ion with a +3 charge has this configuration?

Answer a

Tc^{2+}

Answer b

Ru^{3+}

Summary

The relative energy of the subshells determine the order in which atomic orbitals are filled (1*s*, 2*s*, 2*p*, 3*s*, 3*p*, 4*s*, 3*d*, 4*p*, and so on). Electron configurations and orbital diagrams can be determined by applying the Pauli exclusion principle (no two electrons can have the same set of four quantum numbers) and Hund's rule (whenever possible, electrons retain unpaired spins in degenerate orbitals).

Electrons in the outermost orbitals, called valence electrons, are responsible for most of the chemical behavior of elements. In the periodic table, elements with analogous valence electron configurations usually occur within the same group. There are some exceptions to the predicted filling order, particularly when half-filled or completely filled orbitals can be formed. The periodic table can be divided into three categories based on the orbital in which the last electron to be added is placed: main group elements (*s* and *p* orbitals), transition elements (*d* orbitals), and inner transition elements (*f* orbitals).

9.6: Electron Configurations of Ions is shared under a CC BY-NC-SA 4.0 license and was authored, remixed, and/or curated by LibreTexts.

- **6.4: Electronic Structure of Atoms (Electron Configurations)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

9.7: Periodic Trends

Learning Objectives


- Describe and explain the observed trends in atomic size, ionization energy, and electron affinity of the elements

The elements in groups (vertical columns) of the periodic table exhibit similar chemical behavior. This similarity occurs because the members of a group have the same number and distribution of electrons in their valence shells. However, there are also other patterns in chemical properties on the periodic table. For example, as we move down a group, the metallic character of the atoms increases. Oxygen, at the top of Group 16 (6A), is a colorless gas; in the middle of the group, selenium is a semiconducting solid; and, toward the bottom, polonium is a silver-grey solid that conducts electricity.


As we go across a period from left to right, we add a proton to the nucleus and an electron to the valence shell with each successive element. As we go down the elements in a group, the number of electrons in the valence shell remains constant, but the principal quantum number increases by one each time. An understanding of the electronic structure of the elements allows us to examine some of the properties that govern their chemical behavior. These properties vary periodically as the electronic structure of the elements changes. They are (1) size (radius) of atoms and ions, (2) ionization energies, and (3) electron affinities.

Variation in Covalent Radius

The quantum mechanical picture makes it difficult to establish a definite size of an atom. However, there are several practical ways to define the radius of atoms and, thus, to determine their relative sizes that give roughly similar values. We will use the covalent radius (Figure **9.7.1**), which is defined as one-half the distance between the nuclei of two identical atoms when they are joined by a covalent bond (this measurement is possible because atoms within molecules still retain much of their atomic identity).



(a)



(b)

Figure **9.7.1**: (a) The radius of an atom is defined as one-half the distance between the nuclei in a molecule consisting of two identical atoms joined by a covalent bond. The atomic radius for the halogens increases down the group as n increases. (b) Covalent radii of the elements are shown to scale. The general trend is that radii increase down a group and decrease across a period.

We know that as we scan down a group, the principal quantum number, *n*, increases by one for each element. Thus, the electrons are being added to a region of space that is increasingly distant from the nucleus. Consequently, the size of the atom (and its covalent radius) must increase as we increase the distance of the outermost electrons from the nucleus. This trend is illustrated for the covalent radii of the halogens in Table **9.7.1** and Figure **9.7.1**. The trends for the entire periodic table can be seen in Figure **9.7.2**.


Table **9.7.1**: Covalent Radii of the Halogen Group Elements

Atom	Covalent radius (pm)	Nuclear charge
F	64	+9
Cl	99	+17
Br	114	+35
I	133	+53
At	148	+85

As shown in Figure **9.7.2**, as we move across a period from left to right, we generally find that each element has a smaller covalent radius than the element preceding it. This might seem counterintuitive because it implies that atoms with more electrons have a smaller atomic radius. This can be explained with the concept of effective nuclear charge, Z_{eff}. This is the pull exerted on a specific electron by the nucleus, taking into account any electron–electron repulsions. For hydrogen, there is only one electron and so the nuclear charge (Z) and the effective nuclear charge (Z_{eff}) are equal. For all other atoms, the inner electrons partially *shield* the outer electrons from the pull of the nucleus, and thus:

$$Z_{\text{eff}} = Z - shielding \tag{9.7.1}$$

Shielding is determined by the probability of another electron being between the electron of interest and the nucleus, as well as by the electron–electron repulsions the electron of interest encounters. Core electrons are adept at shielding, while electrons in the same valence shell do not block the nuclear attraction experienced by each other as efficiently. Thus, each time we move from one element to the next across a period, Z increases by one, but the shielding increases only slightly. Thus, Z_{eff} increases as we move from left to right across a period. The stronger pull (higher effective nuclear charge) experienced by electrons on the right side of the periodic table draws them closer to the nucleus, making the covalent radii smaller.



Zeff and Electron Shielding: https://youtu.be/uRXqGwgWPyI




Figure **9.7.2**: Within each period, the trend in atomic radius decreases as Z increases; for example, from K to Kr. Within each group (e.g., the alkali metals shown in purple), the trend is that atomic radius increases as Z increases.

Thus, as we would expect, the outermost or valence electrons are easiest to remove because they have the highest energies, are shielded more, and are farthest from the nucleus. As a general rule, when the representative elements form cations, they do so by the loss of the *ns* or *np* electrons that were added last in the Aufbau process. The transition elements, on the other hand, lose the *ns* electrons before they begin to lose the $(n - 1)d$ electrons, even though the *ns* electrons are added first, according to the Aufbau principle.

✔ Example 9.7.1: Sorting Atomic Radii

Predict the order of increasing covalent radius for Ge, Fl, Br, Kr.

Solution

Radius increases as we move down a group, so Ge < Fl (Note: Fl is the symbol for flerovium, element 114, NOT fluorine). Radius decreases as we move across a period, so Kr < Br < Ge. Putting the trends together, we obtain Kr < Br < Ge < Fl.

? Exercise 9.7.1

Give an example of an atom whose size is smaller than fluorine.

Answer

Ne or He



Atomic Radius: https://youtu.be/ZYKB8SNrGVY

Variation in Ionic Radii

Ionic radius is the measure used to describe the size of an ion. A cation always has fewer electrons and the same number of protons as the parent atom; it is smaller than the atom from which it is derived (Figure **9.7.3**). For example, the covalent radius of an aluminum atom ($1s^2 2s^2 2p^6 3s^2 3p^1$) is 118 pm, whereas the ionic radius of an Al^{3+} ($1s^2 2s^2 2p^6$) is 68 pm. As electrons are removed from the outer valence shell, the remaining core electrons occupying smaller shells experience a greater effective nuclear charge Z_{eff} (as discussed) and are drawn even closer to the nucleus.



Figure **9.7.3**: The radius for a cation is smaller than the parent atom (Al), due to the lost electrons; the radius for an anion is larger than the parent (S), due to the gained electrons.

Cations with larger charges are smaller than cations with smaller charges (e.g., V^{2+} has an ionic radius of 79 pm, while that of V^{3+} is 64 pm). Proceeding down the groups of the periodic table, we find that cations of successive elements with the same charge generally have larger radii, corresponding to an increase in the principal quantum number, *n*.

An anion (negative ion) is formed by the addition of one or more electrons to the valence shell of an atom. This results in a greater repulsion among the electrons and a decrease in Z_{eff} per electron. Both effects (the increased number of electrons and the decreased Z_{eff}) cause the radius of an anion to be larger than that of the parent atom (Figure **9.7.3**). For example, a sulfur atom ($[Ne]3s^2 3p^4$) has a covalent radius of 104 pm, whereas the ionic radius of the sulfide anion ($[Ne]3s^2 3p^6$) is 170 pm. For consecutive elements proceeding down any group, anions have larger principal quantum numbers and, thus, larger radii.

Atoms and ions that have the same electron configuration are said to be isoelectronic. Examples of isoelectronic species are N^{3-}, O^{2-}, F^-, Ne, Na^+, Mg^{2+}, and Al^{3+} ($1s^2 2s^2 2p^6$). Another isoelectronic series is P^{3-}, S^{2-}, Cl^-, Ar, K^+, Ca^{2+}, and Sc^{3+} ($[Ne]3s^2 3p^6$). For atoms or ions that are isoelectronic, the number of protons determines the size. The greater the nuclear charge, the smaller the radius in a series of isoelectronic ions and atoms.

Variation in Ionization Energies

The amount of energy required to remove the most loosely bound electron from a gaseous atom in its ground state is called its first ionization energy (IE_1). The first ionization energy for an element, X, is the energy required to form a cation with +1 charge:

$$\mathbf{X}(g) \longrightarrow \mathbf{X}^+(g) + \mathbf{e}^- \quad \mathbf{IE}_1 \tag{9.7.2}$$

The energy required to remove the second most loosely bound electron is called the second ionization energy (IE_2).

$$\mathbf{X}^+(g) \longrightarrow \mathbf{X}^{2+}(g) + \mathbf{e}^- \quad \mathbf{IE}_2 \tag{9.7.3}$$

The energy required to remove the third electron is the third ionization energy, and so on. Energy is always required to remove electrons from atoms or ions, so ionization processes are endothermic and IE values are always positive. For larger atoms, the most loosely bound electron is located farther from the nucleus and so is easier to remove. Thus, as size (atomic radius) increases, the ionization energy should decrease. Relating this logic to what we have just learned about radii, we would expect first ionization energies to decrease down a group and to increase across a period.




Figure **9.7.4**: The first ionization energy of the elements in the first five periods are plotted against their atomic number.

Figure **9.7.4** graphs the relationship between the first ionization energy and the atomic number of several elements. Within a period, the values of first ionization energy for the elements (IE_1) generally increases with increasing *Z*. Down a group, the IE_1 value generally decreases with increasing *Z*. There are some systematic deviations from this trend, however. Note that the ionization energy of boron (atomic number 5) is less than that of beryllium (atomic number 4) even though the nuclear charge of boron is greater by one proton. This can be explained because the energy of the subshells increases as *l* increases, due to penetration and shielding (as discussed previously in this chapter). Within any one shell, the *s* electrons are lower in energy than the *p* electrons. This means that an *s* electron is harder to remove from an atom than a *p* electron in the same shell. The electron removed during the ionization of beryllium ($[He]2s^2$) is an *s* electron, whereas the electron removed during the ionization of boron ($[He]2s^22p^1$) is a *p* electron; this results in a lower first ionization energy for boron, even though its nuclear charge is greater by one proton. Thus, we see a small deviation from the predicted trend occurring each time a new subshell begins.





Figure **9.7.5**: This version of the periodic table shows the first ionization energy of (IE: $_1$), in kJ/mol, of selected elements.

Another deviation occurs as orbitals become more than one-half filled. The first ionization energy for oxygen is slightly less than that for nitrogen, despite the trend in increasing IE_1 values across a period. Looking at the orbital diagram of oxygen, we can see

that removing one electron will eliminate the electron–electron repulsion caused by pairing the electrons in the 2*p* orbital and will result in a half-filled orbital (which is energetically favorable). Analogous changes occur in succeeding periods (note the dip for sulfur after phosphorus in Figure **9.7.4**.



Removing an electron from a cation is more difficult than removing an electron from a neutral atom because of the greater electrostatic attraction to the cation. Likewise, removing an electron from a cation with a higher positive charge is more difficult than removing an electron from an ion with a lower charge. Thus, successive ionization energies for one element always increase. As seen in Table **9.7.2**, there is a large increase in the ionization energies (color change) for each element. This jump corresponds to removal of the core electrons, which are harder to remove than the valence electrons. For example, Sc and Ga both have three valence electrons, so the rapid increase in ionization energy occurs after the third ionization.

Table 9.7.2: Successive Ionization Energies for Selected Elements (kJ/mol)

Element	IE_1	IE_2	IE_3	IE_4	IE_5	IE_6	IE_7
K	418.8	3051.8	4419.6	5876.9	7975.5	9590.6	11343
Ca	589.8	1145.4	4912.4	6490.6	8153.0	10495.7	12272.9
Sc	633.1	1235.0	2388.7	7090.6	8842.9	10679.0	13315.0
Ga	578.8	1979.4	2964.6	6180	8298.7	10873.9	13594.8
Ge	762.2	1537.5	3302.1	4410.6	9021.4	Not available	Not available
As	944.5	1793.6	2735.5	4836.8	6042.9	12311.5	Not available

✔ Example 9.7.2: Ranking Ionization Energies

Predict the order of increasing energy for the following processes: IE_1 for Al, IE_1 for Tl, IE_2 for Na, IE_3 for Al.

Solution

Removing the $6p^1$ electron from Tl is easier than removing the $3p^1$ electron from Al because the higher *n* orbital is farther from the nucleus, so $IE_1(Tl) < IE_1(Al)$. Ionizing the third electron from

$$\mathbf{Al} \quad (\mathbf{Al^{2+} \longrightarrow Al^{3+} + e^-})$$

requires more energy because the cation Al^{2+} exerts a stronger pull on the electron than the neutral Al atom, so $IE_1(Al) < IE_3(Al)$. The second ionization energy for sodium removes a core electron, which is a much higher energy process than removing valence electrons. Putting this all together, we obtain:

$$IE_1(Tl) < IE_1(Al) < IE_3(Al) < IE_2(Na).$$

? Exercise 9.7.2

Which has the lowest value for IE_1: O, Po, Pb, or Ba?

Answer

Ba



Ionization Energy: https://youtu.be/k7j-u02ifzo

Variation in Electron Affinities

The electron affinity [EA] is the energy change for the process of adding an electron to a gaseous atom to form an anion (negative ion).

$$\mathrm{X}(g) + \mathrm{e}^- \longrightarrow \mathrm{X}^-(g) \quad \mathrm{EA}_1 \tag{9.7.4}$$

This process can be either endothermic or exothermic, depending on the element. The EA of some of the elements is given in Figure **9.7.6**. You can see that many of these elements have negative values of EA, which means that energy is released when the gaseous atom accepts an electron. However, for some elements, energy is required for the atom to become negatively charged and the value of their EA is positive. Just as with ionization energy, subsequent EA values are associated with forming ions with more charge. The second EA is the energy associated with adding an electron to an anion to form a –2 ion, and so on.




Figure **9.7.6**: This version of the periodic table displays the electron affinity values (in kJ/mol) for selected elements.:

As we might predict, it becomes easier to add an electron across a series of atoms as the effective nuclear charge of the atoms increases. We find, as we go from left to right across a period, EAs tend to become more negative. The exceptions found among the elements of group 2 (2A), group 15 (5A), and group 18 (8A) can be understood based on the electronic structure of these groups. The noble gases, group 18 (8A), have a completely filled shell and the incoming electron must be added to a higher *n* level, which is more difficult to do. Group 2 (2A) has a filled *ns* subshell, and so the next electron added goes into the higher energy *np*, so, again, the observed EA value is not as the trend would predict. Finally, group 15 (5A) has a half-filled *np* subshell and the next

electron must be paired with an existing *np* electron. In all of these cases, the initial relative stability of the electron configuration disrupts the trend in EA.

We also might expect the atom at the top of each group to have the largest EA; their first ionization potentials suggest that these atoms have the largest effective nuclear charges. However, as we move down a group, we see that the second element in the group most often has the greatest EA. The reduction of the EA of the first member can be attributed to the small size of the $n = 2$ shell and the resulting large electron–electron repulsions. For example, chlorine, with an EA value of –348 kJ/mol, has the highest value of any element in the periodic table. The EA of fluorine is –322 kJ/mol. When we add an electron to a fluorine atom to form a fluoride anion (F^-), we add an electron to the $n = 2$ shell. The electron is attracted to the nucleus, but there is also significant repulsion from the other electrons already present in this small valence shell. The chlorine atom has the same electron configuration in the valence shell, but because the entering electron is going into the $n = 3$ shell, it occupies a considerably larger region of space and the electron–electron repulsions are reduced. The entering electron does not experience as much repulsion and the chlorine atom accepts an additional electron more readily.

The properties discussed in this section (size of atoms and ions, effective nuclear charge, ionization energies, and electron affinities) are central to understanding chemical reactivity. For example, because fluorine has an energetically favorable EA and a large energy barrier to ionization (IE), it is much easier to form fluorine anions than cations. Metallic properties including conductivity and malleability (the ability to be formed into sheets) depend on having electrons that can be removed easily. Thus, metallic character increases as we move down a group and decreases across a period in the same trend observed for atomic size because it is easier to remove an electron that is farther away from the nucleus.



Electron Affinity: https://youtu.be/M5MsRM2Xtds

Summary

Electron configurations allow us to understand many periodic trends. Covalent radius increases as we move down a group because the *n* level (orbital size) increases. Covalent radius mostly decreases as we move left to right across a period because the effective nuclear charge experienced by the electrons increases, and the electrons are pulled in tighter to the nucleus. Anionic radii are larger than the parent atom, while cationic radii are smaller, because the number of valence electrons has changed while the nuclear charge has remained constant. Ionization energy (the energy associated with forming a cation) decreases down a group and mostly increases across a period because it is easier to remove an electron from a larger, higher energy orbital. Electron affinity (the energy associated with forming an anion) is more favorable (exothermic) when electrons are placed into lower energy orbitals, closer to the nucleus. Therefore, electron affinity becomes increasingly negative as we move left to right across the periodic table and decreases as we move down a group. For both IE and electron affinity data, there are exceptions to the trends when dealing with completely filled or half-filled subshells.

Glossary

covalent radius

one-half the distance between the nuclei of two identical atoms when they are joined by a covalent bond

effective nuclear charge

charge that leads to the Coulomb force exerted by the nucleus on an electron, calculated as the nuclear charge minus shielding

electron affinity

energy required to add an electron to a gaseous atom to form an anion

ionization energy

energy required to remove an electron from a gaseous atom or ion. The associated number (e.g., second ionization energy) corresponds to the charge of the ion produced (X^{2+})

isoelectronic

group of ions or atoms that have identical electron configurations

---

9.7: Periodic Trends is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **6.5: Periodic Variations in Element Properties** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

9.8: End of Chapter Problems

1. The light produced by a red neon sign is due to the emission of light by excited neon atoms. Qualitatively describe the spectrum produced by passing light from a neon lamp through a prism.

Answer

The spectrum consists of colored lines, at least one of which (probably the brightest) is red.

2. An FM radio station found at 103.1 on the FM dial broadcasts at a frequency of 1.031×10^8 s^{-1} (103.1 MHz). What is the wavelength of these radio waves in meters?

Answer

$$\lambda = \frac{c}{\nu}$$

$$\lambda = \frac{2.998 \times 10^8 \frac{m}{s}}{1.031 \times 10^8 \frac{1}{s}} = 2.908\, m$$

3. FM-95, an FM radio station, broadcasts at a frequency of 9.51×10^7 s^{-1} (95.1 MHz). What is the wavelength of these radio waves in meters?

Answer

$$\lambda = \frac{c}{\nu}$$

$$\lambda = \frac{2.998 \times 10^8 \frac{m}{s}}{9.51 \times 10^7 \frac{1}{s}} = 3.15\, m$$

4. A bright violet line occurs at 435.8 nm in the emission spectrum of mercury vapor. What amount of energy, in joules, must be released by an electron in a mercury atom to produce a photon of this light?

Answer

$$E = \frac{hc}{\lambda}$$

$$E = \frac{(2.998 \times 10^8 \frac{m}{s})\,(6.6262 \times 10^{-34} Js)}{4.358 \times 10^{-7} m}$$

$$= 4.56 \times 10^{-19} J$$

5. Light with a wavelength of 614.5 nm looks orange. What is the energy, in joules, per photon of this orange light? What is the energy in eV (1 eV = 1.602×10^{-19} J)?

Answer

1.) First convert 614.5 nm into meters

$6.145 nm = 6.145 \times 10^{-7} m$

2.) Then calculate the amount of energy this wavelength of light contains using the equations:

$E = h\nu$ and $\nu = \frac{c}{\lambda}$ which can be manipulated algebraically into: $E = \frac{hc}{\lambda}$

h = Plancks constant → $6.6262 \times 10^{-34} Js$ c = Speed of light → $2.998 \times 10^8 \frac{m}{s}$ λ = wavelength of photon → $6.145 \times 10^{-7} m$

$$= \frac{(6.6262 \times 10^{-34}\ Js)\ (2.998 \times 10^8 \frac{m}{s})}{6.145 \times 10^{-7} m} = 3.233 \times 10^{-19} J \quad (9.8.1)$$

3.) Then convert Joules into eV:

$$= (3.233 \times 10^{-19} J) \times \frac{1 eV}{1.602 \times 10^{-19} J} \tag{9.8.2}$$

$$= 2.018 eV \tag{9.8.3}$$

6. Heated lithium atoms emit photons of light with an energy of 2.961×10^{-19} J. Calculate the frequency and wavelength of one of these photons. What is the total energy in 1 mole of these photons? What is the color of the emitted light?

Answer

1.) $E = h\nu$ and $\nu = \frac{E}{h}$

h = Plancks constant → $6.6262 \times 10^{-34} Js$

Frequency: $\nu = \frac{2.961 \times 10^{-19} J}{6.6262 \times 10^{-34} Js} = 4.469 \times 10^{14} Hz$

2.) $\lambda = \frac{c}{\nu}$

c = Speed of light → $2.998 \times 10^{8} \frac{m}{s}$

Wavelength: $\lambda = \frac{2.998 \times 10^{8} \frac{m}{s}}{4.469 \times 10^{14} \frac{1}{s}} = 6.709 \times 10^{-7} m$ = **Red Light**

Total energy:

$$E = \frac{2.961 \times 10^{-19} J}{1 \, photon} \times \frac{6.022 \times 10^{23} \, photons}{1 \, mole} = 1.783 \times 10^{5} J$$

7. A photon of light produced by a surgical laser has an energy of 3.027×10^{-19} J. Calculate the frequency and wavelength of the photon. What is the total energy in 1 mole of photons? What is the color of the emitted light?

Answer

$\nu = 4.568 \times 10^{14}$ s; $\lambda = 656.3$ nm; Energy mol$^{-1} = 1.823 \times 10^{5}$ J mol^{-1}; red

8. When rubidium ions are heated to a high temperature, two lines are observed in its line spectrum at wavelengths (a) 7.9×10^{-7} m and (b) 4.2×10^{-7} m. What are the frequencies of the two lines? What color do we see when we heat a rubidium compound?
9. The emission spectrum of cesium contains two lines whose frequencies are (a) 3.45×10^{14} Hz and (b) 6.53×10^{14} Hz. What are the wavelengths and energies per photon of the two lines? What color are the lines?

Answer

(a) $\lambda = 8.69 \times 10^{-7}$ m; $E = 2.29 \times 10^{-19}$ J; (b) $\lambda = 4.59 \times 10^{-7}$ m; $E = 4.33 \times 10^{-19}$ J; The color of (a) is red; (b) is blue.

10. Photons of infrared radiation are responsible for much of the warmth we feel when holding our hands before a fire. These photons will also warm other objects. How many infrared photons with a wavelength of 1.5×10^{-6} m must be absorbed by the water to warm a cup of water (175 g) from 25.0 °C to 40 °

Answer

1.) First we must use the equation: q=mCΔT$^{\circ}$ to calculate the amount of Energy in Joules (J) to warm 175g of H_2O a total of 15° Celsius

m = mass in grams(g) → 175g C = Specific heat of $H_2O_{(l)}$ → $\frac{4.184 J}{g°C}$ ΔT$^{\circ}$ = Difference in temperature → 40 - 25 =15°

$$q = 175g \times \frac{4.184 J}{g°C} \times 15°C \tag{9.8.4}$$

q= 11,000 J

2.) Now we need to calculate the amount of energy in Joules (J) that one Photon with a wavelength of 1.5x10^{-6} m contains. We will use the equations:

$E = h\nu$ and $\nu = \frac{c}{\lambda}$ which can be manipulated algebraically into: $E = \frac{hc}{\lambda}$

h = Plancks constant → $6.6262 \times 10^{-34} Js$ c = Speed of light → $2.998 \times 10^{8} \frac{m}{s}$ λ = wavelength of photon → $1.5 \times 10^{-6} m$

$$= \frac{(6.6262 \times 10^{-34}\ Js)\ (2.998 \times 10^{8}\ \frac{m}{s})}{1.5 \times 10^{-6} m} = 1.3 \times 10^{-19} J \tag{9.8.5}$$

This is the energy in one photon, so now we have to see how many times 1.3x10^{-19} J fits into the 11,000 J from our first calculation:

$$= \frac{11,000\ J}{1.3 \times 10^{-19}\ \frac{J}{photon}} = 8.3 \times 10^{22} photons \tag{9.8.6}$$

$$= 8.3 \times 10^{22} photons \tag{9.8.7}$$

11. One of the radiographic devices used in a dentist's office emits an X-ray of wavelength 2.090 × 10^{-11} m. What is the energy, in joules, and frequency of this X-ray?

Answer

E = 9.502 × 10^{-15} J; ν = 1.434 × 10^{19} s^{-1}

12. The eyes of certain reptiles pass a single visual signal to the brain when the visual receptors are struck by photons of a wavelength of 850 nm. If a total energy of 3.15 × 10^{-14} J is required to trip the signal, what is the minimum number of photons that must strike the receptor?

Answer

1.) First we need to convert nanometers to meters

850nm = 8.5 x 10^{-7} m

2. Then calculate Energy in Joules a photon of this wavelength (λ) produces:

$$(E = \frac{hc}{\lambda}) = \frac{(6.6262 \times 10^{-34}\ Js)\ (2.998 \times 10^{8}\ \frac{m}{s})}{8.5 \times 10^{-7} m} = 2.3 \times 10^{-19} \frac{J}{photon} \tag{9.8.8}$$

3.) Then we need to find out how many of these photons it will take to trip the visual signal to the brain:

$$= \frac{3.15 \times 10^{-14}\ \cancel{J}}{2.3 \times 10^{-19}\ \frac{\cancel{J}}{photon}} \tag{9.8.9}$$

$$= 1.3 \times 10^{5}\ photons \tag{9.8.10}$$

13. RGB color television and computer displays use cathode ray tubes that produce colors by mixing red, green, and blue light. If we look at the screen with a magnifying glass, we can see individual dots turn on and off as the colors change. Using a spectrum of visible light, determine the approximate wavelength of each of these colors. What is the frequency and energy of a photon of each of these colors?

Answer

Red: 660 nm; 4.54 × 10^{14} Hz; 3.01 × 10^{-19} J.

Green: 520 nm; 5.77 × 10^{14} Hz; 3.82 × 10^{-19} J.

Blue: 440 nm; 6.81 × 10^{14} Hz; 4.51 × 10^{-19} J.

Somewhat different numbers are also possible.

14. Answer the following questions about a Blu-ray laser:
    a. The laser on a Blu-ray player has a wavelength of 405 nm. In what region of the electromagnetic spectrum is this radiation? What is its frequency?
    b. A Blu-ray laser has a power of 5 milliwatts (1 watt = 1 J s^{-1}). How many photons of light are produced by the laser in 1 hour?
    c. The ideal resolution of a player using a laser (such as a Blu-ray player), which determines how close together data can be stored on a compact disk, is determined using the following formula: Resolution = 0.60(λ/NA), where λ is the wavelength of the laser and NA is the numerical aperture. Numerical aperture is a measure of the size of the spot of light on the disk; the larger the NA, the smaller the spot. In a typical Blu-ray system, NA = 0.95. If the 405-nm laser is used in a Blu-ray player, what is the closest that information can be stored on a Blu-ray disk?
    d. The data density of a Blu-ray disk using a 405-nm laser is 1.5×10^7 bits mm^{-2}. Disks have an outside diameter of 120 mm and a hole of 15-mm diameter. How many data bits can be contained on the disk? If a Blu-ray disk can hold 9,400,000 pages of text, how many data bits are needed for a typed page? (Hint: Determine the area of the disk that is available to hold data. The area inside a circle is given by $A = \pi r^2$, where the radius r is one-half of the diameter.)
15. What is the threshold frequency for sodium metal if a photon with frequency 6.66×10^{14} s^{-1} ejects a photon with 7.74×10^{-20} J kinetic energy? Will the photoelectric effect be observed if sodium is exposed to orange light?

Answer

5.49×10^{14} s^{-1}; no

16. Why is the electron in a Bohr hydrogen atom bound less tightly when it has a quantum number of 3 than when it has a quantum number of 1?
17. What does it mean to say that the energy of the electrons in an atom is quantized?

Answer

Quantized energy means that the electrons can possess only certain discrete energy values; values between those quantized values are not permitted.

18. Using the Bohr model, determine the energy, in joules, necessary to ionize a ground-state hydrogen atom. Show your calculations.\
19. The electron volt (eV) is a convenient unit of energy for expressing atomic-scale energies. It is the amount of energy that an electron gains when subjected to a potential of 1 volt; $1\ eV = 1.602 \times 10^{-19}\ J$. Using the Bohr model, determine the energy, in electron volts, of the photon produced when an electron in a hydrogen atom moves from the orbit with $n = 5$ to the orbit with $n = 2$. Show your calculations.

Answer

5

$$E = E_2 - E_5 = 2.179 \times 10^{-18} \left(\frac{1}{n_2^2} - \frac{1}{n_5^2} \right) J \tag{9.8.11}$$

$$= 2.179 \times 10^{-18} \left(\frac{1}{2^2} - \frac{1}{5^2} \right) = 4.576 \times 10^{-19}\ J \tag{9.8.12}$$

$$= \frac{4.576 \times 10^{-19}\ J}{1.602 \times 10^{-19}\ J\ eV^{-1}} = 2.856\ eV \tag{9.8.13}$$

20. Using the Bohr model, determine the energy of an electron with $n = 6$ in a hydrogen atom.

Answer

−8.716 × 10−18 J

21. Using the Bohr model, determine the energy of an electron with $n = 8$ in a hydrogen atom.

22. How far from the nucleus in angstroms (1 angstrom = 1×10^{-10} m) is the electron in a hydrogen atom if it has an energy of -8.72×10^{-20} J?

Answer

$-3.405 \times 10^{-20} J$

23. What is the radius, in angstroms, of the orbital of an electron with n = 8 in a hydrogen atom?

24. Using the Bohr model, determine the energy in joules of the photon produced when an electron in a He^{+} ion moves from the orbit with n = 5 to the orbit with n = 2.

25. Using the Bohr model, determine the energy in joules of the photon produced when an electron in a Li2+ ion moves from the orbit with n = 2 to the orbit with n = 1.

Answer

1.471 × 10−17 J

26. Consider a large number of hydrogen atoms with electrons randomly distributed in the n = 1, 2, 3, and 4 orbits

    a. How many different wavelengths of light are emitted by these atoms as the electrons fall into lower-energy orbitals?
    b. Calculate the lowest and highest energies of light produced by the transitions described in part (a).
    c. Calculate the frequencies and wavelengths of the light produced by the transitions described in part (b).

27. How are the Bohr model and the Rutherford model of the atom similar? How are they different?

28. The spectra of hydrogen and of calcium are shown in [link]. What causes the lines in these spectra? Why are the colors of the lines different? Suggest a reason for the observation that the spectrum of calcium is more complicated than the spectrum of hydrogen

Answer

Both involve a relatively heavy nucleus with electrons moving around it, although strictly speaking, the Bohr model works only for one-electron atoms or ions. According to classical mechanics, the Rutherford model predicts a miniature “solar system” with electrons moving about the nucleus in circular or elliptical orbits that are confined to planes. If the requirements of classical electromagnetic theory that electrons in such orbits would emit electromagnetic radiation are ignored, such atoms would be stable, having constant energy and angular momentum, but would not emit any visible light (contrary to observation). If classical electromagnetic theory is applied, then the Rutherford atom would emit electromagnetic radiation of continually increasing frequency (contrary to the observed discrete spectra), thereby losing energy until the atom collapsed in an absurdly short time (contrary to the observed long-term stability of atoms). The Bohr model retains the classical mechanics view of circular orbits confined to planes having constant energy and angular momentum, but restricts these to quantized values dependent on a single quantum number, n. The orbiting electron in Bohr’s model is assumed not to emit any electromagnetic radiation while moving about the nucleus in its stationary orbits, but the atom can emit or absorb electromagnetic radiation when the electron changes from one orbit to another. Because of the quantized orbits, such “quantum jumps” will produce discrete spectra, in agreement with observations.

29. How are the Bohr model and the quantum mechanical model of the hydrogen atom similar? How are they different?

Answer

Both models have a central positively charged nucleus with electrons moving about the nucleus in accordance with the Coulomb electrostatic potential. The Bohr model *assumes* that the electrons move in circular orbits that have quantized energies, angular momentum, and radii that are specified by a single quantum number, n = 1, 2, 3, …, but this quantization is an ad hoc assumption made by Bohr to incorporate quantization into an essentially classical mechanics description of the atom. Bohr also assumed that electrons orbiting the nucleus normally do not emit or absorb electromagnetic radiation, but do so when the electron switches to a different orbit. In the quantum mechanical model, the electrons do not move in precise orbits (such orbits violate the Heisenberg uncertainty principle) and, instead, a probabilistic interpretation of the electron’s position at any given instant is used, with a mathematical function ψ called a wavefunction that can be used to determine the electron’s spatial

probability distribution. These wavefunctions, or orbitals, are three-dimensional stationary waves that can be specified by three quantum numbers that arise naturally from their underlying mathematics (no ad hoc assumptions required): the principal quantum number, n (the same one used by Bohr), which specifies shells such that orbitals having the same n all have the same energy and approximately the same spatial extent; the angular momentum quantum number l, which is a measure of the orbital's angular momentum and corresponds to the orbitals' general shapes, as well as specifying subshells such that orbitals having the same l (and n) all have the same energy; and the orientation quantum number m, which is a measure of the z component of the angular momentum and corresponds to the orientations of the orbitals. The Bohr model gives the same expression for the energy as the quantum mechanical expression and, hence, both properly account for hydrogen's discrete spectrum (an example of getting the right answers for the wrong reasons, something that many chemistry students can sympathize with), but gives the wrong expression for the angular momentum (Bohr orbits necessarily all have non-zero angular momentum, but some quantum orbitals [s orbitals] can have zero angular momentum).

30. What are the allowed values for each of the four quantum numbers: n, l, m_l, and m_s?

31. Describe the properties of an electron associated with each of the following four quantum numbers: n, l, m_l, and m_s.

Answer

n determines the general range for the value of energy and the probable distances that the electron can be from the nucleus. l determines the shape of the orbital. m_l determines the orientation of the orbitals of the same l value with respect to one another. m_s determines the spin of an electron.

32. Answer the following questions:

    a. Without using quantum numbers, describe the differences between the shells, subshells, and orbitals of an atom.
    b. How do the quantum numbers of the shells, subshells, and orbitals of an atom differ?

33. Identify the subshell in which electrons with the following quantum numbers are found:

    a. $n = 2$, $l = 1$
    b. $n = 4$, $l = 2$
    c. $n = 6$, $l = 0$

Answer

(a) 2p; (b) 4d; (c) 6s

34. Which of the subshells described in Question 5 contain degenerate orbitals? How many degenerate orbitals are in each?
35. Identify the subshell in which electrons with the following quantum numbers are found:


    a. $n = 3$, $l = 2$
    b. $n = 1$, $l = 0$
    c. $n = 4$, $l = 3$

Answer

(a) 3d; (b) 1s; (c) 4f


36. Which of the subshells described in Question 7 contain degenerate orbitals? How many degenerate orbitals are in each?

37. Sketch the boundary surface of a $d_{x^2-y^2}$ and a p_y orbital. Be sure to show and label the axes.



38. Sketch the p_x and d_{xz} orbitals. Be sure to show and label the coordinates.

39. Consider the orbitals shown here in outline.



a. What is the maximum number of electrons contained in an orbital of type (x)? Of type (y)? Of type (z)?
b. How many orbitals of type (x) are found in a shell with $n = 2$? How many of type (y)? How many of type (z)?
c. Write a set of quantum numbers for an electron in an orbital of type (x) in a shell with $n = 4$. Of an orbital of type (y) in a shell with $n = 2$. Of an orbital of type (z) in a shell with $n = 3$.
d. What is the smallest possible n value for an orbital of type (x)? Of type (y)? Of type (z)?
e. What are the possible l and m_l values for an orbital of type (x)? Of type (y)? Of type (z)?

Answer

(a) x. 2, y. 2, z. 2; (b) x. 1, y. 3, z. 0; (c) x. 4 0 0 $\frac{1}{2}$, y. 2 1 0 $\frac{1}{2}$, z. 3 2 0 $\frac{1}{2}$; (d) x. 1, y. 2, z. 3; (e) x. $l = 0$, $m_l = 0$, y. $l = 1$, $m_l = –1$, 0, or +1, z. $l = 2$, $m_l = –2, –1, 0, +1, +2$

40. State the Heisenberg uncertainty principle. Describe briefly what the principle implies.

41. How many electrons could be held in the second shell of an atom if the spin quantum number m_s could have three values instead of just two? (Hint: Consider the Pauli exclusion principle.)

Answer

12

42. Which of the following equations describe particle-like behavior? Which describe wavelike behavior? Do any involve both types of behavior? Describe the reasons for your choices.

a. $c = \lambda\nu$
b. $E = \frac{m\nu^2}{2}$
c. $r = \frac{n^2 a_0}{Z}$
d. $E = h\nu$
e. $\lambda = \frac{h}{m\nu}$

43. Write a set of quantum numbers for each of the electrons with an n of 4 in a Se atom.

Answer

n	l	m_l	s
4	0	0	$+\frac{1}{2}$
4	0	0	$-\frac{1}{2}$
4	1	−1	$+\frac{1}{2}$
4	1	0	$+\frac{1}{2}$
4	1	+1	$+\frac{1}{2}$
4	1	−1	$-\frac{1}{2}$

44. Read the labels of several commercial products and identify monatomic ions of at least four transition elements contained in the products. Write the complete electron configurations of these cations.

45. Read the labels of several commercial products and identify monatomic ions of at least six main group elements contained in the products. Write the complete electron configurations of these cations and anions.

Answer

For example, Na^+: $1s^22s^22p^6$; Ca^{2+}: $1s^22s^22p^6$; Sn^{2+}: $1s^22s^22p^63s^23p^63d^{10}4s^24p^64d^{10}5s^2$; F^-: $1s^22s^22p^6$; O^{2-}: $1s^22s^22p^6$; Cl^-: $1s^22s^22p^63s^23p^6$.

46. Using complete subshell notation (not abbreviations, $1s^22s^22p^6$, and so forth), predict the electron configuration of each of the following atoms:

    a. C
    b. P
    c. V
    d. Sb
    e. Sm

Answer

a.) $1s^22s^22p^2$

b.) $1s^22s^22p^63s^23p^3$

c.) $1s^22s^22p^63s^23p^63d^34s^2$

d.) $1s^22s^22p^63s^23p^63d^{10}4s^24p^64d^{10}5s^25p^3$

e.) $1s^22s^22p^63s^23p^63d^{10}4s^24p^64d^{10}4f^65s^25p^66s^2$

47. Using complete subshell notation ($1s^22s^22p^6$, and so forth), predict the electron configuration of each of the following atoms:

    a. N
    b. Si
    c. Fe
    d. Te
    e. Tb

Answer

a. $1s^22s^22p^3$;

b. $1s^22s^22p^63s^23p^2$;

c. $1s^22s^22p^63s^23p^64s^23d^6$;

d. $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10} 4p^6 5s^2 4d^{10} 5p^4$;

e. $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10} 4p^6 5s^2 4d^{10} 5p^6 6s^2 4f^9$

48. Is $1s^2 2s^2 2p^6$ the symbol for a macroscopic property or a microscopic property of an element? Explain your answer.

49. What additional information do we need to answer the question "Which ion has the electron configuration $1s^2 2s^2 2p^6 3s^2 3p^6$"?

Answer

The charge on the ion.

50. Draw the orbital diagram for the valence shell of each of the following atoms:


a. C
b. P
c. V
d. Sb
e. Ru

51. Use an orbital diagram to describe the electron configuration of the valence shell of each of the following atoms:


1. N
2. Si
3. Fe
4. Te
5. Mo

Answer


(a)




(b)




(c)



(d)



(e)



52. Using complete subshell notation ($1s^2 2s^2 2p^6$, and so forth), predict the electron configurations of the following ions.
    a. N^{3-}
    b. Ca^{2+}
    c. S^{-}
    d. Cs^{2+}
    e. Cr^{2+}
    f. Gd^{3+}

53. Which atom has the electron configuration: $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10} 4p^6 5s^2 4d^2$?

Answer

Zr

54. Which atom has the electron configuration: $1s^2 2s^2 2p^6 3s^2 3p^6 3d^7 4s^2$?

Answer

Co ; Cobalt

55. Which ion with a +1 charge has the electron configuration $1s^2 2s^2 2p^6 3s^2 3p^6 3d^{10} 4s^2 4p^6$? Which ion with a –2 charge has this configuration?

Answer

Rb^{+}, Se^{2-}

56. Which of the following atoms contains only three valence electrons: Li, B, N, F, Ne?

Answer

B ; Boron

57. Which of the following has two unpaired electrons?
    a. Mg
    b. Si
    c. S
    d. Both Mg and S
    e. Both Si and S.

Answer

Although both (b) and (c) are correct, (e) encompasses both and is the best answer.

58. Which atom would be expected to have a half-filled 6*p* subshell?

Answer

Bi ; Bismuth

59. Which atom would be expected to have a half-filled 4*s* subshell?

Answer

K

60. In one area of Australia, the cattle did not thrive despite the presence of suitable forage. An investigation showed the cause to be the absence of sufficient cobalt in the soil. Cobalt forms cations in two oxidation states, Co^{2+} and Co^{3+}. Write the electron structure of the two cations.

61. Thallium was used as a poison in the Agatha Christie mystery story “The Pale Horse.” Thallium has two possible cationic forms, +1 and +3. The +1 compounds are the more stable. Write the electron structure of the +1 cation of thallium.

Answer

$1s^2 2s^2 2p^6 3s^2 3p^6 3d^{10} 4s^2 4p^6 4d^{10} 5s^2 5p^6 6s^2 4f^{14} 5d^{10}$

62. Write the electron configurations for the following atoms or ions:
    a. B^{3+}
    b. O^{-}
    c. Cl^{3+}
    d. Ca^{2+}
    e. Ti

63. Cobalt–60 and iodine–131 are radioactive isotopes commonly used in nuclear medicine. How many protons, neutrons, and electrons are in atoms of these isotopes? Write the complete electron configuration for each isotope.

Answer

Co has 27 protons, 27 electrons, and 33 neutrons: $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^7$.

I has 53 protons, 53 electrons, and 78 neutrons: $1s^2 2s^2 2p^6 3s^2 3p^6 3d^{10} 4s^2 4p^6 4d^{10} 5s^2 5p^5$.

64. Write a set of quantum numbers for each of the electrons with an n of 3 in a Sc atom.

65. Based on their positions in the periodic table, predict which has the smallest atomic radius: Mg, Sr, Si, Cl, I.

Answer

Cl

66. Based on their positions in the periodic table, predict which has the largest atomic radius: Li, Rb, N, F, I.

67. Based on their positions in the periodic table, predict which has the largest first ionization energy: Mg, Ba, B, O, Te.

Answer

O

68. Based on their positions in the periodic table, predict which has the smallest first ionization energy: Li, Cs, N, F, I.

69. Based on their positions in the periodic table, rank the following atoms in order of increasing first ionization energy: F, Li, N, Rb

Answer

Rb < Li < N < F

70. Based on their positions in the periodic table, rank the following atoms or compounds in order of increasing first ionization energy: Mg, O, S, Si

71. Atoms of which group in the periodic table have a valence shell electron configuration of $ns^2 np^3$?

Answer

15 (5A)

72. Atoms of which group in the periodic table have a valence shell electron configuration of ns^2?

73. Based on their positions in the periodic table, list the following atoms in order of increasing radius: Mg, Ca, Rb, Cs.

Answer

Mg < Ca < Rb < Cs

74. Based on their positions in the periodic table, list the following atoms in order of increasing radius: Sr, Ca, Si, Cl.

75. Based on their positions in the periodic table, list the following ions in order of increasing radius: K^+, Ca^{2+}, Al^{3+}, Si^{4+}.

Answer

$Si^{4+} < Al^{3+} < Ca^{2+} < K^+$

76. List the following ions in order of increasing radius: Li^+, Mg^{2+}, Br^-, Te^{2-}.

77. Which atom and/or ion is (are) isoelectronic with Br^+: Se^{2+}, Se, As^-, Kr, Ga^{3+}, Cl^-?

Answer

Se, As^-

78. Which of the following atoms and ions is (are) isoelectronic with S^{2+}: Si^{4+}, Cl^{3+}, Ar, As^{3+}, Si, Al^{3+}?

79. Compare both the numbers of protons and electrons present in each to rank the following ions in order of increasing radius: As^{3-}, Br^-, K^+, Mg^{2+}.

Answer

$Mg^{2+} < K^+ < Br^- < As^{3-}$

80. Of the five elements Al, Cl, I, Na, Rb, which has the most exothermic reaction? (E represents an atom.) What name is given to the energy for the reaction? Hint: note the process depicted does *not* correspond to electron affinity

$$\mathrm{E^+}(g) + \mathrm{e^-} \longrightarrow \mathrm{E}(g)$$

81. Of the five elements Sn, Si, Sb, O, Te, which has the most endothermic reaction? (E represents an atom.) What name is given to the energy for the reaction?

$$\mathrm{E}(g) \longrightarrow \mathrm{E^+}(g) + \mathrm{e^-} \tag{9.8.14}$$

Answer

O, IE_1

82. The ionic radii of the ions S^{2-}, Cl^-, and K^+ are 184, 181, 138 pm respectively. Explain why these ions have different sizes even though they contain the same number of electrons.

83. Which main group atom would be expected to have the lowest second ionization energy?

Answer

Ra

84. Explain why Al is a member of group 13 rather than group 3?

9.8: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

10: Lewis Structure and Bond Energy

10.3: Covalent Bonding and Electronegativity
10.7: Formal Charges
10.1: Lewis Symbol of Atoms
10.2: Ionic Bonding
10.4: Lewis Structures of Molecular Compounds
10.5: Exceptions to the Octet Rule
10.6: Resonance Strucutres
10.8: Strengths of Ionic and Covalent Bonds
10.9: End of Chapter Problems

10: Lewis Structure and Bond Energy is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

10.3: Covalent Bonding and Electronegativity

Learning Objectives

By the end of this section, you will be able to:

- Describe the formation of covalent bonds
- Define electronegativity and assess the polarity of covalent bonds

Ionic bonding results from the electrostatic attraction of oppositely charged ions that are typically produced by the transfer of electrons between metallic and nonmetallic atoms. A different type of bonding results from the mutual attraction of atoms for a "shared" pair of electrons. Such bonds are called covalent bonds. Covalent bonds are formed between two atoms when both have similar tendencies to attract electrons to themselves (i.e., when both atoms have identical or fairly similar ionization energies and electron affinities). For example, two hydrogen atoms bond covalently to form an H_2 molecule; each hydrogen atom in the H_2 molecule has two electrons stabilizing it, giving each atom the same number of valence electrons as the noble gas He.

Compounds that contain covalent bonds exhibit different physical properties than ionic compounds. Because the attraction between molecules, which are electrically neutral, is weaker than that between electrically charged ions, covalent compounds generally have much lower melting and boiling points than ionic compounds. In fact, many covalent compounds are liquids or gases at room temperature, and, in their solid states, they are typically much softer than ionic solids. Furthermore, whereas ionic compounds are good conductors of electricity when dissolved in water, most covalent compounds are insoluble in water; since they are electrically neutral, they are poor conductors of electricity in any state.

Formation of Covalent Bonds

Nonmetal atoms frequently form covalent bonds with other nonmetal atoms. For example, the hydrogen molecule, H_2, contains a covalent bond between its two hydrogen atoms. Figure **10.3.1** illustrates why this bond is formed. Starting on the far right, we have two separate hydrogen atoms with a particular potential energy, indicated by the red line. Along the *x*-axis is the distance between the two atoms. As the two atoms approach each other (moving left along the *x*-axis), their valence orbitals (1*s*) begin to overlap. The single electrons on each hydrogen atom then interact with both atomic nuclei, occupying the space around both atoms. The strong attraction of each shared electron to both nuclei stabilizes the system, and the potential energy decreases as the bond distance decreases. If the atoms continue to approach each other, the positive charges in the two nuclei begin to repel each other, and the potential energy increases. The bond length is determined by the distance at which the lowest potential energy is achieved.




Figure **10.3.1**: The potential energy of two separate hydrogen atoms (right) decreases as they approach each other, and the single electrons on each atom are shared to form a covalent bond. The bond length is the internuclear distance at which the lowest potential energy is achieved.

It is essential to remember that energy must be added to break chemical bonds (an endothermic process), whereas forming chemical bonds releases energy (an exothermic process). In the case of H_2, the covalent bond is very strong; a large amount of energy, 436 kJ, must be added to break the bonds in one mole of hydrogen molecules and cause the atoms to separate:

$$\mathrm{H_2\,(g) \longrightarrow 2\,H\,(g)} \quad \Delta H = 436\,\mathrm{kJ}$$

Conversely, the same amount of energy is released when one mole of H_2 molecules forms from two moles of H atoms:

$$\mathrm{2\,H\,(g) \longrightarrow H_2\,(g)} \quad \Delta H = -436\,\mathrm{kJ}$$

Pure vs. Polar Covalent Bonds

If the atoms that form a covalent bond are identical, as in H_2, Cl_2, and other diatomic molecules, then the electrons in the bond must be shared equally. We refer to this as a pure covalent bond. Electrons shared in pure covalent bonds have an equal probability of being near each nucleus.

In the case of Cl_2, each atom starts off with seven valence electrons, and each Cl shares one electron with the other, forming one covalent bond:

$$\mathrm{Cl + Cl \longrightarrow Cl_2}$$

The total number of electrons around each individual atom consists of six nonbonding electrons and two shared (i.e., bonding) electrons for eight total electrons, matching the number of valence electrons in the noble gas argon. Since the bonding atoms are identical, Cl_2 also features a pure covalent bond.

When the atoms linked by a covalent bond are different, the bonding electrons are shared, but no longer equally. Instead, the bonding electrons are more attracted to one atom than the other, giving rise to a shift of electron density toward that atom. This unequal distribution of electrons is known as a polar covalent bond, characterized by a partial positive charge on one atom and a partial negative charge on the other. The atom that attracts the electrons more strongly acquires the partial negative charge and vice versa. For example, the electrons in the H–Cl bond of a hydrogen chloride molecule spend more time near the chlorine atom than near the hydrogen atom. Thus, in an HCl molecule, the chlorine atom carries a partial negative charge and the hydrogen atom has a partial positive charge. Figure **10.3.2** shows the distribution of electrons in the H–Cl bond. Note that the shaded area around Cl is

much larger than it is around H. Compare this to Figure **10.3.1**, which shows the even distribution of electrons in the H_2 nonpolar bond.

We sometimes designate the positive and negative atoms in a polar covalent bond using a lowercase Greek letter "delta," δ, with a plus sign or minus sign to indicate whether the atom has a partial positive charge (δ+) or a partial negative charge (δ–). This symbolism is shown for the H–Cl molecule in Figure **10.3.2**.




Figure **10.3.2**: (a) The distribution of electron density in the HCl molecule is uneven. The electron density is greater around the chlorine nucleus. The small, black dots indicate the location of the hydrogen and chlorine nuclei in the molecule. (b) Symbols δ+ and δ– indicate the polarity of the H–Cl bond.

Electronegativity

Whether a bond is nonpolar or polar covalent is determined by a property of the bonding atoms called electronegativity. Electronegativity is a measure of the tendency of an atom to attract electrons (or electron density) towards itself. It determines how the shared electrons are distributed between the two atoms in a bond. The more strongly an atom attracts the electrons in its bonds, the larger its electronegativity. Electrons in a polar covalent bond are shifted toward the more electronegative atom; thus, the more electronegative atom is the one with the partial negative charge. The greater the difference in electronegativity, the more polarized the electron distribution and the larger the partial charges of the atoms.

Figure **10.3.3** shows the electronegativity values of the elements as proposed by one of the most famous chemists of the twentieth century: Linus Pauling (Figure **10.3.4**). In general, electronegativity increases from left to right across a period in the periodic table and decreases down a group. Thus, the nonmetals, which lie in the upper right, tend to have the highest electronegativities, with fluorine the most electronegative element of all (EN = 4.0). Metals tend to be less electronegative elements, and the group 1 metals have the lowest electronegativities. Note that noble gases are excluded from this figure because these atoms usually do not share electrons with others atoms since they have a full valence shell. (While noble gas compounds such as XeO_2 do exist, they can only be formed under extreme conditions, and thus they do not fit neatly into the general model of electronegativity.)




Figure **10.3.3**: The electronegativity values derived by Pauling follow predictable periodic trends, with the higher electronegativities toward the upper right of the periodic table.

Electronegativity versus Electron Affinity

We must be careful not to confuse electronegativity and electron affinity. The electron affinity of an element is a measurable physical quantity, namely, the energy released or absorbed when an isolated gas-phase atom acquires an electron, measured in kJ/mol. Electronegativity, on the other hand, describes how tightly an atom attracts electrons in a bond. It is a dimensionless

quantity that is calculated, not measured. Pauling derived the first electronegativity values by comparing the amounts of energy required to break different types of bonds. He chose an arbitrary relative scale ranging from 0 to 4.

Portrait of a Chemist: Linus Pauling

Linus Pauling, shown in Figure **10.3.4**, is the only person to have received two unshared (individual) Nobel Prizes: one for chemistry in 1954 for his work on the nature of chemical bonds and one for peace in 1962 for his opposition to weapons of mass destruction. He developed many of the theories and concepts that are foundational to our current understanding of chemistry, including electronegativity and resonance structures.




Figure **10.3.4**: Linus Pauling (1901–1994) made many important contributions to the field of chemistry. He was also a prominent activist, publicizing issues related to health and nuclear weapons.

Pauling also contributed to many other fields besides chemistry. His research on sickle cell anemia revealed the cause of the disease—the presence of a genetically inherited abnormal protein in the blood—and paved the way for the field of molecular genetics. His work was also pivotal in curbing the testing of nuclear weapons; he proved that radioactive fallout from nuclear testing posed a public health risk.

Electronegativity and Bond Type

The absolute value of the difference in electronegativity (ΔEN) of two bonded atoms provides a rough measure of the polarity to be expected in the bond and, thus, the bond type. When the difference is very small or zero, the bond is covalent and nonpolar. When it is large, the bond is polar covalent or ionic. The absolute values of the electronegativity differences between the atoms in the bonds H–H, H–Cl, and Na–Cl are 0 (nonpolar), 0.9 (polar covalent), and 2.1 (ionic), respectively. The degree to which electrons are shared between atoms varies from completely equal (pure covalent bonding) to not at all (ionic bonding). Figure **10.3.5** shows the relationship between electronegativity difference and bond type.



Bond Type	Electronegativity Difference
pure covalent	< 0.4
polar covalent	between 0.4 and 1.8
ionic	> 1.8

Figure **10.3.5**: As the electronegativity difference increases between two atoms, the bond becomes more ionic.

A rough approximation of the electronegativity differences associated with covalent, polar covalent, and ionic bonds is shown in Figure **10.3.5**. This table is just a general guide, however, with many exceptions. For example, the H and F atoms in HF have an electronegativity difference of 1.9, and the N and H atoms in NH_3 a difference of 0.9, yet both of these compounds form bonds that

are considered polar covalent. Likewise, the Na and Cl atoms in NaCl have an electronegativity difference of 2.1, and the Mn and I atoms in MnI_2 have a difference of 1.0, yet both of these substances form ionic compounds.

The best guide to the covalent or ionic character of a bond is to consider the types of atoms involved and their relative positions in the periodic table. Bonds between two nonmetals are generally covalent; bonding between a metal and a nonmetal is often ionic.

Some compounds contain both covalent and ionic bonds. The atoms in polyatomic ions, such as OH^-, and are held together by polar covalent bonds. However, these polyatomic ions form ionic compounds by combining with ions of opposite charge. For example, potassium nitrate, KNO_3, contains the K^+ cation and the polyatomic anion. Thus, bonding in potassium nitrate is ionic, resulting from the electrostatic attraction between the ions K^+ and as well as covalent between the nitrogen and oxygen atoms in

Example 10.3.1: Electronegativity and Bond Polarity

Bond polarities play an important role in determining the structure of proteins. Using the electronegativity values in Figure **10.3.3**, arrange the following covalent bonds—all commonly found in amino acids—in order of increasing polarity. Then designate the positive and negative atoms using the symbols δ+ and δ–:

C–H, C–N, C–O, N–H, O–H, S–H

Solution

The polarity of these bonds increases as the absolute value of the electronegativity difference increases. The atom with the δ– designation is the more electronegative of the two. Table **10.3.1** shows these bonds in order of increasing polarity.

Table **10.3.1**: Bond Polarity and Electronegativity Difference

Bond	ΔEN	Polarity
C–H	0.4	
S–H	0.4	
C–N	0.5	
N–H	0.9	
C–O	1.0	
O–H	1.4	

Exercise 10.3.1

Silicones are polymeric compounds containing, among others, the following types of covalent bonds: Si–O, Si–C, C–H, and C–C. Using the electronegativity values in Figure **10.3.3**, arrange the bonds in order of increasing polarity and designate the positive and negative atoms using the symbols δ+ and δ–.

Answer

Bond	Electronegativity Difference	Polarity
C–C	0.0	nonpolar
C–H	0.4	
Si–C	0.7	
Si–O	1.7	

This page titled 10.3: Covalent Bonding and Electronegativity is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **7.2: Covalent Bonding** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

10.7: Formal Charges

Learning Objectives

By the end of this section, you will be able to:

- Compute formal charges for atoms in any Lewis structure
- Use formal charges to identify the most reasonable Lewis structure for a given molecule

In the previous section, we discussed resonance structures. As we have seen, in some cases, there is more than one valid structure for a molecule. We can use the concept of formal charges to help us predict the most appropriate Lewis structure when more than one is reasonable.

Calculating Formal Charge

The formal charge of an atom in a molecule is the *hypothetical* charge the atom would have if we could redistribute the electrons in the bonds evenly between the atoms. Another way of saying this is that formal charge results when we take the number of valence electrons of a neutral atom, subtract the nonbonding electrons, and then subtract the number of bonds connected to that atom in the Lewis structure.

Thus, we calculate formal charge as follows:

$$\text{formal charge} = \#\text{ valence shell electrons (free atom)} - \#\text{ lone pair electrons} - \frac{1}{2}\#\text{ bonding electrons}$$

We can double-check formal charge calculations by determining the sum of the formal charges for the whole structure. The sum of the formal charges of all atoms in a molecule must be zero; the sum of the formal charges in an ion should equal the charge of the ion.


We must remember that the formal charge calculated for an atom is not the *actual* charge of the atom in the molecule. Formal charge is only a useful bookkeeping procedure; it does not indicate the presence of actual charges.

Example 10.7.1: Calculating Formal Charge from Lewis Structures

Assign formal charges to each atom in the interhalogen ion

Solution

Step 1. *We divide the bonding electron pairs equally for all I–Cl bonds:*



Step 2. *We assign lone pairs of electrons to their atoms*. Each Cl atom now has seven electrons assigned to it, and the I atom has eight.

Step 3. *Subtract this number from the number of valence electrons for the neutral atom:*

I: 7 – 8 = –1
Cl: 7 – 7 = 0

The sum of the formal charges of all the atoms equals –1, which is identical to the charge of the ion (–1).

Exercise 10.7.1

Calculate the formal charge for each atom in the carbon monoxide molecule:



Answer


C −1, O +1

Example 10.7.2: Calculating Formal Charge from Lewis Structures

Assign formal charges to each atom in the interhalogen molecule $BrCl_3$.

Solution

Step 1. *Assign one of the electrons in each Br–Cl bond to the Br atom and one to the Cl atom in that bond:*



Step 2. *Assign the lone pairs to their atom.* Now each Cl atom has seven electrons and the Br atom has seven electrons.

Step 3. *Subtract this number from the number of valence electrons for the neutral atom.* This gives the formal charge:

Br: 7 – 7 = 0
Cl: 7 – 7 = 0


All atoms in $BrCl_3$ have a formal charge of zero, and the sum of the formal charges totals zero, as it must in a neutral molecule.

Exercise 10.7.2

Determine the formal charge for each atom in NCl_3.

Answer

N: 0; all three Cl atoms: 0




Using Formal Charge to Predict Molecular Structure

The arrangement of atoms in a molecule or ion is called its **molecular structure**. In many cases, following the steps for writing Lewis structures may lead to more than one possible molecular structure—different multiple bond and lone-pair electron placements or different arrangements of atoms, for instance. A few guidelines involving formal charge can be helpful in deciding which of the possible structures is most likely for a particular molecule or ion:


1. A molecular structure in which all formal charges are zero is preferable to one in which some formal charges are not zero.
2. If the Lewis structure must have nonzero formal charges, the arrangement with the smallest nonzero formal charges is preferable.
3. Lewis structures are preferable when adjacent formal charges are zero or of the opposite sign.
4. When we must choose among several Lewis structures with similar distributions of formal charges, the structure with the negative formal charges on the more electronegative atoms is preferable.

To see how these guidelines apply, let us consider some possible structures for carbon dioxide, CO_2. We know from our previous discussion that the less electronegative atom typically occupies the central position, but formal charges allow us to understand *why* this occurs. We can draw three possibilities for the structure: carbon in the center and double bonds, carbon in the center with a single and triple bond, and oxygen in the center with double bonds:



Comparing the three formal charges, we can definitively identify the structure on the left as preferable because it has only formal charges of zero (Guideline 1).


As another example, the thiocyanate ion, an ion formed from a carbon atom, a nitrogen atom, and a sulfur atom, could have three different molecular structures: NCS^-, CNS^-, or CSN^-. The formal charges present in each of these molecular structures can help us pick the most likely arrangement of atoms. Possible Lewis structures and the formal charges for each of the three possible structures for the thiocyanate ion are shown here:



Note that the sum of the formal charges in each case is equal to the charge of the ion (–1). However, the first arrangement of atoms is preferred because it has the lowest number of atoms with nonzero formal charges (Guideline 2). Also, it places the least electronegative atom in the center, and the negative charge on the more electronegative element (Guideline 4).


✔ Example 10.7.3: Using Formal Charge to Determine Molecular Structure

Nitrous oxide, N_2O, commonly known as laughing gas, is used as an anesthetic in minor surgeries, such as the routine extraction of wisdom teeth. Which is the more likely structure for nitrous oxide?




Solution

Determining formal charge yields the following:




The structure with a terminal oxygen atom best satisfies the criteria for the most stable distribution of formal charge:



The number of atoms with formal charges are minimized (Guideline 2), there is no formal charge with a magnitude greater than one (Guideline 2), the negative formal charge is on the more electronegative element (Guideline 4), and the less electronegative atom is in the center position.

? Exercise 10.7.3

Which is the most likely molecular structure for the nitrite ion?



Answer

ONO^-

This page titled 10.7: Formal Charges is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **7.4: Formal Charges and Resonance** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

10.1: Lewis Symbol of Atoms

Learning Objectives

- To use Lewis electron dot symbols to predict the number of bonds an element will form.

Why are some substances chemically bonded molecules and others are an association of ions? The answer to this question depends upon the electronic structures of the atoms and nature of the chemical forces within the compounds. Although there are no sharply defined boundaries, chemical bonds are typically classified into three main types: ionic bonds, covalent bonds, and metallic bonds. In this chapter, each type of bond wil be discussed and the general properties found in typical substances in which the bond type occurs

1. Ionic bonds results from ***electrostatic forces that exist between ions of opposite charge***. These bonds typically involves a metal with a nonmetal
2. Covalent bonds ***result from the sharing of electrons between two atoms***. The bonds typically involves one nonmetallic element with another
3. Metallic bonds These bonds are found in solid metals (copper, iron, aluminum) with each metal bonded to several neighboring groups and bonding electrons free to move throughout the 3-dimensional structure.

Each bond classification is discussed in detail in subsequent sections of the chapter. Let's look at the preferred arrangements of electrons in atoms when they form chemical compounds.




Figure **10.1.1**: G. N. Lewis and the Octet Rule. (a) Lewis is working in the laboratory. (b) In Lewis's original sketch for the octet rule, he initially placed the electrons at the corners of a cube rather than placing them as we do now.

Lewis Symbols

At the beginning of the 20th century, the American chemist G. N. Lewis (1875–1946) devised a system of symbols—now called *Lewis electron dot symbols* (often shortened to *Lewis dot symbols*) that can be used for predicting the number of bonds formed by most elements in their compounds. Each Lewis dot symbol consists of the chemical symbol for an element surrounded by dots that represent its valence electrons.

Lewis Dot symbols:

- convenient representation of valence electrons
- allows you to keep track of valence electrons during bond formation
- consists of the chemical symbol for the element plus a dot for each valence electron

To write an element's Lewis dot symbol, we place dots representing its valence electrons, one at a time, around the element's chemical symbol. Up to four dots are placed above, below, to the left, and to the right of the symbol (in any order, as long as elements with four or fewer valence electrons have no more than one dot in each position). The next dots, for elements with more than four valence electrons, are again distributed one at a time, each paired with one of the first four. For example, the electron configuration for atomic sulfur is [Ne]$3s^2 3p^4$, thus there are ***six*** valence electrons. Its Lewis symbol would therefore be:



Fluorine, for example, with the electron configuration [He]$2s^2 2p^5$, has seven valence electrons, so its Lewis dot symbol is constructed as follows:




Figure 8.1.2.

Lewis used the unpaired dots to predict the number of bonds that an element will form in a compound. Consider the symbol for nitrogen in Figure 8.1.2. The Lewis dot symbol explains why nitrogen, with three unpaired valence electrons, tends to form compounds in which it shares the unpaired electrons to form three bonds. Boron, which also has three unpaired valence electrons in its Lewis dot symbol, also tends to form compounds with three bonds, whereas carbon, with four unpaired valence electrons in its Lewis dot symbol, tends to share all of its unpaired valence electrons by forming compounds in which it has four bonds.

Element	Electron config.	Electron dot symbol
Li	[He]$2s^1$	Li•
Be	[He]$2s^2$	•Be•
B	[He]$2s^2 2p^1$	•B•
C	[He]$2s^2 2p^2$	•C•
N	[He]$2s^2 2p^3$	•N:
O	[He]$2s^2 2p^4$	:O:
F	[He]$2s^2 2p^5$	:F:
Ne	[He]$2s^2 2p^6$	:Ne:

Figure **10.1.2**: Lewis Dot Symbols for the Elements in Period 2



The Octet Rule

In 1904, Richard Abegg formulated what is now known as *Abegg's rule*, which states that the difference between the maximum positive and negative valences of an element is frequently eight. This rule was used later in 1916 when Gilbert N. Lewis formulated the "octet rule" in his cubical atom theory. The **octet rule** refers to the tendency of atoms to prefer to have eight electrons in the *valence shell*. When atoms have fewer than eight electrons, they tend to react and form more stable compounds. Atoms will react to get in the most stable state possible. A complete octet is very stable because all orbitals will be full. Atoms with greater stability have less energy, so a reaction that increases the stability of the atoms will release energy in the form of heat or light ;reactions that decrease stability must absorb energy, getting colder.

When discussing the octet rule, we do not consider *d* or *f* electrons. Only the s and p electrons are involved in the octet rule, making it a useful rule for the *main group elements* (elements not in the transition metal or inner-transition metal blocks); an octet in these atoms corresponds to an electron configurations ending with s^2p^6.

Definition: Octet Rule

A stable arrangement is attended when the atom is surrounded by eight electrons. This octet can be made up by own electrons and some electrons which are shared. Thus, an atom continues to form bonds until an octet of electrons is made. This is known as octet rule by Lewis.

1. Normally two electrons pairs up and forms a bond, e.g., $\mathbf{H_2}$
2. For most atoms there will be a maximum of eight electrons in the valence shell (octet structure), e.g., $\mathbf{CH_4}$




Figure 1: Bonding in $\boldsymbol{H_2}$ and methane ($\boldsymbol{CH_4}$)

The other tendency of atoms is to maintain a neutral charge. Only the noble gases (the elements on the right-most column of the periodic table) have zero charge with filled valence octets. All of the other elements have a charge when they have eight electrons all to themselves. The result of these two guiding principles is the explanation for much of the reactivity and bonding that is observed within atoms: atoms seek to share electrons in a way that minimizes charge while fulfilling an octet in the valence shell.

The noble gases rarely form compounds. They have the most stable configuration (full octet, no charge), so they have no reason to react and change their configuration. All other elements attempt to gain, lose, or share electrons to achieve a noble gas configuration.

Example 10.1.1: Salt

The formula for table salt is NaCl. It is the result of Na^+ ions and Cl^- ions bonding together. If sodium metal and chlorine gas mix under the right conditions, they will form salt. The sodium loses an electron, and the chlorine gains that electron. In the process, a great amount of light and heat is released. The resulting salt is mostly unreactive — it is stable. It will not undergo any explosive reactions, unlike the sodium and chlorine that it is made of. Why?

Solution

Referring to the octet rule, atoms attempt to get a noble gas electron configuration, which is eight valence electrons. Sodium has one valence electron, so giving it up would result in the same electron configuration as neon. Chlorine has seven valence electrons, so if it takes one it will have eight (an octet). Chlorine has the electron configuration of argon when it gains an electron.

The octet rule could have been satisfied if chlorine gave up all seven of its valence electrons and sodium took them. In that case, both would have the electron configurations of noble gasses, with a full valence shell. However, their charges would be much higher. It would be Na^{7-} and Cl^{7+}, which is much less stable than Na^+ and Cl^-. Atoms are more stable when they have no charge, or a small charge.

Lewis dot symbols can also be used to represent the ions in ionic compounds. The reaction of cesium with fluorine, for example, to produce the ionic compound CsF can be written as follows:



No dots are shown on Cs^+ in the product because cesium has lost its single valence electron to fluorine. The transfer of this electron produces the Cs^+ ion, which has the valence electron configuration of Xe, and the F^- ion, which has a total of eight valence electrons (an octet) and the Ne electron configuration. This description is consistent with the statement that among the main group elements, ions in simple binary ionic compounds generally have the electron configurations of the nearest noble gas. The charge of each ion is written in the product, and the anion and its electrons are enclosed in brackets. This notation emphasizes that the ions are associated electrostatically; no electrons are shared between the two elements.

> *Atoms often gain, lose, or share electrons to achieve the same number of electrons as the noble gas closest to them in the periodic table.*

As you might expect for such a qualitative approach to bonding, there are exceptions to the octet rule, which we describe elsewhere. These include molecules in which one or more atoms contain fewer or more than eight electrons.

Summary

Lewis dot symbols can be used to predict the number of bonds formed by most elements in their compounds. One convenient way to predict the number and basic arrangement of bonds in compounds is by using **Lewis electron dot symbols**, which consist of the chemical symbol for an element surrounded by dots that represent its valence electrons, grouped into pairs often placed above, below, and to the left and right of the symbol. The structures reflect the fact that the elements in period 2 and beyond tend to gain, lose, or share electrons to reach a total of eight valence electrons in their compounds, the so-called **octet rule**. Hydrogen, with only two valence electrons, does not obey the octet rule.

Contributors and Attributions

- Mike Blaber (Florida State University)
- Wikipedia
- National Programme on Technology Enhanced Learning (India)

10.1: Lewis Symbol of Atoms is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **7.3: Covalent Bonding** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **8.1: Chemical Bonds, Lewis Symbols, and the Octet Rule** is licensed CC BY-NC-SA 3.0.

10.2: Ionic Bonding

Learning Objectives

- To describe the characteristics of ionic bonding.
- To quantitatively describe the energetic factors involved in the formation of an ionic bond.

Ions are atoms or molecules which are electrically charged. **Cations** are positively charged and **anions** carry a negative charge. Ions form when atoms gain or lose electrons. Since electrons are negatively charged, an atom that loses one or more electrons will become positively charged; an atom that gains one or more electrons becomes negatively charged. **Ionic bonding** is the attraction between positively- and negatively-charged ions. These oppositely charged ions attract each other to form ionic networks (or **lattices**). Electrostatics explains why this happens: opposite charges attract and like charges repel. When many ions attract each other, they form large, ordered, crystal lattices in which each ion is surrounded by ions of the opposite charge. Generally, when metals react with non-metals, electrons are transferred from the metals to the non-metals. The metals form positively-charged ions and the non-metals form negatively-charged ions.

Lewis symbols can be used to illustrate the formation of cations from atoms, as shown here for sodium and calcium:



Likewise, they can be used to show the formation of anions from atoms, as shown here for chlorine and sulfur:



Figure **10.2.1** demonstrates the use of Lewis symbols to show the transfer of electrons during the formation of ionic compounds.

Metal		Nonmetal		Ionic Compound
Na•	+	:Cl•	→	$Na^+[:\ddot{Cl}:]^-$
sodium atom		chlorine atom		sodium chloride (sodium ion and chloride ion)
•Mg•	+	:O•	→	$Mg^{2+}[:\ddot{O}:]^{2-}$
magnesium atom		oxygen atom		magnesium oxide (magnesium ion and oxide ion)
•Ca•	+	2 :F•	→	$Ca^{2+}[:\ddot{F}:]^-_2$
calcium atom		fluorine atoms		calcium fluoride (calcium ion and two fluoride ions)

Figure **10.2.2**: Cations are formed when atoms lose electrons, represented by fewer Lewis dots, whereas anions are formed by atoms gaining electrons. The total number of electrons does not change.



Lewis Structures of Ionic Compounds: https://youtu.be/oJ9975tmjc0

Energetics of Ionic Bond Formation

Ionic bonds are formed when positively and negatively charged ions are held together by electrostatic forces. Consider a single pair of ions, one cation and one anion. How strong will the force of their attraction be? According to **Coulomb's Law**, the energy of the electrostatic attraction (E) between two charged particles is proportional to the magnitude of the charges and inversely proportional to the internuclear distance between the particles (r):

$$E \propto \frac{Q_1 Q_2}{r} \tag{10.2.1}$$

$$E = k\frac{Q_1 Q_2}{r} \tag{10.2.2}$$

where each ion's charge is represented by the symbol Q. The proportionality constant k is equal to 2.31×10^{-28} J·m. This value of k includes the charge of a single electron (1.6022×10^{-19} C) for each ion. The equation can also be written using the charge of each ion, expressed in coulombs (C), incorporated in the constant. In this case, the proportionality constant, k, equals 8.999 × 109 J·m/C^2. In the example given, $Q_1 = +1(1.6022 \times 10^{-19}$ C) and $Q_2 = -1(1.6022 \times 10^{-19}$ C). If Q_1 and Q_2 have opposite signs (as in NaCl, for example, where Q_1 is +1 for Na^+ and Q_2 is −1 for Cl^-), then E is negative, which means that energy is *released* when oppositely charged ions are brought together from an infinite distance to form an isolated ion pair.

> *Energy is always released when a bond is formed and correspondingly, it always requires energy to break a bond.*

As shown by the green curve in the lower half of Figure **10.2.3**, the maximum energy would be released when the ions are infinitely close to each other, at $r = 0$. Because ions occupy space and have a structure with the positive nucleus being surrounded by electrons, however, they cannot be infinitely close together. At very short distances, repulsive electron–electron interactions between electrons on adjacent ions become stronger than the attractive interactions between ions with opposite charges, as shown by the red curve in the upper half of Figure **10.2.3**. The total energy of the system is a balance between the attractive and repulsive interactions. The purple curve in Figure **10.2.3** shows that the total energy of the system reaches a minimum at r_0, the point where the electrostatic repulsions and attractions are exactly balanced. This distance is the same as the experimentally measured **bond distance**.




Figure 10.2.3: A Plot of Potential Energy versus Internuclear Distance for the Interaction between a Gaseous Na^+ Ion and a Gaseous Cl^- Ion. The energy of the system reaches a minimum at a particular distance (r_0) when the attractive and repulsive interactions are balanced.

Consider the energy released when a gaseous Na^+ ion and a gaseous Cl^- ion are brought together from $r = \infty$ to $r = r_0$. Given that the observed gas-phase internuclear distance is 236 pm, the energy change associated with the formation of an ion pair from an $Na^+_{(g)}$ ion and a $Cl^-_{(g)}$ ion is as follows:

$$\begin{aligned} E &= k\frac{Q_1Q_2}{r_0} \\ &= (2.31 \times 10^{-28}\,\text{J} \cdot \cancel{\text{m}}) \left(\frac{(+1)(-1)}{236\ \cancel{\text{pm}} \times 10^{-12}\ \cancel{\text{m/pm}}} \right) \\ &= -9.79 \times 10^{-19}\ J/ion\ pair \end{aligned}$$

The negative value indicates that energy is released. Our convention is that if a chemical process provides energy to the outside world, the energy change is negative. If it requires energy, the energy change is positive. To calculate the energy change in the formation of a mole of NaCl pairs, we need to multiply the energy per ion pair by Avogadro's number:

$$E = \left(-9.79 \times 10^{-19}\ J/\cancel{ionpair}\right)\left(6.022 \times 10^{23}\ \cancel{ion\ pair}/mol\right) = -589\ kJ/mol \tag{10.2.3}$$

This is the energy released when 1 mol of gaseous ion pairs is formed, *not* when 1 mol of positive and negative ions condenses to form a crystalline lattice. Because of long-range interactions in the lattice structure, this energy does not correspond directly to the **lattice energy** of the crystalline solid. However, the large negative value indicates that bringing positive and negative ions together is energetically very favorable, whether an ion pair or a crystalline lattice is formed.

We summarize the important points about ionic bonding:

- At r_0, the ions are more stable (have a lower potential energy) than they are at an infinite internuclear distance. When oppositely charged ions are brought together from $r = \infty$ to $r = r_0$, the energy of the system is lowered (energy is released).
- Because of the low potential energy at r_0, energy must be added to the system to separate the ions. The amount of energy needed is the bond energy.
- The energy of the system reaches a minimum at a particular internuclear distance (the bond distance).

✔ Example 10.2.1: LiF

Calculate the amount of energy released when 1 mol of gaseous Li^+F^- ion pairs is formed from the separated ions. The observed internuclear distance in the gas phase is 156 pm.

Given: cation and anion, amount, and internuclear distance

Asked for: energy released from formation of gaseous ion pairs

Strategy:

Substitute the appropriate values into Equation 10.2.2 to obtain the energy released in the formation of a single ion pair and then multiply this value by Avogadro's number to obtain the energy released per mole.

Solution:

Inserting the values for Li^+F^- into Equation 10.2.2 (where Q_1 = +1, Q_2 = −1, and r = 156 pm), we find that the energy associated with the formation of a single pair of Li^+F^- ions is

$$\begin{aligned} E &= k\frac{Q_1Q_2}{r_0} \\ &= \left(2.31 \times 10^{-28} J \cdot \cancel{m}\right)\left(\frac{(+1)(-1)}{156\ pm \times 10^{-12}\ \cancel{m}/\cancel{pm}}\right) \\ &= -1.48 \times 10^{-18} \end{aligned}$$

Then the energy released per mole of Li^+F^- ion pairs is

$$\begin{aligned} E &= \left(-1.48 \times 10^{-18} J/\cancel{\text{ion pair}}\right)\left(6.022 \times 10^{23}\ \cancel{\text{ion pair}}/mol\right) \\ &- 891\ kJ/mol \end{aligned}$$

Because Li^+ and F^- are smaller than Na^+ and Cl^- (see Section 7.3), the internuclear distance in LiF is shorter than in NaCl. Consequently, in accordance with Equation 10.2.2, much more energy is released when 1 mol of gaseous Li^+F^- ion pairs is formed (−891 kJ/mol) than when 1 mol of gaseous Na^+Cl^- ion pairs is formed (−589 kJ/mol).

? Exercise 10.2.1: Magnesium oxide

Calculate the amount of energy released when 1 mol of gaseous **MgO** ion pairs is formed from the separated ions. The internuclear distance in the gas phase is 175 pm.

Answer

−3180 kJ/mol = -3.18×10^3 kJ/mol

Summary

The amount of energy needed to separate a gaseous ion pair is its bond energy. The formation of ionic compounds are usually ***extremely exothermic***. The strength of the electrostatic attraction between ions with opposite charges is directly proportional to the magnitude of the charges on the ions and inversely proportional to the internuclear distance. The total energy of the system is a balance between the repulsive interactions between electrons on adjacent ions and the attractive interactions between ions with opposite charges.

Contributors and Attributions

- http://en.wikibooks.org/wiki/User:Jplego/Collections
- Mike Blaber (Florida State University)
- Modified by Joshua Halpern (Howard University)

10.2: Ionic Bonding is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **7.3: Covalent Bonding** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **8.2: Ionic Bonding** is licensed CC BY-NC-SA 3.0.
- **7.4: Lewis Symbols and Structures** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

10.4: Lewis Structures of Molecular Compounds

Learning Objectives

- To use Lewis dot symbols to explain the stoichiometry of a compound

We begin our discussion of the relationship between structure and bonding in covalent compounds by describing the interaction between two identical neutral atoms—for example, the H_2 molecule, which contains a purely covalent bond. Each hydrogen atom in H_2 contains one electron and one proton, with the electron attracted to the proton by electrostatic forces. As the two hydrogen atoms are brought together, additional interactions must be considered (Figure **10.4.1**):

- The electrons in the two atoms repel each other because they have the same charge (
- *The electrons in the two atoms repel each other because they have the same charge (E > 0).*
- *Similarly, the protons in adjacent atoms repel each other (E > 0).*
- *The electron in one atom is attracted to the oppositely charged proton in the other atom and vice versa (E < 0). Recall that it is impossible to specify precisely the position of the electron in either hydrogen atom. Hence the quantum mechanical probability distributions must be used.*




Figure **10.4.1**: Attractive and Repulsive Interactions between Electrons and Nuclei in the Hydrogen Molecule. Electron–electron and proton–proton interactions are repulsive; electron–proton interactions are attractive. At the observed bond distance, the repulsive and attractive interactions are balanced.

A plot of the potential energy of the system as a function of the internuclear distance (Figure **10.4.2**) shows that the system becomes more stable (the energy of the system decreases) as two hydrogen atoms move toward each other from $r = \infty$, until the energy reaches a minimum at $r = r_0$ (the observed internuclear distance in H_2 is 74 pm). Thus at intermediate distances, proton–electron attractive interactions dominate, but as the distance becomes very short, electron–electron and proton–proton repulsive interactions cause the energy of the system to increase rapidly. Notice the similarity between Figures **10.4.1** and **10.4.2**, which described a system containing two oppositely charged *ions*. The shapes of the energy versus distance curves in the two figures are similar because they both result from attractive and repulsive forces between charged entities.





Figure **10.4.2**: A Plot of Potential Energy versus Internuclear Distance for the Interaction between Two Gaseous Hydrogen Atoms.

At long distances, both attractive and repulsive interactions are small. As the distance between the atoms decreases, the attractive electron–proton interactions dominate, and the energy of the system decreases. At the observed bond distance, the repulsive electron–electron and proton–proton interactions just balance the attractive interactions, preventing a further decrease in the

internuclear distance. At very short internuclear distances, the repulsive interactions dominate, making the system less stable than the isolated atoms.


Using Lewis Dot Symbols to Describe Covalent Bonding

The valence electron configurations of the constituent atoms of a covalent compound are important factors in determining its structure, stoichiometry, and properties. For example, chlorine, with seven valence electrons, is one electron short of an octet. If two chlorine atoms share their unpaired electrons by making a covalent bond and forming Cl_2, they can each complete their valence shell:




Each chlorine atom now has an octet. The electron pair being shared by the atoms is called a bonding pair; the other three pairs of electrons on each chlorine atom are called lone pairs. Lone pairs are not involved in covalent bonding. If both electrons in a covalent bond come from the same atom, the bond is called a coordinate covalent bond. Examples of this type of bonding are presented in Section 8.6 when we discuss atoms with less than an octet of electrons.

We can illustrate the formation of a water molecule from two hydrogen atoms and an oxygen atom using Lewis dot symbols:



The structure on the right is the *Lewis electron structure*, or *Lewis structure*, for H_2O. With two bonding pairs and two lone pairs, the oxygen atom has now completed its octet. Moreover, by sharing a bonding pair with oxygen, each hydrogen atom now has a full valence shell of two electrons. Chemists usually indicate a bonding pair by a single line, as shown here for our two examples:



The following procedure can be used to construct Lewis electron structures for more complex molecules and ions:

1. **Arrange the atoms to show specific connections.** When there is a central atom, it is usually the least electronegative element in the compound. Chemists usually list this central atom first in the chemical formula (as in CCl_4 and CO_3^{2-}, which both have C as the central atom), which is another clue to the compound's structure. Hydrogen and the halogens are almost always connected to only one other atom, so they are usually *terminal* rather than central.
2. **Determine the total number of valence electrons in the molecule or ion.** Add together the valence electrons from each atom. (Recall that the number of valence electrons is indicated by the position of the element in the periodic table.) If the species is a polyatomic ion, remember to add or subtract the number of electrons necessary to give the total charge on the ion. For CO_3^{2-}, for example, we add two electrons to the total because of the −2 charge.
3. **Place a bonding pair of electrons between each pair of adjacent atoms to give a single bond.** In H_2O, for example, there is a bonding pair of electrons between oxygen and each hydrogen.
4. **Beginning with the terminal atoms, add enough electrons to each atom to give each atom an octet (two for hydrogen).** These electrons will usually be lone pairs.
5. **If any electrons are left over, place them on the central atom.** We will explain later that some atoms are able to accommodate more than eight electrons.
6. **If the central atom has fewer electrons than an octet, use lone pairs from terminal atoms to form multiple (double or triple) bonds to the central atom to achieve an octet.** This will not change the number of electrons on the terminal atoms.

Now let's apply this procedure to some particular compounds, beginning with one we have already discussed.

> The central atom is usually the least electronegative element in the molecule or ion; hydrogen and the halogens are usually terminal.

The H_2O Molecule

1. Because H atoms are almost always terminal, the arrangement within the molecule must be HOH.


2. Each H atom (group 1) has 1 valence electron, and the O atom (group 16) has 6 valence electrons, for a total of 8 valence electrons.
3. Placing one bonding pair of electrons between the O atom and each H atom gives H:O:H, with 4 electrons left over.
4. Each H atom has a full valence shell of 2 electrons.
5. Adding the remaining 4 electrons to the oxygen (as two lone pairs) gives the following structure:



This is the Lewis structure we drew earlier. Because it gives oxygen an octet and each hydrogen two electrons, we do not need to use step 6.

The OCl^- Ion

1. With only two atoms in the molecule, there is no central atom.
2. Oxygen (group 16) has 6 valence electrons, and chlorine (group 17) has 7 valence electrons; we must add one more for the negative charge on the ion, giving a total of 14 valence electrons.
3. Placing a bonding pair of electrons between O and Cl gives O:Cl, with 12 electrons left over.
4. If we place six electrons (as three lone pairs) on each atom, we obtain the following structure:



Both the oxygen and chlorine have 3 electron pairs drawn around them with a bond drawn between them. The molecule has square brackets placed around it and has a negative charge.

Each atom now has an octet of electrons, so steps 5 and 6 are not needed. The Lewis electron structure is drawn within brackets as is customary for an ion, with the overall charge indicated outside the brackets, and the bonding pair of electrons is indicated by a solid line. OCl^- is the hypochlorite ion, the active ingredient in chlorine laundry bleach and swimming pool disinfectant.


The CH_2O Molecule

1. Because carbon is less electronegative than oxygen and hydrogen is normally terminal, C must be the central atom. One possible arrangement is as follows:




2. Each hydrogen atom (group 1) has one valence electron, carbon (group 14) has 4 valence electrons, and oxygen (group 16) has 6 valence electrons, for a total of [(2)(1) + 4 + 6] = 12 valence electrons.

3. Placing a bonding pair of electrons between each pair of bonded atoms gives the following:



Six electrons are used, and 6 are left over.


4. Adding all 6 remaining electrons to oxygen (as three lone pairs) gives the following:



Although oxygen now has an octet and each hydrogen has 2 electrons, carbon has only 6 electrons.

5. There are no electrons left to place on the central atom.

6. To give carbon an octet of electrons, we use one of the lone pairs of electrons on oxygen to form a carbon–oxygen double bond:



The bond between the oxygen and carbon is replaced with a double bond. The oxygen also has two lone pairs drawn.

Both the oxygen and the carbon now have an octet of electrons, so this is an acceptable Lewis electron structure. The O has two bonding pairs and two lone pairs, and C has four bonding pairs. This is the structure of formaldehyde, which is used in embalming fluid.

An alternative structure can be drawn with one H bonded to O. *Formal charges*, discussed later in this section, suggest that such a structure is less stable than that shown previously.

Example 10.4.1

Write the Lewis electron structure for each species.

a. NCl_3
b. S_2^{2-}
c. NOCl

Given: chemical species


Asked for: Lewis electron structures

Strategy:


Use the six-step procedure to write the Lewis electron structure for each species.

Solution:

a. Nitrogen is less electronegative than chlorine, and halogen atoms are usually terminal, so nitrogen is the central atom. The nitrogen atom (group 15) has 5 valence electrons and each chlorine atom (group 17) has 7 valence electrons, for a total of 26 valence electrons. Using 2 electrons for each N–Cl bond and adding three lone pairs to each Cl account for (3 × 2) + (3 × 2 × 3) = 24 electrons. Rule 5 leads us to place the remaining 2 electrons on the central N:




Nitrogen trichloride is an unstable oily liquid once used to bleach flour; this use is now prohibited in the United States.




Nitrogen trichloride


b. In a diatomic molecule or ion, we do not need to worry about a central atom. Each sulfur atom (group 16) contains 6 valence electrons, and we need to add 2 electrons for the −2 charge, giving a total of 14 valence electrons. Using 2 electrons for the S–S bond, we arrange the remaining 12 electrons as three lone pairs on each sulfur, giving each S atom an octet of electrons:




c. Because nitrogen is less electronegative than oxygen or chlorine, it is the central atom. The N atom (group 15) has 5 valence electrons, the O atom (group 16) has 6 valence electrons, and the Cl atom (group 17) has 7 valence electrons, giving a total of 18 valence electrons. Placing one bonding pair of electrons between each pair of bonded atoms uses 4 electrons and gives the following:




Adding three lone pairs each to oxygen and to chlorine uses 12 more electrons, leaving 2 electrons to place as a lone pair on nitrogen:



Because this Lewis structure has only 6 electrons around the central nitrogen, a lone pair of electrons on a terminal atom must be used to form a bonding pair. We could use a lone pair on either O or Cl. Because we have seen many structures in which O forms a double bond but none with a double bond to Cl, it is reasonable to select a lone pair from O to give the following:



All atoms now have octet configurations. This is the Lewis electron structure of nitrosyl chloride, a highly corrosive, reddish-orange gas.




? Exercise 10.4.1

Write Lewis electron structures for CO_2 and SCl_2, a vile-smelling, unstable red liquid that is used in the manufacture of rubber.


Answer

1.






2.




Two chlorines are bonded to a sulfur. The sulfur has 2 lone pairs while the chlorines have 3 lone pairs each.




Using Lewis Electron Structures to Explain Stoichiometry

Lewis dot symbols provide a simple rationalization of why elements form compounds with the observed stoichiometries. In the Lewis model, the number of bonds formed by an element in a neutral compound is the same as the number of unpaired electrons it must share with other atoms to complete its octet of electrons. For the elements of Group 17 (the halogens), this number is one; for the elements of Group 16 (the chalcogens), it is two; for Group 15 elements, three; and for Group 14 elements four. These requirements are illustrated by the following Lewis structures for the hydrides of the lightest members of each group:



Elements may form multiple bonds to complete an octet. In ethylene, for example, each carbon contributes two electrons to the double bond, giving each carbon an octet (two electrons/bond × four bonds = eight electrons). Neutral structures with fewer or more bonds exist, but they are unusual and violate the octet rule.



Allotropes of an element can have very different physical and chemical properties because of different three-dimensional arrangements of the atoms; the number of bonds formed by the component atoms, however, is always the same. As noted at the beginning of the chapter, diamond is a hard, transparent solid; graphite is a soft, black solid; and the fullerenes have open cage structures. Despite these differences, the carbon atoms in all three allotropes form four bonds, in accordance with the octet rule.

> Lewis structures explain why the elements of groups 14–17 form neutral compounds with four, three, two, and one bonded atom(s), respectively.

Elemental phosphorus also exists in three forms: white phosphorus, a toxic, waxy substance that initially glows and then spontaneously ignites on contact with air; red phosphorus, an amorphous substance that is used commercially in safety matches, fireworks, and smoke bombs; and black phosphorus, an unreactive crystalline solid with a texture similar to graphite (Figure **10.4.3**). Nonetheless, the phosphorus atoms in all three forms obey the octet rule and form three bonds per phosphorus atom.




Figure **10.4.3**: The Three Allotropes of Phosphorus: White, Red, and Black. ll three forms contain only phosphorus atoms, but they differ in the arrangement and connectivity of their atoms. White phosphorus contains P_4 tetrahedra, red phosphorus is a network of linked P_8 and P_9 units, and black phosphorus forms sheets of six-membered rings. As a result, their physical and chemical properties differ dramatically.

Formal Charges

It is sometimes possible to write more than one Lewis structure for a substance that does not violate the octet rule, as we saw for CH_2O, but not every Lewis structure may be equally reasonable. In these situations, we can choose the most stable Lewis structure

by considering the formal charge on the atoms, which is the difference between the number of valence electrons in the free atom and the number assigned to it in the Lewis electron structure. The formal charge is a way of computing the charge distribution within a Lewis structure; the sum of the formal charges on the atoms within a molecule or an ion must equal the overall charge on the molecule or ion. A formal charge does *not* represent a true charge on an atom in a covalent bond but is simply used to predict the most likely structure when a compound has more than one valid Lewis structure.


To calculate formal charges, we assign electrons in the molecule to individual atoms according to these rules:

- Nonbonding electrons are assigned to the atom on which they are located.
- Bonding electrons are divided equally between the bonded atoms.

For each atom, we then compute a formal charge:

$$\textit{formal charge} = \underset{(\textit{free atom})}{\textit{valence } e^-} - \underset{(\textit{atom in Lewis structure})}{\left(\textit{non} - \textit{bonding } e^- + \frac{\textit{bonding } e^-}{2}\right)} \text{ (atom in Lewis structure)}$$

To illustrate this method, let's calculate the formal charge on the atoms in ammonia (NH_3) whose Lewis electron structure is as follows:



Ammonia

A neutral nitrogen atom has five valence electrons (it is in group 15). From its Lewis electron structure, the nitrogen atom in ammonia has one lone pair and shares three bonding pairs with hydrogen atoms, so nitrogen itself is assigned a total of five electrons [2 nonbonding e^- + (6 bonding e^-/2)]. Substituting into Equation 10.4.1, we obtain

$$\textit{formal charge}\,(N) = 5\ \textit{valence } e^- - \left(2\ \textit{non} - \textit{bonding } e^- + \frac{6\ \textit{bonding } e^-}{2}\right) = 0 \qquad (10.4.1)$$

A neutral hydrogen atom has one valence electron. Each hydrogen atom in the molecule shares one pair of bonding electrons and is therefore assigned one electron [0 nonbonding e^- + (2 bonding e^-/2)]. Using Equation 10.4.1 to calculate the formal charge on hydrogen, we obtain

$$\textit{formal charge}\,(H) = 1\ \textit{valence } e^- - \left(0\ \textit{non} - \textit{bonding } e^- + \frac{2\ \textit{bonding } e^-}{2}\right) = 0 \qquad (10.4.2)$$

The hydrogen atoms in ammonia have the same number of electrons as neutral hydrogen atoms, and so their formal charge is also zero. Adding together the formal charges should give us the overall charge on the molecule or ion. In this example, the nitrogen and each hydrogen has a formal charge of zero. When summed the overall charge is zero, which is consistent with the overall charge on the NH_3 molecule.

> An atom, molecule, or ion has a formal charge of zero if it has the number of bonds that is typical for that species.

Typically, the structure with the most charges on the atoms closest to zero is the more stable Lewis structure. In cases where there are positive or negative formal charges on various atoms, stable structures generally have negative formal charges on the more electronegative atoms and positive formal charges on the less electronegative atoms. The next example further demonstrates how to calculate formal charges.



Example 10.4.2: The Ammonium Ion

Calculate the formal charges on each atom in the NH_4^+ ion.

Given: chemical species


Asked for: formal charges

Strategy:

Identify the number of valence electrons in each atom in the NH_4^+ ion. Use the Lewis electron structure of NH_4^+ to identify the number of bonding and nonbonding electrons associated with each atom and then use Equation 10.4.1 to calculate the formal charge on each atom.

Solution:

The Lewis electron structure for the NH_4^+ ion is as follows:



The central nitrogen is bonded to four hydrogens. The molecule is surrounded by square brackets. Outside the bracket is where the positive charge is placed.


The nitrogen atom shares four bonding pairs of electrons, and a neutral nitrogen atom has five valence electrons. Using Equation ???, the formal charge on the nitrogen atom is therefore

$$formal\ charge\,(N) = 5 - \left(0 + \frac{8}{2}\right) = 0$$

Each hydrogen atom in has one bonding pair. The formal charge on each hydrogen atom is therefore

$$formal\ charge\,(H) = 1 - \left(0 + \frac{2}{2}\right) = 0$$

The formal charges on the atoms in the NH_4^+ ion are thus




In the Lewis structure, each hydrogen has a zero placed nearby while the nitrogen has a +1 placed nearby.

Adding together the formal charges on the atoms should give us the total charge on the molecule or ion. In this case, the sum of the formal charges is 0 + 1 + 0 + 0 + 0 = +1.

? Exercise 10.4.2

Write the formal charges on all atoms in BH_4^-.

Answer



Four hydrogens are bonded to a central boron. Each hydrogen has a zero placed nearby while the boron has a -1. The molecule is surrounded by square brackets. Outside of the brackets is a negative charge.

If an atom in a molecule or ion has the number of bonds that is typical for that atom (e.g., four bonds for carbon), its formal charge is zero.

Using Formal Charges to Distinguish Viable Lewis Structures

10.4: Lewis Structures of Molecular Compounds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **8.5: Drawing Lewis Structures** is licensed CC BY-NC-SA 3.0.

10.5: Exceptions to the Octet Rule

Learning Objectives

- Draw Lewis structures depicting the bonding in molecules that don't obey the octet rule.

Many covalent molecules have central atoms that do not have eight electrons in their Lewis structures. These molecules fall into three categories:


- Odd-electron molecules have an odd number of valence electrons, and therefore have an unpaired electron.
- Electron-deficient molecules have a central atom that has fewer electrons than needed for a noble gas configuration.
- Hypervalent molecules have a central atom that has more electrons than needed for a noble gas configuration.

Odd-electron Molecules


We call molecules that contain an odd number of electrons free radicals. Nitric oxide, NO, is an example of an odd-electron molecule; it is produced in internal combustion engines when oxygen and nitrogen react at high temperatures.

To draw the Lewis structure for an odd-electron molecule like NO, we follow the same five steps we would for other molecules, but with a few minor changes:

1. *Determine the total number of valence (outer shell) electrons*. The sum of the valence electrons is 5 (from N) + 6 (from O) = 11. The odd number immediately tells us that we have a free radical, so we know that not every atom can have eight electrons in its valence shell.
2. *Draw a skeleton structure of the molecule*. We can easily draw a skeleton with an N–O single bond: N–O
3. *Distribute the remaining electrons as lone pairs on the terminal atoms*. In this case, there is no central atom, so we distribute the electrons around both atoms. We give eight electrons to the more electronegative atom in these situations; thus oxygen has the filled valence shell:




4. *Place all remaining electrons on the central atom*. Since there are no remaining electrons, this step does not apply.
5. *Rearrange the electrons to make multiple bonds with the central atom in order to obtain octets wherever possible.* We know that an odd-electron molecule cannot have an octet for every atom, but we want to get each atom as close to an octet as possible. In this case, nitrogen has only five electrons around it. To move closer to an octet for nitrogen, we take one of the lone pairs from oxygen and use it to form a NO double bond. (We cannot take another lone pair of electrons on oxygen and form a triple bond because nitrogen would then have nine electrons:)




Electron-deficient Molecules

We will also encounter a few molecules that contain central atoms that do not have a filled valence shell. Generally, these are molecules with central atoms from groups 2 and 13 and outer atoms that are hydrogen or other atoms that do not form multiple bonds. For example, in the Lewis structures of beryllium dihydride, BeH_2, and boron trifluoride, BF_3, the beryllium and boron atoms each have only four and six electrons, respectively. It is possible to draw a structure with a double bond between a boron atom and a fluorine atom in BF_3, satisfying the octet rule, but experimental evidence indicates the bond lengths are closer to that expected for B–F single bonds. This suggests the best Lewis structure has three B–F single bonds and an electron deficient boron. The reactivity of the compound is also consistent with an electron deficient boron. However, the B–F bonds are slightly shorter than what is actually expected for B–F single bonds, indicating that some double bond character is found in the actual molecule.



An atom like the boron atom in BF_3, which does not have eight electrons, is very reactive. It readily combines with a molecule containing an atom with a lone pair of electrons. For example, NH_3 reacts with BF_3 because the lone pair on nitrogen can be shared with the boron atom:



Hypervalent Molecules

Elements in the second period of the periodic table ($n = 2$) can accommodate only eight electrons in their valence shell orbitals because they have only four valence orbitals (one 2*s* and three 2*p* orbitals). Elements in the third and higher periods ($n \geq 3$) have more than four valence orbitals and can share more than four pairs of electrons with other atoms because they have empty *d* orbitals in the same shell. Molecules formed from these elements are sometimes called hypervalent molecules.Table **10.5.1** shows the Lewis structures for two hypervalent molecules, PCl_5 and SF_6.





Table **10.5.1***: In PCl_5, the central atom phosphorus shares five pairs of electrons. In SF_6, sulfur shares six pairs of electrons.*

In some hypervalent molecules, such as IF_5 and XeF_4, some of the electrons in the outer shell of the central atom are lone pairs:



When we write the Lewis structures for these molecules, we find that we have electrons left over after filling the valence shells of the outer atoms with eight electrons. These additional electrons must be assigned to the central atom.

✔ Example **10.5.1**: Octet Rule Violations

Xenon is a noble gas, but it forms a number of stable compounds. We examined **XeF_4** earlier. What are the Lewis structures of **XeF_2** and **XeF_6**?

Solution


We can draw the Lewis structure of any covalent molecule by following the six steps discussed earlier. In this case, we can condense the last few steps, since not all of them apply.

Step 1: Calculate the number of valence electrons:

XeF_2: $8 + (2 \times 7) = 22$


XeF_6: $8 + (6 \times 7) = 50$

Step 2: Draw a skeleton joining the atoms by single bonds. **Xenon will be the central atom because fluorine cannot be a central atom:**




Step 3: Distribute the remaining electrons.

XeF_2: We place three lone pairs of electrons around each F atom, accounting for 12 electrons and giving each F atom 8 electrons. Thus, six electrons (three lone pairs) remain. These lone pairs must be placed on the Xe atom. This is acceptable because Xe atoms have empty valence shell *d* orbitals and can accommodate more than eight electrons. The Lewis structure of XeF_2 shows two bonding pairs and three lone pairs of electrons around the Xe atom:




XeF_6: We place three lone pairs of electrons around each F atom, accounting for 36 electrons. Two electrons remain, and this lone pair is placed on the Xe atom:



Exercise 10.5.1: interhalogens

The halogens form a class of compounds called the interhalogens, in which halogen atoms covalently bond to each other. Write the Lewis structures for the interhalogens $BrCl_3$ and ICl_4^-.

Answer





Expanded Valence Shell Bonding: https://youtu.be/Y4fBdOJBSHI

Summary

Most structures—especially those containing second row elements—obey the octet rule, in which every atom (except H) is surrounded by eight electrons. Exceptions to the octet rule occur for odd-electron molecules (free radicals), electron-deficient molecules, and hypervalent molecules.

10.5: Exceptions to the Octet Rule is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **7.3: Covalent Bonding** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **8.5: Drawing Lewis Structures** is licensed CC BY-NC-SA 3.0.
- **7.4: Lewis Symbols and Structures** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

10.6: Resonance Strucutres

Learning Objectives

- To understand the concept of resonance.

Resonance structures are a set of two or more Lewis Structures that collectively describe the electronic bonding a single polyatomic species including fractional bonds and fractional charges. Resonance structures are capable of describing delocalized electrons that cannot be expressed by a single Lewis formula with an integer number of covalent bonds.

Sometimes one Lewis Structure is not Enough

Sometimes, even when formal charges are considered, the bonding in some molecules or ions cannot be described by a single Lewis structure. Resonance is a way of describing delocalized electrons within certain molecules or polyatomic ions where the bonding cannot be expressed by a single Lewis formula. A molecule or ion with such delocalized electrons is represented by several contributing structures (also called resonance structures or canonical forms). Such is the case for ozone ($\mathbf{O_3}$), an allotrope of oxygen with a V-shaped structure and an O–O–O angle of 117.5°.


Ozone (O_3)

1. We know that ozone has a V-shaped structure, so one O atom is central:




2. Each O atom has 6 valence electrons, for a total of 18 valence electrons.

3. Assigning one bonding pair of electrons to each oxygen–oxygen bond gives




with 14 electrons left over.

4. If we place three lone pairs of electrons on each terminal oxygen, we obtain




and have 2 electrons left over.

5. At this point, both terminal oxygen atoms have octets of electrons. We therefore place the last 2 electrons on the central atom:




6. The central oxygen has only 6 electrons. We must convert one lone pair on a terminal oxygen atom to a bonding pair of electrons —but which one? Depending on which one we choose, we obtain either



Which is correct? In fact, neither is correct. Both predict one O–O single bond and one O=O double bond. As you will learn, if the bonds were of different types (one single and one double, for example), they would have different lengths. It turns out, however, that both O–O bond distances are identical, 127.2 pm, which is shorter than a typical O–O single bond (148 pm) and longer than the O=O double bond in O_2 (120.7 pm).

Equivalent Lewis dot structures, such as those of ozone, are called **resonance structures**. The position of the *atoms* is the same in the various resonance structures of a compound, but the position of the *electrons* is different. Double-headed arrows link the different resonance structures of a compound:




The double-headed arrow indicates that the actual electronic structure is an *average* of those shown, not that the molecule oscillates between the two structures.

> *When it is possible to write more than one equivalent resonance structure for a molecule or ion, the actual structure is the average of the resonance structures.*

The Carbonate (CO_3^{2-}) Ion


Like ozone, the electronic structure of the carbonate ion cannot be described by a single Lewis electron structure. Unlike O_3, though, the actual structure of CO_3^{2-} is an average of *three* resonance structures.

1. Because carbon is the least electronegative element, we place it in the central position:




2. Carbon has 4 valence electrons, each oxygen has 6 valence electrons, and there are 2 more for the −2 charge. This gives 4 + (3 × 6) + 2 = 24 valence electrons.

3. Six electrons are used to form three bonding pairs between the oxygen atoms and the carbon:




4. We divide the remaining 18 electrons equally among the three oxygen atoms by placing three lone pairs on each and indicating the −2 charge:




5. No electrons are left for the central atom.

6. At this point, the carbon atom has only 6 valence electrons, so we must take one lone pair from an oxygen and use it to form a carbon–oxygen double bond. In this case, however, there are *three* possible choices:



As with ozone, none of these structures describes the bonding exactly. Each predicts one carbon–oxygen double bond and two carbon–oxygen single bonds, but experimentally all C–O bond lengths are identical. We can write resonance structures (in this case, three of them) for the carbonate ion:




The actual structure is an average of these three resonance structures.


The Nitrate (NO_3^-) ion

1. Count up the valence electrons: (1*5) + (3*6) + 1(ion) = **24** electrons


2. Draw the bond connectivities:



3. Add octet electrons to the atoms bonded to the center atom:




4. Place any leftover electrons (24-24 = **0**) on the center atom:




5. Does the central atom have an octet?

- **NO**, it has 6 electrons
- Add a multiple bond (first try a double bond) to see if the central atom can achieve an octet:



6. Does the central atom have an octet?

- YES
- Are there possible resonance structures? YES



Note: We would expect that the bond lengths in the $\mathbf{NO_3^-}$ ion to be somewhat shorter than a single bond.



Example 10.6.1: Benzene

Benzene is a common organic solvent that was previously used in gasoline; it is no longer used for this purpose, however, because it is now known to be a carcinogen. The benzene molecule (C_6H_6) consists of a regular hexagon of carbon atoms, each of which is also bonded to a hydrogen atom. Use resonance structures to describe the bonding in benzene.

Given: molecular formula and molecular geometry


Asked for: resonance structures

Strategy:

A. Draw a structure for benzene illustrating the bonded atoms. Then calculate the number of valence electrons used in this drawing.
B. Subtract this number from the total number of valence electrons in benzene and then locate the remaining electrons such that each atom in the structure reaches an octet.
C. Draw the resonance structures for benzene.


Solution:

A Each hydrogen atom contributes 1 valence electron, and each carbon atom contributes 4 valence electrons, for a total of (6 × 1) + (6 × 4) = 30 valence electrons. If we place a single bonding electron pair between each pair of carbon atoms and between each carbon and a hydrogen atom, we obtain the following:



Each carbon atom in this structure has only 6 electrons and has a formal charge of +1, but we have used only 24 of the 30 valence electrons.


B If the 6 remaining electrons are uniformly distributed pairwise on alternate carbon atoms, we obtain the following:




Three carbon atoms now have an octet configuration and a formal charge of −1, while three carbon atoms have only 6 electrons and a formal charge of +1. We can convert each lone pair to a bonding electron pair, which gives each atom an octet of

electrons and a formal charge of 0, by making three C=C double bonds.

C There are, however, two ways to do this:



Each structure has alternating double and single bonds, but experimentation shows that each carbon–carbon bond in benzene is identical, with bond lengths (139.9 pm) intermediate between those typically found for a C–C single bond (154 pm) and a C=C double bond (134 pm). We can describe the bonding in benzene using the two resonance structures, but the actual electronic structure is an average of the two. The existence of multiple resonance structures for aromatic hydrocarbons like benzene is often indicated by drawing either a circle or dashed lines inside the hexagon:




Benzene

? Exercise 10.6.1: Nitrate Ion

The sodium salt of nitrite is used to relieve muscle spasms. Draw two resonance structures for the nitrite ion (NO_2^-).

Answer



Resonance structures are particularly common in oxoanions of the *p*-block elements, such as sulfate and phosphate, and in aromatic hydrocarbons, such as benzene and naphthalene.

Warning

If several reasonable resonance forms for a molecule exists, the "actual electronic structure" of the molecule will probably be intermediate between all the forms that you can draw. The classic example is benzene in Example 10.6.1. One would expect the double bonds to be shorter than the single bonds, but if once overlays the two structures, you see that one structure has a single bond where the other structure has a double bond. The best measurements that we can make of benzene do not show two bond lengths - instead, they show that the bond length is intermediate between the two resonance structures.

Resonance structures is a mechanism that allows us to use all of the possible resonance structures to try to predict what the actual form of the molecule would be. Single bonds, double bonds, triple bonds, +1 charges, -1 charges, these are our limitations in explaining the structures, and the true forms can be in between - a carbon-carbon bond could be mostly single bond with a little bit of double bond character and a partial negative charge, for example.

Summary

Some molecules have two or more chemically equivalent Lewis electron structures, called resonance structures. Resonance is a mental exercise and method within the Valence Bond Theory of bonding that describes the delocalization of electrons within molecules. These structures are written with a **double-headed arrow** between them, indicating that none of the Lewis structures accurately describes the bonding but that the actual structure is an average of the individual resonance structures. Resonance

structures are used when one Lewis structure for a single molecule cannot fully describe the bonding that takes place between neighboring atoms relative to the empirical data for the actual bond lengths between those atoms. The net sum of valid resonance structures is defined as a resonance hybrid, which represents the overall delocalization of electrons within the molecule. A molecule that has several resonance structures is more stable than one with fewer. Some resonance structures are more favorable than others.

10.6: Resonance Strucutres is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **7.3: Covalent Bonding** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **8.6: Resonance Structures** is licensed CC BY-NC-SA 3.0.

10.8: Strengths of Ionic and Covalent Bonds

Learning Objectives

- Describe the energetics of covalent and ionic bond formation and breakage
- Use the Born-Haber cycle to compute lattice energies for ionic compounds
- Use average covalent bond energies to estimate enthalpies of reaction

A bond's strength describes how strongly each atom is joined to another atom, and therefore how much energy is required to break the bond between the two atoms. In this section, you will learn about the bond strength of covalent bonds, and then compare that to the strength of ionic bonds, which is related to the lattice energy of a compound.

Bond Strength: Covalent Bonds

Stable molecules exist because covalent bonds hold the atoms together. We measure the strength of a covalent bond by the energy required to break it, that is, the energy necessary to separate the bonded atoms. Separating any pair of bonded atoms requires energy; *the stronger a bond, the greater the energy required to break it.* The energy required to break a specific covalent bond in one mole of gaseous molecules is called the bond energy or the bond dissociation energy. The bond energy for a diatomic molecule, D_{X-Y}, is defined as the standard enthalpy change for the endothermic reaction:


$$XY_{(g)} \longrightarrow X_{(g)} + Y_{(g)} \quad D_{X-Y} = \Delta H° \tag{10.8.1}$$

For example, the bond energy of the pure covalent H–H bond, Δ_{H-H}, is 436 kJ per mole of H–H bonds broken:

$$H_{2(g)} \longrightarrow 2H_{(g)} \quad D_{H-H} = \Delta H° = 436kJ \tag{10.8.2}$$

> *Breaking a bond **always** require energy to be added to the molecule. Correspondingly, making a bond **always** releases energy.*

Molecules with three or more atoms have two or more bonds. The sum of all bond energies in such a molecule is equal to the standard enthalpy change for the endothermic reaction that breaks all the bonds in the molecule. For example, the sum of the four C–H bond energies in CH_4, 1660 kJ, is equal to the standard enthalpy change of the reaction:



A reaction is shown with Lewis structures. The first structure shows a carbon atom single bonded to four hydrogen atoms with the symbol, "(g)" written next to it. A right-facing arrow points to the letter "C" and the symbol "(g)," which is followed by a plus sign. Next is the number 4, the letter "H" and the symbol, "(g)." To the right of this equation is another equation: capital delta H superscript degree symbol equals 1660 k J.

The average C–H bond energy, D_{C-H}, is 1660/4 = 415 kJ/mol because there are four moles of C–H bonds broken per mole of the reaction. Although the four C–H bonds are equivalent in the original molecule, they do not each require the same energy to break; once the first bond is broken (which requires 439 kJ/mol), the remaining bonds are easier to break. The 415 kJ/mol value is the average, not the exact value required to break any one bond.

The strength of a bond between two atoms increases as the number of electron pairs in the bond increases. Generally, as the bond strength increases, the bond length decreases. Thus, we find that triple bonds are stronger and shorter than double bonds between the same two atoms; likewise, double bonds are stronger and shorter than single bonds between the same two atoms. Average bond energies for some common bonds appear in Table **10.8.2**, and a comparison of bond lengths and bond strengths for some common bonds appears in Table **10.8.2**. When one atom bonds to various atoms in a group, the bond strength typically decreases as we move down the group. For example, C–F is 439 kJ/mol, C–Cl is 330 kJ/mol, and C–Br is 275 kJ/mol.

Table **10.8.1**: Bond Energies (kJ/mol)

Bond	Bond Energy	Bond	Bond Energy	Bond	Bond Energy
H–H	436	C–S	260	F–Cl	255
H–C	415	C–Cl	330	F–Br	235
H–N	390	C–Br	275	Si–Si	230
H–O	464	C–I	240	Si–P	215
H–F	569	N–N	160	Si–S	225
H–Si	395	N = N	418	Si–Cl	359
H–P	320	N ≡ N	946	Si–Br	290
H–S	340	N–O	200	Si–I	215
H–Cl	432	N–F	270	P–P	215
H–Br	370	N–P	210	P–S	230
H–I	295	N–Cl	200	P–Cl	330
C–C	345	N–Br	245	P–Br	270
C = C	611	O–O	140	P–I	215
C ≡ C	837	O = O	498	S–S	215
C–N	290	O–F	160	S–Cl	250
C = N	615	O–Si	370	S–Br	215
C ≡ N	891	O–P	350	Cl–Cl	243
C–O	350	O–Cl	205	Cl–Br	220
C = O	741	O–I	200	Cl–I	210
C ≡ O	1080	F–F	160	Br–Br	190
C–F	439	F–Si	540	Br–I	180
C–Si	360	F–P	489	I–I	150
C–P	265	F–S	285		

Table **10.8.2**: Average Bond Lengths and Bond Energies for Some Common Bonds

Bond	Bond Length (Å)	Bond Energy (kJ/mol)
C–C	1.54	345
C = C	1.34	611
C ≡ C	1.20	837
C–N	1.43	290
C = N	1.38	615
C ≡ N	1.16	891
C–O	1.43	350
C = O	1.23	741
C ≡ O	1.13	1080

We can use bond energies to calculate approximate enthalpy changes for reactions where enthalpies of formation are not available. Calculations of this type will also tell us whether a reaction is exothermic or endothermic.

- An **exothermic reaction** (ΔH negative, heat produced) results when the bonds in the products are stronger than the bonds in the reactants.
- An **endothermic reaction** (ΔH positive, heat absorbed) results when the bonds in the products are weaker than those in the reactants.

The enthalpy change, ΔH, for a chemical reaction is approximately equal to the sum of the energy required to break all bonds in the reactants (energy "in", positive sign) plus the energy released when all bonds are formed in the products (energy "out," negative sign). This can be expressed mathematically in the following way:

$$\Delta H = \sum D_{\text{bonds broken}} - \sum D_{\text{bonds formed}} \tag{10.8.3}$$

In this expression, the symbol Σ means "the sum of" and D represents the bond energy in kilojoules per mole, which is always a positive number. The bond energy is obtained from a table and will depend on whether the particular bond is a single, double, or triple bond. Thus, in calculating enthalpies in this manner, it is important that we consider the bonding in all reactants and products. Because D values are typically averages for one type of bond in many different molecules, this calculation provides a rough estimate, not an exact value, for the enthalpy of reaction.

Consider the following reaction:

$$\mathrm{H_{2(g)} + Cl_{2(g)} \longrightarrow 2\,HCl_{(g)}} \tag{10.8.4}$$

or

$$\mathrm{H{-}H_{(g)} + Cl{-}Cl_{(g)} \longrightarrow 2\,H{-}Cl_{(g)}} \tag{10.8.5}$$

To form two moles of HCl, one mole of H–H bonds and one mole of Cl–Cl bonds must be broken. The energy required to break these bonds is the sum of the bond energy of the H–H bond (436 kJ/mol) and the Cl–Cl bond (243 kJ/mol). During the reaction, two moles of H–Cl bonds are formed (bond energy = 432 kJ/mol), releasing 2 × 432 kJ; or 864 kJ. Because the bonds in the products are stronger than those in the reactants, the reaction releases more energy than it consumes:

$$\begin{aligned}\Delta H &= \sum \mathrm{D_{bonds\ broken}} - \sum \mathrm{D_{bonds\ formed}} \\ &= [\mathrm{D_{H-H}} + \mathrm{D_{Cl-Cl}}] - 2\mathrm{D_{H-Cl}} \\ &= [436 + 243] - 2(432) = -185\ \mathrm{kJ}\end{aligned}$$

This excess energy is released as heat, so the reaction is exothermic. Table T2 gives a value for the standard molar enthalpy of formation of HCl(g), ΔH_f°, of –92.307 kJ/mol. Twice that value is –184.6 kJ, which agrees well with the answer obtained earlier for the formation of two moles of HCl.


Example 10.8.1: Using Bond Energies to Approximate Enthalpy Changes

Methanol, CH_3OH, may be an excellent alternative fuel. The high-temperature reaction of steam and carbon produces a mixture of the gases carbon monoxide, CO, and hydrogen, H_2, from which methanol can be produced. Using the bond energies in Table **10.8.2**, calculate the approximate enthalpy change, ΔH, for the reaction here:

$$CO_{(g)} + 2H2_{(g)} \longrightarrow CH_3OH_{(g)}$$

Solution

First, we need to write the Lewis structures of the reactants and the products:



A set of Lewis diagrams show a chemical reaction. The first structure shows a carbon atom with a lone pair of electrons triple bonded to an oxygen with a lone pair of electrons. To the right of this structure is a plus sign, then the number 2 followed by a hydrogen atom single bonded to a hydrogen atom. To the right of this structure is a right-facing arrow followed by a hydrogen atom single bonded to a carbon atom that is single bonded to two hydrogen atoms and an oxygen atom with two lone pairs of electrons. The oxygen atom is also single bonded to a hydrogen atom.

From this, we see that ΔH for this reaction involves the energy required to break a C–O triple bond and two H–H single bonds, as well as the energy produced by the formation of three C–H single bonds, a C–O single bond, and an O–H single bond. We can express this as follows (via Equation 10.8.3):

$$\Delta H = \sum D_{bonds\ broken} - \sum D_{bonds\ formed}$$
$$\Delta H = [\mathrm{D_{C\equiv O}} + 2(\mathrm{D_{H-H}})] - [3(\mathrm{D_{C-H}}) + \mathrm{D_{C-O}} + \mathrm{D_{O-H}}]$$

Using the bond energy values in Table **10.8.2**, we obtain:

$$\begin{aligned}\Delta H &= [1080 + 2(436)] - [3(415) + 350 + 464] \\ &= -107\ k\,\mathrm{J}\end{aligned}$$


We can compare this value to the value calculated based on ΔH_f° data from Appendix G:

$$\begin{aligned}\Delta H &= [\Delta H_f^\circ \mathrm{CH_3OH}(g)] - [\Delta H_f^\circ \mathrm{CO}(g) + 2 \times \Delta H_f^\circ \mathrm{H_2}] \\ &= [-201.0] - [-110.52 + 2 \times 0] \\ &= -90.5\ \mathrm{kJ}\end{aligned}$$

Note that there is a fairly significant gap between the values calculated using the two different methods. This occurs because D values are the *average* of different bond strengths; therefore, they often give only rough agreement with other data.

Exercise 10.8.1

Ethyl alcohol, CH_3CH_2OH, was one of the first organic chemicals deliberately synthesized by humans. It has many uses in industry, and it is the alcohol contained in alcoholic beverages. It can be obtained by the fermentation of sugar or synthesized by the hydration of ethylene in the following reaction:



A set of Lewis structures show a chemical reaction. The first structure shows two carbon atoms that are double bonded together and are each single bonded to two hydrogen atoms. This structure is followed by a plus sign, then an oxygen atom with two lone pairs of electrons single bonded to two hydrogen atoms. A right-facing arrow leads to a carbon atom single bonded to three hydrogen atoms and a second carbon atom. The second carbon atom is single bonded to two hydrogen atoms and an oxygen atom with two lone pairs of electrons. The oxygen atom is single bonded to a hydrogen atom as well.

Using the bond energies in Table **10.8.2**, calculate an approximate enthalpy change, Δ*H*, for this reaction.

Answer

–35 kJ

Ionic Bond Strength and Lattice Energy

An ionic compound is stable because of the electrostatic attraction between its positive and negative ions. The lattice energy of a compound is a measure of the strength of this attraction. The lattice energy ($\Delta H_{lattice}$) of an ionic compound is defined as the energy required to separate one mole of the solid into its component gaseous ions. For the ionic solid MX, the lattice energy is the enthalpy change of the process:

$$MX_{(s)} \longrightarrow Mn^{+}_{(g)} + X^{n-}_{(g)} \quad \Delta H_{lattice} \tag{10.8.6}$$

Note that we are using the convention where the ionic solid is separated into ions, so our lattice energies will be endothermic (positive values). Some texts use the equivalent but opposite convention, defining lattice energy as the energy released when separate ions combine to form a lattice and giving negative (exothermic) values. Thus, if you are looking up lattice energies in another reference, be certain to check which definition is being used. In both cases, a larger magnitude for lattice energy indicates a more stable ionic compound. For sodium chloride, $\Delta H_{\text{lattice}}$ = 769 kJ. Thus, it requires 769 kJ to separate one mole of solid NaCl into gaseous Na^+ and Cl^- ions. When one mole each of gaseous Na^+ and Cl^- ions form solid NaCl, 769 kJ of heat is released.

The lattice energy $\Delta H_{lattice}$ of an ionic crystal can be expressed by the following equation (derived from Coulomb's law, governing the forces between electric charges):

$$\Delta H_{lattice} = \frac{C(Z^+)(Z^-)}{R_o} \tag{10.8.7}$$

in which

- **C** is a constant that depends on the type of crystal structure;
- Z^+ and Z^- are the charges on the ions; and
- R_o is the interionic distance (the sum of the radii of the positive and negative ions).

Thus, the lattice energy of an ionic crystal increases rapidly as the charges of the ions increase and the sizes of the ions decrease. When all other parameters are kept constant, doubling the charge of both the cation and anion quadruples the lattice energy. For example, the lattice energy of LiF (Z^+ and Z^- = 1) is 1023 kJ/mol, whereas that of MgO (Z^+ and Z^- = 2) is 3900 kJ/mol (R_o is nearly the same—about 200 pm for both compounds).

Different interatomic distances produce different lattice energies. For example, we can compare the lattice energy of MgF_2 (2957 kJ/mol) to that of MgI_2 (2327 kJ/mol) to observe the effect on lattice energy of the smaller ionic size of F^- as compared to I^-.

✔ Example 10.8.2: Lattice Energy Comparisons

The precious gem ruby is aluminum oxide, Al_2O_3, containing traces of Cr^{3+}. The compound Al_2Se_3 is used in the fabrication of some semiconductor devices. Which has the larger lattice energy, Al_2O_3 or Al_2Se_3?

Solution

In these two ionic compounds, the charges Z^+ and Z^- are the same, so the difference in lattice energy will mainly depend upon R_o. The O^{2-} ion is smaller than the Se^{2-} ion. Thus, Al_2O_3 would have a shorter interionic distance than Al_2Se_3, and Al_2O_3 would have the larger lattice energy.

? Exercise 10.8.2

Zinc oxide, ZnO, is a very effective sunscreen. How would the lattice energy of ZnO compare to that of NaCl?

Answer

ZnO would have the larger lattice energy because the Z values of both the cation and the anion in ZnO are greater, and the interionic distance of ZnO is smaller than that of NaCl.

The Born-Haber Cycle

It is not possible to measure lattice energies directly. However, the lattice energy can be calculated using the equation given in the previous section or by using a thermochemical cycle. The Born-Haber cycle is an application of Hess's law that breaks down the formation of an ionic solid into a series of individual steps:

- ΔH_f°, the standard enthalpy of formation of the compound
- IE, the ionization energy of the metal
- EA, the electron affinity of the nonmetal
- ΔH_s°, the enthalpy of sublimation of the metal
- D, the bond dissociation energy of the nonmetal
- $\Delta H_{lattice}$, the lattice energy of the compound

Figure 10.8.1 diagrams the Born-Haber cycle for the formation of solid cesium fluoride.




Figure **10.8.1**: The Born-Haber cycle shows the relative energies of each step involved in the formation of an ionic solid from the necessary elements in their reference states.

A diagram is shown. An upward facing arrow is drawn to the far left of the chart and is labeled “H increasing.” A horizontal line is drawn at the bottom of the chart. A downward-facing, vertical arrow to the left side of this line is labeled, “Overall change.” Beside this arrow is another label, “capital delta H subscript f, equals negative 553.5 k J per mol, (Enthalpy of formation).” Three horizontal lines, one above the other, and all above the bottom line, are labeled, from bottom to top, as: “C s (s), plus sign, one half F subscript 2, (g),” “C s (g), plus sign, one half F subscript 2, (g),” and “C s, superscript positive sign, (g), plus sign, one half F subscript 2, (g).” Each of these lines is connected by an upward-facing vertical arrow. Each arrow is labeled, “capital delta H subscript 1, equals 76.5 k J per mol, (Enthalpy of sublimation),” “capital delta H subscript 2, equals 375.7 k J per mol, (ionization energy),” and “capital delta H subscript 3 equals 79.4 k J / mol (one half dissociation energy).” Another horizontal line is drawn in the center top portion of the diagram and is labeled “C s, superscript positive sign, (g), plus sign, F, (g).” There is one more horizontal line drawn to the right of the overall diagram and located halfway down the image. An arrow connects the top line to this line and is labeled, “capital delta H equals negative 328.2 k J / mol (electron affinity).” The line is labeled, “C s superscript positive sign (g) plus F superscript negative sign (g).” The arrow connecting this line to the bottom line is labeled, “negative capital delta H subscript lattice equals negative 756.9 k J / mol.” The arrow points to a label on the bottom line which reads, “C s F (s).”

We begin with the elements in their most common states, Cs(s) and $F_2(g)$. The ΔH_s° represents the conversion of solid cesium into a gas, and then the ionization energy converts the gaseous cesium atoms into cations. In the next step, we account for the energy required to break the F–F bond to produce fluorine atoms. Converting one mole of fluorine atoms into fluoride ions is an exothermic process, so this step gives off energy (the electron affinity) and is shown as decreasing along the y-axis. We now have one mole of Cs cations and one mole of F anions. These ions combine to produce solid cesium fluoride. The enthalpy change in this step is the negative of the lattice energy, so it is also an exothermic quantity. The total energy involved in this conversion is equal to the experimentally determined enthalpy of formation, ΔH_f°, of the compound from its elements. In this case, the overall change is exothermic.

Hess’s law can also be used to show the relationship between the enthalpies of the individual steps and the enthalpy of formation. Table **10.8.3** shows this for cesium fluoride, CsF.

Table **10.8.3**: Enthalpies of Select Transitions

Enthalpy of sublimation of Cs(s)	$\mathrm{Cs}(s) \longrightarrow \mathrm{Cs}(g) \quad \Delta H = \Delta H_s^\circ = 77\ \mathrm{kJ/mol}$
One-half of the bond energy of F_2	$\frac{1}{2}\mathrm{F_2}(g) \longrightarrow \mathrm{F}(g) \quad \Delta H = \frac{1}{2}D = 79\ \mathrm{kJ/mol}$
Ionization energy of Cs(g)	$\mathrm{Cs}(g) \longrightarrow \mathrm{Cs^+}(g) + \mathrm{e^-} \quad \Delta H = IE = 376\ k\mathrm{J/mol}$
Negative of the electron affinity of F	$\mathrm{F}(g) + \mathrm{e^-} \longrightarrow \mathrm{F^-}(g) \quad \Delta H = -EA = -328\ k\mathrm{J/mol}$
Negative of the lattice energy of CsF(s)	$\mathrm{Cs^+}(g) + \mathrm{F^-}(g) \longrightarrow \mathrm{CsF}(s) \quad \Delta H = -\Delta H_{\text{lattice}} = ?$
Enthalpy of formation of CsF(s), add steps 1–5	$\Delta H = \Delta H_f^\circ = \Delta H_s^\circ + \frac{1}{2}D + IE + (-EA) + (-\Delta H_{\text{lattice}})$ $\mathrm{Cs}(s) + \frac{1}{2}\mathrm{F_2}(g) \longrightarrow \mathrm{CsF}(s) = -554\ k\mathrm{J/mol}$

Thus, the lattice energy can be calculated from other values. For cesium chloride, using this data, the lattice energy is:

$$\Delta H_{\text{lattice}} = (411 + 109 + 122 + 496 + 368)\ \text{kJ} = 770\ \text{kJ}$$

The Born-Haber cycle may also be used to calculate any one of the other quantities in the equation for lattice energy, provided that the remainder is known. For example, if the relevant enthalpy of sublimation ΔH_s°, ionization energy (IE), bond dissociation enthalpy (D), lattice energy $\Delta H_{\text{lattice}}$, and standard enthalpy of formation ΔH_f° are known, the Born-Haber cycle can be used to determine the electron affinity of an atom.

Lattice energies calculated for ionic compounds are typically much larger than bond dissociation energies measured for covalent bonds. Whereas lattice energies typically fall in the range of 600–4000 kJ/mol (some even higher), covalent bond dissociation energies are typically between 150–400 kJ/mol for single bonds. Keep in mind, however, that these are not directly comparable values. For ionic compounds, lattice energies are associated with many interactions, as cations and anions pack together in an extended lattice. For covalent bonds, the bond dissociation energy is associated with the interaction of just two atoms.

Summary

The strength of a covalent bond is measured by its bond dissociation energy, that is, the amount of energy required to break that particular bond in a mole of molecules. Multiple bonds are stronger than single bonds between the same atoms. The enthalpy of a reaction can be estimated based on the energy input required to break bonds and the energy released when new bonds are formed. For ionic bonds, the lattice energy is the energy required to separate one mole of a compound into its gas phase ions. Lattice energy increases for ions with higher charges and shorter distances between ions. Lattice energies are often calculated using the Born-Haber cycle, a thermochemical cycle including all of the energetic steps involved in converting elements into an ionic compound.

Key Equations

- Bond energy for a diatomic molecule: $\text{XY}(g) \longrightarrow \text{X}(g) + \text{Y}(g) \quad D_{\text{X–Y}} = \Delta H^\circ$
- Enthalpy change: $\Delta H = \Sigma D_{\text{bonds broken}} - \Sigma D_{\text{bonds formed}}$
- Lattice energy for a solid MX: $\text{MX}(s) \longrightarrow \text{M}^{n+}(g) + \text{X}^{n-}(g) \quad \Delta H_{\text{lattice}}$
- Lattice energy for an ionic crystal: $\Delta H_{\text{lattice}} = \dfrac{C(Z^+)(Z^-)}{R_o}$

Footnotes

1. This question is taken from the Chemistry Advanced Placement Examination and is used with the permission of the Educational Testing Service.

Glossary

bond energy
(also, bond dissociation energy) energy required to break a covalent bond in a gaseous substance

Born-Haber cycle
thermochemical cycle relating the various energetic steps involved in the formation of an ionic solid from the relevant elements

lattice energy ($\Delta H_{\text{lattice}}$)
energy required to separate one mole of an ionic solid into its component gaseous ions

---

10.8: Strengths of Ionic and Covalent Bonds is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **7.6: Strengths of Ionic and Covalent Bonds** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

10.9: End of Chapter Problems

1. Describe the differences in behavior between NaOH and CH_3OH in aqueous solution. Which solution would be a better conductor of electricity? Explain your reasoning.
2. What is the relationship between the strength of the electrostatic attraction between oppositely charged ions and the distance between the ions? How does the strength of the electrostatic interactions change as the size of the ions increases?
3. Which will result in the release of more energy: the interaction of a gaseous sodium ion with a gaseous oxide ion or the interaction of a gaseous sodium ion with a gaseous bromide ion? Why?

Answer

The interaction of a sodium ion and an oxide ion. The electrostatic attraction energy between ions of opposite charge is directly proportional to the charge on each ion (Q_1 and Q_2 in Equation 9.1). Thus, more energy is released as the charge on the ions increases (assuming the internuclear distance does not increase substantially). A sodium ion has a +1 charge; an oxide ion, a −2 charge; and a bromide ion, a −1 charge. For the interaction of a sodium ion with an oxide ion, $Q_1 = +1$ and $Q_2 = −2$, whereas for the interaction of a sodium ion with a bromide ion, $Q_1 = +1$ and $Q_2 = −1$. The larger value of $Q_1 \times Q_2$ for the sodium ion–oxide ion interaction means it will release more energy.


4. Which will result in the release of more energy: the interaction of a gaseous chloride ion with a gaseous sodium ion or a gaseous potassium ion? Explain your answer.
5. What are the predominant interactions when oppositely charged ions are
   a. far apart?
   b. at internuclear distances close to r_0?
   c. very close together (at a distance that is *less* than the sum of the ionic radii)?
6. Several factors contribute to the stability of ionic compounds. Describe one type of interaction that *destabilizes* ionic compounds. Describe the interactions that *stabilize* ionic compounds.
7. What is the relationship between the electrostatic attractive energy between charged particles and the distance between the particles?
8. How does the energy of the electrostatic interaction between ions with charges +1 and −1 compare to the interaction between ions with charges +3 and −1 if the distance between the ions is the same in both cases? How does this compare with the magnitude of the interaction between ions with +3 and −3 charges?

Answer

According to Equation 9.1, in the first case $Q_1Q_2 = (+1)(−1) = −1$; in the second case, $Q_1Q_2 = (+3)(−1) = −3$. Thus, E will be three times larger for the +3/−1 ions. For +3/−3 ions, $Q_1Q_2 = (+3)(−3) = −9$, so E will be nine times larger than for the +1/−1 ions.

9. How many grams of gaseous $MgCl_2$ are needed to give the same electrostatic attractive energy as 0.5 mol of gaseous LiCl? The ionic radii are $Li^+ = 76$ pm, $Mg^{+2} = 72$ pm, and $Cl^− = 181$ pm.
10. Sketch a diagram showing the relationship between potential energy and internuclear distance (from $r = \infty$ to $r = 0$) for the interaction of a bromide ion and a potassium ion to form gaseous KBr. Explain why the energy of the system increases as the distance between the ions decreases from $r = r_0$ to $r = 0$.

Answer



At $r < r_0$, the energy of the system increases due to electron–electron repulsions between the overlapping electron distributions on *adjacent* ions. At very short internuclear distances, electrostatic repulsions between adjacent *nuclei* also become important.

11. Calculate the magnitude of the electrostatic attractive energy (E, in kilojoules) for 85.0 g of gaseous SrS ion pairs. The observed internuclear distance in the gas phase is 244.05 pm.
12. What is the electrostatic attractive energy (E, in kilojoules) for 130 g of gaseous HgI_2? The internuclear distance is 255.3 pm.
13. Why is it incorrect to speak of a molecule of solid NaCl?

Answer

NaCl consists of discrete ions arranged in a crystal lattice, not covalently bonded molecules.

14. What information can you use to predict whether a bond between two atoms is covalent or ionic?
15. Predict which of the following compounds are ionic and which are covalent, based on the location of their constituent atoms in the periodic table:
    a. Cl_2CO
    b. MnO
    c. NCl_3
    d. $CoBr_2$
    e. K_2S
    f. CO
    g. CaF_2
    h. HI
    i. CaO
    j. IBr
    k. CO_2

Answer

ionic: (b), (d), (e), (g), and (i); covalent: (a), (c), (f), (h), (j), and (k)

16. Explain the difference between a nonpolar covalent bond, a polar covalent bond, and an ionic bond.
17. From its position in the periodic table, determine which atom in each pair is more electronegative:
    a. Br or Cl
    b. N or O
    c. S or O
    d. P or S
    e. Si or N
    f. Ba or P
    g. N or K

Answer

Cl; O; O; S; N; P; N

18. From its position in the periodic table, determine which atom in each pair is more electronegative:
    a. N or P
    b. N or Ge
    c. S or F
    d. Cl or S
    e. H or C
    f. Se or P
    g. C or Si

19. From their positions in the periodic table, arrange the atoms in each of the following series in order of increasing electronegativity:
    a. C, F, H, N, O
    b. Br, Cl, F, H, I
    c. F, H, O, P, S
    d. Al, H, Na, O, P
    e. Ba, H, N, O, As

Answer

H, C, N, O, F; H, I, Br, Cl, F; H, P, S, O, F; Na, Al, H, P, O; Ba, H, As, N, O

20. From their positions in the periodic table, arrange the atoms in each of the following series in order of increasing electronegativity:
    a. As, H, N, P, Sb
    b. Cl, H, P, S, Si
    c. Br, Cl, Ge, H, Sr
    d. Ca, H, K, N, Si
    e. Cl, Cs, Ge, H, Sr

21. Which atoms can bond to sulfur so as to produce a positive partial charge on the sulfur atom?

    N, O, F, and Cl

22. Which is the most polar bond?
    a. C–C
    b. C–H
    c. N–H
    d. O–H
    e. Se–H

23. Identify the more polar bond in each of the following pairs of bonds:
    a. HF or HCl
    b. NO or CO
    c. SH or OH
    d. PCl or SCl
    e. CH or NH
    f. SO or PO
    g. CN or NN

Answer

HF; CO; OH; PCl; NH; PO; CN

24. Which of the following molecules or ions contain polar bonds?

a. O_3
b. S_8
c. O_2^{2-}
d. NO_3^-
e. CO_2
f. H_2S
g. BH_4^-

25. Write the Lewis symbols for each of the following ions:
    a. As^{3-}
    b. I^-
    c. Be^{2+}
    d. O^{2-}
    e. Ga^{3+}
    f. Li^+
    g. N^{3-}

Answer

eight electrons:



eight electrons:



no electrons

Be^{2+};

eight electrons:



no electrons

Ga^{3+};

no electrons

Li^+;

eight electrons:




26. Many monatomic ions are found in seawater, including the ions formed from the following list of elements. Write the Lewis symbols for the monatomic ions formed from the following elements:
    a. Cl
    b. Na
    c. Mg
    d. Ca
    e. K

f. Br
g. Sr
h. F

27. Write the Lewis symbols of the ions in each of the following ionic compounds and the Lewis symbols of the atom from which they are formed:
    a. MgS
    b. Al_2O_3
    c. $GaCl_3$
    d. K_2O
    e. Li_3N
    f. KF


Answer

(a)




;

(b)




;

(c)



;

(d)




;


(e)





;


(f)




28. In the Lewis structures listed here, M and X represent various elements in the third period of the periodic table. Write the formula of each compound using the chemical symbols of each element:
    a. 

    b. 

    c. 

    d. 

29. Write the Lewis structure for the diatomic molecule P_2, an unstable form of phosphorus found in high-temperature phosphorus vapor.



30. Write Lewis structures for the following:
    a. H_2
    b. HBr
    c. PCl_3
    d. SF_2
    e. H_2CCH_2
    f. HNNH
    g. H_2CNH


h. NO^-
i. N_2
j. CO
k. CN^-

31. Write Lewis structures for the following:

a. O_2
b. H_2CO
c. AsF_3
d. ClNO
e. $SiCl_4$
f. H_3O^+
g. $\mathbf{NH_4^+}$
h. (h) $\mathbf{BF_4^-}$
i. (i) HCCH
j. (j) ClCN
k. (k) $\mathbf{C_2^{2+}}$


Answer

(a)



A Lewis structure shows two oxygen atoms double bonded together, and each has two lone pairs of electrons.

In this case, the Lewis structure is inadequate to depict the fact that experimental studies have shown two unpaired electrons in each oxygen molecule.


(b)


A Lewis structure shows a carbon atom that is single bonded to two hydrogen atoms and double bonded to an oxygen atom. The oxygen atom has two lone pairs of electrons. ;

(c)



A Lewis structure shows an arsenic atom single bonded to three fluorine atoms. Each fluorine atom has a lone pair of electrons. ;

(d)



A Lewis structure shows a nitrogen atom with a lone pair of electrons single bonded to a chlorine atom that has three lone pairs of electrons. The nitrogen is also double bonded to an oxygen which has two lone pairs of electrons.

;


(e)


A Lewis structure shows a silicon atom that is single bonded to four chlorine atoms. Each chlorine atom has three lone pairs of electrons. ;


(f)


A Lewis structure shows an oxygen atom with a lone pair of electrons single bonded to three hydrogen atoms. The structure is surrounded by brackets with a superscripted positive sign. ;


(g)


A Lewis structure shows a nitrogen atom single bonded to four hydrogen atoms. The structure is surrounded by brackets with a superscripted positive sign. ;


(h)


A Lewis structure shows a boron atom single bonded to four fluorine atoms. Each fluorine atom has three lone pairs of electrons. The structure is surrounded by brackets with a superscripted negative sign. ;


(i)


A Lewis structure shows two carbon atoms that are triple bonded together. Each carbon is also single bonded to a hydrogen atom. ;

(j)


A Lewis structure shows a carbon atom that is triple bonded to a nitrogen atom that has one lone pair of electrons. The carbon is also single bonded to a chlorine atom that has three lone pairs of electrons. ;


(k)




32. Write Lewis structures for the following:
    a. ClF_3
    b. PCl_5
    c. BF_3
    d. $\mathbf{PF_6^-}$
33. Write Lewis structures for the following:
    a. SeF_6
    b. XeF_4
    c. $\mathbf{SeCl_3^+}$
    d. Cl_2BBCl_2 (contains a B–B bond)

Answer


SeF_6:




XeF_4:



$\mathbf{SeCl_3^+}$:



Cl_2BBCl_2:




34. Write Lewis structures for:
    a. $\mathbf{PO_4^{3-}}$
    b. $\mathbf{ICl_4^-}$
    c. $\mathbf{SO_3^{2-}}$
    d. HONO
35. Correct the following statement: “The bonds in solid $PbCl_2$ are ionic; the bond in a HCl molecule is covalent. Thus, all of the valence electrons in $PbCl_2$ are located on the Cl^- ions, and all of the valence electrons in a HCl molecule are shared between the H and Cl atoms.”

Answer

Two valence electrons per Pb atom are transferred to Cl atoms; the resulting Pb^{2+} ion has a $6s^2$ valence shell configuration. Two of the valence electrons in the HCl molecule are shared, and the other six are located on the Cl atom as lone pairs of electrons.


36. Write Lewis structures for the following molecules or ions:
    a. SbH_3
    b. XeF_2
    c. Se_8 (a cyclic molecule with a ring of eight Se atoms)
37. Methanol, H_3COH, is used as the fuel in some race cars. Ethanol, C_2H_5OH, is used extensively as motor fuel in Brazil. Both methanol and ethanol produce CO_2 and H_2O when they burn. Write the chemical equations for these combustion reactions using Lewis structures instead of chemical formulas.

Answer


Two reactions are shown using Lewis structures. The top reaction shows a carbon atom, single bonded to three hydrogen atoms and single bonded to an oxygen atom with two lone pairs of electrons. The oxygen atom is also bonded to a hydrogen atom. This is followed by a plus sign and the number one point five, followed by two oxygen atoms bonded together with a double bond and each with two lone pairs of electrons. A right-facing arrow leads to a carbon atom that is double bonded to two oxygen atoms, each of which has two lone pairs of electrons. This structure is followed by a plus sign, a number two, and a structure made up of an oxygen with two lone pairs of electrons single bonded to two hydrogen atoms. The bottom reaction shows a carbon atom, single bonded to three hydrogen atoms and single bonded to another carbon atom. The second carbon atom is single bonded to two hydrogen atoms and one oxygen atom with two lone pairs of electrons. The oxygen atom is also bonded to a hydrogen atom. This is followed by a plus sign and the number three, followed by two oxygen atoms bonded together with a double bond. Each oxygen atom has two lone pairs of electrons. A right-facing arrow leads to a number two and a carbon atom that is double bonded to two oxygen atoms, each of which has two lone pairs of electrons. This structure is followed by a plus sign, a number three, and a structure made up of an oxygen with two lone pairs of electrons single bonded to two hydrogen atoms.


38. Many planets in our solar system contain organic chemicals including methane (CH_4) and traces of ethylene (C_2H_4), ethane (C_2H_6), propyne (H_3CCCH), and diacetylene (HCCCCH). Write the Lewis structures for each of these molecules.
39. Carbon tetrachloride was formerly used in fire extinguishers for electrical fires. It is no longer used for this purpose because of the formation of the toxic gas phosgene, Cl_2CO. Write the Lewis structures for carbon tetrachloride and phosgene.

Answer



Two Lewis structures are shown. The left depicts a carbon atom single bonded to four chlorine atoms, each with three lone pairs of electrons. The right shows a carbon atom double bonded to an oxygen atom that has two lone pairs of electrons. The carbon atom is also single bonded to two chlorine atoms, each of which has three lone pairs of electrons.

40. Identify the atoms that correspond to each of the following electron configurations. Then, write the Lewis symbol for the common ion formed from each atom:
    a. $1s^2 2s^2 2p^5$
    b. $1s^2 2s^2 2p^6 3s^2$
    c. $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10}$
    d. $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10} 4p^4$
    e. $1s^2 2s^2 2p^6 3s^2 3p^6 4s^2 3d^{10} 4p^1$
41. The arrangement of atoms in several biologically important molecules is given here. Complete the Lewis structures of these molecules by adding multiple bonds and lone pairs. Do not add any more atoms.


the amino acid serine:


A Lewis structure is shown. A nitrogen atom is single bonded to two hydrogen atoms and a carbon atom. The carbon atom is single bonded to a hydrogen atom and two other carbon atoms. One of these carbon atoms is single bonded to two hydrogen atoms and an oxygen atom. The oxygen atom is bonded to a hydrogen atom. The other carbon atom is single bonded to two oxygen atoms, one of which is bonded to a hydrogen atom.


urea:


A Lewis structure is shown. A nitrogen atom is single bonded to two hydrogen atoms and a carbon atom. The carbon atom is single bonded to an oxygen atom and another nitrogen atom. That nitrogen atom is then single bonded to two hydrogen atoms.


pyruvic acid:


A Lewis structure is shown. A carbon atom is single bonded to three hydrogen atoms and another carbon atom. The second carbon atom is single bonded to an oxygen atom and a third carbon atom. This carbon is then single bonded to two oxygen atoms, one of which is single bonded to a hydrogen atom.

uracil:



A Lewis hexagonal ring structure is shown. From the top of the ring (moving clockwise), three carbon atoms, one nitrogen atom, a carbon atom, and a nitrogen atom are single bonded to each another. The top carbon atom is single bonded to an oxygen atom. The second and third carbons and the nitrogen atom are each single bonded to a hydrogen atom. The next carbon atom is single bonded to an oxygen atom, and the last nitrogen atom is single bonded to a hydrogen atom.

carbonic acid:


A Lewis structure is shown. A carbon atom is single bonded to three oxygen atoms. Two of those oxygen atoms are each single bonded to a hydrogen atom.


Answer

(a)


A Lewis structure is shown. A nitrogen atom is single bonded to two hydrogen atoms and a carbon atom. The carbon atom is single bonded to a hydrogen atom and two other carbon atoms. One of these carbon atoms is single bonded to two hydrogen atoms and an oxygen atom. The oxygen atom is bonded to a hydrogen atom. The other carbon is single bonded to two oxygen atoms, one of which is bonded to a hydrogen atom. The oxygen atoms have two lone pairs of electron dots, and the nitrogen atom has one lone pair of electron dots.


;

(b)


A Lewis structure is shown. A nitrogen atom is single bonded to two hydrogen atoms and a carbon atom. The carbon atom is single bonded to an oxygen atom and one nitrogen atom. That nitrogen atom is then single bonded to two hydrogen atoms. The oxygen atom has two lone pairs of electron dots, and the nitrogen atoms have one lone pair of electron dots each.


;

(c)


A Lewis structure is shown. A carbon atom is single bonded to three hydrogen atoms and a carbon atom. The carbon atom is single bonded to an oxygen atom and a third carbon atom. This carbon is then single bonded to two oxygen atoms, one of which is single bonded to a hydrogen atom. Each oxygen atom has two lone pairs of electron dots.


;

(d)



A Lewis hexagonal ring structure is shown. From the top of the ring, three carbon atoms, one nitrogen atom, a carbon atom and a nitrogen atom are single bonded to one another. The top carbon is single bonded to an oxygen, the second and third carbons and the nitrogen atom are each single bonded to a hydrogen atom. The next carbon is single bonded to an oxygen atom and the last nitrogen is single bonded to a hydrogen atom. The oxygen atoms have two lone pairs of electron dots, and the nitrogen atoms have one lone pair of electron dots.

;

(e)


A Lewis structure is shown. A carbon atom is single bonded to three oxygen atoms. Two of those oxygen atoms are each single bonded to a hydrogen atom. Each oxygen atom has two lone pairs of electron dots.

42. A compound with a molar mass of about 28 g/mol contains 85.7% carbon and 14.3% hydrogen by mass. Write the Lewis structure for a molecule of the compound.
43. A compound with a molar mass of about 42 g/mol contains 85.7% carbon and 14.3% hydrogen by mass. Write the Lewis structure for a molecule of the compound.



A Lewis structure is shown. A carbon atom is single bonded to three hydrogen atoms and another carbon atom. The second carbon atom is double bonded to another carbon atom and single bonded to a hydrogen atom. The last carbon is single bonded to two hydrogen atoms.

44. Two arrangements of atoms are possible for a compound with a molar mass of about 45 g/mol that contains 52.2% C, 13.1% H, and 34.7% O by mass. Write the Lewis structures for the two molecules.
45. How are single, double, and triple bonds similar? How do they differ?


Answer

Each bond includes a sharing of electrons between atoms. Two electrons are shared in a single bond; four electrons are shared in a double bond; and six electrons are shared in a triple bond.

46. Write resonance forms that describe the distribution of electrons in each of these molecules or ions.
    a. selenium dioxide, OSeO
    b. nitrate ion, NO_3^-
    c. nitric acid, HNO_3 (N is bonded to an OH group and two O atoms)
    d. benzene, C_6H_6:
47. Write resonance forms that describe the distribution of electrons in each of these molecules or ions.
    a. sulfur dioxide, SO_2
    b. carbonate ion, CO_3^{2-}
    c. hydrogen carbonate ion, HCO_3^- (C is bonded to an OH group and two O atoms)
    d. pyridine:



A Lewis structure depicts a hexagonal ring composed of five carbon atoms and one nitrogen atom. Each carbon atom is single bonded to a hydrogen atom.

e. the allyl ion:


A Lewis structure shows a carbon atom single bonded to two hydrogen atoms and a second carbon atom. The second carbon atom is single bonded to a hydrogen atom and a third carbon atom. The third carbon atom is single bonded to two hydrogen atoms. The whole structure is surrounded by brackets, and there is a superscripted negative sign.


Answer

(a)


Two Lewis structures are shown with a double-headed arrow in between. The left structure shows a sulfur atom with a lone pair of electrons single bonded to the left to an oxygen atom with three lone pairs of electrons. The sulfur atom is also double bonded on the right to an oxygen atom with two lone pairs of electrons. The right structure depicts the same atoms, but this time the double bond is between the left oxygen and the sulfur atom. The lone pairs of electrons have also shifted to account for the change of bond types. The sulfur atom in the right structures, also has a third electron dot below it.


;

(b)


Three Lewis structures are shown, with double-headed arrows in between, each surrounded by brackets and a superscripted two negative sign. The left structure depicts a carbon atom bonded to three oxygen atoms. It is single bonded to two of these oxygen atoms, each of which has three lone pairs of electrons, and double bonded to the third, which has two lone pairs of electrons. The double bond is located between the bottom oxygen and the carbon. The central and right structures are the same as the first, but the position of the double bonded oxygen has moved to the left oxygen in the right structure while the central structure only has single bonds. The lone pairs of electrons change to correspond with the bonds as well.


;

(c)


Two Lewis structures are shown, with a double-headed arrow in between, each surrounded by brackets and a superscripted negative sign. The left structure depicts a carbon atom bonded to three oxygen atoms. It is single bonded to one of these oxygen atoms, which has three lone pairs of electrons, and double bonded to the other two, which have two lone pairs of electrons. One of the double bonded oxygen atoms also has a single bond to a hydrogen atom. The right structure is the same as the first, but there is only one double bonded oxygen. The oxygen with the single bonded hydrogen now has a single bond to the carbon atom. The lone pairs of electrons have also changed to correspond with the bonds.


;

(d)



Two Lewis structures are shown with a double-headed arrow in between. The left structure depicts a hexagonal ring composed of five carbon atoms, each single bonded to a hydrogen atom, and one nitrogen atom that has a lone pair of electrons. The ring has alternating single and double bonds. The right structure is the same as the first, but each double bond has rotated to a new position.

;


(e)


Two Lewis structures are shown with a double-headed arrow in between. The left structure shows a carbon atom single bonded to two hydrogen atoms and a second carbon atom. The second carbon atom is single bonded to a hydrogen atom and double bonded to a third carbon atom. The third carbon atom is single bonded to two hydrogen atoms. The whole structure is surrounded by brackets and a superscripted negative sign. The right structure shows a carbon atom single bonded to two hydrogen atoms and double bonded to a second carbon atom. The second carbon atom is single bonded to a hydrogen atom and a third carbon atom. The third carbon atom is single bonded to two hydrogen atoms. The whole structure is surrounded by brackets and a superscripted negative sign.

48. Write the resonance forms of ozone, O_3, the component of the upper atmosphere that protects the Earth from ultraviolet radiation.
49. Sodium nitrite, which has been used to preserve bacon and other meats, is an ionic compound. Write the resonance forms of the nitrite ion, $\mathbf{NO_2^-}$.


Two pairs of Lewis structures are shown with a double-headed arrow in between each pair. The left structure of the first pair shows a nitrogen atom with one lone pair of electrons single bonded to an oxygen atom with three lone pairs of electrons. It is also double bonded to an oxygen with two lone pairs of electrons. The right image of this pair depicts the mirror image of the left. Both images are surrounded by brackets and a superscripted negative sign. They are labeled, “For N O subscript two superscript negative sign.” The left structure of the second pair shows an oxygen atom with one lone pair of electrons single bonded to an oxygen atom with three lone pairs of electrons. It is also double bonded to an oxygen atom with two lone pairs of electrons. The right structure appears as a mirror image of the left. These structures are labeled, “For O subscript three.”


50. In terms of the bonds present, explain why acetic acid, CH_3CO_2H, contains two distinct types of carbon-oxygen bonds, whereas the acetate ion, formed by loss of a hydrogen ion from acetic acid, only contains one type of carbon-oxygen bond. The skeleton structures of these species are shown:


Two Lewis structures are shown with a double headed arrow in between. The left structure shows a carbon atom single bonded to three hydrogen atoms and a second carbon atom. The second carbon is single bonded to two oxygen atoms. One of the oxygen atoms is single bonded to a hydrogen atom. The right structure, surrounded by brackets and with a superscripted negative sign, depicts a carbon atom single bonded to three hydrogen atoms and a second carbon atom. The second carbon atom is single bonded to two oxygen atoms.


51. Write the Lewis structures for the following, and include resonance structures where appropriate. Indicate which has the strongest carbon-oxygen bond.
    a. CO_2
    b. CO

Answer

(a)


This structure shows a carbon atom double bonded to two oxygen atoms, each of which has two lone pairs of electrons.

(b)


The right structure of this pair shows a carbon atom with one lone pair of electrons triple bonded to an oxygen with one lone pair of electrons.

CO has the strongest carbon-oxygen bond because there is a triple bond joining C and O. CO_2 has double bonds.

52. Toothpastes containing sodium hydrogen carbonate (sodium bicarbonate) and hydrogen peroxide are widely used. Write Lewis structures for the hydrogen carbonate ion and hydrogen peroxide molecule, with resonance forms where appropriate.
53. Determine the formal charge of each element in the following:
    a. HCl
    b. CF_4

c. PCl_3
d. PF_5

Answer

H: 0, Cl: 0; C: 0, F: 0; P: 0, Cl 0; P: 0, F: 0

54. Determine the formal charge of each element in the following:
    a. H_3O^+
    b. $\mathbf{SO_4^{2-}}$
    c. NH_3
    d. $\mathbf{O_2^{2-}}$
    e. H_2O_2

55. Calculate the formal charge of chlorine in the molecules Cl_2, $BeCl_2$, and ClF_5.

Answer


Cl in Cl_2: 0; Cl in $BeCl_2$: 0; Cl in ClF_5: 0

56. Calculate the formal charge of each element in the following compounds and ions:
    a. F_2CO
    b. NO^-
    c. $\mathbf{BF_4^-}$
    d. $\mathbf{SnCl_3^-}$
    e. H_2CCH_2
    f. ClF_3
    g. SeF_6
    h. $\mathbf{PO_4^{3-}}$


57. Draw all possible resonance structures for each of these compounds. Determine the formal charge on each atom in each of the resonance structures:
    a. O_3
    b. SO_2
    c. $\mathbf{NO_2^-}$
    d. $\mathbf{NO_3^-}$

Answer


(a)


Two Lewis structures are shown with a double-headed arrow in between. The left structure shows an oxygen atom with one lone pair of electrons single bonded to an oxygen atom with three lone pairs of electrons. It is also double bonded to an oxygen atom with two lone pairs of electrons. The symbols and numbers below this structure read, “(0), (positive 1), (negative 1).” The phrase, “Formal charge,” and a right-facing arrow lie to the left of this structure. The right structure appears as a mirror image of the left and the symbols and numbers below this structure read, “(negative 1), (positive 1), (0).”


(b)


Two Lewis structures are shown, with a double-headed arrow in between. The left structure shows a sulfur atom with one lone pair of electrons single bonded to an oxygen atom with three lone pairs of electrons. The sulfur atom also double bonded to an oxygen atom with two lone pairs of electrons. The symbols and numbers below this structure read, “(negative 1), (positive 1), (0).” The right structure appears as a mirror image of the left and the symbols and numbers below this structure read, “(0), (positive 1), (negative 1).”

(c)


[Two Lewis structures are shown, with brackets surrounding each with a superscripted negative sign and a double ended arrow in between. The left structure shows a nitrogen atom with one lone pair of electrons single bonded to an oxygen atom with three lone pairs of electrons and double bonded to an oxygen atom with two lone pairs of electrons. The symbols and numbers below this structure read “open parenthesis, 0, close parenthesis, open parenthesis, 0, close parenthesis, open parenthesis, negative 1, close parenthesis. The right structure appears as a mirror image of the left and the symbols and numbers below this structure read “open parenthesis, negative 1, close parenthesis, open parenthesis, 0, close parenthesis, open parenthesis, 0, close parenthesis.]

(d)


[Three Lewis structures are shown, with brackets surrounding each with a superscripted negative sign and a double ended arrow in between. The left structure shows a nitrogen atom single bonded to two oxygen atoms, each with three lone pairs of electrons and double bonded to an oxygen atom with two lone pairs of electrons. The single bonded oxygen atoms are labeled, from the top of the structure and going clockwise, “open parenthesis, negative 1, close parenthesis, open parenthesis, positive 1, close parenthesis”. The symbols and numbers below this structure read “open parenthesis, 0, close parenthesis, open parenthesis, negative 1, close parenthesis. The middle structure shows a nitrogen atom single bonded to two oxygen atoms, each with three lone pairs of electrons, one of which is labeled “open parenthesis, positive 1, close parenthesis” and double bonded to an oxygen atom with two lone pairs of electrons labeled “open parenthesis, 0, close parenthesis”. The symbols and numbers below this structure read “open parenthesis, negative 1, close parenthesis, open parenthesis, negative 1, close parenthesis. The right structure shows a nitrogen atom single bonded to two oxygen atoms, each with three lone pairs of electrons and double bonded to an oxygen atom with two lone pairs of electrons. One of the single bonded oxygen atoms is labeled, “open parenthesis, negative 1, close parenthesis while the double bonded oxygen is labeled, “open parenthesis, positive 1, close parenthesis”. The symbols and numbers below this structure read “open parenthesis, negative 1, close parenthesis” and “open parenthesis, 0, close parenthesis”.]


58. Based on formal charge considerations, which of the following would likely be the correct arrangement of atoms in nitrosyl chloride: ClNO or ClON?
59. Based on formal charge considerations, which of the following would likely be the correct arrangement of atoms in hypochlorous acid: HOCl or OClH?

Answer

HOCl

60. Based on formal charge considerations, which of the following would likely be the correct arrangement of atoms in sulfur dioxide: OSO or SOO?
61. Draw the structure of hydroxylamine, H_3NO, and assign formal charges; look up the structure. Is the actual structure consistent with the formal charges?


    The structure that gives zero formal charges is consistent with the actual structure:

    
    A Lewis structure shows a nitrogen atom with one lone pair of electrons single bonded to two hydrogen atoms and an oxygen atom which has two lone pairs of electrons. The oxygen atom is single bonded to a hydrogen atom.


62. Iodine forms a series of fluorides (listed here). Write Lewis structures for each of the four compounds and determine the formal charge of the iodine atom in each molecule:
    a. IF
    b. IF_3
    c. IF_5
    d. IF_7
63. Write the Lewis structure and chemical formula of the compound with a molar mass of about 70 g/mol that contains 19.7% nitrogen and 80.3% fluorine by mass, and determine the formal charge of the atoms in this compound.

Answer

NF_3;



A Lewis structure shows a nitrogen atom with one lone pair of electrons single bonded to three fluorine atoms, each with three lone pairs of electrons.

64. Which of the following structures would we expect for nitrous acid? Determine the formal charges:

    
    Two Lewis structures are shown, with the word “or” in between. The left structure shows a nitrogen atom single bonded to an oxygen atom with three lone pairs of electrons. It is also single bonded to a hydrogen atom and double bonded to an oxygen atom with two lone pairs of electrons. The right structure shows a hydrogen atom single bonded to an oxygen atom with two lone pairs of electrons. The oxygen atom is single bonded to a nitrogen atom which is double bonded to an oxygen atom with two lone pairs of electrons.

65. Sulfuric acid is the industrial chemical produced in greatest quantity worldwide. About 90 billion pounds are produced each year in the United States alone. Write the Lewis structure for sulfuric acid, H_2SO_4, which has two oxygen atoms and two OH groups bonded to the sulfur.

Answer


A Lewis structure shows a hydrogen atom single bonded to an oxygen atom with two lone pairs of electrons. The oxygen atom is single bonded to a sulfur atom. The sulfur atom is double bonded to two oxygen atoms, each of which have three lone pairs of electrons, and single bonded to an oxygen atom with two lone pairs of electrons. This oxygen atom is single bonded to a hydrogen atom.

66. Which bond in each of the following pairs of bonds is the strongest?
    a. C–C or $\mathbf{C=C}$
    b. C–N or $\mathbf{C\equiv N}$
    c. $\mathbf{C\equiv O}$ or $\mathbf{C=O}$

d. H–F or H–Cl
e. C–H or O–H
f. C–N or C–O

67. Using the bond energies in Table, determine the approximate enthalpy change for each of the following reactions:
    a. $\mathrm{H_2}(g) + \mathrm{Br_2}(g) \longrightarrow 2\,\mathrm{HBr}(g)$
    b. $\mathrm{CH_4}(g) + \mathrm{I_2}(g) \longrightarrow \mathrm{CH_3I}(g) + \mathrm{HI}(g)$
    c. (c) $\mathrm{C_2H_4}(g) + 3\,\mathrm{O_2}(g) \longrightarrow 2\,\mathrm{CO_2}(g) + 2\,\mathrm{H_2O}(g)$
68. Using the bond energies in Table, determine the approximate enthalpy change for each of the following reactions:
    a. $\mathrm{H_2}(g) + \mathrm{Br_2}(g) \longrightarrow 2\,\mathrm{HBr}(g)$
    b. $\mathrm{CH_4}(g) + \mathrm{I_2}(g) \longrightarrow \mathrm{CH_3I}(g) + \mathrm{HI}(g)$
    c. $\mathrm{C_2H_4}(g) + 3\,\mathrm{O_2}(g) \longrightarrow 2\,\mathrm{CO_2}(g) + 2\,\mathrm{H_2O}(g)$


Answer

(a) −114 kJ;

(b) 30 kJ;

(c) −1055 kJ

69. Using the bond energies in Table, determine the approximate enthalpy change for each of the following reactions:
    a. $\mathrm{Cl_2}(g) + 3\,\mathrm{F_2}(g) \longrightarrow 2\,\mathrm{ClF_3}(g)$
    b. $\mathrm{H_2C{=}CH_2}(g) + \mathrm{H_2}(g) \longrightarrow \mathrm{H_3CCH_3}(g)$
    c. (c) $2\,\mathrm{C_2H_6}(g) + 7\,\mathrm{O_2}(g) \longrightarrow 4\,\mathrm{CO_2}(g) + 6\,\mathrm{H_2O}(g)$
70. When a molecule can form two different structures, the structure with the stronger bonds is usually the more stable form. Use bond energies to predict the correct structure of the hydroxylamine molecule:


Two Lewis structures are shows with the word “or” written in between them. The left structure shows a nitrogen atom with one lone pair of electrons single bonded to two hydrogen atoms. It is also bonded to an oxygen atom with two lone pairs of electrons. The oxygen atom is bonded to a hydrogen atom. The right structure shows a nitrogen atom single bonded to three hydrogen atoms and an oxygen atom with three lone pairs of electrons.

Answer

The greater bond energy is in the figure on the left. It is the more stable form.

71. How does the bond energy of HCl differ from the standard enthalpy of formation of HCl(g)?
72. Using the standard enthalpy of formation data in Appendix G, show how the standard enthalpy of formation of HCl(g) can be used to determine the bond energy.

Answer

$$\begin{aligned}
\mathrm{HCl}(g) &\longrightarrow \tfrac{1}{2}\mathrm{H_2}(g) + \tfrac{1}{2}\mathrm{Cl_2}(g) && \Delta H_1^\circ = -\Delta H_{f[\mathrm{HCl}(g)]}^\circ \\
\tfrac{1}{2}\mathrm{H_2}(g) &\longrightarrow \mathrm{H}(g) && \Delta H_2^\circ = \Delta H_{f[\mathrm{H}(g)]}^\circ \\
\tfrac{1}{2}\mathrm{Cl_2}(g) &\longrightarrow \mathrm{Cl}(g) && \Delta H_3^\circ = \Delta H_{f[\mathrm{Cl}(g)]}^\circ \\
\hline
\mathrm{HCl}(g) &\longrightarrow \mathrm{H}(g) + \mathrm{Cl}(g) && \Delta H_{298}^\circ = \Delta H_1^\circ + \Delta H_2^\circ + \Delta H_3^\circ
\end{aligned}$$


$$\begin{aligned}
D_{\mathrm{HCl}} = \Delta H_{298}^\circ &= \Delta H_{f[\mathrm{HCl}(g)]}^\circ + \Delta H_{f[\mathrm{H}(g)]}^\circ + \Delta H_{f[\mathrm{Cl}(g)]}^\circ && (10.9.1)\\
&= -(-92.307\ \mathrm{kJ}) + 217.97\ \mathrm{kJ} + 121.3\ \mathrm{kJ} && (10.9.2)\\
&= 431.6\ \mathrm{kJ} && (10.9.3)
\end{aligned}$$

73. Using the standard enthalpy of formation data in Appendix G, calculate the bond energy of the carbon-sulfur double bond in CS_2.
74. Using the standard enthalpy of formation data in Appendix G, determine which bond is stronger: the S–F bond in $SF_4(g)$ or in $SF_6(g)$?


Answer

The S–F bond in SF_4 is stronger.

75. Using the standard enthalpy of formation data in Appendix G, determine which bond is stronger: the P–Cl bond in $PCl_3(g)$ or in $PCl_5(g)$?
76. Complete the following Lewis structure by adding bonds (not atoms), and then indicate the longest bond:



A Lewis structure is shown that is missing its bonds. It shows a horizontal row of six carbon atoms, equally spaced. Three hydrogen atoms are drawn around the first carbon, two around the second, one above the fifth, and two by the sixth.

Answer


A Lewis structure is shown. A carbon atom that is single bonded to three hydrogen atoms is bonded to a second carbon atom. The second carbon atom is single bonded to two hydrogen atoms. The second carbon atom is single bonded to a third carbon atom that is triple bonded to a fourth carbon atom and single bonded to a fifth carbon atom. The fifth carbon atom is single bonded to a hydrogen atom and double bonded to a sixth carbon atom that is single bonded to two hydrogen atoms.

The C–C single bonds are longest.

77. Use the bond energy to calculate an approximate value of ΔH for the following reaction. Which is the more stable form of FNO_2?


Two Lewis structures are shown with a right-facing arrow in between. The left structure shows a nitrogen atom double bonded to an oxygen atom with two lone pairs of electrons. It is also bonded to a fluorine atom and another oxygen atom, each with three lone pairs of electrons. The right structure shows an oxygen atom with two lone pairs of electrons double bonded to a nitrogen atom with one lone pair of electrons. This nitrogen atom is single bonded to an oxygen with two lone pairs of electrons. The oxygen atom is single bonded to a fluorine atom with three lone pairs of electrons.

78. Use principles of atomic structure to answer each of the following:[1]

    a. The radius of the Ca atom is 197 pm; the radius of the Ca^{2+} ion is 99 pm. Account for the difference.
    b. The lattice energy of CaO(*s*) is –3460 kJ/mol; the lattice energy of K_2O is –2240 kJ/mol. Account for the difference.
    c. Given these ionization values, explain the difference between Ca and K with regard to their first and second ionization energies.

Element	First Ionization Energy (kJ/mol)	Second Ionization Energy (kJ/mol)
K	419	3050
Ca	590	1140

    d. The first ionization energy of Mg is 738 kJ/mol and that of Al is 578 kJ/mol. Account for this difference.

Answer

When two electrons are removed from the valence shell, the Ca radius loses the outermost energy level and reverts to the lower $n = 3$ level, which is much smaller in radius. The +2 charge on calcium pulls the oxygen much closer compared with K, thereby increasing the lattice energy relative to a less charged ion. (c) Removal of the 4*s* electron in Ca requires more energy than removal of the 4*s* electron in K because of the stronger attraction of the nucleus and the extra energy required to break the pairing of the electrons. The second ionization energy for K requires that an electron be removed from a lower energy level, where the attraction is much stronger from the nucleus for the electron. In addition, energy is required to unpair two electrons in a full orbital. For Ca, the second ionization potential requires removing only a lone electron in the exposed outer energy level. In Al, the removed electron is relatively unprotected and unpaired in a *p* orbital. The higher energy for Mg mainly reflects the unpairing of the 2*s* electron.

79. The lattice energy of LiF is 1023 kJ/mol, and the Li–F distance is 200.8 pm. NaF crystallizes in the same structure as LiF but with a Na–F distance of 231 pm. Which of the following values most closely approximates the lattice energy of NaF: 510, 890, 1023, 1175, or 4090 kJ/mol? Explain your choice.
80. For which of the following substances is the least energy required to convert one mole of the solid into separate ions?

    a. MgO
    b. SrO
    c. (c) KF
    d. CsF
    e. MgF_2

81. The reaction of a metal, M, with a halogen, X_2, proceeds by an exothermic reaction as indicated by this equation: $M(s) + X_2(g) \longrightarrow MX_2(s)$. For each of the following, indicate which option will make the reaction more exothermic. Explain your answers.
    a. a large radius vs. a small radius for M^{+2}
    b. a high ionization energy vs. a low ionization energy for M
    c. an increasing bond energy for the halogen
    d. a decreasing electron affinity for the halogen
    e. an increasing size of the anion formed by the halogen
82. The lattice energy of LiF is 1023 kJ/mol, and the Li–F distance is 201 pm. MgO crystallizes in the same structure as LiF but with a Mg–O distance of 205 pm. Which of the following values most closely approximates the lattice energy of MgO: 256 kJ/mol, 512 kJ/mol, 1023 kJ/mol, 2046 kJ/mol, or 4008 kJ/mol? Explain your choice.

Answer

4008 kJ/mol; both ions in MgO have twice the charge of the ions in LiF; the bond length is very similar and both have the same structure; a quadrupling of the energy is expected based on the equation for lattice energy

83. Which compound in each of the following pairs has the larger lattice energy? Note: Mg^{2+} and Li^+ have similar radii; O^{2-} and F^- have similar radii. Explain your choices.
    a. MgO or MgSe
    b. LiF or MgO
    c. (c) Li_2O or LiCl
    d. Li_2Se or MgO
84. Which compound in each of the following pairs has the larger lattice energy? Note: Ba^{2+} and K^+ have similar radii; S^{2-} and Cl^- have similar radii. Explain your choices.
    a. K_2O or Na_2O
    b. K_2S or BaS
    c. (c) KCl or BaS
    d. BaS or $BaCl_2$

Answer

Na_2O; Na^+ has a smaller radius than K^+; BaS; Ba has a larger charge than K; (c) BaS; Ba and S have larger charges; BaS; S has a larger charge

85. Which of the following compounds requires the most energy to convert one mole of the solid into separate ions?
    a. MgO
    b. SrO
    c. KF
    d. CsF
    e. MgF_2
86. Which of the following compounds requires the most energy to convert one mole of the solid into separate ions?
    a. K_2S
    b. K_2O
    c. CaS
    d. Cs_2S
    e. CaO
87. The lattice energy of KF is 794 kJ/mol, and the interionic distance is 269 pm. The Na–F distance in NaF, which has the same structure as KF, is 231 pm. Which of the following values is the closest approximation of the lattice energy of NaF: 682 kJ/mol, 794 kJ/mol, 924 kJ/mol, 1588 kJ/mol, or 3175 kJ/mol? Explain your answer.

10.9: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

11: Theories of Chemical Bonding

11.1: VSEPR Theory
11.2: Polarity of Molecules
11.3: Valence Bond theory
11.4: Hybrid Atomic Orbitals
11.5: Overlap of Hybrid Orbitals
11.6: Molecular Orbital Theory
11.7: End of Chapter Problems

11: Theories of Chemical Bonding is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

11.1: VSEPR Theory

Learning Objectives

- Predict the structures of small molecules using valence shell electron pair repulsion (VSEPR) theory
- Explain the concepts of polar covalent bonds and molecular polarity
- Assess the polarity of a molecule based on its bonding and structure

Thus far, we have used two-dimensional Lewis structures to represent molecules. However, molecular structure is actually three-dimensional, and it is important to be able to describe molecular bonds in terms of their distances, angles, and relative arrangements in space (Figure **11.1.1**). A bond angle is the angle between any two bonds that include a common atom, usually measured in degrees. A bond distance (or bond length) is the distance between the nuclei of two bonded atoms along the straight line joining the nuclei. Bond distances are measured in Ångstroms (1 Å = 10^{-10} m) or picometers (1 pm = 10^{-12} m, 100 pm = 1 Å).




Figure **11.1.1**: Bond distances (lengths) and angles are shown for the formaldehyde molecule, H_2CO.

VSEPR Theory

Valence shell electron-pair repulsion theory (VSEPR theory) enables us to predict the molecular structure, including approximate bond angles around a central atom, of a molecule from an examination of the number of bonds and lone electron pairs in its Lewis structure. The VSEPR model assumes that electron pairs in the valence shell of a central atom will adopt an arrangement that minimizes repulsions between these electron pairs by maximizing the distance between them. The electrons in the valence shell of a central atom form either bonding pairs of electrons, located primarily between bonded atoms, or lone pairs. The electrostatic repulsion of these electrons is reduced when the various regions of high electron density assume positions as far from each other as possible.

VSEPR theory predicts the arrangement of electron pairs around each central atom and, usually, the correct arrangement of atoms in a molecule. We should understand, however, that the theory only considers electron-pair repulsions. Other interactions, such as nuclear-nuclear repulsions and nuclear-electron attractions, are also involved in the final arrangement that atoms adopt in a particular molecular structure.

As a simple example of VSEPR theory, let us predict the structure of a gaseous BeF_2 molecule. The Lewis structure of BeF_2 (Figure **11.1.2**) shows only two electron pairs around the central beryllium atom. With two bonds and no lone pairs of electrons on the central atom, the bonds are as far apart as possible, and the electrostatic repulsion between these regions of high electron density is reduced to a minimum when they are on opposite sides of the central atom. The bond angle is 180° (Figure **11.1.2**).




Figure **11.1.2**: The BeF_2 molecule adopts a linear structure in which the two bonds are as far apart as possible, on opposite sides of the Be atom.

Figure **11.1.3** illustrates this and other electron-pair geometries that minimize the repulsions among regions of high electron density (bonds and/or lone pairs). Two regions of electron density around a central atom in a molecule form a linear geometry; three

regions form a trigonal planar geometry; four regions form a tetrahedral geometry; five regions form a trigonal bipyramidal geometry; and six regions form an octahedral geometry.










Number of regions	Two regions of high electron density (bonds and/or unshared pairs)	Three regions of high electron density (bonds and/or unshared pairs)	Four regions of high electron density (bonds and/or unshared pairs)	Five regions of high electron density (bonds and/or unshared pairs)	Six regions of high electron density (bonds and/or unshared pairs)
Spatial arrangement					
Line-dash-wedge notation					
Electron pair geometry	Linear; 180° angle	Trigonal planar; all angles 120°	Tetrahedral; all angles 109.5°	Trigonal bipyramidal; angles of 90° or 120° An attached atom may be equatorial (in the plane of the triangle) or axial (above or below the plane of the triangle).	Octahedral; all angles 90° or 180°

Figure **11.1.3**: The basic electron-pair geometries predicted by VSEPR theory maximize the space around any region of electron density (bonds or lone pairs).

Electron-pair Geometry versus Molecular Structure

It is important to note that electron-pair geometry around a central atom is *not* the same thing as its molecular structure. The electron-pair geometries shown in Figure **11.1.3** describe all regions where electrons are located, bonds as well as lone pairs. Molecular structure describes the location of the *atoms*, not the electrons.

We differentiate between these two situations by naming the geometry that includes *all* electron pairs the electron-pair geometry. The structure that includes only the placement of the atoms in the molecule is called the molecular structure. The electron-pair geometries will be the same as the molecular structures when there are no lone electron pairs around the central atom, but they will be different when there are lone pairs present on the central atom.




Figure **11.1.4**: The molecular structure of the methane molecule, CH_4, is shown with a tetrahedral arrangement of the hydrogen atoms. VSEPR structures like this one are often drawn using the wedge and dash notation, in which solid lines represent bonds in the plane of the page, solid wedges represent bonds coming up out of the plane, and dashed lines represent bonds going down into the plane.

For example, the methane molecule, CH_4, which is the major component of natural gas, has four bonding pairs of electrons around the central carbon atom; the electron-pair geometry is tetrahedral, as is the molecular structure (Figure **11.1.4**). On the other hand,

the ammonia molecule, NH_3, also has four electron pairs associated with the nitrogen atom, and thus has a tetrahedral electron-pair geometry. One of these regions, however, is a lone pair, which is not included in the molecular structure, and this lone pair influences the shape of the molecule (Figure **11.1.5**).




Figure **11.1.5**: (a) The electron-pair geometry for the ammonia molecule is tetrahedral with one lone pair and three single bonds. (b) The trigonal pyramidal molecular structure is determined from the electron-pair geometry. (c) The actual bond angles deviate slightly from the idealized angles because the lone pair takes up a larger region of space than do the single bonds, causing the HNH angle to be slightly smaller than 109.5°.

Small distortions from the ideal angles in Figure **11.1.5** can result from differences in repulsion between various regions of electron density. VSEPR theory predicts these distortions by establishing an order of repulsions and an order of the amount of space occupied by different kinds of electron pairs. The order of electron-pair repulsions from greatest to least repulsion is:

lone pair-lone pair > lone pair-bonding pair > bonding pair-bonding pair

This order of repulsions determines the amount of space occupied by different regions of electrons. A lone pair of electrons occupies a larger region of space than the electrons in a triple bond; in turn, electrons in a triple bond occupy more space than those in a double bond, and so on. The order of sizes from largest to smallest is:

lone pair > triple bond > double bond > single bond

Consider formaldehyde, H_2CO, which is used as a preservative for biological and anatomical specimens. This molecule has regions of high electron density that consist of two single bonds and one double bond. The basic geometry is trigonal planar with 120° bond angles, but we see that the double bond causes slightly larger angles (121°), and the angle between the single bonds is slightly smaller (118°).

In the ammonia molecule, the three hydrogen atoms attached to the central nitrogen are not arranged in a flat, trigonal planar molecular structure, but rather in a three-dimensional trigonal pyramid (Figure **11.1.6**) with the nitrogen atom at the apex and the three hydrogen atoms forming the base. The ideal bond angles in a trigonal pyramid are based on the tetrahedral electron pair geometry. Again, there are slight deviations from the ideal because lone pairs occupy larger regions of space than do bonding electrons. The H–N–H bond angles in NH_3 are slightly smaller than the 109.5° angle in a regular tetrahedron (Figure **11.1.6**) because the lone pair-bonding pair repulsion is greater than the bonding pair-bonding pair repulsion. The ideal molecular structures are predicted based on the electron-pair geometries for various combinations of lone pairs and bonding pairs.











Number of electron pairs	Electron pair geometries: 0 lone pair	1 lone pair	2 lone pairs	3 lone pairs	4 lone pairs
2	 Linear				
3	 Trigonal planar	 Bent or angular			
4	 Tetrahedral	 Trigonal pyramid	 Bent or angular		
5	 Trigonal bipyramid	 Sawhorse or seesaw	 T-shape	 Linear	
6	 Octahedral	 Square pyramid	 Square planar	 T-shape	 Linear

Figure **11.1.6**: The molecular structures are identical to the electron-pair geometries when there are no lone pairs present (first column). For a particular number of electron pairs (row), the molecular structures for one or more lone pairs are determined based on modifications of the corresponding electron-pair geometry.

According to VSEPR theory, the terminal atom locations (Xs in Figure **11.1.7**) are equivalent within the linear, trigonal planar, and tetrahedral electron-pair geometries (the first three rows of the table). It does not matter which X is replaced with a lone pair because the molecules can be rotated to convert positions. For trigonal bipyramidal electron-pair geometries, however, there are two distinct X positions (Figure **11.1.7**a): an axial position (if we hold a model of a trigonal bipyramid by the two axial positions, we have an axis around which we can rotate the model) and an equatorial position (three positions form an equator around the middle of the molecule). The axial position is surrounded by bond angles of 90°, whereas the equatorial position has more space available because of the 120° bond angles. In a trigonal bipyramidal electron-pair geometry, lone pairs always occupy equatorial positions because these more spacious positions can more easily accommodate the larger lone pairs.

Theoretically, we can come up with three possible arrangements for the three bonds and two lone pairs for the ClF_3 molecule (Figure **11.1.7**). The stable structure is the one that puts the lone pairs in equatorial locations, giving a T-shaped molecular structure.




Figure **11.1.7**: (a) In a trigonal bipyramid, the two axial positions are located directly across from one another, whereas the three equatorial positions are located in a triangular arrangement. (b–d) The two lone pairs (red lines) in ClF_3 have several possible arrangements, but the T-shaped molecular structure (b) is the one actually observed, consistent with the larger lone pairs both occupying equatorial positions.

When a central atom has two lone electron pairs and four bonding regions, we have an octahedral electron-pair geometry. The two lone pairs are on opposite sides of the octahedron (180° apart), giving a square planar molecular structure that minimizes lone pair-lone pair repulsions.

Predicting Electron Pair Geometry and Molecular Structure

The following procedure uses VSEPR theory to determine the electron pair geometries and the molecular structures:

1. Write the Lewis structure of the molecule or polyatomic ion.
2. Count the number of regions of electron density (lone pairs and bonds) around the central atom. A single, double, or triple bond counts as one region of electron density.
3. Identify the electron-pair geometry based on the number of regions of electron density: linear, trigonal planar, tetrahedral, trigonal bipyramidal, or octahedral (Figure **11.1.7**, first column).
4. Use the number of lone pairs to determine the molecular structure (Figure **11.1.7**). If more than one arrangement of lone pairs and chemical bonds is possible, choose the one that will minimize repulsions, remembering that lone pairs occupy more space than multiple bonds, which occupy more space than single bonds. In trigonal bipyramidal arrangements, repulsion is minimized when every lone pair is in an equatorial position. In an octahedral arrangement with two lone pairs, repulsion is minimized when the lone pairs are on opposite sides of the central atom.

The following examples illustrate the use of VSEPR theory to predict the molecular structure of molecules or ions that have no lone pairs of electrons. In this case, the molecular structure is identical to the electron pair geometry.


Example 11.1.1: Predicting Electron-pair Geometry and Molecular Structure

Predict the electron-pair geometry and molecular structure for each of the following:

a. carbon dioxide, CO_2, a molecule produced by the combustion of fossil fuels
b. boron trichloride, BCl_3, an important industrial chemical


Solution

(a) We write the Lewis structure of CO_2 as:




This shows us two regions of high electron density around the carbon atom—each double bond counts as one region, and there are no lone pairs on the carbon atom. Using VSEPR theory, we predict that the two regions of electron density arrange themselves on opposite sides of the central atom with a bond angle of 180°. The electron-pair geometry and molecular structure are identical, and CO_2 molecules are linear.

(b) We write the Lewis structure of BCl_3 as:



Thus we see that BCl_3 contains three bonds, and there are no lone pairs of electrons on boron. The arrangement of three regions of high electron density gives a trigonal planar electron-pair geometry. The B–Cl bonds lie in a plane with 120° angles between them. BCl_3 also has a trigonal planar molecular structure.



The electron-pair geometry and molecular structure of BCl_3 are both trigonal planar. Note that the VSEPR geometry indicates the correct bond angles (120°), unlike the Lewis structure shown above.

? Exercise 11.1.1

Carbonate, CO_3^{2-}, is a common polyatomic ion found in various materials from eggshells to antacids. What are the electron-pair geometry and molecular structure of this polyatomic ion?

Answer

The electron-pair geometry is trigonal planar and the molecular structure is trigonal planar. Due to resonance, all three C–O bonds are identical. Whether they are single, double, or an average of the two, each bond counts as one region of electron density.

✓ Example 11.1.2: Predicting Electron-pair Geometry and Molecular Structure

Two of the top 50 chemicals produced in the United States, ammonium nitrate and ammonium sulfate, both used as fertilizers, contain the ammonium ion. Predict the electron-pair geometry and molecular structure of the NH_4^+ cation.

Solution

We write the Lewis structure of NH_4^+ as:




Figure 11.1.7).




Figure 11.1.8: *The ammonium ion displays a tetrahedral electron-pair geometry as well as a tetrahedral molecular structure.*

? Exercise 11.1.2

Identify a molecule with trigonal bipyramidal molecular structure.

Answer

Any molecule with five electron pairs around the central atoms including no lone pairs will be trigonal bipyramidal. PF_5 is a common example

The next several examples illustrate the effect of lone pairs of electrons on molecular structure.

✓ Example 11.1.3: Lone Pairs on the Central Atom

Predict the electron-pair geometry and molecular structure of a water molecule.

Solution

The Lewis structure of H_2O indicates that there are four regions of high electron density around the oxygen atom: two lone pairs and two chemical bonds:




Figure **11.1.9**. Thus, the electron-pair geometry is tetrahedral and the molecular structure is bent with an angle slightly less than 109.5°. In fact, the bond angle is 104.5°.




Figure **11.1.9**: (a) H_2O has four regions of electron density around the central atom, so it has a tetrahedral electron-pair geometry. (b) Two of the electron regions are lone pairs, so the molecular structure is bent.

? Exercise 11.1.3

The hydronium ion, H_3O^+, forms when acids are dissolved in water. Predict the electron-pair geometry and molecular structure of this cation.

Answer

electron pair geometry: tetrahedral; molecular structure: trigonal pyramidal

✔ Example 11.1.4: SF_4 Sulfur tetrafluoride,

Predicting Electron-pair Geometry and Molecular Structure: SF_4, is extremely valuable for the preparation of fluorine-containing compounds used as herbicides (i.e., SF_4 is used as a fluorinating agent). Predict the electron-pair geometry and molecular structure of a SF_4 molecule.

Solution

The Lewis structure of SF_4 indicates five regions of electron density around the sulfur atom: one lone pair and four bonding pairs:




Figure **11.1.10**).




Figure **11.1.10**: (a) SF_4 has a trigonal bipyramidal arrangement of the five regions of electron density. (b) One of the regions is a lone pair, which results in a seesaw-shaped molecular structure.

? Exercise 11.1.4

Predict the electron pair geometry and molecular structure for molecules of XeF_2.

Answer

The electron-pair geometry is trigonal bipyramidal. The molecular structure is linear.

✔ Example 11.1.4: XeF_4

Of all the noble gases, xenon is the most reactive, frequently reacting with elements such as oxygen and fluorine. Predict the electron-pair geometry and molecular structure of the XeF_4 molecule.

Solution

The Lewis structure of XeF_4 indicates six regions of high electron density around the xenon atom: two lone pairs and four bonds:




Figure **11.1.11**: The five atoms are all in the same plane and have a square planar molecular structure.




Figure **11.1.11**: (a) XeF_4 adopts an octahedral arrangement with two lone pairs (red lines) and four bonds in the electron-pair geometry. (b) The molecular structure is square planar with the lone pairs directly across from one another.

? Exercise 11.1.4

In a certain molecule, the central atom has three lone pairs and two bonds. What will the electron pair geometry and molecular structure be?

Answer

electron pair geometry: trigonal bipyramidal; molecular structure: linear




Shapes of Molecules: https://youtu.be/FUuI83PPua8

Molecular Structure for Multicenter Molecules


When a molecule or polyatomic ion has only one central atom, the molecular structure completely describes the shape of the molecule. Larger molecules do not have a single central atom, but are connected by a chain of interior atoms that each possess a "local" geometry. The way these local structures are oriented with respect to each other also influences the molecular shape, but such considerations are largely beyond the scope of this introductory discussion. For our purposes, we will only focus on determining the local structures.

Example 11.1.5: Predicting Structure in Multicenter Molecules

The Lewis structure for the simplest amino acid, glycine, $H_2NCH_2CO_2H$, is shown here. Predict the local geometry for the nitrogen atom, the two carbon atoms, and the oxygen atom with a hydrogen atom attached:



Solution



Consider each central atom independently. The electron-pair geometries:

- nitrogen—four regions of electron density; tetrahedral
- carbon ($\underline{C}H_2$)—four regions of electron density; tetrahedral
- carbon ($\underline{C}O_2$)—three regions of electron density; trigonal planar
- oxygen ($\underline{O}H$)—four regions of electron density; tetrahedral


The local structures:

- nitrogen—three bonds, one lone pair; trigonal pyramidal
- carbon ($\underline{C}H_2$)—four bonds, no lone pairs; tetrahedral
- carbon ($\underline{C}O_2$)—three bonds (double bond counts as one bond), no lone pairs; trigonal planar

- oxygen (OH)—two bonds, two lone pairs; bent (109°)

? Exercise 11.1.5

Another amino acid is alanine, which has the Lewis structure shown here. Predict the electron-pair geometry and local structure of the nitrogen atom, the three carbon atoms, and the oxygen atom with hydrogen attached:



Answer

electron-pair geometries: nitrogen—tetrahedral; carbon (CH)—tetrahedral; carbon (CH_3)—tetrahedral; carbon (CO_2)—trigonal planar; oxygen (OH)—tetrahedral; local structures: nitrogen—trigonal pyramidal; carbon (CH)—tetrahedral; carbon (CH_3)—tetrahedral; carbon (CO_2)—trigonal planar; oxygen (OH)—bent (109°)

✓ Example 11.1.6: Molecular Simulation

Using this molecular shape simulator allows us to control whether bond angles and/or lone pairs are displayed by checking or unchecking the boxes under “Options” on the right. We can also use the “Name” checkboxes at bottom-left to display or hide the electron pair geometry (called “electron geometry” in the simulator) and/or molecular structure (called “molecular shape” in the simulator).

Build the molecule HCN in the simulator based on the following Lewis structure:

$$\mathbf{H–C\equiv N}$$

Click on each bond type or lone pair at right to add that group to the central atom. Once you have the complete molecule, rotate it to examine the predicted molecular structure. What molecular structure is this?

Solution

The molecular structure is linear.

? Exercise 11.1.6

Build a more complex molecule in the simulator. Identify the electron-group geometry, molecular structure, and bond angles. Then try to find a chemical formula that would match the structure you have drawn.

Answer

Answers will vary. For example, an atom with four single bonds, a double bond, and a lone pair has an octahedral electron-group geometry and a square pyramidal molecular structure. $XeOF_4$ is a molecule that adopts this structure.

Summary

VSEPR theory predicts the three-dimensional arrangement of atoms in a molecule. It states that valence electrons will assume an electron-pair geometry that minimizes repulsions between areas of high electron density (bonds and/or lone pairs). Molecular structure, which refers only to the placement of atoms in a molecule and not the electrons, is equivalent to electron-pair geometry only when there are no lone electron pairs around the central atom.

Glossary

axial position
location in a trigonal bipyramidal geometry in which there is another atom at a 180° angle and the equatorial positions are at a 90° angle

bond angle
angle between any two covalent bonds that share a common atom

bond distance
(also, bond length) distance between the nuclei of two bonded atoms

bond dipole moment
separation of charge in a bond that depends on the difference in electronegativity and the bond distance represented by partial charges or a vector

dipole moment
property of a molecule that describes the separation of charge determined by the sum of the individual bond moments based on the molecular structure

electron-pair geometry
arrangement around a central atom of all regions of electron density (bonds, lone pairs, or unpaired electrons)

equatorial position
one of the three positions in a trigonal bipyramidal geometry with 120° angles between them; the axial positions are located at a 90° angle

linear
shape in which two outside groups are placed on opposite sides of a central atom

molecular structure
structure that includes only the placement of the atoms in the molecule

octahedral
shape in which six outside groups are placed around a central atom such that a three-dimensional shape is generated with four groups forming a square and the other two forming the apex of two pyramids, one above and one below the square plane

polar molecule
(also, dipole) molecule with an overall dipole moment

tetrahedral
shape in which four outside groups are placed around a central atom such that a three-dimensional shape is generated with four corners and 109.5° angles between each pair and the central atom

trigonal bipyramidal
shape in which five outside groups are placed around a central atom such that three form a flat triangle with 120° angles between each pair and the central atom, and the other two form the apex of two pyramids, one above and one below the triangular plane

trigonal planar
shape in which three outside groups are placed in a flat triangle around a central atom with 120° angles between each pair and the central atom

valence shell electron-pair repulsion theory (VSEPR)

theory used to predict the bond angles in a molecule based on positioning regions of high electron density as far apart as possible to minimize electrostatic repulsion

vector

quantity having magnitude and direction

11.1: VSEPR Theory is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **7.7: Molecular Structure and Polarity** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

11.2: Polarity of Molecules

Learning Objectives

- Assess the polarity of a molecule based on its bonding and structure

In section 10.3, we discussed the polarity of covalent bond. In this section, we will discuss the polarity of molecules which deprnds on both the polarity of the covalent bonds anf the shape of the moalcule.

Molecular Polarity and Dipole Moment

As discussed previously, polar covalent bonds connect two atoms with differing electronegativities, leaving one atom with a partial positive charge (δ+) and the other atom with a partial negative charge (δ–), as the electrons are pulled toward the more electronegative atom. This separation of charge gives rise to a bond dipole moment. The magnitude of a bond dipole moment is represented by the Greek letter mu (μ) and is given by

$$\mu = Qr \tag{11.2.1}$$

where

- Q is the magnitude of the partial charges (determined by the electronegativity difference) and
- r is the distance between the charges:

This bond moment can be represented as a vector, a quantity having both direction and magnitude (Figure **11.2.1**). Dipole vectors are shown as arrows pointing along the bond from the less electronegative atom toward the more electronegative atom. A small plus sign is drawn on the less electronegative end to indicate the partially positive end of the bond. The length of the arrow is proportional to the magnitude of the electronegativity difference between the two atoms.




Figure **11.2.1**: (a) There is a small difference in electronegativity between C and H, represented as a short vector. (b) The electronegativity difference between B and F is much larger, so the vector representing the bond moment is much longer.

A whole molecule may also have a separation of charge, depending on its molecular structure and the polarity of each of its bonds. If such a charge separation exists, the molecule is said to be a polar molecule (or dipole); otherwise the molecule is said to be nonpolar. The dipole moment measures the extent of net charge separation in the molecule as a whole. We determine the dipole moment by adding the bond moments in three-dimensional space, taking into account the molecular structure.

For diatomic molecules, there is only one bond, so its bond dipole moment determines the molecular polarity. Homonuclear diatomic molecules such as Br_2 and N_2 have no difference in electronegativity, so their dipole moment is zero. For heteronuclear molecules such as CO, there is a small dipole moment. For HF, there is a larger dipole moment because there is a larger difference in electronegativity.

When a molecule contains more than one bond, the geometry must be taken into account. If the bonds in a molecule are arranged such that their bond moments cancel (vector sum equals zero), then the molecule is nonpolar. This is the situation in CO_2 (Figure **11.2.2*A***). Each of the bonds is polar, but the molecule as a whole is nonpolar. From the Lewis structure, and using VSEPR theory, we determine that the CO_2 molecule is linear with polar C=O bonds on opposite sides of the carbon atom. The bond moments cancel because they are pointed in opposite directions. In the case of the water molecule (Figure **11.2.2*B***), the Lewis structure again shows that there are two bonds to a central atom, and the electronegativity difference again shows that each of these bonds has a nonzero bond moment. In this case, however, the molecular structure is bent because of the lone pairs on O, and the two bond moments do not cancel. Therefore, water does have a net dipole moment and is a polar molecule (dipole).





Figure **11.2.2**: The overall dipole moment of a molecule depends on the individual bond dipole moments and how they are arranged. (a) Each CO bond has a bond dipole moment, but they point in opposite directions so that the net CO_2 molecule is nonpolar. (b) In contrast, water is polar because the OH bond moments do not cancel out.

The OCS molecule has a structure similar to CO_2, but a sulfur atom has replaced one of the oxygen atoms. To determine if this molecule is polar, we draw the molecular structure. VSEPR theory predicts a linear molecule:




The C–O bond is considerably polar. Although C and S have very similar electronegativity values, S is slightly more electronegative than C, and so the C-S bond is just slightly polar. Because oxygen is more electronegative than sulfur, the oxygen end of the molecule is the negative end.

Chloromethane, CH_3Cl, is another example of a polar molecule. Although the polar C–Cl and C–H bonds are arranged in a tetrahedral geometry, the C–Cl bonds have a larger bond moment than the C–H bond, and the bond moments do not completely cancel each other. All of the dipoles have a upward component in the orientation shown, since carbon is more electronegative than hydrogen and less electronegative than chlorine:



When we examine the highly symmetrical molecules BF_3 (trigonal planar), CH_4 (tetrahedral), PF_5 (trigonal bipyramidal), and SF_6 (octahedral), in which all the polar bonds are identical, the molecules are nonpolar. The bonds in these molecules are arranged such that their dipoles cancel. However, just because a molecule contains identical bonds does not mean that the dipoles will always cancel. Many molecules that have identical bonds and lone pairs on the central atoms have bond dipoles that do not cancel. Examples include H_2S and NH_3. A hydrogen atom is at the positive end and a nitrogen or sulfur atom is at the negative end of the polar bonds in these molecules:



To summarize, to be polar, a molecule must:

1. Contain at least one polar covalent bond.
2. Have a molecular structure such that the sum of the vectors of each bond dipole moment does not cancel.

Properties of Polar Molecules

Polar molecules tend to align when placed in an electric field with the positive end of the molecule oriented toward the negative plate and the negative end toward the positive plate (Figure **11.2.3**). We can use an electrically charged object to attract polar molecules, but nonpolar molecules are not attracted. Also, polar solvents are better at dissolving polar substances, and nonpolar solvents are better at dissolving nonpolar substances.




Figure **11.2.3**: (a) Molecules are always randomly distributed in the liquid state in the absence of an electric field. (b) When an electric field is applied, polar molecules like HF will align to the dipoles with the field direction.

Example 11.2.1: Polarity Simulations

Open the molecule polarity simulation and select the "Three Atoms" tab at the top. This should display a molecule ABC with three electronegativity adjustors. You can display or hide the bond moments, molecular dipoles, and partial charges at the right. Turning on the Electric Field will show whether the molecule moves when exposed to a field, similar to Figure **11.2.14**.

Use the electronegativity controls to determine how the molecular dipole will look for the starting bent molecule if:

a. A and C are very electronegative and B is in the middle of the range.
b. A is very electronegative, and B and C are not.

Solution

a. Molecular dipole moment points immediately between A and C.
b. Molecular dipole moment points along the A–B bond, toward A.

Exercise 11.2.1

Determine the partial charges that will give the largest possible bond dipoles.

Answer

The largest bond moments will occur with the largest partial charges. The two solutions above represent how unevenly the electrons are shared in the bond. The bond moments will be maximized when the electronegativity difference is greatest. The controls for A and C should be set to one extreme, and B should be set to the opposite extreme. Although the magnitude of the bond moment will not change based on whether B is the most electronegative or the least, the direction of the bond moment will.

Summary

A dipole moment measures a separation of charge. For one bond, the bond dipole moment is determined by the difference in electronegativity between the two atoms. For a molecule, the overall dipole moment is determined by both the individual bond moments and how these dipoles are arranged in the molecular structure. Polar molecules (those with an appreciable dipole moment) interact with electric fields, whereas nonpolar molecules do not.

11.2: Polarity of Molecules is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **7.7: Molecular Structure and Polarity** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

11.3: Valence Bond theory

Learning Objectives

- Describe the formation of covalent bonds in terms of atomic orbital overlap
- Define and give examples of σ and π bonds

As we know, a scientific theory is a strongly supported explanation for observed natural laws or large bodies of experimental data. For a theory to be accepted, it must explain experimental data and be able to predict behavior. For example, VSEPR theory has gained widespread acceptance because it predicts three-dimensional molecular shapes that are consistent with experimental data collected for thousands of different molecules. However, VSEPR theory does not provide an explanation of chemical bonding.

There are successful theories that describe the electronic structure of atoms. We can use quantum mechanics to predict the specific regions around an atom where electrons are likely to be located: A spherical shape for an *s* orbital, a dumbbell shape for a *p* orbital, and so forth. However, these predictions only describe the orbitals around free atoms. When atoms bond to form molecules, atomic orbitals are not sufficient to describe the regions where electrons will be located in the molecule. A more complete understanding of electron distributions requires a model that can account for the electronic structure of molecules. One popular theory holds that a covalent bond forms when a pair of electrons is shared by two atoms and is simultaneously attracted by the nuclei of both atoms. In the following sections, we will discuss how such bonds are described by valence bond theory and hybridization.

Valence bond theory describes a covalent bond as the overlap of half-filled atomic orbitals (each containing a single electron) that yield a pair of electrons shared between the two bonded atoms. We say that orbitals on two different atoms overlap when a portion of one orbital and a portion of a second orbital occupy the same region of space. According to valence bond theory, a covalent bond results when two conditions are met:

1. an orbital on one atom overlaps an orbital on a second atom and
2. the single electrons in each orbital combine to form an electron pair.

The mutual attraction between this negatively charged electron pair and the two atoms' positively charged nuclei serves to physically link the two atoms through a force we define as a covalent bond. The strength of a covalent bond depends on the extent of overlap of the orbitals involved. Orbitals that overlap extensively form bonds that are stronger than those that have less overlap.

The energy of the system depends on how much the orbitals overlap. Figure **11.3.1** illustrates how the sum of the energies of two hydrogen atoms (the colored curve) changes as they approach each other. When the atoms are far apart there is no overlap, and by convention we set the sum of the energies at zero. As the atoms move together, their orbitals begin to overlap. Each electron begins to feel the attraction of the nucleus in the other atom. In addition, the electrons begin to repel each other, as do the nuclei. While the atoms are still widely separated, the attractions are slightly stronger than the repulsions, and the energy of the system decreases. (A bond begins to form.) As the atoms move closer together, the overlap increases, so the attraction of the nuclei for the electrons continues to increase (as do the repulsions among electrons and between the nuclei). At some specific distance between the atoms, which varies depending on the atoms involved, the energy reaches its lowest (most stable) value. This optimum distance between the two bonded nuclei is the bond distance between the two atoms. The bond is stable because at this point, the attractive and repulsive forces combine to create the lowest possible energy configuration. If the distance between the nuclei were to decrease further, the repulsions between nuclei and the repulsions as electrons are confined in closer proximity to each other would become stronger than the attractive forces. The energy of the system would then rise (making the system destabilized), as shown at the far left of Figure **11.3.1**.




Figure **11.3.1**: The interaction of two hydrogen atoms changes as a function of distance. The energy of the system changes as the atoms interact. The lowest (most stable) energy occurs at a distance of 74 pm, which is the bond length observed for the H_2 molecule.

The bond energy is the difference between the energy minimum (which occurs at the bond distance) and the energy of the two separated atoms. This is the quantity of energy released when the bond is formed. Conversely, the same amount of energy is required to break the bond. For the H_2 molecule shown in Figure **11.3.1**, at the bond distance of 74 pm the system is $7.24 \times 10^{-19}\ J$ lower in energy than the two separated hydrogen atoms. This may seem like a small number. However, we know from our earlier description of thermochemistry that bond energies are often discussed on a per-mole basis. For example, it requires $7.24 \times 10^{-19}\ J$ to break one H–H bond, but it takes $4.36 \times 10^{5}\ J$ to break 1 mole of H–H bonds. A comparison of some bond lengths and energies is shown in Table **11.3.1**. We can find many of these bonds in a variety of molecules, and this table provides average values. For example, breaking the first C–H bond in CH4 requires 439.3 kJ/mol, while breaking the first C–H bond in $\mathbf{H{-}CH_2C_6H_5}$ (a common paint thinner) requires 375.5 kJ/mol.

Table **11.3.1**: Representative Bond Energies and Lengths

Bond	Length (pm)	Energy (kJ/mol)		Bond	Length (pm)	Energy (kJ/mol)
H–H	74	436		C–O	140.1	358
H–C	106.8	413		C = O	119.7	745
H–N	101.5	391		C ≡ O	113.7	1072
H–O	97.5	467		H–Cl	127.5	431
C–C	150.6	347		H–Br	141.4	366
C = C	133.5	614		H–I	160.9	298
C ≡ C	120.8	839		O–O	148	146
C–N	142.1	305		O = O	120.8	498
C = N	130.0	615		F–F	141.2	159
C ≡ N	116.1	891		Cl–Cl	198.8	243

In addition to the distance between two orbitals, the orientation of orbitals also affects their overlap (other than for two *s* orbitals, which are spherically symmetric). Greater overlap is possible when orbitals are oriented such that they overlap on a direct line between the two nuclei. Figure **11.3.2** illustrates this for two *p* orbitals from different atoms; the overlap is greater when the orbitals overlap end to end rather than at an angle.




Figure **11.3.2**: (a) The overlap of two p orbitals is greatest when the orbitals are directed end to end. (b) Any other arrangement results in less overlap. The dots indicate the locations of the nuclei.

The overlap of two *s* orbitals (as in H_2), the overlap of an *s* orbital and a *p* orbital (as in HCl), and the end-to-end overlap of two *p* orbitals (as in Cl_2) all produce sigma bonds (σ bonds), as illustrated in Figure **11.3.3**. A σ bond is a covalent bond in which the electron density is concentrated in the region along the internuclear axis; that is, a line between the nuclei would pass through the center of the overlap region. Single bonds in Lewis structures are described as σ bonds in valence bond theory.




Figure **11.3.3**: Sigma (σ) bonds form from the overlap of the following: (a) two s orbitals, (b) an s orbital and a p orbital, and (c) two p orbitals. The dots indicate the locations of the nuclei.

A pi bond (π bond) is a type of covalent bond that results from the side-by-side overlap of two *p* orbitals, as illustrated in Figure **11.3.4**. In a π bond, the regions of orbital overlap lie on opposite sides of the internuclear axis. Along the axis itself, there is a node, that is, a plane with no probability of finding an electron.





Figure **11.3.4**: Pi (π) bonds form from the side-by-side overlap of two p orbitals. The dots indicate the location of the nuclei.

While all single bonds are σ bonds, multiple bonds consist of both σ and π bonds. As the Lewis structures suggest, O_2 contains a double bond, and N_2 contains a triple bond. The double bond consists of one σ bond and one π bond, and the triple bond consists of one σ bond and two π bonds. Between any two atoms, the first bond formed will always be a σ bond, but there can only be one σ bond in any one location. In any multiple bond, there will be one σ bond, and the remaining one or two bonds will be π bonds. These bonds are described in more detail later in this chapter.




As seen in Table **11.3.1**, an average carbon-carbon single bond is 347 kJ/mol, while in a carbon-carbon double bond, the π bond increases the bond strength by 267 kJ/mol. Adding an additional π bond causes a further increase of 225 kJ/mol. We can see a similar pattern when we compare other σ and π bonds. Thus, each individual π bond is generally weaker than a corresponding σ bond between the same two atoms. In a σ bond, there is a greater degree of orbital overlap than in a π bond.



Sigma (s) and Pi (p) Bonds: https://youtu.be/VZxqI7ai38k

Example 11.3.1: Counting σ and π Bonds

Butadiene, C_4H_6, is used to make synthetic rubber. Identify the number of σ and π bonds contained in this molecule.



Butadiene


Solution

There are six σ C–H bonds and one σ C–C bond, for a total of seven from the single bonds. There are two double bonds that each have a π bond in addition to the σ bond. This gives a total nine σ and two π bonds overall.

Exercise 11.3.1

Identify each illustration as depicting a σ or π bond:

a. side-by-side overlap of a 4*p* and a 2*p* orbital
b. end-to-end overlap of a 4*p* and 4*p* orbital
c. end-to-end overlap of a 4*p* and a 2*p* orbital



Answer

(a) is a π bond with a node along the axis connecting the nuclei while (b) and (c) are σ bonds that overlap along the axis.



Determining Orbital Overlap for Covalent Bonding: https://youtu.be/P6PExjfuBcs

Summary

Valence bond theory describes bonding as a consequence of the overlap of two separate atomic orbitals on different atoms that creates a region with one pair of electrons shared between the two atoms. When the orbitals overlap along an axis containing the nuclei, they form a σ bond. When they overlap in a fashion that creates a node along this axis, they form a π bond.

Glossary

overlap
: coexistence of orbitals from two different atoms sharing the same region of space, leading to the formation of a covalent bond

node
: plane separating different lobes of orbitals, where the probability of finding an electron is zero

pi bond (π bond)
: covalent bond formed by side-by-side overlap of atomic orbitals; the electron density is found on opposite sides of the internuclear axis

sigma bond (σ bond)
: covalent bond formed by overlap of atomic orbitals along the internuclear axis

valence bond theory
: description of bonding that involves atomic orbitals overlapping to form σ or π bonds, within which pairs of electrons are shared

---

11.3: Valence Bond theory is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **8.2: Valence Bond Theory** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

11.4: Hybrid Atomic Orbitals

Learning Objectives

- Explain the concept of atomic orbital hybridization
- Determine the hybrid orbitals associated with various molecular geometries

Thinking in terms of overlapping atomic orbitals is one way for us to explain how chemical bonds form in diatomic molecules. However, to understand how molecules with more than two atoms form stable bonds, we require a more detailed model. As an example, let us consider the water molecule, in which we have one oxygen atom bonding to two hydrogen atoms. Oxygen has the electron configuration $1s^2 2s^2 2p^4$, with two unpaired electrons (one in each of the two 2*p* orbitals). Valence bond theory would predict that the two O–H bonds form from the overlap of these two 2*p* orbitals with the 1*s* orbitals of the hydrogen atoms. If this were the case, the bond angle would be 90°, as shown in Figure **11.4.1**, because *p* orbitals are perpendicular to each other. Experimental evidence shows that the bond angle is 104.5°, not 90°. The prediction of the valence bond theory model does not match the real-world observations of a water molecule; a different model is needed.




Figure **11.4.1**: The hypothetical overlap of two of the 2p orbitals on an oxygen atom (red) with the 1s orbitals of two hydrogen atoms (blue) would produce a bond angle of 90°. This is not consistent with experimental evidence.[1]

Two peanut-shaped orbitals lie perpendicular to one another. They overlap with spherical orbitals to the left and top of the diagram.

Quantum-mechanical calculations suggest why the observed bond angles in H_2O differ from those predicted by the overlap of the 1*s* orbital of the hydrogen atoms with the 2*p* orbitals of the oxygen atom. The mathematical expression known as the wave function, ψ, contains information about each orbital and the wavelike properties of electrons in an isolated atom. When atoms are bound together in a molecule, the wave functions combine to produce new mathematical descriptions that have different shapes. This process of combining the wave functions for atomic orbitals is called hybridization and is mathematically accomplished by the *linear combination of atomic orbitals*, LCAO, (a technique that we will encounter again later). The new orbitals that result are called hybrid orbitals. The valence orbitals in an *isolated* oxygen atom are a 2*s* orbital and three 2*p* orbitals. The valence orbitals in an oxygen atom in a water molecule differ; they consist of four equivalent hybrid orbitals that point approximately toward the corners of a tetrahedron (Figure **11.4.2**). Consequently, the overlap of the O and H orbitals should result in a tetrahedral bond angle (109.5°). The observed angle of 104.5° is experimental evidence for which quantum-mechanical calculations give a useful explanation: Valence bond theory must include a hybridization component to give accurate predictions.




Figure **11.4.2**: (a) A water molecule has four regions of electron density, so VSEPR theory predicts a tetrahedral arrangement of hybrid orbitals. (b) Two of the hybrid orbitals on oxygen contain lone pairs, and the other two overlap with the 1s orbitals of hydrogen atoms to form the O–H bonds in H_2O. This description is more consistent with the experimental structure.

Two diagrams are shown and labeled “a” and “b.” Diagram a shows two peanut-shaped orbitals lying in a tetrahedral arrangement around the letter “O.” Diagram b shows the same two orbitals, but they now overlap to the top and to the left with two spherical orbitals, each labeled “H.” A pair of electrons occupies each lobe of the peanut-shaped orbitals.

The following ideas are important in understanding hybridization:

1. Hybrid orbitals do not exist in isolated atoms. They are formed only in covalently bonded atoms.
2. Hybrid orbitals have shapes and orientations that are very different from those of the atomic orbitals in isolated atoms.
3. A set of hybrid orbitals is generated by combining atomic orbitals. The number of hybrid orbitals in a set is equal to the number of atomic orbitals that were combined to produce the set.
4. All orbitals in a set of hybrid orbitals are equivalent in shape and energy.
5. The type of hybrid orbitals formed in a bonded atom depends on its electron-pair geometry as predicted by the VSEPR theory.
6. Hybrid orbitals overlap to form σ bonds. Unhybridized orbitals overlap to form π bonds.

In the following sections, we shall discuss the common types of hybrid orbitals.

sp Hybridization

The beryllium atom in a gaseous $BeCl_2$ molecule is an example of a central atom with no lone pairs of electrons in a linear arrangement of three atoms. There are two regions of valence electron density in the $BeCl_2$ molecule that correspond to the two covalent Be–Cl bonds. To accommodate these two electron domains, two of the Be atom’s four valence orbitals will mix to yield two hybrid orbitals. This hybridization process involves mixing of the valence *s* orbital with one of the valence *p* orbitals to yield two equivalent *sp* hybrid orbitals that are oriented in a linear geometry (Figure **11.4.3**). In this figure, the set of *sp* orbitals appears similar in shape to the original *p* orbital, but there is an important difference. The number of atomic orbitals combined always equals the number of hybrid orbitals formed. The *p* orbital is one orbital that can hold up to two electrons. The *sp* set is two equivalent orbitals that point 180° from each other. The two electrons that were originally in the *s* orbital are now distributed to the two *sp* orbitals, which are half filled. In gaseous $BeCl_2$, these half-filled hybrid orbitals will overlap with orbitals from the chlorine atoms to form two identical σ bonds.




Figure **11.4.3**: Hybridization of an s orbital (blue) and a p orbital (red) of the same atom produces two sp hybrid orbitals (yellow). Each hybrid orbital is oriented primarily in just one direction. Note that each sp orbital contains one lobe that is significantly larger than the other. The set of two sp orbitals are oriented at 180°, which is consistent with the geometry for two domains.

A series of three diagrams connected by a right-facing arrow that is labeled, “Hybridization,” and a downward-facing arrow labeled, “Gives a linear arrangement,” are shown. The first diagram shows a blue spherical orbital and a red, peanut-shaped orbital, each placed on an X, Y, Z axis system. The second diagram shows the same two orbitals, but they are now purple and have one enlarged lobe and one smaller lobe. Each lies along the x-axis in the drawing. The third diagram shows the same two orbitals, but their smaller lobes now overlap along the x-axis while their larger lobes are located at and labeled as “180 degrees” from one another.

We illustrate the electronic differences in an isolated Be atom and in the bonded Be atom in the orbital energy-level diagram in Figure **11.4.4**. These diagrams represent each orbital by a horizontal line (indicating its energy) and each electron by an arrow. Energy increases toward the top of the diagram. We use one upward arrow to indicate one electron in an orbital and two arrows (up and down) to indicate two electrons of opposite spin.




Figure **11.4.4**: This orbital energy-level diagram shows the sp hybridized orbitals on Be in the linear $BeCl_2$ molecule. Each of the two sp hybrid orbitals holds one electron and is thus half filled and available for bonding via overlap with a Cl 3p orbital.

A diagram is shown in two parts, connected by a right facing arrow labeled, “Hybridization.” The left diagram shows an up-facing arrow labeled, “E.” To the lower right of the arrow is a short, horizontal line labeled, “2 s,” that has two vertical half-arrows facing up and down on it. To the upper right of the arrow are a series of three short, horizontal lines labeled, “2 p.” Above these two sets of lines is the phrase, “Orbitals in an isolated B e atom.” The right side of the diagram shows two short, horizontal lines placed halfway up the space and each labeled, “s p.” An upward-facing half arrow is drawn vertically on each line. Above these lines are two other short, horizontal lines, each labeled, “2 p.” Above these two sets of lines is the phrase, “Orbitals in the s p hybridized B e in B e C l subscript 2.”

When atomic orbitals hybridize, the valence electrons occupy the newly created orbitals. The Be atom had two valence electrons, so each of the *sp* orbitals gets one of these electrons. Each of these electrons pairs up with the unpaired electron on a chlorine atom when a hybrid orbital and a chlorine orbital overlap during the formation of the Be–Cl bonds. Any central atom surrounded by just two regions of valence electron density in a molecule will exhibit *sp* hybridization. Other examples include the mercury atom in the linear $HgCl_2$ molecule, the zinc atom in $Zn(CH_3)_2$, which contains a linear C–Zn–C arrangement, and the carbon atoms in HCCH and CO_2.

sp^2 Hybridization

The valence orbitals of a central atom surrounded by three regions of electron density consist of a set of three sp^2 hybrid orbitals and one unhybridized p orbital. This arrangement results from sp^2 hybridization, the mixing of one s orbital and two p orbitals to produce three identical hybrid orbitals oriented in a trigonal planar geometry (Figure **11.4.5**).




Figure **11.4.5**: The hybridization of an s orbital (blue) and two p orbitals (red) produces three equivalent sp^2 hybridized orbitals (yellow) oriented at 120° with respect to each other. The remaining unhybridized p orbital is not shown here, but is located along the z axis.

A series of three diagrams connected by a right-facing arrow that is labeled, “Hybridization,” and a downward-facing arrow labeled, “Gives a trigonal planar arrangement,” are shown. The first diagram shows a blue spherical orbital and two red, peanut-shaped orbitals, each placed on an X, Y, Z axis system. The two red orbitals are located on the x and z axes, respectively. The second diagram shows the same three orbitals, but they are now purple and have one enlarged lobe and one smaller lobe. Each lies in a different axis in the drawing. The third diagram shows the same three orbitals, but their smaller lobes now overlap while their larger lobes are located at and labeled as “120 degrees” from one another.

Although quantum mechanics yields the “plump” orbital lobes as depicted in Figure **11.4.5**, sometimes for clarity these orbitals are drawn thinner and without the minor lobes, as in Figure **11.4.6**, to avoid obscuring other features of a given illustration. We will use these “thinner” representations whenever the true view is too crowded to easily visualize.




Figure **11.4.6**: This alternate way of drawing the trigonal planar sp^2 hybrid orbitals is sometimes used in more crowded figures.

Three balloon-like orbitals are shown, and connect together near their narrower ends in one plane. The angle between a pair of lobes is labeled, “120 degrees.”

The observed structure of the borane molecule, BH_3, suggests sp^2 hybridization for boron in this compound. The molecule is trigonal planar, and the boron atom is involved in three bonds to hydrogen atoms (Figure **11.4.7**).




Figure **11.4.7**: BH_3 is an electron-deficient molecule with a trigonal planar structure.

A boron atom is shown connected to three hydrogen atoms, which are arranged around it like a pyramid. The angle from one line connecting the boron atom to a hydrogen atom to another line connecting the boron atom to a hydrogen atom is labeled, “120 degrees.”

We can illustrate the comparison of orbitals and electron distribution in an isolated boron atom and in the bonded atom in BH_3 as shown in the orbital energy level diagram in Figure **11.4.8**. We redistribute the three valence electrons of the boron atom in the three sp^2 hybrid orbitals, and each boron electron pairs with a hydrogen electron when B–H bonds form.




Figure **11.4.8**: In an isolated B atom, there are one 2s and three 2p valence orbitals. When boron is in a molecule with three regions of electron density, three of the orbitals hybridize and create a set of three sp^2 orbitals and one unhybridized 2p orbital. The three half-filled hybrid orbitals each overlap with an orbital from a hydrogen atom to form three σ bonds in BH_3.

A diagram is shown in two parts, connected by a right facing arrow labeled, “Hybridization.” The left diagram shows an up-facing arrow labeled “E.” To the lower right of the arrow is a short, horizontal line labeled, “2 s,” that has two vertical half-arrows facing up and down on it. To the upper right of the arrow are a series of three short, horizontal lines labeled, “2 p.” Above both sets of these lines is the phrase, “Orbitals in an isolated B atom.” One of the lines has a vertical, up-facing arrow drawn on it. The right side of the diagram shows three short, horizontal lines placed halfway up the space and each labeled, “s p superscript 2.” An upward-facing half arrow is drawn vertically on each line. Above these lines is one other short, horizontal line, labeled, “2 p.” Above both sets of lines is the phrase, “Orbitals in the s p superscript 2 hybridized B atom in B H subscript 3.”

Any central atom surrounded by three regions of electron density will exhibit sp^2 hybridization. This includes molecules with a lone pair on the central atom, such as ClNO (Figure **11.4.9**), or molecules with two single bonds and a double bond connected to the central atom, as in formaldehyde, CH_2O, and ethene, H_2CCH_2.




Figure **11.4.9**: The central atom(s) in each of the structures shown contain three regions of electron density and are sp^2 hybridized. As we know from the discussion of VSEPR theory, a region of electron density contains all of the electrons that point in one direction. A lone pair, an unpaired electron, a single bond, or a multiple bond would each count as one region of electron density.

Three Lewis structures are shown. The left-hand structure shows a chlorine atom surrounded by three lone pairs of electrons single bonded to a nitrogen atom with one lone pair of electrons and double bonded to an oxygen atom with two lone pairs of electrons. The middle structure shows a carbon atom single bonded to two hydrogen atoms and double bonded to an oxygen atom that has two lone pairs of electrons. The right-hand structure shows two carbon atoms, double bonded to one another and each single bonded to two hydrogen atoms.

sp^3 Hybridization

The valence orbitals of an atom surrounded by a tetrahedral arrangement of bonding pairs and lone pairs consist of a set of four sp^3 hybrid orbitals. The hybrids result from the mixing of one *s* orbital and all three *p* orbitals that produces four identical sp^3 hybrid orbitals (Figure **11.4.10**). Each of these hybrid orbitals points toward a different corner of a tetrahedron.




Figure **11.4.10**: The hybridization of an s orbital (blue) and three p orbitals (red) produces four equivalent sp^3 hybridized orbitals (yellow) oriented at 109.5° with respect to each other.

A series of three diagrams connected by a right-facing arrow that is labeled, “Hybridization,” and a downward-facing arrow labeled, “Gives a tetrahedral arrangement,” are shown. The first diagram shows a blue spherical orbital and three red, peanut-shaped orbitals, each placed on an x, y, z axis system. The three red orbitals are located on the x , y and z axes, respectively. The second diagram shows the same four orbitals, but they are now purple and have one enlarged lobe and one smaller lobe. Each lies in a different axis in the drawing. The third diagram shows the same four orbitals, but their smaller lobes now overlap to form a tetrahedral structure.

A molecule of methane, CH_4, consists of a carbon atom surrounded by four hydrogen atoms at the corners of a tetrahedron. The carbon atom in methane exhibits sp^3 hybridization. We illustrate the orbitals and electron distribution in an isolated carbon atom and in the bonded atom in CH_4 in Figure **11.4.11**. The four valence electrons of the carbon atom are distributed equally in the hybrid orbitals, and each carbon electron pairs with a hydrogen electron when the C–H bonds form.




Figure **11.4.11**: The four valence atomic orbitals from an isolated carbon atom all hybridize when the carbon bonds in a molecule like CH_4 with four regions of electron density. This creates four equivalent sp^3 hybridized orbitals. Overlap of each of the hybrid orbitals with a hydrogen orbital creates a C–H σ bond.

A diagram is shown in two parts, connected by a right facing arrow labeled, “Hybridization.” The left diagram shows an up-facing arrow labeled “E.” To the lower right of the arrow is a short, horizontal line labeled, “2 s,” that has two vertical half-arrows facing up and down on it. To the upper right of the arrow are a series of three short, horizontal lines labeled, “2 p.” Two of the lines have a vertical, up-facing arrow drawn on them. Above both sets of lines is the phrase, “Orbitals in an isolated C atom.” The right side of the diagram shows four short, horizontal lines placed halfway up the space and each labeled, “s p superscript 3.” An upward-facing half arrow is drawn vertically on each line. Above these lines is the phrase, “Orbitals in the s p superscript 3 hybridized C atom in C H subscript 4.”

In a methane molecule, the 1*s* orbital of each of the four hydrogen atoms overlaps with one of the four sp^3 orbitals of the carbon atom to form a sigma (σ) bond. This results in the formation of four strong, equivalent covalent bonds between the carbon atom and each of the hydrogen atoms to produce the methane molecule, CH_4.

The structure of ethane, C_2H_6, is similar to that of methane in that each carbon in ethane has four neighboring atoms arranged at the corners of a tetrahedron—three hydrogen atoms and one carbon atom (Figure **11.4.10**). However, in ethane an sp^3 orbital of one carbon atom overlaps end to end with an sp^3 orbital of a second carbon atom to form a σ bond between the two carbon atoms. Each of the remaining sp^3 hybrid orbitals overlaps with an *s* orbital of a hydrogen atom to form carbon–hydrogen σ bonds. The structure and overall outline of the bonding orbitals of ethane are shown in Figure **11.4.12**. The orientation of the two CH_3 groups is not fixed relative to each other. Experimental evidence shows that rotation around σ bonds occurs easily.




Figure **11.4.12**: (a) In the ethane molecule, C_2H_6, each carbon has four sp^3 orbitals. (b) These four orbitals overlap to form seven σ bonds.

Two diagrams are shown and labeled “a” and “b.” Diagram a shows two carbon atoms, each surrounded by their four s p subscript three hybridized orbitals in a three dimensional arrangement. Each of the orbitals is shown overlapping with a spherical hydrogen atom. Diagram b shows the same general arrangement, but the hydrogen atoms are just represented by an, “H” and their spherical orbitals are not shown.

An sp^3 hybrid orbital can also hold a lone pair of electrons. For example, the nitrogen atom in ammonia is surrounded by three bonding pairs and a lone pair of electrons directed to the four corners of a tetrahedron. The nitrogen atom is sp^3 hybridized with one hybrid orbital occupied by the lone pair.

The molecular structure of water is consistent with a tetrahedral arrangement of two lone pairs and two bonding pairs of electrons. Thus we say that the oxygen atom is sp^3 hybridized, with two of the hybrid orbitals occupied by lone pairs and two by bonding pairs. Since lone pairs occupy more space than bonding pairs, structures that contain lone pairs have bond angles slightly distorted from the ideal. Perfect tetrahedra have angles of 109.5°, but the observed angles in ammonia (107.3°) and water (104.5°) are slightly smaller. Other examples of sp^3 hybridization include CCl_4, PCl_3, and NCl_3.

sp^3d and sp^3d^2 Hybridization

To describe the five bonding orbitals in a trigonal bipyramidal arrangement, we must use five of the valence shell atomic orbitals (the *s* orbital, the three *p* orbitals, and one of the *d* orbitals), which gives five sp^3d hybrid orbitals. With an octahedral arrangement of six hybrid orbitals, we must use six valence shell atomic orbitals (the *s* orbital, the three *p* orbitals, and two of the *d* orbitals in its valence shell), which gives six sp^3d^2 hybrid orbitals. These hybridizations are only possible for atoms that have *d* orbitals in their valence subshells (that is, not those in the first or second period).




Figure **11.4.13**: The three compounds pictured exhibit sp^3d hybridization in the central atom and a trigonal bipyramid form. SF_4 and ClF_4^+ *have one lone pair of electrons on the central atom, and* ClF_3 *has two lone pairs giving it the T-shape shown.*

Three Lewis structures are shown along with designations of molecular shape. The left image shows a sulfur atom singly bonded to four fluorine atoms. The sulfur atom has one lone pair of electrons while each fluorine has three. Two fluorine atoms are drawn vertically up and down from the sulfur while the other two are shown going into and out of the page. The second structure shows one chlorine atom singly bonded to three fluorine atoms. The chlorine has two lone pairs of electrons while each fluorine has three. Two fluorine atoms are drawn vertically up and down from the sulfur while the other is shown horizontally. The right structure shows a chlorine atom singly bonded to four fluorine atoms. The chlorine atom has one lone pair of electrons and a superscript plus sign, while each fluorine has three lone pairs of electrons. Two fluorine atoms are drawn vertically up and down from the sulfur while the other two are shown going into and out of the page.

In a molecule of phosphorus pentachloride, PCl_5, there are five P–Cl bonds (thus five pairs of valence electrons around the phosphorus atom) directed toward the corners of a trigonal bipyramid. We use the 3*s* orbital, the three 3*p* orbitals, and one of the 3*d* orbitals to form the set of five sp^3d hybrid orbitals (Figure **11.4.13**) that are involved in the P–Cl bonds. Other atoms that exhibit sp^3d hybridization include the sulfur atom in SF_4 and the chlorine atoms in ClF_3 and in ClF_4^+. (The electrons on fluorine atoms are omitted for clarity.)




Figure **11.4.14**: (a) The five regions of electron density around phosphorus in PCl_5 require five hybrid sp^3d orbitals. (b) These orbitals combine to form a trigonal bipyramidal structure with each large lobe of the hybrid orbital pointing at a vertex. As before, there are also small lobes pointing in the opposite direction for each orbital (not shown for clarity).

Two images are shown and labeled “a” and “b.” Image a depicts a ball-and-stick model in a trigonal bipyramidal arrangement. Image b depicts the hybrid orbitals in the same arrangement and each is labeled, “s p superscript three d.”

The sulfur atom in sulfur hexafluoride, SF_6, exhibits sp^3d^2 hybridization. A molecule of sulfur hexafluoride has six bonding pairs of electrons connecting six fluorine atoms to a single sulfur atom. There are no lone pairs of electrons on the central atom. To bond six fluorine atoms, the 3*s* orbital, the three 3*p* orbitals, and two of the 3*d* orbitals form six equivalent sp^3d^2 hybrid orbitals, each directed toward a different corner of an octahedron. Other atoms that exhibit sp^3d^2 hybridization include the phosphorus atom in PCl_6^-, the iodine atom in the interhalogens IF_6^+, IF_5, ICl_4^-, IF_4^- and the xenon atom in XeF_4.




Figure **11.4.15**: (a) Sulfur hexafluoride, SF_6, has an octahedral structure that requires sp^3d^2 hybridization. (b) The six sp^3d^2 orbitals form an octahedral structure around sulfur. Again, the minor lobe of each orbital is not shown for clarity.

Two images are shown and labeled “a” and “b.” Image a depicts a ball-and-stick model in an octahedral arrangement. Image b depicts the hybrid orbitals in the same arrangement and each is labeled, “s p superscript three d superscript two.”

Assignment of Hybrid Orbitals to Central Atoms

The hybridization of an atom is determined based on the number of regions of electron density that surround it. The geometrical arrangements characteristic of the various sets of hybrid orbitals are shown in Figure **11.4.16**. These arrangements are identical to those of the electron-pair geometries predicted by VSEPR theory. VSEPR theory predicts the shapes of molecules, and hybrid orbital theory provides an explanation for how those shapes are formed. To find the hybridization of a central atom, we can use the following guidelines:

1. Determine the Lewis structure of the molecule.
2. Determine the number of regions of electron density around an atom using VSEPR theory, in which single bonds, multiple bonds, radicals, and lone pairs each count as one region.
3. Assign the set of hybridized orbitals from Figure **11.4.16** that corresponds to this geometry.









Regions of Electron Density	Arrangement		Hybridization	
2		linear	*sp*	
3		trigonal planar	sp^2	
4		tetrahedral	sp^3	
5		trigonal bipyramidal	sp^3d	
6		octahedral	sp^3d^2	

Figure **11.4.16**: The shapes of hybridized orbital sets are consistent with the electron-pair geometries. For example, an atom surrounded by three regions of electron density is sp^2 hybridized, and the three sp^2 orbitals are arranged in a trigonal planar fashion.

A table is shown that is composed of five columns and six rows. The header row contains the phrases, “Regions of electron density,” “Arrangement,” (which has two columns below it), and “Hybridization,” (which has two columns below it). The first column contains the numbers “2,” “3,” “4,” “5,” and “6.” The second column contains images of a line, a triangle, a three sided pyramid, a trigonal bipyramid, and an eight-faced ocatahedron. The third column contains the terms, “Linear,” “Trigonal planar,” “Tetrahedral,” “Trigonal bipyramidal,” and “Octahedral.” The fourth column contains the terms “s p,” “s p superscript 2,” “s p superscript 3,” “s p superscript 3 d,” and “s p superscript 3 d superscript 2.” The last column contains drawings of the molecules beginning with a peanut-shaped structure marked with an angle of “180 degrees.” The second structure is made up of three equal-sized, rounded structures connected at one point with an angle of “120 degrees,” while the third structure is a three-dimensional arrangement of four equal-sized, rounded structures labeled as “109.5 degrees.” The fourth structure is made up of five equal-sized, rounded structures connected at “120 and 90 degrees,” while the fifth structure has six equal-sized, rounded structures connected at “90 degrees.”

> *It is important to remember that hybridization was devised to rationalize experimentally observed molecular geometries, not the other way around.*

The model works well for molecules containing small central atoms, in which the valence electron pairs are close together in space. However, for larger central atoms, the valence-shell electron pairs are farther from the nucleus, and there are fewer repulsions. Their compounds exhibit structures that are often not consistent with VSEPR theory, and hybridized orbitals are not necessary to explain the observed data.



Three Lewis structures are shown. The left structure shows an oxygen atom with two lone pairs of electrons single bonded to two hydrogen atoms. The middle structure is made up of a sulfur atom with two lone pairs of electrons single bonded to two hydrogen atoms. The right structure is made up of a tellurium atom with two lone pairs of electrons single bonded to two hydrogen atoms. From left to right, the bond angles of each molecule decrease.

For example, we have discussed the H–O–H bond angle in H_2O, 104.5°, which is more consistent with sp^3 hybrid orbitals (109.5°) on the central atom than with 2*p* orbitals (90°). Sulfur is in the same group as oxygen, and H_2S has a similar Lewis structure. However, it has a much smaller bond angle (92.1°), which indicates much less hybridization on sulfur than oxygen. Continuing down the group, tellurium is even larger than sulfur, and for H_2Te, the observed bond angle (90°) is consistent with overlap of the 5*p* orbitals, without invoking hybridization. We invoke hybridization where it is necessary to explain the observed structures.

Example 11.4.1: Assigning Hybridization

Ammonium sulfate is important as a fertilizer. What is the hybridization of the sulfur atom in the sulfate ion, SO_4^{2-}?

Solution

The Lewis structure of sulfate shows there are four regions of electron density.





Figure 11.4.16).

A structure is shown in which a sulfur atom is bonded to four oxygen atoms in a tetrahedral arrangement. Two of the oxygen atoms have a negative charge.

Exercise 11.4.1

What is the hybridization of the selenium atom in SeF_4?



A Lewis structure is shown in which four fluorine atoms are each attached to one sulfur atom. Two of the attached fluorine atoms are vertically attached up and down, while two are attached into and out of the page to the right. The sulfur also has one lone pair of electrons attached to the left of the structure.

Answer

The selenium atom is sp^3d hybridized.

Example 11.4.2: Assigning Hybridization

Urea, $NH_2C(O)NH_2$, is sometimes used as a source of nitrogen in fertilizers. What is the hybridization of each nitrogen and carbon atom in urea?

Solution

The Lewis structure of urea is





Figure **11.4.16**). This is the hybridization of the nitrogen atoms in urea.

A Lewis structure is shown in which a carbon atom is double bonded to an oxygen atom that has two lone pairs of electrons. The carbon atom forms single bonds to two nitrogen atoms. Each nitrogen is single bonded to two hydrogen atoms, and each nitrogen atoms has one lone pair of electrons.

The carbon atom is surrounded by three regions of electron density, positioned in a trigonal planar arrangement. The hybridization in a trigonal planar electron pair geometry is sp^2 (Figure **11.4.16**), which is the hybridization of the carbon atom in urea.

Exercise 11.4.1

Acetic acid, $H_3CC(O)OH$, is the molecule that gives vinegar its odor and sour taste. What is the hybridization of the two carbon atoms in acetic acid?



A Lewis structure is shown in which a carbon atom is double bonded to an oxygen atom that has two lone pairs of electrons and single bonded to another oxygen atom that is single boned to a hydrogen atom. This second oxygen atom has two lone pairs of electrons. The carbon is also single bonded to a carbon atom that is single bonded to three hydrogen atoms.

Answer

$H_3\underline{C}$, sp^3; $\underline{C}(O)OH$, sp^2

Summary

We can use hybrid orbitals, which are mathematical combinations of some or all of the valence atomic orbitals, to describe the electron density around covalently bonded atoms. These hybrid orbitals either form sigma (σ) bonds directed toward other atoms of the molecule or contain lone pairs of electrons. We can determine the type of hybridization around a central atom from the geometry of the regions of electron density about it. Two such regions imply *sp* hybridization; three, sp^2 hybridization; four, sp^3 hybridization; five, sp^3d hybridization; and six, sp^3d^2 hybridization. Pi (π) bonds are formed from unhybridized atomic orbitals (*p* or *d* orbitals).

Footnotes

1. Note that orbitals may sometimes be drawn in an elongated “balloon” shape rather than in a more realistic “plump” shape in order to make the geometry easier to visualize.

Glossary

hybrid orbital
orbital created by combining atomic orbitals on a central atom

hybridization
model that describes the changes in the atomic orbitals of an atom when it forms a covalent compound

***sp* hybrid orbital**
one of a set of two orbitals with a linear arrangement that results from combining one *s* and one *p* orbital

sp^2 hybrid orbital
one of a set of three orbitals with a trigonal planar arrangement that results from combining one *s* and two *p* orbitals

sp^3 hybrid orbital
one of a set of four orbitals with a tetrahedral arrangement that results from combining one *s* and three *p* orbitals

sp^3d hybrid orbital
one of a set of five orbitals with a trigonal bipyramidal arrangement that results from combining one *s*, three *p*, and one *d* orbital

sp^3d^2 hybrid orbital
one of a set of six orbitals with an octahedral arrangement that results from combining one *s*, three *p*, and two *d* orbitals

---

11.4: Hybrid Atomic Orbitals is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **8.3: Hybrid Atomic Orbitals** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

11.5: Overlap of Hybrid Orbitals

Learning Objectives

- Describe multiple covalent bonding in terms of atomic orbital overlap
- Relate the concept of resonance to π-bonding and electron delocalization

The hybrid orbital model appears to account well for the geometry of molecules involving single covalent bonds. Is it also capable of describing molecules containing double and triple bonds? We have already discussed that multiple bonds consist of σ and π bonds. Next we can consider how we visualize these components and how they relate to hybrid orbitals. The Lewis structure of ethene, C_2H_4, shows us that each carbon atom is surrounded by one other carbon atom and two hydrogen atoms.




Figure **11.5.2**).

A Lewis structure is shown in which two carbon atoms are bonded together by a double bond. Each carbon atom is bonded to two hydrogen atoms by a single bond.




Figure **11.5.1**: In ethene, each carbon atom is sp^2 hybridized, and the sp^2 orbitals and the *p* orbital are singly occupied. The hybrid orbitals overlap to form σ bonds, while the *p* orbitals on each carbon atom overlap to form a π bond.

A diagram is shown in two parts, connected by a right facing arrow labeled, “Hybridization.” The left diagram shows an up-facing arrow labeled, “E.” To the lower right of the arrow is a short, horizontal line labeled, “2 s,” that has two vertical half-arrows facing up and down on it. To the upper right of the arrow are a series of three short, horizontal lines labeled, “2 p.” Above both sets of lines is the phrase, “Orbitals in an isolated C atom.” Two of the lines have vertical, up-facing arrows drawn on them. The right side of the diagram shows three short, horizontal lines placed halfway up the space and each labeled, “s p superscript 2.” An upward-facing half arrow is drawn vertically on each line. Above these lines is one other short, horizontal line, labeled, “p.” Above both sets of lines is the phrase, “Orbitals in the s p superscript 2 hybridized C atom in C subscript 2 H subscript 4.”

The π bond in the C=C double bond results from the overlap of the third (remaining) 2*p* orbital on each carbon atom that is not involved in hybridization. This unhybridized *p* orbital (lobes shown in red and blue in Figure **11.5.2**) is perpendicular to the plane of the sp^2 hybrid orbitals. Thus the unhybridized 2*p* orbitals overlap in a side-by-side fashion, above and below the internuclear axis and form a π bond.





Figure **11.5.2**: In the ethene molecule, C_2H_4, there are (a) five σ bonds. One C–C σ bond results from overlap of sp^2 hybrid orbitals on the carbon atom with one sp^2 hybrid orbital on the other carbon atom. Four C–H bonds result from the overlap between the C atoms' sp^2 orbitals with s orbitals on the hydrogen atoms. (b) The π bond is formed by the side-by-side overlap of the two unhybridized p orbitals in the two carbon atoms. The two lobes of the π bond are above and below the plane of the σ system.

Two diagrams are shown labeled, “a” and “b.” Diagram a shows two carbon atoms with three purple balloon-like orbitals arranged in a plane around them and two red balloon-like orbitals arranged vertically and perpendicularly to the plane. There is an overlap of two of the purple orbitals in between the two carbon atoms, and the other four purple orbitals that face the outside of the molecule are shown interacting with spherical blue orbitals from four hydrogen atoms. Diagram b depicts a similar image to diagram a, but the red, vertical orbitals are interacting above and below the plane of the molecule to form two areas labeled, “One pi bond.”

In an ethene molecule, the four hydrogen atoms and the two carbon atoms are all in the same plane. If the two planes of sp^2 hybrid orbitals tilted relative to each other, the *p* orbitals would not be oriented to overlap efficiently to create the π bond. The planar configuration for the ethene molecule occurs because it is the most stable bonding arrangement. This is a significant difference between σ and π bonds; rotation around single (σ) bonds occurs easily because the end-to-end orbital overlap does not depend on the relative orientation of the orbitals on each atom in the bond. In other words, rotation around the internuclear axis does not change the extent to which the σ bonding orbitals overlap because the bonding electron density is symmetric about the axis. Rotation about the internuclear axis is much more difficult for multiple bonds; however, this would drastically alter the off-axis overlap of the π bonding orbitals, essentially breaking the π bond.



A diagram of a carbon atom with two balloon-like purple orbitals labeled, “sp” arranged in a linear fashion around it is shown. Four red balloon-like orbitals are aligned in pairs in the y and z axes around the carbon and are labeled, “unhybridized p orbital,” and, “Second unhybridized p orbital.”

Figure **11.5.3**: Diagram of the two linear sp hybrid orbitals of a carbon atom, which lie in a straight line, and the two unhybridized p orbitals at perpendicular angles.

In molecules with sp hybrid orbitals, two unhybridized p orbitals remain on the atom (Figure **11.5.3**). We find this situation in acetylene, H−C≡C−H, which is a linear molecule. The sp hybrid orbitals of the two carbon atoms overlap end to end to form a σ bond between the carbon atoms (Figure **11.5.4**). The remaining *sp* orbitals form σ bonds with hydrogen atoms. The two unhybridized *p* orbitals per carbon are positioned such that they overlap side by side and, hence, form two π bonds. The two carbon atoms of acetylene are thus bound together by one σ bond and two π bonds, giving a triple bond.





Figure **11.5.4**: (a) In the acetylene molecule, C_2H_2, there are two C–H σ bonds and a C≡C triple bond involving one C–C σ bond and two C–C π bonds. The dashed lines, each connecting two lobes, indicate the side-by-side overlap of the four unhybridized p orbitals. (b) This shows the overall outline of the bonds in C_2H_2. The two lobes of each of the π bonds are positioned across from each other around the line of the C–C σ bond.

Two diagrams are shown and labeled, “a” and “b.” Diagram a shows two carbon atoms with two purple balloon-like orbitals arranged in a plane around each of them, and four red balloon-like orbitals arranged along the y and z axes perpendicular to the plane of the molecule. There is an overlap of two of the purple orbitals in between the two carbon atoms. The other two purple orbitals that face the outside of the molecule are shown interacting with spherical blue orbitals from two hydrogen atoms. Diagram b depicts a similar image to diagram a, but the red, vertical orbitals are interacting above and below and to the front and back of the plane of the molecule to form two areas labeled, “One pi bond,” and, “Second pi bond,” each respectively.

Hybridization involves only σ bonds, lone pairs of electrons, and single unpaired electrons (radicals). Structures that account for these features describe the correct hybridization of the atoms. However, many structures also include resonance forms. Remember that resonance forms occur when various arrangements of π bonds are possible. Since the arrangement of π bonds involves only the unhybridized orbitals, resonance does not influence the assignment of hybridization.

For example, molecule benzene has two resonance forms (Figure **11.5.5**). We can use either of these forms to determine that each of the carbon atoms is bonded to three other atoms with no lone pairs, so the correct hybridization is sp^2. The electrons in the unhybridized *p* orbitals form π bonds. Neither resonance structure completely describes the electrons in the π bonds. They are not located in one position or the other, but in reality are delocalized throughout the ring. Valence bond theory does not easily address delocalization. Bonding in molecules with resonance forms is better described by molecular orbital theory.



A diagram is shown that is made up of two Lewis structures connected by a double ended arrow. The left image shows six carbon atoms bonded together with alternating double and single bonds to form a six-sided ring. Each carbon is also bonded to a hydrogen atom by a single bond. The right image shows the same structure, but the double and single bonds in between the carbon atoms have changed positions.

Figure **11.5.5**: Each carbon atom in benzene, C_6H_6, is sp^2 hybridized, independently of which resonance form is considered. The electrons in the π bonds are not located in one set of p orbitals or the other, but rather delocalized throughout the molecule.

✔ Example 11.5.1: Assignment of Hybridization Involving Resonance

Some acid rain results from the reaction of sulfur dioxide with atmospheric water vapor, followed by the formation of sulfuric acid. Sulfur dioxide, $\mathbf{SO_2}$, is a major component of volcanic gases as well as a product of the combustion of sulfur-containing coal. What is the hybridization of the $\boldsymbol{S}$ atom in $\mathbf{SO_2}$?

Solution

The resonance structures of $\mathbf{SO_2}$ are



Two Lewis structures connected by a double-ended arrow are shown. The left structure shows a sulfur atom with one lone pair of electrons and a positive sign which is single bonded on one side to an oxygen atom with three lone pairs of electrons and a negative sign. The sulfur atom is double bonded on the other side to another oxygen atom with two lone pairs of electrons. The right-hand structure is the same as the left except that the position of the double bonded oxygen atom is switched. In both structures the attached oxygen atoms form an acute angle in terms of the sulfur atom.

The sulfur atom is surrounded by two bonds and one lone pair of electrons in either resonance structure. Therefore, the electron-pair geometry is trigonal planar, and the hybridization of the sulfur atom is sp^2.

? Exercise 11.5.1

Another acid in acid rain is nitric acid, HNO_3, which is produced by the reaction of nitrogen dioxide, NO_2, with atmospheric water vapor. What is the hybridization of the nitrogen atom in NO_2? (Note: the lone electron on nitrogen occupies a hybridized orbital just as a lone pair would.)

Answer

sp^2

Summary

Multiple bonds consist of a σ bond located along the axis between two atoms and one or two π bonds. The σ bonds are usually formed by the overlap of hybridized atomic orbitals, while the π bonds are formed by the side-by-side overlap of unhybridized orbitals. Resonance occurs when there are multiple unhybridized orbitals with the appropriate alignment to overlap, so the placement of π bonds can vary.

11.5: Overlap of Hybrid Orbitals is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.


- **8.4: Multiple Bonds** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

11.6: Molecular Orbital Theory

Learning Objectives

- Outline the basic quantum-mechanical approach to deriving molecular orbitals from atomic orbitals
- Describe traits of bonding and antibonding molecular orbitals
- Calculate bond orders based on molecular electron configurations
- Write molecular electron configurations for first- and second-row diatomic molecules
- Relate these electron configurations to the molecules' stabilities and magnetic properties

For almost every covalent molecule that exists, we can now draw the Lewis structure, predict the electron-pair geometry, predict the molecular geometry, and come close to predicting bond angles. However, one of the most important molecules we know, the oxygen molecule O_2, presents a problem with respect to its Lewis structure. We would write the following Lewis structure for O_2:



A Lewis structure is shown. It is made up of two oxygen atoms, each with two lone pairs of electrons, bonded together with a double bond.

This electronic structure adheres to all the rules governing Lewis theory. There is an O=O double bond, and each oxygen atom has eight electrons around it. However, this picture is at odds with the magnetic behavior of oxygen. By itself, O_2 is not magnetic, but it is attracted to magnetic fields. Thus, when we pour liquid oxygen past a strong magnet, it collects between the poles of the magnet and defies gravity. Such attraction to a magnetic field is called paramagnetism, and it arises in molecules that have unpaired electrons. And yet, the Lewis structure of O_2 indicates that all electrons are paired. How do we account for this discrepancy?

Magnetic susceptibility measures the force experienced by a substance in a magnetic field. When we compare the weight of a sample to the weight measured in a magnetic field (Figure **11.6.1**), paramagnetic samples that are attracted to the magnet will appear heavier because of the force exerted by the magnetic field. We can calculate the number of unpaired electrons based on the increase in weight.




Figure **11.6.1**: A Gouy balance compares the mass of a sample in the presence of a magnetic field with the mass with the electromagnet turned off to determine the number of unpaired electrons in a sample.

Experiments show that each O_2 molecule has two unpaired electrons. The Lewis-structure model does not predict the presence of these two unpaired electrons. Unlike oxygen, the apparent weight of most molecules decreases slightly in the presence of an inhomogeneous magnetic field. Materials in which all of the electrons are paired are diamagnetic and weakly repel a magnetic field. Paramagnetic and diamagnetic materials do not act as permanent magnets. Only in the presence of an applied magnetic field do they demonstrate attraction or repulsion.



Video 11.6.1: Water, like most molecules, contains all paired electrons. Living things contain a large percentage of water, so they demonstrate diamagnetic behavior. If you place a frog near a sufficiently large magnet, it will levitate. You can see videos of diamagnetic floating frogs, strawberries, and more (levitating frog [www.youtube.com])

Molecular orbital theory (MO theory) provides an explanation of chemical bonding that accounts for the paramagnetism of the oxygen molecule. It also explains the bonding in a number of other molecules, such as violations of the octet rule and more molecules with more complicated bonding (beyond the scope of this text) that are difficult to describe with Lewis structures. Additionally, it provides a model for describing the energies of electrons in a molecule and the probable location of these electrons. Unlike valence bond theory, which uses hybrid orbitals that are assigned to one specific atom, MO theory uses the combination of atomic orbitals to yield molecular orbitals that are delocalized over the entire molecule rather than being localized on its constituent atoms. MO theory also helps us understand why some substances are electrical conductors, others are semiconductors, and still others are insulators. Table 11.6.1 summarizes the main points of the two complementary bonding theories. Both theories provide different, useful ways of describing molecular structure.

Table \(\PageIndex{1}\): Comparison of Bonding Theories

Valence Bond Theory	Molecular Orbital Theory
considers bonds as localized between one pair of atoms	considers electrons delocalized throughout the entire molecule
creates bonds from overlap of atomic orbitals (*s*, *p*, *d*…) and hybrid orbitals (*sp*, sp^2, sp^3…)	combines atomic orbitals to form molecular orbitals (σ, σ*, π, π*)
forms σ or π bonds	creates bonding and antibonding interactions based on which orbitals are filled
predicts molecular shape based on the number of regions of electron density	predicts the arrangement of electrons in molecules
needs multiple structures to describe resonance	

Molecular orbital theory describes the distribution of electrons in molecules in much the same way that the distribution of electrons in atoms is described using atomic orbitals. Using quantum mechanics, the behavior of an electron in a molecule is still described by a wave function, Ψ, analogous to the behavior in an atom. Just like electrons around isolated atoms, electrons around atoms in molecules are limited to discrete (quantized) energies. The region of space in which a valence electron in a molecule is likely to be found is called a molecular orbital (Ψ^2). Like an atomic orbital, a molecular orbital is full when it contains two electrons with opposite spin.

We will consider the molecular orbitals in molecules composed of two identical atoms (H_2 or Cl_2, for example). Such molecules are called homonuclear diatomic molecules. In these diatomic molecules, several types of molecular orbitals occur.

The mathematical process of combining atomic orbitals to generate molecular orbitals is called the linear combination of atomic orbitals (LCAO). The wave function describes the wavelike properties of an electron. Molecular orbitals are combinations of atomic orbital wave functions. Combining waves can lead to constructive interference, in which peaks line up with peaks, or

destructive interference, in which peaks line up with troughs (Figure **11.6.2**). In orbitals, the waves are three dimensional, and they combine with in-phase waves producing regions with a higher probability of electron density and out-of-phase waves producing nodes, or regions of no electron density.



Figure **11.6.2**: (a) When in-phase waves combine, constructive interference produces a wave with greater amplitude. (b) When out-of-phase waves combine, destructive interference produces a wave with less (or no) amplitude.

A pair of diagrams are shown and labeled, “a” and “b.” Diagram a shows two identical waves with two crests and two troughs. They are drawn one above the other with a plus sign in between and an equal sign to the right. To the right of the equal sign is a much taller wave with a same number of troughs and crests. Diagram b shows two waves with two crests and two troughs, but they are mirror images of one another rotated over a horizontal axis. They are drawn one above the other with a plus sign in between and an equal sign to the right. To the right of the equal sign is a flat line.

There are two types of molecular orbitals that can form from the overlap of two atomic *s* orbitals on adjacent atoms. The two types are illustrated in Figure **11.6.3**. The in-phase combination produces a lower energy σ_s molecular orbital (read as "sigma-s") in which most of the electron density is directly between the nuclei. The out-of-phase addition (which can also be thought of as subtracting the wave functions) produces a higher energy σ_s^* molecular orbital (read as "sigma-s-star") molecular orbital in which there is a node between the nuclei. The asterisk signifies that the orbital is an antibonding orbital. Electrons in a σ_s orbital are attracted by both nuclei at the same time and are more stable (of lower energy) than they would be in the isolated atoms. Adding electrons to these orbitals creates a force that holds the two nuclei together, so we call these orbitals bonding orbitals. Electrons in the σ_s^* orbitals are located well away from the region between the two nuclei. The attractive force between the nuclei and these electrons pulls the two nuclei apart. Hence, these orbitals are called antibonding orbitals. Electrons fill the lower-energy bonding orbital before the higher-energy antibonding orbital, just as they fill lower-energy atomic orbitals before they fill higher-energy atomic orbitals.





Figure **11.6.3**: Sigma (σ) and sigma-star (σ*) molecular orbitals are formed by the combination of two s atomic orbitals. The plus (+) signs indicate the locations of nuclei.

A diagram is shown that depicts a vertical upward-facing arrow that lies to the left of all the other portions of the diagram and is labeled, “E.” To the immediate right of the midpoint of the arrow are two circles each labeled with a positive sign, the letter S, and the phrase, “Atomic orbitals.” These are followed by a right-facing horizontal arrow that points to the same two circles labeled with plus signs, but they are now touching and are labeled, “Combine atomic orbitals.” Two right-facing arrows lead to the last portion of the diagram, one facing upward and one facing downward. The upper arrow is labeled, “Subtract,” and points to two oblong ovals labeled with plus signs, and the phrase, “Antibonding orbitals sigma subscript s superscript asterisk.” The lower arrow is labeled, “Add,” and points to an elongated oval with two plus signs that is labeled, “Bonding orbital sigma subscript s.” The heading over the last section of the diagram are the words, “Molecular orbitals.”

In *p* orbitals, the wave function gives rise to two lobes with opposite phases, analogous to how a two-dimensional wave has both parts above and below the average. We indicate the phases by shading the orbital lobes different colors. When orbital lobes of the same phase overlap, constructive wave interference increases the electron density. When regions of opposite phase overlap, the destructive wave interference decreases electron density and creates nodes. When *p* orbitals overlap end to end, they create σ and σ* orbitals (Figure **11.6.4**). If two atoms are located along the *x*-axis in a Cartesian coordinate system, the two p_x orbitals overlap

end to end and form σ_{px} (bonding) and σ^*_{px} (antibonding) (read as "sigma-p-x" and "sigma-p-x star," respectively). Just as with *s*-orbital overlap, the asterisk indicates the orbital with a node between the nuclei, which is a higher-energy, antibonding orbital.



Two horizontal rows of diagrams are shown. The upper diagram shows two equally-sized peanut-shaped orbitals with a plus sign in between them connected to a merged orbital diagram by a right facing arrow. The merged diagram has a much larger oval at the center and much smaller ovular orbitals on the edge. It is labeled, “sigma subscript p x.” The lower diagram shows two equally-sized peanut-shaped orbitals with a plus sign in between them connected to a split orbital diagram by a right facing arrow. The split diagram has a much larger oval at the outer ends and much smaller ovular orbitals on the inner edges. It is labeled, “sigma subscript p x superscript asterisk”.

Figure **11.6.4**: Combining wave functions of two p atomic orbitals along the internuclear axis creates two molecular orbitals, σp and σ^*_p.

The side-by-side overlap of two *p* orbitals gives rise to a pi (π) bonding molecular orbital and a \(π^*\) antibonding molecular orbital, as shown in Figure **11.6.5**. In valence bond theory, we describe π bonds as containing a nodal plane containing the internuclear axis and perpendicular to the lobes of the *p* orbitals, with electron density on either side of the node. In molecular orbital theory, we describe the π orbital by this same shape, and a π bond exists when this orbital contains electrons. Electrons in this orbital interact with both nuclei and help hold the two atoms together, making it a bonding orbital. For the out-of-phase combination, there are two nodal planes created, one along the internuclear axis and a perpendicular one between the nuclei.





Figure **11.6.5**: Side-by-side overlap of each two p orbitals results in the formation of two π molecular orbitals. Combining the out-of-phase orbitals results in an antibonding molecular orbital with two nodes. One contains the internuclear axis, and one is perpendicular to the axis. Combining the in-phase orbitals results in a bonding orbital. There is a node (blue plane) containing the internuclear axis with the two lobes of the orbital located above and below this node.

Two horizontal rows of diagrams are shown. The upper and lower diagrams both begin with two vertical peanut-shaped orbitals with a plus sign in between followed by a right-facing arrow. The upper diagram shows the same vertical peanut orbitals bending slightly away from one another and separated by a dotted line. It is labeled, “pi subscript p superscript asterisk.” The lower diagram shows the horizontal overlap of the two orbitals and is labeled, “pi subscript p.”

In the molecular orbitals of diatomic molecules, each atom also has two sets of *p* orbitals oriented side by side (p_y and p_z), so these four atomic orbitals combine pairwise to create two π orbitals and two π^* orbitals. The π_{py} and π^*_{py} orbitals are oriented at right angles to the π_{pz} and π^*_{pz} orbitals. Except for their orientation, the π_{py} and π_{pz} orbitals are identical and have the same energy; they are degenerate orbitals. The π^*_{py} and π^*_{pz} antibonding orbitals are also degenerate and identical except for their orientation. A total of six molecular orbitals results from the combination of the six atomic *p* orbitals in two atoms: σ_{px} and σ^*_{px}, π_{py} and π^*_{py}, π_{pz} and π^*_{pz}.

Example 11.6.1: Molecular Orbitals

Predict what type (if any) of molecular orbital would result from adding the wave functions so each pair of orbitals shown overlap. The orbitals are all similar in energy.



Three diagrams are shown and labeled “a,” “b,” and “c.” Diagram a shows two horizontal peanut-shaped orbitals laying side-by-side. They are labeled, “3 p subscript x and 3 p subscript x.” Diagram b shows one vertical and one horizontal peanut-shaped orbital which are at right angles to one another. They are labeled, “3 p subscript x and 3 p subscript y.” Diagram c shows two vertical peanut-shaped orbitals laying side-by-side and labeled, “3 p subscript y and 3 p subscript y.”

Solution

a. This is an in-phase combination, resulting in a σ_{3p} orbital
b. This will not result in a new orbital because the in-phase component (bottom) and out-of-phase component (top) cancel out. Only orbitals with the correct alignment can combine.
c. This is an out-of-phase combination, resulting in a π^*_{3p} orbital.

Exercise 11.6.1

Label the molecular orbital shown as σ or π, bonding or antibonding and indicate where the node occurs.



Two orbitals are shown lying end-to-end. Each has one enlarged and one small side. The small sides are facing one another

Answer

The orbital is located along the internuclear axis, so it is a σ orbital. There is a node bisecting the internuclear axis, so it is an antibonding orbital.



Two orbitals are shown lying end-to-end. Each has one enlarged and one small side. The small sides are facing one another and are separated by a vertical dotted line.

Application: Computational Chemistry in Drug Design

While the descriptions of bonding described in this chapter involve many theoretical concepts, they also have many practical, real-world applications. For example, drug design is an important field that uses our understanding of chemical bonding to develop pharmaceuticals. This interdisciplinary area of study uses biology (understanding diseases and how they operate) to identify specific targets, such as a binding site that is involved in a disease pathway. By modeling the structures of the binding site and potential drugs, computational chemists can predict which structures can fit together and how effectively they will bind (Figure **11.6.6**). Thousands of potential candidates can be narrowed down to a few of the most promising candidates. These candidate molecules are then carefully tested to determine side effects, how effectively they can be transported through

the body, and other factors. Dozens of important new pharmaceuticals have been discovered with the aid of computational chemistry, and new research projects are underway.




Figure 11.6.6: The molecule shown, HIV-1 protease, is an important target for pharmaceutical research. By designing molecules that bind to this protein, scientists are able to drastically inhibit the progress of the disease.

A diagram of a molecule is shown. The image shows a tangle of ribbon-like, intertwined, pink and green curling lines with a complex ball and stick model in the center.

Molecular Orbital Energy Diagrams

The relative energy levels of atomic and molecular orbitals are typically shown in a molecular orbital diagram (Figure 11.6.7). For a diatomic molecule, the atomic orbitals of one atom are shown on the left, and those of the other atom are shown on the right. Each horizontal line represents one orbital that can hold two electrons. The molecular orbitals formed by the combination of the atomic orbitals are shown in the center. Dashed lines show which of the atomic orbitals combine to form the molecular orbitals. For each pair of atomic orbitals that combine, one lower-energy (bonding) molecular orbital and one higher-energy (antibonding) orbital result. Thus we can see that combining the six 2*p* atomic orbitals results in three bonding orbitals (one σ and two π) and three antibonding orbitals (one σ* and two π*).




Figure 11.6.7: This is the molecular orbital diagram for the homonuclear diatomic Be_2^+, showing the molecular orbitals of the valence shell only. The molecular orbitals are filled in the same manner as atomic orbitals, using the Aufbau principle and Hund's rule.

A diagram is shown that has an upward-facing vertical arrow running along the left side labeled, "E." At the bottom center of the diagram is a horizontal line labeled, "sigma subscript 2 s," that has two vertical half arrows drawn on it, one facing up and one facing down. This line is connected to the right and left by upward-facing, dotted lines to two more horizontal lines, each labeled, "2 s." The line on the left has two vertical half arrows drawn on it, one facing up and one facing down while the line of the right has one half arrow facing up drawn on it. These two lines are connected by upward-facing dotted lines to another line in the center of the diagram, but further up from the first. It is labeled, "sigma subscript 2 s superscript asterisk." This horizontal line has one upward-facing vertical half-arrow drawn on it. Moving farther up the center of the diagram is a long horizontal line labeled, "sigma subscript 2 p subscript x," which lies below two horizontal lines. These two horizontal lines lie side-by-side, and labeled, "pi subscript 2 p subscript y," and, "pi subscript 2 p subscript z." Both the bottom and top lines are connected to the right and left by upward-facing, dotted lines to three more horizontal lines, each labeled, "2 p." These sets of lines are connected by upward-facing dotted lines to another single line and then pair of double lines in the center of the diagram, but farther up from the lower lines. They are labeled, "sigma subscript 2 p subscript x superscript asterisk," and, ""pi subscript 2 p subscript y superscript asterisk," and, "pi subscript 2 p subscript z superscript asterisk," respectively. The left and right sides of the diagram have headers that read, "Atomic orbitals," while the center is header reads "Molecular orbitals".

We predict the distribution of electrons in these molecular orbitals by filling the orbitals in the same way that we fill atomic orbitals, by the Aufbau principle. Lower-energy orbitals fill first, electrons spread out among degenerate orbitals before pairing, and each orbital can hold a maximum of two electrons with opposite spins (Figure 11.6.7). Just as we write electron configurations for atoms, we can write the molecular electronic configuration by listing the orbitals with superscripts indicating the number of electrons present. For clarity, we place parentheses around molecular orbitals with the same energy. In this case, each orbital is at a different energy, so parentheses separate each orbital. Thus we would expect a diatomic molecule or ion containing seven electrons (such as Be_2^+) would have the molecular electron configuration $(\sigma_{1s})^2(\sigma_{1s}^*)^2(\sigma_{2s})^2(\sigma_{2s}^*)^1$. It is common to omit the core electrons from molecular orbital diagrams and configurations and include only the valence electrons.

Bond Order

The filled molecular orbital diagram shows the number of electrons in both bonding and antibonding molecular orbitals. The net contribution of the electrons to the bond strength of a molecule is identified by determining the bond order that results from the filling of the molecular orbitals by electrons.

When using Lewis structures to describe the distribution of electrons in molecules, we define bond order as the number of bonding pairs of electrons between two atoms. Thus a single bond has a bond order of 1, a double bond has a bond order of 2, and a triple bond has a bond order of 3. We define bond order differently when we use the molecular orbital description of the distribution of electrons, but the resulting bond order is usually the same. The MO technique is more accurate and can handle cases when the Lewis structure method fails, but both methods describe the same phenomenon.

In the molecular orbital model, an electron contributes to a bonding interaction if it occupies a bonding orbital and it contributes to an antibonding interaction if it occupies an antibonding orbital. The bond order is calculated by subtracting the destabilizing (antibonding) electrons from the stabilizing (bonding) electrons. Since a bond consists of two electrons, we divide by two to get the bond order. We can determine bond order with the following equation:

$$\text{bond order} = \frac{(\text{number of bonding electrons}) - (\text{number of antibonding electrons})}{2}$$

The order of a covalent bond is a guide to its strength; a bond between two given atoms becomes stronger as the bond order increases. If the distribution of electrons in the molecular orbitals between two atoms is such that the resulting bond would have a bond order of zero, a stable bond does not form. We next look at some specific examples of MO diagrams and bond orders.

Bonding in Diatomic Molecules

A dihydrogen molecule (H_2) forms from two hydrogen atoms. When the atomic orbitals of the two atoms combine, the electrons occupy the molecular orbital of lowest energy, the σ_{1s} bonding orbital. A dihydrogen molecule, H_2, readily forms because the energy of a H_2 molecule is lower than that of two H atoms. The σ_{1s} orbital that contains both electrons is lower in energy than either of the two 1*s* atomic orbitals.

A molecular orbital can hold two electrons, so both electrons in the H_2 molecule are in the σ_{1s} bonding orbital; the electron configuration is $(\sigma_{1s})^2$. We represent this configuration by a molecular orbital energy diagram (Figure **11.6.8**) in which a single upward arrow indicates one electron in an orbital, and two (upward and downward) arrows indicate two electrons of opposite spin.




Figure **11.6.8**: The molecular orbital energy diagram predicts that H_2 will be a stable molecule with lower energy than the separated atoms.

A diagram is shown that has an upward-facing vertical arrow running along the left side labeled “E.” At the bottom center of the diagram is a horizontal line labeled, “sigma subscript 1 s,” that has two vertical half arrows drawn on it, one facing up and one facing down. This line is connected to the right and left by upward-facing, dotted lines to two more horizontal lines, each labeled, “1 s,” and each with one vertical half-arrow facing up drawn on it. These two lines are connected by upward-facing dotted lines to another line in the center of the diagram, but farther up from the first, and labeled, “sigma subscript 1 s superscript asterisk.” The left and right sides of the diagram have headers that read, ”Atomic orbitals,” while the center header reads, “Molecular orbitals.” The bottom left and right are labeled “H” while the center is labeled “H subscript 2.”

A dihydrogen molecule contains two bonding electrons and no antibonding electrons so we have

$$\text{bond order in } H_2 = \frac{(2-0)}{2} = 1$$

Because the bond order for the H–H bond is equal to 1, the bond is a single bond.

A helium atom has two electrons, both of which are in its 1*s* orbital. Two helium atoms do not combine to form a dihelium molecule, He_2, with four electrons, because the stabilizing effect of the two electrons in the lower-energy bonding orbital would be offset by the destabilizing effect of the two electrons in the higher-energy antibonding molecular orbital. We would write the hypothetical electron configuration of He_2 as $(\sigma_{1s})^2(\sigma^*_{1s})^2$ as in Figure **11.6.9**. The net energy change would be zero, so there is no driving force for helium atoms to form the diatomic molecule. In fact, helium exists as discrete atoms rather than as diatomic molecules. The bond order in a hypothetical dihelium molecule would be zero.

$$\text{bond order in } He_2 = \frac{(2-2)}{2} = 0$$

A bond order of zero indicates that no bond is formed between two atoms.




Figure **11.6.9**: The molecular orbital energy diagram predicts that He_2 will not be a stable molecule, since it has equal numbers of bonding and antibonding electrons.

A diagram is shown that has an upward-facing vertical arrow running along the left side labeled, “E.” At the bottom center of the diagram is a horizontal line labeled, “sigma subscript 1 s,” that has two vertical half arrows drawn on it, one facing up and one facing down. This line is connected to the right and left by upward-facing, dotted lines to two more horizontal lines, each labeled, “1 s,” and each with one vertical half-arrow facing up and one facing down drawn on it. These two lines are connected by upward-facing dotted lines to another line in the center of the diagram, but farther up from the first, and labeled, “sigma subscript 1 s superscript asterisk.” This line has one upward-facing and one downward-facing vertical arrow drawn on it. The left and right sides of the diagram have headers that read, “Atomic orbitals,” while the center header reads, “Molecular orbitals.” The bottom left and right are labeled, “H e,” while the center is labeled, “H e subscript 2.”

The Diatomic Molecules of the Second Period

Eight possible homonuclear diatomic molecules might be formed by the atoms of the second period of the periodic table: Li_2, Be_2, B_2, C_2, N_2, O_2, F_2, and Ne_2. However, we can predict that the Be_2 molecule and the Ne_2 molecule would not be stable. We can see this by a consideration of the molecular electron configurations (Table **11.6.1**).

Table **11.6.1**: Electron Configuration and Bond Order for Molecular Orbitals in Homonuclear Diatomic Molecules of Period Two Elements

Molecule	Electron Configuration	Bond Order
Li_2	$(\sigma_{2s})^2$	1
Be_2 (unstable)	$(\sigma_{2s})^2(\sigma^*_{2s})^2$	0
B_2	$(\sigma_{2s})^2(\sigma^*_{2s})^2(\pi_{2py},\ \pi_{2pz})^2$	1
C_2	$(\sigma_{2s})^2(\sigma^*_{2s})^2(\pi_{2py},\ \pi_{2pz})^4$	2
N_2	$(\sigma_{2s})^2(\sigma^*_{2s})^2(\pi_{2py},\ \pi_{2pz})^4(\sigma_{2px})^2$	3
O_2	$(\sigma_{2s})^2(\sigma^*_{2s})^2(\sigma_{2px})^2(\pi_{2py},\ \pi_{2pz})^4(\pi^*_{2py},\pi^*_{2pz})^2$	2
F_2	$(\sigma_{2s})^2(\sigma^*_{2s})^2(\sigma_{2px})^2(\pi_{2py},\ \pi_{2pz})^4(\pi^*_{2py},\ \pi^*_{2pz})^4$	1
Ne_2 (unstable)	$(\sigma_{2s})^2(\sigma^*_{2s})^2(\sigma_{2px})^2(\pi_{2py},\ \pi_{2pz})^4(\pi^*_{2py},\pi^*_{2pz})^4(\sigma^*_{2px})^2$	0

We predict valence molecular orbital electron configurations just as we predict electron configurations of atoms. Valence electrons are assigned to valence molecular orbitals with the lowest possible energies. Consistent with Hund’s rule, whenever there are two or more degenerate molecular orbitals, electrons fill each orbital of that type singly before any pairing of electrons takes place.




Figure **11.6.10**: This shows the MO diagrams for each homonuclear diatomic molecule in the second period. The orbital energies decrease across the period as the effective nuclear charge increases and atomic radius decreases. Between N_2 and O_2, the order of the orbitals changes.

A graph is shown in which the y-axis is labeled, “E,” and appears as a vertical, upward-facing arrow. Across the top, the graph reads, “L i subscript 2,” “B e subscript 2,” “B subscript 2,” “C subscript 2,” “N subscript 2,” “O subscript 2,” “F subscript 2,” and “Ne subscript 2.” Directly below each of these element terms is a single pink line, and all lines are connected to one another by a dashed line, to create an overall line that decreases in height as it moves from left to right across the graph. This line is labeled, “sigma subscript 2 p x superscript asterisk”. Directly below each of these lines is a set of two pink lines, and all lines are connected to one another by a dashed line, to create an overall line that decreases in height as it moves from left to right across the graph. It is consistently lower than the first line. This line is labeled, “pi subscript 2 p y superscript asterisk,” and, “pi subscript 2 p z superscript asterisk.” Directly below each of these double lines is a single pink line, and all lines are connected to one another by a dashed line, to create an overall line that decreases in height as it moves from left to right across the graph. It has a distinctive drop at the label, “O subscript 2.” This line is labeled, “sigma subscript 2 p x.” Directly below each of these lines is a set of two pink lines, and all lines are connected to one another by a dashed line to create an overall line that decreases very slightly in height as it moves from left to right across the graph. It is consistently lower than the third line until it reaches the point labeled, “O subscript 2.” This line is labeled, “pi subscript 2 p y,” and, “pi subscript 2 p z.” Directly below each of these lines is a single blue line, and all lines are connected to one another by a dashed line to create an overall line that decreases in height as it moves from left to right across the graph. This line is labeled, “sigma subscript 2 s superscript asterisk.” Finally, directly below each of these lines is a single blue line, and all lines are connected to one another by a dashed line to create an overall line that decreases in height as it moves from left to right across the graph. This line is labeled. “sigma subscript 2 s.”

As we saw in valence bond theory, σ bonds are generally more stable than π bonds formed from degenerate atomic orbitals. Similarly, in molecular orbital theory, σ orbitals are usually more stable than π orbitals. However, this is not always the case. The MOs for the valence orbitals of the second period are shown in Figure **11.6.10**. Looking at Ne_2 molecular orbitals, we see that the order is consistent with the generic diagram shown in the previous section. However, for atoms with three or fewer electrons in the *p* orbitals (Li through N) we observe a different pattern, in which the σ_p orbital is higher in energy than the π_p set. Obtain the molecular orbital diagram for a homonuclear diatomic ion by adding or subtracting electrons from the diagram for the neutral molecule.

This switch in orbital ordering occurs because of a phenomenon called s-p mixing. s-p mixing does not create new orbitals; it merely influences the energies of the existing molecular orbitals. The σ_s wavefunction mathematically combines with the σ_p wavefunction, with the result that the σ_s orbital becomes more stable, and the σ_p orbital becomes less stable (Figure **11.6.11**). Similarly, the antibonding orbitals also undergo s-p mixing, with the σ_{s*} becoming more stable and the σ_{p*} becoming less stable.




Figure **11.6.11**: Without mixing, the MO pattern occurs as expected, with the σ_p orbital lower in energy than the σ_p orbitals. When s-p mixing occurs, the orbitals shift as shown, with the σ_p orbital higher in energy than the π_p orbitals.

A diagram is shown. At the bottom left of the diagram is a horizontal line that is connected to the right and left by upward-facing, dotted lines to two more horizontal lines. Those two lines are connected by upward-facing dotted lines to another line in the center of the diagram but farther up from the first. Each of the bottom two central lines has a vertical downward-facing arrow. Above this structure is a horizontal line that is connected to the right and left by upward-facing, dotted lines to two sets of three horizontal lines and those two lines are connected by upward-facing dotted lines to another line in the center of the diagram, but further up from the first. In between the horizontal lines of this structure are two pairs of horizontal lines that are above the first line but below the second and connected by dotted lines to the side horizontal lines. The bottom and top central lines each have an upward-facing vertical arrow. These two structures are redrawn on the right side of the diagram, but this time, the central lines of the bottom structure are moved downward in relation to the side lines. The upper portion of the structure has its central lines shifted upward in relation to the side lines. This structure also shows the bottom line appearing above the set of two lines.

s-p mixing occurs when the *s* and *p* orbitals have similar energies. The energy difference between 2*s* and 2*p* orbitals in O, F, and Ne is greater than that in Li, Be, B, C, and N. Because of this, O_2, F_2, and Ne exhibit negligible s-p mixing (not sufficient to change the energy ordering), and their MO diagrams follow the normal pattern, as shown in Figure **11.6.7**. All of the other period 2 diatomic molecules do have s-p mixing, which leads to the pattern where the σ_p orbital is raised above the π_p set.

Using the MO diagrams shown in Figure **11.6.11**, we can add in the electrons and determine the molecular electron configuration and bond order for each of the diatomic molecules. As shown in Table **11.6.1**, Be_2 and Ne_2 molecules would have a bond order of 0, and these molecules do not exist.

The combination of two lithium atoms to form a lithium molecule, Li_2, is analogous to the formation of H_2, but the atomic orbitals involved are the valence 2*s* orbitals. Each of the two lithium atoms has one valence electron. Hence, we have two valence electrons available for the σ_{2s} bonding molecular orbital. Because both valence electrons would be in a bonding orbital, we would predict the Li_2 molecule to be stable. The molecule is, in fact, present in an appreciable concentration in lithium vapor at temperatures near the boiling point of the element. All of the other molecules in Table **11.6.1** with a bond order greater than zero are also known.

The O_2 molecule has enough electrons to half fill the (π^*_{2py}, π^*_{2pz}) level. We expect the two electrons that occupy these two degenerate orbitals to be unpaired, and this molecular electronic configuration for O_2 is in accord with the fact that the oxygen molecule has two unpaired electrons (Figure **11.6.10**). The presence of two unpaired electrons has proved to be difficult to explain using Lewis structures, but the molecular orbital theory explains it quite well. In fact, the unpaired electrons of the oxygen molecule provide a strong piece of support for the molecular orbital theory.

Application: Band Theory in Extended Systems

When two identical atomic orbitals on different atoms combine, two molecular orbitals result (e.g., H_2 in Figure 11.6.8). The bonding orbital is lower in energy than the original atomic orbitals because the atomic orbitals are in-phase in the molecular orbital. The antibonding orbital is higher in energy than the original atomic orbitals because the atomic orbitals are out-of-phase.

In a solid, similar things happen, but on a much larger scale. Remember that even in a small sample there are a huge number of atoms (typically > 10^{23} atoms), and therefore a huge number of atomic orbitals that may be combined into molecular orbitals. When *N* valence atomic orbitals, all of the same energy and each containing one (1) electron, are combined, *N*/2 (filled) bonding orbitals and *N*/2 (empty) antibonding orbitals will result. Each bonding orbital will show an energy lowering as the atomic orbitals are *mostly* in-phase, but each of the bonding orbitals will be a little different and have slightly different energies. The antibonding orbitals will show an increase in energy as the atomic orbitals are *mostly* out-of-phase, but each of the antibonding orbitals will also be a little different and have slightly different energies. The allowed energy levels for all the bonding orbitals are so close together that they form a band, called the valence band. Likewise, all the antibonding orbitals are very close together and form a band, called the conduction band. Figure 11.6.12) shows the bands for three important classes of materials: insulators, semiconductors, and conductors.




Figure 11.6.12: Molecular orbitals in solids are so closely spaced that they are described as bands. The valence band is lower in energy and the conduction band is higher in energy. The type of solid is determined by the size of the "band gap" between the valence and conduction bands. Only a very small amount of energy is required to move electrons from the valence band to the conduction band in a conductor, and so they conduct electricity well. In an insulator, the band gap is large, so that very few electrons move, and they are poor conductors of electricity. Semiconductors are in between: they conduct electricity better than insulators, but not as well as conductors.

This figure shows three diagrams. The first is labeled, "Insulator," and it consists of two boxes. The "conduction" box is above and the "valence" box is below. A large gap marked by 4 dashed lines contains a double-headed arrow. One head pointing towards the "conduction box" and the other towards the "valence" box. The arrow is labeled, "Band gap." The second diagram is similar to the first, but the band gap is about half as large. This diagram is labeled, "Semiconductor." The third diagram is similar to the other two, but the band gap is about a fifth that of the "Semiconductor" diagram. This diagram is labeled, "Conductor."

In order to conduct electricity, electrons must move from the filled valence band to the empty conduction band where they can move throughout the solid. The size of the band gap, or the energy difference between the top of the valence band and the bottom of the conduction band, determines how easy it is to move electrons between the bands. Only a small amount of energy is required in a conductor because the band gap is very small. This small energy difference is "easy" to overcome, so they are good conductors of electricity. In an insulator, the band gap is so "large" that very few electrons move into the conduction band; as a result, insulators are poor conductors of electricity. Semiconductors conduct electricity when "moderate" amounts of energy are provided to move electrons out of the valence band and into the conduction band. Semiconductors, such as silicon, are found in many electronics.

Semiconductors are used in devices such as computers, smartphones, and solar cells. Solar cells produce electricity when light provides the energy to move electrons out of the valence band. The electricity that is generated may then be used to power a light or tool, or it can be stored for later use by charging a battery. As of December 2014, up to 46% of the energy in sunlight could be converted into electricity using solar cells.

Example 11.6.2: Molecular Orbital Diagrams, Bond Order, and Number of Unpaired Electrons

Draw the molecular orbital diagram for the oxygen molecule, O_2. From this diagram, calculate the bond order for O_2. How does this diagram account for the paramagnetism of O_2?

Solution

We draw a molecular orbital energy diagram similar to that shown in Figure **11.6.7**. Each oxygen atom contributes six electrons, so the diagram appears as shown in Figure **11.6.7**.




Figure **11.6.13**: The molecular orbital energy diagram for O_2 predicts two unpaired electrons.

We calculate the bond order as

$$O_2 = \frac{(8-4)}{2} = 2$$

Oxygen's paramagnetism is explained by the presence of two unpaired electrons in the $(\pi_{2py}, \pi_{2pz})^*$ molecular orbitals.

Exercise 11.6.2

The main component of air is N_2. From the molecular orbital diagram of N_2, predict its bond order and whether it is diamagnetic or paramagnetic.

Answer

N_2 has a bond order of 3 and is diamagnetic.

Example 11.6.3: Ion Predictions with MO Diagrams

Give the molecular orbital configuration for the valence electrons in C_2^{2-}. Will this ion be stable?

Solution

Looking at the appropriate MO diagram, we see that the π orbitals are lower in energy than the σ_p orbital. The valence electron configuration for C_2 is

$$(\sigma_{2s})^2(\sigma^*_{2s})^2(\pi_{2py}, \pi_{2pz})^4.$$

Adding two more electrons to generate the C_2^{2-} anion will give a valence electron configuration of

$$(\sigma_{2s})^2(\sigma^*_{2s})^2(\pi_{2py},\ \pi_{2pz})^4(\sigma_{2px})^2$$

Since this has six more bonding electrons than antibonding, the bond order will be 3, and the ion should be stable.

? Exercise 11.6.3

How many unpaired electrons would be present on a Be_2^{2-} ion? Would it be paramagnetic or diamagnetic?

Answer

two, paramagnetic

Key Concepts and Summary

Molecular orbital (MO) theory describes the behavior of electrons in a molecule in terms of combinations of the atomic wave functions. The resulting molecular orbitals may extend over all the atoms in the molecule. Bonding molecular orbitals are formed by in-phase combinations of atomic wave functions, and electrons in these orbitals stabilize a molecule. Antibonding molecular orbitals result from out-of-phase combinations of atomic wave functions and electrons in these orbitals make a molecule less stable. Molecular orbitals located along an internuclear axis are called σ MOs. They can be formed from *s* orbitals or from *p* orbitals oriented in an end-to-end fashion. Molecular orbitals formed from *p* orbitals oriented in a side-by-side fashion have electron density on opposite sides of the internuclear axis and are called π orbitals.

We can describe the electronic structure of diatomic molecules by applying molecular orbital theory to the valence electrons of the atoms. Electrons fill molecular orbitals following the same rules that apply to filling atomic orbitals; Hund's rule and the Aufbau principle tell us that lower-energy orbitals will fill first, electrons will spread out before they pair up, and each orbital can hold a maximum of two electrons with opposite spins. Materials with unpaired electrons are paramagnetic and attracted to a magnetic field, while those with all-paired electrons are diamagnetic and repelled by a magnetic field. Correctly predicting the magnetic properties of molecules is in advantage of molecular orbital theory over Lewis structures and valence bond theory.

11.6: Molecular Orbital Theory is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **8.5: Molecular Orbital Theory** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

11.7: End of Chapter Problems

1. Explain why the HOH molecule is bent, whereas the HBeH molecule is linear.

Answer

The placement of the two sets of unpaired electrons in water forces the bonds to assume a tetrahedral arrangement, and the resulting HOH molecule is bent. The HBeH molecule (in which Be has only two electrons to bond with the two electrons from the hydrogens) must have the electron pairs as far from one another as possible and is therefore linear.

2. What feature of a Lewis structure can be used to tell if a molecule's (or ion's) electron-pair geometry and molecular structure will be identical?
3. Explain the difference between electron-pair geometry and molecular structure.

Answer

Space must be provided for each pair of electrons whether they are in a bond or are present as lone pairs. Electron-pair geometry considers the placement of all electrons. Molecular structure considers only the bonding-pair geometry.

4. Why is the H–N–H angle in NH_3 smaller than the H–C–H bond angle in CH_4? Why is the H–N–H angle in NH_4^+ identical to the H–C–H bond angle in CH_4?
5. Explain how a molecule that contains polar bonds can be nonpolar.

Answer

As long as the polar bonds are compensated (for example. two identical atoms are found directly across the central atom from one another), the molecule can be nonpolar.

6. As a general rule, MX_n molecules (where M represents a central atom and X represents terminal atoms; n = 2 – 5) are polar if there is one or more lone pairs of electrons on M. NH_3 (M = N, X = H, n = 3) is an example. There are two molecular structures with lone pairs that are exceptions to this rule. What are they?
7. Predict the electron pair geometry and the molecular structure of each of the following molecules or ions:

    a. SF_6
    b. PCl_5
    c. (c) BeH_2
    d. CH_3^+

Answer

a. Both the electron geometry and the molecular structure are octahedral.

b. Both the electron geometry and the molecular structure are trigonal bipyramid.

c. Both the electron geometry and the molecular structure are linear.

d. Both the electron geometry and the molecular structure are trigonal planar.

8. Identify the electron pair geometry and the molecular structure of each of the following molecules or ions:

    a. IF_6^+
    b. CF_4
    c. (c) BF_3
    d. SiF_5^-
    e. $BeCl_2$

9. What are the electron-pair geometry and the molecular structure of each of the following molecules or ions?

    a. ClF_5
    b. ClO_2^-
    c. (c) $TeCl_4^{2-}$

d. PCl_3
e. SeF_4
f. $\mathbf{PH_2^-}$

Answer

a. electron-pair geometry: octahedral, molecular structure: square pyramidal; b. electron-pair geometry: tetrahedral, molecular structure: bent; c. electron-pair geometry: octahedral, molecular structure: square planar; d. electron-pair geometry: tetrahedral, molecular structure: trigonal pyramidal;e. electron-pair geometry: trigonal bypyramidal, molecular structure: seesaw; f. electron-pair geometry: tetrahedral, molecular structure: bent (109°)

10. Predict the electron pair geometry and the molecular structure of each of the following ions:

a. H_3O^+
b. $\mathbf{PCl_4^-}$
c. (c) $\mathbf{SnCl_3^-}$
d. $\mathbf{BrCl_4^-}$
e. ICl_3
f. XeF_4
g. (g) SF_2

11. Identify the electron pair geometry and the molecular structure of each of the following molecules:

a. ClNO (N is the central atom)
b. CS_2
c. (c) Cl_2CO (C is the central atom)
d. Cl_2SO (S is the central atom)
e. SO_2F_2 (S is the central atom)
f. XeO_2F_2 (Xe is the central atom)
g. $\mathbf{ClOF_2^+}$ (Cl is the central atom)

Answer

a. electron-pair geometry: trigonal planar, molecular structure: bent (120°); b. electron-pair geometry: linear, molecular structure: linear; c. electron-pair geometry: trigonal planar, molecular structure: trigonal planar;d. electron-pair geometry: tetrahedral, molecular structure: trigonal pyramidal; e. electron-pair geometry: tetrahedral, molecular structure: tetrahedral; f. electron-pair geometry: trigonal bipyramidal, molecular structure: seesaw; g electron-pair geometry: tetrahedral, molecular structure: trigonal pyramidal

12. Predict the electron pair geometry and the molecular structure of each of the following:

a. IOF_5 (I is the central atom)
b. $POCl_3$ (P is the central atom)
c. (c) Cl_2SeO (Se is the central atom)
d. $ClSO^+$ (S is the central atom)
e. F_2SO (S is the central atom)
f. $\mathbf{NO_2^-}$
g. (g) $\mathbf{SiO_4^{4-}}$

13. Which of the following molecules and ions contain polar bonds? Which of these molecules and ions have dipole moments?

a. ClF_5
b. $\mathbf{ClO_2^-}$
c. (c) $\mathbf{TeCl_4^{2-}}$
d. PCl_3
e. SeF_4
f. $\mathbf{PH_2^-}$
g. (g) XeF_2

Answer

All of these molecules and ions contain polar bonds. Only ClF_5, $\mathbf{ClO_2^-}$, PCl_3, SeF_4, and $\mathbf{PH_2^-}$ have dipole moments.

14. Which of the molecules and ions in Exercise contain polar bonds? Which of these molecules and ions have dipole moments?
    a. H_3O^+
    b. $\mathbf{PCl_4^-}$
    c. (c) $\mathbf{SnCl_3^-}$
    d. $\mathbf{BrCl_4^-}$
    e. ICl_3
    f. XeF_4
    g. (g) SF_2
15. Which of the following molecules have dipole moments?
    a. CS_2
    b. SeS_2
16. (c) CCl_2F_2
    a. PCl_3 (P is the central atom)
    b. ClNO (N is the central atom)

Answer

SeS_2, CCl_2F_2, PCl_3, and ClNO all have dipole moments.

16. Identify the molecules with a dipole moment:
    a. SF_4
    b. CF_4
    c. Cl_2CCBr_2
    d. CH_3Cl
    e. H_2CO
17. The molecule XF_3 has a dipole moment. Is X boron or phosphorus?

Answer

P

18. The molecule XCl_2 has a dipole moment. Is X beryllium or sulfur?
19. Is the Cl_2BBCl_2 molecule polar or nonpolar?

Answer


nonpolar

20. There are three possible structures for PCl_2F_3 with phosphorus as the central atom. Draw them and discuss how measurements of dipole moments could help distinguish among them.
21. Describe the molecular structure around the indicated atom or atoms:
    a. the sulfur atom in sulfuric acid, H_2SO_4 [$(HO)_2SO_2$]
    b. the chlorine atom in chloric acid, $HClO_3$ [$HOClO_2$]
    c. the oxygen atom in hydrogen peroxide, HOOH
    d. the nitrogen atom in nitric acid, HNO_3 [$HONO_2$]
    e. the oxygen atom in the OH group in nitric acid, HNO_3 [$HONO_2$]
    f. the central oxygen atom in the ozone molecule, O_3
    g. each of the carbon atoms in propyne, CH_3CCH
    h. the carbon atom in Freon, CCl_2F_2
    i. each of the carbon atoms in allene, H_2CCCH_2


Answer


a. tetrahedral; b. trigonal pyramidal; c. bent (109°); d. trigonal planar; e. bent (109°); f. bent (109°); g. CH_3CCH tetrahedral, CH_3CCH linear; h. tetrahedral; i. H_2CCCH_2 linear, H_2CCCH_2 trigonal planar


22. Draw the Lewis structures and predict the shape of each compound or ion:
    a. CO_2
    b. $\mathbf{NO_2^-}$
    c. (c) SO_3
    d. $\mathbf{SO_3^{2-}}$
23. A molecule with the formula AB_2, in which A and B represent different atoms, could have one of three different shapes. Sketch and name the three different shapes that this molecule might have. Give an example of a molecule or ion for each shape.



    A molecule with the formula AB_3, in which A and B represent different atoms, could have one of three different shapes. Sketch and name the three different shapes that this molecule might have. Give an example of a molecule or ion that has each shape.
24. Draw the Lewis electron dot structures for these molecules, including resonance structures where appropriate:
    a. $\mathbf{CS_3^{2-}}$
    b. CS_2
    c. (c) CS
25. predict the molecular shapes for $\mathbf{CS_3^{2-}}$ and CS_2 and explain how you arrived at your predictions

    a. 

    b. 

    c. 


Answer

$\mathbf{CS_3^{2-}}$ includes three regions of electron density (all are bonds with no lone pairs); the shape is trigonal planar; CS_2 has only two regions of electron density (all bonds with no lone pairs); the shape is linear

What is the molecular structure of the stable form of FNO_2? (N is the central atom.)

A compound with a molar mass of about 42 g/mol contains 85.7% carbon and 14.3% hydrogen. What is its molecular structure?

The Lewis structure is made from three units, but the atoms must be rearranged:



Use the simulation to perform the following exercises for a two-atom molecule:

22. Adjust the electronegativity value so the bond dipole is pointing toward B. Then determine what the electronegativity values must be to switch the dipole so that it points toward A.
23. With a partial positive charge on A, turn on the electric field and describe what happens.
24. (c) With a small partial negative charge on A, turn on the electric field and describe what happens.
25. Reset all, and then with a large partial negative charge on A, turn on the electric field and describe what happens.
26. Use the simulation to perform the following exercises for a real molecule. You may need to rotate the molecules in three dimensions to see certain dipoles.
27. Sketch the bond dipoles and molecular dipole (if any) for O_3. Explain your observations.
28. Look at the bond dipoles for NH_3. Use these dipoles to predict whether N or H is more electronegative.
29. (c) Predict whether there should be a molecular dipole for NH_3 and, if so, in which direction it will point. Check the molecular dipole box to test your hypothesis.
30. The molecular dipole points away from the hydrogen atoms.

Use the Molecule Shape simulator to build a molecule. Starting with the central atom, click on the double bond to add one double bond. Then add one single bond and one lone pair. Rotate the molecule to observe the complete geometry. Name the electron group geometry and molecular structure and predict the bond angle. Then click the check boxes at the bottom and right of the simulator to check your answers.

Use the Molecule Shape simulator to explore real molecules. On the Real Molecules tab, select H_2O. Switch between the "real" and "model" modes. Explain the difference observed.

The structures are very similar. In the model mode, each electron group occupies the same amount of space, so the bond angle is shown as 109.5°. In the "real" mode, the lone pairs are larger, causing the hydrogens to be compressed. This leads to the smaller angle of 104.5°.

Use the Molecule Shape simulator to explore real molecules. On the Real Molecules tab, select "model" mode and S_2O. What is the model bond angle? Explain whether the "real" bond angle should be larger or smaller than the ideal model angle.

31. Explain how σ and π bonds are similar and how they are different.


Answer

Similarities: Both types of bonds result from overlap of atomic orbitals on adjacent atoms and contain a maximum of two electrons. **Differences**: σ bonds are stronger and result from end-to-end overlap and all single bonds are σ bonds; π bonds between the same two atoms are weaker because they result from side-by-side overlap, and multiple bonds contain one or more π bonds (in addition to a σ bond).

32. Draw a curve that describes the energy of a system with H and Cl atoms at varying distances. Then, find the minimum energy of this curve two ways.
    a. Use the bond energy to calculate the energy for one single HCl bond (Hint: How many bonds are in a mole?)
    b. Use the enthalpy of reaction and the bond energies for H_2 and Cl_2 to solve for the energy of one mole of HCl bonds.

$$H_{2(g)} + Cl_{2(g)} \rightleftharpoons 2HCl_{(g)} \quad \Delta H^\circ_{rxn} = -184.7\ kJ/mol \tag{11.7.1}$$

Answer



When H and Cl are separate (the x axis) the energy is at a particular value. As they approach, it decreases to a minimum at 127 pm (the bond distance), and then it increases sharply as you get closer.

a. (a) H–Cl431 kJ/mol 427kJmol×mol6.022×1023bonds×1000 JkJ=7.09×10−19
b. (b) We know Hess's law related to bond energies: ΔH°=ΣΔH∘BDE(broken)−ΣΔH∘BDE(formed) We are given the enthalpy of reaction

$$-184.7kJ/mol = (\Delta H \circ BDE(H–H) + \Delta H \circ BDE(Cl–Cl)) - (2\Delta H \circ BDE(H–Cl)) \tag{11.7.2}$$

$$H–His436kJ/molandCl–Clis243 \tag{11.7.3}$$

$$-184.7kJ/mol = (436 + 243) - 2x = 679 - 2x \tag{11.7.4}$$

$$2x = 863.7kJ/mol \tag{11.7.5}$$

$$x = 432\ kJ/mol \tag{11.7.6}$$

This is very close to the value from part (a).

33. Explain why bonds occur at specific average bond distances instead of the atoms approaching each other infinitely close.

Answer

The specific average bond distance is the distance with the lowest energy. At distances less than the bond distance, the positive charges on the two nuclei repel each other, and the overall energy increases.

34. Use valence bond theory to explain the bonding in F_2, HF, and ClBr. Sketch the overlap of the atomic orbitals involved in the bonds.


Answer

The single bond present in each molecule results from overlap of the relevant orbitals: F 2*p* orbitals in F_2, the H 1*s* and F 2*p* orbitals in HF, and the Cl 3*p* orbital and Br 4*p* orbital in ClBr.

35. Use valence bond theory to explain the bonding in O_2. Sketch the overlap of the atomic orbitals involved in the bonds in O_2.

Answer


Bonding: One σ bond and one π bond. The *s* orbitals are filled and do not overlap. The *p* orbitals overlap along the axis to form a σ bond and side by side to form the π bond.



36. How many σ and π bonds are present in the molecule HCN?

Answer


H–C≡N has two σ (H–C and C–N) and two π (making the CN triple bond).



37. A friend tells you N_2 has three π bonds due to overlap of the three *p*-orbitals on each N atom. Do you agree?

Answer

No, two of the *p* orbitals (one on each N) will be oriented end-to-end and will form a σ bond.




38. Draw the Lewis structures for CO_2 and CO, and predict the number of σ and π bonds for each molecule.

a. CO_2
b. CO

Answer

(a) 2 σ 2 π;



(b) 1 σ 2 π;



39. why is the concept of hybridization required in valence bond theory?

Answer

Hybridization is introduced to explain the geometry of bonding orbitals in valance bond theory.

40. Give the shape that describes each hybrid orbital set:
    a. sp^2
    b. sp^3d
    c. sp
    d. sp^3d^2

41. Explain why a carbon atom cannot form five bonds using sp^3d hybrid orbitals.

Answer

There are no *d* orbitals in the valence shell of carbon.


42. What is the hybridization of the central atom in each of the following?
    a. BeH_2
    b. SF_6
    c. $\mathbf{PO_4^{3-}}$
    d. PCl_5

43. A molecule with the formula AB_3 could have one of four different shapes. Give the shape and the hybridization of the central A atom for each.

Answer

trigonal planar, sp^2; trigonal pyramidal (one lone pair on A) sp^3; T-shaped (two lone pairs on A sp^3d, or (three lone pairs on A) sp^3d^2

44. Methionine, $CH_3SCH_2CH_2CH(NH_2)CO_2H$, is an amino acid found in proteins. Draw a Lewis structure of this compound. What is the hybridization type of each carbon, oxygen, the nitrogen, and the sulfur?


A Lewis structure is shown in which a carbon atom is single bonded to three hydrogen atoms and single bonded to a sulfur atom with two lone pairs of electrons. The sulfur atom is attached to a chain of four singly bonded carbon atoms, the first two of which are single bonded to two hydrogen atoms each, and the third of which is single bonded to a hydrogen atom and single bonded to a nitrogen atom which has one lone electron pair. The nitrogen atom is also single bonded to two hydrogen atoms. The fourth andfinal carbon in the chain is double bonded to an oxygen with two lone pairs of electrons and single bonded to an oxygen atom with two lone pairs of electrons. The second oxygen atom is single bonded to a hydrogen atom.

45. Sulfuric acid is manufactured by a series of reactions represented by the following equations:

$$\mathrm{S_8}(s) + 8\,\mathrm{O_2}(g) \longrightarrow 8\,\mathrm{SO_2}(g)$$

$$2\,\mathrm{SO_2}(g) + \mathrm{O_2}(g) \longrightarrow 2\,\mathrm{SO_3}(g)$$

$$\mathrm{SO_3}(g) + \mathrm{H_2O}(l) \longrightarrow \mathrm{H_2SO_4}(l)$$

Draw a Lewis structure, predict the molecular geometry by VSEPR, and determine the hybridization of sulfur for the following:

(a) circular S_8 molecule


(b) SO_2 molecule

(c) SO_3 molecule


(d) H_2SO_4 molecule (the hydrogen atoms are bonded to oxygen atoms)

Answer


(a) Each S has a bent (109°) geometry, sp^3


A Lewis structure is shown in which eight sulfur atoms, each with two lone pairs of eletrons, are single bonded together into an eight-sided ring.


(b) Bent (120°), sp^2


Two Lewis structure are shown, connected by a double-ended arrow. The left structure shows a sulfur atom with one lone pair of electrons double bonded to an oxygen atom with two lone pairs of electrons on the left and single bonded to an oxygen atom with three lone pairs of electrons on the right. The right structure shows the same molecule, except that the double bonded oxygen is on the right side of the sulfur and the single bonded oxygen is to the left of the sulfur.

(c) Trigonal planar, sp^2


A Lewis structure of a sulfur atom singly bonded to two oxygen atoms, each with three lone pairs of electrons, and double bonded to a third oxygen atom with two lone pairs of electrons is shown.

(d) Tetrahedral, sp^3


A Lewis structure is shown in which a sulfur atom is single bonded to four oxygen atoms. Two of the oxygen atoms have three lone pairs of electrons while the other two each have two lone pairs of electrons and are each singly bonded to a hydrogen atom.

Two important industrial chemicals, ethene, C_2H_4, and propene, C_3H_6, are produced by the steam (or thermal) cracking process:


$$2\,C_3H_8(g) \longrightarrow C_2H_4(g) + C_3H_6(g) + CH_4(g) + H_2(g)$$

46. For each of the four carbon compounds, do the following:
    a. Draw a Lewis structure.
    b. Predict the geometry about the carbon atom.
    c. Determine the hybridization of each type of carbon atom.
47. For many years after they were discovered, it was believed that the noble gases could not form compounds. Now we know that belief to be incorrect. A mixture of xenon and fluorine gases, confined in a quartz bulb and placed on a windowsill, is found to slowly produce a white solid. Analysis of the compound indicates that it contains 77.55% Xe and 22.45% F by mass.
    a. What is the formula of the compound?
    b. Write a Lewis structure for the compound.
    c. Predict the shape of the molecules of the compound.
    d. What hybridization is consistent with the shape you predicted?

Answer


(a) XeF_2

(b)


A Lewis structure is shown in which a xenon atom that has three lone pairs of electrons is single bonded to two fluorine atoms, each of which has three lone pairs of electrons.

(c) linear (d) sp^3d


48. Consider nitrous acid, HNO_2 (HONO).
    a. Write a Lewis structure.
    b. What are the electron pair and molecular geometries of the internal oxygen and nitrogen atoms in the HNO_2 molecule?
    c. What is the hybridization on the internal oxygen and nitrogen atoms in HNO_2?
49. Strike-anywhere matches contain a layer of $KClO_3$ and a layer of P_4S_3. The heat produced by the friction of striking the match causes these two compounds to react vigorously, which sets fire to the wooden stem of the match. $KClO_3$ contains the ClO_3^- ion. P_4S_3 is an unusual molecule with the skeletal structure.


A Lewis structure is shown in which three phosphorus atoms are single bonded together to form a triangle. Each phosphorus is bonded to a sulfur atom by a vertical single bond and each of those sulfur atoms is then bonded to a single phosphorus atom so that a six-sided ring is created with a sulfur in the middle.

a. Write Lewis structures for P_4S_3 and the ClO_3^- ion.
b. Describe the geometry about the P atoms, the S atom, and the Cl atom in these species.
c. Assign a hybridization to the P atoms, the S atom, and the Cl atom in these species.
d. Determine the oxidation states and formal charge of the atoms in P_4S_3 and the ClO_3^- ion.


Answer

(a)



Two Lewis structure are shown, the left of which depicts three phosphorus atoms single bonded together to form a triangle. Each phosphorus is bonded to a sulfur atom by a vertical single bond and each of those sulfur atoms is then bonded to a single phosphorus atom so that a six-sided ring is created with a sulfur in the middle. Each sulfur atom in this structure has two lone pairs of electrons while each phosphorus has one lone pair. The second Lewis structure shows a chlorine atom with one lone pair of electrons single bonded to three oxygen atoms, each of which has three lone pairs of electrons.

(b) P atoms, trigonal pyramidal; S atoms, bent, with two lone pairs; Cl atoms, trigonal pyramidal; (c) Hybridization about P, S, and Cl is, in all cases, sp^3; (d) Oxidation states P +1, S $-1\frac{1}{3}$, Cl +5, O –2. Formal charges: P 0; S 0; Cl +2: O –1

50. Identify the hybridization of each carbon atom in the following molecule. (The arrangement of atoms is given; you need to determine how many bonds connect each pair of atoms.)


A Lewis structure is shown that is missing all of its bonds. Six carbon atoms form a chain. There are three hydrogen atoms located around the first carbon, two located around the second, one located near the fifth, and two located around the sixth carbon.

51. Write Lewis structures for NF_3 and PF_5. On the basis of hybrid orbitals, explain the fact that NF_3, PF_3, and PF_5 are stable molecules, but NF_5 does not exist.


Two Lewis structures are shown. The left structure shows a nitrogen atom with one lone pair of electrons single bonded to three fluorine atoms, each of which has three lone pairs of electrons. The right structure shows a phosphorus atoms single bonded to five fluorine atoms, each of which has three lone pairs of electrons.

Answer

Phosphorus and nitrogen can form sp^3 hybrids to form three bonds and hold one lone pair in PF_3 and NF_3, respectively. However, nitrogen has no valence *d* orbitals, so it cannot form a set of sp^3d hybrid orbitals to bind five fluorine atoms in NF_5. Phosphorus has *d* orbitals and can bind five fluorine atoms with sp^3d hybrid orbitals in PF_5.

52. In addition to NF_3, two other fluoro derivatives of nitrogen are known: N_2F_4 and N_2F_2. What shapes do you predict for these two molecules? What is the hybridization for the nitrogen in each molecule?

53. The bond energy of a C–C single bond averages 347 kJ mol^{-1}; that of a C≡C triple bond averages 839 kJ mol^{-1}. Explain why the triple bond is not three times as strong as a single bond.


Answer

A triple bond consists of one σ bond and two π bonds. A σ bond is stronger than a π bond due to greater overlap.

54. For the carbonate ion, CO_3^{2-}, draw all of the resonance structures. Identify which orbitals overlap to create each bond.
55. A useful solvent that will dissolve salts as well as organic compounds is the compound acetonitrile, H_3CCN. It is present in paint strippers.
    a. Write the Lewis structure for acetonitrile, and indicate the direction of the dipole moment in the molecule.
    b. Identify the hybrid orbitals used by the carbon atoms in the molecule to form σ bonds.
    c. Describe the atomic orbitals that form the π bonds in the molecule. Note that it is not necessary to hybridize the nitrogen atom.

Answer

(a)


A Lewis structure is shown in which a carbon atom is attached by single bonds to three hydrogen atoms. It is also attached by a single bond to a carbon atom that is triple bonded to a nitrogen atom with one lone electron pair. Below the structure is a right facing arrow with its head near the nitrogen and its tail, which looks like a plus sign, located near the carbon atoms. The arrow is labeled, “dipole moment.”

(b) The terminal carbon atom uses sp^3 hybrid orbitals, while the central carbon atom is sp hybridized. (c) Each of the two π bonds is formed by overlap of a 2p orbital on carbon and a nitrogen 2p orbital.

56. For the molecule allene, $\mathbf{H_2C=C=CH_2}$, give the hybridization of each carbon atom. Will the hydrogen atoms be in the same plane or perpendicular planes?
57. Identify the hybridization of the central atom in each of the following molecules and ions that contain multiple bonds:
    a. ClNO (N is the central atom)
    b. CS_2
    c. Cl_2CO (C is the central atom)
    d. Cl_2SO (S is the central atom)
    e. SO_2F_2 (S is the central atom)
    f. XeO_2F_2 (Xe is the central atom)
    g. $\mathbf{ClOF_2^+}$ (Cl is the central atom)

Answer

(a) sp^2; (b) sp; (c) sp^2; (d) sp^3; (e) sp^3; (f) sp^3d; (g) sp^3


58. Describe the molecular geometry and hybridization of the N, P, or S atoms in each of the following compounds.
    a. H_3PO_4, phosphoric acid, used in cola soft drinks
    b. NH_4NO_3, ammonium nitrate, a fertilizer and explosive
    c. S_2Cl_2, disulfur dichloride, used in vulcanizing rubber
    d. $K_4[O_3POPO_3]$, potassium pyrophosphate, an ingredient in some toothpastes

59. For each of the following molecules, indicate the hybridization requested and whether or not the electrons will be delocalized:
    a. ozone (O_3) central O hybridization
    b. carbon dioxide (CO_2) central C hybridization
    c. nitrogen dioxide (NO_2) central N hybridization
    d. phosphate ion ($\mathbf{PO_4^{3-}}$) central P hybridization


Answer

(a) sp^2, delocalized; (b) sp, localized; (c) sp^2, delocalized; (d) sp^3, delocalized


60. For each of the following structures, determine the hybridization requested and whether the electrons will be delocalized:
    a. Hybridization of each carbon


A Lewis structure is shown in which a carbon atom is single bonded to three hydrogen atoms and a second carbon atom. This second carbon atom is, in turn, double bonded to an oxygen atom with two lone pairs of electrons. The second carbon atom is also single bonded to another carbon atom that is single bonded to three hydrogen atoms.

    b. Hybridization of sulfur



A Lewis structure is shown in which a sulfur atom with two lone pairs of electrons and a positive sign is double bonded to an oxygen with two lone pairs of electrons. The sulfur atom is also single bonded to an oxygen with three lone pairs of electrons with a negative sign. It is drawn in an angular shape.

    c. All atoms


A Lewis structure is shown in which a hexagonal ring structure is made up of five carbon atoms and one nitrogen atom with a lone pair of electrons. There are alternating double and single bonds in between each carbon atom. Each carbon atom is also single bonded to one hydrogen atom.

61. Draw the orbital diagram for carbon in CO_2 showing how many carbon atom electrons are in each orbital.

Answer



Each of the four electrons is in a separate orbital and overlaps with an electron on an oxygen atom.

62. Sketch the distribution of electron density in the bonding and antibonding molecular orbitals formed from two *s* orbitals and from two *p* orbitals.
63. How are the following similar, and how do they differ?
    a. σ molecular orbitals and π molecular orbitals
    b. ψ for an atomic orbital and ψ for a molecular orbital
    c. bonding orbitals and antibonding orbitals

Answer

(a) Similarities: Both are bonding orbitals that can contain a maximum of two electrons. Differences: σ orbitals are end-to-end combinations of atomic orbitals, whereas π orbitals are formed by side-by-side overlap of orbitals. (b) Similarities: Both are quantum-mechanical constructs that represent the probability of finding the electron about the atom or the molecule. Differences: ψ for an atomic orbital describes the behavior of only one electron at a time based on the atom. For a molecule, ψ represents a mathematical combination of atomic orbitals. (c) Similarities: Both are orbitals that can contain two electrons. Differences: Bonding orbitals result in holding two or more atoms together. Antibonding orbitals have the effect of destabilizing any bonding that has occurred.

64. If molecular orbitals are created by combining five atomic orbitals from atom A and five atomic orbitals from atom B combine, how many molecular orbitals will result?
65. Can a molecule with an odd number of electrons ever be diamagnetic? Explain why or why not.

Answer

An odd number of electrons can never be paired, regardless of the arrangement of the molecular orbitals. It will always be paramagnetic.

66. Can a molecule with an even number of electrons ever be paramagnetic? Explain why or why not.
67. Why are bonding molecular orbitals lower in energy than the parent atomic orbitals?

Answer

Bonding orbitals have electron density in close proximity to more than one nucleus. The interaction between the bonding positively charged nuclei and negatively charged electrons stabilizes the system.

68. Calculate the bond order for an ion with this configuration:

$$(\sigma_{2s})^2(\sigma^*_{2s})^2(\sigma_{2px})^2(\pi_{2py},\ \pi_{2pz})^4(\pi^*_{2py},\ \pi^*_{2pz})^3$$

69. Explain why an electron in the bonding molecular orbital in the H_2 molecule has a lower energy than an electron in the 1*s* atomic orbital of either of the separated hydrogen atoms.
70. The pairing of the two bonding electrons lowers the energy of the system relative to the energy of the nonbonded electrons. Predict the valence electron molecular orbital configurations for the following, and state whether they will be stable or unstable ions.
    a. Na_2^{2+}
    b. Mg_2^{2+}
    c. Al_2^{2+}
    d. Si_2^{2+}
    e. P_2^{2+}
    f. S_2^{2+}

g. $\mathbf{F_2^{2+}}$
h. $\mathbf{Ar_2^{2+}}$

71. Determine the bond order of each member of the following groups, and determine which member of each group is predicted by the molecular orbital model to have the strongest bond.
    a. (a) H_2, $\mathbf{H_2^+}$, $\mathbf{H_2^-}$
    b. (b) O_2, $\mathbf{O_2^{2+}}$, $\mathbf{O_2^{2-}}$
    c. (c) Li_2, $\mathbf{Be_2^+}$, Be_2
    d. (d) F_2, $\mathbf{F_2^+}$, $\mathbf{F_2^-}$
    e. (e) N_2, $\mathbf{N_2^+}$, $\mathbf{N_2^-}$

Answer

(a) H_2 bond order = 1, $\mathbf{H_2^+}$ bond order = 0.5, $\mathbf{H_2^-}$ bond order = 0.5, strongest bond is H_2; (b) O_2 bond order = 2, $\mathbf{O_2^{2+}}$ bond order = 3; $\mathbf{O_2^{2-}}$ bond order = 1, strongest bond is $\mathbf{O_2^{2+}}$; (c) Li_2 bond order = 1, $\mathbf{Be_2^+}$ bond order = 0.5, Be_2 bond order = 0, strongest bond is $\mathbf{Li_2}$;(d) F_2 bond order = 1, $\mathbf{F_2^+}$ bond order = 1.5, $\mathbf{F_2^-}$ bond order = 0.5, strongest bond is $\mathbf{F_2^+}$; (e) N_2 bond order = 3, $\mathbf{N_2^+}$ bond order = 2.5, $\mathbf{N_2^-}$ bond order = 2.5, strongest bond is N_2

72. For the first ionization energy for an N_2 molecule, what molecular orbital is the electron removed from?
73. Compare the atomic and molecular orbital diagrams to identify the member of each of the following pairs that has the highest first ionization energy (the most tightly bound electron) in the gas phase:
    a. H and H_2
    b. N and N_2
    c. O and O_2
    d. C and C_2
    e. B and B_2

Answer

(a) H_2; (b) N_2; (c) O; (d) C_2; (e) B_2

74. Which of the period 2 homonuclear diatomic molecules are predicted to be paramagnetic?
75. A friend tells you that the 2*s* orbital for fluorine starts off at a much lower energy than the 2*s* orbital for lithium, so the resulting σ_{2s} molecular orbital in F_2 is more stable than in Li_2. Do you agree?

Answer

Yes, fluorine is a smaller atom than Li, so atoms in the 2*s* orbital are closer to the nucleus and more stable.

76. True or false: Boron contains $2s^2 2p^1$ valence electrons, so only one *p* orbital is needed to form molecular orbitals.
77. What charge would be needed on F_2 to generate an ion with a bond order of 2?

Answer

2+

78. Predict whether the MO diagram for S_2 would show s-p mixing or not.
79. Explain why $\mathbf{N_2^{2+}}$ is diamagnetic, while $\mathbf{O_2^{4+}}$, which has the same number of valence electrons, is paramagnetic.

Answer

N_2 has s-p mixing, so the π orbitals are the last filled in $\mathbf{N_2^{2+}}$. O_2 does not have s-p mixing, so the σ_p orbital fills before the π orbitals.

80. Using the MO diagrams, predict the bond order for the stronger bond in each pair:
    a. B_2 or $\mathbf{B_2^+}$
    b. F_2 or $\mathbf{F_2^+}$

c. O_2 or O_2^{2+}
d. C_2^+ or C_2^-

11.7: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

12: Liquids and Solids

12.1: Intermolecular forces
12.2: Properties of Liquids
12.3: Phase Changes
12.4: Phase diagram
12.5: The Solid State of Matter
12.6: Lattice Structure in Crystalline Solids
12.7: End of Chapter Problems

12: Liquids and Solids is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

12.1: Intermolecular forces

Learning Objectives

- Describe the types of intermolecular forces possible between atoms or molecules in condensed phases (dispersion forces, dipole-dipole attractions, and hydrogen bonding)
- Identify the types of intermolecular forces experienced by specific molecules based on their structures
- Explain the relation between the intermolecular forces present within a substance and the temperatures associated with changes in its physical state

As was the case for gaseous substances, the kinetic molecular theory may be used to explain the behavior of solids and liquids. In the following description, the term *particle* will be used to refer to an atom, molecule, or ion. Note that we will use the popular phrase "intermolecular attraction" to refer to attractive forces between the particles of a substance, regardless of whether these particles are molecules, atoms, or ions.

Consider these two aspects of the molecular-level environments in solid, liquid, and gaseous matter:

- Particles in a solid are tightly packed together and often arranged in a regular pattern; in a liquid, they are close together with no regular arrangement; in a gas, they are far apart with no regular arrangement.
- Particles in a solid vibrate about fixed positions and do not generally move in relation to one another; in a liquid, they move past each other but remain in essentially constant contact; in a gas, they move independently of one another except when they collide.

The differences in the properties of a solid, liquid, or gas reflect the strengths of the attractive forces between the atoms, molecules, or ions that make up each phase. The phase in which a substance exists depends on the relative extents of its intermolecular forces (IMFs) and the kinetic energies (KE) of its molecules. IMFs are the various forces of attraction that may exist between the atoms and molecules of a substance due to electrostatic phenomena, as will be detailed in this module. These forces serve to hold particles close together, whereas the particles' KE provides the energy required to overcome the attractive forces and thus increase the distance between particles. Figure **12.1.1** illustrates how changes in physical state may be induced by changing the temperature, hence, the average KE, of a given substance.




Figure **12.1.1**: Transitions between solid, liquid, and gaseous states of a substance occur when conditions of temperature or pressure favor the associated changes in intermolecular forces. (Note: The space between particles in the gas phase is much greater than shown.)

Three sealed flasks are labeled, "Crystalline solid," "Liquid," and "Gas," from left to right. The first flask holds a cube composed of small spheres sitting on the bottom while the second flask shows a lot of small spheres in the bottom that are spaced a small distance apart from one another and have lines around them to indicate motion. The third flask shows a few spheres spread far from one another with larger lines to indicate motion. There is a right-facing arrow that spans the top of all three flasks. The arrow is labeled, "Increasing K E (temperature)." There is a left-facing arrow that spans the bottom of all three flasks. The arrow is labeled, "Increasing I M F."

As an example of the processes depicted in this figure, consider a sample of water. When gaseous water is cooled sufficiently, the attractions between H_2O molecules will be capable of holding them together when they come into contact with each other; the gas

condenses, forming liquid H_2O. For example, liquid water forms on the outside of a cold glass as the water vapor in the air is cooled by the cold glass, as seen in Figure **12.1.2**.



Figure **12.1.2**: Condensation forms when water vapor in the air is cooled enough to form liquid water, such as (a) on the outside of a cold beverage glass or (b) in the form of fog. (credit a: modification of work by Jenny Downing; credit b: modification of work by Cory Zanker)

Image a shows a brown colored beverage in a glass with condensation on the outside. Image b shows a body of water with fog hovering above the surface of the water.

We can also liquefy many gases by compressing them, if the temperature is not too high. The increased pressure brings the molecules of a gas closer together, such that the attractions between the molecules become strong relative to their KE. Consequently, they form liquids. Butane, C_4H_{10}, is the fuel used in disposable lighters and is a gas at standard temperature and pressure. Inside the lighter's fuel compartment, the butane is compressed to a pressure that results in its condensation to the liquid state, as shown in Figure **12.1.3**.



Figure **12.1.3**: Gaseous butane is compressed within the storage compartment of a disposable lighter, resulting in its condensation to the liquid state. (credit: modification of work by "Sam-Cat"/Flickr)

Finally, if the temperature of a liquid becomes sufficiently low, or the pressure on the liquid becomes sufficiently high, the molecules of the liquid no longer have enough KE to overcome the IMF between them, and a solid forms. A more thorough discussion of these and other changes of state, or phase transitions, is provided in a later module of this chapter.

Forces between Molecules

Under appropriate conditions, the attractions between all gas molecules will cause them to form liquids or solids. This is due to intermolecular forces, not *intra*molecular forces. *Intra*molecular forces are those *within* the molecule that keep the molecule

together, for example, the bonds between the atoms. *Inter*molecular forces are the attractions *between* molecules, which determine many of the physical properties of a substance. Figure 12.1.4 illustrates these different molecular forces. The strengths of these attractive forces vary widely, though usually the IMFs between small molecules are weak compared to the intramolecular forces that bond atoms together within a molecule. For example, to overcome the IMFs in one mole of liquid HCl and convert it into gaseous HCl requires only about 17 kilojoules. However, to break the covalent bonds between the hydrogen and chlorine atoms in one mole of HCl requires about 25 times more energy—430 kilojoules.




Figure 12.1.4: Intramolecular forces keep a molecule intact. Intermolecular forces hold multiple molecules together and determine many of a substance's properties.

An image is shown in which two molecules composed of a green sphere labeled "C l" connected on the right to a white sphere labeled "H" are near one another with a dotted line labeled "Intermolecular force (weak)" drawn between them. A line connects the two spheres in each molecule and the line is labeled "Intramolecular force (strong)."

All of the attractive forces between neutral atoms and molecules are known as van der Waals forces, although they are usually referred to more informally as intermolecular attraction. We will consider the various types of IMFs in the next three sections of this module.

Dispersion Forces

One of the three van der Waals forces is present in all condensed phases, regardless of the nature of the atoms or molecules composing the substance. This attractive force is called the London dispersion force in honor of German-born American physicist Fritz London who, in 1928, first explained it. This force is often referred to as simply the dispersion force. Because the electrons of an atom or molecule are in constant motion (or, alternatively, the electron's location is subject to quantum-mechanical variability), at any moment in time, an atom or molecule can develop a temporary, instantaneous dipole if its electrons are distributed asymmetrically. The presence of this dipole can, in turn, distort the electrons of a neighboring atom or molecule, producing an induced dipole. These two rapidly fluctuating, temporary dipoles thus result in a relatively weak electrostatic attraction between the species—a so-called dispersion force like that illustrated in Figure 12.1.5.




Figure 12.1.5: Dispersion forces result from the formation of temporary dipoles, as illustrated here for two nonpolar diatomic molecules.

Two pairs of molecules are shown where each molecule has one larger blue side labeled "delta sign, negative sign" and a smaller red side labeled "delta sign, positive sign." Toward the middle of the both molecules, but still on each distinct side, is a black dot. Between the two images is a dotted line labeled, "Attractive force." In the first image, the red and blue sides are labeled, "Unequal distribution of electrons." Below both images are brackets. The brackets are labeled, "Temporary dipoles."

Dispersion forces that develop between atoms in different molecules can attract the two molecules to each other. The forces are relatively weak, however, and become significant only when the molecules are very close. Larger and heavier atoms and molecules exhibit stronger dispersion forces than do smaller and lighter atoms and molecules. F_2 and Cl_2 are gases at room temperature

(reflecting weaker attractive forces); Br_2 is a liquid, and I_2 is a solid (reflecting stronger attractive forces). Trends in observed melting and boiling points for the halogens clearly demonstrate this effect, as seen in Table **12.1.1**.

Table **12.1.1**: Melting and Boiling Points of the Halogens

Halogen	Molar Mass	Atomic Radius	Melting Point	Boiling Point
fluorine, F_2	38 g/mol	72 pm	53 K	85 K
chlorine, Cl_2	71 g/mol	99 pm	172 K	238 K
bromine, Br_2	160 g/mol	114 pm	266 K	332 K
iodine, I_2	254 g/mol	133 pm	387 K	457 K
astatine, At_2	420 g/mol	150 pm	575 K	610 K

The increase in melting and boiling points with increasing atomic/molecular size may be rationalized by considering how the strength of dispersion forces is affected by the electronic structure of the atoms or molecules in the substance. In a larger atom, the valence electrons are, on average, farther from the nuclei than in a smaller atom. Thus, they are less tightly held and can more easily form the temporary dipoles that produce the attraction. The measure of how easy or difficult it is for another electrostatic charge (for example, a nearby ion or polar molecule) to distort a molecule's charge distribution (its electron cloud) is known as polarizability. A molecule that has a charge cloud that is easily distorted is said to be very polarizable and will have large dispersion forces; one with a charge cloud that is difficult to distort is not very polarizable and will have small dispersion forces.

Example 12.1.1: London Forces and Their Effects


Order the following compounds of a group 14 element and hydrogen from lowest to highest boiling point: CH_4, SiH_4, GeH_4, and SnH_4. Explain your reasoning.

Solution

Applying the skills acquired in the chapter on chemical bonding and molecular geometry, all of these compounds are predicted to be nonpolar, so they may experience only dispersion forces: the smaller the molecule, the less polarizable and the weaker the dispersion forces; the larger the molecule, the larger the dispersion forces. The molar masses of CH_4, SiH_4, GeH_4, and SnH_4 are approximately 16 g/mol, 32 g/mol, 77 g/mol, and 123 g/mol, respectively. Therefore, CH_4 is expected to have the lowest boiling point and SnH_4 the highest boiling point. The ordering from lowest to highest boiling point is expected to be

$$CH_4 < SiH_4 < GeH_4 < SnH_4$$

A graph of the actual boiling points of these compounds versus the period of the group 14 elements shows this prediction to be correct:



A line graph, titled “Carbon Family,” is shown where the y-axis is labeled “Temperature, (degree sign C)” and has values of “negative 200” to “negative 40” from bottom to top in increments of 20. The x-axis is labeled “Period” and has values of “0” to “5” in increments of 1. The first point on the graph is labeled “C H subscript 4” and is at point “2, negative 160.” The second point on the graph is labeled “S i H subscript 4” and is at point “3, negative 120” while the third point on the graph is labeled “G e H subscript 4” and is at point “4, negative 100.” The fourth point on the graph is labeled “S n H subscript 4” and is at point “5, negative 60.”

? Exercise 12.1.1

Order the following hydrocarbons from lowest to highest boiling point: C_2H_6, C_3H_8, and C_4H_{10}.

Answer

All of these compounds are nonpolar and only have London dispersion forces: the larger the molecule, the larger the dispersion forces and the higher the boiling point. The ordering from lowest to highest boiling point is therefore

$$C_2H_6 < C_3H_8 < C_4H_{10}.$$

The shapes of molecules also affect the magnitudes of the dispersion forces between them. For example, boiling points for the isomers *n*-pentane, isopentane, and neopentane (shown in Figure **12.1.6**) are 36 °C, 27 °C, and 9.5 °C, respectively. Even though these compounds are composed of molecules with the same chemical formula, C_5H_{12}, the difference in boiling points suggests that dispersion forces in the liquid phase are different, being greatest for *n*-pentane and least for neopentane. The elongated shape of *n*-pentane provides a greater surface area available for contact between molecules, resulting in correspondingly stronger dispersion forces. The more compact shape of isopentane offers a smaller surface area available for intermolecular contact and, therefore, weaker dispersion forces. Neopentane molecules are the most compact of the three, offering the least available surface area for intermolecular contact and, hence, the weakest dispersion forces. This behavior is analogous to the connections that may be formed between strips of VELCRO brand fasteners: the greater the area of the strip’s contact, the stronger the connection.




Figure **12.1.6**: The strength of the dispersion forces increases with the contact area between molecules, as demonstrated by the boiling points of these pentane isomers.

Three images of molecules are shown. The first shows a cluster of large, gray spheres each bonded together and to several smaller, white spheres. There is a gray, jagged line and then the mirror image of the first cluster of spheres is shown. Above these two clusters is the label, “Small contact area, weakest attraction,” and below is the label, “neopentane boiling point: 9.5 degrees C.” The second shows a chain of three gray spheres bonded by the middle sphere to a fourth gray sphere. Each gray sphere is bonded to several smaller, white spheres. There is a jagged, gray line and then the mirror image of the first chain appears. Above these two chains is the label, “Less surface area, less attraction,” and below is the label, “isopentane boiling point: 27 degrees C.” The third image shows a chain of five gray spheres bonded together and to several smaller, white spheres. There is a jagged gray line and then the mirror image of the first chain appears. Above these chains is the label, “Large contact area, strong attraction,” and below is the label, “n-pentane boiling point 36 degrees C.”

Applications: Geckos and Intermolecular Forces

Geckos have an amazing ability to adhere to most surfaces. They can quickly run up smooth walls and across ceilings that have no toe-holds, and they do this without having suction cups or a sticky substance on their toes. And while a gecko can lift its feet easily as it walks along a surface, if you attempt to pick it up, it sticks to the surface. How are geckos (as well as spiders and some other insects) able to do this? Although this phenomenon has been investigated for hundreds of years, scientists only recently uncovered the details of the process that allows geckos’ feet to behave this way.




Figure **12.1.7**: Geckos’ toes contain large numbers of tiny hairs (setae), which branch into many triangular tips (spatulae). Geckos adhere to surfaces because of van der Waals attractions between the surface and a gecko’s millions of spatulae. By changing how the spatulae contact the surface, geckos can turn their stickiness “on” and “off.” (credit photo: modification of work by “JC*+A!”/Flickr)

Three figures are shown. The first is a photo of the bottom of a gecko’s foot. The second is bigger version which shows the setae. The third is a bigger version of the setae and shows the spatulae.

Geckos’ toes are covered with hundreds of thousands of tiny hairs known as *setae*, with each seta, in turn, branching into hundreds of tiny, flat, triangular tips called *spatulae*. The huge numbers of spatulae on its setae provide a gecko, shown in Figure **12.1.7**, with a large total surface area for sticking to a surface. In 2000, Kellar Autumn, who leads a multi-institutional gecko research team, found that geckos adhered equally well to both polar silicon dioxide and nonpolar gallium arsenide. This proved that geckos stick to surfaces because of dispersion forces—weak intermolecular attractions arising from temporary,

synchronized charge distributions between adjacent molecules. Although dispersion forces are very weak, the total attraction over millions of spatulae is large enough to support many times the gecko's weight.

In 2014, two scientists developed a model to explain how geckos can rapidly transition from "sticky" to "non-sticky." Alex Greaney and Congcong Hu at Oregon State University described how geckos can achieve this by changing the angle between their spatulae and the surface. Geckos' feet, which are normally nonsticky, become sticky when a small shear force is applied. By curling and uncurling their toes, geckos can alternate between sticking and unsticking from a surface, and thus easily move across it. Further investigations may eventually lead to the development of better adhesives and other applications.



Watch this video to learn more about Kellar Autumn's research that determined that van der Waals forces are responsible for a gecko's ability to cling and climb.

Dipole-Dipole Attractions

Recall from the chapter on chemical bonding and molecular geometry that *polar* molecules have a partial positive charge on one side and a partial negative charge on the other side of the molecule—a separation of charge called a *dipole*. Consider a polar molecule such as hydrogen chloride, HCl. In the HCl molecule, the more electronegative Cl atom bears the partial negative charge, whereas the less electronegative H atom bears the partial positive charge. An attractive force between HCl molecules results from the attraction between the positive end of one HCl molecule and the negative end of another. This attractive force is called a dipole-dipole attraction—the electrostatic force between the partially positive end of one polar molecule and the partially negative end of another, as illustrated in Figure 12.1.8.




Figure 12.1.8: This image shows two arrangements of polar molecules, such as HCl, that allow an attraction between the partial negative end of one molecule and the partial positive end of another.

Two pairs of molecules are shown where each molecule has one larger blue side labeled "delta sign, negative sign" and a smaller red side labeled "delta sign, positive sign. In the first pair, the red sides of the two molecules both face to the left and the blue side to the right. A horizontal dotted line lies in between the two. In the second pair, the molecules face up and down, with the red and blue ends aligning. A horizontal dotted line lies between the red and blue ends facing upward and another lies between the red and blue ends facing downward.

The effect of a dipole-dipole attraction is apparent when we compare the properties of HCl molecules to nonpolar F_2 molecules. Both HCl and F_2 consist of the same number of atoms and have approximately the same molecular mass. At a temperature of 150 K, molecules of both substances would have the same average KE. However, the dipole-dipole attractions between HCl molecules are sufficient to cause them to "stick together" to form a liquid, whereas the relatively weaker dispersion forces between nonpolar F_2 molecules are not, and so this substance is gaseous at this temperature. The higher normal boiling point of HCl (188 K) compared to F_2 (85 K) is a reflection of the greater strength of dipole-dipole attractions between HCl molecules, compared to the

attractions between nonpolar F_2 molecules. We will often use values such as boiling or freezing points, or enthalpies of vaporization or fusion, as indicators of the relative strengths of IMFs of attraction present within different substances.

Example 12.1.2: Dipole-Dipole Forces and Their Effects

Predict which will have the higher boiling point: N_2 or CO. Explain your reasoning.

Solution

CO and N_2 are both diatomic molecules with masses of about 28 amu, so they experience similar London dispersion forces. Because CO is a polar molecule, it experiences dipole-dipole attractions. Because N_2 is nonpolar, its molecules cannot exhibit dipole-dipole attractions. The dipole-dipole attractions between CO molecules are comparably stronger than the dispersion forces between nonpolar N_2 molecules, so CO is expected to have the higher boiling point.

A common method for preparing oxygen is the decomposition

Exercise 12.1.2

Predict which will have the higher boiling point: **ICl** or $\mathbf{Br_2}$. Explain your reasoning.

Answer

ICl. ICl and Br_2 have similar masses (~160 amu) and therefore experience similar London dispersion forces. ICl is polar and thus also exhibits dipole-dipole attractions; Br_2 is nonpolar and does not. The relatively stronger dipole-dipole attractions require more energy to overcome, so ICl will have the higher boiling point.

Hydrogen Bonding

Nitrosyl fluoride (ONF, molecular mass 49 amu) is a gas at room temperature. Water (H_2O, molecular mass 18 amu) is a liquid, even though it has a lower molecular mass. We clearly cannot attribute this difference between the two compounds to dispersion forces. Both molecules have about the same shape and ONF is the heavier and larger molecule. It is, therefore, expected to experience more significant dispersion forces. Additionally, we cannot attribute this difference in boiling points to differences in the dipole moments of the molecules. Both molecules are polar and exhibit comparable dipole moments. The large difference between the boiling points is due to a particularly strong dipole-dipole attraction that may occur when a molecule contains a hydrogen atom bonded to a fluorine, oxygen, or nitrogen atom (the three most electronegative elements). The very large difference in electronegativity between the H atom (2.1) and the atom to which it is bonded (4.0 for an F atom, 3.5 for an O atom, or 3.0 for a N atom), combined with the very small size of a H atom and the relatively small sizes of F, O, or N atoms, leads to *highly concentrated partial charges* with these atoms. Molecules with F-H, O-H, or N-H moieties are very strongly attracted to similar moieties in nearby molecules, a particularly strong type of dipole-dipole attraction called hydrogen bonding. Examples of hydrogen bonds include HF⋯HF, H_2O⋯HOH, and H_3N⋯HNH_2, in which the hydrogen bonds are denoted by dots. Figure **12.1.9** illustrates hydrogen bonding between water molecules.




Figure **12.1.9**: Water molecules participate in multiple hydrogen-bonding interactions with nearby water molecules.

Five water molecules are shown near one another, but not touching. A dotted line lies between many of the hydrogen atoms on one molecule and the oxygen atom on another molecule.

Despite use of the word “bond,” keep in mind that hydrogen bonds are *intermolecular* attractive forces, not *intramolecular* attractive forces (covalent bonds). Hydrogen bonds are much weaker than covalent bonds, only about 5 to 10% as strong, but are

generally much stronger than other dipole-dipole attractions and dispersion forces.

Hydrogen bonds have a pronounced effect on the properties of condensed phases (liquids and solids). For example, consider the trends in boiling points for the binary hydrides of group 15 (NH_3, PH_3, AsH_3, and SbH_3), group 16 hydrides (H_2O, H_2S, H_2Se, and H_2Te), and group 17 hydrides (HF, HCl, HBr, and HI). The boiling points of the heaviest three hydrides for each group are plotted in Figure **12.1.10**. As we progress down any of these groups, the polarities of the molecules decrease slightly, whereas the sizes of the molecules increase substantially. The effect of increasingly stronger dispersion forces dominates that of increasingly weaker dipole-dipole attractions, and the boiling points are observed to increase steadily. For the group 15, 16, and 17 hydrides, the boiling points for each class of compounds increase with increasing molecular mass for elements in periods 3, 4, and 5.




Figure **12.1.10**: In comparison to periods 3−5, the binary hydrides of period 2 elements in groups 17, 16 and 15 (F, O and N, respectively) exhibit anomalously high boiling points due to hydrogen bonding.

A line graph is shown where the y-axis is labeled “Boiling point (, degree sign, C)” and has values of “ negative 150” to “150” from bottom to top in increments of 50. The x-axis is labeled “Period” and has values of “0” to “5” in increments of 1. Three lines are shown on the graph and are labeled in the legend. The red line is labeled as “halogen family,” the blue is “oxygen family” and the green is “nitrogen family.” The first point on the red line is labeled “question mark” and is at point “2, negative 120”. The second point on the line is labeled “H C l” and is at point “3, negative 80” while the third point on the line is labeled “H B r” and is at point “4, negative 60”. The fourth point on the line is labeled “H I” and is at point “5, negative 40.” The first point on the green line is labeled “question mark” and is at point “2, negative 125.” The second point on the line is labeled “P H, subscript 3” and is at point “3, negative 80” while the third point on the line is labeled “A s H, subscript 3” and is at point “4, negative 55.” The fourth point on the line is labeled “S b H, subscript 3” and is at point “5, negative 10.” The first point on the blue line is labeled “question mark” and is at point “2, negative 80.” The second point on the line is labeled “H, subscript 2, S” and is at point “3, negative 55” while the third point on the line is labeled “H, subscript 2, S e” and is at point “4, negative 45.” The fourth point on the line is labeled “H, subscript 2, T e” and is at point “5, negative 3.”

If we use this trend to predict the boiling points for the lightest hydride for each group, we would expect NH_3 to boil at about −120 °C, H_2O to boil at about −80 °C, and HF to boil at about −110 °C. However, when we measure the boiling points for these compounds, we find that they are dramatically higher than the trends would predict, as shown in Figure **12.1.10**. The stark contrast between our naïve predictions and reality provides compelling evidence for the strength of hydrogen bonding.

✔ Example **12.1.3**: Effect of Hydrogen Bonding on Boiling Points

Consider the compounds dimethylether (CH_3OCH_3), ethanol (CH_3CH_2OH), and propane ($CH_3CH_2CH_3$). Their boiling points, not necessarily in order, are −42.1 °C, −24.8 °C, and 78.4 °C. Match each compound with its boiling point. Explain your reasoning.

Solution

The VSEPR-predicted shapes of CH_3OCH_3, CH_3CH_2OH, and $CH_3CH_2CH_3$ are similar, as are their molar masses (46 g/mol, 46 g/mol, and 44 g/mol, respectively), so they will exhibit similar dispersion forces. Since $CH_3CH_2CH_3$ is nonpolar, it may

exhibit *only* dispersion forces. Because CH_3OCH_3 is polar, it will also experience dipole-dipole attractions. Finally, CH_3CH_2OH has an −OH group, and so it will experience the uniquely strong dipole-dipole attraction known as hydrogen bonding. So the ordering in terms of strength of IMFs, and thus boiling points, is $CH_3CH_2CH_3 < CH_3OCH_3 < CH_3CH_2OH$. The boiling point of propane is −42.1 °C, the boiling point of dimethylether is −24.8 °C, and the boiling point of ethanol is 78.5 °C.

? Exercise 12.1.3

Ethane (CH_3CH_3) has a melting point of −183 °C and a boiling point of −89 °C. Predict the melting and boiling points for methylamine (CH_3NH_2). Explain your reasoning.

Answer

The melting point and boiling point for methylamine are predicted to be significantly greater than those of ethane. CH_3CH_3 and CH_3NH_2 are similar in size and mass, but methylamine possesses an −NH group and therefore may exhibit hydrogen bonding. This greatly increases its IMFs, and therefore its melting and boiling points. It is difficult to predict values, but the known values are a melting point of −93 °C and a boiling point of −6 °C.

Hydrogen Bonding and DNA

Deoxyribonucleic acid (DNA) is found in every living organism and contains the genetic information that determines the organism's characteristics, provides the blueprint for making the proteins necessary for life, and serves as a template to pass this information on to the organism's offspring. A DNA molecule consists of two (anti-)parallel chains of repeating nucleotides, which form its well-known double helical structure, as shown in Figure **12.1.10**.




Figure **12.1.11**: Two separate DNA molecules form a double-stranded helix in which the molecules are held together via hydrogen bonding. (credit: modification of work by Jerome Walker, Dennis Myts)

Two images are shown. The first lies on the left side of the page and shows a helical structure like a twisted ladder where the rungs of the ladder, labeled “Base pair” are red, yellow, green and blue paired bars. The red and yellow bars, which are always paired together, are labeled in the legend, which is titled “Nitrogenous bases” as “adenine” and “thymine,” respectively. The blue and green bars, which are always paired together, are labeled in the legend as “guanine” and “cytosine,” respectively. At the top of the helical structure, the left-hand side rail, or “Sugar, dash, phosphate backbone,” is labeled as “3, prime” while the right is labeled as “5, prime.” These labels are reversed at the bottom of the helix. To the right of the page is a large Lewis structure. The top left corner of this structure, labeled “5, prime,” shows a phosphorus atom single bonded to three oxygen atoms, one of which has a superscripted negative charge, and double bonded to a fourth oxygen atom. One of the single bonded oxygen atoms is single bonded to the left corner of a five-membered ring with an oxygen atom at its top point and which is single bonded to an oxygen atom on the bottom left. This oxygen atom is single bonded to a phosphorus atom that is single bonded to two other hydrogen atoms and double bonded to a fourth oxygen atom. The lower left of these oxygen atoms is single bonded to another oxygen atom that is single bonded to a five-membered ring with an oxygen in the upper bonding site. The bottom left of this ring has a hydroxyl group attached to it while the upper right carbon is single bonded to a nitrogen atom that is part of a five-membered ring bonded to a six-membered ring. Both of these rings have points of unsaturation and nitrogen atoms bonded into their structures. On the right side of the six-membered ring are two single bonded amine groups and a double bonded oxygen. Three separate dotted lines extend from these sites to corresponding sites on a second six-membered ring. This ring has points of unsaturation and a nitrogen atom in the bottom right bonding position that is single bonded to a five-membered ring on the right side of the image. This ring is single bonded to a carbon that is single bonded to an oxygen that is single bonded to a phosphorus. The phosphorus is single bonded to two other oxygen atoms and double bonded to a fourth oxygen atom. This group is labeled “5, prime.” The five-membered ring is also bonded on the top side to an oxygen that is bonded to a phosphorus single bonded to two other oxygen atoms and double bonded to a fourth oxygen atom. The upper left oxygen of this group is single bonded to a carbon that is single bonded to a five-membered ring with an oxygen in the bottom bonding position. This ring has a hydroxyl group on its upper right side that is labeled “3, prime” and is bonded on the left side to a nitrogen that is a member of a five-membered ring. This ring is bonded to a six-membered ring and both have points of unsaturation. This ring has a nitrogen on the left side, as well as an amine group, that have two dotted lines leading from them to an oxygen and amine group on a six membered ring. These dotted lines are labeled “Hydrogen bonds.” The six membered ring also has a double bonded oxygen on its lower side and a nitrogen atom on its left side that is single bonded to a five-membered ring. This ring connects to the two phosphate groups mentioned at the start of this to form a large circle. The name “guanine” is written below the lower left side of this image while the name “cytosine” is written on the lower right. The name “thymine” is written above the right side of the image and “adenine” is written on the top right. Three sections are indicated below the images where the left is labeled “Sugar, dash, phosphate backbone,” the middle is labeled “Bases” and the right is labeled “Sugar, dash, phosphate backbone.”

Each nucleotide contains a (deoxyribose) sugar bound to a phosphate group on one side, and one of four nitrogenous bases on the other. Two of the bases, cytosine (C) and thymine (T), are single-ringed structures known as pyrimidines. The other two, adenine (A) and guanine (G), are double-ringed structures called purines. These bases form complementary base pairs consisting of one purine and one pyrimidine, with adenine pairing with thymine, and cytosine with guanine. Each base pair is held together by hydrogen bonding. A and T share two hydrogen bonds, C and G share three, and both pairings have a similar shape and structure Figure **12.1.12**




Figure 12.1.12: The geometries of the base molecules result in maximum hydrogen bonding between adenine and thymine (AT) and between guanine and cytosine (GC), so-called “complementary base pairs.”

A large Lewis structure is shown. The top left corner of this structure, labeled “5, prime,” shows a phosphorus atom single bonded to three oxygen atoms, one of which has a superscripted negative charge, and double bonded to a fourth oxygen atom. One of the single bonded oxygen atoms is single bonded to the left corner of a five-membered ring with an oxygen atom at its top point and which is single bonded to an oxygen atom on the bottom left. This oxygen atom is single bonded to a phosphorus atom that is single bonded to two other hydrogen atoms and double bonded to a fourth oxygen atom. The lower left of these oxygen atoms is single bonded to another oxygen atom that is single bonded to a five-membered ring with an oxygen in the upper bonding site. The bottom left of this ring has a hydroxyl group attached to it while the upper right carbon is single bonded to a nitrogen atom that is part of a five-membered ring bonded to a six-membered ring. Both of these rings have points of unsaturation and nitrogen atoms bonded into their structures. On the right side of the six-membered ring are two single bonded amine groups and a double bonded oxygen. Three separate dotted lines extend from these sites to corresponding sites on a second six-membered ring. This ring has points of unsaturation and a nitrogen atom in the bottom right bonding position that is single bonded to a five-membered ring on the right side of the image. This ring is single bonded to a carbon that is single bonded to an oxygen that is single bonded to a phosphorus. The phosphorus is single bonded to two other oxygen atoms and double bonded to a fourth oxygen atom. This group is labeled “5, prime.” The five-membered ring is also bonded on the top side to an oxygen that is bonded to a phosphorus single bonded to two other oxygen atoms and double bonded to a fourth oxygen atom. The upper left oxygen of this group is single bonded to a carbon that is single bonded to a five-membered ring with an oxygen in the bottom bonding position. This ring has a hydroxyl group on its upper right side that is labeled “3, prime” and is bonded on the left side to a nitrogen that is a member of a five-membered ring. This ring is bonded to a six-membered ring and both have points of unsaturation. This ring has a nitrogen on the left side, as well as an amine group, that have two dotted lines leading from them to an oxygen and amine group on a six membered ring. These dotted lines are labeled “Hydrogen bonds.” The six membered ring also has a double bonded oxygen on its lower side and a nitrogen atom on its left side that is single bonded to a five-membered ring. This ring connects to the two phosphate groups mentioned at the start of this to form a large circle. The name “guanine” is written below the lower left side of this image while the name “cytosine” is written on the lower right. The name “thymine” is written above the right side of the image and “adenine” is written on the top right. Three sections are indicated below the images where the left is labeled “Sugar, dash, phosphate backbone,” the middle is labeled “Bases” and the right is labeled “Sugar, dash, phosphate backbone.”

The cumulative effect of millions of hydrogen bonds effectively holds the two strands of DNA together. Importantly, the two strands of DNA can relatively easily “unzip” down the middle since hydrogen bonds are relatively weak compared to the covalent bonds that hold the atoms of the individual DNA molecules together. This allows both strands to function as a template for replication.

Summary

The physical properties of condensed matter (liquids and solids) can be explained in terms of the kinetic molecular theory. In a liquid, intermolecular attractive forces hold the molecules in contact, although they still have sufficient kinetic energy to move past each other. Intermolecular attractive forces, collectively referred to as van der Waals forces, are responsible for the behavior of liquids and solids and are electrostatic in nature. Dipole-dipole attractions result from the electrostatic attraction of the partial negative end of one dipolar molecule for the partial positive end of another. The temporary dipole that results from the motion of the electrons in an atom can induce a dipole in an adjacent atom and give rise to the London dispersion force. London forces

increase with increasing molecular size. Hydrogen bonds are a special type of dipole-dipole attraction that results when hydrogen is bonded to one of the three most electronegative elements: F, O, or N.

Glossary

dipole-dipole attraction
intermolecular attraction between two permanent dipoles

dispersion force
(also, London dispersion force) attraction between two rapidly fluctuating, temporary dipoles; significant only when particles are very close together

hydrogen bonding
occurs when exceptionally strong dipoles attract; bonding that exists when hydrogen is bonded to one of the three most electronegative elements: F, O, or N

induced dipole
temporary dipole formed when the electrons of an atom or molecule are distorted by the instantaneous dipole of a neighboring atom or molecule

instantaneous dipole
temporary dipole that occurs for a brief moment in time when the electrons of an atom or molecule are distributed asymmetrically

intermolecular force
noncovalent attractive force between atoms, molecules, and/or ions

polarizability
measure of the ability of a charge to distort a molecule's charge distribution (electron cloud)

van der Waals force
attractive or repulsive force between molecules, including dipole-dipole, dipole-induced dipole, and London dispersion forces; does not include forces due to covalent or ionic bonding, or the attraction between ions and molecules

---

12.1: Intermolecular forces is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **10.2: Intermolecular Forces** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

12.2: Properties of Liquids

Learning Objectives

- Distinguish between adhesive and cohesive forces
- Define viscosity, surface tension, and capillary rise
- Describe the roles of intermolecular attractive forces in each of these properties/phenomena

When you pour a glass of water, or fill a car with gasoline, you observe that water and gasoline flow freely. But when you pour syrup on pancakes or add oil to a car engine, you note that syrup and motor oil do not flow as readily. The viscosity of a liquid is a measure of its resistance to flow. Water, gasoline, and other liquids that flow freely have a low viscosity. Honey, syrup, motor oil, and other liquids that do not flow freely, like those shown in Figure **12.2.1**, have higher viscosities. We can measure viscosity by measuring the rate at which a metal ball falls through a liquid (the ball falls more slowly through a more viscous liquid) or by measuring the rate at which a liquid flows through a narrow tube (more viscous liquids flow more slowly).



Figure **12.2.1**: (a) Honey and (b) motor oil are examples of liquids with high viscosities; they flow slowly. (credit a: modification of work by Scott Bauer; credit b: modification of work by David Nagy)

Two photographs are shown and labeled “a” and “b.” Photo a shows a jar of honey with a dipper drizzling it onto a biscuit. More biscuits are shown in a basket in the background. Photo b shows the engine of a car and a person adding motor oil to the engine.

The IMFs between the molecules of a liquid, the size and shape of the molecules, and the temperature determine how easily a liquid flows. As Table **12.2.1** shows, the more structurally complex are the molecules in a liquid and the stronger the IMFs between them, the more difficult it is for them to move past each other and the greater is the viscosity of the liquid. As the temperature increases, the molecules move more rapidly and their kinetic energies are better able to overcome the forces that hold them together; thus, the viscosity of the liquid decreases.

Table **12.2.1**: Viscosities of Common Substances at 25 °C

Substance	Formula	Viscosity (mPa·s)
water	H_2O	0.890
mercury	Hg	1.526
ethanol	C_2H_5OH	1.074
octane	C_8H_{18}	0.508
ethylene glycol	$CH_2(OH)CH_2(OH)$	16.1
honey	variable	~2,000–10,000
motor oil	variable	~50–500

The various IMFs between identical molecules of a substance are examples of cohesive forces. The molecules within a liquid are surrounded by other molecules and are attracted equally in all directions by the cohesive forces within the liquid. However, the molecules on the surface of a liquid are attracted only by about one-half as many molecules. Because of the unbalanced molecular

attractions on the surface molecules, liquids contract to form a shape that minimizes the number of molecules on the surface—that is, the shape with the minimum surface area. A small drop of liquid tends to assume a spherical shape, as shown in Figure **12.2.2**, because in a sphere, the ratio of surface area to volume is at a minimum. Larger drops are more greatly affected by gravity, air resistance, surface interactions, and so on, and as a result, are less spherical.




Figure **12.2.2**: Attractive forces result in a spherical water drop that minimizes surface area; cohesive forces hold the sphere together; adhesive forces keep the drop attached to the web. (credit photo: modification of work by "OliBac"/Flickr)

A photo of a spider's web with droplets of water attached to it is shown. Two images are shown the right of the photo and arrows lead from the photo to the images. The upper image shows twenty eight blue spheres stacked one atop the other in the bottom of a circular background. Five arrows are drawn pointing to the sides and downward from the sphere in the top middle of the drawing. The lower image shows another circular background of the same size as the first, but this time the blue spheres fill the image and are packed closely together. A sphere in the middle has six arrows pointing in all directions away from it.

Surface tension is defined as the energy required to increase the surface area of a liquid, or the force required to increase the length of a liquid surface by a given amount. This property results from the cohesive forces between molecules at the surface of a liquid, and it causes the surface of a liquid to behave like a stretched rubber membrane. Surface tensions of several liquids are presented in Table **12.2.2**.

Table **12.2.2**: Surface Tensions of Common Substances at 25 °C

Substance	Formula	Surface Tension (mN/m)
water	H_2O	71.99
mercury	Hg	458.48
ethanol	C_2H_5OH	21.97
octane	C_8H_{18}	21.14
ethylene glycol	$CH_2(OH)CH_2(OH)$	47.99

Among common liquids, water exhibits a distinctly high surface tension due to strong hydrogen bonding between its molecules. As a result of this high surface tension, the surface of water represents a relatively "tough skin" that can withstand considerable force without breaking. A steel needle carefully placed on water will float. Some insects, like the one shown in Figure **12.2.3**, even though they are denser than water, move on its surface because they are supported by the surface tension.




Figure **12.2.3**: Surface tension (right) prevents this insect, a "water strider," from sinking into the water.

A photo and a diagram as shown and a right-facing arrow leads from the photo to the image. The photo shows an insect standing on the surface of a sample of water. The image shows a square background that is two thirds covered in blue spheres that are closely packet together. A brown line starts at the upper left corner of the background and rests on top of the first row of spheres. The sphere directly under this low point of the line has four arrows drawn on it that face to both sides and downward. A sphere in the bottom center of the image has six arrows drawn on it that all face outward in different directions.

The IMFs of attraction between two *different* molecules are called adhesive forces. Consider what happens when water comes into contact with some surface. If the adhesive forces between water molecules and the molecules of the surface are weak compared to the cohesive forces between the water molecules, the water does not “wet” the surface. For example, water does not wet waxed surfaces or many plastics such as polyethylene. Water forms drops on these surfaces because the cohesive forces within the drops are greater than the adhesive forces between the water and the plastic. Water spreads out on glass because the adhesive force between water and glass is greater than the cohesive forces within the water. When water is confined in a glass tube, its meniscus (surface) has a concave shape because the water wets the glass and creeps up the side of the tube. On the other hand, the cohesive forces between mercury atoms are much greater than the adhesive forces between mercury and glass. Mercury therefore does not wet glass, and it forms a convex meniscus when confined in a tube because the cohesive forces within the mercury tend to draw it into a drop (Figure **12.2.4**).




Figure **12.2.4**: Differences in the relative strengths of cohesive and adhesive forces result in different meniscus shapes for mercury (left) and water (right) in glass tubes. (credit: Mark Ott)

This figure shows two test tubes. The test tube on the left contains mercury with a meniscus that rounds up. The test tube on the right contains water with a meniscus that rounds down.

If you place one end of a paper towel in spilled wine, as shown in Figure **12.2.5**, the liquid wicks up the paper towel. A similar process occurs in a cloth towel when you use it to dry off after a shower. These are examples of capillary action—when a liquid flows within a porous material due to the attraction of the liquid molecules to the surface of the material and to other liquid molecules. The adhesive forces between the liquid and the porous material, combined with the cohesive forces within the liquid, may be strong enough to move the liquid upward against gravity.




Figure **12.2.5**: Wine wicks up a paper towel (left) because of the strong attractions of water (and ethanol) molecules to the −OH groups on the towel’s cellulose fibers and the strong attractions of water molecules to other water (and ethanol) molecules (right). (credit photo: modification of work by Mark Blaser)

A photo and a diagram are shown. In the photo, a paper towel is dipped into a bowl full of a red liquid sitting on a countertop. The red liquid is traveling up the lower part of the paper towel, and this section of the photo has a square drawn around it. A right-facing arrow leads from this square to the image. The image is square and has a background of two types of molecules, mixed together. The first type of molecule is composed of two bonded black spheres, one of which is single bonded to three white spheres and one of which is single bonded to two white spheres and a red sphere that is itself bonded to a white sphere. The other type of molecule is composed of six black spheres bonded together in a row and bonded to other red and white spheres. Six upward-facing arrows are drawn on top of this background. They have positive signs on their lower ends and negative signs on their heads. Four upward-facing arrows are drawn with their signs reversed.

Towels soak up liquids like water because the fibers of a towel are made of molecules that are attracted to water molecules. Most cloth towels are made of cotton, and paper towels are generally made from paper pulp. Both consist of long molecules of cellulose

that contain many −OH groups. Water molecules are attracted to these −OH groups and form hydrogen bonds with them, which draws the H_2O molecules up the cellulose molecules. The water molecules are also attracted to each other, so large amounts of water are drawn up the cellulose fibers.

Capillary action can also occur when one end of a small diameter tube is immersed in a liquid, as illustrated in Figure **12.2.6**. If the liquid molecules are strongly attracted to the tube molecules, the liquid creeps up the inside of the tube until the weight of the liquid and the adhesive forces are in balance. The smaller the diameter of the tube is, the higher the liquid climbs. It is partly by capillary action occurring in plant cells called xylem that water and dissolved nutrients are brought from the soil up through the roots and into a plant. Capillary action is the basis for thin layer chromatography, a laboratory technique commonly used to separate small quantities of mixtures. You depend on a constant supply of tears to keep your eyes lubricated and on capillary action to pump tear fluid away.




Figure **12.2.6**: Depending upon the relative strengths of adhesive and cohesive forces, a liquid may rise (such as water) or fall (such as mercury) in a glass capillary tube. The extent of the rise (or fall) is directly proportional to the surface tension of the liquid and inversely proportional to the density of the liquid and the radius of the tube.

An image of two beakers and a tube is shown. The first beaker, drawn on the left and labeled “Water,” is drawn half-full of a blue liquid. Two tubes are placed vertically in the beaker and inserted into the liquid. The liquid is shown higher in the tubes than in the beaker and is labeled “Capillary attraction.” The second beaker, drawn in the middle and labeled “Mercury,” is drawn half-full of a gray liquid. Two tubes are placed vertically in the beaker and inserted into the liquid. The liquid is shown lower in the tubes than in the beaker and is labeled “Capillary repulsion.” Lines point to the vertical tubes and label them “Capillary tubes.” A separate drawing of one of the vertical tubes from the first beaker is shown on the right. A right-facing arrow leads from the liquid in the tube to a square call-out box that shows a close-up view of the liquid’s surface. The distance across the tube is labeled “2 r” in this image.

The height to which a liquid will rise in a capillary tube is determined by several factors as shown in the following equation:

$$h = \frac{2T\cos\theta}{r\rho g} \tag{12.2.1}$$

where

- h is the height of the liquid inside the capillary tube relative to the surface of the liquid outside the tube,
- T is the surface tension of the liquid,
- θ is the contact angle between the liquid and the tube,
- r is the radius of the tube, ρ is the density of the liquid, and
- g is the acceleration due to gravity, 9.8 m/s^2.

When the tube is made of a material to which the liquid molecules are strongly attracted, they will spread out completely on the surface, which corresponds to a contact angle of 0°. This is the situation for water rising in a glass tube.

Example 12.2.1: Capillary Rise

At 25 °C, how high will water rise in a glass capillary tube with an inner diameter of 0.25 mm?

For water, T = 71.99 mN/m and ρ = 1.0 g/cm^3.

Solution

The liquid will rise to a height h given by Equation 12.2.1 :

$$h = \frac{2T\cos\theta}{r\rho g}$$

The Newton is defined as a kg m/s^2, and so the provided surface tension is equivalent to 0.07199 kg/s^2. The provided density must be converted into units that will cancel appropriately: ρ = 1000 kg/m^3. The diameter of the tube in meters is 0.00025 m, so the radius is 0.000125 m. For a glass tube immersed in water, the contact angle is θ = 0°, so cos θ = 1. Finally, acceleration due to gravity on the earth is g = 9.8 m/s^2. Substituting these values into the equation, and cancelling units, we have:

$$h = \frac{2(0.07199\ \text{kg/s}^2)}{(0.000125\ \text{m})(1000\ \text{kg/m}^3)(9.8\ \text{m/s}^2)} = 0.12\ \text{m} = 12\ \text{cm}$$

? Exercise 12.2.1

Water rises in a glass capillary tube to a height of 8.4 cm. What is the diameter of the capillary tube?

Answer

diameter = 0.36 mm

Applications: Capillary Action is Used to Draw Blood

Many medical tests require drawing a small amount of blood, for example to determine the amount of glucose in someone with diabetes or the hematocrit level in an athlete. This procedure can be easily done because of capillary action, the ability of a liquid to flow up a small tube against gravity, as shown in Figure 12.2.7. When your finger is pricked, a drop of blood forms and holds together due to surface tension—the unbalanced intermolecular attractions at the surface of the drop. Then, when the open end of a narrow-diameter glass tube touches the drop of blood, the adhesive forces between the molecules in the blood and those at the glass surface draw the blood up the tube. How far the blood goes up the tube depends on the diameter of the tube (and the type of fluid). A small tube has a relatively large surface area for a given volume of blood, which results in larger (relative) attractive forces, allowing the blood to be drawn farther up the tube. The liquid itself is held together by its own cohesive forces. When the weight of the liquid in the tube generates a downward force equal to the upward force associated with capillary action, the liquid stops rising.



Figure 12.2.7:: Blood is collected for medical analysis by capillary action, which draws blood into a small diameter glass tube. (credit: modification of work by Centers for Disease Control and Prevention)

A photograph shows a person’s hand being held by a person wearing medical gloves. A thin glass tube is pressed against the persons finger and blood is moving up the tube.

Key Concepts and Summary

The intermolecular forces between molecules in the liquid state vary depending upon their chemical identities and result in corresponding variations in various physical properties. Cohesive forces between like molecules are responsible for a liquid’s viscosity (resistance to flow) and surface tension (elasticity of a liquid surface). Adhesive forces between the molecules of a liquid and different molecules composing a surface in contact with the liquid are responsible for phenomena such as surface wetting and capillary rise.

Key Equations

- $h = \frac{2T\cos\theta}{r\rho g}$

Glossary

adhesive force
force of attraction between molecules of different chemical identities

capillary action
flow of liquid within a porous material due to the attraction of the liquid molecules to the surface of the material and to other liquid molecules

cohesive force
force of attraction between identical molecules

surface tension
energy required to increase the area, or length, of a liquid surface by a given amount

viscosity
measure of a liquid’s resistance to flow

12.2: Properties of Liquids is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **10.3: Properties of Liquids** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

12.3: Phase Changes

Learning Objectives

- Define phase transitions and phase transition temperatures
- Explain the relation between phase transition temperatures and intermolecular attractive forces
- Describe the processes represented by typical heating and cooling curves, and compute heat flows and enthalpy changes accompanying these processes

We witness and utilize changes of physical state, or phase transitions, in a great number of ways. As one example of global significance, consider the evaporation, condensation, freezing, and melting of water. These changes of state are essential aspects of our earth's water cycle as well as many other natural phenomena and technological processes of central importance to our lives. In this module, the essential aspects of phase transitions are explored.

Vaporization and Condensation

When a liquid vaporizes in a closed container, gas molecules cannot escape. As these gas phase molecules move randomly about, they will occasionally collide with the surface of the condensed phase, and in some cases, these collisions will result in the molecules re-entering the condensed phase. The change from the gas phase to the liquid is called condensation. When the rate of condensation becomes equal to the rate of vaporization, neither the amount of the liquid nor the amount of the vapor in the container changes. The vapor in the container is then said to be *in equilibrium* with the liquid. Keep in mind that this is not a static situation, as molecules are continually exchanged between the condensed and gaseous phases. Such is an example of a dynamic equilibrium, the status of a system in which reciprocal processes (for example, vaporization and condensation) occur at equal rates. The pressure exerted by the vapor in equilibrium with a liquid in a closed container at a given temperature is called the liquid's vapor pressure (or equilibrium vapor pressure). The area of the surface of the liquid in contact with a vapor and the size of the vessel have no effect on the vapor pressure, although they do affect the time required for the equilibrium to be reached. We can measure the vapor pressure of a liquid by placing a sample in a closed container, like that illustrated in Figure **12.3.1**, and using a manometer to measure the increase in pressure that is due to the vapor in equilibrium with the condensed phase.




Figure **12.3.1**: In a closed container, dynamic equilibrium is reached when (a) the rate of molecules escaping from the liquid to become the gas (b) increases and eventually (c) equals the rate of gas molecules entering the liquid. When this equilibrium is reached, the vapor pressure of the gas is constant, although the vaporization and condensation processes continue.


Three images are shown and labeled "a," "b," and "c." Each image shows a round bulb connected on the right to a tube that is horizontal, then is bent vertically, curves, and then is vertical again to make a u-shape. A valve is located in the horizontal portion of the tube. Image a depicts a liquid in the bulb, labeled, "Liquid," and upward-facing arrows leading away from the surface of the liquid. The phrase, "Molecules escape surface and form vapor" is written below the bulb, and a gray liquid in the u-shaped portion of the tube is shown at equal heights on the right and left sides. Image b depicts a liquid in the bulb, labeled, "Liquid," and upward-facing arrows leading away from the surface of the liquid to molecules drawn in the upper portion of the bulb. A gray liquid in the u-shaped portion of the tube is shown slightly higher on the right side than on the left side. Image c depicts a liquid in the bulb, labeled, "Liquid," and upward-facing arrows leading away from the surface of the liquid to molecules drawn in the upper portion of the bulb. There are more molecules present in c than in b. The phrase "Equilibrium reached, vapor pressure determined," is written below the bulb and a gray liquid in the u-shaped portion of the tube is shown higher on the right side. A horizontal line is drawn level with each of these liquid levels and the distance between the lines is labeled with a double-headed arrow. This section is labeled with the phrase, "Vapor pressure."

The chemical identities of the molecules in a liquid determine the types (and strengths) of intermolecular attractions possible; consequently, different substances will exhibit different equilibrium vapor pressures. Relatively strong intermolecular attractive

forces will serve to impede vaporization as well as favoring “recapture” of gas-phase molecules when they collide with the liquid surface, resulting in a relatively low vapor pressure. Weak intermolecular attractions present less of a barrier to vaporization, and a reduced likelihood of gas recapture, yielding relatively high vapor pressures. The following example illustrates this dependence of vapor pressure on intermolecular attractive forces.

Example 12.3.1: Explaining Vapor Pressure in Terms of IMFs

Given the shown structural formulas for these four compounds, explain their relative vapor pressures in terms of types and extents of IMFs:



ethanol ethylene glycol diethyl ether water

Solution

Diethyl ether has a very small dipole and most of its intermolecular attractions are London forces. Although this molecule is the largest of the four under consideration, its IMFs are the weakest and, as a result, its molecules most readily escape from the liquid. It also has the highest vapor pressure. Due to its smaller size, ethanol exhibits weaker dispersion forces than diethyl ether. However, ethanol is capable of hydrogen bonding and, therefore, exhibits stronger overall IMFs, which means that fewer molecules escape from the liquid at any given temperature, and so ethanol has a lower vapor pressure than diethyl ether. Water is much smaller than either of the previous substances and exhibits weaker dispersion forces, but its extensive hydrogen bonding provides stronger intermolecular attractions, fewer molecules escaping the liquid, and a lower vapor pressure than for either diethyl ether or ethanol. Ethylene glycol has two −OH groups, so, like water, it exhibits extensive hydrogen bonding. It is much larger than water and thus experiences larger London forces. Its overall IMFs are the largest of these four substances, which means its vaporization rate will be the slowest and, consequently, its vapor pressure the lowest.

Exercise 12.3.1

At 20 °C, the vapor pressures of several alcohols are given in this table. Explain these vapor pressures in terms of types and extents of IMFs for these alcohols:

At 20 °C, the vapor pressures of several alcohols

Compound	methanol CH_3OH	ethanol C_2H_5OH	propanol C_3H_7OH	butanol C_4H_9OH
Vapor Pressure at 20 °C	11.9 kPa	5.95 kPa	2.67 kPa	0.56 kPa

Answer

All these compounds exhibit hydrogen bonding; these strong IMFs are difficult for the molecules to overcome, so the vapor pressures are relatively low. As the size of molecule increases from methanol to butanol, dispersion forces increase, which means that the vapor pressures decrease as observed:

$$P_{methanol} > P_{ethanol} > P_{propanol} > P_{butanol}$$

As temperature increases, the vapor pressure of a liquid also increases due to the increased average KE of its molecules. Recall that at any given temperature, the molecules of a substance experience a range of kinetic energies, with a certain fraction of molecules having a sufficient energy to overcome IMF and escape the liquid (vaporize). At a higher temperature, a greater fraction of molecules have enough energy to escape from the liquid, as shown in Figure 12.3.2. The escape of more molecules per unit of time and the greater average speed of the molecules that escape both contribute to the higher vapor pressure.




Figure 12.3.2: Temperature affects the distribution of kinetic energies for the molecules in a liquid. At the higher temperature, more molecules have the necessary kinetic energy, KE, to escape from the liquid into the gas phase.

A graph is shown where the y-axis is labeled “Number of molecules” and the x-axis is labeled “Kinetic Energy.” Two lines are graphed and a vertical dotted line, labeled “Minimum K E needed to escape,” is drawn halfway across the x-axis. The first line move sharply upward and has a high peak near the left side of the x-axis. It drops just as steeply and ends about 60 percent of the way across the x-axis. This line is labeled “Low T.” A second line, labeled “High T,” begins at the same point as the first, but does not go to such a high point, is wider, and ends slightly further to the right on the x-axis.

Boiling Points

When the vapor pressure increases enough to equal the external atmospheric pressure, the liquid reaches its boiling point. The boiling point of a liquid is the temperature at which its equilibrium vapor pressure is equal to the pressure exerted on the liquid by its gaseous surroundings. For liquids in open containers, this pressure is that due to the earth’s atmosphere. The normal boiling point of a liquid is defined as its boiling point when surrounding pressure is equal to 1 atm (101.3 kPa). Figure **12.3.3** shows the variation in vapor pressure with temperature for several different substances. Considering the definition of boiling point, these curves may be seen as depicting the dependence of a liquid’s boiling point on surrounding pressure.




Figure 12.3.3: The boiling points of liquids are the temperatures at which their equilibrium vapor pressures equal the pressure of the surrounding atmosphere. Normal boiling points are those corresponding to a pressure of 1 atm (101.3 kPa.)

A graph is shown where the x-axis is labeled “Temperature (degree sign, C)” and has values of 200 to 1000 in increments of 200 and the y-axis is labeled “Pressure (k P a)” and has values of 20 to 120 in increments of 20. A horizontal dotted line extends across the graph at point 780 on the y-axis while three vertical dotted lines extend from points 35, 78, and 100 to meet the horizontal dotted line. Four lines are graphed. The first line, labeled “ethyl ether,” begins at the point “0 , 200” and extends in a slight curve to point “45, 1000” while the second line, labeled “ethanol”, extends from point “0, 20” to point “88, 1000” in a more extreme curve. The third line, labeled “water,” begins at the point “0, 0” and extends in a curve to point “108, 1000” while the fourth line, labeled “ethylene glycol,” extends from point “80, 0” to point “140, 100” in a very shallow curve.

Example 12.3.2: A Boiling Point at Reduced Pressure

A typical atmospheric pressure in Leadville, Colorado (elevation 10,200 feet) is 68 kPa. Use the graph in Figure **12.3.3** to determine the boiling point of water at this elevation.

Solution

The graph of the vapor pressure of water versus temperature in Figure **12.3.3** indicates that the vapor pressure of water is 68 kPa at about 90 °C. Thus, at about 90 °C, the vapor pressure of water will equal the atmospheric pressure in Leadville, and water will boil.

Exercise 12.3.2

The boiling point of ethyl ether was measured to be 10 °C at a base camp on the slopes of Mount Everest. Use Figure **12.3.3** to determine the approximate atmospheric pressure at the camp.

Answer

Approximately 40 kPa (0.4 atm)

The quantitative relation between a substance's vapor pressure and its temperature is described by the Clausius-Clapeyron equation:

$$P = Ae^{-\Delta H_{vap}/RT} \tag{12.3.1}$$

where

- ΔH_{vap} is the enthalpy of vaporization for the liquid,
- R is the gas constant, and
- $\ln A$ is a constant whose value depends on the chemical identity of the substance.

Equation 12.3.1 is often rearranged into logarithmic form to yield the linear equation:

$$\ln P = -\frac{\Delta H_{vap}}{RT} + \ln A \tag{12.3.2}$$

This linear equation may be expressed in a two-point format that is convenient for use in various computations, as demonstrated in the examples and exercises that follow. If at temperature T_1, the vapor pressure is P_1, and at temperature T_2, the vapor pressure is T_2, the corresponding linear equations are:

$$\ln P_1 = -\frac{\Delta H_{vap}}{RT_1} + \ln A$$

and

$$\ln P_2 = -\frac{\Delta H_{vap}}{RT_2} + \ln A \tag{12.3.3}$$

Since the constant, ln A, is the same, these two equations may be rearranged to isolate $\ln A$ and then set them equal to one another:

$$\ln P_1 + \frac{\Delta H_{vap}}{RT_1} = \ln P_2 + \frac{\Delta H_{vap}}{RT_2}$$

which can be combined into:

$$\ln\left(\frac{P_2}{P_1}\right) = \frac{\Delta H_{vap}}{R}\left(\frac{1}{T_1} - \frac{1}{T_2}\right) \tag{12.3.4}$$

Example 12.3.3: Estimating Enthalpy of Vaporization

Isooctane (2,2,4-trimethylpentane) has an octane rating of 100. It is used as one of the standards for the octane-rating system for gasoline. At 34.0 °C, the vapor pressure of isooctane is 10.0 kPa, and at 98.8 °C, its vapor pressure is 100.0 kPa. Use this information to estimate the enthalpy of vaporization for isooctane.

Solution

The enthalpy of vaporization, ΔH_{vap}, can be determined by using the Clausius-Clapeyron equation (Equation 12.3.4):

$$\ln\left(\frac{P_2}{P_1}\right) = \frac{\Delta H_{\text{vap}}}{R}\left(\frac{1}{T_1} - \frac{1}{T_2}\right)$$

Since we have two vapor pressure-temperature values

- $T_1 = 34.0°C = 307.2\,K$
- $P_1 = 10.0\,kPa$ and
- $T_2 = 98.8°C = 372.0\,K$
- $P_2 = 100\,kPa$

we can substitute them into this equation and solve for ΔH_{vap}. Rearranging the Clausius-Clapeyron equation and solving for ΔH_{vap} yields:

$$\begin{aligned}\Delta H_{\text{vap}} &= \frac{R \cdot \ln\left(\frac{P_2}{P_1}\right)}{\left(\frac{1}{T_1} - \frac{1}{T_2}\right)} \\ &= \frac{(8.3145\ J/mol \cdot K) \cdot \ln\left(\frac{100\ kPa}{10.0\ kPa}\right)}{\left(\frac{1}{307.2\ K} - \frac{1}{372.0\ K}\right)} \\ &= 33,800\ J/mol = 33.8\ kJ/mol\end{aligned}$$

Note that the pressure can be in any units, so long as they agree for both P values, but the temperature must be in kelvin for the Clausius-Clapeyron equation to be valid.

Exercise 12.3.3

At 20.0 °C, the vapor pressure of ethanol is 5.95 kPa, and at 63.5 °C, its vapor pressure is 53.3 kPa. Use this information to estimate the enthalpy of vaporization for ethanol.

Answer

47,782 J/mol = 47.8 kJ/mol

Example 12.3.4: Estimating Temperature (or Vapor Pressure)

For benzene (C_6H_6), the normal boiling point is 80.1 °C and the enthalpy of vaporization is 30.8 kJ/mol. What is the boiling point of benzene in Denver, where atmospheric pressure = 83.4 kPa?

Solution

If the temperature and vapor pressure are known at one point, along with the enthalpy of vaporization, ΔH_{vap}, then the temperature that corresponds to a different vapor pressure (or the vapor pressure that corresponds to a different temperature) can be determined by using the Clausius-Clapeyron equation (Equation 12.3.1) :

$$\ln\left(\frac{P_2}{P_1}\right) = \frac{\Delta H_{\text{vap}}}{R}\left(\frac{1}{T_1} - \frac{1}{T_2}\right)$$

Since the normal boiling point is the temperature at which the vapor pressure equals atmospheric pressure at sea level, we know one vapor pressure-temperature value (T_1 = 80.1 °C = 353.3 K, P_1 = 101.3 kPa, ΔH_{vap} = 30.8 kJ/mol) and want to find the temperature (T_2) that corresponds to vapor pressure P_2 = 83.4 kPa. We can substitute these values into the Clausius-Clapeyron equation and then solve for T_2. Rearranging the Clausius-Clapeyron equation and solving for T_2 yields:

$$\begin{aligned} T_2 &= \left(\frac{-R \cdot \ln\left(\frac{P_2}{P_1}\right)}{\Delta H_{vap}} + \frac{1}{T_1} \right)^{-1} \\ &= \left(\frac{-(8.3145\ \text{J/mol·K}) \cdot \ln\left(\frac{83.4\ \text{kPa}}{101.3\ \text{kPa}}\right)}{30{,}800\ \text{J/mol}} + \frac{1}{353.3\ \text{K}} \right)^{-1} \\ &= 346.9\ \text{K or } 73.8^\circ\text{C} \end{aligned}$$

Exercise 12.3.4

For acetone $(CH_3)_2CO$, the normal boiling point is 56.5 °C and the enthalpy of vaporization is 31.3 kJ/mol. What is the vapor pressure of acetone at 25.0 °C?

Answer

30.1 kPa

Enthalpy of Vaporization

Vaporization is an endothermic process. The cooling effect can be evident when you leave a swimming pool or a shower. When the water on your skin evaporates, it removes heat from your skin and causes you to feel cold. The energy change associated with the vaporization process is the enthalpy of vaporization, ΔH_{vap}. For example, the vaporization of water at standard temperature is represented by:

$$H_2O(l) \longrightarrow H_2O(g) \quad \Delta H_{vap} = 44.01\ \text{kJ/mol}$$

As described in the chapter on thermochemistry, the reverse of an endothermic process is exothermic. And so, the condensation of a gas releases heat:

$$H_2O(g) \longrightarrow H_2O(l) \quad \Delta H_{con} = -\Delta H_{vap} = -44.01\ \text{kJ/mol}$$

Example 12.3.5: Using Enthalpy of Vaporization

One way our body is cooled is by evaporation of the water in sweat (Figure 12.3.4). In very hot climates, we can lose as much as 1.5 L of sweat per day. Although sweat is not pure water, we can get an approximate value of the amount of heat removed by evaporation by assuming that it is. How much heat is required to evaporate 1.5 L of water (1.5 kg) at T = 37 °C (normal body temperature); $\Delta H_{vap} = 43.46\ kJ/mol$ at 37 °C.



Figure 12.3.4: Evaporation of sweat helps cool the body. (credit: “Kullez”/Flickr)

Solution We start with the known volume of sweat (approximated as just water) and use the given information to convert to the amount of heat needed:

$$1.5 \cancel{L} \times \frac{1000 \cancel{g}}{1 \cancel{L}} \times \frac{1 \cancel{\text{mol}}}{18 \cancel{g}} \times \frac{43.46 \text{ kJ}}{1 \cancel{\text{mol}}} = 3.6 \times 10^3 \text{ kJ}$$

Thus, 3600 kJ of heat are removed by the evaporation of 1.5 L of water.

? Exercise 12.3.5: Boiling Ammonia

How much heat is required to evaporate 100.0 g of liquid ammonia, NH_3, at its boiling point if its enthalpy of vaporization is 4.8 kJ/mol?

Answer

28 kJ

Melting and Freezing

When we heat a crystalline solid, we increase the average energy of its atoms, molecules, or ions and the solid gets hotter. At some point, the added energy becomes large enough to partially overcome the forces holding the molecules or ions of the solid in their fixed positions, and the solid begins the process of transitioning to the liquid state, or melting. At this point, the temperature of the solid stops rising, despite the continual input of heat, and it remains constant until all of the solid is melted. Only after all of the solid has melted will continued heating increase the temperature of the liquid (Figure 12.3.5.



Figure 12.3.5: (a) This beaker of ice has a temperature of −12.0 °C. (b) After 10 minutes the ice has absorbed enough heat from the air to warm to 0 °C. A small amount has melted. (c) Thirty minutes later, the ice has absorbed more heat, but its temperature is still 0 °C. The ice melts without changing its temperature. (d) Only after all the ice has melted does the heat absorbed cause the temperature to increase to 22.2 °C. (credit: modification of work by Mark Ott).

This figure shows four photos each labeled, “a,” “b,” “c,” and, “d.” Each photo shows a beaker with ice and a digital thermometer. The first photo shows ice cubes in the beaker, and the thermometer reads negative 12.0 degrees C. The second photo shows slightly melted ice, and the thermometer reads 0.0 degrees C. The third photo shows more water than ice in the beaker. The thermometer reads 0.0 degrees C. The fourth photo shows the ice completely melted, and the thermometer reads 22.2 degrees C.

If we stop heating during melting and place the mixture of solid and liquid in a perfectly insulated container so no heat can enter or escape, the solid and liquid phases remain in equilibrium. This is almost the situation with a mixture of ice and water in a very good thermos bottle; almost no heat gets in or out, and the mixture of solid ice and liquid water remains for hours. In a mixture of solid and liquid at equilibrium, the reciprocal processes of melting and freezing occur at equal rates, and the quantities of solid and liquid therefore remain constant. The temperature at which the solid and liquid phases of a given substance are in equilibrium is called the melting point of the solid or the freezing point of the liquid. Use of one term or the other is normally dictated by the direction of the phase transition being considered, for example, solid to liquid (melting) or liquid to solid (freezing).

The enthalpy of fusion and the melting point of a crystalline solid depend on the strength of the attractive forces between the units present in the crystal. Molecules with weak attractive forces form crystals with low melting points. Crystals consisting of particles with stronger attractive forces melt at higher temperatures.

The amount of heat required to change one mole of a substance from the solid state to the liquid state is the enthalpy of fusion, ΔHfus of the substance. The enthalpy of fusion of ice is 6.0 kJ/mol at 0 °C. Fusion (melting) is an endothermic process:

$$\mathrm{H_2O_{(s)} \rightarrow H_2O_{(l)} \quad \Delta H_{fus} = 6.01\ kJ/mol} \tag{12.3.5}$$

The reciprocal process, freezing, is an exothermic process whose enthalpy change is −6.0 kJ/mol at 0 °C:

$$\mathrm{H_2O_{(l)} \rightarrow H_2O_{(s)} \quad \Delta H_{frz} = -\Delta H_{fus} = -6.01\ kJ/mol} \tag{12.3.6}$$

Sublimation and Deposition

Some solids can transition directly into the gaseous state, bypassing the liquid state, via a process known as sublimation. At room temperature and standard pressure, a piece of dry ice (solid CO_2) sublimes, appearing to gradually disappear without ever forming any liquid. Snow and ice sublime at temperatures below the melting point of water, a slow process that may be accelerated by winds and the reduced atmospheric pressures at high altitudes. When solid iodine is warmed, the solid sublimes and a vivid purple vapor forms (Figure **12.3.6**). The reverse of sublimation is called deposition, a process in which gaseous substances condense directly into the solid state, bypassing the liquid state. The formation of frost is an example of deposition.



Figure **12.3.6**: Sublimation of solid iodine in the bottom of the tube produces a purple gas that subsequently deposits as solid iodine on the colder part of the tube above. (credit: modification of work by Mark Ott)

This figure shows a test tube. In the bottom is a dark substance which breaks up into a purple gas at the top.

Like vaporization, the process of sublimation requires an input of energy to overcome intermolecular attractions. The enthalpy of sublimation, ΔHsub, is the energy required to convert one mole of a substance from the solid to the gaseous state. For example, the sublimation of carbon dioxide is represented by:

$$\mathrm{CO_2(s) \longrightarrow CO_2(g) \quad \Delta H_{sub} = 26.1\ kJ/mol}$$

Likewise, the enthalpy change for the reverse process of deposition is equal in magnitude but opposite in sign to that for sublimation:

$$\mathrm{CO_2(g) \longrightarrow CO_2(s) \quad \Delta H_{dep} = -\Delta H_{sub} = -26.1\ kJ/mol}$$

Consider the extent to which intermolecular attractions must be overcome to achieve a given phase transition. Converting a solid into a liquid requires that these attractions be only partially overcome; transition to the gaseous state requires that they be completely overcome. As a result, the enthalpy of fusion for a substance is less than its enthalpy of vaporization. This same logic

can be used to derive an approximate relation between the enthalpies of all phase changes for a given substance. Though not an entirely accurate description, sublimation may be conveniently modeled as a sequential two-step process of melting followed by vaporization in order to apply Hess's Law.

$$\begin{aligned} \text{solid} &\longrightarrow \text{liquid} \quad \Delta H_{\text{fus}} \\ \text{liquid} &\longrightarrow \text{gas} \quad \Delta H_{\text{vap}} \\ \hline \text{solid} &\longrightarrow \text{gas} \quad \Delta H_{\text{sub}} = \Delta H_{\text{fus}} + \Delta H_{\text{vap}} \end{aligned}$$

Viewed in this manner, the enthalpy of sublimation for a substance may be estimated as the sum of its enthalpies of fusion and vaporization, as illustrated in Figure 12.3.7. For example:




Figure 12.3.7: For a given substance, the sum of its enthalpy of fusion and enthalpy of vaporization is approximately equal to its enthalpy of sublimation.

A diagram is shown with a vertical line drawn on the left side and labeled "Energy" and three horizontal lines drawn near the bottom, lower third and top of the diagram. These three lines are labeled, from bottom to top, "Solid," "Liquid" and "Gas." Near the middle of the diagram, a vertical, upward-facing arrow is drawn from the solid line to the gas line and labeled "Sublimation, delta sign, H, subscript sub." To the right of this arrow is a second vertical, upward-facing arrow that is drawn from the solid line to the liquid line and labeled "Fusion, delta sign, H, subscript fus." Above the second arrow is a third arrow drawn from the liquid line to the gas line and labeled, "Vaporization, delta sign, H, subscript vap."

Heating and Cooling Curves

In the chapter on thermochemistry, the relation between the amount of heat absorbed or related by a substance, q, and its accompanying temperature change, ΔT, was introduced:

$$q = mc\Delta T$$

where m is the mass of the substance and c is its specific heat. The relation applies to matter being heated or cooled, but not undergoing a change in state. When a substance being heated or cooled reaches a temperature corresponding to one of its phase transitions, further gain or loss of heat is a result of diminishing or enhancing intermolecular attractions, instead of increasing or decreasing molecular kinetic energies. While a substance is undergoing a change in state, its temperature remains constant. Figure 12.3.8 shows a typical heating curve.




Figure **12.3.8**: A typical heating curve for a substance depicts changes in temperature that result as the substance absorbs increasing amounts of heat. Plateaus in the curve (regions of constant temperature) are exhibited when the substance undergoes phase transitions.

A graph is shown where the x-axis is labeled “Amount of heat added” and the y-axis is labeled “Temperature (degree sign C)” and has values of negative 10 to 100 in increments of 20. A right-facing horizontal arrow extends from point “0, 0” to the right side of the graph. A line graph begins at the lower left of the graph and moves to point “0” on the y-axis. This segment of the line is labeled “H, subscript 2, O (s).” The line then flattens and travels horizontally for a small distance. This segment is labeled “Solid begins to melt” on its left side and “All solid melted” on its right side. The line then goes steeply upward in a linear fashion until it hits point “100” on the y-axis. This segment of the line is labeled “H, subscript 2, O,(l).” The line then flattens and travels horizontally for a moderate distance. This segment is labeled “Liquid begins to boil” on its left side and “All liquid evaporated” on its right side. The line then rises to a point above “100” on the y-axis. This segment of the line is labeled “H, subscript 2, O (g).”

Consider the example of heating a pot of water to boiling. A stove burner will supply heat at a roughly constant rate; initially, this heat serves to increase the water’s temperature. When the water reaches its boiling point, the temperature remains constant despite the continued input of heat from the stove burner. This same temperature is maintained by the water as long as it is boiling. If the burner setting is increased to provide heat at a greater rate, the water temperature does not rise, but instead the boiling becomes more vigorous (rapid). This behavior is observed for other phase transitions as well: For example, temperature remains constant while the change of state is in progress.

✔ Example **12.3.6**: Total Heat Needed to Change Temperature and Phase for a Substance

How much heat is required to convert 135 g of ice at −15 °C into water vapor at 120 °C?

Solution

The transition described involves the following steps:

1. Heat ice from −15 °C to 0 °C
2. Melt ice
3. Heat water from 0 °C to 100 °C
4. Boil water
5. Heat steam from 100 °C to 120 °C

The heat needed to change the temperature of a given substance (with no change in phase) is: $q = m \times c \times \Delta T$ (see previous chapter on thermochemistry). The heat needed to induce a given change in phase is given by $q = n \times \Delta H$.

Using these equations with the appropriate values for specific heat of ice, water, and steam, and enthalpies of fusion and vaporization, we have:

$$q_{\text{total}} = (m \cdot c \cdot \Delta T)_{\text{ice}} + n \cdot \Delta H_{\text{fus}} + (m \cdot c \cdot \Delta T)_{\text{water}} + n \cdot \Delta H_{\text{vap}} + (m \cdot c \cdot \Delta T)_{\text{steam}}$$

$$= (135\ \text{g} \cdot 2.09\ \text{J/g·°C} \cdot 15\text{°C}) + \left(135 \cdot \frac{1\ \text{mol}}{18.02\ \text{g}} \cdot 6.01\ \text{kJ/mol}\right)$$

$$+(135\ \text{g} \cdot 4.18\ \text{J/g·°C} \cdot 100\text{°C}) + \left(135\ \text{g} \cdot \frac{1\ \text{mol}}{18.02\ \text{g}} \cdot 40.67\ \text{kJ/mol}\right)$$

$$+(135\ \text{g} \cdot 1.84\ \text{J/g·°C} \cdot 20\text{°C})$$

$$= 4230\ \text{J} + 45.0\ \text{kJ} + 56,500\ \text{J} + 305\ \text{kJ} + 4970\ \text{J}$$

Converting the quantities in J to kJ permits them to be summed, yielding the total heat required:

$$= 4.23\ \text{kJ} + 45.0\ \text{kJ} + 56.5\ \text{kJ} + 305\ \text{kJ} + 4.97\ \text{kJ} = 416\ \text{kJ}$$

? Exercise 12.3.6

What is the total amount of heat released when 94.0 g water at 80.0 °C cools to form ice at −30.0 °C?

Answer

40.5 kJ

Summary

Phase transitions are processes that convert matter from one physical state into another. There are six phase transitions between the three phases of matter. Melting, vaporization, and sublimation are all endothermic processes, requiring an input of heat to overcome intermolecular attractions. The reciprocal transitions of freezing, condensation, and deposition are all exothermic processes, involving heat as intermolecular attractive forces are established or strengthened. The temperatures at which phase transitions occur are determined by the relative strengths of intermolecular attractions and are, therefore, dependent on the chemical identity of the substance.

Key Equations

- $P = Ae^{-\Delta H_{\text{vap}}/RT}$
- $\ln P = -\dfrac{\Delta H_{\text{vap}}}{RT} + \ln A$
- $\ln\left(\dfrac{P_2}{P_1}\right) = \dfrac{\Delta H_{\text{vap}}}{R}\left(\dfrac{1}{T_1} - \dfrac{1}{T_2}\right)$

Glossary

boiling point
temperature at which the vapor pressure of a liquid equals the pressure of the gas above it

Clausius-Clapeyron equation
mathematical relationship between the temperature, vapor pressure, and enthalpy of vaporization for a substance

condensation
change from a gaseous to a liquid state

deposition
change from a gaseous state directly to a solid state

dynamic equilibrium
state of a system in which reciprocal processes are occurring at equal rates

freezing
change from a liquid state to a solid state

freezing point

temperature at which the solid and liquid phases of a substance are in equilibrium; see also *melting point*

melting

change from a solid state to a liquid state

melting point

temperature at which the solid and liquid phases of a substance are in equilibrium; see also *freezing point*

normal boiling point

temperature at which a liquid’s vapor pressure equals 1 atm (760 torr)

sublimation

change from solid state directly to gaseous state

vapor pressure

(also, equilibrium vapor pressure) pressure exerted by a vapor in equilibrium with a solid or a liquid at a given temperature

vaporization

change from liquid state to gaseous state

12.3: Phase Changes is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **10.4: Phase Transitions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

12.4: Phase diagram

Learning Objectives

- Explain the construction and use of a typical phase diagram
- Use phase diagrams to identify stable phases at given temperatures and pressures, and to describe phase transitions resulting from changes in these properties
- Describe the supercritical fluid phase of matter

In the previous module, the variation of a liquid's equilibrium vapor pressure with temperature was described. Considering the definition of boiling point, plots of vapor pressure versus temperature represent how the boiling point of the liquid varies with pressure. Also described was the use of heating and cooling curves to determine a substance's melting (or freezing) point. Making such measurements over a wide range of pressures yields data that may be presented graphically as a phase diagram. A phase diagram combines plots of pressure versus temperature for the liquid-gas, solid-liquid, and solid-gas phase-transition equilibria of a substance. These diagrams indicate the physical states that exist under specific conditions of pressure and temperature, and also provide the pressure dependence of the phase-transition temperatures (melting points, sublimation points, boiling points). A typical phase diagram for a pure substance is shown in Figure **12.4.1**.




Figure **12.4.1**: The physical state of a substance and its phase-transition temperatures are represented graphically in a phase diagram.

A graph is shown where the x-axis is labeled "Temperature" and the y-axis is labeled "Pressure." A line extends from the lower left bottom of the graph sharply upward to a point that is a third across the x-axis. A second line begins at the lower third of the first line at a point labeled "triple point" and extends to the upper right corner of the graph where it is labeled "critical point." The two lines bisect the graph area to create three sections, labeled "solid" near the top left, "liquid" in the top middle and "gas" near the bottom right. A pair of horizontal arrows, one left-facing and labeled "deposition" and one right-facing and labeled" sublimation," are drawn on top of the bottom section of the first line. A second pair of horizontal arrows, one left-facing and labeled "freezing" and one right-facing and labeled "melting", are drawn on top of the upper section of the first line. A third pair of horizontal arrows, one left-facing and labeled "condensation" and one right-facing and labeled "vaporization," are drawn on top of the middle section of the second line.

To illustrate the utility of these plots, consider the phase diagram for water shown in Figure **12.4.2**.




Figure **12.4.2**: The pressure and temperature axes on this phase diagram of water are not drawn to constant scale in order to illustrate several important properties.

A graph is shown where the x-axis is labeled “Temperature in degrees Celsius” and the y-axis is labeled “Pressure (k P a).” A line extends from the origin of the graph which is labeled “A” sharply upward to a point in the bottom third of the diagram labeled “B” where it branches into a line that slants slightly backward until it hits the highest point on the y-axis labeled “D” and a second line that extends to the upper right corner of the graph labeled “C”. C is labeled “Critical point, with a dotted line extending downward to the x-axis labeled 374 degrees Celsius, and another dotted line extending to the y-axis labeled 22,089 k P a. The two lines bisect the graph area to create three sections, labeled “Ice (solid)” near the middle left, “Water (liquid)” in the top middle and “Water vapor (gas)” near the bottom middle. Point B is labeled “Triple point” and has a dotted line extending downward to the x-axis labeled 0.01, and another dotted line extending to the y-axis labeled 0.6. Halfway between points B and C a dotted line extends from the originally discussed line downward to the point 100 degrees Celsius on the x-axis, and another dotted line extends to the y-axis at 101 k P a. Another dotted line extends from this dotted line downward at 0 degrees Celsius.

We can use the phase diagram to identify the physical state of a sample of water under specified conditions of pressure and temperature. For example, a pressure of 50 kPa and a temperature of −10 °C correspond to the region of the diagram labeled “ice.” Under these conditions, water exists only as a solid (ice). A pressure of 50 kPa and a temperature of 50 °C correspond to the “water” region—here, water exists only as a liquid. At 25 kPa and 200 °C, water exists only in the gaseous state. Note that on the H_2O phase diagram, the pressure and temperature axes are not drawn to a constant scale in order to permit the illustration of several important features as described here.

The curve BC in Figure **12.4.2** is the plot of vapor pressure versus temperature as described in the previous module of this chapter. This “liquid-vapor” curve separates the liquid and gaseous regions of the phase diagram and provides the boiling point for water at any pressure. For example, at 1 atm, the boiling point is 100 °C. Notice that the liquid-vapor curve terminates at a temperature of 374 °C and a pressure of 218 atm, indicating that water cannot exist as a liquid above this temperature, regardless of the pressure. The physical properties of water under these conditions are intermediate between those of its liquid and gaseous phases. This unique state of matter is called a supercritical fluid, a topic that will be described in the next section of this module.

The solid-vapor curve, labeled AB in Figure **12.4.2**, indicates the temperatures and pressures at which ice and water vapor are in equilibrium. These temperature-pressure data pairs correspond to the sublimation, or deposition, points for water. If we could zoom in on the solid-gas line in Figure **12.4.2**, we would see that ice has a vapor pressure of about 0.20 kPa at −10 °C. Thus, if we place a frozen sample in a vacuum with a pressure less than 0.20 kPa, ice will sublime. This is the basis for the “freeze-drying” process often used to preserve foods, such as the ice cream shown in Figure **12.4.3**.



Figure **12.4.3**: Freeze-dried foods, like this ice cream, are dehydrated by sublimation at pressures below the triple point for water. (credit: "lwao"/Flickr)

The solid-liquid curve labeled BD shows the temperatures and pressures at which ice and liquid water are in equilibrium, representing the melting/freezing points for water. Note that this curve exhibits a slight negative slope (greatly exaggerated for clarity), indicating that the melting point for water decreases slightly as pressure increases. Water is an unusual substance in this regard, as most substances exhibit an increase in melting point with increasing pressure. This behavior is partly responsible for the movement of glaciers, like the one shown in Figure **12.4.4**. The bottom of a glacier experiences an immense pressure due to its weight that can melt some of the ice, forming a layer of liquid water on which the glacier may more easily slide.



Figure **12.4.4**: The immense pressures beneath glaciers result in partial melting to produce a layer of water that provides lubrication to assist glacial movement. This satellite photograph shows the advancing edge of the Perito Moreno glacier in Argentina. (credit: NASA)

A photograph shows an aerial view of a land mass. The white mass of a glacier is shown near the top left quadrant of the photo and leads to two branching blue rivers. The open land is shown in brown.

The point of intersection of all three curves is labeled B in Figure **12.4.2**. At the pressure and temperature represented by this point, all three phases of water coexist in equilibrium. This temperature-pressure data pair is called the triple point. At pressures lower than the triple point, water cannot exist as a liquid, regardless of the temperature.

✔ Example 12.4.1: Determining the State of Water

Using the phase diagram for water given in Figure 10.4.2, determine the state of water at the following temperatures and pressures:

a. −10 °C and 50 kPa
b. 25 °C and 90 kPa
c. 50 °C and 40 kPa
d. 80 °C and 5 kPa
e. −10 °C and 0.3 kPa
f. 50 °C and 0.3 kPa

Solution

Using the phase diagram for water, we can determine that the state of water at each temperature and pressure given are as follows: (a) solid; (b) liquid; (c) liquid; (d) gas; (e) solid; (f) gas.

Exercise 12.4.1

What phase changes can water undergo as the temperature changes if the pressure is held at 0.3 kPa? If the pressure is held at 50 kPa?

Answer

At 0.3 kPa: s⟶ g at −58 °C. At 50 kPa: s⟶ l at 0 °C, l ⟶ g at 78 °C

Consider the phase diagram for carbon dioxide shown in Figure **12.4.5** as another example. The solid-liquid curve exhibits a positive slope, indicating that the melting point for CO_2 increases with pressure as it does for most substances (water being a notable exception as described previously). Notice that the triple point is well above 1 atm, indicating that carbon dioxide cannot exist as a liquid under ambient pressure conditions. Instead, cooling gaseous carbon dioxide at 1 atm results in its deposition into the solid state. Likewise, solid carbon dioxide does not melt at 1 atm pressure but instead sublimes to yield gaseous CO_2. Finally, notice that the critical point for carbon dioxide is observed at a relatively modest temperature and pressure in comparison to water.




Figure **12.4.5**: The pressure and temperature axes on this phase diagram of carbon dioxide are not drawn to constant scale in order to illustrate several important properties.

A graph is shown where the x-axis is labeled “Temperature (degree sign, C)” and has values of negative 100 to 100 in increments of 25 and the y-axis is labeled “Pressure (k P a)” and has values of 10 to 1,000,000. A line extends from the lower left bottom of the graph upward to a point around“27, 9000,” where it ends. The space under this curve is labeled “Gas.” A second line extends in a curve from point around “-73, 100” to “27, 1,000,000.” The area to the left of this line and above the first line is labeled “Solid” while the area to the right is labeled “Liquid.” A section on the graph under the second line and past the point “28” on the x-axis is labeled “S C F.”

Example 12.4.2: Determining the State of Carbon Dioxide

Using the phase diagram for carbon dioxide shown in Figure 10.4.5, determine the state of CO_2 at the following temperatures and pressures:

a. −30 °C and 2000 kPa
b. −60 °C and 1000 kPa
c. −60 °C and 100 kPa
d. 20 °C and 1500 kPa
e. 0 °C and 100 kPa
f. 20 °C and 100 kPa

Solution

Using the phase diagram for carbon dioxide provided, we can determine that the state of CO_2 at each temperature and pressure given are as follows: (a) liquid; (b) solid; (c) gas; (d) liquid; (e) gas; (f) gas.

? Exercise 12.4.2

Determine the phase changes carbon dioxide undergoes when its temperature is varied, thus holding its pressure constant at 1500 kPa? At 500 kPa? At what approximate temperatures do these phase changes occur?

Answer

at 1500 kPa: s⟶ l at −45 °C, l⟶ g at −10 °C; at 500 kPa: s⟶ g at −58 °C

Supercritical Fluids

If we place a sample of water in a sealed container at 25 °C, remove the air, and let the vaporization-condensation equilibrium establish itself, we are left with a mixture of liquid water and water vapor at a pressure of 0.03 atm. A distinct boundary between the more dense liquid and the less dense gas is clearly observed. As we increase the temperature, the pressure of the water vapor increases, as described by the liquid-gas curve in the phase diagram for water (Figure **12.4.2**), and a two-phase equilibrium of liquid and gaseous phases remains. At a temperature of 374 °C, the vapor pressure has risen to 218 atm, and any further increase in temperature results in the disappearance of the boundary between liquid and vapor phases. All of the water in the container is now present in a single phase whose physical properties are intermediate between those of the gaseous and liquid states. This phase of matter is called a supercritical fluid, and the temperature and pressure above which this phase exists is the critical point (Figure **12.4.5**). Above its critical temperature, a gas cannot be liquefied no matter how much pressure is applied. The pressure required to liquefy a gas at its critical temperature is called the critical pressure. The critical temperatures and critical pressures of some common substances are given in Table **12.4.1**.

Table **12.4.1**: Critical Temperatures and Critical Pressures of select substances

Substance	Critical Temperature (K)	Critical Pressure (atm)
hydrogen	33.2	12.8
nitrogen	126.0	33.5
oxygen	154.3	49.7
carbon dioxide	304.2	73.0
ammonia	405.5	111.5
sulfur dioxide	430.3	77.7
water	647.1	217.7

Like a gas, a supercritical fluid will expand and fill a container, but its density is much greater than typical gas densities, typically being close to those for liquids. Similar to liquids, these fluids are capable of dissolving nonvolatile solutes. They exhibit essentially no surface tension and very low viscosities, however, so they can more effectively penetrate very small openings in a solid mixture and remove soluble components. These properties make supercritical fluids extremely useful solvents for a wide range of applications. For example, supercritical carbon dioxide has become a very popular solvent in the food industry, being used to decaffeinate coffee, remove fats from potato chips, and extract flavor and fragrance compounds from citrus oils. It is nontoxic, relatively inexpensive, and not considered to be a pollutant. After use, the CO_2 can be easily recovered by reducing the pressure and collecting the resulting gas.




Figure 12.4.6: (a) A sealed container of liquid carbon dioxide slightly below its critical point is heated, resulting in (b) the formation of the supercritical fluid phase. Cooling the supercritical fluid lowers its temperature and pressure below the critical point, resulting in the reestablishment of separate liquid and gaseous phases (c and d). Colored floats illustrate differences in density between the liquid, gaseous, and supercritical fluid states. (credit: modification of work by "mrmrobin"/YouTube)

Four photographs are shown where each shows a circular container with a green and red float in each. In the left diagram, the container is half filled with a colorless liquid and the floats sit on the surface of the liquid. In the second photo, the green float is near the top and the red float lies near the bottom of the container. In the third photo, the fluid is darker and the green float sits halfway up the container while the red is sitting at the bottom. In the right photo, the liquid is colorless again and the two floats sit on the surface.

Example 12.4.3: The Critical Temperature of Carbon Dioxide

If we shake a carbon dioxide fire extinguisher on a cool day (18 °C), we can hear liquid CO_2 sloshing around inside the cylinder. However, the same cylinder appears to contain no liquid on a hot summer day (35 °C). Explain these observations.

Solution

On the cool day, the temperature of the CO_2 is below the critical temperature of CO_2, 304 K or 31 °C (Table 12.4.1), so liquid CO_2 is present in the cylinder. On the hot day, the temperature of the CO_2 is greater than its critical temperature of 31 °C. Above this temperature no amount of pressure can liquefy CO_2 so no liquid CO_2 exists in the fire extinguisher.

Exercise 12.4.3

Ammonia can be liquefied by compression at room temperature; oxygen cannot be liquefied under these conditions. Why do the two gases exhibit different behavior?

Answer

The critical temperature of ammonia is 405.5 K, which is higher than room temperature. The critical temperature of oxygen is below room temperature; thus oxygen cannot be liquefied at room temperature.

Decaffeinating Coffee Using Supercritical CO_2

Coffee is the world's second most widely traded commodity, following only petroleum. Across the globe, people love coffee's aroma and taste. Many of us also depend on one component of coffee—caffeine—to help us get going in the morning or stay alert in the afternoon. But late in the day, coffee's stimulant effect can keep you from sleeping, so you may choose to drink decaffeinated coffee in the evening.

Since the early 1900s, many methods have been used to decaffeinate coffee. All have advantages and disadvantages, and all depend on the physical and chemical properties of caffeine. Because caffeine is a somewhat polar molecule, it dissolves well in water, a polar liquid. However, since many of the other 400-plus compounds that contribute to coffee's taste and aroma also dissolve in H_2O, hot water decaffeination processes can also remove some of these compounds, adversely affecting the smell and taste of the decaffeinated coffee. Dichloromethane (CH_2Cl_2) and ethyl acetate ($CH_3CO_2C_2H_5$) have similar polarity to caffeine, and are therefore very effective solvents for caffeine extraction, but both also remove some flavor and aroma components, and their use requires long extraction and cleanup times. Because both of these solvents are toxic, health concerns have been raised regarding the effect of residual solvent remaining in the decaffeinated coffee.




Figure **12.4.7**: (a) Caffeine molecules have both polar and nonpolar regions, making it soluble in solvents of varying polarities. (b) The schematic shows a typical decaffeination process involving supercritical carbon dioxide.

Two images are shown and labeled “a” and “b.” Image a shows a molecule composed of a five member ring composed of two blue spheres and three black spheres. One of the blue spheres is bonded to a black sphere bonded to three white spheres and one of the black spheres is bonded to a white sphere. The other two black spheres are double bonded together and make up one side of a six-membered ring that is also composed of two more black spheres and two blue spheres, both of which are bonded to a black sphere bonded to three white spheres. The black spheres are each double bonded to red spheres. Image b shows a diagram of two vertical tubes that lie next to one another. The left-hand tube is labeled “Extraction vessel.” A small tube labeled “Soaked beans” leads into the top of the tube and a label at the bottom of the tube reads “Decaffeinated beans.” The right tube is labeled “Absorption vessel.” A tube near the top of this tube is labeled “Water” and another tube leads from the right tube to the left. This tube is labeled with a left-facing arrow and the phrase “supercritical carbon dioxide.” There is a tube leading away from the bottom which is labeled, “Caffeine and water.” There is another tube that leads from the extraction vessel to the absorption vessel which is labeled, “supercritical C O subscript 2 plus caffeine.”

Supercritical fluid extraction using carbon dioxide is now being widely used as a more effective and environmentally friendly decaffeination method (Figure **12.4.7**). At temperatures above 304.2 K and pressures above 7376 kPa, CO_2 is a supercritical fluid, with properties of both gas and liquid. Like a gas, it penetrates deep into the coffee beans; like a liquid, it effectively dissolves certain substances. Supercritical carbon dioxide extraction of steamed coffee beans removes 97−99% of the caffeine, leaving coffee’s flavor and aroma compounds intact. Because CO_2 is a gas under standard conditions, its removal from the extracted coffee beans is easily accomplished, as is the recovery of the caffeine from the extract. The caffeine recovered from coffee beans via this process is a valuable product that can be used subsequently as an additive to other foods or drugs.

Summary

The temperature and pressure conditions at which a substance exists in solid, liquid, and gaseous states are summarized in a phase diagram for that substance. Phase diagrams are combined plots of three pressure-temperature equilibrium curves: solid-liquid, liquid-gas, and solid-gas. These curves represent the relationships between phase-transition temperatures and pressures. The point of intersection of all three curves represents the substance’s triple point—the temperature and pressure at which all three phases are in equilibrium. At pressures below the triple point, a substance cannot exist in the liquid state, regardless of its temperature. The terminus of the liquid-gas curve represents the substance’s critical point, the pressure and temperature above which a liquid phase cannot exist.

Glossary

critical point

temperature and pressure above which a gas cannot be condensed into a liquid

phase diagram

pressure-temperature graph summarizing conditions under which the phases of a substance can exist

supercritical fluid

substance at a temperature and pressure higher than its critical point; exhibits properties intermediate between those of gaseous and liquid states

triple point

temperature and pressure at which the vapor, liquid, and solid phases of a substance are in equilibrium

---

12.4: Phase diagram is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **10.5: Phase Diagrams** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

12.5: The Solid State of Matter

Learning Objectives

- Define and describe the bonding and properties of ionic, molecular, metallic, and covalent network crystalline solids
- Describe the main types of crystalline solids: ionic solids, metallic solids, covalent network solids, and molecular solids
- Explain the ways in which crystal defects can occur in a solid

When most liquids are cooled, they eventually freeze and form crystalline solids, solids in which the atoms, ions, or molecules are arranged in a definite repeating pattern. It is also possible for a liquid to freeze before its molecules become arranged in an orderly pattern. The resulting materials are called amorphous solids or noncrystalline solids (or, sometimes, glasses). The particles of such solids lack an ordered internal structure and are randomly arranged (Figure **12.5.1**).




Figure **12.5.1**: The entities of a solid phase may be arranged in a regular, repeating pattern (crystalline solids) or randomly (amorphous).

The crystalline arrangement shows many circles drawn in rows and stacked together tightly. The amorphous arrangement shows many circles spread slightly apart and in no organized pattern.

Metals and ionic compounds typically form ordered, crystalline solids. Substances that consist of large molecules, or a mixture of molecules whose movements are more restricted, often form amorphous solids. For examples, candle waxes are amorphous solids composed of large hydrocarbon molecules. Some substances, such as boron oxide (Figure **12.5.2**), can form either crystalline or amorphous solids, depending on the conditions under which it is produced. Also, amorphous solids may undergo a transition to the crystalline state under appropriate conditions.




Figure **12.5.2**: (a) Diboron trioxide, B_2O_3, is normally found as a white, amorphous solid (a glass), which has a high degree of disorder in its structure. (b) By careful, extended heating, it can be converted into a crystalline form of B_2O_3, which has a very ordered arrangement.

The first structure of diboron trioxide shows five identical and separated hexagonal rings. The second structure of diboron trioxide shows a more interconnected structure with four large rings forming a more stable structure.

Crystalline solids are generally classified according the nature of the forces that hold its particles together. These forces are primarily responsible for the physical properties exhibited by the bulk solids. The following sections provide descriptions of the major types of crystalline solids: ionic, metallic, covalent network, and molecular.

Ionic Solids

Ionic solids, such as sodium chloride and nickel oxide, are composed of positive and negative ions that are held together by electrostatic attractions, which can be quite strong (Figure **12.5.3**). Many ionic crystals also have high melting points. This is due to the very strong attractions between the ions—in ionic compounds, the attractions between full charges are (much) larger than those between the partial charges in polar molecular compounds. This will be looked at in more detail in a later discussion of lattice energies. Although they are hard, they also tend to be brittle, and they shatter rather than bend. Ionic solids do not conduct electricity; however, they do conduct when molten or dissolved because their ions are free to move. Many simple compounds formed by the reaction of a metallic element with a nonmetallic element are ionic.




Figure **12.5.3**: Sodium chloride is an ionic solid.

A cube composed of purple and green spheres is shown. The cube has dimensions of three by three spheres. The purple spheres are slightly larger than the green spheres.

Metallic Solids

Metallic solids such as crystals of copper, aluminum, and iron are formed by metal atoms Figure **12.5.4**. The structure of metallic crystals is often described as a uniform distribution of atomic nuclei within a “sea” of delocalized electrons. The atoms within such a metallic solid are held together by a unique force known as *metallic bonding* that gives rise to many useful and varied bulk properties. All exhibit high thermal and electrical conductivity, metallic luster, and malleability. Many are very hard and quite strong. Because of their malleability (the ability to deform under pressure or hammering), they do not shatter and, therefore, make useful construction materials. The melting points of the metals vary widely. Mercury is a liquid at room temperature, and the alkali metals melt below 200 °C. Several post-transition metals also have low melting points, whereas the transition metals melt at temperatures above 1000 °C. These differences reflect differences in strengths of metallic bonding among the metals.




Figure **12.5.4**: Copper is a metallic solid.

Covalent Network Solids

Covalent network solids include crystals of diamond, silicon, some other nonmetals, and some covalent compounds such as silicon dioxide (sand) and silicon carbide (carborundum, the abrasive on sandpaper). Many minerals have networks of covalent bonds. The atoms in these solids are held together by a network of covalent bonds, as shown in Figure **12.5.5**. To break or to melt a covalent network solid, covalent bonds must be broken. Because covalent bonds are relatively strong, covalent network solids are typically characterized by hardness, strength, and high melting points. For example, diamond is one of the hardest substances known and melts above 3500 °C.




Figure **12.5.5**. A covalent crystal contains a three-dimensional network of covalent bonds, as illustrated by the structures of diamond, silicon dioxide, silicon carbide, and graphite. Graphite is an exceptional example, composed of planar sheets of covalent crystals that are held together in layers by noncovalent forces. Unlike typical covalent solids, graphite is very soft and electrically conductive.

The complex three dimensional structure of diamond, silicon dioxide, silicon carbide and graphite is shown along with a a smaller repeating unit of the structure shown above each structure.

Molecular Solids

Molecular solids, such as ice, sucrose (table sugar), and iodine, as shown in Figure **12.5.6**, are composed of neutral molecules. The strengths of the attractive forces between the units present in different crystals vary widely, as indicated by the melting points of the crystals. Small symmetrical molecules (nonpolar molecules), such as H_2, N_2, O_2, and F_2, have weak attractive forces and form molecular solids with very low melting points (below −200 °C). Substances consisting of larger, nonpolar molecules have larger attractive forces and melt at higher temperatures. Molecular solids composed of molecules with permanent dipole moments (polar molecules) melt at still higher temperatures. Examples include ice (melting point, 0 °C) and table sugar (melting point, 185 °C).




Figure **12.5.6**: Carbon dioxide (CO_2) consists of small, nonpolar molecules and forms a molecular solid with a melting point of −78 °C. Iodine (I_2) consists of larger, nonpolar molecules and forms a molecular solid that melts at 114 °C.

On the left, many red and grey molecules are densely stacked in a 3-D drawing to represent carbon dioxide. On the right, purple molecules are scattered randomly to represent iodine.

Properties of Solids

A crystalline solid, like those listed in Table **12.5.1** has a precise melting temperature because each atom or molecule of the same type is held in place with the same forces or energy. Thus, the attractions between the units that make up the crystal all have the same strength and all require the same amount of energy to be broken. The gradual softening of an amorphous material differs dramatically from the distinct melting of a crystalline solid. This results from the structural nonequivalence of the molecules in the amorphous solid. Some forces are weaker than others, and when an amorphous material is heated, the weakest intermolecular attractions break first. As the temperature is increased further, the stronger attractions are broken. Thus amorphous materials soften over a range of temperatures.

Table 12.5.1: Types of Crystalline Solids and Their Properties

Type of Solid	Type of Particles	Type of Attractions	Properties	Examples
ionic	ions	ionic bonds	hard, brittle, conducts electricity as a liquid but not as a solid, high to very high melting points	NaCl, Al_2O_3
metallic	atoms of electropositive elements	metallic bonds	shiny, malleable, ductile, conducts heat and electricity well, variable hardness and melting temperature	Cu, Fe, Ti, Pb, U
covalent network	atoms of electronegative elements	covalent bonds	very hard, not conductive, very high melting points	C (diamond), SiO_2, SiC
molecular	molecules (or atoms)	IMFs	variable hardness, variable brittleness, not conductive, low melting points	H_2O, CO_2, I_2, $C_{12}H_{22}O_{11}$

Graphene: Material of the Future

Carbon is an essential element in our world. The unique properties of carbon atoms allow the existence of carbon-based life forms such as ourselves. Carbon forms a huge variety of substances that we use on a daily basis, including those shown in Figure 12.5.7. You may be familiar with diamond and graphite, the two most common *allotropes* of carbon. (Allotropes are different structural forms of the same element.) Diamond is one of the hardest-known substances, whereas graphite is soft enough to be used as pencil lead. These very different properties stem from the different arrangements of the carbon atoms in the different allotropes.




Figure **12.5.7**: Diamond is extremely hard because of the strong bonding between carbon atoms in all directions. Graphite (in pencil lead) rubs off onto paper due to the weak attractions between the carbon layers. An image of a graphite surface shows the distance between the centers of adjacent carbon atoms. (credit left photo: modification of work by Steve Jurvetson; credit middle photo: modification of work by United States Geological Survey)

A close up of a piece of diamond shows a three dimensional sturcture of a complex network of well bonded carbon atoms. A close up of a graphite shows several layers of carbon sheets. Each sheet is composed of a repeated and connected hexagonal structure of carbon atoms. The third diagram shows that the distance between the center of atoms is 1.4 times 10 to the power of negative 10 meters.

You may be less familiar with a recently discovered form of carbon: graphene. Graphene was first isolated in 2004 by using tape to peel off thinner and thinner layers from graphite. It is essentially a single sheet (one atom thick) of graphite. Graphene, illustrated in Figure **12.5.8**, is not only strong and lightweight, but it is also an excellent conductor of electricity and heat. These properties may prove very useful in a wide range of applications, such as vastly improved computer chips and circuits, better batteries and solar cells, and stronger and lighter structural materials. The 2010 Nobel Prize in Physics was awarded to Andre Geim and Konstantin Novoselov for their pioneering work with graphene.




Figure 12.5.8: Graphene sheets can be formed into buckyballs, nanotubes, and stacked layers.

A sheet of interconnected hexagonal rings is shown at the top. Below it, a bukcyball is shown which is a sphere is composed of hexagonal rings. In the lower middle image, a nanotube is shown that is made by rolling a graphene sheet into a tube. In the lower right image, stacked sheets made up of four horizontal sheets composed of joined, hexagonal rings is shown.

Crystal Defects

In a crystalline solid, the atoms, ions, or molecules are arranged in a definite repeating pattern, but occasional defects may occur in the pattern. Several types of defects are known, as illustrated in Figure 12.5.9. Vacancies are defects that occur when positions that should contain atoms or ions are vacant. Less commonly, some atoms or ions in a crystal may occupy positions, called interstitial sites, located between the regular positions for atoms. Other distortions are found in impure crystals, as, for example, when the cations, anions, or molecules of the impurity are too large to fit into the regular positions without distorting the structure. Trace amounts of impurities are sometimes added to a crystal (a process known as *doping)* in order to create defects in the structure that yield desirable changes in its properties. For example, silicon crystals are doped with varying amounts of different elements to yield suitable electrical properties for their use in the manufacture of semiconductors and computer chips.




Figure 12.5.9: Types of crystal defects include vacancies, interstitial atoms, and substitutions impurities.

Summary

Some substances form crystalline solids consisting of particles in a very organized structure; others form amorphous (noncrystalline) solids with an internal structure that is not ordered. The main types of crystalline solids are ionic solids, metallic

solids, covalent network solids, and molecular solids. The properties of the different kinds of crystalline solids are due to the types of particles of which they consist, the arrangements of the particles, and the strengths of the attractions between them. Because their particles experience identical attractions, crystalline solids have distinct melting temperatures; the particles in amorphous solids experience a range of interactions, so they soften gradually and melt over a range of temperatures. Some crystalline solids have defects in the definite repeating pattern of their particles. These defects (which include vacancies, atoms or ions not in the regular positions, and impurities) change physical properties such as electrical conductivity, which is exploited in the silicon crystals used to manufacture computer chips.

Glossary

amorphous solid

(also, noncrystalline solid) solid in which the particles lack an ordered internal structure

covalent network solid

solid whose particles are held together by covalent bonds

crystalline solid

solid in which the particles are arranged in a definite repeating pattern

interstitial sites

spaces between the regular particle positions in any array of atoms or ions

ionic solid

solid composed of positive and negative ions held together by strong electrostatic attractions

metallic solid

solid composed of metal atoms

molecular solid

solid composed of neutral molecules held together by intermolecular forces of attraction

vacancy

defect that occurs when a position that should contain an atom or ion is vacant

---

12.5: The Solid State of Matter is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **10.6: The Solid State of Matter** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

12.6: Lattice Structure in Crystalline Solids

Learning Objectives

- Describe the arrangement of atoms and ions in crystalline structures
- Compute ionic radii using unit cell dimensions
- Explain the use of X-ray diffraction measurements in determining crystalline structures

Over 90% of naturally occurring and man-made solids are crystalline. Most solids form with a regular arrangement of their particles because the overall attractive interactions between particles are maximized, and the total intermolecular energy is minimized, when the particles pack in the most efficient manner. The regular arrangement at an atomic level is often reflected at a macroscopic level. In this module, we will explore some of the details about the structures of metallic and ionic crystalline solids, and learn how these structures are determined experimentally.

The Structures of Metals

We will begin our discussion of crystalline solids by considering elemental metals, which are relatively simple because each contains only one type of atom. A pure metal is a crystalline solid with metal atoms packed closely together in a repeating pattern. Some of the properties of metals in general, such as their malleability and ductility, are largely due to having identical atoms arranged in a regular pattern. The different properties of one metal compared to another partially depend on the sizes of their atoms and the specifics of their spatial arrangements. We will explore the similarities and differences of four of the most common metal crystal geometries in the sections that follow.

Unit Cells of Metals

The structure of a crystalline solid, whether a metal or not, is best described by considering its simplest repeating unit, which is referred to as its unit cell. The unit cell consists of lattice points that represent the locations of atoms or ions. The entire structure then consists of this unit cell repeating in three dimensions, as illustrated in Figure **12.6.1**.




Figure **12.6.1**: A unit cell shows the locations of lattice points repeating in all directions.

A diagram of two images is shown. In the first image, a cube with a sphere at each corner is shown. The cube is labeled “Unit cell” and the spheres at the corners are labeled “Lattice points.” The second image shows the same cube, but this time it is one cube amongst eight that make up a larger cube. The original cube is shaded a color while the other cubes are not.

Let us begin our investigation of crystal lattice structure and unit cells with the most straightforward structure and the most basic unit cell. To visualize this, imagine taking a large number of identical spheres, such as tennis balls, and arranging them uniformly in a container. The simplest way to do this would be to make layers in which the spheres in one layer are directly above those in the layer below, as illustrated in Figure **12.6.2**. This arrangement is called simple cubic structure, and the unit cell is called the simple cubic unit cell or primitive cubic unit cell.





Figure 12.6.2: .When metal atoms are arranged with spheres in one layer directly above or below spheres in another layer, the lattice structure is called simple cubic. Note that the spheres are in contact.

A diagram of three images is shown. In the first image, a cube with a sphere at each corner is shown. The spheres at the corners are circled. The second image shows the same cube, but this time the spheres at the corners are larger and shaded in. In the third image, the cube is one cube amongst eight that make up a larger cube. The original cube is shaded a color while the other cubes are not.

In a simple cubic structure, the spheres are not packed as closely as they could be, and they only "fill" about 52% of the volume of the container. This is a relatively inefficient arrangement, and only one metal (polonium, Po) crystallizes in a simple cubic structure. As shown in Figure 12.6.3, a solid with this type of arrangement consists of planes (or layers) in which each atom contacts only the four nearest neighbors in its layer; one atom directly above it in the layer above; and one atom directly below it in the layer below. The number of other particles that each particle in a crystalline solid contacts is known as its coordination number. For a polonium atom in a simple cubic array, the coordination number is, therefore, six.



" height="200" width="463" src="/@api/deki/files/61021/CNX_Chem_10_06_SimpleCub2.jpg">

Figure 12.6.3: An atom in a simple cubic lattice structure contacts six other atoms, so it has a coordination number of six.

In a simple cubic lattice, the unit cell that repeats in all directions is a cube defined by the centers of eight atoms, as shown in Figure 12.6.4. Atoms at adjacent corners of this unit cell contact each other, so the edge length of this cell is equal to two atomic radii, or one atomic diameter. A cubic unit cell contains only the parts of these atoms that are within it. Since an atom at a corner of a simple cubic unit cell is contained by a total of eight unit cells, only one-eighth of that atom is within a specific unit cell. And since each simple cubic unit cell has one atom at each of its eight "corners," there is $8 \times \frac{1}{8} = 1$ atom within one simple cubic unit cell.




Figure 12.6.4: A simple cubic lattice unit cell contains one-eighth of an atom at each of its eight corners, so it contains one atom total.

A diagram of two images is shown. In the first image, eight spheres are stacked together to form a cube and dots at the center of each sphere are connected to form a cube shape. The dots are labeled "Lattice points" while a label under the image reads "Simple cubic lattice cell." The second image shows the portion of each sphere that lie inside the cube. The corners of the cube are shown with small circles labeled "Lattice points" and the phrase "8 corners" is written below the image.


Example 12.6.1: Calculating Atomic Radius and Density for Metals (Part 1)

The edge length of the unit cell of alpha polonium is 336 pm.

a. Determine the radius of a polonium atom.
b. Determine the density of alpha polonium.

Solution

Alpha polonium crystallizes in a simple cubic unit cell:



(a) Two adjacent Po atoms contact each other, so the edge length of this cell is equal to two Po atomic radii: $l = 2r$. Therefore, the radius of Po is

$$r = \frac{l}{2} = \frac{336\ \text{pm}}{2} = 168\ \text{pm}$$

(b) Density is given by

$$\text{density} = \frac{\text{mass}}{\text{volume}}.$$

The density of polonium can be found by determining the density of its unit cell (the mass contained within a unit cell divided by the volume of the unit cell). Since a Po unit cell contains one-eighth of a Po atom at each of its eight corners, a unit cell contains one Po atom.

The mass of a Po unit cell can be found by:

$$1\ \text{Po unit cell} \times \frac{1\ \text{Po atom}}{1\ \text{Po unit cell}} \times \frac{1\ \text{mol Po}}{6.022 \times 10^{23}\ \text{Po atoms}} \times \frac{208.998\ \text{g}}{1\ \text{mol Po}} = 3.47 \times 10^{-22}\ \text{g}$$

The volume of a Po unit cell can be found by:

$$V = l^3 = (336 \times 10^{-10}\ \text{cm})^3 = 3.79 \times 10^{-23}\ \text{cm}^3$$

(Note that the edge length was converted from pm to cm to get the usual volume units for density.)

Therefore, the density of

$$\text{Po} = \frac{3.471 \times 10^{-22}\ \text{g}}{3.79 \times 10^{-23}\ \text{cm}^3} = 9.16\ \text{g/cm}^3$$

? Exercise 12.6.1

The edge length of the unit cell for nickel is 0.3524 nm. The density of Ni is 8.90 g/cm^3. Does nickel crystallize in a simple cubic structure? Explain.

Answer

No. If Ni were simple cubic, its density would be given by:

$$1\ \text{Ni atom} \times \frac{1\ \text{mol Ni}}{6.022 \times 10^{23}\ \text{Ni atoms}} \times \frac{58.693\ \text{g}}{1\ \text{mol Ni}} = 9.746 \times 10^{-23}\ \text{g}$$

$$V = l^3 = (3.524 \times 10^{-8}\ \text{cm})^3 = 4.376 \times 10^{-23}\ \text{cm}^3$$

Then the density of Ni would be

$$(= \frac{9.746 \times 10^{-23}\ \text{g}}{4.376 \times 10^{-23}\ \text{cm}^3} = 2.23\ \text{g/cm}^3$$

> Since the actual density of Ni is not close to this, Ni does not form a simple cubic structure.

Most metal crystals are one of the four major types of unit cells. For now, we will focus on the three cubic unit cells: simple cubic (which we have already seen), body-centered cubic unit cell, and face-centered cubic unit cell—all of which are illustrated in Figure **12.6.5**. (Note that there are actually seven different lattice systems, some of which have more than one type of lattice, for a total of 14 different types of unit cells. We leave the more complicated geometries for later in this module.)




Figure **12.6.5**: Cubic unit cells of metals show (in the upper figures) the locations of lattice points and (in the lower figures) metal atoms located in the unit cell.

Three pairs of images are shown. The first three images are in a row and are labeled “Lattice point locations” while the second three images are in a row labeled “Cubic unit cells.” The first image in the top row shows a cube with black dots at each corner while the first image in the second row is composed of eight spheres that are stacked together to form a cube and dots at the center of each sphere are connected to form a cube shape. The name under this image reads “Simple cubic.” The second image in the top row shows a cube with black dots at each corner and a red dot in the center while the second image in the second row is composed of eight spheres that are stacked together to form a cube with one sphere in the center of the cube and dots at the center of each corner sphere connected to form a cube shape. The name under this image reads “Body-centered cubic.” The third image in the top row shows a cube with black dots at each corner and red dots in the center of each face while the third image in the second row is composed of eight spheres that are stacked together to form a cube with six more spheres located in the center of each face of the cube. Dots at the center of each corner sphere are connected to form a cube shape. The name under this image reads “Face-centered cubic.”

Some metals crystallize in an arrangement that has a cubic unit cell with atoms at all of the corners and an atom in the center, as shown in Figure **12.6.6**. This is called a body-centered cubic (BCC) solid. Atoms in the corners of a BCC unit cell do not contact each other but contact the atom in the center. A BCC unit cell contains two atoms: one-eighth of an atom at each of the eight corners ($8 \times \frac{1}{8} = 1$ atom from the corners) plus one atom from the center. Any atom in this structure touches four atoms in the layer above it and four atoms in the layer below it. Thus, an atom in a BCC structure has a coordination number of eight.




Figure **12.6.6**: In a body-centered cubic structure, atoms in a specific layer do not touch each other. Each atom touches four atoms in the layer above it and four atoms in the layer below it.

Three images are shown. The first image shows a cube with black dots at each corner and a red dot in the center while the second image is composed of eight spheres that are stacked together to form a cube with one sphere in the center of the cube and dots at the center of each corner sphere connected to form a cube shape. The name under this image reads “Body-centered cubic structure.” The third image is the same as the second, but only shows the portions of the spheres that lie inside the cube shape.

Atoms in BCC arrangements are much more efficiently packed than in a simple cubic structure, occupying about 68% of the total volume. Isomorphous metals with a BCC structure include K, Ba, Cr, Mo, W, and Fe at room temperature. (Elements or compounds that crystallize with the same structure are said to be isomorphous.)

Many other metals, such as aluminum, copper, and lead, crystallize in an arrangement that has a cubic unit cell with atoms at all of the corners and at the centers of each face, as illustrated in Figure **12.6.7**. This arrangement is called a face-centered cubic (FCC) solid. A FCC unit cell contains four atoms: one-eighth of an atom at each of the eight corners ($8 \times \frac{1}{8} = 1$ atom from the corners) and one-half of an atom on each of the six faces ($6 \times \frac{1}{2} = 3$ atoms from the faces). The atoms at the corners touch the atoms in the centers of the adjacent faces along the face diagonals of the cube. Because the atoms are on identical lattice points, they have identical environments.




Figure **12.6.7**:A face-centered cubic solid has atoms at the corners and, as the name implies, at the centers of the faces of its unit cells.

Three images are shown. The first image shows a cube with black dots at each corner and red dots in the center of each face of the cube while the second image is composed of eight spheres that are stacked together to form a cube with six more spheres, one located on each face of the structure. Dots at the center of each corner sphere are connected to form a cube shape. The name under this image reads “Face-centered cubic structure.” The third image is the same as the second, but only shows the portions of the spheres that lie inside the cube shape.

Atoms in an FCC arrangement are packed as closely together as possible, with atoms occupying 74% of the volume. This structure is also called cubic closest packing (CCP). In CCP, there are three repeating layers of hexagonally arranged atoms. Each atom contacts six atoms in its own layer, three in the layer above, and three in the layer below. In this arrangement, each atom touches 12 near neighbors, and therefore has a coordination number of 12. The fact that FCC and CCP arrangements are equivalent may not be immediately obvious, but why they are actually the same structure is illustrated in Figure **12.6.8**.




Figure **12.6.8**: A CCP arrangement consists of three repeating layers (ABCABC…) of hexagonally arranged atoms. Atoms in a CCP structure have a coordination number of 12 because they contact six atoms in their layer, plus three atoms in the layer above and three atoms in the layer below. By rotating our perspective, we can see that a CCP structure has a unit cell with a face containing an atom from layer A at one corner, atoms from layer B across a diagonal (at two corners and in the middle of the face), and an atom from layer C at the remaining corner. This is the same as a face-centered cubic arrangement.

Three images are shown. In the first image, a side view shows a layer of blue spheres, labeled “C” stacked on top of, and sitting in between the gaps in a second layer that is composed of green spheres, labeled “B,” which are sitting atop a purple layer of spheres labeled “A.” A label below this image reads “Side view.” The second image shows a top view of the same layers of spheres, where the top layer is “C,” the second layer is “B” and the lowest layer is “C.” This image is labeled “Top view” and written under this is the phrase “Cubic closest packed structure.” The third image shows an upper view of the side of a cube composed of two sets of the repeating layers shown in the other images. The layers are arranged “C, B, A, C, B, A, C” and the phrase written under this image reads “Rotated view.”

Because closer packing maximizes the overall attractions between atoms and minimizes the total intermolecular energy, the atoms in most metals pack in this manner. We find two types of closest packing in simple metallic crystalline structures: CCP, which we have already encountered, and hexagonal closest packing (HCP) shown in Figure **12.6.9**. Both consist of repeating layers of hexagonally arranged atoms. In both types, a second layer (B) is placed on the first layer (A) so that each atom in the second layer is in contact with three atoms in the first layer. The third layer is positioned in one of two ways. In HCP, atoms in the third layer are directly above atoms in the first layer (i.e., the third layer is also type A), and the stacking consists of alternating type A and type B close-packed layers (i.e., ABABAB⋯). In CCP, atoms in the third layer are not above atoms in either of the first two layers (i.e., the third layer is type C), and the stacking consists of alternating type A, type B, and type C close-packed layers (i.e., ABCABCABC⋯). About two–thirds of all metals crystallize in closest-packed arrays with coordination numbers of 12. Metals that crystallize in an HCP structure include Cd, Co, Li, Mg, Na, and Zn, and metals that crystallize in a CCP structure include Ag, Al, Ca, Cu, Ni, Pb, and Pt.




Figure **12.6.9**: In both types of closest packing, atoms are packed as compactly as possible. Hexagonal closest packing consists of two alternating layers (ABABAB…). Cubic closest packing consists of three alternating layers (ABCABCABC…).

Two images are shown. The first image, labeled “Hexagonal closest packed,” shows seven green spheres arranged in a circular sheet lying atop another sheet that is the same except the spheres are purple. The second sheet is offset just a bit so that the spheres of the top sheet lie in the grooves of the second sheet. Two more alternating green and purple layers of spheres lie below the first pair. The second image shows seven blue spheres, labeled “Layer C,” arranged in a circular sheet laying atop another sheet, labeled “Layer B” that is the same except the spheres are green. The second sheet is offset just a bit so that the spheres of the top sheet lie in the grooves of the second sheet. Two more alternating purple and then blue layers of spheres lie below the first pair. The purple layer is labeled “Layer A” and the phrase written below this image reads “Cubic closest packed.”


✔ Example 12.6.2: Calculating Atomic Radius and Density for Metals (Part 2)

Calcium crystallizes in a face-centered cubic structure. The edge length of its unit cell is 558.8 pm.

a. What is the atomic radius of Ca in this structure?
b. Calculate the density of Ca.

Solution

(a) In an FCC structure, Ca atoms contact each other across the diagonal of the face, so the length of the diagonal is equal to four Ca atomic radii (d = 4*r*).



Two adjacent edges and the diagonal of the face form a right triangle, with the length of each side equal to 558.8 pm and the length of the hypotenuse equal to four Ca atomic radii:

$$a^2 + a^2 = d^2$$

$$(558.8\ \text{pm})^2 + (558.5\ \text{pm})^2 = (4r)^2$$

Solving this gives

$$r = \sqrt{\frac{(558.8\ \text{pm})^2 + (558.5\ \text{pm})^2}{16}} = 197.6\ \text{pmg for a Ca radius.}$$

(b) Density is given by $\textbf{density} = \frac{\textbf{mass}}{\textbf{volume}}$. The density of calcium can be found by determining the density of its unit cell: for example, the mass contained within a unit cell divided by the volume of the unit cell. A face-centered Ca unit cell has one-eighth of an atom at each of the eight corners ($8 \times \frac{1}{8} = 1$atom) and one-half of an atom on each of the six faces $6 \times \frac{1}{2} = 3$ atoms), for a total of four atoms in the unit cell.

The mass of the unit cell can be found by:

$$1\ \text{Ca unit cell} \times \frac{4\ \text{Ca atoms}}{1\ \text{Ca unit cell}} \times \frac{1\ \text{mol Ca}}{6.022 \times 10^{23}\ \text{Ca atoms}} \times \frac{40.078\ \text{g}}{1\ \text{mol Ca}} = 2.662 \times 10^{-22}\ \text{g}$$

The volume of a Ca unit cell can be found by:

$$V = a^3 = (558.8 \times 10^{-10}\ \text{cm})^3 = 1.745 \times 10^{-22}\ \text{cm}^3$$

(Note that the edge length was converted from pm to cm to get the usual volume units for density.)

Then, the density of polonium:

$$\text{Po} = \frac{2.662 \times 10^{-22}\ \text{g}}{1.745 \times 10^{-22}\ \text{cm}^3} = 1.53\ \text{g/cm}^3$$

? Exercise 12.6.2

Silver crystallizes in an FCC structure. The edge length of its unit cell is 409 pm.

a. What is the atomic radius of Ag in this structure?
b. Calculate the density of Ag.

Answer a

144 pm

Answer b

10.5 g/cm^3

In general, a unit cell is defined by the lengths of three axes (*a*, *b*, and *c*) and the angles (*α*, *β*, and *γ*) between them, as illustrated in Figure **12.6.10**. The axes are defined as being the lengths between points in the space lattice. Consequently, unit cell axes join points with identical environments.




Figure **12.6.10**: A unit cell is defined by the lengths of its three axes (a, b, and c) and the angles (α, β, and γ) between the axes.

A cube is shown where each corner has a black dot drawn on it. A circle in the bottom of the cube is composed of three double-ended arrows. The left top of this circle is labeled “alpha,” the top right is labeled “beta” and the bottom is labeled “gamma.” The bottom left corner of the cube is labeled “a” while the bottom of the back face is labeled “b” and the top, back, left corner is labeled “c.”

There are seven different lattice systems, some of which have more than one type of lattice, for a total of fourteen different unit cells, which have the shapes shown in Figure **12.6.11**.






System/Axes/Angles	Unit Cells
Cubic $a = b = c$ $\alpha = \beta = \gamma = 90^\circ$	
Tetragonal $a = b \neq c$ $\alpha = \beta = \gamma = 90^\circ$	
Orthorhombic $a \neq b \neq c$ $\alpha = \beta = \gamma = 90^\circ$	
Monoclinic $a \neq b \neq c$ $\alpha = \gamma = 90^\circ; \beta \neq 90^\circ$	
Triclinic $a \neq b \neq c$ $\alpha \neq \beta \neq \gamma \neq 90^\circ$	
Hexagonal $a = b \neq c$ $\alpha = \beta = 90^\circ; \gamma = 120^\circ$	
Rhombohedral $a = b = c$ $\alpha = \beta = \gamma \neq 90^\circ$	

Figure **12.6.11**:There are seven different lattice systems and 14 different unit cells.

A table is composed of two columns and eight rows. The header row reads “System / Axes / Angles” and “Unit Cells .” The first column reads “Cubic, a equals b equals c, alpha equals beta equals gamma equals 90 degrees,” “Tetragonal, a equals b does not equal c, alpha equals beta equals gamma equals 90 degrees,” “Orthorhombic, a does not equal b does not equal c, alpha equals beta equals gamma equals 90 degrees,” “Monoclinic, a does not equal b does not equal c, alpha equals gamma equals 90 degrees, beta does not equal 90 degrees,” “Triclinic, a does not equal b does not equal c, alpha does not equal beta does not equal gamma does not equal 90 degrees,” “Hexagonal, a equals b does not equal c, alpha equals beta equals 90 degrees, gamma equals 120 degrees,” “Rhombohedral, a equals b equals c, alpha equals beta equals gamma does not equal 90 degrees.” The second column is composed of diagrams. The first set of diagrams in the first cell show a cube with spheres at each corner labeled “Simple,” a cube with spheres in each corner and on each face labeled “Face-centered” and a cube with spheres in each corner and one in the center labeled “Body-centered.” The second set of diagrams in the second cell show a vertical rectangle with spheres at each corner labeled “Simple” and a vertical rectangle with spheres in each corner and one in the center labeled “Body-centered.” The third set of diagrams in the third cell show a vertical rectangle with spheres at each corner labeled “Simple,” a vertical rectangle with spheres in each corner and one in the center labeled “Body-centered,” a vertical rectangle with spheres in each corner and one on the top and bottom faces labeled “Base-centered,” and a vertical rectangle with spheres in each corner and one on each face labeled “Face-centered.” The fourth set of diagrams in the fourth cell show a vertical rectangle with spheres at each corner that is slanted to one side labeled “Simple” and a vertical rectangle with spheres in each corner that is slanted to one side and has two spheres in the center is labeled “Body-centered.” The fifth diagrams in the fifth cell show a cube that is slanted with spheres at each corner while the sixth diagram in the sixth cell shows a pair of hexagonal rings that are connected together to form a six-sided shape with spheres at each corner. The seventh diagram in the seventh cell shows a rectangle that is slanted with spheres at each corner.

The Structures of Ionic Crystals

Ionic crystals consist of two or more different kinds of ions that usually have different sizes. The packing of these ions into a crystal structure is more complex than the packing of metal atoms that are the same size. Most monatomic ions behave as charged spheres, and their attraction for ions of opposite charge is the same in every direction. Consequently, stable structures for ionic compounds result (1) when ions of one charge are surrounded by as many ions as possible of the opposite charge and (2) when the cations and anions are in contact with each other. Structures are determined by two principal factors: the relative sizes of the ions and the ratio of the numbers of positive and negative ions in the compound.

In simple ionic structures, we usually find the anions, which are normally larger than the cations, arranged in a closest-packed array. (As seen previously, additional electrons attracted to the same nucleus make anions larger and fewer electrons attracted to the same nucleus make cations smaller when compared to the atoms from which they are formed.) The smaller cations commonly occupy one of two types of holes (or interstices) remaining between the anions. The smaller of the holes is found between three anions in one plane and one anion in an adjacent plane. The four anions surrounding this hole are arranged at the corners of a tetrahedron, so the hole is called a tetrahedral hole. The larger type of hole is found at the center of six anions (three in one layer and three in an adjacent layer) located at the corners of an octahedron; this is called an octahedral hole. Figure **12.6.12** illustrates both of these types of holes.




Figure **12.6.12**: Cations may occupy two types of holes between anions: octahedral holes or tetrahedral holes.

An image shows a top-view of a layer of blue spheres arranged in a sheet lying atop another sheet that is the same except the spheres are green. The second sheet is offset just a bit so that the spheres of the top sheet lie in the grooves of the second sheet. A third sheet composed of purple spheres lies at the bottom. The spaces created between the spheres in each layer are labeled “Octahedral holes” and “Tetrahedral holes.”

Depending on the relative sizes of the cations and anions, the cations of an ionic compound may occupy tetrahedral or octahedral holes, as illustrated in Figure **12.6.13**. Relatively small cations occupy tetrahedral holes, and larger cations occupy octahedral holes. If the cations are too large to fit into the octahedral holes, the anions may adopt a more open structure, such as a simple cubic array. The larger cations can then occupy the larger cubic holes made possible by the more open spacing.




Figure **12.6.13**:A cation's size and the shape of the hole occupied by the compound are directly related.

A diagram of three images is shown. In the first image, eight stacked cubes, with purple spheres at each corner, that make up one large cube are shown. The bottom left cube is different. It has green spheres at each corner and has four orange and six light purple spheres located on the faces of the cube. Labels below this structure read "Tetrahedral hole" and "Cation radius is about 22.5 to 41.4 percent of the anion radius. In the second image, eight stacked cubes, with alternating orange and green spheres at each corner, make up one large cube that is shown. The bottom left cube has darker lines that connect the spheres together. Labels below this structure read "Octahedral hole" and "Cation radius is about 41.4 to 73.2 percent of the anion radius. In the third image, eight stacked cubes, with purple spheres at each corner and light purple spheres on their interior faces, make up one large cube that is shown. Labels below this structure read "Cubic hole" and "Cation radius is about 73.2 to 100 percent of the anion radius."

There are two tetrahedral holes for each anion in either an HCP or CCP array of anions. A compound that crystallizes in a closest-packed array of anions with cations in the tetrahedral holes can have a maximum cation:anion ratio of 2:1; all of the tetrahedral holes are filled at this ratio. Examples include Li_2O, Na_2O, Li_2S, and Na_2S. Compounds with a ratio of less than 2:1 may also crystallize in a closest-packed array of anions with cations in the tetrahedral holes, if the ionic sizes fit. In these compounds, however, some of the tetrahedral holes remain vacant.

✔ Example 12.6.3: Occupancy of Tetrahedral Holes

Zinc sulfide is an important industrial source of zinc and is also used as a white pigment in paint. Zinc sulfide crystallizes with zinc ions occupying one-half of the tetrahedral holes in a closest-packed array of sulfide ions. What is the formula of zinc sulfide?

Solution

Because there are two tetrahedral holes per anion (sulfide ion) and one-half of these holes are occupied by zinc ions, there must be $\frac{1}{2} \times 2$, or 1, zinc ion per sulfide ion. Thus, the formula is ZnS.

? Exercise 12.6.3: Lithium selenide

Lithium selenide can be described as a closest-packed array of selenide ions with lithium ions in all of the tetrahedral holes. What it the formula of lithium selenide?

Answer

Li_2Se

The ratio of octahedral holes to anions in either an HCP or CCP structure is 1:1. Thus, compounds with cations in octahedral holes in a closest-packed array of anions can have a maximum cation:anion ratio of 1:1. In NiO, MnS, NaCl, and KH, for example, all of the octahedral holes are filled. Ratios of less than 1:1 are observed when some of the octahedral holes remain empty.

✔ Example 12.6.4: Stoichiometry of Ionic Compounds Sapphire

Aluminum oxide crystallizes with aluminum ions in two-thirds of the octahedral holes in a closest-packed array of oxide ions. What is the formula of aluminum oxide?

Solution

Because there is one octahedral hole per anion (oxide ion) and only two-thirds of these holes are occupied, the ratio of aluminum to oxygen must be $\frac{2}{3}$:1, which would give $\mathbf{Al_{2/3}O}$. The simplest whole number ratio is 2:3, so the formula is Al_2O_3.

? Exercise 12.6.4

The white pigment titanium oxide crystallizes with titanium ions in one-half of the octahedral holes in a closest-packed array of oxide ions. What is the formula of titanium oxide?

Answer

$\mathbf{TiO_2}$

In a simple cubic array of anions, there is one cubic hole that can be occupied by a cation for each anion in the array. In CsCl, and in other compounds with the same structure, all of the cubic holes are occupied. Half of the cubic holes are occupied in SrH_2, UO_2, $SrCl_2$, and CaF_2.

Different types of ionic compounds often crystallize in the same structure when the relative sizes of their ions and their stoichiometries (the two principal features that determine structure) are similar.

Unit Cells of Ionic Compounds

Many ionic compounds crystallize with cubic unit cells, and we will use these compounds to describe the general features of ionic structures. When an ionic compound is composed of cations and anions of similar size in a 1:1 ratio, it typically forms a simple cubic structure. Cesium chloride, CsCl, (Figure **12.6.14**) is an example of this, with Cs^+ and Cl^- having radii of 174 pm and 181 pm, respectively. We can think of this as chloride ions forming a simple cubic unit cell, with a cesium ion in the center; or as cesium ions forming a unit cell with a chloride ion in the center; or as simple cubic unit cells formed by Cs^+ ions overlapping unit cells formed by Cl^- ions. Cesium ions and chloride ions touch along the body diagonals of the unit cells. One cesium ion and one chloride ion are present per unit cell, giving the l:l stoichiometry required by the formula for cesium chloride. Note that there is no lattice point in the center of the cell, and CsCl is not a BCC structure because a cesium ion is not identical to a chloride ion.



Figure **12.6.14**: Ionic compounds with similar-sized cations and anions, such as CsCl, usually form a simple cubic structure. They can be described by unit cells with either cations at the corners or anions at the corners.

Three images are shown. The first image shows a cube with black dots at each corner and a red dot in the center. This cube is stacked with seven others that are not colored to form a larger cube. The second image is composed of eight spheres that are grouped together to form a cube with one smaller sphere in the center. The name under this image reads “Body-centered simple cubic structure.” The third image shows five horizontal layers of purple spheres with layers of smaller green spheres in between.

We have said that the location of lattice points is arbitrary. This is illustrated by an alternate description of the CsCl structure in which the lattice points are located in the centers of the cesium ions. In this description, the cesium ions are located on the lattice points at the corners of the cell, and the chloride ion is located at the center of the cell. The two unit cells are different, but they describe identical structures.


When an ionic compound is composed of a 1:1 ratio of cations and anions that differ significantly in size, it typically crystallizes with an FCC unit cell, like that shown in Figure **12.6.15**. Sodium chloride, NaCl, is an example of this, with Na^+ and Cl^- having radii of 102 pm and 181 pm, respectively. We can think of this as chloride ions forming an FCC cell, with sodium ions located in the octahedral holes in the middle of the cell edges and in the center of the cell. The sodium and chloride ions touch each other along the cell edges. The unit cell contains four sodium ions and four chloride ions, giving the 1:1 stoichiometry required by the formula, NaCl.



Figure **12.6.15**: Ionic compounds with anions that are much larger than cations, such as NaCl, usually form an FCC structure. They can be described by FCC unit cells with cations in the octahedral holes.

Three images are shown. The first image shows a cube with black dots at each corner and a red dot in the center. This cube is stacked with seven others that are not colored to form a larger cube. The second image is composed of eight spheres that are grouped together to form a cube with one much larger sphere in the center. The name under this image reads “Body-centered simple cubic structure.” The third image shows seven horizontal layers of alternating purple and green spheres that are slightly offset with one another and form a large cube.

The cubic form of zinc sulfide, zinc blende, also crystallizes in an FCC unit cell, as illustrated in Figure **12.6.16**. This structure contains sulfide ions on the lattice points of an FCC lattice. (The arrangement of sulfide ions is identical to the arrangement of chloride ions in sodium chloride.) The radius of a zinc ion is only about 40% of the radius of a sulfide ion, so these small Zn^{2+} ions are located in alternating tetrahedral holes, that is, in one half of the tetrahedral holes. There are four zinc ions and four sulfide ions in the unit cell, giving the empirical formula ZnS.




ZnS face-centered unit cell

Figure **12.6.16**: ZnS, zinc sulfide (or zinc blende) forms an FCC unit cell with sulfide ions at the lattice points and much smaller zinc ions occupying half of the tetrahedral holes in the structure.

Two images are shown. The first image shows a cube with black dots at each corner and a red dot in the center of each face of the cube. This cube is stacked with seven others that are not colored to form a larger cube. The second image is composed of eight spheres that form the corners of a cube with six other spheres located in the face of the cube. The spheres are connected to one another by lines. The name under this image reads “Z n S, face-centered unit cell.”

A calcium fluoride unit cell, like that shown in Figure **12.6.17**, is also an FCC unit cell, but in this case, the cations are located on the lattice points; equivalent calcium ions are located on the lattice points of an FCC lattice. All of the tetrahedral sites in the FCC array of calcium ions are occupied by fluoride ions. There are four calcium ions and eight fluoride ions in a unit cell, giving a calcium:fluorine ratio of 1:2, as required by the chemical formula, CaF_2. Close examination of Figure **12.6.17** will reveal a simple cubic array of fluoride ions with calcium ions in one half of the cubic holes. The structure cannot be described in terms of a space lattice of points on the fluoride ions because the fluoride ions do not all have identical environments. The orientation of the four calcium ions about the fluoride ions differs.



CaF_2 face-centered unit cell

Figure **12.6.17**: Calcium fluoride, CaF_2, forms an FCC unit cell with calcium ions (green) at the lattice points and fluoride ions (red) occupying all of the tetrahedral sites between them.

Two images are shown. The first image shows a cube with black dots at each corner and a red dot in the center of each face of the cube. This cube is stacked with seven others that are not colored to form a larger cube. The second image is composed of eight small green spheres that form the corners of a cube with six other small green spheres located in the faces of the cube. Eight larger green spheres are spaced inside the cube and all of the spheres are connect to one another by lines. The name under this image reads “C a F, subscript 2, face-centered unit cell.”

Calculation of Ionic Radii


If we know the edge length of a unit cell of an ionic compound and the position of the ions in the cell, we can calculate ionic radii for the ions in the compound if we make assumptions about individual ionic shapes and contacts.

Example 12.6.5: Calculation of Ionic Radii

The edge length of the unit cell of LiCl (NaCl-like structure, FCC) is 0.514 nm or 5.14 Å. Assuming that the lithium ion is small enough so that the chloride ions are in contact, calculate the ionic radius for the chloride ion. Note: The length unit angstrom, Å, is often used to represent atomic-scale dimensions and is equivalent to 10^{-10} m.

Solution

On the face of a LiCl unit cell, chloride ions contact each other across the diagonal of the face:



Drawing a right triangle on the face of the unit cell, we see that the length of the diagonal is equal to four chloride radii (one radius from each corner chloride and one diameter—which equals two radii—from the chloride ion in the center of the face), so $d = 4r$. From the Pythagorean theorem, we have:

$$a^2 + a^2 = d^2$$

which yields:

$$(0.514\ \text{nm})^2 + (0.514\ \text{nm})^2 = (4r)^2 = 16r^2$$

Solving this gives:

$$r = \sqrt{\frac{(0.514\ \text{nm})^2 + (0.514\ \text{nm})^2}{16}} = 0.182\ \text{nm}\ (1.82\ \text{Å})\ \text{for a}\ Cl^-\ \text{radius.}$$

Exercise 12.6.6

The edge length of the unit cell of KCl (NaCl-like structure, FCC) is 6.28 Å. Assuming anion-cation contact along the cell edge, calculate the radius of the potassium ion. The radius of the chloride ion is 1.82 Å.

Answer

The radius of the potassium ion is 1.33 Å.

It is important to realize that values for ionic radii calculated from the edge lengths of unit cells depend on numerous assumptions, such as a perfect spherical shape for ions, which are approximations at best. Hence, such calculated values are themselves approximate and comparisons cannot be pushed too far. Nevertheless, this method has proved useful for calculating ionic radii from experimental measurements such as X-ray crystallographic determinations.

X-Ray Crystallography

The size of the unit cell and the arrangement of atoms in a crystal may be determined from measurements of the *diffraction* of X-rays by the crystal, termed X-ray crystallography. Diffraction is the change in the direction of travel experienced by an electromagnetic wave when it encounters a physical barrier whose dimensions are comparable to those of the wavelength of the light. X-rays are electromagnetic radiation with wavelengths about as long as the distance between neighboring atoms in crystals (on the order of a few Å).

When a beam of monochromatic X-rays strikes a crystal, its rays are scattered in all directions by the atoms within the crystal. When scattered waves traveling in the same direction encounter one another, they undergo *interference*, a process by which the waves combine to yield either an increase or a decrease in amplitude (intensity) depending upon the extent to which the combining waves' maxima are separated (Figure 12.6.18).




Figure 12.6.18: Light waves occupying the same space experience interference, combining to yield waves of greater (a) or lesser (b) intensity, depending upon the separation of their maxima and minima.

A pair of images is shown that has four sections. In the first section, two sinusoidal waves are shown, one drawn above the other, and a section from the top of one curve to the top of the next curve is labeled "lambda." The curves align with one another. The phrase below this reads "Constructive interference." A right facing arrow leads from the first section to the second, which shows one larger sinusoidal curve that has higher and lower peaks and troughs. A section from the top of one curve to the top of the next curve is labeled "lambda" and the phrase below this reads "Maxima and minima reinforce." In the second section, two sinusoidal waves are shown, one drawn above the other, and a section from the top of one curve to the top of the next curve is labeled "lambda." The curves do not align with one another. The phrase below this reads "Destructive interference." A right facing arrow leads from the first section to the second, which shows one flat line. The phrase below this reads "Maxima and minima cancel."

When X-rays of a certain wavelength, λ, are scattered by atoms in adjacent crystal planes separated by a distance, d, they may undergo constructive interference when the difference between the distances traveled by the two waves prior to their combination is an integer factor, n, of the wavelength. This condition is satisfied when the angle of the diffracted beam, θ, is related to the wavelength and interatomic distance by the equation:

$$n\lambda = 2d\sin\theta \tag{12.6.1}$$

This relation is known as the Bragg equation in honor of W. H. Bragg, the English physicist who first explained this phenomenon. Figure 12.6.18 illustrates two examples of diffracted waves from the same two crystal planes. The figure on the left depicts waves diffracted at the Bragg angle, resulting in constructive interference, while that on the right shows diffraction and a different angle that does not satisfy the Bragg condition, resulting in destructive interference.




Figure 12.6.19: The diffraction of X-rays scattered by the atoms within a crystal permits the determination of the distance between the atoms. The top image depicts constructive interference between two scattered waves and a resultant diffracted wave of high intensity. The bottom image depicts destructive interference and a low intensity diffracted wave.

Two similar figures are shown. The first figure, labeled “Constructive Interference,” shows two horizontal rows of seven black dots with a line passing through them. The fourth dots of each row have a vertical line connecting them. The distance between these rows is labeled “d.” A beam labeled “Incident beam” descends at an angle labeled “theta” until it hits the line connecting the fourth dots, after which a diffracted beam ascends at the same angle “theta.” A dotted line is drawn across the diffracted beam. The second figure, labeled “Destructive interference,” is very similar, except that the angles “theta” are far more acute, making the slopes of the beams more shallow.

An X-ray diffractometer, such as the one illustrated in Figure 12.6.20, may be used to measure the angles at which X-rays are diffracted when interacting with a crystal as described earlier. From such measurements, the Bragg equation may be used to compute distances between atoms as demonstrated in the following example exercise.




Figure 12.6.20: (a) In a diffractometer, a beam of X-rays strikes a crystalline material, producing (b) an X-ray diffraction pattern that can be analyzed to determine the crystal structure.

A diagram, labeled “a” shows a cube on the left with a channel bored into its right side labeled “X dash ray source.” A beam is leaving from this channel and traveling in a horizontal line toward an oval-shaped, short tube, labeled “Collimator to focus beam” and “X dash ray diffraction,” where it passes through a cube labeled “Crystalline material” and scatters onto a vertical sheet labeled “Imaging surface.” A second diagram, labeled “b,” shows a square sheet with a large dot in the center labeled “X dash ray beam,” that is surrounded by smaller dots arranged in rings and labeled “Diffracted X dash rays.”

Example 12.6.6: Using the Bragg Equation

In a diffractometer, X-rays with a wavelength of 0.1315 nm were used to produce a diffraction pattern for copper. The first order diffraction ($n = 1$) occurred at an angle $\theta = 25.25°$. Determine the spacing between the diffracting planes in copper.

Solution

The distance between the planes is found by solving the Bragg equation (Equation 12.6.1) for *d*.

This gives

$$d = \frac{n\lambda}{2\sin\theta} = \frac{1(0.1315\ \text{nm})}{2\sin(25.25°)} = 0.154\ \text{nm}$$

Exercise 12.6.6

A crystal with spacing between planes equal to 0.394 nm diffracts X-rays with a wavelength of 0.147 nm. What is the angle for the first order diffraction?

Answer

21.9°

X-ray Crystallographer Rosalind Franklin

The discovery of the structure of DNA in 1953 by Francis Crick and James Watson is one of the great achievements in the history of science. They were awarded the 1962 Nobel Prize in Physiology or Medicine, along with Maurice Wilkins, who provided experimental proof of DNA's structure. British chemist Rosalind Franklin made invaluable contributions to this monumental achievement through her work in measuring X-ray diffraction images of DNA. Early in her career, Franklin's research on the structure of coals proved helpful to the British war effort. After shifting her focus to biological systems in the early 1950s, Franklin and doctoral student Raymond Gosling discovered that DNA consists of two forms: a long, thin fiber formed when wet (type "B") and a short, wide fiber formed when dried (type "A"). Her X-ray diffraction images of DNA provided the crucial information that allowed Watson and Crick to confirm that DNA forms a double helix, and to determine details of its size and structure. Franklin also conducted pioneering research on viruses and the RNA that contains their genetic information, uncovering new information that radically changed the body of knowledge in the field. After developing ovarian cancer, Franklin continued to work until her death in 1958 at age 37. Among many posthumous recognitions of her work, the Chicago Medical School of Finch University of Health Sciences changed its name to the Rosalind Franklin University of Medicine and Science in 2004, and adopted an image of her famous X-ray diffraction image of DNA as its official university logo.




Figure 12.6.7.This illustration shows an X-ray diffraction image similar to the one Franklin found in her research. (credit: National Institutes of Health)

Key Concepts and Summary

The structures of crystalline metals and simple ionic compounds can be described in terms of packing of spheres. Metal atoms can pack in hexagonal closest-packed structures, cubic closest-packed structures, body-centered structures, and simple cubic structures.

The anions in simple ionic structures commonly adopt one of these structures, and the cations occupy the spaces remaining between the anions. Small cations usually occupy tetrahedral holes in a closest-packed array of anions. Larger cations usually occupy octahedral holes. Still larger cations can occupy cubic holes in a simple cubic array of anions. The structure of a solid can be described by indicating the size and shape of a unit cell and the contents of the cell. The type of structure and dimensions of the unit cell can be determined by X-ray diffraction measurements.

Glossary

body-centered cubic (BCC) solid
crystalline structure that has a cubic unit cell with lattice points at the corners and in the center of the cell

body-centered cubic unit cell
simplest repeating unit of a body-centered cubic crystal; it is a cube containing lattice points at each corner and in the center of the cube

Bragg equation
equation that relates the angles at which X-rays are diffracted by the atoms within a crystal

coordination number
number of atoms closest to any given atom in a crystal or to the central metal atom in a complex

cubic closest packing (CCP)
crystalline structure in which planes of closely packed atoms or ions are stacked as a series of three alternating layers of different relative orientations (ABC)

diffraction
redirection of electromagnetic radiation that occurs when it encounters a physical barrier of appropriate dimensions

face-centered cubic (FCC) solid
crystalline structure consisting of a cubic unit cell with lattice points on the corners and in the center of each face

face-centered cubic unit cell
simplest repeating unit of a face-centered cubic crystal; it is a cube containing lattice points at each corner and in the center of each face

hexagonal closest packing (HCP)
crystalline structure in which close packed layers of atoms or ions are stacked as a series of two alternating layers of different relative orientations (AB)

hole
(also, interstice) space between atoms within a crystal

isomorphous
possessing the same crystalline structure

octahedral hole
open space in a crystal at the center of six particles located at the corners of an octahedron

simple cubic unit cell
(also, primitive cubic unit cell) unit cell in the simple cubic structure

simple cubic structure
crystalline structure with a cubic unit cell with lattice points only at the corners

space lattice

all points within a crystal that have identical environments

tetrahedral hole

tetrahedral space formed by four atoms or ions in a crystal

unit cell

smallest portion of a space lattice that is repeated in three dimensions to form the entire lattice

X-ray crystallography

experimental technique for determining distances between atoms in a crystal by measuring the angles at which X-rays are diffracted when passing through the crystal

Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

12.6: Lattice Structure in Crystalline Solids is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **10.7: Lattice Structures in Crystalline Solids** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

12.7: End of Chapter Problems

1. In terms of their bulk properties, how do liquids and solids differ? How are they similar?

Answer

Liquids and solids are similar in that they are matter composed of atoms, ions, or molecules. They are incompressible and have similar densities that are both much larger than those of gases. They are different in that liquids have no fixed shape, and solids are rigid.

2. In terms of the kinetic molecular theory, in what ways are liquids similar to solids? In what ways are liquids different from solids?
3. In terms of the kinetic molecular theory, in what ways are liquids similar to gases? In what ways are liquids different from gases?

Answer

They are similar in that the atoms or molecules are free to move from one position to another. They differ in that the particles of a liquid are confined to the shape of the vessel in which they are placed. In contrast, a gas will expand without limit to fill the space into which it is placed.

4. Explain why liquids assume the shape of any container into which they are poured, whereas solids are rigid and retain their shape.
5. What is the evidence that all neutral atoms and molecules exert attractive forces on each other?

Answer

All atoms and molecules will condense into a liquid or solid in which the attractive forces exceed the kinetic energy of the molecules, at sufficiently low temperature.

6. Open the PhET States of Matter Simulation to answer the following questions:
   a. Select the Solid, Liquid, Gas tab. Explore by selecting different substances, heating and cooling the systems, and changing the state. What similarities do you notice between the four substances for each phase (solid, liquid, gas)? What differences do you notice?
   b. For each substance, select each of the states and record the given temperatures. How do the given temperatures for each state correlate with the strengths of their intermolecular attractions? Explain.
   c. Select the Interaction Potential tab, and use the default neon atoms. Move the Ne atom on the right and observe how the potential energy changes. Select the Total Force button, and move the Ne atom as before. When is the total force on each atom attractive and large enough to matter? Then select the Component Forces button, and move the Ne atom. When do the attractive (van der Waals) and repulsive (electron overlap) forces balance? How does this relate to the potential energy versus the distance between atoms graph? Explain.
7. Define the following and give an example of each:
   a. dispersion force
   b. dipole-dipole attraction
   c. hydrogen bond

Answer

(a) Dispersion forces occur as an atom develops a temporary dipole moment when its electrons are distributed asymmetrically about the nucleus. This structure is more prevalent in large atoms such as argon or radon. A second atom can then be distorted by the appearance of the dipole in the first atom. The electrons of the second atom are attracted toward the positive end of the first atom, which sets up a dipole in the second atom. The net result is rapidly fluctuating, temporary dipoles that attract one another (example: Ar).

(b) A dipole-dipole attraction is a force that results from an electrostatic attraction of the positive end of one polar molecule for the negative end of another polar molecule (example: ICI molecules attract one another by dipole-dipole interaction).

(c) Hydrogen bonds form whenever a hydrogen atom is bonded to one of the more electronegative atoms, such as a fluorine, oxygen, nitrogen, or chlorine atom. The electrostatic attraction between the partially positive hydrogen atom in one molecule and the partially negative atom in another molecule gives rise to a strong dipole-dipole interaction called a hydrogen bond (example: **HF⋯HF**).

8. The types of intermolecular forces in a substance are identical whether it is a solid, a liquid, or a gas. Why then does a substance change phase from a gas to a liquid or to a solid?
9. Why do the boiling points of the noble gases increase in the order He < Ne < Ar < Kr < Xe?

Answer

The London forces typically increase as the number of electrons increase.

10. Neon and HF have approximately the same molecular masses.
    a. Explain why the boiling points of Neon and HF differ.
    b. Compare the change in the boiling points of Ne, Ar, Kr, and Xe with the change of the boiling points of HF, HCl, HBr, and HI, and explain the difference between the changes with increasing atomic or molecular mass.Arrange each of the following sets of compounds in order of increasing boiling point temperature:
11. HCl, H_2O, SiH_4
    a. F_2, Cl_2, Br_2
    b. CH_4, C_2H_6, C_3H_8
    c. O_2, NO, N_2

Answer

(a) SiH_4 < HCl < H_2O; (b) F_2 < Cl_2 < Br_2; (c) CH_4 < C_2H_6 < C_3H_8; (d) N_2 < O_2 < NO

12. The molecular mass of butanol, C_4H_9OH, is 74.14; that of ethylene glycol, $CH_2(OH)CH_2OH$, is 62.08, yet their boiling points are 117.2 °C and 174 °C, respectively. Explain the reason for the difference.
13. On the basis of intermolecular attractions, explain the differences in the boiling points of *n*–butane (−1 °C) and chloroethane (12 °C), which have similar molar masses.

Answer

Only rather small dipole-dipole interactions from C-H bonds are available to hold *n*-butane in the liquid state. Chloroethane, however, has rather large dipole interactions because of the Cl-C bond; the interaction is therefore stronger, leading to a higher boiling point.

14. On the basis of dipole moments and/or hydrogen bonding, explain in a qualitative way the differences in the boiling points of acetone (56.2 °C) and 1-propanol (97.4 °C), which have similar molar masses.
15. The melting point of $H_2O(s)$ is 0 °C. Would you expect the melting point of $H_2S(s)$ to be −85 °C, 0 °C, or 185 °C? Explain your answer.

Answer

−85 °C. Water has stronger hydrogen bonds so it melts at a higher temperature.


16. Silane (SiH_4), phosphine (PH_3), and hydrogen sulfide (H_2S) melt at −185 °C, −133 °C, and −85 °C, respectively. What does this suggest about the polar character and intermolecular attractions of the three compounds?
17. Explain why a hydrogen bond between two water molecules is weaker than a hydrogen bond between two hydrogen fluoride molecules.

Answer

The hydrogen bond between two hydrogen fluoride molecules is stronger than that between two water molecules because the electronegativity of F is greater than that of O. Consequently, the partial negative charge on F is greater than that on O. The


hydrogen bond between the partially positive H and the larger partially negative F will be stronger than that formed between H and O.

18. Under certain conditions, molecules of acetic acid, CH_3COOH, form “dimers,” pairs of acetic acid molecules held together by strong intermolecular attractions:



Draw a dimer of acetic acid, showing how two CH_3COOH molecules are held together, and stating the type of IMF that is responsible.

19. Proteins are chains of amino acids that can form in a variety of arrangements, one of which is a helix. What kind of IMF is responsible for holding the protein strand in this shape? On the protein image, show the locations of the IMFs that hold the protein together:



Answer


H-bonding is the principle IMF holding the DNA strands together. The H-bonding is between the $\mathbf{N-H}$ and $\mathbf{C=O}$.

20. The density of liquid NH_3 is 0.64 g/mL; the density of gaseous NH_3 at STP is 0.0007 g/mL. Explain the difference between the densities of these two phases.
21. Identify the intermolecular forces present in the following solids:
    a. CH_3CH_2OH
    b. $CH_3CH_2CH_3$
    c. CH_3CH_2Cl

Answer

(a) hydrogen bonding and dispersion forces; (b) dispersion forces; (c) dipole-dipole attraction and dispersion forces

22. The test tubes shown here contain equal amounts of the specified motor oils. Identical metal spheres were dropped at the same time into each of the tubes, and a brief moment later, the spheres had fallen to the heights indicated in the illustration. Rank the motor oils in order of increasing viscosity, and explain your reasoning:



23. Although steel is denser than water, a steel needle or paper clip placed carefully lengthwise on the surface of still water can be made to float. Explain at a molecular level how this is possible:




(credit: Cory Zanker)

Answer

The water molecules have strong intermolecular forces of hydrogen bonding. The water molecules are thus attracted strongly to one another and exhibit a relatively large surface tension, forming a type of “skin” at its surface. This skin can support a bug or paper clip if gently placed on the water.

24. The surface tension and viscosity values for diethyl ether, acetone, ethanol, and ethylene glycol are shown here.

Compound	Molecule	Surface Tension (mN/m)	Viscosity (mPa s)
diethyl ether $C_2H_5OC_2H_5$		17	0.22
acetone $C_2H_5OC_2H_5$		23	0.31
ethanol C_2H_5OH		22	1.07
ethylene glycol $CH_2(OH)CH_2(OH)$		48	16.1

a. Explain their differences in viscosity in terms of the size and shape of their molecules and their IMFs.
b. Explain their differences in surface tension in terms of the size and shape of their molecules and their IMFs:

25. You may have heard someone use the figure of speech “slower than molasses in winter” to describe a process that occurs slowly. Explain why this is an apt idiom, using concepts of molecular size and shape, molecular interactions, and the effect of changing temperature.

Answer

Temperature has an effect on intermolecular forces: the higher the temperature, the greater the kinetic energies of the molecules and the greater the extent to which their intermolecular forces are overcome, and so the more fluid (less viscous) the liquid; the lower the temperature, the lesser the intermolecular forces are overcome, and so the less viscous the liquid.

26. It is often recommended that you let your car engine run idle to warm up before driving, especially on cold winter days. While the benefit of prolonged idling is dubious, it is certainly true that a warm engine is more fuel efficient than a cold one. Explain the reason for this.
27. The surface tension and viscosity of water at several different temperatures are given in this table.

Water	Surface Tension (mN/m)	Viscosity (mPa s)
0 °C	75.6	1.79
20 °C	72.8	1.00
60 °C	66.2	0.47
100 °C	58.9	1. 0.28

a. As temperature increases, what happens to the surface tension of water? Explain why this occurs, in terms of molecular interactions and the effect of changing temperature.
b. As temperature increases, what happens to the viscosity of water? Explain why this occurs, in terms of molecular interactions and the effect of changing temperature.

Answer

(a) As the water reaches higher temperatures, the increased kinetic energies of its molecules are more effective in overcoming hydrogen bonding, and so its surface tension decreases. Surface tension and intermolecular forces are directly related. (b) The same trend in viscosity is seen as in surface tension, and for the same reason.

28. At 25 °C, how high will water rise in a glass capillary tube with an inner diameter of 0.63 mm? Refer to Example for the required information.
29. Water rises in a glass capillary tube to a height of 17 cm. What is the diameter of the capillary tube?

Answer

9.5×10^{-5} m

30. Heat is added to boiling water. Explain why the temperature of the boiling water does not change. What does change?
31. Heat is added to ice at 0 °C. Explain why the temperature of the ice does not change. What does change?

Answer

The heat is absorbed by the ice, providing the energy required to partially overcome intermolecular attractive forces in the solid and causing a phase transition to liquid water. The solution remains at 0 °C until all the ice is melted. Only the amount of water existing as ice changes until the ice disappears. Then the temperature of the water can rise.

32. What feature characterizes the dynamic equilibrium between a liquid and its vapor in a closed container?
33. Identify two common observations indicating some liquids have sufficient vapor pressures to noticeably evaporate?

Answer

We can see the amount of liquid in an open container decrease and we can smell the vapor of some liquids.

34. Identify two common observations indicating some solids, such as dry ice and mothballs, have vapor pressures sufficient to sublime?
35. What is the relationship between the intermolecular forces in a liquid and its vapor pressure?

Answer

The vapor pressure of a liquid decreases as the strength of its intermolecular forces increases.

36. What is the relationship between the intermolecular forces in a solid and its melting temperature?
37. Why does spilled gasoline evaporate more rapidly on a hot day than on a cold day?

Answer

As the temperature increases, the average kinetic energy of the molecules of gasoline increases and so a greater fraction of molecules have sufficient energy to escape from the liquid than at lower temperatures.

38. Carbon tetrachloride, CCl_4, was once used as a dry cleaning solvent, but is no longer used because it is carcinogenic. At 57.8 °C, the vapor pressure of CCl_4 is 54.0 kPa, and its enthalpy of vaporization is 33.05 kJ/mol. Use this information to estimate the normal boiling point for CCl_4.
39. When is the boiling point of a liquid equal to its normal boiling point?

Answer

When the pressure of gas above the liquid is exactly 1 atm

40. How does the boiling of a liquid differ from its evaporation?
41. Use the information in Figure to estimate the boiling point of water in Denver when the atmospheric pressure is 83.3 kPa.

Answer

approximately 95 °C

42. A syringe at a temperature of 20 °C is filled with liquid ether in such a way that there is no space for any vapor. If the temperature is kept constant and the plunger is withdrawn to create a volume that can be occupied by vapor, what would be the approximate pressure of the vapor produced?
43. Explain the following observations:
    a. It takes longer to cook an egg in Ft. Davis, Texas (altitude, 5000 feet above sea level) than it does in Boston (at sea level).
    b. Perspiring is a mechanism for cooling the body.

Answer

(a) At 5000 feet, the atmospheric pressure is lower than at sea level, and water will therefore boil at a lower temperature. This lower temperature will cause the physical and chemical changes involved in cooking the egg to proceed more slowly, and a longer time is required to fully cook the egg. (b) As long as the air surrounding the body contains less water vapor than the maximum that air can hold at that temperature, perspiration will evaporate, thereby cooling the body by removing the heat of vaporization required to vaporize the water.

44. The enthalpy of vaporization of water is larger than its enthalpy of fusion. Explain why.
45. Explain why the molar enthalpies of vaporization of the following substances increase in the order $CH_4 < C_2H_6 < C_3H_8$, even though all three substances experience the same dispersion forces when in the liquid state.

Answer

Dispersion forces increase with molecular mass or size. As the number of atoms composing the molecules in this homologous series increases, so does the extent of intermolecular attraction via dispersion forces and, consequently, the energy required to overcome these forces and vaporize the liquids.

46. Explain why the enthalpies of vaporization of the following substances increase in the order $CH_4 < NH_3 < H_2O$, even though all three substances have approximately the same molar mass.
47. The enthalpy of vaporization of $CO_2(l)$ is 9.8 kJ/mol. Would you expect the enthalpy of vaporization of $CS_2(l)$ to be 28 kJ/mol, 9.8 kJ/mol, or −8.4 kJ/mol? Discuss the plausibility of each of these answers.

Answer

The boiling point of CS_2 is higher than that of CO_2 partially because of the higher molecular weight of CS_2; consequently, the attractive forces are stronger in CS_2. It would be expected, therefore, that the heat of vaporization would be greater than that of 9.8 kJ/mol for CO_2. A value of 28 kJ/mol would seem reasonable. A value of −8.4 kJ/mol would indicate a release of energy upon vaporization, which is clearly implausible.

48. The hydrogen fluoride molecule, HF, is more polar than a water molecule, H_2O (for example, has a greater dipole moment), yet the molar enthalpy of vaporization for liquid hydrogen fluoride is lesser than that for water. Explain.
49. Ethyl chloride (boiling point, 13 °C) is used as a local anesthetic. When the liquid is sprayed on the skin, it cools the skin enough to freeze and numb it. Explain the cooling effect of liquid ethyl chloride.

Answer

The thermal energy (heat) needed to evaporate the liquid is removed from the skin.

50. Which contains the compounds listed correctly in order of increasing boiling points?
    a. $N_2 < CS_2 < H_2O < KCl$
    b. $H_2O < N_2 < CS_2 < KCl$
    c. $N_2 < KCl < CS_2 < H_2O$

d. $CS_2 < N_2 < KCl < H_2O$
e. $KCl < H_2O < CS_2 < N_2$

51. How much heat is required to convert 422 g of liquid H_2O at 23.5 °C into steam at 150 °C?

Answer

1130 kJ

52. Evaporation of sweat requires energy and thus take excess heat away from the body. Some of the water that you drink may eventually be converted into sweat and evaporate. If you drink a 20-ounce bottle of water that had been in the refrigerator at 3.8 °C, how much heat is needed to convert all of that water into sweat and then to vapor?? (Note: Your body temperature is 36.6 °C. For the purpose of solving this problem, assume that the thermal properties of sweat are the same as for water.)
53. Titanium tetrachloride, $TiCl_4$, has a melting point of −23.2 °C and has a $\Delta H_{\text{fusion}} = 9.37$ kJ/mol.
    a. How much energy is required to melt 263.1 g $TiCl_4$?
    b. For $TiCl_4$, which will likely have the larger magnitude: ΔH_{fusion} or $\Delta H_{\text{vaporization}}$? Explain your reasoning.

Answer


(a) 13.0 kJ; (b) It is likely that the heat of vaporization will have a larger magnitude since in the case of vaporization the intermolecular interactions have to be completely overcome, while melting weakens or destroys only some of them.

54. From the phase diagram for water, determine the state of water at:
    a. 35 °C and 85 kPa
    b. −15 °C and 40 kPa
    c. −15 °C and 0.1 kPa
    d. 75 °C and 3 kPa
    e. 40 °C and 0.1 kPa
    f. 60 °C and 50 kPa
55. What phase changes will take place when water is subjected to varying pressure at a constant temperature of 0.005 °C? At 40 °C? At −40 °C?

Answer

At low pressures and 0.005 °C, the water is a gas. As the pressure increases to 4.6 torr, the water becomes a solid; as the pressure increases still more, it becomes a liquid. At 40 °C, water at low pressure is a vapor; at pressures higher than about 75 torr, it converts into a liquid. At −40 °C, water goes from a gas to a solid as the pressure increases above very low values.

56. Pressure cookers allow food to cook faster because the higher pressure inside the pressure cooker increases the boiling temperature of water. A particular pressure cooker has a safety valve that is set to vent steam if the pressure exceeds 3.4 atm. What is the approximate maximum temperature that can be reached inside this pressure cooker? Explain your reasoning.
57. From the phase diagram for carbon dioxide, determine the state of CO_2 at:
    a. 20 °C and 1000 kPa
    b. 10 °C and 2000 kPa
    c. 10 °C and 100 kPa
    d. −40 °C and 500 kPa
    e. −80 °C and 1500 kPa
    f. −80 °C and 10 kPa




The pressure and temperature axes on this phase diagram of carbon dioxide are not drawn to constant scale in order to illustrate several important properties.

Answer

(a) liquid; (b) solid; (c) gas; (d) gas; (e) gas; (f) gas


58. Determine the phase changes that carbon dioxide undergoes as the pressure changes if the temperature is held at −50 °C? If the temperature is held at −40 °C? At 20 °C?



The pressure and temperature axes on this phase diagram of carbon dioxide are not drawn to constant scale in order to illustrate several important properties.

59. Consider a cylinder containing a mixture of liquid carbon dioxide in equilibrium with gaseous carbon dioxide at an initial pressure of 65 atm and a temperature of 20 °C. Sketch a plot depicting the change in the cylinder pressure with time as gaseous carbon dioxide is released at constant temperature.

Answer



60. Dry ice, $CO_2(s)$, does not melt at atmospheric pressure. It sublimes at a temperature of −78 °C. What is the lowest pressure at which $CO_2(s)$ will melt to give $CO_2(l)$? At approximately what temperature will this occur? (See Figure for the phase diagram.)

Answer


Dry ice, $CO_2(s)$, will melt to give $CO_2(l)$ at 5.11 atm at −56.6 °C, the triple point of carbon dioxide.

61. If a severe storm results in the loss of electricity, it may be necessary to use a clothesline to dry laundry. In many parts of the country in the dead of winter, the clothes will quickly freeze when they are hung on the line. If it does not snow, will they dry anyway? Explain your answer.

Answer

Yes, ice will sublime, although it may take it several days. Ice has a small vapor pressure, and some ice molecules form gas and escape from the ice crystals. As time passes, more and more solid converts to gas until eventually the clothes are dry.

62. Is it possible to liquefy nitrogen at room temperature (about 25 °C)? Is it possible to liquefy sulfur dioxide at room temperature? Explain your answers.
63. Elemental carbon has one gas phase, one liquid phase, and three different solid phases, as shown in the phase diagram:



a. Graphite is the most stable phase of carbon at normal conditions. On the phase diagram, label the graphite phase.
b. If graphite at normal conditions is heated to 2500 K while the pressure is increased to 10^{10} Pa, it is converted into diamond. Label the diamond phase.

c. Circle each triple point on the phase diagram.
d. In what phase does carbon exist at 5000 K and 10^8 Pa?
e. If the temperature of a sample of carbon increases from 3000 K to 5000 K at a constant pressure of 10^6 Pa, which phase transition occurs, if any?
f. On the phase diagram, label the gas and liquid regions.

64. What types of liquids typically form amorphous solids?

Answer

Amorphous solids lack an ordered internal structure. Liquid materials that contain large, cumbersome molecules that cannot move readily into ordered positions generally form such solids.

65. At very low temperatures oxygen, O_2, freezes and forms a crystalline solid. Which best describes these crystals?

a. ionic
b. covalent network
c. metallic
d. amorphous
e. molecular crystals

Answer

(e) molecular crystals

66. As it cools, olive oil slowly solidifies and forms a solid over a range of temperatures. Which best describes the solid?

a. ionic
b. covalent network
c. metallic
d. amorphous
e. molecular crystals

Answer

(d) amorphous

67. Explain why ice, which is a crystalline solid, has a melting temperature of 0 °C, whereas butter, which is an amorphous solid, softens over a range of temperatures.

Answer

Ice has a crystalline structure stabilized by hydrogen bonding. These intermolecular forces are of comparable strength and thus require the same amount of energy to overcome. As a result, ice melts at a single temperature and not over a range of temperatures. The various, very large molecules that compose butter experience varied van der Waals attractions of various strengths that are overcome at various temperatures, and so the melting process occurs over a wide temperature range.

68. Identify the type of crystalline solid (metallic, network covalent, ionic, or molecular) formed by each of the following substances:

a. SiO_2
b. KCl
c. Cu
d. CO_2
e. C (diamond)
f. $BaSO_4$
g. NH_3
h. NH_4F
i. C_2H_5OH

Answer

(a) SiO_2, covalent network; (b) KCl, ionic; (c) Cu, metallic; (d) CO, molecular; (e) C (diamond), covalent network; (f) $BaSO_4$, ionic; (g) NH_3, molecular; (h) NH_4F, ionic; (i) C_2H_5OH, molecular

69. Identify the type of crystalline solid (metallic, network covalent, ionic, or molecular) formed by each of the following substances:
    a. $CaCl_2$
    b. SiC
    c. N_2
    d. Fe
    e. C (graphite)
    f. $CH_3CH_2CH_2CH_3$
    g. HCl
    h. NH_4NO_3
    i. K_3PO_4

Answer

(a) $CaCl_2$, ionic; (b) SiC, covalent network; (c) N_2, molecular; (d) Fe, metallic; (e) C (graphite), covalent network; (f) $CH_3CH_2CH_2CH_3$, molecular; (g) HCl, molecular; (h) NH_4NO_3, ionic; (i) K_3PO_4, ionic

70. Classify each substance in the table as either a metallic, ionic, molecular, or covalent network solid:

Substance	Appearance	Melting Point	Electrical Conductivity	Solubility in Water
X	lustrous, malleable	1500 °C	high	insoluble
Y	soft, yellow	113 °C	none	insoluble
Z	hard, white	800 °C	only if melted/dissolved	soluble

Answer

X = metallic; Y = covalent network; Z = ionic

71. Classify each substance in the table as either a metallic, ionic, molecular, or covalent network solid:

Substance	Appearance	Melting Point	Electrical Conductivity	Solubility in Water
X	brittle, white	800 °C	only if melted/dissolved	soluble
Y	shiny, malleable	1100 °C	high	insoluble
Z	hard, colorless	3550 °C	none	insoluble

Answer

X = ionic; Y = metallic; Z = covalent network

72. Identify the following substances as ionic, metallic, covalent network, or molecular solids:
73. Substance A is malleable, ductile, conducts electricity well, and has a melting point of 1135 °C. Substance B is brittle, does not conduct electricity as a solid but does when molten, and has a melting point of 2072 °C. Substance C is very hard, does not conduct electricity, and has a melting point of 3440 °C. Substance D is soft, does not conduct electricity, and has a melting point of 185 °C.

Answer

A = metallic; B = ionic; C = covalent network; D = molecular

74. Substance A is shiny, conducts electricity well, and melts at 975 °C. Substance A is likely a(n):
    a. ionic solid
    b. metallic solid
    c. molecular solid
    d. covalent network solid

Answer

(b) metallic solid

75. Substance B is hard, does not conduct electricity, and melts at 1200 °C. Substance B is likely a(n):
    a. ionic solid
    b. metallic solid
    c. molecular solid
    d. covalent network solid

Answer

(d) covalent network solid

76. Describe the crystal structure of iron, which crystallizes with two equivalent metal atoms in a cubic unit cell.

Answer

The structure of this low-temperature form of iron (below 910 °C) is body-centered cubic. There is one-eighth atom at each of the eight corners of the cube and one atom in the center of the cube.

77. Describe the crystal structure of Pt, which crystallizes with four equivalent metal atoms in a cubic unit cell.
78. What is the coordination number of a chromium atom in the body-centered cubic structure of chromium?

Answer

eight

79. What is the coordination number of an aluminum atom in the face-centered cubic structure of aluminum?
80. Cobalt metal crystallizes in a hexagonal closest packed structure. What is the coordination number of a cobalt atom?

Answer

12

81. Nickel metal crystallizes in a cubic closest packed structure. What is the coordination number of a nickel atom?
82. Tungsten crystallizes in a body-centered cubic unit cell with an edge length of 3.165 Å.
    a. What is the atomic radius of tungsten in this structure?
    b. Calculate the density of tungsten.

Answer

1. (a) 1.370 Å; (b) 19.26 g/cm

83. Platinum (atomic radius = 1.38 Å) crystallizes in a cubic closely packed structure. Calculate the edge length of the face-centered cubic unit cell and the density of platinum.
84. Barium crystallizes in a body-centered cubic unit cell with an edge length of 5.025 Å
    a. What is the atomic radius of barium in this structure?
    b. Calculate the density of barium.

Answer

(a) 2.176 Å; (b) 3.595 g/cm^3

85. Aluminum (atomic radius = 1.43 Å) crystallizes in a cubic closely packed structure. Calculate the edge length of the face-centered cubic unit cell and the density of aluminum.
86. The density of aluminum is 2.7 g/cm^3; that of silicon is 2.3 g/cm^3. Explain why Si has the lower density even though it has heavier atoms.

Answer

The crystal structure of Si shows that it is less tightly packed (coordination number 4) in the solid than Al (coordination number 12).

87. The free space in a metal may be found by subtracting the volume of the atoms in a unit cell from the volume of the cell. Calculate the percentage of free space in each of the three cubic lattices if all atoms in each are of equal size and touch their nearest neighbors. Which of these structures represents the most efficient packing? That is, which packs with the least amount of unused space?
88. Cadmium sulfide, sometimes used as a yellow pigment by artists, crystallizes with cadmium, occupying one-half of the tetrahedral holes in a closest packed array of sulfide ions. What is the formula of cadmium sulfide? Explain your answer.

Answer

In a closest-packed array, two tetrahedral holes exist for each anion. If only half the tetrahedral holes are occupied, the numbers of anions and cations are equal. The formula for cadmium sulfide is CdS.

89. A compound of cadmium, tin, and phosphorus is used in the fabrication of some semiconductors. It crystallizes with cadmium occupying one-fourth of the tetrahedral holes and tin occupying one-fourth of the tetrahedral holes in a closest packed array of phosphide ions. What is the formula of the compound? Explain your answer.
90. What is the formula of the magnetic oxide of cobalt, used in recording tapes, that crystallizes with cobalt atoms occupying one-eighth of the tetrahedral holes and one-half of the octahedral holes in a closely packed array of oxide ions?

Answer

Co_3O_4

91. A compound containing zinc, aluminum, and sulfur crystallizes with a closest-packed array of sulfide ions. Zinc ions are found in one-eighth of the tetrahedral holes and aluminum ions in one-half of the octahedral holes. What is the empirical formula of the compound?
92. A compound of thallium and iodine crystallizes in a simple cubic array of iodide ions with thallium ions in all of the cubic holes. What is the formula of this iodide? Explain your answer.

Answer

In a simple cubic array, only one cubic hole can be occupied be a cation for each anion in the array. The ratio of thallium to iodide must be 1:1; therefore, the formula for thallium is TlI.

93. Which of the following elements reacts with sulfur to form a solid in which the sulfur atoms form a closest-packed array with all of the octahedral holes occupied: Li, Na, Be, Ca, or Al?
94. What is the percent by mass of titanium in rutile, a mineral that contains titanium and oxygen, if structure can be described as a closest packed array of oxide ions with titanium ions in one-half of the octahedral holes? What is the oxidation number of titanium?

Answer

59.95%; The oxidation number of titanium is +4.

95. Explain why the chemically similar alkali metal chlorides NaCl and CsCl have different structures, whereas the chemically different NaCl and MnS have the same structure.
96. As minerals were formed from the molten magma, different ions occupied the same cites in the crystals. Lithium often occurs along with magnesium in minerals despite the difference in the charge on their ions. Suggest an explanation.

Answer

Both ions are close in size: Mg, 0.65; Li, 0.60. This similarity allows the two to interchange rather easily. The difference in charge is generally compensated by the switch of Si^{4+} for Al^{3+}.

99. Rubidium iodide crystallizes with a cubic unit cell that contains iodide ions at the corners and a rubidium ion in the center. What is the formula of the compound?
100. One of the various manganese oxides crystallizes with a cubic unit cell that contains manganese ions at the corners and in the center. Oxide ions are located at the center of each edge of the unit cell. What is the formula of the compound?

Answer

Mn_2O_3

101. NaH crystallizes with the same crystal structure as NaCl. The edge length of the cubic unit cell of NaH is 4.880 Å.
    a. Calculate the ionic radius of H^-. (The ionic radius of Li^+ is 0.0.95 Å.)
    b. Calculate the density of NaH.
102. Thallium(I) iodide crystallizes with the same structure as CsCl. The edge length of the unit cell of TlI is 4.20 Å. Calculate the ionic radius of TI^+. (The ionic radius of I^- is 2.16 Å.)

Answer

1.48 Å

103. A cubic unit cell contains manganese ions at the corners and fluoride ions at the center of each edge.
    a. What is the empirical formula of this compound? Explain your answer.
    b. What is the coordination number of the Mn^{3+} ion?
    c. Calculate the edge length of the unit cell if the radius of a Mn^{3+} ion is 0.65 A.
    d. Calculate the density of the compound.
104. What is the spacing between crystal planes that diffract X-rays with a wavelength of 1.541 nm at an angle θ of 15.55° (first order reflection)?

Answer

2.874 Å

105. A diffractometer using X-rays with a wavelength of 0.2287 nm produced first-order diffraction peak for a crystal angle θ = 16.21°. Determine the spacing between the diffracting planes in this crystal.
106. A metal with spacing between planes equal to 0.4164 nm diffracts X-rays with a wavelength of 0.2879 nm. What is the diffraction angle for the first order diffraction peak?

Answer

20.2°

107. Gold crystallizes in a face-centered cubic unit cell. The second-order reflection (n = 2) of X-rays for the planes that make up the tops and bottoms of the unit cells is at θ = 22.20°. The wavelength of the X-rays is 1.54 Å. What is the density of metallic gold?
108. When an electron in an excited molybdenum atom falls from the L to the K shell, an X-ray is emitted. These X-rays are diffracted at an angle of 7.75° by planes with a separation of 2.64 Å. What is the difference in energy between the K shell and the L shell in molybdenum assuming a first-order diffraction?

Answer

1.74×10^4 eV

12.7: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

CHAPTER OVERVIEW

13: Solution

13.1: How Do Solutions Form?
13.2: Electrolytes
13.3: Factors Affecting Solubility
13.4: Solution Concentration
13.5: Colligative Properties
13.6: Colloids
13.7: End of Chapter Problems

13: Solution is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

13.1: How Do Solutions Form?

Learning Objectives

- Describe the basic properties of solutions and how they form.
- Predict whether a given mixture will yield a solution based on molecular properties of its components.
- Explain why some solutions either produce or absorb heat when they form.

An earlier chapter of this text introduced *solutions*, defined as homogeneous mixtures of two or more substances. Often, one component of a solution is present at a significantly greater concentration, in which case it is called the solvent. The other components of the solution present in relatively lesser concentrations are called solutes. Sugar is a covalent solid composed of sucrose molecules, $\mathrm{C_{12}H_{22}O_{11}}$. When this compound dissolves in water, its molecules become uniformly distributed among the molecules of water:

$$\mathrm{C_{12}H_{22}O_{11}\,(s) \longrightarrow C_{12}H_{22}O_{11}\,(aq)} \tag{13.1.1}$$

The subscript "aq" in the equation signifies that the sucrose molecules are solutes and are therefore *individually dispersed* throughout the *aqueous solution* (water is the solvent). Although sucrose molecules are heavier than water molecules, they remain dispersed throughout the solution; gravity does not cause them to "settle out" over time.

Potassium dichromate, $\mathrm{K_2Cr_2O_7}$, is an ionic compound composed of colorless potassium ions, $\mathrm{K^+}$, and orange dichromate ions, $\mathrm{Cr_2O_7^{2-}}$. When a small amount of solid potassium dichromate is added to water, the compound dissolves and dissociates to yield potassium ions and dichromate ions uniformly distributed throughout the mixture (Figure 13.1.1), as indicated in this equation:

$$\mathrm{K_2Cr_2O_7\,(s) \longrightarrow 2\,K^+\,(aq) + Cr_2O_7^{2-}\,(aq)} \tag{13.1.2}$$

As with the mixture of sugar and water, this mixture is also an aqueous solution. Its solutes, potassium and dichromate ions, remain individually dispersed among the solvent (water) molecules.



Figure 13.1.1: When potassium dichromate ($\mathrm{K_2Cr_2O_7}$) is mixed with water, it forms a homogeneous orange solution. (credit: modification of work by Mark Ott).

Water is used so often as a solvent that the word solution has come to imply an aqueous solution to many people. However, almost any gas, liquid, or solid can act as a solvent. Many alloys are solid solutions of one metal dissolved in another; for example, US five-cent coins contain nickel dissolved in copper. Air is a gaseous solution, a homogeneous mixture of nitrogen, oxygen, and several other gases. Oxygen (a gas), alcohol (a liquid), and sugar (a solid) all dissolve in water (a liquid) to form liquid solutions. Table 13.1.1 gives examples of several different solutions and the phases of the solutes and solvents.

Table 13.1.1: Different Types of Solutions

Solution	Solute	Solvent
air	$O_2(g)$	$N_2(g)$
soft drinks	$CO_2(g)$	$H_2O(l)$
hydrogen in palladium	$H_2(g)$	$Pd(s)$
rubbing alcohol	$H_2O(l)$	$C_3H_8O(l)$ (2-propanol)
saltwater	$NaCl(s)$	$H_2O(l)$
brass	$Zn(s)$	$Cu(s)$

Solutions exhibit these defining traits:

- They are homogeneous; that is, after a solution is mixed, it has the same composition at all points throughout (its composition is uniform).
- The physical state of a solution—solid, liquid, or gas—is typically the same as that of the solvent, as demonstrated by the examples in Table **13.1.1**.
- The components of a solution are dispersed on a molecular scale; that is, they consist of a mixture of separated molecules, atoms, and/or ions.
- The dissolved solute in a solution will not settle out or separate from the solvent.
- The composition of a solution, or the concentrations of its components, can be varied continuously, within limits.

The Formation of Solutions

The formation of a solution is an example of a spontaneous process, a process that occurs under specified conditions without the requirement of energy from some external source. Sometimes we stir a mixture to speed up the dissolution process, but this is not necessary; a homogeneous solution would form if we waited long enough. The topic of spontaneity is critically important to the study of chemical thermodynamics and is treated more thoroughly in a later chapter of this text. For purposes of this chapter's discussion, it will suffice to consider two criteria that *favor*, but do not guarantee, the spontaneous formation of a solution:

1. a decrease in the internal energy of the system (an exothermic change, as discussed in the previous chapter on thermochemistry)
2. an increase in the disorder in the system (which indicates an increase in the *entropy* of the system, as you will learn about in the later chapter on thermodynamics)

In the process of dissolution, an internal energy change often, but not always, occurs as heat is absorbed or evolved. An increase in disorder always results when a solution forms.

When the strengths of the intermolecular forces of attraction between solute and solvent species in a solution are no different than those present in the separated components, the solution is formed with no accompanying energy change. Such a solution is called an ideal solution. A mixture of ideal gases (or gases such as helium and argon, which closely approach ideal behavior) is an example of an ideal solution, since the entities comprising these gases experience no significant intermolecular attractions.

When containers of helium and argon are connected, the gases spontaneously mix due to diffusion and form a solution (Figure **13.1.2**). The formation of this solution clearly involves an increase in disorder, since the helium and argon atoms occupy a volume twice as large as that which each occupied before mixing.




Figure 13.1.2: Samples of helium and argon spontaneously mix to give a solution in which the disorder of the atoms of the two gases is increased.

Ideal solutions may also form when structurally similar liquids are mixed. For example, mixtures of the alcohols methanol (CH_3OH) and ethanol (C_2H_5OH) form ideal solutions, as do mixtures of the hydrocarbons pentane, C_5H_{12}, and hexane, C_6H_{14}. Placing methanol and ethanol, or pentane and hexane, in the bulbs shown in Figure 13.1.2 will result in the same diffusion and subsequent mixing of these liquids as is observed for the He and Ar gases (although at a much slower rate), yielding solutions with no significant change in energy. Unlike a mixture of gases, however, the components of these liquid-liquid solutions do, indeed, experience intermolecular attractive forces. But since the molecules of the two substances being mixed are structurally very similar, the intermolecular attractive forces between like and unlike molecules are essentially the same, and the dissolution process, therefore, does not entail any appreciable increase or decrease in energy. These examples illustrate how diffusion alone can provide the driving force required to cause the spontaneous formation of a solution. In some cases, however, the relative magnitudes of intermolecular forces of attraction between solute and solvent species may prevent dissolution.




Figure 13.1.3: This schematic representation of dissolution shows a stepwise process involving the endothermic separation of solute and solvent species (Steps 1 and 2) and exothermic solvation (Step 3).

Three types of intermolecular attractive forces are relevant to the dissolution process: solute-solute, solvent-solvent, and solute-solvent. As illustrated in Figure 13.1.3, the formation of a solution may be viewed as a stepwise process in which energy is consumed to overcome solute-solute and solvent-solvent attractions (endothermic processes) and released when solute-solvent attractions are established (an exothermic process referred to as solvation). The relative magnitudes of the energy changes associated with these stepwise processes determine whether the dissolution process overall will release or absorb energy. In some cases, solutions do not form because the energy required to separate solute and solvent species is so much greater than the energy released by solvation.



Figure **13.1.4**: A mixture of nonpolar cooking oil and polar water does not yield a solution. (credit: Gautam Dogra).

For example, cooking oils and water will not mix to any appreciable extent to yield solutions (Figure **13.1.4**). Hydrogen bonding is the dominant intermolecular attractive force present in liquid water; the nonpolar hydrocarbon molecules of cooking oils are not capable of hydrogen bonding, instead being held together by dispersion forces. Forming an oil-water solution would require overcoming the very strong hydrogen bonding in water, as well as the significantly strong dispersion forces between the relatively large oil molecules. And, since the polar water molecules and nonpolar oil molecules would not experience very strong intermolecular attraction, very little energy would be released by solvation.

On the other hand, a mixture of ethanol and water will mix in any proportions to yield a solution. In this case, both substances are capable of hydrogen bonding, and so the solvation process is sufficiently exothermic to compensate for the endothermic separations of solute and solvent molecules.



Figure **13.1.5**: An instant cold pack gets cold when certain salts, such as ammonium nitrate, dissolve in water—an endothermic process.

As noted at the beginning of this module, spontaneous solution formation is favored, but not guaranteed, by exothermic dissolution processes. While many soluble compounds do, indeed, dissolve with the release of heat, some dissolve endothermically. Ammonium nitrate (NH_4NO_3) is one such example and is used to make instant cold packs for treating injuries like the one pictured in Figure **13.1.5**. A thin-walled plastic bag of water is sealed inside a larger bag with solid NH_4NO_3. When the smaller bag is broken, a solution of NH_4NO_3 forms, absorbing heat from the surroundings (the injured area to which the pack is applied) and providing a cold compress that decreases swelling. Endothermic dissolutions such as this one require a greater energy input to separate the solute species than is recovered when the solutes are solvated, but they are spontaneous nonetheless due to the increase in disorder that accompanies formation of the solution.



Video* 13.1.1: Watch this brief video illustrating endothermic and exothermic dissolution processes.*

Summary

A solution forms when two or more substances combine physically to yield a mixture that is homogeneous at the molecular level. The solvent is the most concentrated component and determines the physical state of the solution. The solutes are the other components typically present at concentrations less than that of the solvent. Solutions may form endothermically or exothermically, depending upon the relative magnitudes of solute and solvent intermolecular attractive forces. Ideal solutions form with no appreciable change in energy.

Footnotes

1. If bubbles of gas are observed within the liquid, the mixture is not homogeneous and, thus, not a solution.

Glossary

alloy
: solid mixture of a metallic element and one or more additional elements

ideal solution
: solution that forms with no accompanying energy change

solvation
: exothermic process in which intermolecular attractive forces between the solute and solvent in a solution are established

spontaneous process
: physical or chemical change that occurs without the addition of energy from an external source

---

13.1: How Do Solutions Form? is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **11.2: The Dissolution Process** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

13.2: Electrolytes

Learning Objectives

- Define and give examples of electrolytes
- Distinguish between the physical and chemical changes that accompany dissolution of ionic and covalent electrolytes
- Relate electrolyte strength to solute-solvent attractive forces

When some substances are dissolved in water, they undergo either a physical or a chemical change that yields ions in solution. These substances constitute an important class of compounds called electrolytes. Substances that do not yield ions when dissolved are called nonelectrolytes. If the physical or chemical process that generates the ions is essentially 100% efficient (all of the dissolved compound yields ions), then the substance is known as a strong electrolyte. If only a relatively small fraction of the dissolved substance undergoes the ion-producing process, it is called a weak electrolyte.

Substances may be identified as strong, weak, or nonelectrolytes by measuring the electrical conductance of an aqueous solution containing the substance. To conduct electricity, a substance must contain freely mobile, charged species. Most familiar is the conduction of electricity through metallic wires, in which case the mobile, charged entities are electrons. Solutions may also conduct electricity if they contain dissolved ions, with conductivity increasing as ion concentration increases. Applying a voltage to electrodes immersed in a solution permits assessment of the relative concentration of dissolved ions, either quantitatively, by measuring the electrical current flow, or qualitatively, by observing the brightness of a light bulb included in the circuit (Figure **13.2.1**).




Figure **13.2.1**: Solutions of nonelectrolytes such as ethanol do not contain dissolved ions and cannot conduct electricity. Solutions of electrolytes contain ions that permit the passage of electricity. The conductivity of an electrolyte solution is related to the strength of the electrolyte.

Ionic Electrolytes

Water and other polar molecules are attracted to ions, as shown in Figure **13.2.2**. The electrostatic attraction between an ion and a molecule with a dipole is called an ion-dipole attraction. These attractions play an important role in the dissolution of ionic compounds in water.




Figure 13.2.2: As potassium chloride (KCl) dissolves in water, the ions are hydrated. The polar water molecules are attracted by the charges on the K^+ and Cl^- ions. Water molecules in front of and behind the ions are not shown.

When ionic compounds dissolve in water, the ions in the solid separate and disperse uniformly throughout the solution because water molecules surround and solvate the ions, reducing the strong electrostatic forces between them. This process represents a physical change known as dissociation. Under most conditions, ionic compounds will dissociate nearly completely when dissolved, and so they are classified as strong electrolytes.

Let us consider what happens at the microscopic level when we add solid KCl to water. Ion-dipole forces attract the positive (hydrogen) end of the polar water molecules to the negative chloride ions at the surface of the solid, and they attract the negative (oxygen) ends to the positive potassium ions. The water molecules penetrate between individual K^+ and Cl^- ions and surround them, reducing the strong interionic forces that bind the ions together and letting them move off into solution as solvated ions, as Figure shows. The reduction of the electrostatic attraction permits the independent motion of each hydrated ion in a dilute solution, resulting in an increase in the disorder of the system as the ions change from their fixed and ordered positions in the crystal to mobile and much more disordered states in solution. This increased disorder is responsible for the dissolution of many ionic compounds, including KCl, which dissolve with absorption of heat.

In other cases, the electrostatic attractions between the ions in a crystal are so large, or the ion-dipole attractive forces between the ions and water molecules are so weak, that the increase in disorder cannot compensate for the energy required to separate the ions, and the crystal is insoluble. Such is the case for compounds such as calcium carbonate (limestone), calcium phosphate (the inorganic component of bone), and iron oxide (rust).



Why do Ionic Solids Dissolve in Water (Ion-Dipole IMF)?: https://youtu.be/yz1Ml0Q8b_I

Covalent Electrolytes


Pure water is an extremely poor conductor of electricity because it is only very slightly ionized—only about two out of every 1 billion molecules ionize at 25 °C. Water ionizes when one molecule of water gives up a proton to another molecule of water,

yielding hydronium and hydroxide ions.

$$H_2O\ (l) + H_2O\ (l) \rightleftharpoons H_3O^+\ (aq) + OH^-\ (aq) \tag{13.2.1}$$

In some cases, we find that solutions prepared from covalent compounds conduct electricity because the solute molecules react chemically with the solvent to produce ions. For example, pure hydrogen chloride is a gas consisting of covalent HCl molecules. This gas contains no ions. However, when we dissolve hydrogen chloride in water, we find that the solution is a very good conductor. The water molecules play an essential part in forming ions: Solutions of hydrogen chloride in many other solvents, such as benzene, do not conduct electricity and do not contain ions.

Hydrogen chloride is an *acid*, and so its molecules react with water, transferring H^+ ions to form hydronium ions (H_3O^+) and chloride ions (Cl^-):



This reaction is essentially 100% complete for HCl (i.e., it is a *strong acid* and, consequently, a strong electrolyte). Likewise, weak acids and bases that only react partially generate relatively low concentrations of ions when dissolved in water and are classified as weak electrolytes. The reader may wish to review the discussion of strong and weak acids provided in the earlier chapter of this text on reaction classes and stoichiometry.

Summary

Substances that dissolve in water to yield ions are called electrolytes. Electrolytes may be covalent compounds that chemically react with water to produce ions (for example, acids and bases), or they may be ionic compounds that dissociate to yield their constituent cations and anions, when dissolved. Dissolution of an ionic compound is facilitated by ion-dipole attractions between the ions of the compound and the polar water molecules. Soluble ionic substances and strong acids ionize completely and are strong electrolytes, while weak acids and bases ionize to only a small extent and are weak electrolytes. Nonelectrolytes are substances that do not produce ions when dissolved in water.

Glossary

dissociation
: physical process accompanying the dissolution of an ionic compound in which the compound's constituent ions are solvated and dispersed throughout the solution

electrolyte
: substance that produces ions when dissolved in water

ion-dipole attraction
: electrostatic attraction between an ion and a polar molecule

nonelectrolyte
: substance that does not produce ions when dissolved in water

strong electrolyte
: substance that dissociates or ionizes completely when dissolved in water

weak electrolyte
: substance that ionizes only partially when dissolved in water

---

13.2: Electrolytes is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **11.3: Electrolytes** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

13.3: Factors Affecting Solubility

Learning Objectives

- Describe the effects of temperature and pressure on solubility
- State Henry's law and use it in calculations involving the solubility of a gas in a liquid
- Explain the degrees of solubility possible for liquid-liquid solutions

Imagine adding a small amount of salt to a glass of water, stirring until all the salt has dissolved, and then adding a bit more. You can repeat this process until the salt concentration of the solution reaches its natural limit, a limit determined primarily by the relative strengths of the solute-solute, solute-solvent, and solvent-solvent attractive forces discussed in the previous two modules of this chapter. You can be certain that you have reached this limit because, no matter how long you stir the solution, undissolved salt remains. The concentration of salt in the solution at this point is known as its solubility.

The solubility of a solute in a particular solvent is the maximum concentration that may be achieved under given conditions when the dissolution process is at equilibrium. Referring to the example of salt in water:

$$\mathrm{NaCl}(s) \rightleftharpoons \mathrm{Na}^+(aq) + \mathrm{Cl}^-(aq) \tag{13.3.1}$$

When a solute's concentration is equal to its solubility, the solution is said to be saturated with that solute. If the solute's concentration is less than its solubility, the solution is said to be unsaturated. A solution that contains a relatively low concentration of solute is called dilute, and one with a relatively high concentration is called concentrated.

If we add more salt to a saturated solution of salt, we see it fall to the bottom and no more seems to dissolve. In fact, the added salt does dissolve, as represented by the forward direction of the dissolution equation. Accompanying this process, dissolved salt will precipitate, as depicted by the reverse direction of the equation. The system is said to be at equilibrium when these two reciprocal processes are occurring at equal rates, and so the amount of undissolved and dissolved salt remains constant. Support for the simultaneous occurrence of the dissolution and precipitation processes is provided by noting that the number and sizes of the undissolved salt crystals will change over time, though their combined mass will remain the same.



Video **13.3.1**: Watch this impressive video showing the precipitation of sodium acetate from a supersaturated solution.

Solutions may be prepared in which a solute concentration exceeds its solubility. Such solutions are said to be supersaturated, and they are interesting examples of nonequilibrium states. For example, the carbonated beverage in an open container that has not yet "gone flat" is supersaturated with carbon dioxide gas; given time, the CO_2 concentration will decrease until it reaches its equilibrium value.

Solutions of Gases in Liquids

In an earlier module of this chapter, the effect of intermolecular attractive forces on solution formation was discussed. The chemical structures of the solute and solvent dictate the types of forces possible and, consequently, are important factors in determining solubility. For example, under similar conditions, the water solubility of oxygen is approximately three times greater than that of

helium, but 100 times less than the solubility of chloromethane, $CHCl_3$. Considering the role of the solvent's chemical structure, note that the solubility of oxygen in the liquid hydrocarbon hexane, C_6H_{14}, is approximately 20 times greater than it is in water.

Other factors also affect the solubility of a given substance in a given solvent. Temperature is one such factor, with gas solubility typically decreasing as temperature increases (Figure **13.3.1**). This is one of the major impacts resulting from the thermal pollution of natural bodies of water.




Figure **13.3.1**: The solubilities of these gases in water decrease as the temperature increases. All solubilities were measured with a constant pressure of 101.3 kPa (1 atm) of gas above the solutions.

When the temperature of a river, lake, or stream is raised abnormally high, usually due to the discharge of hot water from some industrial process, the solubility of oxygen in the water is decreased. Decreased levels of dissolved oxygen may have serious consequences for the health of the water's ecosystems and, in severe cases, can result in large-scale fish kills (Figure **13.3.2**).



(a) (b)

Figure **13.3.2**: (a) The small bubbles of air in this glass of chilled water formed when the water warmed to room temperature and the solubility of its dissolved air decreased. (b) The decreased solubility of oxygen in natural waters subjected to thermal pollution can result in large-scale fish kills. (credit a: modification of work by Liz West; credit b: modification of work by U.S. Fish and Wildlife Service)

The solubility of a gaseous solute is also affected by the partial pressure of solute in the gas to which the solution is exposed. Gas solubility increases as the pressure of the gas increases. Carbonated beverages provide a nice illustration of this relationship. The carbonation process involves exposing the beverage to a relatively high pressure of carbon dioxide gas and then sealing the beverage container, thus saturating the beverage with CO_2 at this pressure. When the beverage container is opened, a familiar hiss is heard as the carbon dioxide gas pressure is released, and some of the dissolved carbon dioxide is typically seen leaving solution in the form of small bubbles (Figure **13.3.3**). At this point, the beverage is supersaturated with carbon dioxide and, with time, the dissolved carbon dioxide concentration will decrease to its equilibrium value and the beverage will become "flat."




Figure 13.3.3: Opening the bottle of carbonated beverage reduces the pressure of the gaseous carbon dioxide above the beverage. The solubility of CO_2 is thus lowered, and some dissolved carbon dioxide may be seen leaving the solution as small gas bubbles. (credit: modification of work by Derrick Coetzee)

For many gaseous solutes, the relation between solubility, C_g, and partial pressure, P_g, is a proportional one:

$$C_g = kP_g \tag{13.3.2}$$

where k is a proportionality constant that depends on the identities of the gaseous solute and solvent, and on the solution temperature. This is a mathematical statement of Henry's law: The quantity of an ideal gas that dissolves in a definite volume of liquid is directly proportional to the pressure of the gas.

Example 13.3.1: Application of Henry's Law

At 20 °C, the concentration of dissolved oxygen in water exposed to gaseous oxygen at a partial pressure of 101.3 kPa (760 torr) is 1.38×10^{-3} mol L^{-1}. Use Henry's law to determine the solubility of oxygen when its partial pressure is 20.7 kPa (155 torr), the approximate pressure of oxygen in earth's atmosphere.

Solution

According to Henry's law, for an ideal solution the solubility, C_g, of a gas (1.38×10^{-3} mol L^{-1}, in this case) is directly proportional to the pressure, P_g, of the undissolved gas above the solution (101.3 kPa, or 760 torr, in this case). Because we know both C_g and P_g, we can rearrange this expression to solve for k.

$$\begin{aligned} C_g &= kP_g \\ k &= \frac{C_g}{P_g} \\ &= \frac{1.38 \times 10^{-3}\ \text{mol L}^{-1}}{101.3\ \text{kPa}} \\ &= 1.36 \times 10^{-5}\ \text{mol L}^{-1}\ \text{kPa}^{-1} \\ &\quad (1.82 \times 10^{-6}\ \text{mol L}^{-1}\ \text{torr}^{-1}) \end{aligned}$$

Now we can use k to find the solubility at the lower pressure.

$$C_g = kP_g$$

$$\begin{aligned} &1.36 \times 10^{-5}\ \text{mol L}^{-1}\ \text{kPa}^{-1} \times 20.7\ \text{kPa} \\ &(\text{or } 1.82 \times 10^{-6}\ \text{mol L}^{-1}\ \text{torr}^{-1} \times 155\ \text{torr}) \\ &= 2.82 \times 10^{-4}\ \text{mol L}^{-1} \end{aligned}$$

Note that various units may be used to express the quantities involved in these sorts of computations. Any combination of units that yield to the constraints of dimensional analysis are acceptable.

Exercise 13.3.1

Exposing a 100.0 mL sample of water at 0 °C to an atmosphere containing a gaseous solute at 20.26 kPa (152 torr) resulted in the dissolution of 1.45×10^{-3} g of the solute. Use Henry's law to determine the solubility of this gaseous solute when its

pressure is 101.3 kPa (760 torr).

Answer

7.25×10^{-3} g in 100.0 mL or 0.0725 g/L

Case Study: Decompression Sickness (“The Bends”)


Decompression sickness (DCS), or “the bends,” is an effect of the increased pressure of the air inhaled by scuba divers when swimming underwater at considerable depths. In addition to the pressure exerted by the atmosphere, divers are subjected to additional pressure due to the water above them, experiencing an increase of approximately 1 atm for each 10 m of depth. Therefore, the air inhaled by a diver while submerged contains gases at the corresponding higher ambient pressure, and the concentrations of the gases dissolved in the diver’s blood are proportionally higher per Henry’s law.



Figure **13.3.4**: (a) US Navy divers undergo training in a recompression chamber. (b) Divers receive hyperbaric oxygen therapy.

As the diver ascends to the surface of the water, the ambient pressure decreases and the dissolved gases becomes less soluble. If the ascent is too rapid, the gases escaping from the diver’s blood may form bubbles that can cause a variety of symptoms ranging from rashes and joint pain to paralysis and death. To avoid DCS, divers must ascend from depths at relatively slow speeds (10 or 20 m/min) or otherwise make several decompression stops, pausing for several minutes at given depths during the ascent. When these preventive measures are unsuccessful, divers with DCS are often provided hyperbaric oxygen therapy in pressurized vessels called decompression (or recompression) chambers (Figure **13.3.4**).

Deviations from Henry’s law are observed when a chemical reaction takes place between the gaseous solute and the solvent. Thus, for example, the solubility of ammonia in water does not increase as rapidly with increasing pressure as predicted by the law because ammonia, being a base, reacts to some extent with water to form ammonium ions and hydroxide ions.



Gases can form **supersaturated solutions**. If a solution of a gas in a liquid is prepared either at low temperature or under pressure (or both), then as the solution warms or as the gas pressure is reduced, the solution may become supersaturated. In 1986, more than 1700 people in Cameroon were killed when a cloud of gas, almost certainly carbon dioxide, bubbled from Lake Nyos (Figure **13.3.5**), a deep lake in a volcanic crater. The water at the bottom of Lake Nyos is saturated with carbon dioxide by volcanic activity beneath the lake. It is believed that the lake underwent a turnover due to gradual heating from below the lake, and the warmer, less-dense water saturated with carbon dioxide reached the surface. Consequently, tremendous quantities of dissolved CO_2 were released, and the colorless gas, which is denser than air, flowed down the valley below the lake and suffocated humans and animals living in the valley.



(a) (b)

Figure 13.3.5: (a) It is believed that the 1986 disaster that killed more than 1700 people near Lake Nyos in Cameroon resulted when a large volume of carbon dioxide gas was released from the lake. (b) A CO_2 vent has since been installed to help outgas the lake in a slow, controlled fashion and prevent a similar catastrophe from happening in the future. (credit a: modification of work by Jack Lockwood; credit b: modification of work by Bill Evans)



Henry's Law (The Solubility of Gases in Solvents): https://youtu.be/fiJZCGpArJI

Solutions of Liquids in Liquids

We know that some liquids mix with each other in all proportions; in other words, they have infinite mutual solubility and are said to be miscible. Ethanol, sulfuric acid, and ethylene glycol (popular for use as antifreeze, pictured in Figure 13.3.6) are examples of liquids that are completely miscible with water. Two-cycle motor oil is miscible with gasoline.



Figure 13.3.6: Water and antifreeze are miscible; mixtures of the two are homogeneous in all proportions. (credit: “dno1967”/Wikimedia commons)

Liquids that mix with water in all proportions are usually polar substances or substances that form hydrogen bonds. For such liquids, the dipole-dipole attractions (or hydrogen bonding) of the solute molecules with the solvent molecules are at least as strong as those between molecules in the pure solute or in the pure solvent. Hence, the two kinds of molecules mix easily. Likewise, nonpolar liquids are miscible with each other because there is no appreciable difference in the strengths of solute-solute, solvent-

solvent, and solute-solvent intermolecular attractions. The solubility of polar molecules in polar solvents and of nonpolar molecules in nonpolar solvents is, again, an illustration of the chemical axiom “like dissolves like.”

Two liquids that do not mix to an appreciable extent are called immiscible. Layers are formed when we pour immiscible liquids into the same container. Gasoline, oil (Figure **13.3.7**), benzene, carbon tetrachloride, some paints, and many other nonpolar liquids are immiscible with water. The attraction between the molecules of such nonpolar liquids and polar water molecules is ineffectively weak. The only strong attractions in such a mixture are between the water molecules, so they effectively squeeze out the molecules of the nonpolar liquid. The distinction between immiscibility and miscibility is really one of degrees, so that miscible liquids are of infinite mutual solubility, while liquids said to be immiscible are of very low (though not zero) mutual solubility.




Figure **13.3.7**: Water and oil are immiscible. Mixtures of these two substances will form two separate layers with the less dense oil floating on top of the water. (credit: “Yortw”/Flickr)

Two liquids, such as bromine and water, that are of moderate mutual solubility are said to be partially miscible. Two partially miscible liquids usually form two layers when mixed. In the case of the bromine and water mixture, the upper layer is water, saturated with bromine, and the lower layer is bromine saturated with water. Since bromine is nonpolar, and, thus, not very soluble in water, the water layer is only slightly discolored by the bright orange bromine dissolved in it. Since the solubility of water in bromine is very low, there is no noticeable effect on the dark color of the bromine layer (Figure **13.3.8**).



Figure **13.3.8**: Bromine (the deep orange liquid on the left) and water (the clear liquid in the middle) are partially miscible. The top layer in the mixture on the right is a saturated solution of bromine in water; the bottom layer is a saturated solution of water in bromine. (credit: Paul Flowers)



The Miscibility of Liquids: https://youtu.be/J-pDm8xs_to

Solutions of Solids in Liquids

The dependence of solubility on temperature for a number of inorganic solids in water is shown by the solubility curves in Figure **13.3.9**. Reviewing these data indicate a general trend of increasing solubility with temperature, although there are exceptions, as illustrated by the ionic compound cerium sulfate.




Figure **13.3.9**: This graph shows how the solubility of several solids changes with temperature.

The temperature dependence of solubility can be exploited to prepare supersaturated solutions of certain compounds. A solution may be saturated with the compound at an elevated temperature (where the solute is more soluble) and subsequently cooled to a lower temperature without precipitating the solute. The resultant solution contains solute at a concentration greater than its equilibrium solubility at the lower temperature (i.e., it is supersaturated) and is relatively stable. Precipitation of the excess solute can be initiated by adding a seed crystal (see the video in the Link to Learning earlier in this module) or by mechanically agitating the solution. Some hand warmers, such as the one pictured in Figure **13.3.10**, take advantage of this behavior.



Figure 13.3.10: This hand warmer produces heat when the sodium acetate in a supersaturated solution precipitates. Precipitation of the solute is initiated by a mechanical shockwave generated when the flexible metal disk within the solution is "clicked." (credit: modification of work by "Velela"/Wikimedia Commons)



Video 13.3.2: This video shows the crystallization process occurring in a hand warmer.

Summary

The extent to which one substance will dissolve in another is determined by several factors, including the types and relative strengths of intermolecular attractive forces that may exist between the substances' atoms, ions, or molecules. This tendency to dissolve is quantified as substance's solubility, its maximum concentration in a solution at equilibrium under specified conditions. A saturated solution contains solute at a concentration equal to its solubility. A supersaturated solution is one in which a solute's concentration exceeds its solubility—a nonequilibrium (unstable) condition that will result in solute precipitation when the solution is appropriately perturbed. Miscible liquids are soluble in all proportions, and immiscible liquids exhibit very low mutual solubility. Solubilities for gaseous solutes decrease with increasing temperature, while those for most, but not all, solid solutes increase with temperature. The concentration of a gaseous solute in a solution is proportional to the partial pressure of the gas to which the solution is exposed, a relation known as Henry's law.

Key Equations

- $C_g = kP_g$

Glossary

Henry's law
: law stating the proportional relationship between the concentration of dissolved gas in a solution and the partial pressure of the gas in contact with the solution

immiscible
: of negligible mutual solubility; typically refers to liquid substances

miscible
: mutually soluble in all proportions; typically refers to liquid substances

partially miscible
: of moderate mutual solubility; typically refers to liquid substances

saturated

of concentration equal to solubility; containing the maximum concentration of solute possible for a given temperature and pressure

solubility

extent to which a solute may be dissolved in water, or any solvent

supersaturated

of concentration that exceeds solubility; a nonequilibrium state

unsaturated

of concentration less than solubility

13.3: Factors Affecting Solubility is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **11.4: Solubility** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

13.4: Solution Concentration

Learning Objectives

- Define the concentration units of mass percentage, volume percentage, mass-volume percentage, parts-per-million (ppm), parts-per-billion (ppb), molality, and mole fraction.
- Perform computations relating a solution's concentration and its components' volumes and/or masses using these units

In chapter 4, we introduced molarity, a very useful measurement unit for evaluating the concentration of solutions. However, molarity is only one measure of concentration. In this section, we will introduce some other units of concentration that are commonly used in various applications, either for convenience or by convention.

Mass Percentage

Earlier in this chapter, we introduced percent composition as a measure of the relative amount of a given element in a compound. Percentages are also commonly used to express the composition of mixtures, including solutions. The mass percentage of a solution component is defined as the ratio of the component's mass to the solution's mass, expressed as a percentage:

$$\text{mass percentage} = \frac{\text{mass of component}}{\text{mass of solution}} \times 100\% \tag{13.4.1}$$

We are generally most interested in the mass percentages of solutes, but it is also possible to compute the mass percentage of solvent.

Mass percentage is also referred to by similar names such as *percent mass*, *percent weight*, *weight/weight percent*, and other variations on this theme. The most common symbol for mass percentage is simply the percent sign, %, although more detailed symbols are often used including %mass, %weight, and (w/w)%. Use of these more detailed symbols can prevent confusion of mass percentages with other types of percentages, such as volume percentages (to be discussed later in this section).

Mass percentages are popular concentration units for consumer products. The label of a typical liquid bleach bottle (Figure **13.4.1**) cites the concentration of its active ingredient, sodium hypochlorite (**NaOCl**), as being 7.4%. A 100.0-g sample of bleach would therefore contain 7.4 g of **NaOCl**.



Figure **13.4.1**: Liquid bleach is an aqueous solution of sodium hypochlorite (NaOCl). This brand has a concentration of 7.4% NaOCl by mass.

Example 13.4.1: Calculation of Percent by Mass

A 5.0-g sample of spinal fluid contains 3.75 mg (0.00375 g) of glucose. What is the percent by mass of glucose in spinal fluid?

Solution

The spinal fluid sample contains roughly 4 mg of glucose in 5000 mg of fluid, so the mass fraction of glucose should be a bit less than one part in 1000, or about 0.1%. Substituting the given masses into the equation defining mass percentage yields:

$$\%\,\text{glucose} = \frac{3.75\ \text{mg glucose} \times \frac{1\ \text{g}}{1000\ \text{mg}}}{5.0\ \text{g spinal fluid}} = 0.075\%$$

The computed mass percentage agrees with our rough estimate (it's a bit less than 0.1%).

Note that while any mass unit may be used to compute a mass percentage (mg, g, kg, oz, and so on), the same unit must be used for both the solute and the solution so that the mass units cancel, yielding a dimensionless ratio. In this case, we converted the units of solute in the numerator from mg to g to match the units in the denominator. We could just as easily have converted the denominator from g to mg instead. As long as identical mass units are used for both solute and solution, the computed mass percentage will be correct.

Exercise 13.4.1

A bottle of a tile cleanser contains 135 g of $\mathbf{HCl}$ and 775 g of water. What is the percent by mass of $\mathbf{HCl}$ in this cleanser?

Answer


14.8%

Example 13.4.2: Calculations using Mass Percentage

"Concentrated" hydrochloric acid is an aqueous solution of 37.2% $\mathbf{HCl}$ that is commonly used as a laboratory reagent. The density of this solution is 1.19 g/mL. What mass of $\mathbf{HCl}$ is contained in 0.500 L of this solution?

Solution

The HCl concentration is near 40%, so a 100-g portion of this solution would contain about 40 g of HCl. Since the solution density isn't greatly different from that of water (1 g/mL), a reasonable estimate of the HCl mass in 500 g (0.5 L) of the solution is about five times greater than that in a 100 g portion, or $\mathbf{5 \times 40 = 200\ g}$. To derive the mass of solute in a solution from its mass percentage, we need to know the corresponding mass of the solution. Using the solution density given, we can convert the solution's volume to mass, and then use the given mass percentage to calculate the solute mass. This mathematical approach is outlined in this flowchart:



For proper unit cancellation, the 0.500-L volume is converted into 500 mL, and the mass percentage is expressed as a ratio, 37.2 g HCl/g solution:

$$\mathbf{500\ mL\ solution \left(\frac{1.19\ g\ solution}{mL\ solution}\right)\left(\frac{37.2\ g\ HCl}{100\ g\ solution}\right) = 221\ g\ HCl}$$

This mass of HCl is consistent with our rough estimate of approximately 200 g.

Exercise 13.4.2

What volume of concentrated HCl solution contains 125 g of HCl?

Answer

282 mL

Volume Percentage

Liquid volumes over a wide range of magnitudes are conveniently measured using common and relatively inexpensive laboratory equipment. The concentration of a solution formed by dissolving a liquid solute in a liquid solvent is therefore often expressed as a volume percentage, %vol or (v/v)%:

$$\text{volume percentage} = \frac{\text{volume solute}}{\text{volume solution}} \times 100\% \tag{13.4.2}$$

Example 13.4.3: Calculations using Volume Percentage

Rubbing alcohol (isopropanol) is usually sold as a 70%vol aqueous solution. If the density of isopropyl alcohol is 0.785 g/mL, how many grams of isopropyl alcohol are present in a 355 mL bottle of rubbing alcohol?

Solution

Per the definition of volume percentage, the isopropanol volume is 70% of the total solution volume. Multiplying the isopropanol volume by its density yields the requested mass:

$$\begin{aligned} &355 \text{ mL solution} \left(\frac{70 \text{ mL isopropyl alcohol}}{100 \text{ mL solution}}\right)\left(\frac{0.785 \text{ g isopropyl alcohol}}{1 \text{ mL isopropyl alcohol}}\right) \\ &= 195 \text{ g isopropyl alcohol} \end{aligned}$$

Exercise 13.4.3

Wine is approximately 12% ethanol (CH_3CH_2OH) by volume. Ethanol has a molar mass of 46.06 g/mol and a density 0.789 g/mL. How many moles of ethanol are present in a 750-mL bottle of wine?

Answer

1.5 mol ethanol

Mass-Volume Percentage

“Mixed” percentage units, derived from the mass of solute and the volume of solution, are popular for certain biochemical and medical applications. A mass-volume percent is a ratio of a solute’s mass to the solution’s volume expressed as a percentage. The specific units used for solute mass and solution volume may vary, depending on the solution. For example, physiological saline solution, used to prepare intravenous fluids, has a concentration of 0.9% mass/volume (m/v), indicating that the composition is 0.9 g of solute per 100 mL of solution. The concentration of glucose in blood (commonly referred to as “blood sugar”) is also typically expressed in terms of a mass-volume ratio. Though not expressed explicitly as a percentage, its concentration is usually given in milligrams of glucose per deciliter (100 mL) of blood (Figure 13.4.2).



Figure 13.4.2: “Mixed” mass-volume units are commonly encountered in medical settings. (a) The NaCl concentration of physiological saline is 0.9% (m/v). (b) This device measures glucose levels in a sample of blood. The normal range for glucose concentration in blood (fasting) is around 70–100 mg/dL. (credit a: modification of work by “The National Guard”/Flickr; credit b: modification of work by Biswarup Ganguly).

Parts per Million and Parts per Billion


Very low solute concentrations are often expressed using appropriately small units such as parts per million (ppm) or parts per billion (ppb). Like percentage (“part per hundred”) units, ppm and ppb may be defined in terms of masses, volumes, or mixed mass-volume units. There are also ppm and ppb units defined with respect to numbers of atoms and molecules.

The mass-based definitions of ppm and ppb are given here:

$$\text{ppm} = \frac{\text{mass solute}}{\text{mass solution}} \times 10^6 \text{ ppm} \tag{13.4.3}$$

$$\text{ppb} = \frac{\text{mass solute}}{\text{mass solution}} \times 10^9 \text{ ppb} \tag{13.4.4}$$

Both ppm and ppb are convenient units for reporting the concentrations of pollutants and other trace contaminants in water. Concentrations of these contaminants are typically very low in treated and natural waters, and their levels cannot exceed relatively low concentration thresholds without causing adverse effects on health and wildlife. For example, the EPA has identified the maximum safe level of fluoride ion in tap water to be 4 ppm. Inline water filters are designed to reduce the concentration of fluoride and several other trace-level contaminants in tap water (Figure **13.4.3**).



(a) (b)

Figure **13.4.3**: (a) In some areas, trace-level concentrations of contaminants can render unfiltered tap water unsafe for drinking and cooking. (b) Inline water filters reduce the concentration of solutes in tap water. (credit a: modification of work by Jenn Durfey; credit b: modification of work by "vastateparkstaff"/Wikimedia commons).

Example 13.4.4: Parts per Million and Parts per Billion Concentrations

According to the EPA, when the concentration of lead in tap water reaches 15 ppb, certain remedial actions must be taken. What is this concentration in ppm? At this concentration, what mass of lead (μg) would be contained in a typical glass of water (300 mL)?

Solution

The definitions of the ppm and ppb units may be used to convert the given concentration from ppb to ppm. Comparing these two unit definitions shows that ppm is 1000 times greater than ppb (1 ppm = 10^3 ppb). Thus:

$$15 \cancel{\text{ ppb}} \times \frac{1 \text{ ppm}}{10^3 \cancel{\text{ ppb}}} = 0.015 \text{ ppm}$$

The definition of the ppb unit may be used to calculate the requested mass if the mass of the solution is provided. However, only the volume of solution (300 mL) is given, so we must use the density to derive the corresponding mass. We can assume the density of tap water to be roughly the same as that of pure water (~1.00 g/mL), since the concentrations of any dissolved substances should not be very large. Rearranging the equation defining the ppb unit and substituting the given quantities yields:

$$\text{ppb} = \frac{\text{mass solute}}{\text{mass solution}} \times 10^9 \text{ ppb}$$

$$\text{mass solute} = \frac{\text{ppb} \times \text{mass solution}}{10^9 \text{ ppb}}$$

$$\text{mass solute} = \frac{15 \text{ ppb} \times 300 \text{ mL} \times \frac{1.00 \text{ g}}{\text{mL}}}{10^9 \text{ ppb}} = 4.5 \times 10^{-6} \text{ g}$$

Finally, convert this mass to the requested unit of micrograms:

$$4.5 \times 10^{-6}\ \text{g} \times \frac{1\ \mu\text{g}}{10^{-6}\ \text{g}} = 4.5\ \mu\text{g}$$

? Exercise 13.4.4

A 50.0-g sample of industrial wastewater was determined to contain 0.48 mg of mercury. Express the mercury concentration of the wastewater in ppm and ppb units.

Answer

9.6 ppm, 9600 ppb



Measures of Concentration: https://youtu.be/RjMGaUpkg8g

Mole Fraction and Molality

Several units commonly used to express the concentrations of solution components were introduced in an earlier chapter of this text, each providing certain benefits for use in different applications. For example, molarity (M) is a convenient unit for use in stoichiometric calculations, since it is defined in terms of the molar amounts of solute species:

$$M = \frac{\text{mol solute}}{\text{L solution}} \tag{13.4.5}$$

Because solution volumes vary with temperature, molar concentrations will likewise vary. When expressed as molarity, the concentration of a solution with identical numbers of solute and solvent species will be different at different temperatures, due to the contraction/expansion of the solution. More appropriate for calculations involving many colligative properties are mole-based concentration units whose values are not dependent on temperature. Two such units are *mole fraction* (introduced in the previous chapter on gases) and *molality*.

The mole fraction, χ, of a component is the ratio of its molar amount to the total number of moles of all solution components:

$$\chi_{\text{A}} = \frac{\text{mol A}}{\text{total mol of all components}} \tag{13.4.6}$$

Molality is a concentration unit defined as the ratio of the numbers of moles of solute to the mass of the solvent in kilograms:

$$m = \frac{\text{mol solute}}{\text{kg solvent}} \tag{13.4.7}$$

Since these units are computed using only masses and molar amounts, they do not vary with temperature and, thus, are better suited for applications requiring temperature-independent concentrations, including several colligative properties, as will be described in this chapter module.

Example 13.4.5: Calculating Mole Fraction and Molality

The antifreeze in most automobile radiators is a mixture of equal volumes of ethylene glycol and water, with minor amounts of other additives that prevent corrosion. What are the (a) mole fraction and (b) molality of ethylene glycol, $C_2H_4(OH)_2$, in a solution prepared from 2.22×10^3 g of ethylene glycol and 2.00×10^3 g of water (approximately 2 L of glycol and 2 L of water)?

Solution

(a) The mole fraction of ethylene glycol may be computed by first deriving molar amounts of both solution components and then substituting these amounts into the unit definition.

$$\text{mol } C_2H_4(OH)_2 = 2220 \text{ g} \times \frac{1 \text{ mol } C_2H_4(OH)_2}{62.07 \text{ g } C_2H_4(OH)_2} = 35.8 \text{ mol } C_2H_4(OH)_2$$

$$\text{mol } H_2O = 2000 \text{ g} \times \frac{1 \text{ mol } H_2O}{18.02 \text{ g } H_2O} = 111 \text{ mol } H_2O$$

$$\chi_{\text{ethylene glycol}} = \frac{35.8 \text{ mol } C_2H_4(OH)_2}{(35.8 + 111) \text{ mol total}} = 0.245$$

Notice that mole fraction is a dimensionless property, being the ratio of properties with identical units (moles).

(b) To find molality, we need to know the moles of the solute and the mass of the solvent (in kg).

First, use the given mass of ethylene glycol and its molar mass to find the moles of solute:

$$2220 \text{ g } C_2H_4(OH)_2 \left(\frac{\text{mol } C_2H_2(OH)_2}{62.07 \text{ g}} \right) = 35.8 \text{ mol } C_2H_4(OH)_2 \tag{13.4.8}$$

Then, convert the mass of the water from grams to kilograms:

$$2000 \text{ g } H_2O \left(\frac{1 \text{ kg}}{1000 \text{ g}} \right) = 2 \text{ kg } H_2O \tag{13.4.9}$$

Finally, calculate molarity per its definition:

$$\text{molality} = \frac{\text{mol solute}}{\text{kg solvent}}$$

$$\text{molality} = \frac{35.8 \text{ mol } C_2H_4(OH)_2}{2 \text{ kg } H_2O}$$

$$\text{molality} = 17.9 \, m$$

Exercise 13.4.5

What are the mole fraction and molality of a solution that contains 0.850 g of ammonia, NH_3, dissolved in 125 g of water?

Answer

7.14×10^{-3}; 0.399 *m*

Example 13.4.6: Converting Mole Fraction and Molal Concentrations

Calculate the mole fraction of solute and solvent in a 3.0 *m* solution of sodium chloride.

Solution

Converting from one concentration unit to another is accomplished by first comparing the two unit definitions. In this case, both units have the same numerator (moles of solute) but different denominators. The provided molal concentration may be written as:

$$\frac{3.0 \text{ mol NaCl}}{1.0 \text{ kg } H_2O} \tag{13.4.10}$$

The numerator for this solution's mole fraction is, therefore, 3.0 mol NaCl. The denominator may be computed by deriving the molar amount of water corresponding to 1.0 kg

$$1.0\ \text{kg}\ \text{H}_2\text{O}\left(\frac{1000\ \text{g}}{1\ \text{kg}}\right)\left(\frac{\text{mol}\ \text{H}_2\text{O}}{18.02\ \text{g}}\right) = 55\ \text{mol}\ \text{H}_2\text{O} \tag{13.4.11}$$

and then substituting these molar amounts into the definition for mole fraction.

$$X_{\text{H}_2\text{O}} = \frac{\text{mol}\ \text{H}_2\text{O}}{\text{mol NaCl} + \text{mol}\ \text{H}_2\text{O}}$$
$$X_{\text{H}_2\text{O}} = \frac{55\ \text{mol}\ \text{H}_2\text{O}}{3.0\ \text{mol NaCl} + 55\ \text{mol}\ \text{H}_2\text{O}}$$
$$X_{\text{H}_2\text{O}} = 0.95$$
$$X_{\text{NaCl}} = \frac{\text{mol NaCl}}{\text{mol NaCl} + \text{mol}\ \text{H}_2\text{O}}$$
$$X_{\text{NaCl}} = \frac{3.0\ \text{mol NaCl}}{3.0\ \text{mol NaCl} + 55\ \text{mol}\ \text{H}_2\text{O}}$$
$$X_{\text{NaCl}} = 0.052$$

? Exercise 13.4.6

The mole fraction of iodine, I_2, dissolved in dichloromethane, CH_2Cl_2, is 0.115. What is the molal concentration, *m*, of iodine in this solution?

Answer

1.50 *m*



A Video Discussing how to Convert Measures of Concentration. Video Link: https://youtu.be/MG5CZOrazRA

✔ Example 13.4.7: Vodka

Vodka is essentially a solution of ethanol in water. Typical vodka is sold as "80 proof," which means that it contains 40.0% ethanol by volume. The density of pure ethanol is 0.789 g/mL at 20°C. If we assume that the volume of the solution is the sum of the volumes of the components (which is not strictly correct), calculate the following for the ethanol in 80-proof vodka.

a. the mass percentage
b. the mole fraction
c. the molarity
d. the molality

Given: volume percent and density

Asked for: mass percentage, mole fraction, molarity, and molality

Strategy:

A. Use the density of the solute to calculate the mass of the solute in 100.0 mL of solution. Calculate the mass of water in 100.0 mL of solution.
B. Determine the mass percentage of solute by dividing the mass of ethanol by the mass of the solution and multiplying by 100.
C. Convert grams of solute and solvent to moles of solute and solvent. Calculate the mole fraction of solute by dividing the moles of solute by the total number of moles of substances present in solution.
D. Calculate the molarity of the solution: moles of solute per liter of solution. Determine the molality of the solution by dividing the number of moles of solute by the kilograms of solvent.

Solution:

The key to this problem is to use the density of pure ethanol to determine the mass of ethanol (CH_3CH_2OH), abbreviated as EtOH, in a given volume of solution. We can then calculate the number of moles of ethanol and the concentration of ethanol in any of the required units. A Because we are given a percentage by volume, we assume that we have 100.0 mL of solution. The volume of ethanol will thus be 40.0% of 100.0 mL, or 40.0 mL of ethanol, and the volume of water will be 60.0% of 100.0 mL, or 60.0 mL of water. The mass of ethanol is obtained from its density:

$$mass\ of\ EtOH = (40.0\ \cancel{mL}) \left(\frac{0.789\ g}{\cancel{mL}} \right) = 31.6\ g\ EtOH$$

If we assume the density of water is 1.00 g/mL, the mass of water is 60.0 g. We now have all the information we need to calculate the concentration of ethanol in the solution.

B The mass percentage of ethanol is the ratio of the mass of ethanol to the total mass of the solution, expressed as a percentage:

$$\begin{aligned} \%EtOH &= \left(\frac{mass\ of\ EtOH}{mass\ of\ solution} \right) (100) \\ &= \left(\frac{31.6\ \cancel{g}\ EtOH}{31.6\ \cancel{g}\ EtOH + 60.0\ \cancel{g}\ H_2O} \right) (100) \\ &= 34.5\% \end{aligned}$$

C The mole fraction of ethanol is the ratio of the number of moles of ethanol to the total number of moles of substances in the solution. Because 40.0 mL of ethanol has a mass of 31.6 g, we can use the molar mass of ethanol (46.07 g/mol) to determine the number of moles of ethanol in 40.0 mL:

$$\begin{aligned} moles\ CH_3CH_2OH &= (31.6\ \cancel{g\ CH_3CH_2OH}) \left(\frac{1\ mol}{46.07\ \cancel{g\ CH_3CH_2OH}} \right) \\ &= 0.686\ mol\ CH_3CH_2OH \end{aligned}$$

Similarly, the number of moles of water is

$$moles\ H_2O = (60.0\ \cancel{g\ H_2O}) \left(\frac{1\ mol\ H_2O}{18.02\ \cancel{g\ H_2O}} \right) = 3.33\ mol\ H_2O$$

The mole fraction of ethanol is thus

$$\chi_{CH_3CH_2OH} = \frac{0.686\ \cancel{mol}}{0.686\ \cancel{mol} + 3.33\ \cancel{mol}} = 0.171$$

D The molarity of the solution is the number of moles of ethanol per liter of solution. We already know the number of moles of ethanol per 100.0 mL of solution, so the molarity is

$$M_{CH_3CH_2OH} = \left(\frac{0.686\ mol}{100\ \cancel{mL}} \right) \left(\frac{1000\ \cancel{mL}}{L} \right) = 6.86\ M$$

The molality of the solution is the number of moles of ethanol per kilogram of solvent. Because we know the number of moles of ethanol in 60.0 g of water, the calculation is again straightforward:

$$m_{CH_3CH_2OH} = \left(\frac{0.686\ mol\ EtOH}{60.0\ \cancel{g}\ H_2O}\right)\left(\frac{1000\ \cancel{g}}{kg}\right) = \frac{11.4\ mol\ EtOH}{kg\ H_2O} = 11.4\ m$$

? Exercise 13.4.7: Toluene/Benzene Solution

A solution is prepared by mixing 100.0 mL of toluene with 300.0 mL of benzene. The densities of toluene and benzene are 0.867 g/mL and 0.874 g/mL, respectively. Assume that the volume of the solution is the sum of the volumes of the components. Calculate the following for toluene.

a. mass percentage
b. mole fraction
c. molarity
d. molality

Answer a

mass percentage toluene = 24.8%

Answer b

$\chi_{toluene} = 0.219$

Answer c

2.35 M toluene

Answer d

3.59 m toluene

How do chemists decide which units of concentration to use for a particular application?

Although molarity is commonly used to express concentrations for reactions in solution or for titrations, it does have one drawback—molarity is the number of moles of solute divided by the volume of the solution, and the volume of a solution depends on its density, which is a function of temperature. Because volumetric glassware is calibrated at a particular temperature, typically 20°C, the molarity may differ from the original value by several percent if a solution is prepared or used at a significantly different temperature, such as 40°C or 0°C. For many applications this may not be a problem, but for precise work these errors can become important. In contrast, mole fraction, molality, and mass percentage depend on only the masses of the solute and solvent, which are independent of temperature.

Mole fraction is not very useful for experiments that involve quantitative reactions, but it is convenient for calculating the partial pressure of gases in mixtures, as discussed previously. Mole fractions are also useful for calculating the vapor pressures of certain types of solutions. Molality is particularly useful for determining how properties such as the freezing or boiling point of a solution vary with solute concentration. Because mass percentage and parts per million or billion are simply different ways of expressing the ratio of the mass of a solute to the mass of the solution, they enable us to express the concentration of a substance even when the molecular mass of the substance is unknown. Units of ppb or ppm are also used to express very low concentrations, such as those of residual impurities in foods or of pollutants in environmental studies.

Table **13.4.1** summarizes the different units of concentration and typical applications for each. When the molar mass of the solute and the density of the solution are known, it becomes relatively easy with practice to convert among the units of concentration we have discussed, as illustrated in Example **13.4.3**.

Table **13.4.1**: Different Units for Expressing the Concentrations of Solutions*

Unit	Definition	Application
molarity (M)	moles of solute/liter of solution (mol/L)	Used for quantitative reactions in solution and titrations; mass and molecular mass of solute and volume of solution are known.
mole fraction (χ)	moles of solute/total moles present (mol/mol)	Used for partial pressures of gases and vapor pressures of some solutions; mass and molecular mass of each component are known.
molality (m)	moles of solute/kg of solvent (mol/kg)	Used in determining how colligative properties vary with solute concentration; masses and molecular mass of solute are known.
mass percentage (%)	[mass of solute (g)/mass of solution (g)] × 100	Useful when masses are known but molecular masses are unknown.
parts per thousand (ppt)	[mass of solute/mass of solution] × 10^3 (g solute/kg solution)	Used in the health sciences, ratio solutions are typically expressed as a proportion, such as 1:1000.
parts per million (ppm)	[mass of solute/mass of solution] × 10^6 (mg solute/kg solution)	Used for trace quantities; masses are known but molecular masses may be unknown.
parts per billion (ppb)	[mass of solute/mass of solution] × 10^9 (µg solute/kg solution)	Used for trace quantities; masses are known but molecular masses may be unknown.

*The molarity of a solution is temperature dependent, but the other units shown in this table are independent of temperature.

Summary

Different units are used to express the concentrations of a solution depending on the application. The concentration of a solution is the quantity of solute in a given quantity of solution. It can be expressed in several ways: molarity (moles of solute per liter of solution); mole fraction, the ratio of the number of moles of solute to the total number of moles of substances present; mass percentage, the ratio of the mass of the solute to the mass of the solution times 100; parts per thousand (ppt), grams of solute per kilogram of solution; parts per million (ppm), milligrams of solute per kilogram of solution; parts per billion (ppb), micrograms of solute per kilogram of solution; and molality (m), the number of moles of solute per kilogram of solvent.

Glossary

mass percentage
ratio of solute-to-solution mass expressed as a percentage

mass-volume percent
ratio of solute mass to solution volume, expressed as a percentage

parts per billion (ppb)
ratio of solute-to-solution mass multiplied by 10^9

molality (*m*)
a concentration unit defined as the ratio of the numbers of moles of solute to the mass of the solvent in kilograms

parts per million (ppm)
ratio of solute-to-solution mass multiplied by 10^6

volume percentage

ratio of solute-to-solution volume expressed as a percentage

13.4: Solution Concentration is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **3.4: Other Units for Solution Concentrations** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **11.5: Colligative Properties** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.
- **13.4: Ways of Expressing Concentration** by Anonymous is licensed CC BY-NC-SA 3.0.

13.5: Colligative Properties

Learning Objectives

- Describe the effect of solute concentration on various solution properties (vapor pressure, boiling point, freezing point, and osmotic pressure)
- Perform calculations using the mathematical equations that describe these various colligative effects
- Describe the process of distillation and its practical applications
- Explain the process of osmosis and describe how it is applied industrially and in nature

The properties of a solution are different from those of either the pure solute(s) or solvent. Many solution properties are dependent upon the chemical identity of the solute. Compared to pure water, a solution of hydrogen chloride is more acidic, a solution of ammonia is more basic, a solution of sodium chloride is more dense, and a solution of sucrose is more viscous. There are a few solution properties, however, that depend *only* upon the total concentration of solute species, regardless of their identities. These colligative properties include vapor pressure lowering, boiling point elevation, freezing point depression, and osmotic pressure. This small set of properties is of central importance to many natural phenomena and technological applications, as will be described in this module.

Vapor Pressure Lowering

As described in the chapter on liquids and solids, the equilibrium vapor pressure of a liquid is the pressure exerted by its gaseous phase when vaporization and condensation are occurring at equal rates:

$$\text{liquid} \rightleftharpoons \text{gas} \tag{13.5.1}$$

Dissolving a nonvolatile substance in a volatile liquid results in a lowering of the liquid's vapor pressure. This phenomenon can be rationalized by considering the effect of added solute molecules on the liquid's vaporization and condensation processes. To vaporize, solvent molecules must be present at the surface of the solution. The presence of solute decreases the surface area available to solvent molecules and thereby reduces the rate of solvent vaporization. Since the rate of condensation is unaffected by the presence of solute, the net result is that the vaporization-condensation equilibrium is achieved with fewer solvent molecules in the vapor phase (i.e., at a lower vapor pressure) (Figure **13.5.1**). While this kinetic interpretation is useful, it does not account for several important aspects of the colligative nature of vapor pressure lowering. A more rigorous explanation involves the property of *entropy*, a topic of discussion in a later text chapter on thermodynamics. For purposes of understanding the lowering of a liquid's vapor pressure, it is adequate to note that the greater entropy of a solution in comparison to its separate solvent and solute serves to effectively stabilize the solvent molecules and hinder their vaporization. A lower vapor pressure results, and a correspondingly higher boiling point as described in the next section of this module.




Figure **13.5.1**: The presence of nonvolatile solutes lowers the vapor pressure of a solution by impeding the evaporation of solvent molecules.

The relationship between the vapor pressures of solution components and the concentrations of those components is described by Raoult's law: *The partial pressure exerted by any component of an ideal solution is equal to the vapor pressure of the pure component multiplied by its mole fraction in the solution.*

$$P_A = X_A P_A^\circ \tag{13.5.2}$$

where P_A is the partial pressure exerted by component A in the solution, P_A° is the vapor pressure of pure A, and X_A is the mole fraction of A in the solution. (Mole fraction is a concentration unit introduced in the chapter on gases.)

Recalling that the total pressure of a gaseous mixture is equal to the sum of partial pressures for all its components (Dalton's law of partial pressures), the total vapor pressure exerted by a solution containing *i* components is

$$P_{solution} = \sum_i P_i = \sum_i X_i P_i^\circ \tag{13.5.3}$$

A nonvolatile substance is one whose vapor pressure is negligible ($P^\circ \approx 0$), and so the vapor pressure above a solution containing only nonvolatile solutes is due only to the solvent:

$$P_{solution} = X_{solvent} P_{solvent}^\circ \tag{13.5.4}$$

Example 13.5.1: Calculation of a Vapor Pressure

Compute the vapor pressure of an ideal solution containing 92.1 g of glycerin, $C_3H_5(OH)_3$, and 184.4 g of ethanol, C_2H_5OH, at 40 °C. The vapor pressure of pure ethanol is 0.178 atm at 40 °C. Glycerin is essentially nonvolatile at this temperature.

Solution

Since the solvent is the only volatile component of this solution, its vapor pressure may be computed per Raoult's law as:

$$P_{solution} = X_{solvent} P_{solvent}^\circ$$

First, calculate the molar amounts of each solution component using the provided mass data.

$$92.1 \text{ g } C_3H_5(OH)_3 \times \frac{1 \text{ mol } C_3H_5(OH)_3}{92.094 \text{ g } C_3H_5(OH)_3} = 1.00 \text{ mol } C_3H_5(OH)_3$$

$$184.4 \text{ g } C_2H_5OH \times \frac{1 \text{ mol } C_2H_5OH}{46.069 \text{ g } C_2H_5OH} = 4.000 \text{ mol } C_2H_5OH$$

Next, calculate the mole fraction of the solvent (ethanol) and use Raoult's law to compute the solution's vapor pressure.

$$X_{C_2H_5OH} = \frac{4.000 \text{ mol}}{(1.00 \text{ mol} + 4.000 \text{ mol})} = 0.800$$

$$P_{solv} = X_{solv} P_{solv}^\circ = 0.800 \times 0.178 \text{ atm} = 0.142 \text{ atm}$$

Exercise 13.5.1

A solution contains 5.00 g of urea, $CO(NH_2)_2$ (a nonvolatile solute) and 0.100 kg of water. If the vapor pressure of pure water at 25 °C is 23.7 torr, what is the vapor pressure of the solution?

Answer

23.4 torr



Finding the Vapor Pressure of a Solution (Nonionic-Nonvolatile Solute):https://youtu.be/WLceQuRlsPU



Finding the Vapor Pressure of a Solution (Ionic-Nonvolatile Solute): https://youtu.be/sRBaRXsql9s

Elevation of the Boiling Point of a Solvent

As described in the chapter on liquids and solids, the *boiling point* of a liquid is the temperature at which its vapor pressure is equal to ambient atmospheric pressure. Since the vapor pressure of a solution is lowered due to the presence of nonvolatile solutes, it stands to reason that the solution's boiling point will subsequently be increased. Compared to pure solvent, a solution, therefore, will require a higher temperature to achieve any given vapor pressure, including one equivalent to that of the surrounding atmosphere. The increase in boiling point observed when nonvolatile solute is dissolved in a solvent, ΔT_b, is called boiling point elevation and is directly proportional to the molal concentration of solute species:

$$\Delta T_b = K_b m \tag{13.5.5}$$

where

- K_b is the boiling point elevation constant, or the *ebullioscopic constant* and
- m is the molal concentration (molality) of all solute species.

Boiling point elevation constants are characteristic properties that depend on the identity of the solvent. Values of K_b for several solvents are listed in Table **13.5.1**.

Table **13.5.1**: Boiling Point Elevation and Freezing Point Depression Constants for Several Solvents

Solvent	Boiling Point (°C at 1 atm)	K_b (Cm^{-1})	Freezing Point (°C at 1 atm)	K_f (Cm^{-1})
water	100.0	0.512	0.0	1.86
hydrogen acetate	118.1	3.07	16.6	3.9
benzene	80.1	2.53	5.5	5.12
chloroform	61.26	3.63	−63.5	4.68
nitrobenzene	210.9	5.24	5.67	8.1


The extent to which the vapor pressure of a solvent is lowered and the boiling point is elevated depends on the total number of solute particles present in a given amount of solvent, not on the mass or size or chemical identities of the particles. A 1 *m* aqueous solution of sucrose (342 g/mol) and a 1 *m* aqueous solution of ethylene glycol (62 g/mol) will exhibit the same boiling point because each solution has one mole of solute particles (molecules) per kilogram of solvent.

Example 13.5.2: Calculating the Boiling Point of a Solution

What is the boiling point of a 0.33 *m* solution of a nonvolatile solute in benzene?

Solution

Use the equation relating boiling point elevation to solute molality to solve this problem in two steps.



1. *Calculate the change in boiling point.*

$$\Delta T_b = K_b m = 2.53\ °C\ m^{-1} \times 0.33\ m = 0.83\ °C$$

2. *Add the boiling point elevation to the pure solvent's boiling point.*

$$\text{Boiling temperature} = 80.1\ °C + 0.83\ °C = 80.9\ °C$$

Exercise 13.5.2

What is the boiling point of the antifreeze described in Example 13.5.4?

Answer


109.2 °C

Example 13.5.3: The Boiling Point of an Iodine Solution

Find the boiling point of a solution of 92.1 g of iodine, I_2, in 800.0 g of chloroform, $CHCl_3$, assuming that the iodine is nonvolatile and that the solution is ideal.

Solution

We can solve this problem using four steps.



1. *Convert from grams to moles of* $\mathrm{I_2}$ *using the molar mass of* $\mathrm{I_2}$ *in the unit conversion factor.*

Result: 0.363 mol

Determine the molality of the solution from the number of moles of solute and the mass of solvent, in kilograms.

Result: 0.454 *m*

Use the direct proportionality between the change in boiling point and molal concentration to determine how much the boiling point changes.

Result: 1.65 °C

Determine the new boiling point from the boiling point of the pure solvent and the change.

Result: 62.91 °C

Check each result as a self-assessment.

? Exercise 13.5.3: glycerin:Water Solution

What is the boiling point of a solution of 1.0 g of glycerin, $\mathrm{C_3H_5(OH)_3}$, in 47.8 g of water? Assume an ideal solution.

Answer

100.12 °C



Boiling Point Elevation and Freezing Point Depression: https://youtu.be/0MZm1Ay6LhU

Distillation of Solutions

Distillation is a technique for separating the components of mixtures that is widely applied in both in the laboratory and in industrial settings. It is used to refine petroleum, to isolate fermentation products, and to purify water. This separation technique involves the controlled heating of a sample mixture to selectively vaporize, condense, and collect one or more components of interest. A typical apparatus for laboratory-scale distillations is shown in Figure **13.5.2**.




Figure **13.5.2**: A typical laboratory distillation unit is shown in (a) a photograph and (b) a schematic diagram of the components. (credit a: modification of work by "Rifleman82"/Wikimedia commons; credit b: modification of work by "Slashme"/Wikimedia Commons)

Oil refineries use large-scale *fractional distillation* to separate the components of crude oil. The crude oil is heated to high temperatures at the base of a tall *fractionating column*, vaporizing many of the components that rise within the column. As vaporized components reach adequately cool zones during their ascent, they condense and are collected. The collected liquids are simpler mixtures of hydrocarbons and other petroleum compounds that are of appropriate composition for various applications (e.g., diesel fuel, kerosene, gasoline), as depicted in Figure **13.5.3**.




Figure **13.5.3**: Crude oil is a complex mixture that is separated by large-scale fractional distillation to isolate various simpler mixtures.

Depression of the Freezing Point of a Solvent

Solutions freeze at lower temperatures than pure liquids. This phenomenon is exploited in "de-icing" schemes that use salt (Figure **13.5.4**), calcium chloride, or urea to melt ice on roads and sidewalks, and in the use of ethylene glycol as an "antifreeze" in automobile radiators. Seawater freezes at a lower temperature than fresh water, and so the Arctic and Antarctic oceans remain unfrozen even at temperatures below 0 °C (as do the body fluids of fish and other cold-blooded sea animals that live in these oceans).



Figure 13.5.4: Rock salt (NaCl), calcium chloride ($CaCl_2$), or a mixture of the two are used to melt ice. (credit: modification of work by Eddie Welker)

The decrease in freezing point of a dilute solution compared to that of the pure solvent, ΔT_f, is called the freezing point depression and is directly proportional to the molal concentration of the solute

$$\Delta T_f = K_f m \tag{13.5.6}$$

where

- m is the *molal* concentration of the solute in the solvent and
- K_f is called the freezing point depression constant (or *cryoscopic constant*).


Just as for boiling point elevation constants, these are characteristic properties whose values depend on the chemical identity of the solvent. Values of K_f for several solvents are listed in Table 13.5.1.

Example 13.5.4: Calculation of the Freezing Point of a Solution

What is the freezing point of the 0.33 *m* solution of a nonvolatile nonelectrolyte solute in benzene described in Example 13.5.4?

Solution

Use the equation relating freezing point depression to solute molality to solve this problem in two steps.



1. *Calculate the change in freezing point.*

$$\Delta T_f = K_f m = 5.12\ °C\ m^{-1} \times 0.33\ m = 1.7\ °C \tag{13.5.7}$$

2. *Subtract the freezing point change observed from the pure solvent's freezing point.*

$$\text{Freezing Temperature} = 5.5\ °C - 1.7\ °C = 3.8\ °C \tag{13.5.8}$$

Exercise 13.5.4

What is the freezing point of a 1.85 *m* solution of a nonvolatile nonelectrolyte solute in nitrobenzene?

Answer

−9.3 °C

Colligative Properties and De-Icing

Sodium chloride and its group 2 analogs calcium and magnesium chloride are often used to de-ice roadways and sidewalks, due to the fact that a solution of any one of these salts will have a freezing point lower than 0 °C, the freezing point of pure water. The group 2 metal salts are frequently mixed with the cheaper and more readily available sodium chloride ("rock salt")

for use on roads, since they tend to be somewhat less corrosive than the NaCl, and they provide a larger depression of the freezing point, since they dissociate to yield three particles per formula unit, rather than two particles like the sodium chloride.

Because these ionic compounds tend to hasten the corrosion of metal, they would not be a wise choice to use in antifreeze for the radiator in your car or to de-ice a plane prior to takeoff. For these applications, covalent compounds, such as ethylene or propylene glycol, are often used. The glycols used in radiator fluid not only lower the freezing point of the liquid, but they elevate the boiling point, making the fluid useful in both winter and summer. Heated glycols are often sprayed onto the surface of airplanes prior to takeoff in inclement weather in the winter to remove ice that has already formed and prevent the formation of more ice, which would be particularly dangerous if formed on the control surfaces of the aircraft (Video **13.5.1**).



Video* 13.5.1*: *Freezing point depression is exploited to remove ice from the control surfaces of aircraft.*

Phase Diagram for an Aqueous Solution of a Nonelectrolyte

The colligative effects on vapor pressure, boiling point, and freezing point described in the previous section are conveniently summarized by comparing the phase diagrams for a pure liquid and a solution derived from that liquid. Phase diagrams for water and an aqueous solution are shown in Figure **13.5.5**.




Figure **13.5.5**: These phase diagrams show water (solid curves) and an aqueous solution of nonelectrolyte (dashed curves).

The liquid-vapor curve for the solution is located *beneath* the corresponding curve for the solvent, depicting the vapor pressure *lowering*, ΔP, that results from the dissolution of nonvolatile solute. Consequently, at any given pressure, the solution's boiling point is observed at a higher temperature than that for the pure solvent, reflecting the boiling point elevation, ΔT_b, associated with the presence of nonvolatile solute. The solid-liquid curve for the solution is displaced left of that for the pure solvent, representing the freezing point depression, ΔTf, that accompanies solution formation. Finally, notice that the solid-gas curves for the solvent and its solution are identical. This is the case for many solutions comprising liquid solvents and nonvolatile solutes. Just as for vaporization, when a solution of this sort is frozen, it is actually just the *solvent* molecules that undergo the liquid-to-solid transition, forming pure solid solvent that excludes solute species. The solid and gaseous phases, therefore, are composed solvent only, and so transitions between these phases are not subject to colligative effects.

Osmosis and Osmotic Pressure of Solutions

A number of natural and synthetic materials exhibit *selective permeation*, meaning that only molecules or ions of a certain size, shape, polarity, charge, and so forth, are capable of passing through (permeating) the material. Biological cell membranes provide elegant examples of selective permeation in nature, while dialysis tubing used to remove metabolic wastes from blood is a more simplistic technological example. Regardless of how they may be fabricated, these materials are generally referred to as semipermeable membranes.

Consider the apparatus illustrated in Figure **13.5.6**, in which samples of pure solvent and a solution are separated by a membrane that only solvent molecules may permeate. Solvent molecules will diffuse across the membrane in both directions. Since the concentration of *solvent* is greater in the pure solvent than the solution, these molecules will diffuse from the solvent side of the membrane to the solution side at a faster rate than they will in the reverse direction. The result is a net transfer of solvent molecules from the pure solvent to the solution. Diffusion-driven transfer of solvent molecules through a semipermeable membrane is a process known as osmosis.




Figure **13.5.6**: Osmosis results in the transfer of solvent molecules from a sample of low (or zero) solute concentration to a sample of higher solute concentration.

When osmosis is carried out in an apparatus like that shown in Figure **13.5.6**, the volume of the solution increases as it becomes diluted by accumulation of solvent. This causes the level of the solution to rise, increasing its hydrostatic pressure (due to the weight of the column of solution in the tube) and resulting in a faster transfer of solvent molecules back to the pure solvent side. When the pressure reaches a value that yields a reverse solvent transfer rate equal to the osmosis rate, bulk transfer of solvent ceases. This pressure is called the osmotic pressure (Π) of the solution. The osmotic pressure of a dilute solution is related to its solute molarity, M, and absolute temperature, T, according to the equation

$$\Pi = MRT \tag{13.5.9}$$

where R is the universal gas constant.

Example 13.5.5: Calculation of Osmotic Pressure

What is the osmotic pressure (atm) of a 0.30 M solution of glucose in water that is used for intravenous infusion at body temperature, 37 °C?

Solution

We can find the osmotic pressure, Π, using Equation 13.5.9, where T is on the Kelvin scale (310 K) and the value of R is expressed in appropriate units (0.08206 L atm/mol K).

$$\begin{aligned}\Pi &= MRT \\ &= 0.03\ \text{mol/L} \times 0.08206\ \text{L atm/mol K} \times 310\ \text{K} \\ &= 7.6\ \text{atm}\end{aligned}$$

? Exercise 13.5.5

What is the osmotic pressure (atm) a solution with a volume of 0.750 L that contains 5.0 g of methanol, CH_3OH, in water at 37 °C?

Answer

5.3 atm

If a solution is placed in an apparatus like the one shown in Figure **13.5.7**, applying pressure greater than the osmotic pressure of the solution reverses the osmosis and pushes solvent molecules from the solution into the pure solvent. This technique of reverse osmosis is used for large-scale desalination of seawater and on smaller scales to produce high-purity tap water for drinking.




Figure **13.5.7**: Applying a pressure greater than the osmotic pressure of a solution will reverse osmosis. Solvent molecules from the solution are pushed into the pure solvent.

Examples of osmosis are evident in many biological systems because cells are surrounded by semipermeable membranes. Carrots and celery that have become limp because they have lost water can be made crisp again by placing them in water. Water moves into the carrot or celery cells by osmosis. A cucumber placed in a concentrated salt solution loses water by osmosis and absorbs some salt to become a pickle. Osmosis can also affect animal cells. Solute concentrations are particularly important when solutions are injected into the body. Solutes in body cell fluids and blood serum give these solutions an osmotic pressure of approximately 7.7 atm. Solutions injected into the body must have the same osmotic pressure as blood serum; that is, they should be isotonic with blood serum. If a less concentrated solution, a hypotonic solution, is injected in sufficient quantity to dilute the blood serum, water from the diluted serum passes into the blood cells by osmosis, causing the cells to expand and rupture. This process is called hemolysis. When a more concentrated solution, a hypertonic solution, is injected, the cells lose water to the more concentrated solution, shrivel, and possibly die in a process called *crenation* (Figure 11.5.8).




Figure **13.5.8**: Red blood cell membranes are water permeable and will (a) swell and possibly rupture in a hypotonic solution; (b) maintain normal volume and shape in an isotonic solution; and (c) shrivel and possibly die in a hypertonic solution. (credit a/b/c: modifications of work by "LadyofHats"/Wikimedia commons)



Osmotic Pressure: https://youtu.be/uYQxI4mi3DA

Determination of Molar Masses


Osmotic pressure and changes in freezing point, boiling point, and vapor pressure are directly proportional to the concentration of solute present. Consequently, we can use a measurement of one of these properties to determine the molar mass of the solute from the measurements.

Example **13.5.6**: Determining Molar Mass from Freezing Point Depression

A solution of 4.00 g of a nonelectrolyte dissolved in 55.0 g of benzene is found to freeze at 2.32 °C. What is the molar mass of this compound?

Solution

We can solve this problem using the following steps.



1. *Determine the change in freezing point from the observed freezing point and the freezing point of pure benzene* (Table 11.5.1).

$$\Delta T_f = 5.5\ °C - 2.32\ °C = 3.2\ °C$$

1. *Determine the molal concentration from K_f, the freezing point depression constant for benzene* (Table 11.5.1), *and* ΔT_f.

\(ΔT_\ce{f}=K_\ce{f}m\)

$$m = \frac{\Delta T_f}{K_f} = \frac{3.2\ °C}{5.12\ °C m^{-1}} = 0.63\ m$$

1. *Determine the number of moles of compound in the solution from the molal concentration and the mass of solvent used to make the solution.*

$$\text{Moles of solute} = \frac{0.62\ \text{mol solute}}{1.00\ \cancel{\text{kg solvent}}} \times 0.0550\ \cancel{\text{kg solvent}} = 0.035\ \text{mol}$$

2. *Determine the molar mass from the mass of the solute and the number of moles in that mass.*

\(\mathrm{Molar\: mass=\dfrac{4.00\:g}{0.034\:mol}=1.2×10^2\:g/mol}\)

? Exercise 13.5.6

A solution of 35.7 g of a nonelectrolyte in 220.0 g of chloroform has a boiling point of 64.5 °C. What is the molar mass of this compound?

Answer


1.8×10^2 g/mol

✔ Example 13.5.7: Determination of a Molar Mass from Osmotic Pressure

A 0.500 L sample of an aqueous solution containing 10.0 g of hemoglobin has an osmotic pressure of 5.9 torr at 22 °C. What is the molar mass of hemoglobin?

Solution

Here is one set of steps that can be used to solve the problem:



1. $$\Pi = \frac{5.9 \text{ torr} \times 1 \text{ atm}}{760 \text{ torr}} = 7.8 \times 10^{-3} \text{ atm} \tag{13.5.10}$$

$$\Pi = MRT \tag{13.5.11}$$

$$M = \frac{\Pi}{RT} = \frac{7.8 \times 10^{-3} \text{ atm}}{(0.08206 \text{ L atm/mol K})(295 \text{ K})} = 3.2 \times 10^{-4} \text{ M}$$

1. $\text{moles of hemoglobin} = \frac{3.2 \times 10^{-4} \text{ mol}}{1 \cancel{\text{ L solution}}} \times 0.500 \cancel{\text{ L solution}} = 1.6 \times 10^{-4} \text{ mol}$
2. *Determine the molar mass from the mass of hemoglobin and the number of moles in that mass.*

$$\text{molar mass} = \frac{10.0 \text{ g}}{1.6 \times 10^{-4} \text{ mol}} = 6.2 \times 10^{4} \text{ g/mol}$$

? Exercise 13.5.7

What is the molar mass of a protein if a solution of 0.02 g of the protein in 25.0 mL of solution has an osmotic pressure of 0.56 torr at 25 °C?

Answer

2.7×10^4 g/mol



Finding the Molecular Weight of an Unknown using Colligative Properties: https://youtu.be/faSk2REYy74

Colligative Properties of Electrolytes

As noted previously in this module, the colligative properties of a solution depend only on the number, not on the kind, of solute species dissolved. For example, 1 mole of any nonelectrolyte dissolved in 1 kilogram of solvent produces the same lowering of the freezing point as does 1 mole of any other nonelectrolyte. However, 1 mole of sodium chloride (an electrolyte) forms *2 moles* of ions when dissolved in solution. Each individual ion produces the same effect on the freezing point as a single molecule does.

✓ Example 13.5.8: The Freezing Point of a Solution of an Electrolyte

The concentration of ions in seawater is approximately the same as that in a solution containing 4.2 g of NaCl dissolved in 125 g of water. Assume that each of the ions in the NaCl solution has the same effect on the freezing point of water as a nonelectrolyte molecule, and determine the freezing temperature the solution (which is approximately equal to the freezing temperature of seawater).

Solution

We can solve this problem using the following series of steps.

- Convert from grams to moles of NaCl using the molar mass of NaCl in the unit conversion factor. Result: 0.072 mol NaCl

- Determine the number of moles of ions present in the solution using the number of moles of ions in 1 mole of NaCl as the conversion factor (2 mol ions/1 mol NaCl). Result: 0.14 mol ions
- Determine the molality of the ions in the solution from the number of moles of ions and the mass of solvent, in kilograms. Result: 1.1 m
- Use the direct proportionality between the change in freezing point and molal concentration to determine how much the freezing point changes. Result: 2.0 °C
- Determine the new freezing point from the freezing point of the pure solvent and the change. Result: −2.0 °C

Check each result as a self-assessment.

? Exercise 13.5.8

Assume that each of the ions in calcium chloride, $CaCl_2$, has the same effect on the freezing point of water as a nonelectrolyte molecule. Calculate the freezing point of a solution of 0.724 g of $CaCl_2$ in 175 g of water.

Answer

−0.208 °C

Assuming complete dissociation, a 1.0 *m* aqueous solution of NaCl contains 2.0 mole of ions (1.0 mol Na^+ and 1.0 mol Cl^-) per each kilogram of water, and its freezing point depression is expected to be

$$\Delta T_f = 2.0 \text{ mol ions/kg water} \times 1.86 \text{ °C kg water/mol ion} = 3.7 \text{ °C}. \tag{13.5.12}$$

When this solution is actually prepared and its freezing point depression measured, however, a value of 3.4 °C is obtained. Similar discrepancies are observed for other ionic compounds, and the differences between the measured and expected colligative property values typically become more significant as solute concentrations increase. These observations suggest that the ions of sodium chloride (and other strong electrolytes) are not completely dissociated in solution.

To account for this and avoid the errors accompanying the assumption of total dissociation, an experimentally measured parameter named in honor of Nobel Prize-winning German chemist Jacobus Henricus van't Hoff is used. The van't Hoff factor (*i*) is defined as the ratio of solute particles in solution to the number of formula units dissolved:

$$i = \frac{\text{moles of particles in solution}}{\text{moles of formula units dissolved}} \tag{13.5.13}$$

Values for measured van't Hoff factors for several solutes, along with predicted values assuming complete dissociation, are shown in Table **13.5.2**.

Table **13.5.2**: Expected and Observed van't Hoff Factors for Several 0.050 m Aqueous Electrolyte Solutions

Electrolyte	Particles in Solution	*i* (Predicted)	*i* (Measured)
HCl	H^+, Cl^-	2	1.9
NaCl	Na^+, Cl^-	2	1.9
$MgSO_4$	Mg^{2+}, SO_4^{2-}	2	1.3
$MgCl_2$	Mg^{2+}, $2Cl^-$	3	2.7
$FeCl_3$	Fe^{3+}, $3Cl^-$	4	3.4
glucose (a non-electrolyte)	$C_{12}H_{22}O_{11}$	1	1.0

In 1923, the chemists Peter Debye and Erich Hückel proposed a theory to explain the apparent incomplete ionization of strong electrolytes. They suggested that although interionic attraction in an aqueous solution is very greatly reduced by solvation of the ions and the insulating action of the polar solvent, it is not completely nullified. The residual attractions prevent the ions from behaving as totally independent particles (Figure **13.5.9**). In some cases, a positive and negative ion may actually touch, giving a

solvated unit called an ion pair. Thus, the activity, or the effective concentration, of any particular kind of ion is less than that indicated by the actual concentration. Ions become more and more widely separated the more dilute the solution, and the residual interionic attractions become less and less. Thus, in extremely dilute solutions, the effective concentrations of the ions (their activities) are essentially equal to the actual concentrations. Note that the van't Hoff factors for the electrolytes in Table **13.5.2** are for 0.05 *m* solutions, at which concentration the value of *i* for NaCl is 1.9, as opposed to an ideal value of 2.




Figure **13.5.9**: Ions become more and more widely separated the more dilute the solution, and the residual interionic attractions become less.

Summary

Properties of a solution that depend only on the concentration of solute particles are called colligative properties. They include changes in the vapor pressure, boiling point, and freezing point of the solvent in the solution. The magnitudes of these properties depend only on the total concentration of solute particles in solution, not on the type of particles. The total concentration of solute particles in a solution also determines its osmotic pressure. This is the pressure that must be applied to the solution to prevent diffusion of molecules of pure solvent through a semipermeable membrane into the solution. Ionic compounds may not completely dissociate in solution due to activity effects, in which case observed colligative effects may be less than predicted.

Key Equations

- $(P_A = X_A P_A^\circ)$
- $P_{solution} = \sum_i P_i = \sum_i X_i P_i^\circ$
- $P_{solution} = X_{solvent} P_{solvent}^\circ$
- $\Delta T_b = K_b m$
- $\Delta T_f = K_f m$
- $\Pi = MRT$

Footnotes

1. A nonelectrolyte shown for comparison.

Glossary

boiling point elevation

elevation of the boiling point of a liquid by addition of a solute

boiling point elevation constant

the proportionality constant in the equation relating boiling point elevation to solute molality; also known as the ebullioscopic constant

colligative property

property of a solution that depends only on the concentration of a solute species

crenation
process whereby biological cells become shriveled due to loss of water by osmosis

freezing point depression
lowering of the freezing point of a liquid by addition of a solute

freezing point depression constant
(also, cryoscopic constant) proportionality constant in the equation relating freezing point depression to solute molality

hemolysis
rupture of red blood cells due to the accumulation of excess water by osmosis

hypertonic
of greater osmotic pressure

hypotonic
of less osmotic pressure

ion pair
solvated anion/cation pair held together by moderate electrostatic attraction

isotonic
of equal osmotic pressure

Osmosis
diffusion of solvent molecules through a semipermeable membrane

osmotic pressure (*Π*)
opposing pressure required to prevent bulk transfer of solvent molecules through a semipermeable membrane

Raoult's law
the partial pressure exerted by a solution component is equal to the product of the component's mole fraction in the solution and its equilibrium vapor pressure in the pure state

semipermeable membrane
a membrane that selectively permits passage of certain ions or molecules

van't Hoff factor (*i*)
the ratio of the number of moles of particles in a solution to the number of moles of formula units dissolved in the solution

---

13.5: Colligative Properties is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **11.5: Colligative Properties** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

13.6: Colloids

Learning Objectives

- Describe the composition and properties of colloidal dispersions
- List and explain several technological applications of colloids

As a child, you may have made suspensions such as mixtures of mud and water, flour and water, or a suspension of solid pigments in water, known as tempera paint. These suspensions are heterogeneous mixtures composed of relatively large particles that are visible (or that can be seen with a magnifying glass). They are cloudy, and the suspended particles settle out after mixing. On the other hand, when we make a solution, we prepare a homogeneous mixture in which no settling occurs and in which the dissolved species are molecules or ions. Solutions exhibit completely different behavior from suspensions. A solution may be colored, but it is transparent, the molecules or ions are invisible, and they do not settle out on standing. A group of mixtures called colloids (or colloidal dispersions) exhibit properties intermediate between those of suspensions and solutions (Figure **13.6.1**). The particles in a colloid are larger than most simple molecules; however, colloidal particles are small enough that they do not settle out upon standing.




Figure **13.6.1**: (a) A solution is a homogeneous mixture that appears clear, such as the saltwater in this aquarium. (b) In a colloid, such as milk, the particles are much larger but remain dispersed and do not settle. (c) A suspension, such as mud, is a heterogeneous mixture of suspended particles that appears cloudy and in which the particles can settle. (credit a photo: modification of work by Adam Wimsatt; credit b photo: modification of work by Melissa Wiese; credit c photo: modification of work by Peter Burgess)

The particles in a colloid are large enough to scatter light, a phenomenon called the Tyndall effect. This can make colloidal mixtures appear cloudy or opaque, such as the searchlight beams shown in Figure **13.6.2**. Clouds are colloidal mixtures. They are composed of water droplets that are much larger than molecules, but that are small enough that they do not settle out.



Figure **13.6.2**: The paths of searchlight beams are made visible when light is scattered by colloidal-size particles in the air (fog, smoke, etc.). (credit: “Bahman”/Wikimedia Commons)

The term “colloid”—from the Greek words *kolla*, meaning “glue,” and *eidos*, meaning “like”—was first used in 1861 by Thomas Graham to classify mixtures such as starch in water and gelatin. Many colloidal particles are aggregates of hundreds or thousands of molecules, but others (such as proteins and polymer molecules) consist of a single extremely large molecule. The protein and synthetic polymer molecules that form colloids may have molecular masses ranging from a few thousand to many million atomic mass units.

Analogous to the identification of solution components as “solute” and “solvent,” the components of a colloid are likewise classified according to their relative amounts. The particulate component typically present in a relatively minor amount is called the dispersed phase and the substance or solution throughout which the particulate is dispersed is called the dispersion medium. Colloids may involve virtually any combination of physical states (gas in liquid, liquid in solid, solid in gas, etc.), as illustrated by the examples of colloidal systems given in Table **13.6.1**.

Table **13.6.1**: Examples of Colloidal Systems

Dispersed Phase	Dispersion Medium	Common Examples	Name
solid	gas	smoke, dust	—
solid	liquid	starch in water, some inks, paints, milk of magnesia	sol
solid	solid	some colored gems, some alloys	—
liquid	gas	clouds, fogs, mists, sprays	aerosol
liquid	liquid	milk, mayonnaise, butter	emulsion
liquid	solid	jellies, gels, pearl, opal (H_2O in SiO_2)	gel
gas	liquid	foams, whipped cream, beaten egg whites	foam
gas	solid	pumice, floating soaps	—

Preparation of Colloidal Systems

We can prepare a colloidal system by producing particles of colloidal dimensions and distributing these particles throughout a dispersion medium. Particles of colloidal size are formed by two methods:

1. Dispersion methods: that is, by breaking down larger particles. For example, paint pigments are produced by dispersing large particles by grinding in special mills.
2. Condensation methods: that is, growth from smaller units, such as molecules or ions. For example, clouds form when water molecules condense and form very small droplets.

A few solid substances, when brought into contact with water, disperse spontaneously and form colloidal systems. Gelatin, glue, starch, and dehydrated milk powder behave in this manner. The particles are already of colloidal size; the water simply disperses them. Powdered milk particles of colloidal size are produced by dehydrating milk spray. Some atomizers produce colloidal dispersions of a liquid in air.

We can prepare an emulsion by shaking together or blending two immiscible liquids. This breaks one liquid into droplets of colloidal size, which then disperse throughout the other liquid. Oil spills in the ocean may be difficult to clean up, partly because wave action can cause the oil and water to form an emulsion. In many emulsions, however, the dispersed phase tends to coalesce, form large drops, and separate. Therefore, emulsions are usually stabilized by an emulsifying agent, a substance that inhibits the coalescence of the dispersed liquid. For example, a little soap will stabilize an emulsion of kerosene in water. Milk is an emulsion of butterfat in water, with the protein casein as the emulsifying agent. Mayonnaise is an emulsion of oil in vinegar, with egg yolk components as the emulsifying agents.

Condensation methods form colloidal particles by aggregation of molecules or ions. If the particles grow beyond the colloidal size range, drops or precipitates form, and no colloidal system results. Clouds form when water molecules aggregate and form colloid-sized particles. If these water particles coalesce to form adequately large water drops of liquid water or crystals of solid water, they settle from the sky as rain, sleet, or snow. Many condensation methods involve chemical reactions. We can prepare a red colloidal suspension of iron(III) hydroxide by mixing a concentrated solution of iron(III) chloride with hot water:

$$\mathrm{Fe^{3+}_{(aq)} + 3Cl^-_{(aq)} + 6H_2O_{(l)} \longrightarrow Fe(OH)_{3(s)} + H_3O^+_{(aq)} + 3Cl^-_{(aq)}} \tag{13.6.1}$$

A colloidal gold sol results from the reduction of a very dilute solution of gold(III) chloride by a reducing agent such as formaldehyde, tin(II) chloride, or iron(II) sulfate:

$$\mathrm{Au^{3+} + 3\,e^- \rightarrow Au} \tag{13.6.2}$$

Some gold sols prepared in 1857 are still intact (the particles have not coalesced and settled), illustrating the long-term stability of many colloids.

Soaps and Detergents

Pioneers made soap by boiling fats with a strongly basic solution made by leaching potassium carbonate, $\mathrm{K_2CO_3}$, from wood ashes with hot water. Animal fats contain polyesters of fatty acids (long-chain carboxylic acids). When animal fats are treated with a base like potassium carbonate or sodium hydroxide, glycerol and salts of fatty acids such as palmitic, oleic, and stearic acid are formed. The salts of fatty acids are called soaps. The sodium salt of stearic acid, sodium stearate, has the formula $\mathrm{C_{17}H_{35}CO_2Na}$ and contains an uncharged nonpolar hydrocarbon chain, the $\mathrm{C_{17}H_{35}-}$ unit, and an ionic carboxylate group, the $\mathrm{-CO_2^-}$ unit (Figure 13.6.3).




Figure 13.6.3: Soaps contain a nonpolar hydrocarbon end (blue) and an ionic end (red). The ionic end is a carboxylate group. The length of the hydrocarbon end can vary from soap to soap.

*Deterg*ents (soap substitutes) also contain nonpolar hydrocarbon chains, such as $\mathrm{C_{12}H_{25}}$—, and an ionic group, such as a sulfate —$\mathrm{OSO_3^-}$, or a sulfonate —$\mathrm{SO_3^-}$ (Figure 13.6.4). Soaps form insoluble calcium and magnesium compounds in hard water; detergents form water-soluble products—a definite advantage for detergents.




Figure **13.6.4**: Detergents contain a nonpolar hydrocarbon end (blue) and an ionic end (red). The ionic end can be either a sulfate or a sulfonate. The length of the hydrocarbon end can vary from detergent to detergent.

The cleaning action of soaps and detergents can be explained in terms of the structures of the molecules involved. The hydrocarbon (nonpolar) end of a soap or detergent molecule dissolves in, or is attracted to, nonpolar substances such as oil, grease, or dirt particles. The ionic end is attracted by water (polar), illustrated in Figure **13.6.5**. As a result, the soap or detergent molecules become oriented at the interface between the dirt particles and the water so they act as a kind of bridge between two different kinds of matter, nonpolar and polar. Molecules such as this are termed amphiphilic since they have both a hydrophobic ("water-fearing") part and a hydrophilic ("water-loving") part. As a consequence, dirt particles become suspended as colloidal particles and are readily washed away.




Figure **13.6.5**: This diagrammatic cross section of an emulsified drop of oil in water shows how soap or detergent acts as an emulsifier.

Deepwater Horizon Oil Spill

The blowout of the Deepwater Horizon oil drilling rig on April 20, 2010, in the Gulf of Mexico near Mississippi began the largest marine oil spill in the history of the petroleum. In the 87 days following the blowout, an estimated 4.9 million barrels (210 million gallons) of oil flowed from the ruptured well 5000 feet below the water's surface. The well was finally declared sealed on September 19, 2010.

Crude oil is immiscible with and less dense than water, so the spilled oil rose to the surface of the water. Floating booms, skimmer ships, and controlled burns were used to remove oil from the water's surface in an attempt to protect beaches and wetlands along the Gulf coast. In addition to removal of the oil, attempts were also made to lessen its environmental impact by rendering it "soluble" (in the loose sense of the term) and thus allowing it to be diluted to hopefully less harmful levels by the vast volume of ocean water. This approach used 1.84 million gallons of the oil dispersant Corexit 9527, most of which was injected underwater at the site of the leak, with small amounts being sprayed on top of the spill. Corexit 9527 contains 2-butoxyethanol ($C_6H_{14}O_2$), an amphiphilic molecule whose polar and nonpolar ends are useful for emulsifying oil into small droplets, increasing the surface area of the oil and making it more available to marine bacteria for digestion (Figure **13.6.6**). While this approach avoids many of the immediate hazards that bulk oil poses to marine and coastal ecosystems, it introduces the possibility of long-term effects resulting from the introduction of the complex and potential toxic components of petroleum into the ocean's food chain. A number of organizations are involved in monitoring the extended impact of this oil spill, including the National Oceanic and Atmospheric Administration.



Figure 13.6.6: (a) This NASA satellite image shows the oil slick from the Deepwater Horizon spill. (b) A US Air Force plane sprays Corexit, a dispersant. (c) The molecular structure of 2-butoxyethanol is shown. (credit a: modification of work by "NASA, FT2, demis.nl"/Wikimedia Commons; credit b: modification of work by "NASA/MODIS Rapid Response Team"/Wikimedia Commons)

Electrical Properties of Colloidal Particles

Dispersed colloidal particles are often electrically charged. A colloidal particle of iron(III) hydroxide, for example, does not contain enough hydroxide ions to compensate exactly for the positive charges on the iron(III) ions. Thus, each individual colloidal particle bears a positive charge, and the colloidal dispersion consists of charged colloidal particles and some free hydroxide ions, which keep the dispersion electrically neutral. Most metal hydroxide colloids have positive charges, whereas most metals and metal sulfides form negatively charged dispersions. All colloidal particles in any one system have charges of the same sign. This helps keep them dispersed because particles containing like charges repel each other.

We can take advantage of the charge on colloidal particles to remove them from a variety of mixtures. If we place a colloidal dispersion in a container with charged electrodes, positively charged particles, such as iron(III) hydroxide particles, would move to the negative electrode. There, the colloidal particles lose their charge and coagulate as a precipitate.




Figure 13.6.7: In a Cottrell precipitator, positively and negatively charged particles are attracted to highly charged electrodes, where they are neutralized and deposited as dust.

The carbon and dust particles in smoke are often colloidally dispersed and electrically charged. The charged particles are attracted to highly charged electrodes, where they are neutralized and deposited as dust (Figure 13.6.7. This is one of the important methods used to clean up the smoke from a variety of industrial processes. The process is also important in the recovery of valuable products from the smoke and flue dust of smelters, furnaces, and kilns. There are also ionic air filters designed for home use to improve indoor air quality.

Gels

When we make gelatin, such as Jell-O, we are making a type of colloid (Figure 13.6.8). Gelatin sets on cooling because the hot aqueous mixture of gelatin coagulates as it cools and the whole mass, including the liquid, sets to an extremely viscous body

known as a gel, a colloid in which the dispersing medium is a solid and the dispersed phase is a liquid. It appears that the fibers of the dispersing medium form a complex three-dimensional network, the interstices being filled with the liquid medium or a dilute solution of the dispersing medium. Because the formation of a gel is accompanied by the taking up of water or some other solvent, the gel is said to be hydrated or solvated.




Figure **13.6.8**: Gelatin desserts are colloids in which an aqueous solution of sweeteners and flavors is dispersed throughout a medium of solid proteins. (credit photo: modification of work by Steven Depolo).

Pectin, a carbohydrate from fruit juices, is a gel-forming substance important in jelly making. Silica gel, a colloidal dispersion of hydrated silicon dioxide, is formed when dilute hydrochloric acid is added to a dilute solution of sodium silicate. Canned Heat is a gel made by mixing alcohol and a saturated aqueous solution of calcium acetate.

Summary

Colloids are mixtures in which one or more substances are dispersed as relatively large solid particles or liquid droplets throughout a solid, liquid, or gaseous medium. The particles of a colloid remain dispersed and do not settle due to gravity, and they are often electrically charged. Colloids are widespread in nature and are involved in many technological applications.

Glossary

amphiphilic
molecules possessing both hydrophobic (nonpolar) and a hydrophilic (polar) parts

colloid
(also, colloidal dispersion) mixture in which relatively large solid or liquid particles are dispersed uniformly throughout a gas, liquid, or solid

dispersion medium
solid, liquid, or gas in which colloidal particles are dispersed

dispersed phase
substance present as relatively large solid or liquid particles in a colloid

emulsifying agent
amphiphilic substance used to stabilize the particles of some emulsions

emulsion
colloid formed from immiscible liquids

gel

colloidal dispersion of a liquid in a solid

Tyndall effect

scattering of visible light by a colloidal dispersion

13.6: Colloids is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **11.6: Colloids** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/chemistry-2e.

13.7: End of Chapter Problems

1. How do solutions differ from compounds? From other mixtures?

Answer

A solution can vary in composition, while a compound cannot vary in composition. Solutions are homogeneous at the molecular level, while other mixtures are heterogeneous.

2. Which of the principal characteristics of solutions can we see in the solutions of $\mathbf{K_2Cr_2O_7}$ shown in



Figure: When potassium dichromate ($\mathbf{K_2Cr_2O_7}$) is mixed with water, it forms a homogeneous orange solution. (credit: modification of work by Mark Ott)

Answer

The solutions are the same throughout (the color is constant throughout), and the composition of a solution of $K_2Cr_2O_7$ in water can vary.

3. When KNO_3 is dissolved in water, the resulting solution is significantly colder than the water was originally.
   a. Is the dissolution of KNO_3 an endothermic or an exothermic process?
   b. What conclusions can you draw about the intermolecular attractions involved in the process?
   c. Is the resulting solution an ideal solution?

Answer

(a) The process is endothermic as the solution is consuming heat. (b) Attraction between the K^+ and $\mathbf{NO_3^-}$ ions is stronger than between the ions and water molecules (the ion-ion interactions have a lower, more negative energy). Therefore, the dissolution process increases the energy of the molecular interactions, and it consumes the thermal energy of the solution to make up for the difference. (c) No, an ideal solution is formed with no appreciable heat release or consumption.

4. Give an example of each of the following types of solutions:
   a. a gas in a liquid
   b. a gas in a gas
   c. a solid in a solid

Answer

(a) CO_2 in water; (b) O_2 in N_2 (air); (c) bronze (solution of tin or other metals in copper)

5. Indicate the most important types of intermolecular attractions in each of the following solutions:
   a. The solution in Figure.
   b. NO(*l*) in CO(*l*)
   c. $Cl_2(g)$ in $Br_2(l)$
   d. HCl(*aq*) in benzene $C_6H_6(l)$
   e. Methanol $CH_3OH(l)$ in $H_2O(l)$

Answer

(a) ion-dipole forces; (b) dipole-dipole forces; (c) dispersion forces; (d) dispersion forces; (e) hydrogen bonding

6. Predict whether each of the following substances would be more soluble in water (polar solvent) or in a hydrocarbon such as heptane (C_7H_{16}, nonpolar solvent):
   a. vegetable oil (nonpolar)
   b. isopropyl alcohol (polar)
   c. potassium bromide (ionic)

Answer

(a) heptane; (b) water; (c) water

7. Heat is released when some solutions form; heat is absorbed when other solutions form. Provide a molecular explanation for the difference between these two types of spontaneous processes.

Answer

Heat is released when the total intermolecular forces (IMFs) between the solute and solvent molecules are stronger than the total IMFs in the pure solute and in the pure solvent: Breaking weaker IMFs and forming stronger IMFs releases heat. Heat is absorbed when the total IMFs in the solution are weaker than the total of those in the pure solute and in the pure solvent: Breaking stronger IMFs and forming weaker IMFs absorbs heat.

8. Solutions of hydrogen in palladium may be formed by exposing Pd metal to H_2 gas. The concentration of hydrogen in the palladium depends on the pressure of H_2 gas applied, but in a more complex fashion than can be described by Henry's law. Under certain conditions, 0.94 g of hydrogen gas is dissolved in 215 g of palladium metal.
   a. Determine the molarity of this solution (solution density = 1.8 g/cm^3).
   b. Determine the molality of this solution (solution density = 1.8 g/cm^3).
   c. Determine the percent by mass of hydrogen atoms in this solution (solution density = 1.8 g/cm^3).

Answer

http://cnx.org/contents/mH6aqegx@2/The-Dissolution-Process

9. Explain why the ions Na^+ and Cl^- are strongly solvated in water but not in hexane, a solvent composed of nonpolar molecules.

Answer


Crystals of NaCl dissolve in water, a polar liquid with a very large dipole moment, and the individual ions become strongly solvated. Hexane is a nonpolar liquid with a dipole moment of zero and, therefore, does not significantly interact with the ions of the NaCl crystals.

10. Explain why solutions of HBr in benzene (a nonpolar solvent) are nonconductive, while solutions in water (a polar solvent) are conductive.

Answer

HBr is an acid and so its molecules react with water molecules to form H_3O^+ and Br^- ions that provide conductivity to the solution. Though HBr is soluble in benzene, it does not react chemically but remains dissolved as neutral HBr molecules. With no ions present in the benzene solution, it is electrically nonconductive.

11. Consider the solutions presented:
   a. Which of the following sketches best represents the ions in a solution of $Fe(NO_3)_3(aq)$?



b. Write a balanced chemical equation showing the products of the dissolution of $Fe(NO_3)_3$.

Answer

(a) $Fe(NO_3)_3$ is a strong electrolyte, thus it should completely dissociate into Fe^{3+} and (NO_3^-) ions. Therefore, (z) best represents the solution. (b) $\mathbf{Fe(NO_3)_3(s) \longrightarrow Fe^{3+}(aq) + 3\,NO_3^-(aq)}$


12. Compare the processes that occur when methanol (CH_3OH), hydrogen chloride (HCl), and sodium hydroxide (NaOH) dissolve in water. Write equations and prepare sketches showing the form in which each of these compounds is present in its respective solution.

Answer

Methanol, $\boldsymbol{CH_3OH}$, dissolves in water in all proportions, interacting via hydrogen bonding.

Methanol:

$$CH_3OH_{(l)} + H_2O_{(l)} \longrightarrow CH_3OH_{(aq)} \tag{13.7.1}$$



hydrogen bonding

Hydrogen chloride, HCl, dissolves in and reacts with water to yield hydronium cations and chloride anions that are solvated by strong ion-dipole interactions.


Hydrogen chloride:

$$HCl(g) + H_2O_{(l)} \rightarrow H_3O^+_{(aq)} + Cl^-_{(aq)} \tag{13.7.2}$$

Sodium hydroxide, NaOH, dissolves in water and dissociates to yield sodium cations and hydroxide anions that are strongly solvated by ion-dipole interactions and hydrogen bonding, respectively.

Sodium hydroxide:

$$NaOH_{(s)} \rightarrow Na^+_{(aq)} + OH^-_{(aq)} \tag{13.7.3}$$



Ion-dipole attraction hydrogen bonding

13. What is the expected electrical conductivity of the following solutions?
    a. NaOH(*aq*)
    b. HCl(*aq*)
    c. $C_6H_{12}O_6$(*aq*) (glucose)
    d. NH_3(*l*)

Answer

(a) high conductivity (solute is an ionic compound that will dissociate when dissolved); (b) high conductivity (solute is a strong acid and will ionize completely when dissolved); (c) nonconductive (solute is a covalent compound, neither acid nor base, unreactive towards water); (d) low conductivity (solute is a weak base and will partially ionize when dissolved)

14. Why are most *solid* ionic compounds electrically nonconductive, whereas aqueous solutions of ionic compounds are good conductors? Would you expect a *liquid* (molten) ionic compound to be electrically conductive or nonconductive? Explain.

Answer

A medium must contain freely mobile, charged entities to be electrically conductive. The ions present in a typical ionic solid are immobilized in a crystalline lattice and so the solid is not able to support an electrical current. When the ions are mobilized, either by melting the solid or dissolving it in water to dissociate the ions, current may flow and these forms of the ionic compound are conductive.

15. Indicate the most important type of intermolecular attraction responsible for solvation in each of the following solutions:
    a. the solutions in Figure
    b. methanol, CH_3OH, dissolved in ethanol, C_2H_5OH
    c. methane, CH_4, dissolved in benzene, C_6H_6
    d. the polar halocarbon CF_2Cl_2 dissolved in the polar halocarbon $CF_2ClCFCl_2$
    e. $O_2(l)$ in $N_2(l)$

Answer

(a) ion-dipole; (b) hydrogen bonds; (c) dispersion forces; (d) dipole-dipole attractions; (e) dispersion forces

16. Suppose you are presented with a clear solution of sodium thiosulfate, $Na_2S_2O_3$. How could you determine whether the solution is unsaturated, saturated, or supersaturated?

Answer

Add a small crystal of $Na_2S_2O_3$. It will dissolve in an unsaturated solution, remain apparently unchanged in a saturated solution, or initiate precipitation in a supersaturated solution.

17. Supersaturated solutions of most solids in water are prepared by cooling saturated solutions. Supersaturated solutions of most gases in water are prepared by heating saturated solutions. Explain the reasons for the difference in the two procedures.

Answer


The solubility of solids usually decreases upon cooling a solution, while the solubility of gases usually decreases upon heating.

18. Suggest an explanation for the observations that ethanol, C_2H_5OH, is completely miscible with water and that ethanethiol, C_2H_5SH, is soluble only to the extent of 1.5 g per 100 mL of water.

Answer

The hydrogen bonds between water and C_2H_5OH are much stronger than the intermolecular attractions between water and C_2H_5SH.

19. Calculate the percent by mass of KBr in a saturated solution of KBr in water at 10 °C using the following figure for useful data, and report the computed percentage to one significant digit.



This graph shows how the solubility of several solids changes with temperature.

Answer

At 10 °C, the solubility of KBr in water is approximately 60 g per 100 g of water.

$$\% \; KBr = \frac{60 \; g \; KBr}{(60 + 100) \; g \; solution} = 40\% \tag{13.7.4}$$

20. Which of the following gases is expected to be most soluble in water? Explain your reasoning.
    a. CH_4
    b. CCl_4
    c. $CHCl_3$

Answer

(c) $CHCl_3$ is expected to be most soluble in water. Of the three gases, only this one is polar and thus capable of experiencing relatively strong dipole-dipole attraction to water molecules.

21. At 0 °C and 1.00 atm, as much as 0.70 g of O_2 can dissolve in 1 L of water. At 0 °C and 4.00 atm, how many grams of O_2 dissolve in 1 L of water?


Answer

This problem requires the application of Henry's law. The governing equation is $C_g = kP_g$.

$$k = \frac{C_g}{P_g} = \frac{0.70 \; g}{1.00 \; atm} = 0.70 \; g \; atm^{-1} \tag{13.7.5}$$

Under the new conditions, $C_g = 0.70 \; g \; atm^{-1} \times 4.00 \; atm = 2.80 \; g$.

22. Refer to following figure for the following three questions:



    a. How did the concentration of dissolved CO_2 in the beverage change when the bottle was opened?
    b. What caused this change?
    c. Is the beverage unsaturated, saturated, or supersaturated with CO_2?

Answer

(a) It decreased as some of the CO_2 gas left the solution (evidenced by effervescence). (b) Opening the bottle released the high-pressure CO_2 gas above the beverage. The reduced CO_2 gas pressure, per Henry's law, lowers the solubility for CO_2. (c) The dissolved CO_2 concentration will continue to slowly decrease until equilibrium is reestablished between the beverage and the

very low CO_2 gas pressure in the opened bottle. Immediately after opening, the beverage, therefore, contains dissolved CO_2 at a concentration greater than its solubility, a nonequilibrium condition, and is said to be supersaturated.

23. The Henry's law constant for CO_2 is $3.4 \times 10^{-2}\ M/atm$ at 25 °C. What pressure of carbon dioxide is needed to maintain a CO_2 concentration of 0.10 *M* in a can of lemon-lime soda?

Answer

$$P_g = \frac{C_g}{k} = \frac{0.10\ M}{3.4 \times 10^{-2}\ M/atm} = 2.9\ atm \tag{13.7.6}$$

24. The Henry's law constant for O_2 is $1.3 \times 10^{-3}\ M/atm$ at 25 °C. What mass of oxygen would be dissolved in a 40-L aquarium at 25 °C, assuming an atmospheric pressure of 1.00 atm, and that the partial pressure of O_2 is 0.21 atm?

Answer

Start with Henry's law

$$C_g = kP_g \tag{13.7.7}$$

and apply it to O_2

$$C(O_2) = (1.3 \times 10^{-3}\ M/atm)(0.21\ atm) = 2.7 \times 10^{-4}\ mol/L \tag{13.7.8}$$

The total amount is \((2.7 \times 10^{-4}\; mol/L)(40\;L=1.08 \times 10^{-2} \;mol\]

The mass of oxygen is $(1.08 \times 10^{-2}\ mol)(32.0\ g/mol) = 0.346\ g$

or, using two significant figures, $0.35\ g$.

25. How many liters of HCl gas, measured at 30.0 °C and 745 torr, are required to prepare 1.25 L of a 3.20-*M* solution of hydrochloric acid?

Answer

First, calculate the moles of HCl needed. Then use the ideal gas law to find the volume required.

M = mol L−1

3.20M=xmol1.25L

x = 4.00 mol HCl

Before using the ideal gas law, change pressure to atmospheres and convert temperature from °C to kelvin.

\[1\;atmx=760torr745torr

x = 0.9803 atm

V=nRTP=(4.000molHCl)(0.08206LatmK−1mol−1)(303.15K)0.9803atm=102 L HCl

102 L HCl

more http://cnx.org/contents/2488fW6W@2/Solubility

26. Which is/are part of the macroscopic domain of solutions and which is/are part of the microscopic domain: boiling point elevation, Henry's law, hydrogen bond, ion-dipole attraction, molarity, nonelectrolyte, nonstoichiometric compound, osmosis, solvated ion?
27. What is the microscopic explanation for the macroscopic behavior illustrated in [link]?

Answer

The strength of the bonds between like molecules is stronger than the strength between unlike molecules. Therefore, some regions will exist in which the water molecules will exclude oil molecules and other regions will exist in which oil molecules

will exclude water molecules, forming a heterogeneous region.

28. Sketch a qualitative graph of the pressure versus time for water vapor above a sample of pure water and a sugar solution, as the liquids evaporate to half their original volume.
29. A solution of potassium nitrate, an electrolyte, and a solution of glycerin ($C_3H_5(OH)_3$), a nonelectrolyte, both boil at 100.3 °C. What other physical properties of the two solutions are identical?

Answer

Both form homogeneous solutions; their boiling point elevations are the same, as are their lowering of vapor pressures. Osmotic pressure and the lowering of the freezing point are also the same for both solutions.

30. What are the mole fractions of H_3PO_4 and water in a solution of 14.5 g of H_3PO_4 in 125 g of water?
31. What are the mole fractions of HNO_3 and water in a concentrated solution of nitric acid (68.0% HNO_3 by mass)?

Answer

1) Find number of moles of HNO_3 and H_2O in 100 g of the solution. Find the mole fractions for the components.

2) The mole fraction of HNO_3 is 0.378. The mole fraction of H_2O is 0.622.

32. Calculate the mole fraction of each solute and solvent:
    a. 583 g of H_2SO_4 in 1.50 kg of water—the acid solution used in an automobile battery
    b. 0.86 g of NaCl in 1.00×10^2 g of water—a solution of sodium chloride for intravenous injection
    c. 46.85 g of codeine, $C_{18}H_{21}NO_3$, in 125.5 g of ethanol, C_2H_5OH
    d. 25 g of I_2 in 125 g of ethanol, C_2H_5OH

Answer

a. $583\ g\ H_2SO_4 \times \frac{1\ mole\ H_2SO_4}{98.08\ g\ H_2SO_4} = 5.94\ mole\ H_2SO_4$ $\qquad$ $1.50\ kg\ H_2O \times \frac{1000\ g}{1\ kg} \times \frac{1\ mole\ H_2O}{18.02\ g\ H_2O} = 83.2\ moles\ H_2O$

33. Calculate the mole fraction of each solute and solvent:
    a. 0.710 kg of sodium carbonate (washing soda), Na_2CO_3, in 10.0 kg of water—a saturated solution at 0 °C
    b. 125 g of NH_4NO_3 in 275 g of water—a mixture used to make an instant ice pack
    c. 25 g of Cl_2 in 125 g of dichloromethane, CH_2Cl_2
    d. 0.372 g of histamine, C_5H_9N, in 125 g of chloroform, $CHCl_3$

Answer

(a) $X_{Na_2CO_3} = 0.0119$; $X_{H_2O} = 0.988$; (b) $X_{NH_4NO_3} = 0.9927$; $X_{H_2O} = 0.907$; (c) $X_{Cl_2} = 0.192$; $X_{CH_2Cl_2} = 0.808$; (d)$X_{C_5H_9N} = 0.00426$; $X_{CHCl_3} = 0.997$

34. Calculate the mole fractions of methanol, CH_3OH; ethanol, C_2H_5OH; and water in a solution that is 40% methanol, 40% ethanol, and 20% water by mass. (Assume the data are good to two significant figures.)
35. What is the difference between a 1 *M* solution and a 1 *m* solution?

Answer

In a 1 *M* solution, the mole is contained in exactly 1 L of solution. In a 1 *m* solution, the mole is contained in exactly 1 kg of solvent.

36. What is the molality of phosphoric acid, H_3PO_4, in a solution of 14.5 g of H_3PO_4 in 125 g of water?
37. What is the molality of nitric acid in a concentrated solution of nitric acid (68.0% HNO_3 by mass)?

Answer

(a) Determine the molar mass of HNO_3. Determine the number of moles of acid in the solution. From the number of moles and the mass of solvent, determine the molality. (b) 33.7 *m*

38. Calculate the molality of each of the following solutions:
    a. 583 g of H_2SO_4 in 1.50 kg of water—the acid solution used in an automobile battery
    b. 0.86 g of NaCl in 1.00×10^2 g of water—a solution of sodium chloride for intravenous injection
    c. 46.85 g of codeine, $C_{18}H_{21}NO_3$, in 125.5 g of ethanol, C_2H_5OH
    d. 25 g of I_2 in 125 g of ethanol, C_2H_5OH
39. Calculate the molality of each of the following solutions:
    a. 0.710 kg of sodium carbonate (washing soda), Na_2CO_3, in 10.0 kg of water—a saturated solution at 0°C
    b. 125 g of NH_4NO_3 in 275 g of water—a mixture used to make an instant ice pack
    c. 25 g of Cl_2 in 125 g of dichloromethane, CH_2Cl_2
    d. 0.372 g of histamine, C_5H_9N, in 125 g of chloroform, $CHCl_3$

Answer

(a) 6.70×10^{-1} *m*; (b) 5.67 *m*; (c) 2.8 *m*; (d) 0.0358 *m*

40. The concentration of glucose, $C_6H_{12}O_6$, in normal spinal fluid is $\frac{75\text{ mg}}{100\text{ g}}$. What is the molality of the solution?
41. A 13.0% solution of K_2CO_3 by mass has a density of 1.09 g/cm^3. Calculate the molality of the solution.

Answer

1.08 *m*

42. Why does 1 mol of sodium chloride depress the freezing point of 1 kg of water almost twice as much as 1 mol of glycerin?

Answer

Determine the molar mass of sucrose; determine the number of moles of sucrose in the solution; convert the mass of solvent to units of kilograms; from the number of moles and the mass of solvent, determine the molality; determine the difference between the boiling point of water and the boiling point of the solution; determine the new boiling point.

43. What is the boiling point of a solution of 115.0 g of sucrose, $C_{12}H_{22}O_{11}$, in 350.0 g of water?

Answer

100.5 °C

44. What is the boiling point of a solution of 9.04 g of I_2 in 75.5 g of benzene, assuming the I_2 is nonvolatile?
45. What is the freezing temperature of a solution of 115.0 g of sucrose, $C_{12}H_{22}O_{11}$, in 350.0 g of water, which freezes at 0.0 °C when pure?

Answer

(a) Determine the molar mass of sucrose; determine the number of moles of sucrose in the solution; convert the mass of solvent to units of kilograms; from the number of moles and the mass of solvent, determine the molality; determine the difference between the freezing temperature of water and the freezing temperature of the solution; determine the new freezing temperature. (b) −1.8 °C

46. What is the freezing point of a solution of 9.04 g of I_2 in 75.5 g of benzene?
47. What is the osmotic pressure of an aqueous solution of 1.64 g of $Ca(NO_3)_2$ in water at 25 °C? The volume of the solution is 275 mL.

Answer

(a) Determine the molar mass of $Ca(NO_3)_2$; determine the number of moles of $Ca(NO_3)_2$ in the solution; determine the number of moles of ions in the solution; determine the molarity of ions, then the osmotic pressure. (b) 2.67 atm

48. What is osmotic pressure of a solution of bovine insulin (molar mass, 5700 g mol^{-1}) at 18 °C if 100.0 mL of the solution contains 0.103 g of the insulin?

49. What is the molar mass of a solution of 5.00 g of a compound in 25.00 g of carbon tetrachloride (bp 76.8 °C; K_b = 5.02 °C/*m*) that boils at 81.5 °C at 1 atm?

Answer

(a) Determine the molal concentration from the change in boiling point and K_b; determine the moles of solute in the solution from the molal concentration and mass of solvent; determine the molar mass from the number of moles and the mass of solute.
(b) 2.1×10^2 g mol^{-1}

50. A sample of an organic compound (a nonelectrolyte) weighing 1.35 g lowered the freezing point of 10.0 g of benzene by 3.66 °C. Calculate the molar mass of the compound.
51. A 1.0 *m* solution of HCl in benzene has a freezing point of 0.4 °C. Is HCl an electrolyte in benzene? Explain.

Answer

No. Pure benzene freezes at 5.5 °C, and so the observed freezing point of this solution is depressed by $\Delta T_f = 5.5 - 0.4 = 5.1$ °C. The value computed, assuming no ionization of HCl, is ΔT_f = (1.0 m)(5.14 °C/*m*) = 5.1 °C. Agreement of these values supports the assumption that HCl is not ionized.

52. A solution contains 5.00 g of urea, $CO(NH_2)_2$, a nonvolatile compound, dissolved in 0.100 kg of water. If the vapor pressure of pure water at 25 °C is 23.7 torr, what is the vapor pressure of the solution?
53. A 12.0-g sample of a nonelectrolyte is dissolved in 80.0 g of water. The solution freezes at −1.94 °C. Calculate the molar mass of the substance.

Answer

144 g mol^{-1}

54. Arrange the following solutions in order by their decreasing freezing points: 0.1 *m* Na_3PO_4, 0.1 *m* C_2H_5OH, 0.01 *m* CO_2, 0.15 *m* NaCl, and 0.2 *m* $CaCl_2$.
55. Calculate the boiling point elevation of 0.100 kg of water containing 0.010 mol of NaCl, 0.020 mol of Na_2SO_4, and 0.030 mol of $MgCl_2$, assuming complete dissociation of these electrolytes.

Answer

0.870 °C

56. How could you prepare a 3.08 *m* aqueous solution of glycerin, $C_3H_8O_3$? What is the freezing point of this solution?
57. A sample of sulfur weighing 0.210 g was dissolved in 17.8 g of carbon disulfide, CS_2 (K_b = 2.43 °C/*m*). If the boiling point elevation was 0.107 °C, what is the formula of a sulfur molecule in carbon disulfide?

Answer

S_8

58. In a significant experiment performed many years ago, 5.6977 g of cadmium iodide in 44.69 g of water raised the boiling point 0.181 °C. What does this suggest about the nature of a solution of CdI_2?
59. Lysozyme is an enzyme that cleaves cell walls. A 0.100-L sample of a solution of lysozyme that contains 0.0750 g of the enzyme exhibits an osmotic pressure of 1.32×10^{-3} atm at 25 °C. What is the molar mass of lysozyme?

Answer

1.39×10^4 g mol^{-1}

60. The osmotic pressure of a solution containing 7.0 g of insulin per liter is 23 torr at 25 °C. What is the molar mass of insulin?
61. The osmotic pressure of human blood is 7.6 atm at 37 °C. What mass of glucose, $C_6H_{12}O_6$, is required to make 1.00 L of aqueous solution for intravenous feeding if the solution must have the same osmotic pressure as blood at body temperature, 37 °C?

Answer

54 g

62. What is the freezing point of a solution of dibromobenzene, $C_6H_4Br_2$, in 0.250 kg of benzene, if the solution boils at 83.5 °C?
63. What is the boiling point of a solution of NaCl in water if the solution freezes at −0.93 °C?

Answer

100.26 °C

64. The sugar fructose contains 40.0% C, 6.7% H, and 53.3% O by mass. A solution of 11.7 g of fructose in 325 g of ethanol has a boiling point of 78.59 °C. The boiling point of ethanol is 78.35 °C, and K_b for ethanol is 1.20 °C/*m*. What is the molecular formula of fructose?
65. The vapor pressure of methanol, CH_3OH, is 94 torr at 20 °C. The vapor pressure of ethanol, C_2H_5OH, is 44 torr at the same temperature.
    a. Calculate the mole fraction of methanol and of ethanol in a solution of 50.0 g of methanol and 50.0 g of ethanol.
    b. Ethanol and methanol form a solution that behaves like an ideal solution. Calculate the vapor pressure of methanol and of ethanol above the solution at 20 °C.
    c. Calculate the mole fraction of methanol and of ethanol in the vapor above the solution.

Answer

(a) $X_{CH_3OH} = 0.590$; $X_{C_2H_5OH} = 0.410$; (b) Vapor pressures are: CH_3OH: 55 torr; C_2H_5OH: 18 torr; (c) CH_3OH: 0.75; C_2H_5OH: 0.25

66. The triple point of air-free water is defined as 273.15 K. Why is it important that the water be free of air?
67. Meat can be classified as fresh (not frozen) even though it is stored at −1 °C. Why wouldn't meat freeze at this temperature?

Answer

The ions and compounds present in the water in the beef lower the freezing point of the beef below −1 °C.

68. An organic compound has a composition of 93.46% C and 6.54% H by mass. A solution of 0.090 g of this compound in 1.10 g of camphor melts at 158.4 °C. The melting point of pure camphor is 178.4 °C. K_f for camphor is 37.7 °C/*m*. What is the molecular formula of the solute? Show your calculations.
69. A sample of $HgCl_2$ weighing 9.41 g is dissolved in 32.75 g of ethanol, C_2H_5OH (K_b = 1.20 °C/*m*). The boiling point elevation of the solution is 1.27 °C. Is $HgCl_2$ an electrolyte in ethanol? Show your calculations.

Answer

$$\Delta bp = K_b m = (1.20\,°C/m)\left(\frac{9.41\text{ g} \times \frac{1\text{ mol } HgCl_2}{271.496\text{ g}}}{0.03275\text{ kg}}\right) = 1.27\,°C$$

The observed change equals the theoretical change; therefore, no dissociation occurs.

70. A salt is known to be an alkali metal fluoride. A quick approximate determination of freezing point indicates that 4 g of the salt dissolved in 100 g of water produces a solution that freezes at about −1.4 °C. What is the formula of the salt? Show your calculations.
71. Identify the dispersed phase and the dispersion medium in each of the following colloidal systems: starch dispersion, smoke, fog, pearl, whipped cream, floating soap, jelly, milk, and ruby.

Answer

Colloidal System	Dispersed Phase	Dispersion Medium
starch dispersion	starch	water
smoke	solid particles	air
fog	water	air
pearl	water	calcium carbonate ($CaCO_3$)
whipped cream	air	cream
floating soap	air	soap
jelly	fruit juice	pectin gel
milk	butterfat	water
ruby	chromium(III) oxide (Cr_2O_3)	aluminum oxide (Al_2O_3)

72. Distinguish between dispersion methods and condensation methods for preparing colloidal systems.

Answer

Dispersion methods use a grinding device or some other means to bring about the subdivision of larger particles. Condensation methods bring smaller units together to form a larger unit. For example, water molecules in the vapor state come together to form very small droplets that we see as clouds.

73. How do colloids differ from solutions with regard to dispersed particle size and homogeneity?

Answer

Colloidal dispersions consist of particles that are much bigger than the solutes of typical solutions. Colloidal particles are either very large molecules or aggregates of smaller species that usually are big enough to scatter light. Colloids are homogeneous on a macroscopic (visual) scale, while solutions are homogeneous on a microscopic (molecular) scale.

74. Explain the cleansing action of soap.

S11.6.4

Soap molecules have both a hydrophobic and a hydrophilic end. The charged (hydrophilic) end, which is usually associated with an alkali metal ion, ensures water solubility The hydrophobic end permits attraction to oil, grease, and other similar nonpolar substances that normally do not dissolve in water but are pulled into the solution by the soap molecules.

Q11.6.5

How can it be demonstrated that colloidal particles are electrically charged?

S11.6.5

If they are placed in an electrolytic cell, dispersed particles will move toward the electrode that carries a charge opposite to their own charge. At this electrode, the charged particles will be neutralized and will coagulate as a precipitate.

Contributors and Attributions

- Paul Flowers (University of North Carolina - Pembroke), Klaus Theopold (University of Delaware) and Richard Langley (Stephen F. Austin State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at http://cnx.org/contents/85abf193-2bd...a7ac8df6@9.110).

13.7: End of Chapter Problems is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

Index

B

bond length

10.3: Covalent Bonding and Electronegativity

C

covalent bond

10.3: Covalent Bonding and Electronegativity

E

electronegativity

10.3: Covalent Bonding and Electronegativity

F

formal charge

10.7: Formal Charges

M

molecular structure

10.7: Formal Charges

N

nonpolar covalent bond

10.3: Covalent Bonding and Electronegativity

P

polar covalent bond

10.3: Covalent Bonding and Electronegativity

pure covalent bond

10.3: Covalent Bonding and Electronegativity

R

resonance

10.7: Formal Charges

resonance forms

10.7: Formal Charges

resonance hybrid

10.7: Formal Charges

Glossary

ParseError: Maximum iterations exceeded! (click for details)

Detailed Licensing

Overview

Title: Chem 201: General Chemistry I OER

Webpages: 123

Applicable Restrictions: Noncommercial

All licenses found:

- Undeclared: 97.6% (120 pages)
- CC BY 4.0: 1.6% (2 pages)
- CC BY-NC-SA 4.0: 0.8% (1 page)

By Page

- Chem 201: General Chemistry I OER - *Undeclared*
  - Front Matter - *Undeclared*
    - TitlePage - *Undeclared*
    - InfoPage - *Undeclared*
    - Table of Contents - *Undeclared*
    - Licensing - *Undeclared*
  - 1: Matter and Measurements - *Undeclared*
    - 1.1: Chemistry- The Central science - *Undeclared*
    - 1.2: Scientific Approach for Solving Problems - *Undeclared*
    - 1.3: Classification of Matter - *Undeclared*
    - 1.4: Properties of Matter - *Undeclared*
    - 1.5: Units of Measurements - *Undeclared*
    - 1.6: Uncertainty in Measurements - *Undeclared*
    - 1.7: Dimensional Analysis- a Problem Solving Method Used in Chemistry - *Undeclared*
    - 1.8: End of Chapter Problems - *Undeclared*
  - 2: Atoms and Elements - *Undeclared*
    - 2.1: Early Ideas of Atomic Theories - *Undeclared*
    - 2.2: Development of Modern Atomic Tehory - *Undeclared*
    - 2.3: Atomic Structure, Names/Symbols of Atoms, and Ions - *Undeclared*
    - 2.4: Periodic Table - *Undeclared*
    - 2.5: Isotopes and Average Atomic Mass - *Undeclared*
    - 2.6: Molar Mass of Elements - *Undeclared*
    - 2.7: End of Chapter Problems - *Undeclared*
  - 3: Molecules and Compounds - *Undeclared*
    - 3.1: Ionic and Molecular Compounds - *Undeclared*
    - 3.2: Representation of Chemical Compounds - *Undeclared*
    - 3.3: Types of ions - *Undeclared*
    - 3.4: Formulas and names of ionic compounds - *Undeclared*
    - 3.5: Formulas and Names of Covalent Compounds - *Undeclared*
    - 3.6: Formula Mass and Molar Mass of Compounds - *Undeclared*
    - 3.7: Percent Composition, Emperical Formulas, and Molecular Fromulas - *Undeclared*
    - 3.8: Determine Empirical Formula from Combustion Analysis - *Undeclared*
    - 3.9: End of Chapter Problems - *Undeclared*
  - 4: Introduction to Solutions - *Undeclared*
    - 4.1: Introduction to solutions - *Undeclared*
    - 4.2: Solution Concentration - *Undeclared*
    - 4.3: Solution Dilution - *Undeclared*
    - 4.4: Hydration of Ions in Aqueous Solutions - *Undeclared*
    - 4.5: Solubility of Ionic Compounds - *Undeclared*
    - 4.6: Introduction to Acids and Bases - *Undeclared*
    - 4.7: End of Chapter Problems - *Undeclared*
  - 5: Chemical reactions - *Undeclared*
    - 5.1: Writing and Balancing Chemical Reactions - *Undeclared*
    - 5.2: Precipitation Reactions - *Undeclared*
    - 5.3: Representing aqueous reaction- Molecular, complete ionic, and net ionic equations - *Undeclared*
    - 5.4: Neutralization Reactions and Gas Evolution - *Undeclared*
    - 5.5: Oxidation-Reduction reactions - *Undeclared*
    - 5.6: Balancing Redox Reactions - *Undeclared*
    - 5.7: End of Chapter Problems - *Undeclared*
  - 6: Reaction Stoichiometry - *Undeclared*
    - 6.1: Reaction Stoichiometry - *Undeclared*
    - 6.2: Limiting reactant, theoretical yield, and percent yield - *Undeclared*
    - 6.3: solution stoichiometry - *Undeclared*

- 6.4: Quantitative Analysis-Titration and Gravimetric Analysis - *Undeclared*
- 6.5: End of Chapter Problems - *Undeclared*

7: Gases - *Undeclared*

- 7.1: Pressure of the Gas - *Undeclared*
- 7.2: simple Gas Laws - *Undeclared*
- 7.3: Ideal Gas Law - *Undeclared*
- 7.4: Applying the Ideal Gas Law - *Undeclared*
- 7.5: Mixture of Gases - *Undeclared*
- 7.6: Gas Stoichiometry - *Undeclared*
- 7.7: Effusion and Diffusion of Gases - *Undeclared*
- 7.8: Kinetic Molecular Theory - *Undeclared*
- 7.9: Non Ideal Gas Behavior - *Undeclared*
- 7.10: End of Chapter Problems - *Undeclared*

8: Thermochemistry - *Undeclared*

- 8.1: Types of Energy - *Undeclared*
- 8.2: Internal Energy and First Law of Thermodynamics - *Undeclared*
- 8.3: Quantifying Heat and Work - *Undeclared*
- 8.4: Constant Volume Calorimeter - *Undeclared*
- 8.5: Enthalpy of reactions - *Undeclared*
- 8.6: Constant Pressure Calorimeter - *Undeclared*
- 8.7: Standard Enthalpy of formation - *Undeclared*
- 8.8: Calculating Enthalpy of Reactions Using Hess's Law - *Undeclared*
- 8.9: End of Chapter Problems - *Undeclared*

9: Electronic Structure and Periodic Table - *Undeclared*

- 9.1: The Nature of Light - *Undeclared*
- 9.2: Line Spectra and Bohr Model of Atoms - *Undeclared*
- 9.3: Wave Nature of Matter - *Undeclared*
- 9.4: The Quantum-Mechanical Model of an Atom - *Undeclared*
- 9.5: Electron Configuration of Atoms - *Undeclared*
- 9.6: Electron Configurations of Ions - *CC BY-NC-SA 4.0*
- 9.7: Periodic Trends - *Undeclared*
- 9.8: End of Chapter Problems - *Undeclared*

10: Lewis Structure and Bond Energy - *Undeclared*

- 10.3: Covalent Bonding and Electronegativity - *CC BY 4.0*
- 10.7: Formal Charges - *CC BY 4.0*
- 10.1: Lewis Symbol of Atoms - *Undeclared*
- 10.2: Ionic Bonding - *Undeclared*
- 10.4: Lewis Structures of Molecular Compounds - *Undeclared*
- 10.5: Exceptions to the Octet Rule - *Undeclared*
- 10.6: Resonance Strucutres - *Undeclared*
- 10.8: Strengths of Ionic and Covalent Bonds - *Undeclared*
- 10.9: End of Chapter Problems - *Undeclared*

11: Theories of Chemical Bonding - *Undeclared*

- 11.1: VSEPR Theory - *Undeclared*
- 11.2: Polarity of Molecules - *Undeclared*
- 11.3: Valence Bond theory - *Undeclared*
- 11.4: Hybrid Atomic Orbitals - *Undeclared*
- 11.5: Overlap of Hybrid Orbitals - *Undeclared*
- 11.6: Molecular Orbital Theory - *Undeclared*
- 11.7: End of Chapter Problems - *Undeclared*

12: Liquids and Solids - *Undeclared*

- 12.1: Intermolecular forces - *Undeclared*
- 12.2: Properties of Liquids - *Undeclared*
- 12.3: Phase Changes - *Undeclared*
- 12.4: Phase diagram - *Undeclared*
- 12.5: The Solid State of Matter - *Undeclared*
- 12.6: Lattice Structure in Crystalline Solids - *Undeclared*
- 12.7: End of Chapter Problems - *Undeclared*

13: Solution - *Undeclared*

- 13.1: How Do Solutions Form? - *Undeclared*
- 13.2: Electrolytes - *Undeclared*
- 13.3: Factors Affecting Solubility - *Undeclared*
- 13.4: Solution Concentration - *Undeclared*
- 13.5: Colligative Properties - *Undeclared*
- 13.6: Colloids - *Undeclared*
- 13.7: End of Chapter Problems - *Undeclared*

Back Matter - *Undeclared*

- Index - *Undeclared*
- Glossary - *Undeclared*
- Detailed Licensing - *Undeclared*