# ALGEBRA AND TRIGONOMETRY



*Jay Abramson*
Arizona State University



# Arizona State University
# Algebra and Trigonometry

Jay Abramson

This text is disseminated via the Open Education Resource (OER) LibreTexts Project (https://LibreTexts.org) and like the thousands of other texts available within this powerful platform, it is freely available for reading, printing, and "consuming."

The LibreTexts mission is to bring together students, faculty, and scholars in a collaborative effort to provide and accessible, and comprehensive platform that empowers our community to develop, curate, adapt, and adopt openly licensed resources and technologies; through these efforts we can reduce the financial burden born from traditional educational resource costs, ensuring education is more accessible for students and communities worldwide.

Most, but not all, pages in the library have licenses that may allow individuals to make changes, save, and print this book. Carefully consult the applicable license(s) before pursuing such effects. Instructors can adopt existing LibreTexts texts or Remix them to quickly build course-specific resources to meet the needs of their students. Unlike traditional textbooks, LibreTexts' web based origins allow powerful integration of advanced features and new technologies to support learning.




LibreTexts is the adaptable, user-friendly non-profit open education resource platform that educators trust for creating, customizing, and sharing accessible, interactive textbooks, adaptive homework, and ancillary materials. We collaborate with individuals and organizations to champion open education initiatives, support institutional publishing programs, drive curriculum development projects, and more.

The LibreTexts libraries are Powered by NICE CXone Expert and was supported by the Department of Education Open Textbook Pilot Project, the California Education Learning Lab, the UC Davis Office of the Provost, the UC Davis Library, the California State University Affordable Learning Solutions Program, and Merlot. This material is based upon work supported by the National Science Foundation under Grant No. 1246120, 1525057, and 1413739.

Any opinions, findings, and conclusions or recommendations expressed in this material are those of the author(s) and do not necessarily reflect the views of the National Science Foundation nor the US Department of Education.

Have questions or comments? For information about adoptions or adaptions contact info@LibreTexts.org or visit our main website at https://LibreTexts.org.

This text was compiled on 06/09/2025

# TABLE OF CONTENTS


Licensing

## 1: Prerequisites

- 1.1: Prelude to Prerequisites
- 1.2: Real Numbers - Algebra Essentials
  - 1.2E: Real Numbers - Algebra Essentials (Exercises)
- 1.3: Exponents and Scientific Notation
  - 1.3E: Exponents and Scientific Notation (Exercises)
- 1.4: Radicals and Rational Expressions
  - 1.4E: Radicals and Rational Expressions (Exercise)
- 1.5: Polynomials
  - 1.5E: Polynomials (Exercises)
- 1.6: Factoring Polynomials
  - 1.6E: Factoring Polynomials (Exercises)
- 1.7: Rational Expressions
  - 1.7E: Rational Expressions (Exercises)

## 2: Equations and Inequalities

- 2.1: Prelude to Equations and Inequalities
- 2.2: The Rectangular Coordinate Systems and Graphs
  - 2.2E: The Rectangular Coordinate Systems and Graphs (Exercises)
- 2.3: Linear Equations in One Variable
  - 2.3E: Linear Equations in One Variable (Exercises)
- 2.4: Complex Numbers
  - 2.4E: Complex Numbers (Exercises)
- 2.5: Quadratic Equations
  - 2.5E: Quadratic Equations (Exercises)
- 2.6: Other Types of Equations
  - 2.6E: Other Types of Equations (Exercises)
- 2.7: Modeling with Equations
  - 2.7.1: Models and Applications
    - 2.7.1E: Models and Applications (Exercises)
  - 2.7.2: Solve Mixture and Uniform Motion Applications
    - 2.7.2E: Exercises
  - 2.7.3: Solve Applications with Rational Equations
    - 2.7.3E: Exercises
- 2.8: Linear and Absolute Value Inequalities
  - 2.8.1: Linear Inequalities
    - 2.8.1E: Exercises
  - 2.8.2: Solve Absolute Value Inequalities
    - 2.8.2E: Exercises

- 2.8E: Linear Inequalities and Absolute Value Inequalities (Exercises)

## 3: Functions

- 3.1: Prelude to Functions
- 3.2: Functions and Function Notation
  - 3.2E: Functions and Function Notation (Exercises)
- 3.3: Domain and Range
  - 3.3E: Domain and Range (Exercises)
- 3.4: Rates of Change and Behavior of Graphs
  - 3.4E: Rates of Change and Behavior of Graphs (Exercises)
- 3.5: Linear Functions
  - 3.5.1: Prelude to Linear Functions
  - 3.5.2: Linear Functions
  - 3.5.3: Graphs of Linear Functions
  - 3.5.4: Modeling with Linear Functions
  - 3.5.5: Fitting Linear Models to Data
  - 3.5.E: Linear Functions(Exercises)
  - 3.5.R: Linear Functions(Review)
- 3.6: Composition of Functions
  - 3.6E: Composition of Functions (Exercises)
- 3.7: Transformation of Functions
  - 3.7E: Transformation of Functions (Exercises)
- 3.8: Absolute Value Functions
  - 3.8E: Absolute Value Functions (Exercises)
- 3.9: Inverse Functions
  - 3.9E: Inverse Functions (Exercises)

## 4: Polynomial and Rational Functions

- 4.1: Prelude to Polynomial and Rational Functions
- 4.2: Quadratic Functions
  - 4.2E: Quadratic Functions (Exercises)
- 4.3: Power Functions and Polynomial Functions
  - 4.3E: Power Functions and Polynomial Functions (Exercises)
- 4.4: Graphs of Polynomial Functions
  - 4.4E: Graphs of Polynomial Functions (Exercises)
- 4.5: Dividing Polynomials
  - 4.5E: Dividing Polynomials (Exercises)
- 4.6: Zeros of Polynomial Functions
  - 4.6E: Zeros of Polynomial Functions (Exercises)
- 4.7: Rational Functions
  - 4.7E: Rational Functions (Exercises)
- 4.8: Non-linear Inequalities
  - 4.8.1: Solve Quadratic Inequalities
    - 4.8.1E: Exercises
  - 4.8.2: Solve Rational Inequalities

- 4.8.2E: Exercises

## 5: Exponential and Logarithmic Functions

- 5.1: Prelude to Exponential and Logarithmic Functions
- 5.2: Exponential Functions
  - 5.2E: Exponential Functions (Exercises)
- 5.3: Graphs of Exponential Functions
  - 5.3E: Graphs of Exponential Functions (Exercises)
- 5.4: Logarithmic Functions
  - 5.4E: Logarithmic Functions (Exercises)
- 5.5: Graphs of Logarithmic Functions
  - 5.5E: Graphs of Logarithmic Functions (Exercises)
- 5.6: Logarithmic Properties
  - 5.6E: Logarithmic Properties (Exercises)
- 5.7: Exponential and Logarithmic Equations
  - 5.7E: Exponential and Logarithmic Equations (Exercises)
- 5.8: Exponential and Logarithmic Models
  - 5.8E: Exponential and Logarithmic Models (Exercises)
- 5.9: Fitting Exponential Models to Data
  - 5.9E: Fitting Exponential Models to Data (Exercises)

## 6: Systems of Equations and Inequalities

- 6.1: Prelude to Systems of Equations and Inequalities
- 6.2: Systems of Linear Equations - Two Variables
  - 6.2E: Systems of Linear Equations - Two Variables (Exercises)
- 6.3: Systems of Linear Equations with Three Variables
  - 6.3E: Systems of Linear Equations with Three Variables (Exercises)
- 6.4: Systems of Nonlinear Equations and Inequalities - Two Variables
  - 6.4E: Systems of Nonlinear Equations and Inequalities - Two Variables (Exercises)
- 6.5: Solving Systems with Gaussian Elimination
  - 6.5E: Solving Systems with Gaussian Elimination (Exercises)

## 7: Analytic Geometry

- 7.1: Prelude to Analytic Geometry
- 7.2: The Parabola
  - 7.2E: The Parabola (Exercises)
- 7.3: The Ellipse
  - 7.3E: The Ellipse (Exercises)
- 7.4: The Hyperbola
  - 7.4E: The Hyperbola (Exercises)

## 8: Sequences, Probability, and Counting Theory

- 8.1: Prelude to Sequences, Probability and Counting Theory
- 8.2: Sequences and Their Notations
  - 8.2E: Sequences and Their Notations (Exercises)

- 8.3: Arithmetic Sequences
  - 8.3E: Arithmetic Sequences (Exercises)
- 8.4: Geometric Sequences
  - 8.4E: Geometric Sequences (Exercises)
- 8.5: Series and Their Notations
  - 8.5E: Series and Their Notations (Exercises)

## 9: Additional Topics for Ch 4, 6, 7 and 8

- 9.1: Inverses and Radical Functions
  - 9.1.1: Inverses and Radical Functions (Exercises)
- 9.2: Modeling Using Variation
  - 9.2E: Modeling Using Variation (Exercises)
- 9.3: Partial Fractions
  - 9.3.1: Partial Fractions (Exercises)
- 9.4: Matrices and Matrix Operations
  - 9.4E: Matrices and Matrix Operations (Exercises)
- 9.5: Solving Systems with Inverses
  - 9.5E: Solving Systems with Inverses (Exercises)
- 9.6: Solving Systems with Cramer's Rule
  - 9.6E: Solving Systems with Cramer's Rule (Exercises)
- 9.7: Rotation of Axes
  - 9.7E: Rotation of Axes (Exercises)
- 9.8: Conic Sections in Polar Coordinates
  - 9.8E: Conic Sections in Polar Coordinates (Exercises)
- 9.9: Counting Principles
  - 9.9E: Counting Principles (Exercises)
- 9.10: Binomial Theorem
  - 9.10E: Binomial Theorem (Exercises)
- 9.11: Probability
  - 9.11E: Probability (Exercises)

## Index

## Glossary

## Detailed Licensing

# Licensing

*A detailed breakdown of this resource's licensing can be found in **Back Matter/Detailed Licensing**.*

# CHAPTER OVERVIEW

## 1: Prerequisites

In this chapter, we will review sets of numbers and properties of operations used to manipulate numbers. This understanding will serve as prerequisite knowledge throughout our study of algebra and trigonometry.


1.1: Prelude to Prerequisites
1.2: Real Numbers - Algebra Essentials
1.2E: Real Numbers - Algebra Essentials (Exercises)
1.3: Exponents and Scientific Notation
1.3E: Exponents and Scientific Notation (Exercises)
1.4: Radicals and Rational Expressions
1.4E: Radicals and Rational Expressions (Exercise)
1.5: Polynomials
1.5E: Polynomials (Exercises)
1.6: Factoring Polynomials
1.6E: Factoring Polynomials (Exercises)
1.7: Rational Expressions
1.7E: Rational Expressions (Exercises)


Thumbnail: A shortcut called FOIL is sometimes used to find the product of two binomials. It is called FOIL because we multiply the first terms, the outer terms, the inner terms, and then the last terms of each binomial.

### Contributors

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.


This page titled 1: Prerequisites is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 1.1: Prelude to Prerequisites

It’s a cold day in Antarctica. In fact, it’s always a cold day in Antarctica. Earth’s southernmost continent, Antarctica experiences the coldest, driest, and windiest conditions known. The coldest temperature ever recorded, over one hundred degrees below zero on the Celsius scale, was recorded by remote satellite. It is no surprise then, that no native human population can survive the harsh conditions. Only explorers and scientists brave the environment for any length of time.



Figure 1.1.1: Credit - Andreas Kambanls

Measuring and recording the characteristics of weather conditions in in Antarctica requires a use of different kinds of numbers. Calculating with them and using them to make predictions requires an understanding of relationships among numbers. In this chapter, we will review sets of numbers and properties of operations used to manipulate numbers. This understanding will serve as prerequisite knowledge throughout our study of algebra and trigonometry.

This page titled 1.1: Prelude to Prerequisites is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.0: Prelude to Prerequisites** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.2: Real Numbers - Algebra Essentials

**Learning Objectives**

- Classify a real number as a natural, whole, integer, rational, or irrational number.
- Perform calculations using order of operations.
- Use the following properties of real numbers: commutative, associative, distributive, inverse, and identity.
- Evaluate algebraic expressions.
- Simplify algebraic expressions.

It is often said that mathematics is the language of science. If this is true, then the language of mathematics is numbers. The earliest use of numbers occurred 100 centuries ago in the Middle East to count, or enumerate items. Farmers, cattlemen, and tradesmen used tokens, stones, or markers to signify a single quantity—a sheaf of grain, a head of livestock, or a fixed length of cloth, for example. Doing so made commerce possible, leading to improved communications and the spread of civilization.

Three to four thousand years ago, Egyptians introduced fractions. They first used them to show reciprocals. Later, they used them to represent the amount when a quantity was divided into equal parts.

But what if there were no cattle to trade or an entire crop of grain was lost in a flood? How could someone indicate the existence of nothing? From earliest times, people had thought of a “base state” while counting and used various symbols to represent this null condition. However, it was not until about the fifth century A.D. in India that zero was added to the number system and used as a numeral in calculations.

Clearly, there was also a need for numbers to represent loss or debt. In India, in the seventh century A.D., negative numbers were used as solutions to mathematical equations and commercial debts. The opposites of the counting numbers expanded the number system even further.

Because of the evolution of the number system, we can now perform complex calculations using these and other categories of real numbers. In this section, we will explore sets of numbers, calculations with different kinds of numbers, and the use of numbers in expressions.

## Classifying a Real Number

The numbers we use for counting, or enumerating items, are the natural numbers: $1, 2, 3, 4, 5$and so on. We describe them in set notation as $\{1, 2, 3, \dots\}$where the ellipsis $(\cdots)$ indicates that the numbers continue to infinity. The natural numbers are, of course, also called the counting numbers. Any time we enumerate the members of a team, count the coins in a collection, or tally the trees in a grove, we are using the set of natural numbers. The set of whole numbers is the set of natural numbers plus zero: $\{0, 1, 2, 3, \dots\}$

The set of integers adds the opposites of the natural numbers to the set of whole numbers: $\{\cdots, -3, -2, -1, 0, 1, 2, 3, \cdots\}$ It is useful to note that the set of integers is made up of three distinct subsets: negative integers, zero, and positive integers. In this sense, the positive integers are just the natural numbers. Another way to think about it is that the natural numbers are a subset of the integers.

$$\overbrace{\cdots, -3, -2, -1,}^{\text{negative integers}} \underbrace{0}_{\text{zero}}, \overbrace{1,\ 2,\ 3,\ \cdots}^{\text{positive integers}}$$

The set of rational numbers is written as $\{\frac{m}{n} | \text{m and n are integers and } n \neq 0\}$ .Notice from the definition that rational numbers are fractions (or quotients) containing integers in both the numerator and the denominator, and the denominator is never $0$. We can also see that every natural number, whole number, and integer is a rational number with a denominator of $1$.

Because they are fractions, any rational number can also be expressed in decimal form. Any rational number can be represented as either:

1. a terminating decimal: $\frac{15}{8} = 1.875$, or
2. a repeating decimal: $\frac{4}{11} = 0.36363636\cdots = 0.\overline{36}$

We use a line drawn over the repeating block of numbers instead of writing the group multiple times.

**Example 1.2.1: Writing Integers as Rational Numbers**

Write each of the following as a rational number. Write a fraction with the integer in the numerator and $1$ in the denominator.

a. $7$
b. $0$
c. $-8$

**Solution**

a. $7 = \frac{7}{1}$

b. $0 = \frac{0}{1}$

c. $-8 = \frac{-8}{1}$

**Exercise 1.2.1**

Write each of the following as a rational number.

a. $11$
b. $3$
c. $-4$

**Answer**

a. $\frac{11}{1}$
b. $\frac{3}{1}$
c. $-\frac{4}{1}$

**Example 1.2.2: Identifying Rational Numbers**

Write each of the following rational numbers as either a terminating or repeating decimal.

a. $-\frac{5}{7}$
b. $\frac{15}{5}$
c. $\frac{13}{25}$

**Solution**

a. a repeating decimal

b. $\frac{15}{5} = 3$ (or $3.0$), a terminating decimal

c. $\frac{13}{25} = 0.52$, a terminating decimal

**Exercise 1.2.2**

Write each of the following rational numbers as either a terminating or repeating decimal.

a. $\frac{68}{17}$
b. $\frac{8}{13}$
c. $-\frac{13}{25}$

**Answer**

a. $4$ (or $4.0$), terminating
b. $0.\overline{615384}$, repeating
c. $-0.85$, terminating

### Irrational Numbers

At some point in the ancient past, someone discovered that not all numbers are rational numbers. A builder, for instance, may have found that the diagonal of a square with unit sides was not $2$ or even $32$, but was something else. Or a garment maker might have observed that the ratio of the circumference to the diameter of a roll of cloth was a little bit more than $3$, but still not a rational number. Such numbers are said to be irrational because they cannot be written as fractions. These numbers make up the set of irrational numbers. Irrational numbers cannot be expressed as a fraction of two integers. It is impossible to describe this set of numbers by a single rule except to say that a number is irrational if it is not rational. So we write this as shown.

$$\{h \mid h \text{ is not a rational number}\} \tag{1.2.1}$$

**Example 1.2.3: Differentiating Rational and Irrational Numbers**

Determine whether each of the following numbers is rational or irrational. If it is rational, determine whether it is a terminating or repeating decimal.

a. $\sqrt{25}$
b. $\frac{33}{9}$
c. $\sqrt{11}$
d. $\frac{17}{34}$
e. $0.3033033303333\ldots$

**Solution**

a. $\sqrt{25}$: This can be simplified as $\sqrt{25} = 5$. Therefore, $\sqrt{25}$ is rational.
b. $\frac{33}{9}$: Because it is a fraction, $\frac{33}{9}$ is a rational number. Next, simplify and divide.

$$\frac{33}{9} = \frac{33}{9\!\!\!/}$$

So, $\frac{33}{9}$ is rational and a repeating decimal.

c. $\sqrt{11}$: This cannot be simplified any further. Therefore, $\sqrt{11}$ is an irrational number.
d. $\frac{17}{34}$: Because it is a fraction, $\frac{17}{34}$ is a rational number. Simplify and divide.

$$\frac{17}{34} = 0.5$$

So, $\frac{17}{34}$ is rational and a terminating decimal.
e. $0.3033033033333\ldots$ is not a terminating decimal. Also note that there is no repeating pattern because the group of $3s$ increases each time. Therefore it is neither a terminating nor a repeating decimal and, hence, not a rational number. It is an irrational number.

**? Exercise 1.2.3**

Determine whether each of the following numbers is rational or irrational. If it is rational, determine whether it is a terminating or repeating decimal.

a. $\frac{7}{77}$
b. $\sqrt{81}$
c. $4.27027002700027\ldots$
d. $\frac{91}{13}$
e. $\sqrt{39}$

**Answer**

a. rational and repeating;
b. rational and terminating;
c. irrational;
d. rational and terminating;
e. irrational

## Real Numbers

Given any number $n$, we know that $n$ is either rational or irrational. It cannot be both. The sets of rational and irrational numbers together make up the set of real numbers. As we saw with integers, the real numbers can be divided into three subsets: negative real numbers, zero, and positive real numbers. Each subset includes fractions, decimals, and irrational numbers according to their algebraic sign (+ or –). Zero is considered neither positive nor negative.

The real numbers can be visualized on a horizontal number line with an arbitrary point chosen as 0, with negative numbers to the left of 0 and positive numbers to the right of 0. A fixed unit distance is then used to mark off each integer (or other basic value) on either side of 0. Any real number corresponds to a unique position on the number line.The converse is also true: Each location on the number line corresponds to exactly one real number. This is known as a one-to-one correspondence. We refer to this as the real number line as shown in Figure (1.2.1.




Figure 1.2.1: The real number line.

**✓ Example 1.2.4: Classifying Real Numbers**

Classify each number as either positive or negative and as either rational or irrational. Does the number lie to the left or the right of 0 on the number line?

a. $-\frac{10}{3}$
b. $\sqrt{5}$
c. $-\sqrt{289}$
d. $-6\pi$
e. $0.615384615384\ldots$

**Solution**

a. $-\frac{10}{3}$ is negative and rational. It lies to the left of 0 on the number line.
b. $\sqrt{5}$ is positive and irrational. It lies to the right of 0.
c. $-\sqrt{289} = -\sqrt{17^2} = -17$ is negative and rational. It lies to the left of 0.
d. $-6\pi$ is negative and irrational. It lies to the left of 0.
e. $0.615384615384\ldots$ is a repeating decimal so it is rational and positive. It lies to the right of 0.

**? Exercise 1.2.4**

Classify each number as either positive or negative and as either rational or irrational. Does the number lie to the left or the right of 0 on the number line?

a. $\sqrt{73}$
b. $-11.411411411\ldots$
c. $\frac{47}{19}$
d. $-\frac{\sqrt{5}}{2}$

e. $6.210735$

**Answer**

a. positive, irrational; right
b. negative, rational; left
c. positive, rational; right
d. negative, irrational; left
e. positive, rational; right

### Sets of Numbers as Subsets

Beginning with the natural numbers, we have expanded each set to form a larger set, meaning that there is a subset relationship between the sets of numbers we have encountered so far. These relationships become more obvious when seen as a diagram, such as Figure(1.2.2).





Figure 1.2.2: Sets of numbers. **N**: the set of natural numbers. **W**: the set of whole numbers. **I**: the set of integers. **Q**: the set of rational numbers. **Q′**: the set of irrational numbers

**SETS OF NUMBERS**

The set of natural numbers includes the numbers used for counting: $\{1, 2, 3, \dots\}$.

The set of whole numbers is the set of natural numbers plus zero: $\{0, 1, 2, 3, \dots\}$

The set of integers adds the negative natural numbers to the set of whole numbers: $\{\dots, -3, -2, -1, 0, 1, 2, 3, \dots\}$

The set of rational numbers includes fractions written as $\{\frac{m}{n} | \text{m and n are integers and } n \neq 0\}$ .

The set of irrational numbers is the set of numbers that are not rational, are nonrepeating, and are nonterminating: $\{h \parallel \text{h is not a rational number}\}$.

**Example 1.2.5: Differentiating the Sets of Numbers**

Classify each number as being a natural number (N), whole number (W), integer (I), rational number (Q), and/or irrational number (Q′).

a. $\sqrt{36}$
b. $\frac{8}{3}$
c. $\sqrt{73}$
d. $-6$
e. $3.2121121112\dots$

**Solution**

| | N | W | I | Q | Q' |
|---|---|---|---|---|---|
| a. $\sqrt{36} = 6$ | X | X | X | X | |
| b. $\frac{8}{3} = 2.\overline{6}$ | | | | X | |
| c. $\sqrt{73}$ | | | | | X |
| d. $-6$ | | | X | X | |
| e. 3.2121121112… | | | | | X |

**Exercise 1.2.5**

Classify each number as being a natural number (N), whole number (W), integer (I), rational number (Q), and/or irrational number (Q′).

a. $-\frac{35}{7}$

b. 0
c. $\sqrt{169}$
d. $\sqrt{24}$
e. $4.763763763\ldots$

**Answer**

| | N | W | I | Q | Q' |
|---|---|---|---|---|---|
| a. $-\frac{35}{7}$ | | | X | X | |
| b. 0 | | X | X | X | |
| c. $\sqrt{169}$ | X | X | X | X | |
| d. $\sqrt{24}$ | | | | | X |
| e. $4.763763763\ldots$ | | | | X | |

## Performing Calculations Using the Order of Operations

When we multiply a number by itself, we square it or raise it to a power of 2. For example, $4^2 = 4 \times 4 = 16$ . We can raise any number to any power. In general, the exponential notation an means that the number or variable $a$ is used as a factor $n$ times.

$$a^n = a \cdot a \cdot a \cdots a \qquad \text{n factors}$$

In this notation, $a^n$ is read as the $n^{th}$ power of $a$, where $a$ is called the base and $n$ is called the exponent. A term in exponential notation may be part of a mathematical expression, which is a combination of numbers and operations. For example, $24 + 6 \times \frac{2}{3} - 4^2$ is a mathematical expression.

To evaluate a mathematical expression, we perform the various operations. However, we do not perform them in any random order. We use the order of operations. This is a sequence of rules for evaluating such expressions.

Recall that in mathematics we use parentheses ( ), brackets [ ], and braces { } to group numbers and expressions so that anything appearing within the symbols is treated as a unit. Additionally, fraction bars, radicals, and absolute value bars are treated as grouping symbols. When evaluating a mathematical expression, begin by simplifying expressions within grouping symbols.

The next step is to address any exponents or radicals. Afterward, perform multiplication and division from left to right and finally addition and subtraction from left to right.

Let's take a look at the expression provided.

$$24 + 6 \times \frac{2}{3} - 4^2$$

There are no grouping symbols, so we move on to exponents or radicals. The number 4 is raised to a power of 2, so simplify $4^2$ as 16.

$$24 + 6 \times \frac{2}{3} - 4^2$$

$$24 + 6 \times \frac{2}{3} - 16$$

Next, perform multiplication or division, left to right.

$$24 + 6 \times \frac{2}{3} - 16$$

$$24 + 4 - 16$$

Lastly, perform addition or subtraction, left to right.

$$24 + 4 - 16$$

$$28 - 16$$

$$12$$

Therefore,

$$24 + 6 \times \frac{2}{3} - 4^2 = 12$$

For some complicated expressions, several passes through the order of operations will be needed. For instance, there may be a radical expression inside parentheses that must be simplified before the parentheses are evaluated. Following the order of operations ensures that anyone simplifying the same mathematical expression will get the same result.

## ORDER OF OPERATIONS

Operations in mathematical expressions must be evaluated in a systematic order, which can be simplified using the acronym **PEMDAS**:

- **P**(arentheses)
- **E**(xponents)
- **M**(ultiplication) and **D**(ivision)
- **A**(ddition) and **S**(ubtraction)

## HOW TO: Given a mathematical expression, simplify it using the order of operations.

1. Simplify any expressions within grouping symbols.
2. Simplify any expressions containing exponents or radicals.
3. Perform any multiplication and division in order, from left to right.
4. Perform any addition and subtraction in order, from left to right.

## Example 1.2.6: Using the Order of Operations

Use the order of operations to evaluate each of the following expressions.

a. $(3\times 2)^2-4\times(6+2)$

b. $\dfrac{5^2-4}{7}-\sqrt{11-2}$

c. $6-|\,5-8\,|+3\times(4-1)$

d. $\dfrac{14-3\times 2}{2\times 5-3^2}$

e. $7\times(5\times 3)-2\times[(6-3)-4^2]+1$

**Solution**

a.

$$\begin{aligned}(3\times 2)^2-4\times(6+2) &= (6)^2-4\times(8) && \text{Simplify parentheses}\\ &= 36-4\times 8 && \text{Simplify exponent}\\ &= 36-32 && \text{Simplify multiplication}\\ &= 4 && \text{Simplify subtraction}\end{aligned}$$

b.

$$\begin{aligned}\frac{5^2-4}{7}-\sqrt{11-2} &= \frac{5^2-4}{7}-\sqrt{9} && \text{Simplify grouping symbols (radical)}\\ &= \frac{5^2-4}{7}-3 && \text{Simplify radical}\\ &= \frac{25-4}{7}-3 && \text{Simplify exponent}\\ &= \frac{21}{7}-3 && \text{Simplify subtraction in numerator}\\ &= 3-3 && \text{Simplify division}\\ &= 0 && \text{Simplify subtraction}\end{aligned}$$

Note that in the first step, the radical is treated as a grouping symbol, like parentheses. Also, in the third step, the fraction bar is considered a grouping symbol so the numerator is considered to be grouped.

c.

$$\begin{aligned}6-|\,5-8\,|+3\times(4-1) &= 6-|-3|+3\times 3 && \text{Simplify inside grouping symbols}\\ &= 6-3+3\times 3 && \text{Simplify absolute value}\\ &= 6-3+9 && \text{Simplify multiplication}\\ &= 3+9 && \text{Simplify subtraction}\\ &= 12 && \text{Simplify addition}\end{aligned}$$

d.

$$\begin{aligned}\frac{14-3\times 2}{2\times 5-3^2} &= \frac{14-3\times 2}{2\times 5-9} && \text{Simplify exponent}\\ &= \frac{14-6}{10-9} && \text{Simplify products}\\ &= \frac{8}{1} && \text{Simplify differences}\\ &= 8 && \text{Simplify quotient}\end{aligned}$$

In this example, the fraction bar separates the numerator and denominator, which we simplify separately until the last step.

e.

| | | |
|---|---|---|
| $7\times(5\times3)-2\times[(6-3)-4^2]+1$ | $=7\times(15)-2\times[(3)-4^2]+1$ | Simplify inside parentheses |
| | $=7\times(15)-2\times(3-16)+1$ | Simplify exponent |
| | $=7\times(15)-2\times(-13)+1$ | Subtract |
| | $=105+26+1$ | Multiply |
| | $=132$ | Add |

**? Exercise 1.2.6**

Use the order of operations to evaluate each of the following expressions.

a. $\sqrt{5^2-4^2}+7\times(5-4)^2$
b. $1+\dfrac{7\times5-8\times4}{9-6}$
c. $|1.8-4.3|+0.4\times\sqrt{15+10}$
d. $\dfrac{1}{2}\times[5\times3^2-7^2]+\dfrac{1}{3}\times9^2$
e. $[(3-8^2)-4]-(3-8)$

**Answer**

a. 10
b. 2
c. 4.5
d. 25
e. $-60$

## Using Properties of Real Numbers

For some activities we perform, the order of certain operations does not matter, but the order of other operations does. For example, it does not make a difference if we put on the right shoe before the left or vice-versa. However, it does matter whether we put on shoes or socks first. The same thing is true for operations in mathematics.

### Commutative Properties

The commutative property of addition states that numbers may be added in any order without affecting the sum.

$$a+b=b+a \tag{1.2.2}$$

We can better see this relationship when using real numbers.

$$(-2)+7=5 \text{ and } 7+(-2)=5$$

Similarly, the **commutative property of multiplication** states that numbers may be multiplied in any order without affecting the product.

$$a\times b=b\times a \tag{1.2.3}$$

Again, consider an example with real numbers.

$$(-11)\times(-4)=44 \text{ and } (-4)\times(-11)=44$$

It is important to note that neither subtraction nor division is commutative. For example, $17-5$ is not the same as $5-17$. Similarly, $20\div5\neq5\div20$.

### Associative Properties

The associative property of multiplication tells us that it does not matter how we group numbers when multiplying. We can move the grouping symbols to make the calculation easier, and the product remains the same.

$$a(bc)=(ab)c \tag{1.2.4}$$

Consider this example.

$$(3\times4)\times5=60 \text{ and } 3\times(4\times5)=60$$

The associative property of addition tells us that numbers may be grouped differently without affecting the sum.

$$a+(b+c)=(a+b)+c \tag{1.2.5}$$

This property can be especially helpful when dealing with negative integers. Consider this example.

$$[15+(-9)]+23=29 \text{ and } 15+[(-9)+23]=29$$

Are subtraction and division associative? Review these examples.

$$8-(3-15) \stackrel{?}{=} (8-3)-15$$
$$8-(-12) \stackrel{?}{=} 5-15$$
$$20 \neq 10$$
$$64 \div (8 \div 4) \stackrel{?}{=} (64 \div 8) \div 4$$
$$64 \div 2 \stackrel{?}{=} 8 \div 4$$
$$32 \neq 2$$

As we can see, neither subtraction nor division is associative.

### Distributive Property

The distributive property states that the product of a factor times a sum is the sum of the factor times each term in the sum.

$$a \times (b+c) = a \times b + a \times c \tag{1.2.6}$$

This property combines both addition and multiplication (and is the only property to do so). Let us consider an example.

$$\begin{aligned} 4 \cdot [12 + (-7)] &= 4 \cdot 12 + 4 \cdot (-7) \\ &= 48 + (-28) \\ &= 20 \end{aligned}$$

Note that $4$ is outside the grouping symbols, so we distribute the $4$ by multiplying it by $12$, multiplying it by $-7$, and adding the products.

**Example 1.2.7**

To be more precise when describing this property, we say that multiplication distributes over addition. The reverse is not true, as we can see in this example.

$$6+(3 \times 5) \stackrel{?}{=} (6+3) \times (6 \times 5)$$
$$6+(15) \stackrel{?}{=} (9) \times (11)$$
$$21 \neq 99$$

Multiplication does not distribute over subtraction, and division distributes over neither addition nor subtraction.

A special case of the distributive property occurs when a sum of terms is subtracted.

$$a-b = a+(-b) \tag{1.2.7}$$

For example, consider the difference $12-(5+3)$. We can rewrite the difference of the two terms $12$ and $(5+3)$ by turning the subtraction expression into addition of the opposite. So instead of subtracting $(5+3)$, we add the opposite.

$$12+(-1) \times (5+3)$$

Now, distribute $-1$ and simplify the result.

$$\begin{aligned} 12-(5+3) &= 12+(-1) \times (5+3) \\ &= 12+[(-1) \times 5+(-1) \times 3] \\ &= 12+(-8) \\ &= 4 \end{aligned}$$

This seems like a lot of trouble for a simple sum, but it illustrates a powerful result that will be useful once we introduce algebraic terms. To subtract a sum of terms, change the sign of each term and add the results. With this in mind, we can rewrite the last example.

$$\begin{aligned} 12-(5+3) &= 12+(-5-3) \\ &= 12-8 \\ &= 4 \end{aligned}$$

### Identity Properties

The **identity property of addition** states that there is a unique number, called the additive identity $(0)$ that, when added to a number, results in the original number.

$$a+0 = a \tag{1.2.8}$$

The **identity property of multiplication** states that there is a unique number, called the multiplicative identity $(1)$ that, when multiplied by a number, results in the original number.

$$a \times 1 = a \tag{1.2.9}$$

For example, we have $(-6)+0 = -6$ and $23 \times 1 = 23$. There are no exceptions for these properties; they work for every real number, including $0$ and $1$.

### Inverse Properties

The inverse property of addition states that, for every real number a, there is a unique number, called the additive inverse (or opposite), denoted $-a$, that, when added to the original number, results in the additive identity, $0$.

$$a+(-a)=0 \tag{1.2.10}$$

For example, if $a=-8$, the additive inverse is 8, since $(-8)+8=0$.

The inverse property of multiplication holds for all real numbers except 0 because the reciprocal of 0 is not defined. The property states that, for every real number $a$, there is a unique number, called the multiplicative inverse (or reciprocal), denoted $1a$, that, when multiplied by the original number, results in the multiplicative identity, 1.

$$a\times\frac{1}{a}=1 \tag{1.2.11}$$

For example, if $a=-\frac{2}{3}$, the reciprocal, denoted $\frac{1}{a}$, is $-\frac{3}{2}$ because

$$a\cdot\frac{1}{a}=\left(-\frac{2}{3}\right)\times\left(-\frac{3}{2}\right)=1$$

**PROPERTIES OF REAL NUMBERS**

The following properties hold for real numbers $a$, $b$, and $c$.

Table 1.2.1

| | Addition | Multiplication |
|---|---|---|
| Commutative Property | $a+b=b+a$ | $a\times b=b\times a$ |
| Associative Property | $a+(b+c)=(a+b)+c$ | $a(bc)=(ab)c$ |
| Distributive Property | $a\times(b+c)=a\times b+a\times c$ | |
| Identity Property | There exists a unique real number called the additive identity, 0, such that, for any real number a $a+0=a$ | |

There exists a unique real number called the multiplicative identity, 1, such that, for any real number a

$$a\times 1=a$$

Inverse Property

Every real number a has an additive inverse, or opposite, denoted –a, such that

$$a+(-a)=0$$

Every nonzero real number a has a multiplicative inverse, or reciprocal, denoted 1a , such that

$$a\times\left(\frac{1}{a}\right)=1$$

**Example 1.2.8: Using Properties of Real Numbers**

Use the properties of real numbers to rewrite and simplify each expression. State which properties apply.

a. $3\times6+3\times4$
b. $(5+8)+(-8)$
c. $6-(15+9)$
d. $\frac{4}{7}\times\left(\frac{2}{3}\times\frac{7}{4}\right)$
e. $100\times[0.75+(-2.38)]$

**Solution**

a.

$$\begin{aligned} 3\times6+3\times4 &= 3\times(6+4) && \text{Distributive property}\\ &= 3\times10 && \text{Simplify}\\ &= 30 && \text{Simplify}\end{aligned}$$

b.

$$\begin{aligned} (5+8)+(-8) &= 5+[8+(-8)] && \text{Associative property of addition}\\ &= 5+0 && \text{Inverse property of addition}\\ &= 5 && \text{Identity property of addition}\end{aligned}$$

c.

$$\begin{aligned} 6-(15+9) &= 6+[(-15)+(-9)] && \text{Distributive property}\\ &= 6+(-24) && \text{Simplify}\\ &= -18 && \text{Simplify}\end{aligned}$$

d.

$$\begin{aligned}
\frac{4}{7}\times\left(\frac{2}{3}\times\frac{7}{4}\right) &= \frac{4}{7}\times\left(\frac{7}{4}\times\frac{2}{3}\right) && \text{Commutative property of multiplication}\\
&= \left(\frac{4}{7}\times\frac{7}{4}\right)\times\frac{2}{3} && \text{Associative property of multiplication}\\
&= 1\times\frac{2}{3} && \text{Inverse property of multiplication}\\
&= \frac{2}{3} && \text{Identity property of multiplication}
\end{aligned}$$

e.

$$\begin{aligned}
100\times[0.75+(-2.38)] &= 100\times 0.75+100\times(-2.38) && \text{Distributive property}\\
&= 75+(-238) && \text{Simplify}\\
&= -163 && \text{Simplify}
\end{aligned}$$

**? Exercise 1.2.7**

Use the properties of real numbers to rewrite and simplify each expression. State which properties apply.

a. $\left(-\frac{23}{5}\right)\times\left[11\times\left(-\frac{5}{23}\right)\right]$
b. $5\times(6.2+0.4)$
c. $18-(7-15)$
d. $\frac{17}{18}+\left[\frac{4}{9}+\left(-\frac{17}{18}\right)\right]$
e. $6\times(-3)+6\times 3$

**Answer**

1. $11$, commutative property of multiplication
2. $33$, distributive property
3. $26$, distributive property
4. $\frac{4}{9}$, commutative property of addition, associative property of addition, inverse property of addition, identity property of addition
5. $0$, distributive property, inverse property of addition, identity property of addition

## Evaluating Algebraic Expressions

So far, the mathematical expressions we have seen have involved real numbers only. In mathematics, we may see expressions such as $x+5$, $\frac{4}{3}\pi r^3$, or $\sqrt{2m^3n^2}$. In the expression $x+5$, $5$ is called a **constant** because it does not vary and $x$ is called a **variable** because it does. (In naming the variable, ignore any exponents or radicals containing the variable.) An **algebraic expression** is a collection of constants and variables joined together by the algebraic operations of addition, subtraction, multiplication, and division.

We have already seen some real number examples of exponential notation, a shorthand method of writing products of the same factor. When variables are used, the constants and variables are treated the same way.

$$\begin{aligned}
(-3)^5 &= (-3)\times(-3)\times(-3)\times(-3)\times(-3) \Rightarrow x^5 = x\times x\times x\times x\times x\\
(2\times 7)^3 &= (2\times 7)\times(2\times 7)\times(2\times 7) \qquad \Rightarrow (yz)^3 = (yz)\times(yz)\times(yz)
\end{aligned}$$

In each case, the exponent tells us how many factors of the base to use, whether the base consists of constants or variables.

Any variable in an algebraic expression may take on or be assigned different values. When that happens, the value of the algebraic expression changes. To evaluate an algebraic expression means to determine the value of the expression for a given value of each variable in the expression. Replace each variable in the expression with the given value, then simplify the resulting expression using the order of operations. If the algebraic expression contains more than one variable, replace each variable with its assigned value and simplify the expression as before.

**✓ Example 1.2.9: Describing Algebraic Expressions**

List the constants and variables for each algebraic expression.

a. $x+5$
b. $\frac{4}{3}\pi r^3$
c. $\sqrt{2m^3n^2}$

**Solution**

| | Constants | Variables |
|---|---|---|
| a. $x+5$ | $5$ | $x$ |
| b. $\frac{4}{3}\pi r^3$ | $\frac{4}{3}, \pi$ | $r$ |
| c. $\sqrt{2m^3n^2}$ | $2$ | $m,n$ |

**? Exercise 1.2.8**

List the constants and variables for each algebraic expression.

a. $2(L+W)$
b. $4y^3+y$

**Answer**

| | Constants | Variables |
|---|---|---|
| a. $2\pi r(r+h)$ | $2,\pi$ | $r,h$ |
| b. $2(L+W)$ | $2$ | $L, W$ |
| c. $4y^3+y$ | $4$ | $y$ |

**✓ Example 1.2.10: Evaluating an Algebraic Expression at Different Values**

Evaluate the expression $2x-7$ for each value for $x$.

a. $x=0$
b. $x=1$
c. $x=12$
d. $x=-4$

**Solution**

a. Substitute $0$ for $x$.

$$\begin{aligned} 2x-7 &= 2(0)-7 \\ &= 0-7 \\ &= -7 \end{aligned}$$

b. Substitute $1$ for $x$.

$$\begin{aligned} 2x-7 &= 2(1)-7 \\ &= 2-7 \\ &= -5 \end{aligned}$$

c. Substitute $\frac{1}{2}$ for $x$.

$$\begin{aligned} 2x-7 &= 2\left(\frac{1}{2}\right)-7 \\ &= 1-7 \\ &= -6 \end{aligned}$$

d. Substitute $-4$ for $x$.

$$\begin{aligned} 2x-7 &= 2(-4)-7 \\ &= -8-7 \\ &= -15 \end{aligned}$$

**? Exercise 1.2.9**

Evaluate the expression $11-3y$ for each value for $y$.

a. $y=2$
b. $y=0$
c. $y=\frac{2}{3}$
d. $y=-5$

**Answer**

1. 11
2. 26

**Example 1.2.11: Evaluating Algebraic Expressions**

Evaluate each expression for the given values.

a. $x+5$ for $x=-5$
b. $\dfrac{t}{2t-1}$ for $t=10$
c. $\dfrac{4}{3}\pi r^3$ for $r=5$
d. $a+ab+b$ for $a=11, b=-8$
e. $\sqrt{2m^3n^2}$ for $m=2, n=3$

Solution

a. Substitute $-5$ for $x$.

$$\begin{aligned} x+5 &= (-5)+5 \\ &= 0 \end{aligned}$$

b. Substitute $10$ for $t$.

$$\begin{aligned} \frac{t}{2t-1} &= \frac{(10)}{2(10)-1} \\ &= \frac{10}{20-1} \\ &= \frac{10}{19} \end{aligned}$$

c. Substitute $5$ for $r$.

$$\begin{aligned} \frac{4}{3}\pi r^3 &= \frac{4}{3}\pi(5)^3 \\ &= \frac{4}{3}\pi(125) \\ &= \frac{500}{3}\pi \end{aligned}$$

d. Substitute $11$ for $a$ and $-8$ for $b$.

$$\begin{aligned} a+ab+b &= (11)+(11)(-8)+(-8) \\ &= 11-88-8 \\ &= -85 \end{aligned}$$

e. Substitute $2$ for $m$ and $3$ for $n$.

$$\begin{aligned} \sqrt{2m^3n^2} &= \sqrt{2(2)^3(3)^2} \\ &= \sqrt{2(8)(9)} \\ &= \sqrt{144} \\ &= 12 \end{aligned}$$

**? Exercise 1.2.10**

Evaluate each expression for the given values.

a. $\dfrac{y+3}{y-3}$ for $y=5$

b. $7-2t$ for $t=-2$

c. $\dfrac{1}{3}\pi r^2$ for $r=11$

d. $(p^2q)^3$ for $p=-2, q=3$

e. $4(m-n)-5(n-m)$ for $m=\dfrac{2}{3}$ $n=\dfrac{1}{3}$

**Answer**

a. 4
b. 11
c. $\dfrac{121}{3}\pi$
d. 1728
e. 3

## Formulas

An equation is a mathematical statement indicating that two expressions are equal. The expressions can be numerical or algebraic. The equation is not inherently true or false, but only a proposition. The values that make the equation true, the solutions, are found using the properties of real numbers and other results. For example, the equation $2x+1=7$ has the unique solution of 3 because when we substitute 3 for $x$ in the equation, we obtain the true statement $2(3)+1=7$.

A formula is an equation expressing a relationship between constant and variable quantities. Very often, the equation is a means of finding the value of one quantity (often a single variable) in terms of another or other quantities. One of the most common examples is the formula for finding the area $A$ of a circle in terms of the radius $r$ of the circle: $A=\pi r^2$. For any value of $r$, the area $A$ can be found by evaluating the expression $\pi r^2$.

**✓ Example 1.2.12: Using a Formula**

A right circular cylinder with radius $r$ and height $h$ has the surface area $S$ (in square units) given by the formula $S=2\pi r(r+h)$. See Figure 1.2.3. Find the surface area of a cylinder with radius 6 in. and height 9 in. Leave the answer in terms of $\pi$.





Figure 1.2.3

Evaluate the expression $2\pi r(r+h)$ for $r=6$ and $h=9$.

Solution

$$\begin{aligned} S &= 2\pi r(r+h) \\ &= 2\pi(6)[(6)+(9)] \\ &= 2\pi(6)(15) \\ &= 180\pi \end{aligned}$$

The surface area is $180\pi$ square inches.

**Exercise 1.2.11**

A photograph with length $L$ and width $W$ is placed in a matte of width 8 centimeters (cm). The area of the matte (in square centimeters, or $cm^2$ is found to be $A = (L + 16)(W + 16) - L \cdot W$. See Figure 1.2.4. Find the area of a matte for a photograph with length 32cm and width 24cm.





Figure 1.2.4

**Answer**

$1152cm^2$

## Simplifying Algebraic Expressions

Sometimes we can simplify an algebraic expression to make it easier to evaluate or to use in some other way. To do so, we use the properties of real numbers. We can use the same properties in formulas because they contain algebraic expressions.

**Example 1.2.13: Simplifying Algebraic Expressions**

Simplify each algebraic expression.

a. $3x - 2y + x - 3y - 7$

b. $2r - 5(3 - r) + 4$

c. $\left(4t - \frac{5}{4}s\right) - \left(\frac{2}{3}t + 2s\right)$

d. $2mn - 5m + 3mn + n$

Solution

a.
$$\begin{aligned} 3x - 2y + x - 3y - 7 &= 3x + x - 2y - 3y - 7 && \text{Commutative property of addition} \\ &= 4x - 5y - 7 && \text{Simplify} \end{aligned}$$

b.
$$\begin{aligned} 2r - 5(3 - r) + 4 &= 2r - 15 + 5r + 4 && \text{Distributive property} \\ &= 2r + 5y - 15 + 4 && \text{Commutative property of addition} \\ &= 7r - 11 && \text{Simplify} \end{aligned}$$

c.
$$\begin{aligned} \left(4t - \frac{5}{4}s\right) - \left(\frac{2}{3}t + 2s\right) &= 4t - \frac{5}{4}s - \frac{2}{3}t - 2s && \text{Distributive property} \\ &= 4t - \frac{2}{3}t - \frac{5}{4}s - 2s && \text{Commutative property of addition} \\ &= \frac{10}{3}t - \frac{13}{4}s && \text{Simplify} \end{aligned}$$

d.
$$\begin{aligned} 2mn - 5m + 3mn + n &= 2mn + 3mn - 5m + n && \text{Commutative property of addition} \\ &= 5mn - 5m + n && \text{Simplify} \end{aligned}$$

**Exercise 1.2.12**

Simplify each algebraic expression.

a. $\frac{2}{3}y - 2\left(\frac{4}{3}y + z\right)$

b. $\frac{5}{t} - 2 - \frac{3}{t} + 1$

c. $4p(q-1) + q(1-p)$

d. $9r - (s + 2r) + (6 - s)$

**Answer**

a. $-2y - 2z$ or $-2(y+z)$

b. $\frac{2}{t} - 1$

c. $3pq - 4p + q$

d. $7r - 2s + 6$

**Example 1.2.14: Simplifying a Formula**

A rectangle with length $L$ and width $W$ has a perimeter $P$ given by $P = L + W + L + W$ . Simplify this expression.

**Solution**

| | |
|---|---|
| $P = L + W + L + W$ | |
| $P = L + L + W + W$ | Commutative property of addition |
| $P = 2L + 2W$ | Simplify |
| $P = 2(L + W)$ | Distributive property |

**Exercise 1.2.13**

If the amount $P$ is deposited into an account paying simple interest $r$ for time $t$, the total value of the deposit $A$ is given by $A = P + Prt$. Simplify the expression. (This formula will be explored in more detail later in the course.)

**Answer**

$A = P(1 + rt)$

Access these online resources for additional instruction and practice with real numbers.

- Simplify an Expression
- Evaluate an Expression1
- Evaluate an Expression2

## Key Concepts

- Rational numbers may be written as fractions or terminating or repeating decimals. See Example and Example.
- Determine whether a number is rational or irrational by writing it as a decimal. See Example.
- The rational numbers and irrational numbers make up the set of real numbers. See Example. A number can be classified as natural, whole, integer, rational, or irrational. See Example.
- The order of operations is used to evaluate expressions. See Example.
- The real numbers under the operations of addition and multiplication obey basic rules, known as the properties of real numbers. These are the commutative properties, the associative properties, the distributive property, the identity properties, and the inverse properties. See Example.
- Algebraic expressions are composed of constants and variables that are combined using addition, subtraction, multiplication, and division. See Example. They take on a numerical value when evaluated by replacing variables with constants. See Example,Example, and Example
- Formulas are equations in which one quantity is represented in terms of other quantities. They may be simplified or evaluated as any mathematical expression. See Example and Example.

## Glossary

**algebraic expression**

constants and variables combined using addition, subtraction, multiplication, and division

**associative property of addition**

the sum of three numbers may be grouped differently without affecting the result; in symbols,a+(b+c)=(a+b)+c

**associative property of multiplication**
the product of three numbers may be grouped differently without affecting the result; in symbols,$a \cdot (b \cdot c) = (a \cdot b) \cdot c$

**base**
in exponential notation, the expression that is being multiplied

**commutative property of addition**
two numbers may be added in either order without affecting the result; in symbols,$a+b=b+a$

**commutative property of multiplication**
two numbers may be multiplied in any order without affecting the result; in symbols,$a \cdot b = b \cdot a$

**constant**
a quantity that does not change value

**distributive property**
the product of a factor times a sum is the sum of the factor times each term in the sum; in symbols,$a \cdot (b+c) = a \cdot b + a \cdot c$

**equation**
a mathematical statement indicating that two expressions are equal

**exponent**
in exponential notation, the raised number or variable that indicates how many times the base is being multiplied

**exponential notation**
a shorthand method of writing products of the same factor

**formula**
an equation expressing a relationship between constant and variable quantities

**identity property of addition**
there is a unique number, called the additive identity, 0, which, when added to a number, results in the original number; in symbols,$a+0=a$

**identity property of multiplication**
there is a unique number, called the multiplicative identity, 1, which, when multiplied by a number, results in the original number; in symbols,$a \cdot 1 = a$

**integers**
the set consisting of the natural numbers, their opposites, and 0:$\{\ldots,-3,-2,-1,0,1,2,3,\ldots\}$

**inverse property of addition**
for every real numbera,there is a unique number, called the additive inverse (or opposite), denoted$-a$,which, when added to the original number, results in the additive identity, 0; in symbols,$a+(-a)=0$

**inverse property of multiplication**
for every non-zero real numbera,there is a unique number, called the multiplicative inverse (or reciprocal), denoted1a,which, when multiplied by the original number, results in the multiplicative identity, 1; in symbols,$a \cdot 1a = 1$

**irrational numbers**
the set of all numbers that are not rational; they cannot be written as either a terminating or repeating decimal; they cannot be expressed as a fraction of two integers

**natural numbers**
the set of counting numbers:$\{1,2,3,\ldots\}$

**order of operations**
a set of rules governing how mathematical expressions are to be evaluated, assigning priorities to operations

**rational numbers**
the set of all numbers of the formmn,wheremandnare integers and$n \neq 0$.Any rational number may be written as a fraction or a terminating or repeating decimal.

**real number line**
a horizontal line used to represent the real numbers. An arbitrary fixed point is chosen to represent 0; positive numbers lie to the right of 0 and negative numbers to the left.

**real numbers**
the sets of rational numbers and irrational numbers taken together

**variable**

a quantity that may change value

**whole numbers**

the set consisting of 0 plus the natural numbers:{0,1,2,3,…}

---

This page titled 1.2: Real Numbers - Algebra Essentials is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.1: Real Numbers - Algebra Essentials** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.2E: Real Numbers - Algebra Essentials (Exercises)

For the following exercises, perform the given operations.

1. $(5-3\cdot 2)^2-6$ ]

**Answer**

-5

2. $64\div(2\cdot 8)+14\div 7$

3. $2\cdot 5^2+6\div 2$

**Answer**

53

For the following exercises, solve the equation.

4. $5x+9=-11$

5. $2y+4^2=64$

**Answer**

$y=24$

For the following exercises, simplify the expression.

6. $9(y+2)\div 3\cdot 2+1$

7. $3m(4+7)-m$

**Answer**

32m

For the following exercises, identify the number as rational, irrational, whole, or natural. Choose the most descriptive answer.

8. 11

9. 0

**Answer**

whole

10. $\frac{5}{6}$

11. $\sqrt{11}$

**Answer**

irrational

This page titled 1.2E: Real Numbers - Algebra Essentials (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.1E: Real Numbers - Algebra Essentials (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.3: Exponents and Scientific Notation

**Learning Objectives**

- Various rules of Exponents
- Scientific Notation

Mathematicians, scientists, and economists commonly encounter very large and very small numbers. But it may not be obvious how common such figures are in everyday life. For instance, a pixel is the smallest unit of light that can be perceived and recorded by a digital camera. A particular camera might record an image that is $2,048$ pixels by $1,536$ pixels, which is a very high resolution picture. It can also perceive a color depth (gradations in colors) of up to $48$ bits per frame, and can shoot the equivalent of $24$ frames per second. The maximum possible number of bits of information used to film a one-hour ($3,600$-second) digital film is then an extremely large number.

Using a calculator, we enter $2,048 \times 1,536 \times 48 \times 24 \times 3,600$ and press ENTER. The calculator displays $1.304596316E13$ What does this mean? The "$E13$" portion of the result represents the exponent $13$ of ten, so there are a maximum of approximately $1.3 \times 10^{13}$ bits of data in that one-hour film. In this section, we review rules of exponents first and then apply them to calculations involving very large or small numbers.

## Using the Product Rule of Exponents

Consider the product $x^3 \times x^4$. Both terms have the same base, $x$, but they are raised to different exponents. Expand each expression, and then rewrite the resulting expression.

$$\begin{aligned} x^3 \times x^4 &= \overbrace{x \times x \times x}^{3 \text{ factors}} \times \overbrace{x \times x \times x \times x}^{4 \text{ factors}} \\ &= \overbrace{x \times x \times x \times x \times x \times x \times x}^{7 \text{ factors}} \\ &= x^7 \end{aligned}$$

The result is that $x^3 \times x^4 = x^{3+4} = x^7$.

Notice that the exponent of the product is the sum of the exponents of the terms. In other words, when multiplying exponential expressions with the same base, we write the result with the common base and add the exponents. This is the product rule of exponents.

$$a^m \times a^n = a^{m+n} \tag{1.3.1}$$

Now consider an example with real numbers.

$$2^3 \times 2^4 = 2^{3+4} = 2^7$$

We can always check that this is true by simplifying each exponential expression. We find that $2^3$ is $8$, $2^4$ is $16$, and $2^7$ is $128$. The product $8 \times 16$ equals $128$, so the relationship is true. We can use the product rule of exponents to simplify expressions that are a product of two numbers or expressions with the same base but different exponents.

**THE PRODUCT RULE OF EXPONENTS**

For any real number a and natural numbers $m$ and $n$, the product rule of exponents states that

$$a^m \times a^n = a^{m+n} \tag{1.3.2}$$

**Example 1.3.1: Using the Product Rule**

Write each of the following products with a single base. Do not simplify further.

a. $t^5 \times t^3$
b. $(-3)^5 \times (-3)$
c. $x^2 \times x^5 \times x^3$

**Solution**

Use the product rule (Equation 1.3.2) to simplify each expression.

a. $t^5 \times t^3 = t^{5+3} = t^8$
b. $(-3)^5 \times (-3) = (-3)^5 \times (-3)^1 = (-3)^{5+1} = (-3)^6$
c. $x^2 \times x^5 \times x^3$

At first, it may appear that we cannot simplify a product of three factors. However, using the associative property of multiplication, begin by simplifying the first two.

$$x^2 \times x^5 \times x^3 = (x^2 \times x^5) \times x^3 = (x^{2+5}) \times x^3 = x^7 \times x^3 = x^{7+3} = x^{10}$$

Notice we get the same result by adding the three exponents in one step.

$$x^2 \times x^5 \times x^3 = x^{2+5+3} = x^{10}$$

**? Exercise 1.3.1**

Write each of the following products with a single base. Do not simplify further.

a. $k^6 \times k^9$
b. $\left(\frac{2}{y}\right)^4 \times \left(\frac{2}{y}\right)$
c. $t^3 \times t^6 \times t^5$

**Answer a**

$k^{15}$

**Answer b**

$\left(\frac{2}{y}\right)^5$

**Answer c**

$t^{14}$

## Using the Quotient Rule of Exponents

The quotient rule of exponents allows us to simplify an expression that divides two numbers with the same base but different exponents. In a similar way to the product rule, we can simplify an expression such as $\frac{y^m}{y^n}$, where $m > n$. Consider the example $\frac{y^9}{y^5}$. Perform the division by canceling common factors.

$$\begin{aligned} \frac{y^9}{y^5} &= \frac{y \cdot y \cdot y \cdot y \cdot y \cdot y \cdot y \cdot y \cdot y}{y \cdot y \cdot y \cdot y \cdot y} \\ &= \frac{y \cdot y \cdot y \cdot y}{1} \\ &= y^4 \end{aligned}$$

Notice that the exponent of the quotient is the difference between the exponents of the divisor and dividend.

$$\frac{a^m}{a^n} = a^{m-n} \tag{1.3.3}$$

In other words, when dividing exponential expressions with the same base, we write the result with the common base and subtract the exponents.

$$\frac{y^9}{y^5} = y^{9-5} = y^4$$

For the time being, we must be aware of the condition $m > n$. Otherwise, the difference $m - n$ could be zero or negative. Those possibilities will be explored shortly. Also, instead of qualifying variables as nonzero each time, we will simplify matters and assume from here on that all variables represent nonzero real numbers.

### THE QUOTIENT RULE OF EXPONENTS

For any real number $a$ and natural numbers $m$ and $n$, such that $m > n$, the quotient rule of exponents states that

$$\frac{a^m}{a^n} = a^{m-n} \tag{1.3.4}$$

### Example 1.3.2: Using the Quotient Rule

Write each of the following products with a single base. Do not simplify further.

a. $\dfrac{(-2)^{14}}{(-2)^9}$
b. $\dfrac{t^{23}}{t^{15}}$
c. $\dfrac{(z\sqrt{2})^5}{z\sqrt{2}}$

**Solution**

Use the quotient rule (Equation 1.3.4) to simplify each expression.

a. $\dfrac{(-2)^{14}}{(-2)^9} = (-2)^{14-9} = (-2)^5$
b. $\dfrac{t^{23}}{t^{15}}$=t^{23−15}=t^8\)
c. $\dfrac{(z\sqrt{2})^5}{z\sqrt{2}} = (z\sqrt{2})^{5-1} = (z\sqrt{2})^4$

### Exercise 1.3.2

Write each of the following products with a single base. Do not simplify further.

a. $\dfrac{s^{75}}{s^{68}}$
b. $\dfrac{(-3)^6}{-3}$
c. $\dfrac{(ef^2)^5}{(ef^2)^3}$

**Answer a**

$s^7$

**Answer b**

$(-3)^5$

**Answer c**

$(ef^2)^2$

## Using the Power Rule of Exponents

Suppose an exponential expression is raised to some power. Can we simplify the result? Yes. To do this, we use the power rule of exponents. Consider the expression $(x^2)^3$. The expression inside the parentheses is multiplied twice because it has an exponent of 2. Then the result is multiplied three times because the entire expression has an exponent of 3.

$$\begin{aligned}(x^2)^3 &= (x^2)\times(x^2)\times(x^2)\\ &= x\times x\times x\times x\times x\times x\\ &= x^6\end{aligned}$$

The exponent of the answer is the product of the exponents: $(x^2)^3 = x^{2\cdot 3} = x^6$ . In other words, when raising an exponential expression to a power, we write the result with the common base and the product of the exponents.

$$(a^m)^n = a^{m\cdot n} \tag{1.3.5}$$

Be careful to distinguish between uses of the product rule and the power rule. When using the product rule, different terms with the same bases are raised to exponents. In this case, you add the exponents. When using the power rule, a term in exponential notation is raised to a power. In this case, you multiply the exponents.

Table 1.3.1

| Product Rule | Power Rule |
|---|---|
| $5^3\times 5^4 = 5^{3+4} = 5^7$ | $(5^3)^4 = 5^{3\times 4} = 5^{12}$ |
| $x^5\times x^2 = x^{5+2} = x^7$ | $(x^5)^2 = x^{5\times 2} = x^{10}$ |
| $(3a)^7\times(3a)^{10} = (3a)^{7+10} = (3a)^{17}$ | $((3a)^7)^{10} = (3a)^{7\times 10} = (3a)^{70}$ |

### THE POWER RULE OF EXPONENTS

For any real number a and positive integers m and n, the power rule of exponents states that

$$(a^m)^n = a^{m\cdot n} \tag{1.3.6}$$

### Example 1.3.3: Using the Power Rule

Write each of the following products with a single base. Do not simplify further.

a. $(x^2)^7$
b. $((2t)^5)^3$
c. $((-3)^5)^{11}$

**Solution**

Use the power rule (Equation 1.3.6) to simplify each expression.

a. $(x^2)^7 = x^{2\cdot 7} = x^{14}$
b. $((2t)^5)^3 = (2t)^{5\cdot 3} = (2t)^{15}$
c. $((-3)^5)^{11} = (-3)^{5\cdot 11} = (-3)^{55}$

### Exercise 1.3.3

Write each of the following products with a single base. Do not simplify further.

a. $((3y)^8)^3$
b. $(t^5)^7$
c. $((-g)^4)^4$

**Answer a**

$(3y)^{24}$

**Answer b**

$t^{35}$

**Answer c**

$(-g)^{16}$

## Using the Zero Exponent Rule of Exponents

Return to the quotient rule. We made the condition that $m > n$ so that the difference $m - n$ would never be zero or negative. What would happen if $m = n$ ? In this case, we would use the zero exponent rule of exponents to simplify the expression to 1. To see how this is done, let us begin with an example.

$$\frac{t^8}{t^8} = 1$$

If we were to simplify the original expression using the quotient rule, we would have

$$\frac{t^8}{t^8} = t^{8-8} = t^0$$

If we equate the two answers, the result is $t^0 = 1$. This is true for any nonzero real number, or any variable representing a real number.

$$a^0 = 1$$

The sole exception is the expression $0^0$. This appears later in more advanced courses, but for now, we will consider the value to be undefined.

**THE ZERO EXPONENT RULE OF EXPONENTS**

For any nonzero real number a, the zero exponent rule of exponents states that

$$a^0 = 1 \tag{1.3.7}$$

**Example 1.3.4: Using the Zero Exponent Rule**

Simplify each expression using the zero exponent rule of exponents.

a. $\frac{c^3}{c^3}$
b. $\frac{-3x^5}{x^5}$
c. $\frac{(j^2k)^4}{(j^2k) \times (j^2k)^3}$
d. $\frac{5(rs^2)^2}{(rs^2)^2}$

**Solution**

Use the zero exponent and other rules to simplify each expression.

a.

$$\begin{aligned}\frac{c^3}{c^3} &= c^{3-3}\\ &= c^0\\ &= 1\end{aligned}$$

b.

$$\begin{aligned}\frac{-3x^5}{x^5} &= -3 \times \frac{x^5}{x^5}\\ &= -3 \times x^{5-5}\\ &= -3 \times x^0\\ &= -3 \times 1\\ &= -3\end{aligned}$$

c.

$$\begin{aligned}\frac{(j^2k)^4}{(j^2k) \times (j^2k)^3} &= \frac{(j^2k)^4}{(j^2k)^{1+3}} && \text{Use the product rule in the denominator}\\ &= \frac{(j^2k)^4}{(j^2k)^4} && \text{Simplify}\\ &= (j^2k)^{4-4} && \text{Use the quotient rule}\\ &= (j^2k)^0 && \text{Simplify}\\ &= 1\end{aligned}$$

d.

$$\begin{aligned}\frac{5(rs^2)^2}{(rs^2)^2} &= 5(rs^2)^{2-2} && \text{Use the quotient rule}\\ &= 5(rs^2)^0 && \text{Simplify}\\ &= 5 \times 1 && \text{Use the zero exponent rule}\\ &= 5 && \text{Simplify}\end{aligned}$$

## Exercise 1.3.4

Simplify each expression using the zero exponent rule of exponents.

a. $\frac{t^7}{t^7}$

b. $\frac{(de^2)^{11}}{2(de^2)^{11}}$

c. $\frac{w^4 \times w^2}{w^6}$

d. $\frac{t^3 \times t^4}{t^2 \times t^5}$

**Answer a**

1

**Answer b**

$\frac{1}{2}$

**Answer c**

1

**Answer d**

1

## Using the Negative Rule of Exponents

Another useful result occurs if we relax the condition that $m > n$ in the quotient rule even further. For example, can we simplify $\frac{t^3}{t^5}$? When $m < n$ —that is, where the difference $m - n$ is negative—we can use the negative rule of exponents to simplify the expression to its reciprocal.

Divide one exponential expression by another with a larger exponent. Use our example, $\frac{t^3}{t^5}$.

$$\begin{aligned}\frac{t^3}{t^5} &= \frac{t \times t \times t}{t \times t \times t \times t \times t} \\ &= \frac{1}{t \times t} \\ &= \frac{1}{h^2}\end{aligned}$$

If we were to simplify the original expression using the quotient rule, we would have

$$\begin{aligned}\frac{t^3}{t^5} &= h^{3-5} \\ &= h^{-2}\end{aligned}$$

Putting the answers together, we have $h^{-2} = \frac{1}{h^2}$. This is true for any nonzero real number, or any variable representing a nonzero real number.

A factor with a negative exponent becomes the same factor with a positive exponent if it is moved across the fraction bar—from numerator to denominator or vice versa.

$$a^{-n} = \frac{1}{a^n} \text{ and } a^n = \frac{1}{a^{-n}}$$

We have shown that the exponential expression an is defined when $n$ is a natural number, $0$, or the negative of a natural number. That means that an is defined for any integer $n$. Also, the product and quotient rules and all of the rules we will look at soon hold for any integer $n$.

### THE NEGATIVE RULE OF EXPONENTS

For any nonzero real number a and natural number n, the negative rule of exponents states that

$$a^{-n} = \frac{1}{a^n} \tag{1.3.8}$$

### Example 1.3.5: Using the Negative Exponent Rule

Write each of the following quotients with a single base. Do not simplify further. Write answers with positive exponents.

a. $\frac{\theta^3}{\theta^{10}}$
b. $\frac{z^2 \times z}{z^4}$
c. $\frac{(-5t^3)^4}{(-5t^3)^8}$

**Solution**

a. $\frac{\theta^3}{\theta^{10}} = \theta^{3-10} = \theta^{-7} = \frac{1}{\theta^7}$
b. $\frac{z^2 \times z}{z^4} = \frac{z^{2+1}}{z^4} = \frac{z^3}{z^4} = z^{3-4} = z^{-1} = \frac{1}{z}$

c. $\dfrac{(-5t^3)^4}{(-5t^3)^8} = (-5t^3)^{4-8} = (-5t^3)^{-4} = \dfrac{1}{(-5t^3)^4}$

## Exercise 1.3.5

Write each of the following quotients with a single base. Do not simplify further. Write answers with positive exponents.

a. $\dfrac{(-3t)^2}{(-3t)^8}$
b. $\dfrac{f^{47}}{f^{49} \times f}$
c. $\dfrac{2k^4}{5k^7}$

**Answer a**

$$\frac{1}{(-3t)^6}$$

**Answer b**

$$\frac{1}{f^3}$$

**Answer c**

$$\frac{2}{5k^3}$$

## Example 1.3.6: Using the Product and Quotient Rules

Write each of the following products with a single base. Do not simplify further. Write answers with positive exponents.

a. $b^2 \times b^{-8}$
b. $(-x)^5 \times (-x)^{-5}$
c. $\dfrac{-7z}{(-7z)^5}$

**Solution**

a. $b^2 \times b^{-8} = b^{2-8} = b^{-6} = \dfrac{1}{b^6}$
b. $(-x)^5 \times (-x)^{-5} = (-x)^{5-5} = (-x)^0 = 1$
c. $\dfrac{-7z}{(-7z)^5} = \dfrac{(-7z)^1}{(-7z)^5} = (-7z)^{1-5} = (-7z)^{-4} = \dfrac{1}{(-7z)^4}$

## Exercise 1.3.6

Write each of the following products with a single base. Do not simplify further. Write answers with positive exponents.

a. $t^{-11} \times t^6$
b. $\dfrac{25^{12}}{25^{13}}$

**Answer a**

$$t^{-5} = \frac{1}{t^5}$$

**Answer b**

$$\frac{1}{25}$$

## Finding the Power of a Product

To simplify the power of a product of two exponential expressions, we can use the power of a product rule of exponents, which breaks up the power of a product of factors into the product of the powers of the factors. For instance, consider $(pq)^3$. We begin by using the associative and commutative properties of multiplication to regroup the factors.

$$\begin{aligned}(pq)^3 &= (pq)\times(pq)\times(pq)\\ &= p\times q\times p\times q\times p\times q\\ &= p^3\times q^3\end{aligned}$$

In other words, $(pq)^3 = p^3\times q^3$ .

### THE POWER OF A PRODUCT RULE OF EXPONENTS

For any real numbers a and b and any integer n, the power of a product rule of exponents states that

$$(ab)^n = a^n b^n \tag{1.3.9}$$

### Example 1.3.7: Using the Power of a Product Rule

Simplify each of the following products as much as possible using the power of a product rule. Write answers with positive exponents.

a. $(ab^2)^3$
b. $(2t)^{15}$
c. $(-2w^3)^3$
d. $\dfrac{1}{(-7z)^4}$
e. $(e^{-2}f^2)^7$

**Solution**

Use the product and quotient rules and the new definitions to simplify each expression.

a. $(ab^2)^3 = (a)^3\times(b^2)^3 = a^{1\times3}\times b^{2\times3} = a^3b^6$
b. $(2t)^{15} = (2)^{15}\times(t)^{15} = 2^{15}t^{15} = 32,768t^{15}$
c. $(-2w^3)^3 = (-2)^3\times(w^3)^3 = -8\times w^{3\times3} = -8w^9$
d. $\dfrac{1}{(-7z)^4} = \dfrac{1}{(-7)^4\times(z)^4} = \dfrac{1}{2401z^4}$
e. $(e^{-2}f^2)^7 = (e^{-2})^7\times(f^2)^7 = e^{-2\times7}\times f^{2\times7} = e^{-14}f^{14} = \dfrac{f^{14}}{e^{14}}$

### Exercise 1.3.7

Simplify each of the following products as much as possible using the power of a product rule. Write answers with positive exponents.

a. $(g^2h^3)^5$
b. $(5t)^3$
c. $(-3y^5)^3$
d. $\dfrac{1}{(a^6b^7)^3}$
e. $(r^3s^{-2})^4$

**Answer a**

$g^{10}h^{15}$

**Answer b**

$125t^3$

**Answer c**

$-27y^{15}$

**Answer d**

$\dfrac{1}{a^{18}b^{21}}$

**Answer e**

$\dfrac{r^{12}}{s^8}$

## Finding the Power of a Quotient

To simplify the power of a quotient of two expressions, we can use the power of a quotient rule, which states that the power of a quotient of factors is the quotient of the powers of the factors. For example, let's look at the following example.

$$(e^{-2}f^2)^7 = \frac{f^{14}}{e^{14}} \tag{1.3.10}$$

Let's rewrite the original problem differently and look at the result.

$$\begin{aligned}(e^{-2}f^2)^7 &= \left(\frac{f^2}{e^2}\right)^7 \\ &= \frac{f^{14}}{e^{14}}\end{aligned}$$

It appears from the last two steps that we can use the power of a product rule as a power of a quotient rule.

$$\begin{aligned}(e^{-2}f^2)^7 &= \left(\frac{f^2}{e^2}\right)^7 \\ &= \frac{(f^2)^7}{(e^2)^7} \\ &= \frac{f^{2\times 7}}{e^{2\times 7}} \\ &= \frac{f^{14}}{e^{14}}\end{aligned}$$

### THE POWER OF A QUOTIENT RULE OF EXPONENTS

For any real numbers a and b and any integer n, the power of a quotient rule of exponents states that

$$\left(\frac{a}{b}\right)^n = \frac{a^n}{b^n} \tag{1.3.11}$$

### Example 1.3.8: Using the Power of a Quotient Rule

Simplify each of the following quotients as much as possible using the power of a quotient rule. Write answers with positive exponents.

a. $\left(\dfrac{4}{z^{11}}\right)^3$

b. $\left(\dfrac{p}{q^3}\right)^6$

c. $\left(\dfrac{-1}{t^2}\right)^{27}$
d. $(j^3k^{-2})^4$
e. $(m^{-2}n^{-2})^3$

**Solution**

a. $\left(\dfrac{4}{z^{11}}\right)^3 = \dfrac{(4)^3}{(z^{11})^3} = \dfrac{64}{z^{11\times 3}} = \dfrac{64}{z^{33}}$

b. $\left(\dfrac{p}{q^3}\right)^6 = \dfrac{(p)^6}{(q^3)^6} = \dfrac{p^{1\times 6}}{q^{3\times 6}} = \dfrac{p^6}{q^{18}}$

c. $\left(\dfrac{-1}{t^2}\right)^{27} = \dfrac{(-1)^{27}}{(t^2)^{27}} = \dfrac{-1}{t^{2\times 27}} = \dfrac{-1}{t^{54}} = -\dfrac{1}{t^{54}}$

d. $(j^3k^{-2})^4 = \left(\dfrac{j^3}{k^2}\right)^4 = \dfrac{(j^3)^4}{(k^2)^4} = \dfrac{j^{3\times 4}}{k^{2\times 4}} = \dfrac{j^{12}}{k^8}$

e. $(m^{-2}n^{-2})^3 = \left(\dfrac{1}{m^2n^2}\right)^3 = \dfrac{(1)^3}{(m^2n^2)^3} = \dfrac{1}{(m^2)^3(n^2)^3} = \dfrac{1}{m^{2\times 3}n^{2\times 3}} = \dfrac{1}{m^6n^6}$

## Exercise 1.3.8

Simplify each of the following quotients as much as possible using the power of a quotient rule. Write answers with positive exponents.

a. $\left(\dfrac{b^5}{c}\right)^3$
b. $\left(\dfrac{5}{u^8}\right)^4$
c. $\left(\dfrac{-1}{w^3}\right)^{35}$
d. $(p^{-4}q^3)^8$
e. $(c^{-5}d^{-3})^4$

**Answer a**

$$\frac{b^{15}}{c^3}$$

**Answer b**

$$\frac{625}{u^{32}}$$

**Answer c**

$$\frac{-1}{w^{105}}$$

**Answer d**

$$\frac{q^{24}}{p^{32}}$$

**Answer e**

$$\frac{1}{c^{20}d^{12}}$$

## Simplifying Exponential Expressions

Recall that to simplify an expression means to rewrite it by combing terms or exponents; in other words, to write the expression more simply with fewer terms. The rules for exponents may be combined to simplify expressions.

### Example 1.3.9: Simplifying Exponential Expressions

Simplify each expression and write the answer with positive exponents only.

a. $(6m^2n^{-1})^3$
b. $17^5 \times 17^{-4} \times 17^{-3}$
c. $\left(\dfrac{u^{-1}v}{v^{-1}}\right)^2$
d. $(-2a^3b^{-1})(5a^{-2}b^2)$
e. $(x^2\sqrt{2})^4(x^2\sqrt{2})^{-4}$
f. $\dfrac{(3w^2)^5}{(6w^{-2})^2}$

**Solution**

a.
$$\begin{aligned}(6m^2n^{-1})^3 &= (6)^3(m^2)^3(n^{-1})^3 && \text{The power of a product rule}\\ &= 6^3m^{2\times3}n^{-1\times3} && \text{The power rule}\\ &= 216m^6n^{-3} && \text{The power rule}\\ &= \frac{216m^6}{n^3} && \text{The negative exponent rule}\end{aligned}$$

b.
$$\begin{aligned}17^5 \times 17^{-4} \times 17^{-3} &= 17^{5-4-3} && \text{The product rule}\\ &= 17^{-2} && \text{Simplify}\\ &= \frac{1}{17^2} \text{ or } \frac{1}{289} && \text{The negative exponent rule}\end{aligned}$$

c.
$$\begin{aligned}\left(\frac{u^{-1}v}{v^{-1}}\right)^2 &= \frac{(u^{-1}v)^2}{(v^{-1})^2} && \text{The power of a quotient rule}\\ &= \frac{u^{-2}v^2}{v^{-2}} && \text{The power of a product rule}\\ &= u^{-2}v^{2-(-2)} && \text{The quotient rule}\\ &= u^{-2}v^4 && \text{Simplify}\\ &= \frac{v^4}{u^2} && \text{The negative exponent rule}\end{aligned}$$

d.
$$\begin{aligned}\left(-2a^3b^{-1}\right)\left(5a^{-2}b^2\right) &= \left(x^2\sqrt{2}\right)^{4-4} && \text{Commutative and associative laws of multiplication}\\ &= -10 \times a^{3-2} \times b^{-1+2} && \text{The product rule}\\ &= -10ab && \text{Simplify}\end{aligned}$$

e.
$$\begin{aligned}\left(x^2\sqrt{2}\right)^4\left(x^2\sqrt{2}\right)^{-4} &= \left(x^2\sqrt{2}\right)^{4-4} && \text{The product rule}\\ &= \left(x^2\sqrt{2}\right)^0 && \text{Simplify}\\ &= 1 && \text{The zero exponent rule}\end{aligned}$$

f.


$$\begin{aligned}
\frac{(3w^2)^5}{(6w^{-2})^2} &= \frac{(3)^5\times(w^2)^5}{(6)^2\times(w^{-2})^2} && \text{The power of a product rule}\\
&= \frac{3^5w^{2\times5}}{6^2w^{-2\times2}} && \text{The power rule}\\
&= \frac{243w^{10}}{36w^{-4}} && \text{Simplify}\\
&= \frac{27w^{10-(-4)}}{4} && \text{The quotient rule and reduce fraction}\\
&= \frac{27w^{14}}{4} && \text{Simplify}
\end{aligned}$$

## Using Scientific Notation

Recall at the beginning of the section that we found the number $1.3\times10^{13}$ when describing bits of information in digital images. Other extreme numbers include the width of a human hair, which is about $0.00005\ m$, and the radius of an electron, which is about $0.00000000000047\ m$How can we effectively work read, compare, and calculate with numbers such as these?

A shorthand method of writing very small and very large numbers is called scientific notation, in which we express numbers in terms of exponents of 10. To write a number in scientific notation, move the decimal point to the right of the first digit in the number. Write the digits as a decimal number between 1 and 10. Count the number of places $n$ that you moved the decimal point. Multiply the decimal number by 10 raised to a power of $n$. If you moved the decimal left as in a very large number, $n$ is positive. If you moved the decimal right as in a small large number, $n$ is negative.

For example, consider the number $2,780,418$ Move the decimal left until it is to the right of the first nonzero digit, which is 2.




We obtain $2.780418$by moving the decimal point 6 places to the left. Therefore, the exponent of 10 is 6, and it is positive because we moved the decimal point to the left. This is what we should expect for a large number.

$$2.780418\times10^6$$

Working with small numbers is similar. Take, for example, the radius of an electron, $0.00000000000047\ m$Perform the same series of steps as above, except move the decimal point to the right.




Be careful not to include the leading 0 in your count. We move the decimal point 13 places to the right, so the exponent of 10 is 13. The exponent is negative because we moved the decimal point to the right. This is what we should expect for a small number.

$$4.7\times10^{-13}$$

**SCIENTIFIC NOTATION**

A number is written in scientific notation if it is written in the form $a\times10^n$ , where $1\le|a|<10$ and $n$ is an integer.

**Example 1.3.10: Converting Standard Notation to Scientific Notation**

Write each number in scientific notation.

a. Distance to Andromeda Galaxy from Earth: $24,000,000,000,000,000,000,000\ m$
b. Diameter of Andromeda Galaxy: $1,300,000,000,000,000,000,000\ m$
c. Number of stars in Andromeda Galaxy: $1,000,000,000,000$
d. Diameter of electron: $0.00000000000094\ m$
e. Probability of being struck by lightning in any single year: $0.00000143$

**Solution**

a. $24,000,000,000,000,000,000,000$ $m$ 22 places

$2.4 \times 10^{22}$ $m$

b. $1,300,000,000,000,000,000,000$ $m$ 21 places

$1.3 \times 10^{21}$ $m$

c. $1,000,000,000,000$ 12 places

$1 \times 10^{12}$

d. $0.00000000000094$ $m$ 13 places

$9.4 \times 10^{-13}$ $m$

e. $0.00000143$ 6 places

$1.43 \times 10^{6}$

**Analysis**

Observe that, if the given number is greater than 1, as in examples a–c, the exponent of 10 is positive; and if the number is less than 1, as in examples d–e, the exponent is negative.

**Exercise 1.3.10**

Write each number in scientific notation.

a. U.S. national debt per taxpayer (April 2014): $\$152,000$
b. World population (April 2014): $7,158,000,000$
c. World gross national income (April 2014): $\$85,500,000,000,000$
d. Time for light to travel 1 $m$ : $0.00000000334$ $s$
e. Probability of winning lottery (match 6 of 49 possible numbers): $0.0000000715$

**Answer a**

$$\$1.52 \times 10^{5}$$

**Answer b**

$$7.158 \times 10^{9}$$

**Answer c**

$$\$8.55 \times 10^{13}$$

**Answer d**

$$3.34 \times 10^{-9}$$

**Answer e**

$$7.15 \times 10^{-8}$$

## Converting from Scientific to Standard Notation

To convert a number in scientific notation to standard notation, simply reverse the process. Move the decimal n places to the right if $n$ is positive or $n$ places to the left if $n$ is negative and add zeros as needed. Remember, if $n$ is positive, the value of the number is greater than 1, and if $n$ is negative, the value of the number is less than one.

### Example 1.3.11: Converting Scientific Notation to Standard Notation

Convert each number in scientific notation to standard notation.

a. $3.547 \times 10^{14}$
b. $-2 \times 10^{6}$
c. $7.91 \times 10^{-7}$
d. $-8.05 \times 10^{-12}$

**Solution**

a. $3.547 \times 10^{14}$

$3.54700000000000$

$\rightarrow 14$ places

$354,700,000,000,000$

b. $-2 \times 10^{6}$

$-2.000000$

$\rightarrow 6$ places

$-2,000,000$

c. $7.91 \times 10^{-7}$

$0000007.91$

$\rightarrow 7$ places

$0.000000791$

d. $-8.05 \times 10^{-12}$

$-000000000008.05$

$\rightarrow 12$ places

$-0.00000000000805$

### Exercise 1.3.11

Convert each number in scientific notation to standard notation.

a. $7.03 \times 10^{5}$
b. $-8.16 \times 10^{11}$
c. $-3.9 \times 10^{-13}$
d. $8 \times 10^{-6}$

**Answer a**

$703,000$

**Answer b**

$-816,000,000,000$

**Answer c**

$-0.00000000000039$

**Answer d**

$0.000008$

## Using Scientific Notation in Applications

Scientific notation, used with the rules of exponents, makes calculating with large or small numbers much easier than doing so using standard notation. For example, suppose we are asked to calculate the number of atoms in 1 $L$ of water. Each water molecule contains 3 atoms (2 hydrogen and 1 oxygen). The average drop of water contains around $1.32 \times 1021$ molecules of water and 1 $L$ of water holds about $1.22 \times 10^4$ average drops. Therefore, there are approximately $3 \cdot (1.32 \times 10^{21}) \cdot (1.22 \times 10^4) \approx 4.83 \times 10^{25}$ atoms in 1 $L$ of water. We simply multiply the decimal terms and add the exponents. Imagine having to perform the calculation without using scientific notation!

When performing calculations with scientific notation, be sure to write the answer in proper scientific notation. For example, consider the product $(7 \times 10^4) \cdot (5 \times 10^6) = 35 \times 10^{10}$ . The answer is not in proper scientific notation because 35 is greater than 10. Consider 35 as $3.5 \times 10$. That adds a ten to the exponent of the answer.

$$(35) \times 10^{10} = (3.5 \times 10) \times 10^{10} = 3.5 \times (10 \times 10^{10}) = 3.5 \times 10^{11}$$

### Example 1.3.12: Using Scientific Notation

Perform the operations and write the answer in scientific notation.

a. $(8.14 \times 10^{-7})(6.5 \times 10^{10})$
b. $(4 \times 10^5) \div (-1.52 \times 10^9)$
c. $(2.7 \times 10^5)(6.04 \times 10^{13})$
d. $(1.2 \times 10^8) \div (9.6 \times 10^5)$
e. $(3.33 \times 10^4)(-1.05 \times 10^7)(5.62 \times 10^5)$

**Solutions**

a. $$\begin{aligned}(8.14 \times 10^{-7})(6.5 \times 10^{10}) &= (8.14 \times 6.5)(10^{-7} \times 10^{10}) \text{ Commutative and associative properties of multiplication} \\ &= (52.91)(10^3) \text{ Product rule of exponents} \\ &= 5.291 \times 10^4 \text{ Scientific notation}\end{aligned}$$

b. $$\begin{aligned}(4 \times 10^5) \div (-1.52 \times 10^9) &= \left(\frac{4}{-1.52}\right)\left(\frac{10^5}{10^9}\right) \text{ Commutative and associative properties of multiplication} \\ &\approx (-2.63)(10^{-4}) \text{ Quotient rule of exponents} \\ &= -2.63 \times 10^{-4} \text{ Scientific notation}\end{aligned}$$

c. $$\begin{aligned}(2.7 \times 10^5)(6.04 \times 10^{13}) &= (2.7 \times 6.04)(10^5 \times 10^{13}) \text{ Commutative and associative properties of multiplication} \\ &= (16.308)(10^{18}) \text{ Product rule of exponents} \\ &= 1.6308 \times 10^{19} \text{ Scientific notation}\end{aligned}$$

d. $$\begin{aligned}(1.2 \times 10^8) \div (9.6 \times 10^5) &= \left(\frac{1.2}{9.6}\right)\left(\frac{10^8}{10^5}\right) \text{ Commutative and associative properties of multiplication} \\ &= (0.125)(10^3) \text{ Quotient rule of exponents} \\ &= 1.25 \times 10^2 \text{ Scientific notation}\end{aligned}$$

e.

$$\begin{aligned}(3.33\times10^4)(-1.05\times10^7)(5.62\times10^5) &= [3.33\times(-1.05)\times5.62](10^4\times10^7\times10^5)\\ &\approx(-19.65)(10^{16})\\ &=-1.965\times10^{17}\end{aligned}$$

**? Exercise 1.3.12**

Perform the operations and write the answer in scientific notation.

a. $(-7.5\times10^8)(1.13\times10^{-2})$
b. $(1.24\times10^{11})\div(1.55\times10^{18})$
c. $(3.72\times10^9)(8\times10^3)$
d. $(9.933\times10^{23})\div(-2.31\times10^{17})$
e. $(-6.04\times10^9)(7.3\times10^2)(-2.81\times10^2)$

**Answer a**

$$-8.475\times10^6$$

**Answer b**

$$8\times10^{-8}$$

**Answer c**

$$2.976\times10^{13}$$

**Answer d**

$$-4.3\times10^6$$

**Answer e**

$$\approx1.24\times10^{15}$$

**✓ Example 1.3.13: Applying Scientific Notation to Solve Problems**

In April 2014, the population of the United States was about $308,000,000$ people. The national debt was about $\$17,547,000,000,000$Write each number in scientific notation, rounding figures to two decimal places, and find the amount of the debt per U.S. citizen. Write the answer in both scientific and standard notations.

**Solution**

The population was $308,000,000=3.08\times10^8$.

The national debt was $\$17,547,000,000,000\approx\$1.75\times10^{13}$?

To find the amount of debt per citizen, divide the national debt by the number of citizens.

$$\begin{aligned}(1.75\times10^{13})\div(3.08\times10^8) &= \left(\frac{1.75}{3.08}\right)(10^5)\\ &\approx0.57\times10^5\\ &=5.7\times10^4\end{aligned}$$

The debt per citizen at the time was about $\$5.7 \times 10^4$, or $\$57,000$.

**Exercise 1.3.13**

An average human body contains around $30,000,000,000,000$ red blood cells. Each cell measures approximately $0.000008$ $m$ long. Write each number in scientific notation and find the total length if the cells were laid end-to-end. Write the answer in both scientific and standard notations.

**Answer**

Number of cells: $3 \times 10^{13}$; length of a cell: $8 \times 10^{-6}$ $m$; total length: $2.4 \times 10^8$ $m$ or $240,000,000$ $m$.

Access these online resources for additional instruction and practice with exponents and scientific notation.

Exponential Notation

Properties of Exponents

Zero Exponent

Simplify Exponent Expressions

Quotient Rule for Exponents

Scientific Notation

Converting to Decimal Notation

## Key Equations

Rules of Exponents For nonzero real numbers a and b and integers m and n

| | |
|---|---|
| Product rule | $a^m \cdot a^n = a^{m+n}$ |
| Quotient rule | $\frac{a^m}{a^n} = a^{m-n}$ |
| Power rule | $(a^m)^n = a^{m \cdot n}$ |
| Zero exponent rule | $a^0 = 1$ |
| Negative rule | $a^{-n} = \frac{1}{a^n}$ |
| Power of a product rule | $(a \cdot b)^n = a^n \cdot b^n$ |
| Power of a quotient rule | $\left(\frac{a}{b}\right)^n = \frac{a^n}{b^n}$ |

## Key Concepts

- Products of exponential expressions with the same base can be simplified by adding exponents. See Example.
- Quotients of exponential expressions with the same base can be simplified by subtracting exponents. See Example.
- Powers of exponential expressions with the same base can be simplified by multiplying exponents. See Example.
- An expression with exponent zero is defined as 1. See Example.
- An expression with a negative exponent is defined as a reciprocal. See Example and Example.
- The power of a product of factors is the same as the product of the powers of the same factors. See Example.
- The power of a quotient of factors is the same as the quotient of the powers of the same factors. See Example.
- The rules for exponential expressions can be combined to simplify more complicated expressions. See Example.
- Scientific notation uses powers of 10 to simplify very large or very small numbers. See Example and Example.
- Scientific notation may be used to simplify calculations with very large or very small numbers. See Example and Example.

This page titled 1.3: Exponents and Scientific Notation is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.2: Exponents and Scientific Notation** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.3E: Exponents and Scientific Notation (Exercises)

For the following exercises, simplify the expression.

12. $2^2 \cdot 2^4$
13. $\frac{4^5}{4^3}$
14. $\left(\frac{a^2}{b^3}\right)^4$
15. $\frac{6a^2-a^0}{2a-4}$
16. $\frac{(xy)^4}{y^3} \cdot \frac{2}{x^5}$
17. $\frac{4^{-2}x^3y^{-3}}{2x^0}$
18. $\left(\frac{2x^2}{y}\right)^{-2}$
19. $\left(\frac{16a^3}{b^2}\right)\left(4ab^{-1}\right)^{-2}$
20. Write the number in standard notation: $2.1314 \times 10^{-6}$
21. Write the number in scientific notation: 16,340,000

---

This page titled 1.3E: Exponents and Scientific Notation (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.2E: Exponents and Scientific Notation (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.4: Radicals and Rational Expressions

**Learning Objectives**

- Evaluate square roots.
- Use the product rule to simplify square roots.
- Use the quotient rule to simplify square roots.
- Add and subtract square roots.
- Rationalize denominators.
- Use rational roots.

A hardware store sells 16-ft ladders and 24-ft ladders. A window is located 12 feet above the ground. A ladder needs to be purchased that will reach the window from a point on the ground 5 feet from the building. To find out the length of ladder needed, we can draw a right triangle as shown in Figure 1.4.1, and use the Pythagorean Theorem.





Figure 1.4.1: A right triangle

$$\begin{aligned} a^2+b^2 &= c^2 \\ 5^2+12^2 &= c^2 \\ 169 &= c^2 \end{aligned}$$

Now, we need to find out the length that, when squared, is 169, to determine which ladder to choose. In other words, we need to find a square root. In this section, we will investigate methods of finding solutions to problems such as this one.

## Evaluating Square Roots

When the square root of a number is squared, the result is the original number. Since $4^2=16$, the square root of 16 is 4.The square root function is the inverse of the squaring function just as subtraction is the inverse of addition. To undo squaring, we take the square root.

In general terms, if $a$ is a positive real number, then the square root of $a$ is a number that, when multiplied by itself, gives $a$.The square root could be positive or negative because multiplying two negative numbers gives a positive number. The principal square root is the nonnegative number that when multiplied by itself equals $a$. The square root obtained using a calculator is the principal square root.

The principal square root of $a$ is written as $\sqrt{a}$. The symbol is called a radical, the term under the symbol is called the radicand, and the entire expression is called a **radical expression**.



**Example 1.4.1**

Does $\sqrt{25} = \pm 5$?

**Solution**

No. Although both $5^2$ and $(-5)^2$ are $25$, the radical symbol implies only a *nonnegative* root, the principal square root. The principal square root of $25$ is $\sqrt{25} = 5$.

**Note**

The principal square root of $a$ is the nonnegative number that, when multiplied by itself, equals $a$. It is written as a radical expression, with a symbol called a *radical* over the term called the *radicand*: $\sqrt{a}$.

**Example 1.4.2: Evaluating Square Roots**

Evaluate each expression.

a. $\sqrt{\sqrt{16}}$
b. $\sqrt{49}$-$\sqrt{81}$

**Solution**

a. $\sqrt{\sqrt{16}} = \sqrt{4} = 2$ because $4^2 = 16$ and $2^2 = 4$
b. $\sqrt{49} - \sqrt{81} = 7 - 9 = -2$ because $7^2 = 49$ and $9^2 = 81$

**Example 1.4.3:**

For $\sqrt{25 + 144}$,can we find the square roots before adding?

**Solution**

No. $\sqrt{25} + \sqrt{144} = 5 + 12 = 17$. This is not equivalent to $\sqrt{25 + 144} = 13$. The order of operations requires us to add the terms in the radicand before finding the square root.

**Exercise 1.4.1**

Evaluate each expression.

a. $\sqrt{\sqrt{81}}$
b. $\sqrt{36} + \sqrt{121}$

**Answer a**

3

**Answer b**

17

## Using the Product Rule to Simplify Square Roots

To simplify a square root, we rewrite it such that there are no perfect squares in the radicand. There are several properties of square roots that allow us to simplify complicated radical expressions. The first rule we will look at is the product rule for simplifying square roots, which allows us to separate the square root of a product of two numbers into the product of two separate rational expressions. For instance, we can rewrite $\sqrt{15}$ as $\sqrt{3} \times \sqrt{5}$. We can also use the product rule to express the product of multiple radical expressions as a single radical expression.

### The Product Rule For Simplifying Square Roots

If $a$ and $b$ are nonnegative, the square root of the product $ab$ is equal to the product of the square roots of $a$ and $b$

$$\sqrt{ab} = \sqrt{a} \times \sqrt{b} \tag{1.4.1}$$

### HOWTO: Given a square root radical expression, use the product rule to simplify it.

1. Factor any perfect squares from the radicand.
2. Write the radical expression as a product of radical expressions.
3. Simplify.

### Example 1.4.4: Using the Product Rule to Simplify Square Roots

Simplify the radical expression.

a. $\sqrt{300}$
b. $\sqrt{162a^5b^4}$

**Solution**

a. $\sqrt{100 \times 3}$ Factor perfect square from radicand.

$\sqrt{100} \times \sqrt{3}$ Write radical expression as product of radical expressions.

$10\sqrt{3}$ Simplify

b. $\sqrt{81a^4b^4 \times 2a}$ Factor perfect square from radicand

$\sqrt{81a^4b^4} \times \sqrt{2a}$ Write radical expression as product of radical expressions

$9a^2b^2\sqrt{2a}$ Simplify

### Exercise 1.4.2

Simplify $\sqrt{50x^2y^3z}$

**Answer**

$5|x||y|\sqrt{2yz}$

Notice the absolute value signs around $x$ and $y$? That's because their value must be positive!

### Howto: Given the product of multiple radical expressions, use the product rule to combine them into one radical expression

1. Express the product of multiple radical expressions as a single radical expression.
2. Simplify.

### Example 1.4.5: Using the Product Rule to Simplify the Product of Multiple Square Roots

Simplify the radical expression.

$\sqrt{12} \times \sqrt{3}$

**Solution**

$\sqrt{12 \times 3}$ Express the product as a single radical expression
$\sqrt{36}$ Simplify
$6$

### Exercise 1.4.3

Simplify $\sqrt{50x} \times \sqrt{2x}$ assuming $x > 0$.

**Answer**

$10|x|$

## Using the Quotient Rule to Simplify Square Roots

Just as we can rewrite the square root of a product as a product of square roots, so too can we rewrite the square root of a quotient as a quotient of square roots, using the quotient rule for simplifying square roots. It can be helpful to separate the numerator and denominator of a fraction under a radical so that we can take their square roots separately. We can rewrite

$$\sqrt{\frac{5}{2}} = \frac{\sqrt{5}}{\sqrt{2}}.$$

### THE QUOTIENT RULE FOR SIMPLIFYING SQUARE ROOTS

The square root of the quotient $\frac{a}{b}$ is equal to the quotient of the square roots of $a$ and $b$, where $b \neq 0$.

$$\sqrt{\frac{a}{b}} = \frac{\sqrt{a}}{\sqrt{b}} \tag{1.4.2}$$

### Howto: Given a radical expression, use the quotient rule to simplify it

1. Write the radical expression as the quotient of two radical expressions.
2. Simplify the numerator and denominator.

### Example 1.4.6: Using the Quotient Rule to Simplify Square Roots

Simplify the radical expression.

$\sqrt{\frac{5}{36}}$

**Solution**

$\frac{\sqrt{5}}{\sqrt{36}}$ Write as quotient of two radical expressions
$\frac{\sqrt{5}}{6}$ Simplify denominator

**Exercise 1.4.4**

Simplify $\sqrt{\frac{2x^2}{9y^4}}$

**Answer**

$\frac{x\sqrt{2}}{3y^2}$

We do not need the absolute value signs for $y^2$ because that term will always be nonnegative.

**Example 1.4.7: Using the Quotient Rule to Simplify an Expression with Two Square Roots**

Simplify the radical expression.

$\frac{\sqrt{234x^{11}y}}{\sqrt{26x^7y}}$

**Solution**

$\sqrt{\frac{234x^{11}y}{26x^7y}}$ Combine numerator and denominator into one radical expression

$\sqrt{9x^4}$ Simplify fraction

$3x^2$ Simplify square root

**Exercise 1.4.5**

Simplify $\frac{\sqrt{9a^5b^{14}}}{\sqrt{3a^4b^5}}$

**Answer**

$b^4\sqrt{3ab}$

## Adding and Subtracting Square Roots

We can add or subtract radical expressions only when they have the same radicand and when they have the same radical type such as square roots. For example, the sum of $\sqrt{2}$ and $3\sqrt{2}$ is $4\sqrt{2}$. However, it is often possible to simplify radical expressions, and that may change the radicand. The radical expression $\sqrt{18}$ can be written with a 2 in the radicand, as $3\sqrt{2}$, so $\sqrt{2}+\sqrt{18}=\sqrt{2}+3\sqrt{2}=4\sqrt{2}$

**Howto: Given a radical expression requiring addition or subtraction of square roots, solve**

1. Simplify each radical expression.
2. Add or subtract expressions with equal radicands.

**Example 1.4.8: Adding Square Roots**

Add $5\sqrt{12}+2\sqrt{3}$.

**Solution**

We can rewrite $5\sqrt{12}$ as $5\sqrt{4\times3}$. According the product rule, this becomes $5\sqrt{4}\sqrt{3}$. The square root of $\sqrt{4}$ is 2, so the expression becomes $5\times2\sqrt{3}$, which is $10\sqrt{3}$. Now we can the terms have the same radicand so we can add.

$$10\sqrt{3}+2\sqrt{3}=12\sqrt{3}$$

**Exercise 1.4.6**

Add $\sqrt{5}+6\sqrt{20}$

**Answer**

$13\sqrt{5}$

**Example 1.4.9: Subtracting Square Roots**

Subtract $20\sqrt{72a^3b^4c}-14\sqrt{8a^3b^4c}$

**Solution**

Rewrite each term so they have equal radicands.

$$\begin{aligned} 20\sqrt{72a^3b^4c} &= 20\sqrt{9}\sqrt{4}\sqrt{2}\sqrt{a}\sqrt{a^2}\sqrt{(b^2)^2}\sqrt{c} \\ &= 20(3)(2)|a|b^2\sqrt{2ac} \\ &= 120|a|b^2\sqrt{2ac} \end{aligned}$$

$$\begin{aligned} 14\sqrt{8a^3b^4c} &= 14\sqrt{2}\sqrt{4}\sqrt{a}\sqrt{a^2}\sqrt{(b^2)^2}\sqrt{c} \\ &= 14(2)|a|b^2\sqrt{2ac} \\ &= 28|a|b^2\sqrt{2ac} \end{aligned}$$

Now the terms have the same radicand so we can subtract.

$$120|a|b^2\sqrt{2ac}-28|a|b^2\sqrt{2ac}=92|a|b^2\sqrt{2ac} \tag{1.4.3}$$

**Exercise 1.4.7**

Subtract $3\sqrt{80x}-4\sqrt{45x}$

**Answer**

$0$

## Rationalizing Denominators

When an expression involving square root radicals is written in simplest form, it will not contain a radical in the denominator. We can remove radicals from the denominators of fractions using a process called rationalizing the denominator.

We know that multiplying by 1 does not change the value of an expression. We use this property of multiplication to change expressions that contain radicals in the denominator. To remove radicals from the denominators of fractions, multiply by the form of 1 that will eliminate the radical.

For a denominator containing a single term, multiply by the radical in the denominator over itself. In other words, if the denominator is $b\sqrt{c}$, multiply by $\frac{\sqrt{c}}{\sqrt{c}}$.

For a denominator containing the sum or difference of a rational and an irrational term, multiply the numerator and denominator by the conjugate of the denominator, which is found by changing the sign of the radical portion of the denominator. If the denominator is $a+b\sqrt{c}$, then the conjugate is $a-b\sqrt{c}$.

**HowTo: Given an expression with a single square root radical term in the denominator, rationalize the denominator**

1. Multiply the numerator and denominator by the radical in the denominator.
2. Simplify.

### Example 1.4.10: Rationalizing a Denominator Containing a Single Term

Write $\frac{2\sqrt{3}}{3\sqrt{10}}$ in simplest form.

**Solution**

The radical in the denominator is $\sqrt{10}$. So multiply the fraction by $\frac{\sqrt{10}}{\sqrt{10}}$. Then simplify.

$$\frac{2\sqrt{3}}{3\sqrt{10}} \times \frac{\sqrt{10}}{\sqrt{10}}$$
$$\frac{2\sqrt{30}}{30}$$
$$\frac{\sqrt{30}}{15}$$

### Exercise 1.4.8

Write $\frac{12\sqrt{3}}{\sqrt{2}}$ in simplest form.

**Answer**

$6\sqrt{6}$

### How to: Given an expression with a radical term and a constant in the denominator, rationalize the denominator

1. Find the conjugate of the denominator.
2. Multiply the numerator and denominator by the conjugate.
3. Use the distributive property.
4. Simplify.

### Example 1.4.11: Rationalizing a Denominator Containing Two Terms

Write $\frac{4}{1+\sqrt{5}}$ in simplest form.

**Solution**

Begin by finding the conjugate of the denominator by writing the denominator and changing the sign. So the conjugate of $1+\sqrt{5}$ is $1-\sqrt{5}$. Then multiply the fraction by $\frac{1-\sqrt{5}}{1-\sqrt{5}}$.

$$\frac{4}{1+\sqrt{5}} \times \frac{1-\sqrt{5}}{1-\sqrt{5}}$$
$$\frac{4-4\sqrt{5}}{-4} \quad \text{Use the distributive property}$$
$$\sqrt{5}-1 \quad \text{Simplify}$$

### Exercise 1.4.9

Write $\frac{7}{2+\sqrt{3}}$ in simplest form.

**Answer**

$14-7\sqrt{3}$

## Using Rational Roots

Although square roots are the most common rational roots, we can also find cube roots, $4^{th}$ roots, $5^{th}$ roots, and more. Just as the square root function is the inverse of the squaring function, these roots are the inverse of their respective power functions. These functions can be useful when we need to determine the number that, when raised to a certain power, gives a certain number.

### Understanding $n^{th}$ Roots

Suppose we know that $a^3=8$. We want to find what number raised to the $3^{rd}$ power is equal to 8. Since $2^3=8$, we say that 2 is the cube root of 8.

The $n^{th}$ root of $a$ is a number that, when raised to the $n^{th}$ power, gives a. For example, $-3$ is the $5^{th}$ root of $-243$ because $(-3)^5=-243$. If $a$ is a real number with at least one $n^{th}$ root, then the principal $n^{th}$ root of $a$ is the number with the same sign as $a$ that, when raised to the $n^{th}$ power, equals $a$.

The principal $n^{th}$ root of $a$ is written as $\sqrt[n]{a}$, where $n$ is a positive integer greater than or equal to 2. In the radical expression, $n$ is called the index of the radical.

**Note: Principal $n^{th}$ Root**

If $a$ is a real number with at least one $n^{th}$ root, then the **principal $n^{th}$ root** of $a$, written as $\sqrt[n]{a}$, is the number with the same sign as $a$ that, when raised to the $n^{th}$ power, equals $a$. The **index** of the radical is $n$.

**Example 1.4.12: Simplifying $n^{th}$ Roots**

Simplify each of the following:

a. $\sqrt[5]{-32}$
b. $\sqrt[4]{4}\times\sqrt[4]{10234}$
c. $-\sqrt[3]{\dfrac{8x^6}{125}}$
d. $8\sqrt[4]{3}-\sqrt[4]{48}$

**Solution**

a. $\sqrt[5]{-32}=-2$ because $(-2)^5=-32$

b. First, express the product as a single radical expression. $\sqrt[4]{4096}=8$ because $8^4=4096$

c.

$$\frac{-\sqrt[3]{8x^6}}{\sqrt[3]{125}} \quad \text{Write as quotient of two radical expressions}$$
$$\frac{-2x^2}{5} \quad \text{Simplify}$$

d.

$$8\sqrt[4]{3}-2\sqrt[4]{3} \quad \text{Simplify to get equal radicands}$$
$$6\sqrt[4]{3} \quad \text{Add}$$

**Exercise 1.4.10**

Simplify

a. $\sqrt[3]{-216}$
b. $\dfrac{3\sqrt[4]{80}}{\sqrt[4]{5}}$

c. $6\sqrt[3]{9000}+7\sqrt[3]{576}$

**Answer a**

$-6$

**Answer b**

$6$

**Answer c**

$88\sqrt[3]{9}$

## Using Rational Exponents

Radical expressions can also be written without using the radical symbol. We can use rational (fractional) exponents. The index must be a positive integer. If the index $n$ is even, then a cannot be negative.

$$a^{\frac{1}{n}} = \sqrt[n]{a} \tag{1.4.4}$$

We can also have rational exponents with numerators other than 1. In these cases, the exponent must be a fraction in lowest terms. We raise the base to a power and take an nth root. The numerator tells us the power and the denominator tells us the root.

$$a^{\frac{m}{n}} = (\sqrt[n]{a})^m = \sqrt[n]{a^m} \tag{1.4.5}$$

All of the properties of exponents that we learned for integer exponents also hold for rational exponents.

**Note: Rational Exponents**

Rational exponents are another way to express principal $n^{th}$ roots. The general form for converting between a radical expression with a radical symbol and one with a rational exponent is

$$a^{\frac{m}{n}} = (\sqrt[n]{a})^m = \sqrt[n]{a^m} \tag{1.4.6}$$

**Howto: Given an expression with a rational exponent, write the expression as a radical**

1. Determine the power by looking at the numerator of the exponent.
2. Determine the root by looking at the denominator of the exponent.
3. Using the base as the radicand, raise the radicand to the power and use the root as the index.

**Example 1.4.13: Writing Rational Exponents as Radicals**

Write $343^{\frac{2}{3}}$ as a radical. Simplify.

**Solution**

The 2 tells us the power and the 3 tells us the root.

$343^{\frac{2}{3}} = (\sqrt[3]{343})^2 = \sqrt[3]{343^2}$

We know that $\sqrt[3]{343} = 7$ because $7^3 = 343$. Because the cube root is easy to find, it is easiest to find the cube root before squaring for this problem. In general, it is easier to find the root first and then raise it to a power.

$$343^{\frac{2}{3}} = (\sqrt[3]{343})^2 = 7^2 = 49 \tag{1.4.7}$$

**Exercise 1.4.11**

Write $9^{\frac{5}{2}}$ as a radical. Simplify.

**Answer**

$(\sqrt{9})^5 = 3^5 = 243$

**Example 1.4.14: Writing Radicals as Rational Exponents**

Write $\frac{4}{\sqrt[7]{a^2}}$ using a rational exponent.

**Solution**

The power is $2$ and the root is $7$, so the rational exponent will be $\frac{2}{7}$. We get $\frac{4}{a^{\frac{2}{7}}}$. Using properties of exponents, we get $\frac{4}{\sqrt[7]{a^2}} = 4a^{\frac{-2}{7}}$

**Exercise 1.4.12**

Write $x\sqrt{(5y)^9}$ using a rational exponent.

**Answer**

$x(5y)^{\frac{9}{2}}$

**Example 1.4.15: Simplifying Rational Exponents**

Simplify:

a. $5(2x^{\frac{3}{4}})(3x^{\frac{1}{5}})$

b. $\left(\frac{16}{9}\right)^{-\frac{1}{2}}$

**Solution**

a.

$30x^{\frac{3}{4}}\ x^{\frac{1}{5}}$ Multiply the coefficients

$30x^{\frac{3}{4}+\frac{1}{5}}$ Use properties of exponents

$30x^{\frac{19}{20}}$ Simplify

b.

$\left(\frac{9}{16}\right)^{\frac{1}{2}}$ Use definition of negative exponents

$\sqrt{\frac{9}{16}}$ Rewrite as a radical

$\frac{\sqrt{9}}{\sqrt{16}}$ Use the quotient rule

$\frac{3}{4}$ Simplify

**? Exercise 1.4.13**

Simplify $(8x)^{\frac{1}{3}}\left(14x^{\frac{6}{5}}\right)$

**Answer**

$28x^{\frac{23}{15}}$

**Media**

Access these online resources for additional instruction and practice with radicals and rational exponents.

Radicals

Rational Exponents

Simplify Radicals

Rationalize Denominator

## Key Concepts

- The principal square root of a number $a$ is the nonnegative number that when multiplied by itself equals $a$. See Example.
- If $a$ and $b$ are nonnegative, the square root of the product $ab$ is equal to the product of the square roots of $a$ and $b$ See Example and Example.
- If $a$ and $b$ are nonnegative, the square root of the quotient $\frac{a}{b}$ is equal to the quotient of the square roots of $a$ and $b$ See Example and Example.
- We can add and subtract radical expressions if they have the same radicand and the same index. See Example and Example.
- Radical expressions written in simplest form do not contain a radical in the denominator. To eliminate the square root radical from the denominator, multiply both the numerator and the denominator by the conjugate of the denominator. See Example and Example.
- The principal $n^{th}$ root of $a$ is the number with the same sign as $a$ that when raised to the $n^{th}$ power equals $a$. These roots have the same properties as square roots. See Example.
- Radicals can be rewritten as rational exponents and rational exponents can be rewritten as radicals. See Example and Example.
- The properties of exponents apply to rational exponents. See Example.

This page titled 1.4: Radicals and Rational Expressions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.3: Radicals and Rational Expressions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.4E: Radicals and Rational Expressions (Exercise)

For the following exercises, find the principal square root.

22. $\sqrt{121}$
23. $\sqrt{196}$
24. $\sqrt{361}$
25. $\sqrt{75}$
26. $\sqrt{162}$
27. $\sqrt{\frac{32}{25}}$
28. $\sqrt{\frac{80}{81}}$
29. $\sqrt{\frac{49}{1250}}$
30. $\frac{2}{4+\sqrt{2}}$
31. $4\sqrt{3}+6\sqrt{3}$
32. $12\sqrt{5}-13\sqrt{5}$
33. $\sqrt[5]{-243}$
34. $\frac{\sqrt[3]{250}}{\sqrt[3]{-8}}$

This page titled 1.4E: Radicals and Rational Expressions (Exercise) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.3E: Radicals and Rational Expressions (Exercise)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.5: Polynomials

**Learning Objectives**

In this section students will:

- Identify the degree and leading coefficient of polynomials.
- Add and subtract polynomials.
- Multiply polynomials.
- Use FOIL to multiply binomials.
- Perform operations with polynomia
- ls of several variables.

Earl is building a doghouse, whose front is in the shape of a square topped with a triangle. There will be a rectangular door through which the dog can enter and exit the house. Earl wants to find the area of the front of the doghouse so that he can purchase the correct amount of paint. Using the measurements of the front of the house, shown in Figure 1.5.1, we can create an expression that combines several variable terms, allowing us to solve this problem and others like it.





Figure 1.5.1

- First find the area of the square in square feet.

$$\begin{aligned} A &= s^2 \\ &= (2x)^2 \\ &= 4x^2 \end{aligned}$$

- Then find the area of the triangle in square feet.

$$\begin{aligned} A &= \frac{1}{2}bh \\ &= \frac{1}{2}(2x)\left(\frac{3}{2}\right) \\ &= \frac{3}{2}x \end{aligned}$$

- Next find the area of the rectangular door in square feet.

$$\begin{aligned} A &= lw \\ &= x \times 1 \\ &= x \end{aligned}$$

The area of the front of the doghouse can be found by adding the areas of the square and the triangle, and then subtracting the area of the rectangle. When we do this, we get

$$4x^2 + \frac{3}{2}x - x \ \ ft^2$$

or

$$4x^2 + \frac{1}{2}x \ \ ft^2$$


In this section, we will examine expressions such as this one, which combine several variable terms.

## Identifying the Degree and Leading Coefficient of Polynomials

The formula just found is an example of a **polynomial**, which is a sum of or difference of terms, each consisting of a variable raised to a nonnegative integer power. A number multiplied by a variable raised to an exponent, such as $384\pi$, is known as a **coefficient**. Coefficients can be positive, negative, or zero, and can be whole numbers, decimals, or fractions. Each product $a_i x^i$, such as $384\pi w$, is a **term of a polynomial**. If a term does not contain a variable, it is called a constant.

A polynomial containing only one term, such as $5x^4$, is called a **monomial**. A polynomial containing two terms, such as $2x-9$, is called a **binomial**. A polynomial containing three terms, such as $-3x^2+8x-7$ , is called a **trinomial**.

We can find the **degree** of a polynomial by identifying the highest power of the variable that occurs in the polynomial. The term with the highest degree is called the **leading term** because it is usually written first. The coefficient of the leading term is called the **leading coefficient**. When a polynomial is written so that the powers are descending, we say that it is in standard form.




### Polynomials

A polynomial is an expression that can be written in the form

$$a_n x^n + \ldots + a_2 x^2 + a_1 x + a_0 \tag{1.5.1}$$

Each real number ai is called a **coefficient**. The number $a_0$ that is not multiplied by a variable is called aconstant. Each product $a_i x^i$ is a **term of a polynomial**. The highest power of the variable that occurs in the polynomial is called the **degree** of a polynomial. The **leading term** is the term with the highest power, and its coefficient is called the **leading coefficient.**

### How to: Given a polynomial expression, identify the degree and leading coefficient.

1. Find the highest power of x to determine the degree.
2. Identify the term containing the highest power of x to find the leading term.
3. Identify the coefficient of the leading term.

### Example 1.5.1: Identifying the Degree and Leading Coefficient of a Polynomial

For the following polynomials, identify the degree, the leading term, and the leading coefficient.

a. $3+2x^2-4x^3$
b. $5t^5-2t^3+7t$
c. $6p-p^3-2$

**Solution**

a. The highest power of $x$ is $3$, so the degree is $3$. The leading term is the term containing that degree, $-4x^3$. The leading coefficient is the coefficient of that term, $-4$.
b. The highest power of $t$ is $5$, so the degree is $5$. The leading term is the term containing that degree, $5t^5$. The leading coefficient is the coefficient of that term, $5$.
c. The highest power of $p$ is $3$, so the degree is $3$. The leading term is the term containing that degree, $-p^3$, The leading coefficient is the coefficient of that term, $-1$.

**Exercise 1.5.1**

Identify the degree, leading term, and leading coefficient of the polynomial $4x^2 - x^6 + 2x - 6$ .

**Answer**

The degree is 6, the leading term is $-x^6$, and the leading coefficient is $-1$.

## Adding and Subtracting Polynomials

We can add and subtract polynomials by combining like terms, which are terms that contain the same variables raised to the same exponents. For example, $5x^2$ and $-2x^2$ are like terms, and can be added to get $3x^2$, but $3x$ and $3x^2$ are not like terms, and therefore cannot be added.

**How to: Given multiple polynomials, add or subtract them to simplify the expressions.**

1. Combine like terms.
2. Simplify and write in standard form.

**Example 1.5.2: Adding Polynomials**

Find the sum.

$$(12x^2 + 9x - 21) + (4x^3 + 8x^2 - 5x + 20)$$

**Solution**

$$4x^3 + (12x^2 + 8x^2) + (9x - 5x) + (-21 + 20) \quad \text{Combine like terms}$$
$$4x^3 + 20x^2 + 4x - 1 \quad \text{Simplify}$$

**Analysis**

We can check our answers to these types of problems using a graphing calculator. To check, graph the problem as given along with the simplified answer. The two graphs should be equivalent. Be sure to use the same window to compare the graphs. Using different windows can make the expressions seem equivalent when they are not.

**Exercise 1.5.2**

Find the sum.

$$(2x^3 + 5x^2 - x + 1) + (2x^2 - 3x - 4)$$

**Answer**

$2x^3 + 7x^2 - 4x - 3$

**Example 1.5.3: Subtracting Polynomials**

Find the difference.

$$(7x^4 - x^2 + 6x + 1) - (5x^3 - 2x^2 + 3x + 2)$$

**Solution**

$7x^4 - 5x^3 + (-x^2 + 2x^2) + (6x - 3x) + (1 - 2)$ Combine like terms

$7x^4 - 5x^3 + x^2 + 3x - 1$ Simplify

**Analysis**

Note that finding the difference between two polynomials is the same as adding the opposite of the second polynomial to the first.

**Exercise 1.5.3**

Find the difference.

$$(-7x^3-7x^2+6x-2)-(4x^3-6x^2-x+7)$$

**Answer**

$-11x^3-x^2+7x-9$

## Multiplying Polynomials

Multiplying polynomials is a bit more challenging than adding and subtracting polynomials. We must use the distributive property to multiply each term in the first polynomial by each term in the second polynomial. We then combine like terms. We can also use a shortcut called the FOIL method when multiplying binomials. Certain special products follow patterns that we can memorize and use instead of multiplying the polynomials by hand each time. We will look at a variety of ways to multiply polynomials.

### Multiplying Polynomials Using the Distributive Property

To multiply a number by a polynomial, we use the distributive property. The number must be distributed to each term of the polynomial. We can distribute the 2 in $2(x+7)$ to obtain the equivalent expression $2x+14$. When multiplying polynomials, the distributive property allows us to multiply each term of the first polynomial by each term of the second. We then add the products together and combine like terms to simplify.

**How to: Given the multiplication of two polynomials, use the distributive property to simplify the expression.**

1. Multiply each term of the first polynomial by each term of the second.
2. Combine like terms.
3. Simplify.

**Example 1.5.4: Multiplying Polynomials Using the Distributive Property**

Find the product.

$$(2x+1)(3x^2-x+4)$$

**Solution**

$$\begin{aligned} &2x(3x^2-x+4)+1(3x^2-x+4) && \text{Use the distributive property}\\ &(6x^3-2x^2+8x)+(3x^2-x+4) && \text{Multiply}\\ &6x^3+(-2x^2+3x^2)+(8x-x)+4 && \text{Combine like terms}\\ &6x^3+x^2+7x+4 && \text{Simplify}\end{aligned}$$

**Analysis**

We can use a table to keep track of our work, as shown in Table 1.5.1. Write one polynomial across the top and the other down the side. For each box in the table, multiply the term for that row by the term for that column. Then add all of the terms together, combine like terms, and simplify.

Table 1.5.1

| | $3x^2$ | $-x$ | $+4$ |
|---|---|---|---|
| $2x$ | $6x^3$ | $-2x^2$ | $8x$ |
| $+1$ | $3x^2$ | $-x$ | $4$ |

**Exercise 1.5.4**

Find the product.


$(3x+2)(x^3-4x^2+7)$

**Answer**

$3x^4-10x^3-8x^2+21x+14$

## Using FOIL to Multiply Binomials

A shortcut called FOIL is sometimes used to find the product of two binomials. It is called FOIL because we multiply the first terms, the outer terms, the inner terms, and then the last terms of each binomial.




The FOIL method arises out of the distributive property. We are simply multiplying each term of the first binomial by each term of the second binomial, and then combining like terms.

**FOIL to simplify expression**

Given two binomials, use FOIL to simplify the expression.

1. Multiply the outer terms of the binomials.
2. Multiply the last terms of each binomial.
3. Combine like terms and simplify.


**Example 1.5.5: Using FOIL to Multiply Binomials**

Use FOIL to find the product.

$$(2x-10)(3x+3)$$

**Solution**

Find the product of the first terms.




Find the product of the outer terms.




Find the product of the inner terms.




Find the product of the last terms.



$$\begin{aligned} 6x^2+6x-54x-54 & \quad \text{Add the products} \\ 6x^2+(6x-54x)-54 & \quad \text{Combine like terms} \\ 6x^2-48x-54 & \quad \text{Simplify} \end{aligned}$$

**? Exercise 1.5.5**

Use FOIL to find the product.

$$(x+7)(3x-5)$$

**Answer**

$3x^2+16x-35$

### Perfect Square Trinomials

Certain binomial products have special forms. When a binomial is squared, the result is called a perfect square trinomial. We can find the square by multiplying the binomial by itself. However, there is a special form that each of these perfect square trinomials takes, and memorizing the form makes squaring binomials much easier and faster. Let's look at a few perfect square trinomials to familiarize ourselves with the form.

$$(x+5)^2 = x^2+10x+25$$

$$(x-3)^2 = x^2-6x+9$$

$$(4x-1)^2 = 16x^2-8x+1$$

Notice that the first term of each trinomial is the square of the first term of the binomial and, similarly, the last term of each trinomial is the square of the last term of the binomial. The middle term is double the product of the two terms. Lastly, we see that the first sign of the trinomial is the same as the sign of the binomial.

**Perfect Square Trinomials**

When a binomial is squared, the result is the first term squared added to double the product of both terms and the last term squared.

$$(x+a)^2 = (x+a)(x+a) = x^2+2ax+a^2 \tag{1.5.2}$$

**How to: Given a binomial, square it using the formula for perfect square trinomials.**

1. Square the first term of the binomial.
2. Square the last term of the binomial.
3. For the middle term of the trinomial, double the product of the two terms.
4. Add and simplify.

**✓ Example 1.5.6: Expanding Perfect Squares**

Expand $(3x-8)^2$.

**Solution**

Begin by squaring the first term and the last term. For the middle term of the trinomial, double the product of the two terms.

$$\begin{aligned} & (3x)^2-2(3x)(8)+(-8)^2 \\ & 9x^2-48x+64 \quad \text{Simplify} \end{aligned}$$

**Exercise 1.5.6**

Expand $(4x-1)^2$.

**Answer**

$16x^2-8x+1$

## Difference of Squares

Another special product is called the difference of squares, which occurs when we multiply a binomial by another binomial with the same terms but the opposite sign. Let's see what happens when we multiply $(x+1)(x-1)$ using the FOIL method.

$$\begin{aligned}(x+1)(x-1) &= x^2-x+x-1\\ &= x^2-1\end{aligned}$$

The middle term drops out, resulting in a difference of squares. Just as we did with the perfect squares, let's look at a few examples.

$$(x+5)(x-5)=x^2-25$$
$$(x+11)(x-11)=x^2-121$$
$$(2x+3)(2x-3)=4x^2-9$$

Because the sign changes in the second binomial, the outer and inner terms cancel each other out, and we are left only with the square of the first term minus the square of the last term.

**Q&A**

**Is there a special form for the sum of squares?**

No. The difference of squares occurs because the opposite signs of the binomials cause the middle terms to disappear. There are no two binomials that multiply to equal a sum of squares.

**Difference of Squares**

When a binomial is multiplied by a binomial with the same terms separated by the opposite sign, the result is the square of the first term minus the square of the last term.

$$(a+b)(a-b)=a^2-b^2 \tag{1.5.3}$$

**Howto: Given a binomial multiplied by a binomial with the same terms but the opposite sign, find the difference of squares.**

1. Square the first term of the binomials.
2. Square the last term of the binomials.
3. Subtract the square of the last term from the square of the first term.

**Example 1.5.7: Multiplying Binomials Resulting in a Difference of Squares**

Multiply $(9x+4)(9x-4)$.

**Solution**

Square the first term to get $(9x)^2=81x^2$. Square the last term to get $4^2=16$. Subtract the square of the last term from the square of the first term to find the product of $81x^2-16$.

**Exercise 1.5.7**

Multiply $(2x+7)(2x-7)$.

**Answer**

$4x^2-49$

## Performing Operations with Polynomials of Several Variables

We have looked at polynomials containing only one variable. However, a polynomial can contain several variables. All of the same rules apply when working with polynomials containing several variables. Consider an example:

| | |
|---|---|
| $(a+2b)(4a-b-c)a(4a-b-c)+2b(4a-b-c)$ | Use the distributive property |
| $4a^2-ab-ac+8ab-2b^2-2bc$ | Multiply |
| $4a^2+(-ab+8ab)-ac-2b^2-2bc$ | Combine like terms |
| $4a^2+7ab-ac-2bc-2b^2$ | Simplify |

**Example 1.5.8: Multiplying Polynomials Containing Several Variables**

Multiply $(x+4)(3x-2y+5)$.

**Solution**

| | |
|---|---|
| $x(3x-2y+5)+4(3x-2y+5)$ | Use the distributive property |
| $3x^2-2xy+5x+12x-8y+20$ | Multiply |
| $3x^2-2xy+(5x+12x)-8y+20$ | Combine like terms |
| $3x^2-2xy+17x-8y+20$ | Simplify |

**Exercise 1.5.8**

Multiply $(3x-1)(2x+7y-9)$.

**Answer**

$6x^2+21xy-29x-7y+9$

**Media**

Access these online resources for additional instruction and practice with polynomials.

1. Adding and Subtracting Polynomials
2. Multiplying Polynomials
3. Special Products of Polynomials

## Key Equations

| | |
|---|---|
| perfect square trinomial | $(x+a)^2=(x+a)(x+a)=x^2+2ax+a^2$ |
| difference of squares | $(a+b)(a-b)=a^2-b^2$ |

## Key Concepts

- A polynomial is a sum of terms each consisting of a variable raised to a non-negative integer power. The degree is the highest power of the variable that occurs in the polynomial. The leading term is the term containing the highest degree, and the leading coefficient is the coefficient of that term. See Example.
- We can add and subtract polynomials by combining like terms. See Example and Example.

- To multiply polynomials, use the distributive property to multiply each term in the first polynomial by each term in the second. Then add the products. See Example.
- FOIL (First, Outer, Inner, Last) is a shortcut that can be used to multiply binomials. See Example.
- Perfect square trinomials and difference of squares are special products. See Example and Example.
- Follow the same rules to work with polynomials containing several variables. See Example.

---

This page titled 1.5: Polynomials is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.4: Polynomials** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.5E: Polynomials (Exercises)

For the following exercises, perform the given operations and simplify.

35. $\left(3x^3+2x-1\right)+\left(4x^2-2x+7\right)$
36. $(2y+1)-\left(2y^2-2y-5\right)$
37. $\left(2x^2+3x-6\right)+\left(3x^2-4x+9\right)$
38. $\left(6a^2+3a+10\right)-\left(6a^2-3a+5\right)$
39. $(k+3)(k-6)$
40. $(2h+1)(3h-2)$
41. $(x+1)\left(x^2+1\right)$
42. $(m-2)\left(m^2+2m-3\right)$
43. $(a+2b)(3a-b)$
44. $(x+y)(x-y)$

This page titled 1.5E: Polynomials (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.4E: Polynomials (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.6: Factoring Polynomials

**Learning Objectives**

In this section students will:

- Factor the greatest common factor of a polynomial.
- Factor a trinomial.
- Factor by grouping.
- Factor a perfect square trinomial.
- Factor a difference of squares.
- Factor the sum and difference of cubes.
- Factor expressions using fractional or negative exponents.

Imagine that we are trying to find the area of a lawn so that we can determine how much grass seed to purchase. The lawn is the green portion in Figure 1.6.1.





Figure 1.6.1

The area of the entire region can be found using the formula for the area of a rectangle.

$$\begin{aligned} A &= lw \\ &= 10x \times 6x \\ &= 60x^2 \ units^2 \end{aligned}$$

The areas of the portions that do not require grass seed need to be subtracted from the area of the entire region. The two square regions each have an area of $A = s^2 = 4^2 = 16 \ units^2$ . The other rectangular region has one side of length $10x - 8$ and one side of length 4, giving an area of

$$A = lw = 4(10x - 8) = 40x - 32 \text{ units}^2.$$

So the region that must be subtracted has an area of

$$2(16) + 40x - 32 = 40x \text{ units}^2.$$

The area of the region that requires grass seed is found by subtracting $60x^2 - 40x \text{ units}^2$. This area can also be expressed in factored form as $20x(3x - 2) \text{ units}^2$. We can confirm that this is an equivalent expression by multiplying.

Many polynomial expressions can be written in simpler forms by factoring. In this section, we will look at a variety of methods that can be used to factor polynomial expressions.

## Factoring the Greatest Common Factor of a Polynomial

When we study fractions, we learn that the greatest common factor (GCF) of two numbers is the largest number that divides evenly into both numbers. For instance, 4 is the GCF of 16 and 20 because it is the largest number that divides evenly into both 16 and 20 The GCF of polynomials works the same way: $4x$ is the GCF of $16x$ and $20x^2$ because it is the largest polynomial that divides evenly into both $16x$ and $20x^2$.

When factoring a polynomial expression, our first step should be to check for a GCF. Look for the GCF of the coefficients, and then look for the GCF of the variables.

**Definition: Greatest Common Factor**

The *greatest common factor* (GCF) of polynomials is the largest polynomial that divides evenly into the polynomials.

**Howto: Given a polynomial expression, factor out the greatest common factor**

1. Identify the GCF of the coefficients.
2. Identify the GCF of the variables.
3. Combine to find the GCF of the expression.
4. Determine what the GCF needs to be multiplied by to obtain each term in the expression.
5. Write the factored expression as the product of the GCF and the sum of the terms we need to multiply by.

**Example 1.6.1: Factoring the Greatest Common Factor**

Factor $6x^3y^3+45x^2y^2+21xy$.

**Solution**

First, find the GCF of the expression. The GCF of 6, 45, and 21 is 3. The GCF of $x^3$,$x^2$, and $x$ is $x$. (Note that the GCF of a set of expressions in the form $x^n$ will always be the exponent of lowest degree.) And the GCF of $y^3$,$y^2$, and $y$ is $y$. Combine these to find the GCF of the polynomial, $3xy$.

Next, determine what the GCF needs to be multiplied by to obtain each term of the polynomial. We find that

- $3xy(2x^2y^2)=6x^3y^3$,
- $3xy(15xy)=45x^2y^2$, and
- $3xy(7)=21xy$.

Finally, write the factored expression as the product of the GCF and the sum of the terms we needed to multiply by.

$$(3xy)(2x^2y^2+15xy+7)$$

**Analysis**

After factoring, we can check our work by multiplying. Use the distributive property to confirm that

$$(3xy)(2x^2y^2+15xy+7)=6x^3y^3+45x^2y^2+21xy$$

**Exercise 1.6.1**

Factor $x(b^2-a)+6(b^2-a)$ by pulling out the GCF.

**Answer**

$(b^2-a)(x+6)$

## Factoring a Trinomial with Leading Coefficient 1

Although we should always begin by looking for a GCF, pulling out the GCF is not the only way that polynomial expressions can be factored. The polynomial $x^2+5x+6$ has a GCF of 1, but it can be written as the product of the factors $(x+2)$ and $(x+3)$.

Trinomials of the form $x^2+bx+c$ can be factored by finding two numbers with a product of $c$ and a sum of $b$. The trinomial $x^2+10x+16$, for example, can be factored using the numbers 2 and 8 because the product of those numbers is 16 and their sum is 10. The trinomial can be rewritten as the product of $(x+2)$ and $(x+8)$.

**FACTORING A TRINOMIAL WITH LEADING COEFFICIENT 1**

A trinomial of the form $x^2+bx+c$ can be written in factored form as $(x+p)(x+q)$ where $pq=c$ and $p+q=b$.

**Q&A: Can every trinomial be factored as a product of binomials?**

No. Some polynomials cannot be factored. These polynomials are said to be *prime*.

**Howto: Given a trinomial in the form $x^2 + bx + c$, factor it**

1. List factors of $c$.
2. Find $p$ and $q$, a pair of factors of $c$ with a sum of $b$.
3. Write the factored expression $(x+p)(x+q)$ .

**Example 1.6.2: Factoring a Trinomial with Leading Coefficient 1**

Factor $x^2+2x-15$ .

**Solution**

We have a trinomial with leading coefficient $1$, $b=2$, and $c=-15$. We need to find two numbers with a product of $-15$ and a sum of $2$. In Table $1.6.1$, we list factors until we find a pair with the desired sum.

Table 1.6.1

| Factors of −15 | Sum of Factors |
|---|---|
| 1,−15 | −14 |
| −1,15 | 14 |
| 3,−5 | −2 |
| −3,5 | |

Now that we have identified $p$ and $q$ as $-3$ and $5$, write the factored form as $(x-3)(x+5)$ .

**Analysis**

We can check our work by multiplying. Use FOIL to confirm that $(x-3)(x+5)=x^2+2x-15$ .

**Q&A: Does the order of the factors matter?**

No. Multiplication is commutative, so the order of the factors does not matter.

**Exercise 1.6.2**

Factor $x^2-7x+6$ .

**Answer**

$(x-6)(x-1)$

## Factoring by Grouping

Trinomials with leading coefficients other than 1 are slightly more complicated to factor. For these trinomials, we can **factor by grouping** by dividing the x term into the sum of two terms, factoring each portion of the expression separately, and then factoring out the GCF of the entire expression. The trinomial $2x^2+5x+3$ can be rewritten as $(2x+3)(x+1)$ using this process. We begin by rewriting the original expression as $2x^2+2x+3x+3$ and then factor each portion of the expression to obtain $2x(x+1)+3(x+1)$ . We then pull out the GCF of $(x+1)$ to find the factored expression.

### Factor by Grouping

To factor a trinomial in the form $ax^2+bx+c$ by grouping, we find two numbers with a product of $ac$ and a sum of $b$. We use these numbers to divide the $x$ term into the sum of two terms and factor each portion of the expression separately, then factor out the GCF of the entire expression.

### Howto: Given a trinomial in the form $ax^2+bx+c$, factor by grouping.

1. List factors of $ac$.
2. Find $p$ and $q$, a pair of factors of $ac$ with a sum of $b$.
3. Rewrite the original expression as $ax^2+px+qx+c$ .
4. Pull out the GCF of $ax^2+px$.
5. Pull out the GCF of $qx+c$.
6. Factor out the GCF of the expression.

### Example 1.6.3: Factoring a Trinomial by Grouping

Factor $5x^2+7x-6$ by grouping.

**Solution**

We have a trinomial with $a=5, b=7$, and $c=-6$. First, determine $ac=-30$. We need to find two numbers with a product of $-30$ and a sum of $7$. In the table below, we list factors until we find a pair with the desired sum.

Table 1.6.2

| Factors of −30 | Sum of Factors |
|---|---|
| 1,−30 | −29 |
| −1,30 | 29 |
| 2,−15 | −13 |
| −2,15 | 13 |
| 3,−10 | −7 |
| −3,10 | 7 |

So $p=-3$ and $q=10$.

$5x^2-3x+10x-6$ Rewrite the original expression as $ax^2+px+qx+c$ .

$x(5x-3)+2(5x-3)$ Factor out the GCF of each part

$(5x-3)(x+2)$ Factor out the GCF of the expression.

**Analysis**

We can check our work by multiplying. Use FOIL to confirm that $(5x-3)(x+2)=5x^2+7x-6$ .

### Exercise 1.6.3

Factor:

a. $2x^2+9x+9$
b. $6x^2+x-1$

**Answer a**

$(2x+3)(x+3)$

**Answer b**

$(3x-1)(2x+1)$

## Factoring a Perfect Square Trinomial

A perfect square trinomial is a trinomial that can be written as the square of a binomial. Recall that when a binomial is squared, the result is the square of the first term added to twice the product of the two terms and the square of the last term.

$$a^2+2ab+b^2=(a+b)^2 \tag{1.6.1}$$

and

$$a^2-2ab+b^2=(a-b)^2 \tag{1.6.2}$$

We can use this equation to factor any perfect square trinomial.

**Perfect Square Trinomials**

A perfect square trinomial can be written as the square of a binomial:

$$a^2+2ab+b^2=(a+b)^2 \tag{1.6.3}$$

**Howto: Given a perfect square trinomial, factor it into the square of a binomial**

1. Confirm that the first and last term are perfect squares.
2. Confirm that the middle term is twice the product of $ab$.
3. Write the factored form as $(a+b)^2$.

**Example 1.6.4: Factoring a Perfect Square Trinomial**

Factor $25x^2+20x+4$.

**Solution**

Notice that $25x^2$ and $4$ are perfect squares because $25x^2=(5x)^2$ and $4=2^2$. Then check to see if the middle term is twice the product of $5x$ and $2$. The middle term is, indeed, twice the product: $2(5x)(2)=20x$. Therefore, the trinomial is a perfect square trinomial and can be written as $(5x+2)^2$.

**Exercise 1.6.4**

Factor $49x^2-14x+1$.

**Answer**

$(7x-1)^2$

## Factoring a Difference of Squares

A difference of squares is a perfect square subtracted from a perfect square. Recall that a difference of squares can be rewritten as factors containing the same terms but opposite signs because the middle terms cancel each other out when the two factors are multiplied.

$$a^2-b^2=(a+b)(a-b) \tag{1.6.4}$$

We can use this equation to factor any differences of squares.

### Differences of Squares

A difference of squares can be rewritten as two factors containing the same terms but opposite signs.

$$a^2 - b^2 = (a+b)(a-b) \tag{1.6.5}$$

### Howto: Given a difference of squares, factor it into binomials

1. Confirm that the first and last term are perfect squares.
2. Write the factored form as $(a+b)(a-b)$ .

### Example 1.6.5: Factoring a Difference of Squares

Factor $9x^2 - 25$.

**Solution**

Notice that $9x^2$ and $25$ are perfect squares because $9x^2 = (3x)^2$ and $25 = 5^2$. The polynomial represents a difference of squares and can be rewritten as $(3x+5)(3x-5)$.

### Exercise 1.6.5

Factor $81y^2 - 100$.

**Answer**

$(9y+10)(9y-10)$

### Q&A: Is there a formula to factor the sum of squares?

No. A sum of squares cannot be factored.

## Factoring the Sum and Difference of Cubes

Now, we will look at two new special products: the sum and difference of cubes. Although the sum of squares cannot be factored, the sum of cubes can be factored into a binomial and a trinomial.

$$a^3 + b^3 = (a+b)(a^2 - ab + b^2) \tag{1.6.6}$$

Similarly, the sum of cubes can be factored into a binomial and a trinomial, but with different signs.

$$a^3 - b^3 = (a-b)(a^2 + ab + b^2) \tag{1.6.7}$$

We can use the acronym SOAP to remember the signs when factoring the sum or difference of cubes. The first letter of each word relates to the signs: Same Opposite Always Positive. For example, consider the following example.

$$x^3 - 2^3 = (x-2)(x^2 + 2x + 4) \tag{1.6.8}$$

The sign of the first 2 is the same as the sign between $x^3 - 2^3$ . The sign of the $2x$ term is opposite the sign between $x^3 - 2^3$ . And the sign of the last term, 4, is always positive.

### Sum and Difference of Cubes

We can factor the sum of two cubes as

$$a^3 + b^3 = (a+b)(a^2 - ab + b^2) \tag{1.6.9}$$

We can factor the difference of two cubes as

$$a^3 - b^3 = (a-b)(a^2 + ab + b^2) \tag{1.6.10}$$

**Howto: Given a sum of cubes or difference of cubes, factor it**

1. Confirm that the first and last term are cubes, $a^3+b^3$ or $a^3-b^3$.
2. For a sum of cubes, write the factored form as $(a+b)(a^2-ab+b^2)$. For a difference of cubes, write the factored form as $(a-b)(a^2+ab+b^2)$.

**Example 1.6.6: Factoring a Sum of Cubes**

Factor $x^3+512$.

**Solution**

Notice that $x^3$ and $512$ are cubes because $8^3=512$. Rewrite the sum of cubes as $(x+8)(x^2-8x+64)$.

**Analysis**

After writing the sum of cubes this way, we might think we should check to see if the trinomial portion can be factored further. However, the trinomial portion cannot be factored, so we do not need to check.

**Exercise 1.6.6**

Factor the sum of cubes: $216a^3+b^3$.

**Answer**

$(6a+b)(36a^2-6ab+b^2)$

**Example 1.6.7: Factoring a Difference of Cubes**

Factor $8x^3-125$.

**Solution**

Notice that $8x^3$ and $125$ are cubes because $8x^3=(2x)^3$ and $125=5^3$. Write the difference of cubes as $(2x-5)(4x^2+10x+25)$.

**Analysis**

Just as with the sum of cubes, we will not be able to further factor the trinomial portion.

**Exercise 1.6.7**

Factor the difference of cubes: $1000x^3-1$

**Answer**

$(10x-1)(100x^2+10x+1)$

## Factoring Expressions with Fractional or Negative Exponents

Expressions with fractional or negative exponents can be factored by pulling out a GCF. Look for the variable or exponent that is common to each term of the expression and pull out that variable or exponent raised to the lowest power. These expressions follow the same factoring rules as those with integer exponents. For instance, $2x^{\frac{1}{4}}+5x^{\frac{3}{4}}$ can be factored by pulling out $x^{\frac{1}{4}}$ and being rewritten as $x^{\frac{1}{4}}(2+5x^{\frac{1}{2}})$.

### Example 1.6.8: Factoring an Expression with Fractional or Negative Exponents

Factor $3x(x+2)^{-\frac{1}{3}}+4(x+2)^{\frac{2}{3}}$.

**Solution**

Factor out the term with the lowest value of the exponent. In this case, that would be $(x+2)^{-\frac{1}{3}}$.

$$(x+2)^{-\frac{1}{3}}(3x+4(x+2)) \qquad \text{Factor out the GCF}$$
$$(x+2)^{-\frac{1}{3}}(3x+4x+8) \qquad \text{Simplify}$$
$$(x+2)^{-\frac{1}{3}}(7x+8)$$

### Exercise 1.6.8

Factor $2(5a-1)^{\frac{3}{4}}+7a(5a-1)^{-\frac{1}{4}}$.

**Answer**

$$(5a-1)^{-\frac{1}{4}}(17a-2)$$

### Media

Access these online resources for additional instruction and practice with factoring polynomials.

1. Identify GCF
2. Factor Trinomials when a Equals 1
3. Factor Trinomials when a is not equal to 1
4. Factor Sum or Difference of Cubes

## Key Equations

| | |
|---|---|
| difference of squares | $a^2-b^2=(a+b)(a-b)$ |
| perfect square trinomial | $a^2+2ab+b^2=(a+b)^2$ |
| sum of cubes | $a^3+b^3=(a+b)(a^2-ab+b^2)$ |
| difference of cubes | $a^3-b^3=(a-b)(a^2+ab+b^2)$ |

- The greatest common factor, or GCF, can be factored out of a polynomial. Checking for a GCF should be the first step in any factoring problem. See Example.
- Trinomials with leading coefficient 1 can be factored by finding numbers that have a product of the third term and a sum of the second term. See Example.
- Trinomials can be factored using a process called factoring by grouping. See Example.
- Perfect square trinomials and the difference of squares are special products and can be factored using equations. See Example and Example.
- The sum of cubes and the difference of cubes can be factored using equations. See Example and Example.
- Polynomials containing fractional and negative exponents can be factored by pulling out a GCF. See Example.

This page titled 1.6: Factoring Polynomials is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.5: Factoring Polynomials** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.6E: Factoring Polynomials (Exercises)

For the following exercises, find the greatest common factor.

45. $81p+9pq-27p^2q^2$
46. $12x^2y+4xy^2-18xy$
47. $88a^3b+4a^2b-144a^2$

For the following exercises, factor the polynomial.

48. $2x^2-9x-18$
49. $8a^2+30a-27$
50. $d^2-5d-66$
51. $x^2+10x+25$
52. $y^2-6y+9$
53. $4h^2-12hk+9k^2$
54. $361x^2-121$
55. $p^3+216$
56. $8x^3-125$
57. $64q^3-27p^3$
58. $4x(x-1)^{-\frac{1}{4}}+3(x-1)^3$
59. $3p(p+3)^{\frac{1}{3}}-8(p+3)^{\frac{4}{3}}$
60. $4r(2r-1)^{-\frac{2}{3}}-5(2r-1)^{\frac{1}{3}}$

This page titled 1.6E: Factoring Polynomials (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.5E: Factoring Polynomials (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.7: Rational Expressions

**Learning Objectives**

In this section students will:

- Simplify rational expressions.
- Multiply rational expressions.
- Divide rational expressions.
- Add and subtract rational expressions.
- Simplify complex rational expressions.

A pastry shop has fixed costs of $\$280$ per week and variable costs of $\$9$ per box of pastries. The shop's costs per week in terms of $x$, the number of boxes made, is $280+9x$. We can divide the costs per week by the number of boxes made to determine the cost per box of pastries.

$$\frac{280+9x}{x}$$

Notice that the result is a polynomial expression divided by a second polynomial expression. In this section, we will explore quotients of polynomial expressions.

## Simplifying Rational Expressions

The quotient of two polynomial expressions is called a rational expression. We can apply the properties of fractions to rational expressions, such as simplifying the expressions by canceling common factors from the numerator and the denominator. To do this, we first need to factor both the numerator and denominator. Let's start with the rational expression shown.

$$\frac{x^2+8x+16}{x^2+11x+28}$$

We can factor the numerator and denominator to rewrite the expression.

$$\frac{(x+4)^2}{(x+4)(x+7)}$$

Then we can simplify that expression by canceling the common factor $(x+4)$.

$$\frac{x+4}{x+7}$$

**Howto: Given a rational expression, simplify it**

1. Factor the numerator and denominator.
2. Cancel any common factors.

**Example 1.7.1: Simplifying Rational Expressions**

Simplify $\dfrac{x^2-9}{x^2+4x+3}$

**Solution**

$$\frac{(x+3)(x-3)}{(x+3)(x+1)} \qquad \text{Factor the numerator and the denominator}$$

$$\frac{x-3}{x+1} \qquad \text{Cancel common factor } (x+3)$$

**Analysis**

We can cancel the common factor because any expression divided by itself is equal to 1.

Q&A

**Can the $x^2$ term be cancelled in the last example?**

No. A factor is an expression that is multiplied by another expression. The $x^2$ term is not a factor of the numerator or the denominator.

**Exercise 1.7.1**

Simplify $\dfrac{x-6}{x^2-36}$

**Answer**

$$\frac{1}{x+6}$$

## Multiplying Rational Expressions

Multiplication of rational expressions works the same way as multiplication of any other fractions. We multiply the numerators to find the numerator of the product, and then multiply the denominators to find the denominator of the product. Before multiplying, it is helpful to factor the numerators and denominators just as we did when simplifying rational expressions. We are often able to simplify the product of rational expressions.

**Howto: Given two rational expressions, multiply them**

1. Factor the numerator and denominator.
2. Multiply the numerators.
3. Multiply the denominators.
4. Simplify.

**Example 1.7.2: Multiplying Rational Expressions**

Multiply the rational expressions and show the product in simplest form:

$$\frac{(x+5)(x-1)}{3(x+6)} \times \frac{(2x-1)}{(x+5)}$$

**Solution**

$$\frac{(x+5)(x-1)}{3(x+6)} \times \frac{(2x-1)}{(x+5)}$$ Factor the numerator and denominator.

$$\frac{(x+5)(x-1)(2x-1)}{3(x+6)(x+5)}$$ Multiply numerators and denominators

$$\frac{(x-1)(2x-1)}{3(x+6)}$$ Cancel common factors to simplify

**Exercise 1.7.2**

Multiply the rational expressions and show the product in simplest form:

$$\frac{x^2+11x+30}{x^2+5x+6} \times \frac{x^2+7x+12}{x^2+8x+16}$$

**Answer**

$$\frac{(x+5)(x+6)}{(x+2)(x+4)}$$

## Dividing Rational Expressions

Division of rational expressions works the same way as division of other fractions. To divide a rational expression by another rational expression, multiply the first expression by the reciprocal of the second. Using this approach, we would rewrite $\frac{1}{x} \div \frac{x^2}{3}$ as the product $\frac{1}{x} \cdot \frac{3}{x^2}$. Once the division expression has been rewritten as a multiplication expression, we can multiply as we did before.

$$\frac{1}{x} \cdot \frac{3}{x^2} = \frac{3}{x^3}$$

**Howto: Given two rational expressions, divide them**

1. Rewrite as the first rational expression multiplied by the reciprocal of the second.
2. Factor the numerators and denominators.
3. Multiply the numerators.
4. Multiply the denominators.
5. Simplify.

**Example 1.7.3: Dividing Rational Expressions**

Divide the rational expressions and express the quotient in simplest form:

$$\frac{2x^2+x-6}{x^2-1} \div \frac{x^2-4}{x^2+2x+1}$$

**Solution**

$$\frac{2x^2+x-6}{x^2-1} \div \frac{x^2-4}{x^2+2x+1}$$

$$\frac{2x^2+x-6}{x^2-1} \times \frac{x^2+2x+1}{x^2-4} \qquad \text{Rewrite as a multiplication problem}$$

$$\frac{(2x-3)(x+2)}{(x-1)(x+1)} \times \frac{(x+1)(x+1)}{(x-2)(x+2)} \qquad \text{Factor the numerator and denominator.}$$

$$\frac{(2x-3)(x+2)(x+1)(x+1)}{(x-1)(x+1)(x-2)(x+2)} \qquad \text{Multiply numerators and denominators}$$

$$\frac{(2x-3)(x+1)}{(x-1)(x-2)} \qquad \text{Cancel common factors to simplify}$$

**Exercise 1.7.3**

Divide the rational expressions and express the quotient in simplest form:

$$\frac{9x^2-16}{3x^2+17x-28} \div \frac{3x^2-2x-8}{x^2+5x-14}$$

**Answer**

1

## Adding and Subtracting Rational Expressions

Adding and subtracting rational expressions works just like adding and subtracting numerical fractions. To add fractions, we need to find a common denominator. Let's look at an example of fraction addition.

$$\begin{aligned}\frac{5}{24}+\frac{1}{40} &= \frac{25}{120}+\frac{3}{120}\\ &= \frac{28}{120}\\ &= \frac{7}{30}\end{aligned}$$

We have to rewrite the fractions so they share a common denominator before we are able to add. We must do the same thing when adding or subtracting rational expressions.

The easiest common denominator to use will be the **least common denominator**, or LCD. The LCD is the smallest multiple that the denominators have in common. To find the LCD of two rational expressions, we factor the expressions and multiply all of the distinct factors. For instance, if the factored denominators were $(x+3)(x+4)$ and $(x+4)(x+5)$, then the LCD would be $(x+3)(x+4)(x+5)$.

Once we find the LCD, we need to multiply each expression by the form of 1 that will change the denominator to the LCD. We would need to multiply the expression with a denominator of $(x+3)(x+4)$ by $\frac{x+5}{x+5}$ and the expression with a denominator of $(x+4)(x+5)$ by $\frac{x+3}{x+3}$.

**Howto: Given two rational expressions, add or subtract them**

1. Factor the numerator and denominator.
2. Find the LCD of the expressions.
3. Multiply the expressions by a form of 1 that changes the denominators to the LCD.
4. Add or subtract the numerators.
5. Simplify.

**Example 1.7.4: Adding Rational Expressions**

Add the rational expressions:

$$\frac{5}{x}+\frac{6}{y}$$

**Solution**

First, we have to find the LCD. In this case, the LCD will be $xy$. We then multiply each expression by the appropriate form of 1 to obtain $xy$ as the denominator for each fraction.

$$\begin{aligned}&\frac{5}{x}\times\frac{y}{y}+\frac{6}{y}\times\frac{x}{x}\\ &\frac{5y}{xy}+\frac{6x}{xy}\end{aligned}$$

Now that the expressions have the same denominator, we simply add the numerators to find the sum.

$$\frac{6x+5y}{xy}$$

**Analysis**

Multiplying by $\frac{y}{y}$ or $\frac{x}{x}$ does not change the value of the original expression because any number divided by itself is 1, and multiplying an expression by 1 gives the original expression.

### Example 1.7.5: Subtracting Rational Expressions

Subtract the rational expressions:

$$\frac{6}{x^2+4x+4}-\frac{2}{x^2-4} \tag{1.7.1}$$

**Solution**

| | |
|---|---|
| $\frac{6}{(x+2)^2}-\frac{2}{(x+2)(x-2)}$ | Factor |
| $\frac{6}{(x+2)^2}\times\frac{x-2}{x-2}-\frac{2}{(x+2)(x-2)}\times\frac{x+2}{x+2}$ | Multiply each fraction to get LCD as denominator |
| $\frac{6(x-2)}{(x+2)^2(x-2)}-\frac{2(x+2)}{(x+2)^2(x-2)}$ | Multiply |
| $\frac{6x-12-(2x+4)}{(x+2)^2(x-2)}$ | Apply distributive property |
| $\frac{4x-16}{(x+2)^2(x-2)}$ | Subtract |
| $\frac{4(x-4)}{(x+2)^2(x-2)}$ | Simplify |

### Q&A

Do we have to use the LCD to add or subtract rational expressions?

No. Any common denominator will work, but it is easiest to use the LCD.

### Exercise 1.7.4

Subtract the rational expressions: $\frac{3}{x+5}-\frac{1}{x-3}$

**Answer**

$$\frac{2(x-7)}{(x+5)(x-3)}$$

## Simplifying Complex Rational Expressions

A complex rational expression is a rational expression that contains additional rational expressions in the numerator, the denominator, or both. We can simplify complex rational expressions by rewriting the numerator and denominator as single rational expressions and dividing. The complex rational expression $\frac{a}{\frac{1}{b}+c}$ can be simplified by rewriting the numerator as the fraction $\frac{a}{1}$ and combining the expressions in the denominator as $\frac{1+bc}{b}$. We can then rewrite the expression as a multiplication problem using the reciprocal of the denominator. We get $\frac{a}{1}\cdot\frac{b}{1+bc}$, which is equal to $\frac{ab}{1+bc}$.

### Howto: Given a complex rational expression, simplify it

1. Combine the expressions in the numerator into a single rational expression by adding or subtracting.
2. Combine the expressions in the denominator into a single rational expression by adding or subtracting.
3. Rewrite as the numerator divided by the denominator.
4. Rewrite as multiplication.
5. Multiply.

6. Simplify.

### Example 1.7.6: Simplifying Complex Rational Expressions

Simplify: $\dfrac{y+\dfrac{1}{x}}{\dfrac{x}{y}}$

**Solution**

Begin by combining the expressions in the numerator into one expression.

$$y \times \frac{x}{x} + \frac{1}{x} \qquad \text{Multiply by } \frac{x}{x} \text{ to get LCD as denominator}$$
$$\frac{xy}{x} + \frac{1}{x}$$
$$\frac{xy+1}{x} \qquad \text{Add numerators}$$

Now the numerator is a single rational expression and the denominator is a single rational expression.

$$\frac{\dfrac{xy+1}{x}}{\dfrac{x}{y}}$$

We can rewrite this as division, and then multiplication.

$$\frac{xy+1}{x} \div \frac{x}{y}$$
$$\frac{xy+1}{x} \times \frac{y}{x} \qquad \text{Rewrite as multiplication}$$
$$\frac{y(xy+1)}{x^2} \qquad \text{Multiply}$$

### Exercise 1.7.5

Simplify: $\dfrac{\dfrac{x}{y}-\dfrac{y}{x}}{y}$

**Answer**

$$\frac{x^2-y^2}{xy^2}$$

### Q&A

Can a complex rational expression always be simplified?

Yes. We can always rewrite a complex rational expression as a simplified rational expression.

### Media

Access these online resources for additional instruction and practice with rational expressions.

1. Simplify Rational Expressions
2. Multiply and Divide Rational Expressions
3. Add and Subtract Rational Expressions

4. Simplify a Complex Fraction

## Key Concepts

- Rational expressions can be simplified by cancelling common factors in the numerator and denominator. See Example.
- We can multiply rational expressions by multiplying the numerators and multiplying the denominators. See Example.
- To divide rational expressions, multiply by the reciprocal of the second expression. See Example.
- Adding or subtracting rational expressions requires finding a common denominator. See Example and Example.
- Complex rational expressions have fractions in the numerator or the denominator. These expressions can be simplified. See Example.

---

This page titled 1.7: Rational Expressions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.6: Rational Expressions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 1.7E: Rational Expressions (Exercises)

For the following exercises, simplify the expression.

61. $\frac{x^2-x-12}{x^2-8x+16}$
62. $\frac{4y^2-25}{4y^2-20y+25}$
63. $\frac{2a^2-a-3}{2a^2-6a-8} \cdot \frac{5a^2-19a-4}{10a^2-13a-3}$
64. $\frac{d-4}{d^2-9} \cdot \frac{d-3}{d^2-16}$
65. $\frac{m^2+5m+6}{2m^2-5m-3} \div \frac{2m^2+3m-9}{4m^2-4m-3}$
66. $\frac{4d^2-7d-2}{6d^2-17d+10} \div \frac{8d^2+6d+1}{6d^2+7d-10}$
67. $\frac{10}{x}+\frac{6}{y}$
68. $\frac{12}{a^2+2a+1}-\frac{3}{a^2-1}$
69. $\frac{\frac{1}{d}+\frac{2}{c}}{\frac{6c+12d}{dc}}$
70. $\frac{\frac{3}{x}-\frac{7}{y}}{\frac{2}{x}}$

This page titled 1.7E: Rational Expressions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.6E: Rational Expressions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# CHAPTER OVERVIEW

## 2: Equations and Inequalities

Recall that a function is a relation that assigns to every element in the domain exactly one element in the range. Linear functions are a specific type of function that can be used to model many real-world applications, such as plant growth over time. In this chapter, we will explore linear functions, their graphs, and how to relate them to data.


2.1: Prelude to Equations and Inequalities
2.2: The Rectangular Coordinate Systems and Graphs
2.2E: The Rectangular Coordinate Systems and Graphs (Exercises)
2.3: Linear Equations in One Variable
2.3E: Linear Equations in One Variable (Exercises)
2.4: Complex Numbers
2.4E: Complex Numbers (Exercises)
2.5: Quadratic Equations
2.5E: Quadratic Equations (Exercises)
2.6: Other Types of Equations
2.6E: Other Types of Equations (Exercises)
2.7: Modeling with Equations
2.7.1: Models and Applications
2.7.1E: Models and Applications (Exercises)
2.7.2: Solve Mixture and Uniform Motion Applications
2.7.2E: Exercises
2.7.3: Solve Applications with Rational Equations
2.7.3E: Exercises
2.8: Linear and Absolute Value Inequalities
2.8.1: Linear Inequalities
2.8.1E: Exercises
2.8.2: Solve Absolute Value Inequalities
2.8.2E: Exercises
2.8E: Linear Inequalities and Absolute Value Inequalities (Exercises)


### Contributors

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.


This page titled 2: Equations and Inequalities is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 2.1: Prelude to Equations and Inequalities

For most people, the term territorial possession indicates restrictions, usually dealing with trespassing or rite of passage and takes place in some foreign location. What most Americans do not realize is that from September through December, territorial possession dominates our lifestyles while watching the NFL. In this area, territorial possession is governed by the referees who make their decisions based on what the chains reveal. If the ball is at point $A(x_1, y_1)$, then it is up to the quarterback to decide which route to point $B(x_2, y_2)$, the end zone, is most feasible.




***Figure* 2.1.1**

This page titled 2.1: Prelude to Equations and Inequalities is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.0: Prelude to Equations and Inequalities** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 2.2: The Rectangular Coordinate Systems and Graphs

**Learning Objectives**

- Plot ordered pairs in a Cartesian coordinate system.
- Graph equations by plotting points.
- Graph equations with a graphing utility.
- Find $x$-intercepts and $y$-intercepts.
- Use the distance formula.
- Use the midpoint formula.

Tracie set out from Elmhurst, IL, to go to Franklin Park. On the way, she made a few stops to do errands. Each stop is indicated by a red dot in Figure 2.2.1. Laying a rectangular coordinate grid over the map, we can see that each stop aligns with an intersection of grid lines. In this section, we will learn how to use grid lines to describe locations and changes in locations.





Figure 2.2.1

## Plotting Ordered Pairs in the Cartesian Coordinate System

An old story describes how seventeenth-century philosopher/mathematician René Descartes invented the system that has become the foundation of algebra while sick in bed. According to the story, Descartes was staring at a fly crawling on the ceiling when he realized that he could describe the fly's location in relation to the perpendicular lines formed by the adjacent walls of his room. He viewed the perpendicular lines as horizontal and vertical axes. Further, by dividing each axis into equal unit lengths, Descartes saw that it was possible to locate any object in a two-dimensional plane using just two numbers—the displacement from the horizontal axis and the displacement from the vertical axis.

While there is evidence that ideas similar to Descartes' grid system existed centuries earlier, it was Descartes who introduced the components that comprise the Cartesian coordinate system, a grid system having perpendicular axes. Descartes named the horizontal axis the $x$-axis and the vertical axis the $y$-axis.

The Cartesian coordinate system, also called the *rectangular coordinate system*, is based on a two-dimensional plane consisting of the $x$-axis and the $y$-axis. Perpendicular to each other, the axes divide the plane into four sections. Each section is called a quadrant; the quadrants are numbered counterclockwise as shown in Figure 2.2.2.





Figure 2.2.2

The center of the plane is the point at which the two axes cross. It is known as the origin, or point $(0, 0)$. From the origin, each axis is further divided into equal units: increasing, positive numbers to the right on the $x$-axis and up the $y$-axis; decreasing, negative numbers to the left on the $x$-axis and down the $y$-axis. The axes extend to positive and negative infinity as shown by the arrowheads in Figure 2.2.3.





Figure 2.2.3

Each point in the plane is identified by its $x$-coordinate, or horizontal displacement from the origin, and its $y$-coordinate, or vertical displacement from the origin. Together, we write them as an ordered pair indicating the combined distance from the origin in the form $(x, y)$. An ordered pair is also known as a coordinate pair because it consists of $x$- and $y$-coordinates. For example, we can represent the point $(3, -1)$ in the plane by moving three units to the right of the origin in the horizontal direction, and one unit down in the vertical direction. See Figure 2.2.4.





Figure 2.2.4

When dividing the axes into equally spaced increments, note that the $x$-axis may be considered separately from the $y$-axis. In other words, while the $x$-axis may be divided and labeled according to consecutive integers, the $y$-axis may be divided and labeled by increments of 2, or 10, or 100. In fact, the axes may represent other units, such as years against the balance in a savings account, or quantity against cost, and so on. Consider the rectangular coordinate system primarily as a method for showing the relationship between two quantities.

### Cartesian Coordinate System

A two-dimensional plane where the

- $x$-axis is the horizontal axis
- $y$-axis is the vertical axis

A point in the plane is defined as an ordered pair, $(x, y)$, such that $x$ is determined by its horizontal distance from the origin and $y$ is determined by its vertical distance from the origin.

### Example 2.2.1: Plotting Points in a Rectangular Coordinate System

Plot the points $(-2, 4)$, $(3, 3)$, and $(0, -3)$ in the plane.

**Solution**

To plot the point $(-2, 4)$, begin at the origin. The $x$-coordinate is $-2$, so move two units to the left. The $y$-coordinate is $4$, so then move four units up in the positive $y$ direction.

To plot the point $(3, 3)$, begin again at the origin. The $x$-coordinate is $3$, so move three units to the right. The $y$-coordinate is also $3$, so move three units up in the positive $y$ direction.

To plot the point $(0, -3)$, begin again at the origin. The $x$-coordinate is $0$. This tells us not to move in either direction along the $x$-axis. The $y$-coordinate is $-3$, so move three units down in the negative $y$ direction. See the graph in Figure $2.2.5$.





Figure 2.2.5

**Analysis**

Note that when either coordinate is zero, the point must be on an axis. If the $x$-coordinate is zero, the point is on the $y$-axis. If the $y$-coordinate is zero, the point is on the $x$-axis.

## Graphing Equations by Plotting Points

We can plot a set of points to represent an equation. When such an equation contains both an $x$ variable and a $y$ variable, it is called an **equation in two variables**. Its graph is called a **graph in two variables**. Any graph on a two-dimensional plane is a graph in two variables.

Suppose we want to graph the equation $y = 2x - 1$. We can begin by substituting a value for $x$ into the equation and determining the resulting value of $y$. Each pair of $x$- and $y$-values is an ordered pair that can be plotted. Table 2.2.1 lists values of $x$ from $-3$ to $3$ and the resulting values for $y$.

Table 2.2.1

| $x$ | $y = 2x - 1$ | $(x, y)$ |
|---|---|---|
| $-3$ | $y = 2(-3) - 1 = -7$ | $(-3, -7)$ |
| $-2$ | $y = 2(-2) - 1 = -5$ | $(-2, -5)$ |
| $-1$ | $y = 2(-1) - 1 = -3$ | $(-1, -3)$ |
| $0$ | $y = 2(0) - 1 = -1$ | $(0, -1)$ |
| $1$ | $y = 2(1) - 1 = 1$ | $(1, 1)$ |
| $2$ | $y = 2(2) - 1 = 3$ | $(2, 3)$ |
| $3$ | $y = 2(3) - 1 = 5$ | $(3, 5)$ |

We can plot the points in the table. The points for this particular equation form a line, so we can connect them (Figure 2.2.6). This is not true for all equations.





Figure 2.2.6

Note that the $x$-values chosen are arbitrary, regardless of the type of equation we are graphing. Of course, some situations may require particular values of $x$ to be plotted in order to see a particular result. Otherwise, it is logical to choose values that can be calculated easily, and it is always a good idea to choose values that are both negative and positive. There is no rule dictating how many points to plot, although we need at least two to graph a line. Keep in mind, however, that the more points we plot, the more accurately we can sketch the graph.

### Howto: Given an equation, graph by plotting points

1. Make a table with one column labeled $x$, a second column labeled with the equation, and a third column listing the resulting ordered pairs.
2. Enter $x$-values down the first column using positive and negative values. Selecting the $x$-values in numerical order will make the graphing simpler.
3. Select $x$-values that will yield $y$-values with little effort, preferably ones that can be calculated mentally.
4. Plot the ordered pairs.
5. Connect the points if they form a line.

### Example 2.2.2: Graphing an Equation in Two Variables by Plotting Points

Graph the equation $y = -x + 2$ by plotting points.

**Solution**

First, we construct a table similar to Table 2.2.2. Choose $x$ values and calculate $y$.

Table 2.2.2

| $x$ | $y = -x + 2$ | $(x, y)$ |
|---|---|---|
| $-5$ | $y = -(-5) + 2 = 7$ | $(-5, 7)$ |
| $-3$ | $y = -(-3) + 2 = 5$ | $(-3, 5)$ |
| $-1$ | $y = -(-1) + 2 = 3$ | $(-1, 3)$ |
| $0$ | $y = -(0) + 2 = 2$ | $(0, 2)$ |
| $1$ | $y = -(1) + 2 = 1$ | $(1, 1)$ |
| $3$ | $y = -(3) + 2 = -1$ | $(3, -1)$ |
| $5$ | $y = -(5) + 2 = -3$ | $(5, -3)$ |

Now, plot the points. Connect them if they form a line. See Figure 2.2.7.





Figure 2.2.7

## Exercise 2.2.1

Construct a table and graph the equation by plotting points: $y = \frac{1}{2}x + 2$.

**Answer**

Please see Table 2.2.3and graph below.

Table 2.2.3

| $x$ | $y = 12x + 2$ | $(x, y)$ |
|---|---|---|
| $-2$ | $y = 12(-2) + 2 = 1$ | $(-2, 1)$ |
| $-1$ | $y = 12(-1) + 2 = 32$ | $(-1, 32)$ |
| $0$ | $y = 12(0) + 2 = 2$ | $(0, 2)$ |
| $1$ | $y = 12(1) + 2 = 52$ | $(1, 52)$ |
| $2$ | $y = 12(2) + 2 = 3$ | $(2, 3)$ |





Figure 2.2.8

## Graphing Equations with a Graphing Utility

Most graphing calculators require similar techniques to graph an equation. The equations sometimes have to be manipulated so they are written in the style $y =$_____ . The TI-84 Plus, and many other calculator makes and models, have a mode function, which allows the window (the screen for viewing the graph) to be altered so the pertinent parts of a graph can be seen.

For example, the equation $y = 2x - 20$ has been entered in the TI-84 Plus shown in Figure $2.2.9a$. In Figure $2.2.9b$, the resulting graph is shown. Notice that we cannot see on the screen where the graph crosses the axes. The standard window screen on the TI-84 Plus shows $-10 \leq x \leq 10$, and $-10 \leq y \leq 10$. See Figure \(\PageIndex{9c}\).





Figure $2.2.9$: a. Enter the equation. b. This is the graph in the original window. c. These are the original settings.

By changing the window to show more of the positive $x$-axis and more of the negative $y$-axis, we have a much better view of the graph and the $x$- and $y$-intercepts. See Figure $2.2.10a$ and Figure $2.2.10b$





Figure 2.2.10: a. This screen shows the new window settings. b. We can clearly view the intercepts in the new window.

### Example 2.2.3: Using a Graphing Utility to Graph an Equation

Use a graphing utility to graph the equation: $y = -\frac{2}{3}x - \frac{4}{3}$ .

**Solution**

Enter the equation in the $y=$ function of the calculator. Set the window settings so that both the $x$- and $y$- intercepts are showing in the window. See Figure 2.2.11.





Figure 2.2.11

## Finding $x$-intercepts and $y$-intercepts

The **intercepts** of a graph are points at which the graph crosses the axes. The $x$-intercept is the point at which the graph crosses the \(x\)-axis. At this point, the $y$-coordinate is zero. The $y$-intercept is the point at which the graph crosses the $y$-axis. At this point, the $x$-coordinate is zero.

To determine the $x$-intercept, we set $y$ equal to zero and solve for $x$. Similarly, to determine the $y$-intercept, we set $x$ equal to zero and solve for $y$. For example, lets find the intercepts of the equation $y=3x-1$.

To find the $x$-intercept, set $y=0$.

$$\begin{aligned} y &= 3x-1 \\ 0 &= 3x-1 \\ 1 &= 3x \\ \frac{1}{3} &= x \end{aligned}$$

**$x$–intercept:** $\left(\frac{1}{3},0\right)$

To find the $y$-intercept, set $x=0$.

$$\begin{aligned} y &= 3x-1 \\ y &= 3(0)-1 \\ y &= -1 \end{aligned}$$

**$y$–intercept:** $(0,-1)$

We can confirm that our results make sense by observing a graph of the equation as in Figure 2.2.12 Notice that the graph crosses the axes where we predicted it would.





Figure 2.2.12

**Howto: GIVEN AN EQUATION, FIND THE INTERCEPTS**

1. Find the $x$-intercept by setting $y = 0$ and solving for $x$.
2. Find the $y$-intercept by setting $x = 0$ and solving for $y$.

**Example 2.2.4: Finding the Intercepts of the Given Equation**

Find the intercepts of the equation $y = -3x - 4$. Then sketch the graph using only the intercepts.

**Solution**

Set $y = 0$ to find the $x$-intercept.

$$\begin{aligned} y &= -3x - 4 \\ 0 &= -3x - 4 \\ 4 &= -3x \\ \frac{4}{3} &= x \end{aligned}$$

**$x$−intercept:** $\left(-\frac{4}{3}, 0\right)$

Set $x = 0$ to find the $y$-intercept.

$$\begin{aligned} y &= -3x - 4 \\ y &= -3(0) - 4 \\ y &= -4 \end{aligned}$$

**$y$−intercept:** $(0, -4)$

Plot both points, and draw a line passing through them as in Figure 2.2.13.





Figure 2.2.13

**Exercise 2.2.2**

Find the intercepts of the equation and sketch the graph: $y = -\frac{3}{4}x + 3$.

**Answer**

$x$-intercept is $(4, 0)$; $y$-intercept is $(0, 3)$





Figure 2.2.14

## Using the Distance Formula

Derived from the **Pythagorean Theorem**, the **distance formula** is used to find the distance between two points in the plane. The Pythagorean Theorem, $a^2 + b^2 = c^2$, is based on a right triangle where $a$ and $b$ are the lengths of the legs adjacent to the right angle, and $c$ is the length of the hypotenuse. See Figure 2.2.15.




Figure 2.2.15

The relationship of sides $|x_2 - x_1|$ and $|y_2 - y_1|$ to side $d$ is the same as that of sides $a$ and $b$ to side $c$. We use the absolute value symbol to indicate that the length is a positive number because the absolute value of any number is positive. (For example, $|-3| = 3$. ) The symbols $|x_2 - x_1|$ and $|y_2 - y_1|$ indicate that the lengths of the sides of the triangle are positive. To find the length $c$, take the square root of both sides of the Pythagorean Theorem.

$$c^2 = a^2 + b^2 \rightarrow c = \sqrt{a^2 + b^2} \tag{2.2.1}$$

It follows that the distance formula is given as

$$d^2 = (x_2 - x_1)^2 + (y_2 - y_1)^2 \rightarrow d = \sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2} \tag{2.2.2}$$

We do not have to use the absolute value symbols in this definition because any number squared is positive.

**distance between two points**

Given endpoints $(x_1, y_1)$ and $(x_2, y_2)$, the distance between two points is given by

$$d = \sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2} \tag{2.2.3}$$

**Example 2.2.5: Finding the Distance between Two Points**

Find the distance between the points $(-3, -1)$ and $(2, 3)$.

**Solution**

Let us first look at the graph of the two points. Connect the points to form a right triangle as in Figure 2.2.16




Figure 2.2.16

Then, calculate the length of $d$ using the distance formula.

$$\begin{aligned} d &= \sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2} \\ &= \sqrt{(2 - (-3))^2 + (3 - (-1))^2} \\ &= \sqrt{(5)^2 + (4)^2} \\ &= \sqrt{25 + 16} \\ &= \sqrt{41} \end{aligned}$$

**Exercise 2.2.3**

Find the distance between two points: $(1, 4)$ and $(11, 9)$.

**Answer**

$\sqrt{125} = 5\sqrt{5}$

**Example 2.2.6: Finding the Distance between Two Locations**

Let's return to the situation introduced at the beginning of this section.

Tracie set out from Elmhurst, IL, to go to Franklin Park. On the way, she made a few stops to do errands. Each stop is indicated by a red dot in Figure 2.2.1. Find the total distance that Tracie traveled. Compare this with the distance between her starting and final positions.

**Solution**

The first thing we should do is identify ordered pairs to describe each position. If we set the starting position at the origin, we can identify each of the other points by counting units east (right) and north (up) on the grid. For example, the first stop is 1 block east and 1 block north, so it is at $(1, 1)$. The next stop is 5 blocks to the east, so it is at $(5, 1)$. After that, she traveled 3 blocks east and 2 blocks north to $(8, 3)$. Lastly, she traveled 4 blocks north to $(8, 7)$. We can label these points on the grid as in Figure 2.2.17.





Figure 2.2.17

Next, we can calculate the distance. Note that each grid unit represents $1,000$ feet.

- From her starting location to her first stop at $(1, 1)$, Tracie might have driven north $1,000$ feet and then east $1,000$ feet, or vice versa. Either way, she drove $2,000$ feet to her first stop.
- Her second stop is at $(5, 1)$. So from $(1, 1)$ to $(5, 1)$, Tracie drove east $4,000$ feet.

- Her third stop is at $(8, 3)$. There are a number of routes from $(5, 1)$ to $(8, 3)$. Whatever route Tracie decided to use, the distance is the same, as there are no angular streets between the two points. Let's say she drove east $3,000$ feet and then north $2,000$ feet for a total of $5,000$ feet.
- Tracie's final stop is at $(8, 7)$. This is a straight drive north from $(8, 3)$ for a total of $4,000$ feet.

Next, we will add the distances listed in Table 2.2.4.

Table 2.2.4

| From/To | Number of Feet Driven |
|---|---|
| $(0, 0)$ to $(1, 1)$ | $2,000$ |
| $(1, 1)$ to $(5, 1)$ | $4,000$ |
| $(5, 1)$ to $(8, 3)$ | $5,000$ |
| $(8, 3)$ to $(8, 7)$ | $4,000$ |
| Total | $15,000$ |

The total distance Tracie drove is $15,000$ feet, or $2.84$ miles. This is not, however, the actual distance between her starting and ending positions. To find this distance, we can use the distance formula between the points $(0, 0)$ and $(8, 7)$.

$$\begin{aligned} d &= \sqrt{(0-8)^2 + (7-0)^2} \\ &= \sqrt{64+49} \\ &= \sqrt{113} \\ &= 10.63 \text{ units} \end{aligned}$$

At $1,000$ feet per grid unit, the distance between Elmhurst, IL, to Franklin Park is $10,630.14$feet, or $2.01$ miles. The distance formula results in a shorter calculation because it is based on the hypotenuse of a right triangle, a straight diagonal from the origin to the point $(8, 7)$. Perhaps you have heard the saying "as the crow flies," which means the shortest distance between two points because a crow can fly in a straight line even though a person on the ground has to travel a longer distance on existing roadways.

## Using the Midpoint Formula

When the endpoints of a line segment are known, we can find the point midway between them. This point is known as the midpoint and the formula is known as the **midpoint formula**. Given the endpoints of a line segment, $(x_1, y_1)$ and $(x_2, y_2)$, the midpoint formula states how to find the coordinates of the midpoint M.

$$M = \left( \frac{x_1 + x_2}{2}, \frac{y_1 + y_2}{2} \right) \tag{2.2.4}$$

A graphical view of a midpoint is shown in Figure 2.2.18. Notice that the line segments on either side of the midpoint are congruent.





Figure 2.2.18

### Example 2.2.7: Finding the Midpoint of the Line Segment

Find the midpoint of the line segment with the endpoints $(7, -2)$ and $(9, 5)$.

**Solution**

Use the formula to find the midpoint of the line segment.

$$\left(\frac{x_1+x_2}{2}, \frac{y_1+y_2}{2}\right) = \left(\frac{7+9}{2}, \frac{-2+5}{2}\right)$$
$$= \left(8, \frac{3}{2}\right)$$

### Exercise 2.2.4

Find the midpoint of the line segment with endpoints $(-2, -1)$ and $(-8, 6)$.

**Answer**

$$\left(-5, \frac{5}{2}\right)$$

### Example 2.2.8: Finding the Center of a Circle

The diameter of a circle has endpoints $(-1, -4)$ and $(5, -4)$. Find the center of the circle.

**Solution**

The center of a circle is the center, or midpoint, of its diameter. Thus, the midpoint formula will yield the center point.

$$\left(\frac{x_1+x_2}{2}, \frac{y_1+y_2}{2}\right) = \left(\frac{-1+5}{2}, \frac{-4-4}{2})\right)$$
$$= \left(\frac{4}{2}, -\frac{8}{2}\right)$$
$$= (2, 4)$$

### Media

Access these online resources for additional instruction and practice with the Cartesian coordinate system.

1. Plotting points on the coordinate plane
2. Find x and y intercepts based on the graph of a line

## Key Concepts

- We can locate, or plot, points in the Cartesian coordinate system using ordered pairs, which are defined as displacement from the $x$-axis and displacement from the $y$-axis. See Example.
- An equation can be graphed in the plane by creating a table of values and plotting points. See Example.
- Using a graphing calculator or a computer program makes graphing equations faster and more accurate. Equations usually have to be entered in the form $y =$_____. See Example.
- Finding the $x$- and $y$-intercepts can define the graph of a line. These are the points where the graph crosses the axes. See Example.
- The distance formula is derived from the Pythagorean Theorem and is used to find the length of a line segment. See Example and Example.
- The midpoint formula provides a method of finding the coordinates of the midpoint dividing the sum of the $x$-coordinates and the sum of the $y$-coordinates of the endpoints by 2. See Example and Example.

This page titled 2.2: The Rectangular Coordinate Systems and Graphs is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.1: The Rectangular Coordinate Systems and Graphs** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 2.2E: The Rectangular Coordinate Systems and Graphs (Exercises)

This page titled 2.2E: The Rectangular Coordinate Systems and Graphs (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 2.3: Linear Equations in One Variable

**Learning Objectives**

- Solve equations in one variable algebraically.
- Solve a rational equation.
- Find a linear equation.
- Given the equations of two lines, determine whether their graphs are parallel or perpendicular.
- Write the equation of a line parallel or perpendicular to a given line.

Caroline is a full-time college student planning a spring break vacation. To earn enough money for the trip, she has taken a part-time job at the local bank that pays $\$15.00/hr$, and she opened a savings account with an initial deposit of $\$400$ on January 15. She arranged for direct deposit of her payroll checks. If spring break begins March 20 and the trip will cost approximately $\$2,500$, how many hours will she have to work to earn enough to pay for her vacation? If she can only work 4 hours per day, how many days per week will she have to work? How many weeks will it take? In this section, we will investigate problems like this and others, which generate graphs like the line in Figure 2.3.1.





Figure 2.3.1

## Solving Linear Equations in One Variable

A *linear equation* is an equation of a straight line, written in one variable. The only power of the variable is 1. Linear equations in one variable may take the form $ax+b=0$ and are solved using basic algebraic operations. We begin by classifying linear equations in one variable as one of three types: identity, conditional, or inconsistent.

- An **identity equation** is true for all values of the variable. Here is an example of an identity equation:

$$3x=2x+x$$

  The *solution set* consists of all values that make the equation true. For this equation, the solution set is all real numbers because any real number substituted for $x$ will make the equation true.
- A **conditional equation** is true for only some values of the variable. For example, if we are to solve the equation $5x+2=3x-6$, we have the following:

$$\begin{aligned} 5x+2 &= 3x-6 \\ 2x &= -8 \\ x &= -4 \end{aligned}$$

  The solution set consists of one number: $-4$. It is the only solution and, therefore, we have solved a conditional equation.
- An **inconsistent equation** results in a false statement. For example, if we are to solve $5x-15=5(x-4)$, we have the following:

$$\begin{aligned} 5x-15 &= 5x-20 \\ 5x-15-5x &= 5x-20-5x \\ -15 &\neq -20 \end{aligned}$$

Indeed, $-15 \neq -20$. There is no solution because this is an inconsistent equation.

Solving linear equations in one variable involves the fundamental properties of equality and basic algebraic operations. A brief review of those operations follows.

### LINEAR EQUATION IN ONE VARIABLE

A linear equation in one variable can be written in the form

$$ax+b=0 \tag{2.3.1}$$

where a and b are real numbers, $a \neq 0$.

### Howto: Given a linear equation in one variable, use algebra to solve it

The following steps are used to manipulate an equation and isolate the unknown variable, so that the last line reads $x =$_____, if $x$ is the unknown. There is no set order, as the steps used depend on what is given:

1. We may add, subtract, multiply, or divide an equation by a number or an expression as long as we do the same thing to both sides of the equal sign. Note that we cannot divide by zero.
2. Apply the distributive property as needed: $a(b+c)=ab+ac$ .
3. Isolate the variable on one side of the equation.
4. When the variable is multiplied by a coefficient in the final stage, multiply both sides of the equation by the reciprocal of the coefficient.

### Example 2.3.1: Solving an Equation in One Variable

Solve the following equation: $2x+7=19$.

**Solution**

This equation can be written in the form $ax+b=0$ by subtracting 19 from both sides. However, we may proceed to solve the equation in its original form by performing algebraic operations.

$$\begin{aligned} 2x+7 &= 19 \\ 2x &= 12 \qquad \text{Subtract 7 from both sides} \\ x &= 6 \qquad \text{Multiply both sides by } \frac{1}{2} \text{ or divide by 2} \end{aligned}$$

The solution is 6.

### Exercise 2.3.1

Solve the linear equation in one variable: $2x+1=-9$.

**Answer**

$x=-5$

### Example 2.3.2: Solving When the Variable Appears on Both Sides

Solve the following equation: $4(x-3)+12=15-5(x+6)$ .

**Solution**

Apply standard algebraic properties.

$$\begin{aligned} 4(x-3)+12 &= 15-5(x+6) \\ 4x-12+12 &= 15-5x-30 \quad \text{Apply the distributive property} \\ 4x &= -15-5x \quad \text{Combine like terms} \\ 9x &= -15 \quad \text{Place x terms on one side and simplify} \\ x &= -\frac{15}{9} \quad \text{Multiply both sides by } \frac{1}{9}\text{, the reciprocal of 9} \\ x &= -\frac{5}{3} \end{aligned}$$

**Analysis**

This problem requires the distributive property to be applied twice, and then the properties of algebra are used to reach the final line, $x=-\frac{5}{3}$.

**? Exercise 2.3.2**

Solve the equation in one variable: $-2(3x-1)+x=14-x$ .

**Answer**

$x=-3$

## Solving a Rational Equation

In this section, we look at rational equations that, after some manipulation, result in a linear equation. If an equation contains at least one rational expression, it is a considered a **rational equation**. Recall that a **rational number** is the ratio of two numbers, such as $\frac{2}{3}$ or $\frac{7}{2}$. A rational expression is the ratio, or quotient, of two polynomials. Here are three examples.

$$\frac{x+1}{x^2-4}$$

$$\frac{1}{x-3}$$

or

$$\frac{4}{x^2+x-2}$$

Rational equations have a variable in the denominator in at least one of the terms. Our goal is to perform algebraic operations so that the variables appear in the numerator. In fact, we will eliminate all denominators by multiplying both sides of the equation by the **least common denominator** (LCD). Finding the LCD is identifying an expression that contains the highest power of all of the factors in all of the denominators. We do this because when the equation is multiplied by the LCD, the common factors in the LCD and in each denominator will equal one and will cancel out.

**✔ Example 2.3.3: Solving a Rational Equation**

Solve the rational equation:

$$\frac{7}{2x}-\frac{5}{3x}=\frac{22}{3}$$

**Solution**

We have three denominators; $2x$,$3x$, and $3$. The LCD must contain $2x$,$3x$, and $3$. An LCD of $6x$ contains all three denominators. In other words, each denominator can be divided evenly into the LCD. Next, multiply both sides of the equation by the LCD $6x$.

$$(6x)\left[\frac{7}{2x}-\frac{5}{3x}\right]=\left[\frac{22}{3}\right](6x)$$

$$(6x)\left(\frac{7}{2x}\right)-(6x)\left(\frac{5}{3x}\right)=\left(\frac{22}{3}\right)(6x)$$ Use the distributive property. Cancel out the common factors

$$3(7)-2(5)=22(2x)$$ Multiply remaining factors by each numerator.

$$21-10=44x$$

$$11=44x$$

$$\frac{11}{44}=x$$

$$\frac{1}{4}=x$$

A common mistake made when solving rational equations involves finding the LCD when one of the denominators is a binomial—two terms added or subtracted—such as $(x+1)$. Always consider a binomial as an individual factor—the terms cannot be separated. For example, suppose a problem has three terms and the denominators are $x$, $x-1$, and $3x-3$. First, factor all denominators. We then have $x$, $(x-1)$, and $3(x-1)$ as the denominators. (Note the parentheses placed around the second denominator.) Only the last two denominators have a common factor of $(x-1)$. The x in the first denominator is separate from the $x$ in the $(x-1)$ denominators. An effective way to remember this is to write factored and binomial denominators in parentheses, and consider each parentheses as a separate unit or a separate factor. The LCD in this instance is found by multiplying together the $x$, one factor of $(x-1)$, and the 3. Thus, the LCD is the following:

$$x(x-1)3=3x(x-1)$$

So, both sides of the equation would be multiplied by $3x(x-1)$. Leave the LCD in factored form, as this makes it easier to see how each denominator in the problem cancels out.

Another example is a problem with two denominators, such as $x$ and $x^2+2x$. Once the second denominator is factored as $x^2+2x=x(x+2)$ , there is a common factor of $x$ in both denominators and the LCD is $x(x+2)$.

Sometimes we have a rational equation in the form of a proportion; that is, when one fraction equals another fraction and there are no other terms in the equation.

$$\frac{a}{b}=\frac{c}{d} \tag{2.3.2}$$

We can use another method of solving the equation without finding the LCD: cross-multiplication. We multiply terms by crossing over the equal sign.

$$\text{If } \frac{a}{b}=\frac{c}{d}, \text{ then } \frac{a}{b}\times\frac{c}{d}.$$

Multiply a(d) and b(c), which results in $ad=bc$ .

Any solution that makes a denominator in the original expression equal zero must be excluded from the possibilities.

### RATIONAL EQUATIONS

A r*ational equation* contains at least one rational expression where the variable appears in at least one of the denominators.

### Howto: Given a rational equation, solve it.

1. Factor all denominators in the equation.
2. Find and exclude values that set each denominator equal to zero.
3. Find the LCD.
4. Multiply the whole equation by the LCD. If the LCD is correct, there will be no denominators left.
5. Solve the remaining equation.
6. Make sure to check solutions back in the original equations to avoid a solution producing zero in a denominator

### Example 2.3.4: Solving a Rational Equation without Factoring

Solve the following rational equation:

$$\frac{2}{x}-\frac{3}{2}=\frac{7}{2x}$$

**Solution**

We have three denominators: $x$, 2, and $2x$. No factoring is required. The product of the first two denominators is equal to the third denominator, so, the LCD is $2x$. Only one value is excluded from a solution set, 0. Next, multiply the whole equation (both sides of the equal sign) by $2x$.

$$\begin{aligned} 2x\left[\frac{2}{x}-\frac{3}{2}\right] &= \left[\frac{7}{2x}\right](2x) \\ 2x\left(\frac{2}{x}\right)-2x\left(\frac{3}{2}\right) &= \left(\frac{7}{2x}\right)(2x) \qquad \text{Distribute } 2x \\ 2(2)-3x &= 7 \qquad \text{Denominators cancel out.} \\ 4-3x &= 7 \\ -3x &= 3 \\ x &= -1 \text{ or } \{-1\} \end{aligned}$$

The proposed solution is $-1$, which is not an excluded value, so the solution set contains one number, $x=-1$, or $\{-1\}$ written in set notation.

### Exercise 2.3.4

Solve the rational equation:

$$\frac{2}{3x}=\frac{1}{4}-\frac{1}{6x}$$

**Answer**

$$x=\frac{10}{3}$$

### Example 2.3.5: Solving a Rational Equation by Factoring the Denominator

Solve the following rational equation:

$$\frac{1}{x}=\frac{1}{10}-\frac{3}{4x}$$

**Solution**

First find the common denominator. The three denominators in factored form are $x, 10=2\cdot 5$, and $4x=2\cdot 2\cdot x$. The smallest expression that is divisible by each one of the denominators is $20x$. Only $x=0$ is an excluded value. Multiply the whole equation by $20x$.

$$\begin{aligned} 20x\left(\frac{1}{x}\right) &= \left(\frac{1}{10}-\frac{3}{4x}\right)20x \\ 20 &= 2x-15 \\ 35 &= 2x \\ \frac{35}{2} &= x \end{aligned}$$

The solution is $\frac{35}{2}$.

**Exercise 2.3.5**

Solve the rational equation:

$$-\frac{5}{2x}+\frac{3}{4x}=-\frac{7}{4}$$

**Answer**

$x=1$

**Example 2.3.6: Solving Rational Equations with a Binomial in the Denominator**

Solve the following rational equations and state the excluded values:

a. $\dfrac{3}{x-6}=\dfrac{5}{x}$

b. $\dfrac{x}{x-3}=\dfrac{5}{x-3}-\dfrac{1}{2}$

c. $\dfrac{x}{x-2}=\dfrac{5}{x-2}-\dfrac{1}{2}$

**Solution**

a.

The denominators $x$ and $x-6$ have nothing in common. Therefore, the LCD is the product $x(x-6)$. However, for this problem, we can cross-multiply.

$$\begin{aligned}\frac{3}{x-6}&=\frac{5}{x}\\ 3x&=5(x-6) \qquad \text{Distribute.}\\ 3x&=5x-30\\ -2x&=-30\\ x&=15\end{aligned}$$

The solution is 15. The excluded values are 6 and 0.

b.

The LCD is $2(x-3)$. Multiply both sides of the equation by $2(x-3)$.

$$\begin{aligned}2(x-3)\left[\frac{x}{x-3}\right]&=\left[\frac{5}{x-3}-\frac{1}{2}\right]2(x-3)\\ \frac{2(x-3)x}{x-3}&=\frac{2(x-3)5}{x-3}-\frac{2(x-3)}{2}\\ 2x&=10-(x-3)\\ 2x&=13-x\\ 3x&=13\\ x&=\frac{13}{3}\end{aligned}$$

The solution is $\dfrac{13}{3}$. The excluded value is 3.

c.

The least common denominator is $2(x-2)$. Multiply both sides of the equation by $x(x-2)$.

$$2(x-2)\left[\frac{x}{x-2}\right] = \left[\frac{5}{x-2}-\frac{1}{2}\right]2(x-2)$$
$$2x = 10-(x-2)$$
$$2x = 12-x$$
$$3x = 12$$
$$x = 4$$

The solution is 4. The excluded value is 2.

**? Exercise 2.3.6**

Solve $\frac{-3}{2x+1} = \frac{4}{3x+1}$. State the excluded values.

**Answer**

$x = -\frac{7}{17}$. Excluded values are $x = -12$ and $x = -13$.

**✓ Example 2.3.7: Solving a Rational Equation with Factored Denominators and Stating Excluded Values**

Solve the rational equation after factoring the denominators: $\frac{2}{x+1} - \frac{1}{x-1} = \frac{2x}{x^2-1}$. State the excluded values.

**Solution**

We must factor the denominator $x^2-1$. We recognize this as the difference of squares, and factor it as $(x-1)(x+1)$. Thus, the LCD that contains each denominator is $(x-1)(x+1)$. Multiply the whole equation by the LCD, cancel out the denominators, and solve the remaining equation.

$$(x+1)(x-1)\left[\frac{2}{x+1}-\frac{1}{x-1}\right] = \left[\frac{2x}{x^2-1}\right](x+1)(x-1)$$
$$2(x-1)-(x+1) = 2x$$
$$2x-2-x-1 = 2x \text{ Distribute the negative sign}$$
$$-3-x = 0$$
$$x = -3$$

The solution is $-3$. The excluded values are 1 and $-1$.

**? Exercise 2.3.7**

Solve the rational equation:

$$\frac{2}{x-2}+\frac{1}{x+1} = \frac{1}{x^2-x-2}$$

**Answer**

$x = \frac{1}{3}$

## Finding a Linear Equation

Perhaps the most familiar form of a linear equation is the *slope-intercept form*, written as

$$y = mx+b \tag{2.3.3}$$

where $m =$ slope and $b = $ y−intercept. Let us begin with the slope.

The **slope** of a line refers to the ratio of the vertical change in $y$ over the horizontal change in $x$ between any two points on a line. It indicates the direction in which a line slants as well as its steepness. Slope is sometimes described as rise over run.

$$m = \frac{y_2 - y_1}{x_2 - x_1} \tag{2.3.4}$$

If the slope is positive, the line slants to the right. If the slope is negative, the line slants to the left. As the slope increases, the line becomes steeper. Some examples are shown in Figure 2.3.2. The lines indicate the following slopes: $m = -3$, $m = 2$, and $m = \frac{1}{3}$.





Figure 2.3.2

### THE SLOPE OF A LINE

The slope of a line, $m$, represents the change in $y$ over the change in $x$. Given two points, $(x_1, y_1)$ and $(x_2, y_2)$, the following formula determines the slope of a line containing these points:

$$m = \frac{y_2 - y_1}{x_2 - x_1} \tag{2.3.5}$$

### Example 2.3.8: Finding the Slope of a Line Given Two Points

Find the slope of a line that passes through the points $(2, -1)$ and $(-5, 3)$.

**Solution**

We substitute the $y$-values and the $x$-values into the formula.

$$\begin{aligned} m &= \frac{3 - (-1)}{-5 - 2} \\ &= \frac{4}{-7} \\ &= -\frac{4}{7} \end{aligned}$$

The slope is $-\frac{4}{7}$

**Analysis**

It does not matter which point is called $(x_1, y_1)$ or $(x_2, y_2)$. As long as we are consistent with the order of the $y$ terms and the order of the $x$ terms in the numerator and denominator, the calculation will yield the same result.

**Exercise 2.3.8**

Find the slope of the line that passes through the points $(-2, 6)$ and $(1, 4)$.

**Answer**

$$m = -\frac{2}{3}$$

**Example 2.3.9: Identifying the Slope and y-intercept of a Line Given an Equation**

Identify the slope and $y$-intercept, given the equation $y = -\frac{3}{4}x - 4$.

**Solution**

As the line is in $y = mx + b$ form, the given line has a slope of $m = -\frac{3}{4}$. The $y$-intercept is $b = -4$.

**Analysis**

The $y$-intercept is the point at which the line crosses the $y$-axis. On the $y$-axis, $x = 0$. We can always identify the $y$-intercept when the line is in slope-intercept form, as it will always equal $b$. Or, just substitute $x = 0$ and solve for $y$.

### The Point-Slope Formula

Given the slope and one point on a line, we can find the equation of the line using the point-slope formula.

$$y - y_1 = m(x - x_1) \tag{2.3.6}$$

This is an important formula, as it will be used in other areas of college algebra and often in calculus to find the equation of a tangent line. We need only one point and the slope of the line to use the formula. After substituting the slope and the coordinates of one point into the formula, we simplify it and write it in slope-intercept form.

**THE POINT-SLOPE FORMULA**

Given one point and the slope, the point-slope formula will lead to the equation of a line:

$$y - y_1 = m(x - x_1) \tag{2.3.7}$$

**Example 2.3.10: Finding the Equation of a Line Given the Slope and One Point**

Write the equation of the line with slope $m = -3$ and passing through the point $(4, 8)$. Write the final equation in slope-intercept form.

**Solution**

Using the point-slope formula, substitute $-3$ for m and the point $(4, 8)$ for $(x_1, y_1)$.

$$\begin{aligned} y - y_1 &= m(x - x_1) \\ y - 8 &= -3(x - 4) \\ y - 8 &= -3x + 12 \\ y &= -3x + 20 \end{aligned}$$

**Analysis**

Note that any point on the line can be used to find the equation. If done correctly, the same final equation will be obtained.

**Exercise 2.3.10**

Given $m = 4$, find the equation of the line in slope-intercept form passing through the point $(2, 5)$.

**Answer**

$y = 4x - 3$

### Example 2.3.11: Finding the Equation of a Line Passing Through Two Given Points

Find the equation of the line passing through the points $(3, 4)$ and $(0, -3)$. Write the final equation in slope-intercept form.

**Solution**

First, we calculate the slope using the slope formula and two points.

$$\begin{aligned} m &= \frac{-3-4}{0-3} \\ m &= \frac{-7}{-3} \\ m &= \frac{7}{3} \end{aligned}$$

Next, we use the point-slope formula with the slope of $\frac{7}{3}$, and either point. Let's pick the point $(3, 4)$ for $(x_1, y_1)$.

$$\begin{aligned} y - 4 &= \frac{7}{3}(x-3) \\ y - 4 &= \frac{7}{3}x - 7 \\ y &= \frac{7}{3}x - 3 \end{aligned}$$

In slope-intercept form, the equation is written as $y = \frac{7}{3}x - 3$

**Analysis**

To prove that either point can be used, let us use the second point $(0, -3)$ and see if we get the same equation.

$$\begin{aligned} y - (-3) &= \frac{7}{3}(x-0) \\ y + 3 &= \frac{7}{3}x \\ y &= \frac{7}{3}x - 3 \end{aligned}$$

We see that the same line will be obtained using either point. This makes sense because we used both points to calculate the slope.

## Standard Form of a Line

Another way that we can represent the equation of a line is in **standard form**. Standard form is given as

$$Ax + By = C \tag{2.3.8}$$

where $A$, $B$, and $C$ are integers. The $x$- and $y$-terms are on one side of the equal sign and the constant term is on the other side.

### Example 2.3.12: Finding the Equation of a Line and Writing It in Standard Form

Find the equation of the line with $m = -6$ and passing through the point $\left(\frac{1}{4}, -2\right)$. Write the equation in standard form.

**Solution**

We begin using the point-slope formula.

$$\begin{aligned} y-(-2) &= -6\left(x-\frac{1}{4}\right) \\ y+2 &= -6x+\frac{3}{2} \end{aligned}$$

From here, we multiply through by 2, as no fractions are permitted in standard form, and then move both variables to the left aside of the equal sign and move the constants to the right.

$$\begin{aligned} 2(y+2) &= \left(-6x+\frac{3}{2}\right)2 \\ 2y+4 &= -12x+3 \\ 12x+2y &= -1 \end{aligned}$$

This equation is now written in standard form.

**? Exercise 2.3.12**

Find the equation of the line in standard form with slope $m=-\frac{1}{3}$ and passing through the point $(1,13)$.

**Answer**

$x+3y=2$

### Vertical and Horizontal Lines

The equations of vertical and horizontal lines do not require any of the preceding formulas, although we can use the formulas to prove that the equations are correct. The equation of a **vertical line** is given as

$$x=c \tag{2.3.9}$$

where $c$ is a constant. The slope of a vertical line is undefined, and regardless of the $y$-value of any point on the line, the $x$-coordinate of the point will be $c$.

Suppose that we want to find the equation of a line containing the following points: $(-3,-5)$,$(-3,1)$,$(-3,3)$, and $(-3,5)$. First, we will find the slope.

$$m=\frac{5-3}{-3-(-3)}=\frac{2}{0}$$

Zero in the denominator means that the slope is undefined and, therefore, we cannot use the point-slope formula. However, we can plot the points. Notice that all of the $x$-coordinates are the same and we find a vertical line through $x=-3$. See Figure 2.3.3.

The equation of a **horizontal line** is given as

$$y=c \tag{2.3.10}$$

where $c$ is a constant. The slope of a horizontal line is zero, and for any $x$-value of a point on the line, the $y$-coordinate will be $c$.

Suppose we want to find the equation of a line that contains the following set of points: $(-2,-2)$,$(0,-2)$,$(3,-2)$, and $(5,-2)$. We can use the point-slope formula. First, we find the slope using any two points on the line.

$$\begin{aligned} m &= \frac{-2-(-2)}{0-(-2)} \\ &= \frac{0}{2} \\ &= 0 \end{aligned}$$

Use any point for $(x_1,y_1)$ in the formula, or use the y-intercept.

$$\begin{aligned} y-(-2) &= 0(x-3) \\ y+2 &= 0 \\ y &= -2 \end{aligned}$$

The graph is a horizontal line through $y = -2$. Notice that all of the y-coordinates are the same. See Figure 2.3.3.





Figure 2.3.3: The line x = −3 is a vertical line. The line y = −2 is a horizontal line

### Example 2.3.13: Finding the Equation of a Line Passing Through the Given Points

Find the equation of the line passing through the given points: $(1, -3)$ and $(1, 4)$.

**Solution**

The $x$-coordinate of both points is 1. Therefore, we have a vertical line, $x = 1$.

### Exercise 2.3.13

Find the equation of the line passing through $(-5, 2)$ and $(2, 2)$.

**Answer**

Horizontal line: $y = 2$

## Determining Whether Graphs of Lines are Parallel or Perpendicular

Parallel lines have the same slope and different y-intercepts. Lines that are parallel to each other will never intersect. For example, Figure 2.3.4 shows the graphs of various lines with the same slope, $m = 2$.





Figure 2.3.4: Parallel lines

All of the lines shown in the graph are parallel because they have the same slope and different y-intercepts.

Lines that are **perpendicular** intersect to form a $90^\circ$ -angle. The slope of one line is the negative **reciprocal** of the other. We can show that two lines are perpendicular if the product of the two slopes is $-1$ : $m_1 \cdot m_2 = -1$ . For example, Figure 2.3.5 shows the graph of two perpendicular lines. One line has a slope of 3; the other line has a slope of $-\frac{1}{3}$.

$$m_1 \cdot m_2 = -1$$
$$3 \cdot \left(-\frac{1}{3}\right) = -1$$





Figure 2.3.5: Perpendicular lines

**Example 2.3.14: Graphing Two Equations, and Determining Whether the Lines are Parallel, Perpendicular, or Neither**

Graph the equations of the given lines, and state whether they are parallel, perpendicular, or neither: $3y = -4x + 3$ and $3x - 4y = 8$.

**Solution**

The first thing we want to do is rewrite the equations so that both equations are in slope-intercept form.

First equation:

$$\begin{aligned} 3y &= -4x+3 \\ y &= -\frac{4}{3}x+1 \end{aligned}$$

Second equation:

$$\begin{aligned} 3x-4y &= 8 \\ -4y &= -3x+8 \\ y &= \frac{3}{4}x-2 \end{aligned}$$

See the graph of both lines in Figure 2.3.6.





Figure 2.3.6

From the graph, we can see that the lines appear perpendicular, but we must compare the slopes.

$$\begin{aligned} m_1 &= -\frac{4}{3} \\ m_2 &= \frac{3}{4} \\ m_1 \cdot m_2 &= \left(-\frac{4}{3}\right)\left(\frac{3}{4}\right) \\ &= -1 \end{aligned}$$

The slopes are negative reciprocals of each other, confirming that the lines are perpendicular.

## Exercise 2.3.14

Graph the two lines and determine whether they are parallel, perpendicular, or neither: $2y-x=10$ and $2y=x+4$.

**Answer**

Parallel lines: equations are written in slope-intercept form.





Figure 2.3.7

## Writing the Equations of Lines Parallel or Perpendicular to a Given Line

As we have learned, determining whether two lines are parallel or perpendicular is a matter of finding the slopes. To write the equation of a line parallel or perpendicular to another line, we follow the same principles as we do for finding the equation of any line. After finding the slope, use the **point-slope formula** to write the equation of the new line.

**Given an equation for a line, write the equation of a line parallel or perpendicular to it.**

1. Find the slope of the given line. The easiest way to do this is to write the equation in slope-intercept form.
2. Use the slope and the given point with the point-slope formula.
3. Simplify the line to slope-intercept form and compare the equation to the given line.

**Example 2.3.15: Writing the Equation of a Line Parallel to a Given Line Passing Through a Given Point**

Write the equation of line parallel to a $5x + 3y = 1$ and passing through the point $(3, 5)$.

**Solution**

First, we will write the equation in slope-intercept form to find the slope.

$$\begin{aligned} 5x + 3y &= 1 \\ 3y &= -5x + 1 \\ y &= -\frac{5}{3}x + \frac{1}{3} \end{aligned}$$

The slope is $m = -\frac{5}{3}$. The y-intercept is $13$, but that really does not enter into our problem, as the only thing we need for two lines to be parallel is the same slope. The one exception is that if the $y$-intercepts are the same, then the two lines are the same line. The next step is to use this slope and the given point with the point-slope formula.

$$\begin{aligned} y - 5 &= -\frac{5}{3}(x - 3) \\ y - 5 &= -\frac{5}{3}x + 5 \\ y &= -\frac{5}{3}x + 10 \end{aligned}$$

The equation of the line is $y = -\frac{5}{3}x + 10$. See Figure 2.3.8.





Figure 2.3.8

**? Exercise 2.3.15**

Find the equation of the line parallel to $5x = 7 + y$ and passing through the point $(-1, -2)$.

**Answer**

$y = 5x + 3$

**✓ Example 2.3.16: Finding the Equation of a Line Perpendicular to a Given Line Passing Through a Given Point**

Find the equation of the line perpendicular to $5x - 3y + 4 = 0$ $(-4, 1)$ .

**Solution**

The first step is to write the equation in slope-intercept form.

$$\begin{aligned} 5x - 3y + 4 &= 0 \\ -3y &= -5x - 4 \\ y &= \frac{5}{3}x + \frac{4}{3} \end{aligned}$$

We see that the slope is $m = \frac{5}{3}$. This means that the slope of the line perpendicular to the given line is the negative reciprocal, or $-\frac{3}{5}$. Next, we use the point-slope formula with this new slope and the given point.

$$\begin{aligned} y - 1 &= -\frac{3}{5}(x - (-4)) \\ y - 1 &= -\frac{3}{5}x - \frac{12}{5} \\ y &= -\frac{3}{5}x - \frac{12}{5} + \frac{5}{5} \\ y &= -\frac{3}{5}x - \frac{7}{5} \end{aligned}$$

**Media**

Access these online resources for additional instruction and practice with linear equations.

1. Solving rational equations
2. Equation of a line given two points
3. Finding the equation of a line perpendicular to another line through a given point
4. Finding the equation of a line parallel to another line through a given point

## Key Concepts

- We can solve linear equations in one variable in the form $ax+b=0$ using standard algebraic properties. See Example and Example.
- A rational expression is a quotient of two polynomials. We use the LCD to clear the fractions from an equation. See Example and Example.
- All solutions to a rational equation should be verified within the original equation to avoid an undefined term, or zero in the denominator. See Example and Example.
- Given two points, we can find the slope of a line using the slope formula. See Example.
- We can identify the slope and $y$-intercept of an equation in slope-intercept form. See Example.
- We can find the equation of a line given the slope and a point. See Example.
- We can also find the equation of a line given two points. Find the slope and use the point-slope formula. See Example.
- The standard form of a line has no fractions. See Example.
- Horizontal lines have a slope of zero and are defined as $y=c$, where $c$ is a constant.
- Vertical lines have an undefined slope (zero in the denominator), and are defined as $x=c$, where $c$ is a constant. See Example.
- Parallel lines have the same slope and different $y$-intercepts. See Example.
- Perpendicular lines have slopes that are negative reciprocals of each other unless one is horizontal and the other is vertical. See Example.

## Contributors and Attributions

**The OpenStax College name, OpenStax College logo, OpenStax College book covers, OpenStax CNX name, and OpenStax CNX logo are not subject to the creative commons license and may not be reproduced without the prior and express written consent of Rice University.** For questions regarding this license, please contact partners@openstaxcollege.org. If you use this textbook as a bibliographic reference, then you should cite it as follows: OpenStax College, Models and Applications. OpenStax CNX. Apr 1, 2015 http://cnx.org/contents/c49b7453-abd...baac08df9ebc@4. If you redistribute this textbook in a print format, then you must include on every physical page the following attribution: "Download for free at http://cnx.org/contents/c49b7453-abd...baac08df9ebc@4." If you redistribute part of this textbook, then you must retain in every digital format page view (including but not limited to EPUB, PDF, and HTML) and on every physical printed page the following attribution: "Download for free at http://cnx.org/contents/c49b7453-abd...baac08df9ebc@4."

---

This page titled 2.3: Linear Equations in One Variable is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.2: Linear Equations in One Variable** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 2.3E: Linear Equations in One Variable (Exercises)

This page titled 2.3E: Linear Equations in One Variable (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 2.4: Complex Numbers

**Learning Objectives**

- Add and subtract complex numbers.
- Multiply and divide complex numbers.
- Solve quadratic equations with complex numbers

Discovered by Benoit Mandelbrot around 1980, the Mandelbrot Set is one of the most recognizable fractal images. The image is built on the theory of self-similarity and the operation of iteration. Zooming in on a fractal image brings many surprises, particularly in the high level of repetition of detail that appears as magnification increases. The equation that generates this image turns out to be rather simple.




Figure 2.4.1: The Mandelbrot set exhibits similarity, which is best shown in an animation.

In order to better understand it, we need to become familiar with a new set of numbers. Keep in mind that the study of mathematics continuously builds upon itself. Negative integers, for example, fill a void left by the set of positive integers. The set of rational numbers, in turn, fills a void left by the set of integers. The set of real numbers fills a void left by the set of rational numbers. Not surprisingly, the set of real numbers has voids as well. In this section, we will explore a set of numbers that fills voids in the set of real numbers and find out how to work within it.

## Expressing Square Roots of Negative Numbers as Multiples of $i$

We know how to find the square root of any positive real number. In a similar way, we can find the square root of any negative number. The difference is that the root is not real. If the value in the radicand is negative, the root is said to be an imaginary number.The imaginary number $i$ is defined as the square root of $-1$.

$$\sqrt{-1} = i \tag{2.4.1}$$

So, using properties of radicals,

$$i^2 = (\sqrt{-1})^2 = -1 \tag{2.4.2}$$

We can write the square root of any negative number as a multiple of $i$. Consider the square root of $-49$.

$$\begin{aligned} \sqrt{-49} &= \sqrt{49 \times (-1)} \\ &= \sqrt{49}\sqrt{-1} \\ &= 7i \end{aligned}$$

We use $7i$ and not $-7i$ because the principal root of $49$ is the positive root.

A complex number is the sum of a real number and an imaginary number. A complex number is expressed in standard form when written $a+bi$ where $a$ is the real part and $b$ is the imaginary part. For example, $5+2i$ is a complex number. So, too, is $3+4i\sqrt{3}$.




Imaginary numbers differ from real numbers in that a squared imaginary number produces a negative real number. Recall that when a positive real number is squared, the result is a positive real number and when a negative real number is squared, the result is also a positive real number. Complex numbers consist of real and imaginary numbers.

**Definition: IMAGINARY AND COMPLEX NUMBERS**

A *complex number* is a number of the form $a+bi$ where

1. $a$ is the real part of the complex number.
2. $b$ is the imaginary part of the complex number.

If $b=0$, then $a+bi$ is a real number. If $a=0$ and $b$ is not equal to $0$, the complex number is called a pure imaginary number. An **imaginary number** is an even root of a negative number.

**Howto: Given an imaginary number, express it in the standard form of a complex number**

1. Write $\sqrt{-a}$ as $\sqrt{a}\sqrt{-1}$.
2. Express $\sqrt{-1}$ as $i$.
3. Write $\sqrt{a}\times i$ in simplest form.

**Example 2.4.1: Expressing an Imaginary Number in Standard Form**

Express $\sqrt{-9}$ in standard form.

**Solution**

$$\begin{aligned}\sqrt{-9} &= \sqrt{9}\sqrt{-1)} \\ &= 3i\end{aligned}$$

In standard form, this is $0+3i$.

**Exercise 2.4.1**

Express $\sqrt{-24}$ in standard form.

**Answer**

$\sqrt{-24}=0+2i\sqrt{6}$

## Plotting a Complex Number on the Complex Plane

We cannot plot complex numbers on a number line as we might real numbers. However, we can still represent them graphically. To represent a complex number, we need to address the two components of the number. We use the **complex plane**, which is a coordinate system in which the horizontal axis represents the real component and the vertical axis represents the imaginary component. Complex numbers are the points on the plane, expressed as ordered pairs $(a,b)$, where $a$ represents the coordinate for the horizontal axis and $b$ represents the coordinate for the vertical axis.

Let's consider the number $-2+3i$. The real part of the complex number is $-2$ and the imaginary part is $3$. We plot the ordered pair $(-2,3)$ to represent the complex number $-2+3i$, as shown in Figure 2.4.2.





Figure 2.4.2

## COMPLEX PLANE

In the complex plane, the horizontal axis is the real axis, and the vertical axis is the imaginary axis, as shown in Figure 2.4.3.





Figure 2.4.3

## Howto: Given a complex number, represent its components on the complex plane

1. Determine the real part and the imaginary part of the complex number.
2. Move along the horizontal axis to show the real part of the number.
3. Move parallel to the vertical axis to show the imaginary part of the number.
4. Plot the point.

## Example 2.4.2: Plotting a Complex Number on the Complex Plane

Plot the complex number $3 - 4i$ on the complex plane.

### Solution

The real part of the complex number is $3$, and the imaginary part is $-4$. We plot the ordered pair $(3, -4)$ as shown in Figure 2.4.4.





Figure 2.4.4

**? Exercise 2.4.2**

Plot the complex number $-4-i$ on the complex plane.

**Answer**





Figure 2.4.5

## Adding and Subtracting Complex Numbers

Just as with real numbers, we can perform arithmetic operations on complex numbers. To add or subtract complex numbers, we combine the real parts and then combine the imaginary parts.

**COMPLEX NUMBERS: ADDITION AND SUBTRACTION**

Adding complex numbers:

$$(a+bi)+(c+di)=(a+c)+(b+d)i \tag{2.4.3}$$

Subtracting complex numbers:

$$(a+bi)-(c+di)=(a-c)+(b-d)i \tag{2.4.4}$$

**Howto: Given two complex numbers, find the sum or difference**

1. Identify the real and imaginary parts of each number.
2. Add or subtract the real parts.
3. Add or subtract the imaginary parts.

**Example 2.4.3: Adding and Subtracting Complex Numbers**

Add or subtract as indicated.

a. $(3-4i)+(2+5i)$
b. $(-5+7i)-(-11+2i)$

**Solution**

a.
$$\begin{aligned}(3-4i)+(2+5i) &= 3-4i+2+5i\\ &= 3+2+(-4i)+5i\\ &= (3+2)+(-4+5)i\\ &= 5+i\end{aligned}$$

b.
$$\begin{aligned}(-5+7i)-(-11+2i) &= -5+7i+11-2i\\ &= -5+11+7i-2i\\ &= (-5+11)+(7-2)i\\ &= 6+5i\end{aligned}$$

**Exercise 2.4.3**

Subtract $2+5i$ from $3-4i$.

**Answer**

$(3-4i)-(2+5i)=1-9i$

## Multiplying Complex Numbers

Multiplying complex numbers is much like multiplying binomials. The major difference is that we work with the real and imaginary parts separately.

### Multiplying a Complex Number by a Real Number

Lets begin by multiplying a complex number by a real number. We distribute the real number just as we would with a binomial. Consider, for example, $3(6+2i)$ :

$$\begin{aligned}3(6+2i) &= (3\cdot 6)+(3\cdot 2i) && \text{Distribute.}\\ &= 18+6i && \text{Simplify.}\end{aligned}$$

**Howto: Given a complex number and a real number, multiply to find the product**

1. Use the distributive property.
2. Simplify.

### Example 2.4.4: Multiplying a Complex Number by a Real Number

Find the product $4(2+5i)$.

**Solution**

Distribute the 4.

$$\begin{aligned} 4(2+5i) &= (4\cdot 2)+(4\cdot 5i) \\ &= 8+20i \end{aligned}$$

### Exercise 2.4.4

Find the product: $\frac{1}{2}(5-2i)$.

**Answer**

$\frac{5}{2}-i$

## Multiplying Complex Numbers Together

Now, let's multiply two complex numbers. We can use either the distributive property or more specifically the FOIL method because we are dealing with binomials. Recall that FOIL is an acronym for multiplying First, Inner, Outer, and Last terms together. The difference with complex numbers is that when we get a squared term, $i^2$, it equals $-1$.

$$\begin{aligned} (a+bi)(c+di) &= ac+adi+bci+bdi^2 \\ &= ac+adi+bci-bd(-1) \qquad i^2=-1 \\ &= ac+adi+bci-bd \\ &= (ac-bd)+(ad+bc)i \end{aligned}$$

Group real terms and imaginary terms.

### Howto: Given two complex numbers, multiply to find the product

1. Use the distributive property or the FOIL method.
2. Remember that $i^2=-1$.
3. Group together the real terms and the imaginary terms

### Example 2.4.5: Multiplying a Complex Number by a Complex Number

Multiply $(4+3i)(2-5i)$.

**Solution**

$$\begin{aligned} (4+3i)(2-5i) &= 4(2)-4(5i)+3i(2)-(3i)(5i) \\ &= 8-20i+6i-15(i^2) \\ &= (8+15)+(-20+6)i \\ &= 23-14i \end{aligned}$$

### Exercise 2.4.5

Multiply: $(3-4i)(2+3i)$.

**Answer**

$18+i$

## Dividing Complex Numbers

Dividing two complex numbers is more complicated than adding, subtracting, or multiplying because we cannot divide by an imaginary number, meaning that any fraction must have a real-number denominator to write the answer in standard form $a+bi$. We need to find a term by which we can multiply the numerator and the denominator that will eliminate the imaginary portion of the denominator so that we end up with a real number as the denominator. This term is called the complex conjugate of the denominator, which is found by changing the sign of the imaginary part of the complex number. In other words, the complex conjugate of $a+bi$ is $a-bi$. For example, the product of $a+bi$ and $a-bi$ is

$$\begin{aligned}(a+bi)(a-bi) &= a^2-abi+abi-b^2i^2\\ &= a^2+b^2\end{aligned}$$

The result is a real number.

Note that complex conjugates have an opposite relationship: The complex conjugate of $a+bi$ is $a-bi$, and the complex conjugate of $a-bi$ is $a+bi$. Further, when a quadratic equation with real coefficients has complex solutions, the solutions are always complex conjugates of one another.

Suppose we want to divide $c+di$ by $a+bi$, where neither $a$ nor $b$ equals zero. We first write the division as a fraction, then find the complex conjugate of the denominator, and multiply.

$$\frac{c+di}{a+bi} \text{ where } a\neq 0 \text{ and } b\neq 0$$

Multiply the numerator and denominator by the complex conjugate of the denominator.

$$\begin{aligned}\frac{(c+di)}{(a+bi)}\cdot\frac{(a-bi)}{(a-bi)} &= \frac{(c+di)(a-bi)}{(a+bi)(a-bi)}\\ &= \frac{ca-cbi+adi-bdi^2}{a^2-abi+abi-b^2i^2} && \text{Apply the distributive property}\\ &= \frac{ca-cbi+adi-bd(-1)}{a^2-abi+abi-b^2(-1)} && \text{Simplify, remembering that } i^2=-1\\ &= \frac{(ca+bd)+(ad-cb)i}{a^2+b^2}\end{aligned}$$

**Definition: THE COMPLEX CONJUGATE**

The complex conjugate of a complex number $a+bi$ is $a-bi$. It is found by changing the sign of the imaginary part of the complex number. The real part of the number is left unchanged.

1. When a complex number is multiplied by its complex conjugate, the result is a real number.
2. When a complex number is added to its complex conjugate, the result is a real number.

**Example 2.4.6: Finding Complex Conjugates**

Find the complex conjugate of each number.

a. $2+i\sqrt{5}$

b. $-\frac{1}{2}i$

**Solution**

a. The number is already in the form $a+bi$. The complex conjugate is $a-bi$, or $2-i\sqrt{5}$.

b. We can rewrite this number in the form $a+bi$ as $0-\frac{1}{2}i$. The complex conjugate is $a-bi$, or $0+\frac{1}{2}i$. This can be written simply as $\frac{1}{2}i$.

**Analysis**

Although we have seen that we can find the complex conjugate of an imaginary number, in practice we generally find the complex conjugates of only complex numbers with both a real and an imaginary component. To obtain a real number from an imaginary number, we can simply multiply by $i$.

**Exercise 2.4.6**

Find the complex conjugate of $-3+4i$.

**Answer**

$-3-4i$

**How to: Given two complex numbers, divide one by the other**

1. Write the division problem as a fraction.
2. Determine the complex conjugate of the denominator.
3. Multiply the numerator and denominator of the fraction by the complex conjugate of the denominator.
4. Simplify.

**Example 2.4.7: Dividing Complex Numbers**

Divide $(2+5i)$ by $(4-i)$.

**Solution**

We begin by writing the problem as a fraction.

$$\frac{(2+5i)}{(4-i)}$$

Then we multiply the numerator and denominator by the complex conjugate of the denominator.

$$\frac{(2+5i)}{(4-i)}\cdot\frac{(4+i)}{(4+i)}$$

To multiply two complex numbers, we expand the product as we would with polynomials (using FOIL).

$$\begin{aligned}\frac{(2+5i)}{(4-i)}\cdot\frac{(4+i)}{(4+i)} &= \frac{8+2i+20i+5i^2}{16+4i-4i-i^2}\\ &= \frac{8+2i+20i+5(-1)}{16+4i-4i-(-1)} \quad i^2=-1\\ &= \frac{3+22i}{17}\\ &= \frac{3}{17}+\frac{22}{17i}\end{aligned}$$

Separate real and imaginary parts.

Note that this expresses the quotient in standard form.

## Simplifying Powers of $i$

The powers of $i$ are cyclic. Let's look at what happens when we raise $i$ to increasing powers.

$$i^1=i$$

$$i^2=-1$$

$$i^3 = i^2 \cdot i = -1 \cdot i = -i$$

$$i^4 = i^3 \cdot i = -i \cdot i = -i^2 = -(-1) = 1$$

$$i^5 = i^4 \cdot i = 1 \cdot i = i$$

We can see that when we get to the fifth power of i , it is equal to the first power. As we continue to multiply $i$ by increasing powers, we will see a cycle of four. Let's examine the next four powers of $i$.

$$i^6 = i^5 \cdot i = i \cdot i = i^2 = -1$$

$$i^7 = i^6 \cdot i = i^2 \cdot i = i^3 = -i$$

$$i^8 = i^7 \cdot i = i^3 \cdot i = i^4 = 1$$

$$i^9 = i^8 \cdot i = i^4 \cdot i = i^5 = i$$

The cycle is repeated continuously: $i, -1, -i, 1,$every four powers.

### Example 2.4.8: Simplifying Powers of $i$

Evaluate: $i^{35}$.

**Solution**

Since $i^4 = 1$, we can simplify the problem by factoring out as many factors of $i^4$ as possible. To do so, first determine how many times 4 goes into $35 : 35 = 4 \cdot 8 + 3$ .

$$i^{35} = i^{4 \cdot 8 + 3} = i^{4 \cdot 8} \cdot i^3 = \left(i^4\right)^8 \cdot i^3 = i^8 \cdot i^3 = i^3 = -i$$

### Exercise 2.4.7

Evaluate: $i^{18}$

**Answer**

$-1$

### Q&A

Can we write $i^{35}$ in other helpful ways?

As we saw in Example 2.4.8, we reduced $i^{35}$ to $i^3$ by dividing the exponent by 4 and using the remainder to find the simplified form. But perhaps another factorization of $i^{35}$ may be more useful. Table 2.4.1 shows some other possible factorizations.

Table 2.4.1

| Factorization of $i^{35}$ | $i^{34} \cdot i$ | $i^{33} \cdot i^2$ | $i^{31} \cdot i^4$ | $i^{19} \cdot i^{16}$ |
|---|---|---|---|---|
| Reduced form | $\left(i^2\right)^{17} \cdot i$ | $i^{33} \cdot (-1)$ | $i^{31} \cdot 1$ | $i^{19} \cdot \left(i^4\right)^4$ |
| Simplified form | $(-1)^{17} \cdot i$ | $-i^{33}$ | $i^{31}$ | $i^{19}$ |

Each of these will eventually result in the answer we obtained above but may require several more steps than our earlier method.

### Media

Access these online resources for additional instruction and practice with complex numbers.

1. Adding and Subtracting Complex Numbers
2. Multiply Complex Numbers

3. Multiplying Complex Conjugates
4. Raising i to Powers

## Key Concepts

- The square root of any negative number can be written as a multiple of $i$. See Example.
- To plot a complex number, we use two number lines, crossed to form the complex plane. The horizontal axis is the real axis, and the vertical axis is the imaginary axis. See Example.
- Complex numbers can be added and subtracted by combining the real parts and combining the imaginary parts. See Example.
- Complex numbers can be multiplied and divided.
  - To multiply complex numbers, distribute just as with polynomials. See Example and Example.
  - To divide complex numbers, multiply both numerator and denominator by the complex conjugate of the denominator to eliminate the complex number from the denominator. See Example and Example.
- The powers of i are cyclic, repeating every fourth one. See Example.

---

This page titled 2.4: Complex Numbers is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.4: Complex Numbers** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 2.4E: Complex Numbers (Exercises)

This page titled 2.4E: Complex Numbers (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 2.5: Quadratic Equations

**Learning Objectives**

- Solve quadratic equations by factoring.
- Solve quadratic equations by the square root property.
- Solve quadratic equations by completing the square.
- Solve quadratic equations by using the quadratic formula.

The computer monitor on the left in Figure $2.5.1$ is a $23.6$-inch model and the one on the right is a $27$-inch model. Proportionally, the monitors appear very similar. If there is a limited amount of space and we desire the largest monitor possible, how do we decide which one to choose? In this section, we will learn how to solve problems such as this using four different methods.



Figure 2.5.1

## Solving Quadratic Equations by Factoring

An equation containing a second-degree polynomial is called a **quadratic equation**. For example, equations such as $2x^2+3x-1=0$ and $x^2-4=0$ are quadratic equations. They are used in countless ways in the fields of engineering, architecture, finance, biological science, and, of course, mathematics.

Often the easiest method of solving a quadratic equation is **factoring**. Factoring means finding expressions that can be multiplied together to give the expression on one side of the equation.

If a quadratic equation can be factored, it is written as a product of linear terms. Solving by factoring depends on the zero-product property, which states that if $a\cdot b=0$, then $a=0$ or $b=0$, where a and b are real numbers or algebraic expressions. In other words, if the product of two numbers or two expressions equals zero, then one of the numbers or one of the expressions must equal zero because zero multiplied by anything equals zero.

Multiplying the factors expands the equation to a string of terms separated by plus or minus signs. So, in that sense, the operation of multiplication undoes the operation of factoring. For example, expand the factored expression $(x-2)(x+3)$ by multiplying the two factors together.

$$\begin{aligned}(x-2)(x+3) &= x^2+3x-2x-6\\ &= x^2+x-6\end{aligned}$$

The product is a quadratic expression. Set equal to zero, $x^2+x-6=0$ is a quadratic equation. If we were to factor the equation, we would get back the factors we multiplied.

The process of factoring a quadratic equation depends on the leading coefficient, whether it is $1$ or another integer. We will look at both situations; but first, we want to confirm that the equation is written in standard form, $ax^2+bx+c=0$, where $a$, $b$, and $c$ are real numbers, and $a\neq 0$. The equation $x^2+x-6=0$ is in standard form.

We can use the zero-product property to solve quadratic equations in which we first have to factor out the greatest common factor(GCF), and for equations that have special factoring formulas as well, such as the difference of squares, both of which we will see later in this section.

**ZERO-PRODUCT PROPERTY AND QUADRATIC EQUATIONS**

The **zero-product property** states

$$\text{If } a\cdot b=0\text{, then } a=0 \text{ or } b=0,$$

where $a$ and $b$ are real numbers or algebraic expressions.

A quadratic equation is an equation containing a second-degree polynomial; for example

$$ax^2+bx+c=0 \tag{2.5.1}$$

where $a$, $b$, and $c$ are real numbers, and if $a \neq 0$, it is in standard form.

## Solving Quadratics with a Leading Coefficient of 1

In the quadratic equation $x^2 + x - 6 = 0$ , the leading coefficient, or the coefficient of $x^2$, is 1. We have one method of factoring quadratic equations in this form.

### How to: Factor a quadratic equation with the leading coefficient of 1

1. Find two numbers whose product equals $c$ and whose sum equals $b$.
2. Use those numbers to write two factors of the form $(x + k)$ or $(x - k)$, where k is one of the numbers found in step 1. Use the numbers exactly as they are. In other words, if the two numbers are 1 and $-2$, the factors are $(x + 1)(x - 2)$.
3. Solve using the zero-product property by setting each factor equal to zero and solving for the variable.

### Example 2.5.1: Solving a Quadratic with Leading Coefficient of 1

Factor and solve the equation: $x^2 + x - 6 = 0$ .

**Solution**

To factor $x^2 + x - 6 = 0$ , we look for two numbers whose product equals $-6$ and whose sum equals 1. Begin by looking at the possible factors of $-6$.

$$1 \cdot (-6)$$

$$(-6) \cdot 1$$

$$2 \cdot (-3)$$

$$3 \cdot (-2)$$

The last pair, $3 \cdot (-2)$ sums to 1, so these are the numbers. Note that only one pair of numbers will work. Then, write the factors.

$$(x - 2)(x + 3) = 0$$

To solve this equation, we use the zero-product property. Set each factor equal to zero and solve.

$$\begin{aligned} (x - 2)(x + 3) &= 0 \\ (x - 2) &= 0 \\ x &= 2 \\ (x + 3) &= 0 \\ x &= -3 \end{aligned}$$

The two solutions are 2 and $-3$. We can see how the solutions relate to the graph in Figure 2.5.2. The solutions are the x-intercepts of $x^2 + x - 6 = 0$ .




Figure 2.5.2

**Exercise 2.5.1**

Factor and solve the quadratic equation: $x^2 - 5x - 6 = 0$ .

**Answer**

$(x-6)(x+1) = 0$ , $x = 6, x = -1$

**Example 2.5.2: Solve the Quadratic Equation by Factoring**

Solve the quadratic equation by factoring: $x^2 + 8x + 15 = 0$ .

**Solution**

Find two numbers whose product equals $15$ and whose sum equals $8$. List the factors of $15$.

$$1 \cdot 15$$

$$3 \cdot 5$$

$$(-1) \cdot (-15)$$

$$(-3) \cdot (-5)$$

The numbers that add to $8$ are $3$ and $5$. Then, write the factors, set each factor equal to zero, and solve.

$$\begin{aligned} (x+3)(x+5) &= 0 \\ (x+3) &= 0 \\ x &= -3 \\ (x+5) &= 0 \\ x &= -5 \end{aligned}$$

The solutions are $-3$ and $-5$.

**Exercise 2.5.2**

Solve the quadratic equation by factoring: $x^2 - 4x - 21 = 0$ .

**Answer**

$(x-7)(x+3) = 0$ , $x = 7, x = -3$

### Example 2.5.3: Using Zero-Product Property to Solve a Quadratic Equation

Solve the difference of squares equation using the zero-product property: $x^2 - 9 = 0$ .

**Solution**

Recognizing that the equation represents the difference of squares, we can write the two factors by taking the square root of each term, using a minus sign as the operator in one factor and a plus sign as the operator in the other. Solve using the zero-factor property.

$$\begin{aligned} x^2 - 9 &= 0 \\ (x-3)(x+3) &= 0 \\ x - 3 &= 0 \\ x &= 3 \\ (x+3) &= 0 \\ x &= -3 \end{aligned}$$

The solutions are $3$ and $-3$.

### Exercise 2.5.3

Solve by factoring: $x^2 - 25 = 0$ .

**Answer**

$(x+5)(x-5) = 0, x = -5, x = 5$

## Factoring and Solving a Quadratic Equation of Higher Order

When the leading coefficient is not $1$, we factor a quadratic equation using the method called *grouping*, which requires four terms.

### Grouping: Steps for factoring quadratic equations

With the equation in standard form, let's review the grouping procedures

1. With the quadratic in standard form, $ax^2 + bx + c = 0$ , multiply $a \cdot c$ .
2. Find two numbers whose product equals ac and whose sum equals $b$.
3. Rewrite the equation replacing the $bx$ term with two terms using the numbers found in step $1$ as coefficients of $x$.
4. Factor the first two terms and then factor the last two terms. The expressions in parentheses must be exactly the same to use grouping.
5. Factor out the expression in parentheses.
6. Set the expressions equal to zero and solve for the variable.

### Example 2.5.4: Solving a Quadratic Equation Using Grouping

Use grouping to factor and solve the quadratic equation: $4x^2 + 15x + 9 = 0$ .

**Solution**

First, multiply $ac$ : $4(9) = 36$ . Then list the factors of $36$.

$$1 \cdot 36$$

$$2 \cdot 18$$

$$3 \cdot 12$$

$$4 \cdot 9$$

$$6 \cdot 6$$

The only pair of factors that sums to $15$ is $3 + 12$. Rewrite the equation replacing the b term, $15x$, with two terms using $3$ and $12$ as coefficients of $x$. Factor the first two terms, and then factor the last two terms.

$$
\begin{aligned}
4x^2+3x+12x+9 &= 0 \\
x(4x+3)+3(4x+3) &= 0 \\
(4x+3)(x+3) &= 0 \qquad \text{Solve using the zero-product property} \\
(4x+3) &= 3 \\
x &= -\frac{3}{4} \\
(x+3) &= 0 \\
x &= -3
\end{aligned}
$$

The solutions are $-\frac{3}{4}$, and $-3$. See Figure 2.5.3.





Figure 2.5.3

**? Exercise 2.5.4**

Solve using factoring by grouping: $12x^2+11x+2=0$ .

**Answer**

$(3x+2)(4x+1)=0$ , $x=-\frac{2}{3}$ , $x=-\frac{1}{4}$

**✓ Example 2.5.5: Solving a Higher Degree Quadratic Equation by Factoring**

Solve the equation by factoring: $-3x^3-5x^2-2x=0$ .

**Solution**

This equation does not look like a quadratic, as the highest power is 3, not 2. Recall that the first thing we want to do when solving any equation is to factor out the GCF, if one exists. And it does here. We can factor out $-x$ from all of the terms and then proceed with grouping.

$$
\begin{aligned}
-3x^3-5x^2-2x &= 0 \\
-x(3x^2+5x+2) &= 0 \\
-x(3x^2+3x+2x+2) &= 0 \qquad \text{Use grouping on the expression in parentheses} \\
-x[3x(x+1)+2(x+1)] &= 0 \\
-x(3x+2)(x+1) &= 0
\end{aligned}
$$

Now, we use the zero-product property. Notice that we have three factors.

$$
\begin{aligned}
-x &= 0 \\
x &= 0 \\
3x+2 &= 0 \\
x &= -\frac{2}{3} \\
x+1 &= 0 \\
x &= -1
\end{aligned}
$$

The solutions are $0$, $-\frac{2}{3}$, and $-1$.

**Exercise 2.5.5**

Solve by factoring: $x^3+11x^2+10x=0$ .

**Answer**

$x=0, x=-10, x=-1$

## Using the Square Root Property

When there is no linear term in the equation, another method of solving a quadratic equation is by using the **square root property**, in which we isolate the $x^2$ term and take the square root of the number on the other side of the equals sign. Keep in mind that sometimes we may have to manipulate the equation to isolate the $x^2$ term so that the square root property can be used.

**THE SQUARE ROOT PROPERTY**

With the $x^2$ term isolated, the square root property states that:

$$\text{if } x^2=k \text{, then } x=\pm\sqrt{k}$$

where $k$ is a nonzero real number.

**Howto: Given a quadratic equation with an $x^2$ term but no $x$ term, use the square root property to solve it**

1. Isolate the $x^2$ term on one side of the equal sign.
2. Take the square root of both sides of the equation, putting a $\pm$ sign before the expression on the side opposite the squared term.
3. Simplify the numbers on the side with the $\pm$ sign.

**Example 2.5.6: Solving a Simple Quadratic Equation Using the Square Root Property**

Solve the quadratic using the square root property: $x^2=8$.

**Solution**

Take the square root of both sides, and then simplify the radical. Remember to use a $\pm$ sign before the radical symbol.

$$\begin{aligned} x^2 &= 8 \\ x &= \pm\sqrt{8} \\ &= \pm 2\sqrt{2} \end{aligned}$$

The solutions are $2\sqrt{2}, -2\sqrt{2}$

**Example 2.5.7: Solving a Quadratic Equation Using the Square Root Property**

Solve the quadratic equation: $4x^2+1=7$ .

**Solution**

First, isolate the $x^2$ term. Then take the square root of both sides.

$$\begin{aligned} 4x^2+1 &= 7 \\ 4x^2 &= 6 \\ x^2 &= \frac{6}{4} \\ x &= \pm\frac{\sqrt{6}}{2} \end{aligned}$$

The solutions are $\frac{\sqrt{6}}{2}$, and $-\frac{\sqrt{6}}{2}$.

**? Exercise 2.5.6**

Solve the quadratic equation using the square root property: $3(x-4)^2=15$.

**Answer**

$x=4\pm\sqrt{5}$

## Completing the Square

Not all quadratic equations can be factored or can be solved in their original form using the square root property. In these cases, we may use a method for solving a **quadratic equation** known as **completing the square**. Using this method, we add or subtract terms to both sides of the equation until we have a perfect square trinomial on one side of the equal sign. We then apply the square root property. To complete the square, the leading coefficient, $a$, must equal 1. If it does not, then divide the entire equation by $a$. Then, we can use the following procedures to solve a quadratic equation by completing the square.

We will use the example $x^2+4x+1=0$ to illustrate each step.

Given a quadratic equation that cannot be factored, and with $a=1$, first add or subtract the constant term to the right sign of the equal sign.

$$\begin{aligned} x^2+4x+1 &= 0 \\ x^2+4x &= -1 \qquad \text{Multiply the b term by } \frac{1}{2} \text{ and square it.} \\ \frac{1}{2}(4) &= 2 \\ 2^2 &= 4 \qquad \text{Add } \left(\frac{1}{2}\right)^2 \text{ to both sides of the equal sign and simplify the right side. We have} \\ x^2+4x+4 &= -1+4 \\ x^2+4x+4 &= 3 \qquad \text{The left side of the equation can now be factored as a perfect square.} \\ (x+2)^2 &= 3 \\ \sqrt{(x+2)^2} &= \pm\sqrt{3} \qquad \text{Use the square root property and solve.} \\ \sqrt{(x+2)^2} &= \pm\sqrt{3} \\ x+2 &= \pm\sqrt{3} \\ x &= -2\pm\sqrt{3} \end{aligned}$$

The solutions are $-2+\sqrt{3}$, and $-2-\sqrt{3}$.

**✓ Example 2.5.8: Solving a Quadratic by Completing the Square**

Solve the quadratic equation by completing the square: $x^2-3x-5=0$ .

**Solution**

First, move the constant term to the right side of the equal sign.

$$\begin{aligned} x^2-3x &= 5 \qquad \text{Then, take } \frac{1}{2} \text{ of the b term and square it.} \\ \frac{1}{2}(-3) &= -\frac{3}{2} \\ \left(-\frac{3}{2}\right)^2 &= \frac{9}{4} \\ x^2-3x+\left(-\frac{3}{2}\right)^2 &= 5+\left(-\frac{3}{2}\right)^2 \qquad \text{Add the result to both sides of the equal sign.} \\ x^2-3x+\frac{9}{4} &= 5+\frac{9}{4} \end{aligned}$$

Factor the left side as a perfect square and simplify the right side.

$$\begin{aligned} \left(x-\frac{3}{2}\right)^2 &= \frac{29}{4} \\ (x-\frac{3}{2}) &= \pm\frac{\sqrt{29}}{2} \qquad \text{Use the square root property and solve.} \\ x &= \frac{3}{2}\pm\frac{\sqrt{29}}{2} \end{aligned}$$

The solutions are $\frac{3}{2}+\frac{\sqrt{29}}{2}$, and $\frac{3}{2}-\frac{\sqrt{29}}{2}$

**Exercise 2.5.7**

Solve by completing the square: $x^2-6x=13$.

**Answer**

$x=3\pm\sqrt{22}$

## Using the Quadratic Formula

The fourth method of solving a **quadratic equation** is by using the **quadratic formula**, a formula that will solve all quadratic equations. Although the quadratic formula works on any quadratic equation in standard form, it is easy to make errors in substituting the values into the formula. Pay close attention when substituting, and use parentheses when inserting a negative number.

We can derive the quadratic formula by **completing the square**. We will assume that the leading coefficient is positive; if it is negative, we can multiply the equation by $-1$ and obtain a positive a. Given $ax^2+bx+c=0, a\neq 0$, we will complete the square as follows:

First, move the constant term to the right side of the equal sign:

$$ax^2+bx=-c$$

As we want the leading coefficient to equal 1, divide through by $a$:

$$x^2+\frac{b}{a}x=-\frac{c}{a}$$

Then, find $\frac{1}{2}$ of the middle term, and add $(\frac{1}{2}\frac{b}{a})^2=\frac{b^2}{4a^2}$ to both sides of the equal sign:

$$x^2+\frac{b}{a}x+\frac{b^2}{4a^2}=\frac{b^2}{4a^2}-\frac{c}{a}$$

Next, write the left side as a perfect square. Find the common denominator of the right side and write it as a single fraction:

$$(x+\frac{b}{2a})^2=\frac{b^2-4ac}{4a^2}$$

Now, use the square root property, which gives

$$x+\frac{b}{2a}=\pm\sqrt{\frac{b^2-4ac}{4a^2}}$$

$$x+\frac{b}{2a}=\frac{\pm\sqrt{b^2-4ac}}{2a}$$

Finally, add $-\frac{b}{2a}$ to both sides of the equation and combine the terms on the right side. Thus,

$$x=\frac{-b\pm\sqrt{b^2-4ac}}{2a}$$

**THE QUADRATIC FORMULA**

Written in standard form, $ax^2+bx+c=0$, any quadratic equation can be solved using the **quadratic formula**:

$$x=\frac{-b\pm\sqrt{b^2-4ac}}{2a} \tag{2.5.2}$$

where $a$, $b$, and $c$ are real numbers and $a\neq 0$.

**How to**

**Given a quadratic equation, solve it using the quadratic formula**

1. Make sure the equation is in standard form: $ax^2+bx+c=0$.
2. Make note of the values of the coefficients and constant term, $a$, $b$, and $c$.

3. Carefully substitute the values noted in step 2 into the equation. To avoid needless errors, use parentheses around each number input into the formula.
4. Calculate and solve.

**Example 2.5.9: Solve the Quadratic Equation Using the Quadratic Formula**

Solve the quadratic equation: $x^2+5x+1=0$ .

**Solution**

Identify the coefficients: $a=1, b=5, c=1$ . Then use the quadratic formula.

$$\begin{aligned} x &= \frac{-(5)\pm\sqrt{(5)^2-4(1)(1)}}{2(1)} \\ &= \frac{-5\pm\sqrt{25-4}}{2} \\ &= \frac{-5\pm\sqrt{21}}{2} \end{aligned}$$

**Example 2.5.10: Solving a Quadratic Equation with the Quadratic Formula**

Use the quadratic formula to solve $x^2+x+2=0$ .

**Solution**

First, we identify the coefficients: $a=1$,$b=1$, and $c=2$.

Substitute these values into the quadratic formula.

$$\begin{aligned} x &= \frac{-b\pm\sqrt{b^2-4ac}}{2a} \\ &= \frac{-(1)\pm\sqrt{(1)^2-4(1)(2)}}{2(1)} \\ &= \frac{-1\pm\sqrt{1-8}}{2} \\ &= \frac{-1\pm\sqrt{-7}}{2} \\ &= \frac{-1\pm i\sqrt{7}}{2} \end{aligned}$$

**Exercise 2.5.8**

Solve the quadratic equation using the quadratic formula: $9x^2+3x-2=0$ .

**Answer**

$x=-\frac{2}{3}, x=\frac{1}{3}$

## The Discriminant

The **quadratic formula** not only generates the solutions to a quadratic equation, it tells us about the nature of the solutions when we consider the **discriminant**, or the expression under the radical, $b^2-4ac$ . The discriminant tells us whether the solutions are real numbers or complex numbers, and how many solutions of each type to expect. Table 2.5.1 relates the value of the discriminant to the solutions of a quadratic equation.

Table 2.5.1

| Value of Discriminant | Results |
|---|---|
| $b^2-4ac=0$ | One rational solution (double solution) |

| Value of Discriminant | Results |
|---|---|
| $b^2-4ac>0$, perfect square | Two rational solutions |
| $b^2-4ac>0$, not a perfect square | Two irrational solutions |
| $b^2-4ac<0$ | Two complex solutions |

**THE DISCRIMINANT**

For $ax^2+bx+c=0$ , where $a$, $b$, and $c$ are real numbers, the **discriminant** is the expression under the radical in the quadratic formula: $b^2-4ac$. It tells us whether the solutions are real numbers or complex numbers and how many solutions of each type to expect.

**Example 2.5.11: Using the Discriminant to Find the Nature of the Solutions to a Quadratic Equation**

Use the discriminant to find the nature of the solutions to the following quadratic equations:

a. $x^2+4x+4=0$
b. $8x^2+14x+3=0$
c. $3x^2-5x-2=0$
d. $3x^2-10x+15=0$

**Solution**

Calculate the discriminant $b^2-4ac$ for each equation and state the expected type of solutions.

a.

$x^2+4x+4=0$

$b^2-4ac=(4)^2-4(1)(4)=0$ There will be one rational double solution.

b.

$8x^2+14x+3=0$

$b^2-4ac=(14)^2-4(8)(3)=100$ As $100$ is a perfect square, there will be two rational solutions.

c.

$3x^2-5x-2=0$

$b^2-4ac=(-5)^2-4(3)(-2)=49$ As $49$ is a perfect square, there will be two rational solutions.

d.

$3x^2-10x+15=0$

$b^2-4ac=(-10)^2-4(3)(15)=-80$ There will be two complex solutions.

## Using the Pythagorean Theorem

One of the most famous formulas in mathematics is the **Pythagorean Theorem**. It is based on a right triangle, and states the relationship among the lengths of the sides as $a^2+b^2=c^2$ , where $a$ and $b$ refer to the legs of a right triangle adjacent to the $90^\circ$ angle, and $c$ refers to the hypotenuse. It has immeasurable uses in architecture, engineering, the sciences, geometry, trigonometry, and algebra, and in everyday applications.

We use the Pythagorean Theorem to solve for the length of one side of a triangle when we have the lengths of the other two. Because each of the terms is squared in the theorem, when we are solving for a side of a triangle, we have a quadratic equation. We can use the methods for solving quadratic equations that we learned in this section to solve for the missing side.

The Pythagorean Theorem is given as

$$a^2+b^2=c^2 \tag{2.5.3}$$

where $a$ and $b$ refer to the legs of a right triangle adjacent to the $90^\circ$ angle, and $c$ refers to the hypotenuse, as shown in .




Figure 2.5.4

### Example 2.5.12: Finding the Length of the Missing Side of a Right Triangle

Find the length of the missing side of the right triangle in Figure 2.5.5.




Figure 2.5.5

**Solution**

As we have measurements for side $b$ and the hypotenuse, the missing side is $a$.

$$\begin{aligned} a^2+b^2 &= c^2 \\ a^2+(4)^2 &= (12)^2 \\ a^2+16 &= 144 \\ a^2 &= 128 \\ a &= \sqrt{128} \\ &= 8\sqrt{2} \end{aligned}$$

### Exercise 2.5.9

Use the Pythagorean Theorem to solve the right triangle problem: Leg a measures 4 units, leg b measures 3 units. Find the length of the hypotenuse.

**Answer**

5 units

### Media

Access these online resources for additional instruction and practice with quadratic equations.

1. Solving Quadratic Equations by Factoring
2. The Zero-Product Property
3. Completing the Square
4. Quadratic Formula with Two Rational Solutions
5. Length of a leg of a right triangle

## Key Equations

| | |
|---|---|
| quadratic formula | $x=\dfrac{-b\pm\sqrt{b^2-4ac}}{2a}$ |

## Key Concepts

- Many quadratic equations can be solved by factoring when the equation has a leading coefficient of 1 or if the equation is a difference of squares. The zero-factor property is then used to find solutions. See Example, Example, and Example.
- Many quadratic equations with a leading coefficient other than 1 can be solved by factoring using the grouping method. See Example and Example.
- Another method for solving quadratics is the square root property. The variable is squared. We isolate the squared term and take the square root of both sides of the equation. The solution will yield a positive and negative solution. See Example and Example.
- Completing the square is a method of solving quadratic equations when the equation cannot be factored. See Example.

- A highly dependable method for solving quadratic equations is the quadratic formula, based on the coefficients and the constant term in the equation. See Example.
- The discriminant is used to indicate the nature of the roots that the quadratic equation will yield: real or complex, rational or irrational, and how many of each. See Example.
- The Pythagorean Theorem, among the most famous theorems in history, is used to solve right-triangle problems and has applications in numerous fields. Solving for the length of one side of a right triangle requires solving a quadratic equation. See Example.

---

This page titled 2.5: Quadratic Equations is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.5: Quadratic Equations** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 2.5E: Quadratic Equations (Exercises)

This page titled 2.5E: Quadratic Equations (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 2.6: Other Types of Equations

**Learning Objectives**

- Solve equations involving rational exponents.
- Solve equations using factoring.
- Solve radical equations.
- Solve absolute value equations.
- Solve other types of equations.

We have solved linear equations, rational equations, and quadratic equations using several methods. However, there are many other types of equations, and we will investigate a few more types in this section. We will look at equations involving rational exponents, polynomial equations, radical equations, absolute value equations, equations in quadratic form, and some rational equations that can be transformed into quadratics. Solving any equation, however, employs the same basic algebraic rules. We will learn some new techniques as they apply to certain equations, but the algebra never changes.

## Solving Equations Involving Rational Exponents

Rational exponents are exponents that are fractions, where the numerator is a power and the denominator is a root. For example, $16^{\frac{1}{2}}$ is another way of writing $\sqrt{16}$; $8^{\frac{1}{3}}$ is another way of writing $\sqrt[3]{8}$. The ability to work with rational exponents is a useful skill, as it is highly applicable in calculus.

We can solve equations in which a variable is raised to a rational exponent by raising both sides of the equation to the reciprocal of the exponent. The reason we raise the equation to the reciprocal of the exponent is because we want to eliminate the exponent on the variable term, and a number multiplied by its reciprocal equals 1. For example,

$$\frac{2}{3}\left(\frac{3}{2}\right)=1$$

$$3\left(\frac{1}{3}\right)=1,$$

and so on.

**RATIONAL EXPONENTS**

A *rational exponent* indicates a power in the numerator and a root in the denominator. There are multiple ways of writing an expression, a variable, or a number with a rational exponent:

$$a^{\frac{m}{n}}=\left(a^{\frac{1}{n}}\right)^{m}=a^{m\frac{1}{n}}=\sqrt[n]{a^{m}}=\left(\sqrt[n]{a}\right)^{m} \tag{2.6.1}$$

**Example 2.6.1: Evaluating a Number Raised to a Rational Exponent**

Evaluate $8^{\frac{2}{3}}$

**Solution**

Whether we take the root first or the power first depends on the number. It is easy to find the cube root of 8, so rewrite $8^{\frac{2}{3}}$ as $\left(8^{\frac{1}{3}}\right)^{2}$.

$$\begin{aligned}\left(8^{\frac{1}{3}}\right)^{2}&=(2)^{2}\\&=4\end{aligned}$$

## Exercise 2.6.1

Evaluate $64^{-\frac{1}{3}}$

**Answer**

$\frac{1}{4}$

## Example 2.6.2: Solve the Equation Including a Variable Raised to a Rational Exponent

Solve the equation in which a variable is raised to a rational exponent: $x^{\frac{5}{4}} = 32$.

### Solution

The way to remove the exponent on $x$ is by raising both sides of the equation to a power that is the reciprocal of $\frac{5}{4}$, which is $\frac{4}{5}$.

$$\begin{aligned} x^{\frac{5}{4}} &= 32 \\ \left(x^{\frac{5}{4}}\right)^{\frac{4}{5}} &= (32)^{\frac{4}{5}} \\ x &= (2)^4 \\ &= 16 \end{aligned}$$

## Exercise 2.6.2

Solve the equation $x^{\frac{3}{2}} = 125$.

**Answer**

$25$

## Example 2.6.3: Solving an Equation Involving Rational Exponents and Factoring

Solve $3x^{\frac{3}{4}} = x^{\frac{1}{2}}$.

### Solution

This equation involves rational exponents as well as factoring rational exponents. Let us take this one step at a time. First, put the variable terms on one side of the equal sign and set the equation equal to zero.

$$\begin{aligned} 3x^{\frac{3}{4}} - \left(x^{\frac{1}{2}}\right) &= x^{\frac{1}{2}} - \left(x^{\frac{1}{2}}\right) \\ 3x^{\frac{3}{4}} - x^{\frac{1}{2}} &= 0 \end{aligned}$$

Now, it looks like we should factor the left side, but what do we factor out? We can always factor the term with the lowest exponent. Rewrite $x^{\frac{1}{2}}$ as $x^{\frac{2}{4}}$. Then, factor out $x^{\frac{2}{4}}$ from both terms on the left.

$$\begin{aligned} 3x^{\frac{3}{4}} - x^{\frac{1}{2}} &= 0 \\ x^{\frac{2}{4}}\left(3x^{\frac{1}{4}} - 1\right) &= 0 \end{aligned}$$

Where did $x^{\frac{1}{4}}$ come from? Remember, when we multiply two numbers with the same base, we add the exponents. Therefore, if we multiply $x^{\frac{2}{4}}$ back in using the distributive property, we get the expression we had before the factoring, which is what should happen. We need an exponent such that when added to $\frac{2}{4}$ equals $\frac{3}{4}$. Thus, the exponent on $x$ in the parentheses is $\frac{1}{4}$.

Let us continue. Now we have two factors and can use the zero factor theorem.

$$\begin{aligned} x^{\frac{2}{4}}\left(3x^{\frac{1}{4}}-1\right) &= 0 \\ x^{\frac{2}{4}} &= 0 \\ x &= 0 \\ 3x^{\frac{1}{4}}-1 &= 0 \\ 3x^{\frac{1}{4}} &= 1 \\ x^{\frac{1}{4}} &= \frac{1}{3}, \qquad \text{Divide both sides by } 3. \\ \left(x^{\frac{1}{4}}\right)^4 &= \left(\frac{1}{3}\right)^4, \qquad \text{Raise both sides to the reciprocal of } \frac{1}{4} \\ x &= \frac{1}{81} \end{aligned}$$

The two solutions are 0 and $\frac{1}{81}$.

**Exercise 2.6.3**

Solve: $(x+5)^{\frac{3}{2}}=8$.

**Answer**

$-1$

## Solving Equations Using Factoring

We have used factoring to solve quadratic equations, but it is a technique that we can use with many types of polynomial equations, which are equations that contain a string of terms including numerical coefficients and variables. When we are faced with an equation containing polynomials of degree higher than 2, we can often solve them by factoring.

**POLYNOMIAL EQUATIONS**

A polynomial of degree $n$ is an expression of the type

$$a_n x^n + a_{n-1}x^{n-1} + \cdots + a_2 x^2 + a_1 x + a_0 \tag{2.6.2}$$

where $n$ is a positive integer and $a_n, \ldots, a_0$ are real numbers and $a_n \neq 0$.

Setting the polynomial equal to zero gives a **polynomial equation**. The total number of solutions (real and complex) to a polynomial equation is equal to the highest exponent $n$.

**Example 2.6.4: Solving a Polynomial by Factoring**

Solve the polynomial by factoring: $5x^4 = 80x^2$.

**Solution**

First, set the equation equal to zero. Then factor out what is common to both terms, the GCF.

$$\begin{aligned} 5x^4 - 80x^2 &= 0 \\ 5x^2(x^2 - 16) &= 0 \end{aligned}$$

Notice that we have the difference of squares in the factor $x^2 - 16$, which we will continue to factor and obtain two solutions. The first term, $5x^2$, generates, technically, two solutions as the exponent is 2, but they are the same solution.

$$\begin{aligned} 5x^2 &= 0 \\ x &= 0 \\ x^2 - 16 &= 0 \\ (x+4)(x-4) &= 0 \\ x &= 4 \\ x &= -4 \end{aligned}$$

The solutions are 0 (double solution), 4, and $-4$.

**Analysis**

We can see the solutions on the graph in Figure 2.6.1. The x-coordinates of the points where the graph crosses the $x$-axis are the solutions—the $x$-intercepts. Notice on the graph that at the solution 0, the graph touches the $x$-axis and bounces back. It does not cross the $x$-axis. This is typical of double solutions.





Figure 2.6.1

**? Exercise 2.6.4**

Solve by factoring: $12x^4 = 3x^2$.

**Answer**

$x = 0, x = 12, x = -12$

**✔ Example 2.6.5: Solve a Polynomial by Grouping**

Solve a polynomial by grouping: $x^3 + x^2 - 9x - 9 = 0$ .

**Solution**

This polynomial consists of 4 terms, which we can solve by grouping. Grouping procedures require factoring the first two terms and then factoring the last two terms. If the factors in the parentheses are identical, we can continue the process and solve, unless more factoring is suggested.

$$\begin{aligned} x^3+x^2-9x-9 &= 0 \\ x^2(x+1)-9(x+1) &= 0 \\ (x^2-9)(x+1) &= 0 \end{aligned}$$

The grouping process ends here, as we can factor $x^2-9$ using the difference of squares formula.

$$\begin{aligned} (x^2-9)(x+1) &= 0 \\ (x-3)(x+3)(x+1) &= 0 \\ x &= 3 \\ x &= -3 \\ x &= -1 \end{aligned}$$

The solutions are $3$, $-3$, and $-1$. Note that the highest exponent is $3$ and we obtained $3$ solutions. We can see the solutions, the x-intercepts, on the graph in Figure $2.6.2$.





Figure 2.6.2

**Analysis**

We looked at solving quadratic equations by factoring when the leading coefficient is $1$. When the leading coefficient is not $1$, we solved by grouping. Grouping requires four terms, which we obtained by splitting the linear term of quadratic equations. We can also use grouping for some polynomials of degree higher than $2$, as we saw here, since there were already four terms.

## Solving Radical Equations

**Radical equations** are equations that contain variables in the **radicand** (the expression under a radical symbol), such as

$$\sqrt{3x+18} = x$$

$$\sqrt{x+3} = x-3$$

$$\sqrt{x+5} - \sqrt{x-3} = 2$$

Radical equations may have one or more radical terms, and are solved by eliminating each radical, one at a time. We have to be careful when solving radical equations, as it is not unusual to find **extraneous solutions**, roots that are not, in fact, solutions to the equation. These solutions are not due to a mistake in the solving method, but result from the process of raising both sides of an equation to a power. However, checking each answer in the original equation will confirm the true solutions.

### RADICAL EQUATIONS

An equation containing terms with a variable in the radicand is called a **radical equation.**

**Howto: Given a radical equation, solve it**

1. Isolate the radical expression on one side of the equal sign. Put all remaining terms on the other side.
2. If the radical is a square root, then square both sides of the equation. If it is a cube root, then raise both sides of the equation to the third power. In other words, for an $n^{th}$ root radical, raise both sides to the $n^{th}$ power. Doing so eliminates the radical symbol.
3. Solve the remaining equation.
4. If a radical term still remains, repeat steps 1–2.
5. Confirm solutions by substituting them into the original equation.

**Example 2.6.6: Solving an Equation with One Radical**

Solve $\sqrt{15-2x}=x$.

**Solution**

The radical is already isolated on the left side of the equal side, so proceed to square both sides.

$$\begin{aligned}\sqrt{15-2x} &= x\\ (\sqrt{15-2x})^2 &= (x)^2\\ 15-2x &= x^2\end{aligned}$$

We see that the remaining equation is a quadratic. Set it equal to zero and solve.

$$\begin{aligned}0 &= x^2+2x-15\\ 0 &= (x+5)(x-3)\\ x &= -5\\ x &= 3\end{aligned}$$

The proposed solutions are $-5$ and $3$. Let us check each solution back in the original equation. First, check $x=-5$.

$$\begin{aligned}\sqrt{15-2x} &= x\\ \sqrt{15-2(-5)} &= -5\\ \sqrt{25} &= -5\\ 5 &\neq -5\end{aligned}$$

This is an extraneous solution. While no mistake was made solving the equation, we found a solution that does not satisfy the original equation.

Check $x=3$.

$$\begin{aligned}\sqrt{15-2x} &= x\\ \sqrt{15-2(3)} &= 3\\ \sqrt{9} &= 3\\ 3 &= 3\end{aligned}$$

The solution is $3$.

**Exercise 2.6.5**

Solve the radical equation: $\sqrt{x+3}=3x-1$

**Answer**

$x=1$, extraneous solution $x=-\frac{2}{9}$

## Example 2.6.7: Solving a Radical Equation Containing Two Radicals

Solve $\sqrt{2x+3}+\sqrt{x-2}=4$

### Solution

As this equation contains two radicals, we isolate one radical, eliminate it, and then isolate the second radical.

$$\sqrt{2x+3}+\sqrt{x-2}=4$$

$$\begin{aligned}\sqrt{2x+3} &= 4-\sqrt{x-2} && \text{Subtract } \sqrt{x-2} \text{ from both sides}\\ (\sqrt{2x+3})^2 &= (4-\sqrt{x-2})^2 && \text{Square both sides}\end{aligned}$$

Use the perfect square formula to expand the right side: $(a-b)^2=a^2-2ab+b^2$ .

$$\begin{aligned}2x+3 &= (4)^2-2(4)\sqrt{x-2}+(\sqrt{x-2})^2\\ 2x+3 &= 16-8\sqrt{x-2}+(x-2)\\ 2x+3 &= 14+x-8\sqrt{x-2} && \text{Combine like terms}\\ x-11 &= -8\sqrt{x-2} && \text{Isolate the second radical}\\ (x-11)^2 &= (-8\sqrt{x-2})^2 && \text{Square both sides}\\ x^2-22x+121 &= 64(x-2)\end{aligned}$$

Now that both radicals have been eliminated, set the quadratic equal to zero and solve.

$$\begin{aligned}x^2-22x+121 &= 64x-128\\ x^2-86x+249 &= 0\\ (x-3)(x-83) &= 0\\ x &= 3\\ x &= 83\end{aligned}$$

The proposed solutions are 3 and 83. Check each solution in the original equation.

$$\begin{aligned}\sqrt{2x+3}+\sqrt{x-2} &= 4\\ \sqrt{2x+3} &= 4-\sqrt{x-2}\\ \sqrt{2(3)+3} &= 4-\sqrt{(3)-2}\\ \sqrt{9} &= 4-\sqrt{1}\\ 3 &= 3\end{aligned}$$

One solution is 3.

Check $x=83$.

$$\begin{aligned}\sqrt{2x+3}+\sqrt{x-2} &= 4\\ \sqrt{2x+3} &= 4-\sqrt{x-2}\\ \sqrt{2(83)+3} &= 4-\sqrt{(83)-2}\\ \sqrt{169} &= 4-\sqrt{81}\\ 13 &\neq -5\end{aligned}$$

The only solution is 3. We see that $x=83$ is an extraneous solution.

## Exercise 2.6.6

Solve the equation with two radicals: $\sqrt{3x+7}+\sqrt{x+2}=1$

**Answer**

$x=-2$, extraneous solution $x=-1$

## Solving an Absolute Value Equation

Next, we will learn how to solve an **absolute value equation**. To solve an equation such as $|2x-6|=8$, we notice that the absolute value will be equal to 8 if the quantity inside the absolute value bars is 8 or $-8$. This leads to two different equations we can solve independently.

$$\begin{aligned} 2x-6 &= 8 \\ 2x &= 14 \\ x &= 7 \end{aligned}$$

OR

$$\begin{aligned} 2x-6 &= -8 \\ 2x &= -2 \\ x &= -1 \end{aligned}$$

Knowing how to solve problems involving absolute value functions is useful. For example, we may need to identify numbers or points on a line that are at a specified distance from a given reference point.

### ABSOLUTE VALUE EQUATIONS

The absolute value of $x$ is written as $|x|$. It has the following properties:

If $x \geq 0$, then $|x| = x$.If $x < 0$, then $x = -x$.

For real numbers $A$ and $B$, an equation of the form $|A| = B$, with $B \geq 0$, will have solutions when $A = B$ or $A = -B$. If $B < 0$, the equation $|A| = B$ has no solution.

An **absolute value equation** in the form $|ax+b|=c$ has the following properties:

- If $c<0$,$|ax+b|=c$ has no solution.
- If $c=0$,$|ax+b|=c$ has one solution.
- If $c>0$,$|ax+b|=c$ has two solutions.

### How to

**Given an absolute value equation, solve it.**

1. Isolate the absolute value expression on one side of the equal sign.
2. If $c>0$, write and solve two equations: $ax+b=c$ and $ax+b=-c$.

### Example 2.6.8: Solving Absolute Value Equations

Solve the following absolute value equations:

a. $|6x+4|=8$
b. $|3x+4|=-9$
c. $|3x-5|-4=6$
d. $|-5x+10|=0$

**Solution**

a. $|6x+4|=8$

Write two equations and solve each:

$$\begin{aligned} 6x+4 &= 8 \\ 6x &= 4 \\ x &= \frac{2}{3} \end{aligned}$$

OR

$$\begin{aligned} 6x+4 &= -8 \\ 6x &= -12 \\ x &= -2 \end{aligned}$$

The two solutions are $\frac{2}{3}$ and $-2$.

b. $|3x+4| = -9$

There is no solution as an absolute value cannot be negative.

c. $|3x-5|-4 = 6$

Isolate the absolute value expression and then write two equations.

$$\begin{aligned} |3x-5|-4 &= 6 \\ |3x-5| &= 10 \\ 3x-5 &= 10 \\ 3x &= 15 \\ x &= 5 \end{aligned}$$

OR

$$\begin{aligned} 3x-5 &= -10 \\ 3x &= -5 \\ x &= \frac{5}{3} \end{aligned}$$

There are two solutions: $5$, and $-\frac{5}{3}$.

d. $|-5x+10| = 0$

The equation is set equal to zero, so we have to write only one equation.

$$\begin{aligned} -5x+10 &= 0 \\ -5x &= -10 \\ x &= 2 \end{aligned}$$

There is one solution: \(2\).

**? Exercise 2.6.7**

Solve the absolute value equation: $|1-4x|+8 = 13$.

**Answer**

$x = -1, x = \frac{3}{2}$

## Solving Other Types of Equations

There are many other types of equations in addition to the ones we have discussed so far. We will see more of them throughout the text. Here, we will discuss equations that are in quadratic form, and rational equations that result in a quadratic.

### Solving Equations in Quadratic Form

**Equations in quadratic form** are equations with three terms. The first term has a power other than 2. The middle term has an exponent that is one-half the exponent of the leading term. The third term is a constant. We can solve equations in this form as if they were quadratic. A few examples of these equations include $x^4-5x^2+4=0$ ,$x^6+7x^3-8=0$ , and $x^{\frac{2}{3}}+4x^{\frac{1}{3}}+2=0$ . In each one, doubling the exponent of the middle term equals the exponent on the leading term. We can solve these equations by substituting a variable for the middle term.

## QUADRATIC FORM

If the exponent on the middle term is one-half of the exponent on the leading term, we have **an equation in quadratic form**, which we can solve as if it were a quadratic. We substitute a variable for the middle term to solve equations in quadratic form.

## Howto: Given an equation quadratic in form, solve it

1. Identify the exponent on the leading term and determine whether it is double the exponent on the middle term.
2. If it is, substitute a variable, such as $u$, for the variable portion of the middle term.
3. Rewrite the equation so that it takes on the standard form of a quadratic.
4. Solve using one of the usual methods for solving a quadratic.
5. Replace the substitution variable with the original term.
6. Solve the remaining equation.

## Example 2.6.9: Solving a Fourth-degree Equation in Quadratic Form

Solve this fourth-degree equation: $3x^4 - 2x^2 - 1 = 0$ .

### Solution

This equation fits the main criteria, that the power on the leading term is double the power on the middle term. Next, we will make a substitution for the variable term in the middle. Let $u = x^2$. Rewrite the equation in $u$.

$$3u^2 - 2u - 1 = 0$$

Now solve the quadratic.

$$\begin{aligned} 3u^2 - 2u - 1 &= 0 \\ (3u+1)(u-1) &= 0 \end{aligned}$$

Solve each factor and replace the original term for $u$.

$$\begin{aligned} 3u + 1 &= 0 \\ 3u &= -1 \\ u &= -\frac{1}{3} \\ x^2 &= -\frac{1}{3} \\ x &= \pm i\sqrt{\frac{1}{3}} \\ u - 1 &= 0 \\ u &= 1 \\ x^2 &= 1 \\ x &= \pm 1 \end{aligned}$$

The solutions are $x = \pm i\sqrt{\frac{1}{3}}$ and $x = \pm 1$

## Exercise 2.6.8

Solve using substitution: $x^4 - 8x^2 - 9 = 0$ .

**Answer**

$x = -3, 3, -i, i$

### Example 2.6.10: Solving an Equation in Quadratic Form Containing a Binomial

Solve the equation in quadratic form: $(x+2)^2+11(x+2)-12=0$ .

**Solution**

This equation contains a binomial in place of the single variable. The tendency is to expand what is presented. However, recognizing that it fits the criteria for being in quadratic form makes all the difference in the solving process. First, make a substitution, letting $u=x+2$. Then rewrite the equation in $u$.

$$\begin{aligned} u^2+11u-12 &= 0 \\ (u+12)(u-1) &= 0 \end{aligned}$$

Solve using the zero-factor property and then replace $u$ with the original expression.

$$\begin{aligned} u+12 &= 0 \\ u &= -12 \\ x+2 &= -12 \\ x &= -14 \end{aligned}$$

The second factor results in

$$\begin{aligned} u-1 &= 0 \\ u &= 1 \\ x+2 &= 1 \\ x &= -1 \end{aligned}$$

We have two solutions: $-14$, and $-1$.

### Exercise 2.6.9

Solve: $(x-5)^2-4(x-5)-21=0$ .

**Answer**

$x=2, x=12$

## Solving Rational Equations Resulting in a Quadratic

Earlier, we solved rational equations. Sometimes, solving a rational equation results in a quadratic. When this happens, we continue the solution by simplifying the quadratic equation by one of the methods we have seen. It may turn out that there is no solution.

### Example 2.6.11: Solving a Rational Equation Leading to a Quadratic

Solve the following rational equation: $\dfrac{-4x}{x-1}+\dfrac{4}{x+1}=\dfrac{-8}{x^2-1}$

**Solution**

We want all denominators in factored form to find the LCD. Two of the denominators cannot be factored further. However, $x^2-1=(x+1)(x-1)$ . Then, the LCD is $(x+1)(x-1)$. Next, we multiply the whole equation by the LCD.

$$
\begin{aligned}
(x+1)(x-1)\left(\frac{-4x}{x-1}+\frac{4}{x+1}\right) &= \left(\frac{-8}{x^2-1}\right)(x+1)(x-1) \\
-4x(x+1)+4(x-1) &= -8 \\
-4x^2-4x+4x-4 &= -8 \\
-4x^2+4 &= 0 \\
-4(x^2-1) &= 0 \\
-4(x+1)(x-1) &= 0 \\
x &= -1 \\
x &= 1
\end{aligned}
$$

In this case, either solution produces a zero in the denominator in the original equation. Thus, there is no solution.

**? Exercise 2.6.10**

Solve $\frac{3x+2}{x-2}+\frac{1}{x}=\frac{-2}{x^2-2x}$

**Answer**

$x=-1, x=0$ is not a solution.

**Media**

Access these online resources for additional instruction and practice with different types of equations.

1. Rational Equation with no Solution
2. Solving equations with rational exponents using reciprocal powers
3. Solving radical equations part 1 of 2
4. Solving radical equations part 2 of 2

## Key Concepts

- Rational exponents can be rewritten several ways depending on what is most convenient for the problem. To solve, both sides of the equation are raised to a power that will render the exponent on the variable equal to 1. See Example, Example, and Example.
- Factoring extends to higher-order polynomials when it involves factoring out the GCF or factoring by grouping. See Example and Example.
- We can solve radical equations by isolating the radical and raising both sides of the equation to a power that matches the index. See Example and Example.
- To solve absolute value equations, we need to write two equations, one for the positive value and one for the negative value. See Example.
- Equations in quadratic form are easy to spot, as the exponent on the first term is double the exponent on the second term and the third term is a constant. We may also see a binomial in place of the single variable. We use substitution to solve. See Example and Example.
- Solving a rational equation may also lead to a quadratic equation or an equation in quadratic form. See Example.

This page titled 2.6: Other Types of Equations is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.6: Other Types of Equations** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 2.6E: Other Types of Equations (Exercises)

This page titled 2.6E: Other Types of Equations (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 2.7: Modeling with Equations

Applications can be written as mathematical problems by identifying known quantities and assigning a variable to unknown quantities. There are many known formulas that can be used to solve applications. Distance problems are solved using the $d = rt$ formula. Many geometry problems are solved using the perimeter formula $P = 2L + 2W$, the area formula $A = LW$, or the volume formula $V = LWH$. In this section you will review several types of Applications.

A linear equation can be used to solve for:

- Models and Applications
- Mixture and Uniform Motion Applications

A rational equation can be used to solve for

- Proportions, Similar figures and Variation
- Uniform Motion
- Work

2.7: Modeling with Equations is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

# 2.7.1: Models and Applications

**Learning Objectives**

- Set up a linear equation to solve a real-world application.
- Use a formula to solve a real-world application.

Josh is hoping to get an $A$ in his college algebra class. He has scores of $75$, $82$, $95$, $91$, and $94$ on his first five tests. Only the final exam remains, and the maximum of points that can be earned is $100$. Is it possible for Josh to end the course with an $A$? A simple linear equation will give Josh his answer.



Figure 2.4.1 Credit: Kevin Dooley

Many real-world applications can be modeled by linear equations. For example, a cell phone package may include a monthly service fee plus a charge per minute of talk-time; it costs a widget manufacturer a certain amount to produce *x* widgets per month plus monthly operating charges; a car rental company charges a daily fee plus an amount per mile driven. These are examples of applications we come across every day that are modeled by linear equations. In this section, we will set up and use linear equations to solve such problems.

## Setting up a Linear Equation to Solve a Real-World Application

To set up or model a linear equation to fit a real-world application, we must first determine the known quantities and define the unknown quantity as a variable. Then, we begin to interpret the words as mathematical expressions using mathematical symbols. Let us use the car rental example above. In this case, a known cost, such as $\$0.10/mi$, is multiplied by an unknown quantity, the number of miles driven. Therefore, we can write $0.10x$. This expression represents a variable cost because it changes according to the number of miles driven.

If a quantity is independent of a variable, we usually just add or subtract it, according to the problem. As these amounts do not change, we call them fixed costs. Consider a car rental agency that charges $\$0.10/mi$ plus a daily fee of $\$50$. We can use these quantities to model an equation that can be used to find the daily car rental cost $C$.

$$C = 0.10x + 50 \tag{2.4.1}$$

When dealing with real-world applications, there are certain expressions that we can translate directly into math. Table $2.7.1.1$ lists some common verbal expressions and their equivalent mathematical expressions.

Table 2.7.1.1: Verbal to math conversion

| Verbal | Translation to Math Operations |
|---|---|
| One number exceeds another by a | $x$, $x + a$ |
| Twice a number | $2x$ |
| One number is $a$ more than another number | $x$, $x + a$ |
| One number is a less than twice another number | $x$, $2x - a$ |

| Verbal | Translation to Math Operations |
|---|---|
| The product of a number and $a$, decreased by $b$ | $ax-b$ |
| The quotient of a number and the number plus $a$ is three times the number | $\frac{x}{x+a}=3x$ |
| The product of three times a number and the number decreased by $b$ is $c$ | $3x(x-b)=c$ |

**How to: Given a real-world problem, model a linear equation to fit it**

1. Identify known quantities.
2. Assign a variable to represent the unknown quantity.
3. If there is more than one unknown quantity, find a way to write the second unknown in terms of the first.
4. Write an equation interpreting the words as mathematical operations.
5. Solve the equation. Be sure the solution can be explained in words, including the units of measure.

**Example 2.7.1.1**

Find a linear equation to solve for the following unknown quantities: One number exceeds another number by 17 and their sum is 31. Find the two numbers.

**Solution**

Let $x$ equal the first number. Then, as the second number exceeds the first by 17, we can write the second number as $x+17$. The sum of the two numbers is 31. We usually interpret the word is as an equal sign.

$$\begin{aligned} x+(x+17) &= 31 \\ 2x+17 &= 31 \\ 2x &= 14 \\ x &= 7 \end{aligned}$$

$$\begin{aligned} x+17 &= 7+17 \\ &= 24 \end{aligned}$$

The two numbers are 7 and 24.

**Exercise 2.7.1.1**

Find a linear equation to solve for the following unknown quantities: One number is three more than twice another number. If the sum of the two numbers is 36, find the numbers.

**Answer**

11 and 25

**Example 2.7.1.2: Setting Up a Equation to Solve a Real-World Application**

There are two cell phone companies that offer different packages. Company A charges a monthly service fee of $\$34$ plus $\$.05/min$talk-time. Company B charges a monthly service fee of $\$40$ plus $\$.04/min$talk-time.

a. Write a linear equation that models the packages offered by both companies.
b. If the average number of minutes used each month is $1,160$, which company offers the better plan?
c. If the average number of minutes used each month is 420, which company offers the better plan?
d. How many minutes of talk-time would yield equal monthly statements from both companies?

**Solution**

a.

The model for Company A can be written as $A = 0.05x + 34$. This includes the variable cost of $0.05x$ plus the monthly service charge of $\$34$. Company B's package charges a higher monthly fee of $\$40$, but a lower variable cost of $0.04x$. Company B's model can be written as $B = 0.04x + \$40$.

b.

If the average number of minutes used each month is $1,160$, we have the following:

$$\begin{aligned} \text{Company A} &= 0.05(1.160) + 34 \\ &= 58 + 34 \\ &= 92 \end{aligned}$$

$$\begin{aligned} \text{Company B} &= 0.04(1,1600) + 40 \\ &= 46.4 + 40 \\ &= 86.4 \end{aligned}$$

So, Company B offers the lower monthly cost of $\$86.40$ as compared with the $\$92$ monthly cost offered by Company A when the average number of minutes used each month is $1,160$.

c.

If the average number of minutes used each month is $420$, we have the following:

$$\begin{aligned} \text{Company A} &= 0.05(420) + 34 \\ &= 21 + 34 \\ &= 55 \end{aligned}$$

$$\begin{aligned} \text{Company B} &= 0.04(420) + 40 \\ &= 16.8 + 40 \\ &= 56.8 \end{aligned}$$

If the average number of minutes used each month is $420$, then Company A offers a lower monthly cost of $\$55$ compared to Company B's monthly cost of $\$56.80$.

d.

To answer the question of how many talk-time minutes would yield the same bill from both companies, we should think about the problem in terms of $(x, y)$ coordinates: At what point are both the $x$-value and the $y$-value equal? We can find this point by setting the equations equal to each other and solving for $x$.

$$\begin{aligned} 0.05x + 34 &= 0.04x + 40 \\ 0.01x &= 6 \\ x &= 600 \end{aligned}$$

Check the $x$-value in each equation.

$$0.05(600) + 34 = 64$$

$$0.04(600) + 40 = 64$$

Therefore, a monthly average of $600$ talk-time minutes renders the plans equal. See Figure $2.7.1.2$





Figure 2.7.1.2

**? Exercise 2.7.1.2**

Find a linear equation to model this real-world application: It costs ABC electronics company $\$2.50$ per unit to produce a part used in a popular brand of desktop computers. The company has monthly operating expenses of $\$350$ for utilities and $\$3,300$ for salaries. What are the company's monthly expenses?

**Answer**

$C = 2.5x + 3,650$

## Using a Formula to Solve a Real-World Application

Many applications are solved using known formulas. The problem is stated, a formula is identified, the known quantities are substituted into the formula, the equation is solved for the unknown, and the problem's question is answered. Typically, these problems involve two equations representing two trips, two investments, two areas, and so on. Examples of formulas include the **area** of a rectangular region,

$$A = LW \tag{2.4.2}$$

the **perimeter** of a rectangle,

$$P = 2L + 2W \tag{2.4.3}$$

and the **volume** of a rectangular solid,

$$V = LWH. \tag{2.4.4}$$

When there are two unknowns, we find a way to write one in terms of the other because we can solve for only one variable at a time.

**✔ Example 2.7.1.3: Solving an Application Using a Formula**

It takes Andrew $30\ min$ to drive to work in the morning. He drives home using the same route, but it takes \(10\; min\) longer, and he averages $10\ mi/h$ less than in the morning. How far does Andrew drive to work?

**Solution**

This is a distance problem, so we can use the formula $d = rt$, where distance equals rate multiplied by time. Note that when rate is given in $mi/h$, time must be expressed in hours. Consistent units of measurement are key to obtaining a correct solution.

First, we identify the known and unknown quantities. Andrew's morning drive to work takes 30 $min$, or 12 $h$ at rate $r$. His drive home takes 40 $min$, or 23 $h$, and his speed averages 10 $mi/h$ less than the morning drive. Both trips cover distance $d$. A table, such as Table 2.7.1.2 is often helpful for keeping track of information in these types of problems.

Table 2.7.1.2

| | $d$ | $r$ | $t$ |
|---|---|---|---|
| To Work | $d$ | $r$ | 12 |
| To Home | $d$ | $r-10$ | 23 |

Write two equations, one for each trip.

$$d = r\left(\frac{1}{2}\right) \qquad \text{To work}$$

$$d = (r-10)\left(\frac{2}{3}\right) \qquad \text{To home}$$

As both equations equal the same distance, we set them equal to each other and solve for $r$.

$$\begin{aligned} r\left(\frac{1}{2}\right) &= (r-10)\left(\frac{2}{3}\right) \\ \frac{1}{2r} &= \frac{2}{3}r - \frac{20}{3} \\ \frac{1}{2}r - \frac{2}{3}r &= -\frac{20}{3} \\ -\frac{1}{6}r &= -\frac{20}{3} \\ r &= -\frac{20}{3}(-6) \\ r &= 40 \end{aligned}$$

We have solved for the rate of speed to work, 40 $mph$. Substituting 40 into the rate on the return trip yields $30 mi/h$. Now we can answer the question. Substitute the rate back into either equation and solve for $d$.

$$\begin{aligned} d &= 40\left(\frac{1}{2}\right) \\ &= 20 \end{aligned}$$

The distance between home and work is 20 $mi$.

**Analysis**

Note that we could have cleared the fractions in the equation by multiplying both sides of the equation by the LCD to solve for $r$.

$$\begin{aligned} r\left(\frac{1}{2}\right) &= (r-10)\left(\frac{2}{3}\right) \\ 6 \times r\left(\frac{1}{2}\right) &= 6 \times (r-10)\left(\frac{2}{3}\right) \\ 3r &= 4(r-10) \\ 3r &= 4r - 40 \\ r &= 40 \end{aligned}$$

**Exercise 2.7.1.3**

On Saturday morning, it took Jennifer $3.6\ h$ to drive to her mother's house for the weekend. On Sunday evening, due to heavy traffic, it took Jennifer $4\ h$ to return home. Her speed was $5\ mi/h$ slower on Sunday than on Saturday. What was her speed on Sunday?

**Answer**

$45\ mi/h$

**Example 2.7.1.4: Solving a Perimeter Problem**

The perimeter of a rectangular outdoor patio is $54\ ft$. The length is $3\ ft$ greater than the width. What are the dimensions of the patio?

**Solution**

The perimeter formula is standard: $P = 2L + 2W$. We have two unknown quantities, length and width. However, we can write the length in terms of the width as $L = W + 3$. Substitute the perimeter value and the expression for length into the formula. It is often helpful to make a sketch and label the sides as in Figure 2.7.1.3





Figure 2.7.1.3

Now we can solve for the width and then calculate the length.

$$\begin{aligned} P &= 2L + 2W \\ 54 &= 2(W+3) + 2W \\ 54 &= 2W + 6 + 2W \\ 54 &= 4W + 6 \\ 48 &= 4W \\ W &= 12 \end{aligned}$$

$$\begin{aligned} L &= 12 + 3 \\ L &= 15 \end{aligned}$$

The dimensions are $L = 15\ ft$ and $W = 12\ ft$.

**Exercise 2.7.1.4**

Find the dimensions of a rectangle given that the perimeter is $110\ cm$ and the length is $1\ cm$ more than twice the width.

**Answer**

$L = 37\ cm$, $W = 18\ cm$

**Example 2.7.1.5: Solving an Area Problem**

The perimeter of a tablet of graph paper is $48\ in.^2$. The length is $6\ in.$ more than the width. Find the area of the graph paper.

**Solution**

The standard formula for area is $A = LW$; however, we will solve the problem using the perimeter formula. The reason we use the perimeter formula is because we know enough information about the perimeter that the formula will allow us to solve

for one of the unknowns. As both perimeter and area use length and width as dimensions, they are often used together to solve a problem such as this one.

We know that the length is $6\ in.$ more than the width, so we can write length as $L = W + 6$. Substitute the value of the perimeter and the expression for length into the perimeter formula and find the length.

$$\begin{aligned} P &= 2L + 2W \\ 48 &= 2(W+6) + 2W \\ 48 &= 2W + 12 + 2W \\ 48 &= 4W + 12 \\ 36 &= 4W \\ W &= 9 \end{aligned}$$

$$\begin{aligned} L &= 9 + 6 \\ L &= 15 \end{aligned}$$

Now, we find the area given the dimensions of $L = 15\ in.$ and $W = 9\ in.$

$$\begin{aligned} A &= LW \\ A &= 15(9) \\ A &= 135\ in.^2 \end{aligned}$$

The area is $135\ in.^2$.

**? Exercise 2.7.1.5**

A game room has a perimeter of $70\ ft.$ The length is five more than twice the width. How many $ft^2$ of new carpeting should be ordered?

**Answer**

$250\ ft^2$

**✓ Example 2.7.1.6: Solving a Volume Problem**

Find the dimensions of a shipping box given that the length is twice the width, the height is $8$ in, and the volume is $1,600\ in.^3$.

**Solution**

The formula for the volume of a box is given as $V = LWH$, the product of length, width, and height. We are given that $L = 2W$, and $H = 8$. The volume is $1,600$ cubic inches.

$$\begin{aligned} V &= LWH \\ 1600 &= (2W)W(8) \\ 1600 &= 16W^2 \\ 100 &= W^2 \\ 10 &= W \end{aligned}$$

The dimensions are $L = 20\ in$, $W = 10\ in$, and $H = 8\ in$.

**Analysis**

Note that the square root of $W^2$ would result in a positive and a negative value. However, because we are describing width, we can use only the positive result.

## Media

Access these online resources for additional instruction and practice with models and applications of linear equations.

1. Problem solving using linear equations
2. Problem solving using equations
3. Finding the dimensions of area given the perimeter
4. Find the distance between the cities using the distance = rate * time formula
5. Linear equation application (Write a cost equation)

## Key Concepts

- A linear equation can be used to solve for an unknown in a number problem. See Example.
- Applications can be written as mathematical problems by identifying known quantities and assigning a variable to unknown quantities. See Example.
- There are many known formulas that can be used to solve applications. Distance problems, for example, are solved using the $d = rt$ formula. See Example.
- Many geometry problems are solved using the perimeter formula $P = 2L + 2W$, the area formula $A = LW$, or the volume formula $V = LWH$. See Example, Example, and Example.

---

This page titled 2.7.1: Models and Applications is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.3: Models and Applications** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 2.7.1E: Models and Applications (Exercises)

This page titled 2.7.1E: Models and Applications (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 2.7.2: Solve Mixture and Uniform Motion Applications

**Learning Objectives**

By the end of this section, you will be able to:

- Solve coin word problems
- Solve ticket and stamp word problems
- Solve mixture word problems
- Solve uniform motion applications

Before you get started, take this readiness quiz.

1. Simplify: $0.25x + 0.10(x + 4)$.
   If you missed this problem, review [link].
2. The number of adult tickets is three more than twice the number of children tickets. Let $c$represent the number of children tickets. Write an expression for the number of adult tickets.
   If you missed this problem, review [link].
3. Convert 4.2% to a decimal.
   If you missed this problem, review [link].

## Solve Coin Word Problems

Using algebra to find the number of nickels and pennies in a piggy bank may seem silly. You may wonder why we just don't open the bank and count them. But this type of problem introduces us to some techniques that will be useful as we move forward in our study of mathematics.



If we have a pile of dimes, how would we determine its value? If we count the number of dimes, we'll know how many we have—the *number* of dimes. But this does not tell us the *value* of all the dimes. Say we counted 23 dimes, how much are they worth? Each dime is worth \$0.10—that is the *value* of one dime. To find the total value of the pile of 23 dimes, multiply 23 by \$0.10 to get \$2.30.

The number of dimes times the value of each dime equals the total value of the dimes.

$$\begin{aligned} number \cdot value &= total\, value \\ 23 \cdot \$0.10 &= \$2.30 \end{aligned}$$

This method leads to the following model.

**TOTAL VALUE OF COINS**

For the same type of coin, the total value of a number of coins is found by using the model

$$number \cdot value = total\, value$$

- *number* is the number of coins
- *value* is the value of each coin
- *total value* is the total value of all the coins

If we had several types of coins, we could continue this process for each type of coin, and then we would know the total value of each type of coin. To get the total value of *all* the coins, add the total value of each type of coin.

## Example 2.7.2.1

Jesse has $3.02 worth of pennies and nickels in his piggy bank. The number of nickels is three more than eight times the number of pennies. How many nickels and how many pennies does Jesse have?

**Answer**

| | |
|---|---|
| **Step 1. Read** the problem.<br>Determine the types of coins involved.<br>Create a table.<br>Write in the value of each type of coin. | pennies and nickels<br><br>Pennies are worth $0.10.<br>Nickels are worth $0.05. |
| **Step 2. Identify** what we are looking for. | the number of pennies and nickels |
| **Step 3. Name**. Represent the number of each type of coin using variables.<br>The number of nickels is defined in terms of the number of pennies, so start with pennies.<br>The number of nickels is three more than eight times the number of pennies. | Let $p =$ number of pennies.<br><br>$8p + 3 =$ number of nickels |

In the chart, multiply the number and the value to get the total value of each type of coin.

| Type | Number | • Value ($) | = Total Value ($) |
|---|---|---|---|
| pennies | $p$ | 0.01 | $0.01p$ |
| nickels | $8p + 3$ | 0.05 | $0.05(8p + 3)$ |
| | | | $3.02 |

| | |
|---|---|
| **Step 4. Translate.** Write the equation by adding the total value of all the types of coins. | $0.01p + 0.05(8p + 3) = 3.02$ |
| **Step 5. Solve** the equation. | $0.01p + 0.40p + 0.15 = 3.02$<br>$0.41p + 0.15 = 3.02$<br>$0.41p = 2.87$<br>$p = 7$ pennies |
| How many nickels? | $8p + 3$<br>$8(7) + 3$<br>59 nickels |
| **Step 6. Check** the answer in the problem and make sure it makes sense.<br>Jesse has 7 pennies and 59 nickels.<br>Is the total value $3.02?<br>$7(0.01) + 59(0.05) \stackrel{?}{=} 3.02$<br>$3.02 = 3.02$✓ | |

## Example 2.7.2.2

Jesse has $6.55 worth of quarters and nickels in his pocket. The number of nickels is five more than two times the number of quarters. How many nickels and how many quarters does Jesse have?

**Answer**

Jess has 41 nickels and 18 quarters.

**Example 2.7.2.3**

Elane has $7.00 total in dimes and nickels in her coin jar. The number of dimes that Elane has is seven less than three times the number of nickels. How many of each coin does Elane have?

**Answer**

Elane has 22 nickels and 59 dimes.

The steps for solving a coin word problem are summarized below.

**SOLVE COIN WORD PROBLEMS.**

1. **Read** the problem. Make sure all the words and ideas are understood.
   - Determine the types of coins involved.
   - Create a table to organize the information.
     - Label the columns “type,” “number,” “value,” and “total value.”
     - List the types of coins.
     - Write in the value of each type of coin.
     - Write in the total value of all the coins.

| Type | Number • | Value ($) = | Total Value ($) |
|---|---|---|---|
| | | | |
| | | | |
| | | | |

2. **Identify** what you are looking for.
3. **Name** what you are looking for. Choose a variable to represent that quantity.
   - Use variable expressions to represent the number of each type of coin and write them in the table.
   - Multiply the number times the value to get the total value of each type of coin.
4. **Translate** into an equation.
   - It may be helpful to restate the problem in one sentence with all the important information. Then, translate the sentence into an equation.
   - Write the equation by adding the total values of all the types of coins.
5. **Solve** the equation using good algebra techniques.
6. **Check** the answer in the problem and make sure it makes sense.
7. **Answer** the question with a complete sentence.

## Solve Ticket and Stamp Word Problems

Problems involving tickets or stamps are very much like coin problems. Each type of ticket and stamp has a value, just like each type of coin does. So to solve these problems, we will follow the same steps we used to solve coin problems.

**Example 2.7.2.4**

Danny paid $15.75 for stamps. The number of 49-cent stamps was five less than three times the number of 35-cent stamps. How many 49-cent stamps and how many 35-cent stamps did Danny buy?

**Answer**

| | |
|---|---|
| **Step 1.** Determine the types of stamps involved. | 49-cent stamps and 35-cent stamps |
| **Step 2. Identify** we are looking for. | the number of 49-cent stamps and the number of 35-cent stamps |

| | |
|---|---|
| **Step 3.** Write variable expressions to represent the number of each type of stamp. | Let $x$ = number of 35-cent stamps. |
| "The number of 49-cent stamps was five less than three times the number of 35-cent stamps." | $3x-5=3x-5=$ number of 49-cent stamps |

| Type | Number | · Value($) | = Total Value ($) |
|---|---|---|---|
| 49 cent stamps | $3x-5$ | 0.49 | $0.49(3x-5)$ |
| 35 cent stamps | $x$ | 0.35 | $0.35x$ |
| | | | 15.75 |

| | |
|---|---|
| **Step 4.** Write the equation from the total values. | $0.49(3x-5)+0.35x=15.75$ |
| **Step 5. Solve** the equation. | $1.47x-2.45+0.35x=15.75$<br>$1.82x-2.45=15.75$<br>$1.82x=18.2$ |
| How many 49-cent stamps? | $x=10$ 35-cent stamps<br>$3x-5$<br>$3(10)-5$<br>25 49-cent stamps |
| **Step 6. Check.** $10(0.35)+25(0.49)3.50+12.2515.75=?=?$ $=15.7515.7515.75\checkmark 10(0.35)+25(0.49)=?15.753.50+12.25=?$ $15.7515.75=15.75\checkmark$ | |
| **Step 7. Answer** the question with a complete sentence. | Danny bought ten 35-cent stamps and twenty-five 49-cent stamps. |

### ? Example 2.7.2.5

Eric paid $19.88 for stamps. The number of 49-cent stamps was eight more than twice the number of 35-cent stamps. How many 49-cent stamps and how many 35-cent stamps did Eric buy?

**Answer**

Eric bought thirty-two 49-cent stamps and twelve 35-cent stamps.

### ? Example 2.7.2.6

Kailee paid $14.74 for stamps. The number of 49-cent stamps was four less than three times the number of 20-cent stamps. How many 49-cent stamps and how many 20-cent stamps did Kailee buy?

**Answer**

Kailee bought twenty-six 49-cent stamps and ten 20-cent stamps.

In most of our examples so far, we have been told that one quantity is four more than twice the other, or something similar. In our next example, we have to relate the quantities in a different way.

Suppose Aniket sold a total of 100 tickets. Each ticket was either an adult ticket or a child ticket. If he sold 20 child tickets, how many adult tickets did he sell?

*Did you say "80"? How did you figure that out? Did you subtract 20 from 100?*

If he sold 45 child tickets, how many adult tickets did he sell?

*Did you say "55"? How did you find it? By subtracting 45 from 100?*

Now, suppose Aniket sold $x$ child tickets. Then how many adult tickets did he sell? To find out, we would follow the same logic we used above. In each case, we subtracted the number of child tickets from 100 to get the number of adult tickets. We now do the same with $x$.

We have summarized this in the table.

| Child tickets | Adult tickets |
|---|---|
| 20 | 80 |
| 45 | 55 |
| 75 | 25 |
| $x$ | $100 - x$ |

We will apply this technique in the next example.

## Example 2.7.2.7

A whale-watching ship had 40 paying passengers on board. The total revenue collected from tickets was $1,196. Full-fare passengers paid $32 each and reduced-fare passengers paid $26 each. How many full-fare passengers and how many reduced-fare passengers were on the ship?

**Answer**

| | |
|---|---|
| **Step 1.** Determine the types of tickets involved. | full-fare tickets and reduced-fare tickets |
| **Step 2. Identify** what we are looking for. | the number of full-fare tickets and reduced-fare tickets |
| **Step 3. Name.** Represent the number of each type of ticket using variables. | Let $f$ = the number of full-fare tickets.<br>$40-f=40-f=$ the number of reduced-fare tickets |
| We know the total number of tickets sold was 40. This means the number of reduced-fare tickets is 40 less the number of full-fare tickets.<br>Multiply the number times the value to get the total value of each type of ticket. | |
| | <table><tr><th>Type</th><th>Number</th><th>·</th><th>Value ($)</th><th>=</th><th>Total Value ($)</th></tr><tr><td>Full-fare</td><td>$f$</td><td></td><td>32</td><td></td><td>$32f$</td></tr><tr><td>Reduced-fare</td><td>$40-f$</td><td></td><td>26</td><td></td><td>$26(40-f)$</td></tr><tr><td></td><td></td><td></td><td></td><td></td><td>1,196</td></tr></table> |
| **Step 4. Translate.** Write the equation by adding the total values of each type of ticket. | $32f + 26(40-f) = 1,196$ |
| **Step 5. Solve** the equation. | $32f + 1,040 - 26f = 1,196$<br>$6f = 156$<br>$f = 26$ full-fare tickets |
| How many reduced-fare? | $40 - f$<br>$40 - 26$<br>$14$ reduced-fare tickets |
| **Step 6. Check** the answer.<br>There were 26 full-fare tickets at $32 each and 14 reduced-fare tickets at $26 each. Is the total value $116?<br>$26 \cdot 32 + 14 \cdot 26 = 832 + 364 = 1,196$ ✓ $26 \cdot 32 + 83 + 14 \cdot 26 = 364 = 1,196$ ✓ | |
| **Step 7. Answer** the question. | They sold 26 full-fare and 14 reduced-fare tickets. |

**Example 2.7.2.8**

During her shift at the museum ticket booth, Leah sold 115 tickets for a total of $1,163. Adult tickets cost $12 and student tickets cost $5. How many adult tickets and how many student tickets did Leah sell?

**Answer**

84 adult tickets, 31 student tickets

**Example 2.7.2.9**

Galen sold 810 tickets for his church's carnival for a total revenue of $2,820. Children's tickets cost $3 each and adult tickets cost $5 each. How many children's tickets and how many adult tickets did he sell?

**Answer**

615 children's tickets and 195 adult tickets

## Solve Mixture Word Problems

Now we'll solve some more general applications of the mixture model. In mixture problems, we are often mixing two quantities, such as raisins and nuts, to create a mixture, such as trail mix. In our tables we will have a row for each item to be mixed as well as one for the final mixture.

**Example 2.7.2.10**

Henning is mixing raisins and nuts to make 25 pounds of trail mix. Raisins cost $4.50 a pound and nuts cost $8 a pound. If Henning wants his cost for the trail mix to be $6.60 a pound, how many pounds of raisins and how many pounds of nuts should he use?

**Answer**

| | |
|---|---|
| **Step 1.** Determine what is being mixed. | The 25 pounds of trail mix will come from mixing raisins and nuts. |
| **Step 2.** Identify what we are looking for. | the number of pounds of raisins and nuts |
| **Step 3.** Represent the number of each type of ticket using variables.<br><br>As before, we fill in a chart to organize our information.<br>We enter the price per pound for each item.<br>We multiply the number times the value to get the total value. | Let x=x= number of pounds of raisins.<br>25−x=25−x= number of pounds of nuts |

| Type | Number of pounds | · Price per Pound ($) | = Total Value ($) |
|---|---|---|---|
| Raisins | $x$ | 4.50 | $4.5x$ |
| Nuts | $25-x$ | 8 | $8(25-x)$ |
| Trail mix | 25 | 6.60 | 25(6.60) |

| | |
|---|---|
| Notice that the last column in the table gives the information for the total amount of the mixture. | |
| **Step 4. Translate** into an equation. | The value of the raisins plus the value of the nuts will be the value of the trail mix. |
| **Step 5. Solve** the equation. | $4.5x + 8(25 - x) = 25(6.60)$ |
| | $4.5x + 200 - 8x = 165$<br>$-3.5x = -35$<br>$x = 10$ pounds of raisins |
| Find the number of pounds of nuts. | $25 - x$<br>$25 - 10$<br>$15$ pounds of nuts |

| | |
|---|---|
| **Step 6. Check.**<br>$4.5(10)+8(15)45+120165=?=?$<br>$=25(6.60)165165\checkmark 4.5(10)+8(15)=?25(6.60)45+120=?$<br>$165165=165\checkmark$ | |
| **Step 7. Answer** the question. | Henning mixed ten pounds of raisins with 15 pounds of nuts. |

**? Example 2.7.2.11**

Orlando is mixing nuts and cereal squares to make a party mix. Nuts sell for $7 a pound and cereal squares sell for $4 a pound. Orlando wants to make 30 pounds of party mix at a cost of $6.50 a pound, how many pounds of nuts and how many pounds of cereal squares should he use?

**Answer**

Orlando mixed five pounds of cereal squares and 25 pounds of nuts.

**? Example 2.7.2.12**

Becca wants to mix fruit juice and soda to make a punch. She can buy fruit juice for $3 a gallon and soda for $4 a gallon. If she wants to make 28 gallons of punch at a cost of $3.25 a gallon, how many gallons of fruit juice and how many gallons of soda should she buy?

**Answer**

Becca mixed 21 gallons of fruit punch and seven gallons of soda.

## Solve Uniform Motion Applications

When you are driving down the interstate using your cruise control, the speed of your car stays the same—it is uniform. We call a problem in which the speed of an object is constant a **uniform motion** application. We will use the distance, rate, and time formula, $D = rt$, to compare two scenarios, such as two vehicles traveling at different rates or in opposite directions.

Our problem solving strategies will still apply here, but we will add to the first step. The first step will include drawing a diagram that shows what is happening in the example. Drawing the diagram helps us understand what is happening so that we will write an appropriate equation. Then we will make a table to organize the information, like we did for the coin, ticket, and stamp applications.

The steps are listed here for easy reference:

**SOLVE A UNIFORM MOTION APPLICATION.**

1. **Read** the problem. Make sure all the words and ideas are understood.
   - Draw a diagram to illustrate what is happening.
   - Create a table to organize the information.
     - Label the columns rate, time, distance.
     - List the two scenarios.
     - Write in the information you know.

| | Rate | • Time | = Distance |
|---|---|---|---|
| | | | |
| | | | |
| | | | |

2. **Identify** what you are looking for.
3. **Name** what you are looking for. Choose a variable to represent that quantity.

- Complete the chart.
- Use variable expressions to represent that quantity in each row.
- Multiply the rate times the time to get the distance.

4. **Translate** into an equation.
   - Restate the problem in one sentence with all the important information.
   - Then, translate the sentence into an equation.
5. **Solve** the equation using good algebra techniques.
6. **Check** the answer in the problem and make sure it makes sense.
7. **Answer** the question with a complete sentence.

?

Wayne and Dennis like to ride the bike path from Riverside Park to the beach. Dennis's speed is seven miles per hour faster than Wayne's speed, so it takes Wayne two hours to ride to the beach while it takes Dennis 1.5 hours for the ride. Find the speed of both bikers.

**Answer**

**Step 1. Read** the problem. Make sure all the words and ideas are understood.

Draw a diagram to illustrate what it happening. Shown below is a sketch of what is happening in the example.




Create a table to organize the information.

- Label the columns "Rate," "Time," and "Distance."
- List the two scenarios.
- Write in the information you know.

| | Rate (mph) | • | Time (hrs) | = | Distance (miles) |
|---|---|---|---|---|---|
| Dennis | | | 1.5 | | |
| Wayne | | | 2 | | |

**Step 2. Identify** what you are looking for.

You are asked to find the speed of both bikers.

Notice that the distance formula uses the word "rate," but it is more common to use "speed"

when we talk about vehicles in everyday English.

**Step 3. Name** what we are looking for. Choose a variable to represent that quantity.

Complete the chart Use variable expressions to represent that quantity in each row.
We are looking for the speed of the bikers. Let's let $r$ represent Wayne's speed. Since Dennis' speed is 7 mph faster, we represent that as $r+7$

$r+7 = \text{Dennis' speed}$

$r = \text{Wayne's speed}$

Fill in the speeds into the chart.

| | Rate (mph) | • | Time (hrs) | = | Distance (miles) |
|---|---|---|---|---|---|
| Dennis | $r+7$ | | 1.5 | | |
| Wayne | $r$ | | 2 | | |

Multiply the rate times the time to get the distance.

| | Rate (mph) | • | Time (hrs) | = | Distance (miles) |
|---|---|---|---|---|---|
| Dennis | $r+7$ | | 1.5 | | $1.5(r+7)$ |
| Wayne | $r$ | | 2 | | $2r$ |

**Step 4. Translate** into an equation.

Restate the problem in one sentence with all the important information.

Then, translate the sentence into an equation.
The equation to model this situation will come from the relation between the distances. Look at the diagram we drew above. How is the distance travelled by Dennis related to the distance travelled by Wayne?
Since both bikers leave from Riverside and travel to the beach, they travel the same distance. So we write:

| | distance traveled by Dennis | = | distance traveled by Wayne |
|---|---|---|---|
| Translate to an equation. | $1.5(r+7)$ | = | $2r$ |

**Step 5. Solve** the equation using algebra techniques.

| | |
|---|---|
| Now solve this equation. | $1.5(r+7)=2r$<br>$1.5r+10.5=2r$<br>$10.5=0.5r$<br>$21=r$<br>So Wayne's speed is 21 mph. |
| Find Dennis' speed. | $r+7$<br>$21+7$<br>$28$<br>Dennis' speed 28 mph. |

**Step 6. Check** the answer in the problem and make sure it makes sense.

$28 \text{ mph}(1.5 \text{ hours}) = 42 \text{ miles}\checkmark$
$21 \text{ mph}(2 \text{ hours}) = 42 \text{ miles}\checkmark$

**Step 7. Answer** the question with a complete sentence.

Wayne rode at 21 mph and Dennis rode at 28 mph.

Restate the problem in one sentence with all the important information.

Then, translate the sentence into an equation.
The equation to model this situation will come from the relation between the distances. Look at the diagram we drew above. How is the distance travelled by Dennis related to the distance travelled by Wayne?
Since both bikers leave from Riverside and travel to the beach, they travel the same distance. So we write:

| | distance traveled by Dennis | = | distance traveled by Wayne |
|---|---|---|---|
| Translate to an equation. | $1.5(r+7)$ | = | $2r$ |

An express train and a local train leave Pittsburgh to travel to Washington, D.C. The express train can make the trip in four hours and the local train takes five hours for the trip. The speed of the express train is 12 miles per hour faster than the speed of the local train. Find the speed of both trains.

**Answer**

The speed of the local train is 48 mph and the speed of the express train is 60 mph.

## Example 2.7.2.15

Jeromy can drive from his house in Cleveland to his college in Chicago in 4.5 hours. It takes his mother six hours to make the same drive. Jeromy drives 20 miles per hour faster than his mother. Find Jeromy's speed and his mother's speed.

**Answer**

Jeromy drove at a speed of 80 mph and his mother drove 60 mph.

In Example, we had two bikers traveling the same distance. In the next example, two people drive toward each other until they meet.


## Example 2.7.2.16

Carina is driving from her home in Anaheim to Berkeley on the same day her brother is driving from Berkeley to Anaheim, so they decide to meet for lunch along the way in Buttonwillow. The distance from Anaheim to Berkeley is 395 miles. It takes Carina three hours to get to Buttonwillow, while her brother drives four hours to get there. Carina's average speed is 15 miles per hour faster than her brother's average speed. Find Carina's and her brother's average speeds.

**Answer**

**Step 1. Read** the problem. Make sure all the words and ideas are understood.

Draw a diagram to illustrate what it happening. Below shows a sketch of what is happening in the example.




Create a table to organize the information.

- Label the columns rate, time, distance.
- List the two scenarios.
- Write in the information you know.

| | Rate (mph) | • | Time (hrs) | = | Distance (miles) |
|---|---|---|---|---|---|
| Carina | | | 3 | | |
| Brother | | | 4 | | |
| | | | | | 395 |

**Step 2. Identify** what we are looking for.

We are asked to find the average speeds of Carina and her brother.

**Step 3. Name** what we are looking for. Choose a variable to represent that quantity.

Complete the chart. Use variable expressions to represent that quantity in each row.
We are looking for their average speeds. Let's let $r$ represent the average speed of Carina. Since the brother's speed is 15

mph faster, we represent that as $r+15$.
Fill in the speeds into the chart. Multiply the rate times the time to get the distance.

| | Rate (mph) | • Time (hrs) | = Distance (miles) |
|---|---|---|---|
| Carina | $r+15$ | 3 | $3(r+15)$ |
| Brother | $r$ | 4 | $4r$ |
| | | | 395 |

**Step 4. Translate** into an equation.

Restate the problem in one sentence with all the important information. Then, translate the sentence into an equation.
Again, we need to identify a relationship between the distances in order to write an equation. Look at the diagram we created above and notice the relationship between the distance Carina traveled and the distance her brother traveled.
The distance Carina traveled plus the distance her brother travel must add up to 410 miles. So we write:

| | distance traveled by Carina | + | distance traveled by her brother | = 395 |
|---|---|---|---|---|
| Translate to an equation. | $3(r+15)$ | + | $4r$ | $=395$ |

**Step 5. Solve** the equation using algebra techniques.

| | |
|---|---|
| Now solve this equation. | $3(r+15)+4r=395$<br>$3r+45+4r=395$<br>$7r+45=395$<br>$7r=350$<br>$r=50$<br>So Carina's brother's speed was 50 mph. |
| Carina's speed is r+15.r+15. | $r+15$<br>$50+15$<br>$65$<br>Her brother's speed was 65 mph. |

**Step 6. Check** the answer in the problem and make sure it makes sense.

$$\begin{aligned} \text{Carina drove} \quad & 65 \text{ mph}(3 \text{ hours}) = \underline{195 \text{ miles}} \\ \text{Her brother drove} \quad & 50 \text{ mph}(4 \text{ hours}) = \underline{200 \text{ miles}} \\ & \qquad\qquad\qquad\quad 395 \text{ miles}\checkmark \end{aligned}$$

**Step 7. Answer** the question with a complete sentence.

Carina drove 65 mph and her brother 50 mph.

my drove at a speed of 80 mph and his mother drove 60 mph.

## ? Example 2.7.2.17

Christopher and his parents live 115 miles apart. They met at a restaurant between their homes to celebrate his mother's birthday. Christopher drove one and a half hours while his parents drove one hour to get to the restaurant. Christopher's average speed was ten miles per hour faster than his parents' average speed. What were the average speeds of Christopher and of his parents as they drove to the restaurant?

**Answer**

Christopher's speed was 50 mph and his parents' speed was 40 mph.

## Example 2.7.2.18

Ashley goes to college in Minneapolis, 234 miles from her home in Sioux Falls. She wants her parents to bring her more winter clothes, so they decide to meet at a restaurant on the road between Minneapolis and Sioux Falls. Ashley and her parents both drove two hours to the restaurant. Ashley's average speed was seven miles per hour faster than her parents' average speed. Find Ashley's and her parents' average speed.

**Answer**

Ashley's parents drove 55 mph and Ashley drove 62 mph.

As you read the next example, think about the relationship of the distances traveled. Which of the previous two examples is more similar to this situation?

## Example 2.7.2.19

Two truck drivers leave a rest area on the interstate at the same time. One truck travels east and the other one travels west. The truck traveling west travels at 70 mph and the truck traveling east has an average speed of 60 mph. How long will they travel before they are 325 miles apart?

**Answer**

**Step 1. Read** the problem. Make all the words and ideas are understood.

Draw a diagram to illustrate what it happening.




Create a table to organize the information.

- Label the columns rate, time, distance.
- List the two scenarios.
- Write in the information you know.

| | Rate (mph) | • | Time (hrs) | = | Distance (miles) |
|---|---|---|---|---|---|
| West | 70 | | | | |
| East | 60 | | | | |
| | | | | | 325 |

**Step 2. Identify** what we are looking for.

We are asked to find the amount of time the trucks will travel until they are 325 miles apart.

**Step 3. Name** what we are looking for. Choose a variable to represent that quantity.

Complete the chart. Use variable expressions to represent that quantity in each row.
We are looking for the time travelled. Both trucks will travel the same amount of time.
Let's call the time $t$. Since their speeds are different, they will travel different distances.

Multiply the rate times the time to get the distance.

| | Rate (mph) | • Time (hrs) | = Distance (miles) |
|---|---|---|---|
| West | 70 | $t$ | $70t$ |
| East | 60 | $t$ | $60t$ |
| | | | 325 |

**Step 4. Translate** into an equation.

Restate the problem in one sentence with all the important information. Then, translate the sentence into an equation.
We need to find a relation between the distances in order to write an equation. Looking at the diagram, what is the relationship between the distances each of the trucks will travel?
The distance travelled by the truck going west plus the distance travelled by the truck going east must add up to 325 miles. So we write:

| | distance traveled by westbound truck | + | distance traveled by eastbound truck | = 325 |
|---|---|---|---|---|
| Translate to an equation. | $70t$ | + | $60t$ | = 325 |

**Step 5. Solve** the equation using algebra techniques.

$$\begin{aligned} \text{Now solve this equation} \qquad 70t+60t &= 325 \\ 130t &= 325 \\ t &= 2.5 \end{aligned}$$

So it will take the trucks $2.5$ hours to be 325 miles apart.

**Step 6. Check** the answer in the problem and make sure it makes sense.

$$\begin{aligned} \text{Truck going West} \quad 70 \text{ mph}(2.5 \text{ hours}) &= 175 \text{ miles} \\ \text{Truck going East} \quad 60 \text{ mph}(2.5 \text{ hours}) &= \underline{150 \text{ miles}} \\ & \quad 325 \text{ miles}\checkmark \end{aligned}$$

**Step 7. Answer** the question with a complete sentence.
It will take the trucks 2.5 hours to be 325 miles apart.

**? Example 2.7.2.20**

Pierre and Monique leave their home in Portland at the same time. Pierre drives north on the turnpike at a speed of 75 miles per hour while Monique drives south at a speed of 68 miles per hour. How long will it take them to be 429 miles apart?

**Answer**

Pierre and Monique will be 429 miles apart in 3 hours.

**? Example 2.7.2.21**

Thanh and Nhat leave their office in Sacramento at the same time. Thanh drives north on I-5 at a speed of 72 miles per hour. Nhat drives south on I-5 at a speed of 76 miles per hour. How long will it take them to be 330 miles apart?

**Answer**

Thanh and Nhat will be 330 miles apart in 2.2 hours.


It is important to make sure that the units match when we use the distance rate and time formula. For instance, if the rate is in miles per hour, then the time must be in hours.

## Example 2.7.2.22

When Naoko walks to school, it takes her 30 minutes. If she rides her bike, it takes her 15 minutes. Her speed is three miles per hour faster when she rides her bike than when she walks. What is her speed walking and her speed riding her bike?

**Answer**

First, we draw a diagram that represents the situation to help us see what is happening.




We are asked to find her speed walking and riding her bike. Let's call her walking speed $r$. Since her biking speed is three miles per hour faster, we will call that speed $r+3$. We write the speeds in the chart.

The speed is in miles per hour, so we need to express the times in hours, too, in order for the units to be the same. Remember, 1 hour is 60 minutes. So:

$$30 \text{ minutes is } \frac{30}{60} \text{ or } \frac{1}{2} \text{ hour}$$
$$15 \text{ minutes is } \frac{15}{60} \text{ or } \frac{1}{4} \text{ hour}$$

We write the times in the chart.

Next, we multiply rate times time to fill in the distance column.

| | Rate (mph) | • Time (hrs) | = Distance (miles) |
|---|---|---|---|
| Walk | $r$ | $\frac{1}{2}$ | $\frac{1}{2}r$ |
| Bike | $r+3$ | $\frac{1}{4}$ | $\frac{1}{4}(r+3)$ |

The equation will come from the fact that the distance from Naoko's home to her school is the same whether she is walking or riding her bike.
So we say:

| | distance walked = distance covered by bike |
|---|---|
| Translate to an equation. | $\frac{1}{2}r = \frac{1}{4}(r+3)$ |
| Solve this equation. | $\frac{1}{2}r = \frac{1}{4}(r+3)$ |
| Clear the fractions by multiplying by the LCD of all the fractions in the equation. | $8 \cdot \frac{1}{2}r = 8 \cdot \frac{1}{4}(r+3)$ |

| | |
|---|---|
| Simplify. | $4r = 2(r + 3)$<br>$4r = 2r + 6$<br>$2r = 6$<br>$r = 3$ mph walking speed<br><br>$r + 3$ biking speed<br>$3 + 3$ |
| | 6 |

Let's check if this works.

$$\begin{aligned} \text{Walk 3 mph } (0.5 \text{ hour}) &= 1.5 \text{ miles} \\ \text{Bike 6 mph } (0.25 \text{ hour}) &= 1.5 \text{ miles} \end{aligned}$$

Yes, either way Naoko travels 1.5 miles to school.

Naoko's walking speed is 3 mph and her speed riding her bike is 6 mph.

**Example 2.7.2.23**

Suzy takes 50 minutes to hike uphill from the parking lot to the lookout tower. It takes her 30 minutes to hike back down to the parking lot. Her speed going downhill is 1.2 miles per hour faster than her speed going uphill. Find Suzy's uphill and downhill speeds.

**Answer**

Suzy's speed uphill is 1.81.8 mph and downhill is three mph.

**Example 2.7.2.24**

Llewyn takes 45 minutes to drive his boat upstream from the dock to his favorite fishing spot. It takes him 30 minutes to drive the boat back downstream to the dock. The boat's speed going downstream is four miles per hour faster than its speed going upstream. Find the boat's upstream and downstream speeds.

**Answer**

The boat's speed upstream is eight mph and downstream is 12 mph.

In the distance, rate and time formula, time represents the actual amount of elapsed time (in hours, minutes, etc.). If a problem gives us starting and ending times as clock times, we must find the elapsed time in order to use the formula.

**Example 2.7.2.25**

Cruz is training to compete in a triathlon. He left his house at 6:00 and ran until 7:30. Then he rode his bike until 9:45. He covered a total distance of 51 miles. His speed when biking was 1.6 times his speed when running. Find Cruz's biking and running speeds.

**Answer**

A diagram will help us model this trip.



Next, we create a table to organize the information. We know the total distance is 51 miles. We are looking for the rate of speed for each part of the trip. The rate while biking is 1.6 times the rate of running. If we let $r$ = the rate running, then the rate biking is $1.6r$.

The times here are given as clock times. Cruz started from home at 6:00 a.m. and started biking at 7:30 a.m. So he spent 1.5 hours running. Then he biked from 7:30 a.m until 9:45 a.m. So he spent 2.25 hours biking.

Now, we multiply the rates by the times.

| | Rate (mph) | • Time (hrs) | = Distance (miles) |
|---|---|---|---|
| run | $r$ | 1.5 | $1.5r$ |
| bike | $1.6r$ | 2.25 | $2.25(1.6r)$ |
| | | | 51 |

By looking at the diagram, we can see that the sum of the distance running and the distance biking is 255 miles.

| | |
|---|---|
| | distance running + distance biking = 51 |
| Translate to an equation. | $1.5r + 2.25(1.6r) = 51$ |
| Solve this equation. | $1.5r + 2.25(1.6r) = 51$<br>$1.5r + 3.6r = 51$<br>$5.1r = 51$<br>$r = 10$ mph running<br>$1.6r$ biking speed<br>$1.6(10)$<br>16 mph |
| Check.<br>Run 10 mph (1.5 hour) = 15 mi<br>Bike 16 mph (2.25 hour) = 36 mi<br>51 mi | |

## Example 2.7.2.26

Hamilton loves to travel to Las Vegas, 255 miles from his home in Orange County. On his last trip, he left his house at 2:00 p.m. The first part of his trip was on congested city freeways. At 4:00 pm, the traffic cleared and he was able to drive through the desert at a speed 1.75 times faster than when he drove in the congested area. He arrived in Las Vegas at 6:30 p.m. How fast was he driving during each part of his trip?

**Answer**

Hamilton drove 40 mph in the city and 70 mph in the desert.

## Example 2.7.2.27

Phuong left home on his bicycle at 10:00. He rode on the flat street until 11:15, then rode uphill until 11:45. He rode a total of 31 miles. His speed riding uphill was 0.6 times his speed on the flat street. Find his speed biking uphill and on the flat street.

**Answer**

Phuong rode uphill at a speed of 12 mph and on the flat street at 20 mph.

## Key Concepts

- **Total Value of Coins**
  For the same type of coin, the total value of a number of coins is found by using the model
  number·value=totalvaluenumber·value=totalvalue
  - *number* is the number of coins
  - *value* is the value of each coin
  - *total value* is the total value of all the coins
- **How to solve coin word problems.**
  1. **Read** the problem. Make sure all the words and ideas are understood.
     Determine the types of coins involved.
     Create a table to organize the information.
     Label the columns “type,” “number,” “value,” “total value.”
     List the types of coins.
     Write in the value of each type of coin.
     Write in the total value of all the coins.

| Type | Number • Value ($) = | Total Value ($) |
|---|---|---|
| | | |
| | | |
| | | |

  2. **Identify** what you are looking for.
  3. **Name** what you are looking for. Choose a variable to represent that quantity.
     Use variable expressions to represent the number of each type of coin and write them in the table.
     Multiply the number times the value to get the total value of each type of coin.
  4. **Translate** into an equation.
     It may be helpful to restate the problem in one sentence with all the important information. Then, translate the sentence into an equation.
     Write the equation by adding the total values of all the types of coins.
  5. **Solve** the equation using good algebra techniques.
  6. **Check** the answer in the problem and make sure it makes sense.
  7. **Answer** the question with a complete sentence.
- **How To Solve a Uniform Motion Application**
  1. **Read** the problem. Make sure all the words and ideas are understood.
     Draw a diagram to illustrate what it happening.
     Create a table to organize the information.
     Label the columns rate, time, distance.
     List the two scenarios.
     Write in the information you know.

| | Rate • Time = | Distance |
|---|---|---|
| | | |
| | | |
| | | |

  2. **Identify** what you are looking for.
  3. **Name** what you are looking for. Choose a variable to represent that quantity.
     Complete the chart.
     Use variable expressions to represent that quantity in each row.
     Multiply the rate times the time to get the distance.
  4. **Translate** into an equation.
     Restate the problem in one sentence with all the important information.
     Then, translate the sentence into an equation.
  5. **Solve** the equation using good algebra techniques.

6. **Check** the answer in the problem and make sure it makes sense.
7. **Answer** the question with a complete sentence.

---

This page titled 2.7.2: Solve Mixture and Uniform Motion Applications is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.5: Solve Mixture and Uniform Motion Applications** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/intermediate-algebra-2e.

# 2.7.2E: Exercises

## Practice Makes Perfect

**Solve Coin Word Problems**

In the following exercises, solve each coin word problem.

1. Michaela has $2.05 in dimes and nickels in her change purse. She has seven more dimes than nickels. How many coins of each type does she have?

**Answer**

nine nickels, 16 dimes

2. Liliana has $2.10 in nickels and quarters in her backpack. She has 12 more nickels than quarters. How many coins of each type does she have?

3. In a cash drawer there is $125 in $5 and $10 bills. The number of $10 bills is twice the number of $5 bills. How many of each type of bill is in the drawer?

**Answer**

ten $10 bills, five $5 bills

4. Sumanta has $175 in $5 and $10 bills in his drawer. The number of $5 bills is three times the number of $10 bills. How many of each are in the drawer?

5. Chi has $11.30 in dimes and quarters. The number of dimes is three more than three times the number of quarters. How many of each are there?

**Answer**

63 dimes, 20 quarters

6. Alison has $9.70 in dimes and quarters. The number of quarters is eight more than four times the number of dimes. How many of each coin does she have?

7. Mukul has $3.75 in quarters, dimes and nickels in his pocket. He has five more dimes than quarters and nine more nickels than quarters. How many of each coin are in his pocket?

**Answer**

16 nickels, 12 dimes, seven quarters

8. Vina has $4.70 in quarters, dimes and nickels in her purse. She has eight more dimes than quarters and six more nickels than quarters. How many of each coin are in her purse?

**Solve Ticket and Stamp Word Problems**

In the following exercises, solve each ticket or stamp word problem.

9. The first day of a water polo tournament the total value of tickets sold was $17,610. One-day passes sold for $20 and tournament passes sold for $30. The number of tournament passes sold was 37 more than the number of day passes sold. How many day passes and how many tournament passes were sold?

**Answer**

330 day passes, 367 tournament passes

10. At the movie theater, the total value of tickets sold was $2,612.50. Adult tickets sold for $10 each and senior/child tickets sold for $7.50 each. The number of senior/child tickets sold was 25 less than twice the number of adult tickets sold. How many senior/child tickets and how many adult tickets were sold?

11. Julie went to the post office and bought both $0.41 stamps and $0.26 postcards. She spent $51.40. The number of stamps was 20 more than twice the number of postcards. How many of each did she buy?

**Answer**

40 postcards, 100 stamps

12. Jason went to the post office and bought both $0.41 stamps and $0.26 postcards and spent $10.28 The number of stamps was four more than twice the number of postcards. How many of each did he buy?

13. Hilda has $210 worth of $10 and $12 stock shares. The number of $10 shares is five more than twice the number of $12 shares. How many of each type of share does she have?

**Answer**

15 $10 shares, five $12 shares

14. Mario invested $475 in $45 and $25 stock shares. The number of $25 shares was five less than three times the number of $45 shares. How many of each type of share did he buy?

15. The ice rink sold 95 tickets for the afternoon skating session, for a total of $828. General admission tickets cost $10 each and youth tickets cost $8 each. How many general admission tickets and how many youth tickets were sold?

**Answer**

34 general, 61 youth

16. For the 7:30 show time, 140 movie tickets were sold. Receipts from the $13 adult tickets and the $10 senior tickets totaled $1,664. How many adult tickets and how many senior tickets were sold?

17. The box office sold 360 tickets to a concert at the college. The total receipts were $4,170. General admission tickets cost $15 and student tickets cost $10. How many of each kind of ticket was sold?

**Answer**

114 general, 246 student

18. Last Saturday, the museum box office sold 281 tickets for a total of $3,954. Adult tickets cost $15 and student tickets cost $12. How many of each kind of ticket was sold

**Solve Mixture Word Problems**

In the following exercises, solve each mixture word problem.

19. Macario is making 12 pounds of nut mixture with macadamia nuts and almonds. Macadamia nuts cost $9 per pound and almonds cost $5.25 per pound. How many pounds of macadamia nuts and how many pounds of almonds should Macario use for the mixture to cost $6.50 per pound to make?

**Answer**

Four pounds of macadamia nuts, eight pounds almonds

20. Carmen wants to tile the floor of his house. He will need 1,000 square feet of tile. He will do most of the floor with a tile that costs $1.50 per square foot,

21. Riley is planning to plant a lawn in his yard. He will need nine pounds of grass seed. He wants to mix Bermuda seed that costs $4.80 per pound with Fescue seed that costs $3.50 per pound. How much of each seed should he buy so that the overall cost will be $4.02 per pound?

**Answer**

3.63.6 lbs Bermuda seed, 5.45.4 lbs Fescue seed

22. Vartan was paid $25,000 for a cell phone app that he wrote and wants to invest it to save for his son's education. He wants to put some of the money into a bond that pays 4% annual interest and the rest into stocks that pay 9% annual interest. If he wants to earn 7.4% annual interest on the total amount, how much money should he invest in each account?

23. Vern sold his 1964 Ford Mustang for $55,000 and wants to invest the money to earn him 5.8% interest per year. He will put some of the money into Fund A that earns 3% per year and the rest in Fund B that earns 10% per year. How much should he invest into each fund if he wants to earn 5.8% interest per year on the total amount?

**Answer**

$33,000 in Fund A, $22,000 in Fund B

24. Dominic pays 7% interest on his $15,000 college loan and 12% interest on his $11,000 car loan. What average interest rate does he pay on the total $26,000 he owes? (Round your answer to the nearest tenth of a percent.)

25. Liam borrowed a total of $35,000 to pay for college. He pays his parents 3% interest on the $8,000 he borrowed from them and pays the bank 6.8% on the rest. What average interest rate does he pay on the total $35,000? (Round your answer to the nearest tenth of a percent.)

**Answer**

5.9

**Solve Uniform Motion Applications**

In the following exercises, solve.

26. Lilah is moving from Portland to Seattle. It takes her three hours to go by train. Mason leaves the train station in Portland and drives to the train station in Seattle with all Lilah's boxes in his car. It takes him 2.4 hours to get to Seattle, driving at 15 miles per hour faster than the speed of the train. Find Mason's speed and the speed of the train.

27. Kathy and Cheryl are walking in a fundraiser. Kathy completes the course in 4.8 hours and Cheryl completes the course in eight hours. Kathy walks two miles per hour faster than Cheryl. Find Kathy's speed and Cheryl's speed.

**Answer**

Kathy 5 mph, Cheryl 3 mph

28. Two busses go from Sacramento to San Diego. The express bus makes the trip in 6.8 hours and the local bus takes 10.2 hours for the trip. The speed of the express bus is 25 mph faster than the speed of the local bus. Find the speed of both busses.

29. A commercial jet and a private airplane fly from Denver to Phoenix. It takes the commercial jet 1.6 hours for the flight, and it takes the private airplane 2.6 hours. The speed of the commercial jet is 210 miles per hour faster than the speed of the private airplane. Find the speed of both airplanes to the nearest 10 mph.

**Answer**

commercial 540 mph, private plane 330 mph

30. Saul drove his truck three hours from Dallas towards Kansas City and stopped at a truck stop to get dinner. At the truck stop he met Erwin, who had driven four hours from Kansas City towards Dallas. The distance between Dallas and Kansas City is 542 miles, and Erwin's speed was eight miles per hour slower than Saul's speed. Find the speed of the two truckers.

31. Charlie and Violet met for lunch at a restaurant between Memphis and New Orleans. Charlie had left Memphis and drove 4.8 hours towards New Orleans. Violet had left New Orleans and drove two hours towards Memphis, at a speed 10 miles per hour faster than Charlie's speed. The distance between Memphis and New Orleans is 394 miles. Find the speed of the two drivers.

**Answer**

Violet 65 mph, Charlie 55 mph

32. Sisters Helen and Anne live 332 miles apart. For Thanksgiving, they met at their other sister's house partway between their homes. Helen drove 3.2 hours and Anne drove 2.8 hours. Helen's average speed was four miles per hour faster than Anne's. Find Helen's average speed and Anne's average speed.

33. Ethan and Leo start riding their bikes at the opposite ends of a 65-mile bike path. After Ethan has ridden 1.5 hours and Leo has ridden two hours, they meet on the path. Ethan's speed is six miles per hour faster than Leo's speed. Find the speed of the two bikers.

**Answer**

Ethan 22 mph, Leo 16 mph

34. Elvira and Aletheia live 3.1 miles apart on the same street. They are in a study group that meets at a coffee shop between their houses. It took Elvira half an hour and Aletheia two-thirds of an hour to walk to the coffee shop. Aletheia's speed is 0.6 miles per hour slower than Elvira's speed. Find both women's walking speeds.

35. DaMarcus and Fabian live 23 miles apart and play soccer at a park between their homes. DaMarcus rode his bike for three-quarters of an hour and Fabian rode his bike for half an hour to get to the park. Fabian's speed was six miles per hour faster than DaMarcus' speed. Find the speed of both soccer players.

**Answer**

DaMarcus 16 mph, Fabian 22 mph

36. Cindy and Richard leave their dorm in Charleston at the same time. Cindy rides her bicycle north at a speed of 18 miles per hour. Richard rides his bicycle south at a speed of 14 miles per hour. How long will it take them to be 96 miles apart?

37. Matt and Chris leave their uncle's house in Phoenix at the same time. Matt drives west on I-60 at a speed of 76 miles per hour. Chris drives east on I-60 at a speed of 82 miles per hour. How many hours will it take them to be 632 miles apart?

**Answer**

four hours

38. Two busses leave Billings at the same time. The Seattle bus heads west on I-90 at a speed of 73 miles per hour while the Chicago bus heads east at a speed of 79 miles an hour. How many hours will it take them to be 532 miles apart?

39. Two boats leave the same dock in Cairo at the same time. One heads north on the Mississippi River while the other heads south. The northbound boat travels four miles per hour. The southbound boat goes eight miles per hour. How long will it take them to be 54 miles apart?

**Answer**

4.5 hours

40. Lorena walks the path around the park in 30 minutes. If she jogs, it takes her 20 minutes. Her jogging speed is 1.5 miles per hour faster than her walking speed. Find Lorena's walking speed and jogging speed

41. Julian rides his bike uphill for 45 minutes, then turns around and rides back downhill. It takes him 15 minutes to get back to where he started. His uphill speed is 3.2 miles per hour slower than his downhill speed. Find Julian's uphill and downhill speed.

**Answer**

uphill 1.6 mph, downhill 4.8 mph

42. Cassius drives his boat upstream for 45 minutes. It takes him 30 minutes to return downstream. His speed going upstream is three miles per hour slower than his speed going downstream. Find his upstream and downstream speeds.

43. It takes Darline 20 minutes to drive to work in light traffic. To come home, when there is heavy traffic, it takes her 36 minutes. Her speed in light traffic is 24 miles per hour faster than her speed in heavy traffic. Find her speed in light traffic and in heavy traffic.

**Answer**

light traffic 54 mph, heavy traffic 30 mph

44. At 1:30, Marlon left his house to go to the beach, a distance of 7.6 miles. He rode his skateboard until 2:15, and then walked the rest of the way. He arrived at the beach at 3:00. Marlon's speed on his skateboard is 2.5 times his walking speed. Find his speed when skateboarding and when walking.

45. Aaron left at 9:15 to drive to his mountain cabin 108 miles away. He drove on the freeway until 10:45 and then drove on a mountain road. He arrived at 11:05. His speed on the freeway was three times his speed on the mountain road. Find Aaron's speed on the freeway and on the mountain road.

**Answer**

freeway 72 mph, mountain road 24 mph

46. Marisol left Los Angeles at 2:30 to drive to Santa Barbara, a distance of 95 miles. The traffic was heavy until 3:20. She drove the rest of the way in very light traffic and arrived at 4:20. Her speed in heavy traffic was 40 miles per hour slower than her speed in light traffic. Find her speed in heavy traffic and in light traffic.

47. Lizette is training for a marathon. At 7:00 she left her house and ran until 8:15 then she walked until 11:15. She covered a total distance of 19 miles. Her running speed was five miles per hour faster than her walking speed. Find her running and walking speeds.

**Answer**

running eight mph, walking three mph

## Everyday Math

48. John left his house in Irvine at 8:35 a.m. to drive to a meeting in Los Angeles, 45 miles away. He arrived at the meeting at 9:50 a.m.. At 5:30 p.m. he left the meeting and drove home. He arrived home at 7:18 p.m.

ⓐ What was his average speed on the drive from Irvine to Los Angeles?

ⓑ What was his average speed on the drive from Los Angeles to Irvine?

ⓒ What was the total time he spent driving to and from this meeting?

49. Sarah wants to arrive at her friend's wedding at 3:00. The distance from Sarah's house to the wedding is 95 miles. Based on usual traffic patterns, Sarah predicts she can drive the first 15 miles at 60 miles per hour, the next 10 miles at 30 miles per hour, and the remainder of the drive at 70 miles per hour.

ⓐ How long will it take Sarah to drive the first 15 miles?

ⓑ How long will it take Sarah to drive the next 10 miles?

ⓒ How long will it take Sarah to drive the rest of the trip?

ⓓ What time should Sarah leave her house?

**Answer**

ⓐ 15 minutes ⓑ 20 minutes ⓒ one hour (d) 1:25

## Writing Exercises

50. Suppose you have six quarters, nine dimes, and four pennies. Explain how you find the total value of all the coins.

51. Do you find it helpful to use a table when solving coin problems? Why or why not?

**Answer**

Answers will vary.

52. In the table used to solve coin problems, one column is labeled "number" and another column is labeled "value." What is the difference between the "number" and the "value"?

53. When solving a uniform motion problem, how does drawing a diagram of the situation help you?

**Answer**

Answers will vary.

## Self Check

ⓐ After completing the exercises, use this checklist to evaluate your mastery of the objectives of this section.

| I can... | Confidently | With some help | No-I don't get it! |
|---|---|---|---|
| solve coin word problems. | | | |
| solve ticket and stamp word problems. | | | |
| solve mixture word problems. | | | |
| solve uniform motion applications. | | | |

ⓑ On a scale of 1-10, how would you rate your mastery of this section in light of your responses on the checklist? How can you improve this?

---

This page titled 2.7.2E: Exercises is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.5E: Exercises** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/intermediate-algebra-2e.

# 2.7.3: Solve Applications with Rational Equations

**Learning Objectives**

- Solve proportions
- Solve similar figure applications
- Solve uniform motion applications
- Solve work applications
- Solve direct variation problems
- Solve inverse variation problems

**Note**

Before you get started, take this readiness quiz.

1. Example 2.2.13. Example 2.5.13. Example 2.2.9.

## Solve Proportions

When two rational expressions are equal, the equation relating them is called a **proportion**.

**Proportion**

A proportion is an equation of the form $\frac{a}{b}=\frac{c}{d}$, where $b\neq 0, d\neq 0$.

The proportion is read "$a$ is to $b$ as $c$ is to $d$."

The equation $\frac{1}{2}=\frac{4}{8}$ is a proportion because the two fractions are equal. The proportion $\frac{1}{2}=\frac{4}{8}$ is read "1 is to 2 as 4 is to 8."

Since a proportion is an equation with rational expressions, we will solve proportions the same way we solved rational equations. We'll multiply both sides of the equation by the LCD to clear the fractions and then solve the resulting equation.

**Example 2.7.3.1**

Solve: $\frac{n}{n+14}=\frac{5}{7}$.

**Solution**

$$\frac{n}{n+14}=\frac{5}{7},\quad n\neq -14$$

Multiply both sides by LCD.

$$7(n+14)\left(\frac{n}{n+14}\right)=7(n+14)\left(\frac{5}{7}\right)$$

Remove common factors on each side.

$$7n=5(n+14)$$

Simplify.

$$7n=5n+70$$

Solve for $n$.

$$\begin{aligned}2n&=70\\ n&=35\end{aligned}$$

Check.

$$\frac{n}{n+14}=\frac{5}{7}$$

Substitute $n=35$

$$\frac{35}{35+14}\stackrel{?}{=}\frac{5}{7}$$

Simplify.

$$\frac{35}{49}\stackrel{?}{=}\frac{5}{7}$$

Show common factors.

$$\frac{5\cdot 7}{7\cdot 7}\stackrel{?}{=}\frac{5}{7}$$

Simplify.

$$\frac{5}{7}=\frac{5}{7}\ \surd$$

**Exercise 2.7.3.1**

Solve the proportion: $\frac{y}{y+55}=\frac{3}{8}$.

**Answer**

$y=33$

**? Exercise 2.7.3.2**

Solve the proportion: $\frac{z}{z-84}=-\frac{1}{5}$.

**Answer**

$z=14$

Notice in the last example that when we cleared the fractions by multiplying by the LCD, the result is the same as if we had cross-multiplied.

$$\begin{aligned} \frac{n}{n+14}&=\frac{5}{7} \\ 7(n+14)\left(\frac{n}{n+14}\right)&=7(n+14)\left(\frac{5}{7}\right) \\ 7n&=5(n+14) \end{aligned} \qquad \begin{aligned} \frac{n}{n+14}&=\frac{5}{7} \\ \frac{n}{n+14}&=\frac{5}{7} \\ 7n&=5(n+14) \end{aligned}$$

For any proportion, $\frac{a}{b}=\frac{c}{d}$, we get the same result when we clear the fractions by multiplying by the LCD as when we cross-multiply.

$$\begin{aligned} \frac{a}{b}&=\frac{c}{d} \\ bd\left(\frac{a}{b}=\frac{c}{d}\right)&bd \\ ad&=bc \end{aligned} \qquad \begin{aligned} \frac{a}{b}&=\frac{c}{d} \\ \frac{a}{b}&=\frac{c}{d} \\ ad&=bc \end{aligned}$$

To solve applications with proportions, we will follow our usual strategy for solving applications But when we set up the proportion, we must make sure to have the units correct—the units in the numerators must match each other and the units in the denominators must also match each other.

When pediatricians prescribe acetaminophen to children, they prescribe 5 milliliters (ml) of acetaminophen for every 25 pounds of the child's weight. If Zoe weighs 80 pounds, how many milliliters of acetaminophen will her doctor prescribe?

**Solution**

Identify what we are asked to find, and choose a variable to represent it.

How many ml of acetaminophen will the doctor prescribe?

Let $a=ml$ of acetaminophen.

Write a sentence that gives the information to find it.

If 5 ml is prescribed for every 25 pounds, how much will be prescribed for 80 pounds?

Translate into a proportion—be careful of the units.


**Step 1**. Write the inequality as one quotient on the left and zero on the right. Our inequality is in this form.

$$\frac{x-1}{x+3}\geq 0$$

**Step 2**. Determine the critical points-the points where the rational expression will be zero or undefined.

The rational expression will be zero when the numerator is zero. Since $x-1=0$ when $x=1$, then 1 is a critical point. The rational expression will be undefined when the denominator is zero. Since $x+3=0$ when $x=-3$, then -3 is a critical point.


**Step 3**. Use the critical points to divide the number line into intervals.




**Step 4**. Above the number line show the sign of each factor of the rational expression in each interval. Below the number line show the sign of the quotient.

Use values in each interval to determine the value of each factor in the interval. In the interval (-3,1), zero is a good value to test. For example, when $x=0$ then $x-1=-1$ and $x+3=3$ The factor $x-1$ is marked negative and $x+3$ marked positive. Since a negative divided by a positive is negative, the quotient is marked negative in that interval.

**Step 5**. Determine the intervals where the inequality is correct. Write the solution in interval notation.




We want the quotient to be greater than or equal to zero, so the numbers in the intervals $(-\infty,-3)$ and $(1,\infty)$ are solutions. Since 3 must be excluded since it makes the rational expression 0, we cannot include it in the solution. We can include 1 in our solution.

$$(-\infty,-3)\cup[1,\infty)$$

Multiply both sides by the LCD, 400. Remove common factors on each side. Simplify, but don't multiply on the left. Notice what the next step will be.

$$16\cdot 5=5a$$

Solve for $a$.

$$\begin{aligned} \frac{16\cdot 5}{5}&=\frac{5a}{5} \\ 16&=a \end{aligned}$$

Check. Is the answer reasonable? Write a complete sentence.

The pediatrician would prescribe 16 ml of acetaminophen to Zoe.

**? Exercise 2.7.3.3**

Pediatricians prescribe 5 milliliters (ml) of acetaminophen for every 25 pounds of a child's weight. How many milliliters of acetaminophen will the doctor prescribe for Emilia, who weighs 60 pounds?

**Answer**

The pediatrician will prescribe 12 ml of acetaminophen to Emilia.

**? Exercise 2.7.3.4**

For every 1 kilogram (kg) of a child's weight, pediatricians prescribe 15 milligrams (mg) of a fever reducer. If Isabella weighs 12 kg, how many milligrams of the fever reducer will the pediatrician prescribe?

**Answer**

The pediatrician will prescribe 180 mg of fever reducer to Isabella.


## Solve similar figure applications

When you shrink or enlarge a photo on a phone or tablet, figure out a distance on a map, or use a pattern to build a bookcase or sew a dress, you are working with similar figures. If two figures have exactly the same shape, but different sizes, they are said to be similar. One is a scale model of the other. All their corresponding angles have the same measures and their corresponding sides have the same ratio.

**Similar Figures**

Two figures are similar if the measures of their corresponding angles are equal and their corresponding sides have the same ratio.


For example, the two triangles in Figure below are similar. Each side of $\Delta ABC$ is four times the length of the corresponding side of $\Delta XYZ$.




This is summed up in the Property of Similar Triangles.

**Property of Similar Triangles**


If $\Delta ABC$ is similar to $\Delta XYZ$, then their corresponding angle measure are equal and their corresponding sides have the same ratio.




To solve applications with similar figures we will follow the Problem-Solving Strategy for Geometry Applications we used earlier.

**✓ Example 2.7.3.3**

On a map, San Francisco, Las Vegas, and Los Angeles form a triangle. The distance between the cities is measured in inches. The figure on the left below represents the triangle formed by the cities on the map. If the actual distance from Los Angeles to Las Vegas is 270 miles, find the distance from Los Angeles to San Francisco.




**Solution**

Since the triangles are similar, the corresponding sides are proportional.

**Read** the problem. Draw the figures and label it with the given information. The figures are shown above.

**Identify** what we are looking for: the actual distance from Los Angeles to San Francisco

**Name** the variables: Let $x$ = distance from Los Angeles to San Francisco.

**Translate** into an equation. Since the triangles are similar, the corresponding sides are proportional. We'll make the numerators "miles" and the denominators "inches".

$$\$\frac{x \text{ miles}}{1.3 \text{ inches}} = \frac{270 \text{ miles}}{1 \text{ inch}}\$$$

**Solve** the equation.

$$1.3\left(\frac{x}{1.3}\right) = 1.3\left(\frac{270}{1}\right)$$
$$x = 351$$


**Check**. On the map, the distance from Los Angeles to San Francisco is more than the distance from Los Angeles to Las Vegas. Since 351 is more than 270 the answer makes sense.

Check $x = 351$ in the original proportion. Use a calculator.

$$\frac{x \text{ miles}}{1.3 \text{ inches}} = \frac{270 \text{ miles}}{1 \text{ inch}}$$
$$\frac{351 \text{ miles}}{1.3 \text{ inches}} \stackrel{?}{=} \frac{270 \text{ miles}}{1 \text{ inch}}$$
$$\frac{270 \text{ miles}}{1 \text{ inch}} = \frac{270 \text{ miles}}{1 \text{ inch}} \surd$$

**Answer** the question: The distance from Los Angeles to San Francisco is 351 miles.

On the map, Seattle, Portland, and Boise form a triangle. The distance between the cities is measured in inches. The figure on the left below represents the triangle formed by the cities on the map. The actual distance from Seattle to Boise is 400 miles.




**? Exercise 2.7.3.5**

Find the actual distance from Seattle to Portland.

**Answer**

The distance is 150 miles.

**? Exercise 2.7.3.6**

Find the actual distance from Portland to Boise.

**Answer**

The distance is 350 miles.


We can use similar figures to find heights that we cannot directly measure.

**✔ Example 2.7.3.4**

Tyler is 6 feet tall. Late one afternoon, his shadow was 8 feet long. At the same time, the shadow of a tree was 24 feet long. Find the height of the tree.

**Solution**

Read the problem and draw a figure. We are looking for $h$, the height of the tree.




We will use similar triangles to write an equation. The small triangle is similar to the large triangle.

$$\frac{h}{24} = \frac{6}{8}$$

Solve the proportion.

$$24\left(\frac{6}{8}\right) = 24\left(\frac{h}{24}\right)$$
$$18 = h$$

Simplify. Check.

Tyler's height is less than his shadow's length so it makes sense that the tree's height is less than the length of its shadow. Check $h = 18$ in the original proportion.

$$\frac{6}{8} = \frac{h}{24}$$
$$\frac{6}{8} \stackrel{?}{=} \frac{18}{24}$$
$$\frac{3}{4} = \frac{3}{4}\surd$$

**Exercise 2.7.3.7**

A telephone pole casts a shadow that is 50 feet long. Nearby, an 8 foot tall traffic sign casts a shadow that is 10 feet long. How tall is the telephone pole?

**Answer**

The telephone pole is 40 feet tall.

**Exercise 2.7.3.8**

A pine tree casts a shadow of 80 feet next to a 30 foot tall building which casts a 40 feet shadow. How tall is the pine tree?

**Answer**

The pine tree is 60 feet tall.

## Solve Uniform Motion Applications

We have solved uniform motion problems using the formula $D = rt$ in previous chapters. We used a table like the one below to organize the information and lead us to the equation.

| | Rate · Time = Distance | | |
|---|---|---|---|
| | | | |
| | | | |

The formula $D = rt$ assumes we know $r$ and $t$ and use them to find $D$. If we know $D$ and $r$ and need to find $t$, we would solve the equation for $t$ and get the formula $t = \frac{D}{r}$.


We have also explained how flying with or against the wind affects the speed of a plane. We will revisit that idea in the next example.

**Example 2.7.3.5**

An airplane can fly 200 miles into a 30 mph headwind in the same amount of time it takes to fly 300 miles with a 30 mph tailwind. What is the speed of the airplane?

**Solution**

This is a uniform motion situation. A diagram will help us visualize the situation.




We fill in the chart to organize the information.

We are looking for the speed of the airplane. Let $r$ = the speed of the airplane.

When the plane flies with the wind, the wind increases its speed and so the rate is $r + 30$.

When the plane flies against the wind, the wind decreases its speed and the rate is $r - 30$.

Write in the rates. Write in the distances. Since $D = r \cdot t$, we solve for $t$ and get $t = \frac{D}{r}$. We divide the distance by the rate in each row, and place the expression in the time column.

| | Rate · Time = Distance | | |
|---|---|---|---|
| Headwind | $r - 30$ | $\frac{200}{r-30}$ | 200 |
| Tailwind | $r + 30$ | $\frac{300}{r+30}$ | 300 |

We know the times are equal and so we write our equation.

$$\frac{200}{r-30} = \frac{300}{r+30}$$

We multiply both sides by the LCD.

$$(r+30)(r-30)\left(\frac{200}{r-30}\right) = (r+30)(r-30)\left(\frac{300}{r+30}\right)$$

Simplify and solve.

$$\begin{aligned}(r+30)(200) &= (r-30)300\\ 200r+6000 &= 300r-9000\\ 15000 &= 100r\end{aligned}$$

Check.

Is 150mph a reasonable speed for an airplane? Yes. If the plane is traveling 150mph and the wind is 30mph,

$$\text{Tailwind} \quad 150+30=180\text{mph} \quad \frac{300}{180}=\frac{5}{3}\text{ hours}$$

$$\text{Headwind } 150-30=120\text{mph} \frac{200}{120}=\frac{5}{3}\text{ hours}$$

The times are equal, so it checks. The plane was traveling 150mph.

**Exercise 2.7.3.9**

Link can ride his bike 20 miles into a 3 mph headwind in the same amount of time he can ride 30 miles with a 3 mph tailwind. What is Link's biking speed?

**Answer**

Link's biking speed is 15 mph.

**Exercise 2.7.3.10**

Danica can sail her boat 5 miles into a 7 mph headwind in the same amount of time she can sail 12 miles with a 7 mph tailwind. What is the speed of Danica's boat without a wind?

**Answer**

The speed of Danica's boat is 17 mph.

In the next example, we will know the total time resulting from traveling different distances at different speeds.

**Example 2.7.3.6**

Jazmine trained for 3 hours on Saturday. She ran 8 miles and then biked 24 miles. Her biking speed is 4 mph faster than her running speed. What is her running speed?

**Solution**

This is a uniform motion situation. A diagram will help us visualize the situation.




We fill in the chart to organize the information. We are looking for Jazmine's running speed. Let $r$ = Jazmine's running speed.

Her biking speed is 4 miles faster than her running speed. $r+4$ = her biking speed

The distances are given, enter them into the chart. Since $D=r\cdot t$, we solve for $t$ and get $t=\frac{D}{r}$.We divide the distance by the rate in each row, and place the expression in the time column.

| | Rate · Time = Distance | | |
|---|---|---|---|
| Run | $r$ | $\frac{8}{r}$ | 8 |
| Bike | $r+4$ | $\frac{24}{r+4}$ | 24 |
| | | 3 | |

Write a word sentence: Her time plus the time biking is 3 hours.

Translate the sentence to get the equation.

$$\frac{8}{r}+\frac{24}{r+4}=3$$

Solve.

$$\begin{aligned} r(r+4)\left(\frac{8}{r}+\frac{24}{r+4}\right) &= 3\cdot r(r+4) \\ 8(r+4)+24r &= 3r(r+4) \\ 8r+32+24r &= 3r^2+12r \\ 32+32r &= 3r^2+12r \\ 0 &= 3r^2-20r-32 \\ 0 &= (3r+4)(r-8) \end{aligned}$$

$$(3r+4)=0 \quad (r-8)=0$$

$$r=\cancel{-\frac{4}{3}} \qquad r=8$$

Check.

A negative speed does not make sense in this problem, so $r=8$ is the solution.

Is 8 mph a reasonable running speed? Yes.

If Jazmine's running rate is 4, then her biking rate, $r+4$, which is $8+4=12$.

$$\text{Run } 8\text{mph} \quad \frac{8\text{miles}}{8\text{mph}}=1\text{ hour}$$

$$\text{Bike } 12\text{ mph} \quad \frac{24\text{ miles}}{12\text{mph}}=2\text{ hours}$$

Total 3 hours.

Jazmine's running speed is 8 mph.

**Exercise 2.7.3.11**

Dennis went cross-country skiing for 6 hours on Saturday. He skied 20 mile uphill and then 20 miles back downhill, returning to his starting point. His uphill speed was 5 mph slower than his downhil

**Answer**

Dennis's uphill speed was 10 mph and his downhill speed was 5 mph.

**Exercise 2.7.3.12**

Joon drove 4 hours to his home, driving 208 miles on the interstate and 40 miles on country roads. If he drove 15 mph faster on the interstate than on the country roads, what was his rate on the countr

**Answer**

Joon's rate on the country roads is 50 mph.


Once again, we will use the uniform motion formula solved for the variable $t$.

**Example 2.7.3.7**

Hamilton rode his bike downhill 12 miles on the river trail from his house to the ocean and then rode uphill to return home. His uphill speed was 8 miles per hour slower than his downhill speed. It too

**Solution**

This is a uniform motion situation. A diagram will help us visualize the situation.




We fill in the chart to organize the information.

We are looking for Hamilton's downhill speed. Let $h$= Hamilton's downhill speed.

His uphill speed is 8 miles per hour slower. $h-8$ = Hamilton's uphill speed.

Enter the rates into the chart.

The distance is the same in both directions: 12 miles.

Since $D=r\cdot t$, we solve for $t$ and get $t=\frac{D}{r}$. We divide the distance by the rate in each row, and place the expression in the time column.

| | Rate · Time = Distance | | |
|---|---|---|---|
| Downhill | $h$ | $\frac{12}{h}$ | 12 |
| Uphill | $h-8$ | $\frac{12}{h-8}$ | 12 |

Write a word sentence about the line: He took 2 hours longer uphill than downhill. The uphill time is 2 more than the downhill time.

Translate the sentence to get the equation.

$$\frac{12}{h-8}=\frac{12}{h}+2$$

Solve.

$$\begin{aligned} h(h-8)\left(\frac{12}{h-8}\right) &= h(h-8)\left(\frac{12}{h}+2\right) \\ 12h &= 12(h-8)+2h(h-8) \\ 12h &= 12h-96+2h^2-16h \\ 0 &= 2h^2-16h-96 \\ 0 &= 2\left(h^2-8h-48\right) \\ 0 &= 2(h-12)(h+4) \end{aligned}$$

$$\begin{aligned} h-12=0 \quad & \quad h+4=0 \\ h=12 \quad & \quad h=\cancel{-4} \end{aligned}$$

Check. Is 12mph a reasonable speed for biking downhill? Yes.

$$\text{Downhill } 12\text{mph} \quad \frac{12 \text{ miles}}{12\text{mph}}=1 \text{ hour}$$

$$\text{Uphill } 12-8=4\text{mph} \quad \frac{12 \text{ miles}}{4\text{mph}}=3 \text{ hours}$$

The uphill time is 2 hours more that the downhill time.

Hamilton's downhill speed is 12mph.

**? Exercise 2.7.3.13**

Kayla rode her bike 75 miles home from college one weekend and then rode the bus back to college. It took her 2 hours less to ride back to college on the bus than it took her to ride home on her bike,

**Answer**

Kayla's biking speed was 15 mph.

**? Exercise 2.7.3.14**

Victoria jogs 12 miles to the park along a flat trail and then returns by jogging on an 20 mile hilly trail. She jogs 1 mile per hour slower on the hilly trail than on the flat trail, and her return trip takes h

**Answer**

Victoria jogged 6 mph on the flat trail.

## Solve Work Applications

The weekly gossip magazine has a big story about the Princess' baby and the editor wants the magazine to be printed as soon as possible. She has asked the printer to run an extra printing press to get the

This is a typical 'work' application. There are three quantities involved here—the time it would take each of the two presses to do the job alone and the time it would take for them to do the job together.

If Press #1 can complete the job in 6 hours, in one hour it would complete $\frac{1}{6}$ of the job.

If Press #2 can complete the job in 12 hours, in one hour it would complete $\frac{1}{12}$ of the job.

We will let $t$ be the number of hours it would take the presses to print the magazines with both presses running together. So in 1 hour working together they have completed $\frac{1}{t}$ of the job.

We can model this with the word equation and then translate to a rational equation. To find the time it would take the presses to complete the job if they worked together, we solve for $t$.

Follow the steps to organize the information. We are looking for how many hours it would take to complete the job with both presses running together.

**Step 1**: Let $t$ = the number of hours needed to complete the job together.

**Step 2**: Enter the hours per job for Press #1, Press #2, and when they work together.

If a job on Press #1 takes 6 hours, then in 1 hour $\frac{1}{6}$ of the job is completed.

Similarly find the part of the job completed/hours for Press #2 and when they both together.

| | Number of hours to complete the job. | Part of job completed/hour |
|---|---|---|
| Press #1 | 6 | $\frac{1}{6}$ |
| Press #2 | 12 | $\frac{1}{12}$ |
| Together | $t$ | $\frac{1}{t}$ |

Write a word sentence. The part completed by Press #1 plus the part completed by Press #2 equals the amount completed together.

**Step 3**: Translate into an equation.

$$\underbrace{\text{Press \#1} + \text{Press \#2} = \text{Together}}_{\text{Work completed by}}$$

$$\frac{1}{6} + \frac{1}{12} = \frac{1}{t}$$

**Step 4**: Solve. Simplify.

$$\frac{1}{6} + \frac{1}{12} = \frac{1}{t}$$

Multiply by the LCD, $12t$ and simplify.

$$12t\left(\frac{1}{6} + \frac{1}{12}\right) = 12t\left(\frac{1}{t}\right)$$
$$2t + t = 12$$
$$3t = 12$$
$$t = 4$$

When both presses are running it takes 4 hours to do the job.

Keep in mind, it should take less time for two presses to complete a job working together than for either press to do it alone.

**✓ Example 2.7.3.8**

Suppose Pete can paint a room in 10 hours. If he works at a steady pace, in 1 hour he would paint $\frac{1}{10}$ of the room. If Alicia would take 8 hours to paint the same room, then in 1 hour she would paint

**Solution**

This is a 'work' application. The steps below will help us organize the information. We are looking for the numbers of hours it will take them to paint the room together.

In one hour Pete did $\frac{1}{10}$ of the job. Alicia did $\frac{1}{8}$ of the job. And together they did $\frac{1}{t}$ of the job.

**Step 1**: Let $t$ be the number of hours needed to paint the room together.

**Step 2**: Enter the hours per job for Pete, Alicia, and when they work together. In 1 hour working together, they have completed $\frac{1}{t}$ of the job. Similarly, find the part of the job completed/hour by Pete a

| | Number of hours to complete the job. | Part of job completed/hour |
|---|---|---|

| | Number of hours to complete the job. | Part of job completed/hour |
|---|---|---|
| Pete | 10 | $\frac{1}{10}$ |
| Alicia | 8 | $\frac{1}{8}$ |
| Together | $t$ | $\frac{1}{t}$ |

Write a word sentence. The work completed by Pete plus the work completed by Alicia equals the total work completed.

**Step 3**: Translate into an equation.

$$\underbrace{\text{Work completed by Pete} + \text{Alicia}}_{\frac{1}{10} \quad + \quad \frac{1}{8}} = \text{Together} \quad = \quad \frac{1}{t}$$

**Step 4**: Simplify. Solve.

Multiply by the LCD, $40t$.

$$40t\left(\frac{1}{10}+\frac{1}{8}\right)=40t\left(\frac{1}{t}\right)$$

Distribute.

$$40t\cdot\frac{1}{10}+40t\cdot\frac{1}{8}=40t\left(\frac{1}{t}\right)$$

Simplify and solve.

$$\begin{aligned} 4t+5t &= 40 \\ 9t &= 40 \\ t &= \frac{40}{9} \end{aligned}$$

We'll write as a mixed number so that we can convert it to hours and minutes.

$$t = 4\frac{4}{9} \text{ hours}$$

Remember, 1 hour = 60 minutes.

$$t = 4 \text{ hours } + \frac{4}{9}(60 \text{ minutes})$$

Multiply, and then round to the nearest minute.

$$t = 4 \text{ hours } + 27 \text{ minutes}$$

It would take Pete and Alica about 4 hours and 27 minutes to paint the room.

**? Exercise 2.7.3.15**

One gardener can mow a golf course in 4 hours, while another gardener can mow the same golf course in 6 hours. How long would it take if the two gardeners worked together to mow the golf course?

**Answer**

When the two gardeners work together it takes 2 hours and 24 minutes.

**? Exercise 2.7.3.16**

Daria can weed the garden in 7 hours, while her mother can do it in 3. How long will it take the two of them working together?

**Answer**

When Daria and her mother work together it takes 2 hours and 6 minutes.

**✓ Example 2.7.3.9**

Ra'shon can clean the house in 7 hours. When his sister helps him it takes 3 hours. How long does it take his sister when she cleans the house alone?

**Solution**

This is a work problem. The steps below will help us organize the information. We are looking for how many hours it would take Ra'shon's sister to complete the job by herself.

**Step 1**: Let $s$ be the number of hours Ra'shon's sister takes to clean the house alone.

**Step 2**: Enter the hours per job for Ra'shon, his sister, and when they work together. If Ra'shon takes 7 hours, then in 1 hour $\frac{1}{s}$ of the job is completed. If Ra'shon's sister takes $s$ hours, then in 1 hour

| | Number of hours to complete the job. | Part of job completed/hour |
|---|---|---|
| Ra'shon | 7 | $\frac{1}{7}$ |
| His sister | $s$ | $\frac{1}{s}$ |
| Together | 3 | $\frac{1}{3}$ |

Write a word sentence. The part completed by Ra'shon plus the part by his sister equals the amount completed together.

**Step 3**: Translate to an equation.

$$\underbrace{\text{Ra'shon} + \text{His sister} = \text{Together}}_{\text{Work completed by}}$$
$$\frac{1}{7} + \frac{1}{s} = \frac{1}{3}$$

**Step 4**: Simplify. Solve.

$$\frac{1}{7}+\frac{1}{5}=\frac{1}{3}$$

Multiply by the LCD, 21s.

$$21s\left(\frac{1}{7}+\frac{1}{s}\right)=\left(\frac{1}{3}\right)21s$$
$$3s+21=7s$$

Simplify.

$$-4s=-21$$
$$s=\frac{-21}{-4}=\frac{21}{4}$$

Write as a mixed number to convert it to hours and minutes.

$$s=5\frac{1}{4}\text{ hours}$$

There are 60 minutes in 1 hour.

$$s=5\text{ hours}+\frac{1}{4}(60\text{ minutes})$$
$$s=5\text{ hours}+15\text{ minutes}$$

It would take Ra'shon's sister 5 hours and 15 minutes to clean the house alone.

**Exercise 2.7.3.17**

Alice can paint a room in 6 hours. If Kristina helps her it takes them 4 hours to paint the room. How long would it take Kristina to paint the room by herself?

**Answer**

Kristina can paint the room in 12 hours.

**Exercise 2.7.3.18**

Tracy can lay a slab of concrete in 3 hours, with Jordan's help they can do it in 2 hours. If Jordan works alone, how long will it take?

**Answer**

It will take Jordan 6 hours.

## Solve Direct Variation Problems

When two quantities are related by a proportion, we say they are proportional to each other. Another way to express this relation is to talk about the variation of the two quantities. We will discuss direct

Lindsay gets paid $15 per hour at her job. If we let $s$ be her salary and h be the number of hours she has worked, we could model this situation with the equation

$$s=15h$$

Lindsay's salary is the product of a constant, 15, and the number of hours she works. We say that Lindsay's salary varies directly with the number of hours she works. Two variables vary directly if one is

**Direct Variation**

For any two variables $x$ and $y$, $y$ varies directly with $x$ if

$$y=kx\text{, where } k\neq 0$$

The constant $k$ is called the constant of variation.

In applications using direct variation, generally we will know values of one pair of the variables and will be asked to find the equation that relates $x$ and $y$. Then we can use that equation to find values o

We'll list the steps here.

**How to Solve direct variation problems**

**Step 1**. Write the formula for direct variation.

**Step 2**. Substitute the given values for the variables.

**Step 3**. Solve for the constant of variation.

**Step 4**. Write the equation that relates $x$ and $y$ using the constant of variation.

Now we'll solve an application of direct variation.

**Example 2.7.3.10**

When Raoul runs on the treadmill at the gym, the number of calories, $c$, he burns varies directly with the number of minutes, $m$, he uses the treadmill. He burned 315 calories when he used the treadm

a. Write the equation that relates $c$ and $m$.
b. How many calories would he burn if he ran on the treadmill for 25 minutes?

**Solution**

a.

The number of calories, $c$, varies directly with the number of minutes, $m$, on the treadmill, and $c = 315$ when $m = 18$.

Write the formula for direct variation.

$$y = kx$$

We will use $c$ in place of $y$ and $m$ in place of $x$.

$$c = km$$

Substitute the given values for the variables.

$$315 = k \cdot 18$$

Solve for the constant of variation.

$$\frac{315}{18} = \frac{k \cdot 18}{18}$$
$$17.5 = k$$

Write the equation that relates $c$ and $m$.

$$c = km$$

Substitute in the constant of variation.

$$c = 17.5m$$

b.

Find $c$ when $m = 25$.

Write the equation that relates $c$ and $m$.

$$c = 17.5m$$

Substitute the given value for $m$.

$$c = 17.5(25)$$

Simplify.

$$c = 437.5$$

Raoul would burn 437.5 calories if he used the treadmill for 25 minutes.

**?** Exercise **2.7.3.19**

The number of calories, $c$, burned varies directly with the amount of time, $t$, spent exercising. Arnold burned 312 calories in 65 minutes exercising.

a. Write the equation that relates $c$ and $t$.
b. How many calories would he burn if he exercises for 90 minutes?

**Answer**

a. $c = 4.8t$
b. He would burn 432 calories.

**?** Exercise **2.7.3.20**

The distance a moving body travels, $d$, varies directly with time, $t$, it moves. A train travels 100 miles in 2 hours.

a. Write the equation that relates $d$ and $t$.
b. How many miles would it travel in 5 hours?

**Answer**

a. $d = 50t$
b. It would travel 250 miles.

## Solve Inverse Variation Problems

Many applications involve two variable that vary inversely. As one variable increases, the other decreases. The equation that relates them is $y = \frac{k}{x}$.

**Inverse Variation**

For any two variables $x$ and $y$, $y$ varies inversely with $x$ if

$$y = \frac{k}{x}, \text{ where } k \neq 0$$

The constant $k$ is called the constant of variation.

The word ‘inverse’ in inverse variation refers to the multiplicative inverse. The multiplicative inverse of $x$ is $\frac{1}{x}$.

We solve inverse variation problems in the same way we solved direct variation problems. Only the general form of the equation has changed. We will copy the procedure box here and just change ‘direc

**how to Solve inverse variation problems**

**Step 1**. Write the formula for inverse variation.

**Step 2**. Substitute the given values for the variables.

**Step 3**. Solve for the constant of variation.

**Step 4**. Write the equation that relates $x$ and $y$ using the constant of variation.

**Example 2.7.3.11**

The frequency of a guitar string varies inversely with its length. A 26 in.-long string has a frequency of 440 vibrations per second.

a. Write the equation of variation.
b. How many vibrations per second will there be if the string's length is reduced to 20 inches by putting a finger on a fret?

**Solution**

a.

The frequency varies inversely with the length.

Name the variables. Let $f$ = frequency. $L$ = length

Write the formula for inverse variation.

$$y = \frac{k}{x}$$

We will use $f$ in place of $y$ and $L$ in place of $x$.

$$f = \frac{k}{L}$$

$$f = 440 \text{ when } L = 26$$

Substitute the given values for the variables.

$$440 = \frac{k}{26}$$

Solve for the constant of variation.

$$26(440) = 26\left(\frac{k}{26}\right)$$

$$11,440 = k$$

Write the equation that relates $f$ and $L$.

$$f = \frac{k}{L}$$

Substitute the constant of variation.

$$f = \frac{11,440}{L}$$

b.

Find $f$ when $L = 20$.

Write the equation that relates $f$ and $L$.

$$f = \frac{11,440}{L}$$

Substitute the given value forL.

$$f = \frac{11,440}{20}$$

Simplify.

$$f = 572$$

A 20"-guitar string has frequency 572 vibrations per second.

**Exercise 2.7.3.21**

The number of hours it takes for ice to melt varies inversely with the air temperature. Suppose a block of ice melts in 2 hours when the temperature is 65 degrees Celsius.

a. Write the equation of variation.
b. How many hours would it take for the same block of ice to melt if the temperature was 78 degrees?

**Answer**

a. $h = \frac{130}{t}$
b. $1\frac{2}{3}$ hours

**Exercise 2.7.3.22**

Xander's new business found that the daily demand for its product was inversely proportional to the price, $p$. When the price is \$5, the demand is 700 units.

a. Write the equation of variation.
b. What is the demand if the price is raised to \$7?

**Answer**

a. $x = \frac{3500}{p}$
b. 500 units

## Media Access Additional Online Resources

Access this online resource for additional instruction and practice with applications of rational expressions

- Applications of Rational Expressions

This page titled 2.7.3: Solve Applications with Rational Equations is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **7.6: Solve Applications with Rational Equations** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/intermediate-algebra-2e.

# 2.7.3E: Exercises

## Solve Proportions

**In the following exercises, solve each proportion.**

1. $\frac{x}{56}=\frac{7}{8}$

**Answer**

$x=49$

2. $\frac{56}{72}=\frac{y}{9}$

3. $\frac{98}{154}=\frac{-7}{p}$

**Answer**

$p=-11$

4. $\frac{72}{156}=\frac{-6}{q}$

5. $\frac{a}{a+12}=\frac{4}{7}$

**Answer**

$a=16$

6. $\frac{b}{b-16}=\frac{11}{9}$

7. $\frac{m+90}{25}=\frac{m+30}{15}$

**Answer**

$m=60$

8. $\frac{n+10}{4}=\frac{40-n}{6}$

9. $\frac{2p+4}{8}=\frac{p+18}{6}$

**Answer**

$p=30$

10. $\frac{q-2}{2}=\frac{2q-7}{18}$

**In the following exercises, solve.**

11. Kevin wants to keep his heart rate at 160 beats per minute while training. During his workout he counts 27 beats in 10 seconds.

a. How many beats per minute is this?
b. Has Kevin met his target heart rate?

**Answer**

a. 162 beats per minute
b. yes

12. Jesse's car gets 30 miles per gallon of gas.
    a. If Las Vegas is 285 miles away, how many gallons of gas are needed to get there and then home?
    b. If gas is $3.09 per gallon, what is the total cost of the gas for the trip?
13. Pediatricians prescribe 5 milliliters (ml) of acetaminophen for every 25 pounds of a child's weight. How many milliliters of acetaminophen will the doctor prescribe for Jocelyn, who weighs 45 pounds?

**Answer**

9 ml

14. A veterinarian prescribed Sunny, a 65-pound dog, an antibacterial medicine in case an infection emerges after her teeth were cleaned. If the dosage is 5 mg for every pound, how much medicine was Sunny given?
15. A new energy drink advertises 106 calories for 8 ounces. How many calories are in 12 ounces of the drink?

**Answer**

159 calories

16. One 12-ounce can of soda has 150 calories. If Josiah drinks the big 32-ounce size from the local mini-mart, how many calories does he get?
17. Kyra is traveling to Canada and will change $250 US dollars into Canadian dollars. At the current exchange rate, $1 US is equal to $1.3 Canadian. How many Canadian dollars will she get for her trip?

**Answer**

325 Canadian Dollars

18. Maurice is traveling to Mexico and needs to exchange $450 into Mexican pesos. If each dollar is worth 12.29 pesos, how many pesos will he get for his trip?
19. Ronald needs a morning breakfast drink that will give him at least 390 calories. Orange juice has 130 calories in one cup. How many cups does he need to drink to reach his calorie goal?

**Answer**

3 cups

20. Sonya drinks a 32-ounce energy drink containing 80 calories per 12 ounce. How many calories did she drink?
21. Phil wants to fertilize his lawn. Each bag of fertilizer covers about 4,000 square feet of lawn. Phil's lawn is approximately 13,500 square feet. How many bags of fertilizer will he have to buy?

**Answer**


4 bags

22. An oatmeal cookie recipe calls for $\frac{1}{2}$ cup of butter to make 4 dozen cookies. Hilda needs to make 10 dozen cookies for the bake sale. How many cups of butter will she need?

## Solve Similar Figure Applications

**In the following exercises, the triangles are similar. Find the length of the indicated side.**

23.





a. side x
b. side b

**Answer**


a. 6
b. 12

24.




a. side d
b. side q

**In the following exercises, use the map shown. On the map, New York City, Chicago, and Memphis form a triangle. The actual distance from New York to Chicago is 800 miles.**





25. Find the actual distance from New York to Memphis.

**Answer**

950 miles

26. Find the actual distance from Chicago to Memphis.

**In the following exercises, use the map shown. On the map, Atlanta, Miami, and New Orleans form a triangle. The actual distance from Atlanta to New Orleans is 420 miles.**



27. Find the actual distance from New Orleans to Miami.

**Answer**

680 miles

28. Find the actual distance from Atlanta to Miami.

**In the following exercises, answer each question.**

29. A 2-foot-tall dog casts a 3-foot shadow at the same time a cat casts a one foot shadow. How tall is the cat?

**Answer**

$\frac{2}{3}$ foot (8 in.)

30. Larry and Tom were standing next to each other in the backyard when Tom challenged Larry to guess how tall he was. Larry knew his own height is 6.5 feet and when they measured their shadows, Larry's shadow was 8 feet and Tom's was 7.75 feet long. What is Tom's height?
31. The tower portion of a windmill is 212 feet tall. A six foot tall person standing next to the tower casts a seven-foot shadow. How long is the windmill's shadow?

**Answer**

247.3 feet

32. The height of the Statue of Liberty is 305 feet. Nikia, who is standing next to the statue, casts a 6-foot shadow and she is 5 feet tall. How long should the shadow of the statue be?

## Solve Uniform Motion Applications

**In the following exercises, solve the application problem provided.**

33. Mary takes a sightseeing tour on a helicopter that can fly 450 miles against a 35-mph headwind in the same amount of time it can travel 702 miles with a 35-mph tailwind. Find the speed of the helicopter.

**Answer**

160 mph

34. A private jet can fly 1,210 miles against a 25-mph headwind in the same amount of time it can fly 1694 miles with a 25-mph tailwind. Find the speed of the jet.
35. A boat travels 140 miles downstream in the same time as it travels 92 miles upstream. The speed of the current is 6mph. What is the speed of the boat?

**Answer**

29 mph

36. Darrin can skateboard 2 miles against a 4-mph wind in the same amount of time he skateboards 6 miles with a 4-mph wind. Find the speed Darrin skateboards with no wind.
37. Jane spent 2 hours exploring a mountain with a dirt bike. First, she rode 40 miles uphill. After she reached the peak she rode for 12 miles along the summit. While going uphill, she went 5 mph slower than when she was on the summit. What was her rate along the summit?

**Answer**

30 mph

38. Laney wanted to lose some weight so she planned a day of exercising. She spent a total of 2 hours riding her bike and jogging. She biked for 12 miles and jogged for 6 miles. Her rate for jogging was 10 mph less than biking rate. What was her rate when jogging?

39. Byron wanted to try out different water craft. He went 62 miles downstream in a motor boat and 27 miles downstream on a jet ski. His speed on the jet ski was 10 mph faster than in the motor boat. Bill spent a total of 4 hours on the water. What was his rate of speed in the motor boat?

**Answer**

20 mph

40. Nancy took a 3-hour drive. She went 50 miles before she got caught in a storm. Then she drove 68 miles at 9 mph less than she had driven when the weather was good. What was her speed driving in the storm?
41. Chester rode his bike uphill 24 miles and then back downhill at 2 mph faster than his uphill. If it took him 2 hours longer to ride uphill than downhill, what was his uphill rate?

**Answer**

4 mph

42. Matthew jogged to his friend's house 12 miles away and then got a ride back home. It took him 2 hours longer to jog there than ride back. His jogging rate was 25 mph slower than the rate when he was riding. What was his jogging rate?
43. Hudson travels 1080 miles in a jet and then 240 miles by car to get to a business meeting. The jet goes 300 mph faster than the rate of the car, and the car ride takes 1 hour longer than the jet. What is the speed of the car?

**Answer**

60 mph

44. Nathan walked on an asphalt pathway for 12 miles. He walked the 12 miles back to his car on a gravel road through the forest. On the asphalt he walked 2 miles per hour faster than on the gravel. The walk on the gravel took one hour longer than the walk on the asphalt. How fast did he walk on the gravel.
45. John can fly his airplane 2800 miles with a wind speed of 50 mph in the same time he can travel 2400 miles against the wind. If the speed of the wind is 50 mph, find the speed of his airplane.

**Answer**

650 mph

46. Jim's speedboat can travel 20 miles upstream against a 3-mph current in the same amount of time it travels 22 miles downstream with a 3-mph current speed . Find the speed of the Jim's boat.
47. Hazel needs to get to her granddaughter's house by taking an airplane and a rental car. She travels 900 miles by plane and 250 miles by car. The plane travels 250 mph faster than the car. If she drives the rental car for 2 hours more than she rode the plane, find the speed of the car.

**Answer**

50 mph

48. Stu trained for 3 hours yesterday. He ran 14 miles and then biked 40 miles. His biking speed is 6 mph faster than his running speed. What is his running speed?
49. When driving the 9-hour trip home, Sharon drove 390 miles on the interstate and 150 miles on country roads. Her speed on the interstate was 15 more than on country roads. What was her speed on country roads?

**Answer**

50 mph

50. Two sisters like to compete on their bike rides. Tamara can go 4 mph faster than her sister, Samantha. If it takes Samantha 1 hours longer than Tamara to go 80 miles, how fast can Samantha ride her bike?
51. Dana enjoys taking her dog for a walk, but sometimes her dog gets away, and she has to run after him. Dana walked her dog for 7 miles but then had to run for 1 mile, spending a total time of 2.5 hours with her dog. Her running speed was 3 mph faster than her walking speed. Find her walking speed.

**Answer**

4.2 mph

52. Ken and Joe leave their apartment to go to a football game 45 miles away. Ken drives his car 30 mph faster Joe can ride his bike. If it takes Joe 2 hours longer than Ken to get to the game, what is Joe's speed?

## Solve Work Applications

53. Mike, an experienced bricklayer, can build a wall in 3 hours, while his son, who is learning, can do the job in 6 hours. How long does it take for them to build a wall together?

**Answer**

2 hours

54. It takes Sam 4 hours to rake the front lawn while his brother, Dave, can rake the lawn in 2 hours. How long will it take them to rake the lawn working together?
55. Mia can clean her apartment in 6 hours while her roommate can clean the apartment in 5 hours. If they work together, how long would it take them to clean the apartment?

**Answer**

2 hours and 44 minutes

56. Brian can lay a slab of concrete in 6 hours, while Greg can do it in 4 hours. If Brian and Greg work together, how long will it take?
57. Josephine can correct her students test papers in 5 hours, but if her teacher's assistant helps, it would take them 3 hours. How long would it take the assistant to do it alone?

**Answer**

7 hours and 30 minutes

58. Washing his dad's car alone, eight year old Levi takes 2.5 hours. If his dad helps him, then it takes 1 hour. How long does it take Levi's dad to wash the car by himself?
59. At the end of the day Dodie can clean her hair salon in 15 minutes. Ann, who works with her, can clean the salon in 30 minutes. How long would it take them to clean the shop if they work together?

**Answer**

10 min

60. Ronald can shovel the driveway in 4 hours, but if his brother Donald helps it would take 2 hours. How long would it take Donald to shovel the driveway alone?

## Solve Direct Variation Problems

**In the following exercises, solve.**

61. If $y$ varies directly as $x$ and $y = 14$, when $x = 3$. Find the equation that relates $x$ and $y$.

**Answer**

$y = \frac{14}{3}x$

62. If $a$ varies directly as $b$ and $a = 16$, when $b = 4$. Find the equation that relates $a$ and $b$.
63. If $p$ varies directly as $q$ and $p = 9$, when $q = 3$. Find the equation that relates $p$ and $q$.

**Answer**

$p = 3.2q$

64. If $v$ varies directly as $w$ and $v = 8$, when $w = 12$. Find the equation that relates $v$ and $w$.
65. The price, $P$, that Eric pays for gas varies directly with the number of gallons, $g$, he buys. It costs him \$50 to buy 20 gallons of gas.
    a. Write the equation that relates $P$ and $g$.
    b. How much would 33 gallons cost Eric?

**Answer**

a. $P = 2.5g$
b. $\$82.50$

66. Joseph is traveling on a road trip. The distance, $d$, he travels before stopping for lunch varies directly with the speed, $v$, he travels. He can travel 120 miles at a speed of 60 mph.
    a. Write the equation that relates $d$ and $v$.
    b. How far would he travel before stopping for lunch at a rate of 65 mph?
67. The mass of a liquid varies directly with its volume. A liquid with mass 16 kilograms has a volume of 2 liters.
    a. Write the equation that relates the mass to the volume.
    b. What is the volume of this liquid if its mass is 128 kilograms?

**Answer**

a. $m = 8v$
b. 16 liters

68. The length that a spring stretches varies directly with a weight placed at the end of the spring. When Sarah placed a 10-pound watermelon on a hanging scale, the spring stretched 5 inches.
    a. Write the equation that relates the length of the spring to the weight.
    b. What weight of watermelon would stretch the spring 6 inches?
69. The maximum load a beam will support varies directly with the square of the diagonal of the beam's cross-section. A beam with diagonal 6 inch will support a maximum load of 108 pounds.
    a. Write the equation that relates the load to the diagonal of the cross-section.
    b. What load will a beam with a 10-inch diagonal support?

**Answer**

a. $L = 3d^2$
b. 300 pounds

70. The area of a circle varies directly as the square of the radius. A circular pizza with a radius of 6 inches has an area of 113.04 square inches.
    a. Write the equation that relates the area to the radius.
    b. What is the area of a personal pizza with a radius 4 inches?

## Solve Inverse Variation Problems

**In the following exercises, solve.**

71. If $y$ varies inversely with $x$ and $y = 5$, when $x = 4$. Find the equation that relates $x$ and $y$.

**Answer**

$$y = \frac{20}{x}$$

72. If $p$ varies inversely with $q$ and $p = 2$, when $q = 1$. Find the equation that relates $p$ and $q$.
73. If $v$ varies inversely with $w$ and $v = 6$, when $w = 12$. Find the equation that relates $v$ and $w$.

**Answer**

$v = \frac{3}{w}$

74. If $a$ varies inversely with $b$ and $a = 12$, when $b = 13$. Find the equation that relates $a$ and $b$.

**In the following exercises, write an inverse variation equation to solve the following problems.**

75. The fuel consumption (mpg) of a car varies inversely with its weight. A Toyota Corolla weighs 2800 pounds getting 33 mpg on the highway.
    a. Write the equation that relates the mpg to the car's weight.
    b. What would the fuel consumption be for a Toyota Sequoia that weighs 5500 pounds?

**Answer**

a. $g = \frac{92,400}{w}$
b. 16.8 mpg

76. A car's value varies inversely with its age. Jackie bought a 10-year-old car for $2,400.
    a. Write the equation that relates the car's value to its age.
    b. What will be the value of Jackie's car when it is 15 years old?

77. The time required to empty a tank varies inversely as the rate of pumping. It took Ada 5 hours to pump her flooded basement using a pump that was rated at 200 gpm (gallons per minute).
    a. Write the equation that relates the number of hours to the pump rate.
    b. How long would it take Ada to pump her basement if she used a pump rated at 400 gpm?

**Answer**

1. $t = \frac{1000}{r}$
2. 2.5 hours

78. On a string instrument, the length of a string varies inversely as the frequency of its vibrations. An 11-inch string on a violin has a frequency of 400 cycles per second.
    a. Write the equation that relates the string length to its frequency.
    b. What is the frequency of a 10 inch string?

79. Paul, a dentist, determined that the number of cavities that develops in his patient's mouth each year varies inversely to the number of minutes spent brushing each night. His patient, Lori, had four cavities when brushing her teeth 30 seconds (0.5 minutes) each night.
    a. Write the equation that relates the number of cavities to the time spent brushing.
    b. How many cavities would Paul expect Lori to have if she had brushed her teeth for 2 minutes each night?

**Answer**

a. $c = \frac{2}{t}$
b. 1 cavity

80. Boyle's law states that if the temperature of a gas stays constant, then the pressure varies inversely to the volume of the gas. Braydon, a scuba diver, has a tank that holds 6 liters of air under a pressure of 220 psi.
    a. Write the equation that relates pressure to volume.
    b. If the pressure increases to 330 psi, how much air can Braydon's tank hold?

81. The cost of a ride service varies directly with the distance traveled. It costs $35 for a ride from the city center to the airport, 14 miles away.
    a. Write the equation that relates the cost, $c$, with the number of miles, $m$.
    b. What would it cost to travel 22 miles with this service?

**Answer**

a. $c = 2.5m$
b. $\$55$

82. The number of hours it takes Jack to drive from Boston to Bangor is inversely proportional to his average driving speed. When he drives at an average speed of 40 miles per hour, it takes him 6 hours for the trip.
    a. Write the equation that relates the number of hours, $h$, with the speed, $s$.
    b. How long would the trip take if his average speed was 75 miles per hour?

## Writing Exercises

83. Marisol solves the proportion $\frac{144}{a} = \frac{9}{4}$ by 'cross multiplying,' so her first step looks like $4 \cdot 144 = 9 \cdot a$. Explain how this differs from the method of solution shown in Example 7.6.2.

**Answer**

Answers will vary.

84. Paula and Yuki are roommates. It takes Paula 3 hours to clean their apartment. It takes Yuki 4 hours to clean the apartment. The equation $\frac{1}{3} + \frac{1}{4} = \frac{1}{t}$ can be used to find $t$, the number of hours it would take both of them, working together, to clean their apartment. Explain how this equation models the situation.
85. In your own words, explain the difference between direct variation and inverse variation.

**Answer**

Answers will vary.


86. Make up an example from your life experience of inverse variation.

---

This page titled 2.7.3E: Exercises is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **7.6E: Exercises** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/intermediate-algebra-2e.

# 2.8: Linear and Absolute Value Inequalities




When the goal is to get a result that is within an certain interval, less than some maximum value or greater than some minimum value, we need to setup and solve an inequality instead of an equation. In this section you will review:

- Linear Inequalities
- Absolute Value Inequalities

Later on in this text, you will review polynomial and rational inequalities, along with their applications.

2.8: Linear and Absolute Value Inequalities is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

# 2.8.1: Linear Inequalities

**Learning Objectives**

- Use interval notation.
- Use properties of inequalities.
- Solve inequalities in one variable algebraically.
- Solve absolute value inequalities.

It is not easy to make the honor role at most top universities. Suppose students were required to carry a course load of at least $12$ credit hours and maintain a grade point average of $3.5$ or above. How could these honor roll requirements be expressed mathematically? In this section, we will explore various ways to express different sets of numbers, inequalities, and absolute value inequalities.



Figure 2.8.1.1

## Using Interval Notation

Indicating the solution to an inequality such as $x \geq 4$ can be achieved in several ways.

- We can use a number line as shown in Figure $2.8.1.2$ The blue ray begins at $x = 4$ and, as indicated by the arrowhead, continues to infinity, which illustrates that the solution set includes all real numbers greater than or equal to $4$.
- We can use **set-builder notation**: $\{x | x \geq 4\}$, which translates to "all real numbers $x$ such that $x$ is greater than or equal to $4$." Notice that braces are used to indicate a set.
- The third method is **interval notation**, in which solution sets are indicated with parentheses or brackets. The solutions to $x \geq 4$ are represented as $[4, \infty)$. This is perhaps the most useful method, as it applies to concepts studied later in this course and to other higher-level math courses.





Figure 2.8.1.2

The main concept to remember is that parentheses represent solutions greater or less than the number, and brackets represent solutions that are greater than or equal to or less than or equal to the number. Use parentheses to represent infinity or negative infinity, since positive and negative infinity are not numbers in the usual sense of the word and, therefore, cannot be "equaled." A few examples of an interval, or a set of numbers in which a solution falls, are $[-2, 6)$, or all numbers between $-2$ and $6$, including $-2$, but not including $6$; $(-1, 0)$, all real numbers between, but not including $-1$ and $0$; and $(-\infty, 1]$, all real numbers less than and including $1$. Table $2.8.1.1$outlines the possibilities.

a}; (a , infinity). The entries in the fourth row are: All real numbers less than b, but not including b; {x| x < b}; (negative infinity, b). The entries in the fifth row are: All real numbers greater than a, including a; {x| x a}; [a, infinity). The entries in the sixth row are: All real numbers less than b, including b; {x| x b}; (negative infinity, b]. The entries in the seventh row are: All real numbers between a and b, including a; {x| a x < b}; [a, b). The entries in the eighth row are: All real numbers between a and b, including b; {x| a < x b}; (a, b]. The entries in the ninth row are: All real numbers between a and b, including a and b; {x| a x b}; [a, b]. The entries in the tenth row are: all real numbers less than a and greater than b; {x| x < a and x > b}; (negative infinity, a) union (b, infinity). The entries in the eleventh row are: All real numbers; {x| x is all real numbers}; (negative infinity, infinity).">

Table 2.8.1.1

| Set Indicated | Set-Builder Notation | Interval Notation |
|---|---|---|
| All real numbers between $a$ and $b$, but not including $a$ or $b$ | $\{x \mid a < x < b\}$ | $(a, b)$ |
| All real numbers greater than $a$, but not including $a$ | $\{x \mid x > a\}$ | $(a, \infty)$ |
| All real numbers less than $b$, but not including $b$ | $\{x \mid x < b\}$ | $(-\infty, b)$ |
| All real numbers greater than $a$, including $a$ | $\{x \mid x \geq a\}$ | $[a, \infty)$ |
| All real numbers less than $b$, including $b$ | $\{x \mid x \leq b\}$ | $(-\infty, b]$ |
| All real numbers between $a$ and $b$, including $a$ | $\{x \mid a \leq x < b\}$ | $[a, b)$ |
| All real numbers between $a$ and $b$, including $b$ | $\{x \mid a < x \leq b\}$ | $(a, b]$ |
| All real numbers between $a$ and $b$, including $a$ and $b$ | $\{x \mid a \leq x \leq b\}$ | $[a, b]$ |
| All real numbers less than $a$ or greater than $b$ | $\{x \mid x < a \; and \; x > b\}$ | $(-\infty, a) \cup (b, \infty)$ |
| All real numbers | $\{x \mid x \; is \; all \; real \; numbers\}$ | $(-\infty, \infty)$ |

### Example 2.8.1.1: Using Interval Notation to Express All Real Numbers Greater Than or Equal to a

Use interval notation to indicate all real numbers greater than or equal to $-2$.

**Solution**

Use a bracket on the left of $-2$ and parentheses after infinity: $[-2, \infty)$. The bracket indicates that $-2$ is included in the set with all real numbers greater than $-2$ to infinity.

### Try It! 2.8.1.1

Use interval notation to indicate all real numbers between and including $-3$ and $5$.

**Answer**

$[-3, 5]$

### Example 2.8.1.2: Using Interval Notation to Express All Real Numbers Less Than or Equal to a or Greater Than or Equal to b

Write the interval expressing all real numbers less than or equal to $-1$ or greater than or equal to $1$.

**Solution**

We have to write two intervals for this example. The first interval must indicate all real numbers less than or equal to $1$. So, this interval begins at $-\infty$ and ends at $-1$, which is written as $(-\infty, -1]$.

The second interval must show all real numbers greater than or equal to $1$, which is written as $[1, \infty)$. However, we want to combine these two sets. We accomplish this by inserting the union symbol, $\cup$, between the two intervals.

$$(-\infty, -1] \cup [1, \infty)$$

**Try It! 2.8.1.2**

Express all real numbers less than $-2$ or greater than or equal to $3$ in interval notation.

**Answer**

$(-\infty, -2) \cup [3, \infty)$

## Using the Properties of Inequalities

When we work with inequalities, we can usually treat them similarly to but not exactly as we treat equalities. We can use the **addition property** and the **multiplication property** to help us solve them. The one exception is when we multiply or divide by a negative number; doing so reverses the inequality symbol.

**PROPERTIES OF INEQUALITIES**

**Addition Property**

- If $a < b$, then $a + c < b + c$ .

**Multiplication Property**

- If $a < b$ and $c > 0$, then $ac < bc$.
- If $a < b$ and $c < 0$, then $ac > bc$.

These properties also apply to $a \leq b$, $a > b$, and $a \geq b$.

**Example 2.8.1.3: Demonstrating the Addition Property**

Illustrate the addition property for inequalities by solving each of the following:

a. (a) $x - 15 < 4$
b. (b) $6 \geq x - 1$
c. (c) $x + 7 > 9$

### Solution

The addition property for inequalities states that if an inequality exists, adding or subtracting the same number on both sides does not change the inequality.

a.

$$\begin{aligned} x - 15 &< 4 \\ x - 15 + 15 &< 4 + 15 \\ x &< 19 \end{aligned}$$

b.

$$\begin{aligned} 6 &\geq x - 1 \\ 6 + 1 &\geq x - 1 + 1 \\ 7 &\geq x \end{aligned}$$

c.

$$\begin{aligned} x + 7 &> 9 \\ x + 7 - 7 &> 9 - 7 \\ x &> 2 \end{aligned}$$

**Try It! 2.8.1.3**

Solve: $3x-2<1$.

**Answer**

$x<1$

**Example 2.8.1.4: Demonstrating the Multiplication Property**

Illustrate the multiplication property for inequalities by solving each of the following:

a. $3x<6$
b. $-2x-1\geq 5$
c. $5-x>10$

**Solution**

a.

$$\begin{aligned} 3x &< 6 \\ \frac{1}{3}(3x) &< (6)\frac{1}{3} \\ x &< 2 \end{aligned}$$

b.

$$\begin{aligned} -2x-1 &\geq 5 \\ -2x &\geq 6 \\ \left(-\frac{1}{2}\right)(-2) &\geq (6)\left(-\frac{1}{2}\right) && \text{Multiply by } \left(-\frac{1}{2}\right) \\ x &\leq -3 && \text{Reverse the inequality.} \end{aligned}$$

c.

$$\begin{aligned} 5-x &> 10 \\ -x &> 5 \\ (-1)(-x) &> (5)(-1) && \text{Multiply by } -1 \\ x &< -5 && \text{Reverse the inequality.} \end{aligned}$$

**Try It! 2.8.1.4**

Solve: $4x+7\geq 2x-3$.

**Answer**

$x\geq -5$

## Solving Inequalities in One Variable Algebraically

As the examples have shown, we can perform the same operations on both sides of an inequality, just as we do with equations; we combine like terms and perform operations. To solve, we isolate the variable.

**Example 2.8.1.5: Solving an Inequality Algebraically**

Solve the inequality: $13-7x\geq 10x-4$.

**Solution**

Solving this inequality is similar to solving an equation up until the last step.

$$\begin{aligned} 13-7x &\geq 10x-4 & \\ 13-17x &\geq -4 & \text{Move variable terms to one side of the inequality} \\ -17x &\geq -17 & \text{Isolate the variable term} \\ x &\leq 1 & \text{Dividing both sides by -17 reverses the inequality.} \end{aligned}$$

The solution set is given by the interval $(-\infty, 1]$, or all real numbers less than and including 1.

**Try It! 2.8.1.5**

Solve the inequality and write the answer using interval notation: $-x+4<\frac{1}{2}x+1$ .

**Answer**

$(2, \infty)$

**Example 2.8.1.6: Solving an Inequality with Fractions**

Solve the following inequality and write the answer in interval notation: $-\frac{3}{4}x \geq -\frac{5}{8}+\frac{2}{3}x$ .

**Solution**

We begin solving in the same way we do when solving an equation.

$$\begin{aligned} -\frac{3}{4}x &\geq -\frac{5}{8}+\frac{2}{3}x & \\ -\frac{3}{4}x-\frac{2}{3}x &\geq -\frac{5}{8} & \text{Put variable terms on one side.} \\ -\frac{9}{12}x-\frac{8}{12}x &\geq -\frac{5}{8} & \text{Write fractions with common denominator.} \\ -\frac{17}{12}x &\geq -\frac{5}{8} & \\ x &\leq -\frac{5}{8}\left(-\frac{12}{17}\right) & \text{Multiplying by a negative number reverses the inequality.} \\ x &\leq \frac{15}{34} & \end{aligned}$$

The solution set is the interval $\left(-\infty, \frac{15}{34}\right]$.

**Try It! 2.8.1.6**

Solve the inequality and write the answer in interval notation: $-\frac{5}{6}x \leq \frac{3}{4}+\frac{8}{3}x$ .

**Answer**

$\left[-\frac{3}{14}, \infty\right)$

## Understanding Compound Inequalities

A **compound inequality** includes two inequalities in one statement. A statement such as $4<x\leq 6$ means $4<x$ and $x\leq 6$. There are two ways to solve compound inequalities: separating them into two separate inequalities or leaving the compound inequality intact and performing operations on all three parts at the same time. We will illustrate both methods.

### Example 2.8.1.7: Solving a Compound Inequality

Solve the compound inequality: $3 \leq 2x+2 < 6$

**Solution**

The first method is to write two separate inequalities: $3 \leq 2x+2$ and $2x+2<6$. We solve them independently.

$$\begin{aligned} 3 &\leq 2x+2 \quad \text{and} \quad 2x+2<6 \\ 1 &\leq 2x \qquad\qquad\quad 2x<4 \\ \tfrac{1}{2} &\leq x \qquad\qquad\quad x<2 \end{aligned}$$

Then, we can rewrite the solution as a compound inequality, the same way the problem began.

$$\frac{1}{2} \leq x < 2$$

In interval notation, the solution is written as $[\frac{1}{2},\ 2)$.

The second method is to leave the compound inequality intact, and perform solving procedures on the three parts at the same time.

$$\begin{aligned} &3 \leq 2x+2 < 6 \\ &1 \leq 2x < 4 && \text{Isolate the variable term, and subtract 2 from all three parts.} \\ &\tfrac{1}{2} \leq x < 2 && \text{Divide through all three parts by 2.} \end{aligned}$$

We get the same solution: $[\frac{1}{2},\ 2)$.

### Try It! 2.8.1.7

Solve the compound inequality: $4 < 2x-8 \leq 10$.

**Answer**

$6 < x \leq 9$ or $(6, 9]$

▼

### Example 2.8.1.8: Solving a Compound Inequality with the Variable in All Three Parts

Solve the compound inequality with variables in all three parts: $3+x > 7x-2 > 5x-10$.

**Solution**

Let's try the first method. Write two inequalities:

$$\begin{aligned} 3+x &> 7x-2 \quad \text{and} \quad 7x-2 > 5x-10 \\ 3 &> 6x-2 \qquad\qquad 2x-2 > -10 \\ 5 &> 6x \qquad\qquad\quad 2x > -8 \\ \tfrac{5}{6} &> x \qquad\qquad\quad -4 < x \end{aligned}$$

The solution set is $-4 < x < \frac{5}{6}$ or in interval notation $\left(-4, \frac{5}{6}\right)$. Notice that when we write the solution in interval notation, the smaller number comes first. We read intervals from left to right, as they appear on a number line. See Figure 2.8.1.3





Figure 2.8.1.3

**Try It! 2.8.1.8**

Solve the compound inequality: $3y < 4 - 5y < 5 + 3y$.

**Answer**

$\left(-\frac{1}{8}, \frac{1}{2}\right)$

▼

## Solving Absolute Value Inequalities

As we know, the absolute value of a quantity is a positive number or zero. From the origin, a point located at $(-x, 0)$ has an absolute value of $x$, as it is $x$ units away. Consider absolute value as the distance from one point to another point. Regardless of direction, positive or negative, the distance between the two points is represented as a positive number or zero.

An absolute value inequality is an equation of the form

$$|A| < B, \quad |A| \leq B, \quad |A| > B, \quad \text{or} \quad |A| \geq B,$$

Where $A$, and sometimes $B$, represents an algebraic expression dependent on a variable $x$. Solving the inequality means finding the set of all $x$-values that satisfy the problem. Usually this set will be an interval or the union of two intervals and will include a range of values.

There are two basic approaches to solving absolute value inequalities: graphical and algebraic. The advantage of the graphical approach is we can read the solution by interpreting the graphs of two equations. The advantage of the algebraic approach is that solutions are exact, as precise solutions are sometimes difficult to read from a graph.

Suppose we want to know all possible returns on an investment if we could earn some amount of money within \$200 of \$600. We can solve algebraically for the set of $x$-values such that the distance between$x$ and $600$ is less than or equal to $200$. We represent the distance between $x$ and $600$ as $|x - 600|$, and therefore, $|x - 600| \leq 200$ or

$$\begin{gathered} -200 \leq x - 600 \leq 200 \\ -200 + 600 \leq x - 600 + 600 \leq 200 + 600 \\ 400 \leq x \leq 800 \end{gathered}$$

This means our returns would be between \$400 and \$800.

To solve absolute value inequalities, just as with absolute value equations, we write two inequalities and then solve them independently.

**Definition: Absolute Value Inequalities**

For an algebraic expression $X$ and $k > 0$, an **absolute value inequality** is an inequality of the form

$$|X| < k \text{ is equivalent to } -k < X < k$$

$$|X| > k \text{ is equivalent to } X < -k \text{ or } X > k$$

These statements also apply to $|X| \leq k$ and $|X| \geq k$.

**Example 2.8.1.9: Determining a Number within a Prescribed Distance**

Describe all values $x$ within a distance of $4$ from the number $5$.

**Solution**

We want the distance between $x$ and $5$ to be less than or equal to $4$. We can draw a number line, such as in Figure $2.8.1.4$,to represent the condition to be satisfied.





Figure 2.8.1.4

The distance from $x$ to 5 can be represented using an absolute value symbol, $|x-5|$. Write the values of $x$ that satisfy the condition as an absolute value inequality.

$$|x-5| \leq 4$$

We need to write two inequalities as there are always two solutions to an absolute value equation.

$$x-5 \leq 4 \quad \text{and} \quad x-5 \geq -4$$
$$x \leq 9 \qquad\qquad x \geq 1$$

If the solution set is $x \leq 9$ and $x \geq 1$, then the solution set is an interval including all real numbers between and including 1 and 9.

So $|x-5| \leq 4$ is equivalent to $[1,9]$ in interval notation.

▼

**? Try It! 2.8.1.9**

Describe all $x$-values within a distance of 3 from the number 2.

**Answer**

$|x-2| \leq 3$

**✓ Example 2.8.1.10: Solving an Absolute Value Inequality**

Solve $|x-1| \leq 3$.

**Solution**

$$|x-1| \leq 3$$
$$-3 \leq x-1 \leq 3$$
$$-2 \leq x \leq 4$$
$$[-2,4]$$

**✓ Example 2.8.1.11: Using a Graphical Approach to Solve Absolute Value Inequalities**

Given the equation $y = -\frac{1}{2}|4x-5|+3$, determine the $x$-values for which the $y$-values are negative.

**Solution**

We are trying to determine where $y<0$, which is when $-\frac{1}{2}|4x-5|+3<0$. We begin by isolating the absolute value.

$$-\tfrac{1}{2}|4x-5| < -3 \qquad \text{Multiply both sides by } -2, \text{ and reverse the inequality.}$$
$$|4x-5| > 6$$

Next, we solve for the equality $|4x-5|=6$.

$$4x-5=6 \qquad\qquad 4x-5=-6$$
$$4x=11 \quad \text{or} \quad 4x=-1$$
$$x=\tfrac{11}{4} \qquad\qquad x=-\tfrac{1}{4}$$

Now, we can examine the graph to observe where the $y$-values are negative. We observe where the branches are below the $x$-axis. Notice that it is not important exactly what the graph looks like, as long as we know that it crosses the horizontal axis at $x = -\frac{1}{4}$ and $x = \frac{11}{4}$, and that the graph opens downward. See Figure 2.8.1.5.





Figure 2.8.1.5

**Try It! 2.8.1.10**

Solve $-2|k-4| \leq -6$.

**Answer**

$k \leq 1$ or $k \geq 7$; in interval notation, this would be $(-\infty, 1] \cup [7, \infty)$.





Figure 2.8.1.6

This page titled 2.8.1: Linear Inequalities is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.7: Linear Inequalities and Absolute Value Inequalities** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/books/algebra-and-trigonometry-2e/pages/2-7-linear-inequalities-and-absolute-value-inequalities.

# 2.8.1E: Exercises

## Practice Makes Perfect

**Graph Inequalities on the Number Line**


In the following exercises, graph each inequality on the number line and write in interval notation.

1. ⓐ $x < -2$
ⓑ $x \geq -3.5$
ⓒ $x \leq \frac{2}{3}$


2. ⓐ $x > 3$
ⓑ $x \leq -0.5$
ⓒ $x \geq \frac{1}{3}$

**Answer**


ⓐ




ⓑ




ⓒ





3. ⓐ $x \geq -4$
ⓑ $x < 2.5$
ⓒ $x > -\frac{3}{2}$


4. ⓐ $x \leq 5$
ⓑ $x \geq -1.5$
ⓒ $x < -\frac{7}{3}$

**Answer**


ⓐ




ⓑ




ⓒ





5. ⓐ $-5 < x < 2$
ⓑ $-3 \leq x < -1$
ⓒ $0 \leq x \leq 1.5$


6. ⓐ $-2 < x < 0$
ⓑ $-5 \leq x < -3$
ⓒ $0 \leq x \leq 3.5$

**Answer**


ⓐ




ⓑ




ⓒ





7. ⓐ $-1 < x < 3$
ⓑ $-3 < x \leq -2$
ⓒ $-1.25 \leq x \leq 0$


8. ⓐ $-4 < x < 2$
ⓑ $-5 < x \leq -2$
ⓒ $-3.75 \leq x \leq 0$

**Answer**


ⓐ




ⓑ




ⓒ




**Solve Linear Inequalities**


In the following exercises, solve each inequality, graph the solution on the number line, and write the solution in interval notation.

9. ⓐ $a+\frac{3}{4}\geq\frac{7}{10}$
ⓑ $8x>72$
ⓒ $20>\frac{2}{5}h$


10. ⓐ $b+\frac{7}{8}\geq\frac{1}{6}$
ⓑ $6y<48$
ⓒ $40<\frac{5}{8}k$

**Answer**


ⓐ




ⓑ




ⓒ





11. ⓐ $f-\frac{13}{20}<-\frac{5}{12}$
ⓑ $9t\geq-27$
ⓒ $\frac{7}{6}j\geq42$


12. ⓐ $g-\frac{11}{12}<-\frac{5}{18}$
ⓑ $7s<-28$
ⓒ $\frac{9}{4}g\leq36$

**Answer**


ⓐ




ⓑ




ⓒ





13. ⓐ $-5u \geq 65$
ⓑ $\frac{a}{-3} \leq 9$


14. ⓐ $-8v \leq 96$
ⓑ $\frac{b}{-10} \geq 30$

**Answer**

ⓐ




ⓑ





15. ⓐ $-9c < 126$
ⓑ $-25 < \frac{p}{-5}$


16. ⓐ $-7d > 105$
ⓑ $-18 > \frac{q}{-6}$

**Answer**

ⓐ




ⓑ





In the following exercises, solve each inequality, graph the solution on the number line, and write the solution in interval notation.

17. $4v \geq 9v - 40$

18. $5u \leq 8u - 21$

**Answer**



https://math.libretexts.org/@go/page/101672




19. $13q < 7q - 29$

20. $9p > 14p - 18$


**Answer**




21. $12x + 3(x + 7) > 10x - 24$

22. $9y + 5(y + 3) < 4y - 35$


**Answer**




23. $6h - 4(h - 1) \leq 7h - 11$

24. $4k - (k - 2) \geq 7k - 26$


**Answer**




25. $8m - 2(14 - m) \geq 7(m - 4) + 3m$

26. $6n - 12(3 - n) \leq 9(n - 4) + 9n$

**Answer**





27. $\frac{3}{4}b - \frac{1}{3}b < \frac{5}{12}b - \frac{1}{2}$

28. $9u + 5(2u - 5) \geq 12(u - 1) + 7u$

**Answer**



https://math.libretexts.org/@go/page/101672




29. $\frac{2}{3}g-\frac{1}{2}(g-14)\leq\frac{1}{6}(g+42)$

30. $\frac{4}{5}h-\frac{2}{3}(h-9)\geq\frac{1}{15}(2h+90)$


**Answer**




31. $\frac{5}{6}a-\frac{1}{4}a>\frac{7}{12}a+\frac{2}{3}$

32. $12v+3(4v-1)\leq19(v-2)+5v$

**Answer**





In the following exercises, solve each inequality, graph the solution on the number line, and write the solution in interval notation.

33. $15k\leq-40$

34. $35k\geq-77$


**Answer**




35. $23p-2(6-5p)>3(11p-4)$

36. $18q-4(10-3q)<5(6q-8)$


**Answer**




37. $-\frac{9}{4}x\geq-\frac{5}{12}$

38. $-\frac{21}{8}y\leq-\frac{15}{28}$


**Answer**




39. $c + 34 < -99$

40. $d + 29 > -61$


**Answer**




41. $\frac{m}{18} \geq -4$

42. $\frac{n}{13} \leq -6$

**Answer**





**Translate to an Inequality and Solve**

In the following exercises, translate and solve. Then graph the solution on the number line and write the solution in interval notation.

43. Three more than $h$ is no less than $25$.

44. Six more than $k$ exceeds $25$.


**Answer**




45. Ten less than $w$ is at least $39$.

46. Twelve less than $x$ is no less than $21$.


**Answer**




47. Negative five times $r$ is no more than $95$.

48. Negative two times $s$ is lower than $56$.


**Answer**




49. Nineteen less than $b$ is at most $-22$.

50. Fifteen less than $a$ is at least $-7$.

**Answer**




**Solve Applications with Linear Inequalities**

In the following exercises, solve.

51. Alan is loading a pallet with boxes that each weighs 45 pounds. The pallet can safely support no more than 900 pounds. How many boxes can he safely load onto the pallet?

52. The elevator in Yehire's apartment building has a sign that says the maximum weight is 2100 pounds. If the average weight of one person is 150 pounds, how many people can safely ride the elevator?

**Answer**

A maximum of 14 people can safely ride in the elevator.

53. Andre is looking at apartments with three of his friends. They want the monthly rent to be no more than $2,360. If the roommates split the rent evenly among the four of them, what is the maximum rent each will pay?

54. Arleen got a $20 gift card for the coffee shop. Her favorite iced drink costs $3.79. What is the maximum number of drinks she can buy with the gift card?

**Answer**

five drinks

55. Teegan likes to play golf. He has budgeted $60 next month for the driving range. It costs him $10.55 for a bucket of balls each time he goes. What is the maximum number of times he can go to the driving range next month?

56. Ryan charges his neighbors $17.50 to wash their car. How many cars must he wash next summer if his goal is to earn at least $1,500?

**Answer**

86 cars

57. Keshad gets paid $2,400 per month plus 6% of his sales. His brother earns $3,300 per month. For what amount of total sales will Keshad's monthly pay be higher than his brother's monthly pay?

58. Kimuyen needs to earn $4,150 per month in order to pay all her expenses. Her job pays her $3,475 per month plus 4% of her total sales. What is the minimum Kimuyen's total sales must be in order for her to pay all her expenses?

**Answer**

$16,875

59. Andre has been offered an entry-level job. The company offered him $48,000 per year plus 3.5% of his total sales. Andre knows that the average pay for this job is $62,000. What would Andre's total sales need to be for his pay to be at least as high as the average pay for this job?

60. Nataly is considering two job offers. The first job would pay her $83,000 per year. The second would pay her $66,500 plus 15% of her total sales. What would her total sales need to be for her salary on the second offer be higher than the first?

**Answer**

$110,000

61. Jake's water bill is $24.80 per month plus $2.20 per ccf (hundred cubic feet) of water. What is the maximum number of ccf Jake can use if he wants his bill to be no more than $60?

62. Kiyoshi's phone plan costs $17.50 per month plus $0.15 per text message. What is the maximum number of text messages Kiyoshi can use so the phone bill is no more than $56.60?

**Answer**

260 messages

63. Marlon's TV plan costs $49.99 per month plus $5.49 per first-run movie. How many first-run movies can he watch if he wants to keep his monthly bill to be a maximum of $100?

64. Kellen wants to rent a banquet room in a restaurant for her cousin's baby shower. The restaurant charges $350 for the banquet room plus $32.50 per person for lunch. How many people can Kellen have at the shower if she wants the maximum cost to be $1,500?

**Answer**

35 people

65. Moshde runs a hairstyling business from her house. She charges $45 for a haircut and style. Her monthly expenses are $960. She wants to be able to put at least $1,200 per month into her savings account order to open her own salon. How many "cut & styles" must she do to save at least $1,200 per month?

66. Noe installs and configures software on home computers. He charges $125 per job. His monthly expenses are $1,600. How many jobs must he work in order to make a profit of at least $2,400?

**Answer**

32 jobs

67. Katherine is a personal chef. She charges $115 per four-person meal. Her monthly expenses are $3,150. How many four-person meals must she sell in order to make a profit of at least $1,900?

68. Melissa makes necklaces and sells them online. She charges $88 per necklace. Her monthly expenses are $3,745. How many necklaces must she sell if she wants to make a profit of at least $1,650?

**Answer**

62 necklaces

69. Five student government officers want to go to the state convention. It will cost them $110 for registration, $375 for transportation and food, and $42 per person for the hotel. There is $450 budgeted for the convention in the student government savings account. They can earn the rest of the money they need by having a car wash. If they charge $5 per car, how many cars must they wash in order to have enough money to pay for the trip?

70. Cesar is planning a four-day trip to visit his friend at a college in another state. It will cost him $198 for airfare, $56 for local transportation, and $45 per day for food. He has $189 in savings and can earn $35 for each lawn he mows. How many lawns must he mow to have enough money to pay for the trip?

**Answer**

seven lawns

71. Alonzo works as a car detailer. He charges $175 per car. He is planning to move out of his parents' house and rent his first apartment. He will need to pay $120 for application fees, $950 for security deposit, and first and last months' rent at $1,140 per month. He has $1,810 in savings. How many cars must he detail to have enough money to rent the apartment?

72. Eun-Kyung works as a tutor and earns $60 per hour. She has $792 in savings. She is planning an anniversary party for her parents. She would like to invite 40 guests. The party will cost her $1,520 for food and drinks and $150 for the photographer. She will also have a favor for each of the guests, and each favor will cost $7.50. How many hours must she tutor to have enough money for the party?

**Answer**

20 hours

## Everyday Math

**73. Maximum load on a stage** In 2014, a high school stage collapsed in Fullerton, California, when 250 students got on stage for the finale of a musical production. Two dozen students were injured. The stage could support a maximum of 12,750 pounds. If the average weight of a student is assumed to be 140 pounds, what is the maximum number of students who could safely be on the stage?

**74. Maximum weight on a boat** In 2004, a water taxi sank in Baltimore harbor and five people drowned. The water taxi had a maximum capacity of 3,500 pounds (25 people with average weight 140 pounds). The average weight of the 25 people on the water taxi when it sank was 168 pounds per person. What should the maximum number of people of this weight have been?

**Answer**

20 people

**75. Wedding budget** Adele and Walter found the perfect venue for their wedding reception. The cost is $9850 for up to 100 guests, plus $38 for each additional guest. How many guests can attend if Adele and Walter want the total cost to be no more than $12,500?

**76. Shower budget** Penny is planning a baby shower for her daughter-in-law. The restaurant charges $950 for up to 25 guests, plus $31.95 for each additional guest. How many guests can attend if Penny wants the total cost to be no more than $1,500?

**Answer**

42 guests

## Writing Exercises

77. Explain why it is necessary to reverse the inequality when solving $-5x > 10$.

78. Explain why it is necessary to reverse the inequality when solving $n - 3 < 12$.

**Answer**

Answers will vary.

79. Find your last month's phone bill and the hourly salary you are paid at your job. Calculate the number of hours of work it would take you to earn at least enough money to pay your phone bill by writing an appropriate inequality and then solving it. Do you feel this is an appropriate number of hours? Is this the appropriate phone plan for you?

80. Find out how many units you have left, after this term, to achieve your college goal and estimate the number of units you can take each term in college. Calculate the number of terms it will take you to achieve your college goal by writing an appropriate inequality and then solving it. Is this an acceptable number of terms until you meet your goal? What are some ways you could accelerate this process?

**Answer**

Answers will vary.

## Self Check

ⓐ After completing the exercises, use this checklist to evaluate your mastery of the objectives of this section.

| I can... | Confidently | With some help | No-I don't get it! |
|---|---|---|---|
| graph inequalities on the number line. | | | |
| solve linear inequalities. | | | |
| translate words to an inequality and solve. | | | |
| solve applications with linear inequalities. | | | |

ⓑ After looking at the checklist, do you think you are well-prepared for the next section? Why or why not?

This page titled 2.8.1E: Exercises is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.6E: Exercises** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/intermediate-algebra-2e.

# 2.8.2: Solve Absolute Value Inequalities

**Learning Objectives**

By the end of this section, you will be able to:

- Solve absolute value equations
- Solve absolute value inequalities with “less than”
- Solve absolute value inequalities with “greater than”
- Solve applications with absolute value

Before you get started, take this readiness quiz.

1. Evaluate: $-|7|$.
   If you missed this problem, review [link].
2. Fill in $<, >, <, >$, or $=$ for each of the following pairs of numbers.
   ⓐ $|-8|\_\_\_-|-8|$ ⓑ $12\_\_\_-|-12|$ ⓒ $|-6|\_\_\_-6$ ⓓ $-(-15)\_\_\_-|-15|$
   If you missed this problem, review [link].
3. Simplify: $14-2|8-3(4-1)|$.
   If you missed this problem, review [link].

## Solve Absolute Value Equations

As we prepare to solve absolute value equations, we review our definition of **absolute value**.

**ABSOLUTE VALUE**

The absolute value of a number is its distance from zero on the number line.

The absolute value of a number $n$ is written as $|n|$ and $|n| \geq 0$ for all numbers.

Absolute values are always greater than or equal to zero.

We learned that both a number and its opposite are the same distance from zero on the number line. Since they have the same distance from zero, they have the same absolute value. For example:

- $-5$ is 5 units away from 0, so $|-5| = 5$.
- $5$ is 5 units away from 0, so $|5| = 5$.

Figure $2.8.2.1$illustrates this idea.





Figure $2.8.2.1$: The numbers 5 and $-5$ are both five units away from zero.

For the equation |x|=5,|x|=5, we are looking for all numbers that make this a true statement. We are looking for the numbers whose distance from zero is 5. We just saw that both 5 and −5−5 are five units from zero on the number line. They are the solutions to the equation.

$$\begin{array}{ll} \text{If} & |x| = 5 \\ \text{then} & x = -5 \text{ or } x = 5 \end{array}$$

The solution can be simplified to a single statement by writing $x = \pm 5$. This is read, “$x$ is equal to positive or negative 5”.

We can generalize this to the following property for absolute value equations.

## ABSOLUTE VALUE EQUATIONS

For any algebraic expression, $u$, and any positive real number, $a$,

$$\begin{aligned} &\text{if} && |u| = a \\ &\text{then} && u = -a \text{ or } u = a \end{aligned}$$

Remember that an absolute value cannot be a negative number.

## Example 2.8.2.1

Solve:

a. $|x| = 8$
b. $|y| = -6$
c. $|z| = 0$

**Solution a**

$$\begin{aligned} & && |x| = 8 \\ &\text{Write the equivalent equations.} && x = -8 \text{ or } x = 8 \\ & && x = \pm 8 \end{aligned}$$

**Solution b**

$$|y| = -6$$

No solution

Since an absolute value is always positive, there are no solutions to this equation.

**Solution c**

$$\begin{aligned} & && |z| = 0 \\ &\text{Write the equivalent equations.} && z = -0 \text{ or } z = 0 \\ &\text{Since } -0 = 0, && z = 0 \end{aligned}$$

Both equations tell us that z=0z=0 and so there is only one solution.

## EXERCISE 2.8.2.2

Solve:

a. $|x| = 2$
b. $|y| = -4$
c. $|z| = 0$

**Answer a**

$\pm 2$

**Answer b**

no solution

**Answer c**

0

## EXERCISE 2.8.2.3

Solve:

a. $|x| = 11$
b. $|y| = -5$

c. $|z| = 0$

**Answer a**

$\pm 11$

**Answer b**

no solution

**Answer c**

0

To solve an **absolute value equation**, we first isolate the absolute value expression using the same procedures we used to solve linear equations. Once we isolate the absolute value expression we rewrite it as the two equivalent equations.

## How to Solve Absolute Value Equations

**? Example 2.8.2.4**

Solve $|5x - 4| - 3 = 8$.

**Solution**

| | | |
|---|---|---|
| **Step 1.** Isolate the absolute value expression. | Add 3 to both sides. | $\|5x-4\|-3=8$<br>$\|5x-4\|=11$ |
| **Step 2.** Write the equivalent equations. | | $5x-4=-11$ or $5x-4=11$ |
| **Step 3.** Solve each equation. | Add 4 to each side.<br>Divide each side by 5. | $5x=-7$ $\quad 5x=15$<br>$x=-\frac{7}{5}$ or $x=3$ |
| **Step 4.** Check each solution. | Substitute 3 and $-\frac{7}{5}$ into the original equation. | $\|5x-4\|-3=8$<br>$x=3$<br>$\|5\cdot 3-4\|-3\stackrel{?}{=}8$<br>$\|15-4\|-3\stackrel{?}{=}8$<br>$\|11\|-3\stackrel{?}{=}8$<br>$11-3\stackrel{?}{=}8$<br>$8=8$ ✓<br>$\|5x-4\|-3=8$<br>$x=-\frac{7}{5}$<br>$\left\|5\left(-\frac{7}{5}\right)-4\right\|-3\stackrel{?}{=}8$<br>$\|-7-4\|-3\stackrel{?}{=}8$<br>$\|-11\|-3\stackrel{?}{=}8$<br>$11-3\stackrel{?}{=}8$<br>$8=8$ ✓ |

**? EXERCISE 2.8.2.5**

Solve: $|3x - 5| - 1 = 6$.

**Answer**

$x = 4,\ x = -\frac{2}{3}$

**EXERCISE 2.8.2.6**

Solve: $|4x - 3| - 5 = 2$.

**Answer**

$x = -1,\ x = \frac{5}{2}$

The steps for solving an absolute value equation are summarized here.

**SOLVE ABSOLUTE VALUE EQUATIONS.**

1. Isolate the absolute value expression.
2. Write the equivalent equations.
3. Solve each equation.
4. Check each solution.

**Example 2.8.2.7**

Solve $2|x - 7| + 5 = 9$.

**Solution**

| | |
|---|---|
| | $2\|x - 7\| + 5 = 9$ |
| Isolate the absolute value expression. | $2\|x - 7\| = 4$ |
| | $\|x - 7\| = 2$ |
| Write the equivalent equations. | $x - 7 = -2$ or $x - 7 = 2$ |
| Solve each equation. | $x = 5$ or $x = 9$ |
| Check: $2\|x-7\|+5=9$ $2\|5-7\|+5\stackrel{?}{=}9$ $2\|-2\|+5\stackrel{?}{=}9$ $2\cdot2+5\stackrel{?}{=}9$ $4+5\stackrel{?}{=}9$ $9=9$ ✓ <br> $2\|x-7\|+5=9$ $2\|9-7\|+5\stackrel{?}{=}9$ $2\|2\|+5\stackrel{?}{=}9$ $2\cdot2+5\stackrel{?}{=}9$ $4+5\stackrel{?}{=}9$ $9=9$ ✓ | |

**Exercise 2.8.2.8**

Solve: $3|x - 4| - 4 = 8$.

**Answer**

$x = 8,\ x = 0$

**Exercise 2.8.2.9**

Solve: $2|x - 5| + 3 = 9$.

**Answer**

$x = 8,\ x = 2$

Remember, an absolute value is always positive!

**Example 2.8.2.10**

Solve: $|\frac{2}{3}x - 4| + 11 = 3$.

**Solution**

| | |
|---|---|
| | $\|\frac{2}{3}x - 4\| = -8$ |
| Isolate the absolute value term. | $\|\frac{2}{3}x - 4\| = -8$ |
| An absolute value cannot be negative. | No solution |

**Exercise 2.8.2.11**

Solve: $|\frac{3}{4}x - 5| + 9 = 4$.

**Answer**

No solution

**Exercise 2.8.2.12**

Solve: $|\frac{5}{6}x + 3| + 8 = 6$.

**Answer**

No solution

Some of our absolute value equations could be of the form $|u| = |v|$ where $u$ and $v$ are algebraic expressions. For example, $|x - 3| = |2x + 1|$.

How would we solve them? If two algebraic expressions are equal in absolute value, then they are either equal to each other or negatives of each other. The property for absolute value equations says that for any algebraic expression, $u$, and a positive real number, $a$, if $|u| = a$, then $u = -a$ or $u = a$.

This tell us that

| | | | |
|---|---|---|---|
| if | $\|u\| = \|v\|$ | | |
| then | $\|u\| = v$ | or | $\|u\| = -v$ |
| and so | $u = v$ or $u = -v$ | or | $u = -v$ or $u = -(-v)$ |

This leads us to the following property for equations with two absolute values.

**EQUATIONS WITH TWO ABSOLUTE VALUES**

For any algebraic expressions, $u$ and $v$,

| | |
|---|---|
| if | $\|u\| = \|v\|$ |
| then | $u = -v$ or $u = v$ |

When we take the opposite of a quantity, we must be careful with the signs and to add parentheses where needed.

**Example 2.8.2.13**

Solve: $|5x-1|=|2x+3|$.

**Solution**

$$|5x-1|=|2x+3|$$

| | | | |
|---|---|---|---|
| Write the equivalent equations. | $5x-1=-(2x+3)$ | or | $5x-1=2x+3$ |
| | $5x-1=-2x-3$ | or | $3x-1=3$ |
| Solve each equation. | $7x-1=-3$ | | $3x=4$ |
| | $7x=-2$ | | $x=43$ |
| | $x=-27$ | or | $x=43$ |

Check.

We leave the check to you.

**Exercise 2.8.2.14**

Solve: $|7x-3|=|3x+7|$.

**Answer**

$x=-\frac{2}{5},\ x=\frac{5}{2}$

**Exercise 2.8.2.15**

Solve: $|6x-5|=|3x+4|$.

**Answer**

$x=3, x=19$

## Solve Absolute Value Inequalities with "Less Than"

Let's look now at what happens when we have an **absolute value inequality**. Everything we've learned about solving inequalities still holds, but we must consider how the absolute value impacts our work. Again we will look at our definition of absolute value. The absolute value of a number is its distance from zero on the number line. For the equation $|x|=5$, we saw that both 5 and $-5$ are five units from zero on the number line. They are the solutions to the equation.

$$|x|=5$$
$$x=-5 \quad \text{or} \quad x=5$$

What about the inequality $|x|\leq 5$? Where are the numbers whose distance is less than or equal to 5? We know $-5$ and 5 are both five units from zero. All the numbers between $-5$ and 5 are less than five units from zero (Figure 2.8.2.2).





Figure 2.8.2.2.

In a more general way, we can see that if $|u|\leq a$, then $-a\leq u\leq a$ (Figure 2.8.2.3).





Figure 2.8.2.3.

This result is summarized here.

**ABSOLUTE VALUE INEQUALITIES WITH $<$ OR $\leq$**

For any algebraic expression, $u$, and any positive real number, $a$,


$$\text{if} \quad |u| < a, \quad \text{then} \; -a < u < a$$
$$\text{if} \quad |u| \leq a, \quad \text{then} \; -a \leq u \leq a$$

After solving an inequality, it is often helpful to check some points to see if the solution makes sense. The graph of the solution divides the number line into three sections. Choose a value in each section and substitute it in the original inequality to see if it makes the inequality true or not. While this is not a complete check, it often helps verify the solution.

**Example 2.8.2.16**

Solve $|x| < 7$. Graph the solution and write the solution in interval notation.


**Solution**

| | $\lvert x\rvert < 7$ |
|---|---|
| Write the equivalent inequality. | $-7 < x < 7$ |
| Graph the solution. |  |
| Write the solution using interval notation. | $(-7, 7)$ |



Check:


To verify, check a value in each section of the number line showing the solution. Choose numbers such as −8,−8, 1, and 9.




**EXERCISE 2.8.2.17**

Graph the solution and write the solution in interval notation: $|x| < 9$.


**Answer**




**EXERCISE 2.8.2.18**

Graph the solution and write the solution in interval notation: $|x| < 1$.

**Answer**




## Example 2.8.2.19

Solve $|5x-6| \leq 4$. Graph the solution and write the solution in interval notation.

**Solution**


| | |
|---|---|
| **Step 1.** Isolate the absolute value expression. It is isolated. | $\lvert 5x-6 \rvert \leq 4$ |
| **Step 2.** Write the equivalent compound inequality. | $-4 \leq 5x-6 \leq 4$ |
| **Step 3.** Solve the compound inequality. | $2 \leq 5x \leq 10$<br>$\frac{2}{5} \leq x \leq 2$ |
| **Step 4.** Graph the solution. |  |
| **Step 5.** Write the solution using interval notation. | $[\frac{2}{5}, 2]$ |
| Check: The check is left to you. | |



## EXERCISE 2.8.2.20

Solve $|2x-1| \leq 5$. Graph the solution and write the solution in interval notation:


**Answer**




## EXERCISE 2.8.2.21

Solve $|4x-5| \leq 3$. Graph the solution and write the solution in interval notation:

**Answer**




## SOLVE ABSOLUTE VALUE INEQUALITIES WITH $<$ OR $\leq$

1. Isolate the absolute value expression.
2. Write the equivalent compound inequality.

$$|u| < a \quad \text{is equivalent to} \quad -a < u < a$$
$$|u| \leq a \quad \text{is equivalent to} \quad -a \leq u \leq a$$

3. Solve the compound inequality.
4. Graph the solution

5. Write the solution using interval notation.

## Solve Absolute Value Inequalities with “Greater Than”

What happens for absolute value inequalities that have “greater than”? Again we will look at our definition of absolute value. The absolute value of a number is its distance from zero on the number line.

We started with the inequality $|x| \leq 5$. We saw that the numbers whose distance is less than or equal to five from zero on the number line were $-5$ and 5 and all the numbers between $-5$ and 5 (Figure 2.8.2.4).





Figure 2.8.2.4.

Now we want to look at the inequality $|x| \geq 5$. Where are the numbers whose distance from zero is greater than or equal to five?

Again both $-5$ and 5 are five units from zero and so are included in the solution. Numbers whose distance from zero is greater than five units would be less than $-5$ and greater than 5 on the number line (Figure 2.8.2.5).





Figure 2.8.2.5.

In a more general way, we can see that if $|u| \geq a$, then $u \leq -a$ or $u \leq a$. See Figure.





Figure 2.8.2.6.

This result is summarized here.

### ABSOLUTE VALUE INEQUALITIES WITH $>$ OR $\geq$


For any algebraic expression, *u*, and any positive real number, *a*,

$$\begin{array}{lll} \text{if} & |u| > a, & \text{then } u < -a \text{ or } u > a \\ \text{if} & |u| \geq a, & \text{then } u \leq -a \text{ or } u \geq a \end{array}$$


### Example 2.8.2.22

Solve $|x| > 4$. Graph the solution and write the solution in interval notation.

**Solution**

| | |
|---|---|
| | $\lvert x\rvert > 4$ |
| Write the equivalent inequality. | $x < -4$ or $x > 4$ |
| Graph the solution. |  |
| Write the solution using interval notation. | $(-\inf, -4) \cup (4, \inf)$ |
| Check: | |


To verify, check a value in each section of the number line showing the solution. Choose numbers such as −6,−6, 0, and 7.




## EXERCISE 2.8.2.23

Solve $|x| > 2$. Graph the solution and write the solution in interval notation.


**Answer**




## EXERCISE 2.8.2.24

Solve $|x| > 1$. Graph the solution and write the solution in interval notation.


**Answer**




## Example 2.8.2.25

Solve $|2x-3| \geq 5$. Graph the solution and write the solution in interval notation.


**Solution**

| | |
|---|---|
| | $\lvert 2x-3\rvert \geq 5$ |
| **Step 1.** Isolate the absolute value expression. It is isolated. | |
| **Step 2.** Write the equivalent compound inequality. | $2x-3 \leq -5$ or $2x-3 \geq 5$ |
| **Step 3.** Solve the compound inequality. | $2x \leq -2$ or $2x \geq 8$<br>$x \leq -1$ or $x \geq 4$ |
| **Step 4.** Graph the solution. |   |
| **Step 5.** Write the solution using interval notation. | $(-\inf, -1] \cup [4, \inf)$ |
| Check:<br>The check is left to you. | |

## EXERCISE 2.8.2.26

Solve $|4x-3| \geq 5$. Graph the solution and write the solution in interval notation.


**Answer**




**EXERCISE 2.8.2.27**

Solve $|3x - 4| \ge 2$. Graph the solution and write the solution in interval notation.

**Answer**




**SOLVE ABSOLUTE VALUE INEQUALITIES WITH $>$ OR $\ge$.**

1. Isolate the absolute value expression.
2. Write the equivalent compound inequality.

$$\begin{array}{lllll} |u| > a & \text{is equivalent to} & u < -a & \text{or} & u > a \\ |u| \ge a & \text{is equivalent to} & u \le -a & \text{or} & u \ge a \\ |u| > a & \text{is equivalent to} & u < -a & \text{or} & u > a \\ |u| \ge a & \text{is equivalent to} & u \le -a & \text{or} & u \ge a \end{array}$$

3. Solve the compound inequality.
4. Graph the solution
5. Write the solution using interval notation.

## Solve Applications with Absolute Value

Absolute value inequalities are often used in the manufacturing process. An item must be made with near perfect specifications. Usually there is a certain *tolerance* of the difference from the specifications that is allowed. If the difference from the specifications exceeds the tolerance, the item is rejected.

$$|\text{actual-ideal}| \le \text{tolerance}$$

**Example 2.8.2.28**

The ideal diameter of a rod needed for a machine is 60 mm. The actual diameter can vary from the ideal diameter by $0.075$ mm. What range of diameters will be acceptable to the customer without causing the rod to be rejected?

**Solution**

| | |
|---|---|
| | Let $x =$ the actual measurement |
| Use an absolute value inequality to express this situation. | $\|\text{actual-ideal}\| \le \text{tolerance}$ |
| | $\|x - 60\| \le 0.075$ |
| Rewrite as a compound inequality. | $-0.075 \le x - 60 \le 0.075$ |
| Solve the inequality. | $59.925 \le x \le 60.075$ |
| Answer the question. | The diameter of the rod can be between $59.925mm$ and $60.075mm$. |

**EXERCISE 2.8.2.29**

The ideal diameter of a rod needed for a machine is 80 mm. The actual diameter can vary from the ideal diameter by 0.009 mm. What range of diameters will be acceptable to the customer without causing the rod to be rejected?

**Answer**

The diameter of the rod can be between 79.991 and 80.009 mm.

**EXERCISE 2.8.2.30**

The ideal diameter of a rod needed for a machine is 75 mm. The actual diameter can vary from the ideal diameter by 0.05 mm. What range of diameters will be acceptable to the customer without causing the rod to be rejected?

**Answer**

The diameter of the rod can be between 74.95 and 75.05 mm.

Access this online resource for additional instruction and practice with solving linear absolute value equations and inequalities.

- Solving Linear Absolute Value Equations and Inequalities

## Key Concepts

- **Absolute Value**
  The absolute value of a number is its distance from 0 on the number line.
  The absolute value of a number *n* is written as $|n|$ and $|n| \geq 0$ for all numbers.
  Absolute values are always greater than or equal to zero.
- **Absolute Value Equations**
  For any algebraic expression, *u*, and any positive real number, *a*,
  if $|u| = a$
  then $u = -a$ or $u = a$
  Remember that an absolute value cannot be a negative number.
- **How to Solve Absolute Value Equations**
  1. Isolate the absolute value expression.
  2. Write the equivalent equations.
  3. Solve each equation.
  4. Check each solution.
- **Equations with Two Absolute Values**
  For any algebraic expressions, *u* and *v*,
  if $|u| = |v|$
  then $u = -v$ or $u = v$
- **Absolute Value Inequalities with** $<$ or $\leq$
  For any algebraic expression, *u*, and any positive real number, *a*,
  if $|u| = a$ then $-a < u < a$
  if $|u| \leq a$ then $-a \leq u \leq a$
- **How To Solve Absolute Value Inequalities with** $<$ or $\leq$
  1. Isolate the absolute value expression.
  2. Write the equivalent compound inequality.
     $|u| < a$ is equivalent to $-a < u < a$
     $|u| \leq a$ is equivalent to $-a \leq u \leq a$
  3. Solve the compound inequality.
  4. Graph the solution
  5. Write the solution using interval notation

- **Absolute Value Inequalities with $>$ or $\geq$**
  For any algebraic expression, $u$, and any positive real number, $a$,
  if $|u| > a$, then $u < -a$ or $u > a$
  if $|u| \geq a$, then $u \leq -a$ or $u \geq a$
- **How To Solve Absolute Value Inequalities with $>$ or $\geq$**
  1. Isolate the absolute value expression.
  2. Write the equivalent compound inequality.
     $|u| > a$ is equivalent to $u < -a$ or $u > a$
     $|u| \geq a$ is equivalent to $u \leq -a$ or $u \geq a$
  3. Solve the compound inequality.
  4. Graph the solution
  5. Write the solution using interval notation

---

This page titled 2.8.2: Solve Absolute Value Inequalities is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.8: Solve Absolute Value Inequalities** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/intermediate-algebra-2e.

# 2.8.2E: Exercises

## Practice Makes Perfect

**Solve Absolute Value Equations**

In the following exercises, solve.

1. a. $|x| = 6$ b. $|y| = -3$ c. $|z| = 0$

2. a. $|x| = 4$ b. $|y| = -5$ c. $|z| = 0$

**Answer**

a. $x = 4, x = -4$ b. no solution c. $z = 0$

3. a. $|x| = 7$ b. $|y| = -11$ c. $|z| = 0$

4. a. $|x| = 3$ b. $|y| = -1$ c. $|z| = 0$

**Answer**

a. $x = 3, x = -3$ b. no solution c. $z = 0$

5. $|2x - 3| - 4 = 1$

6. $|4x - 1| - 3 = 0$

**Answer**

$x = 1,\ x = -\frac{1}{2}$

7. $|3x - 4| + 5 = 7$

8. $|4x + 7| + 2 = 5$

**Answer**

$x = -1,\ x = -\frac{5}{2}$

9. $4|x - 1| + 2 = 10$

10. $3|x - 4| + 2 = 11$

**Answer**

$x = 7,\ x = 1$

11. $3|4x - 5| - 4 = 11$

12. $3|x + 2| - 5 = 4$

**Answer**

$x = 1,\ x = -5$

13. $-2|x-3|+8=-4$

14. $-3|x-4|+4=-5$

**Answer**

$x=7,\ x=1$

15. $|34x-3|+7=2$

16. $|35x-2|+5=2$

**Answer**

no solution

17. $|12x+5|+4=1$

18. $|14x+3|+3=1$

**Answer**

no solution

19. $|3x-2|=|2x-3|$

20. $|4x+3|=|2x+1|$

**Answer**

$x=-1,\ x=-\frac{2}{3}$

21. $|6x-5|=|2x+3|$

22. $|6-x|=|3-2x|$

**Answer**

$x=-3,\ x=3$


**Solve Absolute Value Inequalities with "less than"**

In the following exercises, solve each inequality. Graph the solution and write the solution in interval notation.

23. $|x|<5$

24. $|x|<1$


**Answer**




25. $|x|\leq 8$

26. $|x| \leq 3$


**Answer**




27. $|3x - 3| \leq 6$

28. $|2x - 5| \leq 3$


**Answer**




29. $|2x + 3| + 5 < 4$

30. $|3x - 7| + 3 < 1$


**Answer**




31. $|4x - 3| < 1$

32. $|6x - 5| < 7$


**Answer**




33. $|x - 4| \leq -1$

34. $|5x + 1| \leq -2$

**Answer**





**Solve Absolute Value Inequalities with "greater than"**

In the following exercises, solve each inequality. Graph the solution and write the solution in interval notation.

35. $|x| > 3$

36. $|x| > 6$


**Answer**




37. $|x| \geq 2$

38. $|x| \geq 5$


**Answer**




39. $|3x - 8| > -1$

40. $|x - 5| > -2$


**Answer**




41. $|3x - 2| > 4$

42. $|2x - 1| > 5$


**Answer**




43. $|x + 3| \geq 5$

44. $|x - 7| \geq 1$


**Answer**




45. $3|x| + 4 \geq 1$

46. $5|x| + 6 \geq 1$

**Answer**




In the following exercises, solve. For each inequality, also graph the solution and write the solution in interval notation.

47. $2|x+6|+4=8$

48. $|3x-4| \geq 2$

**Answer**

$x=4, x=27$

49. $|6x-5|=|2x+3|$

50. $|4x-3|<5$

**Answer**

$x=3, x=2$

51. $|2x-5|+2=3$

52. $|3x+1|-3=7$

**Answer**

$x=3, x=-\frac{11}{3}$

53. $|7x+2|+8<4$

54. $5|2x-1|-3=7$


**Answer**

$x=\frac{3}{2}, x=-\frac{1}{2}$

55. $|x-7|>-3$

56. $|8-x|=|4-3x|$

**Answer**




**Solve Applications with Absolute Value**

In the following exercises, solve.

57. A chicken farm ideally produces 200,000 eggs per day. But this total can vary by as much as 25,000 eggs. What is the maximum and minimum expected production at the farm?

58. An organic juice bottler ideally produces 215,000 bottle per day. But this total can vary by as much as 7,500 bottles. What is the maximum and minimum expected production at the bottling company?

**Answer**

The minimum to maximum expected production is 207,500 to 2,225,000 bottles

59. In order to insure compliance with the law, Miguel routinely overshoots the weight of his tortillas by 0.5 gram. He just received a report that told him that he could be losing as much as $100,000 per year using this practice. He now plans to buy new equipment that guarantees the thickness of the tortilla within 0.005 inches. If the ideal thickness of the tortilla is 0.04 inches, what thickness of tortillas will be guaranteed?

60. At Lilly's Bakery, the ideal weight of a loaf of bread is 24 ounces. By law, the actual weight can vary from the ideal by 1.5 ounces. What range of weight will be acceptable to the inspector without causing the bakery being fined?

**Answer**

The acceptable weight is 22.5 to 25.5 ounces.

## Writing Exercises

61. Write a graphical description of the absolute value of a number

62. In your own words, explain how to solve the absolute value inequality, $|3x-2| \geq 4$.

**Answer**

Answers will vary.

## Self Check

a. After completing the exercises, use this checklist to evaluate your mastery of the objectives of this section.

| I can... | Confidently | With some help | No-I don't get it! |
|---|---|---|---|
| solve absolute value equations. | | | |
| solve absolute value inequalities with "less than". | | | |
| solve absolute value inequalities with "greater than". | | | |
| solve applications with absolute value. | | | |

b. What does this checklist tell you about your mastery of this section? What steps will you take to improve?

This page titled 2.8.2E: Exercises is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.8E: Exercises** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/intermediate-algebra-2e.

# 2.8E: Linear Inequalities and Absolute Value Inequalities (Exercises)

This page titled 2.8E: Linear Inequalities and Absolute Value Inequalities (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# CHAPTER OVERVIEW

## 3: Functions


3.1: Prelude to Functions
3.2: Functions and Function Notation
3.2E: Functions and Function Notation (Exercises)
3.3: Domain and Range
3.3E: Domain and Range (Exercises)
3.4: Rates of Change and Behavior of Graphs
3.4E: Rates of Change and Behavior of Graphs (Exercises)
3.5: Linear Functions
3.5.1: Prelude to Linear Functions
3.5.2: Linear Functions
3.5.3: Graphs of Linear Functions
3.5.4: Modeling with Linear Functions
3.5.5: Fitting Linear Models to Data
3.5.E: Linear Functions(Exercises)
3.5.R: Linear Functions(Review)
3.6: Composition of Functions
3.6E: Composition of Functions (Exercises)
3.7: Transformation of Functions
3.7E: Transformation of Functions (Exercises)
3.8: Absolute Value Functions
3.8E: Absolute Value Functions (Exercises)
3.9: Inverse Functions
3.9E: Inverse Functions (Exercises)


Thumbnail: This relationship is a function because each input is associated with a single output. Note that input q and r both give output n.

### Contributors

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.


This page titled 3: Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 3.1: Prelude to Functions

Toward the end of the twentieth century, the values of stocks of internet and technology companies rose dramatically. As a result, the Standard and Poor's stock market average rose as well. The *Standard and Poor's Index* tracks the value of that initial investment of just under $100 over the 40 years. It shows that an investment that was worth less than $500 until about 1995 skyrocketed up to about $1100 by the beginning of 2000. That five-year period became known as the "dot-com bubble" because so many internet startups were formed. As bubbles tend to do, though, the dot-com bubble eventually burst. Many companies grew too fast and then suddenly went out of business. The result caused the sharp decline represented on the graph beginning at the end of 2000.





Figure 3.1.1: Figure of a Bull and a graph of market prices. Standard and Poor's Index with dividends reinvested (credit "bull": modification of work by Prayitno Hadinata; credit "graph": modification of work by MeasuringWorth)

Notice, as we consider this example, that there is a definite relationship between the year and stock market average. For any year we choose, we can determine the corresponding value of the stock market average. In this chapter, we will explore these kinds of relationships and their properties.

This page titled 3.1: Prelude to Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.0: Prelude to Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.2: Functions and Function Notation

**Learning Objectives**

- Determine whether a relation represents a function.
- Find the value of a function.
- Determine whether a function is one-to-one.
- Use the vertical line test to identify functions.
- Graph the functions listed in the library of functions.

A jetliner changes altitude as its distance from the starting point of a flight increases. The weight of a growing child increases with time. In each case, one quantity depends on another. There is a relationship between the two quantities that we can describe, analyze, and use to make predictions. In this section, we will analyze such relationships.

## Determining Whether a Relation Represents a Function

A relation is a set of ordered pairs. The set of the first components of each ordered pair is called the domain and the set of the second components of each ordered pair is called the range. Consider the following set of ordered pairs. The first numbers in each pair are the first five natural numbers. The second number in each pair is twice that of the first.

$$\{(1,2),(2,4),(3,6),(4,8),(5,10)\} \tag{1.1.1}$$

The domain is $\{1,2,3,4,5\}$ The range is $\{2,4,6,8,10\}$

Note that each value in the domain is also known as an **input** value, or **independent variable**, and is often labeled with the lowercase letter $x$. Each value in the range is also known as an output value, or **dependent variable**, and is often labeled lowercase letter $y$.

A function $f$ is a relation that assigns a single value in the range to each value in the domain. In other words, no $x$-values are repeated. For our example that relates the first five **natural numbers** to numbers double their values, this relation is a function because each element in the domain, {1, 2, 3, 4, 5}, is paired with exactly one element in the range, $\{2,4,6,8,10\}$

Now let's consider the set of ordered pairs that relates the terms "even" and "odd" to the first five natural numbers. It would appear as

$$\{(\text{odd},1),(\text{even},2),(\text{odd},3),(\text{even},4),(\text{odd},5)\} \tag{1.1.2}$$

Notice that each element in the domain, {even, odd} is not paired with exactly one element in the range, $\{1,2,3,4,5\}$ For example, the term "odd" corresponds to three values from the range, $\{1,3,5\}$,and the term "even" corresponds to two values from the range, $\{2,4\}$. This violates the definition of a function, so this relation is not a function.

Figure $3.2.1$ compares relations that are functions and not functions.





Figure 3.2.1: (a) This relationship is a function because each input is associated with a single output. Note that input $q$ and $r$ both give output $n$. (b) This relationship is also a function. In this case, each input is associated with a single output. (c) This relationship is not a function because input $q$ is associated with two different outputs.

## Function

A **function** is a relation in which each possible input value leads to exactly one output value. We say "the output is a function of the input."

The **input** values make up the **domain**, and the **output** values make up the **range**.

## How To: Given a relationship between two quantities, determine whether the relationship is a function

1. Identify the input values.
2. Identify the output values.
3. If each input value leads to only one output value, classify the relationship as a function. If any input value leads to two or more outputs, do not classify the relationship as a function.

## Example 3.2.1: Determining If Menu Price Lists Are Functions

The coffee shop menu, shown in Figure 3.2.2 consists of items and their prices.

a. Is price a function of the item?
b. Is the item a function of the price?





Figure 3.2.2: A menu of donut prices from a coffee shop where a plain donut is $1.49 and a jelly donut and chocolate donut are $1.99.

**Solution**

a. Let's begin by considering the input as the items on the menu. The output values are then the prices. See Figure 3.2.3.




Figure 3.2.3: A menu of donut prices from a coffee shop where a plain donut is $1.49 and a jelly donut and chocolate donut are $1.99.

Each item on the menu has only one price, so the price is a function of the item.

a. Two items on the menu have the same price. If we consider the prices to be the input values and the items to be the output, then the same input value could have more than one output associated with it. See Figure 3.2.4.





Figure 3.2.4: Association of the prices to the donuts.

Therefore, the item is a not a function of price.

## Example 3.2.2: Determining If Class Grade Rules Are Functions

In a particular math class, the overall percent grade corresponds to a grade point average. Is grade point average a function of the percent grade? Is the percent grade a function of the grade point average? Table 3.2.1 shows a possible rule for assigning grade points.

Table 3.2.1: Class grade points.

| **Percent grade** | 0–56 | 57–61 | 62–66 | 67–71 | 72–77 | 78–86 | 87–91 | 92–100 |
|---|---|---|---|---|---|---|---|---|
| **Grade point average** | 0.0 | 1.0 | 1.5 | 2.0 | 2.5 | 3.0 | 3.5 | 4.0 |

**Solution**

For any percent grade earned, there is an associated grade point average, so the grade point average is a function of the percent grade. In other words, if we input the percent grade, the output is a specific grade point average.

In the grading system given, there is a range of percent grades that correspond to the same grade point average. For example, students who receive a grade point average of 3.0 could have a variety of percent grades ranging from 78 all the way to 86. Thus, percent grade is not a function of grade point average.

## Exercise 3.2.2

Table 3.2.2 lists the five greatest baseball players of all time in order of rank.

Table 3.2.2: Five greatest baseball players.

| Player | Rank |
|---|---|
| Babe Ruth | 1 |
| Willie Mays | 2 |
| Ty Cobb | 3 |
| Walter Johnson | 4 |
| Hank Aaron | 5 |

a. Is the rank a function of the player name?
b. Is the player name a function of the rank?

**Answer a**

Yes

**Answer b**

yes. (Note: If two players had been tied for, say, 4th place, then the name would not have been a function of rank.)

## Using Function Notation

Once we determine that a relationship is a function, we need to display and define the functional relationships so that we can understand and use them, and sometimes also so that we can program them into computers. There are various ways of representing functions. A standard function notation is one representation that facilitates working with functions.

To represent "height is a function of age," we start by identifying the descriptive variables $h$ for height and $a$ for age. The letters $f$, $g$,and $h$ are often used to represent functions just as we use $x$, $y$,and $z$ to represent numbers and $A$, $B$, and $C$ to represent sets.

$$\begin{aligned} &h \text{ is } f \text{ of } a && \text{We name the function } f\text{; height is a function of age.} \\ &h = f(a) && \text{We use parentheses to indicate the function input.} \\ &f(a) && \text{We name the function } f \text{ ; the expression is read as "} f \text{ of } a\text{."} \end{aligned} \tag{3.2.1}$$

Remember, we can use any letter to name the function; the notation $h(a)$ shows us that $h$ depends on $a$. The value $a$ must be put into the function $h$ to get a result. The parentheses indicate that age is input into the function; they do not indicate multiplication.

We can also give an algebraic expression as the input to a function. For example $f(a+b)$ means "first add $a$ and $b$, and the result is the input for the function $f$." The operations must be performed in this order to obtain the correct result.

### Function Notation

The notation $y = f(x)$ defines a function named $f$. This is read as "$y$ is a function of $x$." The letter $x$ represents the input value, or independent variable. The letter $y$, or $f(x)$, represents the output value, or dependent variable.

### Example 3.2.3: Using Function Notation for Days in a Month

Use function notation to represent a function whose input is the name of a month and output is the number of days in that month.

**Solution**

Using Function Notation for Days in a Month

Use function notation to represent a function whose input is the name of a month and output is the number of days in that month.

The number of days in a month is a function of the name of the month, so if we name the function $f$, we write days $= f(\text{month})$ or $d = f(m)$. The name of the month is the input to a "rule" that associates a specific number (the output) with each input.





Figure 3.2.5: The function $31 = f(January)$ where 31 is the output, f is the rule, and January is the input.

For example, $f(\text{March}) = 31$, because March has 31 days. The notation $d = f(m)$ reminds us that the number of days, $d$ (the output), is dependent on the name of the month, $m$ (the input).

**Analysis**

Note that the inputs to a function do not have to be numbers; function inputs can be names of people, labels of geometric objects, or any other element that determines some kind of output. However, most of the functions we will work with in this book will have numbers as inputs and outputs.

### Example 3.2.3B: Interpreting Function Notation

A function $N = f(y)$ gives the number of police officers, $N$, in a town in year $y$. What does $f(2005) = 300$ represent?

**Solution**

When we read $f(2005) = 300$, we see that the input year is 2005. The value for the output, the number of police officers $(N)$, is 300. Remember, $N = f(y)$. The statement $f(2005) = 300$ tells us that in the year 2005 there were 300 police officers in the town.

### Exercise 3.2.3

Use function notation to express the weight of a pig in pounds as a function of its age in days $d$.

**Answer**

$w = f(d)$

### Q&A

Instead of a notation such as $y = f(x)$, could we use the same symbol for the output as for the function, such as $y = y(x)$, meaning "$y$ is a function of $x$?"

*Yes, this is often done, especially in applied subjects that use higher math, such as physics and engineering. However, in exploring math itself we like to maintain a distinction between a function such as $f$, which is a rule or procedure, and the output $y$ we get by applying $f$ to a particular input $x$. This is why we usually use notation such as $y = f(x), P = W(d)$, and so on.*

## Representing Functions Using Tables

A common method of representing functions is in the form of a table. The table rows or columns display the corresponding input and output values. In some cases, these values represent all we know about the relationship; other times, the table provides a few select examples from a more complete relationship.

Table 3.2.3 lists the input number of each month ($\text{January} = 1$, $\text{February} = 2$, and so on) and the output value of the number of days in that month. This information represents all we know about the months and days for a given year (that is not a leap year). Note that, in this table, we define a days-in-a-month function $f$ where $D = f(m)$ identifies months by an integer rather than by name.

Table 3.2.3: Months and number of days per month.

| **Month number, $m$ (input)** | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 |
|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **Days in month, $D$ (output)** | 31 | 28 | 31 | 30 | 31 | 30 | 31 | 31 | 30 | 31 | 30 | 31 |

Table 3.2.4 defines a function $Q = g(n)$ Remember, this notation tells us that $g$ is the name of the function that takes the input $n$ and gives the output $Q$.

Table 3.2.4: Function $Q = g(n)$

| $n$ | 1 | 2 | 3 | 4 | 5 |
|---|---|---|---|---|---|
| $Q$ | 8 | 6 | 7 | 6 | 8 |

Table 3.2.5 displays the age of children in years and their corresponding heights. This table displays just some of the data available for the heights and ages of children. We can see right away that this table does not represent a function because the same input value, 5 years, has two different output values, 40 in. and 42 in.

Table 3.2.5: Age of children and their corresponding heights.

| **Age in years, $a$ (input)** | 5 | 5 | 6 | 7 | 8 | 9 | 10 |
|---|---|---|---|---|---|---|---|
| **Height in inches, $h$ (output)** | 40 | 42 | 44 | 47 | 50 | 52 | 54 |

**How To: Given a table of input and output values, determine whether the table represents a function**

1. Identify the input and output values.
2. Check to see if each input value is paired with only one output value. If so, the table represents a function.

**Example 3.2.5: Identifying Tables that Represent Functions**

Which table, Table 3.2.6, Table 3.2.7, or Table 3.2.8, represents a function (if any)?

Table 3.2.6

| Input | Output |
|---|---|
| 2 | 1 |
| 5 | 3 |
| 8 | 6 |

Table 3.2.7

| Input | Output |
|---|---|
| -3 | 5 |
| 0 | 1 |
| 4 | 5 |

Table 3.2.8

| Input | Output |
|---|---|
| 1 | 0 |
| 5 | 2 |
| 5 | 4 |

**Solution**

Table 3.2.6 and Table 3.2.7 define functions. In both, each input value corresponds to exactly one output value. Table 3.2.8 does not define a function because the input value of 5 corresponds to two different output values.

When a table represents a function, corresponding input and output values can also be specified using function notation.

The function represented by Table 3.2.6 can be represented by writing

$$f(2) = 1,\ f(5) = 3, \text{ and } f(8) = 6$$

Similarly, the statements

$$g(-3) = 5,\ g(0) = 1, \text{ and } g(4) = 5$$

represent the function in Table 3.2.7.

Table 3.2.8 cannot be expressed in a similar way because it does not represent a function.

**Exercise 3.2.5**

Does Table 3.2.9 represent a function?

Table 3.2.9

| Input | Output |
|---|---|
| 1 | 10 |
| 2 | 100 |
| 3 | 1000 |

**Answer**

yes

## Finding Input and Output Values of a Function

When we know an input value and want to determine the corresponding output value for a function, we evaluate the function. Evaluating will always produce one result because each input value of a function corresponds to exactly one output value.

When we know an output value and want to determine the input values that would produce that output value, we set the output equal to the function's formula and solve for the input. Solving can produce more than one solution because different input values can produce the same output value.

### Evaluation of Functions in Algebraic Forms

When we have a function in formula form, it is usually a simple matter to evaluate the function. For example, the function $f(x) = 5 - 3x^2$ can be evaluated by squaring the input value, multiplying by 3, and then subtracting the product from 5.

**How To: Given the formula for a function, evaluate.**

Given the formula for a function, evaluate.

1. Replace the input variable in the formula with the value provided.
2. Calculate the result.

**Example 3.2.6A: Evaluating Functions at Specific Values**

1. Evaluate $f(x) = x^2 + 3x - 4$ at
   a. $2$
   b. $a$
   c. $a + h$
   d. Evaluate $\frac{f(a+h) - f(a)}{h}$

**Solution**

Replace the x in the function with each specified value.

a. Because the input value is a number, 2, we can use simple algebra to simplify.

$$\begin{aligned} f(2) &= 2^2 + 3(2) - 4 \\ &= 4 + 6 - 4 \\ &= 6 \end{aligned}$$

b. In this case, the input value is a letter so we cannot simplify the answer any further.

$$f(a) = a^2 + 3a - 4$$

c. With an input value of $a+h$, we must use the distributive property.

$$\begin{aligned} f(a+h) &= (a+h)^2 + 3(a+h) - 4 \\ &= a^2 + 2ah + h^2 + 3a + 3h - 4 \end{aligned}$$

d. In this case, we apply the input values to the function more than once, and then perform algebraic operations on the result. We already found that

$$f(a+h) = a^2 + 2ah + h^2 + 3a + 3h - 4$$

and we know that

$$f(a) = a^2 + 3a - 4$$

Now we combine the results and simplify.

$$\begin{aligned} \frac{f(a+h) - f(a)}{h} &= \frac{(a^2 + 2ah + h^2 + 3a + 3h - 4) - (a^2 + 3a - 4)}{h} \\ &= \frac{(2ah + h^2 + 3h)}{h} \\ &= \frac{h(2a + h + 3)}{h} && \text{Factor out h.} \\ &= 2a + h + 3 && \text{Simplify.} \end{aligned}$$

## Example 3.2.6$B$: Evaluating Functions

Given the function $h(p) = p^2 + 2p$, evaluate $h(4)$.

**Solution**

To evaluate $h(4)$, we substitute the value 4 for the input variable p in the given function.

$$\begin{aligned} h(p) &= p^2 + 2p \\ h(4) &= (4)^2 + 2(4) \\ &= 16 + 8 \\ &= 24 \end{aligned}$$

Therefore, for an input of 4, we have an output of 24.

## Exercise 3.2.6

Given the function $g(m) = \sqrt{m-4}$, evaluate $g(5)$.

**Answer**

$g(5) = 1$

## Example 3.2.7: Solving Functions

Given the function $h(p) = p^2 + 2p$, solve for $h(p) = 3$.

**Solution**


$$\begin{aligned} h(p) &= 3 \\ p^2+2p &= 3 \quad \text{Substitute the original function} \\ p^2+2p-3 &= 0 \quad \text{Subtract 3 from each side.} \\ (p+3)(p-1) &= 0 \quad \text{Factor.} \end{aligned}$$

If $(p+3)(p-1)=0$ , either $(p+3)=0$ or $(p-1)=0$ (or both of them equal 0). We will set each factor equal to 0 and solve for $p$ in each case.

$$(p+3)=0,\ p=-3$$

$$(p-1)=0,\ p=1$$

This gives us two solutions. The output $h(p)=3$ when the input is either $p=1$ or $p=-3$. We can also verify by graphing as in Figure 3.2.6. The graph verifies that $h(1)=h(-3)=3$ and $h(4)=24$.




| p | −3 | −2 | 0 | 1 | 4 |
|---|---|---|---|---|---|
| h(p) | 3 | 0 | 0 | 3 | 24 |

Figure 3.2.6: Graph of $h(p)=p^2+2p$

**Exercise 3.2.7**

Given the function $g(m)=\sqrt{m-4}$ , solve $g(m)=2$.

**Answer**

$m=8$

## Evaluating Functions Expressed in Formulas

Some functions are defined by mathematical rules or procedures expressed in **equation** form. If it is possible to express the function output with a formula involving the input quantity, then we can define a function in algebraic form. For example, the equation $2n+6p=12$ expresses a functional relationship between $n$ and $p$. We can rewrite it to decide if $p$ is a function of $n$.

**How to: Given a function in equation form, write its algebraic formula.**

1. Solve the equation to isolate the output variable on one side of the equal sign, with the other side as an expression that involves only the input variable.
2. Use all the usual algebraic methods for solving equations, such as adding or subtracting the same quantity to or from both sides, or multiplying or dividing both sides of the equation by the same quantity.

### Example 3.2.8$A$: Finding an Equation of a Function

Express the relationship $2n+6p=12$ as a function $p=f(n)$, if possible.

**Solution**

To express the relationship in this form, we need to be able to write the relationship where $p$ is a function of $n$, which means writing it as $p=[\text{expression involving } n]$.

$$\begin{aligned} 2n+6p &= 12 \\ 6p &= 12-2n && \text{Subtract 2n from both sides.} \\ p &= \frac{12-2n}{6} && \text{Divide both sides by 6 and simplify.} \\ p &= \frac{12}{6}-\frac{2n}{6} \\ p &= 2-\frac{1}{3}n \end{aligned}$$

Therefore, $p$ as a function of $n$ is written as

$$p=f(n)=2-\frac{1}{3}n$$

**Analysis**

It is important to note that not every relationship expressed by an equation can also be expressed as a function with a formula.

### Example 3.2.8$B$: Expressing the Equation of a Circle as a Function

Does the equation $x^2+y^2=1$ represent a function with $x$ as input and $y$ as output? If so, express the relationship as a function $y=f(x)$.

**Solution**

First we subtract $x^2$ from both sides.

$$y^2=1-x^2$$

We now try to solve for $y$ in this equation.

$$y=\pm\sqrt{1-x^2}$$

$$\text{so, } y=\sqrt{1-x^2} \text{ and } y=-\sqrt{1-x^2}$$

We get two outputs corresponding to the same input, so this relationship cannot be represented as a single function $y=f(x)$.

### Exercise 3.2.8

If $x-8y^3=0$, express $y$ as a function of $x$.

**Answer**

$$y=f(x)=\frac{\sqrt[3]{x}}{2}$$

### Q & A

Are there relationships expressed by an equation that do represent a function but which still cannot be represented by an algebraic formula?

Yes, this can happen. For example, given the equation $x=y+2^y$, if we want to express y as a function of x, there is no simple algebraic formula involving only $x$ that equals $y$. However, each $x$ does determine a unique value for $y$, and there are

mathematical procedures by which $y$ can be found to any desired accuracy. In this case, we say that the equation gives an implicit (implied) rule for $y$ as a function of $x$, even though the formula cannot be written explicitly.

## Evaluating a Function Given in Tabular Form

As we saw above, we can represent functions in tables. Conversely, we can use information in tables to write functions, and we can evaluate functions using the tables. For example, how well do our pets recall the fond memories we share with them? There is an urban legend that a goldfish has a memory of 3 seconds, but this is just a myth. Goldfish can remember up to 3 months, while the beta fish has a memory of up to 5 months. And while a puppy's memory span is no longer than 30 seconds, the adult dog can remember for 5 minutes. This is meager compared to a cat, whose memory span lasts for 16 hours.

The function that relates the type of pet to the duration of its memory span is more easily visualized with the use of a table (Table 3.2.10).

Table 3.2.10

| Pet Memory | span in hours |
|---|---|
| Puppy | 0.008 |
| Adult Dog | 0.083 |
| Cat | 3 |
| Goldfish | 2160 |
| Beta Fish | 3600 |

At times, evaluating a function in table form may be more useful than using equations. Here let us call the function $P$. The domain of the function is the type of pet and the range is a real number representing the number of hours the pet's memory span lasts. We can evaluate the function $P$ at the input value of "goldfish." We would write $P(goldfish) = 2160$. Notice that, to evaluate the function in table form, we identify the input value and the corresponding output value from the pertinent row of the table. The tabular form for function P seems ideally suited to this function, more so than writing it in paragraph or function form.

### How To: Given a function represented by a table, identify specific output and input values

1. Find the given input in the row (or column) of input values.
2. Identify the corresponding output value paired with that input value.
3. Find the given output values in the row (or column) of output values, noting every time that output value appears.
4. Identify the input value(s) corresponding to the given output value.

### Example 3.2.9: Evaluating and Solving a Tabular Function

Using Table 3.2.11,

a. Evaluate $g(3)$.
b. Solve $g(n) = 6$.

Table 3.2.11

| $n$ | 1 | 2 | 3 | 4 | 5 |
|---|---|---|---|---|---|
| $g(n)$ | 8 | 6 | 7 | 6 | 8 |

**Solution**

a. Evaluating $g(3)$ means determining the output value of the function $g$ for the input value of $n = 3$. The table output value corresponding to $n = 3$ is 7, so $g(3) = 7$.
b. Solving $g(n) = 6$ means identifying the input values, n,that produce an output value of 6. Table 3.2.12 shows two solutions: 2 and 4.

Table 3.2.12

| $n$ | 1 | 2 | 3 | 4 | 5 |
|---|---|---|---|---|---|
| $g(n)$ | 8 | 6 | 7 | 6 | 8 |

When we input 2 into the function $g$, our output is 6. When we input 4 into the function $g$, our output is also 6.

**Exercise 3.2.1**

Using Table 3.2.12, evaluate $g(1)$.

**Answer**

$g(1) = 8$

## Finding Function Values from a Graph

Evaluating a function using a graph also requires finding the corresponding output value for a given input value, only in this case, we find the output value by looking at the graph. Solving a function equation using a graph requires finding all instances of the given output value on the graph and observing the corresponding input value(s).

**Example 3.2.10: Reading Function Values from a Graph**

Given the graph in Figure 3.2.7,

a. Evaluate $f(2)$.
b. Solve $f(x) = 4$.






Figure 3.2.7: Graph of a positive parabola centered at $(1, 0)$.

**Solution**

To evaluate $f(2)$, locate the point on the curve where $x = 2$, then read the y-coordinate of that point. The point has coordinates $(2, 1)$, so $f(2) = 1$. See Figure 3.2.8.




3.2.8: Graph of a positive parabola centered at $(1,0)$ with the labeled point $(2,1)$ where $f(2)=1$.

To solve $f(x)=4$, we find the output value 4 on the vertical axis. Moving horizontally along the line $y=4$, we locate two points of the curve with output value 4: $(-1,4)$ and $(3,4)$. These points represent the two solutions to $f(x)=4$: $-1$ or 3. This means $f(-1)=4$ and $f(3)=4$, or when the input is $-1$ or 3, the output is 4. See Figure 3.2.9.





Figure 3.2.9: Graph of an upward-facing parabola with a vertex at $(0,1)$ and labeled points at $(-1,4)$ and $(3,4)$. A line at $y=4$ intersects the parabola at the labeled points.

**Exercise 3.2.10**

Given the graph in Figure 3.2.7, solve $f(x)=1$.

**Answer**

$x=0$ or $x=2$

## Determining Whether a Function is One-to-One

Some functions have a given output value that corresponds to two or more input values. For example, in the stock chart shown in the Figure at the beginning of this chapter, the stock price was $1000 on five different dates, meaning that there were five different input values that all resulted in the same output value of $1000.

However, some functions have only one input value for each output value, as well as having only one output for each input. We call these functions one-to-one functions. As an example, consider a school that uses only letter grades and decimal equivalents, as listed in Table 3.2.13.

Table 3.2.13: Letter grades and decimal equivalents.

| Letter Grade | Grade Point Average |
|---|---|
| A | 4.0 |
| B | 3.0 |
| C | 2.0 |
| D | 1.0 |

This grading system represents a one-to-one function, because each letter input yields one particular grade point average output and each grade point average corresponds to one input letter.

To visualize this concept, let's look again at the two simple functions sketched in Figures 3.2.1a and 3.2.1b. The function in part (a) shows a relationship that is not a one-to-one function because inputs $q$ and $r$ both give output $n$. The function in part (b) shows a relationship that is a one-to-one function because each input is associated with a single output.

### One-to-One Functions

A **one-to-one function** is a function in which each output value corresponds to exactly one input value.

### Example 3.2.11: Determining Whether a Relationship Is a One-to-One Function

Is the area of a circle a function of its radius? If yes, is the function one-to-one?

**Solution**

A circle of radius $r$ has a unique area measure given by $A = \pi r^2$, so for any input, $r$, there is only one output, $A$. The area is a function of radius $r$.

If the function is one-to-one, the output value, the area, must correspond to a unique input value, the radius. Any area measure $A$ is given by the formula $A = \pi r^2$. Because areas and radii are positive numbers, there is exactly one solution: $\sqrt{\frac{A}{\pi}}$. So the area of a circle is a one-to-one function of the circle's radius.

### Exercise 3.2.11A

a. Is a balance a function of the bank account number?
b. Is a bank account number a function of the balance?
c. Is a balance a one-to-one function of the bank account number?

**Answer**

a. yes, because each bank account has a single balance at any given time;

b. no, because several bank account numbers may have the same balance;

c. no, because the same output may correspond to more than one input.

### Exercise 3.2.11B

Evaluate the following:

a. If each percent grade earned in a course translates to one letter grade, is the letter grade a function of the percent grade?
b. If so, is the function one-to-one?

**Answer**

a. Yes, letter grade is a function of percent grade;
b. No, it is not one-to-one. There are 100 different percent numbers we could get but only about five possible letter grades, so there cannot be only one percent number that corresponds to each letter grade.

## Using the Vertical Line Test

As we have seen in some examples above, we can represent a function using a graph. Graphs display a great many input-output pairs in a small space. The visual information they provide often makes relationships easier to understand. By convention, graphs are typically constructed with the input values along the horizontal axis and the output values along the vertical axis.

The most common graphs name the input value $x$ and the output $y$, and we say $y$ is a function of $x$, or $y = f(x)$ when the function is named $f$. The graph of the function is the set of all points $(x, y)$ in the plane that satisfies the equation $y = f(x)$. If the function is defined for only a few input values, then the graph of the function is only a few points, where the x-coordinate of each point is an input value and the y-coordinate of each point is the corresponding output value. For example, the black dots on the graph in Figure 3.2.10 tell us that $f(0) = 2$ and $f(6) = 1$. However, the set of all points $(x, y)$ satisfying $y = f(x)$ is a curve. The curve shown includes $(0, 2)$ and $(6, 1)$ because the curve passes through those points





Figure 3.2.10: Graph of a polynomial.

The vertical line test can be used to determine whether a graph represents a function. If we can draw any vertical line that intersects a graph more than once, then the graph does not define a function because a function has only one output value for each input value. See Figure 3.2.11.





Figure 3.2.11: Three graphs visually showing what is and is not a function.

**Howto: Given a graph, use the vertical line test to determine if the graph represents a function**

1. Inspect the graph to see if any vertical line drawn would intersect the curve more than once.
2. If there is any such line, determine that the graph does not represent a function.

## Example 3.2.12: Applying the Vertical Line Test

Which of the graphs in Figure 3.2.12 represent(s) a function $y = f(x)$?





Figure 3.2.12: Graph of a polynomial (a), a downward-sloping line (b), and a circle (c).

**Solution**

If any vertical line intersects a graph more than once, the relation represented by the graph is not a function. Notice that any vertical line would pass through only one point of the two graphs shown in parts (a) and (b) of Figure 3.2.12 From this we can conclude that these two graphs represent functions. The third graph does not represent a function because, at most x-values, a vertical line would intersect the graph at more than one point, as shown in Figure 3.2.13





Figure 3.2.13: Graph of a circle.

## Exercise 3.2.12

Does the graph in Figure 3.2.14 represent a function?


https://math.libretexts.org/@go/page/96261





Figure 3.2.14: Graph of absolute value function.

**Answer**

yes

## Using the Horizontal Line Test

Once we have determined that a graph defines a function, an easy way to determine if it is a one-to-one function is to use the **horizontal line test**. Draw horizontal lines through the graph. If any horizontal line intersects the graph more than once, then the graph does not represent a one-to-one function.

### Howto: Given a graph of a function, use the horizontal line test to determine if the graph represents a one-to-one function

1. Inspect the graph to see if any horizontal line drawn would intersect the curve more than once.
2. If there is any such line, determine that the function is not one-to-one.

### Example 3.2.13: Applying the Horizontal Line Test

Consider the functions shown in Figure $3.2.12a$ and Figure $3.2.12b$ Are either of the functions one-to-one?

**Solution**

The function in Figure $3.2.12a$ is not one-to-one. The horizontal line shown in Figure $3.2.15$ intersects the graph of the function at two points (and we can even find horizontal lines that intersect it at three points.)





Figure 3.2.15: Graph of a polynomial with a horizontal line crossing through 2 points

The function in Figure $3.2.12b$is one-to-one. Any horizontal line will intersect a diagonal line at most once.

**Exercise 3.2.13**

Is the graph shown in Figure $3.2.13$one-to-one?

**Answer**


No, because it does not pass the horizontal line test.







## Identifying Basic Toolkit Functions



In this text, we will be exploring functions—the shapes of their graphs, their unique characteristics, their algebraic formulas, and how to solve problems with them. When learning to read, we start with the alphabet. When learning to do arithmetic, we start with numbers. When working with functions, it is similarly helpful to have a base set of building-block elements. We call these our "toolkit functions," which form a set of basic named functions for which we know the graph, formula, and special properties. Some of these functions are programmed to individual buttons on many calculators. For these definitions we will use x as the input variable and $y = f(x)$ as the output variable.

We will see these toolkit functions, combinations of toolkit functions, their graphs, and their transformations frequently throughout this book. It will be very helpful if we can recognize these toolkit functions and their features quickly by name, formula, graph, and basic table properties. The graphs and sample table values are included with each function shown in Table $3.2.14$

Table 3.2.14: Toolkit Functions

| Name | Function | Graph |
|---|---|---|
| Constant | $f(x) = c$ where $c$ is a constant |   <table><tr><th>x</th><th>f(x)</th></tr><tr><td>−2</td><td>2</td></tr><tr><td>0</td><td>2</td></tr><tr><td>2</td><td>2</td></tr></table> |

| Name | Function | Graph |
|---|---|---|
| Identity | $f(x) = x$ |   <table><tr><th>x</th><th>f(x)</th></tr><tr><td>−2</td><td>−2</td></tr><tr><td>0</td><td>0</td></tr><tr><td>2</td><td>2</td></tr></table> |
| Absolute Value | $f(x) = \lvert x \rvert$ |   <table><tr><th>x</th><th>f(x)</th></tr><tr><td>−2</td><td>2</td></tr><tr><td>0</td><td>0</td></tr><tr><td>2</td><td>2</td></tr></table> |
| Quadratic | $f(x) = x^2$ |   <table><tr><th>x</th><th>f(x)</th></tr><tr><td>−2</td><td>4</td></tr><tr><td>−1</td><td>1</td></tr><tr><td>0</td><td>0</td></tr><tr><td>1</td><td>1</td></tr><tr><td>2</td><td>4</td></tr></table> |
| Cubic | $f(x) = x^3$ |   <table><tr><th>x</th><th>f(x)</th></tr><tr><td>−1</td><td>−1</td></tr><tr><td>−0.5</td><td>−0.125</td></tr><tr><td>0</td><td>0</td></tr><tr><td>0.5</td><td>0.125</td></tr><tr><td>1</td><td>1</td></tr></table> |
| reciprocal | $f(x) = \frac{1}{x}$ |   <table><tr><th>x</th><th>f(x)</th></tr><tr><td>−2</td><td>−0.5</td></tr><tr><td>−1</td><td>−1</td></tr><tr><td>−0.5</td><td>−2</td></tr><tr><td>0.5</td><td>2</td></tr><tr><td>1</td><td>1</td></tr><tr><td>2</td><td>0.5</td></tr></table> |
| Reciprocal squared | $f(x) = \frac{1}{x^2}$ |   <table><tr><th>x</th><th>f(x)</th></tr><tr><td>−2</td><td>0.25</td></tr><tr><td>−1</td><td>1</td></tr><tr><td>−0.5</td><td>4</td></tr><tr><td>0.5</td><td>4</td></tr><tr><td>1</td><td>1</td></tr><tr><td>2</td><td>0.25</td></tr></table> |

| Name | Function | Graph |
|---|---|---|
| Square root | $f(x) = \sqrt{x}$ |   <table><tr><th>x</th><th>f(x)</th></tr><tr><td>0</td><td>0</td></tr><tr><td>1</td><td>1</td></tr><tr><td>4</td><td>2</td></tr></table> |
| Cube root | $f(x) = \sqrt[3]{x}$ |   <table><tr><th>x</th><th>f(x)</th></tr><tr><td>−1</td><td>−1</td></tr><tr><td>−0.125</td><td>−0.5</td></tr><tr><td>0</td><td>0</td></tr><tr><td>0.125</td><td>0.5</td></tr><tr><td>1</td><td>1</td></tr></table> |

## Key Equations

- Constant function $f(x) = c$, where $c$ is a constant
- Identity function $f(x) = x$
- Absolute value function $f(x) = |x|$
- Quadratic function $f(x) = x^2$
- Cubic function $f(x) = x^3$
- Reciprocal function $f(x) = \dfrac{1}{x}$
- Reciprocal squared function $f(x) = \frac{1}{x^2}$
- Square root function $f(x) = \sqrt{x}$
- Cube root function $f(x) = 3\sqrt{x}$

## Key Concepts

- A relation is a set of ordered pairs. A function is a specific type of relation in which each domain value, or input, leads to exactly one range value, or output.
- Function notation is a shorthand method for relating the input to the output in the form $y = f(x)$.
- In tabular form, a function can be represented by rows or columns that relate to input and output values.
- To evaluate a function, we determine an output value for a corresponding input value. Algebraic forms of a function can be evaluated by replacing the input variable with a given value.
- To solve for a specific function value, we determine the input values that yield the specific output value.
- An algebraic form of a function can be written from an equation.
- Input and output values of a function can be identified from a table.
- Relating input values to output values on a graph is another way to evaluate a function.
- A function is one-to-one if each output value corresponds to only one input value.
- A graph represents a function if any vertical line drawn on the graph intersects the graph at no more than one point.
- The graph of a one-to-one function passes the horizontal line test.

## Footnotes

1 http://www.baseball-almanac.com/lege.../lisn100.shtml. Accessed 3/24/2014.
2 www.kgbanswers.com/how-long-i...y-span/4221590. Accessed 3/24/2014.

## Glossary

**dependent variable**
an output variable

**domain**
the set of all possible input values for a relation

**function**
a relation in which each input value yields a unique output value

**horizontal line test**
a method of testing whether a function is one-to-one by determining whether any horizontal line intersects the graph more than once

**independent variable**
an input variable

**input**
each object or value in a domain that relates to another object or value by a relationship known as a function

**one-to-one function**
a function for which each value of the output is associated with a unique input value

**output**
each object or value in the range that is produced when an input value is entered into a function

**range**
the set of output values that result from the input values in a relation

**relation**
a set of ordered pairs

**vertical line test**
a method of testing whether a graph represents a function by determining whether a vertical line intersects the graph no more than once

---


This page titled 3.2: Functions and Function Notation is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.1: Functions and Function Notation** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.2E: Functions and Function Notation (Exercises)

For the following exercises, determine whether the relation is a function.

1. $\{(a,b),(c,d),(e,d)\}$
2. \{(5,2),(6,1),(6,2),(4,8)\}\)
3. $y^2+4=x,$ for $x$ the independent variable and $y$ the dependent variable
4. Is the graph in Figure 1 a function?




For the following exercises, evaluate the function at the indicated values:

$$f(-3);\quad f(2);\quad f(-a);\quad -f(a);\quad f(a+h).$$


5. $f(x)=-2x^2+3x$
6. $f(x)=2|3x-1|$

For the following exercises, determine whether the functions are one-to-one.


7. $f(x)=-3x+5$
8. $f(x)=|\,x-3$

For the following exercises, use the vertical line test to determine if the relation whose graph is provided is a function.


9.




10.





11.




For the following exercises, graph the functions.

12. $f(x) =\mid x+1$
13. $f(x) = x^2 - 2$

For the following exercises, use Figure 2 to approximate the values.




14. $f(2)$
15. $f(-2)$
16. If $f(x) = -2$, then solve for $x$.
17. If $f(x) = 1$, then solve for $x$.

For the following exercises, use the function $h(t) = -16t^2 + 80t$ to find the values in simplest form.

18. $\frac{h(2)-h(1)}{2-1}$
19. $\frac{h(a)-h(1)}{a-1}$

This page titled 3.2E: Functions and Function Notation (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.1E: Functions and Function Notation (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.3: Domain and Range

**Learning Objectives**

- Find the domain of a function defined by an equation.
- Graph piecewise-defined functions.

If you're in the mood for a scary movie, you may want to check out one of the five most popular horror movies of all time—I am Legend, Hannibal, The Ring, The Grudge, and The Conjuring. Figure 3.3.1 shows the amount, in dollars, each of those movies grossed when they were released as well as the ticket sales for horror movies in general by year. Notice that we can use the data to create a function of the amount each movie earned or the total ticket sales for all horror movies by year. In creating various functions using the data, we can identify different independent and dependent variables, and we can analyze the data and the functions to determine the domain and range. In this section, we will investigate methods for determining the domain and range of functions such as these.





Figure 3.3.1: Graph of the Top-Five Grossing Horror Movies for years 2000-2003, and a Graph of the Market Share of Horror Movies by Year. Based on data compiled by www.the-numbers.com.

## Finding the Domain of a Function Defined by an Equation

In Functions and Function Notation, we were introduced to the concepts of **domain and range**. In this section, we will practice determining domains and ranges for specific functions. Keep in mind that, in determining domains and ranges, we need to consider what is physically possible or meaningful in real-world examples, such as tickets sales and year in the horror movie example above. We also need to consider what is mathematically permitted. For example, we cannot include any input value that leads us to take an even root of a negative number if the domain and range consist of real numbers. Or in a function expressed as a formula, we cannot include any input value in the domain that would lead us to divide by 0.

We can visualize the domain as a "holding area" that contains "raw materials" for a "function machine" and the range as another "holding area" for the machine's products (Figure 3.3.2).





Figure 3.3.2: Diagram of how a function relates two relations

We can write the **domain and range** in **interval notation**, which uses values within brackets to describe a set of numbers. In interval notation, we use a square bracket [ when the set includes the endpoint and a parenthesis ( to indicate that the endpoint is either not included or the interval is unbounded. For example, if a person has $100 to spend, he or she would need to express the interval that is more than 0 and less than or equal to 100 and write $(0, 100]$. We will discuss interval notation in greater detail later.

Let's turn our attention to finding the domain of a function whose equation is provided. Oftentimes, finding the domain of such functions involves remembering three different forms. First, if the function has no denominator or an even root, consider whether the domain could be all real numbers. Second, if there is a denominator in the function's equation, exclude values in the domain that force the denominator to be zero. Third, if there is an even root, consider excluding values that would make the radicand negative.

Before we begin, let us review the conventions of interval notation:

- The smallest term from the interval is written first.
- The largest term in the interval is written second, following a comma.
- Parentheses, ( or ), are used to signify that an endpoint is not included, called exclusive.
- Brackets, [ or ], are used to indicate that an endpoint is included, called inclusive.

See Figure 3.3.3 for a summary of interval notation.

| Inequality | Interval Notation | Graph on Number Line | Description |
|---|---|---|---|
| $x > a$ | $(a, \infty)$ |   | $x$ is greater than $a$ |
| $x < a$ | $(-\infty, a)$ |   | $x$ is less than $a$ |
| $x \geq a$ | $[a, \infty)$ |   | $x$ is greater than or equal to $a$ |
| $x \leq a$ | $(-\infty, a]$ |   | $x$ is less than or equal to $a$ |
| $a < x < b$ | $(a, b)$ |   | $x$ is strictly between $a$ and $b$ |
| $a \leq x < b$ | $[a, b)$ |   | $x$ is between $a$ and $b$, to include $a$ |
| $a < x \leq b$ | $(a, b]$ |   | $x$ is between $a$ and $b$, to include $b$ |
| $a \leq x \leq b$ | $[a, b]$ |   | $x$ is between $a$ and $b$, to include $a$ and $b$ |

Figure 3.3.3: Summary of interval notation.

### Example 3.3.1: Finding the Domain of a Function as a Set of Ordered Pairs

Find the domain of the following function: $\{(2, 10), (3, 10), (4, 20), (5, 30), (6, 40)\}$

**Solution**

First identify the input values. The input value is the first coordinate in an ordered pair. There are no restrictions, as the ordered pairs are simply listed. The domain is the set of the first coordinates of the ordered pairs.

$$\{2, 3, 4, 5, 6\}$$

### Exercse 3.3.1

Find the domain of the function:

$$\{(-5, 4), (0, 0), (5, -4), (10, -8), (15, -12)\}$$

**Answer**

$\{-5, 0, 5, 10, 15\}$

### How To: Given a function written in equation form, find the domain.

1. Identify the input values.
2. Identify any restrictions on the input and exclude those values from the domain.
3. Write the domain in interval form, if possible.

### Example 3.3.2: Finding the Domain of a Function

Find the domain of the function $f(x) = x^2 - 1$ .

**Solution**

The input value, shown by the variable x in the equation, is squared and then the result is lowered by one. Any real number may be squared and then be lowered by one, so there are no restrictions on the domain of this function. The domain is the set of real numbers.

In interval form, the domain of f is $(-\infty, \infty)$.

### Exercse 3.3.2

Find the domain of the function:

$$f(x) = 5 - x + x^3$$

**Answer**

$(-\infty, \infty)$

### Howto: Given a function written in an equation form that includes a fraction, find the domain

1. Identify the input values.
2. Identify any restrictions on the input. If there is a denominator in the function's formula, set the denominator equal to zero and solve for x . If the function's formula contains an even root, set the radicand greater than or equal to 0, and then solve.
3. Write the domain in interval form, making sure to exclude any restricted values from the domain.

### Example 3.3.3: Finding the Domain of a Function Involving a Denominator


Find the domain of the function $f(x) = \dfrac{x+1}{2-x}$.

**Solution**

When there is a denominator, we want to include only values of the input that do not force the denominator to be zero. So, we will set the denominator equal to 0 and solve for x.

$$2-x=0$$
$$-x=-2$$
$$x=2$$

Now, we will exclude 2 from the domain. The answers are all real numbers where $x<2$ or $x>2$. We can use a symbol known as the union, $\cup$,to combine the two sets. In interval notation, we write the solution:$(-\infty,2)\cup(2,\infty)$.




In interval form, the domain of f is $(-\infty,2)\cup(2,\infty)$.

## Exercse 3.3.3

Find the domain of the function:

$$f(x)=\frac{1+4x}{2x-1}$$

**Answer**

$$(-\infty,\frac{1}{2})\cup(\frac{1}{2},\infty)$$

### How To: Given a function written in equation form including an even root, find the domain.

1. Identify the input values.
2. Since there is an even root, exclude any real numbers that result in a negative number in the radicand. Set the radicand greater than or equal to zero and solve for x.
3. The solution(s) are the domain of the function. If possible, write the answer in interval form.

## Example 3.3.4: Finding the Domain of a Function with an Even Root

Find the domain of the function:

$$f(x)=\sqrt{7-x}.$$

**Solution**

When there is an even root in the formula, we exclude any real numbers that result in a negative number in the radicand.

Set the radicand greater than or equal to zero and solve for x.

$$7-x\geq 0$$
$$-x\geq -7$$
$$x\leq 7$$

Now, we will exclude any number greater than 7 from the domain. The answers are all real numbers less than or equal to 7, or $(-\infty,7]$.

## Exercse 3.3.4

Find the domain of the function

$$f(x)=\sqrt{5+2x}.$$

**Answer**

$$[-2.5, \infty)$$

**Q&A: Can there be functions in which the domain and range do not intersect at all?**

Yes. For example, the function $f(x) = -\dfrac{1}{\sqrt{x}}$ *has the set of all positive real numbers as its domain but the set of all negative real numbers as its range. As a more extreme example, a function's inputs and outputs can be completely different categories (for example, names of weekdays as inputs and numbers as outputs, as on an attendance chart), in such cases the domain and range have no elements in common.*

## Using Notations to Specify Domain and Range

In the previous examples, we used inequalities and lists to describe the domain of functions. We can also use inequalities, or other statements that might define sets of values or data, to describe the behavior of the variable in set-builder notation. For example, $\{x|10 \leq x < 30\}$ describes the behavior of x in set-builder notation. The braces $\{\}$ are read as "the set of," and the vertical bar $|$ is read as "such that," so we would read $\{x|10 \leq x < 30\}$ as "the set of x-values such that 10 is less than or equal to x, and x is less than 30."

Figure $3.3.4$ compares inequality notation, set-builder notation, and interval notation.


| | Inequality Notation | Set-builder Notation | Interval Notation |
|---|---|---|---|
|  | $5 < h \leq 10$ | $\{h \mid 5 < h \leq 10\}$ | $(5, 10]$ |
|  | $5 \leq h < 10$ | $\{h \mid 5 \leq h < 10\}$ | $[5, 10)$ |
|  | $5 < h < 10$ | $\{h \mid 5 < h < 10\}$ | $(5, 10)$ |
|  | $h < 10$ | $\{h \mid h < 10\}$ | $(-\infty, 10)$ |
|  | $h \geq 10$ | $\{h \mid h \geq 10\}$ | $[10, \infty)$ |
|  | All real numbers | $\mathbb{R}$ | $(-\infty, \infty)$ |

Figure 3.3.4: Summary of notations for inequalities, set-builder, and interval.

To combine two intervals using inequality notation or set-builder notation, we use the word "or." As we saw in earlier examples, we use the union symbol, $\cup$,to combine two unconnected intervals. For example, the union of the sets $\{2, 3, 5\}$ and $\{4, 6\}$ is the set $\{2, 3, 4, 5, 6\}$. It is the set of all elements that belong to one or the other (or both) of the original two sets. For sets with a finite number of elements like these, the elements do not have to be listed in ascending order of numerical value. If the original two sets have some elements in common, those elements should be listed only once in the union set. For sets of real numbers on intervals, another example of a union is

$$\{x||x| \geq 3\} = (-\infty, -3] \cup [3, \infty) \tag{3.3.1}$$

## Set-Builder Notation and Interval Notation

*Set-builder notation* is a method of specifying a set of elements that satisfy a certain condition. It takes the form $\{x|$ statement about x$\}$ which is read as, "the set of all x such that the statement about x is true." For example,

$$\{x|4 < x \leq 12\}$$

*Interval notation* is a way of describing sets that include all real numbers between a lower limit that may or may not be included and an upper limit that may or may not be included. The endpoint values are listed between brackets or parentheses. A square bracket indicates inclusion in the set, and a parenthesis indicates exclusion from the set. For example,

$$(4, 12]$$

**How to: Given a line graph, describe the set of values using interval notation.**

1. Identify the intervals to be included in the set by determining where the heavy line overlays the real line.
2. At the left end of each interval, use [ with each end value to be included in the set (solid dot) or ( for each excluded end value (open dot).
3. At the right end of each interval, use ] with each end value to be included in the set (filled dot) or ) for each excluded end value (open dot).
4. Use the union symbol $\cup$ to combine all intervals into one set.

## Example 3.3.5: Describing Sets on the Real-Number Line

Describe the intervals of values shown in Figure 3.3.5 using inequality notation, set-builder notation, and interval notation.




Figure 3.3.5: Line graph of $1 \leq x \leq 3$ or $x > 5$ .

**Solution**

To describe the values, $x$, included in the intervals shown, we would say, "$x$ is a real number greater than or equal to 1 and less than or equal to 3, or a real number greater than 5."

Inequality

$$1 \leq x \leq 3 \text{ or } x > 5$$

Set-builder Notation

$$\{x|1 \leq x \leq 3 \text{ or } x > 5\}$$

Interval notation

$$[1, 3] \cup (5, \infty)$$

Remember that, when writing or reading interval notation, using a square bracket means the boundary is included in the set. Using a parenthesis means the boundary is not included in the set.

## Exercse 3.3.5

Given Figure 3.3.6, specify the graphed set in

a. words
b. set-builder notation
c. interval notation




Figure 3.3.6: Line graph of $-2 \leq x$, $-1 \leq x < 3$.leq}x\), $-1 \leq x < 3$.


https://math.libretexts.org/@go/page/96263

**Answer a**

Values that are less than or equal to –2, or values that are greater than or equal to –1 and less than 3;

**Answer b**

$\{x|x \leq -2 or -1 \leq x < 3\}$

**Answer c**

$(-\infty, -2] \cup [-1, 3)$

## Finding Domain and Range from Graphs

Another way to identify the domain and range of functions is by using graphs. Because the domain refers to the set of possible input values, the domain of a graph consists of all the input values shown on the x-axis. The range is the set of possible output values, which are shown on the y-axis. Keep in mind that if the graph continues beyond the portion of the graph we can see, the domain and range may be greater than the visible values. See Figure 3.3.7.





Figure 3.3.7: Graph of a polynomial that shows the x-axis is the domain and the y-axis is the range

We can observe that the graph extends horizontally from −5 to the right without bound, so the domain is $[-5, \infty)$. The vertical extent of the graph is all range values 5 and below, so the range is $(-\infty, 5]$. Note that the domain and range are always written from smaller to larger values, or from left to right for domain, and from the bottom of the graph to the top of the graph for range.

### Example 3.3.6A: Finding Domain and Range from a Graph

Find the domain and range of the function f whose graph is shown in Figure 1.2.8.





Figure 3.3.8: Graph of a function from (-3, 1].

**Solution**

We can observe that the horizontal extent of the graph is –3 to 1, so the domain of f is $(-3, 1]$.

The vertical extent of the graph is 0 to –4, so the range is $[-4, 0)$. See Figure 3.3.9.





Figure 3.3.9: Graph of the previous function shows the domain and range

## Example 3.3.6B: Finding Domain and Range from a Graph of Oil Production

Find the domain and range of the function f whose graph is shown in Figure 3.3.10.





Figure 3.3.10: Graph of the Alaska Crude Oil Production where the y-axis is thousand barrels per day and the -axis is the years(credit: modification of work by the U.S. Energy Information Administration)

**Solution**

The input quantity along the horizontal axis is “years,” which we represent with the variable t for time. The output quantity is “thousands of barrels of oil per day,” which we represent with the variable b for barrels. The graph may continue to the left and right beyond what is viewed, but based on the portion of the graph that is visible, we can determine the domain as $1973 \leq t \leq 2008$ and the range as approximately $180 \leq b \leq 2010$.

In interval notation, the domain is $[1973, 2008]$ and the range is about $[180, 2010]$. For the domain and the range, we approximate the smallest and largest values since they do not fall exactly on the grid lines.

**Exercse 3.3.6**

Given Figure 3.3.11, identify the domain and range using interval notation.





Figure 3.3.11: Graph of World Population Increase where the y-axis represents millions of people and the x-axis represents the year.

**Answer**

domain =$[1950, 2002]$


range = $[47,000,000, 89,000,000]$

**Can a function’s domain and range be the same?**

*Yes. For example, the domain and range of the cube root function are both the set of all real numbers.*

## Finding Domains and Ranges of the Toolkit Functions


We will now return to our set of toolkit functions to determine the domain and range of each.




Domain: $(-\infty, \infty)$
Range: $[c,c]$

Figure 3.3.12: Constant function $f(x) = c$.


For the **constant function** $f(x) = c$, the domain consists of all real numbers; there are no restrictions on the input. The only output value is the constant $c$, so the range is the set $\{c\}$ that contains this single element. In interval notation, this is written as $[c, c]$, the interval that both begins and ends with $c$.




Domain: $(-\infty, \infty)$
Range: $(-\infty, \infty)$

***Figure* 3.3.13:** *Identity function f(x)=x.*


For the **identity function** $f(x) = x$, there is no restriction on $x$. Both the domain and range are the set of all real numbers.




Domain: $(-\infty, \infty)$
Range: $[0, \infty)$

Figure 3.3.14: Absolute function $f(x) = |x|$.


For the **absolute value function** $f(x) = |x|$, there is no restriction on $x$. However, because absolute value is defined as a distance from 0, the output can only be greater than or equal to 0.




Domain: $(-\infty, \infty)$
Range: $[0, \infty)$

Figure 3.3.15: Quadratic function $f(x) = x^2$.


For the **quadratic function** $f(x) = x^2$, the domain is all real numbers since the horizontal extent of the graph is the whole real number line. Because the graph does not include any negative values for the range, the range is only nonnegative real numbers.




Domain: $(-\infty, \infty)$
Range: $(-\infty, \infty)$

Figure 3.3.16: Cubic function $f(x) - x^3$.


For the **cubic function** $f(x) = x^3$, the domain is all real numbers because the horizontal extent of the graph is the whole real number line. The same applies to the vertical extent of the graph, so the domain and range include all real numbers.




Domain: $(-\infty, 0) \cup (0, \infty)$
Range: $(-\infty, 0) \cup (0, \infty)$

Figure 3.3.17: Reciprocal function $f(x) = \frac{1}{x}$.


For the **reciprocal function** $f(x) = \frac{1}{x}$, we cannot divide by 0, so we must exclude 0 from the domain. Further, 1 divided by any value can never be 0, so the range also will not include 0. In set-builder notation, we could also write $\{x | x \neq 0\}$,the set of all real numbers that are not zero.




Domain: $(-\infty, 0) \cup (0, \infty)$
Range: $(0, \infty)$

Figure 3.3.18: Reciprocal squared function $f(x) = \frac{1}{x^2}$


For the **reciprocal squared function** $f(x) = \frac{1}{x^2}$ ,we cannot divide by 0, so we must exclude 0 from the domain. There is also no x that can give an output of 0, so 0 is excluded from the range as well. Note that the output of this function is always positive due to the square in the denominator, so the range includes only positive numbers.




Domain: [0, ∞)
Range: [0, ∞)

***Figure* 3.3.19:** *Square root function* $f(x) = \sqrt{(x)}$.

For the **square root function** $f(x) = \sqrt{x}$, we cannot take the square root of a negative real number, so the domain must be 0 or greater. The range also excludes negative numbers because the square root of a positive number $x$ is defined to be positive, even though the square of the negative number $-\sqrt{x}$ also gives us $x$.




Domain: $(-\infty, \infty)$
Range: $(-\infty, \infty)$

Figure 3.3.20: Cube root function $f(x) = \sqrt[3]{x}$.

For the **cube root function** $f(x) = \sqrt[3]{x}$, the domain and range include all real numbers. Note that there is no problem taking a cube root, or any odd-integer root, of a negative number, and the resulting output is negative (it is an odd function).

**How To: Given the formula for a function, determine the domain and range.**

1. Exclude from the domain any input values that result in division by zero.
2. Exclude from the domain any input values that have nonreal (or undefined) number outputs.
3. Use the valid input values to determine the range of the output values.
4. Look at the function graph and table values to confirm the actual function behavior.

### Finding the Domain and Range Using Toolkit Functions

Find the domain and range of $f(x) = 2x^3 - x$ .

**Solution**

There are no restrictions on the domain, as any real number may be cubed and then subtracted from the result.

The domain is $(-\infty, \infty)$ and the range is also $(-\infty, \infty)$.

### Example 3.3.7B: Finding the Domain and Range

Find the domain and range of $f(x) = \frac{2}{x+1}$.

**Solution**

We cannot evaluate the function at −1 because division by zero is undefined. The domain is $(-\infty, -1) \cup (-1, \infty)$. Because the function is never zero, we exclude 0 from the range. The range is $(-\infty, 0) \cup (0, \infty)$.

### Example 3.3.7C: Finding the Domain and Range

Find the domain and range of $f(x) = 2\sqrt{x+4}$.

**Solution**

We cannot take the square root of a negative number, so the value inside the radical must be nonnegative.

$x + 4 \geq 0$ when $x \geq -4$

The domain of $f(x)$ is $[-4, \infty)$.

We then find the range. We know that $f(-4) = 0$, and the function value increases as $x$ increases without any upper limit. We conclude that the range of f is $[0, \infty)$.

**Analysis**

Figure 3.3.19represents the function $f$.





Figure 3.3.19: Graph of a square root function at $(-4, 0)$.

### Exercise 3.3.7

Find the domain and range of

$f(x) = \sqrt{-2-x}$.

**Answer**

domain: $(-\infty, -2]$

range: $[0, \infty)$

## Graphing Piecewise-Defined Functions

Sometimes, we come across a function that requires more than one formula in order to obtain the given output. For example, in the toolkit functions, we introduced the absolute value function $f(x) = |x|$. With a domain of all real numbers and a range of values greater than or equal to 0, **absolute value** can be defined as the **magnitude**, or **modulus**, of a real number value regardless of sign. It is the distance from 0 on the number line. All of these definitions require the output to be greater than or equal to 0.

If we input 0, or a positive value, the output is the same as the input.

$$f(x) = x \text{ if } x \geq 0$$

If we input a negative value, the output is the opposite of the input.

$$f(x) = -x \text{ if } x < 0$$

Because this requires two different processes or pieces, the absolute value function is an example of a **piecewise function**. A piecewise function is a function in which more than one formula is used to define the output over different pieces of the domain.

We use piecewise functions to describe situations in which a rule or relationship changes as the input value crosses certain "boundaries." For example, we often encounter situations in business for which the cost per piece of a certain item is discounted once the number ordered exceeds a certain value. Tax brackets are another real-world example of piecewise functions. For example, consider a simple tax system in which incomes up to $10,000 are taxed at 10%, and any additional income is taxed at 20%. The tax on a total income S would be $0.1S$ if $S \leq \$10,000$ and $\$1000 + 0.2(S - \$10,000)$ if $S > \$10,000$.

## Piecewise Function

A piecewise function is a function in which more than one formula is used to define the output. Each formula has its own domain, and the domain of the function is the union of all these smaller domains. We notate this idea like this:

$$f(x) = \begin{cases} \text{formula 1} & \text{if x is in domain 1} \\ \text{formula 2} & \text{if x is in domain 2} \\ \text{formula 3} & \text{if x is in domain 3} \end{cases}$$

In piecewise notation, the absolute value function is

$$|x| = \begin{cases} x & \text{if } x \geq 0 \\ -x & \text{if } x < 0 \end{cases}$$

**How To: Given a piecewise function, write the formula and identify the domain for each interval.**

1. Identify the intervals for which different rules apply.
2. Determine formulas that describe how to calculate an output from an input in each interval.
3. Use braces and if-statements to write the function.

### Example 3.3.8A: Writing a Piecewise Function

A museum charges $5 per person for a guided tour with a group of 1 to 9 people or a fixed $50 fee for a group of 10 or more people. Write a **function** relating the number of people, $n$, to the cost, $C$.

**Solution**

Two different formulas will be needed. For $n$-values under 10, $C = 5n$. For values of n that are 10 or greater, $C = 50$.

$$C(n) = \begin{cases} 5n & \text{if } n < 10 \\ 50 & \text{if } n \geq 10 \end{cases}$$

**Analysis**

The function is represented in Figure 3.3.20. The graph is a diagonal line from $n = 0$ to $n = 10$ and a constant after that. In this example, the two formulas agree at the meeting point where $n = 10$, but not all piecewise functions have this property.




Figure 3.3.20

## Example 3.3.8$B$: Working with a Piecewise Function

A cell phone company uses the function below to determine the cost, C, in dollars for g gigabytes of data transfer.

$$C(g) = \begin{cases} 25 & \text{if } 0 < g < 2 \\ 25 + 10(g-2) & \text{if } g \geq 2 \end{cases}$$

Find the cost of using 1.5 gigabytes of data and the cost of using 4 gigabytes of data.

**Soltuion**

To find the cost of using 1.5 gigabytes of data, $C(1.5)$, we first look to see which part of the domain our input falls in. Because 1.5 is less than 2, we use the first formula.

$$C(1.5) = \$25$$

To find the cost of using 4 gigabytes of data, C(4), we see that our input of 4 is greater than 2, so we use the second formula.

$$C(4) = 25 + 10(4-2) = \$45$$

**Analysis**

The function is represented in Figure 3.3.21. We can see where the function changes from a constant to a shifted and stretched identity at $g = 2$. We plot the graphs for the different formulas on a common set of axes, making sure each formula is applied on its proper domain.




Figure 3.3.21

**Given a piecewise function, sketch a graph.**

1. Indicate on the x-axis the boundaries defined by the intervals on each piece of the domain.
2. For each piece of the domain, graph on that interval using the corresponding equation pertaining to that piece. Do not graph two functions over one interval because it would violate the criteria of a function.

## Example 3.3.8C: Graphing a Piecewise Function

Sketch a graph of the function.

$$f(x) = \begin{cases} x^2 & \text{if } x \leq 1 \\ 3 & \text{if } 1 < x \leq 2 \\ x & \text{if } x > 2 \end{cases}$$

**Solution**

Each of the component functions is from our library of toolkit functions, so we know their shapes. We can imagine graphing each function and then limiting the graph to the indicated domain. At the endpoints of the domain, we draw open circles to indicate where the endpoint is not included because of a less-than or greater-than inequality; we draw a closed circle where the endpoint is included because of a less-than-or-equal-to or greater-than-or-equal-to inequality.

Figure 3.3.20 shows the three components of the piecewise function graphed on separate coordinate systems.





***Figure 3.3.20:*** *Graph of each part of the piece-wise function f(x)*

(a) $f(x) = x^2$ if $x \leq 1$; (b) $f(x) = 3$ if $1 < x \leq 2$; (c) $f(x) = x$ if $x > 2$

Now that we have sketched each piece individually, we combine them in the same coordinate plane. See Figure 3.3.21.





Figure 3.3.21: Graph of the entire function.

**Analysis**

Note that the graph does pass the vertical line test even at $x = 1$ and $x = 2$ because the points $(1, 3)$ and $(2, 2)$ are not part of the graph of the function, though $(1, 1)$ and $(2, 3)$ are.

## Exercise 3.3.8

Graph the following piecewise function.


https://math.libretexts.org/@go/page/96263

$$f(x) = \begin{cases} x^3 & \text{if } x < -1 \\ -2 & \text{if } -1 < x < 4 \\ \sqrt{x} & \text{if } x > 4 \end{cases}$$

**Answer**





Figure 3.3.22

**Can more than one formula from a piecewise function be applied to a value in the domain?**

*No. Each value corresponds to one equation in a piecewise formula.*

## Key Concepts

- The domain of a function includes all real input values that would not cause us to attempt an undefined mathematical operation, such as dividing by zero or taking the square root of a negative number.
- The domain of a function can be determined by listing the input values of a set of ordered pairs.
- The domain of a function can also be determined by identifying the input values of a function written as an equation.
- Interval values represented on a number line can be described using inequality notation, set-builder notation, and interval notation.
- For many functions, the domain and range can be determined from a graph.
- An understanding of toolkit functions can be used to find the domain and range of related functions.
- A piecewise function is described by more than one formula.
- A piecewise function can be graphed using each algebraic formula on its assigned subdomain.

## Footnotes

1 The Numbers: Where Data and the Movie Business Meet. “Box Office History for Horror Movies.” http://www.the-numbers.com/market/genre/Horror. Accessed 3/24/2014

2 www.eia.gov/dnav/pet/hist/Lea...s=MCRFPAK2&f=A.

## Glossary

**interval notation**

a method of describing a set that includes all numbers between a lower limit and an upper limit; the lower and upper values are listed between brackets or parentheses, a square bracket indicating inclusion in the set, and a parenthesis indicating exclusion

**piecewise function**

a function in which more than one formula is used to define the output

**set-builder notation**

a method of describing a set by a rule that all of its members obey; it takes the form {x| statement about x}

---

This page titled 3.3: Domain and Range is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.2: Domain and Range** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.3E: Domain and Range (Exercises)

For the following exercises, find the domain of each function, expressing answers using interval notation.

20. $f(x) = \frac{2}{3x+2}$
21. $f(x) = \frac{x-3}{x^2-4x-12}$
22. $f(x) = \frac{\sqrt{x-6}}{\sqrt{x-4}}$
23. Graph this piecewise function: $f(x) = \begin{cases} x+1 & x < -2 \\ -2x-3 & x \geq -2 \end{cases}$

This page titled 3.3E: Domain and Range (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.2E: Domain and Range (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.4: Rates of Change and Behavior of Graphs

**Learning Objectives**

- Find the average rate of change of a function.
- Use a graph to determine where a function is increasing, decreasing, or constant.
- Use a graph to locate local maxima and local minima.
- Use a graph to locate the absolute maximum and absolute minimum.

Gasoline costs have experienced some wild fluctuations over the last several decades. Table 3.4.1 lists the average cost, in dollars, of a gallon of gasoline for the years 2005–2012. The cost of gasoline can be considered as a function of year.

Table 3.4.1

| $y$ | 2005 | 2006 | 2007 | 2008 | 2009 | 2010 | 2011 | 2012 |
|---|---|---|---|---|---|---|---|---|
| $C(y)$ | 2.31 | 2.62 | 2.84 | 3.30 | 2.41 | 2.84 | 3.58 | 3.68 |

If we were interested only in how the gasoline prices changed between 2005 and 2012, we could compute that the cost per gallon had increased from \$2.31 to \$3.68, an increase of \$1.37. While this is interesting, it might be more useful to look at how much the price changed per year. In this section, we will investigate changes such as these.

## Finding the Average Rate of Change of a Function

The price change per year is a **rate of change** because it describes how an output quantity changes relative to the change in the input quantity. We can see that the price of gasoline in Table 3.4.1 did not change by the same amount each year, so the rate of change was not constant. If we use only the beginning and ending data, we would be finding the **average rate of change** over the specified period of time. To find the average rate of change, we divide the change in the output value by the change in the input value.

$$\begin{aligned}\text{Average rate of change} &= \frac{\text{Change in output}}{\text{Change in input}} \\ &= \frac{\Delta y}{\Delta x} \\ &= \frac{y_2 - y_1}{x_2 - x_1} \\ &= \frac{f(x_2) - f(x_1)}{x_2 - x_1}\end{aligned}$$

The Greek letter $\Delta$ (delta) signifies the change in a quantity; we read the ratio as "delta-$y$ over delta-$x$" or "the change in $y$ divided by the change in $x$." Occasionally we write $\Delta f$ instead of $\Delta y$, which still represents the change in the function's output value resulting from a change to its input value. It does not mean we are changing the function into some other function.

In our example, the gasoline price increased by \$1.37 from 2005 to 2012. Over 7 years, the average rate of change was

$$\frac{\Delta y}{\Delta x} = \frac{\$1.37}{7\text{years}} \approx 0.196 \text{ dollars per year.} \tag{3.4.1}$$

On average, the price of gas increased by about 19.6¢ each year. Other examples of rates of change include:

- A population of rats increasing by 40 rats per week
- A car traveling 68 miles per hour (distance traveled changes by 68 miles each hour as time passes)
- A car driving 27 miles per gallon (distance traveled changes by 27 miles for each gallon)
- The current through an electrical circuit increasing by 0.125 amperes for every volt of increased voltage
- The amount of money in a college account decreasing by \$4,000 per quarter

**Definition: Rate of Change**

A **rate of change** describes how an output quantity changes relative to the change in the input quantity. The units on a rate of change are "output units per input units."

The average rate of change between two input values is the total change of the function values (output values) divided by the change in the input values.

$$\frac{\Delta y}{\Delta x} = \frac{f(x_2) - f(x_1)}{x_2 - x_1} \tag{3.4.2}$$

**How To...**

Given the value of a function at different points, calculate the average rate of change of a function for the interval between two values $x_1$ and $x_2$.

1. Calculate the difference $y_2 - y_1 = \Delta y$ .
2. Calculate the difference $x_2 - x_1 = \Delta x$ .
3. Find the ratio $\frac{\Delta y}{\Delta x}$.

**Example 3.4.1: Computing an Average Rate of Change**

Using the data in Table 3.4.1, find the average rate of change of the price of gasoline between 2007 and 2009.

**Solution**

In 2007, the price of gasoline was \$2.84. In 2009, the cost was \$2.41. The average rate of change is

$$\begin{aligned} \frac{\Delta y}{\Delta x} &= \frac{y_2 - y_1}{x_2 - x_1} \\ &= \frac{\$2.41 - \$2.84}{2009 - 2007} \\ &= \frac{-\$0.43}{2 \text{ years}} \\ &= -\$0.22 \text{ per year} \end{aligned}$$

**Analysis**

Note that a decrease is expressed by a negative change or "negative increase." A rate of change is negative when the output decreases as the input increases or when the output increases as the input decreases.

**Exercise 3.4.1**

Using the data in Table 3.4.1, find the average rate of change between 2005 and 2010.

**Solution**

$$\frac{\$2.84 - \$2.315}{5 \text{ years}} = \frac{\$0.535}{5 \text{ years}} = \$0.106 \text{per year.}$$

**Example 3.4.2: Computing Average Rate of Change from a Graph**

Given the function $g(t)$ shown in Figure 3.4.1, find the average rate of change on the interval $[-1, 2]$.





Figure 3.4.1: Graph of a parabola.

**Solution**

At $t=-1$, Figure 3.4.2 shows $g(-1)=4$. At $t=2$,the graph shows $g(2)=1$.





Figure 3.4.2: Graph of a parabola with a line from points (-1, 4) and (2, 1) to show the changes for g(t) and t.

The horizontal change $\Delta t=3$ is shown by the red arrow, and the vertical change $\Delta g(t)=-3$ is shown by the turquoise arrow. The output changes by –3 while the input changes by 3, giving an average rate of change of

$$\frac{1-4}{2-(-1)}=\frac{-3}{3}=-1 \tag{3.4.3}$$

**Analysis**

Note that the order we choose is very important. If, for example, we use $\frac{y_2-y_1}{x_1-x_2}$, we will not get the correct answer. Decide which point will be 1 and which point will be 2, and keep the coordinates fixed as $(x_1,y_1)$ and $(x_2,y_2)$.

## Example 3.4.3: Computing Average Rate of Change from a Table

After picking up a friend who lives 10 miles away, Anna records her distance from home over time. The values are shown in Table 3.4.2. Find her average speed over the first 6 hours.

Table 3.4.2

| $t$ (hours) | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 |
|---|---|---|---|---|---|---|---|---|
| $D(t)$ (miles) | 10 | 55 | 90 | 153 | 214 | 240 | 292 | 300 |

**Solution**

Here, the average speed is the average rate of change. She traveled 292 miles in 6 hours, for an average speed of

$$\frac{292-10}{6-0}=\frac{282}{6}$$
$$=47$$

The average speed is about 47 miles per hour.

**Analysis**

Because the speed is not constant, the average speed depends on the interval chosen. For the interval $[2,3]$, the average speed is 63 miles per hour.

## Example 3.4.4: Computing Average Rate of Change for a Function Expressed as a Formula

Compute the average rate of change of $f(x)=x^2-\frac{1}{x}$ on the interval $[2,4]$.

**Solution**

We can start by computing the function values at each endpoint of the interval.

$$\begin{aligned} f(2) &= 2^2-\frac{1}{2} & f(4) &= 4^2-\frac{1}{4} \\ &= 4-\frac{1}{2} & &= 16-\frac{1}{4} \\ &= 72 & &= \frac{63}{4} \end{aligned}$$

Now we compute the average rate of change.

$$\begin{aligned} \text{Average rate of change} &= \frac{f(4)-f(2)}{4-2} \\ &= \frac{\frac{63}{4}-\frac{7}{2}}{4-2} \\ &= \frac{\frac{49}{4}}{2} \\ &= \frac{49}{8} \end{aligned}$$

## Exercise 3.4.2

Find the average rate of change of $f(x)=x-2\sqrt{x}$ on the interval $[1,9]$.

**Solution**

$\frac{1}{2}$

## Example 3.4.5: Finding the Average Rate of Change of a Force

The electrostatic force $F$, measured in newtons, between two charged particles can be related to the distance between the particles $d$,in centimeters, by the formula $F(d)=\frac{2}{d^2}$. Find the average rate of change of force if the distance between the particles is increased from 2 cm to 6 cm.

**Solution**

We are computing the average rate of change of $F(d)=\dfrac{2}{d^2}$ on the interval $[2,6]$.

$$\begin{aligned}
\text{Average rate of change} &= \frac{F(6)-F(2)}{6-2} \\
&= \frac{\frac{2}{6^2}-\frac{2}{2^2}}{6-2} && \text{Simplify} \\
&= \frac{\frac{2}{36}-\frac{2}{4}}{4} \\
&= \frac{-\frac{16}{36}}{4} && \text{Combine numerator terms.} \\
&= -\frac{1}{9} && \text{Simplify}
\end{aligned}$$

The average rate of change is $-\frac{1}{9}$ newton per centimeter.

### Example 3.4.6: Finding an Average Rate of Change as an Expression

Find the average rate of change of $g(t)=t^2+3t+1$ on the interval $[0,a]$. The answer will be an expression involving $a$.

**Solution**

We use the average rate of change formula.

$$\begin{aligned}
\text{Average rate of change} &= \frac{g(a)-g(0)}{a-0} && \text{Evaluate.} \\
&= \frac{(a^2+3a+1)-(0^2+3(0)+1)}{a-0} && \text{Simplify.} \\
&= \frac{a^2+3a+1-1}{a} && \text{Simplify and factor.} \\
&= \frac{a(a+3)}{a} && \text{Divide by the common factor a.} \\
&= a+3
\end{aligned}$$

This result tells us the average rate of change in terms of a between $t=0$ and any other point $t=a$. For example, on the interval $[0,5]$, the average rate of change would be $5+3=8$.

### Exercise 3.4.3

Find the average rate of change of $f(x)=x^2+2x-8$ on the interval $[5,a]$.

**Solution**

$a+7$

## Using a Graph to Determine Where a Function is Increasing, Decreasing, or Constant

As part of exploring how functions change, we can identify intervals over which the function is changing in specific ways. We say that a function is increasing on an interval if the function values increase as the input values increase within that interval. Similarly, a function is decreasing on an interval if the function values decrease as the input values increase over that interval. The average rate of change of an increasing function is positive, and the average rate of change of a decreasing function is negative. Figure 3.4.3 shows examples of increasing and decreasing intervals on a function.





Figure 3.4.3: The function $f(x) = x^3 - 12x$ is increasing on $(-\infty, -2) \cup (2, \infty)$ and is decreasing on $(-2, 2)$.

While some functions are increasing (or decreasing) over their entire domain, many others are not. A value of the input where a function changes from increasing to decreasing (as we go from left to right, that is, as the input variable increases) is called a **local maximum**. If a function has more than one, we say it has local maxima. Similarly, a value of the input where a function changes from decreasing to increasing as the input variable increases is called a **local minimum**. The plural form is "local minima." Together, local maxima and minima are called **local extrema**, or local extreme values, of the function. (The singular form is "extremum.") Often, the term local is replaced by the term relative. In this text, we will use the term local.

Clearly, a function is neither increasing nor decreasing on an interval where it is constant. A function is also neither increasing nor decreasing at extrema. Note that we have to speak of local extrema, because any given local extremum as defined here is not necessarily the highest maximum or lowest minimum in the function's entire domain.

For the function whose graph is shown in Figure 3.4.4, the local maximum is 16, and it occurs at $x = -2$. The local minimum is $-16$ and it occurs at $x = 2$.





Figure 3.4.4: Graph of a polynomial that shows the increasing and decreasing intervals and local maximum.maximum

To locate the local maxima and minima from a graph, we need to observe the graph to determine where the graph attains its highest and lowest points, respectively, within an open interval. Like the summit of a roller coaster, the graph of a function is higher at a

local maximum than at nearby points on both sides. The graph will also be lower at a local minimum than at neighboring points. Figure 3.4.5 illustrates these ideas for a local maximum.





Figure 3.4.5: Definition of a local maximum

These observations lead us to a formal definition of local extrema.

### Local Minima and Local Maxima

- A function $f$ is an **increasing function** on an open interval if $f(b) > f(a)$ for every $a$, $b$ interval where $b > a$.
- A function $f$ is a **decreasing function** on an open interval if $f(b) < f(a)$ for every $a$, $b$ interval where $b > a$.

A function $f$ has a local maximum at a point $b$ in an open interval $(a, c)$ if $f(b)$ is greater than or equal to $f(x)$ for every point $x$ ($x$ does not equal $b$) in the interval. Likewise, $f$ has a local minimum at a point $b$ in $(a, c)$ if $f(b)$ is less than or equal to $f(x)$ for every $x$ ($x$ does not equal $b$) in the interval.

### Example 3.4.7 Finding Increasing and Decreasing Intervals on a Graph

Given the function $p(t)$ in Figure 3.4.6, identify the intervals on which the function appears to be increasing.





Figure 3.4.6: Graph of a polynomial.

**Solution**

We see that the function is not constant on any interval. The function is increasing where it slants upward as we move to the right and decreasing where it slants downward as we move to the right. The function appears to be increasing from $t = 1$ to $t = 3$ and from $t = 4$ on.

In interval notation, we would say the function appears to be increasing on the interval $(1, 3)$ and the interval $(4, \infty)$.

**Analysis**

Notice in this example that we used open intervals (intervals that do not include the endpoints), because the function is neither increasing nor decreasing at $t = 1$, $t = 3$, and $t = 4$. These points are the local extrema (two minima and a maximum).

## Example 3.4.8: Finding Local Extrema from a Graph

Graph the function $f(x) = \frac{2}{x} + \frac{x}{3}$. Then use the graph to estimate the local extrema of the function and to determine the intervals on which the function is increasing.

**Solution**

Using technology, we find that the graph of the function looks like that in Figure 3.4.7. It appears there is a low point, or local minimum, between $x = 2$ and $x = 3$, and a mirror-image high point, or local maximum, somewhere between $x = -3$ and $x = -2$





Figure 3.4.7: Graph of a reciprocal function.

**Analysis**

Most graphing calculators and graphing utilities can estimate the location of maxima and minima. Figure 3.4.8 provides screen images from two different technologies, showing the estimate for the local maximum and minimum.





Figure 3.4.8: Graph of the reciprocal function on a graphing calculator.


Based on these estimates, the function is increasing on the interval $(-\infty, -2.449)$ and $(2.449, \infty)$. Notice that, while we expect the extrema to be symmetric, the two different technologies agree only up to four decimals due to the differing approximation algorithms used by each. (The exact location of the extrema is at $\pm\sqrt{6}$, but determining this requires calculus.)

## Exercise 3.4.8

Graph the function $f(x) = x^3 - 6x^2 - 15x + 20$ to estimate the local extrema of the function. Use these to determine the intervals on which the function is increasing and decreasing.

**Solution**

The local maximum appears to occur at $(-1, 28)$, and the local minimum occurs at $(5, -80)$. The function is increasing on $(-\infty, -1) \cup (5, \infty)$ and decreasing on $(-1, 5)$.




*Graph of a polynomial with a local maximum at (-1, 28) and local minimum at (5, -80).*

**Example 3.4.9: Finding Local Maxima and Minima from a Graph**

For the function f whose graph is shown in Figure 3.4.9, find all local maxima and minima.





Figure 3.4.9: Graph of a polynomial.

**Solution**

Observe the graph of $f$. The graph attains a local maximum at $x = 1$ because it is the highest point in an open interval around $x = 1$.The local maximum is the y-coordinate at $x = 1$, which is 2.

The graph attains a local minimum at $x = -1$ because it is the lowest point in an open interval around $x = -1$. The local minimum is the y-coordinate at $x = -1$, which is −2.

## Analyzing the Toolkit Functions for Increasing or Decreasing Intervals

We will now return to our toolkit functions and discuss their graphical behavior in Figure 3.4.10, Figure 3.4.11, and Figure 3.4.12.









| Function | Increasing/Decreasing | Example |
|---|---|---|
| Constant Function<br>$f(x) = c$ | Neither increasing nor decreasing |  |
| Identity Function<br>$f(x) = x$ | Increasing |  |
| Quadratic Function<br>$f(x) = x^2$ | Increasing on $(0, \infty)$<br>Decreasing on $(-\infty, 0)$<br>Minimum at $x = 0$ |  |

Figure 3.4.10

| Function | Increasing/Decreasing | Example |
|---|---|---|
| Cubic Function<br>$f(x) = x^3$ | Increasing |  |
| Reciprocal<br>$f(x) = \frac{1}{x}$ | Decreasing $(-\infty, 0) \cup (0, \infty)$ |  |
| Reciprocal Squared<br>$f(x) = \frac{1}{x^2}$ | Increasing on $(-\infty, 0)$<br>Decreasing on $(0, \infty)$ |  |

.

Figure 3.4.11

| Function | Increasing/Decreasing | Example |
|---|---|---|
| Constant Function<br>$f(x) = c$ | Neither increasing nor decreasing |  |
| Identity Function<br>$f(x) = x$ | Increasing |  |








| | | |
|---|---|---|
| Quadratic Function<br>$f(x) = x^2$ | Increasing on $(0, \infty)$<br>Decreasing on $(-\infty, 0)$<br>Minimum at $x = 0$ |  |
| Cubic Function<br>$f(x) = x^3$ | Increasing |  |
| Reciprocal<br>$f(x) = \frac{1}{x}$ | Decreasing $(-\infty, 0) \cup (0, \infty)$ |  |
| Reciprocal Squared<br>$f(x) = \frac{1}{x^2}$ | Increasing on $(-\infty, 0)$<br>Decreasing on $(0, \infty)$ |  |
| Cube Root<br>$f(x) = \sqrt[3]{x}$ | Increasing |  |
| Square Root<br>$f(x) = \sqrt{x}$ | Increasing on $(0, \infty)$ |  |
| Absolute Value<br>$f(x) = \lvert x \rvert$ | Increasing on $(0, \infty)$<br>Decreasing on $(\infty, 0)$ |  |

***Figure* 3.4.12**

## Use A Graph to Locate the Absolute Maximum and Absolute Minimum

There is a difference between locating the highest and lowest points on a graph in a region around an open interval (locally) and locating the highest and lowest points on the graph for the entire domain. The y-coordinates (output) at the highest and lowest points are called the **absolute maximum** and **absolute minimum**, respectively. To locate absolute maxima and minima from a graph, we need to observe the graph to determine where the graph attains it highest and lowest points on the domain of the function (Figure 3.4.13).





Figure 3.4.13: Graph of a segment of a parabola with an absolute minimum at (0, -2) and absolute maximum at (2, 2).

Not every function has an absolute maximum or minimum value. The toolkit function $f(x) = x^3$ is one such function.

### Absolute Maxima and Minima

- The **absolute maximum** of $f$ at $x = c$ is $f(c)$ where $f(c) \geq f(x)$ for all $x$ in the domain of $f$.
- The **absolute minimum** of $f$ at $x = d$ is $f(d)$ where $f(d) \leq f(x)$ for all $x$ in the domain of $f$.

### Example 3.4.10: Finding Absolute Maxima and Minima from a Graph

For the function f shown in Figure 3.4.14, find all absolute maxima and minima.





Figure 3.4.14: Graph of a polynomial.

**Solution**

Observe the graph of $f$. The graph attains an absolute maximum in two locations, $x = -2$ and $x = 2$, because at these locations, the graph attains its highest point on the domain of the function. The absolute maximum is the y-coordinate at $x = -2$ and $x = 2$, which is 16.

The graph attains an absolute minimum at x=3, because it is the lowest point on the domain of the function's graph. The absolute minimum is the y-coordinate at x=3,which is−10.

## Key Equations

- Average rate of change: $\dfrac{\Delta y}{\Delta x} = \dfrac{f(x_2) - f(x_1)}{x_2 - x_1}$

## Key Concepts

- A rate of change relates a change in an output quantity to a change in an input quantity. The average rate of change is determined using only the beginning and ending data. See Example.

- Identifying points that mark the interval on a graph can be used to find the average rate of change. See Example.
- Comparing pairs of input and output values in a table can also be used to find the average rate of change. See Example.
- An average rate of change can also be computed by determining the function values at the endpoints of an interval described by a formula. See Example and Example.
- The average rate of change can sometimes be determined as an expression. See Example.
- A function is increasing where its rate of change is positive and decreasing where its rate of change is negative. See Example.
- A local maximum is where a function changes from increasing to decreasing and has an output value larger (more positive or less negative) than output values at neighboring input values.
- A local minimum is where the function changes from decreasing to increasing (as the input increases) and has an output value smaller (more negative or less positive) than output values at neighboring input values.
- Minima and maxima are also called extrema.
- We can find local extrema from a graph. See Example and Example.
- The highest and lowest points on a graph indicate the maxima and minima. See Example.

---

This page titled 3.4: Rates of Change and Behavior of Graphs is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.3: Rates of Change and Behavior of Graphs** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.


# 3.4E: Rates of Change and Behavior of Graphs (Exercises)

For the following exercises, find the average rate of change of the functions from $x = 1$ to $x = 2$.


24. $f(x) = 4x - 3$
25. $f(x) = 10x^2 + x$
26. $f(x) = -\frac{2}{x^2}$

For the following exercises, use the graphs to determine the intervals on which the functions are increasing, decreasing, or constant.


27




28.




29.




30. Find the local minimum of the function graphed in Exercise 3.27 .
31. Find the local extrema for the function graphed in Exercise 3.28 .
32. For the graph in Figure $3.4E.3$, the domain of the function is [-3,3] . The range is [-10,10] . Find the absolute minimum of the function on this interval.
33. Find the absolute maximum of the function graphed in Figure $3.4E.3$.





Figure $3.4E.3$

---

This page titled 3.4E: Rates of Change and Behavior of Graphs (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.3E: Rates of Change and Behavior of Graphs (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# SECTION OVERVIEW

## 3.5: Linear Functions

Recall that a function is a relation that assigns to every element in the domain exactly one element in the range. Linear functions are a specific type of function that can be used to model many real-world applications, such as plant growth over time. In this chapter, we will explore linear functions, their graphs, and how to relate them to data.


### 3.5.1: Prelude to Linear Functions

### 3.5.2: Linear Functions

### 3.5.3: Graphs of Linear Functions

### 3.5.4: Modeling with Linear Functions

### 3.5.5: Fitting Linear Models to Data

### 3.5.E: Linear Functions(Exercises)

### 3.5.R: Linear Functions(Review)


---


This page titled 3.5: Linear Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 3.5.1: Prelude to Linear Functions

Imagine placing a plant in the ground one day and finding that it has doubled its height just a few days later. Although it may seem incredible, this can happen with certain types of bamboo species. These members of the grass family are the fastest-growing plants in the world. One species of bamboo has been observed to grow nearly 1.5 inches every hour.1 In a twenty-four hour period, this bamboo plant grows about 36 inches, or an incredible 3 feet! A constant rate of change, such as the growth cycle of this bamboo plant, is a linear function.




***Figure* 3.5.1.1*:*** *A bamboo forest in China (credit: "JFXie"/Flickr)*

Recall from Functions and Function Notation that a function is a relation that assigns to every element in the domain exactly one element in the range. Linear functions are a specific type of function that can be used to model many real-world applications, such as plant growth over time. In this chapter, we will explore linear functions, their graphs, and how to relate them to data.

## Footnotes

1 www.guinnessworldrecords.com/...growing-plant/

This page titled 3.5.1: Prelude to Linear Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.0: Prelude to Linear Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.5.2: Linear Functions

**Learning Objectives**

- Represent a linear function.
- Determine whether a linear function is increasing, decreasing, or constant.
- Interpret slope as a rate of change.
- Write and interpret an equation for a linear function.
- Graph linear functions.
- Determine whether lines are parallel or perpendicular.
- Write the equation of a line parallel or perpendicular to a given line.

Just as with the growth of a bamboo plant, there are many situations that involve constant change over time. Consider, for example, the first commercial maglev train in the world, the Shanghai MagLev Train (maglev train in the world, the Shanghai MagLev Train (Figure 3.5.2.1). It carries passengers comfortably for a 30-kilometer trip from the airport to the subway station in only eight minutes.




Figure 3.5.2.1: Shanghai MagLev Train (credit: “kanegen”/Flickr)

Suppose a maglev train were to travel a long distance, and that the train maintains a constant speed of 83 meters per second for a period of time once it is 250 meters from the station. How can we analyze the train’s distance from the station as a function of time? In this section, we will investigate a kind of function that is useful for this purpose, and use it to investigate real-world situations such as the train’s distance from the station at a given point in time.maglev train were to travel a long distance, and that the train maintains a constant speed of 83 meters per second for a period of time once it is 250 meters from the station. How can we analyze the train’s distance from the station as a function of time? In this section, we will investigate a kind of function that is useful for this purpose, and use it to investigate real-world situations such as the train’s distance from the station at a given point in time.

## Representing Linear Functions

The function describing the train’s motion is a **linear function**, which is defined as a function with a constant rate of change, that is, a polynomial of degree 1. There are several ways to represent a linear function, including word form, function notation, tabular form, and graphical form. We will describe the train’s motion as a function using each method.

### Representing a Linear Function in Word Form

Let’s begin by describing the linear function in words. For the train problem we just considered, the following word sentence may be used to describe the function relationship.

- *The train’s distance from the station is a function of the time during which the train moves at a constant speed plus its original distance from the station when it began moving at constant speed.*

The speed is the rate of change. Recall that a rate of change is a measure of how quickly the dependent variable changes with respect to the independent variable. The rate of change for this example is constant, which means that it is the same for each input value. As the time (input) increases by 1 second, the corresponding distance (output) increases by 83 meters. The train began moving at this constant speed at a distance of 250 meters from the station.

### Representing a Linear Function in Function Notation

Another approach to representing linear functions is by using function notation. One example of function notation is an equation written in the form known as the slope-intercept form of a line, where $x$ is the input value, $m$ is the rate of change, and $b$ is the initial value of the dependent variable.

$$\begin{aligned} &\text{Equation form} && y = mx + b \\ &\text{Equation notation} && f(x) = mx + b \end{aligned}$$

In the example of the train, we might use the notation $D(t)$ in which the total distance $D$ is a function of the time $t$. The rate, $m$, is 83 meters per second. The initial value of the dependent variable $b$ is the original distance from the station, 250 meters. We can write a generalized equation to represent the motion of the train.

$$D(t) = 83t + 250 \tag{3.5.2.1}$$

### Representing a Linear Function in Tabular Form

A third method of representing a linear function is through the use of a table. The relationship between the distance from the station and the time is represented in Figure $3.5.2.2$ From the table, we can see that the distance changes by 83 meters for every 1 second increase in time.





Figure 3.5.2.2: Tabular representation of the function $D$ showing selected input and output values

**Q/A? Can the input in the previous example be any real number?**

No. The input represents time, so while nonnegative rational and irrational numbers are possible, negative real numbers are not possible for this example. The input consists of non-negative real numbers.

### Representing a Linear Function in Graphical Form

Another way to represent linear functions is visually, using a graph. We can use the function relationship from above, $D(t) = 83t + 250$, to draw a graph, represented in Figure $3.5.2.3$ Notice the graph is a line. When we plot a linear function, the graph is always a line.

The rate of change, which is constant, determines the slant, or **slope** of the line. The point at which the input value is zero is the vertical intercept, or **y-intercept**, of the line. We can see from the graph in Figure $3.5.2.3$that the y-intercept in the train example we just saw is $(0, 250)$ and represents the distance of the train from the station when it began moving at a constant speed.





Figure 3.5.2.3: The graph of $D(t) = 83t + 250$. Graphs of linear functions are lines because the rate of change is constant.

Notice that the graph of the train example is restricted, but this is not always the case. Consider the graph of the line $f(x) = 2x + 1$. Ask yourself what numbers can be input to the function, that is, what is the domain of the function? The domain is comprised of all real numbers because any number may be doubled, and then have one added to the product.

### Definition: Linear Function

A **linear function** is a function whose graph is a line. Linear functions can be written in the slope-intercept form of a line

$$f(x) = mx + b \tag{3.5.2.2}$$

where $b$ is the initial or starting value of the function (when input, $x = 0$), and $m$ is the constant rate of change, or **slope** of the function. The **y-intercept** is at $(0, b)$.

### Example 3.5.2.1: Using a Linear Function to Find the Pressure on a Diver

The pressure, $P$, in pounds per square inch (PSI) on the diver in Figure 3.5.2.4 depends upon her depth below the water surface, $d$, in feet. This relationship may be modeled by the equation, $P(d) = 0.434d + 14.696$. Restate this function in words.



Figure 3.5.2.4: (credit: Ilse Reijs and Jan-Noud Hutten)Hutten)

To restate the function in words, we need to describe each part of the equation. The pressure as a function of depth equals four hundred thirty-four thousandths times depth plus fourteen and six hundred ninety-six thousandths.

**Analysis**

The initial value, 14.696, is the pressure in PSI on the diver at a depth of 0 feet, which is the surface of the water. The rate of change, or slope, is 0.434 PSI per foot. This tells us that the pressure on the diver increases 0.434 PSI for each foot her depth increases.

## Determining whether a Linear Function Is Increasing, Decreasing, or Constant

The linear functions we used in the two previous examples increased over time, but not every linear function does. A linear function may be increasing, decreasing, or constant. For an increasing function, as with the train example, the output values increase as the input values increase. The graph of an **increasing function** has a positive slope. A line with a positive slope slants upward from left to right as in Figure 3.5.2.5(a). For a **decreasing function**, the slope is negative. The output values decrease as the input values increase. A line with a negative slope slants downward from left to right as in Figure 3.5.2.5(b). If the function is constant, the output values are the same for all input values so the slope is zero. A line with a slope of zero is horizontal as in Figure 3.5.2.5(c).





Figure 3.5.2.5: Three graphs depicting an increasing function, a decreasing function, and a constant function.]
Increasing and Decreasing Functions

### Increasing and Decreasing Functions

The slope determines if the function is an **increasing linear function**, a **decreasing linear function**, or a constant function.

- $f(x) = mx + b$ is an increasing function if $m > 0$.
- $f(x) = mx + b$ is an decreasing function if $m < 0$.
- $f(x) = mx + b$ is a constant function if $m = 0$.

### Example 3.5.2.2: decide whether a Function is Increasing, Decreasing, or Constant

Some recent studies suggest that a teenager sends an average of 60 texts per day. For each of the following scenarios, find the linear function that describes the relationship between the input value and the output value. Then, determine whether the graph of the function is increasing, decreasing, or constant.

a. The total number of texts a teen sends is considered a function of time in days. The input is the number of days, and output is the total number of texts sent.
b. A teen has a limit of 500 texts per month in his or her data plan. The input is the number of days, and output is the total number of texts remaining for the month.
c. A teen has an unlimited number of texts in his or her data plan for a cost of $50 per month. The input is the number of days, and output is the total cost of texting each month.

#### Solution

Analyze each function.

a. The function can be represented as $f(x) = 60x$ where $x$ is the number of days. The slope, 60, is positive so the function is increasing. This makes sense because the total number of texts increases with each day.
b. The function can be represented as $f(x) = 500 - 60x$ where $x$ is the number of days. In this case, the slope is negative so the function is decreasing. This makes sense because the number of texts remaining decreases each day and this function represents the number of texts remaining in the data plan after $x$ days.
c. The cost function can be represented as $f(x) = 50$ because the number of days does not affect the total cost. The slope is 0 so the function is constant.

## Calculating and Interpreting Slope

In the examples we have seen so far, we have had the slope provided for us. However, we often need to calculate the slope given input and output values. Given two values for the input, $x_1$ and $x_2$, and two corresponding values for the output, $y_1$ and $y_2$—which can be represented by a set of points, $(x_1, y_1)$ and $(x_2, y_2)$—we can calculate the slope $m$, as follows

$$m = \frac{\text{change in output (rise)}}{\text{change in input (run)}}$$

$$= \frac{\Delta y}{\Delta x} = \frac{y_2 - y_1}{x_2 - x_1}$$

where $\Delta y$ is the vertical displacement and $\Delta x$ is the horizontal displacement. Note in function notation two corresponding values for the output $y_1$ and $y_2$ for the function $f$, $y_1 = f(x_1)$ and $y_2 = f(x_2)$, so we could equivalently write

$$m = \frac{f(x_2) - f(x_1)}{x_2 - x_1}$$

Figure 3.5.2.6 indicates how the slope of the line between the points, $(x_1, y_1)$ and $(x_2, y_2)$, is calculated. Recall that the slope measures steepness. The greater the absolute value of the slope, the steeper the line is.





Figure 3.5.2.6: The slope of a function is calculated by the change in $y$ divided by the change in $x$. It does not matter which coordinate is used as the $(x_2, y_2)$ and which is the $(x_1, y_1)$,as long as each calculation is started with the elements from the same coordinate pair.

### Q & A

Are the units for slope always $\frac{\text{units for the output}}{\text{units for the input}}$?

Yes. Think of the units as the change of output value for each unit of change in input value. An example of slope could be miles per hour or dollars per day. Notice the units appear as a ratio of units for the output per units for the input.

### Note: Calculate Slope

The slope or rate of change of a function, $m$, can be calculated according to the following:

$$m = \frac{\text{change in output (rise)}}{\text{change in input (run)}} = \frac{\Delta y}{\Delta x} = \frac{y_2 - y_1}{x_2 - x_1} \tag{3.5.2.3}$$

where $x_1$ and $x_2$ are input values, $y_1$ and $y_2$ are output values.

**How to: Given two points from a linear function, calculate and interpret the slope.**

1. Determine the units for output and input values.
2. Calculate the change of output values and change of input values.
3. Interpret the slope as the change in output values per unit of the input value.

**Example 3.5.2.3: Finding the Slope of a Linear Function**

If $f(x)$ is a linear function, and $(3,-2)$ and $(8,1)$ are points on the line, find the slope. Is this function increasing or decreasing?

**Solution**

The coordinate pairs are $(3,-2)$ and $(8,1)$. To find the rate of change, we divide the change in output by the change in input.

$$m=\frac{\text{change in output (rise)}}{\text{change in input (run)}}=\frac{1-(-2)}{8-3}=\frac{3}{5} \tag{3.5.2.4}$$

We could also write the slope as $m=0.6$. The function is increasing because $m>0$.

**Analysis**

As noted earlier, the order in which we write the points does not matter when we compute the slope of the line as long as the first output value, or *y*-coordinate, used corresponds with the first input value, or *x*-coordinate, used.

**Try it! 3.5.2.1**

If $f(x)$ is a linear function, and $(2,3)$ and $(0,4)$ are points on the line, find the slope. Is this function increasing or decreasing?

**Answer**

$m=\frac{4-3}{0-2}=\frac{1}{-2}=-\frac{1}{2}$ ; decreasing because $m<0$.

**Example 3.5.2.4: Finding the Population Change from a Linear Function**

The population of a city increased from 23,400 to 27,800 between 2008 and 2012. Find the change of population per year if we assume the change was constant from 2008 to 2012.

The rate of change relates the change in population to the change in time. The population increased by $27,800-23,400=4400$ people over the four-year time interval. To find the rate of change, divide the change in the number of people by the number of years.

$$\frac{4,400 \text{ people}}{4 \text{ years}}=1,100\frac{\text{people}}{\text{year}} \tag{3.5.2.5}$$

So the population increased by 1,100 people per year.

**Analysis**

Because we are told that the population increased, we would expect the slope to be positive. This positive slope we calculated is therefore reasonable.

**Try it! 3.5.2.2**

The population of a small town increased from 1,442 to 1,868 between 2009 and 2012. Find the change of population per year if we assume the change was constant from 2009 to 2012.

**Answer**

$m = \frac{1{,}868-1{,}442}{2{,}012-2{,}009} = \frac{426}{3} = 142$ people per year

## Writing the Point-Slope Form of a Linear Equation

Up until now, we have been using the slope-intercept form of a linear equation to describe linear functions. Here, we will learn another way to write a linear function, the **point-slope form**.

$$y - y_1 = m(x - x_1) \tag{3.5.2.6}$$

The point-slope form is derived from the slope formula.

$$\begin{aligned} m &= \frac{y-y_1}{x-x_1} && \text{assuming } x \neq x_1 \\ m(x-x_1) &= \frac{y-y_1}{x-x_1}(x-x_1) && \text{Multiply both sides by } (x-x_1). \\ m(x-x_1) &= y-y_1 && \text{Simplify} \\ y-y_1 &= m(x-x_1) && \text{Rearrange} \end{aligned}$$

Keep in mind that the slope-intercept form and the point-slope form can be used to describe the same function. We can move from one form to another using basic algebra. For example, suppose we are given an equation in point-slope form, $y-4 = -\frac{1}{2}(x-6)$ . We can convert it to the slope-intercept form as shown.

$$\begin{aligned} y-4 &= -\frac{1}{2}(x-6) \\ y-4 &= -\frac{1}{2}x+3 && \text{Distribute the } -\frac{1}{2}. \\ y &= -\frac{1}{2}x+7 && \text{Add 4 to each side.} \end{aligned}$$

Therefore, the same line can be described in slope-intercept form as $y = \frac{1}{2}x + 7$ .

**Note: Point-Slope Form of a Linear Equation**

The **point-slope** form of a linear equation takes the form

$$y - y_1 = m(x - x_1) \tag{3.5.2.7}$$

where $m$ is the slope, $x_1$ and $y_1$ are the $x$ and $y$ coordinates of a specific point through which the line passes.

### Writing the Equation of a Line Using a Point and the Slope

The point-slope form is particularly useful if we know one point and the slope of a line. Suppose, for example, we are told that a line has a slope of 2 and passes through the point $(4, 1)$. We know that $m = 2$ and that $x_1 = 4$ and $y_1 = 1$. We can substitute these values into the general point-slope equation.

$$\begin{aligned} y - y_1 &= m(x - x_1) \\ y - 1 &= 2(x - 4) \end{aligned}$$

If we wanted to then rewrite the equation in slope-intercept form, we apply algebraic techniques.

$$\begin{aligned} y-1 &= 2(x-4) \\ y-1 &= 2x-8 && \text{Distribute the 2.} \\ y &= 2x-7 && \text{Add 1 to each side.} \end{aligned}$$

Both equations, $y-1=2(x-4)$ and $y=2x-7$, describe the same line. See Figure 3.5.2.7.





Figure 3.5.2.7

## Example 3.5.2.5: Writing Linear Equations Using a Point and the Slope

Write the point-slope form of an equation of a line with a slope of 3 that passes through the point $(6,-1)$. Then rewrite it in the slope-intercept form.

**Solution**

Let's figure out what we know from the given information. The slope is 3, so $m=3$. We also know one point, so we know $x_1=6$ and $y_1=-1$. Now we can substitute these values into the general point-slope equation.

$$\begin{aligned} y-y_1 &= m(x-x_1) \\ y-(-1) &= 3(x-6) && \text{Substitute known values.} \\ y+1 &= 3(x-6) && \text{Distribute } -1 \text{ to find point-slope form.} \end{aligned}$$

Then we use algebra to find the slope-intercept form.

$$\begin{aligned} y+1 &= 3(x-6) \\ y+1 &= 3x-18 && \text{Distribute 3.} \\ y &= 3x-19 && \text{Simplify to slope-intercept form.} \end{aligned}$$

## Try it! 3.5.2.3

Write the point-slope form of an equation of a line with a slope of –2 that passes through the point $(-2,2)$. Then rewrite it in the slope-intercept form.

**Answer**

$y-2=-2(x+2)$ ; $y=-2x-2$

### Writing the Equation of a Line Using Two Points

The point-slope form of an equation is also useful if we know any two points through which a line passes. Suppose, for example, we know that a line passes through the points $(0,1)$ and $(3,2)$. We can use the coordinates of the two points to find the slope.

$$\begin{aligned} m &= \frac{y_2-y_1}{x_2-x_1} \\ &= \frac{2-1}{3-0} \\ &= \frac{1}{3} \end{aligned}$$

Now we can use the slope we found and the coordinates of one of the points to find the equation for the line. Let use $(0,1)$ for our point.

$$\begin{aligned} y-y_1 &= m(x-x_1) \\ y-1 &= \frac{1}{3}(x-0) \end{aligned}$$

As before, we can use algebra to rewrite the equation in the slope-intercept form.

$$\begin{aligned} y-1 &= \frac{1}{3}(x-0) && \\ y-1 &= \frac{1}{3}x && \text{Distribute the } \frac{1}{3}. \\ y &= \frac{1}{3}x+1 && \text{Add 1 to each side.} \end{aligned}$$

Both equations describe the line shown in Figure 3.5.2.8





Figure 3.5.2.8

**Example 3.5.2.6: Writing Linear Equations Using Two Points**

Write the point-slope form of an equation of a line that passes through the points $(5,1)$ and $(8,7)$. Then rewrite it in the slope-intercept form.

Let's begin by finding the slope.

$$\begin{aligned} m &= \frac{y_2-y_1}{x_2-x_1} \\ &= \frac{7-1}{8-5} \\ &= \frac{6}{3} \\ &= 2 \end{aligned}$$

So $m=2$. Next, we substitute the slope and the coordinates for one of the points into the general point-slope equation. We can choose either point, but we will use $(5,1)$.

$$\begin{aligned} y-y_1 &= m(x-x_1) \\ y-1 &= 2(x-5) \end{aligned}$$

The point-slope equation of the line is $y_2-1=2(x_2-5)$. To rewrite the equation in slope-intercept form, we use algebra.

$$\begin{aligned} y-1 &= 2(x-5) \\ y-1 &= 2x-10 \\ y &= 2x-9 \end{aligned}$$

The slope-intercept equation of the line is $y = 2x - 9$.

**Try It! 3.5.2.4**

Write the point-slope form of an equation of a line that passes through the points $(-1, 3)$ and $(0, 0)$. Then rewrite it in the slope-intercept form.

**Answer**

$y - 0 = -3(x - 0)$ ; $y = -3x$.

## Writing and Interpreting an Equation for a Linear Function

Now that we have written equations for linear functions in both the slope-intercept form and the point-slope form, we can choose which method to use based on the information we are given. That information may be provided in the form of a graph, a point and a slope, two points, and so on. Look at the graph of the function $f$ in Figure 3.5.2.9





Figure 3.5.2.9: Graph depicting how to calculate the slope of a line.

We are not given the slope of the line, but we can choose any two points on the line to find the slope. Let's choose $(0, 7)$ and $(4, 4)$. We can use these points to calculate the slope.

$$\begin{aligned} m &= \frac{y_2 - y_1}{x_2 - x_1} \\ &= \frac{4 - 7}{4 - 0} \\ &= -\frac{3}{4} \end{aligned}$$

Now we can substitute the slope and the coordinates of one of the points into the point-slope form.

$$\begin{aligned} y - y_1 &= m(x - x_1) \\ y - 4 &= -\frac{3}{4}(x - 4) \end{aligned}$$

If we want to rewrite the equation in the slope-intercept form, we would find

$$\begin{aligned} y - 4 &= -\frac{3}{4}(x - 4) \\ y - 4 &= -\frac{3}{4}x + 3 \\ y &= -\frac{3}{4}x + 7 \end{aligned}$$

If we wanted to find the slope-intercept form without first writing the point-slope form, we could have recognized that the line crosses the y-axis when the output value is 7. Therefore, $b = 7$. We now have the initial value $b$ and the slope $m$ so we can substitute $m$ and $b$ into the slope-intercept form of a line.

$$f(x) = mx + b$$

$$m = -\frac{3}{4}, \quad b = 7$$

$$f(x) = -\frac{3}{4}x + 7$$

Figure 3.5.2.10

So the function is $f(x) = -\frac{3}{4}x + 7$, and the linear equation would be $y = -\frac{3}{4}x + 7$.

**How to: Given the graph of a linear function, write an equation to represent the function.**

1. Identify two points on the line.
2. Use the two points to calculate the slope.
3. Determine where the line crosses the y-axis to identify the y-intercept by visual inspection.
4. Substitute the slope and y-intercept into the slope-intercept form of a line equation.

**Example 3.5.2.7: Writing an Equation for a Linear Function**

Write an equation for a linear function given a graph of $f$ shown in Figure 3.5.2.11.





Figure 3.5.2.11

**Solution**

Identify two points on the line, such as $(0, 2)$ and $(-2, -4)$. Use the points to calculate the slope.

$$\begin{aligned} m &= \frac{y_2 - y_1}{x_2 - x_1} \\ &= \frac{4 - 2}{-2 - 0} \\ &= \frac{-6}{-2} \\ &= 3 \end{aligned}$$

Substitute the slope and the coordinates of one of the points into the point-slope form.

$$\begin{aligned} y - y_1 &= m(x - x_1) \\ y - (-4) &= 3(x - (-2)) \\ y + 4 &= 3(x + 2) \end{aligned}$$

We can use algebra to rewrite the equation in the slope-intercept form.

$$\begin{aligned} y+4 &= 3(x+2) \\ y+4 &= 3x+6 \\ y &= 3x+2 \end{aligned}$$

**Analysis**

This makes sense because we can see from Figure 3.5.2.12 that the line crosses the y-axis at the point $(0, 2)$, which is the y-intercept, so $b = 2$.





Figure 3.5.2.12: Graph of an increasing line with points at $(0, 2)$ and $(-2, -4)$.

### Example 3.5.2.8: Writing an Equation for a Linear Cost Function

Suppose Ben starts a company in which he incurs a fixed cost of $1,250 per month for the overhead, which includes his office rent. His production costs are $37.50 per item. Write a linear function $C$ where $C(x)$ is the cost for $x$ items produced in a given month.

**Solution**

The fixed cost is present every month, $1,250. The costs that can vary include the cost to produce each item, which is $37.50 for Ben. The variable cost, called the marginal cost, is represented by 37.5. The cost Ben incurs is the sum of these two costs, represented by $C(x) = 1250 + 37.5x$.

**Analysis**

If Ben produces 100 items in a month, his monthly cost is represented by

$$\begin{aligned} C(100) &= 1250 + 37.5(100) \\ &= 5000 \end{aligned}$$

So his monthly cost would be $5,000.

### Example 3.5.2.9: Writing an Equation for a Linear Function Given Two Points

If $f$ is a linear function, with $f(3) = -2$, and $f(8) = 1$, find an equation for the function in slope-intercept form.

**Solution**

We can write the given points using coordinates.

$$\begin{aligned} f(3) = -2 &\rightarrow (3, 2) \\ f(8) = 1 &\rightarrow (8, 1) \end{aligned}$$

We can then use the points to calculate the slope.

$$\begin{aligned} m &= \frac{y_2 - y_1}{x_2 - x_1} \\ &= \frac{1-(-2)}{8-3} \\ &= \frac{3}{5} \end{aligned}$$

Substitute the slope and the coordinates of one of the points into the point-slope form.

$$\begin{aligned} y - y_1 &= m(x - x_1) \\ y-(-2) &= \frac{3}{5}(x-3) \end{aligned}$$

We can use algebra to rewrite the equation in the slope-intercept form.

$$\begin{aligned} y+2 &= \frac{3}{5}(x-3) \\ y+2 &= \frac{3}{5}x - \frac{9}{5} \\ y &= \frac{3}{5}x - \frac{19}{5} \end{aligned}$$

**? Try It! 3.5.2.5**

If $f(x)$ is a linear function, with $f(2) = -11$, and $f(4) = -25$, find an equation for the function in slope-intercept form.

**Answer**

$y = -7x + 3$

## Modeling Real-World Problems with Linear Functions

In the real world, problems are not always explicitly stated in terms of a function or represented with a graph. Fortunately, we can analyze the problem by first representing it as a linear function and then interpreting the components of the function. As long as we know, or can figure out, the initial value and the rate of change of a linear function, we can solve many different kinds of real-world problems.

**How To: How to: Given a linear function $f$ and the initial value and rate of change, evaluate $f(c)$.**

1. Determine the initial value and the rate of change (slope).
2. Substitute the values into $f(x) = mx + b$.
3. Evaluate the function at $x = c$.

### Example 3.5.2.10: Using a Linear Function to Determine the Number of Songs in a Music Collection

Marcus currently has 200 songs in his music collection. Every month, he adds 15 new songs. Write a formula for the number of songs, $N$, in his collection as a function of time, $t$, the number of months. How many songs will he own in a year?

**Solution**

The initial value for this function is 200 because he currently owns 200 songs, so $N(0) = 200$, which means that $b = 200$.

The number of songs increases by 15 songs per month, so the rate of change is 15 songs per month. Therefore we know that $m = 15$. We can substitute the initial value and the rate of change into the slope-intercept form of a line.




Figure 3.5.2.13

We can write the formula $N(t) = 15t + 200$.

With this formula, we can then predict how many songs Marcus will have in 1 year (12 months). In other words, we can evaluate the function at $t = 12$.

$$\begin{aligned} N(12) &= 15(12) + 200 \\ &= 180 + 200 \\ &= 380 \end{aligned}$$

Marcus will have 380 songs in 12 months.

**Analysis**

Notice that $N$ is an increasing linear function. As the input (the number of months) increases, the output (number of songs) increases as well.

## Example 3.5.2.11: Using a Linear Function to Calculate Salary Plus Commission

Working as an insurance salesperson, Ilya earns a base salary plus a commission on each new policy. Therefore, Ilya's weekly income, I,depends on the number of new policies, $n$, he sells during the week. Last week he sold 3 new policies, and earned \$760 for the week. The week before, he sold 5 new policies and earned \$920. Find an equation for $I(n)$, and interpret the meaning of the components of the equation.

**Solution**

The given information gives us two input-output pairs: $(3, 760)$ and $(5, 920)$. We start by finding the rate of change.

$$\begin{aligned} m &= \frac{920 - 760}{5 - 3} \\ &= \frac{\$160}{2 \text{ policies}} \\ &= \$80 \text{ per policy} \end{aligned}$$

Keeping track of units can help us interpret this quantity. Income increased by \$160 when the number of policies increased by 2, so the rate of change is \$80 per policy. Therefore, Ilya earns a commission of \$80 for each policy sold during the week.

We can then solve for the initial value.

$$\begin{aligned} I(n) &= 80n + b \\ 760 &= 80(3) + b \text{ when } n = 3, I(3) = 760 \\ 760 - 80(3) &= b \\ 520 &= b \end{aligned}$$

The value of $b$ is the starting value for the function and represents Ilya's income when $n = 0$, or when no new policies are sold. We can interpret this as Ilya's base salary for the week, which does not depend upon the number of policies sold.

We can now write the final equation.

$$I(n) = 80n + 520$$

Our final interpretation is that Ilya's base salary is \$520 per week and he earns an additional \$80 commission for each policy sold.

### Example 3.5.2.12: Using Tabular Form to Write an Equation for a Linear Function

Table 3.5.2.1relates the number of rats in a population to time, in weeks. Use the table to write a linear equation.

Table 3.5.2.1

| w, number of weeks | 0 | 2 | 4 | 6 |
|---|---|---|---|---|
| P(w), number of rats | 1000 | 1080 | 1160 | 1240 |

**Solution**

We can see from the table that the initial value for the number of rats is 1000, so $b = 1000$.

Rather than solving for $m$, we can tell from looking at the table that the population increases by 80 for every 2 weeks that pass. This means that the rate of change is 80 rats per 2 weeks, which can be simplified to 40 rats per week.

$$P(w) = 40w + 1000$$

If we did not notice the rate of change from the table we could still solve for the slope using any two points from the table. For example, using $(2, 1080)$and $(6, 1240)$

$$\begin{aligned} m &= \frac{1240 - 1080}{6 - 2} \\ &= \frac{160}{4} \\ &= 40 \end{aligned}$$

### Is the initial value always provided in a table of values?

*No. Sometimes the initial value is provided in a table of values, but sometimes it is not. If you see an input of 0, then the initial value would be the corresponding output. If the initial value is not provided because there is no value of input on the table equal to 0, find the slope, substitute one coordinate pair and the slope into $f(x) = mx + b$ , and solve for $b$.*

### Try It 3.5.2.6

A new plant food was introduced to a young tree to test its effect on the height of the tree. Table 3.5.2.2shows the height of the tree, in feet, $x$ months since the measurements began. Write a linear function, $H(x)$, where $x$ is the number of months since the start of the experiment.

Table 3.5.2.2

| $x$ | 0 | 2 | 4 | 8 | 12 |
|---|---|---|---|---|---|
| $H(x)$ | 12.5 | 13.5 | 14.5 | 16.5 | 18.5 |

**Answer**

$H(x) = 0.5x + 12.5$

## Key Equations

- slope-intercept form of a line: $f(x) = mx + b$

- slope: $m = \frac{\text{change in output (rise)}}{\text{change in input (run)}} = \frac{\Delta y}{\Delta x} = \frac{y_2 - y_1}{x_2 - x_1}$
- point-slope form of a line: $y - y_1 = m(x - x_1)$

## Key Concepts

- The ordered pairs given by a linear function represent points on a line.
- Linear functions can be represented in words, function notation, tabular form, and graphical form.
- The rate of change of a linear function is also known as the slope.
- An equation in the slope-intercept form of a line includes the slope and the initial value of the function.
- The initial value, or y-intercept, is the output value when the input of a linear function is zero. It is the y-value of the point at which the line crosses the y-axis.
- An increasing linear function results in a graph that slants upward from left to right and has a positive slope.
- A decreasing linear function results in a graph that slants downward from left to right and has a negative slope.
- A constant linear function results in a graph that is a horizontal line.
- Analyzing the slope within the context of a problem indicates whether a linear function is increasing, decreasing, or constant.
- The slope of a linear function can be calculated by dividing the difference between y-values by the difference in corresponding x-values of any two points on the line.
- The slope and initial value can be determined given a graph or any two points on the line.
- One type of function notation is the slope-intercept form of an equation.
- The point-slope form is useful for finding a linear equation when given the slope of a line and one point.
- The point-slope form is also convenient for finding a linear equation when given two points through which a line passes.
- The equation for a linear function can be written if the slope $m$ and initial value $b$ are known.
- A linear function can be used to solve real-world problems.
- A linear function can be written from tabular form.

## Footnotes

1 www.chinahighlights.com/shang...glev-train.htm
2 www.cbsnews.com/8301-501465_1...ay-study-says/

## Glossary

**decreasing linear function**

a function with a negative slope: If $f(x) = mx + b$, then $m < 0$.

**increasing linear function**

a function with a positive slope: If $f(x) = mx + b$, then $m > 0$.

**linear function**

a function with a constant rate of change that is a polynomial of degree 1, and whose graph is a straight line

**point-slope form**

the equation for a line that represents a linear function of the form \(y−y_1=m(x−x_1)

**slope**

the ratio of the change in output values to the change in input values; a measure of the steepness of a line

**slope-intercept form**

the equation for a line that represents a linear function in the form $f(x) = mx + b$

**y-intercept**

the value of a function when the input value is zero; also known as initial value

This page titled 3.5.2: Linear Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.1: Linear Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.5.3: Graphs of Linear Functions

**Learning Objectives**

- Graph linear functions.
- Write the equation for a linear function from the graph of a line.
- Given the equations of two lines, determine whether their graphs are parallel or perpendicular.
- Write the equation of a line parallel or perpendicular to a given line.
- Solve a system of linear equations.

Two competing telephone companies offer different payment plans. The two plans charge the same rate per long distance minute, but charge a different monthly flat fee. A consumer wants to determine whether the two plans will ever cost the same amount for a given number of long distance minutes used. The total cost of each payment plan can be represented by a linear function. To solve the problem, we will need to compare the functions. In this section, we will consider methods of comparing functions using graphs.

## Graphing Linear Functions

Previously, we saw that that the graph of a linear function is a straight line. We were also able to see the points of the function as well as the initial value from a graph. By graphing two functions, then, we can more easily compare their characteristics. There are three basic methods of graphing linear functions:

1. Plot the points and then drawing a line through the points.
2. Use the y-intercept and slope.
3. Use transformations of the identity function $f(x) = x$.

### Graphing a Function by Plotting Points

To find points of a function, we can choose input values, evaluate the function at these input values, and calculate output values. The input values and corresponding output values form coordinate pairs. We then plot the coordinate pairs on a grid. In general, we should evaluate the function at a minimum of two inputs in order to find at least two points on the graph. For example, given the function, $f(x) = 2x$, we might use the input values 1 and 2. Evaluating the function for an input value of 1 yields an output value of 2, which is represented by the point $(1, 2)$. Evaluating the function for an input value of 2 yields an output value of 4, which is represented by the point $(2, 4)$. Choosing three points is often advisable because if all three points do not fall on the same line, we know we made an error.

**How To: Given a linear function, graph by plotting points.**

1. Choose a minimum of two input values.
2. Evaluate the function at each input value.
3. Use the resulting output values to identify coordinate pairs.
4. Plot the coordinate pairs on a grid.
5. Draw a line through the points.

**Example 3.5.3.1: Graphing by Plotting Points**

Graph $f(x) = -\frac{2}{3}x + 5$ by plotting points.

**Solution**

Begin by choosing input values. This function includes a fraction with a denominator of 3, so let's choose multiples of 3 as input values. We will choose 0, 3, and 6.

Evaluate the function at each input value, and use the output value to identify coordinate pairs.

$$x=0 \qquad f(0) = -\frac{2}{3}(0)+5 = 5 \rightarrow (0,5)$$
$$x=3 \qquad f(3) = -\frac{2}{3}(3)+5 = 3 \rightarrow (3,3)$$
$$x=6 \qquad f(6) = -\frac{2}{3}(6)+5 = 1 \rightarrow (6,1)$$

Plot the coordinate pairs and draw a line through the points. Figure 3.5.3.1 represents the graph of the function $f(x) = -\frac{2}{3}x+5$.





Figure 3.5.3.1: The graph of the linear function $f(x) = -\frac{2}{3}x+5$.

**Analysis**

The graph of the function is a line as expected for a linear function. In addition, the graph has a downward slant, which indicates a negative slope. This is also expected from the negative constant rate of change in the equation for the function.

**Exercise 3.5.3.1**

Graph $f(x) = -\frac{3}{4}x+6$ by plotting points.

**Answer**





Figure 3.5.3.2

## Graphing a Function Using y-intercept and Slope

Another way to graph linear functions is by using specific characteristics of the function rather than plotting points. The first characteristic is its **y-intercept**, which is the point at which the input value is zero. To find the y-intercept, we can set $x = 0$ in the equation.

The other characteristic of the linear function is its slope $m$, which is a measure of its steepness. Recall that the slope is the rate of change of the function. The slope of a function is equal to the ratio of the change in outputs to the change in inputs. Another way to

think about the slope is by dividing the vertical difference, or rise, by the horizontal difference, or run. We encountered both the y-intercept and the slope in Linear Functions.

Let's consider the following function.

$$f(x) = \frac{1}{2}x + 1 \tag{3.5.3.1}$$

The slope is $\frac{1}{2}$. Because the slope is positive, we know the graph will slant upward from left to right. The y-intercept is the point on the graph when $x = 0$. The graph crosses the y-axis at $(0, 1)$. Now we know the slope and the y-intercept. We can begin graphing by plotting the point $(0, 1)$ We know that the slope is rise over run, $m = \frac{\text{rise}}{\text{run}}$. From our example, we have $m = \frac{1}{2}$, which means that the rise is 1 and the run is 2. So starting from our y-intercept $(0, 1)$, we can rise 1 and then run 2, or run 2 and then rise 1. We repeat until we have a few points, and then we draw a line through the points as shown in Figure $3.5.3.3$





Figure $3.5.3.3$: Graph of $f(x)$ showing slope and y-intercept

**Graphical Interpretation of a Linear Function**

In the equation $f(x) = mx + b$

- $b$ is the y-intercept of the graph and indicates the point $(0, b)$ at which the graph crosses the y-axis.
- $m$ is the slope of the line and indicates the vertical displacement (rise) and horizontal displacement (run) between each successive pair of points. Recall the formula for the slope:

$$m = \frac{\text{change in output (rise)}}{\text{change in input (run)}} = \frac{\Delta y}{\Delta x} = \frac{y_2 - y_1}{x_2 - x_1} \tag{3.5.3.2}$$

**Exercise $3.5.3.1$**

Do all linear functions have y-intercepts?

**Answer**

Yes. All linear functions cross the y-axis and therefore have y-intercepts. (Note: A vertical line parallel to the y-axis does not have a y-intercept, but it is not a function.)

**How To: Given the equation for a linear function, graph the function using the y-intercept and slope.**

1. Evaluate the function at an input value of zero to find the y-intercept.
2. Identify the slope as the rate of change of the input value.
3. Plot the point represented by the y-intercept.
4. Use $\frac{\text{rise}}{\text{run}}$ to determine at least two more points on the line.
5. Sketch the line that passes through the points.

### Example 3.5.3.2: Graphing by Using the y-intercept and Slope

Graph $f(x) = -\frac{2}{3}x + 5$ using the y-intercept and slope.

**Solution**

Evaluate the function at $x = 0$ to find the y-intercept. The output value when $x = 0$ is 5, so the graph will cross the y-axis at $(0, 5)$.

According to the equation for the function, the slope of the line is $-\frac{2}{3}$. This tells us that for each vertical decrease in the "rise" of –2 units, the "run" increases by 3 units in the horizontal direction. We can now graph the function by first plotting the y-intercept on the graph in Figure 3.5.3.4 From the initial value $(0, 5)$ we move down 2 units and to the right 3 units. We can extend the line to the left and right by repeating, and then draw a line through the points.





Figure 3.5.3.4: Graph of $f(x)$

**Analysis**

The graph slants downward from left to right, which means it has a negative slope as expected.

### Exercise 3.5.3.2

Find a point on the graph we drew in Example 3.5.3.2that has a negative x-value.

**Answer**

Possible answers include $(-3, 7)$, $(-6, 9)$, or $(-9, 11)$.

## Graphing a Function Using Transformations

Another option for graphing is to use **transformations** of the identity function $f(x) = x$. A function may be transformed by a shift up, down, left, or right. A function may also be transformed using a reflection, stretch, or compression.

### Vertical Stretch or Compression

In the equation $f(x) = mx$, the $m$ is acting as the **vertical stretch** or **compression** of the identity function. When $m$ is negative, there is also a vertical reflection of the graph. Notice in Figure 3.5.3.5that multiplying the equation of $f(x) = x$ by $m$ stretches the graph of $f$ by a factor of $m$ units if $m > 1$ and compresses the graph of $f$ by a factor of $m$ units if $0 < m < 1$ . This means the larger the absolute value of $m$, the steeper the slope.





Figure 3.5.3.5: Vertical stretches and compressions and reflections on the function $f(x) = x$.

## Vertical Shift

In $f(x) = mx + b$, the $b$ acts as the **vertical shift**, moving the graph up and down without affecting the slope of the line. Notice in Figure 3.5.3.6that adding a value of $b$ to the equation of $f(x) = x$ shifts the graph of $f$ a total of $b$ units up if $b$ is positive and $|b|$ units down if $b$ is negative.





Figure 3.5.3.6: This graph illustrates vertical shifts of the function $f(x) = x$.

Using vertical stretches or compressions along with vertical shifts is another way to look at identifying different types of linear functions. Although this may not be the easiest way to graph this type of function, it is still important to practice each method.

**How To: Given the equation of a linear function, use transformations to graph the linear function in the form $f(x) = mx + b$.**

1. Graph $f(x) = x$.
2. Vertically stretch or compress the graph by a factor $m$.
3. Shift the graph up or down $b$ units.

**Example 3.5.3.3: Graphing by Using Transformations**

Graph $f(x) = \frac{1}{2}x - 3$ using transformations.

**Solution**

The equation for the function shows that $m = \frac{1}{2}$ so the identity function is vertically compressed by $\frac{1}{2}$. The equation for the function also shows that $b = -3$ so the identity function is vertically shifted down 3 units. First, graph the identity function, and show the vertical compression as in Figure 3.5.3.7.





Figure 3.5.3.7: The function, $y = x$, compressed by a factor of $\frac{1}{2}$.

Then show the vertical shift as in Figure 3.5.3.8





Figure 3.5.3.8: The function $y = \frac{1}{2}x$, shifted down 3 units.

**Exercise 3.5.3.3**

Graph $f(x) = 4 + 2x$, using transformations.

**Answer**





Figure 3.5.3.9

**In Example 2.2.3, could we have sketched the graph by reversing the order of the transformations?**

*No. The order of the transformations follows the order of operations. When the function is evaluated at a given input, the corresponding output is calculated by following the order of operations. This is why we performed the compression first. For example, following the order: Let the input be 2.*

$$f(2) = \frac{1}{2}(2) - 3 \tag{3.5.3.3}$$
$$= 1 - 3 \tag{3.5.3.4}$$
$$= -2 \tag{3.5.3.5}$$

## Writing the Equation for a Function from the Graph of a Line

Recall that in Linear Functions, we wrote the equation for a linear function from a graph. Now we can extend what we know about graphing linear functions to analyze graphs a little more closely. Begin by taking a look at Figure 3.5.3.10 We can see right away that the graph crosses the y-axis at the point $(0, 4)$ so this is the y-intercept.





Figure 3.5.3.10: Graph of a linear function

Then we can calculate the slope by finding the rise and run. We can choose any two points, but let's look at the point (−2,0). To get from this point to the y-intercept, we must move up 4 units (rise) and to the right 2 units (run). So the slope must be

$$m = \frac{\text{rise}}{\text{run}} = \frac{4}{2} = 2 \tag{3.5.3.6}$$

Substituting the slope and y-intercept into the slope-intercept form of a line gives

$$y = 2x + 4 \tag{3.5.3.7}$$

**How To: Given a graph of linear function, find the equation to describe the function.**

1. Identify the y-intercept of an equation.
2. Choose two points to determine the slope.
3. Substitute the y-intercept and slope into the slope-intercept form of a line.

**Example 3.5.3.4: Matching Linear Functions to Their Graphs**

Match each equation of the linear functions with one of the lines in Figure 3.5.3.11.

a. $f(x) = 2x + 3$
b. $g(x) = 2x - 3$
c. $h(x) = -2x + 3$
d. $j(x) = \frac{1}{2}x + 3$





Figure 3.5.3.11: Graph of four linear functions

***Solution***

Analyze the information for each function.

a. This function has a slope of 2 and a y-intercept of 3. It must pass through the point $(0, 3)$ and slant upward from left to right. We can use two points to find the slope, or we can compare it with the other functions listed. Function $g$ has the same slope, but a different y-intercept. Lines I and III have the same slant because they have the same slope. Line III does not pass through $(0, 3)$ so $f$ must be represented by line I.
b. This function also has a slope of 2, but a y-intercept of −3. It must pass through the point $(0, -3)$ and slant upward from left to right. It must be represented by line III.
c. This function has a slope of –2 and a y-intercept of 3. This is the only function listed with a negative slope, so it must be represented by line IV because it slants downward from left to right.
d. This function has a slope of $\frac{1}{2}$ and a y-intercept of 3. It must pass through the point (0, 3) and slant upward from left to right. Lines I and II pass through $(0, 3)$, but the slope of $j$ is less than the slope of $f$ so the line for $j$ must be flatter. This function is represented by Line II.

Now we can re-label the lines as in Figure 3.5.3.12





Figure 3.5.3.12

## Finding the x-intercept of a Line

So far, we have been finding the y-intercepts of a function: the point at which the graph of the function crosses the y-axis. A function may also have an x-intercept, which is the x-coordinate of the point where the graph of the function crosses the x-axis. In other words, it is the input value when the output value is zero.

To find the x-intercept, set a function $f(x)$ equal to zero and solve for the value of $x$. For example, consider the function shown.

$$f(x) = 3x - 6 \tag{3.5.3.8}$$

Set the function equal to 0 and solve for $x$.

$$0 = 3x - 6 \tag{3.5.3.9}$$
$$6 = 3x \tag{3.5.3.10}$$
$$2 = x \tag{3.5.3.11}$$
$$x = 2 \tag{3.5.3.12}$$

The graph of the function crosses the x-axis at the point $(2, 0)$.

**Do all linear functions have x-intercepts?**

Figure 3.5.3.13.





Figure 3.5.3.13: Graph of $y = 5$.

**Note: x-intercept**

The **x-intercept** of the function is value of $x$ when $f(x) = 0$. It can be solved by the equation $0 = mx + b$.

**Example 3.5.3.5: Finding an x-intercept**

Find the x-intercept of $f(x) = \frac{1}{2} - 3$.

**Solution**

Set the function equal to zero to solve for $x$.

$$\begin{aligned} 0 &= \frac{1}{2}x - 3 \\ 3 &= \frac{1}{2}x \\ 6 &= x \\ x &= 6 \end{aligned}$$

The graph crosses the x-axis at the point $(6, 0)$.

**Analysis**

A graph of the function is shown in Figure 3.5.3.14 We can see that the x-intercept is $(6, 0)$ as we expected.





Figure 3.5.3.14: The graph of the linear function $f(x) = \frac{1}{2}x - 3$.

**Exercise 3.5.3.5**


Find the x-intercept of $f(x) = \frac{1}{4}x - 4$.

**Answer**

$(16, 0)$

## Describing Horizontal and Vertical Lines

There are two special cases of lines on a graph—horizontal and vertical lines. A **horizontal line** indicates a constant output, or y-value. In Figure 3.5.3.15, we see that the output has a value of 2 for every input value. The change in outputs between any two points, therefore, is 0. In the slope formula, the numerator is 0, so the slope is 0. If we use $m = 0$ in the equation $f(x) = mx + b$, the equation simplifies to $f(x) = b$. In other words, the value of the function is a constant. This graph represents the function $f(x) = 2$.




| $x$ | $-4$ | $-2$ | $0$ | $2$ | $4$ |
|---|---|---|---|---|---|
| $y$ | $2$ | $2$ | $2$ | $2$ | $2$ |

Figure 3.5.3.15: A horizontal line representing the function $f(x) = 2$.

A **vertical line** indicates a constant input, or x-value. We can see that the input value for every point on the line is 2, but the output value varies. Because this input value is mapped to more than one output value, a vertical line does not represent a function. Notice that between any two points, the change in the input values is zero. In the slope formula, the denominator will be zero, so the slope of a vertical line is undefined.






Figure 3.5.3.16

Notice that a vertical line, such as the one in Figure 3.5.3.17, has an x-intercept, but no y-intercept unless it's the line $x = 0$. This graph represents the line $x = 2$.




| $x$ | $2$ | $2$ | $2$ | $2$ | $2$ |
|---|---|---|---|---|---|
| $y$ | $-4$ | $-2$ | $0$ | $2$ | $4$ |

Figure 3.5.3.17: The vertical line, $x = 2$, which does not represent a function.

**Definitions: Horizontal and Vertical Lines**

Lines can be horizontal or vertical.

- A **horizontal line** is a line defined by an equation in the form $f(x) = b$.
- A **vertical line** is a line defined by an equation in the form $x = a$.

### Example 3.5.3.6: Writing the Equation of a Horizontal Line

Write the equation of the line graphed in Figure 3.5.3.18





Figure 3.5.3.18: Graph of $x = 7$.

**Solution**

For any x-value, the y-value is $-4$, so the equation is $y = -4$.

### Example 3.5.3.7: Writing the Equation of a Vertical Line

Write the equation of the line graphed in Figure 3.5.3.19





Figure 3.5.3.19: Graph of a vertical line

**Solution**

The constant x-value is 7, so the equation is $x = 7$.

## Determining Whether Lines are Parallel or Perpendicular

The two lines in Figure 3.5.3.20 are **parallel lines**: they will never intersect. Notice that they have exactly the same steepness, which means their slopes are identical. The only difference between the two lines is the y-intercept. If we shifted one line vertically toward the y-intercept of the other, they would become the same line.





Figure 3.5.3.20: Parallel lines.

We can determine from their equations whether two lines are parallel by comparing their slopes. If the slopes are the same and the y-intercepts are different, the lines are parallel. If the slopes are different, the lines are not parallel.

$$\left.\begin{array}{l} f(x)=-2x+6 \\ f(x)=-2x-4 \end{array}\right\} \text{ parallel} \qquad \left.\begin{array}{l} f(x)=3x+2 \\ f(x)=2x+2 \end{array}\right\} \text{ not parallel}$$

Figure 3.5.3.21 are perpendicular.





Figure 3.5.3.21: Perpendicular lines.

Perpendicular lines do not have the same slope. The slopes of perpendicular lines are different from one another in a specific way. The slope of one line is the negative reciprocal of the slope of the other line. The product of a number and its reciprocal is 1. So, if $m_1$ and $m_2$ are negative reciprocals of one another, they can be multiplied together to yield –1.

$$m_1 m_2 = -1 \tag{3.5.3.13}$$

To find the reciprocal of a number, divide 1 by the number. So the reciprocal of 8 is $\frac{1}{8}$, and the reciprocal of $\frac{1}{8}$ is 8. To find the negative reciprocal, first find the reciprocal and then change the sign.

As with parallel lines, we can determine whether two lines are perpendicular by comparing their slopes, assuming that the lines are neither horizontal nor perpendicular. The slope of each line below is the negative reciprocal of the other so the lines are perpendicular.

$$f(x) = \frac{1}{4}x + 2 \qquad \text{negative reciprocal of } \frac{1}{4} \text{ is -4} \tag{3.5.3.14}$$

$$f(x) = -4x + 3 \qquad \text{negative reciprocal of -4 is } \frac{1}{4} \tag{3.5.3.15}$$

The product of the slopes is –1.

$$-4\left(\frac{1}{4}\right) = -1 \tag{3.5.3.16}$$

**Definitions: Parallel and Perpendicular Lines**

Two lines are **parallel lines** if they do not intersect. The slopes of the lines are the same.

$f(x) = m_1x + b_1$ and $g(x) = m_2x + b_2$ are parallel if $m_1 = m_2$.

If and only if $b_1 = b_2$ and $m_1 = m_2$, we say the lines coincide. Coincident lines are the same line.

Two lines are **perpendicular lines** if they intersect at right angles.

$f(x) = m_1x + b_1$ and $g(x) = m_2x + b_2$ are perpendicular if $m_1m_2 = -1$, and so $m_2 = \dfrac{-1}{m_1}$.

**Example 3.5.3.8: Identifying Parallel and Perpendicular Lines**

Given the functions below, identify the functions whose graphs are a pair of parallel lines and a pair of perpendicular lines.

$$f(x) = 2x + 3 \qquad h(x) = -2x + 2 \tag{3.5.3.17}$$

$$g(x) = \frac{1}{2}x - 4 \qquad f(x) = 2x - 6 \tag{3.5.3.18}$$

**Solution**

Parallel lines have the same slope. Because the functions $f(x) = 2x + 3$ and $j(x) = 2x - 6$ each have a slope of 2, they represent parallel lines. Perpendicular lines have negative reciprocal slopes. Because −2 and $\frac{1}{2}$ are negative reciprocals, the equations, $g(x) = \frac{1}{2}x - 4$ and $h(x) = -2x + 2$ represent perpendicular lines.

**Analysis**

A graph of the lines is shown in Figure 3.5.3.22





Figure 3.5.3.22: Graph of $h(x)$ (blue), $f(x)$ (orange), $j(x)$ (green), and $g(x)$ (red)

The graph shows that the lines $f(x) = 2x + 3$ and $j(x) = 2x - 6$ are parallel, and the lines $g(x) = \frac{1}{2}x - 4$ and $h(x) = -2x + 2$ are perpendicular.

## Writing the Equation of a Line Parallel or Perpendicular to a Given Line

If we know the equation of a line, we can use what we know about slope to write the equation of a line that is either parallel or perpendicular to the given line.

## Writing Equations of Parallel Lines

Suppose for example, we are given the following equation.

$$f(x) = 3x + 1$$

We know that the slope of the line formed by the function is 3. We also know that the y-intercept is $(0, 1)$. Any other line with a slope of 3 will be parallel to $f(x)$. So the lines formed by all of the following functions will be parallel to $f(x)$.

$$\begin{aligned} g(x) &= 3x + 6 \\ h(x) &= 3x + 1 \\ p(x) &= 3x + \frac{2}{3} \end{aligned}$$

Suppose then we want to write the equation of a line that is parallel to $f$ and passes through the point $(1, 7)$. We already know that the slope is 3. We just need to determine which value for $b$ will give the correct line. We can begin with the point-slope form of an equation for a line, and then rewrite it in the slope-intercept form.

$$\begin{aligned} y - y_1 &= m(x - x_1) \\ y - 7 &= 3(x - 1) \\ y - 7 &= 3x - 3 \\ y &= 3x + 4 \end{aligned}$$

So $g(x) = 3x + 4$ is parallel to $f(x) = 3x + 1$ and passes through the point $(1, 7)$.

**How to ...**

Given the equation of a function and a point through which its graph passes, write the equation of a line parallel to the given line that passes through the given point.

1. Find the slope of the function.
2. Substitute the given values into either the general point-slope equation or the slope-intercept equation for a line.
3. Simplify.

**Example 3.5.3.9: Finding a Line Parallel to a Given Line**

Find a line parallel to the graph of $f(x) = 3x + 6$ that passes through the point $(3, 0)$.

**Solution**

The slope of the given line is 3. If we choose the slope-intercept form, we can substitute $m = 3$, $x = 3$, and $f(x) = 0$ into the slope-intercept form to find the y-intercept.

$$\begin{aligned} g(x) &= 3x + b \\ 0 &= 3(3) + b \\ b &= -9 \end{aligned}$$

The line parallel to $f(x)$ that passes through $(3, 0)$ is $g(x) = 3x - 9$.

**Analysis**

We can confirm that the two lines are parallel by graphing them. Figure 3.5.3.23shows that the two lines will never intersect.





Figure 3.5.3.23: Graph of two functions where the blue line is $y = 3x + 6$ , and the orange line is $y = 3x - 9$ .

## Writing Equations of Perpendicular Lines

We can use a very similar process to write the equation for a line perpendicular to a given line. Instead of using the same slope, however, we use the negative reciprocal of the given slope. Suppose we are given the following function:

$$f(x) = 2x + 4$$

The slope of the line is 2, and its negative reciprocal is $-\frac{1}{2}$. Any function with a slope of $-\frac{1}{2}$ will be perpendicular to $f(x)$. So the lines formed by all of the following functions will be perpendicular to $f(x)$.

$$g(x) = -\frac{1}{2}x + 4$$

$$h(x) = -\frac{1}{2}x + 2$$

$$p(x) = -\frac{1}{2}x - \frac{1}{2}$$

As before, we can narrow down our choices for a particular perpendicular line if we know that it passes through a given point. Suppose then we want to write the equation of a line that is perpendicular to $f(x)$ and passes through the point $(4, 0)$. We already know that the slope is $-\frac{1}{2}$. Now we can use the point to find the y-intercept by substituting the given values into the slope-intercept form of a line and solving for $b$.

$$\begin{aligned} g(x) &= mx + b \\ 0 &= -\frac{1}{2}(4) + b \\ 0 &= -2 + b \\ 2 &= b \\ b &= 2 \end{aligned}$$

The equation for the function with a slope of $-\frac{1}{2}$ and a y-intercept of 2 is

$$g(x) = -\frac{1}{2}x + 2 \tag{3.5.3.19}$$

So $g(x) = -\frac{1}{2}x + 2$ is perpendicular to $f(x) = 2x + 4$ and passes through the point $(4, 0)$. Be aware that perpendicular lines may not look obviously perpendicular on a graphing calculator unless we use the square zoom feature.

**A horizontal line has a slope of zero and a vertical line has an undefined slope. These two lines are perpendicular, but the product of their slopes is not –1. Doesn't this fact contradict the definition of perpendicular lines?**

*No. For two perpendicular linear functions, the product of their slopes is –1. However, a vertical line is not a function so the definition is not contradicted.*

**How To...**

Given the equation of a function and a point through which its graph passes, write the equation of a line perpendicular to the given line.

1. Find the slope of the function.
2. Determine the negative reciprocal of the slope.
3. Substitute the new slope and the values for $x$ and $y$ from the coordinate pair provided into $g(x)=mx+b$.
4. Solve for $b$.
5. Write the equation for the line.

**Example 3.5.3.10: Finding the Equation of a Perpendicular Line**

Find the equation of a line perpendicular to $f(x)=3x+3$ that passes through the point $(3,0)$.

**Solution**

The original line has slope $m=3$, so the slope of the perpendicular line will be its negative reciprocal, or $-\frac{1}{3}$. Using this slope and the given point, we can find the equation for the line.

$$\begin{aligned} g(x) &= -\frac{1}{3}x+b \\ 0 &= -\frac{1}{3}(3)+b \\ 1 &= b \\ b &= 1 \end{aligned}$$

The line perpendicular to $f(x)$ that passes through $(3,0)$ is $g(x)=-\frac{1}{3}x+1$.

**Analysis**

A graph of the two lines is shown in Figure 3.5.3.24below.





Figure 3.5.3.24: Graph of two functions where the blue line is $g(x)=-\frac{1}{3}x+1$, and the orange line is $f(x)=3x+6$.

**Exercise 3.5.3.5**

Given the function $h(x) = 2x - 4$, write an equation for the line passing through $(0, 0)$ that is

a. parallel to $h(x)$
b. perpendicular to $h(x)$

**Answer**

$f(x) = 2x \;\; g(x) = -\frac{1}{2}x$

**How to...**

Given two points on a line and a third point, write the equation of the perpendicular line that passes through the point.

1. Determine the slope of the line passing through the points.
2. Find the negative reciprocal of the slope.
3. Use the slope-intercept form or point-slope form to write the equation by substituting the known values.
4. Simplify.

**Example 3.5.3.11: Finding the Equation of a Line Perpendicular to a Given Line Passing through a Point**

A line passes through the points $(-2, 6)$ and $(4, 5)$. Find the equation of a perpendicular line that passes through the point $(4, 5)$.

From the two points of the given line, we can calculate the slope of that line.

$$\begin{aligned} m_1 &= \frac{5-6}{4-(-2)} \\ &= \frac{-1}{6} \\ &= -\frac{1}{6} \end{aligned}$$

Find the negative reciprocal of the slope.

$$\begin{aligned} m_2 &= \frac{-1}{-\frac{1}{6}} \\ &= -1\left(-\frac{6}{1}\right) \\ &= 6 \end{aligned}$$

We can then solve for the y-intercept of the line passing through the point $(4, 5)$.

$$\begin{aligned} g(x) &= 6x + b \\ 5 &= 6(4) + b \\ 5 &= 24 + b \\ -19 &= b \\ b &= -19 \end{aligned}$$

The equation for the line that is perpendicular to the line passing through the two given points and also passes through point $(4, 5)$ is

$$y = 6x - 19$$

**Exercise 3.5.3.1**

A line passes through the points, $(-2,-15)$ and $(2,-3)$. Find the equation of a perpendicular line that passes through the point, $(6,4)$.

**Answer**

$$y=-\frac{1}{3}x+6$$

## Solving a System of Linear Equations Using a Graph

A system of linear equations includes two or more linear equations. The graphs of two lines will intersect at a single point if they are not parallel. Two parallel lines can also intersect if they are coincident, which means they are the same line and they intersect at every point. For two lines that are not parallel, the single point of intersection will satisfy both equations and therefore represent the solution to the system.

To find this point when the equations are given as functions, we can solve for an input value so that $f(x)=g(x)$. In other words, we can set the formulas for the lines equal to one another, and solve for the input that satisfies the equation.

**Example 3.5.3.12: Finding a Point of Intersection Algebraically**

Find the point of intersection of the lines $h(t)=3t-4$ and $j(t)=5-t$ .

**Solution**

Set $h(t)=j(t)$ .

$$3t-4=5-t \tag{3.5.3.20}$$
$$4t=9 \tag{3.5.3.21}$$
$$t=\frac{9}{4} \tag{3.5.3.22}$$

This tells us the lines intersect when the input is $\frac{9}{4}$.

We can then find the output value of the intersection point by evaluating either function at this input.

$$j\left(\frac{9}{4}\right)=5-\frac{9}{4} \tag{3.5.3.23}$$
$$=\frac{11}{4} \tag{3.5.3.24}$$

These lines intersect at the point $\left(\frac{9}{4},\frac{11}{4}\right)$.

**Analysis**

Looking at Figure 3.5.3.25, this result seems reasonable.





Figure 3.5.3.25: Graph of two functions $h(t) = 3t - 4$ and $j(t) = t + 5$ and their intersection at $(\frac{9}{4}, \frac{11}{4})$.

**If we were asked to find the point of intersection of two distinct parallel lines, should something in the solution process alert us to the fact that there are no solutions?**

*Yes. After setting the two equations equal to one another, the result would be the contradiction "* $0 =$ non-zero real number *".*

## Exercise 3.5.3.7

Look at the graph in Figure 3.5.3.23and identify the following for the function $j(t)$ :

a. y-intercept
b. x-intercept(s)
c. slope
d. Is $j(t)$ parallel or perpendicular to $h(t)$ (or neither)?
e. Is $j(t)$ an increasing or decreasing function (or neither)?
f. Write a transformation description for $j(t)$ from the identity toolkit function $f(x) = x$.

**Answer**

a. $(0, 5)$
b. (5, 0)
c. Slope -1
d. Neither parallel nor perpendicular
e. Decreasing function
f. Given the identity function, perform a vertical flip (over the t-axis) and shift up 5 units.

## Example 3.5.3.13: Finding a Break-Even Point

A company sells sports helmets. The company incurs a one-time fixed cost for $250,000. Each helmet costs $120 to produce, and sells for $140.

a. Find the cost function, $C$, to produce $x$ helmets, in dollars.
b. Find the revenue function, $R$, from the sales of $x$ helmets, in dollars.
c. Find the break-even point, the point of intersection of the two graphs $C$ and $R$.

**Solution**

a. The cost function in the sum of the fixed cost, $125,000, and the variable cost, $120 per helmet.

$$C(x) = 120x + 250,000$$

b. The revenue function is the total revenue from the sale of $x$ helmets, $R(x) = 140x$.

c. The break-even point is the point of intersection of the graph of the cost and revenue functions. To find the x-coordinate of the coordinate pair of the point of intersection, set the two equations equal, and solve for $x$.

$$\begin{aligned} C(x) &= R(x) \\ 250,000 + 120x &= 140x \\ 250,000 &= 20x \\ x &= 12,500 \end{aligned}$$

To find $y$, evaluate either the revenue or the cost function at 12,500.

$$\begin{aligned} R(20) &= 140(12,500) \\ &= \$1,750,000 \end{aligned}$$

The break-even point is $(12,500, 1,750,000)$.

**Analysis**

This means if the company sells 12,500 helmets, they break even; both the sales and cost incurred equaled 1.75 million dollars. See Figure 3.5.3.26





Figure 3.5.3.26: Graph of the two functions, $C(x)$ and $R(x)$ where it shows that below $(12500, 1750000)$ the company loses money and above that point the company makes a profit.

## Key Concepts

- Linear functions may be graphed by plotting points or by using the y-intercept and slope.
- Graphs of linear functions may be transformed by using shifts up, down, left, or right, as well as through stretches, compressions, and reflections.
- The y-intercept and slope of a line may be used to write the equation of a line.
- The x-intercept is the point at which the graph of a linear function crosses the x-axis.
- Horizontal lines are written in the form, $f(x) = b$.

- Vertical lines are written in the form, $x = b$.
- Parallel lines have the same slope.
- Perpendicular lines have negative reciprocal slopes, assuming neither is vertical.
- A line parallel to another line, passing through a given point, may be found by substituting the slope value of the line and the x- and y-values of the given point into the equation, $f(x) = mx + b$, and using the $b$ that results. Similarly, the point-slope form of an equation can also be used.
- A line perpendicular to another line, passing through a given point, may be found in the same manner, with the exception of using the negative reciprocal slope.
- A system of linear equations may be solved setting the two equations equal to one another and solving for $x$. The y-value may be found by evaluating either one of the original equations using this x-value.
- A system of linear equations may also be solved by finding the point of intersection on a graph.

## Glossary

horizontal line
a line defined by $f(x) = b$, where $b$ is a real number. The slope of a horizontal line is 0.

parallel lines
two or more lines with the same slope

perpendicular lines
two lines that intersect at right angles and have slopes that are negative reciprocals of each other

vertical line
a line defined by $x = a$, where a is a real number. The slope of a vertical line is undefined.

x-intercept
the point on the graph of a linear function when the output value is 0; the point at which the graph crosses the horizontal axis

---

This page titled 3.5.3: Graphs of Linear Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.2: Graphs of Linear Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.5.4: Modeling with Linear Functions

**Learning Objectives**

- Build linear models from verbal descriptions.
- Model a set of data with a linear function.

Emily is a college student who plans to spend a summer in Seattle. She has saved $3,500 for her trip and anticipates spending $400 each week on rent, food, and activities. How can we write a linear model to represent her situation? What would be the x-intercept, and what can she learn from it? To answer these and related questions, we can create a model using a linear function. Models such as this one can be extremely useful for analyzing relationships and making predictions based on those relationships. In this section, we will explore examples of **linear function** models.



Figure 3.5.4.1: (credit: EEK Photography/Flickr)

## Identifying Steps to Model and Solve Problems

When **modeling** scenarios with linear functions and solving problems involving quantities with a **constant rate of change**, we typically follow the same problem strategies that we would use for any type of function. Let's briefly review them:

Identify changing quantities, and then define descriptive variables to represent those quantities. When appropriate, sketch a picture or define a coordinate system.
Carefully read the problem to identify important information. Look for information that provides values for the variables or values for parts of the functional model, such as slope and initial value.
Carefully read the problem to determine what we are trying to find, identify, solve, or interpret.
Identify a solution pathway from the provided information to what we are trying to find. Often this will involve checking and tracking units, building a table, or even finding a formula for the function being used to model the problem.
When needed, write a formula for the function.
Solve or evaluate the function using the formula.
Reflect on whether your answer is reasonable for the given situation and whether it makes sense mathematically.
Clearly convey your result using appropriate units, and answer in full sentences when necessary.

## Building Linear Models

Now let's take a look at the student in Seattle. In her situation, there are two changing quantities: time and money. The amount of money she has remaining while on vacation depends on how long she stays. We can use this information to define our variables, including units.

- Output: $M$, money remaining, in dollars
- Input: $t$, time, in weeks

So, the amount of money remaining depends on the number of weeks: $M(t)$

We can also identify the initial value and the rate of change.

- Initial Value: She saved $3,500, so $3,500 is the initial value for M.
- Rate of Change: She anticipates spending $400 each week, so –$400 per week is the rate of change, or slope.

Notice that the unit of dollars per week matches the unit of our output variable divided by our input variable. Also, because the slope is negative, the linear function is decreasing. This should make sense because she is spending money each week.

The **rate of change is constant**, so we can start with the linear model $M(t) = mt + b$ . Then we can substitute the intercept and slope provided.





Figure 3.5.4.2

To find the x-intercept, we set the output to zero, and solve for the input.

$$\begin{aligned} 0 &= -400t + 3500 \\ t &= \frac{3500}{400} \\ &= 8.75 \end{aligned}$$

The x-intercept is 8.75 weeks. Because this represents the input value when the output will be zero, we could say that Emily will have no money left after 8.75 weeks.

When modeling any real-life scenario with functions, there is typically a limited domain over which that model will be valid—almost no trend continues indefinitely. Here the domain refers to the number of weeks. In this case, it doesn't make sense to talk about input values less than zero. A negative input value could refer to a number of weeks before she saved $3,500, but the scenario discussed poses the question once she saved $3,500 because this is when her trip and subsequent spending starts. It is also likely that this model is not valid after the x-intercept, unless Emily will use a credit card and goes into debt. The domain represents the set of input values, so the reasonable domain for this function is $0 \le t \le 8.75$.

In the above example, we were given a written description of the situation. We followed the steps of modeling a problem to analyze the information. However, the information provided may not always be the same. Sometimes we might be provided with an intercept. Other times we might be provided with an output value. We must be careful to analyze the information we are given, and use it appropriately to build a linear model.

## Using a Given Intercept to Build a Model

Some real-world problems provide the y-intercept, which is the constant or initial value. Once the y-intercept is known, the x-intercept can be calculated. Suppose, for example, that Hannah plans to pay off a no-interest loan from her parents. Her loan balance is $1,000. She plans to pay $250 per month until her balance is $0. The y-intercept is the initial amount of her debt, or $1,000. The rate of change, or slope, is -$250 per month. We can then use the slope-intercept form and the given information to develop a linear model.

$$\begin{aligned} f(x) &= mx + b \\ &= -250x + 1000 \end{aligned}$$

Now we can set the function equal to 0, and solve for $x$ to find the x-intercept.

$$\begin{aligned} 0 &= -250 + 1000 \\ 1000 &= 250x \\ 4 &= x \\ x &= 4 \end{aligned}$$

The x-intercept is the number of months it takes her to reach a balance of $0. The x-intercept is 4 months, so it will take Hannah four months to pay off her loan.

## Using a Given Input and Output to Build a Model

Many real-world applications are not as direct as the ones we just considered. Instead they require us to identify some aspect of a linear function. We might sometimes instead be asked to evaluate the linear model at a given input or set the equation of the linear model equal to a specified output.

**How To: Given a word problem that includes two pairs of input and output values, use the linear function to solve a problem.**

1. Identify the input and output values.
2. Convert the data to two coordinate pairs.
3. Find the slope.
4. Write the linear model.
5. Use the model to make a prediction by evaluating the function at a given x-value.
6. Use the model to identify an x-value that results in a given y-value.
7. Answer the question posed.

### Example 3.5.4.1: Using a Linear Model to Investigate a Town's Population

A town's population has been growing linearly. In 2004 the population was 6,200. By 2009 the population had grown to 8,100. Assume this trend continues.

a. Predict the population in 2013.
b. Identify the year in which the population will reach 15,000.

**Solution**

The two changing quantities are the population size and time. While we could use the actual year value as the input quantity, doing so tends to lead to very cumbersome equations because the y-intercept would correspond to the year 0, more than 2000 years ago!

To make computation a little nicer, we will define our input as the number of years since 2004:

- Input: $t$, years since 2004
- Output: $P(t)$, the town's population

To predict the population in 2013 ($t = 9$), we would first need an equation for the population. Likewise, to find when the population would reach 15,000, we would need to solve for the input that would provide an output of 15,000. To write an equation, we need the initial value and the rate of change, or slope.

To determine the rate of change, we will use the change in output per change in input.

$$m = \frac{\text{change in output}}{\text{change in input}} \tag{3.5.4.1}$$

The problem gives us two input-output pairs. Converting them to match our defined variables, the year 2004 would correspond to $t = 0$, giving the point $(0, 6200)$. Notice that through our clever choice of variable definition, we have "given" ourselves the y-intercept of the function. The year 2009 would correspond to $t = 5$, giving the point $(5, 8100)$.

The two coordinate pairs are $(0, 6200)$ and $(5, 8100)$. Recall that we encountered examples in which we were provided two points earlier in the chapter. We can use these values to calculate the slope.

$$\begin{aligned} m &= \frac{8100 - 6200}{5 - 0} \\ &= \frac{1900}{5} \\ &= 380 \text{ people per year} \end{aligned}$$

We already know the y-intercept of the line, so we can immediately write the equation:

$$P(t) = 380t + 6200 \tag{3.5.4.2}$$

To predict the population in 2013, we evaluate our function at $t = 9$.

$$\begin{aligned} P(9) &= 380(9)+6,200 \\ &= 9,620 \end{aligned}$$

If the trend continues, our model predicts a population of 9,620 in 2013.

To find when the population will reach 15,000, we can set $P(t) = 15000$ and solve for $t$.

$$\begin{aligned} 15000 &= 380t+6200 \\ 8800 &= 380t \\ t &\approx 23.158 \end{aligned}$$

Our model predicts the population will reach 15,000 in a little more than 23 years after 2004, or somewhere around the year 2027.

### Exercise 3.5.4.1$A$

A company sells doughnuts. They incur a fixed cost of $25,000 for rent, insurance, and other expenses. It costs $0.25 to produce each doughnut.

a. Write a linear model to represent the cost C of the company as a function of $x$, the number of doughnuts produced.
b. Find and interpret the y-intercept.

**Solution**

a. $C(x) = 0.25x + 25,000$ b. The y-intercept is $(0, 25,000)$. If the company does not produce a single doughnut, they still incur a cost of $25,000.

### Exercise 3.5.4.1$B$

A city's population has been growing linearly. In 2008, the population was 28,200. By 2012, the population was 36,800. Assume this trend continues.

a. Predict the population in 2014.
b. Identify the year in which the population will reach 54,000.

**Solution**

a. 41,100 b. 2020

## Using a Diagram to Model a Problem

It is useful for many real-world applications to draw a picture to gain a sense of how the variables representing the input and output may be used to answer a question. To draw the picture, first consider what the problem is asking for. Then, determine the input and the output. The diagram should relate the variables. Often, geometrical shapes or figures are drawn. Distances are often traced out. If a right triangle is sketched, the Pythagorean Theorem relates the sides. If a rectangle is sketched, labeling width and height is helpful.

### Example 3.5.4.2: Using a Diagram to Model Distance Walked

Anna and Emanuel start at the same intersection. Anna walks east at 4 miles per hour while Emanuel walks south at 3 miles per hour. They are communicating with a two-way radio that has a range of 2 miles. How long after they start walking will they fall out of radio contact?

**Solution**

In essence, we can partially answer this question by saying they will fall out of radio contact when they are 2 miles apart, which leads us to ask a new question:

"How long will it take them to be 2 miles apart?"

In this problem, our changing quantities are time and position, but ultimately we need to know how long will it take for them to be 2 miles apart. We can see that time will be our input variable, so we'll define our input and output variables.

- Input: $t$, time in hours.
- Output: $A(t)$, distance in miles, and $E(t)$, distance in miles

Because it is not obvious how to define our output variable, we'll start by drawing a picture such as Figure 3.5.4.3





Figure 3.5.4.3

- Initial Value: They both start at the same intersection so when $t = 0$, the distance traveled by each person should also be 0. Thus the initial value for each is 0.
- Rate of Change: Anna is walking 4 miles per hour and Emanuel is walking 3 miles per hour, which are both rates of change. The slope for $A$ is 4 and the slope for $E$ is 3.

Using those values, we can write formulas for the distance each person has walked.

$$A(t) = 4t \tag{3.5.4.3}$$

$$E(t) = 3t \tag{3.5.4.4}$$

For this problem, the distances from the starting point are important. To notate these, we can define a coordinate system, identifying the "starting point" at the intersection where they both started. Then we can use the variable, $A$, which we introduced above, to represent Anna's position, and define it to be a measurement from the starting point in the eastward direction. Likewise, can use the variable, $E$, to represent Emanuel's position, measured from the starting point in the southward direction. Note that in defining the coordinate system, we specified both the starting point of the measurement and the direction of measure.

We can then define a third variable, $D$, to be the measurement of the distance between Anna and Emanuel. Showing the variables on the diagram is often helpful, as we can see from Figure 3.5.4.4

Recall that we need to know how long it takes for $D$, the distance between them, to equal 2 miles. Notice that for any given input $t$, the outputs $A(t)$, $E(t)$, and $D(t)$ represent distances.





Figure 3.5.4.4: We can use the Pythagorean Theorem because we have drawn a right angle.

Using the Pythagorean Theorem, we get:

$$\begin{aligned} d(t)^2 &= A(t)^2 + E(t)^2 \\ &= (4t)^2 + (3t)^2 \\ &= 16t^2 + 9t^2 \\ &= 25t^2 \\ D(t) &= \pm\sqrt{25t^2} \qquad \text{Solve for } D(t) \text{ using the square root} \\ &= \pm 5|t| \end{aligned}$$

In this scenario we are considering only positive values of $t$, so our distance $D(t)$ will always be positive. We can simplify this answer to $D(t) = 5t$. This means that the distance between Anna and Emanuel is also a linear function. Because D is a linear function, we can now answer the question of when the distance between them will reach 2 miles. We will set the output $D(t) = 2$ and solve for $t$.

$$\begin{aligned} D(t) &= 2 \\ 5t &= 2 \\ t &= \frac{2}{5} = 0.4 \end{aligned}$$

They will fall out of radio contact in 0.4 hours, or 24 minutes.

**Should I draw diagrams when given information based on a geometric shape?**

*Yes. Sketch the figure and label the quantities and unknowns on the sketch.*

### Example 3.5.4.3: Using a Diagram to Model Distance between Cities

There is a straight road leading from the town of Westborough to Agritown 30 miles east and 10 miles north. Partway down this road, it junctions with a second road, perpendicular to the first, leading to the town of Eastborough. If the town of Eastborough is located 20 miles directly east of the town of Westborough, how far is the road junction from Westborough?

**Solution**

It might help here to draw a picture of the situation. See Figure 3.5.4.5 It would then be helpful to introduce a coordinate system. While we could place the origin anywhere, placing it at Westborough seems convenient. This puts Agritown at coordinates $(30, 10)$, and Eastborough at $(20, 0)$.





Figure 3.5.4.5

Using this point along with the origin, we can find the slope of the line from Westborough to Agritown:

$$m = \frac{10-0}{30-0} = \frac{1}{3} \tag{3.5.4.5}$$

The equation of the road from Westborough to Agritown would be

$$W(x) = \frac{1}{3}x \tag{3.5.4.6}$$

From this, we can determine the perpendicular road to Eastborough will have slope $m = -3$. Because the town of Eastborough is at the point $(20, 0)$, we can find the equation:

$$\begin{aligned} E(x) &= -3x + b \\ 0 &= -3(20) + b \qquad \text{Substitute in } (20, 0) \\ b &= 60 \\ E(x) &= -3x + 60 \end{aligned}$$

We can now find the coordinates of the junction of the roads by finding the intersection of these lines. Setting them equal,

$$\begin{aligned}
\frac{1}{3}x &= -3x+60 \\
\frac{10}{3}x &= 60 \\
10x &= 180 \\
x &= 18 \qquad \text{Substituting this back into } W(x) \\
y &= W(18) \\
&= \frac{1}{3}(18) \\
&= 6
\end{aligned}$$

The roads intersect at the point $(18, 6)$. Using the distance formula, we can now find the distance from Westborough to the junction.

$$\begin{aligned}
\text{distance} &= \sqrt{(x_2-x_1)^2+(y_2-y_1)^2} \\
&= \sqrt{(18-0)^2+(6-0)^2} \\
&\approx 18.743\text{miles}
\end{aligned}$$

**Analysis**

One nice use of linear models is to take advantage of the fact that the graphs of these functions are lines. This means real-world applications discussing maps need linear functions to model the distances between reference points.

**Exercise 3.5.4.2**

There is a straight road leading from the town of Timpson to Ashburn 60 miles east and 12 miles north. Partway down the road, it junctions with a second road, perpendicular to the first, leading to the town of Garrison. If the town of Garrison is located 22 miles directly east of the town of Timpson, how far is the road junction from Timpson?

**Solution**

21.15 miles

## Building Systems of Linear Models

Real-world situations including two or more linear functions may be modeled with a **system of linear equations**. Remember, when solving a system of linear equations, we are looking for points the two lines have in common. Typically, there are three types of answers possible, as shown in Figure 3.5.4.6





Figure 3.5.4.6

**Given a situation that represents a system of linear equations, write the system of equations and identify the solution.**

a. Identify the input and output of each linear model.
b. Identify the slope and y-intercept of each linear model.
c. Find the solution by setting the two linear functions equal to another and solving for $x$,or find the point of intersection on a graph.

### Example 3.5.4.4: Building a System of Linear Models to Choose a Truck Rental Company

Jamal is choosing between two truck-rental companies. The first, Keep on Trucking, Inc., charges an up-front fee of $20, then 59 cents a mile[1]. The second, Move It Your Way, charges an up-front fee of $16, then 63 cents a mile. When will Keep on Trucking, Inc. be the better choice for Jamal?

**Solution**

The two important quantities in this problem are the cost and the number of miles driven. Because we have two companies to consider, we will define two functions.

- Input: $d$, distance driven in miles
- Outputs: $K(d)$ : cost, in dollars, for renting from Keep on Trucking

  $M(d)$ : cost, in dollars, for renting from Move It Your Way
- Initial Value: Up-front fee: $K(0) = 20$ and $M(0) = 16$
- Rate of Change: $K(d) = \dfrac{\$0.59}{\text{mile}}$ and $P(d) = \dfrac{\$0.63}{\text{mile}}$

A linear function is of the form $f(x) = mx + b$. Using the rates of change and initial charges, we can write the equations

$$K(d) = 0.59d + 20$$

$$M(d) = 0.63d + 16$$

Using these equations, we can determine when Keep on Trucking, Inc. will be the better choice. Because all we have to make that decision from is the costs, we are looking for when Keep on Trucking, Inc. will cost less, or when $K(d) < M(d)$ . The solution pathway will lead us to find the equations for the two functions, find the intersection, and then see where the $K(d)$ function is smaller.

These graphs are sketched in Figure 3.5.4.7, with $K(d)$ in blue.





Figure 3.5.4.7

To find the intersection, we set the equations equal and solve:

$$\begin{aligned} K(d) &= M(d) \\ 0.59d + 20 &= 0.63d + 16 \\ 4 &= 0.04d \\ 100 &= d \\ d &= 100 \end{aligned}$$

This tells us that the cost from the two companies will be the same if 100 miles are driven. Either by looking at the graph, or noting that $K(d)$ is growing at a slower rate, we can conclude that Keep on Trucking, Inc. will be the cheaper price when more than 100 miles are driven, that is $d > 100$.

## Key Concepts

- We can use the same problem strategies that we would use for any type of function.
- When modeling and solving a problem, identify the variables and look for key values, including the slope and y-intercept.
- Draw a diagram, where appropriate.
- Check for reasonableness of the answer.
- Linear models may be built by identifying or calculating the slope and using the y-intercept.
- The x-intercept may be found by setting $y = 0$, which is setting the expression $mx + b$ equal to 0.
- The point of intersection of a system of linear equations is the point where the x- and y-values are the same.
- A graph of the system may be used to identify the points where one line falls below (or above) the other line.

## Footnotes

1 Rates retrieved Aug 2, 2010 from www.budgettruck.com and http://www.uhaul.com/

This page titled 3.5.4: Modeling with Linear Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.3: Modeling with Linear Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.5.5: Fitting Linear Models to Data

**Learning Objectives**

- Draw and interpret scatter diagrams.
- Use a graphing utility to find the line of best fit.
- Distinguish between linear and nonlinear relations.
- Fit a regression line to a set of data and use the linear model to make predictions.

A professor is attempting to identify trends among final exam scores. His class has a mixture of students, so he wonders if there is any relationship between age and final exam scores. One way for him to analyze the scores is by creating a diagram that relates the age of each student to the exam score received. In this section, we will examine one such diagram known as a scatter plot.

## Drawing and Interpreting Scatter Plots

A scatter plot is a graph of plotted points that may show a relationship between two sets of data. If the relationship is from a **linear model**, or a model that is nearly linear, the professor can draw conclusions using his knowledge of linear functions. Figure 3.5.5.1 shows a sample scatter plot.





Figure 3.5.5.1: A scatter plot of age and final exam score variables

Notice this scatter plot does not indicate a **linear relationship**. The points do not appear to follow a trend. In other words, there does not appear to be a relationship between the age of the student and the score on the final exam.

**Example 3.5.5.1: Using a Scatter Plot to Investigate Cricket Chirps**

Table shows the number of cricket chirps in 15 seconds, for several different air temperatures, in degrees Fahrenheit[1]. Plot this data, and determine whether the data appears to be linearly related.

Table 3.5.5.1

| **Chirps** | 44 | 35 | 20.4 | 33 | 31 | 35 | 18.5 | 37 | 26 |
|---|---|---|---|---|---|---|---|---|---|
| **Temperature** | 80.5 | 70.5 | 57 | 66 | 68 | 72 | 52 | 73.5 | 53 |

**Solution**

Plotting this data, as depicted in Figure 3.5.5.2 suggests that there may be a trend. We can see from the trend in the data that the number of chirps increases as the temperature increases. The trend appears to be roughly linear, though certainly not perfectly so.





Figure 3.5.5.2: The line regression is generally positive.

## Finding the Line of Best Fit

Once we recognize a need for a linear function to model that data, the natural follow-up question is "what is that linear function?" One way to approximate our linear function is to sketch the line that seems to best fit the data. Then we can extend the line until we can verify the y-intercept. We can approximate the slope of the line by extending it until we can estimate the $\frac{\text{rise}}{\text{run}}$.

### Example 3.5.5.2: Finding a Line of Best Fit

Find a linear function that fits the data in Table 3.5.5.1by "eyeballing" a line that seems to fit.

**Solution**

On a graph, we could try sketching a line.

Using the starting and ending points of our hand drawn line, points $(0, 30)$ and $(50, 90)$, this graph has a slope of

$$m = \frac{60}{50} = 1.2 \tag{3.5.5.1}$$

and a y-intercept at 30. This gives an equation of

$$T(c) = 1.2c + 30 \tag{3.5.5.2}$$

where $c$ is the number of chirps in 15 seconds, and $T(c)$ is the temperature in degrees Fahrenheit. The resulting equation is represented in Figure 3.5.5.3





Figure 3.5.5.3: Scatter plot, showing the line of best fit.

**Analysis**

This linear equation can then be used to approximate answers to various questions we might ask about the trend.

## Recognizing Interpolation or Extrapolation

While the data for most examples does not fall perfectly on the line, the equation is our best guess as to how the relationship will behave outside of the values for which we have data. We use a process known as **interpolation** when we predict a value inside the domain and range of the data. The process of **extrapolation** is used when we predict a value outside the domain and range of the data.

Figure 3.5.5.4 compares the two processes for the cricket-chirp data addressed in Example 3.5.5.2 We can see that interpolation would occur if we used our model to predict temperature when the values for chirps are between 18.5 and 44. Extrapolation would occur if we used our model to predict temperature when the values for chirps are less than 18.5 or greater than 44.

There is a difference between making predictions inside the domain and range of values for which we have data and outside that domain and range. Predicting a value outside of the domain and range has its limitations. When our model no longer applies after a certain point, it is sometimes called **model breakdown**. For example, predicting a cost function for a period of two years may involve examining the data where the input is the time in years and the output is the cost. But if we try to extrapolate a cost when $x = 50$, that is in 50 years, the model would not apply because we could not account for factors fifty years in the future.





Figure 3.5.5.4: Interpolation occurs within the domain and range of the provided data whereas extrapolation occurs outside.

### Interpolation and Extrapolation

Different methods of making predictions are used to analyze data.

- The method of **extrapolation** involves predicting a value outside the domain and/or range of the data.
- **Model breakdown** occurs at the point when the model no longer applies.

### Example 3.5.5.3: Understanding Interpolation and Extrapolation

Use the cricket data from Table 3.5.5.1 to answer the following questions:

a. Would predicting the temperature when crickets are chirping 30 times in 15 seconds be interpolation or extrapolation? Make the prediction, and discuss whether it is reasonable.
b. Would predicting the number of chirps crickets will make at 40 degrees be interpolation or extrapolation? Make the prediction, and discuss whether it is reasonable.

**Solution**

a. The number of chirps in the data provided varied from 18.5 to 44. A prediction at 30 chirps per 15 seconds is inside the domain of our data, so would be interpolation. Using our model:

$$T(30) = 30 + 1.2(30) \quad (3.5.5.3)$$
$$= 66 \text{ degrees} \quad (3.5.5.4)$$

Based on the data we have, this value seems reasonable.
b. The temperature values varied from 52 to 80.5. Predicting the number of chirps at 40 degrees is extrapolation because 40 is outside the range of our data. Using our model:

$$40 = 30 + 1.2c \quad (3.5.5.5)$$
$$10 = 1.2c \quad (3.5.5.6)$$
$$c \approx 8.33 \quad (3.5.5.7)$$

We can compare the regions of interpolation and extrapolation using Figure 3.5.5.5





Figure 3.5.5.5: Scatter plot, showing the line of best fit and where interpolation and extrapolation occurs.

**Analysis**

Our model predicts the crickets would chirp 8.33 times in 15 seconds. While this might be possible, we have no reason to believe our model is valid outside the domain and range. In fact, generally crickets stop chirping altogether below around 50 degrees.

**Exercise 3.5.5.1**

According to the data from Table 3.5.5.1, what temperature can we predict it is if we counted 20 chirps in 15 seconds?

**Solution**

54°F

## Finding the Line of Best Fit Using a Graphing Utility

While eyeballing a line works reasonably well, there are statistical techniques for fitting a line to data that minimize the differences between the line and data values[2]. One such technique is called **least squares regression** and can be computed by many graphing calculators, spreadsheet software, statistical software, and many web-based calculators[3]. Least squares regression is one means to determine the line that best fits the data, and here we will refer to this method as linear regression.

**How To: Given data of input and corresponding outputs from a linear function, find the best fit line using linear regression.**

1. Enter the input in List 1 (L1).
2. Enter the output in List 2 (L2).
3. On a graphing utility, select Linear Regression (LinReg).

**Example 3.5.5.4: Finding a Least Squares Regression Line**

Find the least squares regression line using the cricket-chirp data in Table 3.5.5.1

**Solution**

Enter the input (chirps) in List 1 (L1).
Enter the output (temperature) in List 2 (L2). See Table 3.5.5.2

Table 3.5.5.2

| | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| **L1** | 44 | 35 | 20.4 | 33 | 31 | 35 | 18.5 | 37 | 26 |
| **L2** | 80.5 | 70.5 | 57 | 66 | 68 | 72 | 52 | 73.5 | 53 |

On a graphing utility, select Linear Regression (LinReg). Using the cricket chirp data from earlier, with technology we obtain the equation:

$$T(c) = 30.281 + 1.143c \tag{3.5.5.8}$$

**Analysis**

Notice that this line is quite similar to the equation we "eyeballed" but should fit the data better. Notice also that using this equation would change our prediction for the temperature when hearing 30 chirps in 15 seconds from 66 degrees to:

$$\begin{aligned} T(30) &= 30.281 + 1.143(30) && (3.5.5.9)\\ &= 64.571 && (3.5.5.10)\\ &\approx 64.6 \text{ degrees} && (3.5.5.11) \end{aligned}$$

The graph of the scatter plot with the least squares regression line is shown in Figure 3.5.5.6





Figure 3.5.5.6: Scatter plot, showing the line of best fit.

**Will there ever be a case where two different lines will serve as the best fit for the data?**

*No. There is only one best fit line.*

## Distinguishing Between Linear and Non-Linear Models

As we saw above with the cricket-chirp model, some data exhibit strong linear trends, but other data, like the final exam scores plotted by age, are clearly nonlinear. Most calculators and computer software can also provide us with the **correlation coefficient**, which is a measure of how closely the line fits the data. Many graphing calculators require the user to turn a "diagnostic on" selection to find the correlation coefficient, which mathematicians label as $r$. The correlation coefficient provides an easy way to get an idea of how close to a line the data falls.

We should compute the correlation coefficient only for data that follows a linear pattern or to determine the degree to which a data set is linear. If the data exhibits a nonlinear pattern, the correlation coefficient for a linear regression is meaningless. To get a sense for the relationship between the value of $r$ and the graph of the data, Figure 3.5.5.7 shows some large data sets with their correlation coefficients. Remember, for all plots, the horizontal axis shows the input and the vertical axis shows the output.





Figure 3.5.5.7: Plotted data and related correlation coefficients. (credit: “DenisBoigelot,” Wikimedia Commons)

### Correlation Coefficient

The **correlation coefficient** is a value, $r$, between –1 and 1.

- $r > 0$ suggests a positive (increasing) relationship
- $r < 0$ suggests a negative (decreasing) relationship
- The closer the value is to 0, the more scattered the data.
- The closer the value is to 1 or –1, the less scattered the data is.

### Example 3.5.5.5: Finding a Correlation Coefficient

Calculate the correlation coefficient for cricket-chirp data in Table 3.5.5.1.

**Solution**

Because the data appear to follow a linear pattern, we can use technology to calculate $r$. Enter the inputs and corresponding outputs and select the Linear Regression. The calculator will also provide you with the correlation coefficient, $r = 0.9509$. This value is very close to 1, which suggests a strong increasing linear relationship.

Note: For some calculators, the Diagnostics must be turned "on" in order to get the correlation coefficient when linear regression is performed: [2nd]>[0]>[alpha][x–1], then scroll to DIAGNOSTICSON.

## Predicting with a Regression Line

Once we determine that a set of data is linear using the correlation coefficient, we can use the regression line to make predictions. As we learned above, a regression line is a line that is closest to the data in the scatter plot, which means that only one such line is a best fit for the data.

### Example 3.5.5.6: Using a Regression Line to Make Predictions

Gasoline consumption in the United States has been steadily increasing. Consumption data from 1994 to 2004 is shown in Table 3.5.5.3 Determine whether the trend is linear, and if so, find a model for the data. Use the model to predict the consumption in 2008.

Table 3.5.5.3

| **Year** | '94 | '95 | '96 | '97 | '98 | '99 | '00 | '01 | '02 | '03 | '04 |
|---|---|---|---|---|---|---|---|---|---|---|---|
| **Consumption (billions of gallons)** | 113 | 116 | 118 | 119 | 123 | 125 | 126 | 128 | 131 | 133 | 136 |

The scatter plot of the data, including the least squares regression line, is shown in Figure 3.5.5.8





Figure 3.5.5.8: Scatter plot, showing the line of best fit.

We can introduce new input variable, $t$,representing years since 1994.

The least squares regression equation is:

$$C(t) = 113.318 + 2.209t \tag{3.5.5.12}$$

Using technology, the correlation coefficient was calculated to be 0.9965, suggesting a very strong increasing linear trend.

Using this to predict consumption in 2008 $(t = 14)$,

$$C(14) = 113.318 + 2.209(14) \tag{3.5.5.13}$$
$$= 144.244 \tag{3.5.5.14}$$

The model predicts 144.244 billion gallons of gasoline consumption in 2008.

**Exercise 3.5.5.1**

Use the model we created using technology in Example 3.5.5.6to predict the gas consumption in 2011. Is this an interpolation or an extrapolation?

**Answer**

150.871 billion gallons; extrapolation

## Key Concepts

- Scatter plots show the relationship between two sets of data.
- Scatter plots may represent linear or non-linear models.
- The line of best fit may be estimated or calculated, using a calculator or statistical software.
- Interpolation can be used to predict values inside the domain and range of the data, whereas extrapolation can be used to predict values outside the domain and range of the data.
- The correlation coefficient, $r$, indicates the degree of linear relationship between data.
- A regression line best fits the data.
- The least squares regression line is found by minimizing the squares of the distances of points from a line passing through the data and may be used to make predictions regarding either of the variables.

This page titled 3.5.5: Fitting Linear Models to Data is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.4: Fitting Linear Models to Data** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.5.E: Linear Functions(Exercises)

## 2.1 Linear Functions

### Verbal

1) Terry is skiing down a steep hill. Terry's elevation, $E(t)$, in feet after $t$ seconds is given by $E(t) = 3000 - 70t$. Write a complete sentence describing Terry's starting elevation and how it is changing over time.

**Answer**

Terry starts at an elevation of $3000$feet and descends $70$ feet per second.

2) Maria is climbing a mountain. Maria's elevation, $E(t)$, in feet after $t$ minutes is given by $E(t) = 1200 + 40t$. Write a complete sentence describing Maria's starting elevation and how it is changing over time.

3) Jessica is walking home from a friend's house. After $2$ minutes she is $1.4$ miles from home. Twelve minutes after leaving, she is $0.9$ miles from home. What is her rate in miles per hour?

**Answer**

$3$ miles per hour

4) Sonya is currently $10$ miles from home and is walking farther away at $2$ miles per hour. Write an equation for her distance from home $t$ hours from now.

5) A boat is $100$ miles away from the marina, sailing directly toward it at $10$ miles per hour. Write an equation for the distance of the boat from the marina after $t$ hours.

**Answer**

$d(t) = 100 - 10t$

6) Timmy goes to the fair with $\$40$. Each ride costs $\$2$. How much money will he have left after riding $n$ rides?

### Algebraic

**For the exercises 7-14, determine whether the equation of the curve can be written as a linear function.**

7) $y = \frac{1}{4}x + 6$

**Answer**

Yes

8) $y = 3x - 5$

9) $y = 3x^2 - 2$

**Answer**

No

10) $3x + 5y = 15$

11) $3x^2 + 5y = 15$

**Answer**

No

12) $3x + 5y^2 = 15$

13) $-2x^2 + 3y^2 = 6$

**Answer**

No

14) $-\frac{x-3}{5}=2y$

**For the exercises 15-24, determine whether each function is increasing or decreasing.**

15) $f(x)=4x+3$

**Answer**

Increasing

16) $g(x)=5x+6$

17) $a(x)=5-2x$

**Answer**

Decreasing

18) $b(x)=8-3x$

19) $h(x)=-2x+4$

**Answer**

Decreasing

20) $k(x)=-4x+1$

21) $j(x)=\frac{1}{2}x-3$

**Answer**

Increasing

22) $p(x)=\frac{1}{4}x-5$

23) $n(x)=-\frac{1}{3}x-2$

**Answer**

Decreasing

24) $m(x)=-\frac{3}{8}x+3$

**For the exercises 25-29, find the slope of the line that passes through the two given points.**

25) $(2,4)$ and $(4,10)$

**Answer**

$3$

26) $(1,5)$ and $(4,11)$

27) $(-1,4)$ and $(5,2)$

**Answer**

$-\frac{1}{3}$

28) $(8, -2)$ and $(4, 6)$

29) (6, 11) and (−4, 3)

**Answer**

$\frac{4}{5}$

**For the exercises 30-37, given each set of information, find a linear equation satisfying the conditions, if possible.**

30) $f(-5) = -4$, and $f(5) = 2$

31) $f(-1) = 4$ and $f(5) = 1$

**Answer**

$f(x) = -\frac{1}{2}x + \frac{7}{2}$

32) $(2, 4)$ and $(4, 10)$

33) Passes through $(1, 5)$ and $(4, 11)$

**Answer**

$y = 2x + 3$

34) Passes through $(-1, 4)$ and $(5, 2)$

35) Passes through $(-2, 8)$ and $(4, 6)$

**Answer**

$y = -\frac{1}{3}x + \frac{22}{3}$

36) $x$ intercept at (−2, 0) and $y$ intercept at (0,−3)

37) $x$ intercept at (−5, 0) and $y$ intercept at (0, 4)


**Answer**

$y = \frac{4}{5}x + 4$


## Graphical

**For the exercises 38-,40 find the slope of the lines graphed.**

38)





39)




**Answer**


$-\frac{5}{4}$

40)




**For the exercises 41-46, write an equation for the lines graphed.**

41)





**Answer**


$$y = \frac{2}{3}x + 1$$

42)


https://math.libretexts.org/@go/page/101682





43)




**Answer**


$y = -2x + 3$

44)




45)



https://math.libretexts.org/@go/page/101682




**Answer**

$y = 3$

46)




## Numeric

**For the exercises 47-51, which of the tables could represent a linear function? For each that could be linear, find a linear equation that models the data.**

47)

| $x$ | 0 | 5 | 10 | 15 |
|---|---|---|---|---|
| $g(x)$ | 5 | –10 | –25 | –40 |

**Answer**

Linear, $g(x) = -3x + 5$

48)

| $x$ | 0 | 5 | 10 | 15 |
|---|---|---|---|---|

| $h(x)$ | 5 | 30 | 105 | 230 |
|---|---|---|---|---|

| $x$ | 0 | 5 | 10 | 15 |
|---|---|---|---|---|
| $f(x)$ | –5 | 20 | 45 | 70 |

**Answer**

Linear, $f(x) = 5x - 5$

49)

| $x$ | 5 | 10 | 20 | 25 |
|---|---|---|---|---|
| $k(x)$ | 28 | 13 | 58 | 73 |

| $x$ | 0 | 2 | 4 | 6 |
|---|---|---|---|---|
| $g(x)$ | 6 | –19 | –44 | –69 |

**Answer**

Linear, $g(x) = -\frac{25}{2}x + 6$

50)

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $f(x)$ | –4 | 16 | 36 | 56 |

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $f(x)$ | –4 | 16 | 36 | 56 |

**Answer**

Linear, $f(x) = 10x - 24$

51)

| $x$ | 0 | 2 | 6 | 8 |
|---|---|---|---|---|
| $k(x)$ | 6 | 31 | 106 | 231 |

## Technology

52) If $f$ is a linear function, $f(0.1) = 11.5$, and $f(0.4) = -5.9$, find an equation for the function.


**Answer**

$f(x) = -58x + 17.3$

53) Graph the function $f$ on a domain of $[-10, 10]$ : $f(x) = 0.02x - 0.01$. Enter the function in a graphing utility. For the viewing window, set the minimum value of $x$ to be −10 and the maximum value of $x$ to be 10.

54) Graph the function $f$ on a domain of $[-10, 10]$ : $fx) = 2,500x + 4,000$

**Answer**




55) The Table below shows the input, $w$, and output, $k$, for a linear function $k$.

a. Fill in the missing values of the table.
b. Write the linear function $k$, round to 3 decimal places.

| $w$ | –10 | 5.5 | 67.5 | b |
|---|---|---|---|---|
| $k$ | 30 | –26 | a | –44 |

56) The Table below shows the input, $p$, and output, $q$, for a linear function $q$.

a. Fill in the missing values of the table.
b. Write the linear function $k$.

| $p$ | 0.5 | 0.8 | 12 | b |
|---|---|---|---|---|
| $q$ | 400 | 700 | a | 1,000,000 |


**Answer**

a. $a = 11{,}900$; $b = 1001.1$
b. $q(p) = 1000p - 100$

57) Graph the linear function $f$ on a domain of $[-10, 10]$ for the function whose slope is $\frac{1}{8}$ and y-intercept is $\frac{31}{16}$. Label the points for the input values of $-10$ and 10.

58) Graph the linear function $f$ on a domain of $[-0.1, 0.1]$ for the function whose slope is 75 and $y$-intercept is $-22.5$. Label the points for the input values of $-0.1$ and $0.1$.

**Answer**




59) Graph the linear function $f$ where $f(x) = ax + b$ on the same set of axes on a domain of $[-4, 4]$ for the following values of $a$ and $b$.

i. $a = 2;\ b = 3$
ii. $a = 2;\ b = 4$
iii. $a = 2;\ b = -4$
iv. $a = 2;\ b = -5$

## Extensions

60) Find the value of $x$ if a linear function goes through the following points and has the following slope: $(x, 2), (-4, 6), m = 3$

**Answer**

$$x = -\frac{16}{3}$$

61) Find the value of $y$ if a linear function goes through the following points and has the following slope: $(10, y), (25, 100)$, $m = -5$

62) Find the equation of the line that passes through the following points: $(a, b)$ and $(a, b + 1)$

**Answer**

$$x = a$$

63) Find the equation of the line that passes through the following points: $(2a, b)$ and (a, b+1)

64) Find the equation of the line that passes through the following points: $(a, 0)$ and $(c, d)$

**Answer**

$$y = \frac{d}{c - a}x - \frac{ad}{c - a}$$

## Real-World Applications

65) At noon, a barista notices that she has $\$20$ in her tip jar. If she makes an average of $\$0.50$ from each customer, how much will she have in her tip jar if she serves $n$ more customers during her shift?

66) A gym membership with two personal training sessions costs $\$125$, while gym membership with five personal training sessions costs $\$260$. What is cost per session?

**Answer**

$\$45$ per training session.

67) A clothing business finds there is a linear relationship between the number of shirts, $n$, it can sell and the price, $p$, it can charge per shirt. In particular, historical data shows that $1,000$ shirts can be sold at a price of $\$30$, while $3,000$ shirts can be sold at a price of $\$22$. Find a linear equation in the form $p(n) = mn + b$ that gives the price $p$ they can charge for $n$ shirts.

68) A phone company charges for service according to the formula: $C(n) = 24 + 0.1n$, where $n$ is the number of minutes talked, and $C(n)$ is the monthly charge, in dollars. Find and interpret the rate of change and initial value.

**Answer**

The rate of change is $0.1$. For every additional minute talked, the monthly charge increases by $\$0.1$ or $10$ cents. The initial value is $24$. When there are no minutes talked, initially the charge is $\$24$

69) A farmer finds there is a linear relationship between the number of bean stalks, $n$, she plants and the yield, $y$, each plant produces. When she plants $30$ stalks, each plant yields $30$ oz of beans. When she plants $34$ stalks, each plant produces $28$ oz of beans. Find a linear relationships in the form $y = mn + b$ that gives the yield when $n$ stalks are planted.

70) A city's population in the year 1960 was $287,500$. In 1989 the population was $275,900$. Compute the rate of growth of the population and make a statement about the population rate of change in people per year.

**Answer**

The slope is $-400$. This means for every year between 1960 and 1989, the population dropped by $400$ per year in the city.

71) A town's population has been growing linearly. In 2003, the population was $45,000$, and the population has been growing by $1,700$ people each year. Write an equation, $P(t)$, for the population $t$ years after 2003.

72) Suppose that average annual income (in dollars) for the years 1990 through 1999 is given by the linear function: $I(x) = 1054x + 23{,}286$, where $x$ is the number of years after 1990. Which of the following interprets the slope in the context of the problem?

a. As of 1990, average annual income was $\$23,286$
b. In the ten-year period from 1990–1999, average annual income increased by a total of $\$1,054$
c. Each year in the decade of the 1990s, average annual income increased by $1,054.
d. Average annual income rose to a level of $23,286 by the end of 1999.

**Answer**

c

73) When temperature is $0$ degrees Celsius, the Fahrenheit temperature is $32$. When the Celsius temperature is $100$, the corresponding Fahrenheit temperature is $212$. Express the Fahrenheit temperature as a linear function of $C$, the Celsius temperature, $F(C)$.

a. Find the rate of change of Fahrenheit temperature for each unit change temperature of Celsius.
b. Find and interpret $F(28)$.
c. Find and interpret $F(-40)$.

## 2.2 Graphs of Linear Functions

# Verbal

1) If the graphs of two linear functions are parallel, describe the relationship between the slopes and the $y$-intercepts.

**Answer**

The slopes are equal; $y$-intercepts are not equal.

2) If the graphs of two linear functions are perpendicular, describe the relationship between the slopes and the $y$-intercepts.

3) If a horizontal line has the equation $f(x) = a$ and a vertical line has the equation $x = a$, what is the point of intersection? Explain why what you found is the point of intersection.

**Answer**

The point of intersection is $(a, a)$. This is because for the horizontal line, all of the $y$ coordinates are a and for the vertical line, all of the $x$ coordinates are a. The point of intersection will have these two characteristics.

4) Explain how to find a line parallel to a linear function that passes through a given point.

5) Explain how to find a line perpendicular to a linear function that passes through a given point.

**Answer**

First, find the slope of the linear function. Then take the negative reciprocal of the slope; this is the slope of the perpendicular line. Substitute the slope of the perpendicular line and the coordinate of the given point into the equation $y = mx + b$ and solve for $b$. Then write the equation of the line in the form $y = mx + b$ by substituting in $m$ and $b$.

## Algebraic

**For the exercises 6-11, determine whether the lines given by the equations below are parallel, perpendicular, or neither parallel nor perpendicular:**

6) $4x - 7y = 10$
$7x + 4y = 1$

7) $3y + x = 12$
$-y = 8x + 1$

**Answer**

neither parallel or perpendicular

8) $3y + 4x = 12$
$-6y = 8x + 1$

9) $6x - 9y = 10$
$3x + 2y = 1$

**Answer**

perpendicular

10) $y = \frac{2}{3}x + 1$
$3x + 2y = 1$

11) $y = \frac{3}{4}x + 1$
$-3x + 4y = 1$

**Answer**

parallel

**For the exercises 12-17, find the $x$- and $y$-intercepts of each equation**

12) $f(x) = -x + 2$

13) $g(x) = 2x + 4$

**Answer**

$(-2, 0); (0, 4)$

14) $h(x) = 3x - 5$

15) $k(x) = -5x + 1$

**Answer**

$\left(\frac{1}{5}, 0\right); (0, 1)$

16) $-2x + 5y = 20$

17) $7x + 2y = 56$

**Answer**

$(8, 0); (0, 28)$

**For the exercises 18-23, use the descriptions of each pair of lines given below to find the slopes of Line 1 and Line 2. Is each pair of lines parallel, perpendicular, or neither?**

18)

Line 1: Passes through $(0, 6)$ and $(3, -24)$
Line 2: Passes through $(-1, 19)$ and $(8, -71)$

19)

Line 1: Passes through $(-8, -55)$ and $(10, 89)$
Line 2: Passes through $(9, -44)$ and $(4, -14)$

**Answer**

Line 1: $m = 8$ Line 2: $m = -6$ Neither

20)

Line 1: Passes through $(2, 3)$ and (4,−1)
Line 2: Passes through $(6, 3)$ and $(8, 5)$

21)

Line 1: Passes through $(1, 7)$ and $(5, 5)$
Line 2: Passes through $(-1, -3)$ and $(1, 1)$

**Answer**

Line 1: $m = -12$ Line 2: $m = 2$ Perpendicular

22)

Line 1: Passes through $(0, 5)$ and $(3, 3)$
Line 2: Passes through $(1, -5)$ and $(3, -2)$

23)

Line 1: Passes through $(2,5)$ and $(5,-1)$
Line 2: Passes through $(-3,7)$ and $(3,-5)$

**Answer**

Line 1: $m=-2$ Line 2: $m=-2$ Parallel

24) Write an equation for a line parallel to $f(x)=-5x-3$ and passing through the point $(2,-12)$.

25) Write an equation for a line parallel to $g(x)=3x-1$ and passing through the point $(4,9)$.

**Answer**

$g(x)=3x-3$

26) Write an equation for a line perpendicular to $h(t)=-2t+4$ and passing through the point $(-4,-1)$.

27) Write an equation for a line perpendicular to $p(t)=3t+4$ and passing through the point $(3,1)$.

**Answer**

$p(t)=-\frac{1}{3}t+2$

28) Find the point at which the line $f(x)=-2x-1$ intersects the line $g(x)=-x$.

29) Find the point at which the line $f(x)=2x+5$ intersects the line $g(x)=-3x-5$.

**Answer**

$(-2,1)$

30) Use algebra to find the point at which the line $f(x)=-\frac{4}{5}x+\frac{274}{25}$ intersects the line $h(x)=\frac{9}{4}x+\frac{73}{10}$.


31) Use algebra to find the point at which the line $f(x)=\frac{7}{4}x+\frac{457}{60}$ intersects the line $g(x)=\frac{4}{3}x+\frac{31}{5}$.

**Answer**

$\left(-\frac{17}{5},\frac{5}{3}\right)$

Graphical

**For the exercises 32-37, match the given linear equation with its graph in the Figure below.**




32) $f(x) = -x - 1$

33) $f(x) = -2x - 1$

**Answer**

F

34) $f(x) = -\frac{1}{2}x - 1$

35) $f(x) = 2$

**Answer**

C

36) $f(x) = 2 + x$

37) $f(x) = 3x + 2$

**Answer**


A

**For the exercises 38-43, sketch a line with the given features.**

38) An $x$-intercept of $(-4, 0)$ and $y$-intercept of $(0, -2)$

39) An $x$-intercept of $(-2, 0)$ and $y$-intercept of $(0, 4)$


**Answer**




40) A $y$-intercept of $(0, 7)$ and slope $-\frac{3}{2}$

41) A $y$-intercept of $(0, 3)$ and slope $\frac{2}{5}$


**Answer**




42) Passing through the points $(-6, -2)$ and $(6, -6)$

43) Passing through the points $(-3, -4)$ and $(3, 0)$

**Answer**





**For the exercises 44-58, sketch the graph of each equation.**

44) $f(x) = -2x - 1$

45) $g(x) = -3x + 2$


**Answer**




46) $h(x) = \frac{1}{3}x + 2$

47) $k(x) = \frac{2}{3}x - 3$


**Answer**




48) $f(t) = 3 + 2t$

49) $p(t) = -2 + 3t$


**Answer**




50) $x = 3$

51) $x = -2$


**Answer**




52) $r(x) = 4$

53) $q(x) = 3$


**Answer**




54) $4x = -9y + 36$

55) $\frac{x}{3} - \frac{y}{4} = 1$


**Answer**




56) $3x - 5y = 15$

57) $3x = 15$

**Answer**




58) $3y = 12$

59) If $g(x)$ is the transformation of $f(x) = x$ after a vertical compression by $\frac{3}{4}$, a shift right by $2$, and a shift down by $4$

a. Write an equation for $g(x)$.

b. What is the slope of this line?
c. Find the $y$-intercept of this line.

**Answer**


a. $g(x) = 0.75x - 5.5$
b. $0.75$
c. $0, -5.5)$

60) If $g(x)$ is the transformation of $f(x) = x$ after a vertical compression by $\frac{1}{3}$, a shift left by $1$, and a shift up by $3$

a. Write an equation for $g(x)$.
b. What is the slope of this line?
c. Find the $y$-intercept of this line.

**For the exercises 61-64, write the equation of the line shown in the graph.**


61)





**Answer**

$y = 3$

62)





63)




**Answer**

$x = -3$

64)



**For the exercises 65-69, find the point of intersection of each pair of lines if it exists. If it does not exist, indicate that there is no point of intersection.**

65) $y = \frac{3}{4}x + 1$
$-3x + 4y = 12$

**Answer**

no point of intersection

66) $2x - 3y = 12$
$5y + x = 30$

67) $2x = y - 3$
$y + 4x = 15$

**Answer**

$(2, 7)$

68) $x - 2y + 2 = 3$
$x - y = 3$

69) $5x + 3y = -65$
$x - y = -5$

**Answer**

$(-10, -5)$

### Extensions

70) Find the equation of the line parallel to the line $g(x) = -0.01x + 2.01$ through the point $(1, 2)$.

71) Find the equation of the line perpendicular to the line $g(x) = -0.01x + 2.01$ through the point $(1, 2)$.

**Answer**

$y = 100x - 98$

**For the exercises 72-73, use the functions $f(x) = -0.1x + 200$ and $g(x) = 20x + 0.1$.**

72) Find the point of intersection of the lines $f$ and $g$.

73) Where is $f(x)$ greater than $g(x)$? Where is $g(x)$ greater than $f(x)$?

**Answer**

$x < \frac{1999}{201} x > \frac{1999}{201}$

### Real-World Applications

74) A car rental company offers two plans for renting a car.

Plan A: $30 per day and $0.18 per mile
Plan B: $50 per day with free unlimited mileage

How many miles would you need to drive for plan B to save you money?

75) A cell phone company offers two plans for minutes.

Plan A: $20 per month and $1 for every one hundred texts.
Plan B: $50 per month with free unlimited texts.

How many texts would you need to send per month for plan B to save you money?

**Answer**

Less than 3000texts

76) A cell phone company offers two plans for minutes.

Plan A: $15 per month and $2 for every 300 texts.
Plan B: $25 per month and $0.50 for every 100 texts.

How many texts would you need to send per month for plan B to save you money?

## 2.3 Modeling with Linear Functions

### Verbal

1) Explain how to find the input variable in a word problem that uses a linear function.

**Answer**

Determine the independent variable. This is the variable upon which the output depends.

2) Explain how to find the output variable in a word problem that uses a linear function.

3) Explain how to interpret the initial value in a word problem that uses a linear function.

**Answer**

To determine the initial value, find the output when the input is equal to zero.

4) Explain how to determine the slope in a word problem that uses a linear function.

### Algebraic

5) Find the area of a parallelogram bounded by the $y$ axis, the line $x = 3$, the line $f(x) = 1 + 2x$ ,and the line parallel to $f(x)$ passing through (2, 7).

**Answer**

6 square units

6) Find the area of a triangle bounded by the $x$-axis, the line $f(x) = 12 - \frac{1}{3}x$, and the line perpendicular to $f(x)$ that passes through the origin.

7) Find the area of a triangle bounded by the $y$-axis, the line $f(x) = 9 - \frac{6}{7}x$, and the line perpendicular to $f(x)$ that passes through the origin.

**Answer**

20.012square units

8) Find the area of a parallelogram bounded by the $x$-axis, the line $g(x) = 2$, the line $f(x) = 3x$, and the line parallel to $f(x)$ passing through (6,1).

**For the exercises 9-10, consider this scenario: A town's population has been decreasing at a constant rate. In 2010 the population was $5,900$. By 2012 the population had dropped $4,700$. Assume this trend continues.**

9) Predict the population in 2016.

**Answer**

$2,300$

10) Identify the year in which the population will reach 0.

**For the exercises 11-12, consider this scenario: A town's population has been increased at a constant rate. In 2010 the population was $46,020$. By 2012 the population had increased to $52,070$. Assume this trend continues.**

11) Predict the population in 2016.

**Answer**

$64,170$

12) Identify the year in which the population will reach $75,000$.

**For the exercises 13-18, consider this scenario: A town has an initial population of $75,000$. It grows at a constant rate of $2,500$ per year for $5$ years.**

13) Find the linear function that models the town's population $P$ as a function of the year, $t$, where $t$ is the number of years since the model began.

**Answer**

$P(t) = 75,000 + 2500t$

14) Find a reasonable domain and range for the function $P$.

15) If the function $P$ is graphed, find and interpret the $x$- and $y$-intercepts.

**Answer**

$(-30, 0)$ Thirty years before the start of this model, the town had no. $(0, 75,000)$Initially, the town had a population of $75,000$

16) If the function $P$ is graphed, find and interpret the slope of the function.

17) When will the output reached $100,000$?

**Answer**

Ten years after the model began.

18) What is the output in the year 12 years from the onset of the model?

**For the exercises 19-24, consider this scenario: The weight of a newborn is $7.5$ pounds. The baby gained one-half pound a month for its first year.**

19) Find the linear function that models the baby's weight $W$ as a function of the age of the baby, in months, $t$.

**Answer**

$W(t) = 7.5t + 0.5$

20) Find a reasonable domain and range for the function $W$.

21) If the function $W$ is graphed, find and interpret the $x$- and $y$-intercepts.

**Answer**

$(-15, 0)$: The $x$-intercept is not a plausible set of data for this model because it means the baby weighed 0 pounds 15 months prior to birth. $(0, 7.5)$: The baby weighed $7.5$ pounds at birth.

22) If the function $W$ is graphed, find and interpret the slope of the function.

23) When did the baby weight $10.4$ pounds?

**Answer**

At age $5.8$ months.

24) What is the output when the input is $6.2$? Interpret your answer.

**For the exercises 25-30, consider this scenario: The number of people afflicted with the common cold in the winter months steadily decreased by $205$ each year from 2005 until 2010. In 2005, $12,025$ people were afflicted.**

25) Find the linear function that models the number of people inflicted with the common cold $C$ as a function of the year, $t$.

**Answer**

$C(t) = 12,025 - 205t$

26) Find a reasonable domain and range for the function $C$.

27) If the function $C$ is graphed, find and interpret the $x$- and $y$-intercepts.

**Answer**

$(58.7, 0)$: In roughly $59$ years, the number of people inflicted with the common cold would be $0$. $(0, 12,025)$: Initially there were $12,025$people afflicted by the common cold.

28) If the function $C$ is graphed, find and interpret the slope of the function.


29) When will the output reach $0$?

**Answer**

$2064$

30) In what year will the number of people be $9,700$?

**For the exercises 31-34, use the graph in the Figure below, which shows the profit, $y$, in thousands of dollars, of a company in a given year, $t$, where $t$ represents the number of years since 1980.**




31) Find the linear function $y$, where $y$ depends on $t$, the number of years since 1980.

**Answer**

$y = -2t + 180$

32) Find and interpret the $y$-intercept.


33) Find and interpret the $x$-intercept.

**Answer**

In 2070, the company's profit will be zero.

34) Find and interpret the slope.

**For the exercises 35-38, use the graph in the Figure below, which shows the profit, $y$, in thousands of dollars, of a company in a given year, $t$, where $t$ represents the number of years since 1980.**




35) Find the linear function $y$, where $y$ depends on $t$, the number of years since 1980.

**Answer**

$y = 30t - 300$

36) Find and interpret the $y$-intercept.

37) Find and interpret the $x$-intercept.

**Answer**

$(10, 0)$ In 1990, the profit earned zero profit.

38) Find and interpret the slope.

Numeric

**For the exercises 39-41, use the median home values in Mississippi and Hawaii (adjusted for inflation) shown in the Table below. Assume that the house values are changing linearly.**

| Year | Mississippi | Hawaii |
|---|---|---|
| 1950 | $25,200 | $74,400 |
| 2000 | $71,400 | $272,700 |

39) In which state have home values increased at a higher rate?

**Answer**

Hawaii

40) If these trends were to continue, what would be the median home value in Mississippi in 2010?

41) If we assume the linear trend existed before 1950 and continues after 2000, the two states' median house values will be (or were) equal in what year? (The answer might be absurd.)

**Answer**

During the year 1933

**For the exercises 42-44, use the median home values in Indiana and Alabama (adjusted for inflation) shown in the Table below. Assume that the house values are changing linearly.**

| Year | Indiana | Alabama |
|---|---|---|
| 1950 | $37,700 | $27,100 |
| 2000 | $94,300 | $85,100 |

42) In which state have home values increased at a higher rate?

43) If these trends were to continue, what would be the median home value in Indiana in 2010?

**Answer**

$\$105,620$

44) If we assume the linear trend existed before 1950 and continues after 2000, the two states' median house values will be (or were) equal in what year? (The answer might be absurd.)

# Real-World Applications

45) In 2004, a school population was 1001. By 2008 the population had grown to 1697. Assume the population is changing linearly.

a. How much did the population grow between the year 2004 and 2008?
b. How long did it take the population to grow from 1001 students to 1697 students?
c. What is the average population growth per year?
d. What was the population in the year 2000?
e. Find an equation for the population, $P$, of the school $t$ years after 2000.
f. Using your equation, predict the population of the school in 2011.

**Answer**

a. 696 people
b. 4 years
c. 174 people per year
d. 305 people
e. $P(t) = 305 + 174t$
f. 2219 people

46) In 2003, a town's population was 1431. By 2007 the population had grown to 2134. Assume the population is changing linearly.

a. How much did the population grow between the year 2003 and 2007?
b. How long did it take the population to grow from 1431 people to 2134 people?
c. What is the average population growth per year?
d. What was the population in the year 2000?
e. Find an equation for the population, $P$ of the town $t$ years after 2000.
f. Using your equation, predict the population of the town in 2014.

47) A phone company has a monthly cellular plan where a customer pays a flat monthly fee and then a certain amount of money per minute used on the phone. If a customer uses 410 minutes, the monthly cost will be $71.50. If the customer uses 720 minutes, the monthly cost will be $118.

a. Interpret the slope and $y$-intercept of the equation.
b. Use your equation to find the total monthly cost if 687 minutes are used.

**Answer**

a. $C(x) = 0.15x + 10$
b. The flat monthly fee is $10 and there is an additional $0.15 fee for each additional minute used
c. $113.05

48) A phone company has a monthly cellular data plan where a customer pays a flat monthly fee of $10 and then a certain amount of money per megabyte (MB) of data used on the phone. If a customer uses 20 MB, the monthly cost will be $11.20. If the customer uses 130 MB, the monthly cost will be $17.80.

a. Interpret the slope and $y$-intercept of the equation.
b. Use your equation to find the total monthly cost if 250 MB are used.

49) In 1991, the moose population in a park was measured to be $4,360$. By 1999, the population was measured again to be $5,880$. Assume the population continues to change linearly.

a. What does your model predict the moose population to be in 2003?

**Answer**

a. $P(t) = 190t + 4360$
b. $6640$moose

50) In 2003, the owl population in a park was measured to be $340$. By 2007, the population was measured again to be $285$. The population changes linearly. Let the input be years since 1990.

a. What does your model predict the owl population to be in 2012?

51) The Federal Helium Reserve held about $16$ billion cubic feet of helium in 2010 and is being depleted by about $2.1$ billion cubic feet each year.

a. In 2015, what will the helium reserves be?
b. If the rate of depletion doesn't change, in what year will the Federal Helium Reserve be depleted?

**Answer**

a. $R(t) = 16 - 2.1t$
b. $5.5$ billion cubic feet
c. During the year 2017

52) Suppose the world's oil reserves in 2014 are $1,820$ billion barrels. If, on average, the total reserves are decreasing by $25$ billion barrels of oil each year:

a. Seven years from now, what will the oil reserves be?
b. If the rate at which the reserves are decreasing is constant, when will the world's oil reserves be depleted?

53) You are choosing between two different prepaid cell phone plans. The first plan charges a rate of $26$ cents per minute. The second plan charges a monthly fee of $\$19.95$ plus $11$ cents per minute. How many minutes would you have to use in a month in order for the second plan to be preferable?

**Answer**

More than $133$ minutes

54) You are choosing between two different window washing companies. The first charges $\$5$ per window. The second charges a base fee of $\$40$ plus $\$3$ per window. How many windows would you need to have for the second company to be preferable?

55) When hired at a new job selling jewelry, you are given two pay options:

Option A: Base salary of $\$17,000$ a year with a commission of $12\%$ of your sales
Option B: Base salary of $\$20,000$ a year with a commission of $5\%$ of your sales

How much jewelry would you need to sell for option A to produce a larger income?

**Answer**

More than $\$42,857.14$ worth of jewelry

56) When hired at a new job selling electronics, you are given two pay options:

Option A: Base salary of $\$14,000$ a year with a commission of $10\%$ of your sales

Option B: Base salary of $\$19,000$ a year with a commission of $4\%$ of your sales

How much electronics would you need to sell for option A to produce a larger income?

57) When hired at a new job selling electronics, you are given two pay options:

Option A: Base salary of $\$20,000$ a year with a commission of $12\%$ of your sales

Option B: Base salary of $\$26,000$ a year with a commission of $3\%$ of your sales

How much electronics would you need to sell for option A to produce a larger income?

**Answer**

$\$66,666.67$

58) When hired at a new job selling electronics, you are given two pay options:

Option A: Base salary of $\$10,000$ a year with a commission of $9\%$ of your sales

Option B: Base salary of $\$20,000$ a year with a commission of $4\%$ of your sales

How much electronics would you need to sell for option A to produce a larger income?

## 2.4 Fitting Linear Models to Data

### Verbal

1) Describe what it means if there is a model breakdown when using a linear model.

**Answer**

When our model no longer applies, after some value in the domain, the model itself doesn't hold.

2) What is interpolation when using a linear model?

3) What is extrapolation when using a linear model?

**Answer**

We predict a value outside the domain and range of the data.

4) Explain the difference between a positive and a negative correlation coefficient.

5) Explain how to interpret the absolute value of a correlation coefficient.

**Answer**

The closer the number is to 1, the less scattered the data, the closer the number is to 0, the more scattered the data.

### Algebraic

6) A regression was run to determine whether there is a relationship between hours of TV watched per day (x) and number of sit-ups a person can do (y). The results of the regression are given below. Use this to predict the number of sit-ups a person who watches 11 hours of TV can do.

$$y = ax + b$$
$$a = -1.341$$
$$b = 32.234$$
$$r = -0.896$$

7) A regression was run to determine whether there is a relationship between the diameter of a tree ($x$,in inches) and the tree's age ( $y$,in years). The results of the regression are given below. Use this to predict the age of a tree with diameter 10 inches.

$$y = ax + b$$
$$a = 6.301$$
$$b = -1.044$$
$$r = -0.970$$

**Answer**

61.966years

**For the exercises 8-11, draw a scatter plot for the data provided. Does the data appear to be linearly related?**

8)

| | | | | | |
|---|---|---|---|---|---|
| 0 | 2 | 4 | 6 | 8 | 10 |
| –22 | –19 | –15 | –11 | –6 | –2 |

9)

| | | | | | |
|---|---|---|---|---|---|
| 1 | 2 | 3 | 4 | 5 | 6 |
| 46 | 50 | 59 | 75 | 100 | 136 |

**Answer**

No

10)

| | | | | | |
|---|---|---|---|---|---|
| 100 | 250 | 300 | 450 | 600 | 750 |
| 12 | 12.6 | 13.1 | 14 | 14.5 | 15.2 |

11)

| | | | | | |
|---|---|---|---|---|---|
| 1 | 3 | 5 | 7 | 9 | 11 |
| 1 | 9 | 28 | 65 | 125 | 216 |

**Answer**

No

12) For the following data, draw a scatter plot. If we wanted to know when the population would reach $15,000$, would the answer involve interpolation or extrapolation? Eyeball the line, and estimate the answer.

| Year | Population |
|---|---|
| 1990 | 11,500 |
| 1995 | 12,100 |
| 2000 | 12,700 |
| 2005 | 13,000 |
| 2010 | 13,750 |

13) For the following data, draw a scatter plot. If we wanted to know when the temperature would reach $28^\circ F$, would the answer involve interpolation or extrapolation? Eyeball the line and estimate the answer.


| | | | | | |
|---|---|---|---|---|---|
| Temperature, °F | 16 | 18 | 20 | 25 | 30 |
| Time, seconds | 46 | 50 | 54 | 55 | 62 |

**Answer**


Interpolation. About $60^\circ F$.

## Graphical


**For the exercises 14-17, match each scatterplot with one of the four specified correlations in Figure ab and Figure cd.**




(a)




(b)



(c)




https://math.libretexts.org/@go/page/101682



(d)

Figure ab Figure cd

14) $r = 0.95$

15) $r = -0.89$

**Answer**

C

16) $r = 0.26$


17) $r = -0.39$

**Answer**


B

**For the exercises 18-21, draw a best-fit line for the plotted data.**


18)





19)





**Answer**


10
8
6
4
2
0
0
2
4
6
8
10


20)


10
8
6
4
2
0
0
2
4
6
8
10

21)


10
8
6
4
2
0
0
2
4
6
8
10

**Answer**


10
8
6
4
2
0
0
2
4
6
8
10

## Numeric

22) The U.S. Census tracks the percentage of persons $25$ years or older who are college graduates. That data for several years is given in the Table below. Determine whether the trend appears linear. If so, and assuming the trend continues, in what year will the percentage exceed $35\%$?

| Year | Percent Graduates |
|---|---|
| 1990 | 21.3 |
| 1992 | 21.4 |
| 1994 | 22.2 |
| 1996 | 23.6 |
| 1998 | 24.4 |
| 2000 | 25.6 |
| 2002 | 26.7 |
| 2004 | 27.7 |
| 2006 | 28 |
| 2008 | 29.4 |

23) The U.S. import of wine (in hectoliters) for several years is given in the Table. Determine whether the trend appears linear. If so, and assuming the trend continues, in what year will imports exceed $12,000$hectoliters?

| Year | Imports |
|---|---|
| 1992 | 2665 |
| 1994 | 2688 |
| 1996 | 3565 |
| 1998 | 4129 |
| 2000 | 4584 |
| 2002 | 5655 |
| 2004 | 6549 |
| 2006 | 7950 |
| 2008 | 8487 |
| 2009 | 9462 |

**Answer**

Yes, trend appears linear because $r = 0.985$ and will exceed $12,000$near midyear, 2016, $24.6$years since 1992.

24) The Table shows the year and the number of people unemployed in a particular city for several years. Determine whether the trend appears linear. If so, and assuming the trend continues, in what year will the number of unemployed reach $5$?

| Year | Number Unemployed |
|---|---|
| 1990 | 750 |
| 1992 | 670 |
| 1994 | 650 |

| Year | Number Unemployed |
|---|---|
| 1996 | 605 |
| 1998 | 550 |
| 2000 | 510 |
| 2002 | 460 |
| 2004 | 420 |
| 2006 | 380 |
| 2008 | 320 |

### Technology

**For the exercises 25-31, use each set of data to calculate the regression line using a calculator or other technology tool, and determine the correlation coefficient to 3 decimal places of accuracy.**

25)

| $x$ | 8 | 15 | 26 | 31 | 56 |
|---|---|---|---|---|---|
| $y$ | 23 | 41 | 53 | 72 | 103 |

**Answer**

$y = 1.640x + 13.800, r = 0.987$

26)

| $x$ | 5 | 7 | 10 | 12 | 15 |
|---|---|---|---|---|---|
| $y$ | 4 | 12 | 17 | 22 | 24 |

27)

| $x$ | $y$ | $x$ | $y$ |
|---|---|---|---|
| 3 | 21.9 | 11 | 15.76 |
| 4 | 22.22 | 12 | 13.68 |
| 5 | 22.74 | 13 | 14.1 |
| 6 | 22.26 | 14 | 14.02 |
| 7 | 20.78 | 15 | 11.94 |
| 8 | 17.6 | 16 | 12.76 |
| 9 | 16.52 | 17 | 11.28 |
| 10 | 18.54 | 18 | 9.1 |

**Answer**

$y = -0.962x + 26.86, r = -0.965$

28)

| $x$ | $y$ |
|---|---|

| $x$ | $y$ |
|---|---|
| 4 | 44.8 |
| 5 | 43.1 |
| 6 | 38.8 |
| 7 | 39 |
| 8 | 38 |
| 9 | 32.7 |
| 10 | 30.1 |
| 11 | 29.3 |
| 12 | 27 |
| 13 | 25.8 |

29)

| $x$ | $y$ |
|---|---|
| 21 | 17 |
| 25 | 11 |
| 30 | 2 |
| 31 | −1 |
| 40 | −18 |
| 50 | −40 |

**Answer**

$y = -1.981x + 60.197; r = -0.998$

30)

| $x$ | $y$ |
|---|---|
| 100 | 2000 |
| 80 | 1798 |
| 60 | 1589 |
| 55 | 1580 |
| 40 | 1390 |
| 20 | 1202 |

31)

| $x$ | $y$ |
|---|---|
| 900 | 70 |
| 988 | 80 |

| $x$ | $y$ |
|---|---|
| 1000 | 82 |
| 1010 | 84 |
| 1200 | 105 |
| 1205 | 108 |

**Answer**

$y = 0.121x - 38.841, r = 0.998$

## Extensions

32) Graph $f(x) = 0.5x + 10$. Pick a set of 5 ordered pairs using inputs $x = -2, 1, 5, 6, 9$ and use linear regression to verify that the function is a good fit for the data.

33) Graph $f(x) = -2x - 10$. Pick a set of 5 ordered pairs using inputs $x = -2, 1, 5, 6, 9$ and use linear regression to verify the function.

**Answer**

$(-2, -6), (1, -12), (5, -20), (6, -22), (9, -28); y = -2x - 10$

**For the exercises 34-36, consider this scenario: The profit of a company decreased steadily over a ten-year span. The following ordered pairs shows dollars and the number of units sold in hundreds and the profit in thousands of over the ten-year span, (number of units sold, profit) for specific recorded years:**

$$(46, 1,600), (48, 1,550), (50, 1,505), (52, 1,540), (54, 1,495)$$

34) Use linear regression to determine a function $P$ where the profit in thousands of dollars depends on the number of units sold in hundreds.

35) Find to the nearest tenth and interpret the $x$-intercept.

**Answer**

$(189.8, 0)$If $18,980$units are sold, the company will have a profit of zero dollars.

36) Find to the nearest tenth and interpret the $y$-intercept.

## Real-World Applications

**For the exercises 37-38, consider this scenario: The population of a city increased steadily over a ten-year span. The following ordered pairs shows the population and the year over the ten-year span, (population, year) for specific recorded years:**

$$(2500, 2000), (2650, 2001), (3000, 2003), (3500, 2006), (4200, 2010)$$

37) Use linear regression to determine a function $y$, where the year depends on the population. Round to three decimal places of accuracy.

**Answer**

$y = 0.00587x + 1985.41$

38) Predict when the population will hit $8,000$.

**For the exercises 39-40, consider this scenario: The profit of a company increased steadily over a ten-year span. The following ordered pairs show the number of units sold in hundreds and the profit in thousands of over the ten year span, (number of units sold, profit) for specific recorded years:**

$$(46, 250), (48, 305), (50, 350), (52, 390), (54, 410)$$

39) Use linear regression to determine a function $y$, where the profit in thousands of dollars depends on the number of units sold in hundreds.

**Answer**

$y = 20.25x - 671.5$

40) Predict when the profit will exceed one million dollars.

**For the exercises 41-42, consider this scenario: The profit of a company decreased steadily over a ten-year span. The following ordered pairs show dollars and the number of units sold in hundreds and the profit in thousands of over the ten-year span (number of units sold, profit) for specific recorded years:**

$$(46, 250), (48, 225), (50, 205), (52, 180), (54, 165)$$

41) Use linear regression to determine a function $y$, where the profit in thousands of dollars depends on the number of units sold in hundreds.

**Answer**

$y = -10.75x + 742.50$

42) Predict when the profit will dip below the $\$25,000$threshold.

---

This page titled 3.5.E: Linear Functions(Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.E: Linear Functions(Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.5.R: Linear Functions(Review)

## 2.1 Linear Functions

1) Determine whether the algebraic equation is linear: $2x + 3y = 7$

**Answer**

Yes

2) Determine whether the algebraic equation is linear: $6x^2 - y = 5$

3) Determine whether the function is increasing or decreasing: $f(x) = 7x - 2$

**Answer**

Increasing

4) Determine whether the function is increasing or decreasing: $g(x) = -x + 2$


5) Given each set of information, find a linear equation that satisfies the given conditions, if possible. Passes through $(7, 5)$ and $(3, 17)$

**Answer**

$y = -3x + 26$

6) Given each set of information, find a linear equation that satisfies the given conditions, if possible. $x$ -intercept at $(6, 0)$ and $y$ -intercept at $(0, 10)$


7) Find the slope of the line shown in the line graph.





**Answer**

3

8) Find the slope of the line graphed.




9) Write an equation in slope-intercept form for the line shown.




**Answer**

$y = 2x - 2$

10) Does the following table represent a linear function? If so, find the linear equation that models the data.

| $x$ | –4 | 0 | 2 | 10 |
|---|---|---|---|---|
| $g(x)$ | 18 | –2 | –12 | –52 |

11) Does the following table represent a linear function? If so, find the linear equation that models the data.

| $x$ | 6 | 8 | 12 | 26 |
|---|---|---|---|---|
| $g(x)$ | –8 | –12 | –18 | –46 |

**Answer**

Not linear

12) On June $^{1st}$, a company has $\$4,000,000$ profit. If the company then loses $150,000$ dollars per day thereafter in the month of June, what is the company's profit n$^{th}$ day after June $^{1st}$?

## 2.2 Graphs of Linear Functions

**For the exercises 1-2, determine whether the lines given by the equations below are parallel, perpendicular, or neither parallel nor perpendicular:**

1) $\begin{aligned} 2x-6y &= 12 \\ -x+3y &= 1 \end{aligned}$

**Answer**

parallel

2) $\begin{aligned} y &= \frac{1}{3}x-2 \\ 3x+y &= -9 \end{aligned}$

**For the exercises 3-4, find the $x$- and $y$- intercepts of the given equation**

3) $7x+9y=-63$

**Answer**

$(-9,0);(0,-7)$

4) $f(x)=2x-1$

**For the exercises 5-11, use the descriptions of the pairs of lines to find the slopes of Line 1 and Line 2. Is each pair of lines parallel, perpendicular, or neither?**

5)

Line 1: Passes through $(5,11)$ and $(10,1)$
Line 2 : Passes through $(-1,3)$ and $(-5,11)$

**Answer**

Line 1 : $m=-2$; Line 2 : $m=-2$; Parallel

6)

Line 1: Passes through $(8,-10)$ and $(0,-26)$
Line 2: Passes through $(2,5)$ and $(4,4)$

7) Write an equation for a line perpendicular to $f(x)=5x-1$ and passing through the point $(5,20)$.


**Answer**

$y=-0.2x+21$

8) Find the equation of a line with a $y$ -intercept of $(0,2)$ and slope $-\frac{1}{2}$.

9) Sketch a graph of the linear function $f(t)=2t-5$ .

**Answer**




10) Find the point of intersection for the 2 linear functions: $\begin{aligned} x &= y+6 \\ 2x-y &= 13 \end{aligned}$

11) A car rental company offers two plans for renting a car.

Plan A: 25 dollars per day and 10 cents per mile

Plan B: 50 dollars per day with free unlimited mileage

How many miles would you need to drive for plan B to save you money?

**Answer**

250

## 2.3 Modeling with Linear Functions

1) Find the area of a triangle bounded by the $y$ axis, the line $f(x) = 10 - 2x$, and the line perpendicular to $f$ that passes through the origin.

2) A town's population increases at a constant rate. In 2010 the population was $55,000$. By 2012 the population had increased to $76,000$. If this trend continues, predict the population in 2016.


**Answer**

$118,000$

3) The number of people afflicted with the common cold in the winter months dropped steadily by 50 each year since 2004 until 2010. In 2004, 875 people were inflicted.

4) Find the linear function that models the number of people afflicted with the common cold $C$ as a function of the year, $t$. When will no one be afflicted?

**For the exercises 5-6, use the graph in the Figure below showing the profit, $y$, in thousands of dollars, of a company in a given year, $x$, where $x$ represents years since 1980.**




5) Find the linear function $y$, where $y$ depends on $x$, the number of years since 1980.

**Answer**

$y = -300x + 11,500$

6) Find and interpret the $y$-intercept.

7) For the following exercise, consider this scenario: In 2004, a school population was $1,700$. By 2012 the population had grown to $2,500$. Assume the population is changing linearly.

a. How much did the population grow between the year 2004 and 2012?
b. What is the average population growth per year?
c. Find an equation for the population, $P$, of the school $t$ years after 2004.

**Answer**

a. $800$
b. $100$ students per year
c. $P(t) = 100t + 1700$

**For the exercises 8-9, consider this scenario: In 2000, the moose population in a park was measured to be $6,500$. By 2010, the population was measured to be $12,500$. Assume the population continues to change linearly.**

8) Find a formula for the moose population, $P$.

9) What does your model predict the moose population to be in 2020?

**Answer**

$18,500$

**For the exercises 10-, consider this scenario: The median home values in subdivisions Pima Central and East Valley (adjusted for inflation) are shown in the Table below. Assume that the house values are changing linearly.**

| Year | Pima Central | East Valley |
|---|---|---|
| 1970 | 32,000 | 120,250 |
| 2010 | 85,000 | 150,000 |

10) In which subdivision have home values increased at a higher rate?

11) If these trends were to continue, what would be the median home value in Pima Central in 2015?

**Answer**

$\$91,625$

## 2.4 Fitting Linear Models to Data

1) Draw a scatter plot for the data in the Table below. Then determine whether the data appears to be linearly related.


| | | | | | |
|---|---|---|---|---|---|
| 0 | 2 | 4 | 6 | 8 | 10 |
| –105 | –50 | 1 | 55 | 105 | 160 |

2) Draw a scatter plot for the data in the Table. If we wanted to know when the population would reach $15,000$, would the answer involve interpolation or extrapolation?

| Year | Population |
|---|---|
| 1990 | 5,600 |
| 1995 | 5,950 |
| 2000 | 6,300 |
| 2005 | 6,600 |
| 2010 | 6,900 |

**Answer**


Extrapolation





3) Eight students were asked to estimate their score on a 10-point quiz. Their estimated and actual scores are given in the Table. Plot the points, then sketch a line that fits the data.

| Predicted | Actual |
|---|---|
| 6 | 6 |
| 7 | 7 |
| 7 | 8 |
| 8 | 8 |
| 7 | 9 |
| 9 | 10 |
| 10 | 10 |
| 10 | 9 |

4) Draw a best-fit line for the plotted data.




**Answer**




**For the exercises 5-6, consider the data in the Table below, which shows the percent of unemployed in a city of people 25 years or older who are college graduates is given below, by year.**

| Year | Percent Graduates |
|---|---|
| 2000 | 6.5 |
| 2002 | 7.0 |
| 2005 | 7.4 |
| 2007 | 8.2 |
| 2010 | 9.0 |

5) Determine whether the trend appears to be linear. If so, and assuming the trend continues, find a linear regression model to predict the percent of unemployed in a given year to three decimal places.

6) In what year will the percentage exceed 12%?

**Answer**

Midway through 2024

7) Based on the set of data given in the Table, calculate the regression line using a calculator or other technology tool, and determine the correlation coefficient to three decimal places.

| $x$ | 17 | 20 | 23 | 26 | 29 |
|---|---|---|---|---|---|
| $y$ | 15 | 25 | 31 | 37 | 40 |

8) Based on the set of data given in the Table, calculate the regression line using a calculator or other technology tool, and determine the correlation coefficient to three decimal places.

| $x$ | 10 | 12 | 15 | 18 | 20 |
|---|---|---|---|---|---|
| $y$ | 36 | 34 | 30 | 28 | 22 |

**Answer**

$y = -1.294x + 49.412; r = -0.974$

**For the exercises 9-12, consider this scenario: The population of a city increased steadily over a ten-year span. The following ordered pairs show the population and the year over the ten-year span (population, year) for specific recorded years: $(3,600, 2000); (4,000, 2001); (4,700, 2003); (6,000, 2006)$**

9) Use linear regression to determine a function $y$, where the year depends on the population, to three decimal places of accuracy.

10) Predict when the population will hit $12,000$

**Answer**

Early in 2022

11) What is the correlation coefficient for this model to three decimal places of accuracy?

12) According to the model, what is the population in 2014?

**Answer**

$7,660$

## Practice Test

1) Determine whether the following algebraic equation can be written as a linear function: $2x + 3y = 7$

**Answer**

Yes

2) Determine whether the following function is increasing or decreasing: $f(x) = -2x + 5$

3) Determine whether the following function is increasing or decreasing: $f(x) = 7x + 9$

**Answer**

Increasing

4) Given the following set of information, find a linear equation satisfying the conditions, if possible. Passes through $(5, 1)$ and $(3, -9)$

5) Given the following set of information, find a linear equation satisfying the conditions, if possible. $x$ intercept at $(-4, 0)$ and $y$ -intercept at $(0, -6)$

**Answer**

$y = -1.5x - 6$

6) Find the slope of the line in the Figure below.






Figure below.




**Answer**

$y = -2x - 1$

8) Does the Table represent a linear function? If so, find a linear equation that models the data.

| $x$ | –6 | 0 | 2 | 4 |
|---|---|---|---|---|
| $g(x)$ | 14 | 32 | 38 | 44 |

9) Does the Table represent a linear function? If so, find a linear equation that models the data.

| $x$ | 1 | 3 | 7 | 11 |
|---|---|---|---|---|
| $g(x)$ | 4 | 9 | 19 | 12 |

**Answer**

No

10) At 6 AM, an online company has sold 120 items that day. If the company sells an average of 30 items per hour for the remainder of the day, write an expression to represent the number of items that were sold $n$ after 6 AM.

**For the exercises 11-22, determine whether the lines given by the equations below are parallel, perpendicular, or neither parallel nor perpendicular:**

11) $$\begin{aligned} y &= \frac{3}{4}x - 9 \\ -4x - 3y &= 8 \end{aligned}$$

**Answer**

Perpendicular

12) $$\begin{aligned} -2x + y &= 3 \\ 3x + \frac{3}{2}y &= 5 \end{aligned}$$

13) Find the $x$ - and $y$ -intercepts of the equation $2x + 7y = -14$.

**Answer**

$(-7, 0); (0, -2)$

14) Given below are descriptions of two lines. Find the slopes of Line 1 and Line 2. Is the pair of lines parallel, perpendicular, or neither?

Line 1 : Passes through $(-2, -6)$ and $(3, 14)$
Line 2 : Passes through $(2, 6)$ and $(4, 14)$

15) Write an equation for a line perpendicular to $f(x) = 4x + 3$ and passing through the point $(8, 10)$.


**Answer**

$y = -0.25x + 12$

16) Sketch a line with a $y$-intercept of $(0, 5)$ and slope $-\frac{5}{2}$.

17) Graph of the linear function $f(x) = -x + 6$.

**Answer**




18) For the two linear functions, find the point of intersection: $$\begin{aligned} x &= y + 2 \\ 2x - 3y &= -1 \end{aligned}$$

19) A car rental company offers two plans for renting a car.

Plan A: $\$25$ per day and $\$0.10$ per mile
Plan B: $\$40$ per day with free unlimited mileage

How many miles would you need to drive for plan B to save you money?

**Answer**

150

20) Find the area of a triangle bounded by the $y$ axis, the line $f(x) = 12 - 4x$, and the line perpendicular to $f$ that passes through the origin.


21) A town's population increases at a constant rate. In 2010 the population was $65,000$. By 2012 the population had increased to $90,000$. Assuming this trend continues, predict the population in 2018.

**Answer**

$165,000$

22) The number of people afflicted with the common cold in the winter months dropped steadily by $25$ each year since 2002 until 2012. In 2002, $8,040$ people were inflicted. Find the linear function that models the number of people afflicted with the common cold $C$ as a function of the year, $t$. When will less than $6,000$ people be afflicted?

**For the exercises 23-24, use the graph in Figure, showing the profit, $y$, in thousands of dollars, of a company in a given year, $x$, where $x$ represents years since 1980.**




23) Find the linear function $y$, where $y$ depends on $x$, the number of years since 1980.

**Answer**

$y = 875x + 10,675$

24) Find and interpret the $y$-intercept.

25) In 2004, a school population was $1250$. By 2012 the population had dropped to $875$. Assume the population is changing linearly.

a. How much did the population drop between the year 2004 and 2012?
b. What is the average population decline per year?
c. Find an equation for the population, $P$, of the school $t$ years after 2004.


**Answer**

a. $375$
b. dropped an average of $46.875$,or about $47$ people per year
c. $y = -46.875t + 1250$


26) Draw a scatter plot for the data provided in the Table. Then determine whether the data appears to be linearly related.

| | | | | | |
|---|---|---|---|---|---|
| 0 | 2 | 4 | 6 | 8 | 10 |
| –450 | –200 | 10 | 265 | 500 | 755 |

27) Draw a best-fit line for the plotted data.




**Answer**




**For the exercises 28-29, use the Table below, which shows the percent of unemployed persons 25 years or older who are college graduates in a particular city, by year.**

| Year | Percent Graduates |
|---|---|
| 2000 | 8.5 |
| 2002 | 8.0 |
| 2005 | 7.2 |
| 2007 | 6.7 |
| 2010 | 6.4 |

28) Determine whether the trend appears linear. If so, and assuming the trend continues, find a linear regression model to predict the percent of unemployed in a given year to three decimal places.

29) In what year will the percentage drop below 4%?

**Answer**

Early in 2018

30) Based on the set of data given in the Table below, calculate the regression line using a calculator or other technology tool, and determine the correlation coefficient. Round to three decimal places of accuracy.

| $x$ | 16 | 18 | 20 | 24 | 26 |
|---|---|---|---|---|---|
| $y$ | 106 | 110 | 115 | 120 | 125 |

**For the exercises 31-33, consider this scenario: The population of a city increased steadily over a ten-year span. The following ordered pairs shows the population (in hundreds) and the year over the ten-year span, (population, year) for specific recorded years: $(4,500,2000);(4,700,2001);(5,200,2003);(5,800,2006)$**

31) Use linear regression to determine a function y, where the year depends on the population. Round to three decimal places of accuracy.

**Answer**

$y = 0.00455x + 1979.5$

32) Predict when the population will hit $20,000$

33) What is the correlation coefficient for this model?

**Answer**

$r = 0.999$

---

This page titled 3.5.R: Linear Functions(Review) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **2.R: Linear Functions(Review)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.6: Composition of Functions

**Learning Objectives**

- Combine functions using algebraic operations.
- Create a new function by composition of functions.
- Evaluate composite functions.
- Find the domain of a composite function.
- Decompose a composite function into its component functions.

Suppose we want to calculate how much it costs to heat a house on a particular day of the year. The cost to heat a house will depend on the average daily temperature, and in turn, the average daily temperature depends on the particular day of the year. Notice how we have just defined two relationships: The cost depends on the temperature, and the temperature depends on the day.

Using descriptive variables, we can notate these two functions. The function $C(T)$ gives the cost $C$ of heating a house for a given average daily temperature in $T$ degrees Celsius. The function $T(d)$ gives the average daily temperature on day d of the year. For any given day, $Cost = C(T(d))$ means that the cost depends on the temperature, which in turns depends on the day of the year. Thus, we can evaluate the cost function at the temperature $T(d)$. For example, we could evaluate $T(5)$ to determine the average daily temperature on the 5th day of the year. Then, we could evaluate the **cost function** at that temperature. We would write $C(T(5))$.





Figure 3.6.1: Explanation of $C(T(5))$, which is the cost for the temperature and $T(5)$ is the temperature on day 5.

By combining these two relationships into one function, we have performed function composition, which is the focus of this section.

## Combining Functions Using Algebraic Operations

Function composition is only one way to combine existing functions. Another way is to carry out the usual algebraic operations on functions, such as addition, subtraction, multiplication and division. We do this by performing the operations with the function outputs, defining the result as the output of our new function.

Suppose we need to add two columns of numbers that represent a husband and wife's separate annual incomes over a period of years, with the result being their total household income. We want to do this for every year, adding only that year's incomes and then collecting all the data in a new column. If $w(y)$ is the wife's income and $h(y)$ is the husband's income in year $y$, and we want $T$ to represent the total income, then we can define a new function.

$$T(y) = h(y) + w(y)$$

If this holds true for every year, then we can focus on the relation between the functions without reference to a year and write

$$T = h + w$$

Just as for this sum of two functions, we can define difference, product, and ratio functions for any pair of functions that have the same kinds of inputs (not necessarily numbers) and also the same kinds of outputs (which do have to be numbers so that the usual operations of algebra can apply to them, and which also must have the same units or no units when we add and subtract). In this way, we can think of adding, subtracting, multiplying, and dividing functions.

For two functions $f(x)$ and $g(x)$ with real number outputs, we define new functions $f+g$, $f-g$, $fg$, and $\frac{f}{g}$ by the relations.

$$(f+g)(x) = f(x)+g(x)$$
$$(f-g)(x) = f(x)-g(x)$$
$$(fg)(x) = f(x)g(x)$$
$$\left(\frac{f}{g}\right)(x) = \frac{f(x)}{g(x)}$$

**Example 3.6.1: Performing Algebraic Operations on Functions**

Find and simplify the functions $(g-f)(x)$ and $\left(\frac{g}{f}\right)(x)$, given $f(x)=x-1$ and $g(x)=x^2-1$. Are they the same function?

**Solution**

Begin by writing the general form, and then substitute the given functions.

$$\begin{aligned}(g-f)(x) &= g(x)-f(x)\\ (g-f)(x) &= x^2-1-(x-1)\\ &= x^2-x\\ &= x(x-1)\end{aligned}$$

$$\left(\frac{g}{f}\right)(x) = g(x)f(x)$$

$$\begin{aligned}\left(\frac{g}{f}\right)(x) &= \frac{x^2-1}{x-1}\\ &= \frac{(x+1)(x-1)}{x-1}\\ &= x+1\end{aligned}$$

No, the functions are not the same.

Note: For $\left(\frac{g}{f}\right)(x)$, the condition $x \neq 1$ is necessary because when $x=1$, the denominator is equal to 0, which makes the function undefined.

**Exercise 3.6.1**

Find and simplify the functions $(fg)(x)$ and $(f-g)(x)$.

$$f(x) = x-1$$

and

$$g(x) = x^2-1$$

Are they the same function?

**Answer**

$(fg)(x) = f(x)g(x) = (x-1)(x2-1) = x^3-x^2-x+1$

$(f-g)(x) = f(x)-g(x) = (x-1)-(x^2-1) = x-x^2$

No, the functions are not the same.

## Create a Function by Composition of Functions

Performing algebraic operations on functions combines them into a new function, but we can also create functions by composing functions. When we wanted to compute a heating cost from a day of the year, we created a new function that takes a day as input and yields a cost as output. The process of **combining functions** so that the output of one function becomes the input of another is known as a **composition of functions**. The resulting function is known as a **composite function**. We represent this combination by the following notation:

$$f \circ g(x) = f(g(x)) \tag{3.6.1}$$

We read the left-hand side as"$f$ composed with $g$ at $x$," and the right-hand side as"$f$ of $g$ of $x$."The two sides of the equation have the same mathematical meaning and are equal. The open circle symbol $\circ$ is called the composition operator. We use this operator mainly when we wish to emphasize the relationship between the functions themselves without referring to any particular input value. Composition is a binary operation that takes two functions and forms a new function, much as addition or multiplication takes two numbers and gives a new number. However, it is important not to confuse function composition with multiplication because, as we learned above, in most cases $f(g(x)) \neq f(x)g(x)$.

It is also important to understand the order of operations in evaluating a composite function. We follow the usual convention with parentheses by starting with the innermost parentheses first, and then working to the outside. In the equation above, the function $g$ takes the input $x$ first and yields an output $g(x)$. Then the function $f$ takes $g(x)$ as an input and yields an output $f(g(x))$.





Figure 3.6.2: Explanation of the composite function.

In general, $f \circ g$ and $g \circ f$ are different functions. In other words, in many cases $f(g(x)) \neq g(f(x))$ for all $x$. We will also see that sometimes two functions can be composed only in one specific order.

For example, if $f(x) = x^2$ and $g(x) = x + 2$, then

$$\begin{aligned} f(g(x)) &= f(x+2) \\ &= (x+2)^2 \\ &= x^2 + 4x + 4 \end{aligned}$$

but

$$\begin{aligned} g(f(x)) &= g(x^2) \\ &= x^2 + 2 \end{aligned}$$

These expressions are not equal for all values of x, so the two functions are not equal. It is irrelevant that the expressions happen to be equal for the single input value $x = -\frac{1}{2}$.

Note that the range of the inside function (the first function to be evaluated) needs to be within the domain of the outside function. Less formally, the composition has to make sense in terms of inputs and outputs.

### Composition of Functions

When the output of one function is used as the input of another, we call the entire operation a composition of functions. For any input $x$ and functions $f$ and $g$, this action defines a **composite function**, which we write as $f \circ g$ such that

$$(f \circ g)(x) = f(g(x)) \tag{3.6.2}$$

The domain of the composite function $f \circ g$ is all $x$ such that $x$ is in the domain of $g$ and $g(x)$ is in the domain of $f$.

It is important to realize that the product of functions $fg$ is not the same as the function composition $f(g(x))$, because, in general, $f(x)g(x) \neq f(g(x))$.

### Example 3.6.2: Determining whether Composition of Functions is Commutative

Using the functions provided, find $f(g(x))$ and $g(f(x))$. Determine whether the composition of the functions is **commutative**.

$$f(x)=2x+1 \quad g(x)=3-x$$

**Solution**

Let's begin by substituting $g(x)$ into $f(x)$.

$$\begin{aligned} f(g(x)) &= 2(3-x)+1 \\ &= 6-2x+1 \\ &= 7-2x \end{aligned}$$

Now we can substitute $f(x)$ into $g(x)$.

$$\begin{aligned} g(f(x)) &= 3-(2x+1) \\ &= 3-2x-1 \\ &= 2-2x \end{aligned}$$

We find that $g(f(x))\neq f(g(x))$, so the operation of function composition is not commutative.

### Example 3.6.3: Interpreting Composite Functions

The function $c(s)$ gives the number of calories burned completing $s$ sit-ups, and $s(t)$ gives the number of sit-ups a person can complete in $t$ minutes. Interpret $c(s(3))$.

**Solution**

The inside expression in the composition is $s(3)$. Because the input to the $s$-function is time, $t=3$ represents 3 minutes, and $s(3)$ is the number of sit-ups completed in 3 minutes.

Using $s(3)$ as the input to the function $c(s)$ gives us the number of calories burned during the number of sit-ups that can be completed in 3 minutes, or simply the number of calories burned in 3 minutes (by doing sit-ups).

### Example 3.6.4: Investigating the Order of Function Composition

Suppose $f(x)$ gives miles that can be driven in $x$ hours and $g(y)$ gives the gallons of gas used in driving $y$ miles. Which of these expressions is meaningful: $f(g(y))$ or $g(f(x))$?

**Solution**

The function $y=f(x)$ is a function whose output is the number of miles driven corresponding to the number of hours driven.

$$\text{number of miles } = f(\text{number of hours})$$

The function $g(y)$ is a function whose output is the number of gallons used corresponding to the number of miles driven. This means:

$$\text{number of gallons } = g(\text{number of miles})$$

The expression $g(y)$ takes miles as the input and a number of gallons as the output. The function $f(x)$ requires a number of hours as the input. Trying to input a number of gallons does not make sense. The expression $f(g(y))$ is meaningless.

The expression $f(x)$ takes hours as input and a number of miles driven as the output. The function $g(y)$ requires a number of miles as the input. Using $f(x)$ (miles driven) as an input value for $g(y)$, where gallons of gas depends on miles driven, does make sense. The expression $g(f(x))$ makes sense, and will yield the number of gallons of gas used, $g$, driving a certain number of miles, $f(x)$, in $x$ hours.

Question/Answer

Are there any situations where $f(g(y))$ and $g(f(x))$ would both be meaningful or useful expressions?

Yes. For many pure mathematical functions, both compositions make sense, even though they usually produce different new functions. In real-world problems, functions whose inputs and outputs have the same units also may give compositions that are meaningful in either order

Exercise 3.6.2

The gravitational force on a planet a distance $r$ from the sun is given by the function $G(r)$. The acceleration of a planet subjected to any force $F$ is given by the function $a(F)$. Form a meaningful composition of these two functions, and explain what it means.

**Answer**

A gravitational force is still a force, so $a(G(r))$ makes sense as the acceleration of a planet at a distance $r$ from the Sun (due to gravity), but $G(a(F))$ does not make sense.

## Evaluating Composite Functions

Once we compose a new function from two existing functions, we need to be able to evaluate it for any input in its domain. We will do this with specific numerical inputs for functions expressed as tables, graphs, and formulas and with variables as inputs to functions expressed as formulas. In each case, we evaluate the inner function using the starting input and then use the inner function's output as the input for the outer function.

### Evaluating Composite Functions Using Tables

When working with functions given as tables, we read input and output values from the table entries and always work from the inside to the outside. We evaluate the inside function first and then use the output of the inside function as the input to the outside function.

Example 3.6.5: Using a Table to Evaluate a Composite Function

Using Table 3.6.1, evaluate $f(g(3))$ and $g(f(3))$.

Table 3.6.1

| $x$ | $f(x)$ | $g(x)$ |
|---|---|---|
| 1 | 6 | 3 |
| 2 | 8 | 5 |
| 3 | 3 | 2 |
| 4 | 1 | 7 |

**Solution**

To evaluate $f(g(3))$, we start from the inside with the input value 3. We then evaluate the inside expression $g(3)$ using the table that defines the function $g$ : $g(3) = 2$ . We can then use that result as the input to the function $f$, so $g(3)$ is replaced by 2 and we get $f(2)$. Then, using the table that defines the function $f$, we find that $f(2) = 8$.

$$g(3) = 2$$

$$f(g(3)) = f(2) = 8$$

To evaluate $g(f(3))$, we first evaluate the inside expression $f(3)$ using the first table: $f(3) = 3$. Then, using the table for $g$, we can evaluate

$$g(f(3)) = g(3) = 2$$

Table $3.6.2$ shows the composite functions $f \circ g$ and $g \circ f$ as tables.

Table 3.6.2

| $x$ | $g(x)$ | $f(g(x))$ | $f(x)$ | $g(f(x))$ |
|---|---|---|---|---|
| 3 | 2 | 8 | 3 | 2 |

**Exercise 3.6.3**

Using Table $3.6.1$, evaluate $f(g(1))$ and $g(f(4))$.

**Answer**

$f(g(1)) = f(3) = 3$ and $g(f(4)) = g(1) = 3$

## Evaluating Composite Functions Using Graphs

When we are given individual functions as graphs, the procedure for evaluating composite functions is similar to the process we use for evaluating tables. We read the input and output values, but this time, from the x- and y-axes of the graphs.

**How To ...**

Given a composite function and graphs of its individual functions, evaluate it using the information provided by the graphs.

1. Locate the given input to the inner function on the x-axis of its graph.
2. Read off the output of the inner function from the y-axis of its graph.
3. Locate the inner function output on the x-axis of the graph of the outer function.
4. Read the output of the outer function from the y-axis of its graph. This is the output of the composite function.

**Example 3.6.6: Using a Graph to Evaluate a Composite Function**

Using Figure $3.6.3$, evaluate $f(g(1))$.





Figure 3.6.3: Two graphs of a positive and negative parabola.

**Solution**

To evaluate $f(g(1))$, we start with the inside evaluation. See Figure $3.6.4$.





Figure 3.6.4: Two graphs of a positive parabola $g(x)$ and a negative parabola $f(x)$. The following points are plotted: $g(1) = 3$ and $f(3) = 6$.

We evaluate $g(1)$ using the graph of $g(x)$, finding the input of 1 on the x-axis and finding the output value of the graph at that input. Here, $g(1) = 3$. We use this value as the input to the function $f$.

$$f(g(1)) = f(3)$$

We can then evaluate the composite function by looking to the graph of $f(x)$, finding the input of 3 on the x-axis and reading the output value of the graph at this input. Here, $f(3) = 6$, so $f(g(1)) = 6$.

**Analysis**

Figure 3.6.5 shows how we can mark the graphs with arrows to trace the path from the input value to the output value.





Figure 3.6.5: Two graphs of a positive and negative parabola.

**Exercise 3.6.4**

Using Figure 3.6.3, evaluate $g(f(2))$.

**Answer**

$g(f(2)) = g(5) = 3$

## Evaluating Composite Functions Using Formulas

When evaluating a composite function where we have either created or been given formulas, the rule of working from the inside out remains the same. The input value to the outer function will be the output of the inner function, which may be a numerical value, a variable name, or a more complicated expression.

While we can compose the functions for each individual input value, it is sometimes helpful to find a single formula that will calculate the result of a composition $f(g(x))$. To do this, we will extend our idea of function evaluation. Recall that, when we evaluate a function like $f(t) = t^2 - t$ , we substitute the value inside the parentheses into the formula wherever we see the input variable.

**How To...**

Given a formula for a composite function, evaluate the function.

1. Evaluate the inside function using the input value or variable provided.
2. Use the resulting output as the input to the outside function.

**Example 3.6.7: Evaluating a Composition of Functions Expressed as Formulas with a Numerical Input**

Given $f(t) = t^2 - t$ and $h(x) = 3x + 2$, evaluate $f(h(1))$.

**Solution**

Because the inside expression is $h(1)$, we start by evaluating $h(x)$ at 1.

$$h(1) = 3(1) + 2$$
$$h(1) = 5$$

Then $f(h(1)) = f(5)$, so we evaluate $f(t)$ at an input of 5.

$$f(h(1)) = f(5)$$
$$f(h(1)) = 5^2 - 5$$
$$f(h(1)) = 20$$

**Analysis**

It makes no difference what the input variables $t$ and $x$ were called in this problem because we evaluated for specific numerical values.

**Exercise 3.6.5**

Given $f(t) = t^2 - t$ and $h(x) = 3x + 2$, evaluate

a. $h(f(2))$
b. $h(f(-2))$

**Answer a**

8

**Answer b**

20

## Finding the Domain of a Composite Function

As we discussed previously, the **domain of a composite function** such as $f \circ g$ is dependent on the domain of $g$ and the domain of $f$. It is important to know when we can apply a composite function and when we cannot, that is, to know the domain of a function such as $f \circ g$. Let us assume we know the domains of the functions $f$ and $g$ separately. If we write the composite function for an input $x$ as $f(g(x))$, we can see right away that $x$ must be a member of the domain of g in order for the expression to be meaningful, because otherwise we cannot complete the inner function evaluation. However, we also see that $g(x)$ must be a member of the domain of $f$, otherwise the second function evaluation in $f(g(x))$ cannot be completed, and the expression is still undefined. Thus the domain of $f \circ g$ consists of only those inputs in the domain of $g$ that produce outputs from $g$ belonging to the domain of $f$. Note that the domain of $f$ composed with $g$ is the set of all $x$ such that $x$ is in the domain of $g$ and g(x)\) is in the domain of $f$.

**Definition: Domain of a Composite Function**

The **domain of a composite function** $f(g(x))$ is the set of those inputs $x$ in the domain of $g$ for which $g(x)$ is in the domain of $f$.

**How To...**

Given a function composition $f(g(x))$, determine its domain.

1. Find the domain of $g$.
2. Find the domain of $f$.
3. Find those inputs $x$ in the domain of $g$ for which $g(x)$ is in the domain of $f$. That is, exclude those inputs $x$ from the domain of $g$ for which $g(x)$ is not in the domain of $f$. The resulting set is the domain of $f \circ g$.

**Example 3.6.8A: Finding the Domain of a Composite Function**

Find the domain of

$$(f \circ g)(x) \text{ where } f(x) = \frac{5}{x-1} \text{ and } g(x) = \frac{4}{3x-2}$$

**Solution**

The domain of $g(x)$ consists of all real numbers except $x = \frac{2}{3}$, since that input value would cause us to divide by 0. Likewise, the domain of $f$ consists of all real numbers except 1. So we need to exclude from the domain of $g(x)$ that value of $x$ for which $g(x) = 1$.

$$\begin{aligned} \frac{4}{3x-2} &= 1 \\ 4 &= 3x-2 \\ 6 &= 3x \\ x &= 2 \end{aligned}$$

So the domain of $f \circ g$ is the set of all real numbers except $\frac{2}{3}$ and 2. This means that

$$x \neq \frac{2}{3} \text{ or } x \neq 2$$

We can write this in interval notation as

$$\left(-\infty, \frac{2}{3}\right) \cup \left(\frac{2}{3}, 2\right) \cup (2, \infty)$$

### Example 3.6.8$B$: Finding the Domain of a Composite Function Involving Radicals

Find the domain of

$$(f\circ g)(x) \text{ where } f(x)=\sqrt{x+2} \text{ and } g(x)=\sqrt{3-x}$$

**Solution**

Because we cannot take the square root of a negative number, the domain of $g$ is $(-\infty, 3]$. Now we check the domain of the composite function

$$(f\circ g)(x)=\sqrt{\sqrt{3-x}+2}$$

For $(f\circ g)(x)=\sqrt{\sqrt{3-x}+2}$, $\sqrt{3-x}+2\geq 0$, since the radicand of a square root must be positive. Since square roots are positive, $\sqrt{3-x}\geq 0$,or, $3-x\geq 0$, which gives a domain of $(-\infty, 3]$.

**Analysis**

This example shows that knowledge of the range of functions (specifically the inner function) can also be helpful in finding the domain of a composite function. It also shows that the domain of $f\circ g$ can contain values that are not in the domain of $f$, though they must be in the domain of $g$.

### Exercise 3.6.6

Find the domain of

$$(f\circ g)(x) \text{ where } f(x)=\frac{1}{x-2} \text{ and } g(x)=\sqrt{x+4}$$

**Answer**

$[-4, 0)\cup(0, \infty)$

## Decomposing a Composite Function into its Component Functions

In some cases, it is necessary to decompose a complicated function. In other words, we can write it as a composition of two simpler functions. There may be more than one way to **decompose a composite function**, so we may choose the decomposition that appears to be most expedient.

### Example 3.6.9: Decomposing a Function

Write $f(x)=\sqrt{5-x^2}$ as the composition of two functions.

**Solution**

We are looking for two functions, $g$ and $h$, so $f(x)=g(h(x))$. To do this, we look for a function inside a function in the formula for $f(x)$. As one possibility, we might notice that the expression $5-x^2$ is the inside of the square root. We could then decompose the function as

$$h(x)=5-x^2 \text{ and } g(x)=\sqrt{x}$$

We can check our answer by recomposing the functions.

$$g(h(x))=g(5-x^2)=\sqrt{5-x^2}$$

### Exercise 3.6.7

Write $f(x)=\dfrac{4}{3-\sqrt{4+x^2}}$ as the composition of two functions.

**Answer**

Possible answers:

$g(x) = \sqrt{4 + x^2}$

$h(x) = \dfrac{4}{3 - x}$

$f = h \circ g$

Access these online resources for additional instruction and practice with composite functions.

- Composite Functions (http://openstaxcollege.org/l/compfunction)
- Composite Function Notation Application (http://openstaxcollege.org/l/compfuncnot)
- Composite Functions Using Graphs (http://openstaxcollege.org/l/compfuncgraph)
- Decompose Functions (http://openstaxcollege.org/l/decompfunction)
- Composite Function Values (http://openstaxcollege.org/l/compfuncvalue)

## Key Equation

- Composite function $(f \circ g)(x) = f(g(x))$

## Key Concepts

- We can perform algebraic operations on functions. See Example.
- When functions are combined, the output of the first (inner) function becomes the input of the second (outer) function.
- The function produced by combining two functions is a composite function. See Example and Example.
- The order of function composition must be considered when interpreting the meaning of composite functions. See Example.
- A composite function can be evaluated by evaluating the inner function using the given input value and then evaluating the outer function taking as its input the output of the inner function.
- A composite function can be evaluated from a table. See Example.
- A composite function can be evaluated from a graph. See Example.
- A composite function can be evaluated from a formula. See Example.
- The domain of a composite function consists of those inputs in the domain of the inner function that correspond to outputs of the inner function that are in the domain of the outer function. See Example and Example.
- Just as functions can be combined to form a composite function, composite functions can be decomposed into simpler functions.
- Functions can often be decomposed in more than one way. See Example.

## Glossary

**composite function**

the new function formed by function composition, when the output of one function is used as the input of another

This page titled 3.6: Composition of Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.4: Composition of Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.6E: Composition of Functions (Exercises)

For the following exercises, find $(f \circ g)(x)$ and $(g \circ f)(x)$ for each pair of functions.

34. $f(x) = 4 - x, \quad g(x) = -4x$
35. $f(x) = 3x + 2, \quad g(x) = 5 - 6x$
36. $f(x) = x^2 + 2x, \quad g(x) = 5x + 1$
37. $f(x) = \sqrt{x+2}, \quad g(x) = \frac{1}{x}$
38. $f(x) = \frac{x+3}{2}, \quad g(x) = \sqrt{1-x}$

For the following exercises, find $(f \circ g)$ and the domain for $(f \circ g)(x)$ for each pair of functions.

39. $f(x) = \frac{x+1}{x+4}, \quad g(x) = \frac{1}{x}$
40. $f(x) = \frac{1}{x+3}, \quad g(x) = \frac{1}{x-9}$
41. $f(x) = \frac{1}{x}, \quad g(x) = \sqrt{x}$
42. $f(x) = \frac{1}{x^2-1}, \quad g(x) = \sqrt{x+1}$

For the following exercises, express each function $H$ as a composition of two functions $f$ and $g$ where $H(x) = (f \circ g)(x)$.

43. $H(x) = \sqrt{\frac{2x-1}{3x+4}}$
44. $H(x) = \frac{1}{(3x^2-4)^{-3}}$

This page titled 3.6E: Composition of Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.4E: Composition of Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.7: Transformation of Functions

**Learning Objectives**

- Graph functions using vertical and horizontal shifts.
- Graph functions using reflections about the x-axis and the y-axis.
- Determine whether a function is even, odd, or neither from its graph.
- Graph functions using compressions and stretches.
- Combine transformations.

We all know that a flat mirror enables us to see an accurate image of ourselves and whatever is behind us. When we tilt the mirror, the images we see may shift horizontally or vertically. But what happens when we bend a flexible mirror? Like a carnival funhouse mirror, it presents us with a distorted image of ourselves, stretched or compressed horizontally or vertically. In a similar way, we can distort or transform mathematical functions to better adapt them to describing objects or processes in the real world. In this section, we will take a look at several kinds of transformations.



Figure 3.7.1: (credit: "Misko"/Flickr)

Often when given a problem, we try to model the scenario using mathematics in the form of words, tables, graphs, and equations. One method we can employ is to adapt the basic graphs of the toolkit functions to build new models for a given scenario. There are systematic ways to alter functions to construct appropriate models for the problems we are trying to solve.

## Identifying Vertical Shifts

One simple kind of transformation involves shifting the entire graph of a function up, down, right, or left. The simplest shift is a vertical shift, moving the graph up or down, because this transformation involves adding a positive or negative constant to the function. In other words, we add the same constant to the output value of the function regardless of the input. For a function $g(x) = f(x) + k$, the function $f(x)$ is shifted vertically $k$ units. See Figure 3.7.2 for an example.





Figure 3.7.2: Vertical shift by $k = 1$ of the cube root function $f(x) = \sqrt[3]{x}$.

To help you visualize the concept of a vertical shift, consider that $y = f(x)$. Therefore, $f(x) + k$ is equivalent to $y + k$. Every unit of $y$ is replaced by $y + k$, so the $y$-value increases or decreases depending on the value of $k$. The result is a shift upward or downward.

**Definition: Vertical Shift**

Given a function $f(x)$, a new function $g(x) = f(x) + k$, where $k$ is a constant, is a **vertical shift** of the function $f(x)$. All the output values change by $k$ units. If $k$ is positive, the graph will shift up. If $k$ is negative, the graph will shift down.

**Example 3.7.1: Adding a Constant to a Function**

To regulate temperature in a green building, airflow vents near the roof open and close throughout the day. Figure 3.7.3 shows the area of open vents $V$ (in square feet) throughout the day in hours after midnight, $t$. During the summer, the facilities manager decides to try to better regulate temperature by increasing the amount of open vents by 20 square feet throughout the day and night. Sketch a graph of this new function.





Figure 3.7.3

**Solution**

We can sketch a graph of this new function by adding 20 to each of the output values of the original function. This will have the effect of shifting the graph vertically up, as shown in Figure 3.7.4.





Figure 3.7.4

Notice that in Figure 3.7.4, for each input value, the output value has increased by 20, so if we call the new function $S(t)$,we could write

$$S(t) = V(t) + 20 \tag{3.7.1}$$

This notation tells us that, for any value of $t$,$S(t)$ can be found by evaluating the function $V$ at the same input and then adding 20 to the result. This defines $S$ as a transformation of the function $V$, in this case a vertical shift up 20 units. Notice that, with a vertical shift, the input values stay the same and only the output values change. See Table 3.7.1.

Table 3.7.1

| $t$ | 0 | 8 | 10 | 17 | 19 | 24 |
|---|---|---|---|---|---|---|
| $V(t)$ | 0 | 0 | 220 | 220 | 0 | 0 |

| | | | | | | |
|---|---|---|---|---|---|---|
| $S(t)$ | 20 | 20 | 240 | 240 | 20 | 20 |

**How To...**

Given a tabular function, create a new row to represent a vertical shift.

1. Identify the output row or column.
2. Determine the **magnitude** of the shift.
3. Add the shift to the value in each output cell. Add a positive value for up or a negative value for down.

**Example 3.7.2: Shifting a Tabular Function Vertically**

A function $f(x)$ is given in Table 3.7.2. Create a table for the function $g(x) = f(x) - 3$.

Table 3.7.2

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $f(x)$ | 1 | 3 | 7 | 11 |

**Solution**

The formula $g(x) = f(x) - 3$ tells us that we can find the output values of $g$ by subtracting 3 from the output values of $f$. For example:

$$\begin{aligned} f(x) &= 1 && \text{Given} \\ g(x) &= f(x) - 3 && \text{Given Transformation} \\ g(2) &= f(2) - 3 \\ &= 1 - 3 \\ &= -2 \end{aligned}$$

Subtracting 3 from each $f(x)$ value, we can complete a table of values for $g(x)$ as shown in Table 3.7.3.

Table 3.7.3

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $f(x)$ | 1 | 3 | 7 | 11 |
| $g(x)$ | -2 | 0 | 4 | 8 |

**Analysis**

As with the earlier vertical shift, notice the input values stay the same and only the output values change.

**Exercise 3.7.1**

The function $h(t) = -4.9t^2 + 30t$ gives the height $h$ of a ball (in meters) thrown upward from the ground after $t$ seconds. Suppose the ball was instead thrown from the top of a 10-m building. Relate this new height function $b(t)$ to $h(t)$, and then find a formula for $b(t)$.

**Answer**

$b(t) = h(t) + 10 = -4.9t^2 + 30t + 10$

## Identifying Horizontal Shifts

We just saw that the vertical shift is a change to the output, or outside, of the function. We will now look at how changes to input, on the inside of the function, change its graph and meaning. A shift to the input results in a movement of the graph of the function

left or right in what is known as a **horizontal shift**, shown in Figure 3.7.4.





Figure 3.7.4: Horizontal shift of the function $f(x) = \sqrt[3]{x}$. Note that $h = -1$ shifts the graph to the left, that is, towards negative values of $x$.

For example, if $f(x) = x^2$, then $g(x) = (x-2)^2$ is a new function. Each input is reduced by 2 prior to squaring the function. The result is that the graph is shifted 2 units to the right, because we would need to increase the prior input by 2 units to yield the same output value as given in $f$.

**Definition: Horizontal Shift**

Given a function $f$, a new function $g(x) = f(x-h)$, where $h$ is a constant, is a **horizontal shift** of the function $f$. If $h$ is positive, the graph will shift right. If $h$ is negative, the graph will shift left.

**Example 3.7.4: Adding a Constant to an Input**

Returning to our building airflow example from Figure 3.7.2, suppose that in autumn the facilities manager decides that the original venting plan starts too late, and wants to begin the entire venting program 2 hours earlier. Sketch a graph of the new function.

**Solution**

We can set $V(t)$ to be the original program and $F(t)$ to be the revised program.

$$V(t) = \text{ the original venting plan}$$

$$F(t) = \text{ starting 2 hrs sooner}$$

In the new graph, at each time, the airflow is the same as the original function $V$ was 2 hours later. For example, in the original function $V$, the airflow starts to change at 8 a.m., whereas for the function $F$, the airflow starts to change at 6 a.m. The comparable function values are $V(8) = F(6)$. See Figure 3.7.5. Notice also that the vents first opened to $220\text{ft}^2$ at 10 a.m. under the original plan, while under the new plan the vents reach $220\text{ft}^2$ at 8 a.m., so $V(10) = F(8)$.

In both cases, we see that, because $F(t)$ starts 2 hours sooner, $h = -2$. That means that the same output values are reached when $F(t) = V(t-(-2)) = V(t+2)$ .





Figure 3.7.5

**Analysis**

Note that $V(t+2)$ has the effect of shifting the graph to the left.

Horizontal changes or "inside changes" affect the domain of a function (the input) instead of the range and often seem counterintuitive. The new function $F(t)$ uses the same outputs as $V(t)$, but matches those outputs to inputs 2 hours earlier than those of $V(t)$. Said another way, we must add 2 hours to the input of $V$ to find the corresponding output for $F$ : $F(t)=V(t+2)$ .

How To...

Given a tabular function, create a new row to represent a horizontal shift.

1. Identify the input row or column.
2. Determine the magnitude of the shift.
3. Add the shift to the value in each input cell.

**Example 3.7.5: Shifting a Tabular Function Horizontally**

A function $f(x)$ is given in Table 3.7.4. Create a table for the function $g(x)=f(x-3)$.

Table 3.7.4

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $f(x)$ | 1 | 3 | 7 | 11 |

**Solution**

The formula $g(x)=f(x-3)$ tells us that the output values of $g$ are the same as the output value of $f$ when the input value is 3 less than the original value. For example, we know that $f(2)=1$. To get the same output from the function $g$, we will need an input value that is 3 larger. We input a value that is 3 larger for $g(x)$ because the function takes 3 away before evaluating the function $f$.

$$\begin{aligned} g(5) &= f(5-3) \\ &= f(2) \\ &= 1 \end{aligned}$$

We continue with the other values to create Table 3.7.5.

Table 3.7.5

| $x$ | 5 | 7 | 9 | 11 |
|---|---|---|---|---|
| $x-3$ | 2 | 4 | 6 | 8 |
| $f(x)$ | 1 | 3 | 7 | 11 |
| $g(x)$ | 1 | 3 | 7 | 11 |

The result is that the function $g(x)$ has been shifted to the right by 3. Notice the output values for $g(x)$ remain the same as the output values for $f(x)$, but the corresponding input values, $x$, have shifted to the right by 3. Specifically, 2 shifted to 5, 4 shifted to 7, 6 shifted to 9, and 8 shifted to 11.

**Analysis**

Figure 3.7.6 represents both of the functions. We can see the horizontal shift in each point.





Figure 3.7.6: Graph of the points from the previous table for $f(x)$ and $g(x) = f(x-3)$

## Example 3.7.6: Identifying a Horizontal Shift of a Toolkit Function

Figure 3.7.7 represents a transformation of the toolkit function $f(x) = x^2$. Relate this new function $g(x)$ to $f(x)$, and then find a formula for $g(x)$.





Figure 3.7.7: Graph of a parabola

**Solution**

Notice that the graph is identical in shape to the $f(x) = x^2$ function, but the $x$-values are shifted to the right 2 units. The vertex used to be at $(0, 0)$, but now the vertex is at $(2, 0)$. The graph is the basic quadratic function shifted 2 units to the right, so

$$g(x) = f(x-2)$$

Notice how we must input the value $x = 2$ to get the output value $y = 0$; the $x$-values must be 2 units larger because of the shift to the right by 2 units. We can then use the definition of the $f(x)$ function to write a formula for $g(x)$ by evaluating $f(x-2)$.

$$\begin{aligned} f(x) &= x^2 \\ g(x) &= f(x-2) \\ g(x) &= f(x-2) = (x-2)^2 \end{aligned}$$

**Analysis**

To determine whether the shift is $+2$ or $-2$, consider a single reference point on the graph. For a quadratic, looking at the vertex point is convenient. In the original function, $f(0)=0$. In our shifted function, $g(2)=0$. To obtain the output value of 0 from the function $f$, we need to decide whether a plus or a minus sign will work to satisfy $g(2)=f(x-2)=f(0)=0$ . For this to work, we will need to subtract 2 units from our input values.

### Example 3.7.7: Interpreting Horizontal versus Vertical Shifts

The function $G(m)$ gives the number of gallons of gas required to drive $m$ miles. Interpret $G(m)+10$ and $G(m+10)$

**Solution**

$G(m)+10$ can be interpreted as adding 10 to the output, gallons. This is the gas required to drive $m$ miles, plus another 10 gallons of gas. The graph would indicate a vertical shift.

$G(m+10)$ can be interpreted as adding 10 to the input, miles. So this is the number of gallons of gas required to drive 10 miles more than $m$ miles. The graph would indicate a horizontal shift.

### Exercise 3.7.7

Given the function $f(x)=\sqrt{x}$, graph the original function $f(x)$ and the transformation $g(x)=f(x+2)$ on the same axes. Is this a horizontal or a vertical shift? Which way is the graph shifted and by how many units?

**Answer**

The graphs of $f(x)$ and $g(x)$ are shown below. The transformation is a horizontal shift. The function is shifted to the left by 2 units.





Figure 3.7.8

## Combining Vertical and Horizontal Shifts

Now that we have two transformations, we can combine them together. Vertical shifts are outside changes that affect the output $(y-)$ axis values and shift the function up or down. Horizontal shifts are inside changes that affect the input $(x-)$ axis values and shift the function left or right. Combining the two types of shifts will cause the graph of a function to shift up or down and right or left.

### How To...

**Given a function and both a vertical and a horizontal shift, sketch the graph.**

1. Identify the vertical and horizontal shifts from the formula.
2. The vertical shift results from a constant added to the output. Move the graph up for a positive constant and down for a negative constant.
3. The horizontal shift results from a constant added to the input. Move the graph left for a positive constant and right for a negative constant.
4. Apply the shifts to the graph in either order.

## Example 3.7.8: Graphing Combined Vertical and Horizontal Shifts

Given $f(x) = |x|$, sketch a graph of $h(x) = f(x+1) - 3$ .

**Solution**

The function $f$ is our toolkit absolute value function. We know that this graph has a V shape, with the point at the origin. The graph of $h$ has transformed $f$ in two ways: $f(x+1)$ is a change on the inside of the function, giving a horizontal shift left by 1, and the subtraction by 3 in $f(x+1)-3$ is a change to the outside of the function, giving a vertical shift down by 3. The transformation of the graph is illustrated in Figure 3.7.9.

Let us follow one point of the graph of $f(x) = |x|$.

- The point $(0, 0)$ is transformed first by shifting left 1 unit:$(0, 0) \to (-1, 0)$
- The point $(-1, 0)$ is transformed next by shifting down 3 units:$(-1, 0) \to (-1, -3)$





Figure 3.7.9: Graph of an absolute function, $y = |x|$ , and how it was transformed to $y = |x+1| - 3$

Figure 3.7.10shows the graph of $h$.





Figure 3.7.10: The final function $y = |x+1| - 3$ .

## Exercise 3.7.8

Given $f(x) = |x|$, sketch a graph of $h(x) = f(x-2) + 4$ .

**Answer**





Figure 3.7.11

## Example 3.7.9: Identifying Combined Vertical and Horizontal Shifts

Write a formula for the graph shown in Figure 3.7.12, which is a transformation of the toolkit square root function.





Figure 3.7.12: Graph of a square root function transposed right one unit and up 2.

**Solution**

The graph of the toolkit function starts at the origin, so this graph has been shifted 1 to the right and up 2. In function notation, we could write that as

$$h(x) = f(x-1)+2$$

Using the formula for the square root function, we can write

$$h(x) = \sqrt{x-1}+2$$

**Analysis**

Note that this transformation has changed the domain and range of the function. This new graph has domain $[1, \infty)$ and range $[2, \infty)$.

## Exercise 3.7.9

Write a formula for a transformation of the toolkit reciprocal function $f(x) = \frac{1}{x}$ that shifts the function's graph one unit to the right and one unit up.

**Answer**

$$g(x) = \frac{1}{x-1}+1$$

## Graphing Functions Using Reflections about the Axes

Another transformation that can be applied to a function is a reflection over the x- or y-axis. A **vertical reflection** reflects a graph vertically across the x-axis, while a **horizontal reflection** reflects a graph horizontally across the y-axis. The reflections are shown in Figure 3.7.13.





Figure 3.7.13: Graph of the vertical and horizontal reflection of a function.

Notice that the vertical reflection produces a new graph that is a mirror image of the base or original graph about the x-axis. The horizontal reflection produces a new graph that is a mirror image of the base or original graph about the y-axis.

**Definitions: Reflections**

Given a function $f(x)$, a new function $g(x) = -f(x)$ is a **vertical reflection** of the function $f(x)$, sometimes called a reflection about (or over, or through) the x-axis.

Given a function $f(x)$, a new function $g(x) = f(-x)$ is a **horizontal reflection** of the function $f(x)$, sometimes called a reflection about the y-axis.

**How To...**

Given a function, reflect the graph both vertically and horizontally.

1. Multiply all outputs by –1 for a vertical reflection. The new graph is a reflection of the original graph about the x-axis.
2. Multiply all inputs by –1 for a horizontal reflection. The new graph is a reflection of the original graph about the y-axis.

**Example 3.7.10: Reflecting a Graph Horizontally and Vertically**

Reflect the graph of $s(t) = \sqrt{t}$ (a) vertically and (b) horizontally.

**Solution**

a. Reflecting the graph vertically means that each output value will be reflected over the horizontal t-axis as shown in Figure 3.7.14





Figure 3.7.14: Graph of the vertical reflection of the square root function.

Because each output value is the opposite of the original output value, we can write

$$V(t) = -s(t) \text{ or } V(t) = -\sqrt{t}$$

Notice that this is an outside change, or vertical shift, that affects the output $s(t)$ values, so the negative sign belongs outside of the function.

b. Reflecting horizontally means that each input value will be reflected over the vertical axis as shown in Figure 3.7.15.





Figure 3.7.15: Horizontal reflection of the square root function

Because each input value is the opposite of the original input value, we can write

$$H(t) = s(-t) \text{ or } H(t) = \sqrt{-t}$$

Notice that this is an inside change or horizontal change that affects the input values, so the negative sign is on the inside of the function.

Note that these transformations can affect the domain and range of the functions. While the original square root function has domain $[0, \infty)$ and range $[0, \infty)$, the vertical reflection gives the $V(t)$ function the range $(-\infty, 0]$ and the horizontal reflection gives the $H(t)$ function the domain $(-\infty, 0]$.

## Exercise 3.7.5

Reflect the graph of $f(x) = |x - 1|$ (a) vertically and (b) horizontally.

**Answer**

a.





Figure 3.7.16: Graph of a vertically reflected absolute function.

b.





Figure 3.7.17: Graph of an absolute function translated one unit left.

## Example 3.7.11: Reflecting a Tabular Function Horizontally and Vertically

A function $f(x)$ is given as Table 3.7.6. Create a table for the functions below.

a. $g(x) = -f(x)$
b. $h(x) = f(-x)$

Table 3.7.6

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $f(x)$ | 1 | 3 | 7 | 11 |

a. For $g(x)$, the negative sign outside the function indicates a vertical reflection, so the x-values stay the same and each output value will be the opposite of the original output value. See Table 3.7.7.

Table 3.7.7

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $g(x)$ | -1 | -3 | -7 | -11 |

b. For $h(x)$, the negative sign inside the function indicates a horizontal reflection, so each input value will be the opposite of the original input value and the $h(x)$ values stay the same as the $f(x)$ values. See Table 3.7.8.

Table 3.7.8

| $x$ | -2 | -4 | -6 | -8 |
|---|---|---|---|---|
| $h(x)$ | 1 | 3 | 7 | 11 |

## Exercise 3.7.6

A function $f(x)$ is given as Table 3.7.9. Create a table for the functions below.

a. $g(x) = -f(x)$
b. $h(x) = f(-x)$

Table 3.7.9

| $x$ | -2 | 0 | 2 | 4 |
|---|---|---|---|---|
| $f(x)$ | 5 | 10 | 15 | 20 |

**Answer**

**a.** $g(x) = -f(x)$

Table 3.7.10

| $x$ | -2 | 0 | 2 | 4 |
|---|---|---|---|---|
| $g(x)$ | -5 | -10 | -15 | -20 |

**b.** $h(x) = f(-x)$

Table 3.7.11

| $x$ | -2 | 0 | 2 | -4 |
|---|---|---|---|---|
| $h(x)$ | 15 | 10 | 5 | 20 |

## Example 3.7.12: Applying a Learning Model Equation

A common model for learning has an equation similar to $k(t) = -2^{-t} + 1$ , where $k$ is the percentage of mastery that can be achieved after $t$ practice sessions. This is a transformation of the function $f(t) = 2^t$ shown in Figure 3.7.18. Sketch a graph of $k(t)$.





Figure 3.7.18: Graph of $k(t)$

**Solution**

This equation combines three transformations into one equation.

- A horizontal reflection: $f(-t) = 2^{-t}$

- A vertical reflection: $-f(-t) = -2^{-t}$
- A vertical shift: $-f(-t)+1 = -2^{-t}+1$

We can sketch a graph by applying these transformations one at a time to the original function. Let us follow two points through each of the three transformations. We will choose the points $(0, 1)$ and $(1, 2)$.

- First, we apply a horizontal reflection: $(0, 1)$ $(-1, 2)$.
- Then, we apply a vertical reflection: $(0, -1)$ $(-1, -2)$.
- Finally, we apply a vertical shift: $(0, 0)$ $(-1, -1)$.

This means that the original points, $(0, 1)$ and $(1, 2)$ become $(0, 0)$ and $(-1, -1)$ after we apply the transformations.

In Figure 3.7.19, the first graph results from a horizontal reflection. The second results from a vertical reflection. The third results from a vertical shift up 1 unit.





Figure 3.7.19: Graphs of all the transformations.

**Analysis**

As a model for learning, this function would be limited to a domain of $t \geq 0$, with corresponding range $[0, 1)$.

## Exercise 3.7.7

Given the toolkit function $f(x) = x^2$, graph $g(x) = -f(x)$ and $h(x) = f(-x)$. Take note of any surprising behavior for these functions.

**Answer**





Figure 3.7.20: Graph of $x^2$ and its reflections.

Notice: $g(x) = f(-x)$ looks the same as $f(x)$.

## Determining Even and Odd Functions

Some functions exhibit symmetry so that reflections result in the original graph. For example, horizontally reflecting the toolkit functions $f(x) = x^2$ or $f(x) = |x|$ will result in the original graph. We say that these types of graphs are symmetric about the y-axis. Functions whose graphs are symmetric about the y-axis are called **even functions**.

If the graphs of $f(x) = x^3$ or $f(x) = \frac{1}{x}$ were reflected over both axes, the result would be the original graph, as shown in Figure 3.7.21.





Figure 3.7.21: (a) The cubic toolkit function (b) Horizontal reflection of the cubic toolkit function (c) Horizontal and vertical reflections reproduce the original cubic function.

We say that these graphs are symmetric about the origin. A function with a graph that is symmetric about the origin is called an **odd function**.

Note: A function can be neither even nor odd if it does not exhibit either symmetry. For example, $f(x) = 2^x$ is neither even nor odd. Also, the only function that is both even and odd is the constant function $f(x) = 0$.

### Definitions: Even and Odd Functions

A function is called an **even function** if for every input $x$

$f(x) = f(-x)$

The graph of an even function is symmetric about the y-axis.

A function is called an **odd function** if for every input $x$

$f(x) = -f(-x)$

The graph of an odd function is symmetric about the origin.

### How To...

Given the formula for a function, determine if the function is even, odd, or neither.

1. Determine whether the function satisfies $f(x) = f(-x)$. If it does, it is even.
2. Determine whether the function satisfies $f(x) = -f(-x)$. If it does, it is odd.
3. If the function does not satisfy either rule, it is neither even nor odd.

### Example 3.7.13: Determining whether a Function Is Even, Odd, or Neither

Is the function $f(x) = x^3 + 2x$ even, odd, or neither?

**Solution**

Without looking at a graph, we can determine whether the function is even or odd by finding formulas for the reflections and determining if they return us to the original function. Let's begin with the rule for even functions.

$$f(-x) = (-x)^3 + 2(-x) = -x^3 - 2x$$

This does not return us to the original function, so this function is not even. We can now test the rule for odd functions.

$$-f(-x) = -(-x^3 - 2x) = x^3 + 2x$$

Because $-f(-x) = f(x)$, this is an odd function.

**Analysis**

Consider the graph of $f$ in Figure 3.7.22 Notice that the graph is symmetric about the origin. For every point $(x, y)$ on the graph, the corresponding point $(-x, -y)$ is also on the graph. For example, $(1, 3)$ is on the graph of $f$, and the corresponding point $(-1, -3)$ is also on the graph.





Figure 3.7.22: Graph of $f(x)$ with labeled points at $(1, 3)$ and $(-1, -3)$.

**Exercise 3.7.8**

Is the function $f(s) = s^4 + 3s^2 + 7$ even, odd, or neither?

**Answer**

even

## Graphing Functions Using Stretches and Compressions

Adding a constant to the inputs or outputs of a function changed the position of a graph with respect to the axes, but it did not affect the shape of a graph. We now explore the effects of multiplying the inputs or outputs by some quantity.

We can transform the inside (input values) of a function or we can transform the outside (output values) of a function. Each change has a specific effect that can be seen graphically.

### Vertical Stretches and Compressions

When we multiply a function by a positive constant, we get a function whose graph is stretched or compressed vertically in relation to the graph of the original function. If the constant is greater than 1, we get a **vertical stretch**; if the constant is between 0 and 1, we get a **vertical compression**. Figure 3.7.23 shows a function multiplied by constant factors 2 and 0.5 and the resulting vertical stretch and compression.





Figure 3.7.23: Vertical stretch and compression

**Definitions: Vertical Stretches and Compressions**

Given a function $f(x)$, a new function $g(x) = af(x)$, where $a$ is a constant, is a **vertical stretch** or **vertical compression** of the function $f(x)$.

- If $a > 1$, then the graph will be stretched.
- If $0 < a < 1$, then the graph will be compressed.
- If $a < 0$, then there will be combination of a vertical stretch or compression with a vertical reflection.

**How To...**

Given a function, graph its vertical stretch.

a. Identify the value of $a$.
b. Multiply all range values by $a$
c. If $a > 1$, the graph is stretched by a factor of $a$.
d. If $0 < a < 1$, the graph is compressed by a factor of $a$.
e. If $a < 0$, the graph is either stretched or compressed and also reflected about the x-axis.

**Example 1.5.14: Graphing a Vertical Stretch**

A function $P(t)$ models the population of fruit flies. The graph is shown in Figure $3.7.24$





Figure 3.7.24: Graph to represent the growth of the population of fruit flies.

A scientist is comparing this population to another population, $Q$, whose growth follows the same pattern, but is twice as large. Sketch a graph of this population.

**Solution**

Because the population is always twice as large, the new population's output values are always twice the original function's output values. Graphically, this is shown in Figure $3.7.25$

If we choose four reference points, $(0, 1)$, $(3, 3)$, $(6, 2)$ and $(7, 0)$ we will multiply all of the outputs by 2.

The following shows where the new points for the new graph will be located.

$$(0, 1) \to (0, 2) \tag{3.7.2}$$
$$(3, 3) \to (3, 6) \tag{3.7.3}$$
$$(6, 2) \to (6, 4) \tag{3.7.4}$$
$$(7, 0) \to (7, 0) \tag{3.7.5}$$





Figure 3.7.25: Graph of the population function doubled.

Symbolically, the relationship is written as

$$Q(t) = 2P(t)$$

This means that for any input $t$, the value of the function $Q$ is twice the value of the function $P$. Notice that the effect on the graph is a vertical stretching of the graph, where every point doubles its distance from the horizontal axis. The input values, $t$, stay the same while the output values are twice as large as before.

**How To...**

Given a tabular function and assuming that the transformation is a vertical stretch or compression, create a table for a vertical compression.

1. Determine the value of $a$.
2. Multiply all of the output values by $a$.

**Example 3.7.15: Finding a Vertical Compression of a Tabular Function**

A function $f$ is given as Table 3.7.12 Create a table for the function $g(x) = \frac{1}{2}f(x)$.

Table 3.7.12

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $f(x)$ | 1 | 3 | 7 | 11 |

**Solution**

The formula $g(x) = \frac{1}{2}f(x)$ tells us that the output values of $g$ are half of the output values of $f$ with the same inputs. For example, we know that $f(4) = 3$. Then

$$g(4) = \frac{1}{2}f(4) = \frac{1}{2}(3) = \frac{3}{2}$$

We do the same for the other values to produce Table 3.7.13

Table 3.7.13

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $g(x)$ | $\frac{1}{2}$ | $\frac{3}{2}$ | $\frac{7}{2}$ | $\frac{11}{2}$ |

**Analysis**

The result is that the function $g(x)$ has been compressed vertically by $\frac{1}{2}$. Each output value is divided in half, so the graph is half the original height.

## Exercise 3.7.9

A function $f$ is given as Table 3.7.14 Create a table for the function $g(x) = \frac{3}{4}f(x)$.

Table 3.7.14

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $f(x)$ | 12 | 16 | 20 | 0 |

**Answer**

Table 3.7.15

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $g(x)$ | 9 | 12 | 15 | 0 |

## Example 3.7.16: Recognizing a Vertical Stretch

The graph in Figure 3.7.26 is a transformation of the toolkit function $f(x) = x^3$. Relate this new function $g(x)$ to $f(x)$, and then find a formula for $g(x)$.





Figure 3.7.26: Graph of a transformation of $f(x) = x^3$

When trying to determine a vertical stretch or shift, it is helpful to look for a point on the graph that is relatively clear. In this graph, it appears that $g(2) = 2$. With the basic cubic function at the same input, $f(2) = 2^3 = 8$. Based on that, it appears that the outputs of $g$ are $\frac{1}{4}$ the outputs of the function $f$ because $g(2) = \frac{1}{4}f(2)$. From this we can fairly safely conclude that $g(x) = \frac{1}{4}f(x)$.

We can write a formula for $g$ by using the definition of the function $f$.

$$g(x) = \frac{1}{4}f(x) = \frac{1}{4}x^3. \tag{3.7.6}$$

**Exercise 3.7.1**

Write the formula for the function that we get when we stretch the identity toolkit function by a factor of 3, and then shift it down by 2 units.

**Answer**

$g(x) = 3x - 2$

## Horizontal Stretches and Compressions

Now we consider changes to the inside of a function. When we multiply a function's input by a positive constant, we get a function whose graph is stretched or compressed horizontally in relation to the graph of the original function. If the constant is between 0 and 1, we get a **horizontal stretch**; if the constant is greater than 1, we get a **horizontal compression** of the function.





Figure 3.7.27: Graph of the vertical stretch and compression of $x^2$.

Given a function $y = f(x)$, the form $y = f(bx)$ results in a horizontal stretch or compression. Consider the function $y = x^2$. Observe Figure 3.7.27. The graph of $y = (0.5x)^2$ is a horizontal stretch of the graph of the function $y = x^2$ by a factor of 2. The graph of $y = (2x)^2$ is a horizontal compression of the graph of the function $y = x^2$ by a factor of 2.

**Definitions: Horizontal Stretches and Compressions**

Given a function $f(x)$, a new function $g(x) = f(bx)$, where $b$ is a constant, is a **horizontal stretch** or **horizontal compression** of the function $f(x)$.

- If $b > 1$, then the graph will be compressed by $\frac{1}{b}$.
- If $0 < b < 1$, then the graph will be stretched by $\frac{1}{b}$.
- If $b < 0$, then there will be combination of a horizontal stretch or compression with a horizontal reflection.

**How To...**

Given a description of a function, sketch a horizontal compression or stretch.

1. Write a formula to represent the function.
2. Set $g(x) = f(bx)$ where $b > 1$ for a compression or $0 < b < 1$ for a stretch.

## Example 3.7.17: Graphing a Horizontal Compression

Suppose a scientist is comparing a population of fruit flies to a population that progresses through its lifespan twice as fast as the original population. In other words, this new population, $R$, will progress in 1 hour the same amount as the original population does in 2 hours, and in 2 hours, it will progress as much as the original population does in 4 hours. Sketch a graph of this population.

**Solution**

Symbolically, we could write

$$R(1) = P(2), \tag{3.7.7}$$
$$R(2) = P(4), \quad \text{and in general,} \tag{3.7.8}$$
$$R(t) = P(2t). \tag{3.7.9}$$

See Figure 3.7.28 for a graphical comparison of the original population and the compressed population.





Figure 3.7.28: (a) Original population graph (b) Compressed population graph

**Analysis**

Note that the effect on the graph is a horizontal compression where all input values are half of their original distance from the vertical axis.

## Example 3.7.18: Finding a Horizontal Stretch for a Tabular Function

A function $f(x)$ is given as Table 3.7.16. Create a table for the function $g(x) = f(\frac{1}{2}x)$.

Table 3.7.16

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $f(x)$ | 1 | 3 | 7 | 11 |

The formula $g(x) = f(\frac{1}{2}x)$ tells us that the output values for $g$ are the same as the output values for the function $f$ at an input half the size. Notice that we do not have enough information to determine $g(2)$ because $g(2) = f(\frac{1}{2} \cdot 2) = f(1)$ , and we do not have a value for $f(1)$ in our table. Our input values to $g$ will need to be twice as large to get inputs for $f$ that we can evaluate. For example, we can determine $g(4)$.

$$g(4) = f(\frac{1}{2} \cdot 4) = f(2) = 1 \tag{3.7.10}$$

We do the same for the other values to produce Table 3.7.17.

Table 3.7.17

| $x$ | 4 | 8 | 12 | 16 |
|---|---|---|---|---|

| $g(x)$ | 1 | 3 | 7 | 11 |
|---|---|---|---|---|

Figure 3.7.29 shows the graphs of both of these sets of points.





Figure 3.7.29: Graph of the previous table.

**Analysis**

Because each input value has been doubled, the result is that the function $g(x)$ has been stretched horizontally by a factor of 2.

## Example 3.7.19: Recognizing a Horizontal Compression on a Graph

Relate the function $g(x)$ to $f(x)$ in Figure 3.7.30.





Figure 3.7.30: Graph of $f(x)$ being vertically compressed to $g(x)$.

**Solution**

The graph of $g(x)$ looks like the graph of $f(x)$ horizontally compressed. Because $f(x)$ ends at (6,4) and $g(x)$ ends at (2,4), we can see that the x-values have been compressed by $\frac{1}{3}$, because $6(\frac{1}{3}) = 2$. We might also notice that $g(2) = f(6)$ and $g(1) = f(3)$. Either way, we can describe this relationship as $g(x) = f(3x)$. This is a horizontal compression by $\frac{1}{3}$.

**Analysis**

Notice that the coefficient needed for a horizontal stretch or compression is the reciprocal of the stretch or compression. So to stretch the graph horizontally by a scale factor of 4, we need a coefficient of $\frac{1}{4}$ in our function: $f(\frac{1}{4}x)$. This means that the input values must be four times larger to produce the same result, requiring the input to be larger, causing the horizontal stretching.

## Exercise 3.7.11

Write a formula for the toolkit square root function horizontally stretched by a factor of 3.

**Answer**

$g(x) = f(\frac{1}{3}x)$ , so using the square root function we get $g(x) = \sqrt{\frac{1}{3}x}$

## Performing a Sequence of Transformations

When combining transformations, it is very important to consider the order of the transformations. For example, vertically shifting by 3 and then vertically stretching by 2 does not create the same graph as vertically stretching by 2 and then vertically shifting by 3, because when we shift first, both the original function and the shift get stretched, while only the original function gets stretched when we stretch first.

When we see an expression such as $2f(x)+3$, which transformation should we start with? The answer here follows nicely from the order of operations. Given the output value of $f(x)$, we first multiply by 2, causing the vertical stretch, and then add 3, causing the vertical shift. In other words, multiplication before addition.

Horizontal transformations are a little trickier to think about. When we write $g(x) = f(2x+3)$, for example, we have to think about how the inputs to the function $g$ relate to the inputs to the function $f$. Suppose we know $f(7) = 12$. What input to $g$ would produce that output? In other words, what value of $x$ will allow $g(x) = f(2x+3) = 12$? We would need $2x+3 = 7$. To solve for $x$, we would first subtract 3, resulting in a horizontal shift, and then divide by 2, causing a horizontal compression.

This format ends up being very difficult to work with, because it is usually much easier to horizontally stretch a graph before shifting. We can work around this by factoring inside the function.

$$f(bx+p) = f(b(x+\frac{p}{b}))$$

Let's work through an example.

$$f(x) = (2x+4)^2$$

We can factor out a 2.

$$f(x) = (2(x+2))^2$$

Now we can more clearly observe a horizontal shift to the left 2 units and a horizontal compression. Factoring in this way allows us to horizontally stretch first and then shift horizontally.

### Combining Transformations

- When combining vertical transformations written in the form $af(x)+k$, first vertically stretch by $a$ and then vertically shift by $k$.
- When combining horizontal transformations written in the form $f(bx+h)$, first horizontally shift by $h$ and then horizontally stretch by $\frac{1}{b}$.
- When combining horizontal transformations written in the form $f(b(x+h))$, first horizontally stretch by $\frac{1}{b}$ and then horizontally shift by $h$.
- Horizontal and vertical transformations are independent. It does not matter whether horizontal or vertical transformations are performed first.

### Example 3.7.20: Finding a Triple Transformation of a Tabular Function

Given Table 3.7.18 for the function $f(x)$, create a table of values for the function $g(x) = 2f(3x)+1$.

Table 3.7.18

| $x$ | 6 | 12 | 18 | 24 |
|---|---|---|---|---|
| $f(x)$ | 10 | 14 | 15 | 17 |

**Solution**

There are three steps to this transformation, and we will work from the inside out. Starting with the horizontal transformations, $f(3x)$ is a horizontal compression by $\frac{1}{3}$, which means we multiply each $x$-value by $\frac{1}{3}$.See Table 3.7.19

Table 3.7.19

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $f(3x)$ | 10 | 14 | 15 | 17 |

Looking now to the vertical transformations, we start with the vertical stretch, which will multiply the output values by 2. We apply this to the previous transformation. See Table 3.7.20

Table 3.7.20

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $2f(3x)$ | 20 | 28 | 30 | 34 |

Finally, we can apply the vertical shift, which will add 1 to all the output values. See Table 3.7.21

Table 3.7.21

| $x$ | 2 | 4 | 6 | 8 |
|---|---|---|---|---|
| $g(x)=2f(3x)+1+1$ | 21 | 29 | 31 | 35 |

## Example 3.7.21: Finding a Triple Transformation of a Graph

Use the graph of $f(x)$ in Figure 3.7.31 to sketch a graph of $k(x)=f\left(\frac{1}{2}x+1\right)-3$ .





Figure 3.7.31: Graph of a half-circle.

To simplify, let's start by factoring out the inside of the function.

$$f\left(\frac{1}{2}x+1\right)-3=f\left(\frac{1}{2}(x+2)\right)-3 \tag{3.7.11}$$

By factoring the inside, we can first horizontally stretch by 2, as indicated by the $\frac{1}{2}$ on the inside of the function. Remember that twice the size of 0 is still 0, so the point $(0,2)$ remains at $(0,2)$ while the point $(2,0)$ will stretch to $(4,0)$. See Figure 3.7.32





Figure 3.7.32: Graph of a vertically stretch half-circle.

Next, we horizontally shift left by 2 units, as indicated by $x+2$. See Figure 3.7.33





Figure 3.7.33: Graph of a vertically stretch and translated half-circle.

Last, we vertically shift down by 3 to complete our sketch, as indicated by the $-3$ on the outside of the function. See Figure 3.7.34





Figure 3.7.34: Graph of a vertically stretch and translated half-circle.

## Key Equations

- Vertical shift $g(x) = f(x) + k$ (up for $k > 0$)
- Horizontal shift $g(x) = f(x - h)$ (right) for $h > 0$
- Vertical reflection $g(x) = -f(x)$
- Horizontal reflection $g(x) = f(-x)$
- Vertical stretch $g(x) = af(x)$ (a>0 )
- Vertical compression $g(x) = af(x)$ (0<a<1)
- Horizontal stretch $g(x) = f(bx)(0 < b < 1)$
- Horizontal compression $g(x) = f(bx)$ (b>1)

## Key Concepts

- A function can be shifted vertically by adding a constant to the output.
- A function can be shifted horizontally by adding a constant to the input.
- Relating the shift to the context of a problem makes it possible to compare and interpret vertical and horizontal shifts.
- Vertical and horizontal shifts are often combined.
- A vertical reflection reflects a graph about the x-axis. A graph can be reflected vertically by multiplying the output by –1.
- A horizontal reflection reflects a graph about the y-axis. A graph can be reflected horizontally by multiplying the input by –1.
- A graph can be reflected both vertically and horizontally. The order in which the reflections are applied does not affect the final graph.
- A function presented in tabular form can also be reflected by multiplying the values in the input and output rows or columns accordingly.
- A function presented as an equation can be reflected by applying transformations one at a time.
- Even functions are symmetric about the y-axis, whereas odd functions are symmetric about the origin.
- Even functions satisfy the condition $f(x) = f(-x)$.
- Odd functions satisfy the condition $f(x) = -f(-x)$.
- A function can be odd, even, or neither.
- A function can be compressed or stretched vertically by multiplying the output by a constant.
- A function can be compressed or stretched horizontally by multiplying the input by a constant.
- The order in which different transformations are applied does affect the final function. Both vertical and horizontal transformations must be applied in the order given. However, a vertical transformation may be combined with a horizontal transformation in any order.

## Glossary

**even function**

a function whose graph is unchanged by horizontal reflection, $f(x) = f(-x)$, and is symmetric about the y-axis

**horizontal compression**
a transformation that compresses a function's graph horizontally, by multiplying the input by a constant b>1

**horizontal reflection**
a transformation that reflects a function's graph across the y-axis by multiplying the input by −1

**horizontal shift**
a transformation that shifts a function's graph left or right by adding a positive or negative constant to the input

**horizontal stretch**
a transformation that stretches a function's graph horizontally by multiplying the input by a constant 0<b<1

**odd function**
a function whose graph is unchanged by combined horizontal and vertical reflection, $f(x) = -f(-x)$, and is symmetric about the origin

**vertical compression**
a function transformation that compresses the function's graph vertically by multiplying the output by a constant 0<a<1

**vertical reflection**
a transformation that reflects a function's graph across the x-axis by multiplying the output by −1

**vertical shift**
a transformation that shifts a function's graph up or down by adding a positive or negative constant to the output

**vertical stretch**
a transformation that stretches a function's graph vertically by multiplying the output by a constant a>1

---

This page titled 3.7: Transformation of Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.5: Transformation of Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.7E: Transformation of Functions (Exercises)

For the following exercises, sketch a graph of the given function.

45. $f(x) = (x-3)^2$
46. $f(x) = (x+4)^3$
47. $f(x) = \sqrt{x}+5$
48. $f(x) = -x^3$
49. $f(x) = \sqrt[3]{-x}$
50. $f(x) = 5\sqrt{-x}-4$
51. $f(x) = 4[|x-2|-6]$
52. $f(x) = -(x+2)^2-1$

For the following exercises, sketch the graph of the function $g$ if the graph of the function $f$ is shown Figure $3.7E.1$.





Figure $3.7E.1$


53. $g(x) = f(x-1)$
54. $g(x) = 3f(x)$

For the following exercises, write the equation for the standard function represented by each of the graphs below.

55.




56.





For the following exercises, determine whether each function below is even, odd, or neither.


57. $f(x) = 3x^4$
58. $g(x) = \sqrt{x}$
59. $h(x) = \frac{1}{x} + 3x$

For the following exercises, analyze the graph and determine whether the graphed function is even, odd, or neither.


60.




61.




62.




This page titled 3.7E: Transformation of Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.5E: Transformation of Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.8: Absolute Value Functions

**Learning Objectives**

- Graph an absolute value function.
- Solve an absolute value equation.

Until the 1920s, the so-called spiral nebulae were believed to be clouds of dust and gas in our own galaxy, some tens of thousands of light years away. Then, astronomer Edwin Hubble proved that these objects are galaxies in their own right, at distances of millions of light years. Today, astronomers can detect galaxies that are billions of light years away. Distances in the universe can be measured in all directions. As such, it is useful to consider distance as an absolute value function. In this section, we will investigate **absolute value functions**.



Figure 3.8.1: Distances in deep space can be measured in all directions. As such, it is useful to consider distance in terms of absolute values. (credit: "s58y"/Flickr)

## Understanding Absolute Value

Recall that in its basic form $f(x) = |x|$, the **absolute value** function, is one of our toolkit functions. The absolute value function is commonly thought of as providing the distance the number is from zero on a number line. Algebraically, for whatever the input value is, the output is the value without regard to sign.

**Absolute Value Function**

The absolute value function can be defined as a piecewise function

$$f(x) = |x| = \begin{cases} x & \text{if } x \geq 0 \\ -x & \text{if } x < 0 \end{cases} \tag{3.8.1}$$

**Example 3.8.1: Determine a Number within a Prescribed Distance**

Describe all values $x$ within or including a distance of 4 from the number 5.

**Solution**

We want the distance between $x$ and 5 to be less than or equal to 4. We can draw a number line, such as the one in , to represent the condition to be satisfied.





Figure 3.8.2: Number line describing the difference of the distance of 4 away from 5.

The distance from $x$ to 5 can be represented using the absolute value as $|x-5|$. We want the values of $x$ that satisfy the condition $|x-5| \leq 4$.

**Analysis**

Note that

$$-4 \leq x-5 \qquad x-5 \leq 4$$
$$1 \leq x \qquad\qquad x \leq 9$$

So $|x-5| \leq 4$ is equivalent to $1 \leq x \leq 9$.

However, mathematicians generally prefer absolute value notation.

**Exercise 3.8.1**

Describe all values $x$ within a distance of 3 from the number 2.

**Answer**

$|x-2| \leq 3$

**Example 3.8.2: Resistance of a Resistor**

Electrical parts, such as resistors and capacitors, come with specified values of their operating parameters: resistance, capacitance, etc. However, due to imprecision in manufacturing, the actual values of these parameters vary somewhat from piece to piece, even when they are supposed to be the same. The best that manufacturers can do is to try to guarantee that the variations will stay within a specified range, often ±1%, ±5%, or ±10%.

Suppose we have a resistor rated at 680 ohms, ±5%. Use the absolute value function to express the range of possible values of the actual resistance.

**Solution**

5% of 680 ohms is 34 ohms. The absolute value of the difference between the actual and nominal resistance should not exceed the stated variability, so, with the resistance $R$ in ohms,

$$|R-680| \leq 34$$

**Exercise 3.8.2**

Students who score within 20 points of 80 will pass a test. Write this as a distance from 80 using absolute value notation.

**Answer**

Using the variable $p$ for passing, $|p-80| \leq 20$

## Graphing an Absolute Value Function

The most significant feature of the absolute value graph is the corner point at which the graph changes direction. This point is shown at the origin in Figure 3.8.3.





Figure 3.8.3: Graph of an absolute function.

Figure 3.8.3 shows the graph of $y = 2|x-3|+4$. The graph of $y = |x|$ has been shifted right 3 units, vertically stretched by a factor of 2, and shifted up 4 units. This means that the corner point is located at $(3, 4)$ for this transformed function.





Figure 3.8.4: Graph of the different types of transformations for an absolute function.

## Example 3.8.3: Writing an Equation for an Absolute Value Function

Write an equation for the function graphed in Figure 3.8.5.





Figure 3.8.5: Graph of an absolute function.

**Solution**

The basic absolute value function changes direction at the origin, so this graph has been shifted to the right 3 units and down 2 units from the basic toolkit function. See Figure 3.8.6.





Figure 3.8.6: Graph of two transformations for an absolute function at $(3, -2)$.

We also notice that the graph appears vertically stretched, because the width of the final graph on a horizontal line is not equal to 2 times the vertical distance from the corner to this line, as it would be for an unstretched absolute value function. Instead, the width is equal to 1 times the vertical distance as shown in Figure 3.8.7.





Figure 3.8.7: Graph of two transformations for an absolute function at $(3, -2)$ and the ratios between the two different transformations.

From this information we can write the equation

$$\begin{aligned} f(x) &= 2|x-3|-2, && \text{treating the stretch as a vertial stretch, or} \\ f(x) &= |2(x-3)|-2, && \text{treating the stretch as a horizontal compression.} \end{aligned}$$

**Analysis**

Note that these equations are algebraically equivalent—the stretch for an absolute value function can be written interchangeably as a vertical or horizontal stretch or compression.

Q & A

If we couldn't observe the stretch of the function from the graphs, could we algebraically determine it?

**Answer**

Yes. If we are unable to determine the stretch based on the width of the graph, we can solve for the stretch factor by putting in a known pair of values for $x$ and $f(x)$.

$$f(x) = a|x-3|-2$$

Now substituting in the point $(1, 2)$

$$2 = a|1-3| - 2$$
$$4 = 2a$$
$$a = 2$$

**Exercise 3.8.3**

Write the equation for the absolute value function that is horizontally shifted left 2 units, is vertically flipped, and vertically shifted up 3 units.

**Answer**

$f(x) = -|x+2| + 3$

**Q & A**

Do the graphs of absolute value functions always intersect the vertical axis? The horizontal axis?

**Answer**

Yes, they always intersect the vertical axis. The graph of an absolute value function will intersect the vertical axis when the input is zero.

No, they do not always intersect the horizontal axis. The graph may or may not intersect the horizontal axis, depending on how the graph has been shifted and reflected. It is possible for the absolute value function to intersect the horizontal axis at zero, one, or two points (Figure 3.8.8).





Figure 3.8.8: (a) The absolute value function does not intersect the horizontal axis. (b) The absolute value function intersects the horizontal axis at one point. (c) The absolute value function intersects the horizontal axis at two points.

## Solving an Absolute Value Equation

Now that we can graph an absolute value function, we will learn how to solve an absolute value equation. To solve an equation such as $8 = |2x-6|$, we notice that the absolute value will be equal to 8 if the quantity inside the absolute value is 8 or -8. This leads to two different equations we can solve independently.

$$2x - 6 = 8 \quad \text{or} \quad 2x - 6 = -8$$
$$2x = 14 \qquad 2x = -2$$
$$x = 7 \qquad x = -1$$

Knowing how to solve problems involving absolute value functions is useful. For example, we may need to identify numbers or points on a line that are at a specified distance from a given reference point.

An **absolute value equation** is an equation in which the unknown variable appears in absolute value bars. For example,

$$|x| = 4,$$
$$|2x-1| = 3,$$
$$|5x+2| - 4 = 9.$$

### Solutions to Absolute Value Equations

For real numbers $A$ and $B$, an equation of the form $|A| = B$, with $B \geq 0$, will have solutions when $A = B$ or $A = -B$. If $B < 0$, the equation $|A| = B$ has no solution.

### How To ...

Given the formula for an absolute value function, find the horizontal intercepts of its graph.

1. Isolate the absolute value term.
2. Use $|A| = B$ to write $A = B$ or $-A = B$, assuming $B > 0$.
3. Solve for $x$.

### Example 3.8.4: Finding the Zeros of an Absolute Value Function

For the function $f(x) = |4x+1| - 7$, find the values of $x$ such that $f(x) = 0$.

**Solution**

$$\begin{aligned} 0 &= |4x+1| - 7 && && \text{Substitute 0 for f(x).} \\ 7 &= |4x+1| && && \text{Isolate the absolute value on one side of the equation.} \\ 7 &= 4x+1 && \text{or } -7 = 4x+1 && \text{Break into two separate equations and solve.} \\ 6 &= 4x && -8 = 4x && \\ x &= \frac{6}{4} = 1.5 && x = \frac{-8}{4} = -2 && \end{aligned}$$

The function outputs 0 when $x = 1.5$ or $x = -2$ (Figure 3.8.9).





Figure 3.8.9: Graph of an absolute function with x-intercepts at -2 and 1.5.

### Exercise 3.8.4

For the function $f(x) = |2x-1| - 3$, find the values of $x$ such that $f(x) = 0$.

**Solution**

$x = -1$ or $x = 2$

**Q & A**

Should we always expect two answers when solving $|A| = B$?

**Answer**

No. We may find one, two, or even no answers. For example, there is no solution to $2 + |3x - 5| = 1$.

**How To ...**

Given an absolute value equation, solve it.

1. Isolate the absolute value term.
2. Use $|A| = B$ to write $A = B$ or $A = -B$.
3. Solve for $x$.

**Example 3.8.5: Solving an Absolute Value Equation**

Solve $1 = 4|x - 2| + 2$.

**Solution**

Isolating the absolute value on one side of the equation gives the following.

$$\begin{aligned} 1 &= 4|x-2|+2 \\ -1 &= 4|x-2| \\ -\frac{1}{4} &= |x-2| \end{aligned}$$

The absolute value always returns a positive value, so it is impossible for the absolute value to equal a negative value. At this point, we notice that this equation has no solutions.

**Q & A**

In Example 3.8.5, if $f(x) = 1$ and $g(x) = 4|x - 2| + 2$ were graphed on the same set of axes, would the graphs intersect?

**Answer**

No. The graphs of $f$ and $g$ would not intersect, as shown in Figure 3.8.10. This confirms, graphically, that the equation $1 = 4|x - 2| + 2$ has no solution.





Figure 3.8.10: Graph of $g(x) = 4|x - 2| + 2$ and $f(x) = 1$.

Find where the graph of the function $f(x) = -|x+2|+3$ intersects the horizontal and vertical axes.

$f(0) = 1$, so the graph intersects the vertical axis at $(0, 1)$. $f(x) = 0$ when $x = -5$ and $x = 1$ so the graph intersects the horizontal axis at $(-5, 0)$ and $(1, 0)$.

## Solving an Absolute Value Inequality

Absolute value equations may not always involve equalities. Instead, we may need to solve an equation within a range of values. We would use an **absolute value inequality** to solve such an equation. An absolute value inequality is an equation of the form

$$|A| < B,\ |A| \leq B, |A| > B,$$

or

$$|A| \geq B,$$

where an expression $A$ (and possibly but not usually $B$) depends on a variable $x$. Solving the inequality means finding the set of all $x$ that satisfy the inequality. Usually this set will be an interval or the union of two intervals.

There are two basic approaches to solving absolute value inequalities: graphical and algebraic. The advantage of the graphical approach is we can read the solution by interpreting the graphs of two functions. The advantage of the algebraic approach is it yields solutions that may be difficult to read from the graph.

For example, we know that all numbers within 200 units of 0 may be expressed as

$$|x| < 200$$

or

$$-200 < x < 200$$

Suppose we want to know all possible returns on an investment if we could earn some amount of money within \$200 of \$600. We can solve algebraically for the set of values $x$ such that the distance between $x$ and 600 is less than 200. We represent the distance between $x$ and 600 as $|x - 600|$.

$$|x - 600| < 200 \tag{3.8.2}$$

or

$$-200 < x - 600 < 200 \tag{3.8.3}$$

$$-200 + 600 < x - 600 + 600 < 200 + 600$$

$$400 < x < 800$$

This means our returns would be between \$400 and \$800.

Sometimes an absolute value inequality problem will be presented to us in terms of a shifted and/or stretched or compressed absolute value function, where we must determine for which values of the input the function's output will be negative or positive.

**How To ...**

Given an absolute value inequality of the form $|x - A| \leq B$ for real numbers $a$ and $b$ where $b$ is positive, solve the absolute value inequality algebraically.

1. Find boundary points by solving $|x - A| = B$.
2. Test intervals created by the boundary points to determine where $|x - A| \leq B$.
3. Write the interval or union of intervals satisfying the inequality in interval, inequality, or set-builder notation.

**Example 3.8.6: Solving an Absolute Value Inequality**

Solve $|x - 5| \leq 4$.

**Solution**

With both approaches, we will need to know first where the corresponding equality is true. In this case we first will find where $|x-5|=4$. We do this because the absolute value is a function with no breaks, so the only way the function values can switch from being less than 4 to being greater than 4 is by passing through where the values equal 4. Solve $|x-5|=4$.

$$\begin{aligned} x-5 &= 4 \quad \text{or} \quad x=9 \\ x-5 &= -4 \quad\quad\;\; x=1 \end{aligned}$$

After determining that the absolute value is equal to 4 at $x=1$ and $x=9$, we know the graph can change only from being less than 4 to greater than 4 at these values. This divides the number line up into three intervals:

$$x<1,\ 1<x<9, \text{ and } x>9.$$

To determine when the function is less than 4, we could choose a value in each interval and see if the output is less than or greater than 4, as shown in Table 3.8.1.

Table 3.8.1

| Interval test $x$ | $f(x)$ | $<4$ or $>4$ | |
|---|---|---|---|
| $x<1$ | 0 | $\|0-5\|=5$ | Greater than |
| $1<x<9$ | 6 | $\|6-5\|=1$ | Less than |
| $x>9$ | 11 | $\|11-5\|=6$ | Greater than |

Because $1\leq x\leq 9$ is the only interval in which the output at the test value is less than 4, we can conclude that the solution to $|x-5|\leq 4$ is $1\leq x\leq 9$, or $[1,9]$.

To use a graph, we can sketch the function $f(x)=|x-5|$. To help us see where the outputs are 4, the line $g(x)=4$ could also be sketched as in Figure 3.8.11.





Figure 3.8.11: Graph to find the points satisfying an absolute value inequality.

We can see the following:

- The output values of the absolute value are equal to 4 at $x=1$ and $x=9$.
- The graph of $f$ is below the graph of $g$ on $1<x<9$. This means the output values of $f(x)$ are less than the output values of $g(x)$.
- The absolute value is less than or equal to 4 between these two points, when $1\leq x\leq 9$. In interval notation, this would be the interval $[1,9]$.

**Analysis**

For absolute value inequalities,

$$\begin{aligned} |x-A|<C, &\qquad |x-A|>C, \\ -C<x-A<C, &\quad x-A<-C \text{ or } x-A>C. \end{aligned}$$

The $<$ or $>$ symbol may be replaced by $\leq$ or $\geq$.

So, for this example, we could use this alternative approach.

$$
\begin{aligned}
|x-5| &\leq 4 \\
-4 \leq x-5 &\leq 4 && \text{Rewrite by removing the absolute value bars.} \\
-4+5 \leq x-5+5 &\leq 4+5 && \text{Isolate the x.} \\
1 \leq x &\leq 9
\end{aligned}
$$

**Exercise 3.8.5**

Solve $|x+2| \leq 6$.

**Answer**

$-8 \leq x \leq 4$

**How To ...**

Given an absolute value function, solve for the set of inputs where the output is positive (or negative).

1. Set the function equal to zero, and solve for the boundary points of the solution set.
2. Use test points or a graph to determine where the function's output is positive or negative.

**Example 3.8.7: Using a Graphical Approach to Solve Absolute Value Inequalities**

Given the function $f(x) = -\frac{1}{2}|4x-5|+3$, determine the $x$-values for which the function values are negative.

**Solution**

We are trying to determine where $f(x) < 0$, which is when $-\frac{1}{2}|4x-5|+3 < 0$. We begin by isolating the absolute value.

$$
\begin{aligned}
-\frac{1}{2}|4x-5| &< -3 && \text{Multiply both sides by } -2, \text{ and reverse the inequality.} \\
|4x-5| &> 6
\end{aligned}
$$

Next we solve for the equality $|4x-5| = 6$.

$$
\begin{aligned}
4x-5 &= 6 \qquad 4x-5 = -6 \\
4x-6 &= 6
\end{aligned}
$$

or

$$
\begin{aligned}
4x &= -1 \\
x &= \frac{11}{4} \qquad x = -\frac{1}{4}
\end{aligned}
$$

Now, we can examine the graph of $f$ to observe where the output is negative. We will observe where the branches are below the $x$-axis. Notice that it is not even important exactly what the graph looks like, as long as we know that it crosses the horizontal axis at $x = -\frac{1}{4}$ and $x = \frac{11}{4}$ and that the graph has been reflected vertically. See Figure 3.8.12





Figure 3.8.12: Graph of an absolute function with x-intercepts at -0.25 and 2.75.]

We observe that the graph of the function is below the $x$-axis left of $x = -\frac{1}{4}$ and right of $x = \frac{11}{4}$. This means the function values are negative to the left of the first horizontal intercept at $x = -\frac{1}{4}$, and negative to the right of the second intercept at $x = \frac{11}{4}$. This gives us the solution to the inequality.

$$x < -\frac{1}{4} \text{ or } x > 1\frac{1}{4}$$

In interval notation, this would be $(-\infty, -0.25) \cup (2.75, \infty)$.

**Exercise 3.8.6**

Solve $-2|k-4| \leq -6$.

**Answer**

$k \leq 1$ or $k \geq 7$; in interval notation, this would be $(-\infty, 1] \cup [7, \infty)$

## Key Concepts

- The absolute value function is commonly used to measure distances between points.
- Applied problems, such as ranges of possible values, can also be solved using the absolute value function.
- The graph of the absolute value function resembles a letter V. It has a corner point at which the graph changes direction.
- In an absolute value equation, an unknown variable is the input of an absolute value function.
- If the absolute value of an expression is set equal to a positive number, expect two solutions for the unknown variable.
- An absolute value equation may have one solution, two solutions, or no solutions.
- An absolute value inequality is similar to an absolute value equation but takes the form | A |<B, | A |≤B, | A |>B, or | A |≥B.It can be solved by determining the boundaries of the solution set and then testing which segments are in the set.
- Absolute value inequalities can also be solved graphically.

## Glossary

**absolute value equation**
an equation of the form $|A| = B$, with $B \geq 0$; it will have solutions when $A = B$ or $A = -B$

**absolute value inequality**
a relationship in the form $|A| < B$, $|A| \leq B$, $|A| > B$, or $|A| \geq B$


This page titled 3.8: Absolute Value Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.6: Absolute Value Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.


# 3.8E: Absolute Value Functions (Exercises)

\text { For the following exercises, write an equation for the transformation of } f(x)=|x| .


63.




64.




65.




For the following exercises, graph the absolute value function.

66. $f(x)=|x-5|$
67. $f(x)=-|x-3|$
68. $f(x)=|\ 2x-4$

This page titled 3.8E: Absolute Value Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.6E: Absolute Value Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.9: Inverse Functions

**Learning Objectives**

- Verify inverse functions.
- Determine the domain and range of an inverse function, and restrict the domain of a function to make it one-to-one.
- Find or evaluate the inverse of a function.
- Use the graph of a one-to-one function to graph its inverse function on the same axes.

A reversible heat pump is a climate-control system that is an air conditioner and a heater in a single device. Operated in one direction, it pumps heat out of a house to provide cooling. Operating in reverse, it pumps heat into the building from the outside, even in cool weather, to provide heating. As a heater, a heat pump is several times more efficient than conventional electrical resistance heating.

If some physical machines can run in two directions, we might ask whether some of the function "machines" we have been studying can also run backwards. Figure 3.9.1 provides a visual representation of this question. In this section, we will consider the reverse nature of functions.





***Figure 3.9.1:*** *Can a function "machine" operate in reverse?*

## Verifying That Two Functions Are Inverse Functions

Suppose a fashion designer traveling to Milan for a fashion show wants to know what the temperature will be. He is not familiar with the **Celsius** scale. To get an idea of how temperature measurements are related, he asks his assistant, Betty, to convert 75 degrees **Fahrenheit** to degrees Celsius. She finds the formula

$$C = \frac{5}{9}(F - 32) \tag{3.9.1}$$

and substitutes 75 for $F$ to calculate

$$\frac{5}{9}(75 - 32) \approx 24^{\circ} \tag{3.9.2}$$

Knowing that a comfortable 75 degrees Fahrenheit is about 24 degrees Celsius, he sends his assistant the week's weather forecast from Figure 3.9.2 for Milan, and asks her to convert all of the temperatures to degrees Fahrenheit.





Figure 3.9.2: A forecast of Monday's through Thursday's weather.

At first, Betty considers using the formula she has already found to complete the conversions. After all, she knows her algebra, and can easily solve the equation for $F$ after substituting a value for $C$. For example, to convert 26 degrees Celsius, she could write

$$26 = \frac{5}{9}(F-32) \tag{3.9.3}$$

$$26 \cdot \frac{9}{5} = F-32 \tag{3.9.4}$$

$$F = 26 \cdot \frac{9}{5} + 32 \approx 79 \tag{3.9.5}$$

After considering this option for a moment, however, she realizes that solving the equation for each of the temperatures will be awfully tedious. She realizes that since evaluation is easier than solving, it would be much more convenient to have a different formula, one that takes the Celsius temperature and outputs the Fahrenheit temperature.

The formula for which Betty is searching corresponds to the idea of an **inverse function**, which is a function for which the input of the original function becomes the output of the inverse function and the output of the original function becomes the input of the inverse function.

Given a function $f(x)$, we represent its inverse as $f^{-1}(x)$, read as "$f$ inverse of $x$." The raised $-1$ is part of the notation. It is not an exponent; it does not imply a power of $-1$ . In other words, $f^{-1}(x)$ does not mean $\frac{1}{f(x)}$ because $\frac{1}{f(x)}$ is the reciprocal of $f$ and not the inverse.

The "exponent-like" notation comes from an analogy between function composition and multiplication: just as $a^{-1}a = 1$ (1 is the identity element for multiplication) for any nonzero number $a$, so $f^{-1} \circ f$ equals the identity function, that is,

$$(f^{-1} \circ f)(x) = f^{-1}(f(x)) = f^{-1}(y) = x \tag{3.9.6}$$

This holds for all $x$ in the domain of $f$. Informally, this means that inverse functions "undo" each other. However, just as zero does not have a **reciprocal**, some functions do not have inverses.

Given a function $f(x)$, we can verify whether some other function $g(x)$ is the inverse of $f(x)$ by checking whether either $g(f(x)) = x$ or $f(g(x)) = x$ is true. We can test whichever equation is more convenient to work with because they are logically equivalent (that is, if one is true, then so is the other.)

For example, $y = 4x$ and $y = \frac{1}{4}x$ are inverse functions.

$$(f^{-1} \circ f)(x) = f^{-1}(4x) = \frac{1}{4}(4x) = x \tag{3.9.7}$$

and

$$(f \circ f^{-1})(x) = f\left(\frac{1}{4}x\right) = 4\left(\frac{1}{4}x\right) = x \tag{3.9.8}$$

A few coordinate pairs from the graph of the function $y = 4x$ are $(-2,-8)$, $(0,0)$, and $(2,8)$. A few coordinate pairs from the graph of the function $y = \frac{1}{4}x$ are $(-8,-2)$, $(0,0)$, and $(8,2)$. If we interchange the input and output of each coordinate pair of a function, the interchanged coordinate pairs would appear on the graph of the inverse function.

**Definition: Inverse Function**

For any **one-to-one function** $f(x) = y$, a function $f^{-1}(x)$ is an **inverse function** of $f$ if $f^{-1}(y) = x$. This can also be written as $f^{-1}(f(x)) = x$ for all $x$ in the domain of $f$. It also follows that $f(f^{-1}(x)) = x$ for all $x$ in the domain of $f^{-1}$ if $f^{-1}$ is the inverse of $f$.

The notation $f^{-1}$ is read "$f$ inverse." Like any other function, we can use any variable name as the input for $f^{-1}$, so we will often write $f^{-1}(x)$, which we read as "$f$ inverse of $x$." Keep in mind that

$$f^{-1}(x) \neq \frac{1}{f(x)} \tag{3.9.9}$$

and not all functions have inverses.

### Example 3.9.1: Identifying an Inverse Function for a Given Input-Output Pair

If for a particular one-to-one function $f(2)=4$ and $f(5)=12$, what are the corresponding input and output values for the inverse function?

**Solution**

The inverse function reverses the input and output quantities, so if

$$\begin{aligned} f(2)=4, \text{ then } f^{-1}(4)=2; \\ f(5)=12, \text{ then } f^{-1}(12)=5 \end{aligned} \tag{3.9.10}$$

.

Alternatively, if we want to name the inverse function $g$, then $g(4)=2$ and $g(12)=5$.

**Analysis**

Notice that if we show the coordinate pairs in a table form, the input and output are clearly reversed. See Table 3.9.1.

Table 3.9.1

| $(x, f(x))$ | $(x, g(x))$ |
|---|---|
| $(2, 4)$ | $(4, 2)$ |
| $(5, 12)$ | $(12, 5)$ |

### Exercise 3.9.1

Given that $h^{-1}(6)=2$, what are the corresponding input and output values of the original function $h$?

**Answer**

$h(2)=6$

### How To: Given two functions $f(x)$ and $g(x)$, test whether the functions are inverses of each other.

1. Determine whether $f(g(x))=x$ or $g(f(x))=x$.
2. If both statements are true, then $g=f^{-1}$ and $f=g^{-1}$. If either statement is false, then both are false, and $g \neq f^{-1}$ and $f \neq g^{-1}$.

### Example 3.9.2: Testing Inverse Relationships Algebraically

If $f(x)=\frac{1}{x+2}$ and $g(x)=\frac{1}{x}-2$, is $g=f^{-1}$?

**Solution**

$$g(f(x)) = \frac{1}{(\frac{1}{x+2})-2} \tag{3.9.11}$$

$$= x+2-2 \tag{3.9.12}$$

$$= x \tag{3.9.13}$$

so

$$g=f^{-1} \text{ and } f=g^{-1} \tag{3.9.14}$$

This is enough to answer yes to the question, but we can also verify the other formula.

$$f(g(x)) = \frac{1}{\frac{1}{x} - 2 + 2} \tag{3.9.15}$$

$$= \frac{1}{\frac{1}{x}} \tag{3.9.16}$$

$$= x \tag{3.9.17}$$

**Analysis**

Notice the inverse operations are in reverse order of the operations from the original function.

**Exercise 3.9.2**

If $f(x) = x^3 - 4$ and $g(x) = \sqrt[3]{x+4}$, is $g = f^{-1}$?

**Answer**

Yes

**Example 3.9.3: Determining Inverse Relationships for Power Functions**

If $f(x) = x^3$ (the cube function) and $g(x) = \frac{1}{3}x$, is $g = f^{-1}$?

**Solution**

$$f(g(x)) = \frac{x^3}{27} \neq x \tag{3.9.18}$$

No, the functions are not inverses.

**Analysis**

The correct inverse to the cube is, of course, the cube root $\sqrt[3]{x} = x^{\frac{1}{3}}$, that is, the one-third is an exponent, not a multiplier.

**Exercise 3.9.3**

If $f(x) = (x-1)^3$ and $g(x) = \sqrt[3]{x} + 1$, is $g = f^{-1}$?

**Answer**

Yes

## Finding Domain and Range of Inverse Functions

The outputs of the function $f$ are the inputs to $f^{-1}$, so the range of $f$ is also the domain of $f^{-1}$. Likewise, because the inputs to $f$ are the outputs of $f^{-1}$, the domain of $f$ is the range of $f^{-1}$. We can visualize the situation as in Figure 3.9.3.





***Figure 3.9.3:*** *Domain and range of a function and its inverse.*

When a function has no inverse function, it is possible to create a new function where that new function on a limited domain does have an inverse function. For example, the inverse of $f(x) = \sqrt{x}$ is $f^{-1}(x) = x^2$, because a square "undoes" a square root; but the square is only the inverse of the square root on the domain $[0, \infty)$, since that is the range of $f(x) = \sqrt{x}$.

We can look at this problem from the other side, starting with the square (toolkit quadratic) function $f(x) = x^2$. If we want to construct an inverse to this function, we run into a problem, because for every given output of the quadratic function, there are two corresponding inputs (except when the input is 0). For example, the output 9 from the quadratic function corresponds to the inputs

3 and –3. But an output from a function is an input to its inverse; if this inverse input corresponds to more than one inverse output (input of the original function), then the "inverse" is not a function at all! To put it differently, the quadratic function is not a one-to-one function; it fails the horizontal line test, so it does not have an inverse function. In order for a function to have an inverse, it must be a one-to-one function.

In many cases, if a function is not one-to-one, we can still restrict the function to a part of its domain on which it is one-to-one. For example, we can make a restricted version of the square function $f(x) = x^2$ with its range limited to $[0, \infty)$, which is a one-to-one function (it passes the horizontal line test) and which has an inverse (the square-root function).

If $f(x) = (x-1)^2$ on $[1, \infty)$, then the inverse function is $f^{-1}(x) = \sqrt{x} + 1$ .

- The domain of $f$ = range of $f^{-1} = [1, \infty)$.
- The domain of $f^{-1}$ = range of $f = [0, \infty)$.

**Is it possible for a function to have more than one inverse?**

*No. If two supposedly different functions, say, g and h, both meet the definition of being inverses of another function $f$, then you can prove that $g = h$. We have just seen that some functions only have inverses if we restrict the domain of the original function. In these cases, there may be more than one way to restrict the domain, leading to different inverses. However, on any one domain, the original function still has only one unique inverse.*

**Note: Domain and Range of Inverse Functions**

The range of a function $f(x)$ is the domain of the inverse function $f^{-1}(x)$.

The domain of $f(x)$ is the range of $f^{-1}(x)$.

**How To: Given a function, find the domain and range of its inverse.**

1. If the function is one-to-one, write the range of the original function as the domain of the inverse, and write the domain of the original function as the range of the inverse.
2. If the domain of the original function needs to be restricted to make it one-to-one, then this restricted domain becomes the range of the inverse function.

**Example 3.9.4: Finding the Inverses of Toolkit Functions**

Identify which of the toolkit functions besides the quadratic function are not one-to-one, and find a restricted domain on which each function is one-to-one, if any. The toolkit functions are reviewed in Table 3.9.2. We restrict the domain in such a fashion that the function assumes all y-values exactly once.

Table 3.9.2

| Constant | Identity | Quadratic | Cubic | Reciprocal |
|---|---|---|---|---|
| $f(x) = c$ | $f(x) = x$ | $f(x) = x^2$ | $f(x) = x^3$ | $f(x) = \frac{1}{x}$ |
| Reciprocal squared | Cube Root | Square Root | Absolute Value | |
| $f(x) = \frac{1}{x^2}$ | $f(x) = \sqrt[3]{x}$ | $f(x) = \sqrt{x}$ | $f(x) = \lvert x \rvert$ | |

**Solution**

The constant function is not one-to-one, and there is no domain (except a single point) on which it could be one-to-one, so the constant function has no meaningful inverse.

The absolute value function can be restricted to the domain $[0, \infty)$,where it is equal to the identity function.

The reciprocal-squared function can be restricted to the domain $(0, \infty)$.

**Analysis**

We can see that these functions (if unrestricted) are not one-to-one by looking at their graphs, shown in Figure 3.9.4. They both would fail the horizontal line test. However, if a function is restricted to a certain domain so that it passes the horizontal

line test, then in that restricted domain, it can have an inverse.





***Figure* 3.9.4:** *(a) Absolute value (b) Reciprocal squared*

**3.9.4:** The domain of function $f$ is $(1, \infty)$ and the range of function $f$ is $(-\infty, -2)$. Find the domain and range of the inverse function.

**Solution**

The domain of function $f^{-1}$ is $(-\infty, -2)$ and the range of function $f^{-1}$ is $(1, \infty)$.

## Finding and Evaluating Inverse Functions

Once we have a one-to-one function, we can evaluate its inverse at specific inverse function inputs or construct a complete representation of the inverse function in many cases.

### Inverting Tabular Functions

Suppose we want to find the inverse of a function represented in table form. Remember that the domain of a function is the range of the inverse and the range of the function is the domain of the inverse. So we need to interchange the domain and range.

Each row (or column) of inputs becomes the row (or column) of outputs for the inverse function. Similarly, each row (or column) of outputs becomes the row (or column) of inputs for the inverse function.

**Example 3.9.5: Interpreting the Inverse of a Tabular Function**

A function $f(t)$ is given in Table 3.9.3, showing distance in miles that a car has traveled in $t$ minutes. Find and interpret $f^{-1}(70)$

Table 3.9.3

| $t$ (minutes) | 30 | 50 | 70 | 90 |
|---|---|---|---|---|
| $f(t)$ (miles) | 20 | 40 | 60 | 70 |

The inverse function takes an output of $f$ and returns an input for $f$. So in the expression $f^{-1}(70)$, 70 is an output value of the original function, representing 70 miles. The inverse will return the corresponding input of the original function $f$, 90 minutes, so $f^{-1}(70) = 90$. The interpretation of this is that, to drive 70 miles, it took 90 minutes.

Alternatively, recall that the definition of the inverse was that if $f(a) = b$, then $f^{-1}(b) = a$. By this definition, if we are given $f^{-1}(70) = a$, then we are looking for a value $a$ so that $f(a) = 70$. In this case, we are looking for a $t$ so that $f(t) = 70$, which is when $t = 90$.

## Exercise 3.9.5

Using Table 3.9.4, find and interpret (a) $f(60)$,and (b) $f^{-1}(60)$.

Table 3.9.4

| $t$ (minutes) | 30 | 50 | 60 | 70 | 90 |
|---|---|---|---|---|---|
| $f(t)$ (miles) | 20 | 40 | 50 | 60 | 70 |

**Answer**

$f(60) = 50$. In 60 minutes, 50 miles are traveled.
$f^{-1}(60) = 70$. To travel 60 miles, it will take 70 minutes.

### Evaluating the Inverse of a Function, Given a Graph of the Original Function

We saw in **Functions and Function Notation** that the domain of a function can be read by observing the horizontal extent of its graph. We find the domain of the inverse function by observing the *vertical* extent of the graph of the original function, because this corresponds to the horizontal extent of the inverse function. Similarly, we find the range of the inverse function by observing the *horizontal* extent of the graph of the original function, as this is the vertical extent of the inverse function. If we want to evaluate an inverse function, we find its input within its domain, which is all or part of the vertical axis of the original function's graph.

**How To: Given the graph of a function, evaluate its inverse at specific points.**

1. Find the desired input on the y-axis of the given graph.
2. Read the inverse function's output from the x-axis of the given graph.

## Example 3.9.6: Evaluating a Function and Its Inverse from a Graph at Specific Points

A function $g(x)$ is given in Figure 3.9.5. Find $g(3)$ and $g^{-1}(3)$.
.





Figure 3.9.5: Graph of $g(x)$

**Solution**

To evaluate $g(3)$, we find 3 on the x-axis and find the corresponding output value on the y-axis. The point $(3, 1)$ tells us that $g(3) = 1$.

To evaluate $g^{-1}(3)$, recall that by definition $g^{-1}(3)$ means the value of $x$ for which $g(x) = 3$. By looking for the output value 3 on the vertical axis, we find the point $(5, 3)$ on the graph, which means $g(5) = 3$, so by definition, $g^{-1}(3) = 5$. See Figure 3.9.6.





Figure 3.9.6: Graph of $g(x)$.

**Exercise 3.9.6**

Using the graph in Figure 3.9.6, (a) find $g^{-1}(1)$,and (b) estimate $g^{-1}(4)$.

**Answer a**

3

**Answer b**

5.6

## Finding Inverses of Functions Represented by Formulas

Sometimes we will need to know an inverse function for all elements of its domain, not just a few. If the original function is given as a formula— for example, $y$ as a function of $x$— we can often find the inverse function by solving to obtain $x$ as a function of $y$.

**How To: Given a function represented by a formula, find the inverse.**

1. Make sure $f$ is a one-to-one function.
2. Solve for $x$
3. Interchange $x$ and $y$.

**Example 3.9.7: Inverting the Fahrenheit-to-Celsius Function**

Find a formula for the inverse function that gives Fahrenheit temperature as a function of Celsius temperature.

$$C = \frac{5}{9}(F - 32) \tag{3.9.19}$$

**Solution**

$$C = \frac{5}{9}(F - 32) \tag{3.9.20}$$

$$C \cdot \frac{9}{5} = F - 32 \tag{3.9.21}$$

$$F = \frac{9}{5}C + 32 \tag{3.9.22}$$

By solving in general, we have uncovered the inverse function. If

$$C = h(F) = \frac{5}{9}(F - 32) \tag{3.9.23}$$

,

then

$$F = h^{-1}(C) = \frac{9}{5}C + 32. \tag{3.9.24}$$

In this case, we introduced a function $h$ to represent the conversion because the input and output variables are descriptive, and writing $C^{-1}$ could get confusing.

### Exercise 3.9.7

Solve for $x$ in terms of $y$ given $y = \frac{1}{3}(x-5)$

**Answer**

$x = 3y+5$

### Example 3.9.8: Solving to Find an Inverse Function

Find the inverse of the function $f(x) = \frac{2}{x-3}+4$.

**Solution**

$$y = \frac{2}{x-3+4} \quad \text{Set up an equation.} \tag{3.9.25}$$

$$y-4 = \frac{2}{x-3} \quad \text{Subtract 4 from both sides.} \tag{3.9.26}$$

$$x-3 = \frac{2}{y-4} \quad \text{Multiply both sides by x−3 and divide by y−4.} \tag{3.9.27}$$

$$x = \frac{2}{y-4}+3 \quad \text{Add 3 to both sides.} \tag{3.9.28}$$

So $f^{-1}(y) = \frac{2}{y-4}+3$ or $f^{-1}(x) = \frac{2}{x-4}+3$.

**Analysis**

The domain and range of $f$ exclude the values 3 and 4, respectively. $f$ and $f^{-1}$ are equal at two points but are not the same function, as we can see by creating Table 3.9.5.

Table 3.9.5

| $x$ | 1 | 2 | 5 | $f^{-1}(y)$ |
|---|---|---|---|---|
| $f(x)$ | 3 | 2 | 5 | $y$ |

### Example 3.9.9: Solving to Find an Inverse with Radicals

Find the inverse of the function $f(x) = 2+\sqrt{x-4}$.

**Solution**

$$y = 2+\sqrt{x-4} \tag{3.9.29}$$

$$(y-2)^2 = x-4 \tag{3.9.30}$$

$$x = (y-2)^2+4 \tag{3.9.31}$$

So $f^{-1}(x) = (x-2)^2+4$.

The domain of $f$ is $[4,\infty)$. Notice that the range of $f$ is $[2,\infty)$, so this means that the domain of the inverse function $f^{-1}$ is also $[2,\infty)$

**Analysis**

The formula we found for $f^{-1}(x)$ looks like it would be valid for all real $x$. However, $f^{-1}$ itself must have an inverse (namely, $f$) so we have to restrict the domain of $f^{-1}$ to $[2,\infty)$ in order to make $f^{-1}$ a one-to-one function. This domain of $f^{-1}$ is exactly the range of $f$.

**Exercise 3.9.8**

What is the inverse of the function $f(x) = 2 - \sqrt{x}$ ? State the domains of both the function and the inverse function.

**Answer**

$f^{-1}(x) = (2-x)^2$ ; domain of $f$: $[0, \infty)$; domain of $f^{-1}$: $(-\infty, 2]$

## Finding Inverse Functions and Their Graphs

Now that we can find the inverse of a function, we will explore the graphs of functions and their inverses. Let us return to the quadratic function $f(x) = x^2$ restricted to the domain $[0, \infty)$, on which this function is one-to-one, and graph it as in Figure 3.9.7.





***Figure 3.9.7:*** *Quadratic function with domain restricted to* $[0, \infty)$.

**Restricting the domain** to $[0, \infty)$ makes the function one-to-one (it will obviously pass the horizontal line test), so it has an inverse on this restricted domain.

We already know that the inverse of the toolkit quadratic function is the square root function, that is, $f^{-1}(x) = \sqrt{x}$. What happens if we graph both $f$ and $f^{-1}$ on the same set of axes, using the x-axis for the input to both $f$ and $f^{-1}$?

We notice a distinct relationship: The graph of $f^{-1}(x)$ is the graph of $f(x)$ reflected about the diagonal line $y = x$, which we will call the identity line, shown in Figure 3.9.8.





***Figure 3.9.8:*** *Square and square-root functions on the non-negative domain*

This relationship will be observed for all one-to-one functions, because it is a result of the function and its inverse swapping inputs and outputs. This is equivalent to interchanging the roles of the vertical and horizontal axes.

**Example 3.9.10: Finding the Inverse of a Function Using Reflection about the Identity Line**

Given the graph of $f(x)$ in Figure 3.9.9, sketch a graph of $f^{-1}(x)$.





Figure 3.9.9: Graph of $f^(-1)(x)$.

This is a one-to-one function, so we will be able to sketch an inverse. Note that the graph shown has an apparent domain of $(0, \infty)$ and range of $(-\infty, \infty)$, so the inverse will have a domain of $(-\infty, \infty)$ and range of $(0, \infty)$.

If we reflect this graph over the line $y = x$, the point $(1, 0)$ reflects to $(0, 1)$ and the point $(4, 2)$ reflects to $(2, 4)$. Sketching the inverse on the same axes as the original graph gives Figure 3.9.10.





Figure 3.9.10: The function and its inverse, showing reflection about the identity line

## Exercise 3.9.1

Draw graphs of the functions $f$ and $f^{-1}$ from Example 3.9.8.

**Answer**





Figure 3.9.11: Graph of $f(x)$ and $f^(-1)(x)$.

**Is there any function that is equal to its own inverse?**

*Yes. If $f = f^{-1}$, then $f(f(x)) = x$, and we can think of several functions that have this property. The identity function does, and so does the reciprocal function, because*

$$\frac{1}{\frac{1}{x}} = x \tag{3.9.32}$$

*Any function $f(x) = c - x$, where $c$ is a constant, is also equal to its own inverse.*

## Key Concepts

- If $g(x)$ is the inverse of $f(x)$, then $g(f(x)) = f(g(x)) = x$.
- Each of the toolkit functions has an inverse.
- For a function to have an inverse, it must be one-to-one (pass the horizontal line test).
- A function that is not one-to-one over its entire domain may be one-to-one on part of its domain.
- For a tabular function, exchange the input and output rows to obtain the inverse.
- The inverse of a function can be determined at specific points on its graph.
- To find the inverse of a formula, solve the equation $y = f(x)$ for $x$ as a function of $y$. Then exchange the labels $x$ and $y$.
- The graph of an inverse function is the reflection of the graph of the original function across the line $y = x$.

This page titled 3.9: Inverse Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **1.7: Inverse Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 3.9E: Inverse Functions (Exercises)

For the following exercises, find $f^{-1}(x)$ for each function.

69. $f(x) = 9 + 10x$
70. $f(x) = \frac{x}{x+2}$

For the following exercise, find a domain on which the function $f$ is one-to-one and non-decreasing. Write the domain in interval notation. Then find the inverse of $f$ restricted to that domain.

71. $f(x) = x^2 + 1$
72. Given $f(x) = x^3 - 5$ and $g(x) = \sqrt[3]{x+5}$ :
    a. Find $f(g(x))$ and $g(f(x))$.
    b. What does the answer tell us about the relationship between $f(x)$ and $g(x)$ ?

For the following exercises, use a graphing utility to determine whether each function is one-to-one.

73. $f(x) = \frac{1}{x}$
74. $f(x) = -3x^2 + x$

Practice with function notation:

75. If $f(5) = 2$, find $f^{-1}(2)$.
76. If $f(1) = 4$, find $f^{-1}(4)$.

This page titled 3.9E: Inverse Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.7E: Inverse Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# CHAPTER OVERVIEW

## 4: Polynomial and Rational Functions

Inverse functions make it possible to convert from one file format to another. In this chapter, we will learn about these concepts and discover how mathematics can be used in such applications.


4.1: Prelude to Polynomial and Rational Functions
4.2: Quadratic Functions
4.2E: Quadratic Functions (Exercises)
4.3: Power Functions and Polynomial Functions
4.3E: Power Functions and Polynomial Functions (Exercises)
4.4: Graphs of Polynomial Functions
4.4E: Graphs of Polynomial Functions (Exercises)
4.5: Dividing Polynomials
4.5E: Dividing Polynomials (Exercises)
4.6: Zeros of Polynomial Functions
4.6E: Zeros of Polynomial Functions (Exercises)
4.7: Rational Functions
4.7E: Rational Functions (Exercises)
4.8: Non-linear Inequalities
4.8.1: Solve Quadratic Inequalities
4.8.1E: Exercises
4.8.2: Solve Rational Inequalities
4.8.2E: Exercises


Thumbnail: Identifying the behavior of the graph at an x-intercept by examining the multiplicity of the zero.

### Contributors

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.


This page titled 4: Polynomial and Rational Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 4.1: Prelude to Polynomial and Rational Functions

Digital photography has dramatically changed the nature of photography. No longer is an image etched in the emulsion on a roll of film. Instead, nearly every aspect of recording and manipulating images is now governed by mathematics. An image becomes a series of numbers, representing the characteristics of light striking an image sensor. When we open an image file, software on a camera or computer interprets the numbers and converts them to a visual image. Photo editing software uses complex polynomials to transform images, allowing us to manipulate the image in order to crop details, change the color palette, and add special effects. Inverse functions make it possible to convert from one file format to another. In this chapter, we will learn about these concepts and discover how mathematics can be used in such applications.





***Figure* 4.1.1*:*** *35-mm film, once the standard for capturing photographic images, has been made largely obsolete by digital photography. (credit "film": modification of work by Horia Varlan; credit "memory cards": modification of work by Paul Hudson)*

This page titled 4.1: Prelude to Polynomial and Rational Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.0: Prelude to Polynomial and Rational Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.2: Quadratic Functions

**Learning Objectives**

- Recognize characteristics of parabolas.
- Understand how the graph of a parabola is related to its quadratic function.
- Determine a quadratic function's minimum or maximum value.
- Solve problems involving a quadratic function's minimum or maximum value.

Curved antennas, such as the ones shown in Figure 4.2.1, are commonly used to focus microwaves and radio waves to transmit television and telephone signals, as well as satellite and spacecraft communication. The cross-section of the antenna is in the shape of a parabola, which can be described by a quadratic function.




***Figure* 4.2.1:** *An array of satellite dishes. (credit: Matthew Colvin de Valle, Flickr)*

In this section, we will investigate quadratic functions, which frequently model problems involving area and projectile motion. Working with quadratic functions can be less complex than working with higher degree functions, so they provide a good opportunity for a detailed study of function behavior.

## Recognizing Characteristics of Parabolas

The graph of a quadratic function is a U-shaped curve called a parabola. One important feature of the graph is that it has an extreme point, called the **vertex**. If the parabola opens up, the vertex represents the lowest point on the graph, or the **minimum value** of the quadratic function. If the parabola opens down, the vertex represents the highest point on the graph, or the **maximum value**. In either case, the vertex is a turning point on the graph. The graph is also symmetric with a vertical line drawn through the vertex, called the **axis of symmetry**. These features are illustrated in Figure 4.2.2.





Figure 4.2.2: Graph of a parabola showing where the $x$ and $y$ intercepts, vertex, and axis of symmetry are.

The y-intercept is the point at which the parabola crosses the $y$-axis. The x-intercepts are the points at which the parabola crosses the $x$-axis. If they exist, the x-intercepts represent the **zeros**, or **roots**, of the quadratic function, the values of $x$ at which $y = 0$.

### Example 4.2.1: Identifying the Characteristics of a Parabola

Determine the vertex, axis of symmetry, zeros, and y-intercept of the parabola shown in Figure 4.2.3.





Figure 4.2.3.

**Solution**

The vertex is the turning point of the graph. We can see that the vertex is at $(3, 1)$. Because this parabola opens upward, the axis of symmetry is the vertical line that intersects the parabola at the vertex. So the axis of symmetry is $x = 3$. This parabola does not cross the x-axis, so it has no zeros. It crosses the $y$-axis at $(0, 7)$ so this is the y-intercept.

## Understanding How the Graphs of Parabolas are Related to Their Quadratic Functions

The **general form of a quadratic function** presents the function in the form

$$f(x) = ax^2 + bx + c \tag{4.2.1}$$

where $a$, $b$, and $c$ are real numbers and $a \neq 0$. If $a > 0$, the parabola opens upward. If $a < 0$, the parabola opens downward. We can use the general form of a parabola to find the equation for the axis of symmetry.

The axis of symmetry is defined by $x = -\frac{b}{2a}$. If we use the quadratic formula, $x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$, to solve $ax^2 + bx + c = 0$ for the x-intercepts, or zeros, we find the value of $x$ halfway between them is always $x = -\frac{b}{2a}$, the equation for the axis of symmetry.

Figure $4.2.4$ represents the graph of the quadratic function written in general form as $y = x^2 + 4x + 3$. In this form, $a = 1$, $b = 4$, and $c = 3$. Because $a > 0$, the parabola opens upward. The axis of symmetry is $x = -\frac{4}{2(1)} = -2$. This also makes sense because we can see from the graph that the vertical line $x = -2$ divides the graph in half. The vertex always occurs along the axis of symmetry. For a parabola that opens upward, the vertex occurs at the lowest point on the graph, in this instance, $(-2, -1)$. The x-intercepts, those points where the parabola crosses the x-axis, occur at $(-3, 0)$ and $(-1, 0)$.





Figure 4.2.4: Graph of a parabola showing where the $x$ and $y$ intercepts, vertex, and axis of symmetry are for the function $y = x^2 + 4x + 3$.

The **standard form of a quadratic function** presents the function in the form

$$f(x) = a(x - h)^2 + k \tag{4.2.2}$$

where $(h, k)$ is the vertex. Because the vertex appears in the standard form of the quadratic function, this form is also known as the **vertex form of a quadratic function**.

As with the general form, if $a > 0$, the parabola opens upward and the vertex is a minimum. If $a < 0$, the parabola opens downward, and the vertex is a maximum. Figure $4.2.5$ represents the graph of the quadratic function written in standard form as $y = -3(x + 2)^2 + 4$. Since $x - h = x + 2$ in this example, $h = -2$. In this form, $a = -3$, $h = -2$, and $k = 4$. Because $a < 0$, the parabola opens downward. The vertex is at $(-2, 4)$.





Figure 4.2.5: Graph of a parabola showing where the $x$ and $y$ intercepts, vertex, and axis of symmetry are for the function $y = -3(x+2)^2 + 4$ .

The standard form is useful for determining how the graph is transformed from the graph of $y = x^2$. Figure 4.2.6 is the graph of this basic function.





Figure 4.2.6: Graph of $y = x^2$.

If $k > 0$, the graph shifts upward, whereas if $k < 0$, the graph shifts downward. In Figure 4.2.5, $k > 0$, so the graph is shifted 4 units upward. If $h > 0$, the graph shifts toward the right and if $h < 0$, the graph shifts to the left. In Figure 4.2.5, $h < 0$, so the graph is shifted 2 units to the left. The magnitude of $a$ indicates the stretch of the graph. If $|a| > 1$, the point associated with a particular x-value shifts farther from the x-axis, so the graph appears to become narrower, and there is a vertical stretch. But if $|a| < 1$, the point associated with a particular x-value shifts closer to the x-axis, so the graph appears to become wider, but in fact there is a vertical compression. In Figure 4.2.5, $|a| > 1$, so the graph becomes narrower.

The standard form and the general form are equivalent methods of describing the same function. We can see this by expanding out the general form and setting it equal to the standard form.

$$\begin{aligned} a(x-h)^2+k &= ax^2+bx+c \\ ax^2-2ahx+(ah^2+k) &= ax^2+bx+c \end{aligned}$$

For the linear terms to be equal, the coefficients must be equal.

$$-2ah=b, \text{ so } h=-\frac{b}{2a}.$$

This is the **axis of symmetry** we defined earlier. Setting the constant terms equal:

$$\begin{aligned} ah^2+k &= c \\ k &= c-ah^2 \\ &= c-a\cdot\left(-\frac{b}{2a}\right)^2 \\ &= c-\frac{b^2}{4a} \end{aligned}$$

In practice, though, it is usually easier to remember that $k$ is the output value of the function when the input is $h$, so $f(h)=k$.

**Definitions: Forms of Quadratic Functions**

A quadratic function is a function of degree two. The graph of a *quadratic function* is a parabola.

- The *general form* of a quadratic function is $f(x)=ax^2+bx+c$ where $a$, $b$, and $c$ are real numbers and $a\neq 0$.
- The standard form of a quadratic function is $f(x)=a(x-h)^2+k$ .
- The vertex $(h,k)$ is located at

$$h=-\frac{b}{2a},\ k=f(h)=f(\frac{-b}{2a}). \tag{4.2.3}$$

**HOWTO: Write a quadratic function in a general form**

Given a graph of a quadratic function, write the equation of the function in general form.

1. Identify the horizontal shift of the parabola; this value is $h$. Identify the vertical shift of the parabola; this value is $k$.
2. Substitute the values of the horizontal and vertical shift for $h$ and $k$. in the function $f(x)=a(x-h)^2+k$.
3. Substitute the values of any point, other than the vertex, on the graph of the parabola for $x$ and $f(x)$.
4. Solve for the stretch factor, $|a|$.
5. If the parabola opens up, $a>0$. If the parabola opens down, $a<0$ since this means the graph was reflected about the x-axis.
6. Expand and simplify to write in general form.

**Example 4.2.2: Writing the Equation of a Quadratic Function from the Graph**

Write an equation for the quadratic function $g$ in Figure 4.2.7 as a transformation of $f(x)=x^2$, and then expand the formula, and simplify terms to write the equation in general form.





Figure 4.2.7: Graph of a parabola with its vertex at $(-2, -3)$.

**Solution**

We can see the graph of $g$ is the graph of $f(x) = x^2$ shifted to the left 2 and down 3, giving a formula in the form $g(x) = a(x+2)^2 - 3$.

Substituting the coordinates of a point on the curve, such as $(0, -1)$, we can solve for the stretch factor.

$$-1 = a(0+2)^2 - 3 \tag{4.2.4}$$
$$2 = 4a \tag{4.2.5}$$
$$a = \frac{1}{2} \tag{4.2.6}$$

In standard form, the algebraic model for this graph is $g(x) = \frac{1}{2}(x+2)^2 - 3$.

To write this in general polynomial form, we can expand the formula and simplify terms.

$$g(x) = \frac{1}{2}(x+2)^2 - 3 \tag{4.2.7}$$
$$= \frac{1}{2}(x+2)(x+2) - 3 \tag{4.2.8}$$
$$= \frac{1}{2}(x^2 + 4x + 4) - 3 \tag{4.2.9}$$
$$= \frac{1}{2}x^2 + 2x + 2 - 3 \tag{4.2.10}$$
$$= \frac{1}{2}x^2 + 2x - 1 \tag{4.2.11}$$

Notice that the horizontal and vertical shifts of the basic graph of the quadratic function determine the location of the vertex of the parabola; the vertex is unaffected by stretches and compressions.

**Analysis**

We can check our work using the table feature on a graphing utility. First enter $\mathrm{Y1} = \frac{1}{2}(\mathrm{x}+2)^2 - 3$ . Next, select $\mathrm{TBLSET}$, then use $\mathrm{TblStart} = -6$ and $\Delta\mathrm{Tbl} = 2$, and select $\mathrm{TABLE}$. See Table 4.2.1

Table 4.2.1

| $x$ | -6 | -4 | -2 | 0 | 2 |
|---|---|---|---|---|---|
| $y$ | -5 | -1 | -3 | -1 | 5 |

The ordered pairs in the table correspond to points on the graph.

## Exercise 4.2.2

A coordinate grid has been superimposed over the quadratic path of a basketball in Figure 4.2.8. Find an equation for the path of the ball. Does the shooter make the basket?





***Figure 4.2.8:*** *Stop motioned picture of a boy throwing a basketball into a hoop to show the parabolic curve it makes. (credit: modification of work by Dan Meyer)*

**Answer**

The path passes through the origin and has vertex at $(-4, 7)$, so $h(x) = -\frac{7}{16}(x+4)^2 + 7$ . To make the shot, $h(-7.5)$ would need to be about 4 but $h(-7.5) \approx 1.64$; he doesn't make it.

**How To: Given a quadratic function in general form, find the vertex of the parabola.**

1. Identify $a$, $b$, and $c$.
2. Find $h$, the x-coordinate of the vertex, by substituting $a$ and $b$ into $h = -\frac{b}{2a}$.
3. Find $k$, the y-coordinate of the vertex, by evaluating $k = f(h) = f\left(-\frac{b}{2a}\right)$ .

## Example 4.2.3: Finding the Vertex of a Quadratic Function

Find the vertex of the quadratic function $f(x) = 2x^2 - 6x + 7$. Rewrite the quadratic in standard form (vertex form).

**Solution**

The horizontal coordinate of the vertex will be at

$$h = -\frac{b}{2a} \tag{4.2.12}$$
$$= -\frac{-6}{2(2)} \tag{4.2.13}$$
$$= \frac{6}{4} \tag{4.2.14}$$
$$= \frac{3}{2} \tag{4.2.15}$$

The vertical coordinate of the vertex will be at

$$k = f(h) \tag{4.2.16}$$
$$= f\left(\frac{3}{2}\right) \tag{4.2.17}$$
$$= 2\left(\frac{3}{2}\right)^2 - 6\left(\frac{3}{2}\right) + 7 \tag{4.2.18}$$
$$= \frac{5}{2} \tag{4.2.19}$$

Rewriting into standard form, the stretch factor will be the same as the $a$ in the original quadratic.

$$f(x) = ax^2 + bx + c \tag{4.2.20}$$
$$f(x) = 2x^2 - 6x + 7$$

Using the vertex to determine the shifts,

$$f(x) = 2\left(x - \frac{3}{2}\right)^2 + \frac{5}{2} \tag{4.2.21}$$

**Analysis**

One reason we may want to identify the vertex of the parabola is that this point will inform us what the maximum or minimum value of the function is, $(k)$,and where it occurs, $(h)$.

**Exercise 4.2.3**

Given the equation $g(x) = 13 + x^2 - 6x$ , write the equation in general form and then in standard form.

**Answer**

$g(x) = x^2 - 6x + 13$ in general form; $g(x) = (x-3)^2 + 4$ in standard form.

## Finding the Domain and Range of a Quadratic Function

Any number can be the input value of a quadratic function. Therefore, the domain of any quadratic function is all real numbers. Because parabolas have a maximum or a minimum point, the range is restricted. Since the vertex of a parabola will be either a maximum or a minimum, the range will consist of all y-values greater than or equal to the y-coordinate at the turning point or less than or equal to the y-coordinate at the turning point, depending on whether the parabola opens up or down.

**Definition: Domain and Range of a Quadratic Function**

The domain of any **quadratic function** is all real numbers.

The range of a quadratic function written in general form $f(x) = ax^2 + bx + c$ with a positive $a$ value is $f(x) \geq f\left(-\frac{b}{2a}\right)$, or $[f(-\frac{b}{2a}), \infty)$; the range of a quadratic function written in general form with a negative a value is $f(x) \leq f(-\frac{b}{2a})$, or $(-\infty, f(-\frac{b}{2a})]$.

The range of a quadratic function written in standard form $f(x) = a(x-h)^2 + k$ with a positive $a$ value is $f(x) \geq k$; the range of a quadratic function written in standard form with a negative $a$ value is $f(x) \leq k$.

**How To: Given a quadratic function, find the domain and range.**

1. Identify the domain of any quadratic function as all real numbers.
2. Determine whether $a$ is positive or negative. If $a$ is positive, the parabola has a minimum. If $a$ is negative, the parabola has a maximum.
3. Determine the maximum or minimum value of the parabola, $k$.
4. If the parabola has a minimum, the range is given by $f(x) \geq k$, or $[k, \infty)$. If the parabola has a maximum, the range is given by $f(x) \leq k$, or $(-\infty, k]$.

### Example 4.2.4: Finding the Domain and Range of a Quadratic Function

Find the domain and range of $f(x) = -5x^2 + 9x - 1$ .

**Solution**

As with any quadratic function, the domain is all real numbers.

Because $a$ is negative, the parabola opens downward and has a maximum value. We need to determine the maximum value. We can begin by finding the x-value of the vertex.

$$h = -\frac{b}{2a} \tag{4.2.22}$$
$$= -\frac{9}{2(-5)} \tag{4.2.23}$$
$$= \frac{9}{10} \tag{4.2.24}$$

The maximum value is given by $f(h)$.

$$f(\frac{9}{10}) = 5(\frac{9}{10})^2 + 9(\frac{9}{10}) - 1 \tag{4.2.25}$$
$$= \frac{61}{20} \tag{4.2.26}$$

The range is $f(x) \leq \frac{61}{20}$, or $\left(-\infty, \frac{61}{20}\right]$.

### Exercise 4.2.4


Find the domain and range of $f(x) = 2\left(x - \frac{4}{7}\right)^2 + \frac{8}{11}$ .

**Answer**


The domain is all real numbers. The range is $f(x) \geq \frac{8}{11}$ , or $\left[\frac{8}{11}, \infty\right)$.

## Determining the Maximum and Minimum Values of Quadratic Functions

The output of the quadratic function at the vertex is the maximum or minimum value of the function, depending on the orientation of the **parabola**. We can see the maximum and minimum values in Figure 4.2.9.




(a)




(b)

Figure 4.2.9: Minimum and maximum of two quadratic functions.

There are many real-world scenarios that involve finding the maximum or minimum value of a quadratic function, such as applications involving area and revenue.

### Example 4.2.5: Finding the Maximum Value of a Quadratic Function

A backyard farmer wants to enclose a rectangular space for a new garden within her fenced backyard. She has purchased 80 feet of wire fencing to enclose three sides, and she will use a section of the backyard fence as the fourth side.

a. Find a formula for the area enclosed by the fence if the sides of fencing perpendicular to the existing fence have length $L$.
b. What dimensions should she make her garden to maximize the enclosed area?

**Solution**

Let's use a diagram such as Figure 4.2.10 to record the given information. It is also helpful to introduce a temporary variable, $W$, to represent the width of the garden and the length of the fence section parallel to the backyard fence.





Figure 4.2.10: Diagram of the garden and the backyard.

a. We know we have only 80 feet of fence available, and $L+W+L=80$ , or more simply, $2L+W=80$. This allows us to represent the width, $W$, in terms of $L$.

$$W=80-2L \tag{4.2.27}$$

Now we are ready to write an equation for the area the fence encloses. We know the area of a rectangle is length multiplied by width, so

$$A = LW = L(80-2L) \tag{4.2.28}$$
$$A(L) = 80L-2L^2 \tag{4.2.29}$$

This formula represents the area of the fence in terms of the variable length $L$. The function, written in general form, is

$$A(L)=-2L^2+80L \tag{4.2.30}$$

.

The quadratic has a negative leading coefficient, so the graph will open downward, and the vertex will be the maximum value for the area. In finding the vertex, we must be careful because the equation is not written in standard polynomial form with decreasing powers. This is why we rewrote the function in general form above. Since $a$ is the coefficient of the squared term, $a=-2$ , $b=80$, and $c=0$.

To find the vertex:

$$h=-\frac{80}{2(-2)} \qquad k=A(20) \tag{4.2.31}$$
$$=20 \qquad \text{and} \qquad =80(20)-2(20)^2 \tag{4.2.32}$$
$$=800 \tag{4.2.33}$$

The maximum value of the function is an area of 800 square feet, which occurs when $L=20$ feet. When the shorter sides are 20 feet, there is 40 feet of fencing left for the longer side. To maximize the area, she should enclose the garden so the two shorter sides have length 20 feet and the longer side parallel to the existing fence has length 40 feet.

**Analysis**

This problem also could be solved by graphing the quadratic function. We can see where the maximum area occurs on a graph of the quadratic function in Figure 4.2.11.





Figure 4.2.11: Graph of the parabolic function $A(L) = -2L^2 + 80L$

**How To: Given an application involving revenue, use a quadratic equation to find the maximum.**

1. Write a quadratic equation for revenue.
2. Find the vertex of the quadratic equation.
3. Determine the y-value of the vertex.

### Example 4.2.6: Finding Maximum Revenue

The unit price of an item affects its supply and demand. That is, if the unit price goes up, the demand for the item will usually decrease. For example, a local newspaper currently has 84,000 subscribers at a quarterly charge of $30. Market research has suggested that if the owners raise the price to $32, they would lose 5,000 subscribers. Assuming that subscriptions are linearly related to the price, what price should the newspaper charge for a quarterly subscription to maximize their revenue?

**Solution**

Revenue is the amount of money a company brings in. In this case, the revenue can be found by multiplying the price per subscription times the number of subscribers, or quantity. We can introduce variables, $p$ for price per subscription and $Q$ for quantity, giving us the equation $\text{Revenue} = pQ$.

Because the number of subscribers changes with the price, we need to find a relationship between the variables. We know that currently $p = 30$ and $Q = 84,000$. We also know that if the price rises to $32, the newspaper would lose 5,000 subscribers, giving a second pair of values, $p = 32$ and $Q = 79,000$. From this we can find a linear equation relating the two quantities. The slope will be

$$m = \frac{79,000 - 84,000}{32 - 30} \tag{4.2.34}$$

$$= -\frac{5,000}{2} \tag{4.2.35}$$

$$= -2,500 \tag{4.2.36}$$

This tells us the paper will lose 2,500 subscribers for each dollar they raise the price. We can then solve for the y-intercept.

$$Q = -2500p + b \quad \text{Substitute in the point } Q = 84,000 \text{ and } p = 30 \tag{4.2.37}$$

$$84,000 = -2500(30) + b \quad \text{Solve for } b \tag{4.2.38}$$

$$b = 159,000 \tag{4.2.39}$$

This gives us the linear equation $Q = -2,500p + 159,000$ relating cost and subscribers. We now return to our revenue equation.

$$\text{Revenue} = pQ \tag{4.2.40}$$
$$\text{Revenue} = p(-2,500p + 159,000) \tag{4.2.41}$$
$$\text{Revenue} = -2,500p^2 + 159,000p \tag{4.2.42}$$

We now have a quadratic function for revenue as a function of the subscription charge. To find the price that will maximize revenue for the newspaper, we can find the vertex.

$$h = -\frac{159,000}{2(-2,500)} \tag{4.2.43}$$
$$= 31.8 \tag{4.2.44}$$

The model tells us that the maximum revenue will occur if the newspaper charges $31.80 for a subscription. To find what the maximum revenue is, we evaluate the revenue function.

$$\text{maximum revenue} = -2,500(31.8)^2 + 159,000(31.8) \tag{4.2.45}$$
$$= 2,528,100 \tag{4.2.46}$$

**Analysis**

This could also be solved by graphing the quadratic as in Figure 4.2.12 We can see the maximum revenue on a graph of the quadratic function.





Figure 4.2.12: Graph of the parabolic function

## Finding the x- and y-Intercepts of a Quadratic Function

Much as we did in the application problems above, we also need to find intercepts of quadratic equations for graphing parabolas. Recall that we find the y-intercept of a quadratic by evaluating the function at an input of zero, and we find the x-intercepts at locations where the output is zero. Notice in Figure 4.2.13 that the number of x-intercepts can vary depending upon the location of the graph.





Figure 4.2.13: Number of x-intercepts of a parabola.

**Given a quadratic function $f(x)$, find the y- and x-intercepts.**

1. Evaluate $f(0)$ to find the y-intercept.
2. Solve the quadratic equation $f(x)=0$ to find the x-intercepts.

**Example 4.2.7: Finding the y- and x-Intercepts of a Parabola**

Find the y- and x-intercepts of the quadratic $f(x)=3x^2+5x-2$ .

**Solution**

We find the y-intercept by evaluating $f(0)$.

$$f(0) = 3(0)^2+5(0)-2 \tag{4.2.47}$$
$$= -2 \tag{4.2.48}$$

So the y-intercept is at $(0,-2)$.

For the x-intercepts, we find all solutions of $f(x)=0$.

$$0=3x^2+5x-2 \tag{4.2.49}$$

In this case, the quadratic can be factored easily, providing the simplest method for solution.

$$0=(3x-1)(x+2) \tag{4.2.50}$$
$$0=3x-1 \qquad\qquad 0=x+2 \tag{4.2.51}$$
$$x=\frac{1}{3} \qquad \text{or} \qquad x=-2 \tag{4.2.52}$$

So the x-intercepts are at $(\frac{1}{3},0)$ and $(-2,0)$.

**Analysis**

By graphing the function, we can confirm that the graph crosses the $y$-axis at $(0,-2)$. We can also confirm that the graph crosses the x-axis at $\left(\frac{1}{3},0\right)$ and $(-2,0)$. See Figure 4.2.14





Figure 4.2.14: Graph of a parabola.

## Rewriting Quadratics in Standard Form

In Example 4.2.7, the quadratic was easily solved by factoring. However, there are many quadratics that cannot be factored. We can solve these quadratics by first rewriting them in standard form.

**How To: Given a quadratic function, find the x-intercepts by rewriting in standard form.**

1. Substitute a and $b$ into $h=-\frac{b}{2a}$ .
2. Substitute $x=h$ into the general form of the quadratic function to find $k$.
3. Rewrite the quadratic in standard form using $h$ and $k$.

4. Solve for when the output of the function will be zero to find the x-intercepts.

### Example 4.2.8: Finding the x-Intercepts of a Parabola

Find the x-intercepts of the quadratic function $f(x) = 2x^2 + 4x - 4$ .

**Solution**

We begin by solving for when the output will be zero.

$$0 = 2x^2 + 4x - 4$$

Because the quadratic is not easily factorable in this case, we solve for the intercepts by first rewriting the quadratic in standard form.

$$f(x) = a(x-h)^2 + k$$

We know that $a = 2$. Then we solve for $h$ and $k$.

$$\begin{aligned} h &= -\frac{b}{2a} & k &= f(-1) \\ &= -\frac{4}{2(2)} & &= 2(-1)^2 + 4(-1) - 4 \\ &= -1 & &= -6 \end{aligned}$$

So now we can rewrite in standard form.

$$f(x) = 2(x+1)^2 - 6$$

We can now solve for when the output will be zero.

$$\begin{aligned} 0 &= 2(x+1)^2 - 6 \\ 6 &= 2(x+1)^2 \\ 3 &= (x+1)^2 \\ x+1 &= \pm\sqrt{3} \\ x &= -1 \pm \sqrt{3} \end{aligned}$$

The graph has x-intercepts at $(-1-\sqrt{3}, 0)$ and $(-1+\sqrt{3}, 0)$.

**Analysis**

We can check our work by graphing the given function on a graphing utility and observing the x-intercepts. See Figure 4.2.15.





Figure 4.2.15: Graph of a parabola which has the following x-intercepts: $(-2.732, 0)$ and $(0.732, 0)$.

## Exercise 4.2.1

In Try It 4.2.1, we found the standard and general form for the function $g(x) = 13 + x^2 - 6x$ . Now find the y- and x-intercepts (if any).

**Answer**

y-intercept at $(0, 13)$, No x-intercepts

## Example 4.2.9: Solving a Quadratic Equation with the Quadratic Formula

Solve $x^2 + x + 2 = 0$ .

**Solution**

Let's begin by writing the quadratic formula: $x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$.

When applying the quadratic formula, we identify the coefficients $a$, $b$ and $c$. For the equation $x^2 + x + 2 = 0$ , we have $a = 1$ , $b = 1$ , and $c = 2$ . Substituting these values into the formula we have:

$$\begin{aligned} x &= \frac{-b \pm \sqrt{b^2 - 4ac}}{2a} \\ &= \frac{-1 \pm \sqrt{1^2 - 4 \cdot 1 \cdot (2)}}{2 \cdot 1} \\ &= \frac{-1 \pm \sqrt{1 - 8}}{2} \\ &= \frac{-1 \pm \sqrt{-7}}{2} \\ &= \frac{-1 \pm i\sqrt{7}}{2} \end{aligned}$$

The solutions to the equation are $x = \frac{-1 + i\sqrt{7}}{2}$ and $x = \frac{-1 - i\sqrt{7}}{2}$ or $x = -\frac{1}{2} + \frac{i\sqrt{7}}{2}$ and $x = \frac{-1}{2} - \frac{i\sqrt{7}}{2}$ .

## Example 4.2.10: Applying the Vertex and x-Intercepts of a Parabola

A ball is thrown upward from the top of a 40 foot high building at a speed of 80 feet per second. The ball's height above ground can be modeled by the equation $H(t) = -16t^2 + 80t + 40$ .

When does the ball reach the maximum height?
What is the maximum height of the ball?
When does the ball hit the ground?

The ball reaches the maximum height at the vertex of the parabola.

$$h = -\frac{80}{2(-16)} \tag{4.2.53}$$
$$= \frac{80}{32} \tag{4.2.54}$$
$$= \frac{5}{2} \tag{4.2.55}$$
$$= 2.5 \tag{4.2.56}$$

The ball reaches a maximum height after 2.5 seconds.

To find the maximum height, find the y-coordinate of the vertex of the parabola.

$$k = H(-\frac{b}{2a}) \tag{4.2.57}$$
$$= H(2.5) \tag{4.2.58}$$
$$= -16(2.5)^2 + 80(2.5) + 40 \tag{4.2.59}$$
$$= 140 \tag{4.2.60}$$

The ball reaches a maximum height of 140 feet.

To find when the ball hits the ground, we need to determine when the height is zero, $H(t) = 0$.

We use the quadratic formula.

$$t = \frac{-80 \pm \sqrt{80^2 - 4(-16)(40)}}{2(-16)} \tag{4.2.61}$$
$$= \frac{-80 \pm \sqrt{8960}}{-32} \tag{4.2.62}$$

Because the square root does not simplify nicely, we can use a calculator to approximate the values of the solutions.

$$t = \frac{-80 - \sqrt{8960}}{-32} \approx 5.458 \text{ or } t = \frac{-80 + \sqrt{8960}}{-32} \approx -0.458 \tag{4.2.63}$$

The second answer is outside the reasonable domain of our model, so we conclude the ball will hit the ground after about 5.458 seconds. See Figure 4.2.16.





Figure 4.2.16


https://math.libretexts.org/@go/page/96285

**4.2.5:** A rock is thrown upward from the top of a 112-foot high cliff overlooking the ocean at a speed of 96 feet per second. The rock's height above ocean can be modeled by the equation $H(t) = -16t^2 + 96t + 112$ .

a. When does the rock reach the maximum height?
b. What is the maximum height of the rock?
c. When does the rock hit the ocean?

**Solution**

a. 3 seconds b. 256 feet c. 7 seconds

## Key Equations

- general form of a quadratic function: $f(x) = ax^2 + bx + c$
- the quadratic formula: $x = \dfrac{-b \pm \sqrt{b^2 - 4ac}}{2a}$
- standard form of a quadratic function: $f(x) = a(x - h)^2 + k$

## Key Concepts

- A polynomial function of degree two is called a quadratic function.
- The graph of a quadratic function is a parabola. A parabola is a U-shaped curve that can open either up or down.
- The axis of symmetry is the vertical line passing through the vertex. The zeros, or x-intercepts, are the points at which the parabola crosses the x-axis. The y-intercept is the point at which the parabola crosses the $y$-axis.
- Quadratic functions are often written in general form. Standard or vertex form is useful to easily identify the vertex of a parabola. Either form can be written from a graph.
- The vertex can be found from an equation representing a quadratic function. .
- The domain of a quadratic function is all real numbers. The range varies with the function.
- A quadratic function's minimum or maximum value is given by the y-value of the vertex.
- The minimum or maximum value of a quadratic function can be used to determine the range of the function and to solve many kinds of real-world problems, including problems involving area and revenue.
- Some quadratic equations must be solved by using the quadratic formula.
- The vertex and the intercepts can be identified and interpreted to solve real-world problems.

## Glossary

**axis of symmetry**
a vertical line drawn through the vertex of a parabola around which the parabola is symmetric; it is defined by $x = -\frac{b}{2a}$.

**general form of a quadratic function**
the function that describes a parabola, written in the form $f(x) = ax^2 + bx + c$ , where $a, b$, and $c$ are real numbers and a≠0.

**standard form of a quadratic function**
the function that describes a parabola, written in the form $f(x) = a(x - h)^2 + k$ , where $(h, k)$ is the vertex.

**vertex**
the point at which a parabola changes direction, corresponding to the minimum or maximum value of the quadratic function

**vertex form of a quadratic function**
another name for the standard form of a quadratic function

**zeros**
in a given function, the values of $x$ at which $y = 0$, also called roots

---

This page titled 4.2: Quadratic Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.2: Quadratic Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.2E: Quadratic Functions (Exercises)

For the following exercises, write the quadratic function in standard form. Then give the vertex and axes intercepts. Finally, graph the function.

1. $f(x) = x^2 - 4x - 5$

2. $f(x) = -2x^2 - 4x$

For the following exercises, find the equation of the quadratic function using the given information.

3. The vertex is (-2,3) and a point on the graph is (3,6)

4. The vertex is (-3,6.5) and a point on the graph is (2,6) .

For the following exercises, complete the task.

5. A rectangular plot of land is to be enclosed by fencing. One side is along a river and so needs no fence. If the total fencing available is 600 meters, find the dimensions of the plot to have maximum area.

6. An object projected from the ground at a 45 degree angle with initial velocity of 120 feet per second has height, $h$, in terms of horizontal distance traveled, $x$, given by $h(x) = \frac{-32}{(120)^2}x^2 + x$ . Find the maximum height the object attains.

---

This page titled 4.2E: Quadratic Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **5.1E: Quadratic Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.3: Power Functions and Polynomial Functions

**Learning Objectives**

- Identify power functions.
- Identify end behavior of power functions.
- Identify polynomial functions.
- Identify the degree and leading coefficient of polynomial functions.

Suppose a certain species of bird thrives on a small island. Its population over the last few years is shown in Table 4.3.1.

Table 4.3.1

| Year | 2009 | 2010 | 2011 | 2012 | 2013 |
|---|---|---|---|---|---|
| Bird Population | 800 | 897 | 992 | 1,083 | 1,169 |

The population can be estimated using the function $P(t) = -0.3t^3 + 97t + 800$ , where $P(t)$ represents the bird population on the island $t$ years after 2009. We can use this model to estimate the maximum bird population and when it will occur. We can also use this model to predict when the bird population will disappear from the island. In this section, we will examine functions that we can use to estimate and predict these types of changes.



Figure 4.3.1: (credit: Jason Bay, Flickr)

## Identifying Power Functions

In order to better understand the bird problem, we need to understand a specific type of function. A power function is a function with a single term that is the product of a real number, a coefficient, and a variable raised to a fixed real number. (A number that multiplies a variable raised to an exponent is known as a coefficient.)

As an example, consider functions for area or volume. The function for the area of a circle with radius $r$ is

$$A(r) = \pi r^2$$

and the function for the volume of a sphere with radius $r$ is

$$V(r) = \frac{4}{3}\pi r^3$$

Both of these are examples of power functions because they consist of a coefficient, $\pi$ or $\frac{4}{3}\pi$, multiplied by a variable $r$ raised to a power.

**Definition: Power Function**

A *power function* is a function that can be represented in the form

$$f(x) = kx^p \tag{4.3.1}$$

where $k$ and $p$ are real numbers, and $k$ is known as the *coefficient*.

**Q&A: Is $f(x) = 2^x$ a power function?**

*No. A power function contains a variable base raised to a fixed power (Equation 4.3.1). This function has a constant base raised to a variable power. This is called an exponential function, not a power function. This function will be discussed later.*

**Example 4.3.1: Identifying Power Functions**

Which of the following functions are power functions?

| | |
|---|---|
| $f(x) = 1$ | Constant function |
| $f(x) = x$ | Identify function |
| $f(x) = x^2$ | Quadratic function |
| $f(x) = x^3$ | Cubic function |
| $f(x) = \frac{1}{x}$ | Reciprocal function |
| $f(x) = \frac{1}{x^2}$ | Reciprocal squared function |
| $f(x) = \sqrt{x}$ | Square root function |
| $f(x) = \sqrt[3]{x}$ | Cube root function |

**Solution**

All of the listed functions are power functions.

The constant and identity functions are power functions because they can be written as $f(x) = x^0$ and $f(x) = x^1$ respectively.

The quadratic and cubic functions are power functions with whole number powers $f(x) = x^2$ and $f(x) = x^3$.

The **reciprocal** and reciprocal squared functions are power functions with negative whole number powers because they can be written as $f(x) = x^{-1}$ and $f(x) = x^{-2}$.

The square and **cube root** functions are power functions with fractional powers because they can be written as $f(x) = x^{1/2}$ or $f(x) = x^{1/3}$.

**Exercise 4.3.1**

Which functions are power functions?

- $f(x) = 2x^2 \cdot 4x^3$
- $g(x) = -x^5 + 5x^3 - 4x$
- $h(x) = \frac{2x^5 - 1}{3x^2 + 4}$

**Answer**

$f(x)$ is a power function because it can be written as $f(x) = 8x^5$. The other functions are not power functions.

## Identifying End Behavior of Power Functions

Figure 4.3.2 shows the graphs of $f(x) = x^2$, $g(x) = x^4$ and and $h(x) = x^6$, which are all power functions with even, whole-number powers. Notice that these graphs have similar shapes, very much like that of the quadratic function in the toolkit. However, as the power increases, the graphs flatten somewhat near the origin and become steeper away from the origin.





Figure 4.3.2: Even-power functions

To describe the behavior as numbers become larger and larger, we use the idea of infinity. We use the symbol $\infty$ for positive infinity and $-\infty$ for negative infinity. When we say that "x approaches infinity," which can be symbolically written as $x \to \infty$, we are describing a behavior; we are saying that $x$ is increasing without bound.

With the even-power function, as the input increases or decreases without bound, the output values become very large, positive numbers. Equivalently, we could describe this behavior by saying that as $x$ approaches positive or negative infinity, the $f(x)$ values increase without bound. In symbolic form, we could write

$$\text{as } x \to \pm\infty,\ f(x) \to \infty$$

Figure 4.3.3 shows the graphs of $f(x) = x^3$, $g(x) = x^5$, and $h(x) = x^7$, which are all power functions with odd, whole-number powers. Notice that these graphs look similar to the cubic function in the toolkit. Again, as the power increases, the graphs flatten near the origin and become steeper away from the origin.





Figure 4.3.3: Odd-power function

These examples illustrate that functions of the form $f(x) = x^n$ reveal symmetry of one kind or another. First, in Figure 4.3.2 we see that even functions of the form $f(x) = x^n$, $n$ even, are symmetric about the $y$-axis. In Figure 4.3.3 we see that odd functions of the form $f(x) = x^n$, $n$ odd, are symmetric about the origin.

For these odd power functions, as $x$ approaches negative infinity, $f(x)$ decreases without bound. As $x$ approaches positive infinity, $f(x)$ increases without bound. In symbolic form we write

$$\text{as } x \to -\infty,\ f(x) \to -\infty$$
$$\text{as } x \to \infty,\ f(x) \to \infty$$

The behavior of the graph of a function as the input values get very small $(x \to -\infty)$ and get very large $x \to \infty$ is referred to as the *end behavior* of the function. We can use words or symbols to describe end behavior.

Figure 4.3.4 shows the end behavior of power functions in the form $f(x) = kx^n$ where $n$ is a non-negative integer depending on the power and the constant.





| | Even power | Odd power |
|---|---|---|
| Positive constant $k > 0$ |  $x \to -\infty, f(x) \to \infty$ and $x \to \infty, f(x) \to \infty$ |  $x \to -\infty, f(x) \to -\infty$ and $x \to \infty, f(x) \to \infty$ |
| Negative constant $k < 0$ |  $x \to -\infty, f(x) \to -\infty$ and $x \to \infty, f(x) \to -\infty$ |  $x \to -\infty, f(x) \to \infty$ and $x \to \infty, f(x) \to -\infty$ |

Figure 4.3.4

**How To: Given a power function $f(x) = kx^n$ where $n$ is a non-negative integer, identify the end behavior.**

1. Determine whether the power is even or odd.
2. Determine whether the constant is positive or negative.
3. Use Figure 4.3.4 to identify the end behavior.

**Example 4.3.2: Identifying the End Behavior of a Power Function**

Describe the end behavior of the graph of $f(x) = x^8$.

**Solution**

The coefficient is 1 (positive) and the exponent of the power function is 8 (an even number). As $x$ approaches infinity, the output (value of $f(x)$ ) increases without bound. We write as $x \to \infty$, $f(x) \to \infty$. As $x$ approaches negative infinity, the output increases without bound. In symbolic form, as $x \to -\infty$, $f(x) \to \infty$. We can graphically represent the function as shown in Figure 4.3.5.





Figure 4.3.5: Graph of $f(x) = x^8$.

**Example 4.3.3: Identifying the End Behavior of a Power Function.**

Describe the end behavior of the graph of $f(x) = -x^9$.

**Solution**

The exponent of the power function is 9 (an odd number). Because the coefficient is –1 (negative), the graph is the reflection about the $x$-axis of the graph of $f(x) = x^9$. Figure 4.3.6 shows that as $x$ approaches infinity, the output decreases without bound. As $x$ approaches negative infinity, the output increases without bound. In symbolic form, we would write

$$\text{as } x \to -\infty,\ f(x) \to \infty$$
$$\text{as } x \to \infty,\ f(x) \to -\infty$$





Figure 4.3.6: Graph of $f(x) = -x^9$.

**Analysis**

We can check our work by using the table feature on a graphing utility.

Table 4.3.2

| $x$ | $f(x)$ |
|---|---|
| -10 | 1,000,000,000 |
| -5 | 1,953,125 |
| 0 | 0 |
| 5 | -1,953,125 |
| 10 | -1,000,000,000 |

We can see from Table $4.3.2$ that, when we substitute very small values for $x$, the output is very large, and when we substitute very large values for $x$, the output is very small (meaning that it is a very large negative value).

**Exercise 4.3.2**

Describe in words and symbols the end behavior of $f(x) = -5x^4$.

**Answer**

As $x$ approaches positive or negative infinity, $f(x)$ decreases without bound: as $x \to \pm\infty$, $f(x) \to -\infty$ because of the negative coefficient.

## Identifying Polynomial Functions

An oil pipeline bursts in the Gulf of Mexico, causing an oil slick in a roughly circular shape. The slick is currently 24 miles in radius, but that radius is increasing by 8 miles each week. We want to write a formula for the area covered by the oil slick by combining two functions. The radius $r$ of the spill depends on the number of weeks $w$ that have passed. This relationship is linear.

$$r(w) = 24 + 8w$$

We can combine this with the formula for the area A of a circle.

$$A(r) = \pi r^2$$

Composing these functions gives a formula for the area in terms of weeks.

$$\begin{aligned} A(w) &= A(r(w)) \\ &= A(24 + 8w) \\ &= \pi(24 + 8w)^2 \end{aligned}$$

Multiplying gives the formula.

$$A(w) = 576\pi + 384\pi w + 64\pi w^2$$

This formula is an example of a polynomial function. A polynomial function consists of either zero or the sum of a finite number of non-zero terms, each of which is a product of a number, called the coefficient of the term, and a variable raised to a non-negative integer power.

**Definition: Polynomial Functions**

Let $n$ be a non-negative integer. A *polynomial function* is a function that can be written in the form

$$f(x) = a_n x^n + \ldots + a_2 x^2 + a_1 x + a_0 \tag{4.3.2}$$

This is called the general form of a polynomial function. Each $a_i$ is a coefficient and can be any real number. Each product $a_i x^i$ is a *term of a polynomial function.*

### Example 4.3.4: Identifying Polynomial Functions

Which of the following are polynomial functions?

- $f(x) = 2x^3 \cdot 3x + 4$
- $g(x) = -x(x^2 - 4)$
- $h(x) = 5\sqrt{x} + 2$

**Solution**

The first two functions are examples of polynomial functions because they can be written in the form of Equation 4.3.2, where the powers are non-negative integers and the coefficients are real numbers.

- $f(x)$ can be written as $f(x) = 6x^4 + 4$.
- $g(x)$ can be written as $g(x) = -x^3 + 4x$ .
- $h(x)$ cannot be written in this form and is therefore not a polynomial function.

## Identifying the Degree and Leading Coefficient of a Polynomial Function

Because of the form of a polynomial function, we can see an infinite variety in the number of terms and the power of the variable. Although the order of the terms in the polynomial function is not important for performing operations, we typically arrange the terms in descending order of power, or in general form. The degree of the polynomial is the highest power of the variable that occurs in the polynomial; it is the power of the first variable if the function is in general form. The leading term is the term containing the highest power of the variable, or the term with the highest degree. The leading coefficient is the coefficient of the leading term.

### Terminology of Polynomial Functions

We often rearrange polynomials so that the powers are descending.





Figure 4.3.7

When a polynomial is written in this way, we say that it is in *general form*.

### How To: Given a polynomial function, identify the degree and leading coefficient

1. Find the highest power of $x$ to determine the degree function.
2. Identify the term containing the highest power of $x$ to find the leading term.
3. Identify the coefficient of the leading term.

### Example 4.3.5: Identifying the Degree and Leading Coefficient of a Polynomial Function

Identify the degree, leading term, and leading coefficient of the following polynomial functions.

$$f(x) = 3 + 2x^2 - 4x^3$$

$$g(t) = 5t^5 - 2t^3 + 7t$$

$$h(p) = 6p - p^3 - 2$$

**Solution**

For the function $f(x)$, the highest power of $x$ is 3, so the degree is 3. The leading term is the term containing that degree, $-4x^3$. The leading coefficient is the coefficient of that term, −4.

For the function $g(t)$, the highest power of $t$ is 5, so the degree is 5. The leading term is the term containing that degree, $5t^5$. The leading coefficient is the coefficient of that term, 5.

For the function $h(p)$, the highest power of $p$ is 3, so the degree is 3. The leading term is the term containing that degree, $-p^3$; the leading coefficient is the coefficient of that term, $-1$.

**Exercise 4.3.3**

Identify the degree, leading term, and leading coefficient of the polynomial $f(x) = 4x^2 - x^6 + 2x - 6$ .



**Answer**



The degree is $6$. The leading term is $-x^6$. The leading coefficient is $-1$.

## Identifying End Behavior of Polynomial Functions

Knowing the degree of a polynomial function is useful in helping us predict its end behavior. To determine its end behavior, look at the leading term of the polynomial function. Because the power of the leading term is the highest, that term will grow significantly faster than the other terms as $x$ gets very large or very small, so its behavior will dominate the graph. For any polynomial, the end behavior of the polynomial will match the end behavior of the term of highest degree (Table $4.3.3$).

Table 4.3.3

| Polynomial Function | Leading Term | Graph of Polynomial Function |
|---|---|---|
| $f(x) = 5x^4 + 2x^3 - x - 4$ | $5x^4$ |  |
| $f(x) = -2x^6 - x^5 + 3x^4 + x^3$ | $-2x^6$ |  |

| Polynomial Function | Leading Term | Graph of Polynomial Function |
|---|---|---|
| $f(x) = 3x^5 - 4x^4 + 2x^2 + 1$ | $3x^5$ |  |
| $f(x) = -6x^3 + 7x^2 + 3x + 1$ | $-6x^3$ |  |

**Example 4.3.6: Identifying End Behavior and Degree of a Polynomial Function**

Describe the end behavior and determine a possible degree of the polynomial function in Figure 4.3.8.




Figure 4.3.8.

**Solution**

As the input values $x$ get very large, the output values $f(x)$ increase without bound. As the input values $x$ get very small, the output values $f(x)$ decrease without bound. We can describe the end behavior symbolically by writing

$$\text{as } x \to \infty,\ f(x) \to \infty$$

$$\text{as } x \to -\infty,\ f(x) \to -\infty$$

In words, we could say that as $x$ values approach infinity, the function values approach infinity, and as $x$ values approach negative infinity, the function values approach negative infinity.

We can tell this graph has the shape of an odd degree power function that has not been reflected, so the degree of the polynomial creating this graph must be odd and the leading coefficient must be positive.

## Exercise 4.3.1

Describe the end behavior, and determine a possible degree of the polynomial function in Figure 4.3.9.





Figure 4.3.9

**Answer**

As $x \to \infty$, $f(x) \to -\infty$ ; as $x \to -\infty$ , $f(x) \to -\infty$ . It has the shape of an even degree power function with a negative coefficient.

## Example 4.3.7: Identifying End Behavior and Degree of a Polynomial Function

Given the function $f(x) = -3x^2(x-1)(x+4)$ , express the function as a polynomial in general form, and determine the leading term, degree, and end behavior of the function.

**Solution**

Obtain the general form by expanding the given expression for $f(x)$.

$$\begin{aligned} f(x) &= -3x^2(x-1)(x+4) \\ &= -3x^2(x^2+3x-4) \\ &= -3x^4 - 9x^3 + 12x^2 \end{aligned}$$

The general form is $f(x) = -3x^4 - 9x^3 + 12x^2$ . The leading term is $-3x^4$; therefore, the degree of the polynomial is 4. The degree is even (4) and the leading coefficient is negative (–3), so the end behavior is

$$\text{as } x \to -\infty,\ f(x) \to -\infty$$

$$\text{as } x \to \infty,\ f(x) \to -\infty$$

**Exercise 4.3.7**

Given the function $f(x) = 0.2(x-2)(x+1)(x-5)$, express the function as a polynomial in general form and determine the leading term, degree, and end behavior of the function.

**Answer**

The leading term is $0.2x^3$, so it is a degree 3 polynomial. As $x$ approaches positive infinity, $f(x)$ increases without bound; as $x$ approaches negative infinity, $f(x)$ decreases without bound.

## Identifying Local Behavior of Polynomial Functions

In addition to the end behavior of polynomial functions, we are also interested in what happens in the "middle" of the function. In particular, we are interested in locations where graph behavior changes. A **turning point** is a point at which the function values change from increasing to decreasing or decreasing to increasing.

We are also interested in the intercepts. As with all functions, the $y$-intercept is the point at which the graph intersects the vertical axis. The point corresponds to the coordinate pair in which the input value is zero. Because a polynomial is a function, only one output value corresponds to each input value so there can be only one $y$-intercept $(0, a_0)$. The $x$-intercepts occur at the input values that correspond to an output value of zero. It is possible to have more than one $x$-intercept. See Figure 4.3.10.





Figure 4.3.10

**Defintion: Intercepts and Turning Points of Polynomial Functions**

A **turning point** of a graph is a point at which the graph changes direction from increasing to decreasing or decreasing to increasing. The $y$-intercept is the point at which the function has an input value of zero. The $x$-intercepts are the points at which the output value is zero.

**How To: Given a polynomial function, determine the intercepts.**

1. Determine the $y$-intercept by setting $x = 0$ and finding the corresponding output value.
2. Determine the $x$-intercepts by solving for the input values that yield an output value of zero.

## Example 4.3.8: Determining the Intercepts of a Polynomial Function

Given the polynomial function $f(x) = (x-2)(x+1)(x-4)$ , written in factored form for your convenience, determine the $y$- and $x$-intercepts.

**Solution**

The $y$-intercept occurs when the input is zero, so substitute 0 for $x$.

$$\begin{aligned} f(0) &= (0-2)(0+1)(0-4) \\ &= (-2)(1)(-4) \\ &= 8 \end{aligned}$$

The $y$-intercept is $(0, 8)$.

The $x$-intercepts occur when the output is zero.

$$0 = (x-2)(x+1)(x-4)$$

$$\begin{aligned} x-2 &= 0 \quad \text{or} \quad x+1 = 0 \quad \text{or} \quad x-4 = 0 \\ x &= 2 \quad \text{or} \quad x = -1 \quad \text{or} \quad x = 4 \end{aligned}$$

The $x$-intercepts are $(2, 0)$,$(-1, 0)$, and $(4, 0)$.

We can see these intercepts on the graph of the function shown in Figure 4.3.11.





Figure 4.3.11: Graph of $f(x) = (x-2)(x+1)(x-4)$.

## Example 4.3.9: Determining the Intercepts of a Polynomial Function with Factoring

Given the polynomial function $f(x) = x^4 - 4x^2 - 45$ , determine the $y$- and $x$-intercepts.

**Solution**

The $y$-intercept occurs when the input is zero.

$$\begin{aligned} f(0) &= (0)^4 - 4(0)^2 - 45 \\ &= -45 \end{aligned}$$

The $y$-intercept is $(0, -45)$.

The $x$-intercepts occur when the output is zero. To determine when the output is zero, we will need to factor the polynomial.

$$\begin{aligned} f(x) &= x^4 - 4x^2 - 45 \\ &= (x^2 - 9)(x^2 + 5) \\ &= (x-3)(x+3)(x^2+5) \end{aligned}$$

$$0 = (x-3)(x+3)(x^2+5)$$

$$\begin{array}{lllll} x-3=0 & \text{or} & x+3=0 & \text{or} & x^2+5=0 \\ x=3 & \text{or} & x=-3 & \text{or} & \text{(no real solution)} \end{array}$$

The $x$-intercepts are $(3, 0)$ and $(-3, 0)$.

We can see these intercepts on the graph of the function shown in Figure 4.3.12 We can see that the function is even because $f(x) = f(-x)$.





Figure 4.3.12: Graph of $f(x) = x^4 - 4x^2 - 45$ .

**Exercise 4.3.5**

**4.3.5:** Given the polynomial function $f(x) = 2x^3 - 6x^2 - 20x$ , determine the $y$- and $x$-intercepts.

**Solution**

$y$-intercept $(0, 0)$; $x$-intercepts $(0, 0)$,$(-2, 0)$, and $(5, 0)$

## Comparing Smooth and Continuous Graphs

The degree of a polynomial function helps us to determine the number of $x$-intercepts and the number of turning points. A polynomial function of $n^{\text{th}}$ degree is the product of $n$ factors, so it will have at most $n$ roots or zeros, or $x$-intercepts. The graph of the polynomial function of degree $n$ must have at most $n-1$ turning points. This means the graph has at most one fewer turning point than the degree of the polynomial or one fewer than the number of factors.

A **continuous function** has no breaks in its graph: the graph can be drawn without lifting the pen from the paper. A smooth curve is a graph that has no sharp corners. The turning points of a smooth graph must always occur at rounded curves. The graphs of polynomial functions are both continuous and smooth.

### Intercepts and Turning Points of Polynomials

A polynomial of degree $n$ will have, at most, $n$ $x$-intercepts and $n-1$ turning points.

### Example 4.3.10: Determining the Number of Intercepts and Turning Points of a Polynomial

Without graphing the function, determine the local behavior of the function by finding the maximum number of $x$-intercepts and turning points for $f(x)=-3x^{10}+4x^7-x^4+2x^3$ .

**Solution**

The polynomial has a degree of **10**, so there are at most $n$ $x$-intercepts and at most $n-1$ turning points.

### Exercise 4.3.6

Without graphing the function, determine the maximum number of $x$-intercepts and turning points for $f(x)=108-13x^9-8x^4+14x^{12}+2x^3$

**Answer**

There are at most 12 $x$-intercepts and at most 11 turning points.

### Example 4.3.11: Drawing Conclusions about a Polynomial Function from the Graph

What can we conclude about the polynomial represented by the graph shown in Figure 4.3.12 based on its intercepts and turning points?





Figure 4.3.13.

**Solution**

The end behavior of the graph tells us this is the graph of an even-degree polynomial. See Figure 4.3.14


https://math.libretexts.org/@go/page/96287





Figure 4.3.14: Graph of an even-degree polynomial.

The graph has 2 $x$-intercepts, suggesting a degree of 2 or greater, and 3 turning points, suggesting a degree of 4 or greater. Based on this, it would be reasonable to conclude that the degree is even and at least 4.

## Exercise 4.3.7

What can we conclude about the polynomial represented by the graph shown in Figure 4.3.15 based on its intercepts and turning points?





**Figure 4.3.15.**

**Answer**

Add texts here. Do not delete this text first.

**Solution**

The end behavior indicates an odd-degree polynomial function; there are 3 $x$-intercepts and 2 turning points, so the degree is odd and at least 3. Because of the end behavior, we know that the lead coefficient must be negative.

### Example 4.3.12: Drawing Conclusions about a Polynomial Function from the Factors

Given the function $f(x) = -4x(x+3)(x-4)$, determine the local behavior.

**Solution**

The $y$-intercept is found by evaluating $f(0)$.

$$\begin{aligned} f(0) &= -4(0)(0+3)(0-4) \\ &= 0 \end{aligned}$$

The $y$-intercept is $(0, 0)$.

The $x$-intercepts are found by determining the zeros of the function.

$$\begin{aligned} 0 &= -4x(x+3)(x-4) \\ x &= 0 \quad \text{or} \quad x+3 = 0 \quad \text{or} \quad x-4 = 0 \\ x &= 0 \quad \text{or} \quad x = -3 \quad \text{or} \quad x = 4 \end{aligned}$$

The $x$-intercepts are $(0, 0)$,$(-3, 0)$, and $(4, 0)$.

The degree is 3 so the graph has at most 2 turning points.

### Exercise 4.3.8

Given the function $f(x) = 0.2(x-2)(x+1)(x-5)$, determine the local behavior.

**Answer**

The $x$-intercepts are $(2, 0)$, $(-1, 0)$, and $(5, 0)$, the $y$-intercept is $(0, 2)$, and the graph has at most 2 turning points.

## Key Equations

- general form of a polynomial function: $f(x) = a_n x^n + a_{n-1} x^{n-1} \ldots + a_2 x^2 + a_1 x + a_0$

## Key Concepts

- A power function is a variable base raised to a number power.
- The behavior of a graph as the input decreases without bound and increases without bound is called the end behavior.
- The end behavior depends on whether the power is even or odd.
- A polynomial function is the sum of terms, each of which consists of a transformed power function with positive whole number power.
- The degree of a polynomial function is the highest power of the variable that occurs in a polynomial. The term containing the highest power of the variable is called the leading term. The coefficient of the leading term is called the leading coefficient.
- The end behavior of a polynomial function is the same as the end behavior of the power function represented by the leading term of the function.
- A polynomial of degree $n$ will have at most $n$ $x$-intercepts and at most $n-1$ turning points.

## Glossary

**coefficient**

a nonzero real number that is multiplied by a variable raised to an exponent (only the number factor is the coefficient)

**continuous function**

a function whose graph can be drawn without lifting the pen from the paper because there are no breaks in the graph

**degree**

the highest power of the variable that occurs in a polynomial

**end behavior**

the behavior of the graph of a function as the input decreases without bound and increases without bound

**leading coefficient**

the coefficient of the leading term

**leading term**

the term containing the highest power of the variable

**polynomial function**

a function that consists of either zero or the sum of a finite number of non-zero terms, each of which is a product of a number, called the coefficient of the term, and a variable raised to a non-negative integer power.

**power function**

a function that can be represented in the form $f(x) = kx^p$ where $k$ is a constant, the base is a variable, and the exponent, $p$, is a constant

**smooth curve**

a graph with no sharp corners

**term of a polynomial function**

any $a_i x^i$ of a polynomial function in the form $f(x) = a_n x^n + a_{n-1} x^{n-1} \ldots + a_2 x^2 + a_1 x + a_0$

**turning point**

the location at which the graph of a function changes direction

---

This page titled 4.3: Power Functions and Polynomial Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.3: Power Functions and Polynomial Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.3E: Power Functions and Polynomial Functions (Exercises)

For the following exercises, determine if the function is a polynomial function and, if so, give the degree and leading coefficient.

7. $f(x) = 4x^5 - 3x^3 + 2x - 1$

8. $f(x) = 5^{x+1} - x^2$

9. $f(x) = x^2\left(3 - 6x + x^2\right)$

For the following exercises, determine end behavior of the polynomial function.

10. $f(x) = 2x^4 + 3x^3 - 5x^2 + 7$

11. $f(x) = 4x^3 - 6x^2 + 2$

12. $f(x) = 2x^2\left(1 + 3x - x^2\right)$

This page titled 4.3E: Power Functions and Polynomial Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **5.2E: Power Functions and Polynomial Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.4: Graphs of Polynomial Functions

**Learning Objectives**

- Recognize characteristics of graphs of polynomial functions.
- Use factoring to find zeros of polynomial functions.
- Identify zeros and their multiplicities.
- Determine end behavior.
- Understand the relationship between degree and turning points.
- Graph polynomial functions.
- Use the Intermediate Value Theorem.

The revenue in millions of dollars for a fictional cable company from 2006 through 2013 is shown in Table 4.4.1.

Table 4.4.1

| **Year** | 2006 | 2007 | 2008 | 2009 | 2010 | 2011 | 2012 | 2013 |
|---|---|---|---|---|---|---|---|---|
| **Revenues** | 52.4 | 52.8 | 51.2 | 49.5 | 48.6 | 48.6 | 48.7 | 47.1 |

The revenue can be modeled by the polynomial function

$$R(t) = -0.037t^4 + 1.414t^3 - 19.777t^2 + 118.696t - 205.332 \tag{4.4.1}$$

where $R$ represents the revenue in millions of dollars and $t$ represents the year, with $t = 6$ corresponding to 2006. Over which intervals is the revenue for the company increasing? Over which intervals is the revenue for the company decreasing? These questions, along with many others, can be answered by examining the graph of the polynomial function. We have already explored the local behavior of quadratics, a special case of polynomials. In this section we will explore the local behavior of polynomials in general.

## Recognizing Characteristics of Graphs of Polynomial Functions

Polynomial functions of degree 2 or more have graphs that do not have sharp corners; recall that these types of graphs are called smooth curves. Polynomial functions also display graphs that have no breaks. Curves with no breaks are called continuous. Figure 4.4.1 shows a graph that represents a **polynomial function** and a graph that represents a function that is not a polynomial.





Figure 4.4.1: Graph of $f(x) = x^3 - 0.01x$.

**Example 4.4.1: Recognizing Polynomial Functions**

Which of the graphs in Figure 4.4.2 represents a polynomial function?





***Figure* 4.4.2**

**Solution**

- The graphs of $f$ and $h$ are graphs of polynomial functions. They are smooth and **continuous**.
- The graphs of $g$ and $k$ are graphs of functions that are not polynomials. The graph of function $g$ has a sharp corner. The graph of function $k$ is not continuous.

Q&A

Do all polynomial functions have as their domain all real numbers?

- Yes. Any real number is a valid input for a polynomial function.

## Using Factoring to Find Zeros of Polynomial Functions

Recall that if $f$ is a polynomial function, the values of $x$ for which $f(x) = 0$ are called **zeros** of $f$. If the equation of the polynomial function can be factored, we can set each factor equal to zero and solve for the zeros.

We can use this method to find x-intercepts because at the x-intercepts we find the input values when the output value is zero. For general polynomials, this can be a challenging prospect. While quadratics can be solved using the relatively simple quadratic formula, the corresponding formulas for cubic and fourth-degree polynomials are not simple enough to remember, and formulas do not exist for general higher-degree polynomials. Consequently, we will limit ourselves to three cases in this section:

The polynomial can be factored using known methods: greatest common factor and trinomial factoring.
The polynomial is given in factored form.
Technology is used to determine the intercepts.

HOwTO: Given a polynomial function $f$, find the x-intercepts by factoring

1. Set $f(x) = 0$.
2. If the polynomial function is not given in factored form:
   a. Factor out any common monomial factors.
   b. Factor any factorable binomials or trinomials.
3. Set each factor equal to zero and solve to find the x-intercepts.

## Example 4.4.2: Finding the x-Intercepts of a Polynomial Function by Factoring

Find the x-intercepts of $f(x) = x^6 - 3x^4 + 2x^2$ .

**Solution**

We can attempt to factor this polynomial to find solutions for $f(x) = 0$.

$$\begin{aligned} x^6 - 3x^4 + 2x^2 &= 0 && \text{Factor out the greatest common factor.} \\ x^2(x^4 - 3x^2 + 2) &= 0 && \text{Factor the trinomial.} \\ x^2(x^2 - 1)(x^2 - 2) &= 0 && \text{Set each factor equal to zero.} \end{aligned}$$

$$\begin{aligned} x^2 &= 0 \quad & (x^2 - 1) &= 0 \quad & (x^2 - 2) &= 0 \\ x^2 &= 0 \quad \text{or} \quad & x^2 &= 1 \quad \text{or} \quad & x^2 &= 2 \\ x &= 0 & x &= \pm 1 & x &= \pm\sqrt{2} \end{aligned}$$

.

This gives us five x-intercepts: $(0, 0)$, $(1, 0)$, $(-1, 0)$, $(\sqrt{2}, 0)$,and $(-\sqrt{2}, 0)$ (Figure 4.4.3). We can see that this is an even function.





Figure 4.4.3.

## Example 4.4.3: Finding the x-Intercepts of a Polynomial Function by Factoring

Find the x-intercepts of $f(x) = x^3 - 5x^2 - x + 5$ .

**Solution**

Find solutions for $f(x) = 0$ by factoring.

$$\begin{aligned} x^3 - 5x^2 - x + 5 &= 0 && \text{Factor by grouping.} \\ x^2(x - 5) - (x - 5) &= 0 && \text{Factor out the common factor.} \\ (x^2 - 1)(x - 5) &= 0 && \text{Factor the difference of squares.} \\ (x + 1)(x - 1)(x - 5) &= 0 && \text{Set each factor equal to zero.} \end{aligned}$$

$$\begin{aligned} x + 1 &= 0 \quad & x - 1 &= 0 \quad & x - 5 &= 0 \\ x &= -1 \quad \text{or} \quad & x &= 1 \quad \text{or} \quad & x &= 5 \end{aligned}$$

There are three x-intercepts: $(-1, 0)$, $(1, 0)$, and $(5, 0)$ (Figure 4.4.4).





Figure 4.4.4: Graph of $f(x)$.

## Example 4.4.4: Finding the y- and x-Intercepts of a Polynomial in Factored Form

Find the y- and x-intercepts of $g(x) = (x-2)^2(2x+3)$ .

**Solution**

The y-intercept can be found by evaluating $g(0)$.

$$\begin{aligned} g(0) &= (0-2)^2(2(0)+3) \\ &= 12 \end{aligned}$$

So the y-intercept is $(0, 12)$.

The x-intercepts can be found by solving $g(x) = 0$.

$$(x-2)^2(2x+3) = 0 \tag{4.4.2}$$

$$\begin{aligned} (x-2)^2 &= 0 \qquad\qquad (2x+3) = 0 \\ x-2 &= 0 \quad \text{or} \quad x = -\frac{3}{2} \\ x &= 2 \end{aligned}$$

So the x-intercepts are $(2, 0)$ and $\left(-\frac{3}{2}, 0\right)$.

**Analysis**

We can always check that our answers are reasonable by using a graphing calculator to graph the polynomial as shown in Figure 4.4.5.





Figure 4.4.5: Graph of $g(x)$.

## Example 4.4.5: Finding the x-Intercepts of a Polynomial Function Using a Graph

Find the x-intercepts of $h(x) = x^3 + 4x^2 + x - 6$ .

**Solution**

This polynomial is not in factored form, has no common factors, and does not appear to be factorable using techniques previously discussed. Fortunately, we can use technology to find the intercepts. Keep in mind that some values make graphing difficult by hand. In these cases, we can take advantage of graphing utilities.

Looking at the graph of this function, as shown in Figure 4.4.6, it appears that there are x-intercepts at $x = -3, -2, \text{ and } 1$.





Figure 4.4.6: Graph of $h(x)$.

We can check whether these are correct by substituting these values for $x$ and verifying that

$$h(-3) = h(-2) = h(1) = 0.$$

Since $h(x) = x^3 + 4x^2 + x - 6$ , we have:

$$\begin{aligned} h(-3) &= (-3)^3+4(-3)^2+(-3)-6=-27+36-3-6=0 \\ h(-2) &= (-2)^3+4(-2)^2+(-2)-6=-8+16-2-6=0 \\ h(1) &= (1)^3+4(1)^2+(1)-6=1+4+1-6=0 \end{aligned}$$

Each x-intercept corresponds to a zero of the polynomial function and each zero yields a factor, so we can now write the polynomial in factored form.

$$\begin{aligned} h(x) &= x^3+4x^2+x-6 \\ &= (x+3)(x+2)(x-1) \end{aligned}$$

**Exercise 4.4.1**

Find the y-and x-intercepts of the function $f(x)=x^4-19x^2+30x$ .

**Answer**

- y-intercept $(0,0)$;
- x-intercepts $(0,0)$, $(-5,0)$, $(2,0)$, and $(3,0)$

## Identifying Zeros and Their Multiplicities

Graphs behave differently at various x-intercepts. Sometimes, the graph will cross over the horizontal axis at an intercept. Other times, the graph will touch the horizontal axis and bounce off. Suppose, for example, we graph the function

$$f(x)=(x+3)(x-2)^2(x+1)^3. \tag{4.4.3}$$

Notice in Figure 4.4.7 that the behavior of the function at each of the x-intercepts is different.





Figure 4.4.7: Identifying the behavior of the graph at an x-intercept by examining the multiplicity of the zero.

The x-intercept −3 is the solution of equation $(x+3)=0$ . The graph passes directly through thex-intercept at $x=-3$. The factor is linear (has a degree of 1), so the behavior near the intercept is like that of a line—it passes directly through the intercept. We call this a single zero because the zero corresponds to a single factor of the function.

The x-intercept 2 is the repeated solution of equation $(x-2)^2=0$ . The graph touches the axis at the intercept and changes direction. The factor is quadratic (degree 2), so the behavior near the intercept is like that of a quadratic—it bounces off of the horizontal axis at the intercept.

$$(x-2)^2=(x-2)(x-2) \tag{4.4.4}$$

The factor is repeated, that is, the factor $(x-2)$ appears twice. The number of times a given factor appears in the factored form of the equation of a polynomial is called the **multiplicity**. The zero associated with this factor, $x=2$, has multiplicity 2 because the factor $(x-2)$ occurs twice.

The x-intercept −1 is the repeated solution of factor $(x+1)^3=0$ .The graph passes through the axis at the intercept, but flattens out a bit first. This factor is cubic (degree 3), so the behavior near the intercept is like that of a cubic—with the same S-shape near

the intercept as the toolkit function $f(x) = x^3$. We call this a triple zero, or a zero with multiplicity 3.

For **zeros** with even multiplicities, the graphs touch or are tangent to the x-axis. For zeros with odd multiplicities, the graphs cross or intersect the x-axis. See Figure 4.4.8 for examples of graphs of polynomial functions with multiplicity 1, 2, and 3.





Figure 4.4.8: Three graphs showing three different polynomial functions with multiplicity 1, 2, and 3.

For higher even powers, such as 4, 6, and 8, the graph will still touch and bounce off of the horizontal axis but, for each increasing even power, the graph will appear flatter as it approaches and leaves the x-axis.

For higher odd powers, such as 5, 7, and 9, the graph will still cross through the horizontal axis, but for each increasing odd power, the graph will appear flatter as it approaches and leaves the x-axis.

### Graphical Behavior of Polynomials at x-Intercepts

If a polynomial contains a factor of the form $(x-h)^p$, the behavior near the x-intercepth is determined by the power $p$. We say that $x = h$ is a zero of **multiplicity** $p$.

The graph of a polynomial function will touch the x-axis at zeros with even multiplicities. The graph will cross the x-axis at zeros with odd multiplicities.

The sum of the multiplicities is the degree of the polynomial function.

### HOWTO: Given a graph of a polynomial function of degree $n$, identify the zeros and their multiplicities

1. If the graph crosses the x-axis and appears almost linear at the intercept, it is a single zero.
2. If the graph touches the x-axis and bounces off of the axis, it is a zero with even multiplicity.
3. If the graph crosses the x-axis at a zero, it is a zero with odd multiplicity.
4. The sum of the multiplicities is $n$.

### Example 4.4.6: Identifying Zeros and Their Multiplicities

Use the graph of the function of degree 6 in Figure 4.4.9 to identify the zeros of the function and their possible multiplicities.





Figure 4.4.9: Graph of a polynomial function with degree 5.

**Solution**

The polynomial function is of degree $n$. The sum of the multiplicities must be $n$.

Starting from the left, the first zero occurs at $x = -3$. The graph touches the x-axis, so the multiplicity of the zero must be even. The zero of −3 has multiplicity 2.

The next zero occurs at $x = -1$. The graph looks almost linear at this point. This is a single zero of multiplicity 1.

The last zero occurs at $x = 4$.The graph crosses the x-axis, so the multiplicity of the zero must be odd. We know that the multiplicity is likely 3 and that the sum of the multiplicities is likely 6.

**Exercise 4.4.2**

Use the graph of the function of degree 5 in Figure 4.4.10to identify the zeros of the function and their multiplicities.





***Figure* 4.4.10*:*** *Graph of a polynomial function with degree 5.*

**Answer**

The graph has a zero of –5 with multiplicity 1, a zero of –1 with multiplicity 2, and a zero of 3 with even multiplicity.

## Determining End Behavior

As we have already learned, the behavior of a graph of a polynomial function of the form

$$f(x) = a_n x^n + a_{n-1} x^{n-1} + \ldots + a_1 x + a_0 \tag{4.4.5}$$

will either ultimately rise or fall as $x$ increases without bound and will either rise or fall as $x$ decreases without bound. This is because for very large inputs, say 100 or 1,000, the leading term dominates the size of the output. The same is true for very small inputs, say –100 or –1,000.

Recall that we call this behavior the end behavior of a function. As we pointed out when discussing quadratic equations, when the leading term of a polynomial function, $a_n x^n$, is an even power function, as $x$ increases or decreases without bound, $f(x)$ increases without bound. When the leading term is an odd power function, as $x$ decreases without bound, $f(x)$ also decreases without bound; as $x$ increases without bound, $f(x)$ also increases without bound. If the leading term is negative, it will change the direction of the end behavior. Figure $4.4.11$ summarizes all four cases.





Figure 4.4.11.

## Understanding the Relationship between Degree and Turning Points

In addition to the end behavior, recall that we can analyze a polynomial function's local behavior. It may have a turning point where the graph changes from increasing to decreasing (rising to falling) or decreasing to increasing (falling to rising). Look at the graph of the polynomial function $f(x) = x^4 - x^3 - 4x^2 + 4x$ in Figure $4.4.12$ The graph has three turning points.





Figure 4.4.12: Graph of $f(x) = x^4 - x^3 - 4x^2 + 4x$

This function $f$ is a 4th degree polynomial function and has 3 turning points. The maximum number of turning points of a polynomial function is always one less than the degree of the function.

**Definition: Interpreting Turning Points**

A turning point is a point of the graph where the graph changes from increasing to decreasing (rising to falling) or decreasing to increasing (falling to rising). A polynomial of degree $n$ will have at most $n-1$ turning points.

**Example 4.4.7: Finding the Maximum Number of Turning Points Using the Degree of a Polynomial Function**

Find the maximum number of turning points of each polynomial function.

a. $f(x) = -x^3 + 4x^5 - 3x^2 + 1$
b. $f(x) = -(x-1)^2(1+2x^2)$

**Solution**

a. $f(x) = -x^3 + 4x^5 - 3x^2 + 1$

First, rewrite the polynomial function in descending order: $f(x) = 4x^5 - x^3 - 3x^2 + 1$

Identify the degree of the polynomial function. This polynomial function is of degree 5.

The maximum number of turning points is $5 - 1 = 4$.

b. $f(x) = -(x-1)^2(1+2x^2)$

First, identify the leading term of the polynomial function if the function were expanded.

$$f(x) = -(x-1)^2\ (1+2x^2)$$
$$a_n = -(x^2)\ (2x^2) - 2x^4$$

Then, identify the degree of the polynomial function. This polynomial function is of degree 4.

The maximum number of turning points is $4 - 1 = 3$.

## Graphing Polynomial Functions

We can use what we have learned about multiplicities, end behavior, and turning points to sketch graphs of polynomial functions. Let us put this all together and look at the steps required to graph polynomial functions.

**Howto: Given a polynomial function, sketch the graph**

1. Find the intercepts.
2. Check for symmetry. If the function is an even function, its graph is symmetrical about the y-axis, that is, $f(-x) = f(x)$. If a function is an odd function, its graph is symmetrical about the origin, that is, $f(-x) = -f(x)$.
3. Use the multiplicities of the zeros to determine the behavior of the polynomial at the x-intercepts.

4. Determine the end behavior by examining the leading term.
5. Use the end behavior and the behavior at the intercepts to sketch a graph.
6. Ensure that the number of turning points does not exceed one less than the degree of the polynomial.
7. Optionally, use technology to check the graph.

## Example 4.4.8: Sketching the Graph of a Polynomial Function

Sketch a graph of $f(x) = -2(x+3)^2(x-5)$.

**Solution**

This graph has two x-intercepts. At $x = -3$, the factor is squared, indicating a multiplicity of 2. The graph will bounce at this x-intercept. At $x = 5$,the function has a multiplicity of one, indicating the graph will cross through the axis at this intercept.

The y-intercept is found by evaluating $f(0)$.

$$\begin{aligned} f(0) &= -2(0+3)^2(0-5) \\ &= -2 \cdot 9 \cdot (-5) \\ &= 90 \end{aligned}$$

The y-intercept is $(0, 90)$.

Additionally, we can see the leading term, if this polynomial were multiplied out, would be $-2x3$, so the end behavior is that of a vertically reflected cubic, with the outputs decreasing as the inputs approach infinity, and the outputs increasing as the inputs approach negative infinity. See Figure 4.4.13





Figure 4.4.13: Showing the distribution for the leading term.

To sketch this, we consider that:

- As $x \to -\infty$ the function $f(x) \to \infty$,so we know the graph starts in the second quadrant and is decreasing toward the x-axis.
- Since $f(-x) = -2(-x+3)^2(-x-5)$ is not equal to $f(x)$, the graph does not display symmetry.
- At $(-3, 0)$, the graph bounces off of thex-axis, so the function must start increasing.
- At $(0, 90)$, the graph crosses the y-axis at the y-intercept. See Figure 4.4.14





Figure 4.4.14: Graph of the end behavior and intercepts, $(-3,0)$ and $(0,90)$, for the function $f(x)=-2(x+3)^2(x-5)$.

Somewhere after this point, the graph must turn back down or start decreasing toward the horizontal axis because the graph passes through the next intercept at $(5,0)$. See Figure 4.4.15.





Figure 4.4.15: Graph of the end behavior and intercepts, $(-3,0)$, $(0,90)$ and $(5,0)$, for the function $f(x)=-2(x+3)^2(x-5)$.

As $x\to\infty$ the function $f(x)\to-\infty$,

so we know the graph continues to decrease, and we can stop drawing the graph in the fourth quadrant.

Using technology, we can create the graph for the polynomial function, shown in Figure 4.4.16, and verify that the resulting graph looks like our sketch in Figure 4.4.15.





***Figure* 4.4.16:** *The complete graph of the polynomial function* $f(x)=-2(x+3)^2(x-5)$.


https://math.libretexts.org/@go/page/96289

**Exercise 4.4.8**

Sketch a graph of $f(x) = \frac{1}{4}x(x-1)^4(x+3)^3$.

**Answer**





Figure 4.4.17: Graph of $f(x) = \frac{1}{4}x(x-1)^4(x+3)^3$

## Using the Intermediate Value Theorem

In some situations, we may know two points on a graph but not the zeros. If those two points are on opposite sides of the x-axis, we can confirm that there is a zero between them. Consider a polynomial function $f$ whose graph is smooth and continuous. The **Intermediate Value Theorem** states that for two numbers $a$ and $b$ in the domain of $f$,if $a < b$ and $f(a) \neq f(b)$,then the function $f$ takes on every value between $f(a)$ and $f(b)$. We can apply this theorem to a special case that is useful in graphing polynomial functions. If a point on the graph of a continuous function $f$ at $x = a$ lies above the x-axis and another point at $x = b$ lies below thex-axis, there must exist a third point between $x = a$ and $x = b$ where the graph crosses the x-axis. Call this point $(c, f(c))$.This means that we are assured there is a solution $c$ where $f(c) = 0$.

In other words, the **Intermediate Value Theorem** tells us that when a polynomial function changes from a negative value to a positive value, the function must cross the x-axis. Figure $4.4.18$shows that there is a zero between $a$ and $b$.





Figure 4.4.18: Using the Intermediate Value Theorem to show there exists a zero.

**Definition: Intermediate Value Theorem**

Let $f$ be a polynomial function. The **Intermediate Value Theorem** states that if $f(a)$ and $f(b)$ have opposite signs, then there exists at least one value $c$ between $a$ and $b$ for which $f(c) = 0$.

## Example 4.4.9: Using the Intermediate Value Theorem

Show that the function $f(x) = x^3 - 5x^2 + 3x + 6$ has at least two real zeros between $x = 1$ and $x = 4$.

**Solution**

As a start, evaluate $f(x)$ at the integer values $x = 1,\ 2,\ 3,$ and $4$ (Table 4.4.2).

Table 4.4.2

| $x$ | 1 | 2 | 3 | 4 |
|---|---|---|---|---|
| $f(x)$ | 5 | 0 | -3 | 2 |

We see that one zero occurs at $x = 2$. Also, since $f(3)$ is negative and $f(4)$ is positive, by the Intermediate Value Theorem, there must be at least one real zero between 3 and 4.

We have shown that there are at least two real zeros between $x = 1$ and $x = 4$.

**Analysis**

We can also see on the graph of the function in Figure 4.4.19 that there are two real zeros between $x = 1$ and $x = 4$.





Figure 4.4.19.

## Exercise 4.4.4

Show that the function $f(x) = 7x^5 - 9x^4 - x^2$ has at least one real zero between $x = 1$ and $x = 2$.

**Answer**

Because $f$ is a polynomial function and since $f(1)$ is negative and $f(2)$ is positive, there is at least one real zero between $x = 1$ and $x = 2$.

## Writing Formulas for Polynomial Functions

Now that we know how to find zeros of polynomial functions, we can use them to write formulas based on graphs. Because a **polynomial function** written in factored form will have an x-intercept where each factor is equal to zero, we can form a function

that will pass through a set of x-intercepts by introducing a corresponding set of factors.

**Note: Factored Form of Polynomials**

If a polynomial of lowest degree $p$ has horizontal intercepts at $x = x_1, x_2, \ldots, x_n$, then the polynomial can be written in the factored form: $f(x) = a(x - x_1)^{p_1}(x - x_2)^{p_2} \cdots (x - x_n)^{p_n}$ where the powers $p_i$ on each factor can be determined by the behavior of the graph at the corresponding intercept, and the stretch factor $a$ can be determined given a value of the function other than the x-intercept.

**How To: Given a graph of a polynomial function, write a formula for the function.**

1. Identify the x-intercepts of the graph to find the factors of the polynomial.
2. Examine the behavior of the graph at the x-intercepts to determine the multiplicity of each factor.
3. Find the polynomial of least degree containing all the factors found in the previous step.
4. Use any other point on the graph (the y-intercept may be easiest) to determine the stretch factor.

**Example 4.4.10: Writing a Formula for a Polynomial Function from the Graph**

Write a formula for the polynomial function shown in Figure 4.4.20.





Figure 4.4.20.

**Solution**

This graph has three x-intercepts: $x = -3,\ 2,$ and $5$. The y-intercept is located at $(0, 2)$.At $x = -3$ and $x = 5$, the graph passes through the axis linearly, suggesting the corresponding factors of the polynomial will be linear. At $x = 2$, the graph bounces at the intercept, suggesting the corresponding factor of the polynomial will be second degree (quadratic). Together, this gives us

$$f(x) = a(x+3)(x-2)^2(x-5) \tag{4.4.6}$$

To determine the stretch factor, we utilize another point on the graph. We will use the y-intercept $(0, -2)$, to solve for $a$.

$$\begin{aligned} f(0) &= a(0+3)(0-2)^2(0-5) \\ -2 &= a(0+3)(0-2)^2(0-5) \\ -2 &= -60a \\ a &= \frac{1}{30} \end{aligned}$$

The graphed polynomial appears to represent the function $f(x) = \frac{1}{30}(x+3)(x-2)^2(x-5)$ .

**Exercise 4.4.5**

Given the graph shown in Figure 4.4.21, write a formula for the function shown.





Figure 4.4.21.

**Answer**

$f(x) = -\frac{1}{8}(x-2)^3(x+1)^2(x-4)$

## Using Local and Global Extrema

With quadratics, we were able to algebraically find the maximum or minimum value of the function by finding the vertex. For general polynomials, finding these turning points is not possible without more advanced techniques from calculus. Even then, finding where extrema occur can still be algebraically challenging. For now, we will estimate the locations of turning points using technology to generate a graph.

Each turning point represents a local minimum or maximum. Sometimes, a turning point is the highest or lowest point on the entire graph. In these cases, we say that the turning point is a **global maximum** or a **global minimum**. These are also referred to as the absolute maximum and absolute minimum values of the function.

**Note: Local and Global Extrema**

A **local maximum** or **local minimum** at $x = a$ (sometimes called the relative maximum or minimum, respectively) is the output at the highest or lowest point on the graph in an open interval around $x = a$.If a function has a local maximum at $a$, then $f(a) \geq f(x)$for all $x$ in an open interval around $x = a$. If a function has a local minimum at $a$, then $f(a) \leq f(x)$for all $x$ in an open interval around $x = a$.

A **global maximum** or **global minimum** is the output at the highest or lowest point of the function. If a function has a global maximum at $a$, then $f(a) \geq f(x)$ for all $x$. If a function has a global minimum at $a$, then $f(a) \leq f(x)$ for all $x$.

We can see the difference between local and global extrema in Figure 4.4.22





Figure 4.4.22: Graph of an even-degree polynomial that denotes the local maximum and minimum and the global maximum.

**Do all polynomial functions have a global minimum or maximum?**

*No. Only polynomial functions of even degree have a global minimum or maximum. For example, $f(x) = x$ has neither a global maximum nor a global minimum.*

## Example 4.4.11: Using Local Extrema to Solve Applications

An open-top box is to be constructed by cutting out squares from each corner of a 14 cm by 20 cm sheet of plastic then folding up the sides. Find the size of squares that should be cut out to maximize the volume enclosed by the box.

**Solution**

We will start this problem by drawing a picture like that in Figure 4.4.23, labeling the width of the cut-out squares with a variable, $w$.





Figure 4.4.23: Diagram of a rectangle with four squares at the corners.

Notice that after a square is cut out from each end, it leaves $a(14-2w)$ cm by $(20-2w)$ cm rectangle for the base of the box, and the box will be $w$ cm tall. This gives the volume

$$\begin{aligned} V(w) &= (20-2w)(14-2w)w \\ &= 280w - 68w^2 + 4w^3 \end{aligned}$$

Notice, since the factors are $20-2w$, $14-2w$, and $w$, the three zeros are $10$, $7$, and $0$, $)respectively. Becauseaheightof\(0$ cm is not reasonable, we consider the only the zeros $10$ and $7$. The shortest side is $14$ and we are cutting off two squares, so values $w$ may take on are greater than zero or less than $7$. This means we will restrict the domain of this function to $0 < w < 7$.Using technology to sketch the graph of $V(w)$ on this reasonable domain, we get a graph like that in Figure 4.4.24 We can use this graph to estimate the maximum value for the volume, restricted to values for $w$ that are reasonable for this problem—values from 0 to 7.





Figure 4.4.24: Graph of $V(w) = (20 - 2w)(14 - 2w)w$

From this graph, we turn our focus to only the portion on the reasonable domain, $[0, 7]$. We can estimate the maximum value to be around 340 cubic cm, which occurs when the squares are about 2.75 cm on each side. To improve this estimate, we could use advanced features of our technology, if available, or simply change our window to zoom in on our graph to produce Figure 4.4.25.





Figure 4.4.25: Graph of $V(w) = (20 - 2w)(14 - 2w)w$.

From this zoomed-in view, we can refine our estimate for the maximum volume to about 339 cubic cm, when the squares measure approximately 2.7 cm on each side.

## Exercise 4.4.1

Use technology to find the maximum and minimum values on the interval $[-1, 4]$ of the function $f(x) = -0.2(x - 2)^3(x + 1)^2(x - 4)$.

**Answer**

The minimum occurs at approximately the point $(0, -6.5)$,
and the maximum occurs at approximately the point $(3.5, 7)$.

## Key Concepts

- Polynomial functions of degree 2 or more are smooth, continuous functions.
- To find the zeros of a polynomial function, if it can be factored, factor the function and set each factor equal to zero.
- Another way to find the x-intercepts of a polynomial function is to graph the function and identify the points at which the graph crosses the x-axis.
- The multiplicity of a zero determines how the graph behaves at the x-intercepts.
- The graph of a polynomial will cross the horizontal axis at a zero with odd multiplicity.
- The graph of a polynomial will touch the horizontal axis at a zero with even multiplicity.

- The end behavior of a polynomial function depends on the leading term.
- The graph of a polynomial function changes direction at its turning points.
- A polynomial function of degree $n$ has at most $n-1$ turning points.
- To graph polynomial functions, find the zeros and their multiplicities, determine the end behavior, and ensure that the final graph has at most $n-1$ turning points.
- Graphing a polynomial function helps to estimate local and global extremas.
- The Intermediate Value Theorem tells us that if $f(a)$ and $f(b)$ have opposite signs, then there exists at least one value $c$ between $a$ and $b$ for which $f(c)=0$.

## Glossary

**global maximum**
highest turning point on a graph; $f(a)$ where $f(a) \geq f(x)$ for all $x$.

**global minimum**
lowest turning point on a graph; $f(a)$ where $f(a) \leq f(x)$ for all $x$.

**Intermediate Value Theorem**
for two numbers $a$ and $b$ in the domain of $f$, if $a<b$ and $f(a) \neq f(b)$, then the functionf takes on every value between $f(a)$ and $f(b)$; specifically, when a polynomial function changes from a negative value to a positive value, the function must cross the x-axis

**multiplicity**
the number of times a given factor appears in the factored form of the equation of a polynomial; if a polynomial contains a factor of the form $(x-h)^p$, $x=h$ is a zero of multiplicity $p$.

---

This page titled 4.4: Graphs of Polynomial Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.4: Graphs of Polynomial Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.4E: Graphs of Polynomial Functions (Exercises)

For the following exercises, find all zeros of the polynomial function, noting multiplicities.


13. $f(x) = (x+3)^2(2x-1)(x+1)^3$

14. $f(x) = x^5 + 4x^4 + 4x^3$


15. $f(x) = x^3 - 4x^2 + x - 4$

For the following exercises, based on the given graph, determine the zeros of the function and note multiplicity.

16.




17.




18.

Use the Intermediate Value Theorem to show that at least one zero lies between 2 and 3 for the function

$$f(x) = x^3 - 5x + 1$$

This page titled 4.4E: Graphs of Polynomial Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **5.3E: Graphs of Polynomial Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.5: Dividing Polynomials

**Learning Objectives**

- Use long division to divide polynomials.
- Use synthetic division to divide polynomials.

The exterior of the Lincoln Memorial in Washington, D.C., is a large rectangular solid with length $61.5$ meters (m), width $40$ m, and height $30$ m.[1]

We can easily find the volume using elementary geometry.

$$\begin{aligned} V &= l \cdot w \cdot h \\ &= 61.5 \cdot 40 \cdot 30 \\ &= 73,800 \end{aligned}$$

So the volume is $73,800$ cubic meters ($m^3$).



Figure 4.5.1: Lincoln Memorial, Washington, D.C. (credit: Ron Cogswell, Flickr)

Suppose we knew the volume, length, and width. We could divide to find the height.

$$\begin{aligned} h &= \frac{V}{l \cdot w} \\ &= \frac{73,800}{61.5 \cdot 40} \\ &= 30 \end{aligned}$$

As we can confirm from the dimensions above, the height is 30 m. We can use similar methods to find any of the missing dimensions. We can also use the same method if any or all of the measurements contain variable expressions. For example, suppose the volume of a rectangular solid is given by the polynomial $3x^4 - 3x^3 - 33x^2 + 54x$ . The length of the solid is given by $3x$; the width is given by $x - 2$.

To find the height of the solid, we can use polynomial division, which is the focus of this section.

## Using Long Division to Divide Polynomials

We are familiar with the **long division** algorithm for ordinary arithmetic. We begin by dividing into the digits of the dividend that have the greatest place value. We divide, multiply, subtract, include the digit in the next place value position, and repeat. For example, let's divide 178 by 3 using long division.

**Long Division**

$$\begin{array}{r} 59 \\ 3\overline{)178} \\ \underline{-15}\downarrow \\ 28 \\ \underline{-27} \\ 1 \end{array}$$

Step 1: $5 \times 3 = 15$ and $17 - 15 = 2$
Step 2: Bring down the 8
Step 3: $9 \times 3 = 27$ and $28 - 27 = 1$

Answer: $59\,R\,1$ or $59\frac{1}{3}$

Another way to look at the solution is as a sum of parts. This should look familiar, since it is the same method used to check division in elementary arithmetic.

$$\begin{aligned}\text{dividend} &= (\text{divisor}\cdot\text{quotient})+\text{remainder}\\ 178 &= (3\cdot 59)+1\\ &= 177+1\\ &= 178\end{aligned}$$

We call this the **Division Algorithm** and will discuss it more formally after looking at an example.

Division of polynomials that contain more than one term has similarities to long division of whole numbers. We can write a polynomial dividend as the product of the divisor and the quotient added to the remainder. The terms of the polynomial division correspond to the digits (and place values) of the whole number division. This method allows us to divide two polynomials. For example, if we were to divide $2x^3-3x^2+4x+5$ by $x+2$ using the long division algorithm, it would look like this:

$$\begin{array}{rl}
x+2\overline{)2x^3-3x^2+4x+5} & \text{Set up the division problem.}\\[2ex]
\phantom{x+2\overline{)}}2x^2 & 2x^3 \text{ divided by } x \text{ is } 2x^2.\\
x+2\overline{)2x^3-3x^2+4x+5} & \\[2ex]
\phantom{x+2\overline{)}}2x^2 & \\
x+2\overline{)2x^3-3x^2+4x+5} & \\
\underline{-\left(2x^3+4x^2\right)\phantom{+5}} & \text{Multiply } x+2 \text{ by } 2x^2 \text{ and subtract.}\\
\phantom{-(}-7x^2+4x & \text{Bring down the next term.}\\[2ex]
\phantom{x+2\overline{)}}2x^2-7x & -7x^2 \text{ divided by } x \text{ is } -7x.\\
x+2\overline{)2x^3-3x^2+4x+5} & \\
\underline{-\left(2x^3+4x^2\right)\phantom{+5}} & \\
\phantom{-(}-7x^2+4x & \\
\underline{\phantom{-(}-\left(-7x^2-14x\right)} & \text{Multiply } x+2 \text{ by } -7x.\\
\phantom{-(-}18x+5 & \text{Subtract and bring down the next term.}\\[2ex]
\phantom{x+2\overline{)}}2x^2-7x+18 & 18x \text{ divided by } x \text{ is } 18.\\
x+2\overline{)2x^3-3x^2+4x+5} & \\
\underline{-\left(2x^3+4x^2\right)\phantom{+5}} & \\
\phantom{-(}-7x^2+4x & \\
\underline{\phantom{-(}-\left(-7x^2-14x\right)} & \\
\phantom{-(-}18x+\ \ 5 & \\
\underline{\phantom{-(-}-(18x+36)} & \text{Multiply } x+2 \text{ by } 18.\\
\phantom{-(-}-31 & \text{Subtract.}
\end{array}$$

We have found

$$\frac{2x^3-3x^2+4x+5}{x+2}=2x^2-7x+18-\frac{31}{x+2}$$

or

$$2x^3-3x^2+4x+5=(x+2)(2x^2-7x+18)-31$$

We can identify the dividend, the **divisor**, the **quotient**, and the **remainder**.

Writing the result in this manner illustrates the Division Algorithm.

## The Division Algorithm

The Division Algorithm states that, given a polynomial dividend $f(x)$ and a non-zero polynomial divisor $d(x)$ where the degree of $d(x)$ is less than or equal to the degree of $f(x)$, there exist unique polynomials $q(x)$ and $r(x)$ such that

$$f(x) = d(x)q(x) + r(x) \tag{4.5.1}$$

$q(x)$ is the quotient and $r(x)$ is the remainder. The remainder is either equal to zero or has degree strictly less than $d(x)$.

If $r(x) = 0$, then $d(x)$ divides evenly into $f(x)$. This means that, in this case, both $d(x)$ and $q(x)$ are factors of $f(x)$.

## Given a polynomial and a binomial, use long division to divide the polynomial by the binomial

1. Set up the division problem.
2. Determine the first term of the quotient by dividing the leading term of the dividend by the leading term of the divisor.
3. Multiply the answer by the divisor and write it below the like terms of the dividend.
4. Subtract the bottom **binomial** from the top binomial.
5. Bring down the next term of the dividend.
6. Repeat steps 2–5 until reaching the last term of the dividend.
7. If the remainder is non-zero, express as a fraction using the divisor as the denominator.

## Example 4.5.1: Using Long Division to Divide a Second-Degree Polynomial

Divide $5x^2 + 3x - 2$ by $x + 1$.

**Solution**

| | |
|---|---|
| $x+1\ \overline{)\,5x^2+3x-2}$ | Set up division problem. |
| $\phantom{x+1\ \overline{)\,}5x$ | $5x^2$ divided by $x$ is $5x$. |
| $x+1\ \overline{)\,5x^2+3x-2}$<br>$\phantom{x+1\ \overline{)\,}5x$ | Multiply $x+1$ by $5x$. |
| $x+1\ \overline{)\,5x^2+3x-2}$<br>$\underline{-(5x^2+5x)}$<br>$-2x-2$ | Subtract. |
| $\phantom{x+1\ \overline{)\,}5x-2$<br>$x+1\ \overline{)\,5x^2+3x-2}$<br>$\underline{-(5x^2+5x)}$<br>$-2x-2$ | Bring down the next term.<br>$-2x$ divided by $x$ is $-2$. |
| $\phantom{x+1\ \overline{)\,}5x-2$<br>$x+1\ \overline{)\,5x^2+3x-2}$<br>$\underline{-(5x^2+5x)}$<br>$-2x-2$<br>$\underline{-(-2x-2)}$<br>$0$ | Multiply $x+1$ by $-2$.<br>Subtract. |

The quotient is $5x - 2$. The remainder is 0. We write the result as

$$\frac{5x^2+3x-2}{x+1} = 5x - 2$$

or

$$5x^2 + 3x - 2 = (x+1)(5x-2)$$

**Analysis**

This division problem had a remainder of 0. This tells us that the dividend is divided evenly by the divisor, and that the divisor is a factor of the dividend.

## Example 4.5.2: Using Long Division to Divide a Third-Degree Polynomial

Divide $6x^3 + 11x^2 - 31x + 15$ by $3x - 2$.

**Solution**

$$
\begin{array}{rl}
2x^2+\ 5x-\ 7 & 6x^3 \text{ divided by } 3x \text{ is } 2x^2. \\
3x-2\overline{)6x^3+11x^2-31x+15} & \\
\underline{-\left(6x^3-4x^2\right)} & \text{Multiply } 3x-2 \text{ by } 2x^2. \\
15x^2-31x & \text{Subtract. Bring down next term. } 15x^2 \text{ divided by } 3x \text{ is } 5x. \\
\underline{-\left(15x^2-10x\right)} & \text{Multiply } 3x-2 \text{ by } 5x. \\
-21x+15 & \text{Subtract. Bring down next term. } -21x \text{ divided by } 3x \text{ is } -7. \\
\underline{-(-21x+14)} & \text{Multiply } 3x-2 \text{ by } -7. \\
1 & \text{Subtract. The remainder is 1.}
\end{array}
$$

There is a remainder of 1. We can express the result as:

$$\frac{6x^3+11x^2-31x+15}{3x-2}=2x^2+5x-7+\frac{1}{3x-2}$$

**Analysis**

We can check our work by using the Division Algorithm to rewrite the solution. Then multiply.

$$(3x-2)(2x^2+5x-7)+1=6x^3+11x^2-31x+15$$

Notice, as we write our result,

- the dividend is $6x^3+11x^2-31x+15$
- the divisor is $3x-2$
- the quotient is $2x^2+5x-7$
- the remainder is $1$

**Try It! 4.5.2**

Divide $16x^3-12x^2+20x-3$ by $4x+5$.

**Solution**

$$4x^2-8x+15-\frac{78}{4x+5}$$

## Using Synthetic Division to Divide Polynomials

As we've seen, long division of polynomials can involve many steps and be quite cumbersome. **Synthetic division** is a shorthand method of dividing polynomials for the special case of dividing by a linear factor whose leading coefficient is 1.

To illustrate the process, recall the example at the beginning of the section.

Divide $2x^3-3x^2+4x+5$ by $x+2$ using the long division algorithm.

The final form of the process looked like this:

$$
\begin{array}{r}
2x^2-7x+18 \\
x+2\overline{)2x^3-3x^2+4x+5} \\
\underline{-\left(2x^3+4x^2\right)} \\
-7x^2+4x \\
\underline{-\left(-7x^2-14x\right)} \\
18x+\ 5 \\
\underline{-(18x+36)} \\
-31
\end{array}
$$

There is a lot of repetition in the table. If we don't write the variables but, instead, line up their coefficients in columns under the division sign and also eliminate the partial products, we already have a simpler version of the entire problem.

$$\begin{array}{r|rrrr} 2 & 2 & -3 & 4 & 5 \\ & -2 & -4 & & \\ \hline & & -7 & 14 & \\ & & & 18 & -36 \\ \hline & & & & -31 \end{array}$$

Synthetic division carries this simplification even a few more steps. Collapse the table by moving each of the rows up to fill any vacant spots. Also, instead of dividing by 2, as we would in division of whole numbers, then multiplying and subtracting the middle product, we change the sign of the "divisor" to –2, multiply and add. The process starts by bringing down the leading coefficient.

$$\begin{array}{r|rrrr} -2 & 2 & -3 & 4 & 5 \\ & & -4 & 14 & -36 \\ \hline & 2 & -7 & 18 & -31 \end{array}$$

We then multiply it by the "divisor" and add, repeating this process column by column, until there are no entries left. The bottom row represents the coefficients of the quotient; the last entry of the bottom row is the remainder. In this case, the quotient is $2x^2-7x+18$ and the remainder is $-31$. The process will be made more clear in Example $4.5.3$.

### Synthetic Division

Synthetic division is a shortcut that can be used when the divisor is a binomial in the form $x-k$. In *synthetic division*, only the coefficients are used in the division process.

### Given two polynomials, use synthetic division to divide

1. Write $k$ for the divisor.
2. Write the coefficients of the dividend.
3. Bring the lead coefficient down.
4. Multiply the lead coefficient by $k$. Write the product in the next column.
5. Add the terms of the second column.
6. Multiply the result by $k$. Write the product in the next column.
7. Repeat steps 5 and 6 for the remaining columns.
8. Use the bottom numbers to write the quotient. The number in the last column is the remainder and has degree 0, the next number from the right has degree 1, the next number from the right has degree 2, and so on.

### Example $4.5.3$: Using Synthetic Division to Divide a Second-Degree Polynomial

Use synthetic division to divide $5x^2-3x-36$ by $x-3$.

**Solution**

Begin by setting up the synthetic division. Write $k$ and the coefficients.

$$\begin{array}{r|rrr} 3 & 5 & -3 & -36 \\ \hline & & & \end{array}$$

Bring down the lead coefficient. Multiply the lead coefficient by $k$.

$$\begin{array}{r|rrr} 3 & 5 & -3 & -36 \\ & & 15 & \\ \hline & 5 & & \end{array}$$

Continue by adding the numbers in the second column. Multiply the resulting number by $k$.Write the result in the next column. Then add the numbers in the third column.

$$\begin{array}{r|rrr} 3 & 5 & -3 & -36 \\ & & 15 & 36 \\ \hline & 5 & 12 & 0 \end{array}$$

The result is $5x+12$. The remainder is 0. So $x-3$ is a factor of the original polynomial.

**Analysis**

Just as with long division, we can check our work by multiplying the quotient by the divisor and adding the remainder.

$$(x-3)(5x+12)+0=5x^2-3x-36$$

### Example 4.5.4: Using Synthetic Division to Divide a Third-Degree Polynomial

Use synthetic division to divide $4x^3+10x^2-6x-20$ by $x+2$.

**Solution**

The binomial divisor is $x+2$ so $k=-2$. Add each column, multiply the result by –2, and repeat until the last column is reached.

$$\begin{array}{r|rrrr} -2 & 1 & -1 & -11 & 18 \\ & & 2 & 2 & -18 \\ \hline & 1 & 1 & -9 & 0 \end{array}$$

The result is $4x^2+2x-10$.

The remainder is 0. Thus, $x+2$ is a factor of $4x^3+10x^2-6x-20$.

**Analysis**

The graph of the polynomial function $f(x)=4x^3+10x^2-6x-20$ in Figure 4.5.2 shows a zero at $x=k=-2$. This confirms that $x+2$ is a factor of $4x^3+10x^2-6x-20$.





Figure 4.5.2

### Example 4.5.5: Using Synthetic Division to Divide a Fourth-Degree Polynomial

Use synthetic division to divide $-9x^4+10x^3+7x^2-6$ by $x-1$.

**Solution**

Notice there is no $x$-term. We will use a zero as the coefficient for that term.

$$\begin{array}{r|rrrrr} 1 & -9 & 10 & 7 & 0 & -6 \\ & & -9 & 1 & 8 & 8 \\ \hline & -9 & 1 & 8 & 8 & 2 \end{array}$$

The result is $-9x^3+x^2+8x+8+\dfrac{2}{x-1}$ .

### Try It! 4.5.3

Use synthetic division to divide $3x^4+18x^3-3x+40$ by $x+7$.

**Solution**

$$3x^3-3x^2+21x-150+\frac{1090}{x+7}$$

## Using Polynomial Division to Solve Application Problems

Polynomial division can be used to solve a variety of application problems involving expressions for area and volume. We looked at an application at the beginning of this section. Now we will solve that problem in the following example.

### Example 4.5.6: Using Polynomial Division in an Application Problem

The volume of a rectangular solid is given by the polynomial $3x^4-3x^3-33x^2+54x$ . The length of the solid is given by $3x$ and the width is given by $x-2$. Find the height $h$ of the solid.

**Solution**

There are a few ways to approach this problem. We need to divide the expression for the volume of the solid by the expressions for the length and width. Let us create a sketch as in Figure 4.5.3. Let $h$ equal the height of the box.





Figure 4.5.3

We can now write an equation by substituting the known values into the formula for the volume of a rectangular solid.

$$\begin{aligned} V &= l\cdot w\cdot h \\ 3x^4-3x^3-33x^2+54x &= 3x\cdot(x-2)\cdot h \end{aligned}$$

To solve for $h$, first divide both sides by $3x$.

$$\frac{3x\cdot(x-2)\cdot h}{3x}=\frac{3x^4-3x^3-33x^2+54x}{3x}$$

$$(x-2)h=\frac{x^3-x^2-11x+18}{x-2}$$

Now solve for $h$ using synthetic division.

$$h = \frac{x^3 - x^2 - 11x + 18}{x - 2}$$

$$\begin{array}{r|rrrr} 2 & 1 & -1 & -11 & 18 \\ & & 2 & 2 & -18 \\ \hline & 1 & 1 & -9 & 0 \end{array}$$

The quotient is $x^2 + x - 9$ and the remainder is $0$. The height of the solid is $x^2 + x - 9$ .

**Try It! 4.5.4**

The area of a rectangle is given by $3x^3 + 14x^2 - 23x + 6$ . The width of the rectangle is given by $x + 6$. Find an expression for the length of the rectangle.

**Solution**

$3x^2 - 4x + 1$

## Key Equations

Division Algorithm $f(x) = d(x)q(x) + r(x)$ where $q(x) \neq 0$

## Key Concepts

- Polynomial long division can be used to divide a polynomial by any polynomial with equal or lower degree.
- The Division Algorithm tells us that a polynomial dividend can be written as the product of the divisor and the quotient added to the remainder.
- Synthetic division is a shortcut that can be used to divide a polynomial by a binomial in the form $x - k$.
- Polynomial division can be used to solve application problems, including area and volume.

## Footnotes

[1] National Park Service. "Lincoln Memorial Building Statistics." www.nps.gov/linc/historycultu...statistics.htm. Accessed 4/3/2014

## Glossary

**Division Algorithm**

given a polynomial dividend $f(x)$ and a non-zero polynomial divisor $d(x)$ where the degree of $d(x)$ is less than or equal to the degree of $f(x)$, there exist unique polynomials $q(x)$ and $r(x)$ such that $f(x) = d(x)q(x) + r(x)$ where $q(x)$ is the quotient and $r(x)$ is the remainder. The remainder is either equal to zero or has degree strictly less than $d(x)$.

**synthetic division**

a shortcut method that can be used to divide a polynomial by a binomial of the form $x - k$

This page titled 4.5: Dividing Polynomials is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.5: Dividing Polynomials** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.5E: Dividing Polynomials (Exercises)

For the following exercises, use long division to find the quotient and remainder.

19. $\frac{x^3-2x^2+4x+4}{x-2}$

20. $\frac{3x^4-4x^2+4x+8}{x+1}$

For the following exercises, use synthetic division to find the quotient. If the divisor is a factor, then write the factored form.

21. $\frac{x^3-2x^2+5x-1}{x+3}$

22. $\frac{x^3+4x+10}{x-3}$

23. $\frac{2x^3+6x^2-11x-12}{x+4}$

24. $\frac{3x^4+3x^3+2x+2}{x+1}$

This page titled 4.5E: Dividing Polynomials (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **5.4E: Dividing Polynomials (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.6: Zeros of Polynomial Functions

**Learning Objectives**

- Evaluate a polynomial using the Remainder Theorem.
- Use the Factor Theorem to solve a polynomial equation.
- Use the Rational Zero Theorem to find rational zeros.
- Find zeros of a polynomial function.
- Use the Linear Factorization Theorem to find polynomials with given zeros.
- Use Descartes' Rule of Signs.
- Solve real-world applications of polynomial equations

A new bakery offers decorated sheet cakes for children's birthday parties and other special occasions. The bakery wants the volume of a small cake to be 351 cubic inches. The cake is in the shape of a rectangular solid. They want the length of the cake to be four inches longer than the width of the cake and the height of the cake to be one-third of the width. What should the dimensions of the cake pan be?

This problem can be solved by writing a cubic function and solving a cubic equation for the volume of the cake. In this section, we will discuss a variety of tools for writing polynomial functions and solving polynomial equations.

## Evaluating a Polynomial Using the Remainder Theorem

In the last section, we learned how to divide polynomials. We can now use polynomial division to evaluate polynomials using the **Remainder Theorem**. If the polynomial is divided by $x-k$, the remainder may be found quickly by evaluating the polynomial function at $k$, that is, $f(k)$. Let's walk through the proof of the theorem.

Recall that the Division Algorithm states that, given a polynomial dividend $f(x)$ and a non-zero polynomial divisor $d(x)$ where the degree of $d(x)$ is less than or equal to the degree of $f(x)$,there exist unique polynomials $q(x)$ and $r(x)$ such that

$$f(x)=d(x)q(x)+r(x)$$

If the divisor, $d(x)$, is $x-k$, this takes the form

$$f(x)=(x-k)q(x)+r$$

Since the divisor $x-k$

is linear, the remainder will be a constant, $r$. And, if we evaluate this for $x=k$, we have

$$\begin{aligned} f(k) &= (k-k)q(k)+r \\ &= 0\cdot q(k)+r \\ &= r \end{aligned}$$

In other words, $f(k)$ is the remainder obtained by dividing $f(x)$by $x-k$.

**The Remainder Theorem**

If a polynomial $f(x)$ is divided by $x-k$,then the remainder is the value $f(k)$.

How To: Given a polynomial function $f$, evaluate $f(x)$ at $x=k$ using the Remainder Theorem.

1. Use synthetic division to divide the polynomial by $x-k$.
2. The remainder is the value $f(k)$.

**Example 4.6.1: Using the Remainder Theorem to Evaluate a Polynomial**

Use the Remainder Theorem to evaluate $f(x)=6x^4-x^3-15x^2+2x-7$ at $x=2$.

**Solution**

To find the remainder using the Remainder Theorem, use synthetic division to divide the polynomial by $x-2$.

$$\begin{array}{r|rrrrr} 2 & 6 & -1 & -15 & 2 & -7 \\ & & 12 & 22 & 14 & 32 \\ \hline & 6 & 11 & 7 & 16 & 25 \end{array} \tag{4.6.1}$$

The remainder is 25. Therefore, $f(2)=25$.

**Analysis**

We can check our answer by evaluating $f(2)$.

$$\begin{aligned} f(x) &= 6x^4-x^3-15x^2+2x-7 \\ f(2) &= 6(2)^4-(2)^3-15(2)^2+2(2)-7 \\ &= 25 \end{aligned}$$

**Exercise 4.6.1**

se the Remainder Theorem to evaluate $f(x)=2x^5-3x^4-9x^3+8x^2+2$ at $x=-3$.

**Answer**

$f(-3)=-412$

## Using the Factor Theorem to Solve a Polynomial Equation

The **Factor Theorem** is another theorem that helps us analyze polynomial equations. It tells us how the zeros of a polynomial are related to the factors. Recall that the Division Algorithm.

$$f(x)=(x-k)q(x)+r \tag{4.6.2}$$

If $k$ is a zero, then the remainder $r$ is $f(k)=0$ and $f(x)=(x-k)q(x)+0$ or $f(x)=(x-k)q(x)$.

Notice, written in this form, $x-k$ is a factor of $f(x)$. We can conclude if $k$ is a zero of $f(x)$, then $x-k$ is a factor of $f(x)$.

Similarly, if $x-k$ is a factor of $f(x)$, then the remainder of the Division Algorithm $f(x)=(x-k)q(x)+r$ is 0. This tells us that $k$ is a zero.

This pair of implications is the Factor Theorem. As we will soon see, a polynomial of degree $n$ in the complex number system will have $n$ zeros. We can use the Factor Theorem to completely factor a polynomial into the product of $n$ factors. Once the polynomial has been completely factored, we can easily determine the zeros of the polynomial.

**THE FACTOR THEOREM**

According to the Factor Theorem, $k$ is a zero of $f(x)$ if and only if $(x-k)$ is a factor of $f(x)$.

**How to: Given a factor and a third-degree polynomial, use the Factor Theorem to factor the polynomial**

1. Use synthetic division to divide the polynomial by $(x-k)$.
2. Confirm that the remainder is 0.
3. Write the polynomial as the product of $(x-k)$ and the quadratic quotient.
4. If possible, factor the quadratic.
5. Write the polynomial as the product of factors.

**Example 4.6.2: Using the Factor Theorem to Solve a Polynomial Equation**

Show that $(x+2)$ is a factor of $x^3-6x^2-x+30$ . Find the remaining factors. Use the factors to determine the zeros of the **polynomial**.

**Solution**

We can use synthetic division to show that $(x+2)$ is a factor of the polynomial.

$$\begin{array}{r|cccc} -2 & 1 & -6 & -1 & 30 \\ & & -2 & 16 & -30 \\ \hline & 1 & -8 & 15 & 0 \end{array} \tag{4.6.3}$$

The remainder is zero, so $(x+2)$ is a factor of the polynomial. We can use the Division Algorithm to write the polynomial as the product of the divisor and the quotient:

$$(x+2)(x^2-8x+15) \tag{4.6.4}$$

We can factor the quadratic factor to write the polynomial as

$$(x+2)(x-3)(x-5) \tag{4.6.5}$$

By the Factor Theorem, the zeros of $x^3-6x^2-x+30$ are –2, 3, and 5.

**Exercise 4.6.2**

Use the Factor Theorem to find the zeros of $f(x)=x^3+4x^2-4x-16$ given that $(x-2)$ is a factor of the polynomial.

**Answer**

The zeros are 2, –2, and –4.

## Using the Rational Zero Theorem to Find Rational Zeros

Another use for the Remainder Theorem is to test whether a rational number is a zero for a given polynomial. But first we need a pool of rational numbers to test. The **Rational Zero Theorem** helps us to narrow down the number of possible rational zeros using the ratio of the factors of the constant term and factors of the leading **coefficient** of the polynomial

Consider a quadratic function with two zeros, $x=\frac{2}{5}$ and $x=\frac{3}{4}$. By the Factor Theorem, these zeros have factors associated with them. Let us set each factor equal to 0, and then construct the original quadratic function absent its stretching factor.

| | |
|---|---|
| $x-\frac{2}{5}=0$ or $x-\frac{3}{4}=0$ | Set each factor equal to 0. |
| $5x-2=0$ or $4x-3=0$ | Multiply both sides of the equation to eliminate fractions. |
| $f(x)=(5x-2)(4x-3)$ | Create the quadratic function, multiplying the factors. |
| $f(x)=20x^2-23x+6$ | Expand the polynomial. |
| $f(x)=(5\cdot 4)x^2-23x+(2\cdot 3)$ | |

Notice that two of the factors of the constant term, 6, are the two numerators from the original rational roots: 2 and 3. Similarly, two of the factors from the leading coefficient, 20, are the two denominators from the original rational roots: 5 and 4.

We can infer that the numerators of the rational roots will always be factors of the constant term and the denominators will be factors of the leading coefficient. This is the essence of the Rational Zero Theorem; it is a means to give us a pool of possible rational zeros.

**THE RATIONAL ZERO THEOREM**

The Rational Zero Theorem states that, if the polynomial $f(x)=a_nx^n+a_{n-1}x^{n-1}+\ldots+a_1x+a_0$ has integer coefficients, then every rational zero of $f(x)$ has the form $\frac{p}{q}$ where $p$ is a factor of the constant term $a_0$ and $q$ is a factor of the leading coefficient $a_n$.

When the leading coefficient is 1, the possible rational zeros are the factors of the constant term.

**How to: Given a polynomial function $f(x)$, use the Rational Zero Theorem to find rational zeros.**

1. Determine all factors of the constant term and all factors of the leading coefficient.

2. Determine all possible values of $\frac{p}{q}$, where $p$ is a factor of the constant term and $q$ is a factor of the leading coefficient. Be sure to include both positive and negative candidates.
3. Determine which possible zeros are actual zeros by evaluating each case of $f(\frac{p}{q})$.

### Example 4.6.3: Listing All Possible Rational Zeros

List all possible rational zeros of $f(x)=2x^4-5x^3+x^2-4$ .

**Solution**

The only possible rational zeros of $f(x)$ are the quotients of the factors of the last term, –4, and the factors of the leading coefficient, 2.

The constant term is –4; the factors of –4 are $p=\pm1,\pm2,\pm4$.

The leading coefficient is 2; the factors of 2 are $q=\pm1,\pm2$.

If any of the four real zeros are rational zeros, then they will be of one of the following factors of –4 divided by one of the factors of 2.

$$\frac{p}{q}=\pm\frac{1}{1},\pm\frac{1}{2} \qquad \frac{p}{q}=\pm\frac{2}{1},\pm\frac{2}{2} \qquad \frac{p}{q}=\pm\frac{4}{1},\pm\frac{4}{2}$$

Note that $\frac{2}{2}=1$ and $\frac{4}{2}=2$, which have already been listed. So we can shorten our list.

$$\frac{p}{q}=\frac{\text{Factors of the last}}{\text{Factors of the first}}=\pm1,\pm2,\pm4,\pm\frac{1}{2}$$

### Example 4.6.4: Using the Rational Zero Theorem to Find Rational Zeros

Use the Rational Zero Theorem to find the rational zeros of $f(x)=2x^3+x^2-4x+1$ .

**Solution**

The Rational Zero Theorem tells us that if $\frac{p}{q}$ is a zero of $f(x)$, then $p$ is a factor of 1 and $q$ is a factor of 2.

$$\frac{p}{q}=\frac{factor\ of\ constant\ term}{factor\ of\ leading\ coefficient}$$

$$=\frac{factor\ of\ 1}{factor\ of\ 2}$$

The factors of 1 are ±1 and the factors of 2 are ±1 and ±2. The possible values for $\frac{p}{q}$ are ±1 and $\pm\frac{1}{2}$. These are the possible rational zeros for the function. We can determine which of the possible zeros are actual zeros by substituting these values for $x$ in $f(x)$.

$$f(-1)=2(-1)^3+(-1)^2-4(-1)+1=4 \tag{4.6.6}$$

$$f(1)=1(1)^3+(1)^2-4(1)+1=0 \tag{4.6.7}$$

$$f(-\frac{1}{2})=2(-\frac{1}{2})^3+(-\frac{1}{2})^2-4(-\frac{1}{2})+1=3 \tag{4.6.8}$$

$$f(\frac{1}{2})=2(\frac{1}{2})^3+(\frac{1}{2})^2-4(\frac{1}{2})+1=-\frac{1}{2} \tag{4.6.9}$$

Of those, $-1,-\frac{1}{2}$, and $\frac{1}{2}$ are not zeros of $f(x)$. 1 is the only rational zero of $f(x)$.

**Exercise 4.6.3**

Use the Rational Zero Theorem to find the rational zeros of $f(x) = x^3 - 5x^2 + 2x + 1$ .

**Answer**

There are no rational zeros.

## Finding the Zeros of Polynomial Functions

The Rational Zero Theorem helps us to narrow down the list of possible rational zeros for a polynomial function. Once we have done this, we can use **synthetic division** repeatedly to determine all of the **zeros** of a polynomial function.

**How to: Given a polynomial function $f$, use synthetic division to find its zeros.**

1. Use the Rational Zero Theorem to list all possible rational zeros of the function.
2. Use synthetic division to evaluate a given possible zero by synthetically dividing the candidate into the polynomial. If the remainder is 0, the candidate is a zero. If the remainder is not zero, discard the candidate.
3. Repeat step two using the quotient found with synthetic division. If possible, continue until the quotient is a quadratic.
4. Find the zeros of the quadratic function. Two possible methods for solving quadratics are factoring and using the quadratic formula.

**Example 4.6.5: Finding the Zeros of a Polynomial Function with Repeated Real Zeros**

Find the zeros of $f(x) = 4x^3 - 3x - 1$ .

**Solution**

The Rational Zero Theorem tells us that if $\frac{p}{q}$ is a zero of $f(x)$, then $p$ is a factor of –1 and $q$ is a factor of 4.

$$\frac{p}{q} = \frac{factor\ of\ constant\ term}{factor\ of\ leading\ coefficient}$$
$$= \frac{factor\ of\ -1}{factor\ of\ 4}$$

The factors of –1 are ±1 and the factors of 4 are ±1,±2, and ±4. The possible values for $\frac{p}{q}$ are $\pm 1, \pm\frac{1}{2}$, and $\pm\frac{1}{4}$. These are the possible rational zeros for the function. We will use synthetic division to evaluate each possible zero until we find one that gives a remainder of 0. Let's begin with 1.

Dividing by $(x-1)$ gives a remainder of 0, so 1 is a zero of the function. The polynomial can be written as

$$(x-1)(4x^2+4x+1)$$

The quadratic is a perfect square. $f(x)$ can be written as

$$(x-1)(2x+1)^2$$

We already know that 1 is a zero. The other zero will have a multiplicity of 2 because the factor is squared. To find the other zero, we can set the factor equal to 0.

$$2x+1=0$$
$$x=-\frac{1}{2}$$

The zeros of the function are 1 and $-\frac{1}{2}$ with multiplicity 2.

**Analysis**

Look at the graph of the function $f$ in Figure 4.6.1. Notice, at $x = -0.5$, the graph bounces off the x-axis, indicating the even multiplicity (2,4,6…) for the zero −0.5. At $x = 1$, the graph crosses the x-axis, indicating the odd multiplicity (1,3,5…) for the zero $x = 1$.





Figure 4.6.1.

## Using the Fundamental Theorem of Algebra

Now that we can find rational zeros for a polynomial function, we will look at a theorem that discusses the number of complex zeros of a polynomial function. The **Fundamental Theorem of Algebra** tells us that every polynomial function has at least one complex zero. This theorem forms the foundation for solving polynomial equations.

Suppose $f$ is a polynomial function of degree four, and $f(x) = 0$. The Fundamental Theorem of Algebra states that there is at least one complex solution, call it $c_1$. By the Factor Theorem, we can write $f(x)$ as a product of $x - c_1$ and a polynomial quotient. Since $x - c_1$ is linear, the polynomial quotient will be of degree three. Now we apply the Fundamental Theorem of Algebra to the third-degree polynomial quotient. It will have at least one complex zero, call it $c_2$. So we can write the polynomial quotient as a product of $x - c_2$ and a new polynomial quotient of degree two. Continue to apply the Fundamental Theorem of Algebra until all of the zeros are found. There will be four of them and each one will yield a factor of $f(x)$.

### THE FUNDAMENTAL THEOREM OF ALGEBRA

The *Fundamental Theorem of Algebra* states that, if $f(x)$ is a polynomial of degree $n > 0$, then $f(x)$ has at least one complex zero.

We can use this theorem to argue that, if $f(x)$ is a polynomial of degree $n > 0$, and a is a non-zero real number, then $f(x)$ has exactly $n$ linear factors

$$f(x) = a(x - c_1)(x - c_2)\ldots(x - c_n) \tag{4.6.10}$$

where $c_1, c_2,...,c_n$ are complex numbers. Therefore, $f(x)$ has $n$ roots if we allow for multiplicities.

### Q&A: Does every polynomial have at least one imaginary zero?

No. Real numbers are a subset of complex numbers, but not the other way around. A complex number is not necessarily imaginary. Real numbers are also complex numbers.

### Example 4.6.6: Finding the Zeros of a Polynomial Function with Complex Zeros

Find the zeros of $f(x) = 3x^3 + 9x^2 + x + 3$ .

**Solution**

The Rational Zero Theorem tells us that if $\frac{p}{q}$ is a zero of $f(x)$, then $p$ is a factor of 3 and $q$ is a factor of 3.

$$\frac{p}{q} = \frac{factor\ of\ constant\ term}{factor\ of\ leading\ coefficient}$$

$$= \frac{factor\ of\ 3}{factor\ of\ 3}$$

The factors of 3 are ±1 and ±3. The possible values for $\frac{p}{q}$, and therefore the possible rational zeros for the function, are ±3,±1, and $\pm\frac{1}{3}$. We will use synthetic division to evaluate each possible zero until we find one that gives a remainder of 0. Let's begin with –3.

Dividing by $(x+3)$ gives a remainder of 0, so –3 is a zero of the function. The polynomial can be written as

$$(x+3)(3x^2+1)$$

We can then set the quadratic equal to 0 and solve to find the other zeros of the function.

$$\begin{aligned} 3x^2+1 &= 0 \\ x^2 &= -\frac{1}{3} \\ x &= \pm -\sqrt{\frac{1}{3}} \\ &= \pm\frac{i\sqrt{3}}{3} \end{aligned}$$

The zeros of $f(x)$ are $-3$ and $\pm\frac{i\sqrt{3}}{3}$.

**Analysis**

Look at the graph of the function $f$ in Figure 4.6.2. Notice that, at $x=-3$, the graph crosses the x-axis, indicating an odd multiplicity (1) for the zero $x=-3$. Also note the presence of the two turning points. This means that, since there is a $3^{rd}$ degree polynomial, we are looking at the maximum number of turning points. So, the end behavior of increasing without bound to the right and decreasing without bound to the left will continue. Thus, all the x-intercepts for the function are shown. So either the multiplicity of $x=-3$ is 1 and there are two complex solutions, which is what we found, or the multiplicity at $x=-3$ is three. Either way, our result is correct.





Figure 4.6.2.

4.6.4

Find the zeros of $f(x)=2x^3+5x^2-11x+4$ .

**Solution**

The zeros are $-4$, $\frac{1}{2}$, and $1$.

## Using the Linear Factorization Theorem to Find Polynomials with Given Zeros

A vital implication of the **Fundamental Theorem of Algebra**, as we stated above, is that a polynomial function of degree n will have $n$ zeros in the set of complex numbers, if we allow for multiplicities. This means that we can factor the polynomial function into $n$ factors. The **Linear Factorization Theorem** tells us that a polynomial function will have the same number of factors as its degree, and that each factor will be in the form $(x-c)$, where c is a complex number.

Let $f$ be a polynomial function with real coefficients, and suppose $a+bi$, $b \neq 0$, is a zero of $f(x)$. Then, by the Factor Theorem, $x-(a+bi)$ is a factor of $f(x)$. For $f$ to have real coefficients, $x-(a-bi)$ must also be a factor of $f(x)$. This is true because any factor other than $x-(a-bi)$, when multiplied by $x-(a+bi)$, will leave imaginary components in the product. Only multiplication with conjugate pairs will eliminate the imaginary parts and result in real coefficients. In other words, if a polynomial function $f$ with real coefficients has a complex zero $a+bi$, then the complex conjugate $a-bi$ must also be a zero of $f(x)$. This is called the **Complex Conjugate Theorem**.

### COMPLEX CONJUGATE THEOREM

According to the Linear Factorization Theorem, a polynomial function will have the same number of factors as its degree, and each factor will be in the form $(x-c)$, where $c$ is a complex number.

If the polynomial function $f$ has real coefficients and a complex zero in the form $a+bi$, then the complex conjugate of the zero, $a-bi$, is also a zero.

### How to

**Given the zeros of a polynomial function $f$ and a point $(c, f(c))$ on the graph of $f$, use the Linear Factorization Theorem to find the polynomial function.**

1. Use the zeros to construct the linear factors of the polynomial.
2. Multiply the linear factors to expand the polynomial.
3. Substitute $(c, f(c))$ into the function to determine the leading coefficient.
4. Simplify.

### Example 4.6.7: Using the Linear Factorization Theorem to Find a Polynomial with Given Zeros

Find a fourth degree polynomial with real coefficients that has zeros of $-3$, $2$, $i$, such that $f(-2)=100$.

**Solution**

Because $x=i$ is a zero, by the Complex Conjugate Theorem $x=-i$ is also a zero. The polynomial must have factors of $(x+3)$, $(x-2)$, $(x-i)$, and $(x+i)$. Since we are looking for a degree 4 polynomial, and now have four zeros, we have all four factors. Let's begin by multiplying these factors.

$$f(x) = a(x+3)(x-2)(x-i)(x+i) \tag{4.6.11}$$
$$f(x) = a(x^2+x-6)(x^2+1) \tag{4.6.12}$$
$$f(x) = a(x^4+x^3-5x^2+x-6) \tag{4.6.13}$$

We need to find $a$ to ensure $f(-2)=100$. Substitute $x=-2$ and $f(-2)=100$ into $f(x)$.

$$100 = a((-2)^4+(-2)^3-5(-2)^2+(-2)-6) \tag{4.6.14}$$
$$100 = a(-20) \tag{4.6.15}$$
$$-5 = a \tag{4.6.16}$$

So the polynomial function is

$$f(x) = -5(x^4+x^3-5x^2+x-6) \tag{4.6.17}$$

or

$$f(x) = -5x^4-5x^3+25x^2-5x+30 \tag{4.6.18}$$

Analysis

We found that both $i$ and $-i$ were zeros, but only one of these zeros needed to be given. If $i$ is a zero of a polynomial with real coefficients, then $-i$ must also be a zero of the polynomial because $-i$ is the complex conjugate of $i$.

Q&A

**If $2+3i$ were given as a zero of a polynomial with real coefficients, would $2-3i$ also need to be a zero?**

Yes. When any complex number with an imaginary component is given as a zero of a polynomial with real coefficients, the conjugate must also be a zero of the polynomial.

4.6.5

Find a third degree polynomial with real coefficients that has zeros of 5 and $-2i$ such that $f(1)=10$.

**Solution**

$f(x)=-\frac{1}{2}x^3+\frac{5}{2}x^2-2x+10$

## Using Descartes' Rule of Signs

There is a straightforward way to determine the possible numbers of positive and negative real zeros for any polynomial function. If the polynomial is written in descending order, **Descartes' Rule of Signs** tells us of a relationship between the number of sign changes in $f(x)$ and the number of positive real zeros. For example, the polynomial function below has one sign change.

$$f(x) = x^4 + x^3 + x^2 + x - 1$$

This tells us that the function must have 1 positive real zero.

There is a similar relationship between the number of sign changes in $f(-x)$ and the number of negative real zeros.

$$f(-x) = (-x)^4 + (-x)^3 + (-x)^2 + (-x) - 1$$
$$f(-x) = +x^4 - x^3 + x^2 - x - 1$$

In this case, $f(-x)$ has 3 sign changes. This tells us that $f(x)$ could have 3 or 1 negative real zeros.

DESCARTES' RULE OF SIGNS

According to *Descartes' Rule of Signs*, if we let $f(x)=a_nx^n+a_{n-1}x^{n-1}+\ldots+a_1x+a_0$ be a polynomial function with real coefficients:

- The number of positive real zeros is either equal to the number of sign changes of $f(x)$ or is less than the number of sign changes by an even integer.
- The number of negative real zeros is either equal to the number of sign changes of $f(-x)$ or is less than the number of sign changes by an even integer.

Example 4.6.8: Using Descartes' Rule of Signs

Use Descartes' Rule of Signs to determine the possible numbers of positive and negative real zeros for $f(x)=-x^4-3x^3+6x^2-4x-12$ .

**Solution**

Begin by determining the number of sign changes.

There are two sign changes, so there are either 2 or 0 positive real roots. Next, we examine $f(-x)$ to determine the number of negative real roots.

$$f(-x) = -(-x)^4-3(-x)^3+6(-x)^2-4(-x)-12 \quad (4.6.19)$$
$$f(-x) = -x^4+3x^3+6x^2+4x-12 \quad (4.6.20)$$

$$f(-x) = -x^4 + 3x^3 + 6x^2 + 4x - 12$$

Again, there are two sign changes, so there are either 2 or 0 negative real roots.

There are four possibilities, as we can see in Table 4.6.1.

Table 4.6.1

| Positive Real Zeros | Negative Real Zeros | Complex Zeros | Total Zeros |
|---|---|---|---|
| 2 | 2 | 0 | 4 |
| 2 | 0 | 2 | 4 |
| 0 | 2 | 2 | 4 |
| 0 | 0 | 4 | 4 |

**Analysis**

We can confirm the numbers of positive and negative real roots by examining a graph of the function. See Figure 4.6.3. We can see from the graph that the function has 0 positive real roots and 2 negative real roots.





Figure 4.6.3.

**4.6.6**

Use Descartes' Rule of Signs to determine the maximum possible numbers of positive and negative real zeros for $f(x) = 2x^4 - 10x^3 + 11x^2 - 15x + 12$ . Use a graph to verify the numbers of positive and negative real zeros for the function.

**Solution**

There must be 4, 2, or 0 positive real roots and 0 negative real roots. The graph shows that there are 2 positive real zeros and 0 negative real zeros.

## Solving Real-World Applications

We have now introduced a variety of tools for solving polynomial equations. Let's use these tools to solve the bakery problem from the beginning of the section.

**Example 4.6.9**

Solving Polynomial Equations

A new bakery offers decorated sheet cakes for children's birthday parties and other special occasions. The bakery wants the volume of a small cake to be 351 cubic inches. The cake is in the shape of a rectangular solid. They want the length of the cake to be four inches longer than the width of the cake and the height of the cake to be one-third of the width. What should the dimensions of the cake pan be?

**Solution**

Begin by writing an equation for the volume of the cake. The volume of a rectangular solid is given by $V = lwh$. We were given that the length must be four inches longer than the width, so we can express the length of the cake as $l = w + 4$. We were given that the height of the cake is one-third of the width, so we can express the height of the cake as $h = \frac{1}{3}w$. Let's write the volume of the cake in terms of width of the cake.

$$V = (w+4)(w)(\frac{1}{3}w) \tag{4.6.21}$$

$$V = \frac{1}{3}w^3 + \frac{4}{3}w^2 \tag{4.6.22}$$

Substitute the given volume into this equation.

$351 = 13w^3 + 43w^2$ Substitute 351 for V. $1053 = w^3 + 4w^2$ Multiply both sides by 3. $0 = w^3 + 7w^2 - 1053$ Subtract 1053 from both sides.

Descartes' rule of signs tells us there is one positive solution. The Rational Zero Theorem tells us that the possible rational zeros are $\pm 1, \pm 3, \pm 9, \pm 13, \pm 27, \pm 39, \pm 81, \pm 117, \pm 351$, and $\pm 1053$. We can use synthetic division to test these possible zeros. Only positive numbers make sense as dimensions for a cake, so we need not test any negative values. Let's begin by testing values that make the most sense as dimensions for a small sheet cake. Use synthetic division to check $x = 1$.

| | | | | |
|---|---|---|---|---|
| 1 | 1 | 4 | 0 | −1053 |
| | | 1 | 5 | 5 |
| | 1 | 5 | 5 | −1048 |

Since 1 is not a solution, we will check $x = 3$.

| | | | | |
|---|---|---|---|---|
| 3 | 1 | 4 | 0 | −1053 |
| | | 3 | 21 | 63 |
| | 1 | 7 | 21 | −990 |

Since 3 is not a solution either, we will test $x = 9$.

| | | | | |
|---|---|---|---|---|
| 9 | 1 | 4 | 0 | −1053 |
| | | 9 | 117 | 1053 |
| | 1 | 13 | 117 | 0 |

Synthetic division gives a remainder of 0, so 9 is a solution to the equation. We can use the relationships between the width and the other dimensions to determine the length and height of the sheet cake pan.

$l = w + 4 = 9 + 4 = 13$ and $h = \frac{1}{3}w = \frac{1}{3}(9) = 3$

The sheet cake pan should have dimensions 13 inches by 9 inches by 3 inches

**4.6.7**

A shipping container in the shape of a rectangular solid must have a volume of 84 cubic meters. The client tells the manufacturer that, because of the contents, the length of the container must be one meter longer than the width, and the height must be one meter greater than twice the width. What should the dimensions of the container be?

**Solution**

3 meters by 4 meters by 7 meters

**Media**

Access these online resources for additional instruction and practice with zeros of polynomial functions.

- Real Zeros, Factors, and Graphs of Polynomial Functions
- Complex Factorization Theorem
- Find the Zeros of a Polynomial Function

- Find the Zeros of a Polynomial Function 2
- Find the Zeros of a Polynomial Function 3

## Key Concepts

- To find $f(k)$, determine the remainder of the polynomial $f(x)$ when it is divided by $x-k$. This is known as the Remainder Theorem. See Example 4.6.1.
- According to the Factor Theorem, $k$ is a zero of $f(x)$ if and only if $(x-k)$ is a factor of $f(x)$. See Example4.6.2.
- According to the Rational Zero Theorem, each rational zero of a polynomial function with integer coefficients will be equal to a factor of the constant term divided by a factor of the leading coefficient. See Example 4.6.3 and Example 4.6.4.
- When the leading coefficient is 1, the possible rational zeros are the factors of the constant term.
- Synthetic division can be used to find the zeros of a polynomial function. See Example 4.6.5.
- According to the Fundamental Theorem, every polynomial function with degree greater than 0 has at least one complex zero. See Example 4.6.6.
- Allowing for multiplicities, a polynomial function will have the same number of factors as its degree. Each factor will be in the form $(x-c)$, where $c$ is a complex number. See Example 4.6.7.
- The number of positive real zeros of a polynomial function is either the number of sign changes of the function or less than the number of sign changes by an even integer.
- The number of negative real zeros of a polynomial function is either the number of sign changes of $f(-x)$ or less than the number of sign changes by an even integer. See Example 4.6.8.
- Polynomial equations model many real-world scenarios. Solving the equations is easiest done by synthetic division. See Example 4.6.9.

## Glossary

**Descartes' Rule of Signs**

a rule that determines the maximum possible numbers of positive and negative real zeros based on the number of sign changes of $f(x)$ and $f(-x)$

**Factor Theorem**

$k$ is a zero of polynomial function $f(x)$ if and only if $(x-k)$ is a factor of $f(x)$

**Fundamental Theorem of Algebra**

a polynomial function with degree greater than 0 has at least one complex zero

**Linear Factorization Theorem**

allowing for multiplicities, a polynomial function will have the same number of factors as its degree, and each factor will be in the form $(x-c)$, where $c$ is a complex number

**Rational Zero Theorem**

the possible rational zeros of a polynomial function have the form $\frac{p}{q}$ where $p$ is a factor of the constant term and $q$ is a factor of the leading coefficient.

**Remainder Theorem**

if a polynomial $f(x)$ is divided by $x-k$,then the remainder is equal to the value $f(k)$

This page titled 4.6: Zeros of Polynomial Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.6: Zeros of Polynomial Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.6E: Zeros of Polynomial Functions (Exercises)

For the following exercises, use the Rational Zero Theorem to help you solve the polynomial equation.

25. $2x^3 - 3x^2 - 18x - 8 = 0$

26. $3x^3 + 11x^2 + 8x - 4 = 0$

27. $2x^4 - 17x^3 + 46x^2 - 43x + 12 = 0$

28. $4x^4 + 8x^3 + 19x^2 + 32x + 12 = 0$

For the following exercises, use Descartes' Rule of Signs to find the possible number of positive and negative solutions.

29. $x^3 - 3x^2 - 2x + 4 = 0$

30. $2x^4 - x^3 + 4x^2 - 5x + 1 = 0$

---

This page titled 4.6E: Zeros of Polynomial Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **5.5E: Zeros of Polynomial Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.7: Rational Functions

**Learning Objectives**

- Use arrow notation.
- Solve applied problems involving rational functions.
- Find the domains of rational functions.
- Identify vertical asymptotes.
- Identify horizontal asymptotes.
- Graph rational functions.

Suppose we know that the cost of making a product is dependent on the number of items, $x$, produced. This is given by the equation $C(x) = 15,000x - 0.1x^2 + 1000$. If we want to know the average cost for producing $x$ items, we would divide the cost function by the number of items, $x$. The average cost function, which yields the average cost per item for $x$ items produced, is

$$f(x) = \frac{15,000x - 0.1x^2 + 1000}{x}$$

Many other application problems require finding an average value in a similar way, giving us variables in the denominator. Written without a variable in the denominator, this function will contain a negative integer power.

In the last few sections, we have worked with polynomial functions, which are functions with non-negative integers for exponents. In this section, we explore rational functions, which have variables in the denominator.

## Using Arrow Notation

We have seen the graphs of the basic **reciprocal function** and the squared reciprocal function from our study of toolkit functions. Examine these graphs, as shown in Figure 4.7.1, and notice some of their features.





Figure 4.7.1

Several things are apparent if we examine the graph of $f(x) = \frac{1}{x}$.

- On the left branch of the graph, the curve approaches the $x$-axis $(y = 0)$ as $x \to -\infty$.
- As the graph approaches $x = 0$ from the left, the curve drops, but as we approach zero from the right, the curve rises.
- Finally, on the right branch of the graph, the curves approaches the $x$-axis $(y = 0)$ as $x \to \infty$.

To summarize, we use **arrow notation** to show that $x$ or $f(x)$ is approaching a particular value (Table 4.7.1).

Table 4.7.1

| Symbol | Meaning |
|---|---|

| Symbol | Meaning |
|---|---|
| $x \to a^-$ | $x$ approaches a from the left ($x < a$ but close to $a$ ) |
| $x \to a^+$ | $x$ approaches a from the right ($x > a$ but close to $a$ ) |
| $x \to \infty$ | $x$ approaches infinity ($x$ increases without bound) |
| $x \to -\infty$ | $x$ approaches negative infinity ($x$ decreases without bound) |
| $f(x) \to \infty$ | the output approaches infinity (the output increases without bound) |
| $f(x) \to -\infty$ | the output approaches negative infinity (the output decreases without bound) |
| $f(x) \to a$ | the output approaches $a$ |

## Local Behavior of $f(x) = \frac{1}{x}$

Let's begin by looking at the reciprocal function, $f(x) = \frac{1}{x}$. We cannot divide by zero, which means the function is undefined at $x = 0$; so zero is not in the domain. As the input values approach zero from the left side (becoming very small, negative values), the function values decrease without bound (in other words, they approach negative infinity). We can see this behavior in Table 4.7.2.

Table 4.7.2

| $x$ | –0.1 | –0.01 | –0.001 | –0.0001 |
|---|---|---|---|---|
| $f(x) = \frac{1}{x}$ | –10 | –100 | –1000 | –10,000 |

We write in arrow notation

$$\text{as } x \to 0^-, f(x) \to -\infty$$

As the input values approach zero from the right side (becoming very small, positive values), the function values increase without bound (approaching infinity). We can see this behavior in Table 4.7.3.

Table 4.7.3

| $x$ | 0.1 | 0.01 | 0.001 | 0.0001 |
|---|---|---|---|---|
| $f(x) = \frac{1}{x}$ | 10 | 100 | 1000 | 10,000 |

We write in arrow notation

$$\text{As } x \to 0^+, f(x) \to \infty \text{ .}$$

See Figure 4.7.2.





Figure 4.7.2.

This behavior creates a **vertical asymptote**, which is a vertical line that the graph approaches but never crosses. In this case, the graph is approaching the vertical line $x = 0$ as the input becomes close to zero (Figure 4.7.3).





Figure 4.7.3.

**Definition: VERTICAL ASYMPTOTE**

A vertical asymptote of a graph is a vertical line $x = a$ where the graph tends toward positive or negative infinity as the inputs approach $a$. We write

As $x \to a$, $f(x) \to \infty$, or as $x \to a$, $f(x) \to -\infty$.

## End Behavior of $f(x) = \frac{1}{x}$

As the values of $x$ approach infinity, the function values approach 0. As the values of $x$ approach negative infinity, the function values approach 0 (Figure 4.7.4). Symbolically, using arrow notation

As $x \to \infty$, $f(x) \to 0$,and as $x \to -\infty$, $f(x) \to 0$.





Figure 4.7.4.

Based on this overall behavior and the graph, we can see that the function approaches 0 but never actually reaches 0; it seems to level off as the inputs become large. This behavior creates a **horizontal asymptote**, a horizontal line that the graph approaches as the input increases or decreases without bound. In this case, the graph is approaching the horizontal line $y = 0$. See Figure 4.7.5.





Figure 4.7.5.

**Definition: HORIZONTAL ASYMPTOTE**

A *horizontal asymptote* of a graph is a horizontal line $y = b$ where the graph approaches the line as the inputs increase or decrease without bound. We write

$$\text{As } x \to \infty \text{ or } x \to -\infty \text{ , } f(x) \to b.$$

**Example 4.7.1: Using Arrow Notation.**

Use arrow notation to describe the end behavior and local behavior of the function graphed in Figure 4.7.6.





Figure 4.7.6.

**Solution**

Notice that the graph is showing a vertical asymptote at $x = 2$, which tells us that the function is undefined at $x = 2$.

$$\text{As } x \to 2^-,\ f(x) \to -\infty, \text{ and as } x \to 2^+,\ f(x) \to \infty.$$

And as the inputs decrease without bound, the graph appears to be leveling off at output values of 4, indicating a horizontal asymptote at $y = 4$. As the inputs increase without bound, the graph levels off at 4.

$$\text{As } x \to \infty,\ f(x) \to 4 \text{ and as } x \to -\infty,\ f(x) \to 4.$$

## Exercises 4.7.1

Use arrow notation to describe the end behavior and local behavior for the reciprocal squared function.

**Answer**

End behavior: as $x \to \pm\infty$, $f(x) \to 0$;

Local behavior: as $x \to 0$, $f(x) \to \infty$ (there are no x- or y-intercepts)

## Example 4.7.2: Using Transformations to Graph a Rational Function.

Sketch a graph of the reciprocal function shifted two units to the left and up three units. Identify the horizontal and vertical asymptotes of the graph, if any.

**Solution**

Shifting the graph left 2 and up 3 would result in the function

$$f(x) = \frac{1}{x+2} + 3 \tag{4.7.1}$$

or equivalently, by giving the terms a common denominator,

$$f(x) = \frac{3x+7}{x+2} \tag{4.7.2}$$

The graph of the shifted function is displayed in Figure 4.7.7.





Figure 4.7.7.

Notice that this function is undefined at $x = -2$, and the graph also is showing a vertical asymptote at $x = -2$.

$$\text{As } x \to -2^{-}\text{, } f(x) \to -\infty\text{, and as } x \to -2^{+}\text{, } f(x) \to \infty\text{.}$$

As the inputs increase and decrease without bound, the graph appears to be leveling off at output values of 3, indicating a horizontal asymptote at $y = 3$.

$$\text{As } x \to \pm\infty\text{, } f(x) \to 3\text{.}$$

**Analysis**

Notice that horizontal and vertical asymptotes are shifted left 2 and up 3 along with the function.

## Exercise 4.7.2

Sketch the graph, and find the horizontal and vertical asymptotes of the reciprocal squared function that has been shifted right 3 units and down 4 units.

**Solution**





Figure 4.7.8.

The function and the asymptotes are shifted 3 units right and 4 units down. As $x \to 3$, $f(x) \to \infty$, and as $x \to \pm\infty$, $f(x) \to -4$.

The function is $f(x) = \frac{1}{(x-3)^2} - 4$.

## Solving Applied Problems Involving Rational Functions

In Example 4.7.2, we shifted a toolkit function in a way that resulted in the function $f(x)=\frac{3x+7}{x+2}$. This is an example of a rational function. A *rational function* is a function that can be written as the quotient of two polynomial functions. Many real-world problems require us to find the ratio of two polynomial functions. Problems involving rates and concentrations often involve rational functions.

**Definition: RATIONAL FUNCTION**

A ***rational function*** is a function that can be written as the quotient of two polynomial functions $P(x)$ and $Q(x)$.

$$f(x)=\frac{P(x)}{Q(x)}=\frac{a_p x^p+a_{p-1}x^{p-1}+\ldots+a_1 x+a_0}{b_q x^q+b_{q-1}x^{q-1}+\ldots+b_1 x+b_0},\ Q(x)\neq 0 \tag{4.7.3}$$

**Example 4.7.3: Solving an Applied Problem Involving a Rational Function**

A large mixing tank currently contains 100 gallons of water into which 5 pounds of sugar have been mixed. A tap will open pouring 10 gallons per minute of water into the tank at the same time sugar is poured into the tank at a rate of 1 pound per minute. Find the concentration (pounds per gallon) of sugar in the tank after 12 minutes. Is that a greater concentration than at the beginning?

**Solution**

Let t be the number of minutes since the tap opened. Since the water increases at 10 gallons per minute, and the sugar increases at 1 pound per minute, these are constant rates of change. This tells us the amount of water in the tank is changing linearly, as is the amount of sugar in the tank. We can write an equation independently for each:

$$\begin{array}{c}\text{water: } W(t)=100+10t \text{ in gallons}\\ \text{sugar: } S(t)=5+1t \text{ in pounds}\end{array}$$

The concentration, $C$, will be the ratio of pounds of sugar to gallons of water

$$C(t)=\frac{5+t}{100+10t} \tag{4.7.4}$$

The concentration after 12 minutes is given by evaluating $C(t)$ at $t=12$.

$$C(12)=\frac{5+12}{100+10(12)} \tag{4.7.5}$$

$$=\frac{17}{220} \tag{4.7.6}$$

This means the concentration is 17 pounds of sugar to 220 gallons of water.

At the beginning, the concentration is

$$C(0)=\frac{5+0}{100+10(0)} \tag{4.7.7}$$

$$=\frac{1}{20} \tag{4.7.8}$$

Since $\frac{17}{220}\approx 0.08>\frac{1}{20}=0.05$, the concentration is greater after 12 minutes than at the beginning.

**Analysis**

To find the horizontal asymptote, divide the leading coefficient in the numerator by the leading coefficient in the denominator:

$$\frac{1}{10}=0.1 \tag{4.7.9}$$

Notice the horizontal asymptote is $y=0.1$. This means the concentration, $C$, the ratio of pounds of sugar to gallons of water, will approach 0.1 in the long term.

**Exercise 4.7.3**

There are 1,200 freshmen and 1,500 sophomores at a prep rally at noon. After 12 p.m., 20 freshmen arrive at the rally every five minutes while 15 sophomores leave the rally. Find the ratio of freshmen to sophomores at 1 p.m.

**Answer**

$\frac{12}{11}$

## Finding the Domains of Rational Functions

A *vertical asymptote* represents a value at which a rational function is undefined, so that value is not in the domain of the function. A reciprocal function cannot have values in its domain that cause the denominator to equal zero. In general, to find the domain of a rational function, we need to determine which inputs would cause division by zero.

**Definition: DOMAIN OF A RATIONAL FUNCTION**

The domain of a rational function includes all real numbers except those that cause the denominator to equal zero.

**How To: Given a rational function, find the domain.**

1. Set the denominator equal to zero.
2. Solve to find the x-values that cause the denominator to equal zero.
3. The domain is all real numbers except those found in Step 2.

**Example 4.7.4: Finding the Domain of a Rational Function**

Find the domain of $f(x) = \dfrac{x+3}{x^2-9}$.

**Solution**

Begin by setting the denominator equal to zero and solving.

$$x^2 - 9 = 0$$

$$x^2 = 9$$

$$x = \pm 3$$

The denominator is equal to zero when $x = \pm 3$. The domain of the function is all real numbers except $x = \pm 3$.

**Analysis**

A graph of this function, as shown in Figure 4.7.9, confirms that the function is not defined when $x = \pm 3$.





Figure 4.7.9.

There is a vertical asymptote at $x = 3$ and a hole in the graph at $x = -3$. We will discuss these types of holes in greater detail later in this section.

**Exercise 4.7.4**

Find the domain of $f(x) = \dfrac{4x}{5(x-1)(x-5)}$.

**Answer**

The domain is all real numbers except $x = 1$ and $x = 5$.

## Identifying Vertical Asymptotes of Rational Functions

By looking at the graph of a rational function, we can investigate its local behavior and easily see whether there are asymptotes. We may even be able to approximate their location. Even without the graph, however, we can still determine whether a given rational function has any asymptotes, and calculate their location.

### Vertical Asymptotes

The vertical asymptotes of a rational function may be found by examining the factors of the denominator that are not common to the factors in the numerator. Vertical asymptotes occur at the zeros of such factors.

**How To: Given a rational function, identify any vertical asymptotes of its graph**

1. Factor the numerator and denominator.
2. Note any restrictions in the domain of the function.
3. Reduce the expression by canceling common factors in the numerator and the denominator.
4. Note any values that cause the denominator to be zero in this simplified version. These are where the vertical asymptotes occur.
5. Note any restrictions in the domain where asymptotes do not occur. These are removable discontinuities, or "holes."

**Example 4.7.5: Identifying Vertical Asymptotes**

Find the vertical asymptotes of the graph of $k(x) = \dfrac{5+2x^2}{2-x-x^2}$.

**Solution**

First, factor the numerator and denominator.

$$k(x) = \frac{5+2x^2}{2-x-x^2}$$
$$= \frac{5+2x^2}{(2+x)(1-x)}$$

To find the vertical asymptotes, we determine where this function will be undefined by setting the denominator equal to zero:

$$(2+x)(1-x) = 0$$
$$x = -2,\ x = 1$$

Neither $x = -2$ nor $x = 1$ are zeros of the numerator, so the two values indicate two vertical asymptotes. The graph in Figure 4.7.10 confirms the location of the two vertical asymptotes.





***Figure* 4.7.10.**

## Removable Discontinuities

Occasionally, a graph will contain a hole: a single point where the graph is not defined, indicated by an open circle. We call such a hole a *removable discontinuity*. For example, the function $f(x) = \dfrac{x^2 - 1}{x^2 - 2x - 3}$ may be re-written by factoring the numerator and the denominator.

$$f(x) = \frac{(x+1)(x-1)}{(x+1)(x-3)}$$

Notice that $x+1$ is a common factor to the numerator and the denominator. The zero of this factor, $x = -1$, is the location of the removable discontinuity. Notice also that $(x-3)$ is not a factor in both the numerator and denominator. The zero of this factor, $x = 3$, is the vertical asymptote. See Figure 4.7.11. [Note that removable discontinuities may not be visible when we use a graphing calculator, depending upon the window selected.]





Figure 4.7.11.

### REMOVABLE DISCONTINUITIES OF RATIONAL FUNCTIONS

A **removable discontinuity** occurs in the graph of a rational function at $x = a$ if $a$ is a zero for a factor in the denominator that is common with a factor in the numerator. We factor the numerator and denominator and check for common factors. If we find any, we set the common factor equal to 0 and solve. This is the location of the removable discontinuity. This is true if the

multiplicity of this factor is greater than or equal to that in the denominator. If the multiplicity of this factor is greater in the denominator, then there is still an asymptote at that value.

### Example 4.7.6: Identifying Vertical Asymptotes and Removable Discontinuities for a Graph

Find the vertical asymptotes and removable discontinuities of the graph of $k(x) = \dfrac{x-2}{x^2-4}$.

**Solution**

Factor the numerator and the denominator.

$$k(x) = \frac{x-2}{(x-2)(x+2)}$$

Notice that there is a common factor in the numerator and the denominator, $x-2$. The zero for this factor is $x=2$. This is the location of the removable discontinuity.

Notice that there is a factor in the denominator that is not in the numerator, $x+2$. The zero for this factor is $x=-2$. The vertical asymptote is $x=-2$. See Figure 4.7.12





Figure 4.7.12.

The graph of this function will have the vertical asymptote at $x=-2$, but at $x=2$ the graph will have a hole.

### Exercise 4.7.5

Find the vertical asymptotes and removable discontinuities of the graph of $f(x) = \dfrac{x^2-25}{x^3-6x^2+5x}$.

**Answer**

Removable discontinuity at $x=5$.

Vertical asymptotes: $x=0$, $x=1$.

## Identifying Horizontal Asymptotes of Rational Functions

While vertical asymptotes describe the behavior of a graph as the *output* gets very large or very small, horizontal asymptotes help describe the behavior of a graph as the *input* gets very large or very small. Recall that a polynomial's end behavior will mirror that of the leading term. Likewise, a rational function's end behavior will mirror that of the ratio of the function that is the ratio of the leading terms.

There are three distinct outcomes when checking for horizontal asymptotes:

**Case 1**: If the degree of the denominator > degree of the numerator, there is a **horizontal asymptote** at $y=0$.

**Example**: $f(x)=\dfrac{4x+2}{x^2+4x-5}$

In this case, the end behavior is $f(x)\approx\dfrac{4x}{x^2}=\dfrac{4}{x}$. This tells us that, as the inputs increase or decrease without bound, this function will behave similarly to the function $g(x)=\dfrac{4}{x}$, and the outputs will approach zero, resulting in a horizontal asymptote at $y=0$. See **Figure** 4.7.13. Note that this graph crosses the horizontal asymptote.





Figure 4.7.13: Horizontal asymptote $y=0$ when $f(x)=\dfrac{p(x)}{q(x)}$, $q(x)\neq 0$ where degree of $p$ < degree of $q$.

**Case 2**: If the degree of the denominator < degree of the numerator by one, we get a slant asymptote.

**Example**: $f(x)=\dfrac{3x^2-2x+1}{x-1}$

In this case, the end behavior is $f(x)\approx\dfrac{3x^2}{x}=3x$. This tells us that as the inputs increase or decrease without bound, this function will behave similarly to the function $g(x)=3x$. As the inputs grow large, the outputs will grow and not level off, so this graph has no horizontal asymptote. However, the graph of $g(x)=3x$ looks like a diagonal line, and since $f$ will behave similarly to $g$, it will approach a line close to $y=3x$. This line is a slant asymptote.

To find the equation of the slant asymptote, divide $\dfrac{3x^2-2x+1}{x-1}$. The quotient is $3x+1$, and the remainder is 2. The slant asymptote is the graph of the line $g(x)=3x+1$. See Figure 4.7.14





Figure 4.7.14: Slant asymptote when $f(x)=\dfrac{p(x)}{q(x)}$, $q(x)\neq 0$ where degree of $p$ >degree of $q$ by 1.

**Case 3**: If the degree of the denominator = degree of the numerator, there is a horizontal asymptote at $y = \frac{a_n}{b_n}$, where $a_n$ and $b_n$ are respectively the leading coefficients of $p(x)$ and $q(x)$ for $f(x) = \frac{p(x)}{q(x)}$, $q(x) \neq 0$.

**Example**: $f(x) = \frac{3x^2 + 2}{x^2 + 4x - 5}$

In this case, the end behavior is $f(x) \approx \frac{3x^2}{x^2} = 3$. This tells us that as the inputs grow large, this function will behave like the function $g(x) = 3$, which is a horizontal line. As $x \to \pm\infty$, $f(x) \to 3$, resulting in a horizontal asymptote at $y = 3$. See Figure 4.7.15. Note that this graph crosses the horizontal asymptote.





Figure 4.7.15: Horizontal asymptote when $f(x) = \frac{p(x)}{q(x)}$, $q(x) \neq 0$ where degree of $p$ = degree of $q$.

Notice that, while the graph of a rational function will never cross a **vertical asymptote**, the graph may or may not cross a horizontal or slant asymptote. Also, although the graph of a rational function may have many vertical asymptotes, the graph will have at most one horizontal (or slant) asymptote.

It should be noted that, if the degree of the numerator is larger than the degree of the denominator by more than one, the **end behavior** of the graph will mimic the behavior of the reduced end behavior fraction. For instance, if we had the function

$$f(x) = \frac{3x^5 - x^2}{x + 3}$$

with end behavior

$$f(x) \approx \frac{3x^5}{x} = 3x^4$$

the end behavior of the graph would look similar to that of an even polynomial with a positive leading coefficient.

$$x \to \pm\infty, f(x) \to \infty$$

**HORIZONTAL ASYMPTOTES OF RATIONAL FUNCTIONS**

The **horizontal asymptote** of a rational function can be determined by looking at the degrees of the numerator and denominator.

- Degree of numerator is less than degree of denominator: horizontal asymptote at $y = 0$.
- Degree of numerator is greater than degree of denominator by one: no horizontal asymptote; slant asymptote.
- Degree of numerator is equal to degree of denominator: horizontal asymptote at ratio of leading coefficients.

## Example 4.7.7: Identifying Horizontal and Slant Asymptotes

For the functions listed, identify the horizontal or slant asymptote.

1. $g(x) = \dfrac{6x^3 - 10x}{2x^3 + 5x^2}$
2. $h(x) = \dfrac{x^2 - 4x + 1}{x + 2}$
3. $k(x) = \dfrac{x^2 + 4x}{x^3 - 8}$

**Solution**

For these solutions, we will use $f(x) = \dfrac{p(x)}{q(x)},\ q(x) \neq 0$.

1. $g(x) = \dfrac{6x^3 - 10x}{2x^3 + 5x^2}$: The degree of $p =$ degree of $q = 3$, so we can find the horizontal asymptote by taking the ratio of the leading terms. There is a horizontal asymptote at $y = \frac{6}{2}$ or $y = 3$.
2. $h(x) = \dfrac{x^2 - 4x + 1}{x + 2}$: The degree of $p = 2$ and degree of $q = 1$. Since $p > q$ by 1, there is a slant asymptote found at $\dfrac{x^2 - 4x + 1}{x + 2}$.

$$\begin{array}{r|rr} -2 & 1 & -4 & 1 \\ & & -2 & 12 \\ \hline & 1 & -6 & 13 \end{array}$$

3. $k(x) = \dfrac{x^2 + 4x}{x^3 - 8}$ : The degree of $p = 2 <$ degree of $q = 3$, so there is a horizontal asymptote $y = 0$.

## Example 4.7.8 Identifying Horizontal Asymptotes

In the sugar concentration problem earlier, we created the equation $C(t) = \dfrac{5 + t}{100 + 10t}$.

Find the horizontal asymptote and interpret it in context of the problem.

**Solution**

Both the numerator and denominator are linear (degree 1). Because the degrees are equal, there will be a horizontal asymptote at the ratio of the leading coefficients. In the numerator, the leading term is $t$, with coefficient 1. In the denominator, the leading term is 10t, with coefficient 10. The horizontal asymptote will be at the ratio of these values:

$$t \to \infty,\ C(t) \to \tfrac{1}{10}$$

This function will have a horizontal asymptote at $y = \frac{1}{10}$.

This tells us that as the values of $t$ increase, the values of $C$ will approach $\frac{1}{10}$. In context, this means that, as more time goes by, the concentration of sugar in the tank will approach one-tenth of a pound of sugar per gallon of water or $\frac{1}{10}$ pounds per gallon.

## Example 4.7.9: Identifying Horizontal and Vertical Asymptotes

Find the horizontal and vertical asymptotes of the function $f(x) = \dfrac{(x-2)(x+3)}{(x-1)(x+2)(x-5)}$

**Solution**

First, note that this function has no common factors, so there are no potential removable discontinuities.

The function will have vertical asymptotes when the denominator is zero, causing the function to be undefined. The denominator will be zero at $x = 1, -2,$ and $5$, indicating vertical asymptotes at these values.

The numerator has degree $2$, while the denominator has degree $3$. Since the degree of the denominator is greater than the degree of the numerator, the denominator will grow faster than the numerator, causing the outputs to tend towards zero as the inputs get large, and so as $x \to \pm\infty$, $f(x) \to 0$. This function will have a horizontal asymptote at $y = 0$. See Figure 4.7.16.





Figure 4.7.16.

## Exercise 4.7.6

Find the vertical and horizontal asymptotes of the function:

$$f(x) = \frac{(2x-1)(2x+1)}{(x-2)(x+3)}$$

**Answer**

Vertical asymptotes at $x = 2$ and $x = -3$

horizontal asymptote at $y = 4$.

## INTERCEPTS OF RATIONAL FUNCTIONS

A *rational function* will have a $y$-intercept at $f(0)$, if the function is defined at zero. A rational function will not have a $y$-intercept if the function is not defined at zero.

Likewise, a rational function will have $x$-intercepts at the inputs that cause the output to be zero. Since a fraction is only equal to zero when the numerator is zero, x-intercepts can only occur when the numerator of the rational function is equal to zero.

## Example 4.7.10: Finding the Intercepts of a Rational Function

Find the intercepts of $f(x) = \dfrac{(x-2)(x+3)}{(x-1)(x+2)(x-5)}$.

**Solution**

We can find the y-intercept by evaluating the function at zero

$$f(0) = \frac{(0-2)(0+3)}{(0-1)(0+2)(0-5)}$$

$$= -\frac{6}{10}$$
$$= -\frac{3}{5}$$
$$= -0.6$$

The x-intercepts will occur when the function is equal to zero:

$$0 = \frac{(x-2)(x+3)}{(x-1)(x+2)(x-5)} \text{ This is zero when the numerator is zero.}$$

$$0 = (x-2)(x+3)$$

$$x = 2, x = -3$$

The y-intercept is $(0, -0.6)$, the x-intercepts are $(2, 0)$ and $(-3, 0)$. See Figure 4.7.17.





Figure 4.7.17.

## Exercise 4.7.7

Given the reciprocal squared function that is shifted right 3 units and down 4 units, write this as a rational function. Then, find the x- and y-intercepts and the horizontal and vertical asymptotes.

**Answer**

For the transformed reciprocal squared function, we find the rational form.

$$f(x) = \frac{1}{(x-3)^2} - 4 = \frac{1-4(x-3)^2}{(x-3)^2} = \frac{1-4(x^2-6x+9)}{(x-3)(x-3)} = \frac{-4x^2+24x-35}{x^2-6x+9}$$

Because the numerator is the same degree as the denominator we know that as $x \to \pm\infty$, $f(x) \to -4$; so $y = -4$ is the horizontal asymptote. Next, we set the denominator equal to zero, and find that the vertical asymptote is $x = 3$, because as

$x \to 3$, $f(x) \to \infty$. We then set the numerator equal to 0 and find the x-intercepts are at $(2.5, 0)$ and $(3.5, 0)$. Finally, we evaluate the function at 0 and find the y-intercept to be at $(0, -\frac{35}{9})$.

## Graphing Rational Functions

In Example 4.7.10, we see that the numerator of a rational function reveals the *x*-intercepts of the graph, whereas the denominator reveals the vertical asymptotes of the graph. As with polynomials, factors of the numerator may have integer powers greater than one. Fortunately, the effect on the shape of the graph at those intercepts is the same as we saw with polynomials.

The vertical asymptotes associated with the factors of the denominator will mirror one of the two toolkit reciprocal functions. When the degree of the factor in the denominator is odd, the distinguishing characteristic is that on one side of the vertical asymptote the graph heads towards positive infinity, and on the other side the graph heads towards negative infinity. See Figure 4.7.18





Figure 4.7.18.

When the degree of the factor in the denominator is even, the distinguishing characteristic is that the graph either heads toward positive infinity on both sides of the vertical asymptote or heads toward negative infinity on both sides. See Figure 4.7.19





Figure 4.7.19.

For example, the graph of $f(x) = \dfrac{(x+1)^2(x-3)}{(x+3)^2(x-2)}$ is shown in Figure 4.7.20





Figure 4.7.20.

- At the x-intercept $x=-1$ corresponding to the $(x+1)^2$ factor of the numerator, the graph "bounces", consistent with the quadratic nature of the factor.
- At the x-intercept $x=3$ corresponding to the $(x-3)$ factor of the numerator, the graph passes through the axis as we would expect from a linear factor.
- At the vertical asymptote $x=-3$ corresponding to the $(x+3)^2$ factor of the denominator, the graph heads towards positive infinity on both sides of the asymptote, consistent with the behavior of the function $f(x)=\dfrac{1}{x^2}$.
- At the vertical asymptote $x=2$, corresponding to the $(x-2)$ factor of the denominator, the graph heads towards positive infinity on the left side of the asymptote and towards negative infinity on the right side, consistent with the behavior of the function $f(x)=\dfrac{1}{x}$.

**Howto: Given a rational function, sketch a graph.**

1. Evaluate the function at 0 to find the y-intercept.
2. Factor the numerator and denominator.
3. For factors in the numerator not common to the denominator, determine where each factor of the numerator is zero to find the x-intercepts.
4. Find the multiplicities of the x-intercepts to determine the behavior of the graph at those points.
5. For factors in the denominator, note the multiplicities of the zeros to determine the local behavior. For those factors not common to the numerator, find the vertical asymptotes by setting those factors equal to zero and then solve.
6. For factors in the denominator common to factors in the numerator, find the removable discontinuities by setting those factors equal to 0 and then solve.
7. Compare the degrees of the numerator and the denominator to determine the horizontal or slant asymptotes.
8. Sketch the graph.

**Example 4.7.11: Graphing a Rational Function**

Sketch a graph of $f(x)=\frac{(x+2)(x-3)}{(x+1)^2(x-2)}$.

**Solution**

We can start by noting that the function is already factored, saving us a step.

Next, we will find the intercepts. Evaluating the function at zero gives the y-intercept:

$$f(0)=\frac{(0+2)(0-3)}{(0+1)^2(0-2)}=3$$

To find the x-intercepts, we determine when the numerator of the function is zero. Setting each factor equal to zero, we find x-intercepts at $x=-2$ and $x=3$. At each, the behavior will be linear (multiplicity 1), with the graph passing through the intercept.

We have a y-intercept at $(0,3)$ and x-intercepts at $(-2,0)$ and $(3,0)$.

To find the vertical asymptotes, we determine when the denominator is equal to zero. This occurs when $x+1=0$ and when $x-2=0$, giving us vertical asymptotes at $x=-1$ and $x=2$.

There are no common factors in the numerator and denominator. This means there are no removable discontinuities.

Finally, the degree of denominator is larger than the degree of the numerator, telling us this graph has a horizontal asymptote at $y=0$.

To sketch the graph, we might start by plotting the three intercepts. Since the graph has no x-intercepts between the vertical asymptotes, and the y-intercept is positive, we know the function must remain positive between the asymptotes, letting us fill in the middle portion of the graph as shown in Figure 4.7.21.





Figure 4.7.21.

The factor associated with the vertical asymptote at $x=-1$ was squared, so we know the behavior will be the same on both sides of the asymptote. The graph heads toward positive infinity as the inputs approach the asymptote on the right, so the graph will head toward positive infinity on the left as well.

For the vertical asymptote at $x=2$, the factor was not squared, so the graph will have opposite behavior on either side of the asymptote. See Figure 4.7.22 After passing through the x-intercepts, the graph will then level off toward an output of zero, as indicated by the horizontal asymptote.





Figure 4.7.22.

## Exercise 4.7.8

Given the function $f(x) = \frac{(x+2)^2(x-2)}{2(x-1)^2(x-3)}$, use the characteristics of polynomials and rational functions to describe its behavior and sketch the function.

**Answer**

Horizontal asymptote at $y = \frac{1}{2}$. Vertical asymptotes at $x = 1$ and $x = 3$. y-intercept at $(0, \frac{4}{3})$.

x-intercepts at $(2, 0)$ and $(-2, 0)$. $(-2, 0)$ is a zero with multiplicity 2, and the graph bounces off the x-axis at this point. $(2, 0)$ is a single zero and the graph crosses the axis at this point.





Figure 4.7.23.

## Writing Rational Functions

Now that we have analyzed the equations for rational functions and how they relate to a graph of the function, we can use information given by a graph to write the function. A rational function written in factored form will have an *x*-intercept where each factor of the numerator is equal to zero. (An exception occurs in the case of a removable discontinuity.) As a result, we can form a

numerator of a function whose graph will pass through a set of *x*-intercepts by introducing a corresponding set of factors. Likewise, because the function will have a vertical asymptote where each factor of the denominator is equal to zero, we can form a denominator that will produce the vertical asymptotes by introducing a corresponding set of factors.

### WRITING RATIONAL FUNCTIONS FROM INTERCEPTS AND ASYMPTOTES

If a **rational function** has x-intercepts at $x = x_1, x_2, \ldots, x_n$, vertical asymptotes at $x = v_1, v_2, \ldots, v_m$, and no $x_i =$ any $v_j$, then the function can be written in the form:

$$f(x) = a\frac{(x-x_1)^{p_1}(x-x_2)^{p_2}\cdots(x-x_n)^{p_n}}{(x-v_1)^{q_1}(x-v_2)^{q_2}\cdots(x-v_m)^{q_n}}$$

where the powers $p_i$ or $q_i$ on each factor can be determined by the behavior of the graph at the corresponding intercept or asymptote, and the stretch factor $a$ can be determined given a value of the function other than the x-intercept or by the horizontal asymptote if it is nonzero.

### Given a graph of a rational function, write the function.

1. Determine the factors of the numerator. Examine the behavior of the graph at the *x*-intercepts to determine the zeroes and their multiplicities. (This is easy to do when finding the "simplest" function with small multiplicities—such as 1 or 3—but may be difficult for larger multiplicities—such as 5 or 7, for example.)
2. Determine the factors of the denominator. Examine the behavior on both sides of each vertical asymptote to determine the factors and their powers.
3. Use any clear point on the graph to find the stretch factor.

### Example 4.7.12: Writing a Rational Function from Intercepts and Asymptotes

Write an equation for the rational function shown in Figure 4.7.24





Figure 4.7.24.

**Solution**

The graph appears to have x-intercepts at $x = -2$ and $x = 3$. At both, the graph passes through the intercept, suggesting linear factors. The graph has two vertical asymptotes. The one at $x = -1$ seems to exhibit the basic behavior similar to $\frac{1}{x}$, with the graph heading toward positive infinity on one side and heading toward negative infinity on the other. The asymptote at $x = 2$ is exhibiting a behavior similar to $\frac{1}{x^2}$, with the graph heading toward negative infinity on both sides of the asymptote. See Figure 4.7.25





Figure 4.7.25.

We can use this information to write a function of the form

$$f(x) = a\frac{(x+2)(x-3)}{(x+1)(x-2)^2}$$

To find the stretch factor, we can use another clear point on the graph, such as the *y*-intercept $(0,-2)$.

$$-2 = a\frac{(0+2)(0-3)}{(0+1)(0-2)^2}$$
$$-2 = a\frac{-6}{4}$$
$$a = \frac{-8}{-6} = \frac{4}{3}$$

This gives us a final function of $f(x) = \dfrac{4(x+2)(x-3)}{3(x+1)(x-2)^2}$.

## Media

Access these online resources for additional instruction and practice with rational functions.

- Graphing Rational Functions
- Find the Equation of a Rational Function
- Determining Vertical and Horizontal Asymptotes
- Find the Intercepts, Asymptotes, and Hole of a Rational Function

## Key Equations

Rational Function $$f(x) = \frac{P(x)}{Q(x)} = \frac{a_p x^p + a_{p-1}x^{p-1} + \ldots + a_1 x + a_0}{b_q x^q + b_{q-1}x^{q-1} + \ldots + b_1 x + b_0},\ Q(x) \neq 0$$

## Key Concepts

- We can use arrow notation to describe local behavior and end behavior of the toolkit functions $f(x) = \frac{1}{x}$ and $f(x) = \frac{1}{x^2}$. See Example 4.7.1.
- A function that levels off at a horizontal value has a horizontal asymptote. A function can have more than one vertical asymptote. See Example.

- Application problems involving rates and concentrations often involve rational functions. See Example.
- The domain of a rational function includes all real numbers except those that cause the denominator to equal zero. See Example.
- The vertical asymptotes of a rational function will occur where the denominator of the function is equal to zero and the numerator is not zero. See Example.
- A removable discontinuity might occur in the graph of a rational function if an input causes both numerator and denominator to be zero. See Example.
- A rational function's end behavior will mirror that of the ratio of the leading terms of the numerator and denominator functions. See Example, Example, Example, and Example.
- Graph rational functions by finding the intercepts, behavior at the intercepts and asymptotes, and end behavior. See Example.
- If a rational function has x-intercepts at $x = x_1, x_2, \ldots, x_n$, vertical asymptotes at $x = v_1, v_2, \ldots, v_m$, and no $x_i =$ any $v_j$, then the function can be written in the form

---

This page titled 4.7: Rational Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.7: Rational Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.7E: Rational Functions (Exercises)

For the following exercises, find the intercepts and the vertical and horizontal asymptotes, and then use them to sketch a graph of the function.

31. $f(x) = \frac{x+2}{x-5}$

32. $f(x) = \frac{x^2+1}{x^2-4}$

33. $f(x) = \frac{3x^2-27}{x^2+x-2}$

34. $f(x) = \frac{x+2}{x^2-9}$

For the following exercises, find the slant asymptote.

35. $f(x) = \frac{x^2-1}{x+2}$

36. $f(x) = \frac{2x^3-x^2+4}{x^2+1}$

This page titled 4.7E: Rational Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **5.6E: Rational Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 4.8: Non-linear Inequalities

We learned to solve linear inequalities after learning to solve linear equations.

For Rational inequalities, the techniques were very much the same with one major exception. When we multiplied or divided by a negative number, the inequality sign reversed. A rational inequality is an inequality that contains a rational expression.

We will also use some of the techniques from solving linear and rational inequalities as well as quadratic equations. We will solve quadratic inequalities two ways—both graphically and algebraically.

4.8: Non-linear Inequalities is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

# 4.8.1: Solve Quadratic Inequalities

**Learning Objectives**

By the end of this section, you will be able to:

- Solve quadratic inequalities graphically
- Solve quadratic inequalities algebraically

Before you get started, take this readiness quiz.

1. Solve: $2x-3=0$.
   If you missed this problem, review Example 2.2.
2. Solve: $2y^2+y=15$.
   If you missed this problem, review Example 6.45.
3. Solve $\frac{1}{x^2+2x-8}>0$
   If you missed this problem, review Example 7.56.

We have learned how to solve linear inequalities and rational inequalities previously. Some of the techniques we used to solve them were the same and some were different. We will now learn to solve inequalities that have a quadratic expression. We will use some of the techniques from solving linear and rational inequalities as well as quadratic equations. We will solve quadratic inequalities two ways —both graphically and algebraically.

## Solve Quadratic Inequalities Graphically

A **quadratic equation** is in standard form when written as $ax^2+bx+c=0$ . If we replace the equal sign with an inequality sign, we have a **quadratic inequality** in standard form.

**Definition 4.8.1.1: Quadratic Inequality**

A **quadratic inequality** is an inequality that contains a quadratic expression. The standard form of a quadratic inequality is written:

$$ax^2+bx+c<0 \quad ax^2+bx+c\le 0$$
$$ax^2+bx+c>0 \quad ax^2+bx+c\ge 0$$

The graph of a quadratic function $f(x)=ax^2+bx+c=0$ is a parabola. When we ask when is $ax^2+bx+c<0$ , we are asking when is $f(x)<0$. We want to know when the parabola is below the $x$-axis.

When we ask when is $ax^2+bx+c>0$ , we are asking when is $f(x)>0$. We want to know when the parabola is above the $y$-axis.





Figure 9.8.1

## Example 4.8.1.1: How to Solve a Quadratic Inequality Graphically

Solve $x^2-6x+8<0$ graphically. Write the solution in interval notation.

**Solution**:

**Step 1**: Write the quadratic inequality in standard form.

The inequality is in standard form.

$$x^2-6x+8<0$$

**Step 2**: Graph the function $f(x)=ax^2+bx+c$ using properties or transformations.

We will graph using the properties.

$$f(x)=x^2-6x+8$$

Look at $a$ in the equation.

$$a=1, b=-6, c=8$$

$f(x)=x^2-6x+8$

Since $a$ is positive, the parabola opens upward.

**The parabola opens upward.**



Figure 9.8.2

$f(x)=x^2-6x+8$

The axis of symmetry is the line $x=-\frac{b}{2a}$.

Axis of Symmetry

$$x=-\frac{b}{2a}$$
$$x=-\frac{(-6)}{2\cdot 1}$$
$$x=3$$

**The axis of symmetry is the line $x=3$.**

The vertex is on the axis of symmetry. Substitute $x=3$ into the function.

Vertex

$$f(x)=x^2-6x+8$$
$$f(3)=(3)^2-6(3)+8$$
$$f(3)=-1$$

**The vertex is $(3,-1)$.**

We find $f(0)$

$y$-intercept

$$f(x)=x^2-6x+8$$
$$f(0)=(0)^2-6(0)+8$$
$$f(0)=8$$

**The $y$-intercept is $(0,8)$.**

We use the axis of symmetry to find a point symmetric to the $y$-intercept. The $y$-intercept is 3 units left of the axis of symmetry, $x=3$. A point 3 units to the right of the axis of symmetry has $x=6$.

Point symmetric to $y$-intercept

**The point is $(6,8)$.**

We solve $f(x) = 0$.

$x$-intercepts

We can solve this quadratic equation by factoring.

$$\begin{aligned} f(x) &= x^2 - 6x + 8 \\ 0 &= x^2 - 6x + 8 \\ 0 &= (x-2)(x-4) \\ x &= 2 \text{ or } x = 4 \end{aligned}$$

**The $x$-intercepts are $(2,0)$ and $(4,0)$.**

We graph the vertex, intercepts, and the point symmetric to the $y$-intercept. We connect these 5 points to sketch the parabola.





Figure 9.8.3

**Step 3**: Determine the solution from the graph.

$x^2 - 6x + 8 < 0$

The inequality asks for the values of $x$ which make the function less than 0. Which values of $x$ make the parabola below the $x$-axis.

We do not include the values 2, 4 as the inequality is less than only.

The solution, in interval notation, is $(2, 4)$.

## Exercise 4.8.1.1

a. Solve $x^2 + 2x - 8 < 0$ graphically
b. Write the solution in interval notation

**Answer**

a.





***Figure 9.8.4***

b. $(-4, 2)$

## Exercise 4.8.1.2

a. Solve $x^2 - 8x + 12 \geq 0$ graphically
b. Write the solution in interval notation

**Answer**

a.





***Figure 9.8.5***

b. $(-\infty, 2] \cup [6, \infty)$

We list the steps to take to solve a quadratic inequality graphically.

### Solve a Quadratic Inequality Graphically

1. Write the quadratic inequality in standard form.
2. Graph the function $f(x) = ax^2 + bx + c$ .
3. Determine the solution from the graph.

In the last example, the parabola opened upward and in the next example, it opens downward. In both cases, we are looking for the part of the parabola that is below the $x$-axis but note how the position of the parabola affects the solution.


**Example 4.8.1.2**

Solve $-x^2 - 8x - 12 \leq 0$ graphically. Write the solution in interval notation.

**Solution**:

Table 9.8.1

| | |
|---|---|
| The quadratic inequality in standard form. | $-x^2 - 8x - 12 \leq 0$ |
| Graph the function $f(x) = -x^2 - 8x - 12$ | The parabola opens downward.  Figure 9.8.6 |
| Find the line of symmetry. | $x = -\frac{b}{2a}$<br>$x = -\frac{-8}{2(-1)}$<br>$x = -4$ |
| Find the vertex. | $f(x) = -x^2 - 8x - 12$<br>$f(-4) = -(-4)^2 - 8(-4) - 12$<br>$f(-4) = -16 + 32 - 12$<br>$f(-4) = 4$<br>Vertex $(-4, 4)$ |
| Find the $x$-intercepts. Let $f(x) = 0$. | $f(x) = -x^2 - 8x - 12$<br>$0 = -x^2 - 8x - 12$ |
| Factor: Use the Zero Product Property. | $0 = -1(x + 6)(x + 2)$<br>$x = -6 \quad x = -2$ |

| | |
|---|---|
| Graph the parabola. | $x$-intercepts $(-6, 0), (-2.0)$<br>  <br>Figure 9.8.7 |
| Determine the solution from the graph. We include the $x$-intercepts as the inequality is "less than or equal to." | $(-\infty, -6] \cup [-2, \infty)$ |

**? Exercise 4.8.1.3**

a. Solve $-x^2 - 6x - 5 > 0$ graphically
b. Write the solution in interval notation

**Answer**

a.




***Figure 9.8.8***

b. $(-5, -1)$

**? Exercise 4.8.1.4**

a. Solve $-x^2 + 10x - 16 \leq 0$ graphically
b. Write the solution in interval notation

**Answer**

a.




***Figure 9.8.9***

b. $(-\infty, 2] \cup [8, \infty)$

## Solve Quadratic Inequalities Algebraically

The algebraic method we will use is very similar to the method we used to solve rational inequalities. We will find the critical points for the inequality, which will be the solutions to the related quadratic equation. Remember a polynomial expression can change signs only where the expression is zero.

We will use the **critical points** to divide the number line into intervals and then determine whether the quadratic expression will be positive or negative in the interval. We then determine the solution for the inequality.

### Example 4.8.1.3: How to Solve Quadratic Inequalities Algebraically

Solve $x^2 - x - 12 \geq 0$ algebraically. Write the solution in interval notation.

**Solution**:

Table 9.8.2



| | | |
|---|---|---|
| **Step 1**: Write the quadratic inequality in standard form. | The inequality is in standard form. | $x^2 - x - 12 \geq 0$ |
| **Step 2**: Determine the critical points--the solutions to the related quadratic equation. | Change the inequality sign to an equal sign and then solve the equation. | $x^2 - x - 12 = 0$<br>$(x+3)(x-4) = 0$<br>$x+3=0 \quad x-4=0$<br>$x=-3 \quad x=4$ |
| **Step 3**: Use the critical points to divide the number line into intervals. | Use $-3$ and $4$ to divide the number line into intervals. |  |
| **Step 4**: Above the number line show the sign of each quadratic expression using test points from each interval substituted from the original inequality. | Test:<br>$x=-5$<br>$x=0$<br>$x=5$ | $x^2 - x - 12$ $\quad$ $x^2 - x - 12$ $\quad$ $x^2 - x -$<br>$(-5)^2 - (-5) - 12$ $\quad$ $0^2 - 0 - 12$ $\quad$ $5^2 - 5 -$<br>$18 \quad -12 \quad 8$<br>  |

Figure 9.8.11

| | | |
|---|---|---|
| **Step 5**: Determine the intervals where the inequality is correct. Write the solution in interval notation. | $x^2 - x - 12 \geq 0$<br>The inequality is positive in the first and last intervals and equals 0 at the points $-4, 3$. | The solution, in interval notation, is $(-\infty, -3] \cup [4, \infty)$. |

**Exercise 4.8.1.5**

Solve $x^2 + 2x - 8 \geq 0$ algebraically. Write the solution in interval notation.

**Answer**

$(-\infty, -4] \cup [2, \infty)$

**Exercise 4.8.1.6**

Solve $x^2 - 2x - 15 \leq 0$ algebraically. Write the solution in interval notation.

**Answer**

$[-3, 5]$

In this example, since the expression $x^2 - x - 12$ factors nicely, we can also find the sign in each interval much like we did when we solved rational inequalities. We find the sign of each of the factors, and then the sign of the product. Our number line would like this:





Figure 9.8.12

The result is the same as we found using the other method.

We summarize the steps here.

### Solve a Quadratic Inequality Algebraically

1. Write the quadratic inequality in standard form.
2. Determine the critical points—the solutions to the related quadratic equation.
3. Use the critical points to divide the number line into intervals.
4. Above the number line show the sign of each quadratic expression using test points from each interval substituted into the original inequality.
5. Determine the intervals where the inequality is correct. Write the solution in interval notation.


**Example 4.8.1.4**

Solve $x^2 + 6x - 7 \geq 0$ algebraically. Write the solution in interval notation.

**Solution**:

Table 9.8.3

| | |
|---|---|
| Write the quadratic inequality in standard form. | $-x^2 + 6x - 7 \geq 0$ |
| Multiply both sides of the inequality by $-1$. Remember to reverse the inequality sign. | $x^2 - 6x + 7 \leq 0$ |
| Determine the critical points by solving the related quadratic equation. | $x^2 - 6x + 7 = 0$ |
| Write the Quadratic Formula. | $x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$ |

| | |
|---|---|
| Then substitute in the values of $a, b, c$. | $x = \frac{-(-6) \pm \sqrt{(-6)^2 - 4 \cdot 1 \cdot (7)}}{2 \cdot 1}$ |
| Simplify. | $x = \frac{6 \pm \sqrt{8}}{2}$ |
| Simplify the radical. | $x = \frac{6 \pm 2\sqrt{2}}{2}$ |
| Remove the common factor, 2. | $x = \frac{2(3 \pm \sqrt{2})}{2}$<br>$x = 3 \pm \sqrt{2}$<br>$x = 3 + \sqrt{2} \quad x = 3 - \sqrt{2}$<br>$x \approx 1.6 \quad x \approx 4.4$ |
| Use the critical points to divide the number line into intervals. Test numbers from each interval in the original inequality. |  |
| Determine the intervals where the inequality is correct. Write the solution in interval notation. | $-x^2 + 6x - 7 \geq 0$ in the middle interval $[3 - \sqrt{2}, 3 + \sqrt{2}]$ |

**Exercise 4.8.1.7**

Solve $-x^2 + 2x + 1 \geq 0$ algebraically. Write the solution in interval notation.

**Answer**

$[-1 - \sqrt{2}, -1 + \sqrt{2}]$

**Exercise 4.8.1.8**

Solve $-x^2 + 8x - 14 < 0$ algebraically. Write the solution in interval notation.

**Answer**

$(-\infty, 4 - \sqrt{2}) \cup (4 + \sqrt{2}, \infty)$

The solutions of the quadratic inequalities in each of the previous examples, were either an interval or the union of two intervals. This resulted from the fact that, in each case we found two solutions to the corresponding quadratic equation $ax^2 + bx + c = 0$ . These two solutions then gave us either the two $x$-intercepts for the graph or the two critical points to divide the number line into intervals.

This correlates to our previous discussion of the number and type of solutions to a quadratic equation using the discriminant.

For a quadratic equation of the form $ax^2 + bc + c = 0, a \neq 0$ .




| Discriminant | Number/Type of solution | Typical Graph |
|---|---|---|
| $b^2 - 4ac > 0$ | 2 real solutions<br>2 $x$-intercepts on graph |  |
| $b^2 - 4ac = 0$ | 1 real solution<br>1 $x$-intercept on graph |  |
| $b^2 - 4ac < 0$ | 2 complex solutions<br>No $x$-intercept |  |

Figure 9.8.14

The last row of the table shows us when the parabolas never intersect the $x$-axis. Using the Quadratic Formula to solve the quadratic equation, the radicand is a negative. We get two complex solutions.

In the next example, the quadratic inequality solutions will result from the solution of the quadratic equation being complex.

**Example 4.8.1.5**

Solve, writing any solution in interval notation:

a. $x^2 - 3x + 4 > 0$
b. $x^2 - 3x + 4 \leq 0$

**Solution**:

a.

Table 9.8.4

| | |
|---|---|
| Write the quadratic inequality in standard form. | $-x^2 - 3x + 4 > 0$ |
| Determine the critical points by solving the related quadratic equation. | $x^2 - 3x + 4 = 0$ |
| Write the Quadratic Formula. | $x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$ |
| Then substitute in the values of $a, b, c$. | $x = \frac{-(-3) \pm \sqrt{(-3)^2 - 4 \cdot 1 \cdot (4)}}{2 \cdot 1}$ |
| Simplify. | $x = \frac{3 \pm \sqrt{-7}}{2}$ |
| Simplify the radicand. | $x = \frac{3 \pm \sqrt{7}i}{2}$ |
| The complex solutions tell us the parabola does not intercept the $x$-axis. Also, the parabola opens upward. This tells us that the parabola is completely above the $x$-axis. | Complex solutions  |

Figure 9.8.15

We are to find the solution to $x^2-3x+4>0$ . Since for all values of $x$ the graph is above the $x$-axis, all values of $x$ make the inequality true. In interval notation we write $(-\infty,\infty)$.

b. Write the quadratic inequality in standard form.

$$x^2-3x+4\leq 0$$

Determine the critical points by solving the related quadratic equation.

$$x^2-3x+4=0$$

Since the corresponding quadratic equation is the same as in part (a), the parabola will be the same. The parabola opens upward and is completely above the $x$-axis—no part of it is below the $x$-axis.

We are to find the solution to $x^2-3x+4\leq 0$ . Since for all values of $x$ the graph is never below the $x$-axis, no values of $x$ make the inequality true. There is no solution to the inequality.

### ? Exercise 4.8.1.9

Solve and write any solution in interval notation:

a. $-x^2+2x-4\leq 0$
b. $-x^2+2x-4\geq 0$

**Answer**

a. $(-\infty,\infty)$
b. no solution

### ? Exercise 4.8.1.10

Solve and write any solution in interval notation:

a. $x^2+3x+3<0$
b. $x^2+3x+3>0$

**Answer**

a. no solution
b. $(-\infty,\infty)$

## Key Concepts

- Solve a Quadratic Inequality Graphically
  1. Write the quadratic inequality in standard form.
  2. Graph the function $f(x)=ax^2+bx+c$ using properties or transformations.
  3. Determine the solution from the graph.
- How to Solve a Quadratic Inequality Algebraically
  1. Write the quadratic inequality in standard form.
  2. Determine the critical points -- the solutions to the related quadratic equation.
  3. Use the critical points to divide the number line into intervals.
  4. Above the number line show the sign of each quadratic expression using test points from each interval substituted into the original inequality.
  5. Determine the intervals where the inequality is correct. Write the solution in interval notation.

## Glossary

**quadratic inequality**

A quadratic inequality is an inequality that contains a quadratic expression.

4.8.1: Solve Quadratic Inequalities is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

- **9.9: Solve Quadratic Inequalities** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/intermediate-algebra-2e.

# 4.8.1E: Exercises

## Practice Makes Perfect

### Exercise $4.8.1E.11$ Solve Quadratic Inequalities Graphically

In the following exercises,

a. Solve graphically
b. Write the solution in interval notation

1. $x^2+6x+5>0$
2. $x^2+4x-12<0$
3. $x^2+4x+3\leq 0$
4. $x^2-6x+8\geq 0$
5. $-x^2-3x+18\leq 0$
6. $-x^2+2x+24<0$
7. $-x^2+x+12\geq 0$
8. $-x^2+2x+15>0$

**Answer**

1.

a.




***Figure 9.8.16***

b. $(-\infty,-5)\cup(-1,\infty)$

3.

a.




***Figure 9.8.17***

b. $[-3,-1]$

5.


https://math.libretexts.org/@go/page/96258

a.




***Figure 9.8.18***

b. $(-\infty, -6] \cup [3, \infty)$

7.

a.




***Figure 9.8.19***

b. $[-3, 4]$

## Exercise $4.8.1E.12$ Solve Quadratic Inequalities Graphically

In the following exercises, solve each inequality algebraically and write any solution in interval notation.

1. $x^2 + 3x - 4 \geq 0$
2. $x^2 + x - 6 \leq 0$
3. $x^2 - 7x + 10 < 0$
4. $x^2 - 4x + 3 > 0$
5. $x^2 + 8x > -15$
6. $x^2 + 8x < -12$
7. $x^2 - 4x + 2 \leq 0$
8. $-x^2 + 8x - 11 < 0$
9. $x^2 - 10x > -19$
10. $x^2 + 6x < -3$
11. $-6x^2 + 19x - 10 \geq 0$
12. $-3x^2 - 4x + 4 \leq 0$
13. $-2x^2 + 7x + 4 \geq 0$
14. $2x^2 + 5x - 12 > 0$
15. $x^2 + 3x + 5 > 0$

16. $x^2-3x+6\leq 0$
17. $-x^2+x-7>0$
18. $-x^2-4x-5<0$
19. $-2x^2+8x-10<0$
20. $-x^2+2x-7\geq 0$

**Answer**

1. $(-\infty,-4]\cup[1,\infty)$
3. $(2,5)$
5. $(-\infty,-5)\cup(-3,\infty)$
7. $[2-\sqrt{2},2+\sqrt{2}]$
9. $(-\infty,5-\sqrt{6})\cup(5+\sqrt{6},\infty)$
11. $\left(-\infty,-\frac{5}{2}\right]\cup\left[-\frac{2}{3},\infty\right)$
13. $\left[-\frac{1}{2},4\right]$
15. $(-\infty,\infty)$
17. no solution
19. $(-\infty,\infty)$

### Exercise $4.8.1E.13$ Writing Exercises

1. Explain critical points and how they are used to solve quadratic inequalities algebraically.
2. Solve $x^2+2x\geq 8$ both graphically and algebraically. Which method do you prefer, and why?
3. Describe the steps needed to solve a quadratic inequality graphically.
4. Describe the steps needed to solve a quadratic inequality algebraically.

**Answer**

1. Answers may vary.
3. Answers may vary.

## Self Check

a. After completing the exercises, use this checklist to evaluate your mastery of the objectives of this section.

| I can... | Confidently | With some help | No-I don't get it! |
|---|---|---|---|
| solve quadratic inequalities graphically. | | | |
| solve quadratic inequalities algebraically. | | | |

Figure 9.8.20

b. On a scale of 1-10, how would you rate your mastery of this section in light of your responses on the checklist? How can you improve this?

This page titled 4.8.1E: Exercises is shared under a CC BY license and was authored, remixed, and/or curated by OpenStax.

- **9.9E: Exercises** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/intermediate-algebra-2e.

# 4.8.2: Solve Rational Inequalities

**Learning Objectives**

- Solve rational inequalities
- Solve an inequality with rational functions

**Be Prepared**

Before you get started, take this readiness quiz.

1. Find the value of $x-5$ when ⓐ $x=6$ ⓑ $x=-3$ ⓒ $x=5$
   If you missed this problem, review Example 1.2.16.
2. Solve: $8-2x<12$
   If you missed this problem, review Example 2.6.13.
3. Write in interval notation: $-3\le x<5$
   If you missed this problem, review Example 2.6.4.

## Solve Rational Inequalities

We learned to solve linear inequalities after learning to solve linear equations. The techniques were very much the same with one major exception. When we multiplied or divided by a negative number, the inequality sign reversed.

Having just learned to solve rational equations we are now ready to solve rational inequalities. A rational inequality is an inequality that contains a rational expression.

**Rational Inequality**

A rational inequality is an inequality that contains a rational expression.


Inequalities such as $\frac{3}{2x}>1$, $\frac{2x}{x-3}<4$, $\frac{2x-3}{x-6}\ge x$, and $\frac{1}{4}-\frac{2}{x^2}\le\frac{3}{x}$ are rational inequalities as they each contain a rational expression.

When we solve a rational inequality, we will use many of the techniques we used solving linear inequalities. We especially must remember that when we multiply or divide by a negative number, the inequality sign must reverse.

Another difference is that we must carefully consider what value might make the rational expression undefined and so must be excluded.

When we solve an equation and the result is $x=3$, we know there is one solution, which is 3.

When we solve an inequality and the result is $x>3$, we know there are many solutions. We graph the result to better help show all the solutions, and we start with 3. Three becomes a critical point and then we decide whether to shade to the left or right of it. The numbers to the right of 3 are larger than 3, so we shade to the right.




To solve a rational inequality, we first must write the inequality with only one quotient on the left and 0 on the right.

Next we determine the critical points to use to divide the number line into intervals. A **critical point** is a number which make the rational expression zero or undefined.

We then will evaluate the factors of the numerator and denominator, and find the quotient in each interval. This will identify the interval, or intervals, that contains all the solutions of the rational inequality.

We write the solution in interval notation being careful to determine whether the endpoints are included.

**Example 4.8.2.1**

Solve and write the solution in interval notation: $\dfrac{x-1}{x+3} \geq 0$

**Solution**

**Step 1**. Write the inequality as one quotient on the left and zero on the right.

Our inequality is in this form.

$$\frac{x-1}{x+3} \geq 0$$


**Step 2**. Determine the critical points—the points where the rational expression will be zero or undefined.

The rational expression will be zero when the numerator is zero. Since $x-1=0$ when $x=1$, then 1 is a critical point.

The rational expression will be undefined when the denominator is zero. Since $x+3=0$ when $x=-3$, then -3 is a critical point.

The critical points are 1 and -3.

**Step 3**. Use the critical points to divide the number line into intervals.




The number line is divided into three intervals:

$$(-\infty,-3) \quad (-3,1) \quad (1,\infty)$$

**Step 4**. Test a value in each interval. Above the number line show the sign of each factor of the rational expression in each interval. Below the number line show the sign of the quotient.

To find the sign of each factor in an interval, we choose any point in that interval and use it as a test point. Any point in the interval will give the expression the same sign, so we can choose any point in the interval.

$$\text{Interval } (-\infty,-3)$$

The number -4 is in the interval $(-\infty,-3)$. Test $x=-4$ in the expression in the numerator and the denominator.

The numerator:


$$\begin{array}{l} x-1 \\ -4-1 \\ -5 \\ \text{Negative} \end{array}$$

The denominator:

$$\begin{array}{l} x+3 \\ -4+3 \\ -1 \\ \text{Negative} \end{array}$$

Above the number line, mark the factor $x-1$ negative and mark the factor $x+3$ negative.

Since a negative divided by a negative is positive, mark the quotient positive in the interval $(-\infty, -3)$.




Interval $(-3, 1)$

The number 0 is in the interval $(-3, 1)$. Test $x = 0$.

The numerator:


$$x-1$$
$$0-1$$
$$-1$$
Negative

The denominator:

$$x+3$$
$$0+3$$
$$3$$
Positive

Above the number line, mark the factor $x-1$ negative and mark $x+3$ positive.

Since a negative divided by a positive is negative, the quotient is marked negative in the interval $(-3, 1)$.




Interval $(1, \infty)$

The number 2 is in the interval $(1, \infty)$. Test $x = 2$.

The numerator:

$$x-1$$
$$2-1$$
$$1$$
Positive

The denominator:

$x+3$


$2+3$

$5$

Positive

Above the number line, mark the factor $x-1$ positive and mark $x+3$ positive.

Since a positive divided by a positive is positive, mark the quotient positive in the interval $(1,\infty)$.





**Step 5**. Determine the intervals where the inequality is correct. Write the solution in interval notation.

We want the quotient to be greater than or equal to zero, so the numbers in the intervals $(-\infty,-3)$ and $(1,\infty)$are solutions.

But what about the critical points?

The critical point $x=-3$ makes the denominator 0, so it must be excluded from the solution and we mark it with a parenthesis.

The critical point $x=1$ makes the whole rational expression 0. The inequality requires that the rational expression be greater than or equal to. So, 1 is part of the solution and we will mark it with a bracket.




Recall that when we have a solution made up of more than one interval we use the union symbol, $\cup$, to connect the two intervals. The solution in interval notation is $(-\infty,-3)\cup[1,\infty)$.

## Exercise 4.8.2.1

Solve and write the solution in interval notation: $\dfrac{x-2}{x+4}\geq 0$

**Answer**

$(-\infty,-4)\cup[2,\infty)$

## Exercise 4.8.2.2

Solve and write the solution in interval notation: $\dfrac{x+2}{x-4}\geq 0$

**Answer**

$(-\infty, -2] \cup (4, \infty)$

We summarize the steps for easy reference.

**How to Solve a rational inequality**

Step 1. Write the inequality as one quotient on the left and zero on the right.

Step 2. Determine the critical points–the points where the rational expression will be zero or undefined.

Step 3. Use the critical points to divide the number line into intervals.

Step 4. Test a value in each interval. Above the number line show the sign of each factor of the numerator and denominator in each interval. Below the number line show the sign of the quotient.

Step 5. Determine the intervals where the inequality is correct. Write the solution in interval notation.

The next example requires that we first get the rational inequality into the correct form.

**Example 4.8.2.2**

Solve and write the solution in interval notation: $\frac{4x}{x-6} < 1$

**Solution**

$$\frac{4x}{x-6} < 1$$

Subtract 1 to get zero on the right.

$$\frac{4x}{x-6} - 1 < 0$$

Rewrite 1 as a fraction using the LCD.

$$\frac{4x}{x-6} - \frac{x-6}{x-6} < 0$$

Subtract the numerators and place the difference over the common denominator.

$$\frac{4x-(x-6)}{x-6} < 0$$

Simplify.

$$\frac{3x+6}{x-6} < 0$$

Factor the numerator to show all factors.


$$\frac{3(x+2)}{x-6} < 0$$

Find the critical points.

The quotient will be zero when the numerator is zero. The quotient is undefined when the denominator is zero.

$$\begin{aligned} x+2 &= 0 \qquad x-6 = 0 \\ x &= -2 \qquad\quad x = 6 \end{aligned}$$


Use the critical points to divide the number line into intervals.




Test a value in each interval.

| | $(-\infty, -2)$ | $(-2, 6)$ | $(6, \infty)$ |
|---|---|---|---|
| $x + 2)$ | x+2<br>-3+2<br>-1<br>- | x+2<br>0+2<br>2<br>+ | x+2<br>7+2<br>9<br>+ |
| $x - 6$ | x-6<br>-3-6<br>-9<br>- | x-6<br>0-6<br>-6<br>- | x-6<br>7-6<br>1<br>+ |

Above the number line show the sign of each factor of the rational expression in each interval. Below the number line show the sign of the quotient.




Determine the intervals where the inequality is correct. We want the quotient to be negative, so the solution includes the points between −2 and 6. Since the inequality is strictly less than, the endpoints are not included.

We write the solution in interval notation as (−2, 6).

**? Exercise 4.8.2.3**

Solve and write the solution in interval notation: $\frac{3x}{x-3} < 1$.

**Answer**

$\left(-\frac{3}{2}, 3\right)$


https://math.libretexts.org/@go/page/96255

**Exercise 4.8.2.4**

Solve and write the solution in interval notation: $\frac{3x}{x-4} < 2$.

**Answer**

$(-8, 4)$

In the next example, the numerator is always positive, so the sign of the rational expression depends on the sign of the denominator.

**Example 4.8.2.3**

Solve and write the solution in interval notation: $\frac{5}{x^2-2x-15} > 0$.

**Solution**

The inequality is in the correct form.

$$\frac{5}{x^2-2x-15} > 0$$

Factor the denominator.


$$\frac{5}{(x+3)(x-5)} > 0$$

Find the critical points. The quotient is 0 when the numerator is 0. Since the numerator is always 5, the quotient cannot be 0.

The quotient will be undefined when the denominator is zero.

$$(x+3)(x-5) = 0$$
$$x = -3, x = 5$$

Use the critical points to divide the number line into intervals.




Test values in each interval. Above the number line show the sign of each factor of the denominator in each interval. Below the number line, show the sign of the quotient.

Write the solution in interval notation.

$$(-\infty, -3) \cup (5, \infty)$$

**Exercise 4.8.2.5**

Solve and write the solution in interval notation: $\frac{1}{x^2+2x-8} > 0$.

**Answer**

$(-\infty, -4) \cup (2, \infty)$

**Exercise 4.8.2.6**

Solve and write the solution in interval notation: $\dfrac{3}{x^2+x-12} > 0$.

**Answer**

$(-\infty, -4) \cup (3, \infty)$

The next example requires some work to get it into the needed form.

**Example 4.8.2.4**

Solve and write the solution in interval notation: $\dfrac{1}{3} - \dfrac{2}{x^2} < \dfrac{5}{3x}$.

**Solution**

$$\frac{1}{3} - \frac{2}{x^2} < \frac{5}{3x}$$

Subtract $\dfrac{5}{3x}$ to get zero on the right.

$$\frac{1}{3} - \frac{2}{x^2} - \frac{5}{3x} < 0$$

Rewrite to get each fraction with the LCD $3x^2$.

$$\frac{1 \cdot x^2}{3 \cdot x^2} - \frac{2 \cdot 3}{x^2 \cdot 3} - \frac{5 \cdot x}{3x - x} < 0$$

Simplify.

$$\frac{x^2}{3x^2} - \frac{6}{3x^2} - \frac{5x}{3x^2} < 0$$

Subtract the numerators and place the difference over the common denominator.

$$\frac{x^2 - 5x - 6}{3x^2} < 0$$


Factor the numerator.

$$\frac{(x-6)(x+1)}{3x^2} < 0$$

Find the critical points.

$$\begin{array}{lll} 3x^2 = 0 & x - 6 = 0 & x + 1 = 0 \\ x = 0 & x = 6 & x = -1 \end{array}$$

Use the critical points to divide the number line into intervals.




Above the number line show the sign of each factor in each interval. Below the number line, show the sign of the quotient.

Since, 0 is excluded, the solution is the two $(-1,0)\cup(0,6)$ intervals, $(-1,0)$ and $(0,6)$.

**Exercise 4.8.2.7**

Solve and write the solution in interval notation: $\frac{1}{2}+\frac{4}{x^2}<\frac{3}{x}$.

**Answer**

$(2,4)$

**Exercise 4.8.2.8**

Solve and write the solution in interval notation: $\frac{1}{3}+\frac{6}{x^2}<\frac{3}{x}$.

**Answer**

$(3,6)$

## Solve an Inequality with Rational Functions

When working with rational functions, it is sometimes useful to know when the function is greater than or less than a particular value. This leads to a rational inequality.

**Example 4.8.2.5**

Given the function $R(x)=\frac{x+3}{x-5}$, find the values of x that make the function less than or equal to 0.

**Solution**

We want the function to be less than or equal to 0.

$$R(x)\le 0$$


Substitute the rational expression for $R(x)$.

$$\frac{x+3}{x-5}\le 0 \quad x\neq 5$$

Find the critical points.

$$\begin{aligned} x+3&=0 & x-5&=0\\ x&=-3 & x&=5 \end{aligned}$$

Use the critical points to divide the number line into intervals.




Test values in each interval. Above the number line, show the sign of each factor in each interval. Below the number line, show the sign of the quotient. Write the solution in interval notation. Since 5 is excluded we, do not include it in the interval.

$$[-3, 5)$$

**Exercise 4.8.2.9**

Given the function $R(x) = \dfrac{x-2}{x+4}$, find the values of $x$ that make the function less than or equal to 0.

**Answer**

$(-4, 2]$

**Exercise 4.8.2.10**

Given the function $R(x) = \dfrac{x+1}{x-4}$, find the values of $x$ that make the function less than or equal to 0.

**Answer**

$[-1, 4)$

In economics, the function $C(x)$ is used to represent the cost of producing $x$ units of a commodity. The average cost per unit can be found by dividing $C(x)$ by the number of items $x$. Then, the average cost per unit is \(c(x)=\dfrac{C(x)}{x}).

**Example 4.8.2.6**

The function$C(x) = 10x + 3000$ represents the cost to produce $x$, number of items. Find:

a. The average cost function, $c(x)$
b. How many items should be produced so that the average cost is less than $40.

**Solution**

a. $$C(x) = 10x + 3000$$

The average cost function is $c(x) = \dfrac{C(x)}{x}$). To find the average cost function, divide the cost function by $x$.

$$c(x) = \frac{C(x)}{x}$$
$$c(x) = \frac{10x + 3000}{x}$$

The average cost function is $c(x) = \dfrac{10x + 3000}{x}$

b. We want the function $c(x)$ to be less than 40.

$$c(x) < 40$$

Substitute the rational expression forc(x).

$$\frac{10x+3000}{x} < 40, \quad x \neq 0$$

Subtract 40 to get 0 on the right.

$$\frac{10x+3000}{x} - 40 < 0$$

Rewrite the left side as one quotient by finding the LCD and performing the subtraction.

$$\begin{aligned} \frac{10x+3000}{x} - 40\left(\frac{x}{x}\right) &< 0 \\ \frac{10x+3000}{x} - \frac{40x}{x} &< 0 \\ \frac{10x+3000-40x}{x} &< 0 \\ \frac{-30x+3000}{x} &< 0 \end{aligned}$$

Factor the numerator to show all factors.

$$\begin{aligned} \frac{-30(x-100)}{x} &< 0 \\ -30(x-100) = 0 \qquad & x = 0 \end{aligned}$$

Find the critical points.

$$\begin{aligned} -30 \neq 0 \quad & x - 100 = 0 \\ & x = 100 \end{aligned}$$

More than 100 items must be produced to keep the average cost below $40 per item.

**? Exercise 4.8.2.11**

The function$C(x) = 20x + 6000$ represents the cost to produce $x$, number of items. Find:

a. How many items should be produced so that the average cost is less than $60.

**Answer**

a. $c(x) = \dfrac{20x+6000}{x}$

b. More than 150 items must be produced to keep the average cost below $60 per item.

**? Exercise 4.8.2.12**

The function$C(x) = 5x + 900$ represents the cost to produce $x$, number of items. Find:

a. How many items should be produced so that the average cost is less than $20.

**Answer**

a. $c(x) = \dfrac{5x+900}{x}$

b. More than 60 items must be produced to keep the average cost below $20 per item.

This page titled 4.8.2: Solve Rational Inequalities is shared under a CC BY license and was authored, remixed, and/or curated by OpenStax.

- **7.7: Solve Rational Inequalities** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/intermediate-algebra-2e.

# 4.8.2E: Exercises

## Solve Rational Inequalities

**In the following exercises, solve each rational inequality and write the solution in interval notation.**

1. $\frac{x-3}{x+4} \geq 0$

**Answer**

$(-\infty, -4) \cup [3, \infty)$

2. $\frac{x+6}{x-5} \geq 0$

3. $\frac{x+1}{x-3} \leq 0$

**Answer**

$[-1, 3)$

4. $\frac{x-4}{x+2} \leq 0$

5. $\frac{x-7}{x-1} > 0$

**Answer**

$(-\infty, 1) \cup (7, \infty)$

6. $\frac{x+8}{x+3} > 0$

7. $\frac{x-6}{x+5} < 0$

**Answer**

$(-5, 6)$

8. $\frac{x+5}{x-2} < 0$

9. $\frac{3x}{x-5} < 1$

**Answer**

$\left(-\frac{5}{2}, 5\right)$

10. $\frac{5x}{x-2} < 1$

11. $\frac{6x}{x-6} > 2$

**Answer**

$(-\infty, -3) \cup (6, \infty)$

12. $\frac{3x}{x-4} > 2$

13. $\frac{2x+3}{x-6} \leq 1$

**Answer**

$[-9, 6)$

14. $\frac{4x-1}{x-4} \leq 1$

15. $\frac{3x-2}{x-4} \geq 2$

**Answer**

$(-\infty, -6] \cup (4, \infty)$

16. $\frac{4x-3}{x-3} \geq 2$

17. $\frac{1}{a} + \frac{2}{5} = \frac{1}{2}$

**Answer**

$a = 10$

18. $\frac{1}{x^2-4x-12} > 0$

19. $\frac{3}{x^2-5x+4} < 0$

**Answer**

$(1, 4)$

20. $\frac{4}{x^2+7x+12} < 0$

21. $\frac{2}{2x^2+x-15} \geq 0$

**Answer**

$(-\infty, -3) \cup \left(\frac{5}{2}, \infty\right)$

22. $\dfrac{6}{3x^2-2x-5} \geq 0$

23. $\dfrac{-2}{6x^2-13x+6} \leq 0$

**Answer**

$\left(-\infty, \dfrac{2}{3}\right) \cup \left(\dfrac{3}{2}, \infty\right)$

24. $\dfrac{-1}{10x^2+11x-6} \leq 0$

17. $\dfrac{1}{a} + \dfrac{2}{5} = \dfrac{1}{2}$

**Answer**

$a = 10$

18. $\dfrac{1}{x^2-4x-12} > 0$

19. $\dfrac{3}{x^2-5x+4} < 0$

**Answer**

$(1, 4)$

20. $\dfrac{4}{x^2+7x+12} < 0$

25. $\dfrac{1}{2} + \dfrac{12}{x^2} > \dfrac{5}{x}$

**Answer**

$(-\infty, 0) \cup (0, 4) \cup (6, \infty)$

26. $\dfrac{1}{3} + \dfrac{1}{x^2} > \dfrac{4}{3x}$

27. $\dfrac{1}{2} - \dfrac{4}{x^2} \leq \dfrac{1}{x}$

**Answer**

$[-2, 0) \cup (0, 4]$

28. $\dfrac{1}{2} - \dfrac{3}{2x^2} \geq \dfrac{1}{x}$

29. $\dfrac{1}{x^2-16} < 0$

**Answer**

$(-4, 4)$

30. $\frac{4}{x^2 - 25} > 0$

31. $\frac{4}{x-2} \geq \frac{3}{x+1}$

**Answer**

$[-10, -1) \cup (2, \infty)$

32. $\frac{5}{x-1} \leq \frac{4}{x+2}$

## Solve an Inequality with Rational Functions

**In the following exercises, solve each rational function inequality and write the solution in interval notation.**

33. Given the function $R(x) = \frac{x-5}{x-2}$, find the values of $x$ that make the function less than or equal to 0.

**Answer**

$(2, 5]$

34. Given the function $R(x) = \frac{x+1}{x+3}$, find the values of $x$ that make the function less than or equal to 0.

35. Given the function $R(x) = \frac{x-6}{x+2}$, find the values of $x$ that make the function less than or equal to 0.

**Answer**

$(-\infty, -2) \cup [6, \infty)$

36. Given the function $R(x) = \frac{x+1}{x-4}$, find the values of $x$ that make the function less than or equal to 0.

## Writing Exercises

37. Write the steps you would use to explain solving rational inequalities to your little brother.

**Answer**

Answers will vary

38. Create a rational inequality whose solution is $(-\infty, -2] \cup [4, \infty)$.

This page titled 4.8.2E: Exercises is shared under a CC BY license and was authored, remixed, and/or curated by OpenStax.

- **7.7E: Exercises** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/intermediate-algebra-2e.

# CHAPTER OVERVIEW

## 5: Exponential and Logarithmic Functions

In this chapter, we will explore exponential functions, which can be used for, among other things, modeling growth patterns such as those found in bacteria. We will also investigate logarithmic functions, which are closely related to exponential functions. Both types of functions have numerous real-world applications when it comes to modeling and interpreting data.


5.1: Prelude to Exponential and Logarithmic Functions
5.2: Exponential Functions
5.2E: Exponential Functions (Exercises)
5.3: Graphs of Exponential Functions
5.3E: Graphs of Exponential Functions (Exercises)
5.4: Logarithmic Functions
5.4E: Logarithmic Functions (Exercises)
5.5: Graphs of Logarithmic Functions
5.5E: Graphs of Logarithmic Functions (Exercises)
5.6: Logarithmic Properties
5.6E: Logarithmic Properties (Exercises)
5.7: Exponential and Logarithmic Equations
5.7E: Exponential and Logarithmic Equations (Exercises)
5.8: Exponential and Logarithmic Models
5.8E: Exponential and Logarithmic Models (Exercises)
5.9: Fitting Exponential Models to Data
5.9E: Fitting Exponential Models to Data (Exercises)


Thumbnail: The functions $y = e^x$ and $y = \ln(x)$ are inverses of each other, so their graphs are symmetric about the line $y = x$. (CC BY-SA; OpenStax).

### Contributors

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.


This page titled 5: Exponential and Logarithmic Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 5.1: Prelude to Exponential and Logarithmic Functions

Focus in on a square centimeter of your skin. Look closer. Closer still. If you could look closely enough, you would see hundreds of thousands of microscopic organisms. They are bacteria, and they are not only on your skin, but in your mouth, nose, and even your intestines. In fact, the bacterial cells in your body at any given moment outnumber your own cells. But that is no reason to feel bad about yourself. While some bacteria can cause illness, many are healthy and even essential to the body.

Bacteria commonly reproduce through a process called binary fission, during which one bacterial cell splits into two. When conditions are right, bacteria can reproduce very quickly. Unlike humans and other complex organisms, the time required to form a new generation of bacteria is often a matter of minutes or hours, as opposed to days or years. For simplicity's sake, suppose we begin with a culture of one bacterial cell that can divide every hour. Table 5.1.1 shows the number of bacterial cells at the end of each subsequent hour. We see that the single bacterial cell leads to over one thousand bacterial cells in just ten hours! And if we were to extrapolate the table to twenty-four hours, we would have over 16 million!

Table 5.1.1

| **Hour** | 0 | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 |
|---|---|---|---|---|---|---|---|---|---|---|---|
| **Bacteria** | 1 | 2 | 4 | 8 | 16 | 32 | 64 | 128 | 256 | 512 | 1024 |

In this chapter, we will explore exponential functions, which can be used for, among other things, modeling growth patterns such as those found in bacteria. We will also investigate logarithmic functions, which are closely related to exponential functions. Both types of functions have numerous real-world applications when it comes to modeling and interpreting data.

This page titled 5.1: Prelude to Exponential and Logarithmic Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.0: Prelude to Exponential and Logarithmic Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.2: Exponential Functions

**Learning Objectives**

- Evaluate exponential functions.
- Find the equation of an exponential function.
- Use compound interest formulas.
- Evaluate exponential functions with base $e$.

India is the second most populous country in the world with a population of about $1.25$ billion people in 2013. The population is growing at a rate of about $.2\%$ each year. If this rate continues, the population of India will exceed China's population by the year 2031. When populations grow rapidly, we often say that the growth is "exponential," meaning that something is growing very rapidly. To a mathematician, however, the term *exponential growth* has a very specific meaning. In this section, we will take a look at *exponential functions*, which model this kind of rapid growth.

**Identifying Exponential Functions**

When exploring linear growth, we observed a constant rate of change—a constant number by which the output increased for each unit increase in input. For example, in the equation $f(x) = 3x + 4$, the slope tells us the output increases by $3$ each time the input increases by $1$. The scenario in the India population example is different because we have a *percent* change per unit time (rather than a constant change) in the number of people.

## Defining an Exponential Function

A study found that the percent of the population who are vegans in the United States doubled from 2009 to 2011. In 2011, $2.5\%$ of the population was vegan, adhering to a diet that does not include any animal products—no meat, poultry, fish, dairy, or eggs. If this rate continues, vegans will make up $10\%$ of the U.S. population in 2015, $40\%$ in 2019, and $80\%$ in 2050.

What exactly does it mean to *grow exponentially*? What does the word *double* have in common with *percent increase*? People toss these words around errantly. Are these words used correctly? The words certainly appear frequently in the media.

- **Percent change** refers to a *change* based on a *percent* of the original amount.
- **Exponential growth** refers to an *increase* based on a constant multiplicative rate of change over equal increments of time, that is, a *percent* increase of the original amount over time.
- **Exponential decay** refers to a *decrease* based on a constant multiplicative rate of change over equal increments of time, that is, a *percent* decrease of the original amount over time.

For us to gain a clear understanding of **exponential growth**, let us contrast exponential growth with **linear growth**. We will construct two functions. The first function is exponential. We will start with an input of $0$, and increase each input by $1$. We will double the corresponding consecutive outputs. The second function is linear. We will start with an input of $0$, and increase each input by $1$. We will add $2$ to the corresponding consecutive outputs (Table $5.2.1$).

From Table $5.2.1$ we can infer that for these two functions, exponential growth dwarfs linear growth.

- **Exponential growth** refers to the original value from the range increases by the *same percentage* over equal increments found in the domain.
- **Linear growth** refers to the original value from the range increases by the *same amount* over equal increments found in the domain.

Table 5.2.1

| $x$ | $f(x) = 2^x$ | $g(x) = 2x$ |
|---|---|---|
| 0 | 1 | 0 |
| 1 | 2 | 2 |
| 2 | 4 | 4 |

| $x$ | $f(x)=2^x$ | $g(x)=2x$ |
|---|---|---|
| 3 | 8 | 6 |
| 4 | 16 | 8 |
| 5 | 32 | 10 |
| 6 | 64 | 12 |

Apparently, the difference between “the same percentage” and “the same amount” is quite significant. For exponential growth, over equal increments, the constant multiplicative rate of change resulted in doubling the output whenever the input increased by one. For linear growth, the constant additive rate of change over equal increments resulted in adding 2 to the output whenever the input was increased by one.

The general form of the **exponential function** is $f(x)=ab^x$, where $a$ is any nonzero number, $b$ is a positive real number not equal to 1.

- If $b>1$,the function grows at a rate proportional to its size.
- If $0<b<1$, the function decays at a rate proportional to its size.

Let’s look at the function $f(x)=2^x$ from our example. We will create a table (Table 5.2.2) to determine the corresponding outputs over an interval in the domain from $-3$ to 3.

Table 5.2.2

| $x$ | $-3$ | $-2$ | $-1$ | 0 | 1 | 2 | 3 |
|---|---|---|---|---|---|---|---|
| $f(x)=2^x$ | $2^{-3}=\frac{1}{8}$ | $2^{-2}=\frac{1}{4}$ | $2^{-1}=\frac{1}{2}$ | $2^0=1$ | $2^1=2$ | $2^2=4$ | $2^3=8$ |

Let us examine the graph of $f$ by plotting the ordered pairs from Table 5.2.2 and then make a few observations 5.2.1.





Figure 5.2.1

Let’s define the behavior of the graph of the exponential function $f(x)=2^x$ and highlight some its key characteristics.

- the domain is $(-\infty,\infty)$,
- the range is $(0,\infty)$,
- as $x\to\infty$, $f(x)\to\infty$,
- as $x\to-\infty$, $f(x)\to 0$,
- $f(x)$ is always increasing,
- the graph of $f(x)$ will never touch the *x*-axis because base two raised to any exponent never has the result of zero.

- $y = 0$ is the horizontal asymptote.
- the $y$-intercept is $1$.

**Definition: Exponential Functions**

For any real number $x$,an exponential function is a function with the form

$$f(x) = ab^x \tag{5.2.1}$$

where

- $a$ is a non-zero real number called the initial value and
- $b$ is any positive real number such that $b \neq 1$.
- The domain of $f$ is all real numbers.
- The range of $f$ is all positive real numbers if $a > 0$.
- The range of $f$ is all negative real numbers if $a < 0$.
- The $y$-intercept is $(0, a)$,and the horizontal asymptote is $y = 0$.

**Example 5.2.1: Identifying Exponential Functions**

Which of the following equations are *not* exponential functions?

- $f(x) = 4^{3(x-2)}$
- $g(x) = x^3$
- $h(x) = \left(\frac{1}{3}\right)^x$
- $j(x) = (-2)^x$

**Solution**

By definition, an exponential function has a constant as a base and an independent variable as an exponent. Thus, $g(x) = x^3$ does not represent an exponential function because the base is an independent variable. In fact, $g(x) = x^3$ is a power function.

Recall that the base $b$ of an exponential function is always a positive constant, and $b \neq 1$. Thus, $j(x) = (-2)^x$ does not represent an exponential function because the base, $-2$, is less than $0$.

**Exercise 5.2.1**

Which of the following equations represent exponential functions?

- $f(x) = 2x^2 - 3x + 1$
- $g(x) = 0.875^x$
- $h(x) = 1.75x + 2$
- $j(x) = 1095.6^{-2x}$

**Answer**

$g(x) = 0.875^x$ and $j(x) = 1095.6^{-2x}$ represent exponential functions.

## Evaluating Exponential Functions

Recall that the base of an exponential function must be a positive real number other than 1.Why do we limit the base bb to positive values? To ensure that the outputs will be real numbers. Observe what happens if the base is not positive:

- Let $b = -9$ and $x = \frac{1}{2}$. Then $f(x) = f\left(\frac{1}{2}\right) = (-9)^{\frac{1}{2}} = \sqrt{-9}$ ,which is not a real number.

Why do we limit the base to positive values other than 1? Because base 1 results in the constant function. Observe what happens if the base is 1:

- Let $b = 1$. Then $f(x) = 1^x = 1$ for any value of $x$.

To evaluate an exponential function with the form $f(x) = b^x$,we simply substitute $x$ with the given value, and calculate the resulting power. For example:

Let $f(x) = 2^x$. What is $f(3)$?

$$\begin{aligned} f(x) &= 2^x \\ f(3) &= 2^3 \qquad \text{Substitute } x = 3 \\ &= 8 \qquad \text{Evaluate the power} \end{aligned}$$

To evaluate an exponential function with a form other than the basic form, it is important to follow the order of operations. For example:

Let $f(x) = 30(2)^x$. What is $f(3)$?

$$\begin{aligned} f(x) &= 30(2)^x \\ f(3) &= 30(2)^3 \qquad \text{Substitute } x = 3 \\ &= 30(8) \qquad \text{Simplify the power first} \\ &= 240 \qquad \text{Multiply} \end{aligned}$$

Note that if the order of operations were not followed, the result would be incorrect:

$$f(3) = 30(2)^3 \neq 60^3 = 216,000$$

### Example 5.2.2: Evaluating Exponential Functions

Let $f(x) = 5(3)^{x+1}$. Evaluate $f(2)$ without using a calculator.

**Solution**

Follow the order of operations. Be sure to pay attention to the parentheses.

$$\begin{aligned} f(x) &= 5(3)^{x+1} \\ f(2) &= 5(3)^{2+1} \qquad \text{Substitute } x = 2 \\ &= 5(3)^3 \qquad \text{Add the exponents} \\ &= 5(27) \qquad \text{Simplify the power} \\ &= 135 \qquad \text{Multiply} \end{aligned}$$

### Exercise 5.2.2

Let $f(x) = 8(1.2)^{x-5}$. Evaluate $f(3)$ using a calculator. Round to four decimal places.

**Answer**

5.5556

## Defining Exponential Growth

Because the output of exponential functions increases very rapidly, the term “exponential growth” is often used in everyday language to describe anything that grows or increases rapidly. However, exponential growth can be defined more precisely in a mathematical sense. If the growth rate is proportional to the amount present, the function models exponential growth.

### Definition: Exponential Growth

A function that models exponential growth grows by a rate proportional to the amount present. For any real number $x$ and any positive real numbers $a$ and $b$ such that $b \neq 1$,an exponential growth function has the form

$$f(x) = ab^x \tag{5.2.2}$$

where

- $a$ is the initial or starting value of the function.
- $b$ is the growth factor or growth multiplier per unit $x$.

In more general terms, we have an *exponential function*, in which a constant base is raised to a variable exponent. To differentiate between linear and exponential functions, let's consider two companies, A and B. Company A has 100 stores and expands by opening 50 new stores a year, so its growth can be represented by the function $A(x) = 100 + 50x$. Company B has 100 stores and expands by increasing the number of stores by 50% each year, so its growth can be represented by the function $B(x) = 100(1 + 0.5)^x$.

A few years of growth for these companies are illustrated in Table 5.2.3.

Table 5.2.3

| Year, $x$ | Stores, Company A | Stores, Company B |
|---|---|---|
| 0 | $100 + 50(0) = 100$ | $100(1 + 0.5)^0 = 100$ |
| 1 | $100 + 50(1) = 150$ | $100(1 + 0.5)^1 = 150$ |
| 2 | $100 + 50(2) = 200$ | $100(1 + 0.5)^2 = 225$ |
| 3 | $100 + 50(3) = 250$ | $100(1 + 0.5)^3 = 337.5$ |
| $x$ | $A(x) = 100 + 50x$ | $B(x) = 100(1 + 0.5)^x$ |

The graphs comparing the number of stores for each company over a five-year period are shown in Figure 5.2.2. We can see that, with exponential growth, the number of stores increases much more rapidly than with linear growth.





Figure 5.2.2: The graph shows the numbers of stores Companies A and B opened over a five-year period.

Notice that the domain for both functions is $[0, \infty)$,and the range for both functions is $[100, \infty)$. After year 1, Company B always has more stores than Company A.

Now we will turn our attention to the function representing the number of stores for Company $B$, $B(x) = 100(1 + 0.5)^x$. In this exponential function, 100 represents the initial number of stores, 0.50 represents the growth rate, and $1 + 0.5 = 1.5$ represents the

growth factor. Generalizing further, we can write this function as $B(x) = 100(1.5)^x$,where $100$ is the initial value, $1.5$ is called the *base*, and $x$ is called the *exponent*.

### Example 5.2.3: Evaluating a Real-World Exponential Model

At the beginning of this section, we learned that the population of India was about $1.25$ billion in the year 2013, with an annual growth rate of about $1.2\%$. This situation is represented by the growth function $P(t) = 1.25(1.012)^t$, where $t$ is the number of years since 2013. To the nearest thousandth, what will the population of India be in 2031?

**Solution**

To estimate the population in 2031, we evaluate the models for $t = 18$, because 2031 is 18 years after 2013. Rounding to the nearest thousandth,

$$P(18) = 1.25(1.012)^{18} \approx 1.549$$

There will be about $1.549$ billion people in India in the year 2031.

### Exercise 5.2.3

The population of China was about $1.39$ billion in the year 2013, with an annual growth rate of about $0.6\%$. This situation is represented by the growth function $P(t) = 1.39(1.006)^t$, where $t$ is the number of years since 2013.To the nearest thousandth, what will the population of China be for the year 2031? How does this compare to the population prediction we made for India in Example 5.2.3?

**Answer**

About $1.548$ billion people; by the year 2031, India's population will exceed China's by about $0.001$ billion, or 1 million people.

## Finding Equations of Exponential Functions

In the previous examples, we were given an exponential function, which we then evaluated for a given input. Sometimes we are given information about an exponential function without knowing the function explicitly. We must use the information to first write the form of the function, then determine the constants $a$, $a$ and $b$, $b$,and evaluate the function.

### How to: Given two data points, write an exponential model

1. If one of the data points has the form $(0, a)$, then $a$ is the initial value. Using $a$, substitute the second point into the equation $f(x) = a(b)^x$, and solve for $b$.
2. If neither of the data points have the form $(0, a)$, substitute both points into two equations with the form $f(x) = a(b)^x$. Solve the resulting system of two equations in two unknowns to find $a$ and $b$.
3. Using the $a$ and $b$ found in the steps above, write the exponential function in the form $f(x) = a(b)^x$.

### Example 5.2.4: Writing an Exponential Model When the Initial Value Is Known

In 2006, 80 deer were introduced into a wildlife refuge. By 2012, the population had grown to 180 deer. The population was growing exponentially. Write an algebraic function $N(t)$ representing the population $(N)$ of deer over time $t$.

**Solution**

We let our independent variable $t$ be the number of years after 2006. Thus, the information given in the problem can be written as input-output pairs: (0, 80) and (6, 180). Notice that by choosing our input variable to be measured as years after 2006, we have given ourselves the initial value for the function, $a = 80$. We can now substitute the second point into the equation $N(t) = 80b^t$ to find $b$:

$$
\begin{aligned}
N(t) &= 80b^t \\
180 &= 80b^6 && \text{Substitute using point } (6, 180) \\
\frac{9}{4} &= b^6 && \text{Divide and write in lowest terms} \\
b &= \left(\frac{9}{4}\right)^{\frac{1}{6}} && \text{Isolate b using properties of exponents} \\
b &\approx 1.1447 && \text{Round to 4 decimal places}
\end{aligned}
$$

> *Unless otherwise stated, do not round any intermediate calculations. Then round the final answer to four places for the remainder of this section.*

The exponential model for the population of deer is $N(t) = 80(1.1447)^t$. (Note that this exponential function models short-term growth. As the inputs gets large, the output will get increasingly larger, so much so that the model may not be useful in the long term.)

We can graph our model to observe the population growth of deer in the refuge over time. Notice that the graph in Figure $5.2.3$ passes through the initial points given in the problem, $(0, 80)$ and $(6, 180)$. We can also see that the domain for the function is $[0, \infty)$,and the range for the function is $[80, \infty)$.





Figure $5.2.3$: Graph showing the population of deer over time, $N(t) = 80(1.1447)^t$, $t$ years after 2006

## Exercise $5.2.4$

A wolf population is growing exponentially. In 2011, $129$ wolves were counted. By 2013, the population had reached $236$ wolves. What two points can be used to derive an exponential equation modeling this situation? Write the equation representing the population $N$ of wolves over time $t$.

**Answer**

$(0, 129)$ and $(2, 236)$; $N(t) = 129(1.3526)^t$

### Example 5.2.5: Writing an Exponential Model When the Initial Value is Not Known

Find an exponential function that passes through the points $(-2, 6)$ and $(2, 1)$.

**Solution**

Because we don't have the initial value, we substitute both points into an equation of the form $f(x) = ab^x$, and then solve the system for $a$ and $b$.

- Substituting $(-2, 6)$ gives $6 = ab^{-2}$
- Substituting $(2, 1)$ gives $1 = ab^2$

Use the first equation to solve for $a$ in terms of $b$:

$$\begin{aligned} 6 &= ab^{-2} \\ \frac{6}{b^{-2}} &= a \qquad \text{Divide} \\ a &= 6b^2 \qquad \text{Use properties of exponents to rewrite the denominator} \end{aligned}$$

Substitute a in the second equation, and solve for $b$:

$$\begin{aligned} 1 &= ab^2 \\ 1 &= 6b^2b^2 \\ &= 6b^4 \qquad \text{Substitute a} \\ b &= \left(\frac{1}{6}\right)^{\frac{1}{4}} \qquad \text{Round 4 decimal places rewrite the denominator} \\ b &\approx 0.6389 \end{aligned}$$

Use the value of $b$ in the first equation to solve for the value of $a$:

$$\begin{aligned} a &= 6b^2 \\ &\approx 6(0.6389)^2 \\ &\approx 2.4492 \end{aligned}$$

Thus, the equation is $f(x) = 2.4492(0.6389)^x$.

We can graph our model to check our work. Notice that the graph in Figure 5.2.4 passes through the initial points given in the problem, $(-2, 6)$ and $(2, 1)$. The graph is an example of an exponential decay function.





Figure 5.2.4: The graph of $f(x) = 2.4492(0.6389)^x$ models exponential decay.

## Exercise 5.2.5

Given the two points $(1, 3)$ and $(2, 4.5)$, find the equation of the exponential function that passes through these two points.

**Answer**

$f(x) = 2(1.5)^x$

## Q&A: Do two points always determine a unique exponential function?

*Yes, provided the two points are either both above the x-axis or both below the x-axis and have different x-coordinates. But keep in mind that we also need to know that the graph is, in fact, an exponential function. Not every graph that looks exponential really is exponential. We need to know the graph is based on a model that shows the same percent growth with each unit increase in $x$, which in many real world cases involves time.*

## How to: Given the graph of an exponential function, write its equation

1. First, identify two points on the graph. Choose the $y$-intercept as one of the two points whenever possible. Try to choose points that are as far apart as possible to reduce round-off error.
2. If one of the data points is the $y$-intercept $(0, a)$, then $a$ is the initial value. Using $a$, substitute the second point into the equation $f(x) = a(b)^x$, and solve for $b$
3. If neither of the data points have the form $(0, a)$, substitute both points into two equations with the form $f(x) = a(b)^x$. Solve the resulting system of two equations in two unknowns to find $a$ and $b$.
4. Write the exponential function, $f(x) = a(b)^x$.

## Example 5.2.6: Writing an Exponential Function Given Its Graph

Find an equation for the exponential function graphed in Figure 5.2.5.





Figure 5.2.5

**Solution**

We can choose the $y$-intercept of the graph, $(0, 3)$, as our first point. This gives us the initial value, $a = 3$. Next, choose a point on the curve some distance away from $(0, 3)$ that has integer coordinates. One such point is $(2, 12)$.

$$\begin{aligned} y &= ab^x && \text{Write the general form of an exponential equation} \\ y &= 3b^x && \text{Substitute the initial value 3 for } a \\ 12 &= 3b^2 && \text{Substitute in 12 for } y \text{ and 2 for } x \\ 4 &= b^2 && \text{Divide by 3} \\ b &= \pm 2 && \text{Take the square root} \end{aligned}$$

Because we restrict ourselves to positive values of $b$, we will use $b = 2$. Substitute $a$ and $b$ into the standard form to yield the equation $f(x) = 3(2)^x$.

### Exercise 5.2.6

Find an equation for the exponential function graphed in Figure 5.2.6.





Figure 5.2.6

**Answer**

$f(x) = \sqrt{2}(\sqrt{2})^x$ . Answers may vary due to round-off error. The answer should be very close to $1.4142(1.4142)^x$.

### How to: Given two points on the curve of an exponential function, use a graphing calculator to find the equation

1. Press **[STAT].**
2. Clear any existing entries in columns **L1** or **L2.**
3. In **L1**, enter the *x*-coordinates given.
4. In **L2**, enter the corresponding *y*-coordinates.
5. Press **[STAT]** again. Cursor right to **CALC**, scroll down to **ExpReg (Exponential Regression)**, and press **[ENTER].**
6. The screen displays the values of *a* and *b* in the exponential equation $y = a \cdot b^x$ .

### Example 5.2.7: Using a Graphing Calculator to Find an Exponential Function

Use a graphing calculator to find the exponential equation that includes the points $(2, 24.8)$ and $(5, 198.4)$.

**Solution**

Follow the guidelines above. First press **[STAT]**, **[EDIT]**, **[1: Edit…],** and clear the lists **L1** and **L2**. Next, in the **L1** column, enter the $x$-coordinates, 2 and 5. Do the same in the **L2** column for the $y$-coordinates, 24.8 and 198.4.

Now press **[STAT]**, **[CALC]**, **[0: ExpReg]** and press **[ENTER]**. The values $a = 6.2$ and $b = 2$ will be displayed. The exponential equation is $y = 6.2 \cdot 2^x$ .

### Exercise 5.2.7

Use a graphing calculator to find the exponential equation that includes the points $(3, 75.98)$ and $(6, 481.07)$.

**Answer**

$y \approx 12 \cdot 1.85^x$

## Applying the Compound-Interest Formula

Savings instruments in which earnings are continually reinvested, such as mutual funds and retirement accounts, use **compound interest**. The term *compounding* refers to interest earned not only on the original value, but on the accumulated value of the

account.

The **annual percentage rate (APR)** of an account, also called the **nominal rate**, is the yearly interest rate earned by an investment account. The term *nominal* is used when the compounding occurs a number of times other than once per year. In fact, when interest is compounded more than once a year, the effective interest rate ends up being *greater* than the nominal rate! This is a powerful tool for investing.

We can calculate the compound interest using the compound interest formula, which is an exponential function of the variables time $t$, principal $P$, $APR$ $r$, and number of compounding periods in a year $n$:

$$A(t) = P\left(1 + \frac{r}{n}\right)^{nt}$$

For example, observe Table 5.2.4, which shows the result of investing $\$1,000$ at $10\%$ for one year. Notice how the value of the account increases as the compounding frequency increases.

Table 5.2.4

| Frequency | Value after 1 year |
|---|---|
| Annually | $1100 |
| Semiannually | $1102.50 |
| Quarterly | $1103.81 |
| Monthly | $1104.71 |
| Daily | $1105.16 |

**Definition: Compound Interest**

*Compound interest* can be calculated using the formula

$$A(t) = P\left(1 + \frac{r}{n}\right)^{nt} \tag{5.2.3}$$

where

- $A(t)$ is the account value,
- $t$ is measured in years,
- $P$ is the starting amount of the account, often called the principal, or more generally present value,
- $r$ is the annual percentage rate (APR) expressed as a decimal, and
- $n$ is the number of compounding periods in one year.

**Example 5.2.8: Calculating Compound Interest**

If we invest $\$3,000$ in an investment account paying $3\%$ interest compounded quarterly, how much will the account be worth in 10 years?

**Solution**

Because we are starting with $\$3,000$, $P = 3000$. Our interest rate is $3\%$, so $r = 0.03$. Because we are compounding quarterly, we are compounding 4 times per year, so $n = 4$. We want to know the value of the account in 10 years, so we are looking for $A(10)$,the value when $t = 10$.

$$A(t) = P\left(1 + \frac{r}{n}\right)^{nt} \quad \text{Use the compound interest formula}$$

$$A(10) = 3000\left(1 + \frac{0.03}{4}\right)^{(4)\cdot(10)} \quad \text{Substitute using given values}$$

$$\approx \$4045.05 \quad \text{Round to two decimal places}$$

The account will be worth about $\$4,045.05$ in 10 years.

**Exercise 5.2.8**

An initial investment of $\$100,000$ at $12\%$ interest is compounded weekly (use $52$ weeks in a year). What will the investment be worth in $30$ years?

**Answer**

about $\$3,644,675.88$

**Example 5.2.9: Using the Compound Interest Formula to Solve for the Principal**

A 529 Plan is a college-savings plan that allows relatives to invest money to pay for a child's future college tuition; the account grows tax-free. Lily wants to set up a 529 account for her new granddaughter and wants the account to grow to $\$40,000$ over $18$ years. She believes the account will earn $6\%$ compounded semi-annually (twice a year). To the nearest dollar, how much will Lily need to invest in the account now?

**Solution**

The nominal interest rate is $6\%$, so $r = 0.06$. Interest is compounded twice a year, so $k = 2$.

We want to find the initial investment, $P$, needed so that the value of the account will be worth $\$40,000$ in $18$ years. Substitute the given values into the compound interest formula, and solve for $P$.

$$A(t) = P\left(1+\frac{r}{n}\right)^{nt} \quad \text{Use the compound interest formula}$$

$$40,000 = P\left(1+\frac{0.06}{2}\right)^{2(18)} \quad \text{Substitute using given values } A, r, n, t$$

$$40,000 = P(1.03)^{36} \quad \text{Simplify}$$

$$\frac{40,000}{(1.03)^{36}} = P \quad \text{Isolate } P$$

$$P \approx \$13,801 \quad \text{Divide and round to the nearest dollar}$$

Lily will need to invest $\$13,801$ to have $\$40,000$ in $18$ years.

**Exercise 5.2.9**

Refer to Example 5.2.9. To the nearest dollar, how much would Lily need to invest if the account is compounded quarterly?

**Answer**

$\$13,693$

## Evaluating Functions with Base $e$

As we saw earlier, the amount earned on an account increases as the compounding frequency increases. Table 5.2.5 shows that the increase from annual to semi-annual compounding is larger than the increase from monthly to daily compounding. This might lead us to ask whether this pattern will continue.

Examine the value of $\$1$ invested at $100\%$ interest for $1$ year, compounded at various frequencies, listed in Table 5.2.5.

Table 5.2.5

| Frequency | $A(t) = \left(1+\frac{1}{n}\right)^n$ | Value |
|---|---|---|
| Annually | $\left(1+\frac{1}{1}\right)^1$ | $\$2$ |
| Semiannually | $\left(1+\frac{1}{2}\right)^2$ | $\$2.25$ |

| Frequency | $A(t)=\left(1+\frac{1}{n}\right)^n$ | Value |
|---|---|---|
| Quarterly | $\left(1+\frac{1}{4}\right)^4$ | $2.441406 |
| Monthly | $\left(1+\frac{1}{12}\right)^{12}$ | $2.613035 |
| Daily | $\left(1+\frac{1}{365}\right)^{365}$ | $2.714567 |
| Hourly | $\left(1+\frac{1}{8760}\right)^{8760}$ | $2.718127 |
| Once per minute | $\left(1+\frac{1}{525600}\right)^{525600}$ | $2.718279 |
| Once per second | $\left(1+\frac{1}{31536000}\right)^{31536000}$ | $2.718282 |

These values appear to be approaching a limit as $n$ increases without bound. In fact, as $n$ gets larger and larger, the expression $\left(1+\frac{1}{n}\right)^n$ approaches a number used so frequently in mathematics that it has its own name: the letter $e$. This value is an irrational number, which means that its decimal expansion goes on forever without repeating. Its approximation to six decimal places is shown below.

**Definition: The Number e**

The letter $e$ represents the irrational number

$$\left(1+\frac{1}{n}\right)^n \tag{5.2.4}$$

as $n$ increases without bound

The letter $e$ is used as a base for many real-world exponential models. To work with base $e$, we use the approximation, $e \approx 2.718282$. The constant was named by the Swiss mathematician Leonhard Euler (1707–1783) who first investigated and discovered many of its properties.

**Example 5.2.10: Using a Calculator to Find Powers of $e$**

Calculate $e^{3.14}$. Round to five decimal places.

**Solution**

On a calculator, press the button labeled [$e^x$]. The window shows [$e^($]. Type 3.14 and then close parenthesis, [)]. Press [ENTER]. Rounding to 5 decimal places, $e^{3.14} \approx 23.10387$. Caution: Many scientific calculators have an "Exp" button, which is used to enter numbers in scientific notation. It is not used to find powers of $e$.

**Exercise 5.2.10**

Use a calculator to find $e^{-0.5}$. Round to five decimal places.

**Answer**

$e^{-0.5} \approx 0.60653$

## Investigating Continuous Growth

So far we have worked with rational bases for exponential functions. For most real-world phenomena, however, $e$ is used as the base for exponential functions. Exponential models that use $e$ as the base are called continuous growth or decay models. We see these models in finance, computer science, and most of the sciences, such as physics, toxicology, and fluid dynamics.

### Definition: The Continuous Growth/decay Formula

For all real numbers $t$,and all positive numbers $a$ and $r$, continuous growth or decay is represented by the formula

$$A(t) = ae^{rt} \tag{5.2.5}$$

where

- $a$ is the initial value,
- $r$ is the continuous growth rate per unit time,
- $t$ is the elapsed time.

If $r > 0$, then the formula represents continuous growth. If $r < 0$, then the formula represents continuous decay.

For business applications, the continuous growth formula is called the continuous compounding formula and takes the form

$$A(t) = Pe^{rt} \tag{5.2.6}$$

where

- $P$ is the principal or the initial invested,
- $r$ is the growth or interest rate per unit time,
- $t$ is the period or term of the investment.

### How to: Given the initial value, rate of growth or decay, and time $t$, solve a continuous growth or decay function

1. Use the information in the problem to determine $a$, the initial value of the function.
2. Use the information in the problem to determine the growth rate $r$.
   - If the problem refers to continuous growth, then $r > 0$.
   - If the problem refers to continuous decay, then $r < 0$.
3. Use the information in the problem to determine the time $t$.
4. Substitute the given information into the continuous growth formula and solve for $A(t)$.

### Example 5.2.11: Calculating Continuous Growth

A person invested $\$1,000$ in an account earning a nominal $10\%$ per year compounded continuously. How much was in the account at the end of one year?

**Solution**

Since the account is growing in value, this is a continuous compounding problem with growth rate $r = 0.10$. The initial investment was $\$1,000$, so $P = 1000$. We use the continuous compounding formula to find the value after $t = 1$ year:

$$\begin{aligned} A(t) &= Pe^{rt} && \text{Use the continuous compounding formula} \\ &= 1000(e)^{0.1} && \text{Substitute known values for } P, r, t \\ &\approx 1105.17 && \text{Use a calculator to approximate} \end{aligned}$$

The account is worth $\$1,105.17$after one year.

### Exercise 5.2.11

A person invests $\$100,000$ at a nominal $12\%$ interest per year compounded continuously. What will be the value of the investment in $30$ years?

**Answer**

$\$3,659,823.44$

### Example 5.2.12: Calculating Continuous Decay

$Radon-222$ decays at a continuous rate of $17.3\%$ per day. How much will $100mg$ of $Radon-222$ decay to in 3 days?

**Solution**

Since the substance is decaying, the rate, $17.3\%$, is negative. So, $r=-0.173$. The initial amount of $Radon-222$ was 100 mg, so $a=100$. We use the continuous decay formula to find the value after $t=3$ days:

$$\begin{aligned} A(t) &= ae^{rt} && \text{Use the continuous growth formula} \\ &= 100e6-0.173(3) && \text{Substitute known values for } a, r, t \\ &\approx 59.5115 && \text{Use a calculator to approximate} \end{aligned}$$

So $59.5115$mg of $Radon-222$ will remain.

### Exercise 5.2.12

Using the data in Example 5.2.12, how much $Radon-222$ will remain after one year?

**Answer**

$3.77E-26$ (This is calculator notation for the number written as $3.77\times10^{-26}$ in scientific notation. While the output of an exponential function is never zero, this number is so close to zero that for all practical purposes we can accept zero as the answer.)

### Media

Access these online resources for additional instruction and practice with exponential functions.

- Exponential Growth Function
- Compound Interest

## Key Equations

| | |
|---|---|
| definition of the exponential function | $f(x)=b^x$, where $b>0, b\neq1$ |
| definition of exponential growth | $f(x)=ab^x$, where $a>0, b>0, b\neq1$ |
| compound interest formula | $A(t)=P(1+\frac{r}{n})^{nt}$,<br>where $A(t)$ is the account value at time $t$<br>$t$ is the number of years<br>$P$ is the initial investment, often called the principal<br>$r$ is the annual percentage rate (APR), or nominal rate<br>$n$ is the number of compounding periods in one year |
| continuous growth formula | $A(t)=ae^{rt}$, where $t$ is the number of unit time periods of growth $a$ is the starting amount (in the continuous compounding formula a is replaced with $P$, the principal) $e$ is the mathematical constant, $e\approx2.718282$ |

## Key Concepts

- An exponential function is defined as a function with a positive constant other than 1 raised to a variable exponent. See Example.
- A function is evaluated by solving at a specific value. See Example and Example.

- An exponential model can be found when the growth rate and initial value are known. See Example.
- An exponential model can be found when the two data points from the model are known. See Example.
- An exponential model can be found using two data points from the graph of the model. See Example.
- An exponential model can be found using two data points from the graph and a calculator. See Example.
- The value of an account at any time $t$ can be calculated using the compound interest formula when the principal, annual interest rate, and compounding periods are known. See Example.
- The initial investment of an account can be found using the compound interest formula when the value of the account, annual interest rate, compounding periods, and life span of the account are known. See Example.
- The number $e$ is a mathematical constant often used as the base of real world exponential growth and decay models. Its decimal approximation is $e \approx 2.718282$.
- Scientific and graphing calculators have the key $[ex]$ or $[exp(x)]$ for calculating powers of $e$. See Example.
- Continuous growth or decay models are exponential models that use $e$ as the base. Continuous growth and decay models can be found when the initial value and growth or decay rate are known. See Example and Example.

---

This page titled 5.2: Exponential Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.1: Exponential Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.2E: Exponential Functions (Exercises)

1. Determine whether the function $y = 156(0.825)^t$ represents exponential growth, exponential decay, or neither. Explain

2. The population of a herd of deer is represented by the function $A(t) = 205(1.13)^t$, where $t$ is given in years. To the nearest whole number, what will the herd population be after 6 years?

3. Find an exponential equation that passes through the points (2,2.25) and (5,60.75) .

4. Determine whether Table 1 could represent a function that is linear, exponential, or neither. If it appears to be exponential, find a function that passes through the points.

Table 1

| ***x*** | 1 | 2 | 3 | 4 |
|---|---|---|---|---|
| ***f(x)*** | 3 | 0.9 | 0.27 | 0.081 |

5. A retirement account is opened with an initial deposit of $\$8,500$ and earns $8.12\%$ interest compounded monthly. What will the account be worth in 20 years?

6. Hsu-Mei wants to save $\$5,000$ for a down payment on a car. To the nearest dollar, how much will she need to invest in an account now with $7.5\%$ APR, compounded daily, in order to reach her goal in 3 years?

7. Does the equation $y = 2.294e^{-0.654t}$ represent continuous growth, continuous decay, or neither? Explain.

8. Suppose an investment account is opened with an initial deposit of $\$10,500$ earning $6.25\%$ interest, compounded continuously. How much will the account be worth after 25 years?

---

This page titled 5.2E: Exponential Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.1E: Exponential Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.3: Graphs of Exponential Functions

**Learning Objectives**

- Graph exponential functions.
- Graph exponential functions using transformations.

As we discussed in the previous section, exponential functions are used for many real-world applications such as finance, forensics, computer science, and most of the life sciences. Working with an equation that describes a real-world situation gives us a method for making predictions. Most of the time, however, the equation itself is not enough. We learn a lot about things by seeing their pictorial representations, and that is exactly why graphing exponential equations is a powerful tool. It gives us another layer of insight for predicting future events.

## Graphing Exponential Functions

Before we begin graphing, it is helpful to review the behavior of exponential growth. Recall the table of values for a function of the form $f(x) = b^x$ whose base is greater than one. We'll use the function $f(x) = 2^x$. Observe how the output values in Table 5.3.1 change as the input increases by 1.

Table 5.3.1

| $x$ | $-3$ | $-2$ | $-1$ | $0$ | $1$ | $2$ | $3$ |
|---|---|---|---|---|---|---|---|
| $f(x) = 2^x$ | $\frac{1}{8}$ | $\frac{1}{4}$ | $\frac{1}{2}$ | $1$ | $2$ | $4$ | $8$ |

Each output value is the product of the previous output and the base, 2. We call the base 2 the *constant ratio*. In fact, for any exponential function with the form $f(x) = ab^x$, $b$ is the constant ratio of the function. This means that as the input increases by 1, the output value will be the product of the base and the previous output, regardless of the value of $a$.

Notice from the table that

- the output values are positive for all values of $x$;
- as $x$ increases, the output values increase without bound; and
- as $x$ decreases, the output values grow smaller, approaching zero.

Figure 5.3.1 shows the exponential growth function $f(x) = 2^x$.





Figure 5.3.1: Notice that the graph gets close to the x-axis, but never touches it.

The domain of $f(x) = 2^x$ is all real numbers, the range is $(0, \infty)$, and the horizontal asymptote is $y = 0$.

To get a sense of the behavior of exponential decay, we can create a table of values for a function of the form $f(x) = b^x$ whose base is between zero and one. We'll use the function $g(x) = \left(\frac{1}{2}\right)^x$. Observe how the output values in Table $5.3.2$ change as the input increases by $1$.

Table $5.3.2$

| $x$ | $-3$ | $-2$ | $-1$ | $0$ | $1$ | $2$ | $3$ |
|---|---|---|---|---|---|---|---|
| $g(x) = \left(\frac{1}{2}\right)^x$ | $8$ | $4$ | $2$ | $1$ | $\frac{1}{2}$ | $\frac{1}{4}$ | $\frac{1}{8}$ |

Again, because the input is increasing by $1$, each output value is the product of the previous output and the base, or constant ratio $\frac{1}{2}$.

Notice from the table that

- the output values are positive for all values of $x$;
- as $x$ increases, the output values grow smaller, approaching zero; and
- as $x$ decreases, the output values grow without bound.

Figure $5.3.2$ shows the exponential decay function, $g(x) = \left(\frac{1}{2}\right)^x$.





Figure $5.3.2$

The domain of $g(x) = (\frac{1}{2})^x$ is all real numbers, the range is $(0, \infty)$,and the horizontal asymptote is $y = 0$.

### CHARACTERISTICS OF THE GRAPH OF THE PARENT FUNCTION $F(X) = b^x$

An exponential function with the form $f(x) = b^x$, $b > 0$, $b \neq 1$,has these characteristics:

- one-to-one function
- horizontal asymptote: $y = 0$
- domain: $(-\infty, \infty)$
- range: $(0, \infty)$
- $x$-intercept: none

- $y$-intercept: $(0, 1)$
- increasing if $b > 1$
- decreasing if $b < 1$

Figure $5.3.3$ compares the graphs of exponential growth and decay functions.



1 and the second graph is of the same function when b is 0

**Figure 5.3.3**

**How to: Given an exponential function of the form $f(x) = b^x$ ,graph the function**

1. Create a table of points.
2. Plot at least 3 point from the table, including the $y$-intercept $(0, 1)$.
3. Draw a smooth curve through the points.
4. State the domain, $(-\infty, \infty)$,the range, $(0, \infty)$,and the horizontal asymptote, $y = 0$.

**Example 5.3.1: Sketching the Graph of an Exponential Function of the Form $f(x) = b^x$**

Sketch a graph of $f(x) = 0.25^x$. State the domain, range, and asymptote.

**Solution**

Before graphing, identify the behavior and create a table of points for the graph.

Table 5.3.3

| $x$ | $-3$ | $-2$ | $-1$ | $0$ | $1$ | $2$ | $3$ |
|---|---|---|---|---|---|---|---|
| $f(x) = 0.25^x$ | 64 | 16 | 4 | 1 | 0.25 | \(0.0625\0 | 0.015625 |

- Since $b = 0.25$ is between zero and one, we know the function is decreasing. The left tail of the graph will increase without bound, and the right tail will approach the asymptote $y = 0$.
- Create a table of points as in Table $5.3.3$.
- Plot the $y$-intercept, $(0, 1)$,along with two other points. We can use $(-1, 4)$ and $(1, 0.25)$.

Draw a smooth curve connecting the points as in Figure $5.3.4$.





Figure 5.3.4


The domain is $(-\infty, \infty)$; the range is $(0, \infty)$; the horizontal asymptote is $y = 0$.

**Exercise 5.3.1**

Sketch the graph of $f(x) = 4^x$. State the domain, range, and asymptote.

**Answer**

The domain is $(-\infty, \infty)$; the range is $(0, \infty)$; the horizontal asymptote is $y = 0$.




## Graphing Transformations of Exponential Functions

Transformations of exponential graphs behave similarly to those of other functions. Just as with other parent functions, we can apply the four types of transformations—shifts, reflections, stretches, and compressions—to the parent function $f(x) = b^x$ without loss of shape. For instance, just as the quadratic function maintains its parabolic shape when shifted, reflected, stretched, or compressed, the exponential function also maintains its general shape regardless of the transformations applied.

### Graphing a Vertical Shift

The first transformation occurs when we add a constant $d$ to the parent function $f(x) = b^x$, giving us a vertical shiftd d units in the same direction as the sign. For example, if we begin by graphing a parent function, $f(x) = 2^x$, we can then graph two vertical shifts alongside it, using $d = 3$: the upward shift, $g(x) = 2^x + 3$ and the downward shift, $h(x) = 2^x - 3$. Both vertical shifts are shown in Figure 5.3.5.





Figure 5.3.5

Observe the results of shifting $f(x) = 2^x$ vertically:

- The domain, $(-\infty, \infty)$ remains unchanged.

- When the function is shifted up 3 units to $g(x) = 2^x + 3$ :
  - The *y*-intercept shifts up 3 units to $(0, 4)$.
  - The asymptote shifts up 3 units to $y = 3$.
  - The range becomes $(3, \infty)$.
- When the function is shifted down 3 units to $h(x) = 2^x - 3$ :
  - The *y*-intercept shifts down 3 units to $(0, -2)$.
  - The asymptote also shifts down 3 units to $y = -3$.
  - The range becomes $(-3, \infty)$.

### Graphing a Horizontal Shift

The next transformation occurs when we add a constant $c$ to the input of the parent function $f(x) = b^x$, giving us a horizontal shift $c$ units in the *opposite* direction of the sign. For example, if we begin by graphing the parent function $f(x) = 2^x$, we can then graph two horizontal shifts alongside it, using $c = 3$: the shift left, $g(x) = 2^{x+3}$ , and the shift right, $h(x) = 2^{x-3}$ . $h(x) = 2^{x-3}$ . Both horizontal shifts are shown in Figure 5.3.6.





Figure 5.3.6

Observe the results of shifting $f(x) = 2^x$ horizontally:

- The domain, $(-\infty, \infty)$,remains unchanged.
- The asymptote, $y = 0$,remains unchanged.
- The *y*-intercept shifts such that:
  - When the function is shifted left 3 units to $g(x) = 2^{x+3}$ ,the *y*-intercept becomes $(0, 8)$. This is because $2^{x+3} = (8)2^x$ ,so the initial value of the function is 8.
  - When the function is shifted right 3 units to $h(x) = 2^{x-3}$ ,the *y*-intercept becomes $(0, \frac{1}{8})$. Again, see that $2^{x-3} = (\frac{1}{8})2^x$ ,so the initial value of the function is $\frac{1}{8}$.

**SHIFTS OF THE PARENT FUNCTION $F(X) = b^x$**

For any constants $c$ and $d$,the function $f(x) = b^{x+c} + d$ shifts the parent function $f(x) = b^x$

- vertically $d$ units, in the *same* direction of the sign of $d$.
- horizontally $c$ units, in the *opposite* direction of the sign of $c$.
- The *y*-intercept becomes $(0, b^c + d)$.
- The horizontal asymptote becomes $y = d$.
- The range becomes $(d, \infty)$.

- The domain, $(-\infty, \infty)$,remains unchanged.

**How to: Given an exponential function with the form $f(x) = b^{x+c} + d$, graph the translation**

1. Draw the horizontal asymptote $y = d$.
2. Identify the shift as $(-c, d)$. Shift the graph of $f(x) = b^x$ left $c$ units if $c$ is positive, and right $c$ units if $c$ is negative.
3. Shift the graph of $f(x) = b^x$ up $d$ units if $d$ is positive, and down $d$ units if $d$ is negative.
4. State the domain, $(-\infty, \infty)$,the range, $(d, \infty)$,and the horizontal asymptote $y = d$.

**Example 5.3.2: Graphing a Shift of an Exponential Function**

Graph $f(x) = 2^{x+1} - 3$. State the domain, range, and asymptote.

**Solution**

We have an exponential equation of the form $f(x) = b^{x+c} + d$, with $b = 2$, $c = 1$, and $d = -3$.

Draw the horizontal asymptote $y = d$, so draw $y = -3$.

Identify the shift as $(-c, d)$, so the shift is $(-1, -3)$.

Shift the graph of $f(x) = b^x$ left 1 units and down 3 units.





Figure 5.3.7


The domain is $(-\infty, \infty)$; the range is $(-3, \infty)$; the horizontal asymptote is $y = -3$.

**Exercise 5.3.2**

Graph $f(x) = 2^{x-1} + 3$. State domain, range, and asymptote.

**Answer**

The domain is $(-\infty, \infty)$ ; the range is $(3, \infty)$; the horizontal asymptote is $y = 3$.




**How to: Given an equation of the form $f(x) = b^{x+c} + d$ for $x$, use a graphing calculator to approximate the solution**

- Press **[Y=]**. Enter the given exponential equation in the line headed "$\mathbf{Y_1}$=".
- Enter the given value forf(x) f(x) in the line headed "$\mathbf{Y_2}$=".
- Press **[WINDOW]**. Adjust the *y*-axis so that it includes the value entered for "$\mathbf{Y_2}$=".
- Press **[GRAPH]** to observe the graph of the exponential function along with the line for the specified value off(x). f(x).
- To find the value ofx, x,we compute the point of intersection. Press **[2ND]** then **[CALC]**. Select "intersect" and press **[ENTER]** three times. The point of intersection gives the value of *x* for the indicated value of the function.

**Example 5.3.3: Approximating the Solution of an Exponential Equation**

Solve $42 = 1.2(5)^x + 2.8$ graphically. Round to the nearest thousandth.

**Solution**

Press **[Y=]** and enter $1.2(5)^x + 2.8$ next to $\mathbf{Y_1}$=. Then enter $42$ next to **Y2=**. For a window, use the values $-3$ to $3$ for $x$ and $-5$ to $55$ for $y$. Press **[GRAPH]**. The graphs should intersect somewhere near $x = 2$.

For a better approximation, press **[2ND]** then **[CALC]**. Select **[5: intersect]** and press **[ENTER]** three times. The *x*-coordinate of the point of intersection is displayed as $2.1661943$ (Your answer may be different if you use a different window or use a different value for **Guess?**) To the nearest thousandth, $x \approx 2.166$.

**Exercise 5.3.3**

Solve $4 = 7.85(1.15)^x - 2.27$ graphically. Round to the nearest thousandth.

**Answer**

$x \approx -1.608$

## Graphing a Stretch or Compression

While horizontal and vertical shifts involve adding constants to the input or to the function itself, a **stretch** or **compression** occurs when we multiply the parent function $f(x) = b^x$ by a constant $|a| > 0$. For example, if we begin by graphing the parent function $f(x) = 2^x$,we can then graph the stretch, using $a = 3$,to get $g(x) = 3(2)^x$ as shown on the left in Figure 5.3.8, and the compression, using $a = \frac{1}{3}$,to get $h(x) = \frac{1}{3}(2)^x$ as shown on the right in Figure 5.3.8.





Figure 5.3.8: (a) $g(x) = 3(2)^x$ stretches the graph of $f(x) = 2^x$ vertically by a factor of 3. (b) $h(x) = \frac{1}{3}(2)^x$ compresses the graph of $f(x) = 2^x$ vertically by a factor of $\frac{1}{3}$.

### STRETCHES AND COMPRESSIONS OF THE PARENT FUNCTION $F(X) = B^X$

For any factor $a > 0$,the function $f(x) = a(b)^x$

- is stretched vertically by a factor of $a$ if $|a| > 1$.
- is compressed vertically by a factor of $a$ if $|a| < 1$.
- has a $y$-intercept of $(0, a)$.
- has a horizontal asymptote at $y = 0$, a range of $(0, \infty)$, and a domain of $(-\infty, \infty)$,which are unchanged from the parent function.

### Example 5.3.4: Graphing the Stretch of an Exponential Function

Sketch a graph of $f(x) = 4(\frac{1}{2})^x$. State the domain, range, and asymptote.

**Solution**

Before graphing, identify the behavior and key points on the graph.

- Since $b = \frac{1}{2}$ is between zero and one, the left tail of the graph will increase without bound as $x$ decreases, and the right tail will approach the $x$-axis as $x$ increases.
- Since $a = 4$,the graph of $f(x) = (\frac{1}{2})^x$ will be stretched by a factor of 4.
- Create a table of points as shown in Table 5.3.4.

Table 5.3.4

| $x$ | $-3$ | $-2$ | $-1$ | $0$ | $1$ | $2$ | $3$ |
|---|---|---|---|---|---|---|---|
| $f(x) = 4(\frac{1}{2})^x$ | 32 | 16 | 8 | 4 | 2 | 1 | 0.5 |

- Plot the $y$-intercept, $(0, 4)$,along with two other points. We can use $(-1, 8)$ and $(1, 2)$.

Draw a smooth curve connecting the points, as shown in Figure 5.3.9.





Figure 5.3.9


The domain is $(-\infty, \infty)$; the range is $(0, \infty)$; the horizontal asymptote is $y = 0$.

**? Exercise 5.3.4**

Sketch the graph of $f(x) = \frac{1}{2}(4)^x$. State the domain, range, and asymptote.

**Answer**

The domain is $(-\infty, \infty)$; the range is $(0, \infty)$; the horizontal asymptote is $y = 0$.




## Graphing Reflections

In addition to shifting, compressing, and stretching a graph, we can also reflect it about the *x*-axis or the *y*-axis. When we multiply the parent function $f(x) = b^x$ by $-1$,we get a reflection about the *x*-axis. When we multiply the input by $-1$,we get a reflection about the *y*-axis. For example, if we begin by graphing the parent function $f(x) = 2^x$, we can then graph the two reflections alongside it. The reflection about the *x*-axis, $g(x) = -2^x$ ,is shown on the left side of Figure 5.3.10, and the reflection about the y-axis $h(x) = 2^{-x}$ , is shown on the right side of Figure 5.3.10.





Figure 5.3.10: (a) $g(x) = -2^x$ reflects the graph of $f(x) = 2^x$ about the x-axis. (b) $g(x) = 2^{-x}$ reflects the graph of $f(x) = 2^x$ about the y-axis.

### REFLECTIONS OF THE PARENT FUNCTION $F(X) = B^x$

The function $f(x) = -b^x$

- reflects the parent function $f(x) = b^x$ about the *x*-axis.
- has a *y*-intercept of $(0, -1)$.
- has a range of $(-\infty, 0)$
- has a horizontal asymptote at $y = 0$ and domain of $(-\infty, \infty)$,which are unchanged from the parent function.

The function $f(x) = b^{-x}$

- reflects the parent function $f(x) = b^x$ about the *y*-axis.
- has a *y*-intercept of $(0, 1)$, a horizontal asymptote at $y = 0$, a range of $(0, \infty)$, and a domain of $(-\infty, \infty)$, which are unchanged from the parent function.

### Example 5.3.5: Writing and Graphing the Reflection of an Exponential Function

Find and graph the equation for a function, $g(x)$,that reflects $f(x) = (\frac{1}{4})^x$ about the *x*-axis. State its domain, range, and asymptote.

#### Solution

Since we want to reflect the parent function $f(x) = (\frac{1}{4})^x$ about the *x*-axis, we multiply $f(x)$ by $-1$ to get, $g(x) = -(\frac{1}{4})^x$. Next we create a table of points as in Table 5.3.5.

Table 5.3.5

| $x$ | $-3$ | $-2$ | $-1$ | $0$ | $1$ | $2$ | $3$ |
|---|---|---|---|---|---|---|---|
| $g(x) = -(\frac{1}{4})^x$ | $-64$ | $-16$ | $-4$ | $-1$ | $-0.25$ | $\mathbf{-0.0625}$ | $\mathbf{-0.0156}$ |

Plot the $y$-intercept, $(0, -1)$,along with two other points. We can use $(-1, -4)$ and $(1, -0.25)$.

Draw a smooth curve connecting the points:





Figure 5.3.11


The domain is $(-\infty, \infty)$; the range is $(-\infty, 0)$; the horizontal asymptote is $y = 0$.

**? Exercise 5.3.5**

Find and graph the equation for a function, $g(x)$, that reflects $f(x) = 1.25^x$ about the $y$-axis. State its domain, range, and asymptote.

**Answer**

The domain is $(-\infty, \infty)$ ; the range is $(0, \infty)$; the horizontal asymptote is $y = 0$.




## Summarizing Translations of the Exponential Function

Now that we have worked with each type of translation for the exponential function, we can summarize them in **Table 5.3.6** to arrive at the general equation for translating exponential functions.

1, and notes the following changes: the reflected function is decreasing as x moves from 0 to infinity, the asymptote remains x=0, the x-intercept remains (1, 0), the key point changes to (b^(-1), 1), the domain remains (0, infinity), and the range remains (-infinity, infinity). The second column shows the left shift of the equation g(x)=log_b(x) when b>1, and notes the following

changes: the reflected function is decreasing as x moves from 0 to infinity, the asymptote remains x=0, the x-intercept changes to (-1, 0), the key point changes to (-b, 1), the domain changes to (-infinity, 0), and the range remains (-infinity, infinity)."> 

Table 5.3.6: Translations of the Parent Function $f(x) = b^x$

| Translation | Form |
|---|---|
| Shift<br>• Horizontally $c$ units to the left<br>• Vertically $d$ units up | $f(x) = b^{x+c} + d$ |
| Stretch and Compress<br>• Stretch if $\|a\| > 1$<br>• Compression if $0 < \|a\| < 1$ | $f(x) = ab^x$ |
| Reflect about the x-axis | $f(x) = -b^x$ |
| Reflect about the y-axis | $f(x) = b^{-x} = (\frac{1}{b})^x$ |
| General equation for all translations | $f(x) = ab^{x+c} + d$ |

## TRANSLATIONS OF EXPONENTIAL FUNCTIONS

A translation of an exponential function has the form

$$f(x) = ab^{x+c} + d$$

Where the parent function, $y = b^x$, $b > 1$,is

- shifted horizontally $c$ units to the left.
- stretched vertically by a factor of $|a|$ if $|a| > 0$.
- compressed vertically by a factor of $|a|$ if $0 < |a| < 1$.
- shifted vertically $d$ units.
- reflected about the $x$-axis when $a < 0$.

Note the order of the shifts, transformations, and reflections follow the order of operations.

## Example 5.3.6: Writing a Function from a Description

Write the equation for the function described below. Give the horizontal asymptote, the domain, and the range.

$f(x) = e^x$ is vertically stretched by a factor of 2, reflected across the $y$-axis, and then shifted up 4 units.

### Solution

We want to find an equation of the general form f(x)=abx+c+d. f(x)=abx+c+d. We use the description provided to finda, a, b,b, c,c, and d. d.

- We are given the parent function $f(x) = e^x$, so $b = e$.
- The function is stretched by a factor of 2, so $a = 2$.
- The function is reflected about the $y$-axis. We replace $x$ with $-x$ to get: $e^{-x}$.
- The graph is shifted vertically 4 units, so $d = 4$.

Substituting in the general form we get,

$$\begin{aligned} f(x) &= ab^{x+c} + d \\ &= 2e^{-x+0} + 4 \\ &= 2e^{-x} + 4 \end{aligned}$$

The domain is $(-\infty, \infty)$; the range is $(4, \infty)$; the horizontal asymptote is $y = 4$.

**Exercise 5.3.6**

Write the equation for function described below. Give the horizontal asymptote, the domain, and the range.

$f(x) = e^x$ is compressed vertically by a factor of $\frac{1}{3}$, reflected across the *x*-axis and then shifted down 2 units.

**Answer**

$f(x) = -\frac{1}{3}e^x - 2$ ; the domain is $(-\infty, \infty)$ ; the range is $(-\infty, 2)$; the horizontal asymptote is $y = 2$.

**Media**

Access this online resource for additional instruction and practice with graphing exponential functions.

- Graph Exponential Functions

## Key Equations

| | |
|---|---|
| General Form for the Translation of the Parent Function $f(x) = b^x$ | $f(x) = ab^{x+c} + d$ |

## Key Concepts

- The graph of the function $f(x) = b^x$ has a *y*-intercept at $(0, 1)$,domain $(-\infty, \infty)$,range $(0, \infty)$, and horizontal asymptote $y = 0$. See Example.
- If $b > 1$ ,the function is increasing. The left tail of the graph will approach the asymptote $y = 0$, and the right tail will increase without bound.
- If $0 < b < 1$ , the function is decreasing. The left tail of the graph will increase without bound, and the right tail will approach the asymptote $y = 0$.
- The equation $f(x) = b^x + d$ represents a vertical shift of the parent function $f(x) = b^x$ .
- The equation $f(x) = b^{x+c}$ represents a horizontal shift of the parent function $f(x) = b^x$ . See Example.
- Approximate solutions of the equation $f(x) = b^{x+c} + d$ can be found using a graphing calculator. See Example.
- The equation $f(x) = ab^x$ , where $a > 0$ , represents a vertical stretch if $|a| > 1$ or compression if $0 < |a| < 1$ of the parent function $f(x) = b^x$ . See Example.
- When the parent function $f(x) = b^x$ is multiplied by $-1$,the result, $f(x) = -b^x$ , is a reflection about the *x*-axis. When the input is multiplied by $-1$,the result, $f(x) = b^{-x}$ , is a reflection about the *y*-axis. See Example.
- All translations of the exponential function can be summarized by the general equation $f(x) = ab^{x+c} + d$ . See Table.
- Using the general equation $f(x) = ab^{x+c} + d$ , we can write the equation of a function given its description. See Example.

This page titled 5.3: Graphs of Exponential Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.2: Graphs of Exponential Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.3E: Graphs of Exponential Functions (Exercises)

9. Graph the function $f(x) = 3.5(2)^x$. State the domain and range and give the $y$ -intercept.

10. Graph the function $f(x) = 4\left(\frac{1}{8}\right)^x$ and its reflection about the $y$ -axis on the same axes, and give the $y$ -intercept.

11. The graph of $f(x) = 6.5^x$ is reflected about the $y$ -axis and stretched vertically by a factor of $7$. What is the equation of the new function, $g(x)$? State its $y$ -intercept, domain, and range.

12. The graph below shows transformations of the graph of $f(x) = 2^x$. What is the equation for the transformation?





Figure 1

This page titled 5.3E: Graphs of Exponential Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.2E: Graphs of Exponential Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.4: Logarithmic Functions

**Learning Objectives**

- Convert from logarithmic to exponential form.
- Convert from exponential to logarithmic form.
- Evaluate logarithms.
- Use common logarithms.
- Use natural logarithms.

In 2010, a major earthquake struck Haiti, destroying or damaging over 285,000 homes. One year later, another, stronger earthquake devastated Honshu, Japan, destroying or damaging over 332,000 buildings, like those shown in Figure 5.4.1. Even though both caused substantial damage, the earthquake in 2011 was 100 times stronger than the earthquake in Haiti. How do we know? The magnitudes of earthquakes are measured on a scale known as the Richter Scale. The Haitian earthquake registered a 7.0 on the Richter Scale whereas the Japanese earthquake registered a 9.0.



***Figure* 5.4.1*:*** *Devastation of March 11, 2011 earthquake in Honshu, Japan. (credit: Daniel Pierce).*

The Richter Scale is a base-ten logarithmic scale. In other words, an earthquake of magnitude 8 is not twice as great as an earthquake of magnitude 4. It is

$$10^{8-4} = 10^4 = 10,000$$

times as great! In this lesson, we will investigate the nature of the Richter Scale and the base-ten function upon which it depends.

## Converting from Logarithmic to Exponential Form

In order to analyze the magnitude of earthquakes or compare the magnitudes of two different earthquakes, we need to be able to convert between logarithmic and exponential form. For example, suppose the amount of energy released from one earthquake were 500 times greater than the amount of energy released from another. We want to calculate the difference in magnitude. The equation that represents this problem is $10^x = 500$, where $x$ represents the difference in magnitudes on the Richter Scale. How would we solve for $x$?

We have not yet learned a method for solving exponential equations. None of the algebraic tools discussed so far is sufficient to solve $10^x = 500$. We know that $10^2 = 100$ and $10^3 = 1000$, so it is clear that $x$ must be some value between 2 and 3, since $y = 10^x$ is increasing. We can examine a graph, as in Figure 5.4.1, to better estimate the solution.





***Figure* 5.4.2**


Estimating from a graph, however, is imprecise. To find an algebraic solution, we must introduce a new function. Observe that the graph in Figure 5.4.2 passes the horizontal line test. The exponential function $y = b^x$ is one-to-one, so its inverse, $x = b^y$ is also a function. As is the case with all inverse functions, we simply interchange $x$ and $y$ and solve for $y$ to find the inverse function. To represent $y$ as a function of $x$, we use a logarithmic function of the form $y = \log_b(x)$. The base $b$ **logarithm** of a number is the exponent by which we must raise $b$ to get that number.

We read a logarithmic expression as, "The logarithm with base $b$ of $x$ is equal to $y$," or, simplified, "log base $b$ of $x$ is $y$." We can also say, "$b$ raised to the power of $y$ is $x$," because logs are exponents. For example, the base 2 logarithm of 32 is 5, because 5 is the exponent we must apply to 2 to get 32. Since $2^5 = 32$, we can write $\log_2 32 = 5$. We read this as "log base 2 of 32 is 5."

We can express the relationship between logarithmic form and its corresponding exponential form as follows:

$$\log_b(x) = y \Leftrightarrow b^y = x, b > 0, b \neq 1 \tag{5.4.1}$$

Note that the base $b$ is always positive.




Because logarithm is a function, it is most correctly written as $\log_b(x)$, using parentheses to denote function evaluation, just as we would with $f(x)$. However, when the input is a single variable or number, it is common to see the parentheses dropped and the expression written without parentheses, as $\log_b x$. Note that many calculators require parentheses around the $x$.

We can illustrate the notation of logarithms as follows:

Notice that, comparing the logarithm function and the exponential function, the input and the output are switched. This means $y = \log^b(x)$ and $y = b^x$ are inverse functions.

**DEFINITION OF THE LOGARITHMIC FUNCTION**

A logarithm base $b$ of a positive number $x$ satisfies the following definition.

For $x > 0, b > 0, b \neq 1$,

$$y = \log_b(x) \text{ is equivalent to } b^y = x \tag{5.4.2}$$

where,

- we read $\log_b(x)$ as, “the logarithm with base $b$ of $x$” or the “log base $b$ of $x$."
- the logarithm $y$ is the exponent to which $b$ must be raised to get $x$.

Also, since the logarithmic and exponential functions switch the $x$ and $y$ values, the domain and range of the exponential function are interchanged for the logarithmic function. Therefore,

- the domain of the logarithm function with base $b$ is $(0, \infty)$.
- the range of the logarithm function with base $b$ is $(-\infty, \infty)$.

### Q&A: Can we take the logarithm of a negative number?

*No. Because the base of an exponential function is always positive, no power of that base can ever be negative. We can never take the logarithm of a negative number. Also, we cannot take the logarithm of zero. Calculators may output a log of a negative number when in complex mode, but the log of a negative number is not a real number.*

### How to: Given an equation in logarithmic form $\log_b(x) = y$, convert it to exponential form

1. Examine the equation $y = \log_b x$ and identify $b$, $y$,and $x$.
2. Rewrite $\log_b x = y$ as $b^y = x$.

### Example 5.4.1: Converting from Logarithmic Form to Exponential Form

Write the following logarithmic equations in exponential form.

a. $\log_6(\sqrt{6}) = \dfrac{1}{2}$
b. $\log_3(9) = 2$

**Solution**

First, identify the values of $b$, $y$,and $x$. Then, write the equation in the form $b^y = x$.

a. $\log_6(\sqrt{6}) = \dfrac{1}{2}$

Here, $b = 6$, $y = \dfrac{1}{2}$,and $x = \sqrt{6}$. Therefore, the equation $\log_6(\sqrt{6}) = \dfrac{1}{2}$ is equivalent to

$$6^{\frac{1}{2}} = \sqrt{6}$$

b. $\log_3(9) = 2$

Here, $b = 3$, $y = 2$,and $x = 9$. Therefore, the equation $\log_3(9) = 2$ is equivalent to

$$3^2 = 9$$

### Exercise 5.4.1

Write the following logarithmic equations in exponential form.

a. $\log_{10}(1,000,000) = 6$
b. $\log_5(25) = 2$

**Answer a**

$\log_{10}(1,000,000) = 6$is equivalent to $10^6 = 1,000,000$

**Answer b**

$\log_5(25) = 2$ is equivalent to $5^2 = 25$

## Converting from Exponential to Logarithmic Form

To convert from exponents to logarithms, we follow the same steps in reverse. We identify the base $b$,exponent $x$,and output $y$. Then we write $x = \log_b(y)$.

### Example 5.4.2: Converting from Exponential Form to Logarithmic Form

Write the following exponential equations in logarithmic form.

a. $2^3 = 8$
b. $5^2 = 25$
c. $10^{-4} = \dfrac{1}{10,000}$

**Solution**

First, identify the values of $b$, $y$,and $x$. Then, write the equation in the form $x = \log_b(y)$.

a. $2^3 = 8$

Here, $b = 2$, $x = 3$,and $y = 8$. Therefore, the equation $2^3 = 8$ is equivalent to $\log_2(8) = 3$.

b. $5^2 = 25$

Here, $b = 5$, $x = 2$,and $y = 25$. Therefore, the equation $5^2 = 25$ is equivalent to $\log_5(25) = 2$.

c. $10^{-4} = \dfrac{1}{10,000}$

Here, $b = 10$, $x = -4$,and $y = \dfrac{1}{10,000}$. Therefore, the equation $10^{-4} = \dfrac{1}{10,000}$ is equivalent to $\log_{10}\left(\dfrac{1}{10,000}\right) = -4$.

### Exercise 5.4.2

Write the following exponential equations in logarithmic form.

a. $3^2 = 9$
b. $5^3 = 125$
c. $2^{-1} = \dfrac{1}{2}$

**Answer a**

$3^2 = 9$ is equivalent to $\log_3(9) = 2$

**Answer b**

$5^3 = 125$ is equivalent to $\log_5(125) = 3$

**Answer c**

$2^{-1} = \dfrac{1}{2}$ is equivalent to $\log_2\left(\dfrac{1}{2}\right) = -1$

## Evaluating Logarithms

Knowing the squares, cubes, and roots of numbers allows us to evaluate many logarithms mentally. For example, consider $\log_2 8$. We ask, "To what exponent must $2$ be raised in order to get 8?" Because we already know $2^3 = 8$, it follows that $\log_2 8 = 3$.

Now consider solving $\log_7 49$ and $\log_3 27$ mentally.

- We ask, "To what exponent must $7$ be raised in order to get $49$?" We know $7^2 = 49$. Therefore, $\log_7 49 = 2$
- We ask, "To what exponent must $3$ be raised in order to get $27$?" We know $3^3 = 27$. Therefore, $\log_3 27 = 3$

Even some seemingly more complicated logarithms can be evaluated without a calculator. For example, let's evaluate $\log_{\frac{2}{3}} \frac{4}{9}$ mentally.

- We ask, "To what exponent must $\frac{2}{3}$ be raised in order to get $\frac{4}{9}$?" We know $2^2 = 4$ and $3^2 = 9$, so

$$\left(\frac{2}{3}\right)^2 = \frac{4}{9}.$$

Therefore,

$$\log_{\frac{2}{3}}\left(\frac{4}{9}\right) = 2.$$

**How to: Given a logarithm of the form $y = \log_b(x)$,evaluate it mentally**

1. Rewrite the argument $x$ as a power of $b$: $b^y = x$.
2. Use previous knowledge of powers of $b$ identify $y$ by asking, "To what exponent should $b$ be raised in order to get $x$?"

**Example 5.4.3: Solving Logarithms Mentally**

Solve $y = \log_4(64)$ without using a calculator.

**Solution**

First we rewrite the logarithm in exponential form: $4^y = 64$. Next, we ask, "To what exponent must 4 be raised in order to get 64?"

We know

$$4^3 = 64$$

Therefore,

$$\log_4(64) = 3$$

**Exercise 5.4.3**

Solve $y = \log_{121}(11)$ without using a calculator.

**Answer**

$\log_{121}(11) = \frac{1}{2}$ (recalling that $\sqrt{121} = (121)^{\frac{1}{2}} = 11$)

**Example 5.4.4: Evaluating the Logarithm of a Reciprocal**

Evaluate $y = \log_3\left(\frac{1}{27}\right)$ without using a calculator.

**Solution**

First we rewrite the logarithm in exponential form: $3^y = \frac{1}{27}$. Next, we ask, "To what exponent must 3 be raised in order to get $\frac{1}{27}$?"

We know $3^3 = 27$,but what must we do to get the reciprocal, $\frac{1}{27}$? Recall from working with exponents that $b^{-a} = \frac{1}{b^a}$. We use this information to write

$$3^{-3} = \frac{1}{3^3}$$
$$= \frac{1}{27}$$

Therefore, $\log_3\left(\frac{1}{27}\right) = -3$.

**? Exercise 5.4.4**

Evaluate $y = \log_2\left(\frac{1}{32}\right)$ without using a calculator.

**Answer**

$\log_2\left(\frac{1}{32}\right) = -5$

## Using Common Logarithms

Sometimes we may see a logarithm written without a base. In this case, we assume that the base is 10. In other words, the expression $\log(x)$ means $\log_{10}(x)$. We call a base $-10$ logarithm a *common logarithm*. Common logarithms are used to measure the Richter Scale mentioned at the beginning of the section. Scales for measuring the brightness of stars and the pH of acids and bases also use common logarithms.

**DEFINITION OF THE COMMON LOGARITHM**

A common logarithm is a logarithm with base 10. We write $\log_{10}(x)$ simply as $\log(x)$. The common logarithm of a positive number $x$ satisfies the following definition.

For $x > 0$,

$$y = \log(x) \text{ is equivalent to } 10^y = x \tag{5.4.3}$$

We read $\log(x)$ as, "the logarithm with base 10 of $x$ " or "log base 10 of $x$."

The logarithm $y$ is the exponent to which 10 must be raised to get $x$.

**How to: Given a common logarithm of the form $y = \log(x)$, evaluate it mentally**

1. Rewrite the argument $x$ as a power of 10: $10^y = x$.
2. Use previous knowledge of powers of 10 to identify $y$ by asking, "To what exponent must 10 be raised in order to get $x$?"

**✓ Example 5.4.5: Finding the Value of a Common Logarithm Mentally**

Evaluate $y = \log(1000)$ without using a calculator.

**Solution**

First we rewrite the logarithm in exponential form: $10^y = 1000$. Next, we ask, "To what exponent must 10 be raised in order to get 1000?" We know

$$10^3 = 1000$$

Therefore, $\log(1000) = 3$.

**Exercise 5.4.5**

Evaluate $y = \log(1,000,000)$

**Answer**

$\log(1,000,000) = 6$

**How to: Given a common logarithm with the form $y = \log(x)$,evaluate it using a calculator**

1. Press **[LOG]**.
2. Enter the value given for $x$,followed by **[ ) ]**.
3. Press **[ENTER]**.

**Example 5.4.6: Finding the Value of a Common Logarithm Using a Calculator**

Evaluate $y = \log(321)$to four decimal places using a calculator.

**Solution**

- Press **[LOG]**.
- Enter 321, followed by **[ ) ]**.
- Press **[ENTER]**.

Rounding to four decimal places, $\log(321) \approx 2.5065$

**Analysis**

Note that $10^2 = 100$ and that $10^3 = 1000$. Since $321$ is between $100$ and $1000$, we know that $\log(321)$must be between $\log(100)$and $\log(1000)$. This gives us the following:

$$100 < 321 < 1000$$

$$2 < 2.5065 < 3$$

**Exercise 5.4.6**

Evaluate $y = \log(123)$to four decimal places using a calculator.

**Answer**

$\log(123) \approx 2.0899$

**Example 5.4.7: Rewriting and Solving a Real-World Exponential Model**

The amount of energy released from one earthquake was $500$ times greater than the amount of energy released from another. The equation $10^x = 500$ represents this situation, where $x$ is the difference in magnitudes on the Richter Scale. To the nearest thousandth, what was the difference in magnitudes?

**Solution**

We begin by rewriting the exponential equation in logarithmic form.

$$10^x = 500$$

$$\log(500) = x \text{ Use the definition of the common log.}$$

Next we evaluate the logarithm using a calculator:

- Press **[LOG]**.
- Enter 500,followed by **[ ) ]**.
- Press **[ENTER]**.
- To the nearest thousandth, $\log(500) \approx 2.699$

The difference in magnitudes was about $2.699$.

**Exercise 5.4.7**

The amount of energy released from one earthquake was $8,500$ times greater than the amount of energy released from another. The equation $10^x = 8500$ represents this situation, where $x$ is the difference in magnitudes on the Richter Scale. To the nearest thousandth, what was the difference in magnitudes?

**Answer**

The difference in magnitudes was about $3.929$

## Using Natural Logarithms

The most frequently used base for logarithms is $e$. Base $e$ logarithms are important in calculus and some scientific applications; they are called **natural logarithms**. The base $e$ logarithm, $\log_e(x)$, has its own notation, $\ln(x)$. Most values of $\ln(x)$ can be found only using a calculator. The major exception is that, because the logarithm of $1$ is always $0$ in any base, $\ln 1 = 0$. For other natural logarithms, we can use the $\ln$ key that can be found on most scientific calculators. We can also find the natural logarithm of any power of $e$ using the inverse property of logarithms.

**DEFINITION OF THE NATURAL LOGARITHM**

A natural logarithm is a logarithm with base $e$. We write $\log_e(x)$ simply as $\ln(x)$. The natural logarithm of a positive number $x$ satisfies the following definition.

For $x > 0$,

$$y = \ln(x) \text{ is equivalent to } e^y = x$$

We read $\ln(x)$ as, "the logarithm with base $e$ of $x$" or "the natural logarithm of $x$."

The logarithm $y$ is the exponent to which $e$ must be raised to get $x$.

Since the functions $y = e^x$ and $y = \ln(x)$ are inverse functions, $\ln(e^x) = x$ for all $x$ and $e^{\ln(x)} = x$ for $x > 0$.

**How to: Given a natural logarithm with the form $y = \ln(x)$, evaluate it using a calculator**

1. Press **[LN]**.
2. Enter the value given for $x$, followed by **[ ) ]**.
3. Press **[ENTER]**.

**Example 5.4.8: Evaluating a Natural Logarithm Using a Calculator**

Evaluate $y = \ln(500)$ to four decimal places using a calculator.

**Solution**

- Press **[LN]**.
- Enter $500$, followed by **[ ) ]**.
- Press **[ENTER]**.

Rounding to four decimal places, $\ln(500) \approx 6.2146$

**Exercise 5.4.8**

Evaluate $\ln(-500)$.

**Answer**

It is not possible to take the logarithm of a negative number in the set of real numbers.

Media

Access this online resource for additional instruction and practice with logarithms.

- Introduction to Logarithms

## Key Equations

| | |
|---|---|
| Definition of the logarithmic function | For $x > 0$, $b > 0$, $b \neq 1$, $y = \log_b(x)$ if and only if $b^y = x$. |
| Definition of the common logarithm | For $x > 0$, $y = \log(x)$ if and only if $10^y = x$. |
| Definition of the natural logarithm | For $x > 0$, $y = \ln(x)$ if and only if $e^y = x$. |

## Key Concepts

- The inverse of an exponential function is a logarithmic function, and the inverse of a logarithmic function is an exponential function.
- Logarithmic equations can be written in an equivalent exponential form, using the definition of a logarithm. See Example 5.4.1.
- Exponential equations can be written in their equivalent logarithmic form using the definition of a logarithm See Example 5.4.2.
- Logarithmic functions with base $b$ can be evaluated mentally using previous knowledge of powers of $b$. See Example 5.4.3 and Example 5.4.4.
- Common logarithms can be evaluated mentally using previous knowledge of powers of 10. See Example 5.4.5.
- When common logarithms cannot be evaluated mentally, a calculator can be used. See Example 5.4.6.
- Real-world exponential problems with base 10 can be rewritten as a common logarithm and then evaluated using a calculator. See Example 5.4.7.
- Natural logarithms can be evaluated using a calculator Example 5.4.8.

### Contributors and Attributions

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.

This page titled 5.4: Logarithmic Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.3: Logarithmic Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.4E: Logarithmic Functions (Exercises)

13. Rewrite $\log_{17}(4913) = x$ as an equivalent exponential equation.
14. Rewrite $\ln(s) = t$ as an equivalent exponential equation.
15. Rewrite $a^{-\frac{2}{5}} = b$ as an equivalent logarithmic equation.
16. Rewrite $e^{-3.5} = h$ as an equivalent logarithmic equation.
17. Solve for $x$ if $\log_{64}(x) = \frac{1}{3}$ by converting to exponential form.
18. Evaluate $\log_5\left(\frac{1}{125}\right)$ without using a calculator.
19. Evaluate $\log(0.000001)$without using a calculator.
20. Evaluate $\log(4.005)$using a calculator. Round to the nearest thousandth.
21. Evaluate $\ln\left(e^{-0.8648}\right)$ without using a calculator.
22. Evaluate $\ln(\sqrt[3]{18})$ using a calculator. Round to the nearest thousandth.

This page titled 5.4E: Logarithmic Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.3E: Logarithmic Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.5: Graphs of Logarithmic Functions

**Learning Objectives**

- Identify the domain of a logarithmic function.
- Graph logarithmic functions.

In the Section on Graphs of Exponential Functions, we saw how creating a graphical representation of an exponential model gives us another layer of insight for predicting future events. How do logarithmic graphs give us insight into situations? Because every logarithmic function is the inverse function of an exponential function, we can think of every output on a logarithmic graph as the input for the corresponding inverse exponential equation. In other words, logarithms give the *cause* for an *effect*.

To illustrate, suppose we invest $\$2500$ in an account that offers an annual interest rate of 5%, compounded continuously. We already know that the balance in our account for any year $t$ can be found with the equation $A = 2500e^{0.05t}$.

But what if we wanted to know the year for any balance? We would need to create a corresponding new function by interchanging the input and the output; thus we would need to create a logarithmic model for this situation. By graphing the model, we can see the output (year) for any input (account balance). For instance, what if we wanted to know how many years it would take for our initial investment to double? Figure $5.5.1$ shows this point on the logarithmic graph.





Figure 5.5.1

In this section we will discuss the values for which a logarithmic function is defined, and then turn our attention to graphing the family of logarithmic functions.

## Finding the Domain of a Logarithmic Function

Before working with graphs, we will take a look at the domain (the set of input values) for which the logarithmic function is defined.

Recall that the exponential function is defined as $y = b^x$ for any real number $x$ and constant $b > 0$, $b \neq 1$, where

- The domain of $y$ is $(-\infty, \infty)$.
- The range of $y$ is $(0, \infty)$.

In the last section we learned that the logarithmic function $y = \log_b(x)$ is the inverse of the exponential function $y = b^x$. So, as inverse functions:

- The domain of $y = \log_b(x)$ is the range of $y = b^x$: $(0, \infty)$.
- The range of $y = \log_b(x)$ is the domain of $y = b^x$: $(-\infty, \infty)$.

Transformations of the parent function $y = \log_b(x)$ behave similarly to those of other functions. Just as with other parent functions, we can apply the four types of transformations—shifts, stretches, compressions, and reflections—to the parent function without loss of shape.

In Graphs of Exponential Functions we saw that certain transformations can change the *range* of $y = b^x$. Similarly, applying transformations to the parent function $y = \log_b(x)$ can change the *domain*. When finding the domain of a logarithmic function, therefore, it is important to remember that the domain consists *only of positive real numbers*. That is, the argument of the logarithmic function must be greater than zero.

For example, consider $f(x) = \log_4(2x - 3)$. This function is defined for any values of $x$ such that the argument, in this case $2x - 3$,is greater than zero. To find the domain, we set up an inequality and solve for $x$:

$$\begin{aligned} 2x - 3 &> 0 && \text{Show the argument greater than zero} \\ 2x &> 3 && \text{Add 3} \\ x &> 1.5 && \text{Divide by 2} \end{aligned}$$

In interval notation, the domain of $f(x) = \log_4(2x - 3)$ is $(1.5, \infty)$.

**Given a logarithmic function, identify the domain**

1. Set up an inequality showing the argument greater than zero.
2. Solve for $x$.
3. Write the domain in interval notation.

**Example 5.5.1: Identifying the Domain of a Logarithmic Shift**

What is the domain of $f(x) = \log_2(x + 3)$?

**Solution**

The logarithmic function is defined only when the input is positive, so this function is defined when $x + 3 > 0$. Solving this inequality,

$$\begin{aligned} x + 3 &> 0 && \text{The input must be positive} \\ x &> -3 && \text{Subtract 3} \end{aligned}$$

The domain of $f(x) = \log_2(x + 3)$ is $(-3, \infty)$.

**Exercise 5.5.1**

What is the domain of $f(x) = \log_5(x - 2) + 1$ ?

**Answer**

$(2, \infty)$

**Example 5.5.2: Identifying the Domain of a Logarithmic Shift and Reflection**

What is the domain of $f(x) = \log(5 - 2x)$?

**Solution**

The logarithmic function is defined only when the input is positive, so this function is defined when $5 - 2x > 0$. Solving this inequality,

$$\begin{aligned} 5 - 2x &> 0 && \text{The input must be positive} \\ -2x &> -5 && \text{Subtract 5} \\ x &< \frac{5}{2} && \text{Divide by -2 and switch the inequality} \end{aligned}$$

The domain of $f(x) = \log(5 - 2x)$ is $\left(-\infty, \frac{5}{2}\right)$.

**? Exercise 5.5.2**

What is the domain of $f(x) = \log(x - 5) + 2$ ?

**Answer**

$(5, \infty)$

## Graphing Logarithmic Functions

Now that we have a feel for the set of values for which a logarithmic function is defined, we move on to graphing logarithmic functions. The family of logarithmic functions includes the parent function $y = \log_b(x)$ along with all its transformations: shifts, stretches, compressions, and reflections.

We begin with the parent function $y = \log_b(x)$. Because every logarithmic function of this form is the inverse of an exponential function with the form $y = b^x$, their graphs will be reflections of each other across the line $y = x$. To illustrate this, we can observe the relationship between the input and output values of $y = 2^x$ and its equivalent $x = \log_2(y)$ in Table 5.5.1.

Table 5.5.1

| $x$ | $-3$ | $-2$ | $-1$ | $0$ | $1$ | $2$ | $3$ |
|---|---|---|---|---|---|---|---|
| $2^x = y$ | $\frac{1}{8}$ | $\frac{1}{4}$ | $\frac{1}{2}$ | $1$ | $2$ | $4$ | $8$ |
| $\log_2(y) = x$ | $-3$ | $-2$ | $-1$ | $0$ | $1$ | $2$ | $3$ |

Using the inputs and outputs from Table 5.5.1, we can build another table to observe the relationship between points on the graphs of the inverse functions $f(x) = 2^x$ and $g(x) = \log_2(x)$. See Table 5.5.2.

Table 5.5.2

| $f(x) = 2^x$ | $\left(-3, \frac{1}{8}\right)$ | $\left(-2, \frac{1}{4}\right)$ | $\left(-1, \frac{1}{2}\right)$ | $(0, 1)$ | $(1, 2)$ | $(2, 4)$ | $(3, 8)$ |
|---|---|---|---|---|---|---|---|
| $g(x) = \log_2(x)$ | $\left(\frac{1}{8}, -3\right)$ | $\left(\frac{1}{4}, -2\right)$ | $\left(\frac{1}{2}, -1\right)$ | $(1, 0)$ | $(2, 1)$ | $(4, 2)$ | $(8, 3)$ |

As we'd expect, the $x$- and $y$-coordinates are reversed for the inverse functions. Figure 5.5.2 shows the graph of $f$ and $g$.





Figure 5.5.2: Notice that the graphs of $f(x) = 2^x$ and $g(x) = \log_2(x)$ are reflections about the line $y = x$.

Observe the following from the graph:

- $f(x) = 2^x$ has a $y$-intercept at $(0, 1)$ and $g(x) = \log_2(x)$ has an $x$- intercept at $(1, 0)$.
- The domain of $f(x) = 2^x$, $(-\infty, \infty)$, is the same as the range of $g(x) = \log_2(x)$.
- The range of $f(x) = 2^x$, $(0, \infty)$, is the same as the domain of $g(x) = \log_2(x)$.

## CHARACTERISTICS OF THE GRAPH OF THE PARENT FUNCTION, $F(X) = LOG_B(X)$

For any real number $x$ and constant $b > 0$, $b \neq 1$, we can see the following characteristics in the graph of $f(x) = \log_b(x)$:

- one-to-one function
- vertical asymptote: $x = 0$
- domain: $(0, \infty)$
- range: $(-\infty, \infty)$
- $x$-intercept: $(1, 0)$ and key point $(b, 1)$
- $y$-intercept: none
- increasing if $b > 1$
- decreasing if $0 < b < 1$

See Figure 5.5.3.

Two graphs of the function f(x)=log_b(x) with points (1,0) and (b, 1). The first graph shows the line when b
1, and the second graph shows the line when 0
<1.">

**Figure 5.5.3**

Figure 5.5.4 shows how changing the base $b$ in $f(x) = \log_b(x)$ can affect the graphs. Observe that the graphs compress vertically as the value of the base increases. (Note: recall that the function $\ln(x)$ has base $e \approx 2.718$.)





Figure 5.5.4: The graphs of three logarithmic functions with different bases, all greater than 1.

## Given a logarithmic function with the form $f(x) = \log_b(x)$, graph the function.

1. Draw and label the vertical asymptote, $x = 0$.
2. Plot the $x$-intercept, $(1, 0)$.
3. Plot the key point $(b, 1)$.
4. Draw a smooth curve through the points.
5. State the domain, $(0, \infty)$,the range, $(-\infty, \infty)$, and the vertical asymptote, $x = 0$.

## Example 5.5.3: Graphing a Logarithmic Function with the Form $f(x) = log_b(x)$

Graph $f(x) = \log_5(x)$. State the domain, range, and asymptote.

### Solution

Before graphing, identify the behavior and key points for the graph.

- Since $b = 5$ is greater than one, we know the function is increasing. The left tail of the graph will approach the vertical asymptote $x = 0$, and the right tail will increase slowly without bound.
- The $x$-intercept is $(1, 0)$.
- The key point $(5, 1)$ is on the graph.
- We draw and label the asymptote, plot and label the points, and draw a smooth curve through the points (see Figure 5.5.5).





Figure 5.5.5

The domain is $(0, \infty)$, the range is $(-\infty, \infty)$, and the vertical asymptote is $x = 0$.

**? Exercise 5.5.3**

Graph $f(x) = \log_{\frac{1}{5}}(x)$. State the domain, range, and asymptote.

**Answer**





Figure 5.5.6

The domain is $(0, \infty)$, the range is $(-\infty, \infty)$, and the vertical asymptote is $x = 0$.

## Graphing Transformations of Logarithmic Functions

As we mentioned in the beginning of the section, transformations of logarithmic graphs behave similarly to those of other parent functions. We can shift, stretch, compress, and reflect the parent function $y = \log_b(x)$ without loss of shape.

### Graphing a Horizontal Shift of $f(x) = \log_b(x)$

When a constant $c$ is added to the input of the parent function $f(x) = \log_b(x)$, the result is a horizontal shift $c$ units in the *opposite* direction of the sign on $c$. To visualize horizontal shifts, we can observe the general graph of the parent function $f(x) = \log_b(x)$ and for $c > 0$ alongside the shift left, $g(x) = \log_b(x + c)$, and the shift right, $h(x) = \log_b(x - c)$. See Figure 5.5.7.





Figure 5.5.7

### HORIZONTAL SHIFTS OF THE PARENT FUNCTION $Y = LOG_B(X)$

For any constant $c$,the function $f(x) = \log_b(x + c)$

- shifts the parent function $y = \log_b(x)$ left $c$ units if $c > 0$.
- shifts the parent function $y = \log_b(x)$ right $c$ units if $c < 0$.
- has the vertical asymptote $x = -c$.
- has domain $(-c, \infty)$.
- has range $(-\infty, \infty)$.

### Given a logarithmic function with the form $f(x) = \log_b(x + c)$, graph the translation.

1. Identify the horizontal shift:
   - If $c > 0$,shift the graph of $f(x) = \log_b(x)$ left $c$ units.
   - If $c < 0$,shift the graph of $f(x) = \log_b(x)$ right $c$ units.
2. Draw the vertical asymptote $x = -c$.
3. Identify three key points from the parent function. Find new coordinates for the shifted functions by subtracting $c$ from the $x$ coordinate.
4. Label the three points.
5. The Domain is $(-c, \infty)$,the range is $(-\infty, \infty)$, and the vertical asymptote is $x = -c$.

### Example 5.5.4: Graphing a Horizontal Shift of the Parent Function $y = log_b(x)$

Sketch the horizontal shift $f(x) = \log_3(x - 2)$ alongside its parent function. Include the key points and asymptotes on the graph. State the domain, range, and asymptote.

**Solution**

Since the function is $f(x) = \log_3(x - 2)$, we notice $x + (-2) = x - 2$.

Thus $c = -2$, so $c < 0$. This means we will shift the function $f(x) = \log_3(x)$ right 2 units.

The vertical asymptote is $x = -(-2)$ or $x = 2$.

Consider the three key points from the parent function, $\left(\frac{1}{3}, -1\right)$, $(1, 0)$,and $(3, 1)$.

The new coordinates are found by adding $2$ to the $x$ coordinates.

Label the points $\left(\frac{7}{3}, -1\right)$, $(3, 0)$,and $(5, 1)$.

The domain is $(2, \infty)$,the range is $(-\infty, \infty)$,and the vertical asymptote is $x = 2$.





Figure 5.5.8

## Exercise 5.5.4

Sketch a graph of $f(x) = \log_3(x + 4)$ alongside its parent function. Include the key points and asymptotes on the graph. State the domain, range, and asymptote.

**Answer**





Figure 5.5.9

The domain is $(-4, \infty)$,the range $(-\infty, \infty)$ ,and the asymptote $x = -4$.

### Graphing a Vertical Shift of $y = log_b(x)$

When a constant $d$ is added to the parent function $f(x) = \log_b(x)$,the result is a vertical shift $d$ units in the direction of the sign on $d$. To visualize vertical shifts, we can observe the general graph of the parent function $f(x) = \log_b(x)$ alongside the shift up, $g(x) = \log_b(x) + d$ and the shift down, $h(x) = \log_b(x) - d$ .See Figure 5.5.10





Figure 5.5.10

### VERTICAL SHIFTS OF THE PARENT FUNCTION $Y = LOG_B(X)$

For any constant $d$,the function $f(x) = \log_b(x) + d$

- shifts the parent function $y = \log_b(x)$ up $d$ units if $d > 0$.
- shifts the parent function $y = \log_b(x)$ down $d$ units if $d < 0$.
- has the vertical asymptote $x = 0$.
- has domain $(0, \infty)$.
- has range $(-\infty, \infty)$.

### Given a logarithmic function with the form $f(x) = \log_b(x) + d$, graph the translation.

1. Identify the vertical shift:
   - If $d > 0$, shift the graph of $f(x) = \log_b(x)$ up $d$ units.
   - If $d < 0$, shift the graph of $f(x) = \log_b(x)$ down $d$ units.
2. Draw the vertical asymptote $x = 0$.
3. Identify three key points from the parent function. Find new coordinates for the shifted functions by adding $d$ to the $y$ coordinate.
4. Label the three points.
5. The domain is $(0, \infty)$, the range is $(-\infty, \infty)$,and the vertical asymptote is $x = 0$.

### Example 5.5.5: Graphing a Vertical Shift of the Parent Function $y = log_b(x)$

Sketch a graph of $f(x) = \log_3(x) - 2$ alongside its parent function. Include the key points and asymptote on the graph. State the domain, range, and asymptote.

**Solution**

Since the function is $f(x) = \log_3(x) - 2$ ,we will notice $d = -2$. Thus $d < 0$.

This means we will shift the function $f(x) = \log_3(x)$ down 2 units.

The vertical asymptote is $x = 0$.

Consider the three key points from the parent function, $\left(\frac{1}{3}, -1\right)$, $(1, 0)$,and $(3, 1)$.

The new coordinates are found by subtracting 2 from the *y* coordinates.

Label the points $\left(\frac{1}{3}, -3\right)$, $(1, -2)$, and $(3, -1)$.

The domain is $(0, \infty)$,the range is $(-\infty, \infty)$, and the vertical asymptote is $x = 0$.





Figure 5.5.11

The domain is $(0, \infty)$,the range is $(-\infty, \infty)$,and the vertical asymptote is $x = 0$.

**? Exercise 5.5.5**

Sketch a graph of $f(x) = \log_2(x) + 2$ alongside its parent function. Include the key points and asymptote on the graph. State the domain, range, and asymptote.

**Answer**





Figure 5.5.12

The domain is $(0, \infty)$,the range is $(-\infty, \infty)$ , and the vertical asymptote is $x = 0$.

## Graphing Stretches and Compressions of $y = log_b(x)$

When the parent function $f(x) = \log_b(x)$ is multiplied by a constant $a > 0$, the result is a vertical stretch or compression of the original graph. To visualize stretches and compressions, we set $a > 1$ and observe the general graph of the parent function $f(x) = \log_b(x)$ alongside the vertical stretch, $g(x) = a\log_b(x)$ and the vertical compression, $h(x) = \frac{1}{a}\log_b(x)$.See Figure 5.5.13

Graph of two functions. The parent function is f(x)=log_b(x), with an asymptote at x=0 and g(x)=alog_b(x) when a 1 is the translation function with an asymptote at x=0. The graph note the intersection of the two lines at (1, 0). This shows the translation of a vertical stretch." src="/@api/deki/files/12175/fig_6.5.13.jpg">

Figure 5.5.13

### VERTICAL STRETCHES AND COMPRESSIONS OF THE PARENT FUNCTION $Y = LOG_B(X)$

For any constant $a > 1$ ,the function $f(x) = a\log_b(x)$

- stretches the parent function $y = \log_b(x)$ vertically by a factor of $a$ if $a > 1$.
- compresses the parent function $y = \log_b(x)$ vertically by a factor of $a$ if $0 < a < 1$.
- has the vertical asymptote $x = 0$.
- has the $x$-intercept $(1, 0)$.
- has domain $(0, \infty)$.
- has range $(-\infty, \infty)$.

### Given a logarithmic function with the form $f(x) = a\log_b(x)$ , $a > 0$ ,graph the translation.

1. Identify the vertical stretch or compressions:
   - If $|a| > 1$, the graph of $f(x) = \log_b(x)$ is stretched by a factor of $a$ units.
   - If $|a| < 1$, the graph of $f(x) = \log_b(x)$ is compressed by a factor of $a$ units.
2. Draw the vertical asymptote $x = 0$.
3. Identify three key points from the parent function. Find new coordinates for the shifted functions by multiplying they y coordinates by $a$.
4. Label the three points.
5. The domain is $(0, \infty)$, the range is $(-\infty, \infty)$, and the vertical asymptote is $x = 0$.

## Example 5.5.6: Graphing a Stretch or Compression of the Parent Function $y = log_b(x)$

Sketch a graph of $f(x) = 2\log_4(x)$ alongside its parent function. Include the key points and asymptote on the graph. State the domain, range, and asymptote.

### Solution

Since the function is $f(x) = 2\log_4(x)$,we will notice $a = 2$.

This means we will stretch the function $f(x) = \log_4(x)$ by a factor of 2.

The vertical asymptote is $x = 0$.

Consider the three key points from the parent function, $\left(\frac{1}{4}, -1\right)$, $(1, 0)$, and $(4, 1)$.

The new coordinates are found by multiplying the $y$ coordinates by 2.

Label the points $\left(\frac{1}{4}, -2\right)$, $(1, 0)$, and $(4, 2)$.

The domain is $(0, \infty)$, the range is $(-\infty, \infty)$, and the vertical asymptote is $x = 0$. See Figure 5.5.14





Figure 5.5.14

The domain is $(0, \infty)$, the range is $(-\infty, \infty)$, and the vertical asymptote is $x = 0$.

## Exercise 5.5.6

Sketch a graph of $f(x) = \frac{1}{2}\log_4(x)$ alongside its parent function. Include the key points and asymptote on the graph. State the domain, range, and asymptote.

**Answer**





Figure 5.5.15

The domain is $(0, \infty)$, the range is $(-\infty, \infty)$ ,and the vertical asymptote is $x = 0$.

### Example 5.5.7: Combining a Shift and a Stretch

Sketch a graph of $f(x) = 5\log(x + 2)$. State the domain, range, and asymptote.

**Solution**

Remember: what happens inside parentheses happens first. First, we move the graph left 2 units, then stretch the function vertically by a factor of 5, as in Figure 5.5.16. The vertical asymptote will be shifted to $x = -2$. The $x$-intercept will be $(-1, 0)$. The domain will be $(-2, \infty)$. Two points will help give the shape of the graph: $(-1, 0)$ and $(8, 5)$. We chose $x = 8$ as the $x$-coordinate of one point to graph because when $x = 8$, $x + 2 = 10$, the base of the common logarithm.





Figure 5.5.16

The domain is $(-2, \infty)$, the range is $(-\infty, \infty)$,and the vertical asymptote is $x = -2$.

### Exercise 5.5.7

Sketch a graph of the function $f(x) = 3\log(x - 2) + 1$. State the domain, range, and asymptote.

**Answer**





Figure 5.5.17

The domain is $(2, \infty)$,the range is $(-\infty, \infty)$ , and the vertical asymptote is $x = 2$.

## Graphing Reflections of $f(x) = log_b(x)$

When the parent function $f(x) = \log_b(x)$ is multiplied by $-1$,the result is a reflection about the $x$-axis. When the *input* is multiplied by $-1$,the result is a reflection about the $y$-axis. To visualize reflections, we restrict $b > 1$, and observe the general graph of the parent function $f(x) = \log_b(x)$ alongside the reflection about the $x$-axis, $g(x) = -\log_b(x)$ and the reflection about the $y$-axis, $h(x) = \log_b(-x)$.

Graph of two functions. The parent function is f(x)=log_b(x), with an asymptote at x=0 and g(x)=-log_b(x) when b
1 is the translation function with an asymptote at x=0. The graph note the intersection of the two lines at (1, 0). This shows the translation of a reflection about the x-axis." src="/@api/deki/files/12180/fig_6.5.18.jpg">

Figure 5.5.18

### REFLECTIONS OF THE PARENT FUNCTION $Y = LOG_B(X)$

The function $f(x) = -\log_b(x)$

- reflects the parent function $y = \log_b(x)$ about the $x$-axis.
- has domain, $(0, \infty)$, range, $(-\infty, \infty)$, and vertical asymptote, $x = 0$, which are unchanged from the parent function.

The function $f(x) = \log_b(-x)$

- reflects the parent function $y = \log_b(x)$ about the $y$-axis.
- has domain $(-\infty, 0)$.
- has range, $(-\infty, \infty)$, and vertical asymptote, $x = 0$, which are unchanged from the parent function.

### Given a logarithmic function with the parent function $f(x) = \log_b(x)$, graph a translation.

Table 5.5.3

| If $f(x) = -\log_b(x)$ | If $f(x) = \log_b(-x)$ |
|---|---|
| 1. Draw the vertical asymptote, $x = 0$. | 1. Draw the vertical asymptote, $x = 0$. |
| 2. Plot the *x*-intercept, $(1, 0)$. | 2. Plot the *x*-intercept, $(1, 0)$. |
| 3. Reflect the graph of the parent function $f(x) = \log_b(x)$ about the *x*-axis. | 3. Reflect the graph of the parent function $f(x) = \log_b(x)$ about the *y*-axis. |
| 4. Draw a smooth curve through the points. | 4. Draw a smooth curve through the points. |

| If $f(x) = -\log_b(x)$ | If $f(x) = \log_b(-x)$ |
|---|---|
| 5. State the domain, $(0, \infty)$, the range, $(-\infty, \infty)$, and the vertical asymptote $x = 0$. | 5. State the domain, $(-\infty, 0)$, the range, $(-\infty, \infty)$, and the vertical asymptote $x = 0$. |

### Example 5.5.8: Graphing a Reflection of a Logarithmic Function

Sketch a graph of $f(x) = \log(-x)$ alongside its parent function. Include the key points and asymptote on the graph. State the domain, range, and asymptote.

**Solution**

Before graphing $f(x) = log(-x)$, $f(x) = log(-x)$,identify the behavior and key points for the graph.

- Since $b = 10$ is greater than one, we know that the parent function is increasing. Since the *input* value is multiplied by $-1$, $f(x)$ is a reflection of the parent graph about the $y$-axis. Thus, $f(x) = \log(-x)$ will be decreasing as $x$ moves from negative infinity to zero, and the right tail of the graph will approach the vertical asymptote $x = 0$.
- The $x$-intercept is $(-1, 0)$.
- We draw and label the asymptote, plot and label the points, and draw a smooth curve through the points.





Figure 5.5.19

The domain is $(-\infty, 0)$, the range is $(-\infty, \infty)$, and the vertical asymptote is $x = 0$.

### Exercise 5.5.8

Graph $f(x) = -\log(-x)$. State the domain, range, and asymptote.

**Answer**





Figure 5.5.20

The domain is $(-\infty, 0)$,the range is $(-\infty, \infty)$ ,and the vertical asymptote is $x = 0$.

**Given a logarithmic equation, use a graphing calculator to approximate solutions.**

1. Press **[Y=]**. Enter the given logarithm equation or equations as $\mathbf{Y_1}$= and, if needed, $\mathbf{Y_2}$=.
2. Press **[GRAPH]** to observe the graphs of the curves and use **[WINDOW]** to find an appropriate view of the graphs, including their point(s) of intersection.
3. To find the value of $x$, we compute the point of intersection. Press **[2ND]** then **[CALC]**. Select "intersect" and press **[ENTER]** three times. The point of intersection gives the value of $x$,for the point(s) of intersection.

**Example 5.5.9: Approximating the Solution of a Logarithmic Equation**

Solve $4\ln(x)+1=-2\ln(x-1)$ graphically. Round to the nearest thousandth.

**Solution**

Press **[Y=]** and enter $4\ln(x)+1$ next to $\mathbf{Y_1}$=. Then enter $-2\ln(x-1)$ next to $\mathbf{Y_2}$=. For a window, use the values 0 to 5 for $x\backslash 0\ and\backslash(-10$ to 10 for $y$. Press **[GRAPH]**. The graphs should intersect somewhere a little to right of $x=1$.

For a better approximation, press **[2ND]** then **[CALC]**. Select **[5: intersect]** and press **[ENTER]** three times. The *x*-coordinate of the point of intersection is displayed as $1.3385297$ (Your answer may be different if you use a different window or use a different value for **Guess?**) So, to the nearest thousandth, $x\approx 1.339$.

**Exercise 5.5.9**

Solve $5\log(x+2)=4-\log(x)$ graphically. Round to the nearest thousandth.

**Answer**

$x\approx 3.049$

## Summarizing Translations of the Logarithmic Function

Now that we have worked with each type of translation for the logarithmic function, we can summarize each in Table 5.5.4 to arrive at the general equation for translating exponential functions.

1 and a compression is 0<|a|<1. Note its form is f(x)=alog_b(x). The third translation is a reflection about the x-axis with the form f(x) = -log_b(x). The fourth translation is a reflection about the y-axis with the form f(x)=log_b(-x). The general equation for all translations is f(x)=alog_b(x+c)+d.">

***Table* 5.5.4**

| Translations of the Parent Function $y=\log_b(x)$ | |
|---|---|
| Translation | Form |
| Shift<br>Horizontally $c$ units to the left<br>Vertically $d$ units up | $y=\log_b(x+c)+d$ |
| Stretch and Compress<br>Stretch if $\lvert a\rvert>1$<br>Compression if $\lvert a\rvert<1$ | $y=a\log_b(x)$ |
| Reflect about the x-axis | $y=-\log_b(x)$ |
| Reflect about the y-axis | $y=\log_b(-x)$ |
| General equation for all translations | $y=a\log_b(x+c)+d$ |

## TRANSLATIONS OF LOGARITHMIC FUNCTIONS

All translations of the parent logarithmic function, $y = \log_b(x)$, have the form

$$f(x) = a\log_b(x + c) + d$$

where the parent function, $y = \log_b(x)$, $b > 1$,is

- shifted vertically up $d$ units.
- shifted horizontally to the left $c$ units.
- stretched vertically by a factor of $|a|$ if $|a| > 0$.
- compressed vertically by a factor of $|a|$ if $0 < |a| < 1$.
- reflected about the $x$-axis when $a < 0$.

For $f(x) = \log(-x)$, the graph of the parent function is reflected about the $y$-axis.

### Example 5.5.10: Finding the Vertical Asymptote of a Logarithm Graph

What is the vertical asymptote of $f(x) = -2\log_3(x + 4) + 5$ ?

**Solution**

The vertical asymptote is at $x = -4$.

**Analysis**

The coefficient, the base, and the upward translation do not affect the asymptote. The shift of the curve 4 units to the left shifts the vertical asymptote to$x = -4$.

### Exercise 5.5.10

What is the vertical asymptote of $f(x) = 3 + \ln(x - 1)$ ?

**Answer**

$x = 1$

### Example 5.5.11: Finding the Equation from a Graph

Find a possible equation for the common logarithmic function graphed in Figure 5.5.21.





Figure 5.5.21

**Solution**

This graph has a vertical asymptote at $x = -2$ and has been vertically reflected. We do not know yet the vertical shift or the vertical stretch. We know so far that the equation will have form:

$$f(x) = -a\log(x+2)+k$$

It appears the graph passes through the points $(-1,1)$ and $(2,-1)$. Substituting $(-1,1)$,

$$\begin{aligned} 1 &= -a\log(-1+2)+k \qquad \text{Substitute}(-1,1) \\ 1 &= -a\log(1)+k \qquad \text{Arithmetic} \\ 1 &= k\log(1) \\ &= 0 \end{aligned}$$

Next, substituting in $(2,-1)$,

$$\begin{aligned} -1 &= -a\log(2+2)+1 \qquad \text{Substitute}(2,-1) \\ -2 &= -a\log(4) \qquad \text{Arithmetic} \\ a &= \frac{2}{\log(4)} \qquad \text{Solve for a} \end{aligned}$$

This gives us the equation $f(x) = -\frac{2}{\log(4)}\log(x+2)+1$.

**Analysis**

We can verify this answer by comparing the function values in Table 5.5.5 with the points on the graph in Figure 5.5.21.

Table 5.5.5

| $x$ | $-1$ | 0 | 1 | 2 | 3 |
|---|---|---|---|---|---|
| $f(x)$ | 1 | 0 | −0.58496 | −1 | −1.3219 |
| $x$ | 4 | 5 | 6 | 7 | 8 |
| $f(x)$ | −1.5850 | −1.8074 | −2 | −2.1699 | −2.3219 |

**Exercise 5.5.11**

Give the equation of the natural logarithm graphed in Figure 5.5.22





Figure 5.5.22

**Answer**

$f(x) = 2\ln(x+3)-1$

**Media: Is it possible to tell the domain and range and describe the end behavior of a function just by looking at the graph?**

Yes, if we know the function is a general logarithmic function. For example, look at the graph in Figure 5.5.22 The graph approaches $x=-3$ (or thereabouts) more and more closely, so $x=-3$ is, or is very close to, the vertical asymptote. It approaches from the right, so the domain is all points to the right, $x|x>-3$. The range, as with all general logarithmic functions, is all real numbers. And we can see the end behavior because the graph goes down as it goes left and up as it goes right. The end behavior is that as $x\to -3^{+}$, $f(x)\to -\infty$ and as $x\to \infty$, $f(x)\to \infty$.

**Media**

Access these online resources for additional instruction and practice with graphing logarithms.

- Graph an Exponential Function and Logarithmic Function
- Match Graphs with Exponential and Logarithmic Functions
- Find the Domain of Logarithmic Functions

## Key Equations

| | |
|---|---|
| General Form for the Translation of the Parent Logarithmic Function $f(x)=\log_b(x)$ | $f(x)=a\log_b(x+c)+d$ |

## Key Concepts

- To find the domain of a logarithmic function, set up an inequality showing the argument greater than zero, and solve for $x$. See Example 5.5.1 and Example 5.5.2
- The graph of the parent function $f(x)=\log_b(x)$ has an *x*-intercept at $(1,0)$,domain $(0,\infty)$,range $(-\infty,\infty)$,vertical asymptote $x=0$,and
- - if $b>1$,the function is increasing.
  - if $0<b<1$, the function is decreasing.

  See Example 5.5.3.
- The equation $f(x)=\log_b(x+c)$ shifts the parent function $y=\log_b(x)$ horizontally
  - left $c$ units if $c>0$.
  - right $c$ units if $c<0$.

  See Example 5.5.4.
- The equation $f(x)=\log_b(x)+d$ shifts the parent function $y=\log_b(x)$ vertically
  - up $d$ units if $d>0$.
  - down $d$ units if $d<0$.

  See Example 5.5.5.
- For any constant $a>0$, the equation $f(x)=a\log_b(x)$
  - stretches the parent function $y=\log_b(x)$ vertically by a factor of $a$ if $|a|>1$.
  - compresses the parent function $y=\log_b(x)$ vertically by a factor of $a$ if $|a|<1$.

  See Example 5.5.6 and Example 5.5.7.
- When the parent function $y=\log_b(x)$ is multiplied by $-1$, the result is a reflection about the *x*-axis. When the input is multiplied by $-1$, the result is a reflection about the *y*-axis.
  - The equation $f(x)=-\log_b(x)$ represents a reflection of the parent function about the *x*-axis.
  - The equation $f(x)=\log_b(-x)$ represents a reflection of the parent function about the *y*-axis.

  See Example 5.5.8.
  - A graphing calculator may be used to approximate solutions to some logarithmic equations See Example 5.5.9.
- All translations of the logarithmic function can be summarized by the general equation $f(x)=a\log_b(x+c)+d$ . See Table 5.5.4.

- Given an equation with the general form $f(x) = a\log_b(x + c) + d$ ,we can identify the vertical asymptote $x = -c$ for the transformation. See Example 5.5.10
- Using the general equation $f(x) = a\log_b(x + c) + d$ , we can write the equation of a logarithmic function given its graph. See Example 5.5.11.

---

This page titled 5.5: Graphs of Logarithmic Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.4: Graphs of Logarithmic Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.5E: Graphs of Logarithmic Functions (Exercises)

23. Graph the function $g(x) = \log(7x + 21) - 4$ .

24. Graph the function $h(x) = 2\ln(9 - 3x) + 1$ .

25. State the domain, vertical asymptote, and end behavior of the function $g(x) = \ln(4x + 20) - 17$ .

---

This page titled 5.5E: Graphs of Logarithmic Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.4E: Graphs of Logarithmic Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.6: Logarithmic Properties

**Learning Objectives**

- Use the product rule for logarithms.
- Use the quotient rule for logarithms.
- Use the power rule for logarithms.
- Expand logarithmic expressions.
- Condense logarithmic expressions.
- Use the change-of-base formula for logarithms.

In chemistry, the pH scale is used as a measure of the acidity or alkalinity of a substance. Substances with a pH less than $7$ are considered acidic, and substances with a pH greater than $7$ are said to be alkaline. Our bodies, for instance, must maintain a pH close to $7.35$ in order for enzymes to work properly. To get a feel for what is acidic and what is alkaline, consider the following pH levels of some common substances:

- Battery acid: $0.8$
- Stomach acid: $2.7$
- Orange juice: $3.3$
- Pure water: $7$ at $25°C$
- Human blood: $7.35$
- Fresh coconut: $7.8$
- Sodium hydroxide (lye): $14$

To determine whether a solution is acidic or alkaline, we find its pH, which is a measure of the number of active positive hydrogen ions in the solution. The pH is defined by the following formula, where $[\mathrm{H}^+]$ is the concentration of hydrogen ions in the solution

$$pH = -\log([\mathrm{H}^+]) \tag{5.6.1}$$

$$= \log\left(\frac{1}{[\mathrm{H}^+]}\right) \tag{5.6.2}$$

The equivalence of Equations 5.6.1 and 5.6.2 is one of the logarithm properties we will examine in this section.




Figure 5.6.1: The pH of hydrochloric acid is tested with litmus paper. (credit: David Berardan).

## Using the Product Rule for Logarithms

Recall that the logarithmic and exponential functions "undo" each other. This means that logarithms have similar properties to exponents. Some important properties of logarithms are given here. First, the following properties are easy to prove.

$$\log_b 1 = 0$$

$$\log_b b = 1$$

For example, $\log_5 1 = 0$ since $5^0 = 1$. And $\log_5 5 = 1$ since $5^1 = 5$.

Next, we have the inverse property.

$$\log_b(b^x) = x$$
$$b^{\log_b x} = x,\ x > 0$$

For example, to evaluate $\log(100)$, we can rewrite the logarithm as $\log_{10}(10^2)$, and then apply the inverse property $\log_b(b^x) = x$ to get $\log_{10}(10^2) = 2$.

To evaluate $e^{\ln(7)}$, we can rewrite the logarithm as $e^{\log_e 7}$, and then apply the inverse property $b^{\log_b x} = x$ to get $e^{\log_e 7} = 7$.

Finally, we have the one-to-one property.

$$\log_b M = \log_b N \text{ if and only if } M = N \tag{5.6.3}$$

We can use the one-to-one property to solve the equation $\log_3(3x) = \log_3(2x+5)$ for $x$. Since the bases are the same, we can apply the one-to-one property by setting the arguments equal and solving for $x$:

$3x = 2x + 5$ Set the arguments equal.

$x = 5$ Subtract $2x$.

But what about the equation $\log_3(3x) + \log_3(2x+5) = 2$ ? The one-to-one property does not help us in this instance. Before we can solve an equation like this, we need a method for combining terms on the left side of the equation.

Recall that we use the *product rule of exponents* to combine the product of exponents by adding: $x^a x^b = x^{a+b}$. We have a similar property for logarithms, called the **product rule for logarithms**, which says that the logarithm of a product is equal to a sum of logarithms. Because logs are exponents, and we multiply like bases, we can add the exponents. We will use the inverse property to derive the product rule below.

Given any real number $x$ and positive real numbers $M$, $N$, and $b$, where $b \neq 1$, we will show

$$\log_b(MN) = \log_b(M) + \log_b(N)\ .$$

Let $m = \log_b M$ and $n = \log_b N$. In exponential form, these equations are $b^m = M$ and $b^n = N$. It follows that

$$\begin{aligned} \log_b(MN) &= \log_b(b^m b^n) && \text{Substitute for M and N} \\ &= \log_b(b^{m+n}) && \text{Apply the product rule for exponents} \\ &= m+n && \text{Apply the inverse property of logs} \\ &= \log_b(M) + \log_b(N) && \text{Substitute for m and n} \end{aligned}$$

Note that repeated applications of the product rule for logarithms allow us to simplify the logarithm of the product of any number of factors. For example, consider $\log_b(wxyz)$. Using the product rule for logarithms, we can rewrite this logarithm of a product as the sum of logarithms of its factors:

$$\log_b(wxyz) = \log_b w + \log_b x + \log_b y + \log_b z$$

### The Product Rule for Logarithms

The product rule for logarithms can be used to simplify a logarithm of a product by rewriting it as a sum of individual logarithms.

$$\log_b(MN) = \log_b(M) + \log_b(N) \text{ for } b > 0 \tag{5.6.4}$$

### How to: Given the logarithm of a product, use the product rule of logarithms to write an equivalent sum of logarithms

1. Factor the argument completely, expressing each whole number factor as a product of primes.
2. Write the equivalent expression by summing the logarithms of each factor.

### Example 5.6.1: Using the Product Rule for Logarithms

Expand $\log_3(30x(3x+4))$.

**Solution**

We begin by factoring the argument completely, expressing 30 as a product of primes.

$$\log_3(30x(3x+4)) = \log_3(2\cdot 3\cdot 5\cdot x\cdot(3x+4))$$

Next we write the equivalent equation by summing the logarithms of each factor.

$$\log_3(30x(3x+4)) = \log_3(2)+\log_3(3)+\log_3(5)+\log_3(x)+\log_3(3x+4)$$

### Exercise 5.6.1

Expand $\log_b(8k)$.

**Answer**

$$\log_b 2+\log_b 2+\log_b 2+\log_b k = 3\log_b 2+\log_b k$$

## Using the Quotient Rule for Logarithms

For quotients, we have a similar rule for logarithms. Recall that we use the *quotient rule of exponents* to combine the quotient of exponents by subtracting: $x^{\frac{a}{b}} = x^{a-b}$. The **quotient rule for logarithms** says that the logarithm of a quotient is equal to a difference of logarithms.

### The Quotient Rule for Logarithms

The quotient rule for logarithms can be used to simplify a logarithm or a quotient by rewriting it as the difference of individual logarithms.

$$\log_b\left(\frac{M}{N}\right) = \log_b M - \log_b N \tag{5.6.5}$$

Just as with the product rule, we can use the inverse property to derive the quotient rule.

### Proof

Given any real number $x$ and positive real numbers $M$, $N$, and b, b, where $b\neq 1$, we will show

$$\log_b\left(\frac{M}{N}\right) = \log_b(M) - \log_b(N)\ .$$

Let $m = \log_b M$ and $n = \log_b N$. In exponential form, these equations are $b^m = M$ and $b^n = N$. It follows that

$$\begin{aligned}
\log_b\left(\frac{M}{N}\right) &= \log_b\left(\frac{b^m}{b^n}\right) && \text{Substitute for M and N}\\
&= \log_b(b^{m-n}) && \text{Apply the quotient rule for exponents}\\
&= m-n && \text{Apply the inverse property of logs}\\
&= \log_b(M)-\log_b(N) && \text{Substitute for m and n}
\end{aligned}$$

For example, to expand $\log\left(\frac{2x^2+6x}{3x+9}\right)$, we must first express the quotient in lowest terms. Factoring and canceling we get,

$$\log\left(\frac{2x^2+6x}{3x+9}\right)=\log\left(\frac{2x(x+3)}{3(x+3)}\right) \qquad \text{Factor the numerator and denominator}$$

$$=\log\left(\frac{2x}{3}\right) \qquad \text{Cancel the common factors}$$

Next we apply the quotient rule by subtracting the logarithm of the denominator from the logarithm of the numerator. Then we apply the product rule.

$$\log\left(\frac{2x}{3}\right)=\log(2x)-\log(3)$$

$$=\log(2)+\log(x)-\log(3)$$

**How to: Given the logarithm of a quotient, use the quotient rule of logarithms to write an equivalent difference of logarithms**

1. Express the argument in lowest terms by factoring the numerator and denominator and canceling common terms.
2. Write the equivalent expression by subtracting the logarithm of the denominator from the logarithm of the numerator.
3. Check to see that each term is fully expanded. If not, apply the product rule for logarithms to expand completely.

**Example 5.6.2: Using the Quotient Rule for Logarithms**

Expand $log_2\left(\frac{15x(x-1)}{(3x+4)(2-x)}\right)$.

**Solution**

First we note that the quotient is factored and in lowest terms, so we apply the quotient rule.

$$\log_2(\frac{15x(x-1)}{(3x+4)(2-x)})=\log_2(15x(x-1))-\log_2((3x+4)(2-x))$$

Notice that the resulting terms are logarithms of products. To expand completely, we apply the product rule, noting that the prime factors of the factor 15 are 3 and 5.

$$\log_2(15x(x-1))-\log_2((3x+4)(2-x)) = [\log_2(3)+\log_2(5)+\log_2(x)+\log_2(x-1)]-[\log_2(3x+4)+\log_2(2-x)]$$

$$=\log_2(3)+\log_2(5)+\log_2(x)+\log_2(x-1)-\log_2(3x+4)-\log_2(2-x)$$

**Analysis**

There are exceptions to consider in this and later examples. First, because denominators must never be zero, this expression is not defined for $x=-\frac{4}{3}$ and $x=2$. Also, since the argument of a logarithm must be positive, we note as we observe the expanded logarithm, that $x>0$, $x>1$, $x>-\frac{4}{3}$, and $x<2$. Combining these conditions is beyond the scope of this section, and we will not consider them here or in subsequent exercises.

**Exercise 5.6.2**

Expand $\log_3\left(\frac{7x^2+21x}{7x(x-1)(x-2)}\right)$.

**Answer**

$\log_3(x+3)-\log_3(x-1)-\log_3(x-2)$

## Using the Power Rule for Logarithms

We've explored the product rule and the quotient rule, but how can we take the logarithm of a power, such as $x^2$? One method is as follows:

$$\begin{aligned}\log_b(x^2) &= \log_b(x \cdot x) \\ &= \log_b x + \log_b x \\ &= 2\log_b x\end{aligned}$$

Notice that we used the **product rule for logarithms** to find a solution for the example above. By doing so, we have derived the **power rule for logarithms**, which says that the log of a power is equal to the exponent times the log of the base. Keep in mind that, although the input to a logarithm may not be written as a power, we may be able to change it to a power. For example,

$$100 = 10^2 \quad \sqrt{3} = 3^{\frac{1}{2}} \quad \frac{1}{e} = e^{-1}$$

### The Power Rule for Logarithms

The power rule for logarithms can be used to simplify the logarithm of a power by rewriting it as the product of the exponent times the logarithm of the base.

$$\log_b(M^n) = n\log_b M \tag{5.6.6}$$

### How to: Given the logarithm of a power, use the power rule of logarithms to write an equivalent product of a factor and a logarithm

1. Express the argument as a power, if needed.
2. Write the equivalent expression by multiplying the exponent times the logarithm of the base.

### Example 5.6.3: Expanding a Logarithm with Powers

Expand $\log_2 x^5$.

**Solution**

The argument is already written as a power, so we identify the exponent, 5, and the base, $x$, and rewrite the equivalent expression by multiplying the exponent times the logarithm of the base.

$$\log_2(x^5) = 5\log_2 x$$

### Exercise 5.6.3

Expand $\ln x^2$.

**Answer**

$2\ln x$

### Example 5.6.4: Rewriting an Expression as a Power before Using the Power Rule

Expand $\log_3(25)$ using the power rule for logs.

**Solution**

Expressing the argument as a power, we get $\log_3(25) = \log_3(5^2)$.

Next we identify the exponent, 2, and the base, 5, and rewrite the equivalent expression by multiplying the exponent times the logarithm of the base.

$$\log_3(52) = 2\log_3(5)$$

**Exercise 5.6.4**

Expand $\ln\left(\frac{1}{x^2}\right)$.

**Answer**

$-2\ln(x)$

**Example 5.6.5: Using the Power Rule in Reverse**

Rewrite $4\ln(x)$ using the power rule for logs to a single logarithm with a leading coefficient of 1.

**Solution**

Because the logarithm of a power is the product of the exponent times the logarithm of the base, it follows that the product of a number and a logarithm can be written as a power. For the expression $4\ln(x)$, we identify the factor, 4, as the exponent and the argument, $x$, as the base, and rewrite the product as a logarithm of a power: $4\ln(x) = \ln(x^4)$.

**Exercise 5.6.5**

Rewrite $2\log_3 4$ using the power rule for logs to a single logarithm with a leading coefficient of 1.

**Answer**

$\log_3 16$

## Expanding Logarithmic Expressions

Taken together, the product rule, quotient rule, and power rule are often called "laws of logs." Sometimes we apply more than one rule in order to simplify an expression. For example:

$$\begin{aligned}\log_b\left(\frac{6x}{y}\right) &= \log_b(6x) - \log_b y \\ &= \log_b 6 + \log_b x - \log_b y\end{aligned}$$

We can use the power rule to expand logarithmic expressions involving negative and fractional exponents. Here is an alternate proof of the quotient rule for logarithms using the fact that a reciprocal is a negative power:

$$\begin{aligned}\log_b\left(\frac{A}{C}\right) &= \log_b(AC^{-1}) \\ &= \log_b(A) + \log_b(C^{-1}) \\ &= \log_b A + (-1)\log_b C \\ &= \log_b A - \log_b C\end{aligned}$$

We can also apply the product rule to express a sum or difference of logarithms as the logarithm of a product.

With practice, we can look at a logarithmic expression and expand it mentally, writing the final answer. Remember, however, that we can only do this with products, quotients, powers, and roots—never with addition or subtraction inside the argument of the logarithm.

**Example 5.6.6: Expanding Logarithms Using Product, Quotient, and Power Rules**

Rewrite $ln\left(\frac{x^4 y}{7}\right)$ as a sum or difference of logs.

**Solution**

First, because we have a quotient of two expressions, we can use the quotient rule:

$$\ln\left(\frac{x^4y}{7}\right) = \ln(x^4y) - \ln(7)$$

Then seeing the product in the first term, we use the product rule:

$$\ln(x^4y) - \ln(7) = \ln(x^4) + \ln(y) - \ln(7)$$

Finally, we use the power rule on the first term:

$$\ln(x^4) + \ln(y) - \ln(7) = 4\ln(x) + \ln(y) - \ln(7)$$

**? Exercise 5.6.6**

Expand $\log\left(\frac{x^2y^3}{z^4}\right)$.

**Answer**

$2\log x + 3\log y - 4\log z$

**✓ Example 5.6.7: Using the Power Rule for Logarithms to Simplify the Logarithm of a Radical Expression**

Expand $\log(\sqrt{x})$.

**Solution**

$$\log(\sqrt{x}) = \log x^{\left(\frac{1}{2}\right)}$$
$$= \frac{1}{2}\log x$$

**? Exercise 5.6.7**

Expand $\ln(\sqrt[3]{x^2})$.

**Answer**

$\frac{2}{3}\ln x$

**Q&A: Can we expand $\ln(x^2 + y^2)$?**

*No. There is no way to expand the logarithm of a sum or difference inside the argument of the logarithm.*

**✓ Example 5.6.8: Expanding Complex Logarithmic Expressions**

Expand $\log_6\left(\frac{64x^3(4x+1)}{(2x-1)}\right)$.

**Solution**

We can expand by applying the Product and Quotient Rules.

$$\log_6\left(\frac{64x^3(4x+1)}{(2x-1)}\right) = \log_6 64 + \log_6 x^3 + \log_6(4x+1) - \log_6(2x-1) \quad \text{Apply the Quotient Rule}$$
$$= \log_6 2^6 + \log_6 x^3 + \log_6(4x+1) - \log_6(2x-1) \quad \text{Simplify by writing } 64 \text{ as } 2^6$$
$$= 6\log_6 2 + 3\log_6 x + \log_6(4x+1) - \log_6(2x-1) \quad \text{Apply the Power Rule}$$

**Exercise 5.6.8**

Expand $\ln\left(\dfrac{\sqrt{(x-1)(2x+1)^2}}{(x^2-9)}\right)$.

**Answer**

$\dfrac{1}{2}\ln(x-1)+\ln(2x+1)-\ln(x+3)-\ln(x-3)$

## Condensing Logarithmic Expressions

We can use the rules of logarithms we just learned to condense sums, differences, and products with the same base as a single logarithm. It is important to remember that the logarithms must have the same base to be combined. We will learn later how to change the base of any logarithm before condensing.

**How to: Given a sum, difference, or product of logarithms with the same base, write an equivalent expression as a single logarithm**

1. Apply the power property first. Identify terms that are products of factors and a logarithm, and rewrite each as the logarithm of a power.
2. Next apply the product property. Rewrite sums of logarithms as the logarithm of a product.
3. Apply the quotient property last. Rewrite differences of logarithms as the logarithm of a quotient.

**Example 5.6.9: Using the Product and Quotient Rules to Combine Logarithms**

Write $\log_3(5)+\log_3(8)-\log_3(2)$ as a single logarithm.

**Solution**

Using the product and quotient rules

$$\log_3(5)+\log_3(8)=\log_3(5\cdot 8)=\log_3(40)$$

This reduces our original expression to

$$\log_3(40)-\log_3(2)$$

Then, using the quotient rule

$$\log_3(40)-\log_3(2)=\log_3\left(\frac{40}{2}\right)=\log_3(20)$$

**Exercise 5.6.9**

Condense $\log_3-\log_4+\log_5-\log_6$ .

**Answer**

$\log\left(\dfrac{3\cdot 5}{4\cdot 6}\right)$; can also be written $\log\left(\dfrac{5}{8}\right)$ by reducing the fraction to lowest terms.

**Example 5.6.10: Condensing Complex Logarithmic Expressions**

Condense $\log_2(x^2)+\dfrac{1}{2}\log_2(x-1)-3\log_2((x+3)^2)$ .

**Solution**

We apply the power rule first:

$$\log_2(x^2)+\frac{1}{2}\log_2(x-1)-3\log_2((x+3)^2)=\log_2(x^2)+\log_2(\sqrt{x-1})-\log_2((x+3)^6)$$

Next we apply the product rule to the sum:

$$\log_2(x^2)+\log_2(\sqrt{x-1})-\log_2((x+3)^6)=\log_2(x^2\sqrt{x-1})-\log_2((x+3)^6)$$

Finally, we apply the quotient rule to the difference:

$$\log_2(x^2\sqrt{x-1})-\log_2((x+3)^6)=\log_2\frac{x^2\sqrt{x-1}}{(x+3)^6}$$

### Example 5.6.11: Rewriting as a Single Logarithm

Rewrite $2\log x-4\log(x+5)+\frac{1}{x}\log(3x+5)$ as a single logarithm.

**Solution**

We apply the power rule first:

$$2\log x-4\log(x+5)+\frac{1}{x}\log(3x+5)=\log(x^2)-\log(x+5)^4+\log((3x+5)^{x^{-1}})$$

Next we rearrange and apply the product rule to the sum:

$$\begin{aligned}\log(x^2)-\log(x+5)^4+\log((3x+5)^{x^{-1}}) &=\log(x^2)+\log((3x+5)^{x^{-1}}-\log(x+5)^4\\ &=\log(x^2(3x+5)^{x^{-1}})-\log(x+5)^4\\ &=\log\frac{x^2(3x+5)^{x^{-1}}}{(x+5)^4} \qquad \text{Apply the quotient rule to the difference}\end{aligned}$$

### Exercise 5.6.10

Rewrite $\log(5)+0.5\log(x)-\log(7x-1)+3\log(x-1)$ as a single logarithm.

**Answer**

$$\log\frac{5(x-1)^3\sqrt{x}}{(7x-1)}$$

### Exercise 5.6.11

Condense $4(3\log(x)+\log(x+5)-\log(2x+3))$.

**Answer**

$\log\frac{x^{12}(x+5)^4}{(2x+3)^4}$; this answer could also be written $\log\left(\frac{x^3(x+5)}{(2x+3)}\right)^4$

### Example 5.6.12: Applying of the Laws of Logs

Recall that, in chemistry, $pH=-\log[H+]$. If the concentration of hydrogen ions in a liquid is doubled, what is the effect on pH?

**Solution**

Suppose $C$ is the original concentration of hydrogen ions, and $P$ is the original pH of the liquid. Then $P=-\log(C)$. If the concentration is doubled, the new concentration is $2C$. Then the pH of the new liquid is

$$pH=-\log(2C)$$

Using the product rule of logs

$$pH = -\log(2C) = -(\log(2) + \log(C)) = -\log(2) - \log(C)$$

Since $P = -\log(C)$,the new pH is

$$pH = P - \log(2) \approx P - 0.301$$

**Exercise 5.6.12**

When the concentration of hydrogen ions is doubled, the pH decreases by about $0.301$.

How does the pH change when the concentration of positive hydrogen ions is decreased by half?

**Answer**

The pH increases by about $0.301$.

## Using the Change-of-Base Formula for Logarithms

Most calculators can evaluate only common and natural logs. In order to evaluate logarithms with a base other than 10 ore, e,we use the **change-of-base formula** to rewrite the logarithm as the quotient of logarithms of any other base; when using a calculator, we would change them to common or natural logs.

To derive the change-of-base formula, we use the **one-to-one** property and **power rule for logarithms**.

Given any positive real numbers $M$, $b$, and $n$, where $n \neq 1$ and $b \neq 1$,we show

$$\log_b M = \frac{\log_n M}{\log_n b}$$

Let $y = \log_b M$. By taking the log base $n$ of both sides of the equation, we arrive at an exponential form, namely $b^y = M$. It follows that

$$\begin{aligned} \log_n(b^y) &= \log_n M && \text{Apply the one-to-one property} \\ y\log_n b &= \log_n M && \text{Apply the power rule for logarithms} \\ y &= \frac{\log_n M}{\log_n b} && \text{Isolate y} \\ \log_b M &= \frac{\log_n M}{\log_n b} && \text{Substitute for y} \end{aligned}$$

For example, to evaluate $\log_5 36$ using a calculator, we must first rewrite the expression as a quotient of common or natural logs. We will use the common log.

$$\begin{aligned} \log_5 36 &= \frac{\log(36)}{\log(5)} && \text{Apply the change of base formula using base 10} \\ &\approx 2.2266 && \text{Use a calculator to evaluate to 4 decimal places} \end{aligned}$$

**THE CHANGE-OF-BASE FORMULA**

The change-of-base formula can be used to evaluate a logarithm with any base.

For any positive real numbers $M$, $b$, and $n$, where $n \neq 1$ and $b \neq 1$,

$$\log_b M = \frac{\log_n M}{\log_n b} \tag{5.6.7}$$

It follows that the change-of-base formula can be used to rewrite a logarithm with any base as the quotient of common or natural logs.

$$\log_b M = \frac{\ln M}{\ln b} \tag{5.6.8}$$

and

$$\log_b M = \frac{\log M}{\log b} \tag{5.6.9}$$

**How to: Given a logarithm with the form $\log_b M$, use the change-of-base formula to rewrite it as a quotient of logs with any positive base $n$, where $n \neq 1$**

1. Determine the new base $n$, remembering that the common log, $\log(x)$, has base 10, and the natural log, $\ln(x)$,has base $e$.
2. Rewrite the log as a quotient using the change-of-base formula
   - The numerator of the quotient will be a logarithm with base $n$ and argument $M$.
   - The denominator of the quotient will be a logarithm with base $n$ and argument $b$.

**Example 5.6.13: Changing Logarithmic Expressions to Expressions Involving Only Natural Logs**

Change $\log_5 3$ to a quotient of natural logarithms.

**Solution**

Because we will be expressing $\log_5 3$ as a quotient of natural logarithms, the new base, $n = e$.

We rewrite the log as a quotient using the change-of-base formula. The numerator of the quotient will be the natural log with argument 3. The denominator of the quotient will be the natural log with argument 5.

$$\log_b M = \frac{\ln M}{\ln b}$$

$$\log_5 3 = \frac{\ln 3}{\ln 5}$$

**Exercise 5.6.13**

Change $\log 0.58$ to a quotient of natural logarithms.

**Answer**

$$\frac{\ln 8}{\ln 0.5}$$

**Q&A: Can we change common logarithms to natural logarithms?**

*Yes. Remember that* $\log 9$ *means* $\log_{10} 9$. *So,* $\log 9 = \frac{\ln 9}{\ln 10}$.

**Example 5.6.14: Using the Change-of-Base Formula with a Calculator**

Evaluate $\log_2(10)$ using the change-of-base formula with a calculator.

**Solution**

According to the change-of-base formula, we can rewrite the log base 2 as a logarithm of any other base. Since our calculators can evaluate the natural log, we might choose to use the natural logarithm, which is the log base $e$.

$$\log_2 10 = \frac{\ln 10}{\ln 2} \qquad \text{Apply the change of base formula using base } e$$

$$\approx 3.3219 \qquad \text{Use a calculator to evaluate to 4 decimal places}$$

## Exercise 5.6.14

Evaluate $\log_5(100)$ using the change-of-base formula.

**Answer**

$$\frac{\ln 100}{\ln 5} \approx \frac{4.6051}{1.6094} = 2.861$$

## Media

Access these online resources for additional instruction and practice with laws of logarithms.

- The Properties of Logarithms
- Expand Logarithmic Expressions
- Evaluate a Natural Logarithmic Expression

## Key Equations

| | |
|---|---|
| The Product Rule for Logarithms | $\log_b(MN) = \log_b(M) + \log_b(N)$ |
| The Quotient Rule for Logarithms | $\log_b(\frac{M}{N}) = \log_b M - \log_b N$ |
| The Power Rule for Logarithms | $\log_b(M^n) = n\log_b M$ |
| The Change-of-Base Formula | $\log_b M = \frac{\log_n M}{\log_n b} \quad n > 0, n \neq 1, b \neq 1$ |

## Key Concepts

- We can use the product rule of logarithms to rewrite the log of a product as a sum of logarithms. See Example 5.6.1.
- We can use the quotient rule of logarithms to rewrite the log of a quotient as a difference of logarithms. See Example 5.6.2.
- We can use the power rule for logarithms to rewrite the log of a power as the product of the exponent and the log of its base. See Example 5.6.3, Example 5.6.4, and Example 5.6.5.
- We can use the product rule, the quotient rule, and the power rule together to combine or expand a logarithm with a complex input. See Example 5.6.6, Example 5.6.7, and Example 5.6.8.
- The rules of logarithms can also be used to condense sums, differences, and products with the same base as a single logarithm. See Example 5.6.9, Example 5.6.10, Example 5.6.11, and Example 5.6.12
- We can convert a logarithm with any base to a quotient of logarithms with any other base using the change-of-base formula. See Example 5.6.13
- The change-of-base formula is often used to rewrite a logarithm with a base other than 10 and $e$ as the quotient of natural or common logs. That way a calculator can be used to evaluate. See Example 5.6.14

This page titled 5.6: Logarithmic Properties is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.5: Logarithmic Properties** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.6E: Logarithmic Properties (Exercises)

26. Rewrite $\ln(7r \cdot 11st)$ in expanded form.

27. Rewrite $\log_8(x)+\log_8(5)+\log_8(y)+\log_8(13)$ in compact form.

28. Rewrite $\log_m\left(\frac{67}{83}\right)$ in expanded form.

29. Rewrite $\ln(z)-\ln(x)-\ln(y)$ in compact form.

30. Rewrite $\ln\left(\frac{1}{x^5}\right)$ as a product.

31. Rewrite $-\log_y\left(\frac{1}{12}\right)$ as a single logarithm.

32. Use properties of logarithms to expand $\log\left(\frac{r^2 s^{11}}{t^{14}}\right)$.

33. Use properties of logarithms to expand $\ln\left(2b\sqrt{\frac{b+1}{b-1}}\right)$.

34. Condense the expression $5\ln(b)+\ln(c)+\frac{\ln(4-a)}{2}$ to a single logarithm.

35. Condense the expression $3\log_7 v+6\log_7 w-\frac{\log_7 u}{3}$ to a single logarithm.

36. Rewrite $\log_3(12.75)$ to base $e$.

37. Rewrite $5^{12x-17}=125$ as a logarithm. Then apply the change of base formula to solve for $x$ using the common log. Round to the nearest thousandth.

This page titled 5.6E: Logarithmic Properties (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.5E: Logarithmic Properties (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.7: Exponential and Logarithmic Equations

**Learning Objectives**

- Use like bases to solve exponential equations.
- Use logarithms to solve exponential equations.
- Use the definition of a logarithm to solve logarithmic equations.
- Use the one-to-one property of logarithms to solve logarithmic equations.
- Solve applied problems involving exponential and logarithmic equations.

In 1859, an Australian landowner named Thomas Austin released 24 rabbits into the wild for hunting. Because Australia had few predators and ample food, the rabbit population exploded. In fewer than ten years, the rabbit population numbered in the millions.



Figure 5.7.1: Wild rabbits in Australia. The rabbit population grew so quickly in Australia that the event became known as the "rabbit plague." (credit: Richard Taylor, Flickr)

Uncontrolled population growth, as in the wild rabbits in Australia, can be modeled with exponential functions. Equations resulting from those exponential functions can be solved to analyze and make predictions about exponential growth. In this section, we will learn techniques for solving exponential functions.

## Using Like Bases to Solve Exponential Equations

The first technique involves two functions with like bases. Recall that the one-to-one property of exponential functions tells us that, for any real numbers $b$, $S$, and $T$, where $b > 0$, $b \neq 1$, $b^S = b^T$ if and only if $S = T$.

In other words, when an **exponential equation** has the same base on each side, the exponents must be equal. This also applies when the exponents are algebraic expressions. Therefore, we can solve many exponential equations by using the rules of exponents to rewrite each side as a power with the same base. Then, we use the fact that exponential functions are one-to-one to set the exponents equal to one another, and solve for the unknown.

For example, consider the equation $3^{4x-7} = \dfrac{3^{2x}}{3}$. To solve for $x$, we use the division property of exponents to rewrite the right side so that both sides have the common base, 3. Then we apply the one-to-one property of exponents by setting the exponents equal to one another and solving for $x$:

$$
\begin{aligned}
3^{4x-7} &= \frac{3^{2x}}{3} && \\
3^{4x-7} &= \frac{3^{2x}}{3^1} && \text{Rewrite 3 as } 3^1 \\
3^{4x-7} &= 3^{2x-1} && \text{Use the division property of exponents} \\
4x-7 &= 2x-1 && \text{Apply the one-to-one property of exponents} \\
2x &= 6 && \text{Subtract 2x and add 7 to both sides} \\
x &= 3 && \text{Divide by 3}
\end{aligned}
$$

### USING THE ONE-TO-ONE PROPERTY OF EXPONENTIAL FUNCTIONS TO SOLVE EXPONENTIAL EQUATIONS

For any algebraic expressions $S$ and $T$, and any positive real number $b \neq 1$,

$$b^S = b^T \text{ if and only if } S = T \tag{5.7.1}$$

### How to: Given an exponential equation with the form $b^S = b^T$, where $S$ and $T$ are algebraic expressions with an unknown, solve for the unknown.

1. Use the rules of exponents to simplify, if necessary, so that the resulting equation has the form $b^S = b^T$.
2. Use the one-to-one property to set the exponents equal.
3. Solve the resulting equation, $S = T$, for the unknown.

### Example 5.7.1: Solving an Exponential Equation with a Common Base

Solve $2^{x-1} = 2^{2x-4}$.

**Solution**

| | |
|---|---|
| $2^{x-1} = 2^{2x-4}$ | The common base is 2 |
| $x - 1 = 2x - 4$ | By the one-to-one property the exponents must be equal |
| $x = 3$ | Solve for x |

### Exercise 5.7.1

Solve $5^{2x} = 5^{3x+2}$.

**Answer**

$x = -2$

## Rewrite Equations So All Powers Have the Same Base

Sometimes the *common base* for an exponential equation is not explicitly shown. In these cases, we simply rewrite the terms in the equation as powers with a common base, and solve using the one-to-one property.

For example, consider the equation $256 = 4^{x-5}$. We can rewrite both sides of this equation as a power of 2. Then we apply the rules of exponents, along with the one-to-one property, to solve for $x$:

| | |
|---|---|
| $256 = 4^{x-5}$ | |
| $2^8 = (2^2)^{x-5}$ | Rewrite each side as a power with base 2 |
| $2^8 = 2^{2x-10}$ | Use the one-to-one property of exponents |
| $8 = 2x - 10$ | Apply the one-to-one property of exponents |
| $18 = 2x$ | Add 10 to both sides |
| $x = 9$ | Divide by 2 |

### How to: Given an exponential equation with unlike bases, use the one-to-one property to solve it.

1. Rewrite each side in the equation as a power with a common base.
2. Use the rules of exponents to simplify, if necessary, so that the resulting equation has the form $b^S = b^T$.
3. Use the one-to-one property to set the exponents equal.
4. Solve the resulting equation, $S = T$, for the unknown.

### Example 5.7.2: Solving Equations by Rewriting Them to Have a Common Base

Solve $8^{x+2} = 16^{x+1}$.

**Solution**

$$
\begin{aligned}
8^{x+2} &= 16^{x+1} && \\
(2^3)^{x+2} &= (2^4)^{x+1} && \text{Write 8 and 16 as powers of 2} \\
2^{3x+6} &= 2^{4x+4} && \text{To take a power of a power, multiply exponents} \\
3x+6 &= 4x+4 && \text{Use the one-to-one property to set the exponents equal} \\
x &= 2 && \text{Solve for x}
\end{aligned}
$$

### Exercise 5.7.2

Solve $5^{2x} = 25^{3x+2}$.

**Answer**

$x = -1$

### Example 5.7.3: Solving Equations by Rewriting Roots with Fractional Exponents to Have a Common Base

Solve $2^{5x} = \sqrt{2}$.

**Solution**

$$
\begin{aligned}
2^{5x} &= 2^{\frac{1}{2}} && \text{Write the square root of 2 as a power of 2} \\
5x &= \frac{1}{2} && \text{Use the one-to-one property} \\
x &= \frac{1}{10} && \text{Solve for x}
\end{aligned}
$$

### Exercise 5.7.3

Solve $5^x = \sqrt{5}$.

**Answer**

$x = \frac{1}{2}$

### Q&A: Do all exponential equations have a solution? If not, how can we tell if there is a solution during the problem-solving process?

*No. Recall that the range of an exponential function is always positive. While solving the equation, we may obtain an expression that is undefined.*

### Example 5.7.4: Solving an Equation with Positive and Negative Powers

Solve $3^{x+1} = -2$.

**Solution**

This equation has no solution. There is no real value of $x$ that will make the equation a true statement because any power of a positive number is positive.

Analysis

Figure 5.7.2 shows that the two graphs do not cross so the left side is never equal to the right side. Thus the equation has no solution.





Figure 5.7.2

**Exercise 5.7.4**

Solve $2^x = -100$.

**Answer**

The equation has no solution.

## Solving Exponential Equations Using Logarithms

Sometimes the terms of an exponential equation cannot be rewritten with a common base. In these cases, we solve by taking the logarithm of each side. Recall, since $\log(a) = \log(b)$ is equivalent to $a = b$, we may apply logarithms with the same base on both sides of an exponential equation.

**How to: Given an exponential equation in which a common base cannot be found, solve for the unknown**

1. Apply the logarithm of both sides of the equation.
   - If one of the terms in the equation has base 10, use the common logarithm.
   - If none of the terms in the equation has base 10, use the natural logarithm.
2. Use the rules of logarithms to solve for the unknown.

**Example 5.7.5: Solving an Equation Containing Powers of Different Bases**

Solve $5^{x+2} = 4^x$.

**Solution**

| | | |
|---|---|---|
| $5^{x+2}$ | $=4^{x}$ | There is no easy way to get the powers to have the same base |
| $\ln 5^{x+2}$ | $=\ln 4^{x}$ | Take ln of both sides |
| $(x+2)\ln 5$ | $=x\ln 4$ | Use laws of logs |
| $x\ln 5+2\ln 5$ | $=x\ln 4$ | Use the distributive law |
| $x\ln 5-x\ln 4$ | $=-2\ln 5$ | Get terms containing x on one side, terms without x on the other |
| $x(\ln 5-\ln 4)$ | $=-2\ln 5$ | On the left hand side, factor out an x |
| $x\ln\left(\frac{5}{4}\right)$ | $=\ln\left(\frac{1}{25}\right)$ | Use the laws of logs |
| $x$ | $=\frac{\ln\left(\frac{1}{25}\right)}{\ln\left(\frac{5}{4}\right)}$ | Divide by the coefficient of x |

**? Exercise 5.7.5**

Solve $2^{x}=3^{x+1}$.

**Answer**

$$x=\frac{\ln 3}{\ln\left(\frac{2}{3}\right)}$$

**Q&A: Is there any way to solve $2^{x}=3^{x}$?**

*Yes. The solution is* $0$.

## Equations Containing $e$

One common type of exponential equations are those with base $e$. This constant occurs again and again in nature, in mathematics, in science, in engineering, and in finance. When we have an equation with a base $e$ on either side, we can use the natural logarithm to solve it.

**How to: Given an equation of the form $y=Ae^{kt}$, solve for $t$.**

1. Divide both sides of the equation by $A$.
2. Apply the natural logarithm of both sides of the equation.
3. Divide both sides of the equation by $k$.

**✓ Example 5.7.6: Solve an Equation of the Form $y=Ae^{kt}$**

Solve $100=20e^{2t}$.

**Solution**

| | | |
|---|---|---|
| $100$ | $=20e^{2t}$ | |
| $5$ | $=e^{2t}$ | Divide by the coefficient of the power |
| $\ln 5$ | $=2t$ | Take ln of both sides. Use the fact that $ln(x)$ and $e^{x}$ are inverse functions |
| $t$ | $=\frac{\ln 5}{2}$ | Divide by the coefficient of t |

**Analysis**

Using laws of logs, we can also write this answer in the form $t=\ln\sqrt{5}$. If we want a decimal approximation of the answer, we use a calculator.

**Exercise 5.7.6**

Solve $3e^{0.5t} = 11$.

**Answer**

$$t = 2\ln\left(\frac{11}{3}\right) \text{ or } \ln\left(\frac{11}{3}\right)^2$$

**Q&A: Does every equation of the form $y = Ae^{kt}$ have a solution?**

No. There is a solution when $k \neq 0$ ,and when $y$ and $A$ are either both 0 or neither 0, and they have the same sign. An example of an equation with this form that has no solution is $2 = -3e^t$.

**Example 5.7.7: Solving an Equation That Can Be Simplified to the Form $y = Ae^{kt}$**

Solve $4e^{2x} + 5 = 12$.

**Solution**

| | |
|---|---|
| $4e^{2x} + 5 = 12$ | |
| $4e^{2x} = 7$ | Combine like terms |
| $e^{2x} = \frac{7}{4}$ | Divide by the coefficient of the power |
| $2x = \ln\left(\frac{7}{4}\right)$ | Take ln of both sides |
| $x = \frac{1}{2}\ln\left(\frac{7}{4}\right)$ | Solve for x |

**Exercise 5.7.7**

Solve $3 + e^{2t} = 7e^{2t}$ .

**Answer**

$$t = \ln\left(\frac{1}{\sqrt{2}}\right) = -\frac{1}{2}\ln(2)$$

## Extraneous Solutions

Sometimes the methods used to solve an equation introduce an **extraneous solution**, which is a solution that is correct algebraically but does not satisfy the conditions of the original equation. One such situation arises in solving when the logarithm is taken on both sides of the equation. In such cases, remember that the argument of the logarithm must be positive. If the number we are evaluating in a logarithm function is negative, there is no output.

**Example 5.7.8: Solving Exponential Functions in Quadratic Form**

Solve $e^{2x} - e^x = 56$.

**Solution**

$$
\begin{aligned}
e^{2x}-e^{x} &= 56 & \\
e^{2x}-e^{x}-56 &= 0 & \text{Get one side of the equation equal to zero} \\
(e^{x}+7)(e^{x}-8) &= 0 & \text{Factor by the FOIL method} \\
e^{x}+7 &= 0 & \text{or} \\
e^{x}-8 &= 0 & \text{If a product is zero, then one factor must be zero} \\
e^{x} &= -7 & \text{or} \\
e^{x} &= 8 & \text{Isolate the exponentials} \\
e^{x} &= 8 & \text{Reject the equation in which the power equals a negative number} \\
x &= \ln 8 & \text{Solve the equation in which the power equals a positive number}
\end{aligned}
$$

**Analysis**

When we plan to use factoring to solve a problem, we always get zero on one side of the equation, because zero has the unique property that when a product is zero, one or both of the factors must be zero. We reject the equation $e^{x}=-7$ because a positive number never equals a negative number. The solution $\ln(-7)$ is not a real number, and in the real number system this solution is rejected as an extraneous solution.

**? Exercise 5.7.8**

Solve $e^{2x}=e^{x}+2$ .

**Answer**

$x=\ln 2$

**Q&A: Does every logarithmic equation have a solution?**

*No. Keep in mind that we can only apply the logarithm to a positive number. Always check for extraneous solutions.*

## Using the Definition of a Logarithm to Solve Logarithmic Equations

We have already seen that every logarithmic equation $\log_b(x)=y$ is equivalent to the exponential equation $b^{y}=x$. We can use this fact, along with the rules of logarithms, to solve logarithmic equations where the argument is an algebraic expression.

For example, consider the equation $\log_2(2)+\log_2(3x-5)=3$ . To solve this equation, we can use rules of logarithms to rewrite the left side in compact form and then apply the definition of logs to solve for $x$:

$$
\begin{aligned}
\log_2(2)+\log_2(3x-5) &= 3 & \\
\log_2(2(3x-5)) &= 3 & \text{Apply the product rule of logarithms} \\
\log_2(6x-10) &= 3 & \text{Distribute} \\
2^{3} &= 6x-10 & \text{Apply the definition of a logarithm} \\
8 &= 6x-10 & \text{Calculate } 2^{3} \\
18 &= 6x & \text{Add 10 to both sides} \\
x &= 3 & \text{Divide by 6}
\end{aligned}
$$

**USING THE DEFINITION OF A LOGARITHM TO SOLVE LOGARITHMIC EQUATIONS**

For any algebraic expression $S$ and real numbers $b$ and $c$,where $b>0$, $b\neq 1$,

$$\log_b(S)=c \text{ if and only if } b^{c}=S \tag{5.7.2}$$

**✓ Example 5.7.9: Using Algebra to Solve a Logarithmic Equation**

Solve $2\ln x+3=7$.

**Solution**

$$
\begin{aligned}
2\ln x + 3 &= 7 \\
2\ln x &= 4 && \text{Subtract 3} \\
\ln x &= 2 && \text{Divide by 2} \\
x &= e^2 && \text{Rewrite in exponential form}
\end{aligned}
$$

**? Exercise 5.7.9**

Solve $6 + \ln x = 10$.

**Answer**

$x = e^4$

**✓ Example 5.7.10: Using Algebra Before and After Using the Definition of the Natural Logarithm**

Solve $2\ln(6x) = 7$.

**Solution**

$$
\begin{aligned}
2\ln(6x) &= 7 \\
\ln(6x) &= \frac{7}{2} && \text{Divide by 2} \\
6x &= e^{\left(\frac{7}{2}\right)} && \text{Use the definition of ln} \\
x &= \frac{1}{6}e^{\left(\frac{7}{2}\right)} && \text{Divide by 6}
\end{aligned}
$$

**? Exercise 5.7.10**

Solve $2\ln(x+1) = 10$.

**Answer**

$x = e^5 - 1$

**✓ Example 5.7.11: Using a Graph to Understand the Solution to a Logarithmic Equation**

Solve $\ln x = 3$.

**Solution**

$$
\begin{aligned}
\ln x &= 3 \\
x &= e^3 && \text{Use the definition of the natural logarithm}
\end{aligned}
$$

Figure 5.7.3 represents the graph of the equation. On the graph, the *x*-coordinate of the point at which the two graphs intersect is close to 20. In other words $e^3 \approx 20$. A calculator gives a better approximation: $e^3 \approx 20.0855$.





Figure 5.7.3: The graphs of $y = \ln x$ and $y = 3$ cross at the point $(e^3, 3)$, which is approximately $(20.0855, 3)$.

**? Exercise 5.7.11**

Use a graphing calculator to estimate the approximate solution to the logarithmic equation $2^x = 1000$ to 2 decimal places.

**Answer**

$x \approx 9.97$

## Using the One-to-One Property of Logarithms to Solve Logarithmic Equations

As with exponential equations, we can use the one-to-one property to solve logarithmic equations. The one-to-one property of logarithmic functions tells us that, for any real numbers $x > 0$, $S > 0$, $T > 0$ and any positive real number $b$, where $b \neq 1$,

$$\log_b S = \log_b T \text{ if and only if } S = T.$$

For example,

$$\text{If } \log_2(x-1) = \log_2(8), \text{ then } x - 1 = 8.$$

So, if $x - 1 = 8$, then we can solve for $x$,and we get $x = 9$. To check, we can substitute $x = 9$ into the original equation: $\log_2(9-1) = \log_2(8) = 3$ . In other words, when a logarithmic equation has the same base on each side, the arguments must be equal. This also applies when the arguments are algebraic expressions. Therefore, when given an equation with logs of the same base on each side, we can use rules of logarithms to rewrite each side as a single logarithm. Then we use the fact that logarithmic functions are one-to-one to set the arguments equal to one another and solve for the unknown.

For example, consider the equation $\log(3x-2) - \log(2) = \log(x+4)$. To solve this equation, we can use the rules of logarithms to rewrite the left side as a single logarithm, and then apply the one-to-one property to solve for $x$:

$$\begin{aligned}
\log(3x-2) - \log(2) &= \log(x+4) \\
\log\left(\frac{3x-2}{2}\right) &= \log(x+4) && \text{Apply the quotient rule of logarithms} \\
\frac{3x-2}{2} &= x+4 && \text{Apply the one to one property of a logarithm} \\
3x-2 &= 2x+8 && \text{Multiply both sides of the equation by 2} \\
x &= 10 && \text{Subtract 2x and add 2}
\end{aligned}$$

To check the result, substitute $x = 10$ into $\log(3x-2) - \log(2) = \log(x+4)$.

$$\begin{aligned}
\log(3(10)-2) - \log(2) &= \log((10)+4) \\
\log(28) - \log(2) &= \log(14) \\
\log\left(\frac{28}{2}\right) &= \log(14) && \text{The solution checks}
\end{aligned}$$

### USING THE ONE-TO-ONE PROPERTY OF LOGARITHMS TO SOLVE LOGARITHMIC EQUATIONS

For any algebraic expressions $S$ and $T$ and any positive real number $b$, where $b \neq 1$,

$$b^S = b^T \text{ if and only if } S = T \tag{5.7.3}$$

Note, when solving an equation involving logarithms, always check to see if the answer is correct or if it is an extraneous solution.

### How to: Given an equation containing logarithms, solve it using the one-to-one property

1. Use the rules of logarithms to combine like terms, if necessary, so that the resulting equation has the form $\log_b S = \log_b T$.
2. Use the one-to-one property to set the arguments equal.
3. Solve the resulting equation, $S = T$, for the unknown.

### Example 5.7.12: Solving an Equation Using the One-to-One Property of Logarithms

Solve $\ln(x^2) = \ln(2x+3)$.

**Solution**

$$\begin{aligned} \ln(x^2) &= \ln(2x+3) \\ x^2 &= 2x+3 \quad \text{Use the one-to-one property of the logarithm} \\ x^2-2x-3 &= 0 \quad \text{Get zero on one side before factoring} \\ (x-3)(x+1) &= 0 \quad \text{Factor using FOIL} \\ x-3 &= 0 \quad \text{or } x+1=0 \text{ If a product is zero, one of the factors must be zero} \\ x &= 3 \quad \text{or} \\ x &= -11 \quad \text{Solve for x} \end{aligned}$$

**Analysis**

There are two solutions: $3$ or $-1$. The solution $-1$ is negative, but it checks when substituted into the original equation because the argument of the logarithm functions is still positive.

### Exercise 5.7.12

Solve $\ln(x^2) = \ln 1$.

**Answer**

$x = 1$ or $x = -1$

## Solving Applied Problems Using Exponential and Logarithmic Equations

In previous sections, we learned the properties and rules for both exponential and logarithmic functions. We have seen that any exponential function can be written as a logarithmic function and vice versa. We have used exponents to solve logarithmic equations and logarithms to solve exponential equations. We are now ready to combine our skills to solve equations that model real-world situations, whether the unknown is in an exponent or in the argument of a logarithm.

One such application is in science, in calculating the time it takes for half of the unstable material in a sample of a radioactive substance to decay, called its **half-life**. Table 5.7.1 lists the half-life for several of the more common radioactive substances.

Table 5.7.1

| *Substance* | *Use* | *Half-life* |
|---|---|---|
| *gallium-67* | *nuclear medicine* | *80 hours* |
| *cobalt-60* | *manufacturing* | *5.3 years* |

| Substance | Use | Half-life |
|---|---|---|
| *technetium-99m* | *nuclear medicine* | *6 hours* |
| *americium-241* | *construction* | *432 years* |
| *carbon-14* | *archeological dating* | *5,715 years* |
| *uranium-235* | *atomic power* | *703,800,000 years* |

We can see how widely the half-lives for these substances vary. Knowing the half-life of a substance allows us to calculate the amount remaining after a specified time. We can use the formula for radioactive decay:

$$A(t) = A_0 e^{\frac{\ln(0.5)}{T}t} \tag{5.7.4}$$

$$A(t) = A_0 e^{\frac{\ln(0.5)t}{T}} \tag{5.7.5}$$

$$A(t) = A_0 (e^{\ln(0.5)})^{\frac{t}{T}} \tag{5.7.6}$$

$$A(t) = A_0 \left(\frac{1}{2}\right)^{\frac{t}{T}} \tag{5.7.7}$$

where

- $A_0$ is the amount initially present
- $T$ is the half-life of the substance
- $t$ is the time period over which the substance is studied
- $y$ is the amount of the substance present after time $t$

### Example 5.7.13: Using the Formula for Radioactive Decay to Find the Quantity of a Substance

How long will it take for ten percent of a 1000-gram sample of uranium-235 to decay?

**Solution**

$$\begin{aligned}
y &= 1000e^{\frac{\ln(0.5)}{703,800,000}t} \\
900 &= 1000e^{\frac{\ln(0.5)}{703,800,000}t} && \text{After } 10\% \text{ decays, 900 grams are left} \\
0.9 &= e^{\frac{\ln(0.5)}{703,800,000}t} && \text{Divide by 1000} \\
\ln(0.9) &= \ln\left(e^{\frac{\ln(0.5)}{703,800,000}t}\right) && \text{Take ln of both sides} \\
\ln(0.9) &= \frac{\ln(0.5)}{703,800,000}t && \ln(e^M) = M \\
t &= 703,800,000 \times \frac{\ln(0.9)}{\ln(0.5)} && \text{years Solve for t} \\
t &\approx 106,979,777 && \text{years}
\end{aligned}$$

**Analysis**

Ten percent of 1000 grams is 100 grams. If 100 grams decay, the amount of uranium-235 remaining is 900 grams.

### Exercise 5.7.13

How long will it take before twenty percent of our 1000-gram sample of uranium-235 has decayed?

**Answer**

$t = 703,800,000 \times \frac{\ln(0.8)}{\ln(0.5)}$ years ≈ 226,572,993 years.

**Media**

Access these online resources for additional instruction and practice with exponential and logarithmic equations.

- Solving Logarithmic Equations
- Solving Exponential Equations with Logarithms

## Key Equations

| | |
|---|---|
| One-to-one property for exponential functions | For any algebraic expressions $S$ and $T$ and any positive real number $b$, where $b^S = b^T$ if and only if $S = T$. |
| Definition of a logarithm | For any algebraic expression S and positive real numbers $b$ and $c$, where $b \neq 1$, $\log_b(S) = c$ if and only if $b^c = S$. |
| One-to-one property for logarithmic functions | For any algebraic expressions $S$ and $T$ and any positive real number $b$, where $b \neq 1$, $\log_b S = \log_b T$ if and only if $S = T$. |

## Key Concepts

- We can solve many exponential equations by using the rules of exponents to rewrite each side as a power with the same base. Then we use the fact that exponential functions are one-to-one to set the exponents equal to one another and solve for the unknown.
- When we are given an exponential equation where the bases are explicitly shown as being equal, set the exponents equal to one another and solve for the unknown. See Example 5.7.1.
- When we are given an exponential equation where the bases are *not* explicitly shown as being equal, rewrite each side of the equation as powers of the same base, then set the exponents equal to one another and solve for the unknown. See Example 5.7.2, Example 5.7.3, and Example 5.7.4.
- When an exponential equation cannot be rewritten with a common base, solve by taking the logarithm of each side. See Example 5.7.5.
- We can solve exponential equations with base $e$,by applying the natural logarithm of both sides because exponential and logarithmic functions are inverses of each other. See Example 5.7.6 and Example 5.7.7.
- After solving an exponential equation, check each solution in the original equation to find and eliminate any extraneous solutions. See Example 5.7.8.
- When given an equation of the form $\log_b(S) = c$, where $S$ is an algebraic expression, we can use the definition of a logarithm to rewrite the equation as the equivalent exponential equation $b^c = S$, and solve for the unknown. See Example 5.7.9 and Example 5.7.10.
- We can also use graphing to solve equations with the form $\log_b(S) = c$. We graph both equations $y = \log_b(S)$ and $y = c$ on the same coordinate plane and identify the solution as the *x*-value of the intersecting point. See Example 5.7.11.
- When given an equation of the form $\log_b S = \log_b T$, where $S$ and $T$ are algebraic expressions, we can use the one-to-one property of logarithms to solve the equation $S = T$ for the unknown. See Example 5.7.12.
- Combining the skills learned in this and previous sections, we can solve equations that model real world situations, whether the unknown is in an exponent or in the argument of a logarithm. See Example 5.7.13.

This page titled 5.7: Exponential and Logarithmic Equations is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.6: Exponential and Logarithmic Equations** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.7E: Exponential and Logarithmic Equations (Exercises)

38. Solve $216^{3x} \cdot 216^{x} = 36^{3x+2}$ by rewriting each side with a common base.

39. Solve $\frac{125}{\left(\frac{1}{625}\right)^{-x-3}} = 5^{3}$ by rewriting each side with a common base.

40. Use logarithms to find the exact solution for $7 \cdot 17^{-9x} - 7 = 49$. If there is no solution, write no solution.

41. Use logarithms to find the exact solution for $3e^{6n-2} + 1 = -60$. If there is no solution, write no solution.

42. Find the exact solution for $5e^{3x} - 4 = 6$. If there is no solution, write no solution.

43. Find the exact solution for $2e^{5x-2} - 9 = -56$. If there is no solution, write no solution.

44. Find the exact solution for $5^{2x-3} = 7^{x+1}$. If there is no solution, write no solution.

45. Find the exact solution for $e^{2x} - e^{x} - 110 = 0$. If there is no solution, write no solution.

46. Use the definition of a logarithm to solve. $-5\log_{7}(10n) = 5$.

47. Use the definition of a logarithm to find the exact solution for $9 + 6\ln(a+3) = 33$.

48. Use the one-to-one property of logarithms to find an exact solution for $\log_{8}(7) + \log_{8}(-4x) = \log_{8}(5)$. If there is no solution, write *no* solution.

49. Use the one-to-one property of logarithms to find an exact solution for $\ln(5) + \ln\left(5x^{2} - 5\right) = \ln(56)$. If there is no solution, write no solution.

50. The formula for measuring sound intensity in decibels $D$ is defined by the equation $D = 10\log\left(\frac{I}{I_0}\right)$, where $I$ is the intensity of the sound in watts per square meter and $I_0 = 10^{-12}$ is the lowest level of sound that the average person can hear. How many decibels are emitted from a large orchestra with a sound intensity of $6.3 \cdot 10^{-3}$ watts per square meter?

51. The population of a city is modeled by the equation $P(t) = 256,114e^{0.25t}$ where $t$ is measured in years. If the city continues to grow at this rate, how many years will it take for the population to reach one million?

52. Find the inverse function $f^{-1}$ for the exponential function $f(x) = 2 \cdot e^{x+1} - 5$.

53. Find the inverse function $f^{-1}$ for the logarithmic function $f(x) = 0.25 \cdot \log_{2}\left(x^{3} + 1\right)$.

---

This page titled 5.7E: Exponential and Logarithmic Equations (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.6E: Exponential and Logarithmic Equations (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.8: Exponential and Logarithmic Models

**Learning Objectives**

- Model exponential growth and decay.
- Use Newton's Law of Cooling.
- Use logistic-growth models.
- Choose an appropriate model for data.
- Express an exponential model in base $e$.

We have already explored some basic applications of exponential and logarithmic functions. In this section, we explore some important applications in more depth, including radioactive isotopes and Newton's Law of Cooling.




Figure 5.8.1: A nuclear research reactor inside the Neely Nuclear Research Center on the Georgia Institute of Technology campus (credit: Georgia Tech Research Institute)

## Modeling Exponential Growth and Decay

In real-world applications, we need to model the behavior of a function. In mathematical modeling, we choose a familiar general function with properties that suggest that it will model the real-world phenomenon we wish to analyze. In the case of rapid growth, we may choose the exponential growth function:

$$y = A_0 e^{kt} \tag{5.8.1}$$

where $A_0$ is equal to the value at time zero, $e$ is Euler's constant, and $k$ is a positive constant that determines the rate (percentage) of growth. We may use the exponential growth function in applications involving **doubling time**, the time it takes for a quantity to double. Such phenomena as wildlife populations, financial investments, biological samples, and natural resources may exhibit growth based on a doubling time. In some applications, however, as we will see when we discuss the logistic equation, the logistic model sometimes fits the data better than the exponential model.

On the other hand, if a quantity is falling rapidly toward zero, without ever reaching zero, then we should probably choose the **exponential decay** model. Again, we have the form $y = A_0 e^{kt}$ where $A_0$ is the starting value, and $e$ is Euler's constant. Now $k$ is a negative constant that determines the rate of decay. We may use the exponential decay model when we are calculating half-life, or the time it takes for a substance to exponentially decay to half of its original quantity. We use half-life in applications involving radioactive isotopes.

In our choice of a function to serve as a mathematical model, we often use data points gathered by careful observation and measurement to construct points on a graph and hope we can recognize the shape of the graph. Exponential growth and decay graphs have a distinctive shape, as we can see in Figure 5.8.2 and Figure 5.8.3. It is important to remember that, although parts of each of the two graphs seem to lie on the $x$-axis, they are really a tiny distance above the $x$-axis.





Figure 5.8.2: A graph showing exponential growth. The equation is $y = 2e^{3x}$.





Figure 5.8.3: A graph showing exponential decay. The equation is $y = 3e^{-2x}$.

Exponential growth and decay often involve very large or very small numbers. To describe these numbers, we often use orders of magnitude. The **order of magnitude** is the power of ten, when the number is expressed in scientific notation, with one digit to the left of the decimal. For example, the distance to the nearest star, **Proxima Centauri**, measured in kilometers, is $40,113,497,200,000$kilometers. Expressed in scientific notation, this is $4.01134972 \times 1013$ So, we could describe this number as having order of magnitude $1013$.

### $y = a_0 e^{kt}$

An exponential function with the form $y = A_0 e^{kt}$ has the following characteristics:

- one-to-one function
- horizontal asymptote: $y = 0$
- domain: $(-\infty, \infty)$
- range: $(0, \infty)$
- $x$ intercept: none
- $y$-intercept: $(0, A_0)$
- increasing if $k > 0$ (see Figure 5.8.4)
- decreasing if $k < 0$ (see Figure 5.8.4)

Two graphs of y=(A_0)(e^(kt)) with the asymptote at y=0. The first graph is of when k
0 and with the labeled points (1/k, (A_0)e), (0, A_0), and (-1/k, (A_0)/e). The second graph is of when k<0 and with the labeled points (-1/k, (A_0)e), (0, A_0), and (1/k, (A_0)/e)." src="/@api/deki/files/12238/fig_6.8.4.jpg">

Figure 5.8.4: An exponential function models exponential growth when $k > 0$ and exponential decay when $k < 0$.

### Example 5.8.1: Graphing Exponential Growth

A population of bacteria doubles every hour. If the culture started with 10 bacteria, graph the population as a function of time.

**Solution**

When an amount grows at a fixed percent per unit time, the growth is exponential. To find $A_0$ we use the fact that $A_0$ is the amount at time zero, so $A_0 = 10$. To find $k$, use the fact that after one hour $(t = 1)$ the population doubles from 10 to 20.The formula is derived as follows

$$\begin{aligned} 20 &= 10e^{k\cdot 1} \\ 2 &= e^{k} \qquad \text{Divide by 10} \\ \ln 2 &= k \qquad \text{Take the natural logarithm} \end{aligned}$$

so $k = \ln(2)$. Thus the equation we want to graph is $y = 10e^{(\ln 2)t} = 10(e^{\ln 2})^{t} = 10 \cdot 2^{t}$ . The graph is shown in Figure 5.8.5.





Figure 5.8.5: The graph of $y = 10e^{(\ln 2)t}$

**Analysis**

The population of bacteria after ten hours is $10,240$. We could describe this amount is being of the order of magnitude $10^4$. The population of bacteria after twenty hours is $10,485,760$which is of the order of magnitude $10^7$, so we could say that the population has increased by three orders of magnitude in ten hours.

## Half-Life

We now turn to **exponential decay**. One of the common terms associated with exponential decay, as stated above, is **half-life**, the length of time it takes an exponentially decaying quantity to decrease to half its original amount. Every radioactive isotope has a half-life, and the process describing the exponential decay of an isotope is called radioactive decay.

To find the half-life of a function describing exponential decay, solve the following equation:

$$\frac{1}{2}A_0 = A_0 e^{kt}$$

We find that the half-life depends only on the constant $k$ and not on the starting quantity $A_0$.

The formula is derived as follows

$$\begin{aligned}
\frac{1}{2}A_0 &= A_0 e^{kt} \\
\frac{1}{2} &= e^{kt} && \text{Divide by } A_0 \\
\ln\left(\frac{1}{2}\right) &= ktv && \text{Take the natural log} \\
-\ln(2) &= kt && \text{Apply laws of logarithms} \\
-\ln(2)k &= t && \text{Divide by k}
\end{aligned}$$

Since $t$, the time, is positive, $k$ must, as expected, be negative. This gives us the half-life formula

$$t = -\frac{\ln(2)}{k} \tag{5.8.2}$$

**Given the half-life, find the decay rate.**

1. Write $A = A_0 e^{kt}$.
2. Replace $A$ by $\frac{1}{2}A_0$ and replace $t$ by the given half-life.
3. Solve to find $k$. Express $k$ as an exact value (do not round).

Note: It is also possible to find the decay rate using $k = -\ln(2)t$.

**Example 5.8.2: Finding the Function that Describes Radioactive Decay**

The half-life of carbon-14 is $5,730$ years. Express the amount of carbon-14 remaining as a function of time, $t$.

**Solution**

This formula is derived as follows.

$$\begin{aligned}
A &= A_0 e^{kt} && \text{The continuous growth formula} \\
0.5A_0 &= A_0 e^{k\cdot 5730} && \text{Substitute the half-life for t and } 0.5A_0 \text{ for } f(t) \\
0.5 &= e^{5730k} && \text{Divide by } A_0 \\
\ln(0.5) &= 5730k && \text{Take the natural log of both sides} \\
k &= \frac{\ln(0.5)}{5730} && \text{Divide by the coefficient of k} \\
A &= A_0 e^{\left(\frac{\ln(0.5)}{5730}\right)t} && \text{Substitute for r in the continuous growth formula}
\end{aligned}$$

The function that describes this continuous decay is $f(t) = A_0 e^{\left(\frac{\ln(0.5)}{5730}\right)t}$. We observe that the coefficient of $t$, $\frac{\ln(0.5)}{5730} \approx -1.2097 \times 10^{-4}$ is negative, as expected in the case of exponential decay.

**Exercise 5.8.1**

The half-life of plutonium-244 is $80,000,000$ years. Find function gives the amount of carbon-14 remaining as a function of time, measured in years.

**Answer**

$f(t) = A_0 e^{-0.0000000087t}$

## Radiocarbon Dating

The formula for radioactive decay is important in **radiocarbon dating**, which is used to calculate the approximate date a plant or animal died. Radiocarbon dating was discovered in 1949 by Willard Libby, who won a Nobel Prize for his discovery. It compares

the difference between the ratio of two isotopes of carbon in an organic artifact or fossil to the ratio of those two isotopes in the air. It is believed to be accurate to within about $1\%$ error for plants or animals that died within the last $60,000$ years.

Carbon-14 is a radioactive isotope of carbon that has a half-life of $5,730$ years. It occurs in small quantities in the carbon dioxide in the air we breathe. Most of the carbon on Earth is carbon-12, which has an atomic weight of $12$ and is not radioactive. Scientists have determined the ratio of carbon-14 to carbon-12 in the air for the last $60,000$ years, using tree rings and other organic samples of known dates—although the ratio has changed slightly over the centuries.

As long as a plant or animal is alive, the ratio of the two isotopes of carbon in its body is close to the ratio in the atmosphere. When it dies, the carbon-14 in its body decays and is not replaced. By comparing the ratio of carbon-14 to carbon-12 in a decaying sample to the known ratio in the atmosphere, the date the plant or animal died can be approximated.

Since the half-life of carbon-14 is $5,730$ years, the formula for the amount of carbon-14 remaining after $t$ years is

$$A \approx A_0 e^{\left(\frac{\ln(0.5)}{5730}\right)t}$$

where

- $A$ is the amount of carbon-14 remaining
- $A_0$ is the amount of carbon-14 when the plant or animal began decaying.

This formula is derived as follows:

$$\begin{aligned} A &= A_0 e^{kt} && \text{The continuous growth formula} \\ 0.5A_0 &= A_0 e^{k \cdot 5730} && \text{Substitute the half-life for t and } 0.5A_0 \text{ for f(t)} \\ 0.5 &= e^{5730k} && \text{Divide by } A_0 \\ \ln(0.5) &= 5730k && \text{Take the natural log of both sides} \\ k &= \frac{\ln(0.5)}{5730} && \text{Divide by the coefficient of k} \\ A &= A_0 e^{\left(\frac{\ln(0.5)}{5730}\right)t} && \text{Substitute for r in the continuous growth formula} \end{aligned}$$

To find the age of an object, we solve this equation for $t$:

$$t = \frac{\ln\left(\frac{A}{A_0}\right)}{-0.000121}$$

Out of necessity, we neglect here the many details that a scientist takes into consideration when doing carbon-14 dating, and we only look at the basic formula. The ratio of carbon-14 to carbon-12 in the atmosphere is approximately $0.0000000001$ Let $r$ be the ratio of carbon-14 to carbon-12 in the organic artifact or fossil to be dated, determined by a method called liquid scintillation. From the equation $A \approx A_0 e^{-0.000121t}$ we know the ratio of the percentage of carbon-14 in the object we are dating to the percentage of carbon-14 in the atmosphere is $r = \frac{A}{A_0} \approx e^{-0.000121t}$. We solve this equation for $t$, to get

$$t = \frac{\ln(r)}{-0.000121}$$

1. Express the given percentage of carbon-14 as an equivalent decimal, $k$.
2. Substitute for $k$ in the equation $t = \frac{\ln(r)}{-0.000121}$ and solve for the age, $t$.

### Example 5.8.3: Finding the Age of a Bone

A bone fragment is found that contains $20\%$ of its original carbon-14. To the nearest year, how old is the bone?

**Solution**

We substitute $20\% = 0.20$ for $k$ in the equation and solve for $t$:

$$\begin{aligned} t &= \frac{\ln(r)}{-0.000121} && \text{Use the general form of the equation} \\ &= \frac{\ln(0.20)}{-0.000121} && \text{Substitute for r} \\ &\approx 13301 && \text{Round to the nearest year} \end{aligned}$$

The bone fragment is about $13,301$ years old.

**Analysis**

The instruments that measure the percentage of carbon-14 are extremely sensitive and, as we mention above, a scientist will need to do much more work than we did in order to be satisfied. Even so, carbon dating is only accurate to about $1\%$, so this age should be given as $13,301$ years $\pm 1\%$ or $13,301$ years $\pm 133$ years.

**? Exercise 5.8.2**

Cesium-137 has a half-life of about 30 years. If we begin with 200 mg of cesium-137, will it take more or less than 230 years until only 1 milligram remains?

**Answer**

less than 230 years, 229.3157 to be exact

### Calculating Doubling Time

For decaying quantities, we determined how long it took for half of a substance to decay. For growing quantities, we might want to find out how long it takes for a quantity to double. As we mentioned above, the time it takes for a quantity to double is called the **doubling time**.

Given the basic **exponential growth** equation $A = A_0 e^{kt}$, doubling time can be found by solving for when the original quantity has doubled, that is, by solving $2A_0 = A_0 e^{kt}$.

The formula is derived as follows:

$$\begin{aligned} 2A_0 &= A_0 e^{kt} \\ 2 &= e^{kt} && \text{Divide by } A_0 \\ \ln 2 &= kt && \text{Take the natural logarithm} \\ t &= \frac{\ln 2}{k} && \text{Divide by the coefficient of t} \end{aligned}$$

Thus the doubling time is

$$t = \frac{\ln 2}{k} \tag{5.8.3}$$

**✓ Example 5.8.4: Finding a Function That Describes Exponential Growth**

According to Moore's Law, the doubling time for the number of transistors that can be put on a computer chip is approximately two years. Give a function that describes this behavior.

**Solution**

The formula is derived as follows:

$$\begin{aligned} t &= \frac{\ln 2}{k} && \text{The doubling time formula} \\ 2 &= \frac{\ln 2}{k} && \text{Use a doubling time of two years} \\ k &= \frac{\ln 2}{2} && \text{Multiply by k and divide by 2} \\ A &= A_0 e^{\frac{\ln 2}{2} t} && \text{Substitute k into the continuous growth formula} \end{aligned}$$

The function is $A = A_0 e^{\frac{\ln 2}{2} t}$.

**Exercise 5.8.3**

Recent data suggests that, as of 2013, the rate of growth predicted by Moore's Law no longer holds. Growth has slowed to a doubling time of approximately three years. Find the new function that takes that longer doubling time into account.

**Answer**

$f(t) = A_0 e^{\frac{\ln 2}{3} t}$

## Using Newton's Law of Cooling

Exponential decay can also be applied to temperature. When a hot object is left in surrounding air that is at a lower temperature, the object's temperature will decrease exponentially, leveling off as it approaches the surrounding air temperature. On a graph of the temperature function, the leveling off will correspond to a horizontal asymptote at the temperature of the surrounding air. Unless the room temperature is zero, this will correspond to a **vertical shift** of the generic **exponential decay** function. This translation leads to **Newton's Law of Cooling**, the scientific formula for temperature as a function of time as an object's temperature is equalized with the ambient temperature

$$T(t) = ae^{kt} + T_s$$

This formula is derived as follows:

$$\begin{aligned} T(t) &= Ab^{ct} + T_s \\ T(t) &= Ae^{\ln(b^{ct})} + T_s && \text{Laws of logarithms} \\ T(t) &= Ae^{ct \ln b} + T_s && \text{Laws of logarithms} \\ T(t) &= Ae^{kt} + T_s && \text{Rename the constant c } lnb\text{, calling it } k \end{aligned}$$

**NEWTON'S LAW OF COOLING**

The temperature of an object, $T$, in surrounding air with temperature $T_s$ will behave according to the formula

$$T(t) = Ae^{kt} + T_s \tag{5.8.4}$$

where

- $t$ is time
- $A$ is the difference between the initial temperature of the object and the surroundings
- $k$ is a constant, the continuous rate of cooling of the object

**Given a set of conditions, apply Newton's Law of Cooling.**

1. Set $T_s$ equal to the $y$-coordinate of the horizontal asymptote (usually the ambient temperature).
2. Substitute the given values into the continuous growth formula $T(t) = Ae^{kt} + T_s$ to find the parameters $A$ and $k$.
3. Substitute in the desired time to find the temperature or the desired temperature to find the time.

**Example 5.8.5: Using Newton's Law of Cooling**

A cheesecake is taken out of the oven with an ideal internal temperature of $165^\circ F$, and is placed into a $35^\circ F$ refrigerator. After 10 minutes, the cheesecake has cooled to $150^\circ F$. If we must wait until the cheesecake has cooled to $70^\circ F$ before we eat it, how long will we have to wait?

**Solution**

Because the surrounding air temperature in the refrigerator is 35 degrees, the cheesecake's temperature will decay exponentially toward 35, following the equation

$$T(t) = Ae^{kt} + 35$$

We know the initial temperature was 165, so $T(0) = 165$.

$$\begin{aligned} 165 &= Ae^{k0} + 35 && \text{Substitute } (0, 165) \\ A &= 130 && \text{Solve for A} \end{aligned}$$

We were given another data point, $T(10) = 150$, which we can use to solve for $k$.

$$\begin{aligned} 150 &= 130e^{k10} + 35 && \text{Substitute } (10, 150) \\ 115 &= 130e^{k10} && \text{Subtract 35} \\ \frac{115}{130} &= e^{10k} && \text{Divide by 130} \\ \ln\left(\frac{115}{130}\right) &= 10k && \text{Take the natural log of both sides} \\ k &= \frac{\ln\left(\frac{115}{130}\right)}{10} \\ &= -0.0123 && \text{Divide by the coefficient of k} \end{aligned}$$

This gives us the equation for the cooling of the cheesecake: $T(t) = 130e^{-0.0123t} + 35$.

Now we can solve for the time it will take for the temperature to cool to 70 degrees.

$$\begin{aligned} 70 &= 130e^{-0.0123t} + 35 && \text{Substitute in 70 for } T(t) \\ 35 &= 130e^{-0.0123t} && \text{Subtract 35} \\ \frac{35}{130} &= e^{-0.0123t} && \text{Divide by 130} \\ \ln\left(\frac{35}{130}\right) &= -0.0123t && \text{Take the natural log of both sides} \\ t &= \frac{\ln\left(\frac{35}{130}\right)}{-0.0123} \\ &\approx 106.68 && \text{Divide by the coefficient of t} \end{aligned}$$

It will take about 107 minutes, or one hour and 47 minutes, for the cheesecake to cool to $70^\circ F$.

**? Exercise 5.8.4**

A pitcher of water at 40 degrees Fahrenheit is placed into a 70 degree room. One hour later, the temperature has risen to 45 degrees. How long will it take for the temperature to rise to 60 degrees?

**Answer**

6.026hours

## Using Logistic Growth Models

Exponential growth cannot continue forever. Exponential models, while they may be useful in the short term, tend to fall apart the longer they continue. Consider an aspiring writer who writes a single line on day one and plans to double the number of lines she writes each day for a month. By the end of the month, she must write over 17 billion lines, or one-half-billion pages. It is impractical, if not impossible, for anyone to write that much in such a short period of time. Eventually, an exponential model must begin to approach some limiting value, and then the growth is forced to slow. For this reason, it is often better to use a model with an upper bound instead of an exponential growth model, though the **exponential growth** model is still useful over a short term, before approaching the limiting value.

The **logistic growth model** is approximately exponential at first, but it has a reduced rate of growth as the output approaches the model's upper bound, called the **carrying capacity**. For constants $a$, $b$, and $c$, the logistic growth of a population over time $x$ is

represented by the model

$$f(x) = \frac{c}{1 + ae^{-bx}}$$

The graph in Figure 5.8.6 shows how the growth rate changes over time. The graph increases from left to right, but the growth rate only increases until it reaches its point of maximum growth rate, at which point the rate of increase decreases.





Figure 5.8.6

## LOGISTIC GROWTH

The logistic growth model is

$$f(x) = \frac{c}{1 + ae^{-bx}} \tag{5.8.5}$$

where

- $\frac{c}{1+a}$ is the initial value
- $c$ is the *carrying capacity*, or *limiting value*
- $b$ is a constant determined by the rate of growth.

## Example 5.8.6: Using the Logistic-Growth Model

An influenza epidemic spreads through a population rapidly, at a rate that depends on two factors: The more people who have the flu, the more rapidly it spreads, and also the more uninfected people there are, the more rapidly it spreads. These two factors make the logistic model a good one to study the spread of communicable diseases. And, clearly, there is a maximum value for the number of people infected: the entire population.

For example, at time $t = 0$ there is one person in a community of $1,000$ people who has the flu. So, in that community, at most $1,000$ people can have the flu. Researchers find that for this particular strain of the flu, the logistic growth constant is $b = 0.6030$. Estimate the number of people in this community who will have had this flu after ten days. Predict how many people in this community will have had this flu after a long period of time has passed.

### Solution

We substitute the given data into the logistic growth model

$$f(x) = \frac{c}{1 + ae^{-bx}}$$

Because at most $1,000$ people, the entire population of the community, can get the flu, we know the limiting value is $c = 1000$. To find $a$,we use the formula that the number of cases at time $t = 0$ is $\frac{c}{1+a} = 1$, from which it follows that $a = 999$.This model predicts that, after ten days, the number of people who have had the flu is

$f(x) = \dfrac{1000}{1 + 999e^{-0.6030x}} \approx 293.8$. Because the actual number must be a whole number (a person has either had the flu or not) we round to $294$. In the long term, the number of people who will contract the flu is the limiting value, $c = 1000$.

**Analysis**

Remember that, because we are dealing with a virus, we cannot predict with certainty the number of people infected. The model only approximates the number of people infected and will not give us exact or actual values.

The graph in Figure $5.8.7$ gives a good picture of how this model fits the data.





Figure $5.8.7$: The graph of $f(x) = \dfrac{1000}{1 + 999e^{-0.6030x}}$

**? Exercise $5.8.5$**

Using the model in the Example above, estimate the number of cases of flu on day $15$.

**Answer**

$895$ cases on day $15$

## Choosing an Appropriate Model for Data

Now that we have discussed various mathematical models, we need to learn how to choose the appropriate model for the raw data we have. Many factors influence the choice of a mathematical model, among which are experience, scientific laws, and patterns in the data itself. Not all data can be described by elementary functions. Sometimes, a function is chosen that approximates the data over a given interval. For instance, suppose data were gathered on the number of homes bought in the United States from the years 1960 to 2013. After plotting these data in a scatter plot, we notice that the shape of the data from the years 2000 to 2013 follow a logarithmic curve. We could restrict the interval from 2000 to 2010, apply regression analysis using a logarithmic model, and use it to predict the number of home buyers for the year 2015.

Three kinds of functions that are often useful in mathematical models are linear functions, exponential functions, and logarithmic functions. If the data lies on a straight line, or seems to lie approximately along a straight line, a linear model may be best. If the data is non-linear, we often consider an exponential or logarithmic model, though other models, such as quadratic models, may also be considered.

In choosing between an exponential model and a logarithmic model, we look at the way the data curves. This is called the concavity. If we draw a line between two data points, and all (or most) of the data between those two points lies above that line, we say the curve is concave down. We can think of it as a bowl that bends downward and therefore cannot hold water. If all (or most)

of the data between those two points lies below the line, we say the curve is concave up. In this case, we can think of a bowl that bends upward and can therefore hold water. An exponential curve, whether rising or falling, whether representing growth or decay, is always concave up away from its horizontal asymptote. A logarithmic curve is always concave away from its vertical asymptote. In the case of positive data, which is the most common case, an exponential curve is always concave up, and a logarithmic curve always concave down.

A logistic curve changes concavity. It starts out concave up and then changes to concave down beyond a certain point, called a point of inflection.

After using the graph to help us choose a type of function to use as a model, we substitute points, and solve to find the parameters. We reduce round-off error by choosing points as far apart as possible.

### Example 5.8.7: Choosing a Mathematical Model

Does a linear, exponential, logarithmic, or logistic model best fit the values listed in Table 5.8.1? Find the model, and use a graph to check your choice.

Table 5.8.1

| $x$ | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
|---|---|---|---|---|---|---|---|---|---|
| $y$ | 0 | 1.386 | 2.197 | 2.773 | 3.219 | 3.584 | 3.892 | 4.159 | 4.394 |

**Solution**

First, plot the data on a graph as in Figure 5.8.8. For the purpose of graphing, round the data to two significant digits.





Figure 5.8.8

Clearly, the points do not lie on a straight line, so we reject a linear model. If we draw a line between any two of the points, most or all of the points between those two points lie above the line, so the graph is concave down, suggesting a logarithmic model. We can try $y = a\ln(bx)$. Plugging in the first point, $(1, 0)$, gives $0 = a\ln b$. We reject the case that $a = 0$ (if it were, all outputs would be 0), so we know $\ln(b) = 0$. Thus $b = 1$ and $y = a\ln(x)$. Next we can use the point $(9, 4.394)$ to solve for $a$:

$$\begin{aligned} y &= a\ln(x) \\ 4.394 &= a\ln(9) \\ a &= \frac{4.394}{\ln(9)} \end{aligned}$$

Because $a = \dfrac{4.394}{\ln(9)} \approx 2$ ,an appropriate model for the data is $y = 2\ln(x)$.

To check the accuracy of the model, we graph the function together with the given points as in Figure 5.8.9.





Figure 5.8.9: The graph of $y = 2 \ln x$.

We can conclude that the model is a good fit to the data.

Compare Figure 5.8.9 to the graph of $y = \ln(x^2)$ shown in Figure 5.8.10.





Figure 5.8.10: The graph of $y = \ln(x^2)$

The graphs appear to be identical when $x > 0$. A quick check confirms this conclusion: $y = \ln(x^2) = 2 \ln(x)$ for $x > 0$.

However, if $x < 0$, the graph of $y = \ln(x^2)$ includes a "extra" branch, as shown in Figure 5.8.11. This occurs because, while $y = 2 \ln(x)$ cannot have negative values in the domain (as such values would force the argument to be negative), the function $y = \ln(x^2)$ can have negative domain values.





Figure 5.8.11

**Exercise 5.8.6**

Does a linear, exponential, or logarithmic model best fit the data in Table 5.8.2? Find the model.

Table 5.8.2

| $x$ | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 |
|---|---|---|---|---|---|---|---|---|---|
| $y$ | 3.297 | 5.437 | 8.963 | 14.778 | 24.365 | 40.172 | 66.231 | 109.196 | 180.034 |

**Answer**

Exponential $y = 2e^{0.5x}$.

## Expressing an Exponential Model in Base $e$

While powers and logarithms of any base can be used in modeling, the two most common bases are 10 and $e$. In science and mathematics, the base $e$ is often preferred. We can use laws of exponents and laws of logarithms to change any base to base $e$.

**Given a model with the form $y = ab^x$, change it to the form $y = A_0e^{kx}$.**

1. Rewrite $y = ab^x$ as $y = ae^{\ln(b^x)}$.
2. Use the power rule of logarithms to rewrite $y$ as $y = ae^{x\ln(b)} = ae^{\ln(b)^x}$.
3. Note that $a = A_0$ and $k = \ln(b)$ in the equation $y = A_0e^{kx}$.

**Example 5.8.8: Changing to base $e$**

Change the function $y = 2.5(3.1)^x$ so that this same function is written in the form $y = A_0e^{kx}$.

**Solution**

The formula is derived as follows

$$\begin{aligned} y &= 2.5(3.1)^x \\ &= 2.5e^{\ln(3.1^x)} && \text{Insert exponential and its inverse} \\ &= 2.5e^{x\ln 3.1} && \text{Laws of logs} \\ &= 2.5e^{(\ln 3.1)x} && \text{Commutative law of multiplication} \end{aligned}$$

**Exercise 5.8.7**

Change the function $y = 3(0.5)^x$ to one having $e$ as the base.

**Answer**

$y = 3e^{(\ln 0.5)x}$

## Media

Access these online resources for additional instruction and practice with exponential and logarithmic models.

- Logarithm Application – pH
- Exponential Model – Age Using Half-Life
- Newton's Law of Cooling
- Exponential Growth Given Doubling Time
- Exponential Growth – Find Initial Amount Given Doubling Time

## Key Equations

| | |
|---|---|
| Half-life formula | If $A = A_0 e^{kt}$, $k < 0$, the half-life is $t = -\frac{\ln(2)}{k}$. |
| Carbon-14 dating | $t = \frac{\ln(\frac{A}{A_0})}{-0.000121}$.<br>$A_0$ $A$ is the amount of carbon-14 when the plant or animal died<br>$t$ is the amount of carbon-14 remaining today<br>is the age of the fossil in years |
| Doubling time formula | If $A = A_0 e^{kt}$, $k > 0$, the doubling time is $t = \frac{\ln 2}{k}$ |
| Newton's Law of Cooling | $T(t) = Ae^{kt} + T_s$ , where $T_s$ is the ambient temperature, $A = T(0) - T_s$ , and $k$ is the continuous rate of cooling. |

## Key Concepts

- The basic exponential function is $f(x) = ab^x$. If $b > 1$,we have exponential growth; if $0 < b < 1$, we have exponential decay.
- We can also write this formula in terms of continuous growth as $A = A_0 e^{kx}$, where $A_0$ is the starting value. If $A_0$ is positive, then we have exponential growth when $k > 0$ and exponential decay when $k < 0$. See Example 5.8.1.
- In general, we solve problems involving exponential growth or decay in two steps. First, we set up a model and use the model to find the parameters. Then we use the formula with these parameters to predict growth and decay. See Example 5.8.2.
- We can find the age, $t$, of an organic artifact by measuring the amount, $k$, of carbon-14 remaining in the artifact and using the formula $t = \frac{\ln(k)}{-0.000121}$ to solve for $t$. See Example 5.8.3.
- Given a substance's doubling time or half-time, we can find a function that represents its exponential growth or decay. See Example 5.8.4.
- We can use Newton's Law of Cooling to find how long it will take for a cooling object to reach a desired temperature, or to find what temperature an object will be after a given time. See Example 5.8.5.
- We can use logistic growth functions to model real-world situations where the rate of growth changes over time, such as population growth, spread of disease, and spread of rumors. See Example 5.8.6.
- We can use real-world data gathered over time to observe trends. Knowledge of linear, exponential, logarithmic, and logistic graphs help us to develop models that best fit our data. See Example 5.8.7.
- Any exponential function with the form $y = abx$ can be rewritten as an equivalent exponential function with the form $y = A_0 e^{kx}$ where $k = \ln b$. See Example 5.8.8.

This page titled 5.8: Exponential and Logarithmic Models is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.7: Exponential and Logarithmic Models** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.8E: Exponential and Logarithmic Models (Exercises)

For the following exercises, use this scenario: A doctor prescribes 300 milligrams of a therapeutic drug that decays by about $17\%$ each hour.

54. To the nearest minute, what is the half-life of the drug?

55. Write an exponential model representing the amount of the drug remaining in the patient's system after $t$ hours. Then use the formula to find the amount of the drug that would remain in the patient's system after 24 hours. Round to the nearest hundredth of a gram.

For the following exercises, use this scenario: A soup with an internal temperature of $350^{\circ}$ Fahrenheit was taken off the stove to cool in a $71^{\circ}\mathrm{F}$ room. After fifteen minutes, the internal temperature of the soup was $175^{\circ}\mathrm{F}$.\

56. Use Newton's Law of Cooling to write a formula that models this situation.

57. How many minutes will it take the soup to cool to $85^{\circ}\mathrm{F}$?

For the following exercises, use this scenario: The equation $N(t)=\frac{1200}{1+199e^{-0.625t}}$ models the number of people in a school who have heard a rumor after $t$ days.

58. How many people started the rumor?

59. To the nearest tenth, how many days will it be before the rumor spreads to half the carrying capacity?

60. What is the carrying capacity?

For the following exercises, enter the data from each table into a graphing calculator and graph the resulting scatter plots. Determine whether the data from the table would likely represent a function that is linear, exponential, or logarithmic.

**61**.

| *x* | *f(x)* |
|---|---|
| 1 | 3.05 |
| 2 | 4.42 |
| 3 | 6.4 |
| 4 | 9.28 |
| 5 | 13.46 |
| 6 | 19.52 |
| 7 | 28.3 |
| 8 | 41.04 |
| 9 | 59.5 |
| 10 | 86.28 |

**62**.

| *x* | *f(x)* |
|---|---|
| 0.5 | 18.05 |
| 1 | 17 |
| 3 | 15.33 |
| 5 | 14.55 |
| 7 | 14.04 |

| *x* | *f(x)* |
|---|---|
| 10 | 13.5 |
| 12 | 13.22 |
| 13 | 13.1 |
| 15 | 12.88 |
| 17 | 12.69 |
| 20 | 12.45 |

63. Find a formula for an exponential equation that goes through the points (-2,100) and (0,4). Then express the formula as an equivalent equation with base $e$.

---

This page titled 5.8E: Exponential and Logarithmic Models (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.7E: Exponential and Logarithmic Models (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.9: Fitting Exponential Models to Data

**Learning Objectives**

- Build an exponential model from data.
- Build a logarithmic model from data.
- Build a logistic model from data.

In previous sections of this chapter, we were either given a function explicitly to graph or evaluate, or we were given a set of points that were guaranteed to lie on the curve. Then we used algebra to find the equation that fit the points exactly. In this section, we use a modeling technique called *regression analysis* to find a curve that models data collected from real-world observations. With regression analysis, we don't expect all the points to lie perfectly on the curve. The idea is to find a model that best fits the data. Then we use the model to make predictions about future events.

Do not be confused by the word *model*. In mathematics, we often use the terms *function*, *equation*, and *model* interchangeably, even though they each have their own formal definition. The term *model* is typically used to indicate that the equation or function approximates a real-world situation.

We will concentrate on three types of regression models in this section: exponential, logarithmic, and logistic. Having already worked with each of these functions gives us an advantage. Knowing their formal definitions, the behavior of their graphs, and some of their real-world applications gives us the opportunity to deepen our understanding. As each regression model is presented, key features and definitions of its associated function are included for review. Take a moment to rethink each of these functions, reflect on the work we've done so far, and then explore the ways regression is used to model real-world phenomena.

## Building an Exponential Model from Data

As we've learned, there are a multitude of situations that can be modeled by exponential functions, such as investment growth, radioactive decay, atmospheric pressure changes, and temperatures of a cooling object. What do these phenomena have in common? For one thing, all the models either increase or decrease as time moves forward. But that's not the whole story. It's the *way* data increase or decrease that helps us determine whether it is best modeled by an exponential equation. Knowing the behavior of exponential functions in general allows us to recognize when to use exponential regression, so let's review exponential growth and decay.

Recall that exponential functions have the form $y = ab^x$ or $y = A_0e^{kx}$. When performing regression analysis, we use the form most commonly used on graphing utilities, $y = ab^x$. Take a moment to reflect on the characteristics we've already learned about the exponential function $y = ab^x$ (assume $a > 0$):

- $b$ must be greater than zero and not equal to one.
- The initial value of the model is $y = a$.
  - If $b > 1$, the function models exponential growth. As $x$ increases, the outputs of the model increase slowly at first, but then increase more and more rapidly, without bound.
  - If $0 < b < 1$, the function models **exponential decay**. As $x$ increases, the outputs for the model decrease rapidly at first and then level off to become asymptotic to the *x*-axis. In other words, the outputs never become equal to or less than zero.

As part of the results, your calculator will display a number known as the *correlation coefficient*, labeled by the variable $r$, or $r^2$. (You may have to change the calculator's settings for these to be shown.) The values are an indication of the "goodness of fit" of the regression equation to the data. We more commonly use the value of $r^2$ instead of $r$, but the closer either value is to 1, the better the regression equation approximates the data.

**EXPONENTIAL REGRESSION**

*Exponential regression* is used to model situations in which growth begins slowly and then accelerates rapidly without bound, or where decay begins rapidly and then slows down to get closer and closer to zero. We use the command "ExpReg" on a graphing utility to fit an exponential function to a set of data points. This returns an equation of the form,

$$y = ab^x \tag{5.9.1}$$

Note that:

- $b$ must be non-negative.
- when $b > 1$, we have an exponential growth model.
- when $0 < b < 1$, we have an exponential decay model.

**How to: Given a set of data, perform exponential regression using a graphing utility**

1. Use the STAT then EDIT menu to enter given data.
   i. Clear any existing data from the lists.
   ii. List the input values in the L1 column.
   iii. List the output values in the L2 column.
2. Graph and observe a scatter plot of the data using the STATPLOT feature.
   i. Use ZOOM [9] to adjust axes to fit the data.
   ii. Verify the data follow an exponential pattern.
3. Find the equation that models the data.
   i. Select "ExpReg" from the STAT then CALC menu.
   ii. Use the values returned for $a$ and $b$ to record the model, $y = ab^x$.
4. Graph the model in the same window as the scatterplot to verify it is a good fit for the data.

In 2007, a university study was published investigating the crash risk of alcohol impaired driving. Data from $2,871$ crashes were used to measure the association of a person's blood alcohol level (BAC) with the risk of being in an accident. Table $5.9.1$ shows results from the study. The *relative risk* is a measure of how many times more likely a person is to crash. So, for example, a person with a BAC of $0.09$ is $3.54$ times as likely to crash as a person who has not been drinking alcohol.

Table 5.9.1

| BAC | 0 | 0.01 | 0.03 | 0.05 | 0.07 | 0.09 |
|---|---|---|---|---|---|---|
| Relative Risk of Crashing | 1 | 1.03 | 1.06 | 1.38 | 2.09 | 3.54 |
| BAC | 0.11 | 0.13 | 0.15 | 0.17 | 0.19 | 0.21 |
| Relative Risk of Crashing | 6.41 | 12.6 | 22.1 | 39.05 | 65.32 | 99.78 |

a. Let $x$ represent the BAC level, and let $y$ represent the corresponding relative risk. Use exponential regression to fit a model to these data.
b. After $6$ drinks, a person weighing $160$ pounds will have a BAC of about $0.16$. How many times more likely is a person with this weight to crash if they drive after having a $6$-pack of beer? Round to the nearest hundredth.

**Solution**

a. Using the STAT then EDIT menu on a graphing utility, list the BAC values in L1 and the relative risk values in L2. Then use the STATPLOT feature to verify that the scatterplot follows the exponential pattern shown in Figure $5.9.1$:




Figure 5.9.1

Use the "ExpReg" command from the STAT then CALC menu to obtain the exponential model,

$$y = 0.58304829(2.20720213E10)^x$$

Converting from scientific notation, we have:

$$y = 0.58304829(22,072,021,300)^x$$

Notice that $r^2 \approx 0.97$ which indicates the model is a good fit to the data. To see this, graph the model in the same window as the scatterplot to verify it is a good fit as shown in Figure 5.9.2:




Figure 5.9.2

b. Use the model to estimate the risk associated with a BAC of $0.16$. Substitute $0.16$ for $x$ in the model and solve for $y$.

$$\begin{aligned} y &= 0.58304829(22,072,021,300)^x && \text{Use the regression model found in part } (a) \\ &= 0.58304829(22,072,021,300)^{0.16} && \text{Substitute } 0.16 \text{ for x} \\ &\approx 26.35 && \text{Round to the nearest hundredth} \end{aligned}$$

If a $160$-pound person drives after having $6$ drinks, he or she is about $26.35$ times more likely to crash than if driving while sober.

## Exercise 5.9.1

Table 5.9.2 shows a recent graduate's credit card balance each month after graduation.

Table 5.9.2

| Month | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 |
|---|---|---|---|---|---|---|---|---|
| Debt ($) | 620.00 | 761.88 | 899.80 | 1039.93 | 1270.63 | 1589.04 | 1851.31 | 2154.92 |

a. Use exponential regression to fit a model to these data.
b. If spending continues at this rate, what will the graduate's credit card debt be one year after graduating?

**Answer a**

The exponential regression model that fits these data is $y = 522.88585984(1.19645256)^x$

**Answer b**

If spending continues at this rate, the graduate's credit card debt will be $\$4,499.38$ after one year.

### Q&A: Is it reasonable to assume that an exponential regression model will represent a situation indefinitely?

*No. Remember that models are formed by real-world data gathered for regression. It is usually reasonable to make estimates within the interval of original observation (interpolation). However, when a model is used to make predictions, it is important to use reasoning skills to determine whether the model makes sense for inputs far beyond the original observation interval (extrapolation).*

## Building a Logarithmic Model from Data

Just as with exponential functions, there are many real-world applications for logarithmic functions: intensity of sound, pH levels of solutions, yields of chemical reactions, production of goods, and growth of infants. As with exponential models, data modeled by logarithmic functions are either always increasing or always decreasing as time moves forward. Again, it is the *way* they increase or decrease that helps us determine whether a **logarithmic model** is best.

Recall that logarithmic functions increase or decrease rapidly at first, but then steadily slow as time moves on. By reflecting on the characteristics we've already learned about this function, we can better analyze real world situations that reflect this type of growth or decay. When performing logarithmic **regression analysis**, we use the form of the logarithmic function most commonly used on graphing utilities, $y = a + b\ln(x)$ . For this function

- All input values, $x$,must be greater than zero.
- The point $(1, a)$ is on the graph of the model.
- If $b > 0$,the model is increasing. Growth increases rapidly at first and then steadily slows over time.
- If $b < 0$,the model is decreasing. Decay occurs rapidly at first and then steadily slows over time.

### LOGARITHMIC REGRESSION

*Logarithmic regression* is used to model situations where growth or decay accelerates rapidly at first and then slows over time. We use the command "LnReg" on a graphing utility to fit a logarithmic function to a set of data points. This returns an equation of the form,

$$y = a + b\ln(x) \tag{5.9.2}$$

Note that

- all input values, $x$,must be non-negative.
- when $b > 0$, the model is increasing.
- when $b < 0$, the model is decreasing.

**How to: Given a set of data, perform logarithmic regression using a graphing utility**

1. Use the STAT then EDIT menu to enter given data.
   i. Clear any existing data from the lists.
   ii. List the input values in the L1 column.
   iii. List the output values in the L2 column.
2. Graph and observe a scatter plot of the data using the STATPLOT feature.
   i. Use ZOOM [9] to adjust axes to fit the data.
   ii. Verify the data follow a logarithmic pattern.
3. Find the equation that models the data.
   i. Select "LnReg" from the STAT then CALC menu.
   ii. Use the values returned for $a$ and $b$ to record the model, $y = a + b\ln(x)$.
4. Graph the model in the same window as the scatterplot to verify it is a good fit for the data.

**Example 5.9.2: Using Logarithmic Regression to Fit a Model to Data**

Due to advances in medicine and higher standards of living, life expectancy has been increasing in most developed countries since the beginning of the 20th century. Table 5.9.3 shows the average life expectancies, in years, of Americans from 1900–2010.

**Table 5.9.3**

| Year | 1900 | 1910 | 1920 | 1930 | 1940 | 1950 |
|---|---|---|---|---|---|---|
| Life Expectancy(Years) | 47.3 | 50.0 | 54.1 | 59.7 | 62.9 | 68.2 |
| Year | 1960 | 1970 | 1980 | 1990 | 2000 | 2010 |
| Life Expectancy(Years) | 69.7 | 70.8 | 73.7 | 75.4 | 76.8 | 78.7 |

a. Let $x$ represent time in decades starting with $x = 1$ for the year 1900, $x = 2$ for the year 1910, and so on. Let $y$ represent the corresponding life expectancy. Use logarithmic regression to fit a model to these data.
b. Use the model to predict the average American life expectancy for the year 2030.

**Solution**

a. Using the STAT then EDIT menu on a graphing utility, list the years using values $1-12$ in L1 and the corresponding life expectancy in L2. Then use the STATPLOT feature to verify that the scatterplot follows a logarithmic pattern as shown in Figure 5.9.3:





Figure 5.9.3

Use the "LnReg" command from the STAT then CALC menu to obtain the logarithmic model,

$$y = 42.52722583 + 13.85752327 \ln(x)$$

Next, graph the model in the same window as the scatterplot to verify it is a good fit as shown in Figure 5.9.4:





Figure 5.9.4

b. To predict the life expectancy of an American in the year 2030, substitute $x = 14$ for the in the model and solve for $y$:

$$\begin{aligned} y &= 42.52722583 + 13.85752327 \ln(x) && \text{Use the regression model found in part } (a) \\ &= 42.52722583 + 13.85752327 \ln(14) && \text{Substitute 14 for x} \\ &\approx 79.1 && \text{Round to the nearest tenth} \end{aligned}$$

If life expectancy continues to increase at this pace, the average life expectancy of an American will be 79.1 by the year 2030.

## ? Exercise 5.9.2

Sales of a video game released in the year 2000 took off at first, but then steadily slowed as time moved on. Table 5.9.4 shows the number of games sold, in thousands, from the years 2000–2010.

Table 5.9.4

| Year | 2000 | 2001 | 2002 | 2003 | 2004 | 2005 |
|---|---|---|---|---|---|---|

| | | | | | | |
|---|---|---|---|---|---|---|
| Number Sold (thousands) | 142 | 149 | 154 | 155 | 159 | 161 |
| Year | 2006 | 2007 | 2008 | 2009 | 2010 | - |
| Number Sold (thousands) | 163 | 164 | 164 | 166 | 167 | - |

Let $x$ represent time in years starting with $x = 1$ for the year 2000. Let $y$ represent the number of games sold in thousands.

a. Use logarithmic regression to fit a model to these data.
b. If games continue to sell at this rate, how many games will sell in 2015? Round to the nearest thousand.

**Answer a**

The logarithmic regression model that fits these data is $y = 141.91242949 + 10.45366573 \ln(x)$

**Answer b**

If sales continue at this rate, about $171,000$games will be sold in the year $2015$

## Building a Logistic Model from Data

Like exponential and logarithmic growth, logistic growth increases over time. One of the most notable differences with logistic growth models is that, at a certain point, growth steadily slows and the function approaches an upper bound, or *limiting value*. Because of this, logistic regression is best for modeling phenomena where there are limits in expansion, such as availability of living space or nutrients.

It is worth pointing out that logistic functions actually model resource-limited exponential growth. There are many examples of this type of growth in real-world situations, including population growth and spread of disease, rumors, and even stains in fabric. When performing logistic regression analysis, we use the form most commonly used on graphing utilities:

$$y = \frac{c}{1 + ae^{-bx}}$$

Recall that:

- $\frac{c}{1+a}$ is the initial value of the model.
- when $b > 0$, the model increases rapidly at first until it reaches its point of maximum growth rate, $(\frac{\ln(a)}{b}, \frac{c}{2})$. At that point, growth steadily slows and the function becomes asymptotic to the upper bound $y = c$.
- $c$ is the limiting value, sometimes called the *carrying capacity*, of the model.

### LOGISTIC REGRESSION

*Logistic regression* is used to model situations where growth accelerates rapidly at first and then steadily slows to an upper limit. We use the command “Logistic” on a graphing utility to fit a logistic function to a set of data points. This returns an equation of the form

$$y = \frac{c}{1 + ae^{-bx}} \tag{5.9.3}$$

Note that

- The initial value of the model is $\frac{c}{1+a}$.
- Output values for the model grow closer and closer to $y = c$ as time increases.

### How to: Given a set of data, perform logistic regression using a graphing utility

1. Use the STAT then EDIT menu to enter given data.
   i. Clear any existing data from the lists.
   ii. List the input values in the L1 column.
   iii. List the output values in the L2 column.
2. Graph and observe a scatter plot of the data using the STATPLOT feature.
   i. Use ZOOM [9] to adjust axes to fit the data.
   ii. Verify the data follow a logistic pattern.
3. Find the equation that models the data.
   i. Select "Logistic" from the STAT then CALC menu.
   ii. Use the values returned for $a$, $b$, and $c$ to record the model, $y = \dfrac{c}{1+ae^{-bx}}$.
4. Graph the model in the same window as the scatterplot to verify it is a good fit for the data.

### Example 5.9.3: Using Logistic Regression to Fit a Model to Data

Mobile telephone service has increased rapidly in America since the mid 1990s. Today, almost all residents have cellular service. Table 5.9.5 shows the percentage of Americans with cellular service between the years 1995 and 2012.

Table 5.9.5

| Year | Americans with Cellular Service (%) | Year | Americans with Cellular Service (%) |
|---|---|---|---|
| 1995 | 12.69 | 2004 | 62.852 |
| 1996 | 16.35 | 2005 | 68.63 |
| 1997 | 20.29 | 2006 | 76.64 |
| 1998 | 25.08 | 2007 | 82.47 |
| 1999 | 30.81 | 2008 | 85.68 |
| 2000 | 38.75 | 2009 | 89.14 |
| 2001 | 45.00 | 2010 | 91.86 |
| 2002 | 49.16 | 2011 | 95.28 |
| 2003 | 55.15 | 2012 | 98.17 |

a. Let $x$ represent time in years starting with $x = 0$ for the year 1995. Let $y$ represent the corresponding percentage of residents with cellular service. Use logistic regression to fit a model to these data.
b. Use the model to calculate the percentage of Americans with cell service in the year 2013. Round to the nearest tenth of a percent.
c. Discuss the value returned for the upper limit, $c$. What does this tell you about the model? What would the limiting value be if the model were exact?

**Solution**

a. Using the STAT then EDIT menu on a graphing utility, list the years using values $0-15$ in L1 and the corresponding percentage in L2. Then use the STATPLOT feature to verify that the scatterplot follows a logistic pattern as shown in Figure 5.9.5:





Figure 5.9.5

Use the "Logistic" command from the STAT then CALC menu to obtain the logistic model,

$$y = 105.73795261 + 6.88328979e^{-0.2595440013x} \tag{5.9.4}$$

Next, graph the model in the same window as shown in Figure 5.9.6 the scatterplot to verify it is a good fit:





Figure 5.9.6

b. To approximate the percentage of Americans with cellular service in the year 2013, substitute $x = 18$ for the in the model and solve for $y$:

$$\begin{aligned} y &= \frac{105.7379526}{1 + 6.88328979e^{-0.2595440013x}} && \text{Use the regression model found in part } (a) \\ &= \frac{105.7379526}{1 + 6.88328979e^{-0.2595440013(18)}} && \text{Substitute 18 for x} \\ &\approx 99.3 && \text{Round to the nearest tenth} \end{aligned}$$

According to the model, about 98.8% of Americans had cellular service in 2013.

c. The model gives a limiting value of about 105. This means that the maximum possible percentage of Americans with cellular service would be 105, which is impossible. (How could over 100 of a population have cellular service?) If the model were exact, the limiting value would be $c = 100$ and the model's outputs would get very close to, but never actually reach 100. After all, there will always be someone out there without cellular service!

## Exercise 5.9.3

Table 5.9.6 shows the population, in thousands, of harbor seals in the Wadden Sea over the years 1997 to 2012.

Table 5.9.6

| Year | Seal Population (Thousands) | Year | Seal Population (Thousands) |
|---|---|---|---|
| 1997 | 3.493 | 2005 | 19.590 |
| 1998 | 5.282 | 2006 | 21.955 |
| 1999 | 6.357 | 2007 | 22.862 |
| 2000 | 9.201 | 2008 | 23.869 |
| 2001 | 11.224 | 2009 | 24.243 |
| 2002 | 12.964 | 2010 | 24.344 |
| 2003 | 16.226 | 2011 | 24.919 |
| 2004 | 18.137 | 2012 | 25.108 |

Let $x$ represent time in years starting with $x = 0$ for the year 1997. Let $y$ represent the number of seals in thousands.

a. Use logistic regression to fit a model to these data.
b. Use the model to predict the seal population for the year 2020.
c. To the nearest whole number, what is the limiting value of this model?

**Answer a**

The logistic regression model that fits these data is $y = \dfrac{25.65665979}{1 + 6.113686306e^{-0.3852149008x}}$.

**Answer b**

If the population continues to grow at this rate, there will be about $25,634$seals in 2020.

**Answer c**

To the nearest whole number, the carrying capacity is $25,657$.

## Media

Access this online resource for additional instruction and practice with exponential function models.

- Exponential Regression on a Calculator

Visit this website for additional practice questions from Learningpod.

## Key Concepts

- Exponential regression is used to model situations where growth begins slowly and then accelerates rapidly without bound, or where decay begins rapidly and then slows down to get closer and closer to zero.
- We use the command "ExpReg" on a graphing utility to fit function of the form $y = ab^x$ to a set of data points. See Example 5.9.1.
- Logarithmic regression is used to model situations where growth or decay accelerates rapidly at first and then slows over time.

- We use the command “LnReg” on a graphing utility to fit a function of the form $y = a + b\ln(x)$ to a set of data points. See Example 5.9.2.
- Logistic regression is used to model situations where growth accelerates rapidly at first and then steadily slows as the function approaches an upper limit.
- We use the command “Logistic” on a graphing utility to fit a function of the form $y = \dfrac{c}{1 + ae^{-bx}}$ to a set of data points. See Example 5.9.3.

## Contributors and Attributions

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.

---

This page titled 5.9: Fitting Exponential Models to Data is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.8: Fitting Exponential Models to Data** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 5.9E: Fitting Exponential Models to Data (Exercises)

64. What is the carrying capacity for a population modeled by the logistic equation $P(t) = \frac{250,000}{1+499e^{-0.45t}}$? What is the initial population for the model?

65. The population of a culture of bacteria is modeled by the logistic equation $P(t) = \frac{14,250}{1+29e^{-0.62t}}$, where $t$ is in days. To the nearest tenth, how many days will it take the culture to reach $75\%$ of its carrying capacity?

For the following exercises, use a graphing utility to create a scatter diagram of the data given in the table. Observe the shape of the scatter diagram to determine whether the data is best described by an exponential, logarithmic, or logistic model. Then use the appropriate regression feature to find an equation that models the data. When necessary, round values to five decimal places.

**66**.

| *x* | *f(x)* |
|---|---|
| 1 | 409.4 |
| 2 | 260.7 |
| 3 | 170.4 |
| 4 | 110.6 |
| 5 | 74 |
| 6 | 44.7 |
| 7 | 32.4 |
| 8 | 19.5 |
| 9 | 12.7 |
| 10 | 8.1 |

67.

| *x* | *f(x)* |
|---|---|
| 0.15 | 36.21 |
| 0.25 | 28.88 |
| 0.5 | 24.39 |
| 0.75 | 18.28 |
| 1 | 16.5 |
| 1.5 | 12.99 |
| 2 | 9.91 |
| 2.25 | 8.57 |
| 2.75 | 7.23 |
| 3 | 5.99 |
| 3.5 | 4.81 |

**68**.

| *x* | *f(x)* |
|---|---|

| | |
|---|---|
| 0 | 9 |
| 2 | 22.6 |
| 4 | 44.2 |
| 5 | 62.1 |
| 7 | 96.9 |
| 8 | 113.4 |
| 10 | 133.4 |
| 11 | 137.6 |
| 15 | 148.4 |
| 17 | 149.3 |

This page titled 5.9E: Fitting Exponential Models to Data (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **6.8E: Fitting Exponential Models to Data (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# CHAPTER OVERVIEW

## 6: Systems of Equations and Inequalities

In this chapter, we will investigate matrices and their inverses, and various ways to use matrices to solve systems of equations. First, however, we will study systems of equations on their own: linear and nonlinear, and then partial fractions.


6.1: Prelude to Systems of Equations and Inequalities

6.2: Systems of Linear Equations - Two Variables

6.2E: Systems of Linear Equations - Two Variables (Exercises)

6.3: Systems of Linear Equations with Three Variables

6.3E: Systems of Linear Equations with Three Variables (Exercises)

6.4: Systems of Nonlinear Equations and Inequalities - Two Variables

6.4E: Systems of Nonlinear Equations and Inequalities - Two Variables (Exercises)

6.5: Solving Systems with Gaussian Elimination

6.5E: Solving Systems with Gaussian Elimination (Exercises)


Thumbnail: Possible types of solutions for the points of Intersection of a circle and an ellipse.

### Contributors

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.


This page titled 6: Systems of Equations and Inequalities is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 6.1: Prelude to Systems of Equations and Inequalities



Figure 6.1.1: Enigma machines like this one, once owned by Italian dictator Benito Mussolini, were used by government and military officials for enciphering and deciphering top-secret communications during World War II. (credit: Dave Addey, Flickr)

By 1943, it was obvious to the Nazi regime that defeat was imminent unless it could build a weapon with unlimited destructive power, one that had never been seen before in the history of the world. In September, Adolf Hitler ordered German scientists to begin building an atomic bomb. Rumors and whispers began to spread from across the ocean. Refugees and diplomats told of the experiments happening in Norway. However, Franklin D. Roosevelt wasn't sold, and even doubted British Prime Minister Winston Churchill's warning. Roosevelt wanted undeniable proof. Fortunately, he soon received the proof he wanted when a group of mathematicians cracked the "Enigma" code, proving beyond a doubt that Hitler was building an atomic bomb. The next day, Roosevelt gave the order that the United States begin work on the same.

The Enigma is perhaps the most famous cryptographic device ever known. It stands as an example of the pivotal role cryptography has played in society. Now, technology has moved cryptanalysis to the digital world.

Many ciphers are designed using invertible matrices as the method of message transference, as finding the inverse of a matrix is generally part of the process of decoding. In addition to knowing the matrix and its inverse, the receiver must also know the key that, when used with the matrix inverse, will allow the message to be read.

In this chapter, we will investigate matrices and their inverses, and various ways to use matrices to solve systems of equations. First, however, we will study systems of equations on their own: linear and nonlinear, and then partial fractions. We will not be breaking any secret codes here, but we will lay the foundation for future courses.

---

This page titled 6.1: Prelude to Systems of Equations and Inequalities is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.0: Prelude to Systems of Equations and Inequalities** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 6.2: Systems of Linear Equations - Two Variables

**Learning Objectives**

- Solve systems of equations by graphing.
- Solve systems of equations by substitution.
- Solve systems of equations by addition.
- Identify inconsistent systems of equations containing two variables.
- Express the solution of a system of dependent equations containing two variables.

A skateboard manufacturer introduces a new line of boards. The manufacturer tracks its costs, which is the amount it spends to produce the boards, and its revenue, which is the amount it earns through sales of its boards. How can the company determine if it is making a profit with its new line? How many skateboards must be produced and sold before a profit is possible? In this section, we will consider linear equations with two variables to answer these and similar questions.



Figure 6.2.1

## Introduction to Systems of Equations

In order to investigate situations such as that of the skateboard manufacturer, we need to recognize that we are dealing with more than one variable and likely more than one equation. **A system of linear equations** consists of two or more linear equations made up of two or more variables such that all equations in the system are considered simultaneously. To find the unique solution to a system of linear equations, we must find a numerical value for each variable in the system that will satisfy all equations in the system at the same time. Some linear systems may not have a solution and others may have an infinite number of solutions. In order for a linear system to have a unique solution, there must be at least as many equations as there are variables. Even so, this does not guarantee a unique solution.

In this section, we will look at systems of linear equations in two variables, which consist of two equations that contain two different variables. For example, consider the following system of linear equations in two variables.

$$\begin{aligned} 2x+y &= 15 \\ 3x-y &= 5 \end{aligned}$$

The *solution* to a system of linear equations in two variables is any ordered pair that satisfies each equation independently. In this example, the ordered pair $(4,7)$ is the solution to the system of linear equations. We can verify the solution by substituting the values into each equation to see if the ordered pair satisfies both equations. Shortly we will investigate methods of finding such a solution if it exists.

$$\begin{aligned} 2(4)+(7) &= 15 \text{ True} \\ 3(4)-(7) &= 5 \text{ True} \end{aligned}$$

In addition to considering the number of equations and variables, we can categorize systems of linear equations by the number of solutions. A consistent system of equations has at least one solution. A consistent system is considered to be an **independent system** if it has a single solution, such as the example we just explored. The two lines have different slopes and intersect at one point in the plane. A consistent system is considered to be a **dependent system** if the equations have the same slope and the same $y$-intercepts. In other words, the lines coincide so the equations represent the same line. Every point on the line represents a coordinate pair that satisfies the system. Thus, there are an infinite number of solutions.

Another type of system of linear equations is an **inconsistent system**, which is one in which the equations represent two parallel lines. The lines have the same slope and different $y$-intercepts. There are no points common to both lines; hence, there is no solution to the system.

## TYPES OF LINEAR SYSTEMS

There are three types of systems of linear equations in two variables, and three types of solutions.

- An independent system has exactly one solution pair $(x, y)$. The point where the two lines intersect is the only solution.
- An inconsistent system has no solution. Notice that the two lines are parallel and will never intersect.
- A dependent system has infinitely many solutions. The lines are coincident. They are the same line, so every coordinate pair on the line is a solution to both equations.

Figure $6.2.2$ compares graphical representations of each type of system.





Figure 6.2.2

## Given a system of linear equations and an ordered pair, determine whether the ordered pair is a solution

1. Substitute the ordered pair into each equation in the system.
2. Determine whether true statements result from the substitution in both equations; if so, the ordered pair is a solution.

## Example 6.2.1: Determining Whether an Ordered Pair Is a Solution to a System of Equations

Determine whether the ordered pair $(5, 1)$ is a solution to the given system of equations.

$$\begin{aligned} x + 3y &= 8 \\ 2x - 9 &= y \end{aligned}$$

### Solution

Substitute the ordered pair $(5, 1)$ into both equations.

$$\begin{aligned} (5) + 3(1) &= 8 \\ 8 &= 8 \text{ True} \\ 2(5) - 9 &= (1) \\ 1 &= 1 \text{ True} \end{aligned}$$

The ordered pair $(5, 1)$ satisfies both equations, so it is the solution to the system.

**Analysis**

We can see the solution clearly by plotting the graph of each equation. Since the solution is an ordered pair that satisfies both equations, it is a point on both of the lines and thus the point of intersection of the two lines. See Figure $6.2.3$.





Figure 6.2.3

**? Exercise 6.2.1**

Determine whether the ordered pair $(8, 5)$ is a solution to the following system.

$$\begin{aligned} 5x - 4y &= 20 \\ 2x + 1 &= 3y \end{aligned}$$

**Answer**

Not a solution.

## Solving Systems of Equations by Graphing

There are multiple methods of solving systems of linear equations. For a system of linear equations in two variables, we can determine both the type of system and the solution by graphing the system of equations on the same set of axes.

**✔ Example 6.2.2: Solving a System of Equations in Two Variables by Graphing**

Solve the following system of equations by graphing. Identify the type of system.

$$\begin{aligned} 2x + y &= -8 \\ x - y &= -1 \end{aligned}$$

**Solution**

Solve the first equation for $y$.

$$\begin{aligned} 2x + y &= -8 \\ y &= -2x - 8 \end{aligned}$$

Solve the second equation for $y$.

$$\begin{aligned} x - y &= -1 \\ y &= x + 1 \end{aligned}$$

Graph both equations on the same set of axes as in Figure 6.2.4.





Figure 6.2.4

The lines appear to intersect at the point $(-3,-2)$. We can check to make sure that this is the solution to the system by substituting the ordered pair into both equations.

$$\begin{aligned} 2(-3)+(-2) &= -8 \\ -8 &= -8 \text{ True} \\ (-3)-(-2) &= -1 \\ -1 &= -1 \text{ True} \end{aligned}$$

The solution to the system is the ordered pair $(-3,-2)$,so the system is independent.

## Exercise 6.2.2

Solve the following system of equations by graphing.

$$\begin{aligned} 2x-5y &= -25 \\ -4x+5y &= 35 \end{aligned}$$

**Answer**

The solution to the system is the ordered pair $(-5,3)$.





Figure 6.2.5

## Q&A

**Can graphing be used if the system is inconsistent or dependent?**

*Yes, in both cases we can still graph the system to determine the type of system and solution. If the two lines are parallel, the system has no solution and is inconsistent. If the two lines are identical, the system has infinite solutions and is a dependent*

*system.*

### Solving Systems of Equations by Substitution

Solving a linear system in two variables by graphing works well when the solution consists of integer values, but if our solution contains decimals or fractions, it is not the most precise method. We will consider two more methods of solving a **system of linear equations** that are more precise than graphing. One such method is solving a system of equations by the **substitution method**, in which we solve one of the equations for one variable and then substitute the result into the second equation to solve for the second variable. Recall that we can solve for only one variable at a time, which is the reason the substitution method is both valuable and practical.

**How to: Given a system of two equations in two variables, solve using the substitution method.**

1. Solve one of the two equations for one of the variables in terms of the other.
2. Substitute the expression for this variable into the second equation, then solve for the remaining variable.
3. Substitute that solution into either of the original equations to find the value of the first variable. If possible, write the solution as an ordered pair.
4. Check the solution in both equations.

**Example 6.2.3: Solving a System of Equations in Two Variables by Substitution**

Solve the following system of equations by substitution.

$$\begin{aligned} -x+y &= -5 \\ 2x-5y &= 1 \end{aligned}$$

**Solution**

First, we will solve the first equation for $y$.

$$\begin{aligned} -x+y &= -5 \\ y &= x-5 \end{aligned}$$

Now we can substitute the expression $x-5$ for $y$ in the second equation.

$$\begin{aligned} 2x-5y &= 1 \\ 2x-5(x-5) &= 1 \\ 2x-5x+25 &= 1 \\ -3x &= -24 \\ x &= 8 \end{aligned}$$

Now, we substitute $x=8$ into the first equation and solve for $y$.

$$\begin{aligned} -(8)+y &= -5 \\ y &= 3 \end{aligned}$$

Our solution is $(8,3)$.

Check the solution by substituting $(8,3)$ into both equations.

$$\begin{aligned} -x+y &= -5 \\ -(8)+(3) &= -5 \text{ True} \\ 2x-5y &= 1 \\ 2(8)-5(3) &= 1 \text{ True} \end{aligned}$$

**Exercise 6.2.3**

Solve the following system of equations by substitution.

$$x = y + 3$$
$$4 = 3x - 2y$$

**Answer**

$(-2, -5)$

**Q&A**

**Can the substitution method be used to solve any linear system in two variables?**

*Yes, but the method works best if one of the equations contains a coefficient of* $1$ *or* $-1$ *so that we do not have to deal with fractions.*

## Solving Systems of Equations in Two Variables by the Addition Method

A third method of solving systems of linear equations is the addition method. In this method, we add two terms with the same variable, but opposite coefficients, so that the sum is zero. Of course, not all systems are set up with the two terms of one variable having opposite coefficients. Often we must adjust one or both of the equations by multiplication so that one variable will be eliminated by addition.

**How to: Given a system of equations, solve using the addition method.**

1. Write both equations with *x*- and *y*-variables on the left side of the equal sign and constants on the right.
2. Write one equation above the other, lining up corresponding variables. If one of the variables in the top equation has the opposite coefficient of the same variable in the bottom equation, add the equations together, eliminating one variable. If not, use multiplication by a nonzero number so that one of the variables in the top equation has the opposite coefficient of the same variable in the bottom equation, then add the equations to eliminate the variable.
3. Solve the resulting equation for the remaining variable.
4. Substitute that value into one of the original equations and solve for the second variable.
5. Check the solution by substituting the values into the other equation.

**Example 6.2.4: Solving a System by the Addition Method**

Solve the given system of equations by addition.

$$x + 2y = -1$$
$$-x + y = 3$$

**Solution**

Both equations are already set equal to a constant. Notice that the coefficient of $x$ in the second equation, $-1$, is the opposite of the coefficient of $x$ in the first equation, $1$. We can add the two equations to eliminate $x$ without needing to multiply by a constant.

$$\begin{aligned} x + 2y &= -1 \\ \underline{-x + y} &= \underline{3} \\ 3y &= 2 \end{aligned}$$

Now that we have eliminated $x$, we can solve the resulting equation for $y$.

$$3y = 2$$
$$y = \frac{2}{3}$$

Then, we substitute this value for $y$ into one of the original equations and solve for $x$.

$$\begin{aligned} -x+y &= 3 \\ -x+\frac{2}{3} &= 3 \\ -x &= 3-\frac{2}{3} \\ -x &= \frac{7}{3} \\ x &= -\frac{7}{3} \end{aligned}$$

The solution to this system is $\left(-\frac{7}{3}, \frac{2}{3}\right)$.

Check the solution in the first equation.

$$\begin{aligned} x+2y &= -1 \\ \left(-\frac{7}{3}\right)+2\left(\frac{2}{3}\right) &= \\ -\frac{7}{3}+\frac{4}{3} &= -\frac{3}{3} \\ -1 &= -1 \qquad \text{True} \end{aligned}$$

**Analysis**

We gain an important perspective on systems of equations by looking at the graphical representation. See Figure 6.2.6 to find that the equations intersect at the solution. We do not need to ask whether there may be a second solution because observing the graph confirms that the system has exactly one solution.





Figure 6.2.6

## Example 6.2.5: Using the Addition Method When Multiplication of One Equation Is Required

Solve the given system of equations by the addition method.

$$\begin{aligned} 3x+5y &= -11 \\ x-2y &= 11 \end{aligned}$$

**Solution**

Adding these equations as presented will not eliminate a variable. However, we see that the first equation has $3x$ in it and the second equation has $x$. So if we multiply the second equation by $-3$,the $x$-terms will add to zero.

$$\begin{aligned} x-2y &= 11 \\ -3(x-2y) &= -3(11) \qquad \text{Multiply both sides by } -3. \\ -3x+6y &= -33 \qquad \text{Use the distributive property.} \end{aligned}$$

Now, let's add them.

$$\begin{aligned} 3x+5y &= -11 \\ \underline{-3x+6y} &= \underline{-33} \\ 11y &= -44 \\ y &= -4 \end{aligned}$$

For the last step, we substitute $y=-4$ into one of the original equations and solve for $x$.

$$\begin{aligned} 3x+5y &= -11 \\ 3x+5(-4) &= -11 \\ 3x-20 &= -11 \\ 3x &= 9 \\ x &= 3 \end{aligned}$$

Our solution is the ordered pair $(3,-4)$. See Figure 6.2.7. Check the solution in the original second equation.

$$\begin{aligned} x-2y &= 11 \\ (3)-2(-4) &= 3+8 \\ &= 11 \qquad \text{True} \end{aligned}$$





Figure 6.2.7

**? Exercise 6.2.4**

Solve the system of equations by addition.

$$\begin{aligned} 2x-7y &= 2 \\ 3x+y &= -20 \end{aligned}$$

**Answer**

$(-6,-2)$

**✓ Example 6.2.6: Using the Addition Method When Multiplication of Both Equations Is Required**

Solve the given system of equations in two variables by addition.

$$\begin{aligned} 2x+3y &= -16 \\ 5x-10y &= 30 \end{aligned}$$

**Solution**

One equation has $2x$ and the other has $5x$. The least common multiple is $10x$ so we will have to multiply both equations by a constant in order to eliminate one variable. Let's eliminate $x$ by multiplying the first equation by $-5$ and the second equation by 2.

$$\begin{aligned} -5(2x+3y) &= -5(-16) \\ -10x-15y &= 80 \\ 2(5x-10y) &= 2(30) \\ 10x-20y &= 60 \end{aligned}$$

Then, we add the two equations together.

$$\begin{aligned} -10x-15y &= 80 \\ \underline{10x-20y} &= \underline{60} \\ -35y &= 140 \\ y &= -4 \end{aligned}$$

Substitute $y=-4$ into the original first equation.

$$\begin{aligned} 2x+3(-4) &= -16 \\ 2x-12 &= -16 \\ 2x &= -4 \\ x &= -2 \end{aligned}$$

The solution is $(-2,-4)$. Check it in the other equation.

$$\begin{aligned} 5x-10y &= 30 \\ 5(-2)-10(-4) &= 30 \\ -10+40 &= 30 \\ 30 &= 30 \end{aligned}$$

See Figure 6.2.8.





Figure 6.2.8

### Example 6.2.7: Using the Addition Method in Systems of Equations Containing Fractions

Solve the given system of equations in two variables by addition.

$$\begin{aligned} \frac{x}{3}+\frac{y}{6} &= 3 \\ \frac{x}{2}-\frac{y}{4} &= 1 \end{aligned}$$

**Solution**

First clear each equation of fractions by multiplying both sides of the equation by the least common denominator.

$$6\left(\frac{x}{3}+\frac{y}{6}\right)=6(3)$$
$$2x+y=18$$
$$4\left(\frac{x}{2}-\frac{y}{4}\right)=4(1)$$
$$2x-y=4$$

Now multiply the second equation by $-1$ so that we can eliminate the $x$-variable.

$$-1(2x-y)=-1(4)$$
$$-2x+y=-4$$

Add the two equations to eliminate the $x$-variable and solve the resulting equation.

$$2x+y=18$$
$$-2x+y=-4$$
$$2y=14$$
$$y=7$$

Substitute $y=7$ into the first equation.

$$2x+(7)=18$$
$$2x=11$$
$$x=\frac{11}{2}$$
$$=7.5$$

The solution is $\left(\frac{11}{2},7\right)$. Check it in the other equation.

$$\frac{x}{2}-\frac{y}{4}=1$$
$$\frac{\frac{11}{2}}{2}-\frac{7}{4}=1$$
$$\frac{11}{4}-\frac{7}{4}=1$$
$$\frac{4}{4}=1$$

**? Exercise 6.2.5**

Solve the system of equations by addition.

$$2x+3y=8$$
$$3x+5y=10$$

**Answer**

$(10,-4)$

### Identifying Inconsistent Systems of Equations Containing Two Variables

Now that we have several methods for solving systems of equations, we can use the methods to identify inconsistent systems. Recall that an inconsistent system consists of parallel lines that have the same slope but different y-intercepts. They will never intersect. When searching for a solution to an inconsistent system, we will come up with a false statement, such as $12=0$.

## Example 6.2.8: Solving an Inconsistent System of Equations

Solve the following system of equations.

$$\begin{aligned} x &= 9-2y \\ x+2y &= 13 \end{aligned}$$

### Solution

We can approach this problem in two ways. Because one equation is already solved for $x$, the most obvious step is to use substitution.

$$\begin{aligned} x+2y &= 13 \\ (9-2y)+2y &= 13 \\ 9+0y &= 13 \\ 9 &= 13 \end{aligned}$$

Clearly, this statement is a contradiction because $9 \neq 13$. Therefore, the system has no solution.

The second approach would be to first manipulate the equations so that they are both in slope-intercept form. We manipulate the first equation as follows.

$$\begin{aligned} x &= 9-2y \\ 2y &= -x+9 \\ y &= -\frac{1}{2}x+\frac{9}{2} \end{aligned}$$

We then convert the second equation expressed to slope-intercept form.

$$\begin{aligned} x+2y &= 13 \\ 2y &= -x+13 \\ y &= -\frac{1}{2}x+\frac{13}{2} \end{aligned}$$

Comparing the equations, we see that they have the same slope but different $y$-intercepts. Therefore, the lines are parallel and do not intersect.

$$\begin{aligned} y &= -\frac{1}{2}x+\frac{9}{2} \\ y &= -\frac{1}{2}x+\frac{13}{2} \end{aligned}$$

### Analysis

Writing the equations in slope-intercept form confirms that the system is inconsistent because all lines will intersect eventually unless they are parallel. Parallel lines will never intersect; thus, the two lines have no points in common. The graphs of the equations in this example are shown in Figure 6.2.9.





Figure 6.2.9

**Exercise 6.2.6**

Solve the following system of equations in two variables.

$$\begin{aligned} 2y-2x &= 2 \\ 2y-2x &= 6 \end{aligned}$$

**Answer**

No solution. It is an inconsistent system.

### Expressing the Solution of a System of Dependent Equations Containing Two Variables

Recall that a dependent system of equations in two variables is a system in which the two equations represent the same line. Dependent systems have an infinite number of solutions because all of the points on one line are also on the other line. After using substitution or addition, the resulting equation will be an identity, such as $0=0$.

**Example 6.2.9: Finding a Solution to a Dependent System of Linear Equations**

Find a solution to the system of equations using the **addition method**.

$$\begin{aligned} x+3y &= 2 \\ 3x+9y &= 6 \end{aligned}$$

**Solution**

With the addition method, we want to eliminate one of the variables by adding the equations. In this case, let's focus on eliminating $x$. If we multiply both sides of the first equation by $-3$, then we will be able to eliminate the x-variable.

$$\begin{aligned} x+3y &= 2 \\ (-3)(x+3y) &= (-3)(2) \\ -3x-9y &= -6 \end{aligned}$$

Now add the equations.

$$\begin{aligned} -3x-9y &= -6 \\ \underline{+\,3x+9y} &= \underline{6} \\ 0 &= 0 \end{aligned}$$

We can see that there will be an infinite number of solutions that satisfy both equations.

**Analysis**

If we rewrote both equations in the slope-intercept form, we might know what the solution would look like before adding. Let's look at what happens when we convert the system to slope-intercept form.

$$\begin{aligned} x+3y &= 2 \\ 3y &= -x+2 \\ y &= -\frac{1}{3}x+\frac{2}{3} \\ 3x+9y &= 6 \\ 9y &= -3x+6 \\ y &= -\frac{3}{9}x+\frac{6}{9} \\ y &= -\frac{1}{3}x+\frac{2}{3} \end{aligned}$$

See Figure 6.2.10. Notice the results are the same. The general solution to the system is $\left(x, -\frac{1}{3}x+\frac{2}{3}\right)$.





Figure 6.2.10

**Exercise 6.2.7**

Solve the following system of equations in two variables.

$$\begin{aligned} y-2x &= 5 \\ -3y+6x &= -15 \end{aligned}$$

**Answer**

The system is dependent so there are infinite solutions of the form $(x, 2x+5)$.

## Using Systems of Equations to Investigate Profits

Using what we have learned about systems of equations, we can return to the skateboard manufacturing problem at the beginning of the section. The skateboard manufacturer's revenue function is the function used to calculate the amount of money that comes into the business. It can be represented by the equation $R = xp$, where $x$=quantity and $p$=price. The revenue function is shown in orange in Figure 6.2.11.

The cost function is the function used to calculate the costs of doing business. It includes fixed costs, such as rent and salaries, and variable costs, such as utilities. The cost function is shown in blue in Figure 6.2.11. The $x$-axis represents quantity in hundreds of units. The $y$-axis represents either cost or revenue in hundreds of dollars.





Figure 6.2.11

The point at which the two lines intersect is called the break-even point. We can see from the graph that if 700 units are produced, the cost is $\$3,300$ and the revenue is also $\$3,300$. In other words, the company breaks even if they produce and sell 700 units. They neither make money nor lose money.

The shaded region to the right of the break-even point represents quantities for which the company makes a profit. The shaded region to the left represents quantities for which the company suffers a loss. The profit function is the revenue function minus the cost function, written as $P(x) = R(x) - C(x)$. Clearly, knowing the quantity for which the cost equals the revenue is of great importance to businesses.

## Example 6.2.10: Finding the Break-Even Point and the Profit Function Using Substitution

Given the cost function $C(x) = 0.85x + 35,000$ and the revenue function $R(x) = 1.55x$, find the break-even point and the profit function.

### Solution

Write the system of equations using $y$ to replace function notation.

$$\begin{aligned} y &= 0.85x + 35,000 \\ y &= 1.55x \end{aligned}$$

Substitute the expression $0.85x + 35,000$ from the first equation into the second equation and solve for $x$.

$$\begin{aligned} 0.85x + 35,000 &= 1.55x \\ 35,000 &= 0.7x \\ 50,000 &= x \end{aligned}$$

Then, we substitute $x = 50,000$ into either the cost function or the revenue function.

$$1.55(50,000) = 77,500$$

The break-even point is $(50,000, 77,500)$.

The profit function is found using the formula $P(x) = R(x) - C(x)$.

$$\begin{aligned} P(x) &= 1.55x - (0.85x + 35,000) \\ &= 0.7x - 35,000 \end{aligned}$$

The profit function is $P(x) = 0.7x - 35,000$.

**Analysis**

The cost to produce $50,000$ units is $\$77,500$, and the revenue from the sales of $50,000$ units is also $\$77,500$. To make a profit, the business must produce and sell more than $50,000$ units. See Figure 6.2.12.





Figure 6.2.12

We see from the graph in Figure 6.2.13 that the profit function has a negative value until $x = 50,000$, when the graph crosses the $x$-axis. Then, the graph emerges into positive $y$-values and continues on this path as the profit function is a straight line. This illustrates that the break-even point for businesses occurs when the profit function is 0. The area to the left of the break-even point represents operating at a loss.





Figure 6.2.13

### Example 6.2.11: Writing and Solving a System of Equations in Two Variables

The cost of a ticket to the circus is $\$25.00$ for children and $\$50.00$ for adults. On a certain day, attendance at the circus is $2,000$ and the total gate revenue is $\$70,000$. How many children and how many adults bought tickets?

**Solution**

Let $c$ = the number of children and $a$ = the number of adults in attendance.

The total number of people is $2,000$. We can use this to write an equation for the number of people at the circus that day.

$$c+a=2,000$$

The revenue from all children can be found by multiplying $\$25.00$ by the number of children, $25c$. The revenue from all adults can be found by multiplying $\$50.00$ by the number of adults, $50a$. The total revenue is $\$70,000$. We can use this to write an equation for the revenue.

$$25c+50a=70,000$$

We now have a system of linear equations in two variables.

$$c+a=2,000$$
$$25c+50a=70,000$$

In the first equation, the coefficient of both variables is $1$. We can quickly solve the first equation for either $c$ or $a$. We will solve for $a$.

$$\begin{aligned} c+a &= 2,000 \\ a &= 2,000-c \end{aligned}$$

Substitute the expression $2,000-c$ in the second equation fora a and solve for $c$.

$$\begin{aligned} 25c+50(2,000-c) &= 70,000 \\ 25c+100,000-50c &= 70,000 \\ -25c &= -30,000 \\ c &= 1,200 \end{aligned}$$

Substitute $c=1,200$ into the first equation to solve for $a$.

$$\begin{aligned} 1,200+a &= 2,000 \\ a &= 800 \end{aligned}$$

We find that $1,200$ children and $800$ adults bought tickets to the circus that day.

## Exercise 6.2.8

Meal tickets at the circus cost $\$4.00$ for children and $\$12.00$ for adults. If $1,650$ meal tickets were bought for a total of, $\$14,200$, how many children and how many adults bought meal tickets?

**Answer**

$700$ children, $950$ adults

## Media

Access these online resources for additional instruction and practice with systems of linear equations.

- Solving Systems of Equations Using Substitution
- Solving Systems of Equations Using Elimination
- Applications of Systems of Equations

### Key Concepts

- A system of linear equations consists of two or more equations made up of two or more variables such that all equations in the system are considered simultaneously.
- The solution to a system of linear equations in two variables is any ordered pair that satisfies each equation independently. See Example $6.2.1$.
- Systems of equations are classified as independent with one solution, dependent with an infinite number of solutions, or inconsistent with no solution.
- One method of solving a system of linear equations in two variables is by graphing. In this method, we graph the equations on the same set of axes. See Example $6.2.2$.
- Another method of solving a system of linear equations is by substitution. In this method, we solve for one variable in one equation and substitute the result into the second equation. See Example $6.2.3$.
- A third method of solving a system of linear equations is by addition, in which we can eliminate a variable by adding opposite coefficients of corresponding variables. See Example $6.2.4$.
- It is often necessary to multiply one or both equations by a constant to facilitate elimination of a variable when adding the two equations together. See Example $6.2.5$, Example $6.2.6$, and Example $6.2.7$.
- Either method of solving a system of equations results in a false statement for inconsistent systems because they are made up of parallel lines that never intersect. See Example $6.2.8$.
- The solution to a system of dependent equations will always be true because both equations describe the same line. See Example $6.2.9$.
- Systems of equations can be used to solve real-world problems that involve more than one variable, such as those relating to revenue, cost, and profit. See Example $6.2.10$ and Example $6.2.11$.

This page titled 6.2: Systems of Linear Equations - Two Variables is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.1: Systems of Linear Equations - Two Variables** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 6.2E: Systems of Linear Equations - Two Variables (Exercises)

For the following exercises, determine whether the ordered pair is a solution to the system of equations.

$3x - y = 4$

1. and (-1,1) $x + 4y = -3$
$6x - 2y = 24$

2. $-3x + 3y = 18$

For the following exercises, use substitution to solve the system of equations.

3
$10x + 5y = -5$
$3x - 2y = -12$

4
$\frac{4}{7}x + \frac{1}{5}y = \frac{43}{70}$
$\frac{5}{6}x - \frac{1}{3}y = -\frac{2}{3}$

5

$5x + 6y = 14$
$4x + 8y = 8$

For the following exercises, use addition to solve the system of equations.

6
$3x + 2y = -7$
$2x + 4y = 6$

7.

$3x + 4y = 2$
$9x + 12y = 3$

8.

$8x + 4y = 2$
$6x - 5y = 0.7$

For the following exercises, write a system of equations to solve each problem. Solve the system of equations.

9. A factory has a cost of production $C(x) = 150x + 15,000$ and a revenue function $R(x) = 200x$. What is the break-even point?

10. A performer charges $C(x) = 50x + 10,000$, where $x$ is the total number of attendees at a show. The venue charges $\$75$ per ticket. After how many people buy tickets does the venue break even, and what is the value of the total tickets sold at that point?

---

This page titled 6.2E: Systems of Linear Equations - Two Variables (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.1E: Systems of Linear Equations - Two Variables (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 6.3: Systems of Linear Equations with Three Variables

**Learning Objectives**

- Solve systems of three equations in three variables.
- Identify inconsistent systems of equations containing three variables.
- Express the solution of a system of dependent equations containing three variables.

John received an inheritance of $\$12,000$ that he divided into three parts and invested in three ways: in a money-market fund paying $3\%$ annual interest; in municipal bonds paying $4\%$ annual interest; and in mutual funds paying $7\%$ annual interest. John invested $\$4,000$ more in municipal funds than in municipal bonds. He earned $\$670$ in interest the first year. How much did John invest in each type of fund?



Figure 6.3.1: (credit: "Elembis," Wikimedia Commons)

Understanding the correct approach to setting up problems such as this one makes finding a solution a matter of following a pattern. We will solve this and similar problems involving three equations and three variables in this section. Doing so uses similar techniques as those used to solve systems of two equations in two variables. However, finding solutions to systems of three equations requires a bit more organization and a touch of visual gymnastics.

## Solving Systems of Three Equations in Three Variables

In order to solve systems of equations in three variables, known as three-by-three systems, the primary tool we will be using is called Gaussian elimination, named after the prolific German mathematician Karl Friedrich Gauss. While there is no definitive order in which operations are to be performed, there are specific guidelines as to what type of moves can be made. We may number the equations to keep track of the steps we apply. The goal is to eliminate one variable at a time to achieve upper triangular form, the ideal form for a three-by-three system because it allows for straightforward back-substitution to find a solution $(x, y, z)$, which we call an ordered triple. A system in upper triangular form looks like the following:

$$\begin{aligned} Ax + By + Cz &= D \\ Ey + Fz &= G \\ Hz &= K \end{aligned}$$

The third equation can be solved for $z$,and then we back-substitute to find $y$ and $x$. To write the system in upper triangular form, we can perform the following operations:

1. Interchange the order of any two equations.
2. Multiply both sides of an equation by a nonzero constant.
3. Add a nonzero multiple of one equation to another equation.

The **solution set** to a three-by-three system is an ordered triple $(x, y, z)$. Graphically, the ordered triple defines the point that is the intersection of three planes in space. You can visualize such an intersection by imagining any corner in a rectangular room. A corner is defined by three planes: two adjoining walls and the floor (or ceiling). Any point where two walls and the floor meet represents the intersection of three planes.

## NUMBER OF POSSIBLE SolutionS

Figure 6.3.2 and Figure 6.3.3 illustrate possible solution scenarios for three-by-three systems.

- Systems that have a single solution are those which, after elimination, result in a solution set consisting of an ordered triple $(x, y, z)$. Graphically, the ordered triple defines a point that is the intersection of three planes in space.
- Systems that have an infinite number of solutions are those which, after elimination, result in an expression that is always true, such as $0 = 0$. Graphically, an infinite number of solutions represents a line or coincident plane that serves as the intersection of three planes in space.
- Systems that have no solution are those that, after elimination, result in a statement that is a contradiction, such as $3 = 0$. Graphically, a system with no solution is represented by three planes with no point in common.





Figure 6.3.2: (a)Three planes intersect at a single point, representing a three-by-three system with a single solution. (b) Three planes intersect in a line, representing a three-by-three system with infinite solutions.





Figure 6.3.3: All three figures represent three-by-three systems with no solution. (a) The three planes intersect with each other, but not at a common point. (b) Two of the planes are parallel and intersect with the third plane, but not with each other. (c) All three planes are parallel, so there is no point of intersection.

## Example 6.3.1: Determining Whether an Ordered Triple Is a Solution to a System

Determine whether the ordered triple $(3, -2, 1)$ is a solution to the system.

$$\begin{aligned} x + y + z &= 2 \\ 6x - 4y + 5z &= 31 \\ 5x + 2y + 2z &= 13 \end{aligned}$$

**Solution**

We will check each equation by substituting in the values of the ordered triple for $x$, $y$, and $z$.

| | | |
|---|---|---|
| $x + y + z = 2$ | $6x - 4y + 5z = 31$ | $5x + 2y + 2z = 13$ |
| $(3) + (-2) + (1) = 2$ | $6(3) - 4(-2) + 5(1) = 31$ | $5(3) + 2(-2) + 2(1) = 13$ |
| True | $18 + 8 + 5 = 31$ | $15 - 4 + 2 = 13$ |
| | True | True |

The ordered triple $(3, -2, 1)$ is indeed a solution to the system.

## How to: Given a linear system of three equations, solve for three unknowns

1. Pick any pair of equations and solve for one variable.
2. Pick another pair of equations and solve for the same variable.
3. You have created a system of two equations in two unknowns. Solve the resulting two-by-two system.

4. Back-substitute known variables into any one of the original equations and solve for the missing variable.

### Example 6.3.2: Solving a System of Three Equations in Three Variables by Elimination

Find a solution to the following system:

$$\begin{aligned} x-2y+3z &= 9 \quad (1)\\ -x+3y-z &= -6 \quad (2)\\ 2x-5y+5z &= 17 \quad (3) \end{aligned}$$

**Solution**

There will always be several choices as to where to begin, but the most obvious first step here is to eliminate $x$ by adding equations (1) and (2).

$$\begin{aligned} x-2y+3z &= 9 \quad (1)\\ \underline{-x+3y-z} &\underline{= -6 \quad (2)}\\ y+2z &= 3 \quad (4) \end{aligned}$$

The second step is multiplying equation (1) by $-2$ and adding the result to equation (3). These two steps will eliminate the variable $x$.

$$\begin{aligned} -2x+4y-6z &= -18 \quad (1) \quad \text{multiplied by } -2\\ \underline{2x-5y+5z} &\underline{= 17 \quad (3)}\\ -y-z &= -1 \quad (5) \end{aligned}$$

In equations (4) and (5), we have created a new two-by-two system. We can solve for $z$ by adding the two equations.

$$\begin{aligned} y+2z &= 3 \quad (4)\\ \underline{-y-z} &\underline{= -1 \quad (5)}\\ z &= 2 \quad (6) \end{aligned}$$

Choosing one equation from each new system, we obtain the upper triangular form:

$$\begin{aligned} x-2y+3z &= 9 \quad (1)\\ y+2z &= 3 \quad (4)\\ z &= 2 \quad (6) \end{aligned}$$

Next, we back-substitute $z=2$ into equation (4) and solve for $y$.

$$\begin{aligned} y+2(2) &= 3\\ y+4 &= 3\\ y &= -1 \end{aligned}$$

Finally, we can back-substitute $z=2$ and $y=-1$ into equation (1). This will yield the solution for $x$.

$$\begin{aligned} x-2(-1)+3(2) &= 9\\ x+2+6 &= 9\\ x &= 1 \end{aligned}$$

The solution is the ordered triple $(1,-1,2)$. See Figure 6.3.4.




Figure 6.3.4

**Example 6.3.3: Solving a Real-World Problem Using a System of Three Equations in Three Variables**

In the problem posed at the beginning of the section, John invested his inheritance of $\$12,000$ in three different funds: part in a money-market fund paying $3\%$ interest annually; part in municipal bonds paying $4\%$ annually; and the rest in mutual funds paying $7\%$ annually. John invested $\$4,000$ more in mutual funds than he invested in municipal bonds. The total interest earned in one year was $\$670$. How much did he invest in each type of fund?

**Solution**

To solve this problem, we use all of the information given and set up three equations. First, we assign a variable to each of the three investment amounts:

$$x = \text{amount invested in money-market fund}$$
$$y = \text{amount invested in municipal bonds}$$
$$z = \text{amount invested in mutual funds}$$

The first equation indicates that the sum of the three principal amounts is $\$12,000$.

$$x + y + z = 12,000$$

We form the second equation according to the information that John invested $\$4,000$ more in mutual funds than he invested in municipal bonds.

$$z = y + 4,000$$

The third equation shows that the total amount of interest earned from each fund equals $\$670$.

$$0.03x + 0.04y + 0.07z = 670$$

Then, we write the three equations as a system.

$$\begin{aligned} x + y + z &= 12,000 \\ -y + z &= 4,000 \\ 0.03x + 0.04y + 0.07z &= 670 \end{aligned}$$

To make the calculations simpler, we can multiply the third equation by $100$. Thus,

$$\begin{aligned} x + y + z &= 12,000 \quad (1) \\ -y + z &= 4,000 \quad (2) \\ 3x + 4y + 7z &= 67,000 \quad (3) \end{aligned}$$

Step 1. Interchange equation (2) and equation (3) so that the two equations with three variables will line up.

$$\begin{aligned} x+y+z &= 12,000 \\ 3x+4y+7z &= 67,000 \\ -y+z &= 4,000 \end{aligned}$$

Step 2. Multiply equation (1) by $-3$ and add to equation (2). Write the result as row 2.

$$\begin{aligned} x+y+z &= 12,000 \\ y+4z &= 31,000 \\ -y+z &= 4,000 \end{aligned}$$

Step 3. Add equation (2) to equation (3) and write the result as equation (3).

$$\begin{aligned} x+y+z &= 12,000 \\ y+4z &= 31,000 \\ 5z &= 35,000 \end{aligned}$$

Step 4. Solve for $z$ in equation (3). Back-substitute that value in equation (2) and solve for $y$. Then, back-substitute the values for $z$ and $y$ into equation (1) and solve for $x$.

$$\begin{aligned} 5z &= 35,000 \\ z &= 7,000 \end{aligned}$$

$$\begin{aligned} y+4(7,000) &= 31,000 \\ y &= 3,000 \end{aligned}$$

$$\begin{aligned} x+3,000+7,000 &= 12,000 \\ x &= 2,000 \end{aligned}$$

John invested $\$2,000$ in a money-market fund, $\$3,000$ in municipal bonds, and $\$7,000$ in mutual funds.

**? Exercise 6.3.1**

Solve the system of equations in three variables.

$$\begin{aligned} 2x+y-2z &= -1 \\ 3x-3y-z &= 5 \\ x-2y+3z &= 6 \end{aligned}$$

**Answer**

$(1,-1,1)$

### Identifying Inconsistent Systems of Equations Containing Three Variables

Just as with systems of equations in two variables, we may come across an inconsistent system of equations in three variables, which means that it does not have a solution that satisfies all three equations. The equations could represent three parallel planes, two parallel planes and one intersecting plane, or three planes that intersect the other two but not at the same location. The process of elimination will result in a false statement, such as $3=7$ or some other contradiction.

**✓ Example 6.3.4: Solving an Inconsistent System of Three Equations in Three Variables**

Solve the following system.

$$x-3y+z=4 \quad (6.3.1)$$
$$-x+2y-5z=3 \quad (6.3.2)$$
$$5x-13y+13z=8 \quad (6.3.3)$$

**Solution**

Looking at the coefficients of $x$, we can see that we can eliminate $x$ by adding Equation 6.3.1 to Equation 6.3.2.

$$\begin{aligned} x-3y+z&=4\,(1)\\ -x+2y-5z&=3\,(2)\\ \hline -y-4z&=7\,(4)\end{aligned}$$

Next, we multiply equation (1) by $-5$ and add it to equation (3).

$$\begin{aligned} -5x+15y-5z&=-20\,(1) \quad \text{multiplied by } -5\\ 5x-13y+13z&=8\,(3)\\ \hline 2y+8z&=-12\,(5)\end{aligned}$$

Then, we multiply equation (4) by 2 and add it to equation (5).

$$\begin{aligned} -2y-8z&=14\,(4) \quad \text{multiplied by } 2\\ 2y+8z&=-12\,(5)\\ \hline 0&=2\end{aligned}$$

The final equation $0=2$ is a contradiction, so we conclude that the system of equations in inconsistent and, therefore, has no solution.

**Analysis**

In this system, each plane intersects the other two, but not at the same location. Therefore, the system is inconsistent.

**? Exercise 6.3.2**

Solve the system of three equations in three variables.

$$x+y+z=2$$
$$y-3z=1$$
$$2x+y+5z=0$$

**Answer**

No solution.

### Expressing the Solution of a System of Dependent Equations Containing Three Variables

We know from working with systems of equations in two variables that a dependent system of equations has an infinite number of solutions. The same is true for dependent systems of equations in three variables. An infinite number of solutions can result from several situations. The three planes could be the same, so that a solution to one equation will be the solution to the other two equations. All three equations could be different but they intersect on a line, which has infinite solutions. Or two of the equations could be the same and intersect the third on a line.

**✓ Example 6.3.5: Finding the Solution to a Dependent System of Equations**

Find the solution to the given system of three equations in three variables.

$$2x+y-3z=0 \quad (1)$$
$$4x+2y-6z=0 \quad (2)$$
$$x-y+z=0 \quad (3)$$

**Solution**

First, we can multiply equation (1) by $-2$ and add it to equation (2).

$$-4x-2y+6z=0\ (1) \quad \text{multiplied by } -2$$
$$\underline{4x+2y-6z=0\,(2)}$$
$$0=0$$

We do not need to proceed any further. The result we get is an identity, $0=0$, which tells us that this system has an infinite number of solutions. There are other ways to begin to solve this system, such as multiplying equation (3) by $-2$, and adding it to equation (1). We then perform the same steps as above and find the same result, $0=0$.

When a system is dependent, we can find general expressions for the solutions. Adding equations (1) and (3), we have

$$2x+y-3z=0$$
$$x-y+z=0$$
$$3x-2z=0$$

We then solve the resulting equation for $z$.

$$3x-2z=0$$
$$z=\frac{3}{2}x$$

We back-substitute the expression for $z$ into one of the equations and solve for $y$.

$$2x+y-3\left(\frac{3}{2}x\right)=0$$
$$2x+y-\frac{9}{2}x=0$$
$$y=\frac{9}{2}x-2x$$
$$y=\frac{5}{2}x$$

So the general solution is $\left(x,\frac{5}{2}x,\frac{3}{2}x\right)$. In this solution, $x$ can be any real number. The values of $y$ and $z$ are dependent on the value selected for $x$.

**Analysis**

As shown in Figure 6.3.5, two of the planes are the same and they intersect the third plane on a line. The solution set is infinite, as all points along the intersection line will satisfy all three equations.





Figure 6.3.5

**Q&A: Does the generic solution to a dependent system always have to be written in terms of $x$?**

No, you can write the generic solution in terms of any of the variables, but it is common to write it in terms of $x$ and if needed $x$ and $y$.

**Exercise 6.3.3:**

Solve the following system.

$$\begin{aligned} x+y+z &= 7 \\ 3x-2y-z &= 4 \\ x+6y+5z &= 24 \end{aligned}$$

**Answer**

Infinite number of solutions of the form $(x, 4x-11, -5x+18)$.

**Media**

Access these online resources for additional instruction and practice with systems of equations in three variables.

- Ex 1: System of Three Equations with Three Unknowns Using Elimination
- Ex. 2: System of Three Equations with Three Unknowns Using Elimination

## Key Concepts

- A solution set is an ordered triple {(x,y,z)} that represents the intersection of three planes in space. See Example 6.3.1.
- A system of three equations in three variables can be solved by using a series of steps that forces a variable to be eliminated. The steps include interchanging the order of equations, multiplying both sides of an equation by a nonzero constant, and adding a nonzero multiple of one equation to another equation. See Example 6.3.2.
- Systems of three equations in three variables are useful for solving many different types of real-world problems. See Example 6.3.3.
- A system of equations in three variables is inconsistent if no solution exists. After performing elimination operations, the result is a contradiction. See Example 6.3.4.
- Systems of equations in three variables that are inconsistent could result from three parallel planes, two parallel planes and one intersecting plane, or three planes that intersect the other two but not at the same location.
- A system of equations in three variables is dependent if it has an infinite number of solutions. After performing elimination operations, the result is an identity. See Example 6.3.5.
- Systems of equations in three variables that are dependent could result from three identical planes, three planes intersecting at a line, or two identical planes that intersect the third on a line.

### Contributors

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.

This page titled 6.3: Systems of Linear Equations with Three Variables is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.2: Systems of Linear Equations with Three Variables** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 6.3E: Systems of Linear Equations with Three Variables (Exercises)

For the following exercises, solve the system of three equations using substitution or addition.

11.

$0.5x - 0.5y = 10$

$-0.2y + 0.2x = 4$
$0.1x + 0.1z = 2$

12.

$5x + 3y - z = 5$

$3x - 2y + 4z = 13$
$4x + 3y + 5z = 22$

13.

$x + y + z = 1$

$2x + 2y + 2z = 1$
$3x + 3y = 2$

14.

$2x - 3y + z = -1$

$x + y + z = -4$
$4x + 2y - 3z = 33$

15.

$3x + 2y - z = -10$

$x - y + 2z = 7$
$-x + 3y + z = -2$

16.

$3x + 4z = -11$

$x - 2y = 5$
$4y - z = -10$

17.

$2x - 3y + z = 0$

$2x + 4y - 3z = 0$
$6x - 2y - z = 0$

18.

$6x - 4y - 2z = 2$

$3x + 2y - 5z = 4$
$6y - 7z = 5$

For the following exercises, write a system of equations to solve each problem. Solve the system of equations.

19. Three odd numbers sum up to 61 . The smaller is one-third the larger and the middle number is 16 less than the larger. What are the three numbers?

20. A local theatre sells out for their show. They sell all 500 tickets for a total purse of $\$8,070.00$.The tickets were priced at $\$15$ for students, $\$12$ for children, and $\$18$ for adults. If the band sold three times as many adult tickets as children's tickets, how many of each type was sold?

This page titled 6.3E: Systems of Linear Equations with Three Variables (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.2E: Systems of Linear Equations with Three Variables (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 6.4: Systems of Nonlinear Equations and Inequalities - Two Variables

**Learning Objectives**

- Solve a system of nonlinear equations using substitution.
- Solve a system of nonlinear equations using elimination.
- Graph a nonlinear inequality.
- Graph a system of nonlinear inequalities.

Halley's Comet (Figure 6.4.1) orbits the sun about once every 75 years. Its path can be considered to be a very elongated ellipse. Other comets follow similar paths in space. These orbital paths can be studied using systems of equations. These systems, however, are different from the ones we considered in the previous section because the equations are not linear.



***Figure* 6.4.1*:*** *Halley's Comet (credit: "NASA Blueshift"/Flickr)*

In this section, we will consider the intersection of a parabola and a line, a circle and a line, and a circle and an ellipse. The methods for solving systems of nonlinear equations are similar to those for linear equations.

## Solving a System of Nonlinear Equations Using Substitution

A system of nonlinear equations is a system of two or more equations in two or more variables containing at least one equation that is not linear. Recall that a linear equation can take the form $Ax + By + C = 0$ . Any equation that cannot be written in this form in nonlinear. The substitution method we used for linear systems is the same method we will use for nonlinear systems. We solve one equation for one variable and then substitute the result into the second equation to solve for another variable, and so on. There is, however, a variation in the possible outcomes.

### Intersection of a Parabola and a Line

There are three possible types of solutions for a system of nonlinear equations involving a parabola and a line.

**Possible Types of Solutions For Points of Intersection of a Parabola and a Line**

Figure 6.4.2 illustrates possible solution sets for a system of equations involving a parabola and a line.

- No solution - The line will never intersect the parabola.
- One solution - The line is tangent to the parabola and intersects the parabola at exactly one point.
- Two solutions - The line crosses on the inside of the parabola and intersects the parabola at two points.





***Figure* 6.4.2**

**How to: Given a system of equations containing a line and a parabola, find the solution**

1. Solve the linear equation for one of the variables.
2. Substitute the expression obtained in step one into the parabola equation.
3. Solve for the remaining variable.
4. Check your solutions in both equations.

**Example 6.4.1: Solving a System of Nonlinear Equations Representing a Parabola and a Line**

Solve the system of equations.

$$\begin{aligned} x-y &= -1 \\ y &= x^2+1 \end{aligned}$$

**Solution**

Solve the first equation for $x$ and then substitute the resulting expression into the second equation.

$$\begin{aligned} x-y &= -1 \\ x &= y-1 \qquad \text{Solve for } x. \end{aligned}$$

$$\begin{aligned} y &= x^2+1 \\ y &= (y-1)^2+1 \qquad \text{Substitute expression for } x. \end{aligned}$$

Expand the equation and set it equal to zero.

$$\begin{aligned} y &= (y-1)^2+1 \\ &= (y^2-2y+1)+1 \\ &= y^2-2y+2 \\ 0 &= y^2-3y+2 \\ &= (y-2)(y-1) \end{aligned}$$

Solving for $y$ gives $y=2$ and $y=1$. Next, substitute each value for $y$ into the first equation to solve for $x$. Always substitute the value into the linear equation to check for extraneous solutions.

$$\begin{aligned} x-y &= -1 \\ x-(2) &= -1 \\ x &= 1 \\ x-(1) &= -1 \\ x &= 0 \end{aligned}$$

The solutions are $(1, 2)$ and $(0, 1)$,which can be verified by substituting these $(x, y)$ values into both of the original equations (Figure 6.4.3).





***Figure* 6.4.3**

**Q&A: Could we have substituted values for $y$ into the second equation to solve for $x$ in last example?**

Yes, but because $x$ is squared in the second equation this could give us extraneous solutions for $x$.

For $y = 1$

$$\begin{aligned} y &= x^2 + 1 \\ y &= x^2 + 1 \\ x^2 &= 0 \\ x &= \pm\sqrt{0} = 0 \end{aligned}$$

This gives us the same value as in the solution.

For $y = 2$

$$\begin{aligned} y &= x^2 + 1 \\ 2 &= x^2 + 1 \\ x^2 &= 1 \\ x &= \pm\sqrt{1} = \pm 1 \end{aligned}$$

Notice that $-1$ is an extraneous solution.

**Exercise 6.4.1**

Solve the given system of equations by substitution.

$$\begin{aligned} 3x - y &= -2 \\ 2x^2 - y &= 0 \end{aligned}$$

**Answer**

$\left(-\frac{1}{2}, \frac{1}{2}\right)$ and $(2, 8)$

## Intersection of a Circle and a Line

Just as with a parabola and a line, there are three possible outcomes when solving a system of equations representing a circle and a line.

## POSSIBLE TYPES OF SOLUTIONS FOR THE POINTS OF INTERSECTION OF A CIRCLE AND A LINE

Figure 6.4.4 illustrates possible solution sets for a system of equations involving a circle and a line.

- No solution - The line does not intersect the circle.
- One solution - The line is tangent to the circle and intersects the circle at exactly one point.
- Two solutions - The line crosses the circle and intersects it at two points.





***Figure* 6.4.4**

## How to: Given a system of equations containing a line and a circle, find the solution

1. Solve the linear equation for one of the variables.
2. Substitute the expression obtained in step one into the equation for the circle.
3. Solve for the remaining variable.
4. Check your solutions in both equations.

## Example 6.4.2: Finding the Intersection of a Circle and a Line by Substitution

Find the intersection of the given circle and the given line by substitution.

$$\begin{aligned} x^2+y^2 &= 5 \\ y &= 3x-5 \end{aligned}$$

**Solution**

One of the equations has already been solved for $y$. We will substitute $y=3x-5$ into the equation for the circle.

$$\begin{aligned} x^2+(3x-5)^2 &= 5 \\ x^2+9x^2-30x+25 &= 5 \\ 10x^2-30x+20 &= 0 \end{aligned}$$

Now, we factor and solve for $x$.

$$\begin{aligned} 10(x2-3x+2) &= 0 \\ 10(x-2)(x-1) &= 0 \\ x &= 2 \\ x &= 1 \end{aligned}$$

Substitute the two $x$-values into the original linear equation to solve for $y$.

$$\begin{aligned} y &= 3(2)-5 \\ &= 1 \\ y &= 3(1)-5 \\ &= -2 \end{aligned}$$

The line intersects the circle at $(2,1)$ and $(1,-2)$,which can be verified by substituting these $(x,y)$ values into both of the original equations (Figure 6.4.5).





***Figure* 6.4.5**

**? Exercise 6.4.2**

Solve the system of nonlinear equations.

$$\begin{aligned} x^2+y^2 &= 10 \\ x-3y &= -10 \end{aligned}$$

**Answer**

$(-1,3)$

## Solving a System of Nonlinear Equations Using Elimination

We have seen that substitution is often the preferred method when a system of equations includes a linear equation and a nonlinear equation. However, when both equations in the system have like variables of the second degree, solving them using elimination by addition is often easier than substitution. Generally, elimination is a far simpler method when the system involves only two equations in two variables (a two-by-two system), rather than a three-by-three system, as there are fewer steps. As an example, we will investigate the possible types of solutions when solving a system of equations representing a circle and an ellipse.

**POSSIBLE TYPES OF SOLUTIONS FOR THE POINTS OF INTERSECTION OF A CIRCLE AND AN ELLIPSE**

Figure 6.4.6 illustrates possible solution sets for a system of equations involving a circle and an ellipse.

- No solution - The circle and ellipse do not intersect. One shape is inside the other or the circle and the ellipse are a distance away from the other.
- One solution - The circle and ellipse are tangent to each other, and intersect at exactly one point.
- Two solutions - The circle and the ellipse intersect at two points.
- Three solutions - The circle and the ellipse intersect at three points.
- Four solutions - The circle and the ellipse intersect at four points.





***Figure* 6.4.6**

**Example 6.4.3: Solving a System of Nonlinear Equations Representing a Circle and an Ellipse**

Solve the system of nonlinear equations.

$$\begin{aligned} x^2+y^2 &= 26 \quad (1)\\ 3x^2+25y^2 &= 100 \quad (2)\end{aligned}$$

**Solution**

Let's begin by multiplying equation (1) by $-3$,and adding it to equation (2).

$$\begin{aligned} (-3)(x^2+y^2) &= (-3)(26)\\ -3x^2-3y^2 &= -78\\ 3x^2+25y^2 &= 100\\ \hline 22y^2 &= 22\end{aligned}$$

After we add the two equations together, we solve for $y$.

$$\begin{aligned} y^2 &= 1\\ y &= \pm\sqrt{1} = \pm 1\end{aligned}$$

Substitute $y = \pm 1$ into one of the equations and solve for $x$.

$$\begin{aligned} x^2+(1)^2 &= 26\\ x^2+1 &= 26\\ x^2 &= 25\\ x &= \pm\sqrt{25} = \pm 5\\ x^2+(-1)^2 &= 26\\ x^2+1 &= 26\\ x^2 &= \pm\sqrt{25} = \pm 5\end{aligned}$$

There are four solutions: $(5,1)$, $(-5,1)$, $(5,-1)$,and $(-5,-1)$. See Figure 6.4.7.





***Figure* 6.4.7**

**? Exercise 6.4.3**

Find the solution set for the given system of nonlinear equations.

$$\begin{aligned} 4x^2+y^2 &= 13 \\ x^2+y^2 &= 10 \end{aligned}$$

**Answer**

$(1,3),(1,-3),(-1,3),(-1,-3)$

## Graphing a Nonlinear Inequality

All of the equations in the systems that we have encountered so far have involved equalities, but we may also encounter systems that involve inequalities. We have already learned to graph linear inequalities by graphing the corresponding equation, and then shading the region represented by the inequality symbol. Now, we will follow similar steps to graph a nonlinear **inequality** so that we can learn to solve systems of nonlinear inequalities. A **nonlinear inequality** is an inequality containing a nonlinear expression. Graphing a nonlinear inequality is much like graphing a linear inequality.

Recall that when the inequality is greater than, $y > a$,or less than, $y < a$,the graph is drawn with a dashed line. When the inequality is greater than or equal to, $y \geq a$,or less than or equal to, $y \leq a$,the graph is drawn with a solid line. The graphs will create regions in the plane, and we will test each region for a solution. If one point in the region works, the whole region works. That is the region we shade (Figure 6.4.8).




*Figure* **6.4.8:** *(a) an example of $y > a$; (b) an example of $y \geq a$; (c) an example of $y < a$; (d) an example of $y \leq a$*

**How to: Given an inequality bounded by a parabola, sketch a graph**

1. Graph the parabola as if it were an equation. This is the boundary for the region that is the solution set.
2. If the boundary is included in the region (the operator is $\leq$ or $\geq$), the parabola is graphed as a solid line.
3. If the boundary is not included in the region (the operator is $<$ or $>$), the parabola is graphed as a dashed line.
4. Test a point in one of the regions to determine whether it satisfies the inequality statement. If the statement is true, the solution set is the region including the point. If the statement is false, the solution set is the region on the other side of the boundary line.
5. Shade the region representing the solution set.

**Example 6.4.4: Graphing an Inequality for a Parabola**

Graph the inequality $y > x^2 + 1$ .

**Solution**

First, graph the corresponding equation $y = x^2 + 1$ . Since $y > x^2 + 1$ has a greater than symbol, we draw the graph with a dashed line. Then we choose points to test both inside and outside the parabola. Let's test the points

$(0, 2)$ and $(2, 0)$. One point is clearly inside the parabola and the other point is clearly outside.

$$\begin{aligned} y &> x^2 + 1 \\ 2 &> (0)^2 + 1 \\ 2 &> 1 \qquad \text{True} \end{aligned}$$

$$\begin{aligned} 0 &> (2)^2 + 1 \\ 0 &> 5 \qquad \text{False} \end{aligned}$$

The graph is shown in Figure 6.4.9. We can see that the solution set consists of all points inside the parabola, but not on the graph itself.





*Figure* **6.4.9**

## Graphing a System of Nonlinear Inequalities

Now that we have learned to graph nonlinear inequalities, we can learn how to graph systems of nonlinear inequalities. A **system of nonlinear inequalities** is a system of two or more inequalities in two or more variables containing at least one inequality that is not linear. Graphing a system of nonlinear inequalities is similar to graphing a system of linear inequalities. The difference is that our graph may result in more shaded regions that represent a solution than we find in a system of linear inequalities. The solution to a nonlinear system of inequalities is the region of the graph where the shaded regions of the graph of each inequality overlap, or where the regions intersect, called the **feasible region**.

**How to: Given a system of nonlinear inequalities, sketch a graph**

1. Find the intersection points by solving the corresponding system of nonlinear equations.
2. Graph the nonlinear equations.
3. Find the shaded regions of each inequality.
4. Identify the feasible region as the intersection of the shaded regions of each inequality or the set of points common to each inequality.

**Example 6.4.5: Graphing a System of Inequalities**

Graph the given system of inequalities.

$$\begin{aligned} x^2 - y &\leq 0 \\ 2x^2 + y &\leq 12 \end{aligned}$$

**Solution**

These two equations are clearly parabolas. We can find the points of intersection by the elimination process: Add both equations and the variable $y$ will be eliminated. Then we solve for $x$.

$$\begin{aligned} x^2 - y &= 0 \\ \underline{2x^2 + y} &= \underline{12} \\ 3x^2 &= 12 \\ x^2 &= 4 \\ x &= \pm 2 \end{aligned}$$

Substitute the $x$-values into one of the equations and solve for $y$.

$$\begin{aligned} x^2 - y &= 0 \\ (2)^2 - y &= 0 \\ 4 - y &= 0 \\ y &= 4 \end{aligned}$$

$$\begin{aligned} (-2)^2 - y &= 0 \\ 4 - y &= 0 \\ y &= 4 \end{aligned}$$

The two points of intersection are $(2, 4)$ and $(-2, 4)$. Notice that the equations can be rewritten as follows.

$$\begin{aligned} x^2 - y &\leq 0 \\ x^2 &\leq y \\ y &\geq x^2 \end{aligned}$$

$$\begin{aligned} 2x^2 + y &\leq 12 \\ y &\leq -2x^2 + 12 \end{aligned}$$

Graph each inequality. See Figure 6.4.10. The feasible region is the region between the two equations bounded by $2x^2 + y \leq 12$ on the top and $x^2 - y \leq 0$ on the bottom.





***Figure* 6.4.10**

## Exercise 6.4.5

Graph the given system of inequalities.

$$y \geq x^2 - 1$$
$$x - y \geq -1$$

**Answer**

Shade the area bounded by the two curves, above the quadratic and below the line.





***Figure* 6.4.11**

## Media

Access these online resources for additional instruction and practice with nonlinear equations.

- Solve a System of Nonlinear Equations Using Substitution
- Solve a System of Nonlinear Equations Using Elimination

## Key Concepts

- There are three possible types of solutions to a system of equations representing a line and a parabola: (1) no solution, the line does not intersect the parabola; (2) one solution, the line is tangent to the parabola; and (3) two solutions, the line intersects the

parabola in two points. See Example 6.4.1.

- There are three possible types of solutions to a system of equations representing a circle and a line: (1) no solution, the line does not intersect the circle; (2) one solution, the line is tangent to the parabola; (3) two solutions, the line intersects the circle in two points. See Example 6.4.2.
- There are five possible types of solutions to the system of nonlinear equations representing an ellipse and a circle: (1) no solution, the circle and the ellipse do not intersect; (2) one solution, the circle and the ellipse are tangent to each other; (3) two solutions, the circle and the ellipse intersect in two points; (4) three solutions, the circle and ellipse intersect in three places; (5) four solutions, the circle and the ellipse intersect in four points. See Example 6.4.3.
- An inequality is graphed in much the same way as an equation, except for > or <, we draw a dashed line and shade the region containing the solution set. See Example 6.4.4.
- Inequalities are solved the same way as equalities, but solutions to systems of inequalities must satisfy both inequalities. See Example 6.4.5.

## Contributors and Attributions

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.

---

This page titled 6.4: Systems of Nonlinear Equations and Inequalities - Two Variables is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.3: Systems of Nonlinear Equations and Inequalities - Two Variables** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 6.4E: Systems of Nonlinear Equations and Inequalities - Two Variables (Exercises)

For the following exercises, solve the system of nonlinear equations.

21. $y = x^2 - 7$

$$y = 5x - 13 \tag{6.4E.1}$$

22. $y = x^2 - 4$

$$y = 5x + 10 \tag{6.4E.2}$$

23.
$x^2 + y^2 = 16$
$y = x - 8$

24
$x^2 + y^2 = 25$
$y = x^2 + 5$

25.

$x^2 + y^2 = 4$

$y - x^2 = 3$

For the following exercises, graph the inequality.

26. $y > x^2 - 1$

27. $\frac{1}{4}x^2 + y^2 < 4$

For the following exercises, graph the system of inequalities.

28

$x^2 + y^2 + 2x < 3$
$y > -x^2 - 3$

29.

$x^2 - 2x + y^2 - 4x < 4$
$y < -x + 4$

30.

$x^2 + y^2 < 1$
$y^2 < x$

---

This page titled 6.4E: Systems of Nonlinear Equations and Inequalities - Two Variables (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.3E: Systems of Nonlinear Equations and Inequalities - Two Variables (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 6.5: Solving Systems with Gaussian Elimination

**Learning Objectives**

- Write the augmented matrix of a system of equations.
- Write the system of equations from an augmented matrix.
- Perform row operations on a matrix.
- Solve a system of linear equations using matrices.

Carl Friedrich Gauss lived during the late $18^{th}$ century and early $19^{th}$ century, but he is still considered one of the most prolific mathematicians in history. His contributions to the science of mathematics and physics span fields such as algebra, number theory, analysis, differential geometry, astronomy, and optics, among others. His discoveries regarding matrix theory changed the way mathematicians have worked for the last two centuries.



Figure 6.5.1: German mathematician Carl Friedrich Gauss (1777–1855).

We first encountered Gaussian elimination in Systems of Linear Equations: Two Variables. In this section, we will revisit this technique for solving systems, this time using matrices.

## Writing the Augmented Matrix of a System of Equations

A matrix can serve as a device for representing and solving a system of equations. To express a system in matrix form, we extract the coefficients of the variables and the constants, and these become the entries of the matrix. We use a vertical line to separate the coefficient entries from the constants, essentially replacing the equal signs. When a system is written in this form, we call it an **augmented matrix**.

For example, consider the following $2 \times 2$ system of equations.

$$\begin{aligned} 3x+4y &= 7 \\ 4x-2y &= 5 \end{aligned}$$

We can write this system as an augmented matrix:

$$\left[\begin{array}{cc|c} 3 & 4 & 7 \\ 4 & -2 & 5 \end{array}\right]$$

We can also write a matrix containing just the coefficients. This is called the **coefficient matrix.**

$$\begin{bmatrix} 3 & 4 \\ 4 & -2 \end{bmatrix}$$

A three-by-three **system of equations** such as

$$\begin{aligned} 3x-y-z &= 0 \\ x+y &= 5 \\ 2x-3z &= 2 \end{aligned}$$

has a coefficient matrix

$$\begin{bmatrix} 3 & -1 & -1 \\ 1 & 1 & 0 \\ 2 & 0 & -3 \end{bmatrix}$$

and is represented by the augmented matrix

$$\left[\begin{array}{ccc|c} 3 & -1 & -1 & 0 \\ 1 & 1 & 0 & 5 \\ 2 & 0 & -3 & 2 \end{array}\right]$$

Notice that the matrix is written so that the variables line up in their own columns: $x$-terms go in the first column, $y$-terms in the second column, and $z$-terms in the third column. It is very important that each equation is written in standard form $ax+by+cz=d$ so that the variables line up. When there is a missing variable term in an equation, the coefficient is $0$.

**How to: Given a system of equations, write an augmented matrix**

1. Write the coefficients of the $x$-terms as the numbers down the first column.
2. Write the coefficients of the $y$-terms as the numbers down the second column.
3. If there are $z$-terms, write the coefficients as the numbers down the third column.
4. Draw a vertical line and write the constants to the right of the line.

**Example 6.5.1: Writing the Augmented Matrix for a System of Equations**

Write the augmented matrix for the given system of equations.

$$\begin{aligned} x+2y-z &= 3 \\ 2x-y+2z &= 6 \\ x-3y+3z &= 4 \end{aligned}$$

**Solution**

The augmented matrix displays the coefficients of the variables, and an additional column for the constants.

$$\left[\begin{array}{ccc|c} 1 & 2 & -1 & 3 \\ 2 & -1 & 2 & 6 \\ 1 & -3 & 3 & 4 \end{array}\right]$$

**Exercise 6.5.1**

Write the augmented matrix of the given system of equations.

$$\begin{aligned} 4x-3y &= 11 \\ 3x+2y &= 4 \end{aligned}$$

**Answer**

$$\left[\begin{array}{cc|c} 4 & -3 & 11 \\ 3 & 2 & 4 \end{array}\right]$$

## Writing a System of Equations from an Augmented Matrix

We can use augmented matrices to help us solve systems of equations because they simplify operations when the systems are not encumbered by the variables. However, it is important to understand how to move back and forth between formats in order to make finding solutions smoother and more intuitive. Here, we will use the information in an augmented matrix to write the system of equations in standard form.

### Example 6.5.2: Writing a System of Equations from an Augmented Matrix Form

Find the system of equations from the augmented matrix.

$$\left[\begin{array}{ccc|c} 1 & -3 & -5 & -2 \\ 2 & -5 & -4 & 5 \\ -3 & 5 & 4 & 6 \end{array}\right]$$

**Solution**

When the columns represent the variables $x$, $y$, and $z$,

$$\left[\begin{array}{ccc|c} 1 & -3 & -5 & -2 \\ 2 & -5 & -4 & 5 \\ -3 & 5 & 4 & 6 \end{array}\right] \rightarrow \begin{aligned} x-3y-5z &= -2 \\ 2x-5y-4z &= 5 \\ -3x+5y+4z &= 6 \end{aligned}$$

### Exercise 6.5.2

Write the system of equations from the augmented matrix.

$$\left[\begin{array}{ccc|c} 1 & -1 & 1 & 5 \\ 2 & -1 & 3 & 1 \\ 0 & 1 & 1 & -9 \end{array}\right]$$

**Answer**

$$\begin{aligned} x-y+z &= 5 \\ 2x-y+3z &= 1 \\ y+z &= -9 \end{aligned}$$

## Performing Row Operations on a Matrix

Now that we can write systems of equations in augmented matrix form, we will examine the various **row operations** that can be performed on a matrix, such as addition, multiplication by a constant, and interchanging rows.

Performing row operations on a matrix is the method we use for solving a system of equations. In order to solve the system of equations, we want to convert the matrix to **row-echelon** form, in which there are ones down the **main diagonal** from the upper left corner to the lower right corner, and zeros in every position below the main diagonal as shown.

$$\text{Row-echelon form } \begin{bmatrix} 1 & a & b \\ 0 & 1 & d \\ 0 & 0 & 1 \end{bmatrix}$$

We use row operations corresponding to equation operations to obtain a new matrix that is **row-equivalent** in a simpler form. Here are the guidelines to obtaining row-echelon form.

1. In any nonzero row, the first nonzero number is a 1. It is called a *leading* 1.
2. Any all-zero rows are placed at the bottom on the matrix.
3. Any leading 1 is below and to the right of a previous leading 1.
4. Any column containing a leading 1 has zeros in all other positions in the column.

To solve a system of equations we can perform the following row operations to convert the **coefficient matrix** to row-echelon form and do back-substitution to find the solution.

1. Interchange rows. (Notation: $R_i \leftrightarrow R_j$)
2. Multiply a row by a constant. (Notation: $cR_i$)
3. Add the product of a row multiplied by a constant to another row. (Notation: $R_i + cR_j$)

Each of the row operations corresponds to the operations we have already learned to solve systems of equations in three variables. With these operations, there are some key moves that will quickly achieve the goal of writing a matrix in row-echelon form. To

obtain a matrix in row-echelon form for finding solutions, we use Gaussian elimination, a method that uses row operations to obtain a 1 as the first entry so that row 1 can be used to convert the remaining rows.

### GAUSSIAN ELIMINATION

The Gaussian elimination method refers to a strategy used to obtain the row-echelon form of a matrix. The goal is to write matrix $A$ with the number 1 as the entry down the main diagonal and have all zeros below.

$$A=\begin{bmatrix} a_{11} & a_{12} & a_{13} \\ a_{21} & a_{22} & a_{23} \\ a_{31} & a_{32} & a_{33} \end{bmatrix} \xrightarrow{After\ Gaussian\ elimination} A=\begin{bmatrix} 1 & b_{12} & b_{13} \\ 0 & 1 & b_{23} \\ 0 & 0 & 1 \end{bmatrix}$$

The first step of the Gaussian strategy includes obtaining a 1 as the first entry, so that row 1 may be used to alter the rows below.

### How to: Given an augmented matrix, perform row operations to achieve row-echelon form

1. The first equation should have a leading coefficient of 1. Interchange rows or multiply by a constant, if necessary.
2. Use row operations to obtain zeros down the first column below the first entry of 1.
3. Use row operations to obtain a 1 in row 2, column 2.
4. Use row operations to obtain zeros down column 2, below the entry of 1.
5. Use row operations to obtain a 1 in row 3, column 3.
6. Continue this process for all rows until there is a \(1 in every entry down the main diagonal and there are only zeros below.
7. If any rows contain all zeros, place them at the bottom.

### Example 6.5.3: Solving a $2\times 2$ System by Gaussian Elimination

Solve the given system by Gaussian elimination.

$$\begin{aligned} 2x+3y &= 6 \\ x-y &= \frac{1}{2} \end{aligned}$$

**Solution**

First, we write this as an augmented matrix.

$$\left[\begin{array}{cc|c} 2 & 3 & 6 \\ 1 & -1 & \frac{1}{2} \end{array}\right]$$

We want a 1 in row 1, column 1. This can be accomplished by interchanging row 1 and row 2.

$$R_1 \leftrightarrow R_2 \rightarrow \left[\begin{array}{cc|c} 1 & -1 & \frac{1}{2} \\ 2 & 3 & 6 \end{array}\right]$$

We now have a 1 as the first entry in row 1, column 1. Now let's obtain a 0 in row 2, column 1. This can be accomplished by multiplying row 1 by $-2$, and then adding the result to row 2.

$$-2R_1+R_2=R_2 \rightarrow \left[\begin{array}{cc|c} 1 & -1 & \frac{1}{2} \\ 0 & 5 & 5 \end{array}\right]$$

We only have one more step, to multiply row 2 by $\frac{1}{5}$.

$$\frac{1}{5}R_2=R_2 \rightarrow \left[\begin{array}{cc|c} 1 & -1 & \frac{1}{2} \\ 0 & 1 & 1 \end{array}\right]$$

Use back-substitution. The second row of the matrix represents $y = 1$. Back-substitute $y = 1$ into the first equation.

$$x - (1) = \frac{1}{2}$$
$$x = \frac{3}{2}$$

The solution is the point $\left(\frac{3}{2}, 1\right)$.

### Exercise 6.5.3

Solve the given system by Gaussian elimination.

$$4x + 3y = 11$$
$$x - 3y = -1$$

**Answer**

$(2, 1)$

### Example 6.5.4: Using Gaussian Elimination to Solve a System of Equations

Use **Gaussian elimination** to solve the given $2 \times 2$ **system of equations**.

$$2x + y = 1$$
$$4x + 2y = 6$$

**Solution**

Write the system as an **augmented matrix**.

$$\left[\begin{array}{cc|c} 2 & 1 & 1 \\ 4 & 2 & 6 \end{array}\right]$$

Obtain a 1 in row 1, column 1. This can be accomplished by multiplying the first row by $\frac{1}{2}$.

$$\frac{1}{2}R_1 = R_1 \rightarrow \left[\begin{array}{cc|c} 1 & \frac{1}{2} & \frac{1}{2} \\ 4 & 2 & 6 \end{array}\right]$$

Next, we want a 0 in row 2, column 1. Multiply row 1 by $-4$ and add row 1 to row 2.

$$-4R_1 + R_2 = R_2 \rightarrow \left[\begin{array}{cc|c} 1 & \frac{1}{2} & \frac{1}{2} \\ 0 & 0 & 4 \end{array}\right]$$

The second row represents the equation $0 = 4$. Therefore, the system is inconsistent and has no solution.

### Example 6.5.5: Solving a Dependent System

Solve the system of equations.

$$3x + 4y = 12$$
$$6x + 8y = 24$$

**Solution**

Perform **row operations** on the augmented matrix to try and achieve **row-echelon form**.

$$A = \left[\begin{array}{cc|c} 3 & 4 & 12 \\ 6 & 8 & 24 \end{array}\right]$$

$$-\frac{1}{2}R_2+R_1=R_1\rightarrow\left[\begin{array}{cc|c}0&0&0\\6&8&24\end{array}\right]$$

$$R_1\leftrightarrow R_2=\left[\begin{array}{cc|c}6&8&24\\0&0&0\end{array}\right]$$

The matrix ends up with all zeros in the last row: $0y=0$. Thus, there are an infinite number of solutions and the system is classified as dependent. To find the generic solution, return to one of the original equations and solve for $y$.

$$\begin{aligned}3x+4y&=12\\4y&=12-3x\\y&=3-\frac{3}{4}x\end{aligned}$$

So the solution to this system is $\left(x,3-\frac{3}{4}x\right)$.

### Example 6.5.6: Performing Row Operations on a $3\times3$ Augmented Matrix to Obtain Row-Echelon Form

Perform row operations on the given matrix to obtain row-echelon form.

$$\left[\begin{array}{ccc|c}1&-3&4&3\\2&-5&6&6\\-3&3&4&6\end{array}\right]$$

**Solution**

The first row already has a 1 in row 1, column 1. The next step is to multiply row 1 by $-2$ and add it to row 2. Then replace row 2 with the result.

$$-2R_1+R_2=R_2\left[\begin{array}{ccc|c}1&-3&4&3\\0&1&-2&0\\-3&3&4&6\end{array}\right]$$

Next, obtain a zero in row 3, column 1.

$$3R_1+R_3=R_3\left[\begin{array}{ccc|c}1&-3&4&3\\0&1&-2&0\\0&-6&16&15\end{array}\right]$$

Next, obtain a zero in row 3, column 2.

$$6R_2+R_3=R_3\left[\begin{array}{ccc|c}1&-3&4&3\\0&1&-2&0\\0&0&4&15\end{array}\right]$$

The last step is to obtain a 1 in row 3, column 3.

$$\frac{1}{4}R_3=R_3\left[\begin{array}{ccc|c}1&-3&4&3\\0&1&-2&0\\0&0&1&\frac{15}{4}\end{array}\right]$$

### Exercise 6.5.4

Write the system of equations in row-echelon form.

$$\begin{aligned} x-2y+3z &= 9 \\ -x+3y &= -4 \\ 2x-5y+5z &= 17 \end{aligned}$$

**Answer**

$$\left[\begin{array}{ccc|c} 1 & -\frac{5}{2} & \frac{5}{2} & \frac{17}{2} \\ 0 & 1 & 5 & 9 \\ 0 & 0 & 1 & 2 \end{array}\right]$$

## Solving a System of Linear Equations Using Matrices

We have seen how to write a **system of equations** with an **augmented matrix**, and then how to use row operations and back-substitution to obtain row-echelon form. Now, we will take **row-echelon form** a step farther to solve a 3 by 3 system of linear equations. The general idea is to eliminate all but one variable using row operations and then back-substitute to solve for the other variables.

### Example 6.5.7: Solving a System of Linear Equations Using Matrices

Solve the system of linear equations using matrices.

$$\begin{aligned} x-y+z &= 8 \\ 2x+3y-z &= -2 \\ 3x-2y-9z &= 9 \end{aligned}$$

**Solution**

First, we write the augmented matrix.

$$\left[\begin{array}{ccc|c} 1 & -1 & 1 & 8 \\ 2 & 3 & -1 & -2 \\ 3 & -2 & -9 & 9 \end{array}\right]$$

Next, we perform row operations to obtain row-echelon form.

$$-2R_1+R_2=R_2 \rightarrow \left[\begin{array}{ccc|c} 1 & -1 & 1 & 8 \\ 0 & 5 & -3 & -18 \\ 3 & -2 & -9 & 9 \end{array}\right]$$

$$-3R_1+R_3=R_3 \rightarrow \left[\begin{array}{ccc|c} 1 & -1 & 1 & 8 \\ 0 & 5 & -3 & -18 \\ 0 & 1 & -12 & -15 \end{array}\right]$$

The easiest way to obtain a 1 in row 2 of column 1 is to interchange $R_2$ and $R_3$.

$$Interchange\ R_2\ and\ R_3 \rightarrow \left[\begin{array}{ccc|c} 1 & -1 & 1 & 8 \\ 0 & 1 & -12 & -15 \\ 0 & 5 & -3 & -18 \end{array}\right]$$

Then

$$-5R_2+R_3=R_3 \rightarrow \left[\begin{array}{ccc|c} 1 & -1 & 1 & 8 \\ 0 & 1 & -12 & -15 \\ 0 & 0 & 57 & 57 \end{array}\right]$$

$$-\frac{1}{57}R_3=R_3 \rightarrow \left[\begin{array}{ccc|c} 1 & -1 & 1 & 8 \\ 0 & 1 & -12 & -15 \\ 0 & 0 & 1 & 1 \end{array}\right]$$

The last matrix represents the equivalent system.

$$\begin{aligned} x-y+z &= 8 \\ y-12z &= -15 \\ z &= 1 \end{aligned}$$

Using back-substitution, we obtain the solution as $(4,-3,1)$.

### Example 6.5.8: Solving a Dependent System of Linear Equations Using Matrices

Solve the following system of linear equations using matrices.

$$\begin{aligned} -x-2y+z &= -1 \\ 2x+3y &= 2 \\ y-2z &= 0 \end{aligned}$$

**Solution**

Write the augmented matrix.

$$\left[\begin{array}{ccc|c} -1 & -2 & 1 & -1 \\ 2 & 3 & 0 & 2 \\ 0 & 1 & -2 & 0 \end{array}\right]$$

First, multiply row 1 by $-1$ to get a 1 in row 1, column 1. Then, perform **row operations** to obtain row-echelon form.

$$-R_1 \rightarrow \left[\begin{array}{ccc|c} 1 & 2 & -1 & 1 \\ 2 & 3 & 0 & 2 \\ 0 & 1 & -2 & 0 \end{array}\right]$$

$$R_2 \leftrightarrow R_3 \rightarrow \left[\begin{array}{ccc|c} 1 & 2 & -1 & 1 \\ 0 & 1 & -2 & 0 \\ 2 & 3 & 0 & 2 \end{array}\right]$$

$$-2R_1+R_3=R_3 \rightarrow \left[\begin{array}{ccc|c} 1 & 2 & -1 & 1 \\ 0 & 1 & -2 & 0 \\ 0 & -1 & 2 & 0 \end{array}\right]$$

$$R_2+R_3=R_3 \rightarrow \left[\begin{array}{ccc|c} 1 & 2 & -1 & 1 \\ 0 & 1 & -2 & 0 \\ 0 & 0 & 0 & 0 \end{array}\right]$$

The last matrix represents the following system.

$$\begin{aligned} x+2y-z &= 1 \\ y-2z &= 0 \\ 0 &= 0 \end{aligned}$$

We see by the identity $0=0$ that this is a dependent system with an infinite number of solutions. We then find the generic solution. By solving the second equation for $y$ and substituting it into the first equation we can solve for $z$ in terms of $x$.

$$\begin{aligned} x+2y-z &= 1 \\ y &= 2z \\ x+2(2z)-z &= 1 \\ x+3z &= 1 \\ z &= \frac{1-x}{3} \end{aligned}$$

Now we substitute the expression for $z$ into the second equation to solve for $y$ in terms of $x$.

$$\begin{aligned} y-2z &= 0 \\ z &= \frac{1-x}{3} \\ y-2\left(\frac{1-x}{3}\right) &= 0 \\ y &= \frac{2-2x}{3} \end{aligned}$$

The generic solution is $\left(x, \frac{2-2x}{3}, \frac{1-x}{3}\right)$.

### Exercise 6.5.5

Solve the system using matrices.

$$\begin{aligned} x+4y-z &= 4 \\ 2x+5y+8z &= 1 \\ 5x+3y-3z &= 1 \end{aligned}$$

**Answer**

$(1,1,1)$

### Q&A: Can any system of linear equations be solved by Gaussian elimination?

*Yes, a system of linear equations of any size can be solved by Gaussian elimination.*

### How to: Given a system of equations, solve with matrices using a calculator

1. Save the augmented matrix as a matrix variable $[A], [B], [C], \ldots$.
2. Use the **ref(** function in the calculator, calling up each matrix variable as needed.

### Example 6.5.9A: Solving Systems of Equations with Matrices Using a Calculator

Solve the system of equations.

$$\begin{aligned} 5x+3y+9z &= -1 \\ -2x+3y-z &= -2 \\ -x-4y+5z &= 1 \end{aligned}$$

**Solution**

Write the augmented matrix for the system of equations.

$$\left[\begin{array}{ccc|c} 5 & 3 & 9 & -1 \\ -2 & 3 & -1 & -2 \\ -1 & -4 & 5 & 1 \end{array}\right]$$

On the matrix page of the calculator, enter the augmented matrix above as the matrix variable $[A]$.

$$[A] = \left[\begin{array}{ccc|c} 5 & 3 & 9 & -1 \\ -2 & 3 & -1 & -2 \\ -1 & -4 & 5 & 1 \end{array}\right]$$

Use the **ref(** function in the calculator, calling up the matrix variable $[A]$.

**ref([A])**

**Evaluate**

$$\left[\begin{array}{ccc|c} 1 & \frac{3}{5} & \frac{9}{5} & \frac{1}{5} \\ 0 & 1 & \frac{13}{21} & -\frac{4}{7} \\ 0 & 0 & 1 & -\frac{24}{187} \end{array}\right] \rightarrow \begin{aligned} x+\frac{3}{5}y+\frac{9}{5}z &= -\frac{1}{5} \\ y+\frac{13}{21}z &= -\frac{4}{7} \\ z &= -\frac{24}{187} \end{aligned}$$

Using back-substitution, the solution is $\left(\frac{61}{187}, -\frac{92}{187}, -\frac{24}{187}\right)$.

### Example 6.5.9B: Applying $2 \times 2$ Matrices to Finance

Carolyn invests a total of $\$12,000$ in two municipal bonds, one paying $10.5$ interest and the other paying $12$ interest. The annual interest earned on the two investments last year was $\$1,335$. How much was invested at each rate?

**Solution**

We have a system of two equations in two variables. Let $x =$ the amount invested at $10.5$ interest, and $y =$ the amount invested at $12$ interest.

$$\begin{aligned} x+y &= 12,000 \\ 0.105x+0.12y &= 1,335 \end{aligned}$$

As a matrix, we have

$$\left[\begin{array}{cc|c} 1 & 1 & 12,000 \\ 0.105 & 0.12 & 1,335 \end{array}\right]$$

Multiply row $1$ by $-0.105$ and add the result to row $2$.

$$\left[\begin{array}{cc|c} 1 & 1 & 12,000 \\ 0 & 0.015 & 75 \end{array}\right]$$

Then,

$$\begin{aligned} 0.015y &= 75 \\ y &= 5,000 \end{aligned}$$

So $12,000-5,000=7,000$.

Thus, $\$5,000$ was invested at $12$ interest and $\$7,000$ at $10.5$ interest.

### Example 6.5.10: Applying $3 \times 3$ Matrices to Finance

Ava invests a total of $\$10,000$ in three accounts, one paying $5$ interest, another paying $8$ interest, and the third paying $9$ interest. The annual interest earned on the three investments last year was $\$770$. The amount invested at $9$ was twice the amount invested at $5$. How much was invested at each rate?

**Solution**

We have a system of three equations in three variables. Let $x$ be the amount invested at $5$ interest, let $y$ be the amount invested at $8$ interest, and let $z$ be the amount invested at $9$ interest. Thus,

$$\begin{aligned} x+y+z &= 10,000 \\ 0.05x+0.08y+0.09z &= 770 \\ 2x-z &= 0 \end{aligned}$$

As a matrix, we have

$$\left[\begin{array}{ccc|c} 1 & 1 & 1 & 10,000 \\ 0.05 & 0.08 & 0.09 & 770 \\ 2 & 0 & -1 & 0 \end{array}\right]$$

Now, we perform Gaussian elimination to achieve row-echelon form.

$$-0.05R_1 + R_2 = R_2 \rightarrow \left[\begin{array}{ccc|c} 1 & 1 & 1 & 10,000 \\ 0 & 0.03 & 0.04 & 270 \\ 2 & 0 & -1 & 0 \end{array}\right]$$

$$-2R_1 + R_3 = R_3 \rightarrow \left[\begin{array}{ccc|c} 1 & 1 & 1 & 10,000 \\ 0 & 0.03 & 0.04 & 270 \\ 0 & -2 & -3 & -20,000 \end{array}\right]$$

$$\frac{1}{0.03}R_2 = R_2 \rightarrow \left[\begin{array}{ccc|c} 1 & 1 & 1 & 10,000 \\ 0 & 1 & \frac{4}{3} & 9,000 \\ 0 & -2 & -3 & -20,000 \end{array}\right]$$

$$2R_2 + R_3 = R_3 \rightarrow \left[\begin{array}{ccc|c} 1 & 1 & 1 & 10,000 \\ 0 & 1 & \frac{4}{3} & 9,000 \\ 0 & 0 & -\frac{1}{3} & -2,000 \end{array}\right]$$

The third row tells us $-\frac{1}{3}z = -2,000$; thus $z = 6,000$.

The second row tells us $y + \frac{4}{3}z = 9,000$. Substituting $z = 6,000$,we get

$$\begin{aligned} y + \frac{4}{3}(6,000) &= 9,000 \\ y + 8,000 &= 9,000 \\ y &= 1,000 \end{aligned}$$

The first row tells us $x + y + z = 10,000$. Substituting $y = 1,000$ and $z = 6,000$,we get

$$\begin{aligned} x + 1,000 + 6,000 &= 10,000 \\ x &= 3,000 \end{aligned}$$

The answer is $\$3,000$ invested at 5 interest, $\$1,000$ invested at 8, and $\$6,000$ invested at 9 interest.

## Exercise 6.5.6

A small shoe company took out a loan of $\$1,500,000$ to expand their inventory. Part of the money was borrowed at 7, part was borrowed at 8, and part was borrowed at 10. The amount borrowed at 10 was four times the amount borrowed at 7, and the annual interest on all three loans was $\$130,500$ Use matrices to find the amount borrowed at each rate.

**Answer**

$\$150,000$ at 7, $\$750,000$ at 8, $\$600,000$ at 10

## Media

Access these online resources for additional instruction and practice with solving systems of linear equations using Gaussian elimination.

- Solve a System of Two Equations Using an Augmented Matrix
- Solve a System of Three Equations Using an Augmented Matrix

- Augmented Matrices on the Calculator

## Key Concepts

- An augmented matrix is one that contains the coefficients and constants of a system of equations. See Example 6.5.1.
- A matrix augmented with the constant column can be represented as the original system of equations. See Example 6.5.2.
- Row operations include multiplying a row by a constant, adding one row to another row, and interchanging rows.
- We can use Gaussian elimination to solve a system of equations. See Example 6.5.3, Example 6.5.4, and Example 6.5.5.
- Row operations are performed on matrices to obtain row-echelon form. See Example 6.5.6.
- To solve a system of equations, write it in augmented matrix form. Perform row operations to obtain row-echelon form. Back-substitute to find the solutions. See Example 6.5.7 and Example 6.5.8.
- A calculator can be used to solve systems of equations using matrices. See Example 6.5.9.
- Many real-world problems can be solved using augmented matrices. See Example 6.5.10 and Example 6.5.11.

---

This page titled 6.5: Solving Systems with Gaussian Elimination is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.6: Solving Systems with Gaussian Elimination** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 6.5E: Solving Systems with Gaussian Elimination (Exercises)

For the following exercises, write the system of linear equations from the augmented matrix. Indicate whether there will be a unique solution.

51. $\left[\begin{array}{ccc|c} 1 & 0 & -3 & 7 \\ 0 & 1 & 2 & -5 \\ 0 & 0 & 0 & 0 \end{array}\right]$

52. $\left[\begin{array}{ccc|c} 1 & 0 & 5 & -9 \\ 0 & 1 & -2 & 4 \\ 0 & 0 & 0 & 3 \end{array}\right]$

For the following exercises, write the augmented matrix from the system of linear equations.

53.

$-2x+2y+z=7$

$2x-8y+5z=0$

$19x-10y+22z=3$

54.

$4x+2y-3z=14$

$-12x+3y+z=100$

$9x-6y+2z=31$

55.

$x+3z=12$

$-x+4y=0$

$y+2z=-7$

For the following exercises, solve the system of linear equations using Gaussian elimination.

56.

$3x-4y=-7$
$-6x+8y=14$

57

$3x-4y=1$
$-6x+8y=6$

58.

$-1.1x-2.3y=6.2$
$-5.2x-4.1y=4.3$

59.

$2x+3y+2z=1$

$-4x-6y-4z=-2$
$10x+15y+10z=0$

60.

$-x+2y-4z=8$

$3y+8z=-4$
$-7x+y+2z=1$

This page titled 6.5E: Solving Systems with Gaussian Elimination (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.6E: Solving Systems with Gaussian Elimination (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# CHAPTER OVERVIEW

## 7: Analytic Geometry

In this chapter, we will investigate the two-dimensional figures that are formed when a right circular cone is intersected by a plane. We will begin by studying each of three figures created in this manner. We will develop defining equations for each figure and then learn how to use these equations to solve a variety of problems. Conic sections are formed when a plane intersects two right circular cones aligned tip to tip and extending infinitely far in opposite directions, which we also call a cone. The way in which we slice the cone will determine the type of conic section formed at the intersection. A circle is formed by slicing a cone with a plane perpendicular to the axis of symmetry of the cone. An ellipse is formed by slicing a single cone with a slanted plane not perpendicular to the axis of symmetry.


7.1: Prelude to Analytic Geometry

7.2: The Parabola

7.2E: The Parabola (Exercises)

7.3: The Ellipse

7.3E: The Ellipse (Exercises)

7.4: The Hyperbola

7.4E: The Hyperbola (Exercises)


Thumbnail: Conic sections can also be described by a set of points in the coordinate plane. This section focuses on the four variations of the standard form of the equation for the ellipse. An ellipse is the set of all points $(x,y)(x,y)$ in a plane such that the sum of their distances from two fixed points is a constant. Each fixed point is called a focus(plural: foci).

### Contributors

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.


This page titled 7: Analytic Geometry is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 7.1: Prelude to Analytic Geometry

The Greek mathematician Menaechmus (c. 380–c. 320 BCE) is generally credited with discovering the shapes formed by the intersection of a plane and a right circular cone. Depending on how he tilted the plane when it intersected the cone, he formed different shapes at the intersection–beautiful shapes with near-perfect symmetry. It was also said that Aristotle may have had an intuitive understanding of these shapes, as he observed the orbit of the planet to be circular. He presumed that the planets moved in circular orbits around Earth, and for nearly 2000 years this was the commonly held belief.




***Figure* 7.1.1*:*** *(a) Greek philosopher Aristotle (384–322 BCE) (b) German mathematician and astronomer Johannes Kepler (1571–1630)*

It was not until the Renaissance movement that Johannes Kepler noticed that the orbits of the planet were not circular in nature. His published law of planetary motion in the 1600s changed our view of the solar system forever. He claimed that the sun was at one end of the orbits, and the planets revolved around the sun in an oval-shaped path. In this chapter, we will investigate the two-dimensional figures that are formed when a right circular cone is intersected by a plane. We will begin by studying each of three figures created in this manner. We will develop defining equations for each figure and then learn how to use these equations to solve a variety of problems.

This page titled 7.1: Prelude to Analytic Geometry is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **12.0: Prelude to Analytic Geometry** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 7.2: The Parabola

**Learning Objectives**

- Graph parabolas with vertices at the origin.
- Write equations of parabolas in standard form.
- Graph parabolas with vertices not at the origin.
- Solve applied problems involving parabolas.

Did you know that the Olympic torch is lit several months before the start of the games? The ceremonial method for lighting the flame is the same as in ancient times. The ceremony takes place at the Temple of Hera in Olympia, Greece, and is rooted in Greek mythology, paying tribute to Prometheus, who stole fire from Zeus to give to all humans. One of eleven acting priestesses places the torch at the focus of a parabolic mirror (Figure 7.2.1), which focuses light rays from the sun to ignite the flame.



Figure 7.2.1: The Olympic torch concludes its journey around the world when it is used to light the Olympic cauldron during the opening ceremony. (credit: Ken Hackman, U.S. Air Force)

Parabolic mirrors (or reflectors) are able to capture energy and focus it to a single point. The advantages of this property are evidenced by the vast list of parabolic objects we use every day: satellite dishes, suspension bridges, telescopes, microphones, spotlights, and car headlights, to name a few. Parabolic reflectors are also used in alternative energy devices, such as solar cookers and water heaters, because they are inexpensive to manufacture and need little maintenance. In this section we will explore the parabola and its uses, including low-cost, energy-efficient solar designs.

## Graphing Parabolas with Vertices at the Origin

Previously, we saw that an ellipse is formed when a plane cuts through a right circular cone. If the plane is parallel to the edge of the cone, an unbounded curve is formed. This curve is a *parabola* (Figure 7.2.2).




Figure 7.2.2: Parabola

Like the ellipse and hyperbola, the parabola can also be defined by a set of points in the coordinate plane. A parabola is the set of all points $(x, y)$ in a plane that are the same distance from a fixed line, called the *directrix*, and a fixed point (the *focus*) not on the directrix.

Previously, we learned about a parabola's vertex and axis of symmetry. Now we extend the discussion to include other key features of the parabola (Figure 7.2.3). Notice that the axis of symmetry passes through the focus and vertex and is perpendicular to the directrix. The vertex is the midpoint between the directrix and the focus. The line segment that passes through the focus and is parallel to the directrix is called the *latus rectum*. The endpoints of the latus rectum lie on the curve. By definition, the distance d from the focus to any point $P$ on the parabola is equal to the distance from $P$ to the directrix.





Figure 7.2.3: Key features of the parabola

To work with parabolas in the *coordinate plane*, we consider two cases: those with a vertex at the origin and those with a *vertex* at a point other than the origin. We begin with the former.





Figure 7.2.4

Let $(x, y)$ be a point on the parabola with vertex $(0, 0)$, focus $(0, p)$,and directrix $y = -p$ as shown in Figure 7.2.4. The distance d from point $(x, y)$ to point $(x, -p)$ on the directrix is the difference of the *y*-values: $d = y + p$ . The distance from the focus $(0, p)$ to the point $(x, y)$ is also equal to $d$ and can be expressed using the distance formula.

$$\begin{aligned} d &= \sqrt{(x-0)^2 + (y-p)^2} \\ &= \sqrt{x^2 + (y-p)^2} \end{aligned}$$

Set the two expressions for $d$ equal to each other and solve for $y$ to derive the equation of the parabola. We do this because the distance from $(x, y)$ to $(0, p)$ equals the distance from $(x, y)$ to $(x, -p)$.

$$\sqrt{x^2 + (y-p)^2} = y + p \tag{7.2.1}$$

We then square both sides of the equation, expand the squared terms, and simplify by combining like terms.

$$\begin{aligned} x^2+(y-p)^2 &= (y+p)^2 \\ x^2+y^2-2py+p^2 &= y^2+2py+p^2 \\ x^2-2py &= 2py \\ x^2 &= 4py \end{aligned}$$

The equations of parabolas with vertex $(0,0)$ are $y^2=4px$ when the $x$-axis is the axis of symmetry and $x^2=4py$ when the $y$-axis is the axis of symmetry. These standard forms are given below, along with their general graphs and key features.

## STANDARD FORMS OF PARABOLAS WITH VERTEX $(0,0)$

Table 7.2.1 and Figure 7.2.5 summarize the standard features of parabolas with a vertex at the origin.

Table 7.2.1

| Axis of Symmetry | Equation | Focus | Directrix | Endpoints of Latus Rectum |
|---|---|---|---|---|
| $x$-axis | $y^2=4px$ | $(p,0)$ | $x=-p$ | $(p,\pm 2p)$ |
| $y$-axis | $x^2=4py$ | $(0,p)$ | $y=-p$ | $(\pm 2p,p)$ |





Figure 7.2.5: (a) When $p>0$ and the axis of symmetry is the x-axis, the parabola opens right. (b) When $p<0$ and the axis of symmetry is the x-axis, the parabola opens left. (c) When $p<0$ and the axis of symmetry is the y-axis, the parabola opens up. (d) When $p<0$ and the axis of symmetry is the y-axis, the parabola opens down.

The key features of a parabola are its vertex, axis of symmetry, focus, directrix, and *latus rectum* (Figure 7.2.5). When given a standard equation for a parabola centered at the origin, we can easily identify the key features to graph the parabola. A line is said to be tangent to a curve if it intersects the curve at exactly one point. If we sketch lines tangent to the parabola at the endpoints of the *latus rectum*, these lines intersect on the axis of symmetry, as shown in Figure 7.2.6.





Figure 7.2.6

**How to: Given a standard form equation for a parabola centered at $(0, 0)$, sketch the graph**

1. Determine which of the standard forms applies to the given equation: $y^2 = 4px$ or $x^2 = 4py$.
2. Use the standard form identified in Step 1 to determine the axis of symmetry, focus, equation of the directrix, and endpoints of the latus rectum.
   - If the equation is in the form $y^2 = 4px$, then
     - the axis of symmetry is the $x$-axis, $y = 0$
     - set $4p$ equal to the coefficient of $x$ in the given equation to solve for $p$. If $p > 0$, the parabola opens right. If $p < 0$, the parabola opens left.
     - use $p$ to find the coordinates of the focus, $(p, 0)$
     - use $p$ to find the equation of the directrix, $x = -p$
     - use $p$ to find the endpoints of the latus rectum, $(p, \pm 2p)$. Alternately, substitute $x = p$ into the original equation.
   - If the equation is in the form $x^2 = 4py$,then
     - the axis of symmetry is the $y$-axis, $x = 0$
     - set $4p$ equal to the coefficient of $y$ in the given equation to solve for $p$. If $p > 0$, the parabola opens up. If $p < 0$, the parabola opens down.
     - use $p$ to find the coordinates of the focus, $(0, p)$
     - use $p$ to find equation of the directrix, $y = -p$
     - use $p$ to find the endpoints of the latus rectum, $(\pm 2p, p)$
3. Plot the focus, directrix, and latus rectum, and draw a smooth curve to form the parabola.

**-axis as the Axis of Symmetry**

Graph $y^2 = 24x$. Identify and label the focus, directrix, and endpoints of the *latus rectum*.

**Solution**

The standard form that applies to the given equation is $y^2 = 4px$. Thus, the axis of symmetry is the *x*-axis. It follows that:

- $24 = 4p$, so $p = 6$. Since $p > 0$, the parabola opens right
- the coordinates of the focus are $(p, 0) = (6, 0)$
- the equation of the directrix is $x = -p = -6$
- the endpoints of the latus rectum have the same *x*-coordinate at the focus. To find the endpoints, substitute $x = 6$ into the original equation: $(6, \pm 12)$

Next we plot the focus, directrix, and latus rectum, and draw a smooth curve to form the parabola (Figure 7.2.7).





Figure 7.2.7

## Exercise 7.2.1

Graph $y^2 = -16x$. Identify and label the focus, directrix, and endpoints of the *latus rectum*.

**Answer**

- Focus: $(-4, 0)$
- Directrix: $x = 4$
- Endpoints of the latus rectum: $(-4, \pm 8)$





Figure 7.2.8

## -axis as the Axis of Symmetry

Graph $x^2 = -6y$. Identify and label the focus, directrix, and endpoints of the *latus rectum*.

**Solution**

The standard form that applies to the given equation is $x^2 = 4py$. Thus, the axis of symmetry is the $y$-axis. It follows that:

- $-6 = 4p$,so $p = -\frac{3}{2}$. Since $p < 0$, the parabola opens down.
- the coordinates of the focus are $(0, p) = (0, -\frac{3}{2})$
- the equation of the directrix is $y = -p = \frac{3}{2}$
- the endpoints of the latus rectum can be found by substituting $y = \frac{3}{2}$ into the original equation, $(\pm 3, -\frac{3}{2})$

Next we plot the focus, directrix, and *latus rectum*, and draw a smooth curve to form the parabola.





Figure 7.2.9

**Exercise 7.2.2**

Graph $x^2 = 8y$. Identify and label the focus, directrix, and endpoints of the *latus rectum*.

**Answer**

- Focus: $(0, 2)$
- Directrix: $y = -2$
- Endpoints of the latus rectum: $(\pm 4, 2)$.





Figure 7.2.10

## Writing Equations of Parabolas in Standard Form

In the previous examples, we used the standard form equation of a parabola to calculate the locations of its key features. We can also use the calculations in reverse to write an equation for a parabola when given its key features.

**How to: Given its focus and directrix, write the equation for a parabola in standard form**

1. Determine whether the axis of symmetry is the $x$- or $y$-axis.
   i. If the given coordinates of the focus have the form $(p, 0)$, then the axis of symmetry is the $x$-axis. Use the standard form $y^2 = 4px$.
   ii. If the given coordinates of the focus have the form $(0, p)$, then the axis of symmetry is the $y$-axis. Use the standard form $x^2 = 4py$.
2. Multiply $4p$.
3. Substitute the value from Step 2 into the equation determined in Step 1.

### Example 7.2.3: Writing the Equation of a Parabola in Standard Form Given its Focus and Directrix

What is the equation for the parabola with focus $(-\frac{1}{2}, 0)$ and directrix $x = \frac{1}{2}$?

**Solution**

The focus has the form $(p, 0)$, so the equation will have the form $y^2 = 4px$.

- Multiplying $4p$, we have $4p = 4(-\frac{1}{2}) = -2$.
- Substituting for $4p$, we have $y^2 = 4px = -2x$.=

Therefore, the equation for the parabola is $y^2 = -2x$.

### Exercise 7.2.3

What is the equation for the parabola with focus $\left(0, \frac{7}{2}\right)$ and directrix $y = -\frac{7}{2}$?

**Answer**

$x^2 = 14y$.

## Graphing Parabolas with Vertices Not at the Origin

Like other graphs we've worked with, the graph of a parabola can be translated. If a parabola is translated $h$ units horizontally and $k$ units vertically, the vertex will be $(h, k)$. This translation results in the standard form of the equation we saw previously with $x$ replaced by $(x - h)$ and $y$ replaced by $(y - k)$.

To graph parabolas with a vertex $(h, k)$ other than the origin, we use the standard form $(y - k)^2 = 4p(x - h)$ for parabolas that have an axis of symmetry parallel to the $x$-axis, and $(x - h)^2 = 4p(y - k)$ for parabolas that have an axis of symmetry parallel to the $y$-axis. These standard forms are given below, along with their general graphs and key features.

### STANDARD FORMS OF PARABOLAS WITH VERTEX $(H, K)$

Table 7.2.2 and Figure 7.2.11 summarize the standard features of parabolas with a vertex at a point $(h, k)$.

Table 7.2.2

| Axis of Symmetry | Equation | Focus | Directrix | Endpoints of Latus Rectum |
|---|---|---|---|---|
| $y = k$ | $(y - k)^2 = 4p(x - h)$ | $(h + p, k)$ | $x = h - p$ | $(h + p, k \pm 2p)$ |
| $x = h$ | $(x - h)^2 = 4p(y - k)$ | $(h, k + p)$ | $y = k - p$ | $(h \pm 2p, k + p)$ |





Figure 7.2.11: (a) When $p > 0$, the parabola opens right. (b) When $p < 0$, the parabola opens left. (c) When $p > 0$,the parabola opens up. (d) When $p < 0$, the parabola opens down.

### How to: Given a standard form equation for a parabola centered at $(h, k)$, sketch the graph

1. Determine which of the standard forms applies to the given equation: $(y-k)^2 = 4p(x-h)$ or $(x-h)^2 = 4p(y-k)$.
2. Use the standard form identified in Step 1 to determine the vertex, axis of symmetry, focus, equation of the directrix, and endpoints of the latus rectum.
   - If the equation is in the form $(y-k)^2 = 4p(x-h)$,then:
     - use the given equation to identify $h$ and $k$ for the vertex, $(h, k)$
     - use the value of $k$ to determine the axis of symmetry, $y = k$
     - set $4p$ equal to the coefficient of $(x-h)$ in the given equation to solve for $p$. If $p > 0$,the parabola opens right. If $p < 0$, the parabola opens left.
     - use $h$, $k$, and $p$ to find the coordinates of the focus, $(h+p, k)$
     - use $h$ andp p to find the equation of the directrix, $x = h-p$
     - use $h$, $k$, and $p$ to find the endpoints of the latus rectum, $(h+p, k \pm 2p)$
   - If the equation is in the form $(x-h)^2 = 4p(y-k)$,then:
     - use the given equation to identify $h$ and $k$ for the vertex, $(h, k)$
     - use the value of $h$ to determine the axis of symmetry, $x = h$

- set $4p$ equal to the coefficient of $(y-k)$ in the given equation to solve for $p$. If $p>0$, the parabola opens up. If $p<0$, the parabola opens down.
- use $h$, $k$, and $p$ to find the coordinates of the focus, $(h, k+p)$
- use $k$ and $p$ to find the equation of the directrix, $y=k-p$
- use $h$, $k$, and $p$ to find the endpoints of the latus rectum, $(h \pm 2p, k+p)$

3. Plot the vertex, axis of symmetry, focus, directrix, and latus rectum, and draw a smooth curve to form the parabola.

### Example 7.2.4: Graphing a Parabola with Vertex $(h, k)$ and Axis of Symmetry Parallel to the $x$-axis

Graph $(y-1)^2=-16(x+3)$. Identify and label the vertex, axis of symmetry, focus, directrix, and endpoints of the latus rectum.

**Solution**

The standard form that applies to the given equation is $(y-k)^2=4p(x-h)$. Thus, the axis of symmetry is parallel to the $x$-axis. It follows that:

- the vertex is $(h, k)=(-3, 1)$
- the axis of symmetry is $y=k=1$
- $-16=4p$,so $p=-4$. Since $p<0$, the parabola opens left.
- the coordinates of the focus are $(h+p, k)=(-3+(-4), 1)=(-7, 1)$
- the equation of the directrix is $x=h-p=-3-(-4)=1$
- the endpoints of the latus rectum are $(h+p, k \pm 2p)=(-3+(-4), 1 \pm 2(-4))$ , or $(-7, -7)$ and $(-7, 9)$

Next we plot the vertex, axis of symmetry, focus, directrix, and latus rectum, and draw a smooth curve to form the parabola (Figure 7.2.10).





Figure 7.2.12

### Exercise 7.2.4

Graph $(y+1)^2=4(x-8)$. Identify and label the vertex, axis of symmetry, focus, directrix, and endpoints of the *latus rectum*.

**Answer**

- Vertex: $(8, -1)$
- Axis of symmetry: $y=-1$
- Focus: $(9, -1)$
- Directrix: $x=7$

- Endpoints of the *latus rectum*: $(9, -3)$ and $(9, 1)$.





Figure 7.2.13

## Example 7.2.5: Graphing a Parabola from an Equation Given in General Form

Graph $x^2 - 8x - 28y - 208 = 0$ . Identify and label the vertex, axis of symmetry, focus, directrix, and endpoints of the *latus rectum*.

### Solution

Start by writing the equation of the parabola in standard form. The standard form that applies to the given equation is $(x-h)^2 = 4p(y-k)$ . Thus, the axis of symmetry is parallel to the $y$-axis. To express the equation of the parabola in this form, we begin by isolating the terms that contain the variable $x$ in order to complete the square.

$$\begin{aligned} x^2 - 8x - 28y - 208 &= 0 \\ x^2 - 8x &= 28y + 208 \\ x^2 - 8x + 16 &= 28y + 208 + 16 \\ (x-4)^2 &= 28y + 224 \\ (x-4)^2 &= 28(y+8) \\ (x-4)^2 &= 4 \cdot 7 \cdot (y+8) \end{aligned}$$

It follows that:

- the vertex is $(h, k) = (4, -8)$
- the axis of symmetry is $x = h = 4$
- since $p = 7$, $p > 0$ and so the parabola opens up
- the coordinates of the focus are $(h, k+p) = (4, -8+7) = (4, -1)$
- the equation of the directrix is $y = k - p = -8 - 7 = -15$
- the endpoints of the latus rectum are $(h \pm 2p, k+p) = (4 \pm 2(7), -8+7)$ , or $(-10, -1)$ and $(18, -1)$

Next we plot the vertex, axis of symmetry, focus, directrix, and latus rectum, and draw a smooth curve to form the parabola (Figure 7.2.14).





Figure 7.2.14

**? Exercise 7.2.5**

Graph $(x+2)^2 = -20(y-3)$. Identify and label the vertex, axis of symmetry, focus, directrix, and endpoints of the *latus rectum*.

**Answer**

- Vertex: $(-2, 3)$
- Axis of symmetry: $x = -2$
- Focus: $(-2, -2)$
- Directrix: $y = 8$
- Endpoints of the *latus rectum*: $(-12, -2)$ and $(8, -2)$.





Figure 7.2.15

## Solving Applied Problems Involving Parabolas

As we mentioned at the beginning of the section, parabolas are used to design many objects we use every day, such as telescopes, suspension bridges, microphones, and radar equipment. Parabolic mirrors, such as the one used to light the Olympic torch, have a very unique reflecting property. When rays of light parallel to the parabola's axis of symmetry are directed toward any surface of the mirror, the light is reflected directly to the focus (Figure 7.2.16). This is why the Olympic torch is ignited when it is held at the focus of the parabolic mirror.





Figure 7.2.16: Reflecting property of parabolas

Parabolic mirrors have the ability to focus the sun's energy to a single point, raising the temperature hundreds of degrees in a matter of seconds. Thus, parabolic mirrors are featured in many low-cost, energy efficient solar products, such as solar cookers, solar heaters, and even travel-sized fire starters.

### Example 7.2.6: Solving Applied Problems Involving Parabolas

A cross-section of a design for a travel-sized solar fire starter is shown in Figure 7.2.17. The sun's rays reflect off the parabolic mirror toward an object attached to the igniter. Because the igniter is located at the focus of the parabola, the reflected rays cause the object to burn in just seconds.

a. Find the equation of the parabola that models the fire starter. Assume that the vertex of the parabolic mirror is the origin of the coordinate plane.
b. Use the equation found in part (a) to find the depth of the fire starter.





Figure 7.2.17 Cross-section of a travel-sized solar fire starter

**Solution**

a. The vertex of the dish is the origin of the coordinate plane, so the parabola will take the standard form $x^2 = 4py$,where $p > 0$. The igniter, which is the focus, is $1.7$ inches above the vertex of the dish. Thus we have $p = 1.7$.

$$\begin{aligned} x^2 &= 4py && \text{Standard form of upward-facing parabola with vertex } (0,0) \\ x^2 &= 4(1.7)y && \text{Substitute } 1.7 \text{ for } p \\ x^2 &= 6.8y && \text{Multiply.} \end{aligned}$$

b. The dish extends $\dfrac{4.5}{2} = 2.25$ inches on either side of the origin. We can substitute $2.25$ for $x$ in the equation from part (a) to find the depth of the dish.

$$\begin{aligned} x^2 &= 6.8y && \text{Equation found in part } (a) \\ (2.25)^2 &= 6.8y && \text{Substitute } 2.25 \text{ for } x \\ y &\approx 0.74 && \text{Solve for } y \end{aligned}$$

The dish is about $0.74$ inches deep.

## Exercise 7.2.6

Balcony-sized solar cookers have been designed for families living in India. The top of a dish has a diameter of 1600 mm. The sun's rays reflect off the parabolic mirror toward the "cooker," which is placed 320 mm from the base.

a. Find an equation that models a cross-section of the solar cooker. Assume that the vertex of the parabolic mirror is the origin of the coordinate plane, and that the parabola opens to the right (i.e., has the *x*-axis as its axis of symmetry).
b. Use the equation found in part (a) to find the depth of the cooker.

**Answer a**

$y^2 = 1280x$

**Answer b**

The depth of the cooker is 500 mm

## Key Equations

| | |
|---|---|
| Parabola, vertex at origin, axis of symmetry on *x*-axis | $y^2 = 4px$ |
| Parabola, vertex at origin, axis of symmetry on *y*-axis | $x^2 = 4py$ |
| Parabola, vertex at $(h, k)$,axis of symmetry on *x*-axis | $(y-k)^2 = 4p(x-h)$ |
| Parabola, vertex at $(h, k)$,axis of symmetry on *y*-axis | $(x-h)^2 = 4p(y-k)$ |

## Key Concepts

- A parabola is the set of all points $(x, y)$ in a plane that are the same distance from a fixed line, called the directrix, and a fixed point (the focus) not on the directrix.
- The standard form of a parabola with vertex $(0, 0)$ and the *x*-axis as its axis of symmetry can be used to graph the parabola. If $p > 0$, the parabola opens right. If $p < 0$, the parabola opens left. See Example 7.2.1.
- The standard form of a parabola with vertex $(0, 0)$ and the *y*-axis as its axis of symmetry can be used to graph the parabola. If $p > 0$, the parabola opens up. If $p < 0$, the parabola opens down. See Example 7.2.2.
- When given the focus and directrix of a parabola, we can write its equation in standard form. See Example 7.2.3.
- The standard form of a parabola with vertex $(h, k)$ and axis of symmetry parallel to the $x$-axis can be used to graph the parabola. If $p > 0$, the parabola opens right. If $p < 0$, the parabola opens left. See Example 7.2.4.
- The standard form of a parabola with vertex $(h, k)$ and axis of symmetry parallel to the $y$-axis can be used to graph the parabola. If $p > 0$, the parabola opens up. If $p < 0$, the parabola opens down. See Example 7.2.5.
- Real-world situations can be modeled using the standard equations of parabolas. For instance, given the diameter and focus of a cross-section of a parabolic reflector, we can find an equation that models its sides. See Example 7.2.6.

This page titled 7.2: The Parabola is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **12.3: The Parabola** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 7.2E: The Parabola (Exercises)

For the following exercises, write the equation of the parabola in standard form. Then give the vertex, focus, and directrix.

22. $y^2 = 12x$

23. $(x+2)^2 = \frac{1}{2}(y-1)$

24. $y^2 - 6y - 6x - 3 = 0$

25. $x^2 + 10x - y + 23 = 0$

For the following exercises, graph the parabola, labeling vertex, focus, and directrix.

26. $x^2 + 4y = 0$

27. $(y-1)^2 = \frac{1}{2}(x+3)$

28. $x^2 - 8x - 10y + 46 = 0$

29. $2y^2 + 12y + 6x + 15 = 0$

For the following exercises, write the equation of the parabola using the given information.

30. Focus at (-4,0) ; directrix is $x = 4$

31. Focus at $\left(2, \frac{9}{8}\right)$ ; directrix is $y = \frac{7}{8}$

32. A cable TV receiving dish is the shape of a paraboloid of revolution. Find the location of the receiver, which is placed at the focus, if the dish is 5 feet across at its opening and 1.5 feet deep.

This page titled 7.2E: The Parabola (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **12.3E: The Parabola (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

## 7.3: The Ellipse

**Learning Objectives**

- Write equations of ellipses in standard form.
- Graph ellipses centered at the origin.
- Graph ellipses not centered at the origin.
- Solve applied problems involving ellipses.

Can you imagine standing at one end of a large room and still being able to hear a whisper from a person standing at the other end? The National Statuary Hall in Washington, D.C., shown in Figure 7.3.1, is such a room. It is an oval-shaped room called a *whispering chamber* because the shape makes it possible for sound to travel along the walls. In this section, we will investigate the shape of this room and its real-world applications, including how far apart two people in Statuary Hall can stand and still hear each other whisper.



Figure 7.3.1: The National Statuary Hall in Washington, D.C. (credit: Greg Palmer, Flickr)

### Writing Equations of Ellipses in Standard Form

A conic section, or conic, is a shape resulting from intersecting a right circular cone with a plane. The angle at which the plane intersects the cone determines the shape, as shown in Figure 7.3.2.





Figure 7.3.2

Conic sections can also be described by a set of points in the coordinate plane. Later in this chapter, we will see that the graph of any quadratic equation in two variables is a conic section. The signs of the equations and the coefficients of the variable terms determine the shape. This section focuses on the four variations of the standard form of the equation for the ellipse. An ellipse is the set of all points $(x, y)$ in a plane such that the sum of their distances from two fixed points is a constant. Each fixed point is called a focus(plural: foci).

We can draw an ellipse using a piece of cardboard, two thumbtacks, a pencil, and string. Place the thumbtacks in the cardboard to form the foci of the ellipse. Cut a piece of string longer than the distance between the two thumbtacks (the length of the string represents the constant in the definition). Tack each end of the string to the cardboard, and trace a curve with a pencil held taut against the string. The result is an ellipse. See Figure 7.3.3.





Figure 7.3.3

Every ellipse has two axes of symmetry. The longer axis is called the major axis, and the shorter axis is called the minor axis. Each endpoint of the major axis is the vertex of the ellipse (plural: vertices), and each endpoint of the minor axis is a co-vertex of the ellipse. The center of an ellipse is the midpoint of both the major and minor axes. The axes are perpendicular at the center. The foci always lie on the major axis, and the sum of the distances from the foci to any point on the ellipse (the constant sum) is greater than the distance between the foci (Figure 7.3.4).





Figure 7.3.4

In this section, we restrict ellipses to those that are positioned vertically or horizontally in the coordinate plane. That is, the axes will either lie on or be parallel to the $x$- and $y$-axes. Later in the chapter, we will see ellipses that are rotated in the coordinate plane.

To work with horizontal and vertical ellipses in the coordinate plane, we consider two cases: those that are centered at the origin and those that are centered at a point other than the origin. First we will learn to derive the equations of ellipses, and then we will learn how to write the equations of ellipses in standard form. Later we will use what we learn to draw the graphs.

### Deriving the Equation of an Ellipse Centered at the Origin

To derive the equation of an **ellipse** centered at the origin, we begin with the foci $(-c,0)$ and $(c,0)$. The ellipse is the set of all points $(x,y)$ such that the sum of the distances from $(x,y)$ to the foci is constant, as shown in Figure 7.3.5.





Figure 7.3.5

If $(a,0)$ is a vertex of the ellipse, the distance from $(-c,0)$ to $(a,0)$ is $a-(-c)=a+c$ . The distance from $(c,0)$ to $(a,0)$ is $a-c$ . The sum of the distances from the foci to the vertex is

$$(a+c)+(a-c)=2a$$

If $(x,y)$ is a point on the ellipse, then we can define the following variables:

- $d_1 =$ the distance from $(-c,0)$ to $(x,y)$
- $d_2 =$ the distance from $(c,0)$ to $(x,y)$

By the definition of an ellipse, $d_1+d_2$ is constant for any point $(x,y)$ on the ellipse. We know that the sum of these distances is $2a$ for the vertex $(a,0)$. It follows that $d_1+d_2=2a$ for any point on the ellipse. We will begin the derivation by applying the distance formula. The rest of the derivation is algebraic.

$$\begin{aligned}
d_1+d_2 &= 2a \\
\sqrt{(x-(-c))^2+(y-0)^2}+\sqrt{(x-c)^2+(y-0)^2} &= 2a && \text{Distance formula} \\
\sqrt{(x+c)^2+y^2}+\sqrt{(x-c)^2+y^2} &= 2a && \text{Simplify expressions.} \\
\sqrt{(x+c)^2+y^2} &= 2a-\sqrt{(x-c)^2+y^2} && \text{Move radical to opposite side.} \\
(x+c)^2+y^2 &= \left[2a-\sqrt{(x-c)^2+y^2}\right]^2 && \text{Square both sides.} \\
x^2+2cx+c^2+y^2 &= 4a^2-4a\sqrt{(x-c)^2+y^2}+(x-c)^2+y^2 && \text{Expand the squares.} \\
x^2+2cx+c^2+y^2 &= 4a^2-4a\sqrt{(x-c)^2+y^2}+x^2-2cx+c^2+y^2 && \text{Expand remaining squares.} \\
2cx &= 4a^2-4a\sqrt{(x-c)^2+y^2}-2cx && \text{Combine like terms.} \\
4cx-4a^2 &= -4a\sqrt{(x-c)^2+y^2} && \text{Isolate the radical.} \\
cx-a^2 &= -a\sqrt{(x-c)^2+y^2} && \text{Divide by 4.} \\
\left[cx-a^2\right]^2 &= a^2\left[\sqrt{(x-c)^2+y^2}\right]^2 && \text{Square both sides.} \\
c^2x^2-2a^2cx+a^4 &= a^2(x^2-2cx+c^2+y^2) && \text{Expand the squares.} \\
c^2x^2-2a^2cx+a^4 &= a^2x^2-2a^2cx+a^2c^2+a^2y^2 && \text{Distribute } a^2 \\
a^2x^2-c^2x^2+a^2y^2 &= a^4-a^2c^2 && \text{Rewrite.} \\
x^2(a^2-c^2)+a^2y^2 &= a^2(a^2-c^2) && \text{Factor common terms.} \\
x^2b^2+a^2y^2 &= a^2b^2 && \text{Set } b^2=a^2-c^2 \\
\frac{x^2b^2}{a^2b^2}+\frac{a^2y^2}{a^2b^2} &= \frac{a^2b^2}{a^2b^2} && \text{Divide both sides by } a^2b^2 \\
\frac{x^2}{a^2}+\frac{y^2}{b^2} &= 1 && \text{Simplify}
\end{aligned}$$

Thus, the standard equation of an ellipse is $\frac{x^2}{a^2}+\frac{y^2}{b^2}=1$ .This equation defines an ellipse centered at the origin. If $a>b$ ,the ellipse is stretched further in the horizontal direction, and if $b>a$ , the ellipse is stretched further in the vertical direction.

### Writing Equations of Ellipses Centered at the Origin in Standard Form

Standard forms of equations tell us about key features of graphs. Take a moment to recall some of the standard forms of equations we've worked with in the past: linear, quadratic, cubic, exponential, logarithmic, and so on. By learning to interpret standard forms of equations, we are bridging the relationship between algebraic and geometric representations of mathematical phenomena.

The key features of the **ellipse** are its center, **vertices**, **co-vertices**, **foci**, and lengths and positions of the **major and minor axes**. Just as with other equations, we can identify all of these features just by looking at the standard form of the equation. There are four variations of the standard form of the ellipse. These variations are categorized first by the location of the center (the origin or not the origin), and then by the position (horizontal or vertical). Each is presented along with a description of how the parts of the equation relate to the graph. Interpreting these parts allows us to form a mental picture of the ellipse.

## STANDARD FORMS OF THE EQUATION OF AN ELLIPSE WITH CENTER $(0,0)$

The standard form of the equation of an ellipse with center $(0,0)$ and major axis on the $x$-*axis* is

$$\frac{x^2}{a^2}+\frac{y^2}{b^2}=1 \tag{7.3.1}$$

where

- $a>b$
- the length of the major axis is $2a$
- the coordinates of the vertices are $(\pm a,0)$
- the length of the minor axis is $2b$
- the coordinates of the co-vertices are $(0,\pm b)$
- the coordinates of the foci are $(\pm c,0)$, where $c^2=a^2-b^2$ . See Figure 7.3.6*a*.

The standard form of the equation of an ellipse with center $(0,0)$ and major axis on the $y$-*axis* is

$$\frac{x^2}{b^2}+\frac{y^2}{a^2}=1 \tag{7.3.2}$$

where

- $a>b$
- the length of the major axis is $2a$
- the coordinates of the vertices are $(0,\pm a)$
- the length of the minor axis is $2b$
- the coordinates of the co-vertices are $(\pm b,0)$
- the coordinates of the foci are $(0,\pm c)$, where $c^2=a^2-b^2$ . See Figure 7.3.6*b*.

Note that the vertices, co-vertices, and foci are related by the equation $c^2=a^2-b^2$ . When we are given the coordinates of the foci and vertices of an ellipse, we can use this relationship to find the equation of the ellipse in standard form.





Figure 7.3.6: (a) Horizontal ellipse with center $(0,0)$ (b) Vertical ellipse with center $(0,0)$

### How to: Given the vertices and foci of an ellipse centered at the origin, write its equation in standard form

1. Determine whether the major axis lies on the *x*- or *y*-axis.
   - If the given coordinates of the vertices and foci have the form $(\pm a,0)$ and $(\pm c,0)$ respectively, then the major axis is the *x*-axis. Use the standard form $\frac{x^2}{a^2}+\frac{y^2}{b^2}=1$
   - If the given coordinates of the vertices and foci have the form $(0,\pm a)$ and $(\pm c,0)$,respectively, then the major axis is the *y*-axis. Use the standard form $\frac{x^2}{b^2}+\frac{y^2}{a^2}=1$
2. Use the equation $c^2=a^2-b^2$ , along with the given coordinates of the vertices and foci, to solve for $b^2$.
3. Substitute the values for $a^2$ and $b^2$ into the standard form of the equation determined in Step 1.

### Example 7.3.1: Writing the Equation of an Ellipse Centered at the Origin in Standard Form

What is the standard form equation of the ellipse that has vertices $(\pm 8,0)$ and foci $(\pm 5,0)$?

**Solution**

The foci are on the $x$-axis, so the major axis is the $x$-axis. Thus, the equation will have the form $\frac{x^2}{a^2}+\frac{y^2}{b^2}=1$

The vertices are $(\pm 8,0)$,so $a=8$ and $a^2=64$.

The foci are $(\pm 5,0)$,so $c=5$ and $c^2=25$.

We know that the vertices and foci are related by the equation $c^2=a^2-b^2$ . Solving for $b^2$, we have:

$$\begin{aligned} c^2 &= a^2-b^2 \\ 25 &= 64-b^2 \qquad \text{Substitute for } c^2 \text{ and } a^2 \\ b^2 &= 39 \qquad \text{Solve for } b^2 \end{aligned}$$

Now we need only substitute $a^2=64$ and $b^2=39$ into the standard form of the equation. The equation of the ellipse is $\frac{x^2}{64}+\frac{y^2}{39}=1$ .

### Exercise 7.3.1

What is the standard form equation of the ellipse that has vertices $(0,\pm 4)$ and foci $(0,\pm\sqrt{15})$?

**Answer**

$$x^2+\frac{y^2}{16}=1$$

Q&A

**Can we write the equation of an ellipse centered at the origin given coordinates of just one focus and vertex?**

*Yes. Ellipses are symmetrical, so the coordinates of the vertices of an ellipse centered around the origin will always have the form* $(\pm a, 0)$ *or* $(0, \pm a)$. *Similarly, the coordinates of the foci will always have the form* $(\pm c, 0)$ *or* $(0, \pm c)$. *Knowing this, we can use* $a$ *and* $c$ *from the given points, along with the equation* $c^2 = a^2 - b^2$ *, to find* $b^2$.

### Writing Equations of Ellipses Not Centered at the Origin

Like the graphs of other equations, the graph of an **ellipse** can be translated. If an ellipse is translated $h$ units horizontally and $k$ units vertically, the center of the ellipse will be $(h, k)$. This **translation** results in the standard form of the equation we saw previously, with $x$ replaced by $(x - h)$ and $y$ replaced by $(y - k)$.

STANDARD FORMS OF THE EQUATION OF AN ELLIPSE WITH CENTER $(H, K)$

The standard form of the equation of an ellipse with center $(h, k)$ and major axis parallel to the $x$-axis is

$$\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{b^2} = 1 \tag{7.3.3}$$

where

- $a > b$
- the length of the major axis is $2a$
- the coordinates of the vertices are $(h \pm a, k)$
- the length of the minor axis is $2b$
- the coordinates of the co-vertices are $(h, k \pm b)$
- the coordinates of the foci are $(h \pm c, k)$ ,where $c^2 = a^2 - b^2$ . See Figure 7.3.7a

The standard form of the equation of an ellipse with center $(h, k)$ and major axis parallel to the $y$-axis is

$$\frac{(x-h)^2}{b^2} + \frac{(y-k)^2}{a^2} = 1 \tag{7.3.4}$$

where

- $a > b$
- the length of the major axis is $2a$
- the coordinates of the vertices are $(h, k \pm a)$
- the length of the minor axis is $2b$
- the coordinates of the co-vertices are $(h \pm b, k)$
- the coordinates of the foci are $(h, k \pm c)$ , where $c^2 = a^2 - b^2$ . See Figure 7.3.7b

Just as with ellipses centered at the origin, ellipses that are centered at a point $(h, k)$ have vertices, co-vertices, and foci that are related by the equation $c^2 = a^2 - b^2$ . We can use this relationship along with the midpoint and distance formulas to find the equation of the ellipse in standard form when the vertices and foci are given.





Figure 7.3.7: (a) Horizontal ellipse with center $(h, k)$ (b) Vertical ellipse with center $(h, k)$

How to: Given the vertices and foci of an ellipse not centered at the origin, write its equation in standard form

1. Determine whether the major axis is parallel to the $x$- or $y$-axis.
   - If the $y$-coordinates of the given vertices and foci are the same, then the major axis is parallel to the $x$-axis. Use the standard form $\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{b^2} = 1$
   - If the $x$-coordinates of the given vertices and foci are the same, then the major axis is parallel to the $y$-axis. Use the standard form $\frac{(x-h)^2}{b^2} + \frac{(y-k)^2}{a^2} = 1$
2. Identify the center of the ellipse $(h, k)$ using the midpoint formula and the given coordinates for the vertices.
3. Find $a^2$ by solving for the length of the major axis, $2a$, which is the distance between the given vertices.
4. Find $c^2$ using $h$ and $k$, found in Step 2, along with the given coordinates for the foci.
5. Solve for $b^2$ using the equation $c^2 = a^2 - b^2$ .
6. Substitute the values for $h$, $k$, $a^2$, and $b^2$ into the standard form of the equation determined in Step 1.

Example 7.3.2: Writing the Equation of an Ellipse Centered at a Point Other Than the Origin

What is the standard form equation of the ellipse that has vertices $(-2, -8)$ and $(-2, 2)$ and foci $(-2, -7)$ and $(-2, 1)$?

**Solution**

The $x$-coordinates of the vertices and foci are the same, so the major axis is parallel to the $y$-axis. Thus, the equation of the ellipse will have the form

$$\frac{(x-h)^2}{b^2} + \frac{(y-k)^2}{a^2} = 1$$

First, we identify the center, $(h, k)$. The center is halfway between the vertices, $(-2, -8)$ and $(-2, 2)$. Applying the midpoint formula, we have:

$$(h,k)=\left(\frac{-2+(-2)}{2},\frac{-8+2}{2}\right)$$
$$=(-2,-3)$$

Next, we find $a^2$. The length of the major axis, $2a$, is bounded by the vertices. We solve for $a$ by finding the distance between the $y$-coordinates of the vertices.

$$\begin{aligned}2a&=2-(-8)\\2a&=10\\a&=5\end{aligned}$$

So $a^2=25$.

Now we find $c^2$. The foci are given by $(h,k\pm c)$. So, $(h,k-c)=(-2,-7)$ and $(h,k+c)=(-2,1)$. We substitute $k=-3$ using either of these points to solve for $c$.

$$\begin{aligned}k+c&=1\\-3+c&=1\\c&=4\end{aligned}$$

So $c^2=16$.

Next, we solve for $b^2$ using the equation $c^2=a^2-b^2$.

$$\begin{aligned}c^2&=a^2-b^2\\16&=25-b^2\\b^2&=9\end{aligned}$$

Finally, we substitute the values found for $h$, $k$, $a^2$, and $b^2$ into the standard form equation for an ellipse:

$$\frac{(x+2)^2}{9}+\frac{(y+3)^2}{25}=1$$

**Exercise 7.3.2**

What is the standard form equation of the ellipse that has vertices $(-3,3)$ and $(5,3)$ and foci $(1-2\sqrt{3},3)$ and $(1+2\sqrt{3},3)$?

**Answer**

$$\frac{(x-1)^2}{16}+\frac{(y-3)^2}{4}=1$$

## Graphing Ellipses Centered at the Origin

Just as we can write the equation for an ellipse given its graph, we can graph an ellipse given its equation. To graph ellipses centered at the origin, we use the standard form

$$\frac{x^2}{a^2}+\frac{y^2}{b^2}=1, a>b \text{ for horizontal ellipses}$$

and

$$\frac{x^2}{b^2}+\frac{y^2}{a^2}=1, a>b \text{ for vertical ellipses}$$

**How to: Given the standard form of an equation for an ellipse centered at $(0,0)$, sketch the graph.**

1. Use the standard forms of the equations of an ellipse to determine the major axis, vertices, co-vertices, and foci.
   - If the equation is in the form $\frac{x^2}{a^2}+\frac{y^2}{b^2}=1$, where $a>b$, then
     - the major axis is the $x$-axis
     - the coordinates of the vertices are $(\pm a,0)$
     - the coordinates of the co-vertices are $(0,\pm b)$
     - the coordinates of the foci are $(\pm c,0)$
   - If the equation is in the form $x^2b^2+y^2a^2=1$, where $a>b$, then
     - the major axis is the $y$-axis
     - the coordinates of the vertices are $(0,\pm a)$
     - the coordinates of the co-vertices are $(\pm b,0)$
     - the coordinates of the foci are $(0,\pm c)$
2. Solve for $c$ using the equation $c^2=a^2-b^2$.
3. Plot the center, vertices, co-vertices, and foci in the coordinate plane, and draw a smooth curve to form the ellipse.

**Example 7.3.3: Graphing an Ellipse Centered at the Origin**

Graph the ellipse given by the equation, $\frac{x^2}{9}+\frac{y^2}{25}=1$. Identify and label the center, vertices, co-vertices, and foci.

**Solution**

First, we determine the position of the major axis. Because $25>9$, the major axis is on the $y$-axis. Therefore, the equation is in the form $\frac{x^2}{b^2}+\frac{y^2}{a^2}=1$, where $b^2=9$ and $a^2=25$. It follows that:

- the center of the ellipse is $(0,0)$
- the coordinates of the vertices are $(0,\pm a)=(0,\pm\sqrt{25})=(0,\pm 5)$
- the coordinates of the co-vertices are $(\pm b,0)=(\pm 9,0)=(\pm 3,0)$
- the coordinates of the foci are $(0,\pm c)$, where $c^2=a^2-b^2$ Solving for $c$, we have:

$$\begin{aligned}c&=\pm\sqrt{a^2-b^2}\\&=\pm\sqrt{25-9}\\&=\pm\sqrt{16}\\&=\pm 4\end{aligned}$$

Therefore, the coordinates of the foci are $(0,\pm 4)$.

Next, we plot and label the center, vertices, co-vertices, and foci, and draw a smooth curve to form the ellipse. See Figure 7.3.8.





Figure 7.3.8

**? Exercise 7.3.3**

Graph the ellipse given by the equation $\frac{x^2}{36}+\frac{y^2}{4}=1$ . Identify and label the center, vertices, co-vertices, and foci.

**Answer**

center: $(0,0)$; vertices: $(\pm 6,0)$; co-vertices: $(0,\pm 2)$; foci: $(\pm 4\sqrt{2},0)$





Figure 7.3.9

**✓ Example 7.3.4: Graphing an Ellipse Centered at the Origin from an Equation Not in Standard Form**

Graph the ellipse given by the equation $4x^2+25y^2=100$. Rewrite the equation in standard form. Then identify and label the center, vertices, co-vertices, and foci.

**Solution**

First, use algebra to rewrite the equation in standard form.

$$\begin{aligned} 4x^2+25y^2 &= 100 \\ \frac{4x^2}{100}+\frac{25y^2}{100} &= \frac{100}{100} \\ \frac{x^2}{25}+\frac{y^2}{4} &= 1 \end{aligned}$$

Next, we determine the position of the major axis. Because $25>4$, the major axis is on the $x$-axis. Therefore, the equation is in the form $\frac{x^2}{a^2}+\frac{y^2}{b^2}=1$ , where $a^2=25$ and $b^2=4$. It follows that:

- the center of the ellipse is $(0,0)$
- the coordinates of the vertices are $(\pm a,0)=(\pm\sqrt{25},0)=(\pm 5,0)$
- the coordinates of the co-vertices are $(0,\pm b)=(0,\pm\sqrt{4})=(0,\pm 2)$
- the coordinates of the foci are $(\pm c,0)$, where $c^2=a^2-b^2$ . Solving for $c$, we have:

$$\begin{aligned} c &= \pm\sqrt{a^2-b^2} \\ &= \pm\sqrt{25-4} \\ &= \pm\sqrt{21} \end{aligned}$$

Therefore the coordinates of the foci are $(\pm\sqrt{21},0)$.

Next, we plot and label the center, vertices, co-vertices, and foci, and draw a smooth curve to form the ellipse.





Figure 7.3.10

**Exercise 7.3.4**

Graph the ellipse given by the equation $49x^2 + 16y^2 = 784$. Rewrite the equation in standard form. Then identify and label the center, vertices, co-vertices, and foci.

**Answer**

Standard form: $\frac{x^2}{16} + \frac{y^2}{49} = 1$ ; center: $(0, 0)$; vertices: $(0, \pm 7)$; co-vertices: $(\pm 4, 0)$; foci: $(0, \pm\sqrt{33})$





Figure 7.3.11

## Graphing Ellipses Not Centered at the Origin

When an **ellipse** is not centered at the origin, we can still use the standard forms to find the key features of the graph. When the ellipse is centered at some point, $(h, k)$,we use the standard forms $\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{b^2} = 1$ , $a > b$ for horizontal ellipses and $\frac{(x-h)^2}{b^2} + \frac{(y-k)^2}{a^2} = 1$ , $a > b$ for vertical ellipses. From these standard equations, we can easily determine the center, vertices, co-vertices, foci, and positions of the major and minor axes.

**How to: Given the standard form of an equation for an ellipse centered at $(h, k)$, sketch the graph.**

1. Use the standard forms of the equations of an ellipse to determine the center, position of the major axis, vertices, co-vertices, and foci.
   - If the equation is in the form $\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{b^2} = 1$ , where $a > b$, then
     - the center is $(h, k)$
     - the major axis is parallel to the $x$-axis
     - the coordinates of the vertices are $(h \pm a, k)$
     - the coordinates of the co-vertices are $(h, k \pm b)$
     - the coordinates of the foci are $(h \pm c, k)$
   - If the equation is in the form $\frac{(x-h)^2}{b^2} + \frac{(y-k)^2}{a^2} = 1$ , where $a > b$, then
     - the center is $(h, k)$
     - the major axis is parallel to the $y$-axis
     - the coordinates of the vertices are $(h, k \pm a)$
     - the coordinates of the co-vertices are $(h \pm b, k)$
     - the coordinates of the foci are $(h, k \pm c)$
2. Solve for $c$ using the equation $c^2 = a^2 - b^2$ .
3. Plot the center, vertices, co-vertices, and foci in the coordinate plane, and draw a smooth curve to form the ellipse.

### Example 7.3.5: Graphing an Ellipse Centered at $(h, k)$

Graph the ellipse given by the equation, $\frac{(x+2)^2}{4}+\frac{(y-5)^2}{9}=1$. Identify and label the center, vertices, co-vertices, and foci.

**Solution**

First, we determine the position of the major axis. Because $9>4$, the major axis is parallel to the $y$-axis. Therefore, the equation is in the form $\frac{(x-h)^2}{b^2}+\frac{(y-k)^2}{a^2}=1$, where $b^2=4$ and $a^2=9$. It follows that:

- the center of the ellipse is $(h, k)=(-2,5)$
- the coordinates of the vertices are $(h, k \pm a)=(-2,5 \pm \sqrt{9})=(-2,5 \pm 3)$ , or $(-2,2)$ and $(-2,8)$
- the coordinates of the co-vertices are $(h \pm b, k)=(-2 \pm \sqrt{4}, 5)=(-2 \pm 2,5)$ , or $(-4,5)$ and $(0,5)$
- the coordinates of the foci are $(h, k \pm c)$, where $c^2=a^2-b^2$ . Solving for $c$,we have:

$$\begin{aligned} c &= \pm\sqrt{a^2-b^2} \\ &= \pm\sqrt{9-4} \\ &= \pm\sqrt{5} \end{aligned}$$

Therefore, the coordinates of the foci are $(-2,5-\sqrt{5})$ and $(-2,5+\sqrt{5})$.

Next, we plot and label the center, vertices, co-vertices, and foci, and draw a smooth curve to form the ellipse.





Figure 7.3.12

### Exercise 7.3.5

Graph the ellipse given by the equation $\frac{(x-4)^2}{36}+\frac{(y-2)^2}{20}=1$. Identify and label the center, vertices, co-vertices, and foci.

**Answer**

Center: $(4,2)$; vertices: $(-2,2)$ and $(10,2)$; co-vertices: $(4,2-2\sqrt{5})$ and $(4,2+2\sqrt{5})$; foci: $(0,2)$ and $(8,2)$





Figure 7.3.13

### How to: Given the general form of an equation for an ellipse centered at $(h, k)$, express the equation in standard form.

1. Recognize that an ellipse described by an equation in the form $ax^2+by^2+cx+dy+e=0$ is in general form.
2. Rearrange the equation by grouping terms that contain the same variable. Move the constant term to the opposite side of the equation.
3. Factor out the coefficients of the $x^2$ and $y^2$ terms in preparation for completing the square.
4. Complete the square for each variable to rewrite the equation in the form of the sum of multiples of two binomials squared set equal to a constant, $m_1(x-h)^2+m_2(y-k)^2=m_3$ , where $m_1$, $m_2$,and $m_3$ are constants.
5. Divide both sides of the equation by the constant term to express the equation in standard form.

**Example 7.3.6: Graphing an Ellipse Centered at $(h, k)$ by First Writing It in Standard Form**

Graph the ellipse given by the equation $4x^2 + 9y^2 - 40x + 36y + 100 = 0$ . Identify and label the center, vertices, co-vertices, and foci.

**Solution**

We must begin by rewriting the equation in standard form.

$$4x^2 + 9y^2 - 40x + 36y + 100 = 0$$

Group terms that contain the same variable, and move the constant to the opposite side of the equation.

$$(4x^2 - 40x) + (9y^2 + 36y) = -100$$

Factor out the coefficients of the squared terms.

$$4(x^2 - 10x) + 9(y^2 + 4y) = -100$$

Complete the square twice. Remember to balance the equation by adding the same constants to each side.

$$4(x^2 - 10x + 25) + 9(y^2 + 4y + 4) = -100 + 100 + 36$$

Rewrite as perfect squares.

$$4(x-5)^2 + 9(y+2)^2 = 36$$

Divide both sides by the constant term to place the equation in standard form.

$$\frac{(x-5)^2}{9} + \frac{(y+2)^2}{4} = 1$$

Now that the equation is in standard form, we can determine the position of the major axis. Because $9 > 4$, the major axis is parallel to the $x$-axis. Therefore, the equation is in the form $\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{b^2} = 1$ , where $a^2 = 9$ and $b^2 = 4$. It follows that:

- the center of the ellipse is $(h, k) = (5, -2)$
- the coordinates of the vertices are $(h \pm a, k) = (5 \pm \sqrt{9}, -2) = (5 \pm 3, -2)$ , or $(2, -2)$ and $(8, -2)$
- the coordinates of the co-vertices are $(h, k \pm b) = (5, -2 \pm \sqrt{4}) = (5, -2 \pm 2)$ , or $(5, -4)$ and $(5, 0)$
- the coordinates of the foci are $(h \pm c, k)$, where $c^2 = a^2 - b^2$ . Solving for $c$, we have:

$$\begin{aligned} c &= \pm\sqrt{a^2 - b^2} \\ &= \pm\sqrt{9 - 4} \\ &= \pm\sqrt{5} \end{aligned}$$

Therefore, the coordinates of the foci are $(5 - \sqrt{5}, -2)$ and $(5 + \sqrt{5}, -2)$.

Next we plot and label the center, vertices, co-vertices, and foci, and draw a smooth curve to form the ellipse as shown in Figure 7.3.14





Figure 7.3.14

**Exercise 7.3.6**

Express the equation of the ellipse given in standard form. Identify the center, vertices, co-vertices, and foci of the ellipse.

$$4x^2 + y^2 - 24x + 2y + 21 = 0$$

**Answer**

$\frac{(x-3)^2}{4} + \frac{(y+1)^2}{16} = 1$ ; center: $(3, -1)$; vertices: $(3, -5)$ and $(3, 3)$; co-vertices: $(1, -1)$ and $(5, -1)$; foci: $(3, -1 - 2\sqrt{3})$ and $(3, -1 + 2\sqrt{3})$

## Solving Applied Problems Involving Ellipses

Many real-world situations can be represented by ellipses, including orbits of planets, satellites, moons and comets, and shapes of boat keels, rudders, and some airplane wings. A medical device called a lithotripter uses elliptical reflectors to break up kidney stones by generating sound waves. Some buildings, called whispering chambers, are designed with elliptical domes so that a person whispering at one focus can easily be heard by someone standing at the other focus. This occurs because of the acoustic properties of an ellipse. When a sound wave originates at one focus of a whispering chamber, the sound wave will be reflected off the elliptical dome and back to the other focus (Figure 7.3.15). In the whisper chamber at the Museum of Science and Industry in Chicago, two people standing at the foci—about 43 feet apart—can hear each other whisper.





Figure 7.3.15: Sound waves are reflected between foci in an elliptical room, called a whispering chamber.

### Example 7.3.7: Locating the Foci of a Whispering Chamber

The Statuary Hall in the Capitol Building in Washington, D.C. is a whispering chamber. Its dimensions are 46 feet wide by 96 feet long as shown in Figure 7.3.16

a. What is the standard form of the equation of the ellipse representing the outline of the room? ***Hint:*** assume a horizontal ellipse, and let the center of the room be the point $(0,0)$.
b. If two senators standing at the foci of this room can hear each other whisper, how far apart are the senators? Round to the nearest foot.





Figure 7.3.16

**Solution**

a. We are assuming a horizontal ellipse with center $(0,0)$, so we need to find an equation of the form $\frac{x^2}{a^2}+\frac{y^2}{b^2}=1$ , where $a>b$. We know that the length of the major axis, $2a$, is longer than the length of the minor axis, $2b$. So the length of the room, 96, is represented by the major axis, and the width of the room, 46, is represented by the minor axis.

Therefore, the equation of the ellipse is \[(dfrac{x^2}{2304}+\dfrac{y^2}{529}=1\)

- Solving for $a$, we have $2a=96$, so $a=48$, and $a^2=2304$.
- Solving for $b$, we have $2b=46$, so $b=23$, and $b^2=529$.

b. To find the distance between the senators, we must find the distance between the foci, $(\pm c,0)$, where $c^2=a^2-b^2$ . Solving for $c$,we have:

$$\begin{aligned} c^2 &= a^2-b^2 \\ c^2 &= 2304-529 \quad \text{Substitute using the values found in part } (a) \\ c &= \pm\sqrt{2304-529} \quad \text{Take the square root of both sides.} \\ c &= \pm\sqrt{1775} \quad \text{Subtract.} \\ c &\approx \pm 42 \quad \text{Round to the nearest foot.} \end{aligned}$$

The points $(\pm 42,0)$ represent the foci. Thus, the distance between the senators is $2(42)=84$ feet.

### Exercise 7.3.7

Suppose a whispering chamber is 480 feet long and 320 feet wide.

a. What is the standard form of the equation of the ellipse representing the room? Hint: assume a horizontal ellipse, and let the center of the room be the point $(0,0)$.
b. If two people are standing at the foci of this room and can hear each other whisper, how far apart are the people? Round to the nearest foot.

**Answer a**

$$\frac{x^2}{57,600}+\frac{y^2}{25,600}=1$$

**Answer b**

The people are standing 358 feet apart.

### Media

Access these online resources for additional instruction and practice with ellipses.

- Conic Sections: The Ellipse
- Graph an Ellipse with Center at the Origin
- Graph an Ellipse with Center Not at the Origin

## Key Equations

| | |
|---|---|
| Horizontal ellipse, center at origin | $\frac{x^2}{a^2}+\frac{y^2}{b^2}=1\ ,\ a>b$ |
| Vertical ellipse, center at origin | $\frac{x^2}{b^2}+\frac{y^2}{a^2}=1\ ,\ a>b$ |
| Horizontal ellipse, center $(h,k)$ | $\frac{(x-h)^2}{a^2}+\frac{(y-k)^2}{b^2}=1\ ,\ a>b$ |
| Vertical ellipse, center $(h,k)$ | $\frac{(x-h)^2}{b^2}+\frac{(y-k)^2}{a^2}=1\ ,\ a>b$ |

## Key Concepts

- An ellipse is the set of all points $(x, y)$ in a plane such that the sum of their distances from two fixed points is a constant. Each fixed point is called a focus (plural: foci).
- When given the coordinates of the foci and vertices of an ellipse, we can write the equation of the ellipse in standard form. See Example $7.3.1$ and Example $7.3.2$.
- When given an equation for an ellipse centered at the origin in standard form, we can identify its vertices, co-vertices, foci, and the lengths and positions of the major and minor axes in order to graph the ellipse. See Example $7.3.3$ and Example $7.3.4$.
- When given the equation for an ellipse centered at some point other than the origin, we can identify its key features and graph the ellipse. See Example $7.3.5$ and Example $7.3.6$.
- Real-world situations can be modeled using the standard equations of ellipses and then evaluated to find key features, such as lengths of axes and distance between foci. See Example $7.3.7$.

## Contributors and Attributions

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.

---

This page titled 7.3: The Ellipse is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **12.1: The Ellipse** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 7.3E: The Ellipse (Exercises)

For the following exercises, write the equation of the ellipse in standard form. Then identify the center, vertices, and foci.

1. $\frac{x^2}{25}+\frac{y^2}{64}=1$

2. $\frac{(x-2)^2}{100}+\frac{(y+3)^2}{36}=1$

3. $9x^2+y^2+54x-4y+76=0$

4. $9x^2+36y^2-36x+72y+36=0$

For the following exercises, graph the ellipse, noting center, vertices, and foci.

5. $\frac{x^2}{36}+\frac{y^2}{9}=1$

6. $\frac{(x-4)^2}{25}+\frac{(y+3)^2}{49}=1$

7. $4x^2+y^2+16x+4y-44=0$

8. $2x^2+3y^2-20x+12y+38=0$

For the following exercises, use the given information to find the equation for the ellipse.

9. Center at (0,0) , focus at (3,0) , vertex at (-5,0)

10. Center at $(2,-2)$, vertex at $(7,-2)$, focus at (4,-2)

11. A whispering gallery is to be constructed such that the foci are located 35 feet from the center. If the length of the gallery is to be 100 feet, what should the height of the ceiling be?

---

This page titled 7.3E: The Ellipse (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **12.1E: The Ellipse (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 7.4: The Hyperbola

**Learning Objectives**

- Locate a hyperbola's vertices and foci.
- Write equations of hyperbolas in standard form.
- Graph hyperbolas centered at the origin.
- Graph hyperbolas not centered at the origin.
- Solve applied problems involving hyperbolas.

What do paths of comets, supersonic booms, ancient Grecian pillars, and natural draft cooling towers have in common? They can all be modeled by the same type of **conic**. For instance, when something moves faster than the speed of sound, a shock wave in the form of a cone is created. A portion of a conic is formed when the wave intersects the ground, resulting in a sonic boom (Figure 7.4.1).





Figure 7.4.1: A shock wave intersecting the ground forms a portion of a conic and results in a sonic boom.

Most people are familiar with the sonic boom created by supersonic aircraft, but humans were breaking the sound barrier long before the first supersonic flight. The crack of a whip occurs because the tip is exceeding the speed of sound. The bullets shot from many firearms also break the sound barrier, although the bang of the gun usually supersedes the sound of the sonic boom.

## Locating the Vertices and Foci of a Hyperbola

In analytic geometry, a **hyperbola** is a conic section formed by intersecting a right circular cone with a plane at an angle such that both halves of the cone are intersected. This intersection produces two separate unbounded curves that are mirror images of each other (Figure 7.4.2).




Figure 7.4.2: A hyperbola

Like the ellipse, the hyperbola can also be defined as a set of points in the coordinate plane. A hyperbola is the set of all points $(x, y)$ in a plane such that the difference of the distances between $(x, y)$ and the foci is a positive constant.

Notice that the definition of a hyperbola is very similar to that of an ellipse. The distinction is that the hyperbola is defined in terms of the *difference* of two distances, whereas the ellipse is defined in terms of the *sum* of two distances.

As with the ellipse, every hyperbola has two **axes of symmetry**. The **transverse axis** is a line segment that passes through the center of the hyperbola and has vertices as its endpoints. The foci lie on the line that contains the transverse axis. The **conjugate axis** is perpendicular to

the transverse axis and has the co-vertices as its endpoints. The **center of a hyperbola** is the midpoint of both the transverse and conjugate axes, where they intersect. Every hyperbola also has two **asymptotes** that pass through its center. As a hyperbola recedes from the center, its branches approach these asymptotes. The **central rectangle** of the hyperbola is centered at the origin with sides that pass through each vertex and co-vertex; it is a useful tool for graphing the hyperbola and its asymptotes. To sketch the asymptotes of the hyperbola, simply sketch and extend the diagonals of the central rectangle (Figure 7.4.3).





Figure 7.4.3: Key features of the hyperbola

In this section, we will limit our discussion to hyperbolas that are positioned vertically or horizontally in the coordinate plane; the axes will either lie on or be parallel to the $x$- and $y$-axes. We will consider two cases: those that are centered at the origin, and those that are centered at a point other than the origin.

## Deriving the Equation of an Ellipse Centered at the Origin

Let $(-c, 0)$ and $(c, 0)$ be the foci of a hyperbola centered at the origin. The hyperbola is the set of all points $(x, y)$ such that the difference of the distances from $(x, y)$ to the foci is constant. See Figure 7.4.4.





Figure 7.4.4

If $(a, 0)$ is a vertex of the hyperbola, the distance from $(-c, 0)$ to $(a, 0)$ is $a-(-c)=a+c$ . The distance from $(c, 0)$ to $(a, 0)$ is $c-a$ . The sum of the distances from the foci to the vertex is

$$(a+c)-(c-a)=2a$$

If $(x, y)$ is a point on the hyperbola, we can define the following variables:

$$d_2 = \text{the distance from } (-c, 0) \text{ to } (x, y)$$

$$d_1 = \text{the distance from } (c, 0) \text{ to } (x, y)$$

By definition of a hyperbola, $d_2-d_1$ is constant for any point $(x, y)$ on the hyperbola. We know that the difference of these distances is $2a$ for the vertex $(a, 0)$. It follows that $d_2-d_1=2a$ for any point on the hyperbola. As with the derivation of the equation of an ellipse, we will begin by applying the **distance formula**. The rest of the derivation is algebraic. Compare this derivation with the one from the previous section for ellipses.

$$
\begin{aligned}
d_2 - d_1 &= 2a \\
\sqrt{(x-(-c))^2+(y-0)^2} - \sqrt{(x-c)^2+(y-0)^2} &= 2a \qquad \text{Distance Formula} \\
\sqrt{(x+c)^2+y^2} - \sqrt{(x-c)^2+y^2} &= 2a \qquad \text{Simplify expressions.} \\
\sqrt{(x+c)^2+y^2} &= 2a + \sqrt{(x-c)^2+y^2} \qquad \text{Move radical to opposite side.} \\
(x+c)^2+y^2 &= \left(2a + \sqrt{(x-c)^2+y^2}\right)^2 \qquad \text{Square both sides.} \\
x^2+2cx+c^2+y^2 &= 4a^2 + 4a\sqrt{(x-c)^2+y^2} + (x-c)^2 + y^2 \qquad \text{Expand the squares.} \\
x^2+2cx+c^2+y^2 &= 4a^2 + 4a\sqrt{(x-c)^2+y^2} + x^2 - 2cx + c^2 + y^2 \qquad \text{Expand remaining square.} \\
2cx &= 4a^2 + 4a\sqrt{(x-c)^2+y^2} - 2cx \qquad \text{Combine like terms.} \\
4cx - 4a^2 &= 4a\sqrt{(x-c)^2+y^2} \qquad \text{Isolate the radical.} \\
cx - a^2 &= a\sqrt{(x-c)^2+y^2} \qquad \text{Divide by 4.} \\
(cx-a^2)^2 &= a^2\left[\sqrt{(x-c)^2+y^2}\right]^2 \qquad \text{Square both sides.} \\
c^2x^2 - 2a^2cx + a^4 &= a^2(x^2 - 2cx + c^2 + y^2) \qquad \text{Expand the squares.} \\
c^2x^2 - 2a^2cx + a^4 &= a^2x^2 - 2a^2cx + a^2c^2 + a^2y^2 \qquad \text{Distribute } a^2 \\
a^4 + c^2x^2 &= a^2x^2 + a^2c^2 + a^2y^2 \qquad \text{Combine like terms.} \\
c^2x^2 - a^2x^2 - a^2y^2 &= a^2c^2 - a^4 \qquad \text{Rearrange terms.} \\
x^2(c^2-a^2) - a^2y^2 &= a^2(c^2-a^2) \qquad \text{Factor common terms.} \\
x^2b^2 - a^2y^2 &= a^2b^2 \qquad \text{Set } b^2 = c^2 - a^2 \\
\cdot \frac{x^2b^2}{a^2b^2} - \frac{a^2y^2}{a^2b^2} &= \frac{a^2b^2}{a^2b^2} \qquad \text{Divide both sides by } a^2b^2 \\
\frac{x^2}{a^2} - \frac{y^2}{b^2} &= 1
\end{aligned}
$$

This equation defines a hyperbola centered at the origin with vertices $(\pm a, 0)$ and co-vertices $(0, \pm b)$.

### STANDARD FORMS OF THE EQUATION OF A HYPERBOLA WITH CENTER $(0,0)$

The standard form of the equation of a hyperbola with center $(0,0)$ and transverse axis on the $x$-axis is

$$\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$$

where

- the length of the transverse axis is $2a$
- the coordinates of the vertices are $(\pm a, 0)$
- the length of the conjugate axis is $2b$
- the coordinates of the co-vertices are $(0, \pm b)$
- the distance between the foci is $2c$, where $c^2 = a^2 + b^2$
- the coordinates of the foci are $(\pm c, 0)$
- the equations of the asymptotes are $y = \pm \frac{b}{a}x$

See Figure 7.4.5a.

The standard form of the equation of a hyperbola with center $(0,0)$ and transverse axis on the $y$-axis is

$$\frac{y^2}{a^2} - \frac{x^2}{b^2} = 1$$

where

- the length of the transverse axis is $2a$
- the coordinates of the vertices are $(0, \pm a)$
- the length of the conjugate axis is $2b$
- the coordinates of the co-vertices are $(\pm b, 0)$
- the distance between the foci is $2c$, where $c^2 = a^2 + b^2$

- the coordinates of the foci are $(0, \pm c)$
- the equations of the asymptotes are $y = \pm \frac{a}{b}x$

See Figure 7.4.5b

Note that the vertices, co-vertices, and foci are related by the equation $c^2 = a^2 + b^2$ . When we are given the equation of a hyperbola, we can use this relationship to identify its vertices and foci.





Figure 7.4.5: (a) Horizontal hyperbola with center $(0, 0)$ (b) Vertical hyperbola with center $(0, 0)$

**How to: Given the equation of a hyperbola in standard form, locate its vertices and foci**

1. Determine whether the transverse axis lies on the $x$- or $y$-axis. Notice that $a^2$ is always under the variable with the positive coefficient. So, if you set the other variable equal to zero, you can easily find the intercepts. In the case where the hyperbola is centered at the origin, the intercepts coincide with the vertices.
   - If the equation has the form $\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$ , then the transverse axis lies on the $x$-axis. The vertices are located at $(\pm a, 0)$, and the foci are located at $(\pm c, 0)$.
   - If the equation has the form $\frac{y^2}{a^2} - \frac{x^2}{b^2} = 1$ , then the transverse axis lies on the $y$-axis. The vertices are located at $(0, \pm a)$, and the foci are located at $(0, \pm c)$.
2. Solve for $a$ using the equation $a = \sqrt{a^2}$ .
3. Solve for $c$ using the equation $c = \sqrt{a^2 + b^2}$ .

**Example 7.4.1: Locating a Hyperbola's Vertices and Foci**

Identify the vertices and foci of the hyperbola with equation $\frac{y^2}{49} - \frac{x^2}{32} = 1$ .

**Solution**

The equation has the form $\frac{y^2}{a^2} - \frac{x^2}{b^2} = 1$ , so the transverse axis lies on the $y$-axis. The hyperbola is centered at the origin, so the vertices serve as the $y$-intercepts of the graph. To find the vertices, set $x = 0$, and solve for $y$.

$$\begin{aligned} 1 &= \frac{y^2}{49} - \frac{x^2}{32} \\ 1 &= \frac{y^2}{49} - \frac{0^2}{32} \\ 1 &= \frac{y^2}{49} \\ y^2 &= 49 \\ y &= \pm\sqrt{49} \\ &= \pm 7 \end{aligned}$$

The foci are located at $(0, \pm c)$. Solving for $c$,

$$\begin{aligned} c &= \sqrt{a^2+b^2} \\ &= \sqrt{49+32} \\ &= \sqrt{81} \\ &= 9 \end{aligned}$$

Therefore, the vertices are located at $(0, \pm 7)$, and the foci are located at $(0, 9)$.

**? Exercise 7.4.1**

Identify the vertices and foci of the hyperbola with equation $\frac{x^2}{9} - \frac{y^2}{25} = 1$ .

**Answer**

Vertices: $(\pm 3, 0)$; Foci: $(\pm\sqrt{34}, 0)$

## Writing Equations of Hyperbolas in Standard Form

Just as with ellipses, writing the equation for a hyperbola in standard form allows us to calculate the key features: its center, vertices, co-vertices, foci, asymptotes, and the lengths and positions of the transverse and conjugate axes. Conversely, an equation for a hyperbola can be found given its key features. We begin by finding standard equations for hyperbolas centered at the origin. Then we will turn our attention to finding standard equations for hyperbolas centered at some point other than the origin.

## Hyperbolas Centered at the Origin

Reviewing the standard forms given for hyperbolas centered at $(0, 0)$,we see that the vertices, co-vertices, and foci are related by the equation $c^2 = a^2 + b^2$ . Note that this equation can also be rewritten as $b^2 = c^2 - a^2$ . This relationship is used to write the equation for a hyperbola when given the coordinates of its foci and vertices.

**How to: Given the vertices and foci of a hyperbola centered at $(0, 0)$, write its equation in standard form**

1. Determine whether the transverse axis lies on the $x$- or $y$-axis.
   - If the given coordinates of the vertices and foci have the form $(\pm a, 0)$ and $(\pm c, 0)$, respectively, then the transverse axis is the $x$-axis. Use the standard form $\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$ .
   - If the given coordinates of the vertices and foci have the form $(0, \pm a)$ and $(0, \pm c)$, respectively, then the transverse axis is the $y$-axis. Use the standard form $\frac{y^2}{a^2} - \frac{x^2}{b^2} = 1$ .
2. Find $b^2$ using the equation $b^2 = c^2 - a^2$ .
3. Substitute the values for $a^2$ and $b^2$ into the standard form of the equation determined in Step 1.

**Example 7.4.2: Finding the Equation of a Hyperbola Centered at $(0, 0)$ Given its Foci and Vertices**

What is the standard form equation of the hyperbola that has vertices $(\pm 6, 0)$ and foci $(\pm 2\sqrt{10}, 0)$?

**Solution**

The vertices and foci are on the $x$-axis. Thus, the equation for the hyperbola will have the form $\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$ .

The vertices are $(\pm 6, 0)$, so $a = 6$ and $a^2 = 36$.

The foci are $(\pm 2\sqrt{10}, 0)$, so $c = 2\sqrt{10}$ and $c^2 = 40$.

Solving for $b^2$, we have

$$\begin{aligned} b^2 &= c^2 - a^2 \\ b^2 &= 40 - 36 \qquad \text{Substitute for } c^2 \text{ and } a^2 \\ b^2 &= 4 \qquad \text{Subtract.} \end{aligned}$$

Finally, we substitute $a^2 = 36$ and $b^2 = 4$ into the standard form of the equation, $\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$ . The equation of the hyperbola is $\frac{x^2}{36} - \frac{y^2}{4} = 1$ , as shown in Figure 7.4.6.





Figure 7.4.6

**Exercise 7.4.2**

What is the standard form equation of the hyperbola that has vertices $(0, \pm 2)$ and foci $(0, \pm 2\sqrt{5})$?

**Answer**

$$\frac{y^2}{4} - \frac{x^2}{16} = 1$$

### Hyperbolas Not Centered at the Origin

Like the graphs for other equations, the graph of a hyperbola can be translated. If a hyperbola is translated $h$ units horizontally and $k$ units vertically, the center of the hyperbola will be $(h, k)$. This translation results in the standard form of the equation we saw previously, with $x$ replaced by $(x - h)$ and $y$ replaced by $(y - k)$.

**STANDARD FORMS OF THE EQUATION OF A HYPERBOLA WITH CENTER $(H, K)$**

The standard form of the equation of a hyperbola with center $(h, k)$ and transverse axis parallel to the $x$-axis is

$$\frac{(x-h)^2}{a^2} - \frac{(y-k)^2}{b^2} = 1 \tag{7.4.1}$$

where

- the length of the transverse axis is $2a$
- the coordinates of the vertices are $(h \pm a, k)$
- the length of the conjugate axis is $2b$
- the coordinates of the co-vertices are $(h, k \pm b)$
- the distance between the foci is $2c$, where $c^2 = a^2 + b^2$
- the coordinates of the foci are $(h \pm c, k)$

The asymptotes of the hyperbola coincide with the diagonals of the central rectangle. The length of the rectangle is $2a$ and its width is $2b$. The slopes of the diagonals are $\pm\frac{b}{a}$,and each diagonal passes through the center $(h, k)$. Using the point-slope formula, it is simple to show that the equations of the asymptotes are $y = \pm\frac{b}{a}(x - h) + k$ . See Figure 7.4.7a

The standard form of the equation of a hyperbola with center $(h, k)$ and transverse axis parallel to the $y$-axis is

$$\frac{(y-k)^2}{a^2} - \frac{(x-h)^2}{b^2} = 1 \tag{7.4.2}$$

where

- the length of the transverse axis is $2a$
- the coordinates of the vertices are $(h, k \pm a)$
- the length of the conjugate axis is $2b$
- the coordinates of the co-vertices are $(h \pm b, k)$
- the distance between the foci is $2c$, where $c^2 = a^2 + b^2$
- the coordinates of the foci are $(h, k \pm c)$

Using the reasoning above, the equations of the asymptotes are $y = \pm\frac{a}{b}(x - h) + k$ . See Figure 7.4.7b





Figure 7.4.7: (a) Horizontal hyperbola with center $(h, k)$ (b) Vertical hyperbola with center $(h, k)$

Like hyperbolas centered at the origin, hyperbolas centered at a point $(h, k)$ have vertices, co-vertices, and foci that are related by the equation $c^2 = a^2 + b^2$ . We can use this relationship along with the midpoint and distance formulas to find the standard equation of a hyperbola when the vertices and foci are given.

### How to: Given the vertices and foci of a hyperbola centered at $(h, k)$,write its equation in standard form

1. Determine whether the transverse axis is parallel to the $x$- or $y$-axis.
   - If the $y$-coordinates of the given vertices and foci are the same, then the transverse axis is parallel to the $x$-axis. Use the standard form $\frac{(x-h)^2}{a^2} - \frac{(y-k)^2}{b^2} = 1$ .
   - If the $x$-coordinates of the given vertices and foci are the same, then the transverse axis is parallel to the $y$-axis. Use the standard form $\frac{(y-k)^2}{a^2} - \frac{(x-h)^2}{b^2} = 1$ .
2. Identify the center of the hyperbola, $(h, k)$,using the midpoint formula and the given coordinates for the vertices.
3. Find $a^2$ by solving for the length of the transverse axis, $2a$, which is the distance between the given vertices.
4. Find $c^2$ using $h$ and $k$ found in Step 2 along with the given coordinates for the foci.
5. Solve for $b^2$ using the equation $b^2 = c^2 - a^2$ .
6. Substitute the values for $h$, $k$, $a^2$, and $b^2$ into the standard form of the equation determined in Step 1.

### Example 7.4.3: Finding the Equation of a Hyperbola Centered at $(h, k)$ Given its Foci and Vertices

What is the standard form equation of the **hyperbola** that has vertices at $(0, -2)$ and $(6, -2)$ and foci at $(-2, -2)$ and $(8, -2)$?

**Solution**

The $y$-coordinates of the vertices and foci are the same, so the transverse axis is parallel to the $x$-axis. Thus, the equation of the hyperbola will have the form

$$\frac{(x-h)^2}{a^2} - \frac{(y-k)^2}{b^2} = 1$$

First, we identify the center, $(h, k)$. The center is halfway between the vertices $(0, -2)$ and $(6, -2)$. Applying the midpoint formula, we have

$$(h, k) = \left(\frac{0+6}{2}, \frac{-2+(-2)}{2}\right) = (3, -2)$$

Next, we find $a^2$. The length of the transverse axis, $2a$,is bounded by the vertices. So, we can find $a^2$ by finding the distance between the $x$-coordinates of the vertices.

$$\begin{aligned} 2a &= |0-6| \\ 2a &= 6 \\ a &= 3 \\ a^2 &= 9 \end{aligned}$$

Now we need to find $c^2$. The coordinates of the foci are $(h \pm c, k)$. So $(h-c, k) = (-2, -2)$ and $(h+c, k) = (8, -2)$. We can use the $x$-coordinate from either of these points to solve for $c$. Using the point $(8, -2)$, and substituting $h = 3$,

$$\begin{aligned} h+c &= 8 \\ 3+c &= 8 \\ c &= 5 \\ c^2 &= 25 \end{aligned}$$

Next, solve for $b^2$ using the equation $b^2 = c^2 - a^2$ :

$$\begin{aligned} b^2 &= c^2 - a^2 \\ &= 25 - 9 \\ &= 16 \end{aligned}$$

Finally, substitute the values found for $h$, $k$, $a^2$,and $b^2$ into the standard form of the equation.

$$\frac{(x-3)^2}{9} - \frac{(y+2)^2}{16} = 1$$

**? Exercise 7.4.3**

What is the standard form equation of the hyperbola that has vertices $(1, -2)$ and $(1, 8)$ and foci $(1, -10)$ and $(1, 16)$?

**Answer**

$$\frac{(y-3)^2}{25} + \frac{(x-1)^2}{144} = 1$$

## Graphing Hyperbolas Centered at the Origin

When we have an equation in standard form for a hyperbola centered at the origin, we can interpret its parts to identify the key features of its graph: the center, vertices, co-vertices, asymptotes, foci, and lengths and positions of the transverse and conjugate axes. To graph hyperbolas centered at the origin, we use the standard form $\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$ for horizontal hyperbolas and the standard form $\frac{y^2}{a^2} - \frac{x^2}{b^2} = 1$ for vertical hyperbolas.

**How to: Given a standard form equation for a hyperbola centered at $(0, 0)$, sketch the graph**

1. Determine which of the standard forms applies to the given equation.
2. Use the standard form identified in Step 1 to determine the position of the transverse axis; coordinates for the vertices, co-vertices, and foci; and the equations for the asymptotes.
   - If the equation is in the form $\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$ , then
     - the transverse axis is on the $x$-axis
     - the coordinates of the vertices are \((\pm a,0)\0
     - the coordinates of the co-vertices are $(0, \pm b)$
     - the coordinates of the foci are $(\pm c, 0)$
     - the equations of the asymptotes are $y = \pm \frac{b}{a} x$
   - If the equation is in the form $\frac{y^2}{a^2} - \frac{x^2}{b^2} = 1$ , then
     - the transverse axis is on the $y$-axis
     - the coordinates of the vertices are $(0, \pm a)$
     - the coordinates of the co-vertices are $(\pm b, 0)$
     - the coordinates of the foci are $(0, \pm c)$
     - the equations of the asymptotes are $y = \pm \frac{a}{b} x$

3. Solve for the coordinates of the foci using the equation $c = \pm\sqrt{a^2 + b^2}$ .
4. Plot the vertices, co-vertices, foci, and asymptotes in the coordinate plane, and draw a smooth curve to form the hyperbola.

### Example 7.4.4: Graphing a Hyperbola Centered at $(0, 0)$ Given an Equation in Standard Form

Graph the hyperbola given by the equation $\frac{y^2}{64} - \frac{x^2}{36} = 1$ . Identify and label the vertices, co-vertices, foci, and asymptotes.

**Solution**

The standard form that applies to the given equation is $\frac{y^2}{a^2} - \frac{x^2}{b^2} = 1$ . Thus, the transverse axis is on the $y$-axis

The coordinates of the vertices are $(0, \pm a) = (0, \pm\sqrt{64}) = (0, \pm 8)$

The coordinates of the co-vertices are $(\pm b, 0) = (\pm\sqrt{36}, 0) = (\pm 6, 0)$

The coordinates of the foci are $(0, \pm c)$, where $c = \pm\sqrt{a^2 + b^2}$ . Solving for $c$, we have

$$c = \pm\sqrt{a^2 + b^2} = \pm\sqrt{64 + 36} = \pm\sqrt{100} = \pm 10$$

Therefore, the coordinates of the foci are $(0, \pm 10)$

The equations of the asymptotes are $y = \pm\frac{a}{b}x = \pm\frac{8}{6}x = \pm\frac{4}{3}x$

Plot and label the vertices and co-vertices, and then sketch the central rectangle. Sides of the rectangle are parallel to the axes and pass through the vertices and co-vertices. Sketch and extend the diagonals of the central rectangle to show the asymptotes. The central rectangle and asymptotes provide the framework needed to sketch an accurate graph of the hyperbola. Label the foci and asymptotes, and draw a smooth curve to form the hyperbola, as shown in Figure 7.4.8.





Figure 7.4.8

### Exercise 7.4.4

Graph the hyperbola given by the equation $\frac{x^2}{144} - \frac{y^2}{81} = 1$ . Identify and label the vertices, co-vertices, foci, and asymptotes.

**Answer**

vertices: $(\pm 12, 0)$; co-vertices: $(0, \pm 9)$; foci: $(\pm 15, 0)$; asymptotes: $y = \pm\frac{3}{4}x$ ;





Figure 7.4.9

## Graphing Hyperbolas Not Centered at the Origin

Graphing hyperbolas centered at a point $(h, k)$ other than the origin is similar to graphing ellipses centered at a point other than the origin. We use the standard forms $\frac{(x-h)^2}{a^2} - \frac{(y-k)^2}{b^2} = 1$ for horizontal hyperbolas, and $\frac{(y-k)^2}{a^2} - \frac{(x-h)^2}{b^2} = 1$ for vertical hyperbolas. From these standard form equations we can easily calculate and plot key features of the graph: the coordinates of its center, vertices, co-vertices, and foci; the equations of its asymptotes; and the positions of the transverse and conjugate axes.

### How to: Given a general form for a hyperbola centered at $(h, k)$, sketch the graph

1. Convert the general form to that standard form. Determine which of the standard forms applies to the given equation.
2. Use the standard form identified in Step 1 to determine the position of the transverse axis; coordinates for the center, vertices, co-vertices, foci; and equations for the asymptotes.
   1. If the equation is in the form $\frac{(x-h)^2}{a^2} - \frac{(y-k)^2}{b^2} = 1$ , then
      - the transverse axis is parallel to the $x$-axis
      - the center is $(h, k)$
      - the coordinates of the vertices are $(h \pm a, k)$
      - the coordinates of the co-vertices are $(h, k \pm b)$
      - the coordinates of the foci are $(h \pm c, k)$
      - the equations of the asymptotes are $y = \pm\frac{b}{a}(x-h) + k$
   2. If the equation is in the form $\frac{(y-k)^2}{a^2} - \frac{(x-h)^2}{b^2} = 1$ , then
      - the transverse axis is parallel to the $y$-axis
      - the center is $(h, k)$
      - the coordinates of the vertices are $(h, k \pm a)$
      - the coordinates of the co-vertices are $(h \pm b, k)$
      - the coordinates of the foci are $(h, k \pm c)$
      - the equations of the asymptotes are $y = \pm\frac{a}{b}(x-h) + k$
3. Solve for the coordinates of the foci using the equation $c = \pm\sqrt{a^2 + b^2}$ .
4. Plot the center, vertices, co-vertices, foci, and asymptotes in the coordinate plane and draw a smooth curve to form the hyperbola.

### Example 7.4.5: Graphing a Hyperbola Centered at $(h, k)$ Given an Equation in General Form

Graph the hyperbola given by the equation $9x^2 - 4y^2 - 36x - 40y - 388 = 0$ . Identify and label the center, vertices, co-vertices, foci, and asymptotes.

**Solution**

Start by expressing the equation in standard form. Group terms that contain the same variable, and move the constant to the opposite side of the equation.

$$(9x^2-36x)-(4y^2+40y)=388$$

Factor the leading coefficient of each expression.

$$9(x^2-4x)-4(y^2+10y)=388$$

Complete the square twice. Remember to balance the equation by adding the same constants to each side.

$$9(x^2-4x+4)-4(y^2+10y+25)=388+36-100$$

Rewrite as perfect squares.

$$9(x-2)^2-4(y+5)^2=324$$

Divide both sides by the constant term to place the equation in standard form.

$$\frac{(x-2)^2}{36}-\frac{(y+5)^2}{81}=1$$

The standard form that applies to the given equation is $\frac{(x-h)^2}{a^2}-\frac{(y-k)^2}{b^2}=1$ , where $a^2=36$ and $b^2=81$,or $a=6$ and $b=9$. Thus, the transverse axis is parallel to the $x$-axis. It follows that:

the center of the ellipse is $(h,k)=(2,-5)$

the coordinates of the vertices are $(h\pm a,k)=(2\pm 6,-5)$ , or $(-4,-5)$ and $(8,-5)$

the coordinates of the co-vertices are $(h,k\pm b)=(2,-5\pm 9)$ , or $(2,-14)$ and $(2,4)$

the coordinates of the foci are $(h\pm c,k)$, where $c=\pm\sqrt{a^2+b^2}$ . Solving for $c$,we have

$$c=\pm\sqrt{36+81}=\pm\sqrt{117}=\pm 3\sqrt{13}$$

Therefore, the coordinates of the foci are $(2-3\sqrt{13},-5)$ and $(2+3\sqrt{13},-5)$.

The equations of the asymptotes are $y=\pm\frac{b}{a}(x-h)+k=\pm\frac{3}{2}(x-2)-5$ .

Next, we plot and label the center, vertices, co-vertices, foci, and asymptotes and draw smooth curves to form the hyperbola, as shown in Figure 7.4.10





Figure 7.4.10

## Exercise 7.4.5

Graph the hyperbola given by the standard form of an equation $\frac{(y+4)^2}{100}-\frac{(x-3)^2}{64}=1$ . Identify and label the center, vertices, co-vertices, foci, and asymptotes.

**Answer**

center: $(3,-4)$; vertices: $(3,-14)$ and $(3,6)$; co-vertices: $(-5,-4)$; and $(11,-4)$; foci: $(3,-4-2\sqrt{41})$ and $(3,-4+2\sqrt{41})$; asymptotes: $y=\pm\frac{5}{4}(x-3)-4$





Figure 7.4.11

## Solving Applied Problems Involving Hyperbolas

As we discussed at the beginning of this section, hyperbolas have real-world applications in many fields, such as astronomy, physics, engineering, and architecture. The design efficiency of hyperbolic cooling towers is particularly interesting. Cooling towers are used to transfer waste heat to the atmosphere and are often touted for their ability to generate power efficiently. Because of their hyperbolic form, these structures are able to withstand extreme winds while requiring less material than any other forms of their size and strength (Figure 7.4.12). For example, a 500-foot tower can be made of a reinforced concrete shell only 6 or 8 inches wide!



Figure 7.4.12: Cooling towers at the Drax power station in North Yorkshire, United Kingdom (credit: Les Haines, Flickr)

The first hyperbolic towers were designed in 1914 and were 35 meters high. Today, the tallest cooling towers are in France, standing a remarkable 170 meters tall. In Example 7.4.6 we will use the design layout of a cooling tower to find a hyperbolic equation that models its sides.

### Example 7.4.6: Solving Applied Problems Involving Hyperbolas

The design layout of a cooling tower is shown in Figure 7.4.13. The tower stands 179.6 meters tall. The diameter of the top is 72 meters. At their closest, the sides of the tower are 60 meters apart.





Figure 7.4.13: Project design for a natural draft cooling tower

Find the equation of the hyperbola that models the sides of the cooling tower. Assume that the center of the hyperbola—indicated by the intersection of dashed perpendicular lines in the figure—is the origin of the coordinate plane. Round final values to four decimal places.

### Solution

We are assuming the center of the tower is at the origin, so we can use the standard form of a horizontal hyperbola centered at the origin: $\frac{x^2}{a^2}-\frac{y^2}{b^2}=1$, where the branches of the hyperbola form the sides of the cooling tower. We must find the values of $a^2$ and $b^2$ to complete the model.

First, we find $a^2$. Recall that the length of the transverse axis of a hyperbola is $2a$. This length is represented by the distance where the sides are closest, which is given as $65.3$ meters. So, $2a=60$. Therefore, $a=30$ and $a^2=900$.

To solve for $b^2$,we need to substitute for $x$ and $y$ in our equation using a known point. To do this, we can use the dimensions of the tower to find some point $(x,y)$ that lies on the hyperbola. We will use the top right corner of the tower to represent that point. Since the $y$-axis bisects the tower, our $x$-value can be represented by the radius of the top, or $36$ meters. The $y$-value is represented by the distance from the origin to the top, which is given as $79.6$ meters. Therefore,

$$\begin{aligned}\frac{x^2}{a^2}-\frac{y^2}{b^2}&=1 && \text{Standard form of horizontal hyperbola.}\\ b^2&=\frac{y^2}{\frac{x^2}{a^2}-1} && \text{Isolate } b^2\\ &=\frac{(79.6)^2}{\frac{(36)^2}{900}-1} && \text{Substitute for } a^2,\ x,\ \text{and } y\\ &\approx 14400.3636 && \text{Round to four decimal places}\end{aligned}$$

The sides of the tower can be modeled by the hyperbolic equation

$$\frac{x^2}{900}-\frac{y^2}{14400.3636}=1 \text{ ,or } \frac{x^2}{30^2}-\frac{y^2}{120.0015^2}=1$$

### Exercise 7.4.6

A design for a cooling tower project is shown in Figure 7.4.14 Find the equation of the hyperbola that models the sides of the cooling tower. Assume that the center of the hyperbola—indicated by the intersection of dashed perpendicular lines in the figure—is the origin of the coordinate plane. Round final values to four decimal places.





Figure 7.4.14

**Answer**

The sides of the tower can be modeled by the hyperbolic equation. $\frac{x^2}{400} - \frac{y^2}{3600} = 1$ or $\frac{x^2}{20^2} - \frac{y^2}{60^2} = 1$ .

## Media

Access these online resources for additional instruction and practice with hyperbolas.

- Conic Sections: The Hyperbola Part 1 of 2
- Conic Sections: The Hyperbola Part 2 of 2
- Graph a Hyperbola with Center at Origin
- Graph a Hyperbola with Center not at Origin

## Key Equations

| | |
|---|---|
| Hyperbola, center at origin, transverse axis on *x*-axis | $\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$ |
| Hyperbola, center at origin, transverse axis on *y*-axis | $\frac{y^2}{a^2} - \frac{x^2}{b^2} = 1$ |
| Hyperbola, center at $(h, k)$,transverse axis parallel to *x*-axis | $\frac{(x-h)^2}{a^2} - \frac{(y-k)^2}{b^2} = 1$ |
| Hyperbola, center at $(h, k)$,transverse axis parallel to *y*-axis | $\frac{(y-k)^2}{a^2} - \frac{(x-h)^2}{b^2} = 1$ |

## Key Concepts

- A hyperbola is the set of all points $(x, y)$ in a plane such that the difference of the distances between $(x, y)$ and the foci is a positive constant.
- The standard form of a hyperbola can be used to locate its vertices and foci. See Example 7.4.1.
- When given the coordinates of the foci and vertices of a hyperbola, we can write the equation of the hyperbola in standard form. See Example 7.4.2 and Example 7.4.3.
- When given an equation for a hyperbola, we can identify its vertices, co-vertices, foci, asymptotes, and lengths and positions of the transverse and conjugate axes in order to graph the hyperbola. See Example 7.4.4 and Example 7.4.5.
- Real-world situations can be modeled using the standard equations of hyperbolas. For instance, given the dimensions of a natural draft cooling tower, we can find a hyperbolic equation that models its sides. See Example 7.4.6.

This page titled 7.4: The Hyperbola is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **12.2: The Hyperbola** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 7.4E: The Hyperbola (Exercises)

For the following exercises, write the equation of the hyperbola in standard form. Then give the center, vertices, and foci.

12. $\frac{x^2}{81} - \frac{y^2}{9} = 1$

13. $\frac{(y+1)^2}{16} - \frac{(x-4)^2}{36} = 1$

14. $9y^2 - 4x^2 + 54y - 16x + 29 = 0$

15. $3x^2 - y^2 - 12x - 6y - 9 = 0$

For the following exercises, graph the hyperbola, labeling vertices and foci.

16. $\frac{x^2}{9} - \frac{y^2}{16} = 1$

17. $\frac{(y-1)^2}{49} - \frac{(x+1)^2}{4} = 1$

18. $x^2 - 4y^2 + 6x + 32y - 91 = 0$

19. $2y^2 - x^2 - 12y - 6 = 0$

For the following exercises, find the equation of the hyperbola.

20. Center at (0,0) , vertex at (0,4) , focus at (0,-6)

21. Foci at (3,7) and (7,7) , vertex at (6,7)

---

This page titled 7.4E: The Hyperbola (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **12.2E: The Hyperbola (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# CHAPTER OVERVIEW

## 8: Sequences, Probability, and Counting Theory

In this chapter, we will explore the mathematics behind situations involving probabilities and counting. We will take an in-depth look at annuities. We will also look at the branch of mathematics that would allow us to calculate the number of ways to choose lottery numbers and the probability of winning.


8.1: Prelude to Sequences, Probability and Counting Theory

8.2: Sequences and Their Notations

8.2E: Sequences and Their Notations (Exercises)

8.3: Arithmetic Sequences

8.3E: Arithmetic Sequences (Exercises)

8.4: Geometric Sequences

8.4E: Geometric Sequences (Exercises)

8.5: Series and Their Notations

8.5E: Series and Their Notations (Exercises)


### Contributors

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.


This page titled 8: Sequences, Probability, and Counting Theory is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

# 8.1: Prelude to Sequences, Probability and Counting Theory

A lottery winner has some big decisions to make regarding what to do with the winnings. Buy a villa in Saint Barthélemy? A luxury convertible? A cruise around the world? The likelihood of winning the lottery is slim, but we all love to fantasize about what we could buy with the winnings. One of the first things a lottery winner has to decide is whether to take the winnings in the form of a lump sum or as a series of regular payments, called an annuity, over the next 30 years or so.




Figure 8.1.1: (credit: Robert S. Donovan, Flickr.)

This decision is often based on many factors, such as tax implications, interest rates, and investment strategies. There are also personal reasons to consider when making the choice, and one can make many arguments for either decision. However, most lottery winners opt for the lump sum. In this chapter, we will explore the mathematics behind situations such as these. We will take an in-depth look at annuities. We will also look at the branch of mathematics that would allow us to calculate the number of ways to choose lottery numbers and the probability of winning.

---

This page titled 8.1: Prelude to Sequences, Probability and Counting Theory is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.0: Prelude to Sequences, Probability and Counting Theory** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 8.2: Sequences and Their Notations

**Learning Objectives**

- Write the terms of a sequence defined by an explicit formula.
- Write the terms of a sequence defined by a recursive formula.
- Use factorial notation.

A video game company launches an exciting new advertising campaign. They predict the number of online visits to their website, or hits, will double each day. The model they are using shows 2 hits the first day, 4 hits the second day, 8 hits the third day, and so on (Table 8.2.1).

Table 8.2.1

| **Day** | 1 | 2 | 3 | 4 | 5 | … |
|---|---|---|---|---|---|---|
| **Hits** | 2 | 4 | 8 | 16 | 32 | … |

If their model continues, how many hits will there be at the end of the month? To answer this question, we'll first need to know how to determine a list of numbers written in a specific order. In this section, we will explore these kinds of ordered lists.

## Writing the Terms of a Sequence Defined by an Explicit Formula

One way to describe an ordered list of numbers is as a *sequence*. A sequence is a function whose domain is a subset of the counting numbers. The sequence established by the number of hits on the website is

$$\{2, 4, 8, 16, 32, \ldots\}$$

The *ellipsis* (…) indicates that the sequence continues indefinitely. Each number in the sequence is called a term. The first five terms of this sequence are 2, 4, 8, 16, and 32.

Listing all of the terms for a sequence can be cumbersome. For example, finding the number of hits on the website at the end of the month would require listing out as many as 31 terms. A more efficient way to determine a specific term is by writing a formula to define the sequence.

One type of formula is an *explicit formula*, which defines the terms of a sequence using their position in the sequence. Explicit formulas are helpful if we want to find a specific term of a sequence without finding all of the previous terms. We can use the formula to find the nth *term of the sequence*, where nn is any positive number. In our example, each number in the sequence is double the previous number, so we can use powers of 2 to write a formula for the nth term.

$$\{2,\ 4,\ 8, 16, 32, \ldots, ?, \ldots\}$$
$$\downarrow\ \downarrow\ \downarrow\ \downarrow\ \downarrow\ \downarrow\ \qquad \downarrow$$
$$\{2^1, 2^2, 2^3, 2^4, 2^5, \ldots, 2^n, \ldots\}$$

The first term of the sequence is $2^1 = 2$, the second term is $2^2 = 4$, the third term is $2^3 = 8$, and so on. The nth term of the sequence can be found by raising 2 to the nth power. An explicit formula for a sequence is named by a lower case letter $a$, $b$, $c$... with the subscript $n$. The explicit formula for this sequence is

$$a_n = 2^n$$

Now that we have a formula for the nth term of the sequence, we can answer the question posed at the beginning of this section. We were asked to find the number of hits at the end of the month, which we will take to be 31 days. To find the number of hits on the last day of the month, we need to find the 31st term of the sequence. We will substitute 31 for $n$ in the formula.

$$a_{31} = 2^{31}$$
$$[5pt] = 2,147,483,648$$

If the doubling trend continues, the company will get $2,147,483,648$hits on the last day of the month. That is over 2.1 billion hits! The huge number is probably a little unrealistic because it does not take consumer interest and competition into account. It does, however, give the company a starting point from which to consider business decisions.

Another way to represent the sequence is by using a table. The first five terms of the sequence and the nth term of the sequence are shown in Table 8.2.2.

**Table 8.2.2**

| $n$ | 1 | 2 | 3 | 4 | 5 | $n$ |
|---|---|---|---|---|---|---|
| $n^{th}$ term of the sequence, $a_n$ | 2 | 4 | 8 | 16 | 32 | $2^n$ |

Graphing provides a visual representation of the sequence as a set of distinct points. We can see from the graph in Figure 8.2.1 that the number of hits is rising at an exponential rate. This particular sequence forms an exponential function.





Figure 8.2.1

Lastly, we can write this particular sequence as

$$\{2, 4, 8, 16, 32, \ldots, 2^n, \ldots\}$$

A sequence that continues indefinitely is called an **infinite sequence**. The domain of an infinite sequence is the set of counting numbers. If we consider only the first 10 terms of the sequence, we could write

$$\{2, 4, 8, 16, 32, \ldots, 2^n, \ldots, 1024\}$$

This sequence is called a **finite sequence** because it does not continue indefinitely.

## SEQUENCE

A *sequence* is a function whose domain is the set of positive integers. A *finite sequence* is a sequence whose domain consists of only the first $n$ positive integers. The numbers in a sequence are called *terms*. The variable $a$ with a number subscript is used to represent the terms in a sequence and to indicate the position of the term in the sequence.

$$a_1, a_2, a_3, \ldots, a_n, \ldots \tag{8.2.1}$$

We call $a_1$ the first term of the sequence, $a_2$ the second term of the sequence, $a_3$ the third term of the sequence, and so on. The term $a_n$ is called the nth term of the sequence, or the general term of the sequence. An explicit formula defines the nth term of a sequence using the position of the term. A sequence that continues indefinitely is an infinite sequence.

### Q&A: Does a sequence always have to begin with $a_1$?

*No. In certain problems, it may be useful to define the initial term as $a_0$ instead of $a_1$. In these problems, the domain of the function includes 0.*

### How to: Given an explicit formula, write the first $n$ terms of a sequence

1. Substitute each value of $n$ into the formula. Begin with $n = 1$ to find the first term, $a_1$.
2. To find the second term, $a_2$, use $n = 2$.
3. Continue in the same manner until you have identified all nn terms.

### Example 8.2.1: Writing the Terms of a Sequence Defined by an Explicit Formula

Write the first five terms of the sequence defined by the explicit formula $a_n = -3n + 8$ .

**Solution**

Substitute $n = 1$ into the formula. Repeat with values 2 through 5 for $n$.

$$\begin{aligned} n = 1 \quad & a_1 = -3(1) + 8 = 5 \\ n = 2 \quad & a_2 = -3(2) + 8 = 2 \\ n = 3 \quad & a_3 = -3(3) + 8 = -1 \\ n = 4 \quad & a_4 = -3(4) + 8 = -4 \\ n = 5 \quad & a_5 = -3(5) + 8 = -7 \end{aligned}$$

The first five terms are $\{5, 2, -1, -4, -7\}$.

**Analysis**

The sequence values can be listed in a table. A table, such as Table 8.2.3, is a convenient way to input the function into a graphing utility.

Table 8.2.3

| $n$ | 1 | 2 | 3 | 4 | 5 |
|---|---|---|---|---|---|
| $a_n$ | 5 | 2 | –1 | –4 | –7 |

A graph can be made from this table of values. From the graph in Figure 8.2.2, we can see that this sequence represents a linear function, but notice the graph is not continuous because the domain is over the positive integers only.





Figure 8.2.2

### Exercise 8.2.1

Write the first five terms of the sequence defined by the *explicit formula* $t_n = 5n - 4$ .

**Answer**

The first five terms are $\{1, 6, 11, 16, 21\}$

### Investigating Alternating Sequences

Sometimes sequences have terms that are alternate. In fact, the terms may actually alternate in sign. The steps to finding terms of the sequence are the same as if the signs did not alternate. However, the resulting terms will not show increase or decrease as $n$ increases. Let's take a look at the following sequence.

$$\{2, -4, 6, -8\}$$

Notice the first term is greater than the second term, the second term is less than the third term, and the third term is greater than the fourth term. This trend continues forever. Do not rearrange the terms in numerical order to interpret the sequence.

**How to: Given an explicit formula with alternating terms, write the first nn terms of a sequence**

1. Substitute each value of nn into the formula. Begin with $n=1$ to find the first term, $a_1$. The sign of the term is given by the $(-1)^n$ in the explicit formula.
2. To find the second term, $a_2$, use $n=2$.
3. Continue in the same manner until you have identified all $n$ terms.

**Example 8.2.2: Writing the Terms of an Alternating Sequence Defined by an Explicit Formula**

Write the first five terms of the sequence.

$$a_n=\frac{(-1)^n n^2}{n+1}$$

**Solution**

Substitute $n=1$, $n=2$, and so on in the formula.

$$\begin{aligned} n=1 \quad a_1&=\frac{(-1)^1 2^2}{1+1}=-\frac{1}{2}\\ n=2 \quad a_2&=\frac{(-1)^2 2^2}{2+1}=\frac{4}{3}\\ n=3 \quad a_3&=\frac{(-1)^3 3^2}{3+1}=-\frac{9}{4}\\ n=4 \quad a_4&=\frac{(-1)^4 4^2}{4+1}=\frac{16}{5}\\ n=5 \quad a_5&=\frac{(-1)^5 5^2}{5+1}=-\frac{25}{6} \end{aligned}$$

The first five terms are $\{-12, 43, -94, 165, -256\}$

**Analysis**

The graph of this function, shown in Figure 8.2.3, looks different from the ones we have seen previously in this section because the terms of the sequence alternate between positive and negative values.





Figure 8.2.3

**Q&A: In the example above, does the $(-1)$ to the power of $n$ account for the oscillations of signs?**

*Yes, the power might be $n$, $n+1$, $n-1$, and so on, but any odd powers will result in a negative term, and any even power will result in a positive term.*

**Exercise 8.2.2**

Write the first five terms of the sequence:

$$a_n=\frac{4n}{(-2)^n}$$

**Answer**

The first five terms are $\{-2, 2, -32, 1, -58\}$

## Investigating Piecewise Explicit Formulas

We've learned that sequences are functions whose domain is over the positive integers. This is true for other types of functions, including some piecewise functions. Recall that a *piecewise function* is a function defined by multiple subsections. A different formula might represent each individual subsection.

**How to: Given an explicit formula for a piecewise function, write the first $n$ terms of a sequence**

1. Identify the formula to which $n=1$ applies.
2. To find the first term, $a_1$, use $n=1$ in the appropriate formula.
3. Identify the formula to which $n=2$ applies.
4. To find the second term, $a_2$, use $n=2$ in the appropriate formula.
5. Continue in the same manner until you have identified all $n$ terms.

**Example 8.2.3: Writing the Terms of a Sequence Defined by a Piecewise Explicit Formula**

Write the first six terms of the sequence.

$$a_n = \begin{cases} n^2 \text{ if n is not divisible by 3} \\ \frac{n}{3} \text{if n is divisible by 3} \end{cases}$$

**Solution**

Substitute $n = 1$, $n = 2$, and so on in the appropriate formula. Use $n^2$ when $n$ is not a multiple of 3. Use $n^3$ when $n$ is a multiple of 3.

$$\begin{aligned} a_1 &= 1^2 = 1 && 1 \text{ is not a multiple of 3. Use } n^2. \\ a_2 &= 2^2 = 4 && 2 \text{ is not a multiple of 3 . Use } n^2. \\ a_3 &= \frac{3}{3} = 1 && 3 \text{ is a multiple of 3. Use } \frac{n}{3}. \\ a_4 &= 4^2 = 16 && 4 \text{ is not a multiple of 3. Use } n^2. \\ a_5 &= 5^2 = 25 && 5 \text{ is not a multiple of 3.Use } n^2. \\ a_6 &= \frac{6}{3} = 2 && 6 \text{ is a multiple of 3.Use } \frac{n}{3} \end{aligned}$$

The first six terms are $\{1, 4, 1, 16, 25, 2\}$

**Analysis**

Every third point on the graph shown in Figure 8.2.4 stands out from the two nearby points. This occurs because the sequence was defined by a piecewise function.





Figure 8.2.4

**Exercise 8.2.3**

Write the first six terms of the sequence.

$$a_n = \begin{cases} 2n^3 \text{ if } n \text{ is odd} \\ \frac{5n}{2} \text{ if } n \text{ is even} \end{cases}$$

**Answer**

The first six terms are $\{2, 5, 54, 10, 250, 15\}$

## Finding an Explicit Formula

Thus far, we have been given the explicit formula and asked to find a number of terms of the sequence. Sometimes, the explicit formula for the nth term of a sequence is not given. Instead, we are given several terms from the sequence. When this happens, we can work in reverse to find an explicit formula from the first few terms of a sequence. The key to finding an explicit formula is to look for a pattern in the terms. Keep in mind that the pattern may involve alternating terms, formulas for numerators, formulas for denominators, exponents, or bases.

**How to: Given the first few terms of a sequence, find an explicit formula for the sequence**

1. Look for a pattern among the terms.
2. If the terms are fractions, look for a separate pattern among the numerators and denominators.
3. Look for a pattern among the signs of the terms.
4. Write a formula for $a_n$ in terms of $n$. Test your formula for $n = 1$, $n = 2$, and $n = 3$.

**Example 8.2.4: Writing an Explicit Formula for the *n*th Term of a Sequence**

Write an explicit formula for the nth term of each sequence.

a. $\{-\frac{2}{11}, \frac{3}{13}, -\frac{4}{15}, \frac{5}{17}, -\frac{6}{19}, \ldots\}$

b. $\{-\frac{2}{25}, -\frac{2}{125}, -\frac{2}{625}, -\frac{2}{3,125}, -\frac{2}{15,625}, \ldots\}$

c. $\{e^4, e^5, e^6, e^7, e^8, \ldots\}$

**Solution**

Look for the pattern in each sequence.

a. The terms alternate between positive and negative. We can use $(-1)^n$ to make the terms alternate. The numerator can be represented by $n+1$. The denominator can be represented by $2n+9$.

$$a_n = \frac{(-1)^n(n+1)}{2n+9}$$

b. The terms are all negative. $\left\{-\frac{2}{25}, -\frac{2}{125}, -\frac{2}{625}, -\frac{2}{3,125}, -\frac{2}{15,625}, \ldots\right\}$ The numerator is 2.

$\left\{-\frac{2}{5^2}, -\frac{2}{5^3}, -\frac{2}{5^4}, -\frac{2}{5^6}, -\frac{2}{5^7}, \ldots, -\frac{2}{5^n}\right\}$ The denominators are increasing powers of 5.

So we know that the fraction is negative, the numerator is 2, and the denominator can be represented by $5n+1$.

$a_n = -\frac{2}{5^{n+1}}$

c. The terms are powers of $e$. For $n = 1$, the first term is $e^4$ so the exponent must be $n + 3$.

$$a_n = e^{n+3}$$

**? Exercise 8.2.4A**

Write an explicit formula for the nth term of the sequence.

$$\{9, -81, 729, -6,561, 59,049, \ldots\}$$

**Answer**

$a_n = (-1)^{n+1}9^n$

**? Exercise 8.2.4B**

Write an explicit formula for the nth term of the sequence.

$$\{-34, -98, -2712, -8116, -24320, \ldots\}$$

**Answer**

$a_n = -\frac{3^n}{4n}$

**? Exercise 8.2.4C**

Write an explicit formula for the nth term of the sequence.

$$\left\{\frac{1}{e^2}, \frac{1}{e}, 1, e, e^2, \ldots\right\}$$

**Answer**

$a_n = e^{n-3}$

## Writing the Terms of a Sequence Defined by a Recursive Formula

Sequences occur naturally in the growth patterns of nautilus shells, pinecones, tree branches, and many other natural structures. We may see the sequence in the leaf or branch arrangement, the number of petals of a flower, or the pattern of the chambers in a nautilus shell. Their growth follows the Fibonacci sequence, a famous sequence in which each term can be found by adding the preceding two terms. The numbers in the sequence are $1, 1, 2, 3, 5, 8, 13, 21, 34, \ldots$ Other examples from the natural world that exhibit the Fibonacci sequence are the Calla Lily, which has just one petal, the Black-Eyed Susan with 13 petals, and different varieties of daisies that may have 21 or 34 petals.

Each term of the Fibonacci sequence depends on the terms that come before it. The Fibonacci sequence cannot easily be written using an explicit formula. Instead, we describe the sequence using a **recursive formula**, a formula that defines the terms of a sequence using previous terms.

A recursive formula always has two parts: the value of an initial term (or terms), and an equation defining $a_n$ in terms of preceding terms. For example, suppose we know the following:

$$\begin{aligned} a_1 &= 3 \\ a_n &= 2a_{n-1} - 1, \text{ for } n \geq 2 \end{aligned}$$

We can find the subsequent terms of the sequence using the first term.

$$\begin{aligned} a_1 &= 3 \\ a_2 &= 2a_1 - 1 = 2(3) - 1 = 5 \\ a_3 &= 2a_2 - 1 = 2(5) - 1 = 9 \\ a_4 &= 2a_3 - 1 = 2(9) - 1 = 17 \end{aligned}$$

So the first four terms of the sequence are $\{3, 5, 9, 17\}$.

The recursive formula for the Fibonacci sequence states the first two terms and defines each successive term as the sum of the preceding two terms.

$$\begin{aligned} a_1 &= 1 \\ a_2 &= 1 \\ a_n &= a_{n-1} + a_{n-2}, \text{ for } n \geq 3 \end{aligned}$$

To find the tenth term of the sequence, for example, we would need to add the eighth and ninth terms. We were told previously that the eighth and ninth terms are 21 and 34, so

$$a_{10} = a_9 + a_8 = 34 + 21 = 55$$

**RECURSIVE FORMULA**

A recursive formula is a formula that defines each term of a sequence using preceding term(s). Recursive formulas must always state the initial term, or terms, of the sequence.

**Q&A: Must the first two terms always be given in a recursive formula?**

*No. The Fibonacci sequence defines each term using the two preceding terms, but many recursive formulas define each term using only one preceding term. These sequences need only the first term to be defined.*

**How to: Given a recursive formula with only the first term provided, write the first n terms of a sequence**

1. Identify the initial term, $a_1$, which is given as part of the formula. This is the first term.
2. To find the second term, $a_2$, substitute the initial term into the formula for $a_{n-1}$. Solve.
3. To find the third term, $a_3$, substitute the second term into the formula. Solve.
4. Repeat until you have solved for the nth term.

### Example 8.2.5: Writing the Terms of a Sequence Defined by a Recursive Formula

Write the first five terms of the sequence defined by the recursive formula.

$$\begin{aligned} a_1 &= 9 \\ a_n &= 3a_{n-1} - 20, \text{ for } n \geq 2 \end{aligned}$$

**Solution**

The first term is given in the formula. For each subsequent term, we replace $a_n - 1$ with the value of the preceding term.

$$\begin{aligned} n = 1 \quad & a_1 = 9 \\ n = 2 \quad & a_2 = 3a_1 - 20 = 3(9) - 20 = 27 - 20 = 7 \\ n = 3 \quad & a_3 = 3a_2 - 20 = 3(7) - 20 = 21 - 20 = 1 \\ n = 4 \quad & a_4 = 3a_3 - 20 = 3(1) - 20 = 3 - 20 = -17 \\ n = 5 \quad & a_5 = 3a_4 - 20 = 3(-17) - 20 = -51 - 20 = -71 \end{aligned}$$

The first five terms are $\{9, 7, 1, -17, -71\}$ See Figure 8.2.5.





Figure 8.2.5

### Exercise 8.2.5

Write the first five terms of the sequence defined by the recursive formula.

$$\begin{aligned} a_1 &= 2 \\ a_n &= 2a_{n-1} + 1, \text{ for } n \geq 2 \end{aligned}$$

**Answer**

$\{2, 5, 11, 23, 47\}$

### How to: Given a recursive formula with two initial terms, write the first $n$ terms of a sequence

1. Identify the initial term, $a_1$, which is given as part of the formula.
2. Identify the second term, $a_2$, which is given as part of the formula.
3. To find the third term, substitute the initial term and the second term into the formula. Evaluate.
4. Repeat until you have evaluated the nth term.

### Example 8.2.6: Writing the Terms of a Sequence Defined by a Recursive Formula

Write the first six terms of the sequence defined by the recursive formula.

$$\begin{aligned} a_1 &= 1 \\ a_2 &= 2 \\ a_n &= 3a_{n-1} + 4a_{n-2}, \text{ for } n \geq 3 \end{aligned}$$

**Solution**

The first two terms are given. For each subsequent term, we replace $a_{n-1}$ and $a_{n-2}$ with the values of the two preceding terms.

$$\begin{aligned} n = 3 \quad & a_3 = 3a_2 + 4a_1 = 3(2) + 4(1) = 10 \\ n = 4 \quad & a_4 = 3a_3 + 4a_2 = 3(10) + 4(2) = 38 \\ n = 5 \quad & a_5 = 3a_4 + 4a_3 = 3(38) + 4(10) = 154 \\ n = 6 \quad & a_6 = 3a_5 + 4a_4 = 3(154) + 4(38) = 614 \end{aligned}$$

The first six terms are $\{1, 2, 10, 38, 154, 614\}$See Figure 8.2.6.





Figure 8.2.6

### Exercise 8.2.6

Write the first 8 terms of the sequence defined by the recursive formula.

$$\begin{aligned} a_1 &= 0 \\ a_2 &= 1 \\ a_3 &= 1 \\ a_n &= \frac{a_{n-1}}{a_{n-2}} + a_{n-3}, \text{ for } n \geq 4 \end{aligned}$$

**Answer**

$\{0, 1, 1, 1, 2, 3, 52, 176\}$

## Using Factorial Notation

The formulas for some sequences include products of consecutive positive integers. ***n* factorial**, written as $n!$, is the product of the positive integers from 1 to $n$. For example,

$$\begin{aligned} 4! &= 4 \cdot 3 \cdot 2 \cdot 1 = 24 \\ 5! &= 5 \cdot 4 \cdot 3 \cdot 2 \cdot 1 = 120 \end{aligned}$$

An example of formula containing a **factorial** is $a_n = (n+1)!$. The sixth term of the sequence can be found by substituting 6 for $n$.

$$a_6 = (6+1)! = 7! = 7 \cdot 6 \cdot 5 \cdot 4 \cdot 3 \cdot 2 \cdot 1 = 5040$$

The factorial of any whole number $n$ is $n(n-1)!$ We can therefore also think of $5!$ as $5 \cdot 4!$.

### FACTORIAL

$n$ factorial is a mathematical operation that can be defined using a recursive formula. The factorial of $n$, denoted $n!$, is defined for a positive integer $n$ as:

$$0! = 1 \tag{8.2.2}$$
$$1! = 1 \tag{8.2.3}$$
$$n! = n(n-1)(n-2)\cdots(2)(1), \text{ for } n \geq 2 \tag{8.2.4}$$

The special case $0!$ is defined as $0! = 1$.

### Q&A: Can factorials always be found using a calculator?

*No. Factorials get large very quickly—faster than even exponential functions! When the output gets too large for the calculator, it will not be able to calculate the factorial.*

### Example 8.2.7: Writing the Terms of a Sequence Using Factorials

Write the first five terms of the sequence defined by the explicit formula $a_n = \dfrac{5n}{(n+2)!}$.

**Solution**

Substitute $n = 1$, $n = 2$, and so on in the formula.

$$n = 1 \quad a_1 = \frac{5(1)}{(1+2)!} = \frac{5}{3!} = \frac{5}{3 \cdot 2 \cdot 1} = \frac{5}{6}$$
$$n = 2 \quad a_2 = \frac{5(2)}{(2+2)!} = \frac{10}{4!} = \frac{10}{4 \cdot 3 \cdot 2 \cdot 1} = \frac{5}{12}$$
$$n = 3 \quad a_3 = \frac{5(3)}{(3+2)!} = \frac{15}{5!} = \frac{15}{5 \cdot 4 \cdot 3 \cdot 2 \cdot 1} = \frac{1}{8}$$
$$n = 4 \quad a_4 = \frac{5(4)}{(4+2)!} = \frac{20}{6!} = \frac{20}{6 \cdot 5 \cdot 4 \cdot 3 \cdot 2 \cdot 1} = \frac{1}{36}$$
$$n = 5 \quad a_5 = \frac{5(5)}{(5+2)!} = \frac{25}{7!} = \frac{25}{7 \cdot 6 \cdot 5 \cdot 4 \cdot 3 \cdot 2 \cdot 1} = \frac{5}{1,008}$$

The first five terms are $\left\{\frac{5}{6}, \frac{5}{12}, \frac{1}{8}, \frac{1}{36}, \frac{5}{1,008}\right\}$.

**Analysis**

Figure 8.2.7 shows the graph of the sequence. Notice that, since factorials grow very quickly, the presence of the factorial term in the denominator results in the denominator becoming much larger than the numerator as nn increases. This means the quotient gets smaller and, as the plot of the terms shows, the terms are decreasing and nearing zero.




Figure 8.2.7

### Exercise 8.2.7

Write the first five terms of the sequence defined by the explicit formula $a_n = \dfrac{(n+1)!}{2n}$.

**Answer**

The first five terms are $\left\{1, \frac{3}{2}, 4, 15, 72\right\}$

### Media

Access this online resource for additional instruction and practice with sequences.

- Finding Terms in a Sequence

## Key Equations

| | |
|---|---|
| Formula for a factorial | $0! = 1$<br>$1! = 1$<br>$n! = n(n-1)(n-2)\cdots(2)(1)$ , for $n \geq 2$ |

## Key Concepts

- A sequence is a list of numbers, called terms, written in a specific order.
- Explicit formulas define each term of a sequence using the position of the term. See Example $8.2.1$, Example $8.2.2$, and Example $8.2.3$.
- An explicit formula for thenth nth term of a sequence can be written by analyzing the pattern of several terms. See Example $8.2.4$.
- Recursive formulas define each term of a sequence using previous terms.
- Recursive formulas must state the initial term, or terms, of a sequence.
- A set of terms can be written by using a recursive formula. See Example $8.2.5$ and Example $8.2.6$.
- A factorial is a mathematical operation that can be defined recursively.
- The factorial of $n$ is the product of all integers from $1$ to $n$. See Example $8.2.7$.

## Contributors and Attributions

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.

This page titled 8.2: Sequences and Their Notations is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.1: Sequences and Their Notations** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 8.2E: Sequences and Their Notations (Exercises)

1. Write the first four terms of the sequence defined by the recursive formula $a_1 = 2, \quad a_n = a_{n-1} + n$.

2. Evaluate $\frac{6!}{(5-3)!3!}$.

3. Write the first four terms of the sequence defined by the explicit formula $a_n = 10^n + 3$ .

4. Write the first four terms of the sequence defined by the explicit formula $a_n = \frac{n!}{n(n+1)}$

---

This page titled 8.2E: Sequences and Their Notations (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.1E: Sequences and Their Notations (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 8.3: Arithmetic Sequences

**Learning Objectives**


- Find the common difference for an arithmetic sequence.
- Write terms of an arithmetic sequence.
- Use a recursive formula for an arithmetic sequence.
- Use an explicit formula for an arithmetic sequence.

Companies often make large purchases, such as computers and vehicles, for business use. The book-value of these supplies decreases each year for tax purposes. This decrease in value is called depreciation. One method of calculating depreciation is straight-line depreciation, in which the value of the asset decreases by the same amount each year.


As an example, consider a woman who starts a small contracting business. She purchases a new truck for $\$25,000$. After five years, she estimates that she will be able to sell the truck for $\$8,000$. The loss in value of the truck will therefore be $\$17,000$, which is $\$3,400$ per year for five years. The truck will be worth $\$21,600$ after the first year; $\$18,200$ after two years; $\$14,800$ after three years; $\$11,400$ after four years; and $\$8,000$ at the end of five years. In this section, we will consider specific kinds of sequences that will allow us to calculate depreciation, such as the truck's value.

## Finding Common Differences

The values of the truck in the example are said to form an **arithmetic sequence** because they change by a constant amount each year. Each term increases or decreases by the same constant value called the **common difference** of the sequence. For this sequence, the common difference is $-3,400$.




The sequence below is another example of an arithmetic sequence. In this case, the constant difference is 3. You can choose any term of the sequence, and add 3 to find the subsequent term.




**ARITHMETIC SEQUENCE**

An *arithmetic sequence* is a sequence that has the property that the difference between any two consecutive terms is a constant. This constant is called the *common difference*. If $a_1$ is the first term of an arithmetic sequence and $d$ is the common difference, the sequence will be:

$$\{a_n\} = \{a_1, a_1 + d, a_1 + 2d, a_1 + 3d, \dots\} \tag{8.3.1}$$

**Example 8.3.1: Finding Common Differences**

Is each sequence arithmetic? If so, find the common difference.

a. $\{1, 2, 4, 8, 16, \dots\}$
b. $\{-3, 1, 5, 9, 13, \dots\}$

**Solution**

Subtract each term from the subsequent term to determine whether a common difference exists.

a. The sequence is not arithmetic because there is no common difference.

$$2 - 1 = 1 \qquad 4 - 2 = 2 \qquad 8 - 4 = 4 \qquad 16 - 8 = 8$$

b. The sequence is arithmetic because there is a common difference. The common difference is 4.

$$1 - (-3) = 4 \qquad 5 - 1 = 4 \qquad 9 - 5 = 4 \qquad 13 - 9 = 4$$

**Analysis**

The graph of each of these sequences is shown in Figure 8.3.1. We can see from the graphs that, although both sequences show growth, (a) is not linear whereas (b) is linear. Arithmetic sequences have a constant rate of change so their graphs will always be points on a line.





Figure 8.3.1

**Q&A**

If we are told that a sequence is arithmetic, do we have to subtract every term from the following term to find the common difference?

*No. If we know that the sequence is arithmetic, we can choose any one term in the sequence, and subtract it from the subsequent term to find the common difference.*

**Exercise 8.3.1A**

Is the given sequence arithmetic? If so, find the common difference.

$$\{18, 16, 14, 12, 10, \dots\}$$

**Answer**

The sequence is arithmetic. The common difference is $-2$.

**? Exercise 8.3.1B**

Is the given sequence arithmetic? If so, find the common difference.

$$\{1, 3, 6, 10, 15, \ldots\}$$

**Answer**

The sequence is not arithmetic because $3 - 1 \neq 6 - 3$ .

## Writing Terms of Arithmetic Sequences

Now that we can recognize an arithmetic sequence, we will find the terms if we are given the first term and the common difference. The terms can be found by beginning with the first term and adding the common difference repeatedly. In addition, any term can also be found by plugging in the values of $n$ and $d$ into formula below.

$$a_n = a_1 + (n-1)d \tag{8.3.2}$$

**How to: Given the first term and the common difference of an arithmetic sequence, find the first several terms.**

1. Add the common difference to the first term to find the second term.
2. Add the common difference to the second term to find the third term.
3. Continue until all of the desired terms are identified.
4. Write the terms separated by commas within brackets.

**✓ Example 8.3.2: Writing Terms of Arithmetic Sequences**

Write the first five terms of the arithmetic sequence with $a_1 = 17$ and $d = -3$.

**Solution**

Adding $-3$ is the same as subtracting 3. Beginning with the first term, subtract 3 from each term to find the next term.

The first five terms are $\{17, 14, 11, 8, 5\}$

**Analysis**

As expected, the graph of the sequence consists of points on a line as shown in Figure 8.3.2.





Figure 8.3.2

**? Exercise 8.3.2**

List the first five terms of the arithmetic sequence with $a_1 = 1$ and $d = 5$.

**Answer**

$\{1, 6, 11, 16, 21\}$

**How to: Given any the first term and any other term in an arithmetic sequence, find a given term.**

1. Substitute the values given for $a_1$, $a_n$, $n$ into the formula $a_n = a_1 + (n-1)d$ to solve for $d$.
2. Find a given term by substituting the appropriate values for $a_1$, $n$, and $d$ into the formula $a_n = a_1 + (n-1)d$ .

**✓ Example 8.3.3: Writing Terms of Arithmetic Sequences**

Given $a_1 = 8$ and $a_4 = 14$, find $a_5$.

**Solution**

The sequence can be written in terms of the initial term 8 and the common difference $d$.

$$\{8, 8+d, 8+2d, 8+3d\}$$

We know the fourth term equals 14; we know the fourth term has the form $a_1 + 3d = 8 + 3d$ .

We can find the common difference $d$.

$$\begin{aligned} a_n &= a_1 + (n-1)d \\ a_4 &= a_1 + 3d \\ a_4 &= 8 + 3d \quad \text{Write the fourth term of the sequence in terms of } a_1 \text{ and } d. \\ 14 &= 8 + 3d \quad \text{Substitute 14 for } a_4. \\ d &= 2 \quad \text{Solve for the common difference.} \end{aligned}$$

Find the fifth term by adding the common difference to the fourth term.

$$a_5 = a_4 + 2 = 16$$

**Analysis**

Notice that the common difference is added to the first term once to find the second term, twice to find the third term, three times to find the fourth term, and so on. The tenth term could be found by adding the common difference to the first term nine times or by using the equation $a_n = a_1 + (n-1)d$ .

**? Exercise 8.3.3**

Given $a_3 = 7$ and $a_5 = 17$, find $a_2$.

**Answer**

$a_2 = 2$

## Using Recursive Formulas for Arithmetic Sequences

Some arithmetic sequences are defined in terms of the previous term using a *recursive formula*. The formula provides an algebraic rule for determining the terms of the sequence. A recursive formula allows us to find any term of an arithmetic sequence using a function of the preceding term. Each term is the sum of the previous term and the common difference. For example, if the common difference is 5, then each term is the previous term plus 5. As with any recursive formula, the first term must be given.

$$a_n = a_n - 1 + d$$

for $n \geq 2$

**Note: RECURSIVE FORMULA FOR AN ARITHMETIC SEQUENCE**

The recursive formula for an arithmetic sequence with common difference $d$ is:

$$a_n = a_n - 1 + d \tag{8.3.3}$$

for $n \geq 2$

**How to: Given an arithmetic sequence, write its recursive formula.**

1. Subtract any term from the subsequent term to find the common difference.
2. State the initial term and substitute the common difference into the recursive formula for arithmetic sequences.

**Example 8.3.4: Writing a Recursive Formula for an Arithmetic Sequence**

Write a **recursive formula** for the **arithmetic sequence**.

$$\{-18, -7, 4, 15, 26, \ldots\}$$

**Solution**

The first term is given as $-18$. The common difference can be found by subtracting the first term from the second term.

$$d = -7 - (-18) = 11$$

Substitute the initial term and the common difference into the recursive formula for arithmetic sequences.

$$a_1 = -18$$

$$a_n = a_{n-1} + 11$$

for $n \geq 2$

**Analysis**

We see that the common difference is the slope of the line formed when we graph the terms of the sequence, as shown in Figure 8.3.3. The growth pattern of the sequence shows the constant difference of 11 units.





Figure 8.3.3

**Q&A**

**Do we have to subtract the first term from the second term to find the common difference?**

*No. We can subtract any term in the sequence from the subsequent term. It is, however, most common to subtract the first term from the second term because it is often the easiest method of finding the common difference.*

**? Exercise 8.3.4**

Write a recursive formula for the arithmetic sequence.

$$\{25, 37, 49, 61, \ldots\}$$

**Answer**


$a_1 = 25$
$a_n = a_{n-1} + 12, \text{ for } n \geq 2$

## Using Explicit Formulas for Arithmetic Sequences

We can think of an arithmetic sequence as a function on the domain of the natural numbers; it is a linear function because it has a constant rate of change. The common difference is the constant rate of change, or the slope of the function. We can construct the linear function if we know the slope and the vertical intercept.

$$a_n = a_1 + d(n-1)$$

To find the $y$-intercept of the function, we can subtract the common difference from the first term of the sequence. Consider the following sequence.




The common difference is $-50$, so the sequence represents a linear function with a slope of $-50$. To find the $y$-intercept, we subtract $-50$ from 200: $200-(-50)=200+50=250$. You can also find the $y$-intercept by graphing the function and determining where a line that connects the points would intersect the vertical axis. The graph is shown in Figure 8.3.4.





Figure 8.3.4

Recall the slope-intercept form of a line is $y=mx+b$. When dealing with sequences, we use $a_n$ in place of $y$ and $n$ in place of $x$. If we know the slope and vertical intercept of the function, we can substitute them for $m$ and $b$ in the slope-intercept form of a line. Substituting $-50$ for the slope and 250 for the vertical intercept, we get the following equation:

$$a_n=-50n+250$$

We do not need to find the vertical intercept to write an explicit formula for an arithmetic sequence. Another explicit formula for this sequence is $a_n=200-50(n-1)$, which simplifies to $a_n=-50n+250$.

**Note: EXPLICIT FORMULA FOR AN ARITHMETIC SEQUENCE**

An explicit formula for the $n^{th}$ term of an arithmetic sequence is given by

$$a_n=a_1+d(n-1) \tag{8.3.4}$$

**How to: Given the first several terms for an arithmetic sequence, write an explicit formula.**

1. Find the common difference, $a_2-a_1$.
2. Substitute the common difference and the first term into $a_n=a_1+d(n-1)$.

**Example 8.3.5: Writing the *n*th Term Explicit Formula for an Arithmetic Sequence**

Write an explicit formula for the arithmetic sequence.

$$\{2,12,22,32,42,\ldots\}$$

**Solution**

The common difference can be found by subtracting the first term from the second term.

$$\begin{aligned} d &= a_2-a_1 \\ &= 12-2 \\ &= 10 \end{aligned}$$

The common difference is 10. Substitute the common difference and the first term of the sequence into the formula and simplify.

$$\begin{aligned} a_n &= 2+10(n-1) \\ a_n &= 10n-8 \end{aligned}$$

**Analysis**

The graph of this sequence, represented in Figure 8.3.5, shows a slope of 10 and a vertical intercept of $-8$.




Figure 8.3.5

**Exercise 8.3.5**

Write an explicit formula for the following arithmetic sequence.

$$\{50,47,44,41,\ldots\}$$

**Answer**

$a_n=53-3n$

### Finding the Number of Terms in a Finite Arithmetic Sequence

Explicit formulas can be used to determine the number of terms in a finite arithmetic sequence. We need to find the common difference, and then determine how many times the common difference must be added to the first term to obtain the final term of the sequence.

**How to: Given the first three terms and the last term of a finite arithmetic sequence, find the total number of terms.**

1. Find the common difference $d$.
2. Substitute the common difference and the first term into $a_n=a_1+d(n-1)$.
3. Substitute the last term for $a_n$ and solve for $n$.

**Example 8.3.6: Finding the Number of Terms in a Finite Arithmetic Sequence**

Find the number of terms in the finite arithmetic sequence.

$$\{8,1,-6,\ldots,-41\}$$

**Solution**

The common difference can be found by subtracting the first term from the second term.

$$1-8=-7$$

The common difference is $-7$. Substitute the common difference and the initial term of the sequence into the nth term formula and simplify.

$$\begin{aligned} a_n &= a_1 + d(n-1) \\ a_n &= 8 + -7(n-1) \\ a_n &= 15 - 7n \end{aligned}$$

Substitute $-41$ for $a_n$ and solve for $n$

$$\begin{aligned} -41 &= 15 - 7n \\ 8 &= n \end{aligned}$$

There are eight terms in the sequence.

**? Exercise 8.3.6**

Find the number of terms in the finite arithmetic sequence.

$$\{6, 11, 16, \ldots, 56\}$$

**Answer**

There are 11 terms in the sequence.

### Solving Application Problems with Arithmetic Sequences

In many application problems, it often makes sense to use an initial term of $a_0$ instead of $a_1$. In these problems, we alter the explicit formula slightly to account for the difference in initial terms. We use the following formula:

$$a_n = a_0 + dn \tag{8.3.5}$$

**✓ Example 8.3.7: Solving Application Problems with Arithmetic Sequences**

A five-year old child receives an allowance of \$1 each week. His parents promise him an annual increase of \$2 per week.

a. Write a formula for the child's weekly allowance in a given year.
b. What will the child's allowance be when he is 16 years old?

**Solution**

a. The situation can be modeled by an arithmetic sequence with an initial term of 1 and a common difference of 2.

Let $A$ be the amount of the allowance and $n$ be the number of years after age 5. Using the altered explicit formula for an arithmetic sequence we get:

$$A_n = 1 + 2n$$

b. We can find the number of years since age 5 by subtracting.

$$16 - 5 = 11$$

We are looking for the child's allowance after 11 years. Substitute 11 into the formula to find the child's allowance at age 16.

$$A_{11} = 1 + 2(11) = 23$$

The child's allowance at age 16 will be \$23 per week.

**? Exercise 8.3.7**

A woman decides to go for a 10-minute run every day this week and plans to increase the time of her daily run by 4 minutes each week. Write a formula for the time of her run after $n$ weeks. How long will her daily run be 8 weeks from today?

**Answer**

The formula is $T_n = 10 + 4n$, and it will take her 42 minutes.

**Media**

Access this online resource for additional instruction and practice with arithmetic sequences.

- Arithmetic Sequences

## Key Equations

| | |
|---|---|
| recursive formula for nth term of an arithmetic sequence | $a_n = a_{n-1} + d \;\; n \geq 2$ |
| explicit formula for nth term of an arithmetic sequence | $a_n = a_1 + d(n-1)$ |

## Key Concepts

- An arithmetic sequence is a sequence where the difference between any two consecutive terms is a constant.
- The constant between two consecutive terms is called the common difference.
- The common difference is the number added to any one term of an arithmetic sequence that generates the subsequent term. See Example 8.3.1.
- The terms of an arithmetic sequence can be found by beginning with the initial term and adding the common difference repeatedly. See Example 8.3.2 and Example 8.3.3.
- A recursive formula for an arithmetic sequence with common difference dd is given by $a_n = a_{n-1} + d$ , $n \geq 2$. See Example 8.3.4.
- As with any recursive formula, the initial term of the sequence must be given.
- An explicit formula for an arithmetic sequence with common difference $d$ is given by $a_n = a_1 + d(n-1)$ . See Example 8.3.5.
- An explicit formula can be used to find the number of terms in a sequence. See Example 8.3.6.
- In application problems, we sometimes alter the explicit formula slightly to $a_n = a_0 + dn$ . See Example 8.3.7.

### Contributors and Attributions

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.

This page titled 8.3: Arithmetic Sequences is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.2: Arithmetic Sequences** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 8.3E: Arithmetic Sequences (Exercises)

5. Is the sequence $\frac{4}{7}, \frac{47}{21}, \frac{82}{21}, \frac{39}{7}, \ldots$ arithmetic? If so, find the common difference.

6. Is the sequence $2, 4, 8, 16, \quad \ldots$arithmetic? If so, find the common difference.

7. An arithmetic sequence has the first term $a_1 = 18$ and common difference $d = -8$. What are the first five terms?

8. An arithmetic sequence has terms $a_3 = 11.7$ and $a_8 = -14.6$. What is the first term?

9. Write a recursive formula for the arithmetic sequence $-20, -10, 0, 10, \ldots$

10. Write a recursive formula for the arithmetic sequence $0, \quad -\frac{1}{2}, \quad -1, \quad -\frac{3}{2}, \ldots,$and then find the $31^{\text{st}}$ term.

11. Write an explicit formula for the arithmetic sequence $\frac{7}{8}, \quad \frac{29}{24}, \quad \frac{37}{24}, \quad \frac{15}{8}, \ldots$

12. How many terms are in the finite arithmetic sequence $12, 20, 28, \ldots, 172$?

This page titled 8.3E: Arithmetic Sequences (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.2E: Arithmetic Sequences (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 8.4: Geometric Sequences


**Learning Objectives**

- Find the common ratio for a geometric sequence.
- List the terms of a geometric sequence.
- Use a recursive formula for a geometric sequence.
- Use an explicit formula for a geometric sequence.

Many jobs offer an annual cost-of-living increase to keep salaries consistent with inflation. Suppose, for example, a recent college graduate finds a position as a sales manager earning an annual salary of $\$26,000$. He is promised a $2\%$ cost of living increase each year. His annual salary in any given year can be found by multiplying his salary from the previous year by $102\%$. His salary will be $\$26,520$ after one year; $\$27,050.40$ after two years; $\$27,591.41$ after three years; and so on. When a salary increases by a constant rate each year, the salary grows by a constant factor. In this section, we will review sequences that grow in this way.

## Finding Common Ratios

The yearly salary values described form a **geometric sequence** because they change by a constant factor each year. Each term of a geometric sequence increases or decreases by a constant factor called the **common ratio**. The sequence below is an example of a geometric sequence because each term increases by a constant factor of 6. Multiplying any term of the sequence by the common ratio 6 generates the subsequent term.




**Definition: GEOMETRIC SEQUENCE**

A geometric sequence is one in which any term divided by the previous term is a constant. This constant is called the *common ratio* of the sequence. The common ratio can be found by dividing any term in the sequence by the previous term. If $a_1$ is the initial term of a geometric sequence and $r$ is the common ratio, the sequence will be

$$\{a_1, a_1 r, a_1 r^2, a_1 r^3, \dots\}. \tag{8.4.1}$$

**How to: Given a set of numbers, determine if they represent a geometric sequence.**

1. Divide each term by the previous term.
2. Compare the quotients. If they are the same, a common ratio exists and the sequence is geometric.

**Example 8.4.1: Finding Common Ratios**

Is the sequence geometric? If so, find the common ratio.

a. 1, 2, 4, 8, 16,...
b. 48, 12, 4, 2,...

**Solution**

Divide each term by the previous term to determine whether a common ratio exists.

a. $\frac{2}{1} = 2 \quad \frac{4}{2} = 2 \quad \frac{8}{4} = 2 \quad \frac{16}{8} = 2$

The sequence is geometric because there is a common ratio. The common ratio is 2.

b. $\frac{12}{48} = \frac{1}{4} \quad \frac{4}{12} = \frac{1}{3} \quad \frac{2}{4} = \frac{1}{2}$

The sequence is not geometric because there is not a common ratio.

**Analysis**

The graph of each sequence is shown in Figure 8.4.1. It seems from the graphs that both (a) and (b) appear have the form of the graph of an exponential function in this viewing window. However, we know that (a) is geometric and so this interpretation holds, but (b) is not.





Figure 8.4.1

**Q&A**

**If you are told that a sequence is geometric, do you have to divide every term by the previous term to find the common ratio?**

*No. If you know that the sequence is geometric, you can choose any one term in the sequence and divide it by the previous term to find the common ratio.*

**Exercise 8.4.1A**

Is the sequence geometric? If so, find the common ratio.

$$5, 10, 15, 20,...$$

**Answer**

The sequence is not geometric because $\frac{10}{5} \neq \frac{15}{10}$

**Exercise 8.4.1B**

Is the sequence geometric? If so, find the common ratio.

$$100, 20, 4, \frac{4}{5},...$$

**Answer**

The sequence is geometric. The common ratio is $\frac{1}{5}$

## Writing Terms of Geometric Sequences

Now that we can identify a geometric sequence, we will learn how to find the terms of a geometric sequence if we are given the first term and the common ratio. The terms of a geometric sequence can be found by beginning with the first term and multiplying by the common ratio repeatedly. For instance, if the first term of a geometric sequence is $a_1 = -2$ and the common ratio is $r = 4$, we can find subsequent terms by multiplying $-2 \cdot 4$ to get $-8$ then multiplying the result $-8 \cdot 4$ to get $-32$ and so on.

$$
\begin{aligned}
a_1 &= -2 \\
a_2 &= (-2 \cdot 4) = -8 \\
a_3 &= (-8 \cdot 4) = -32 \\
a_4 &= (-32 \cdot 4) = 128
\end{aligned}
$$

The first four terms are $\{-2, -8, -32, -128\}$

**How to: Given the first term and the common factor, find the first four terms of a geometric sequence.**

1. Multiply the initial term, $a_1$, by the common ratio to find the next term, $a_2$.
2. Repeat the process, using $a_n = a_2$ to find $a_3$ and then use $a_3$ to find $a_4$, until all four terms have been identified.
3. Write the terms separated by commons within brackets.

**Example 8.4.2: Writing the Terms of a Geometric Sequence**

List the first four terms of the geometric sequence with $a_1 = 5$ and $r = -2$.

**Solution**

Multiply $a_1$ by $-2$ to find $a_2$. Repeat the process, using $a_2$ to find $a_3$, and so on.

$$
\begin{aligned}
a_1 &= 5 \\
a_2 &= -2a_1 = -10 \\
a_3 &= -2a_2 = 20 \\
a_4 &= -2a_3 = -40
\end{aligned}
$$

The first four terms are $\{5, -10, 20, -40\}$

**Exercise 8.4.2**

List the first five terms of the geometric sequence with $a_1 = 18$ and $r = \frac{1}{3}$.

**Answer**

$$\left\{18, 6, 2, \frac{2}{3}, \frac{2}{9}\right\}$$

## Using Recursive Formulas for Geometric Sequences

A recursive formula allows us to find any term of a geometric sequence by using the previous term. Each term is the product of the common ratio and the previous term. For example, suppose the common ratio is 9. Then each term is nine times the previous term. As with any recursive formula, the initial term must be given.

**Note: RECURSIVE FORMULA FOR A GEOMETRIC SEQUENCE**

The recursive formula for a geometric sequence with common ratio r and first term $a_1$ is

$$a_n = ra_{n-1}, \quad n \geq 2 \tag{8.4.2}$$

**How to: Given the first several terms of a geometric sequence, write its recursive formula.**

1. State the initial term.
2. Find the common ratio by dividing any term by the preceding term.
3. Substitute the common ratio into the recursive formula for a geometric sequence.

### Example 8.4.3: Using Recursive Formulas for Geometric Sequences

Write a recursive formula for the following geometric sequence.

$$\{6, 9, 13.5, 20.25, \dots\}$$

**Solution**

The first term is given as $6$. The common ratio can be found by dividing the second term by the first term.

$$r = \frac{9}{6} = 1.5$$

Substitute the common ratio into the recursive formula for geometric sequences and define $a_1$.

$$\begin{aligned} a_n &= ra_{n-1} \\ a_n &= 1.5a_{n-1} \text{ for } n \geq 2 \\ a_1 &= 6 \end{aligned}$$

**Analysis**

The sequence of data points follows an exponential pattern. The common ratio is also the base of an exponential function as shown in Figure 8.4.2.





Figure 8.4.2

**Q&A**

**Do we have to divide the second term by the first term to find the common ratio?**

*No. We can divide any term in the sequence by the previous term. It is, however, most common to divide the second term by the first term because it is often the easiest method of finding the common ratio.*

### Exercise 8.4.3

Write a recursive formula for the following geometric sequence.

$$\{2, \tfrac{4}{3}, \tfrac{8}{9}, \tfrac{16}{27}, \dots\}$$

**Answer**

$$\begin{aligned} a_1 &= 2 \\ a_n &= \frac{2}{3}a_{n-1} \text{ for } n \geq 2 \end{aligned}$$

## Using Explicit Formulas for Geometric Sequences

Because a geometric sequence is an exponential function whose domain is the set of positive integers, and the common ratio is the base of the function, we can write explicit formulas that allow us to find particular terms.

$$a_n = a_1 r^{n-1} \tag{8.4.3}$$

Let's take a look at the sequence $\{18, 36, 72, 144, 288, \dots\}$. This is a geometric sequence with a common ratio of $2$ and an exponential function with a base of $2$. An explicit formula for this sequence is

$$a_n = 18 \cdot 2^{n-1}$$

The graph of the sequence is shown in Figure 8.4.3.





Figure 8.4.3

**Note: EXPLICIT FORMULA FOR A GEOMETRIC SEQUENCE**

The $n^{th}$ term of a geometric sequence is given by the *explicit formula*:

$$a_n = a_1 r^{n-1} \tag{8.4.4}$$

**Example 8.4.4: Writing Terms of Geometric Sequences Using the Explicit Formula**

Given a geometric sequence with $a_1 = 3$ and $a_4 = 24$, find $a_2$.

**Solution**

The sequence can be written in terms of the initial term and the common ratio $r$.

$$3, 3r, 3r^2, 3r^3, \ldots$$

Find the common ratio using the given fourth term.

$$\begin{aligned} a_n &= a_1 r^{n-1} \\ a_4 &= 3r^3 \quad \text{Write the fourth term of sequence in terms of } a_1 \text{ and } r \\ 24 &= 3r^3 \quad \text{Substitute 24 for } a_4 \\ 8 &= r^3 \quad \text{Divide} \\ r &= 2 \quad \text{Solve for the common ratio} \end{aligned}$$

Find the second term by multiplying the first term by the common ratio.

$$\begin{aligned} a_2 &= 2 \\ a_1 &= 2(3) \\ &= 6 \end{aligned}$$

**Analysis**

The common ratio is multiplied by the first term once to find the second term, twice to find the third term, three times to find the fourth term, and so on. The tenth term could be found by multiplying the first term by the common ratio nine times or by multiplying by the common ratio raised to the ninth power.

**Exercise 8.4.4**

Given a geometric sequence with $a_2 = 4$ and $2a_3 = 32$, find $a_6$.

**Answer**

$a_6 = 16,384$

**Example 8.4.5: Writing an Explicit Formula for the *n*th Term of a Geometric Sequence**

Write an explicit formula for the nth term of the following geometric sequence.

$$\{2, 10, 50, 250, \dots\}$$

**Solution**

The first term is $2$. The common ratio can be found by dividing the second term by the first term.

$$\frac{10}{2} = 5$$

The common ratio is $5$. Substitute the common ratio and the first term of the sequence into the formula.

$$a_n = a_1 r^{(n-1)}$$
$$a_n = 2 \cdot 5^{n-1}$$

The graph of this sequence in Figure $8.4.4$ shows an exponential pattern.





Figure 8.4.4

**Exercise 8.4.5**

Write an explicit formula for the following geometric sequence.

$$\{-1, 3, -9, 27, \dots\}$$

**Answer**

$a_n = -(-3)^{n-1}$

## Solving Application Problems with Geometric Sequences

In real-world scenarios involving arithmetic sequences, we may need to use an initial term of $a_0$ instead of $a_1$. In these problems, we can alter the explicit formula slightly by using the following formula:

$$a_n = a_0 r^n$$

### Example 8.4.6: Solving Application Problems with Geometric Sequences

In 2013, the number of students in a small school is 284. It is estimated that the student population will increase by 4% each year.

a. Write a formula for the student population.
b. Estimate the student population in 2020.

**Solution**

a. The situation can be modeled by a geometric sequence with an initial term of 284. The student population will be 104% of the prior year, so the common ratio is 1.04.

Let $P$ be the student population and $n$ be the number of years after 2013. Using the explicit formula for a geometric sequence we get

$$P_n = 284 \cdot 1.04^n$$

b. We can find the number of years since 2013 by subtracting.

$$2020 - 2013 = 7$$

We are looking for the population after 7 years. We can substitute 7 for $n$ to estimate the population in 2020.

$$P_7 = 284 \cdot 1.04^7 \approx 374$$

The student population will be about 374 in 2020.

### Exercise 8.4.6

A business starts a new website. Initially the number of hits is 293 due to the curiosity factor. The business estimates the number of hits will increase by 2.6 per week.

a. Write a formula for the number of hits.
b. Estimate the number of hits in 5 weeks.

**Answer a**

$P_n = 293 \cdot 1.026a^n$

**Answer b**

The number of hits will be about 333.

### Media

Access these online resources for additional instruction and practice with geometric sequences.

- Geometric Sequences
- Determine the Type of Sequence
- Find the Formula for a Sequence

## Key Equations

| | |
|---|---|
| recursive formula for nth term of a geometric sequence | $a_n = ra_{n-1}, n \geq 2$ |
| explicit formula for nth term of a geometric sequence | $a_n = a_1 r^{n-1}$ |

## Key Concepts

- A geometric sequence is a sequence in which the ratio between any two consecutive terms is a constant.
- The constant ratio between two consecutive terms is called the common ratio.
- The common ratio can be found by dividing any term in the sequence by the previous term. See Example 8.4.1.

- The terms of a geometric sequence can be found by beginning with the first term and multiplying by the common ratio repeatedly. See Example $8.4.2$ and Example $8.4.4$.
- A recursive formula for a geometric sequence with common ratio $r$ is given by $a_n = ra_{n-1}$ for $n \geq 2$.
- As with any recursive formula, the initial term of the sequence must be given. See Example $8.4.3$.
- An explicit formula for a geometric sequence with common ratio $r$ is given by $a_n = a_1 r^{n-1}$. See Example $8.4.5$.
- In application problems, we sometimes alter the explicit formula slightly to $a_n = a_0 r^n$. See Example $8.4.6$.

## Contributors and Attributions

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.

---

This page titled 8.4: Geometric Sequences is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.3: Geometric Sequences** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 8.4E: Geometric Sequences (Exercises)

13. Find the common ratio for the geometric sequence $2.5, \quad 5, \quad 10, \quad 20, \ldots$

14. Is the sequence $4, 16, 28, 40 \ldots$.geometric? If so find the common ratio. If not, explain why.

15. A geometric sequence has terms $a_7 = 16,384$ and $a_9 = 262,144$. What are the first five terms?

16. A geometric sequence has the first term $a_1 = -3$ and common ratio $r = \frac{1}{2}$. What is the $8^{\text{th}}$ term?

17. What are the first five terms of the geometric sequence $a_1 = 3, \quad a_n = 4 \cdot a_{n-1}$?

18. Write a recursive formula for the geometric sequence $1, \quad \frac{1}{3}, \quad \frac{1}{9}, \quad \frac{1}{27}, \ldots$

19. Write an explicit formula for the geometric sequence $-\frac{1}{5}, \quad -\frac{1}{15}, \quad -\frac{1}{45}, \quad -\frac{1}{135}, \ldots$

20. How many terms are in the finite geometric sequence $-5, -\frac{5}{3}, -\frac{5}{9}, \ldots, -\frac{5}{59,049}$?

This page titled 8.4E: Geometric Sequences (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.3E: Geometric Sequences (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 8.5: Series and Their Notations

**Learning Objectives**

- Use summation notation.
- Use the formula for the sum of the first $n$ terms of an arithmetic series.
- Use the formula for the sum of the first $n$ terms of a geometric series.
- Use the formula for the sum of an infinite geometric series.
- Solve annuity problems.

A couple decides to start a college fund for their daughter. They plan to invest $\$50$ in the fund each month. The fund pays $6\%$ annual interest, compounded monthly. How much money will they have saved when their daughter is ready to start college in $6$ years? In this section, we will learn how to answer this question. To do so, we need to consider the amount of money invested and the amount of interest earned.

## Using Summation Notation


To find the total amount of money in the college fund and the sum of the amounts deposited, we need to add the amounts deposited each month and the amounts earned monthly. The sum of the terms of a sequence is called a *series*. Consider, for example, the following series.

$$3+7+11+15+19+\ldots$$

The $n^{th}$ *partial sum* of a series is the sum of a finite number of consecutive terms beginning with the first term. The notation $S_n$ represents the partial sum.

$$\begin{aligned} S_1 &= 3 \\ S_2 &= 3+7=10 \\ S_3 &= 3+7+11=21 \\ S_4 &= 3+7+11+15=36 \end{aligned}$$

*Summation notation* is used to represent series. Summation notation is often known as sigma notation because it uses the Greek capital letter *sigma*, $\sum$, to represent the sum. Summation notation includes an explicit formula and specifies the first and last terms in the series. An explicit formula for each term of the series is given to the right of the sigma. A variable called the *index of summation* is written below the sigma. The index of summation is set equal to the *lower limit of summation*, which is the number used to generate the first term in the series. The number above the sigma, called the *upper limit of summation*, is the number used to generate the last term in a series.




If we interpret the given notation, we see that it asks us to find the sum of the terms in the series $a_k=2k$ for $k=1$ through $k=5$. We can begin by substituting the terms for $k$ and listing out the terms of this series.

$$\begin{aligned} a_1 &= 2(1)=2 \\ a_2 &= 2(2)=4 \\ a_3 &= 2(3)=6 \\ a_4 &= 2(4)=8 \\ a_5 &= 2(5)=10 \end{aligned}$$

We can find the sum of the series by adding the terms:

$$\sum_{k=1}^{5} 2k = 2+4+6+8+10=30$$

**Definition: SUMMATION NOTATION**

The sum of the first $n$ terms of a series can be expressed in *summation notation* as follows:

$$\sum_{k=1}^{n} a_k \tag{8.5.1}$$

This notation tells us to find the sum of $a_k$ from $k=1$ to $k=n$.

$k$ is called the index of summation, 1 is the lower limit of summation, and $n$ is the upper limit of summation.

**Q&A: Does the lower limit of summation have to be 1?**

*No. The lower limit of summation can be any number, but* 1 *is frequently used. We will look at examples with lower limits of summation other than* 1.

**How to: Given summation notation for a series, evaluate the value**

1. Identify the lower limit of summation.
2. Identify the upper limit of summation.
3. Substitute each value of $k$ from the lower limit to the upper limit into the formula.
4. Add to find the sum.

**Example 8.5.1: Using Summation Notation**

Evaluate

$$\sum_{k=3}^{7} k^2$$

**Solution**

According to the notation, the lower limit of summation is 3 and the upper limit is 7. So we need to find the sum of $k^2$ from $k=3$ to $k=7$. We find the terms of the series by substituting $k=3,4,5,6,$ and 7 into the function $k^2$. We add the terms to find the sum.

$$\begin{aligned}\sum_{k=3}^{7} k^2 &= 3^2+4^2+5^2+6^2+7^2\\ &= 9+16+25+36+49\\ &= 135\end{aligned}$$

**Exercise 8.5.1**

Evaluate

$$\sum_{k=2}^{5}(3k-1)$$

**Answer**

38

## Using the Formula for Arithmetic Series

Just as we studied special types of sequences, we will look at special types of series. Recall that an arithmetic sequence is a sequence in which the difference between any two consecutive terms is the *common difference*, $d$. The sum of the terms of an arithmetic sequence is called an *arithmetic series*. We can write the sum of the first $n$ terms of an arithmetic series as:

$$S_n = a_1+(a_1+d)+(a_1+2d)+\ldots+(a_n-d)+a_n.$$

We can also reverse the order of the terms and write the sum as

$$S_n = a_n + (a_n - d) + (a_n - 2d) + \ldots + (a_1 + d) + a_1.$$

If we add these two expressions for the sum of the first $n$ terms of an arithmetic series, we can derive a formula for the sum of the first $n$ terms of any arithmetic series.

$$\begin{aligned} S_n &= a_1 + (a_1 + d) + (a_1 + 2d) + \ldots + (a_n - d) + a_n \\ +S_n &= a_n + (a_n - d) + (a_n - 2d) + \ldots + (a_1 + d) + a_1 \\ \hline 2S_n &= (a_1 + a_n) + (a_1 + a_n) + \ldots + (a_1 + a_n) \end{aligned}$$

Because there are $n$ terms in the series, we can simplify this sum to

$$2S_n = n(a_1 + a_n).$$

We divide by 2 to find the formula for the sum of the first $n$ terms of an arithmetic series.

$$S_n = \frac{n(a_1 + a_n)}{2}$$

### FORMULA FOR THE SUM OF THE FIRST $N$ TERMS OF AN ARITHMETIC SERIES

An arithmetic series is the sum of the terms of an arithmetic sequence. The formula for the sum of the first $n$ terms of an arithmetic sequence is

$$S_n = \frac{n(a_1 + a_n)}{2} \tag{8.5.2}$$

### How to: Given terms of an arithmetic series, find the sum of the first $n$ terms

1. Identify $a_1$ and $a_n$.
2. Determine $n$.
3. Substitute values for $a_1$, $a_n$, and $n$ into the formula $S_n = \frac{n(a_1 + a_n)}{2}$.
4. Simplify to find $S_n$.

### Terms of an Arithmetic Series

Find the sum of each arithmetic series.

a. $5 + 8 + 11 + 14 + 17 + 20 + 23 + 26 + 29 + 32$
b. $20 + 15 + 10 + \ldots + -50$
c. $\sum_{k=1}^{12} 3k - 8$

**Solution**

a. We are given $a_1 = 5$ and $a_n = 32$.

Count the number of terms in the sequence to find $n = 10$.

Substitute values for $a_1$, $a_n$, and $n$ into the formula and simplify.

$$\begin{aligned} S_n &= \frac{n(a_1 + a_n)}{2} \\ S_{10} &= \frac{10(5 + 32)}{2} \\ &= 185 \end{aligned}$$

2. We are given $a_1 = 20$ and $a_n = -50$.

Use the formula for the general term of an arithmetic sequence to find $n$.

$$\begin{aligned} a_n &= a_1 + (n-1)d \\ -50 &= 20 + (n-1)(-5) \\ -70 &= (n-1)(-5) \\ 14 &= n-1 \\ 15 &= n \end{aligned}$$

Substitute values for $a_1$, $a_n$, $n$ into the formula and simplify.

$$\begin{aligned} S_n &= \frac{n(a_1 + a_n)}{2} \\ S_{15} &= \frac{15(20-50)}{2} \\ &= -225 \end{aligned}$$

c. To find $a_1$, substitute $k = 1$ into the given explicit formula.

$$\begin{aligned} a_k &= 3k - 8 \\ a_1 &= 3(1) - 8 \\ &= -5 \end{aligned}$$

We are given that $n = 12$. To find $a_12$, substitute $k = 12$ into the given explicit formula.

$$\begin{aligned} a_k &= 3k - 8 \\ a_{12} &= 3(12) - 8 \\ &= 28 \end{aligned}$$

Substitute values for $a_1$, $a_n$, and $n$ into the formula and simplify.

$$\begin{aligned} S_n &= \frac{n(a_1 + a_n)}{2} \\ S_{12} &= \frac{12(-5+28)}{2} \\ &= 138 \end{aligned}$$

Use the formula to find the sum of each arithmetic series.

**? Exercise 8.5.2A**

$1.4 + 1.6 + 1.8 + 2.0 + 2.2 + 2.4 + 2.6 + 2.8 + 3.0 + 3.2 + 3.4$

**Answer**

26.4

**? Exercise 8.5.2B**

$13 + 21 + 29 + \ldots + 69$

**Answer**

328

**? Exercise 8.5.2C**

$\sum_{k=1} 105 - 6k$

**Answer**

$-280$

### Example 8.5.3: Solving Application Problems with Arithmetic Series

On the Sunday after a minor surgery, a woman is able to walk a half-mile. Each Sunday, she walks an additional quarter-mile. After 8 weeks, what will be the total number of miles she has walked?

**Solution**

This problem can be modeled by an arithmetic series with $a_1 = \frac{1}{2}$ and $d = \frac{1}{4}$. We are looking for the total number of miles walked after 8 weeks, so we know that $n = 8$, and we are looking for $S_8$. To find $a_8$, we can use the explicit formula for an arithmetic sequence.

$$\begin{aligned} a_n &= a_1 + d(n-1) \\ a_8 &= \frac{1}{2} + \frac{1}{4}(8-1) \\ &= \frac{9}{4} \end{aligned}$$

We can now use the formula for arithmetic series.

$$\begin{aligned} S_n &= \frac{n(a_1 + a_n)}{2} \\ S_8 &= \frac{8\left(\frac{1}{2} + \frac{9}{4}\right)}{2} \\ &= 11 \end{aligned}$$

She will have walked a total of 11 miles.

### Exercise 8.5.3

A man earns $\$100$ in the first week of June. Each week, he earns $\$12.50$ more than the previous week. After 12 weeks, how much has he earned?

**Answer**

$\$2,025$

## Using the Formula for Geometric Series

Just as the sum of the terms of an arithmetic sequence is called an arithmetic series, the sum of the terms in a geometric sequence is called a **geometric series**. Recall that a **geometric sequence** is a sequence in which the ratio of any two consecutive terms is the **common ratio**, $r$. We can write the sum of the first $n$ terms of a geometric series as

$$S_n = a_1 + ra_1 + r^2 a_1 + \ldots + r^{n-1} a_1 \ .$$

Just as with arithmetic series, we can do some algebraic manipulation to derive a formula for the sum of the first $n$ terms of a geometric series. We will begin by multiplying both sides of the equation by $r$.

$$rS_n = ra_1 + r^2 a_1 + r^3 a_1 + \ldots + r^n a_1$$

Next, we subtract this equation from the original equation.

$$\begin{aligned} S_n &= a_1 + ra_1 + r^2 a_1 + \ldots + r^{n-1} a_1 \\ \underline{-rS_n} &= \underline{-(ra_1 + r^2 a_1 + r^3 a_1 + \ldots + r^n a_1)} \\ (1-r)S_n &= a_1 - r^n a_1 \end{aligned}$$

Notice that when we subtract, all but the first term of the top equation and the last term of the bottom equation cancel out. To obtain a formula for $S_n$, divide both sides by $(1-r)$.

$$S_n = \frac{a_1(1-r^n)}{1-r} \quad r \neq 1$$

## TERMS OF A GEOMETRIC SERIES

A geometric series is the sum of the terms in a geometric sequence. The formula for the sum of the first $n$ terms of a geometric sequence is represented as

$$S_n = \frac{a_1(1-r^n)}{1-r} \quad r \neq 1$$

## How to: Given a geometric series, find the sum of the first $n$ terms.

1. Identify $a_1$, $r$, and $n$.
2. Substitute values for $a_1$, $r$, and $n$ into the formula $S_n = \frac{a_1(1-r^n)}{1-r}$.
3. Simplify to find $S_n$.

## Terms of a Geometric Series

Use the formula to find the indicated partial sum of each geometric series.

a. $S_{11}$ for the series $8 + -4 + 2 + \ldots$
b. $\sum_{6}^{k=1} 3 \cdot 2k$

**Solution**

a. $a_1 = 8$, and we are given that $n = 11$.

We can find $r$ by dividing the second term of the series by the first.

$$r = \frac{-4}{8} = -\frac{1}{2}$$

Substitute values for $a_1$, $r$, and $n$ into the formula and simplify.

$$S_n = \frac{a_1(1-r^n)}{1-r}$$

$$S_{11} = \frac{8\left(1-\left(-\frac{1}{2}\right)^{11}\right)}{1-\left(-\frac{1}{2}\right)}$$

$$\approx 5.336$$

b. Find $a_1$ by substituting $k = 1$ into the given explicit formula.

$$a_1 = 3 \cdot 2^1 = 6$$

We can see from the given explicit formula that $r = 2$. The upper limit of summation is 6, so $n = 6$.

Substitute values for $a_1$, $r$, and $n$ into the formula, and simplify.

$$S_n = \frac{a_1(1-r^n)}{1-r}$$

$$S_6 = \frac{6(1-2^6)}{1-2}$$

$$= 378$$

Use the formula to find the indicated partial sum of each geometric series.

**Exercise 8.5.4A**

$S_{20}$ for the series $1,000+500+250+\ldots$

**Answer**

$\approx 2,000.00$

**Exercise 8.5.4B**

$\sum_{k=1}^{8} 3^k$

**Answer**

$9,840$

**Example 8.5.5: Solving an Application Problem with a Geometric Series**

At a new job, an employee's starting salary is $\$26,750$. He receives a $1.6\%$ annual raise. Find his total earnings at the end of 5 years.

**Solution**

The problem can be represented by a geometric series with $a_1 = 26,750$; $n = 5$; and $r = 1.016$. Substitute values for $a_1$, $r$, and $n$ into the formula and simplify to find the total amount earned at the end of 5 years.

$$S_n = \frac{a_1(1-r^n)}{1-r}$$
$$S_5 = \frac{26,750(1-1.016^5)}{1-1.016}$$
$$\approx 138,099.03$$

He will have earned a total of $\$138,099.03$ by the end of 5 years.

**Exercise 8.5.5**

At a new job, an employee's starting salary is $\$32,100$. She receives a $2\%$ annual raise. How much will she have earned by the end of 8 years?

**Answer**

$\$275,513.31$

## Using the Formula for the Sum of an Infinite Geometric Series

Thus far, we have looked only at finite series. Sometimes, however, we are interested in the sum of the terms of an infinite sequence rather than the sum of only the first $n$ terms. An infinite series is the sum of the terms of an **infinite sequence**. An example of an infinite series is $2+4+6+8+\ldots$

This series can also be written in summation notation as $\sum_{k=1}^{\infty} 2k$, where the upper limit of summation is infinity. Because the terms are not tending to zero, the sum of the series increases without bound as we add more terms. Therefore, the sum of this infinite series is not defined. When the sum is not a real number, we say the series **diverges**.

### Determining Whether the Sum of an Infinite Geometric Series is Defined

If the terms of an **infinite geometric series** approach 0, the sum of an infinite geometric series can be defined. The terms in this series approach 0:

$$1+0.2+0.04+0.008+0.0016+\ldots$$

The common ratio $r = 0.2$. As $n$ gets very large, the values of $r^n$ get very small and approach 0. Each successive term affects the sum less than the preceding term. As each succeeding term gets closer to 0, the sum of the terms approaches a finite value. The terms of any infinite geometric series with $-1 < r < 1$ approach 0; the sum of a geometric series is defined when $-1 < r < 1$.

### DETERMINING WHETHER THE SUM OF AN INFINITE GEOMETRIC SERIES IS DEFINED

The sum of an infinite series is defined if the series is geometric and $-1 < r < 1$.

### How to: Given the first several terms of an infinite series, determine if the sum of the series exists.

1. Find the ratio of the second term to the first term.
2. Find the ratio of the third term to the second term.
3. Continue this process to ensure the ratio of a term to the preceding term is constant throughout. If so, the series is geometric.
4. If a common ratio, $r$, was found in step 3, check to see if $-1 < r < 1$. If so, the sum is defined. If not, the sum is not defined.

### Example 8.5.6: Determining Whether the Sum of an Infinite Series is Defined

Determine whether the sum of each infinite series is defined.

a. $12 + 8 + 4 + \ldots$
b. $\frac{3}{4} + \frac{1}{2} + \frac{1}{3} + \ldots$
c. $\sum_{k=1}^{\infty} 27 \cdot \left(\frac{1}{3}\right)^k$
d. $\sum_{k=1}^{\infty} 5k$

**Solution**

a. The ratio of the second term to the first is $\frac{2}{3}$, which is not the same as the ratio of the third term to the second, $\frac{1}{2}$.The series is not geometric.
b. The ratio of the second term to the first is the same as the ratio of the third term to the second. The series is geometric with a common ratio of $\frac{2}{3}$. The sum of the infinite series is defined.
c. The given formula is exponential with a base of $\frac{1}{3}$; the series is geometric with a common ratio of $\frac{1}{3}$. The sum of the infinite series is defined.
d. The given formula is not exponential; the series is not geometric because the terms are increasing, and so cannot yield a finite sum.

Determine whether the sum of the infinite series is defined.

### Exercise 8.5.6A

$\frac{1}{3} + \frac{1}{2} + \frac{3}{4} + \frac{9}{8} + \ldots$

**Answer**

The sum is defined. It is geometric.

### Exercise 8.5.6B

$24 + (-12) + 6 + (-3) + \ldots$

**Answer**

The sum of the infinite series is defined.

**Exercise 8.5.6C**

$\sum_{k=1}^{\infty} 15 \cdot (-0.3)^k$

**Answer**

The sum of the infinite series is defined.

## Finding Sums of Infinite Series

When the sum of an infinite geometric series exists, we can calculate the sum. The formula for the sum of an infinite series is related to the formula for the sum of the first $n$ terms of a geometric series.

$$S_n = \frac{a_1(1-r^n)}{1-r} \tag{8.5.3}$$

We will examine an infinite series with $r = \frac{1}{2}$. What happens to $r^n$ as $n$ increases?

$$\left(\frac{1}{2}\right)^2 = \frac{1}{4}$$
$$\left(\frac{1}{2}\right)^3 = \frac{1}{8}$$
$$\left(\frac{1}{2}\right)^4 = \frac{1}{16}$$

The value of $r^n$ decreases rapidly. What happens for greater values of $n$?

$$\left(\frac{1}{2}\right)^{10} = \frac{1}{1,024}$$
$$\left(\frac{1}{2}\right)^{20} = \frac{1}{1,048,576}$$
$$\left(\frac{1}{2}\right)^{30} = \frac{1}{1,073,741,824}$$

As $n$ gets very large, $r^n$ gets very small. We say that, as $n$ increases without bound, $r^n$ approaches 0. As $r^n$ approaches 0, 1, $-r^n$ approaches 1. When this happens, the numerator approaches $a_1$. This give us a formula for the sum of an infinite geometric series.

**FORMULA FOR THE SUM OF AN INFINITE GEOMETRIC SERIES**

The formula for the sum of an infinite geometric series with $-1 < r < 1$ is

$$S = \frac{a_1}{1-r} \tag{8.5.4}$$

**How to: Given an infinite geometric series, find its sum**

1. Identify $a_1$ and $r$.
2. Confirm that $-1 < r < 1$.
3. Substitute values for $a_1$ and $r$ into the formula, $S = \frac{a_1}{1-r}$.
4. Simplify to find $S$.

## Example 8.5.7A: Finding the Sum of an Infinite Geometric Series

Find the sum, if it exists, for the following:

a. $10+9+8+7+\ldots$
b. $248.6+99.44+39.776+\ldots$
c. $\sum_{k=1}^{\infty} 4,374\cdot(-\frac{1}{3})^{k-1}$
d. $\sum_{k=1}^{\infty} \frac{1}{9}\cdot(\frac{4}{3})^{k}$

**Solution**

a. There is not a constant ratio; the series is not geometric.

b. There is a constant ratio; the series is geometric. $a_1=248.6$ and $r=\dfrac{99.44}{248.6}=0.4$, so the sum exists. Substitute $a_1=248.6$ and $r=0.4$ into the formula and simplify to find the sum:

$$\begin{aligned} S &= \frac{a_1}{1-r} \\ &= \frac{248.6}{1-0.4} \\ &= 414.\overline{3} \end{aligned}$$

c. The formula is exponential, so the series is geometric with $r=-\dfrac{1}{3}$. Find $a_1$ by substituting $k=1$ into the given explicit formula:

$$a_1 = 4,374\cdot(-\frac{1}{3})^{1-1} = 4,374$$

Substitute $a_1=4,374$ and $r=-\dfrac{1}{3}$ into the formula, and simplify to find the sum:

$$\begin{aligned} S &= \frac{a_1}{1-r} \\ &= \frac{4,374}{1-\left(-\frac{1}{3}\right)} \\ &= 3,280.5 \end{aligned}$$

d. The formula is exponential, so the series is geometric, but $r>1$. The sum does not exist.

## Example 8.5.7B: Finding an Equivalent Fraction for a Repeating Decimal

Find an equivalent fraction for the repeating decimal $0.\overline{3}$

**Solution**

We notice the repeating decimal $0.\overline{3}=0.333\ldots$so we can rewrite the repeating decimal as a sum of terms.

$$0.\overline{3}=0.3+0.03+0.003+\ldots$$

Looking for a pattern, we rewrite the sum, noticing that we see the first term multiplied to $0.1$ in the second term, and the second term multiplied to $0.1$ in the third term.

$$0.\overline{3} = 0.3 + (0.1)\underbrace{(0.3)}_{\text{First Term}} + (0.1)\underbrace{(0.1)(0.3)}_{\text{Second Term}}$$

Notice the pattern; we multiply each consecutive term by a common ratio of $0.1$ starting with the first term of $0.3$. So, substituting into our formula for an infinite geometric sum, we have

$$S_n = \frac{a_1}{1-r} = \frac{0.3}{1-0.1} = \frac{0.3}{0.9} = \frac{1}{3} \ .$$

Find the sum, if it exists.

**Exercise 8.5.7A**

$2+23+29+\ldots$

**Answer**

3

**Exercise 8.5.7B**

$\sum_{k=1}^{\infty} 0.76k+1$

**Answer**

The series is not geometric.

**Exercise 8.5.7C**

$\sum_{k=1}^{\infty} \left(-\frac{3}{8}\right)^k$

**Answer**

$-\frac{3}{11}$

## Solving Annuity Problems

At the beginning of the section, we looked at a problem in which a couple invested a set amount of money each month into a college fund for six years. An annuity is an investment in which the purchaser makes a sequence of periodic, equal payments. To find the amount of an annuity, we need to find the sum of all the payments and the interest earned. In the example, the couple invests $\$50$ each month. This is the value of the initial deposit. The account paid $6\%$ annual interest, compounded monthly. To find the interest rate per payment period, we need to divide the $6\%$ annual percentage interest (APR) rate by 12. So the monthly interest rate is $0.5\%$. We can multiply the amount in the account each month by $100.5\%$ to find the value of the account after interest has been added.

We can find the value of the annuity right after the last deposit by using a geometric series with $a_1 = 50$ and $r = 100.5$. After the first deposit, the value of the annuity will be $\$50$. Let us see if we can determine the amount in the college fund and the interest earned.

We can find the value of the annuity after nn deposits using the formula for the sum of the first nn terms of a geometric series. In 6 years, there are 72 months, so $n = 72$. We can substitute $a_1 = 50$, $r = 1.005$, and $n = 72$ into the formula, and simplify to find the value of the annuity after 6 years.

$$S_{72} = \frac{50(1-1.005^{72})}{1-1.005} \approx 4,320.44$$

After the last deposit, the couple will have a total of $\$4,320.44$in the account. Notice, the couple made 72 payments of $\$50$ each for a total of $72(50) = \$3,600$. This means that because of the annuity, the couple earned $\$720.44$interest in their college fund.

**How to: Given an initial deposit and an interest rate, find the value of an annuity.**

1. Determine $a_1$, the value of the initial deposit.
2. Determine $n$, the number of deposits.
3. Determine $r$.
   - Divide the annual interest rate by the number of times per year that interest is compounded.
   - Add 1 to this amount to find $r$.
4. Substitute values for $a_1$, $r$, and $n$ into the formula for the sum of the first nn terms of a geometric series, $S_n = \frac{a_1(1-r^n)}{1-r}$.
5. Simplify to find $S_n$, the value of the annuity after $n$ deposits.

**Example 8.5.8: Solving an Annuity Problem**

A deposit of $\$100$ is placed into a college fund at the beginning of every month for 10 years. The fund earns $9\%$ annual interest, compounded monthly, and paid at the end of the month. How much is in the account right after the last deposit?

**Solution**

The value of the initial deposit is $\$100$, so $a_1 = 100$. A total of 120 monthly deposits are made in the 10 years, so $n = 120$. To find $r$, divide the annual interest rate by 12 to find the monthly interest rate and add 1 to represent the new monthly deposit.

$$r = 1 + \frac{0.09}{12} = 1.0075$$

Substitute $a_1 = 100$, $r = 1.0075$, and $n = 120$ into the formula for the sum of the first $n$ terms of a geometric series, and simplify to find the value of the annuity.

$$S_{120} = \frac{100(1 - 1.0075^{120})}{1 - 1.0075} \approx 19,351.43$$

So the account has $19,351.43 after the last deposit is made.

**Exercise 8.5.8**

At the beginning of each month, $\$200$ is deposited into a retirement fund. The fund earns $6\%$ annual interest, compounded monthly, and paid into the account at the end of the month. How much is in the account if deposits are made for 10 years?

**Answer**

$\$92,408.18$

**Media**

Access these online resources for additional instruction and practice with series.

- Arithmetic Series
- Geometric Series
- Summation Notation

## Key Equations

| | |
|---|---|
| sum of the first $n$ terms of an arithmetic series | $S_n = \frac{n(a_1 + a_n)}{2}$ |
| sum of the first $n$ terms of a geometric series | $S_n = \frac{a_1(1-r^n)}{1-r} \cdot r \neq 1$ |
| sum of an infinite geometric series with $-1 < r < 1$ | $S_n = \frac{a_1}{1-r} \cdot r \neq 1$ |

## Key Concepts

- The sum of the terms in a sequence is called a series.
- A common notation for series is called summation notation, which uses the Greek letter sigma to represent the sum. See Example 8.5.1.
- The sum of the terms in an arithmetic sequence is called an arithmetic series.
- The sum of the first $n$ terms of an arithmetic series can be found using a formula. See Example 8.5.2 and Example 8.5.3.
- The sum of the terms in a geometric sequence is called a geometric series.
- The sum of the first $n$ terms of a geometric series can be found using a formula. See Example 8.5.4 and Example 8.5.5.
- The sum of an infinite series exists if the series is geometric with $-1 < r < 1$.
- If the sum of an infinite series exists, it can be found using a formula. See Example 8.5.6, Example 8.5.7, and Example 8.5.8.
- An annuity is an account into which the investor makes a series of regularly scheduled payments. The value of an annuity can be found using geometric series. See Example 8.5.9.

---

This page titled 8.5: Series and Their Notations is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.4: Series and Their Notations** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 8.5E: Series and Their Notations (Exercises)

21. Use summation notation to write the sum of terms $\frac{1}{2}m+5$ from $m=0$ to $m=5$.

22. Use summation notation to write the sum that results from adding the number 13 twenty times.

23. Use the formula for the sum of the first $n$ terms of an arithmetic series to find the sum of the first eleven terms of the arithmetic series $2.5, 4, 5.5, \ldots$

24. A ladder has 15 tapered rungs, the lengths of which increase by a common difference. The first rung is 5 inches long, and the last rung is 20 inches long. What is the sum of the lengths of the rungs?

25. Use the formula for the sum of the first $n$ terms of a geometric series to find $S_9$ for the series $12, 6, 3, \frac{3}{2}, \ldots$

26. The fees for the first three years of a hunting club membership are given in Table 1 . If fees continue to rise at the same rate, how much will the total cost be for the first ten years of membership?

Table 1

| Year | Membership Fees |
|---|---|
| 1 | $1500 |
| 2 | $1950 |
| 3 | $2535 |

27. Find the sum of the infinite geometric series $\sum_{k=1}^{\infty} 45 \cdot \left(-\frac{1}{3}\right)^{k-1}$.

28. A ball has a bounce-back ratio of $\frac{3}{5}$ the height of the previous bounce. Write a series representing the total distance traveled by the ball, assuming it was initially dropped from a height of 5 feet. What is the total distance? (Hint: the total distance the ball travels on each bounce is the sum of the heights of the rise and the fall.).

29. Alejandro deposits $\$80$ of his monthly earnings into an annuity that earns $6.25\%$ annual interest, compounded monthly. How much money will he have saved after 5 years?

30. The twins Sarah and Scott both opened retirement accounts on their $21^{\text{st}}$ birthday. Sarah deposits $\$4,800.00$each year, earning $5.5\%$ annual interest, compounded monthly. Scott deposits $\$3,600.00$ each year, earning $8.5\%$ annual interest, compounded monthly. Which twin will earn the most interest by the time they are 55 years old? How much more?

This page titled 8.5E: Series and Their Notations (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.4E: Series and Their Notations (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# CHAPTER OVERVIEW

## 9: Additional Topics for Ch 4, 6, 7 and 8


9.1: Inverses and Radical Functions

9.1.1: Inverses and Radical Functions (Exercises)

9.2: Modeling Using Variation

9.2E: Modeling Using Variation (Exercises)

9.3: Partial Fractions

9.3.1: Partial Fractions (Exercises)

9.4: Matrices and Matrix Operations

9.4E: Matrices and Matrix Operations (Exercises)

9.5: Solving Systems with Inverses

9.5E: Solving Systems with Inverses (Exercises)

9.6: Solving Systems with Cramer's Rule

9.6E: Solving Systems with Cramer's Rule (Exercises)

9.7: Rotation of Axes

9.7E: Rotation of Axes (Exercises)

9.8: Conic Sections in Polar Coordinates

9.8E: Conic Sections in Polar Coordinates (Exercises)

9.9: Counting Principles

9.9E: Counting Principles (Exercises)

9.10: Binomial Theorem

9.10E: Binomial Theorem (Exercises)

9.11: Probability

9.11E: Probability (Exercises)



9: Additional Topics for Ch 4, 6, 7 and 8 is shared under a not declared license and was authored, remixed, and/or curated by LibreTexts.

# 9.1: Inverses and Radical Functions

**Learning Objectives**

In this section, you will:

- Find the inverse of an invertible polynomial function.
- Restrict the domain to find the inverse of a polynomial function.

A mound of gravel is in the shape of a cone with the height equal to twice the radius.




Figure 9.1.1

The volume is found using a formula from elementary geometry.

$$\begin{aligned} V &= \frac{1}{3}\pi r^2 h \\ &= \frac{1}{3}\pi r^2 (2r) \\ &= \frac{2}{3}\pi r^3 \end{aligned}$$

We have written the volume $V$ in terms of the radius $r$. However, in some cases, we may start out with the volume and want to find the radius. For example: A customer purchases 100 cubic feet of gravel to construct a cone shape mound with a height twice the radius. What are the radius and height of the new cone? To answer this question, we use the formula

$$r = \sqrt[3]{\frac{3V}{2\pi}}$$

This function is the inverse of the formula for $V$ in terms of $r$.

In this section, we will explore the inverses of polynomial and rational functions and in particular the radical functions we encounter in the process.

## Finding the Inverse of a Polynomial Function

Two functions $f$ and $g$ are inverse functions if for every coordinate pair in $f$, $(a, b)$, there exists a corresponding coordinate pair in the inverse function, $g$, $(b, a)$. In other words, the coordinate pairs of the inverse functions have the input and output interchanged. Only one-to-one functions have inverses. Recall that a one-to-one function has a unique output value for each input value and passes the horizontal line test.

For example, suppose a water runoff collector is built in the shape of a parabolic trough as shown in Figure 9.1.2. We can use the information in the figure to find the surface area of the water in the trough as a function of the depth of the water.





Figure 9.1.2

Because it will be helpful to have an equation for the parabolic cross-sectional shape, we will impose a coordinate system at the cross section, with $x$ measured horizontally and $y$ measured vertically, with the origin at the vertex of the parabola (Figure 9.1.3).





Figure 9.1.3

From this we find an equation for the parabolic shape. We placed the origin at the vertex of the parabola, so we know the equation will have form $y(x) = ax^2$. Our equation will need to pass through the point $(6, 18)$, from which we can solve for the stretch factor $a$.

$$\begin{aligned} 18 &= a6^2 \\ a &= \frac{18}{36} \\ &= \frac{1}{2} \end{aligned}$$

Our parabolic cross section has the equation

$$y(x) = \frac{1}{2}x^2$$

We are interested in the *surface area* of the water, so we must determine the width at the top of the water as a function of the water depth. For any depth $y$, the width will be given by $2x$, so we need to solve the equation above for $x$ and find the inverse function. However, notice that the original function is not one-to-one, and indeed, given any output there are two inputs that produce the same output, one positive and one negative.

To find an inverse, we can restrict our original function to a limited domain on which it *is* one-to-one. In this case, it makes sense to restrict ourselves to positive $x$ values. On this domain, we can find an inverse by solving for the input variable:

$$\begin{aligned} y &= \frac{1}{2}x^2 \\ 2y &= x^2 \\ x &= \pm\sqrt{2y} \end{aligned}$$

This is not a function as written. We are limiting ourselves to positive $x$ values, so we eliminate the negative solution, giving us the inverse function we're looking for.

$$y = \frac{x^2}{2}, x > 0$$

Because $x$ is the distance from the center of the parabola to either side, the entire width of the water at the top will be $2x$. The trough is 3 feet (36 inches) long, so the surface area will then be:

$$\begin{aligned} \text{Area } &= l \cdot w \\ &= 36 \cdot 2x \\ &= 72x \\ &= 72\sqrt{2y} \end{aligned}$$

This example illustrates two important points:

1. When finding the inverse of a quadratic, we have to limit ourselves to a domain on which the function is one-to-one.
2. The inverse of a quadratic function is a square root function. Both are toolkit functions and different types of power functions.

Functions involving roots are often called **radical functions**. While it is not possible to find an inverse of most polynomial functions, some basic polynomials do have inverses. Such functions are called **invertible functions**, and we use the notation $f^{-1}(x)$.

Warning: $f^{-1}(x)$ is not the same as the reciprocal of the function $f(x)$. This use of "–1" is reserved to denote inverse functions. To denote the reciprocal of a function $f(x)$, we would need to write:

$$(f(x))^{-1} = \frac{1}{f(x)}. \tag{9.1.1}$$

An important relationship between inverse functions is that they "undo" each other. If $f^{-1}$ is the inverse of a function $f$, then $f$ is the inverse of the function $f^{-1}$. In other words, whatever the function $f$ does to $x$, $f^{-1}$ undoes it—and vice-versa.

$$f^{-1}(f(x)) = x, \text{ for all } x \text{ in the domain of } f$$

and

$$f(f^{-1}(x)) = x, \text{ for all } x \text{ in the domain of } f^{-1}$$

Note that the inverse switches the domain and range of the original function.

### VERIFYING TWO FUNCTIONS ARE INVERSES OF ONE ANOTHER

Two functions, $f$ and $g$, are inverses of one another if for all $x$ in the domain of $f$ and $g$,

$$g(f(x)) = f(g(x)) = x$$

### Howto: Given a polynomial function, find the inverse of the function by restricting the domain in such a way that the new function is one-to-one

1. Replace $f(x)$ with $y$.
2. Interchange $x$ and $y$.
3. Solve for $y$, and rename the function $f^{-1}(x)$.

### Example 9.1.1: Verifying Inverse Functions

Show that $f(x) = \frac{1}{x+1}$ and $f^{-1}(x) = \frac{1}{x} - 1$ are inverses, for $x \neq 0, -1$.

**Solution**

We must show that $f^{-1}(f(x)) = x$ and $f(f^{-1}(x)) = x$.

$$f^{-1}(f(x)) = f^{-1}\left(\frac{1}{x+1}\right)$$
$$= \frac{1}{\frac{1}{x+1}} - 1$$
$$= (x+1) - 1$$
$$= x$$

and

$$f(f^{-1}(x)) = f(\frac{1}{x-1})$$
$$= \frac{1}{\left(\frac{1}{x-1}\right)+1}$$
$$= \frac{1}{\frac{1}{x}}$$
$$= x$$

Therefore, $f(x) = \dfrac{1}{x+1}$ and $f^{-1}(x) = \dfrac{1}{x} - 1$ are inverses.

### Exercise 9.1.1

Show that $f(x) = \frac{x+5}{3}$ and $f^{-1}(x) = 3x - 5$ are inverses.

**Answer a**

$f^{-1}(f(x)) = f^{-1}(\frac{x+5}{3}) = 3(\frac{x+5}{3}) - 5 = (x-5) + 5 = x$

**Answer b**

$f(f^{-1}(x)) = f(3x-5) = \frac{(3x-5)+5}{3} = \frac{3x}{3} = x$

### Example 9.1.2: Finding the Inverse of a Cubic Function

Find the inverse of the function $f(x) = 5x^3 + 1$.

**Solution**

This is a transformation of the basic cubic toolkit function, and based on our knowledge of that function, we know it is one-to-one. Solving for the inverse by solving for $x$.

$$y = 5x^3 + 1$$
$$x = 5y^3 + 1$$
$$x - 1 = 5y^3$$
$$\frac{x-1}{5} = y^3$$
$$f^{-1}(x) = \sqrt[3]{\frac{x-1}{5}}$$

**Analysis**

Look at the graph of $f$ and $f^{-1}$. Notice that one graph is the reflection of the other about the line $y = x$. This is always the case when graphing a function and its inverse function.

Also, since the method involved interchanging $x$ and $y$, notice corresponding points. If $(a, b)$ is on the graph of $f$,then $(b, a)$ is on the graph of $f^{-1}$. Since $(0, 1)$ is on the graph of $f$, then $(1, 0)$ is on the graph of $f^{-1}$. Similarly, since $(1, 6)$ is on the graph of $f$,then $(6, 1)$ is on the graph of $f^{-1}$ (Figure 9.1.9).





Figure 9.1.4

**Exercise 9.1.2**

Find the inverse function of $f(x) = \sqrt[3]{x+4}$.

**Answer**

$f^{-1}(x) = x^3 - 4$

## Restricting the Domain to Find the Inverse of a Polynomial Function

So far, we have been able to find the inverse functions of **cubic functions** without having to restrict their domains. However, as we know, not all cubic polynomials are one-to-one. Some functions that are not one-to-one may have their domain restricted so that they are one-to-one, but only over that domain. The function over the restricted domain would then have an **inverse function**. Since quadratic functions are not one-to-one, we must restrict their domain in order to find their inverses.

**RESTRICTING THE DOMAIN**

If a function is not one-to-one, it cannot have an inverse. If we restrict the domain of the function so that it becomes one-to-one, thus creating a new function, this new function will have an inverse.

**How to: Given a polynomial function, restrict the domain of a function that is not one-to-one and then find the inverse**

1. Restrict the domain by determining a domain on which the original function is one-to-one.
2. Replace $f(x)$ with $y$.
3. Interchange $x$ and $y$.
4. Solve for $y$, and rename the function or pair of function $f^{-1}(x)$.
5. Revise the formula for $f^{-1}(x)$ by ensuring that the outputs of the inverse function correspond to the restricted domain of the original function.

## Example 9.1.3: Restricting the Domain to Find the Inverse of a Polynomial Function

Find the inverse function of $f$:

1. $f(x) = (x-4)^2$, $x \geq 4$
2. $f(x) = (x-4)^2$, $x \leq 4$

**Solution**

The original function $f(x) = (x-4)^2$ is not one-to-one, but the function is restricted to a domain of $x \geq 4$ or $x \leq 4$ on which it is one-to-one (Figure 9.1.6).





Figure 9.1.5

To find the inverse, start by replacing $f(x)$ with the simple variable $y$.

$$y = (x-4)^2 \text{ Interchange } x \text{ and } y.$$

$$x = (y-4)^2 \text{ Take the square root.}$$

$$\pm\sqrt{x} = y - 4 \text{ Add 4 to both sides.}$$

$$4 \pm \sqrt{x} = y$$

This is not a function as written. We need to examine the restrictions on the domain of the original function to determine the inverse. Since we reversed the roles of $x$ and $y$ for the original $f(x)$, we looked at the domain: the values $x$ could assume. When we reversed the roles of $x$ and $y$, this gave us the values $y$ could assume. For this function, $x \geq 4$, so for the inverse, we should have $y \geq 4$, which is what our inverse function gives.

1. The domain of the original function was restricted to $x \geq 4$, so the outputs of the inverse need to be the same, $f(x) \geq 4$, and we must use the + case:
$$f^{-1}(x) = 4 + \sqrt{x}$$
2. The domain of the original function was restricted to $x \leq 4$, so the outputs of the inverse need to be the same, $f(x) \leq 4$, and we must use the – case:
$$f^{-1}(x) = 4 - \sqrt{x}$$

**Analysis**

On the graphs in Figure 9.1.6, we see the original function graphed on the same set of axes as its inverse function. Notice that together the graphs show symmetry about the line $y = x$. The coordinate pair $(4, 0)$ is on the graph off f and the coordinate pair $(0, 4)$ is on the graph of $f^{-1}$. For any coordinate pair, if $(a, b)$ is on the graph of $f$, then $(b, a)$ is on the graph of $f^{-1}$. Finally, observe that the graph of $f$ intersects the graph of $f^{-1}$ on the line $y = x$. Points of intersection for the graphs of $f$ and $f^{-1}$ will always lie on the line $y = x$.




Figure 9.1.6

## Example 9.1.4: Finding the Inverse of a Quadratic Function When the Restriction Is Not Specified

Restrict the domain and then find the inverse of

$$f(x) = (x-2)^2 - 3\,.$$

**Solution**

We can see this is a parabola with vertex at $(2,-3)$ that opens upward. Because the graph will be decreasing on one side of the vertex and increasing on the other side, we can restrict this function to a domain on which it will be one-to-one by limiting the domain to $x \geq 2$.

To find the inverse, we will use the vertex form of the quadratic. We start by replacing $f(x)$ with a simple variable, $y$, then solve for $x$.

$$y = (x-2)^2 - 3 \text{ Interchange } x \text{ and } y.$$

$$x = (y-2)^2 - 3 \text{ Add 3 to both sides.}$$

$$x+3 = (y-2)^2 \text{ Take the square root.}$$

$$\pm\sqrt{x+3} = y-2 \text{ Add 2 to both sides.}$$

$$2 \pm \sqrt{x+3} = y \text{ Rename the function.}$$

$$f^{-1}(x) = 2 \pm \sqrt{x+3}$$

Now we need to determine which case to use. Because we restricted our original function to a domain of $x \geq 2$, the outputs of the inverse should be the same, telling us to utilize the + case

$$f^{-1}(x) = 2 + \sqrt{x+3}$$

If the quadratic had not been given in vertex form, rewriting it into vertex form would be the first step. This way we may easily observe the coordinates of the vertex to help us restrict the domain.

Analysis

Notice that we arbitrarily decided to restrict the domain on $x \geq 2$. We could just as easily have opted to restrict the domain to $x \leq 2$, in which case $f^{-1}(x) = 2 - \sqrt{x+3}$ . Observe the original function graphed on the same set of axes as its inverse function in Figure 9.1.7. Notice that both graphs show symmetry about the line $y = x$. The coordinate pair $(2,-3)$ is on the graph of $f$ and the coordinate pair $(-3,2)$ is on the graph of $f^{-1}$. Observe from the graph of both functions on the same set of axes that

$$\text{domain of } f = \text{range of } f^{-1} = [2,\infty)$$

and

$$\text{domain of } f^{-1} = \text{range of } f = [-3,\infty).$$

Finally, observe that the graph of $f$ intersects the graph of $f^{-1}$ along the line $y = x$.





Figure 9.1.7

**Exercise 9.1.4**

Find the inverse of the function $f(x) = x^2 + 1$, on the domain $x \geq 0$.

**Answer**

$f^{-1}(x) = \sqrt{x-1}$

## Finding Inverses

Notice that the functions from previous examples were all polynomials, and their inverses were radical functions. If we want to find the inverse of a radical function, we will need to restrict the domain of the answer because the range of the original function is limited.

**How to: Given a radical function, find the inverse**

1. Determine the range of the original function.
2. Replace $f(x)$ with $y$, then solve for $x$.
3. If necessary, restrict the domain of the inverse function to the range of the original function.

**Example 9.1.5: Finding the Inverse of a Radical Function**

Restrict the domain of the function $f(x) = \sqrt{x-4}$ and then find the inverse.

**Solution**

Note that the original function has range $f(x) \geq 0$. Replace $f(x)$ with $y$, then solve for $x$.

$$y = \sqrt{x-4} \text{ Replace } f(x) \text{ with } y.$$
$$x = \sqrt{y-4} \text{ Interchange } x \text{ and } y.$$
$$x = \sqrt{y-4} \text{ Square each side.}$$
$$x^2 = y - 4 \text{ Add 4.}$$
$$x^2 + 4 = y \text{ Rename the function } f^{-1}(x).$$
$$f^{-1}(x) = x^2 + 4$$

Recall that the domain of this function must be limited to the range of the original function.

$$f^{-1}(x) = x^2 + 4, \; x \geq 0$$

**Analysis**

Notice in Figure 9.1.8 that the inverse is a reflection of the original function over the line $y = x$. Because the original function has only positive outputs, the inverse function has only nonnegative inputs.




Figure 9.1.8

**Exercise 9.1.5**

Restrict the domain and then find the inverse of the function $f(x)=\sqrt{2x+3}$.

**Answer**

$f^{-1}(x)=\frac{x^2-3}{2}$, $x\geq 0$

## Solving Applications of Radical Functions

Radical functions are common in physical models, as we saw in the section opener. We now have enough tools to be able to solve the problem posed at the start of the section.

**Example 9.1.6: Solving an Application with a Cubic Function**

A mound of gravel is in the shape of a cone with the height equal to twice the radius. The volume of the cone in terms of the radius is given by

$$V=\frac{2}{3}\pi r^3$$

Find the inverse of the function $V=\frac{2}{3}\pi r^3$ that determines the volume $V$ of a cone and is a function of the radius $r$. Then use the inverse function to calculate the radius of such a mound of gravel measuring 100 cubic feet. Use $\pi=3.14$.

**Solution**

Start with the given function for $V$. Notice that the meaningful domain for the function is $r>0$ since negative radii would not make sense in this context nor would a radius of 0. Also note the range of the function (hence, the domain of the inverse function) is $V>0$. Solve for $r$ in terms of $V$, using the method outlined previously. Note that in real-world applications, we do not swap the variables when finding inverses. Instead, we change which variable is considered to be the independent variable.

$$V=\frac{2}{3}\pi r^3$$

Solve for $r^3$.

$$r^3=\frac{3V}{2\pi}$$

Solve for $r$.

$$r=\sqrt[3]{\frac{3V}{2\pi}}$$

This is the result stated in the section opener. Now evaluate this for $V=100$ and $\pi=3.14$.

$$
\begin{aligned}
r &= \sqrt[3]{\frac{3V}{2\pi}} \\
&= \sqrt[3]{\frac{3 \cdot 100}{2 \cdot 3.14}} \\
&\approx \sqrt[3]{47.7707} \\
&\approx 3.63
\end{aligned}
$$

Therefore, the radius is about 3.63 ft.

### Determining the Domain of a Radical Function Composed with Other Functions

When radical functions are composed with other functions, determining domain can become more complicated.

**Example 9.1.7: Finding the Domain of a Radical Function Composed with a Rational Function**

Find the domain of the function:

$$f(x) = \sqrt{\frac{(x+2)(x-3)}{(x-1)}}.$$

**Solution**

Because a square root is only defined when the quantity under the radical is non-negative, we need to determine where

$$\frac{(x+2)(x-3)}{(x-1)} \geq 0.$$

The output of a rational function can change signs (change from positive to negative or vice versa) at *x*-intercepts and at vertical asymptotes. For this equation, the graph could change signs at $x = -2$, 1, and 3.

To determine the intervals on which the rational expression is positive, we could test some values in the expression or sketch a graph. While both approaches work equally well, for this example we will use a graph as shown in Figure 9.1.9.





Figure 9.1.9

This function has two *x*-intercepts, both of which exhibit linear behavior near the *x*-intercepts. There is one vertical asymptote, corresponding to a linear factor; this behavior is similar to the basic reciprocal toolkit function, and there is no horizontal asymptote because the degree of the numerator is larger than the degree of the denominator. There is a *y*-intercept at $(0, \sqrt{6})$.

From the *y*-intercept and *x*-intercept at $x = -2$, we can sketch the left side of the graph. From the behavior at the asymptote, we can sketch the right side of the graph.

From the graph, we can now tell on which intervals the outputs will be non-negative, so that we can be sure that the original function $f(x)$ will be defined. $f(x)$ has domain $-2 \leq x < 1$ or $x \geq 3$, or in interval notation, $[-2, 1) \cup [3, \infty)$.

## Finding Inverses of Rational Functions

As with finding inverses of quadratic functions, it is sometimes desirable to find the *inverse of a rational function*, particularly of rational functions that are the ratio of linear functions, such as in concentration applications.

### Example 9.1.8: Finding the Inverse of a Rational Function

The function

$$C = \frac{20 + 0.4n}{100 + n} \tag{9.1.2}$$

represents the concentration $C$ of an acid solution after $n$ mL of 40% solution has been added to 100 mL of a 20% solution. First, find the inverse of the function; that is, find an expression for $n$ in terms of $C$. Then use your result to determine how much of the 40% solution should be added so that the final mixture is a 35% solution.

**Solution**

We first want the inverse of the function in order to determine how many mL we need for a given concentration. We will solve for $n$ in terms of $C$.

$$\begin{aligned} C &= \frac{20 + 0.4n}{100 + n} \\ C(100 + n) &= 20 + 0.4n \\ 100C + Cn &= 20 + 0.4n \\ 100C - 20 &= 0.4n - Cn \\ 100C - 20 &= (0.4 - C)n \\ n &= \frac{100C - 20}{0.4 - C} \end{aligned}$$

Now evaluate this function at 35%, which is $C = 0.35$.

$$\begin{aligned} n &= \frac{100(0.35) - 20}{0.4 - 0.35} \\ &= \frac{15}{0.05} \\ &= 300 \end{aligned}$$

We can conclude that 300 mL of the 40% solution should be added.

### Exercise 9.1.8

Find the inverse of the function $f(x) = \frac{x+3}{x-2}$.

**Answer**

$f^{-1}(x) = \frac{2x+3}{x-1}$

### Media

Access these online resources for additional instruction and practice with inverses and radical functions.

- Graphing the Basic Square Root Function
- Find the Inverse of a Square Root Function
- Find the Inverse of a Rational Function
- Find the Inverse of a Rational Function and an Inverse Function Value
- Inverse Functions

## Key Concepts

- The inverse of a quadratic function is a square root function.
- If $f^{-1}$ is the inverse of a function $f$, then $f$ is the inverse of the function $f^{-1}$. See Example $9.1.1$.
- While it is not possible to find an inverse of most polynomial functions, some basic polynomials are invertible. See Example $9.1.2$.
- To find the inverse of certain functions, we must restrict the function to a domain on which it will be one-to-one. See Examples $9.1.3$ and $9.1.4$
- When finding the inverse of a radical function, we need a restriction on the domain of the answer. See Example $9.1.5$ and $9.1.7$.
- Inverse and radical and functions can be used to solve application problems. See Examples $9.1.6$ and $9.1.8$.

---

This page titled 9.1: Inverses and Radical Functions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.8: Inverses and Radical Functions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.1.1: Inverses and Radical Functions (Exercises)

For the following exercises, find the inverse of the function with the domain given.

37. $f(x) = (x-2)^2, \quad x \geq 2$

38. $f(x) = (x+4)^2 - 3, \quad x \geq -4$

39. $f(x) = x^2 + 6x - 2, \quad x \geq -3$

40. $f(x) = 2x^3 - 3$

41. $f(x) = \sqrt{4x+5} - 3$

42. $f(x) = \frac{x-3}{2x+1}$

This page titled 9.1.1: Inverses and Radical Functions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **5.7E: Inverses and Radical Functions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.2: Modeling Using Variation

**Learning Objectives**

In this section, you will:

- Solve direct variation problems.
- Solve inverse variation problems.
- Solve problems involving joint variation.

A used-car company has just offered their best candidate, Nicole, a position in sales. The position offers 16% commission on her sales. Her earnings depend on the amount of her sales. For instance, if she sells a vehicle for $4,600, she will earn $736. She wants to evaluate the offer, but she is not sure how. In this section, we will look at relationships, such as this one, between earnings, sales, and commission rate.

## Solving Direct Variation Problems

In the example above, Nicole's earnings can be found by multiplying her sales by her commission. The formula $e = 0.16s$ tells us her earnings, $e$, come from the product of 0.16, her commission, and the sale price of the vehicle. If we create a table, we observe that as the sales price increases, the earnings increase as well, which should be intuitive. See **Table 5.8.1**.

| $s$, sales price | $e = 0.16s$ | Interpretation |
|---|---|---|
| $9,200 | $e = 0.16(9,200) = 1,472$ | A sale of a $9,200 vehicle results in $1472 earnings. |
| $4,600 | $e = 0.16(4,600) = 736$ | A sale of a $4,600 vehicle results in $736 earnings. |
| $18,400 | $e = 0.16(18,400) = 2,944$ | A sale of a $18,400 vehicle results in $2944 earnings. |

**Table 5.8.1**

Notice that earnings are a multiple of sales. As sales increase, earnings increase in a predictable way. Double the sales of the vehicle from $4,600 to $9,200, and we double the earnings from $736 to $1,472. As the input increases, the output increases as a multiple of the input. A relationship in which one quantity is a constant multiplied by another quantity is called **direct variation**. Each variable in this type of relationship **varies directly** with the other.

Figure 5.8.1 represents the data for Nicole's potential earnings. We say that earnings vary directly with the sales price of the car. The formula $y = kx^n$ is used for direct variation. The value $k$ is a nonzero constant greater than zero and is called the **constant of variation**. In this case, $k = 0.16$ and $n = 1$. We saw functions like this one when we discussed power functions.

Figure has invalid source: image visible until saved.... src="/@api/deki/pages/=Bookshelves%252FPrecalculus%252FBook%25253A_Precalculus_(OpenStax)%252F03%25253A_Polynomial_and_Rational_Functions%252F3.9%25253A_Modeling_Using_Variation/files/CNX_Precalc_Figure_03_09_001.jpg

Figure 5.8.1

**A General Note: DIRECT VARIATION**

If $x$ and $y$ are related by an equation of the form

$$y = kx^n$$

then we say that the relationship is **direct variation** and $y$ **varies directly** with, or is proportional to, the $n$th power of $x$. In direct variation relationships, there is a nonzero constant ratio $k = \frac{y}{x^n}$, where $k$ is called the **constant of variation**, which help defines the relationship between the variables.

## Given a description of a direct variation problem, solve for an unknown.

1. Identify the input, $x$,and the output, $y$.
2. Determine the constant of variation. You may need to divide $y$ by the specified power of $x$ to determine the constant of variation.
3. Use the constant of variation to write an equation for the relationship.
4. Substitute known values into the equation to find the unknown.

## Example

Solving a Direct Variation Problem

The quantity $y$ varies directly with the cube of $x$. If $y = 25$ when $x = 2$, find $y$ when $x$ is 6.

**Solution**

The general formula for direct variation with a cube is $y = kx^3$ . The constant can be found by dividing $y$ by the cube of $x$.

$$\begin{aligned} k &= \frac{y}{x^3} \\ &= \frac{25}{2^3} \\ &= \frac{25}{8} \end{aligned}$$

Now use the constant to write an equation that represents this relationship.

$$y = \frac{25}{8}x^3$$

Substitute $x = 6$ and solve for $y$.

$$\begin{aligned} y &= \frac{25}{8}(6)^3 \\ &= 675 \end{aligned}$$

Analysis

The graph of this equation is a simple cubic, as shown in **Figure 5.8.2**.





Figure 5.8.2

## Q&A

**Do the graphs of all direct variation equations look like Example?**

*No. Direct variation equations are power functions—they may be linear, quadratic, cubic, quartic, radical, etc. But all of the graphs pass through* $(0, 0)$.

**Exercise**

The quantity $y$ varies directly with the square of $x$. If $y = 24$ when $x = 3$, find $y$ when $x$ is 4.

**Solution**

$\frac{128}{3}$

## Solving Inverse Variation Problems

Water temperature in an ocean varies inversely to the water's depth. The formula $T = \frac{14{,}000}{d}$ gives us the temperature in degrees Fahrenheit at a depth in feet below Earth's surface. Consider the Atlantic Ocean, which covers 22% of Earth's surface. At a certain location, at the depth of 500 feet, the temperature may be 28°F.

If we create **Table 5.8.2**, we observe that, as the depth increases, the water temperature decreases.

| $d$, depth | $T = \frac{14{,}000}{d}$ | Interpretation |
|---|---|---|
| 500 ft | $\frac{14{,}000}{500} = 28$ | At a depth of 500 ft, the water temperature is 28° F. |
| 1000 ft | $\frac{14{,}000}{1000} = 14$ | At a depth of 1,000 ft, the water temperature is 14° F. |
| 2000 ft | $\frac{14{,}000}{2000} = 7$ | At a depth of 2,000 ft, the water temperature is 7° F. |

**Table 5.8.2**

We notice in the relationship between these variables that, as one quantity increases, the other decreases. The two quantities are said to be **inversely proportional** and each term **varies inversely** with the other. Inversely proportional relationships are also called **inverse variations**.

For our example, **Figure 5.8.3** depicts the inverse variation. We say the water temperature varies inversely with the depth of the water because, as the depth increases, the temperature decreases. The formula $y = \frac{k}{x}$ for inverse variation in this case uses $k = 14,000$.





Figure 5.8.3

**A General Note: INVERSE VARIATION**

If $x$ and $y$ are related by an equation of the form

$$y = \frac{k}{x^n}$$

where $k$ is a nonzero constant, then we say that $y$ **varies inversely** with the $n$th power of $x$. In **inversely proportional** relationships, or **inverse variations**, there is a constant multiple $k = x^n y$.

**Example**

Writing a Formula for an Inversely Proportional Relationship

A tourist plans to drive 100 miles. Find a formula for the time the trip will take as a function of the speed the tourist drives.

**Solution**

Recall that multiplying speed by time gives distance. If we let $t$ represent the drive time in hours, and $v$ represent the velocity (speed or rate) at which the tourist drives, then $vt =$ distance. Because the distance is fixed at 100 miles, $vt = 100$ so $t = \frac{100}{v}$. Because time is a function of velocity, we can write $t(v)$.

$$t(v) = \frac{100}{v}$$
$$= 100v^{-1}$$

We can see that the constant of variation is 100 and, although we can write the relationship using the negative exponent, it is more common to see it written as a fraction. We say that time varies inversely with velocity.

**Given a description of an indirect variation problem, solve for an unknown.**

1. Identify the input, $x$, and the output, $y$.
2. Determine the constant of variation. You may need to multiply $y$ by the specified power of $x$ to determine the constant of variation.
3. Use the constant of variation to write an equation for the relationship.
4. Substitute known values into the equation to find the unknown.

**Example**

Solving an Inverse Variation Problem

A quantity $y$ varies inversely with the cube of $x$. If $y = 25$ when $x = 2$, find $y$ when $x$ is 6.

**Solution**

The general formula for inverse variation with a cube is $y = \frac{k}{x^3}$. The constant can be found by multiplying $y$ by the cube of $x$.

$$k = x^3 y$$
$$= 2^3 \cdot 25$$
$$= 200$$

Now we use the constant to write an equation that represents this relationship.

$$y = \frac{k}{x^3}, k = 200$$
$$y = \frac{200}{x^3}$$

Substitute $x = 6$ and solve for $y$.

$$y = \frac{200}{6^3}$$
$$= \frac{25}{27}$$

Analysis

The graph of this equation is a rational function, as shown in **Figure 5.8.4**.





Figure 5.8.4

**Exercise**

A quantity $y$ varies inversely with the square of $x$. If $y = 8$ when $x = 3$, find $y$ when $x$ is 4.

**Solution**

$\frac{9}{2}$

## Solving Problems Involving Joint Variation

Many situations are more complicated than a basic direct variation or inverse variation model. One variable often depends on multiple other variables. When a variable is dependent on the product or quotient of two or more variables, this is called **joint variation**. For example, the cost of busing students for each school trip varies with the number of students attending and the distance from the school. The variable $c$,cost, varies jointly with the number of students, $n$,and the distance, $d$.

**A General Note: JOINT VARIATION**

Joint variation occurs when a variable varies directly or inversely with multiple variables.

For instance, if $x$ varies directly with both $y$ and $z$, we have $x = kyz$. If $x$ varies directly with $y$ and inversely with $z$,we have $x = \frac{ky}{z}$. Notice that we only use one constant in a joint variation equation.

**Example**

Solving Problems Involving Joint Variation

A quantity $x$ varies directly with the square of $y$ and inversely with the cube root of $z$. If $x = 6$ when $y = 2$ and $z = 8$, find $x$ when $y = 1$ and $z = 27$.

**Solution**

Begin by writing an equation to show the relationship between the variables.

$$x = \frac{ky^2}{\sqrt[3]{z}}$$

Substitute $x = 6$, $y = 2$, and $z = 8$ to find the value of the constant $k$.

$$6 = \frac{k2^2}{\sqrt[3]{8}}$$

$$6 = \frac{4k}{2}$$

$$3 = k$$

Now we can substitute the value of the constant into the equation for the relationship.

$$x = \frac{3y^2}{\sqrt[3]{z}}$$

To find $x$ when $y = 1$ and $z = 27$, we will substitute values for $y$ and $z$ into our equation.

$$x = \frac{3(1)^2}{\sqrt[3]{27}}$$
$$= 1$$

**Exercise**

A quantity $x$ varies directly with the square of $y$ and inversely with $z$. If $x = 40$ when $y = 4$ and $z = 2$, find $x$ when $y = 10$ and $z = 25$.

**Solution**

$x = 20$

**Media**

Access these online resources for additional instruction and practice with direct and inverse variation.

- Direct Variation
- Inverse Variation
- Direct and Inverse Variation

Visit this website for additional practice questions from Learningpod.

## Key Equations

| | |
|---|---|
| Direct variation | $y = kx^n$, $k$ is a nonzero constant. |
| Inverse variation | $y = \frac{k}{x^n}$, $k$ is a nonzero constant. |

## Key Concepts

- A relationship where one quantity is a constant multiplied by another quantity is called direct variation. See Example.
- Two variables that are directly proportional to one another will have a constant ratio.
- A relationship where one quantity is a constant divided by another quantity is called inverse variation. See Example.
- Two variables that are inversely proportional to one another will have a constant multiple. See Example.
- In many problems, a variable varies directly or inversely with multiple variables. We call this type of relationship joint variation. See Example.

This page titled 9.2: Modeling Using Variation is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **3.9: Modeling Using Variation** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.2E: Modeling Using Variation (Exercises)

For the following exercises, find the unknown value.

43. $y$ varies directly as the square of $x$. If when $x = 3, \quad y = 36$, find $y$ if $x = 4$.

44. $y$ varies inversely as the square root of $x$ If when $x = 25, \quad y = 2$, find $y$ if $x = 4$.

45. $y$ varies jointly as the cube of $x$ and as $z$. If when $x = 1$ and $z = 2, y = 6,$ find $y$ if $x = 2$ and $z = 3$.

46. $y$ varies jointly as $x$ and the square of $z$ and inversely as the cube of $w$. If when $x = 3, z = 4$, and $w = 2, y = 48$, find $y$ if $x = 4, z = 5,$ and $w = 3$.

For the following exercises, solve the application problem.

47. The weight of an object above the surface of the earth varies inversely with the distance from the center of the earth. If a person weighs 150 pounds when he is on the surface of the earth $(3,960$ miles from center), find the weight of the person if he is 20 miles above the surface.

48. The volume $V$ of an ideal gas varies directly with the temperature $T$ and inversely with the pressure P. A cylinder contains oxygen at a temperature of 310 degrees K and a pressure of 18 atmospheres in a volume of 120 liters. Find the pressure if the volume is decreased to 100 liters and the temperature is increased to 320 degrees $K$.

---

This page titled 9.2E: Modeling Using Variation (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **5.8E: Modeling Using Variation (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.3: Partial Fractions

**Learning Objectives**

Decompose $\frac{P(x)}{Q(x)}$, where

- $Q(x)$ has only nonrepeated linear factors.
- $Q(x)$ has repeated linear factors.
- $Q(x)$ has a nonrepeated irreducible quadratic factor.
- $Q(x)$ has a repeated irreducible quadratic factor.

Earlier in this chapter, we studied systems of two equations in two variables, systems of three equations in three variables, and nonlinear systems. Here we introduce another way that systems of equations can be utilized—the decomposition of rational expressions. Fractions can be complicated; adding a variable in the denominator makes them even more so. The methods studied in this section will help simplify the concept of a rational expression.

## Decomposing $\frac{P(x)}{Q(x)}$ where $Q(x)$ Has Only Nonrepeated Linear Factors

Recall the algebra regarding adding and subtracting rational expressions. These operations depend on finding a common denominator so that we can write the sum or difference as a single, simplified rational expression. In this section, we will look at **partial fraction decomposition**, which is the undoing of the procedure to add or subtract rational expressions. In other words, it is a return from the single simplified **rational expression** to the original expressions, called the **partial fractions**.

For example, suppose we add the following fractions:

$$\frac{2}{x-3}+\frac{-1}{x+2}$$

We would first need to find a common denominator: $(x+2)(x-3)$.

Next, we would write each expression with this common denominator and find the sum of the terms.

$$\begin{aligned}\frac{2}{x-3}\left(\frac{x+2}{x+2}\right)+\frac{-1}{x+2}\left(\frac{x-3}{x-3}\right) &= \frac{2x+4-x+3}{(x+2)(x-3)}\\ &= \frac{x+7}{x^2-x-6}\end{aligned}$$

Partial fraction **decomposition** is the reverse of this procedure. We would start with the solution and rewrite (decompose) it as the sum of two fractions.

$$\underbrace{\frac{x+7}{x^2-x-6}}_{\text{Simplified sum}}=\underbrace{\frac{2}{x-3}+\frac{-1}{x+2}}_{\text{Partial fraction decomposition}}$$

We will investigate rational expressions with linear factors and quadratic factors in the denominator where the degree of the numerator is less than the degree of the denominator. Regardless of the type of expression we are decomposing, the first and most important thing to do is factor the denominator.

When the denominator of the simplified expression contains distinct linear factors, it is likely that each of the original rational expressions, which were added or subtracted, had one of the linear factors as the denominator. In other words, using the example above, the factors of $x^2-x-6$ are $(x-3)(x+2)$, the denominators of the decomposed rational expression. So we will rewrite the simplified form as the sum of individual fractions and use a variable for each numerator. Then, we will solve for each numerator using one of several methods available for partial fraction decomposition.

## PARTIAL FRACTION DECOMPOSITION OF $\frac{P(x)}{Q(x)}$: $Q(x)$ HAS NONREPEATED LINEAR FACTORS

The *partial fraction decomposition* of $\dfrac{P(x)}{Q(x)}$ when $Q(x)$ has nonrepeated linear factors and the degree of $P(x)$ is less than the degree of $Q(x)$ is

$$\frac{P(x)}{Q(x)}=\frac{A_1}{(a_1x+b_1)}+\frac{A_2}{(a_2x+b_2)}+\frac{A_3}{(a_3x+b_3)}+\cdots+\frac{A_n}{(a_nx+b_n)} \tag{9.3.1}$$

## How to: Given a rational expression with distinct linear factors in the denominator, decompose it

1. Use a variable for the original numerators, usually $A$, $B$, or $C$, depending on the number of factors, placing each variable over a single factor. For the purpose of this definition, we use $A_n$ for each numerator
$$\frac{P(x)}{Q(x)}=\frac{A_1}{(a_1x+b_1)}+\frac{A_2}{(a_2x+b_2)}+\frac{A_3}{(a_3x+b_3)}+\cdots+\frac{A_n}{(a_nx+b_n)}$$
2. Multiply both sides of the equation by the common denominator to eliminate fractions.
3. Expand the right side of the equation and collect like terms.
4. Set coefficients of like terms from the left side of the equation equal to those on the right side to create a system of equations to solve for the numerators.

## Example 9.3.1: Decomposing a Rational Function with Distinct Linear Factors

Decompose the given rational expression with distinct linear factors.

$$\frac{3x}{(x+2)(x-1)}$$

**Solution**

We will separate the denominator factors and give each numerator a symbolic label, like $A$, $B$ ,or $C$.

$$\frac{3x}{(x+2)(x-1)}=\frac{A}{(x+2)}+\frac{B}{(x-1)}$$

Multiply both sides of the equation by the common denominator to eliminate the fractions:

$$(x+2)(x-1)\left[\frac{3x}{(x+2)(x-1)}\right]=(x+2)(x-1)\left[\frac{A}{(x+2)}\right]+(x+2)(x-1)\left[\frac{B}{(x-1)}\right]$$

The resulting equation is

$$3x=A(x-1)+B(x+2)$$

Expand the right side of the equation and collect like terms.

$$\begin{aligned}3x&=Ax-A+Bx+2B\\3x&=(A+B)x-A+2B\end{aligned}$$

Set up a system of equations associating corresponding coefficients.

$$\begin{aligned}3&=A+B\\0&=-A+2B\end{aligned}$$

Add the two equations and solve for $B$.

$$\begin{aligned}3&=A+B\\\underline{0}&=\underline{-A+2B}\\3&=0+3B\\1&=B\end{aligned}$$

Substitute $B=1$ into one of the original equations in the system.

$$\begin{aligned} 3 &= A+1 \\ 2 &= A \end{aligned}$$

Thus, the partial fraction decomposition is

$$\frac{3x}{(x+2)(x-1)} = \frac{2}{(x+2)} + \frac{1}{(x-1)}$$

Another method to use to solve for $A$ or $B$ is by considering the equation that resulted from eliminating the fractions and substituting a value for $x$ that will make either the $A-$ or $B-$term equal 0. If we let $x=1$, the

$A-$ term becomes 0 and we can simply solve for $B$.

$$\begin{aligned} 3x &= A(x-1)+B(x+2) \\ 3(1) &= A[(1)-1]+B[(1)+2] \\ 3 &= 0+3B \\ 1 &= B \end{aligned}$$

Next, either substitute $B=1$ into the equation and solve for $A$, or make the $B-$term 0 by substituting $x=-2$ into the equation.

$$\begin{aligned} 3x &= A(x-1)+B(x+2) \\ 3(-2) &= A[(-2)-1]+B[(-2)+2] \\ -6 &= -3A+0 \\ \frac{-6}{-3} &= A \\ 2 &= A \end{aligned}$$

We obtain the same values for $A$ and $B$ using either method, so the decompositions are the same using either method.

$$\frac{3x}{(x+2)(x-1)} = \frac{2}{(x+2)} + \frac{1}{(x-1)}$$

Although this method is not seen very often in textbooks, we present it here as an alternative that may make some partial fraction decompositions easier. It is known as the **Heaviside method**, named after Charles Heaviside, a pioneer in the study of electronics.

**? Exercise 9.3.1**

Find the partial fraction decomposition of the following expression.

$$\frac{x}{(x-3)(x-2)}$$

**Answer**

$$\frac{3}{x-3} - \frac{2}{x-2}$$

## Decomposing $\frac{P(x)}{Q(x)}$ where $Q(x)$ Has Repeated Linear Factors

Some fractions we may come across are special cases that we can decompose into partial fractions with repeated linear factors. We must remember that we account for repeated factors by writing each factor in increasing powers.

## PARTIAL FRACTION DECOMPOSITION OF $\frac{P(x)}{Q(x)}$: $Q(x)$ HAS REPEATED LINEAR FACTORS

The partial fraction decomposition of $\frac{P(x)}{Q(x)}$, when $Q(x)$ has a repeated linear factor occurringn n times and the degree of $P(x)$ is less than the degree of $Q(x)$, is

$$\frac{P(x)}{Q(x)} = \frac{A_1}{(a_1x+b_1)} + \frac{A_2}{(a_2x+b_2)} + \frac{A_3}{(a_3x+b_3)} + \cdots + \frac{A_n}{(a_nx+b_n)} \tag{9.3.2}$$

Write the denominator powers in increasing order.

## How to: decompose a rational expression with repeated linear factors

1. Use a variable like $A$, $B$, or $C$ for the numerators and account for increasing powers of the denominators.

$$\frac{P(x)}{Q(x)} = \frac{A_1}{(a_1x+b_1)} + \frac{A_2}{(a_2x+b_2)} + \frac{A_3}{(a_3x+b_3)} + \cdots + \frac{A_n}{(a_nx+b_n)} \tag{9.3.3}$$

2. Multiply both sides of the equation by the common denominator to eliminate fractions.
3. Expand the right side of the equation and collect like terms.
4. Set coefficients of like terms from the left side of the equation equal to those on the right side to create a system of equations to solve for the numerators.

## Example 9.3.2: Decomposing with Repeated Linear Factors

Decompose the given rational expression with repeated linear factors.

$$\frac{-x^2+2x+4}{x^3-4x^2+4x}$$

### Solution

The denominator factors are $x(x-2)^2$. To allow for the repeated factor of $(x-2)$, the decomposition will include three denominators: $x$, $(x-2)$, and $(x-2)^2$. Thus,

$$\frac{-x^2+2x+4}{x^3-4x^2+4x} = \frac{A}{x} + \frac{B}{(x-2)} + \frac{C}{(x-2)^2}$$

Next, we multiply both sides by the common denominator.

$$x(x-2)^2\left[\frac{-x^2+2x+4}{x(x-2)^2}\right] = \left[\frac{A}{x} + \frac{B}{(x-2)} + \frac{C}{(x-2)^2}\right] x(x-2)^2$$

$$-x^2+2x+4 = A(x-2)^2 + Bx(x-2) + Cx$$

On the right side of the equation, we expand and collect like terms.

$$\begin{aligned} -x^2+2x+4 &= A(x^2-4x+4) + B(x^2-2x) + Cx \\ &= Ax^2 - 4Ax + 4A + Bx^2 - 2Bx + Cx \\ &= (A+B)x^2 + (-4A-2B+C)x + 4A \end{aligned}$$

Next, we compare the coefficients of both sides. This will give the system of equations in three variables:

$$-x^2+2x+4 = (A+B)x^2 + (-4A-2B+C)x + 4A \tag{9.3.4}$$

$$A+B = -1 \tag{9.3.5}$$

$$-4A-2B+C = 2 \tag{9.3.6}$$

$$4A = 4 \tag{9.3.7}$$

Solving for $A$ in Equation 9.3.7, we have

$$\begin{aligned} 4A &= 4 \\ A &= 1 \end{aligned}$$

Substitute $A = 1$ into Equation 9.3.5.

$$\begin{aligned} A + B &= -1 \\ (1) + B &= -1 \\ B &= -2 \end{aligned}$$

Then, to solve for $C$, substitute the values for $A$ and $B$ into Equation 9.3.6.

$$\begin{aligned} -4A - 2B + C &= 2 \\ -4(1) - 2(-2) + C &= 2 \\ -4 + 4 + C &= 2 \\ C &= 2 \end{aligned}$$

Thus,

$$\frac{-x^2 + 2x + 4}{x^3 - 4x^2 + 4x} = \frac{1}{x} - \frac{2}{(x-2)} + \frac{2}{(x-2)^2}$$

**? Exercise 9.3.2**

Find the partial fraction decomposition of the expression with repeated linear factors.

$$\frac{6x - 11}{(x-1)^2}$$

**Answer**

$$\frac{6}{x-1} - \frac{5}{(x-1)^2}$$

## Decomposing $\frac{P(x)}{Q(x)}$, where $Q(x)$ Has a Nonrepeated Irreducible Quadratic Factor

So far, we have performed partial fraction decomposition with expressions that have had linear factors in the denominator, and we applied numerators $A$, $B$, or $C$ representing constants. Now we will look at an example where one of the factors in the denominator is a quadratic expression that does not factor. This is referred to as an irreducible quadratic factor. In cases like this, we use a linear numerator such as $Ax + B$, $Bx + C$, etc.

**DECOMPOSITION OF $\frac{P(x)}{Q(x)}$: $Q(x)$ HAS A NONREPEATED IRREDUCIBLE QUADRATIC FACTOR**

The partial fraction decomposition of $\dfrac{P(x)}{Q(x)}$ such that $Q(x)$ has a nonrepeated irreducible quadratic factor and the degree of $P(x)$ is less than the degree of $Q(x)$ is written as

$$\frac{P(x)}{Q(x)} = \frac{A_1 x + B_1}{(a_1 x^2 + b1_x + c_1)} + \frac{A_2 x + B_2}{(a_2 x^2 + b_2 x + c_2)} + \cdots + \frac{A_n x + B_n}{(a_n x^2 + b_n x + c_n)} \tag{9.3.8}$$

The decomposition may contain more rational expressions if there are linear factors. Each linear factor will have a different constant numerator: $A$, $B$, $C$, and so on.

**Howto: decompose a rational expression where the factors of the denominator are distinct, irreducible quadratic factors**

1. Use variables such as $A$, $B$, or $C$ for the constant numerators over linear factors, and linear expressions such as $A_1x+B_1$, $A_2x+B_2$, etc., for the numerators of each quadratic factor in the denominator.

$$\frac{P(x)}{Q(x)}=\frac{A}{ax+b}+\frac{A_1x+B_1}{(a_1x^2+b1_x+c_1)}+\frac{A_2x+B_2}{(a_2x^2+b_2x+c_2)}+\cdots+\frac{A_nx+B_n}{(a_nx^2+b_nx+c_n)}$$

2. Multiply both sides of the equation by the common denominator to eliminate fractions.
3. Expand the right side of the equation and collect like terms.
4. Set coefficients of like terms from the left side of the equation equal to those on the right side to create a system of equations to solve for the numerators.

**Example 9.3.3: Decomposing $\frac{P(x)}{Q(x)}$ When $Q(x)$ Contains a Nonrepeated Irreducible Quadratic Factor**

Find a partial fraction decomposition of the given expression.

$$\frac{8x^2+12x-20}{(x+3)(x^2+x+2)}$$

**Solution**

We have one linear factor and one irreducible quadratic factor in the denominator, so one numerator will be a constant and the other numerator will be a linear expression. Thus,

$$\frac{8x^2+12x-20}{(x+3)(x^2+x+2)}=\frac{A}{(x+3)}+\frac{Bx+C}{(x^2+x+2)}$$

We follow the same steps as in previous problems. First, clear the fractions by multiplying both sides of the equation by the common denominator.

$$\begin{aligned}(x+3)(x^2+x+2)\left[\frac{8x^2+12x-20}{(x+3)(x^2+x+2)}\right] &= \left[\frac{A}{(x+3)}+\frac{Bx+C}{(x^2+x+2)}\right](x+3)(x^2+x+2)\\ 8x^2+12x-20 &= A(x^2+x+2)+(Bx+C)(x+3)\end{aligned}$$

Notice we could easily solve for $A$ by choosing a value for $x$ that will make the $Bx+C$ term equal 0. Let $x=-3$ and substitute it into the equation.

$$\begin{aligned}8x^2+12x-20 &= A(x^2+x+2)+(Bx+C)(x+3)\\ 8(-3)^2+12(-3)-20 &= A((-3)^2+(-3)+2)+(B(-3)+C)((-3)+3)\\ 16 &= 8A\\ A &= 2\end{aligned}$$

Now that we know the value of $A$, substitute it back into the equation. Then expand the right side and collect like terms.

$$\begin{aligned}8x^2+12x-20 &= 2(x^2+x+2)+(Bx+C)(x+3)\\ 8x^2+12x-20 &= 2x^2+2x+4+Bx^2+3B+Cx+3C\\ 8x^2+12x-20 &= (2+B)x^2+(2+3B+C)x+(4+3C)\end{aligned}$$

Setting the coefficients of terms on the right side equal to the coefficients of terms on the left side gives the system of equations.

$$2+B=8 \tag{9.3.9}$$

$$2+3B+C=12 \tag{9.3.10}$$

$$4+3C=-20 \tag{9.3.11}$$

Solve for $B$ using Equation 9.3.9

\[

$$2+B=8$$
$$B=6$$

and solve for $C$ using Equation 9.3.11.

$$4+3C=-20$$
$$3C=-24$$
$$C=-8$$

Thus, the partial fraction decomposition of the expression is

$$\frac{8x^2+12x-20}{(x+3)(x^2+x+2)}=\frac{2}{(x+3)}+\frac{6x-8}{(x^2+x+2)}$$

**Q&A: Could we have just set up a system of equations to solve the example above?**

Yes, we could have solved it by setting up a system of equations without solving for $A$ first. The expansion on the right would be:

$$8x^2+12x-20 = Ax^2+Ax+2A+Bx^2+3B+Cx+3C$$
$$8x^2+12x-20 = (A+B)x^2+(A+3B+C)x+(2A+3C)$$

So the system of equations would be:

$$A+B=8$$
$$A+3B+C=12$$
$$2A+3C=-20$$

**? Exercise 9.3.3**

Find the partial fraction decomposition of the expression with a nonrepeating irreducible quadratic factor.

$$\frac{5x^2-6x+7}{(x-1)(x^2+1)}$$

**Answer**

$$\frac{3}{x-1}+\frac{2x-4}{x^2+1}$$

## Decomposing $\frac{P(x)}{Q(x)}$ When $Q(x)$ Has a Repeated Irreducible Quadratic Factor

Now that we can decompose a simplified rational expression with an irreducible quadratic factor, we will learn how to do partial fraction decomposition when the simplified rational expression has repeated irreducible quadratic factors. The decomposition will consist of partial fractions with linear numerators over each irreducible quadratic factor represented in increasing powers.

**DECOMPOSITION OF $\frac{P(x)}{Q(x)}$ WHEN $Q(X)$ HAS A REPEATED IRREDUCIBLE QUADRATIC FACTOR**

The partial fraction decomposition of $\frac{P(x)}{Q(x)}$, when $Q(x)$ has a repeated irreducible quadratic factor and the degree of $P(x)$ is less than the degree of $Q(x)$, is

$$\frac{P(x)}{(ax^2+bx+c)^n}=\frac{A_1x+B_1}{(ax^2+bx+c)}+\frac{A_2x+B_2}{(ax^2+bx+c)^2}+\frac{A_3x+B_3}{(ax^2+bx+c)^3}+\cdots+\frac{A_nx+B_n}{(ax^2+bx+c)^n} \quad (9.3.12)$$

Write the denominators in increasing powers.

**How to: decompose a rational expression that has a repeated irreducible factor**

1. Use variables like $A$, $B$, or $C$ for the constant numerators over linear factors, and linear expressions such as $A_1x+B_1$, $A_2x+B_2$, etc., for the numerators of each quadratic factor in the denominator written in increasing powers, such as
$$\frac{P(x)}{Q(x)}=\frac{A}{ax+b}+\frac{A_1x+B_1}{(ax^2+bx+c)}+\frac{A_2x+B_2}{(ax^2+bx+c)^2}+\cdots+\frac{A_nx+B_n}{(ax^2+bx+c)^n}$$
2. Multiply both sides of the equation by the common denominator to eliminate fractions.
3. Expand the right side of the equation and collect like terms.
4. Set coefficients of like terms from the left side of the equation equal to those on the right side to create a system of equations to solve for the numerators.

**Example 9.3.4: Decomposing a Rational Function with a Repeated Irreducible Quadratic Factor in the Denominator**

Decompose the given expression that has a repeated irreducible factor in the denominator.
$$\frac{x^4+x^3+x^2-x+1}{x(x^2+1)^2}$$

**Solution**

The factors of the denominator are $x$, $(x^2+1)$, and $(x^2+1)^2$. Recall that, when a factor in the denominator is a quadratic that includes at least two terms, the numerator must be of the linear form $Ax+B$. So, let's begin the decomposition.
$$\frac{x^4+x^3+x^2-x+1}{x(x^2+1)^2}=\frac{A}{x}+\frac{Bx+C}{(x^2+1)}+\frac{Dx+E}{(x^2+1)^2}$$

We eliminate the denominators by multiplying each term by $x(x^2+1)^2$. Thus,
$$\begin{aligned} x^4+x^3+x^2-x+1 &= A(x^2+1)^2+(Bx+C)(x)(x^2+1)+(Dx+E)(x) \\ x^4+x^3+x^2-x+1 &= A(x^4+2x^2+1)+Bx^4+Bx^2+Cx^3+Cx+Dx^2+Ex \qquad \text{Expand the right side.} \\ &= Ax^4+2Ax^2+A+Bx^4+Bx^2+Cx^3+Cx+Dx^2+Ex \end{aligned}$$

Now we will collect like terms.
$$x^4+x^3+x^2-x+1=(A+B)x^4+(C)x^3+(2A+B+D)x^2+(C+E)x+A$$

Set up the system of equations matching corresponding coefficients on each side of the equal sign.
$$\begin{aligned} A+B &= 1 \\ C &= 1 \\ 2A+B+D &= 1 \\ C+E &= -1 \\ A &= 1 \end{aligned}$$

We can use substitution from this point. Substitute $A=1$ into the first equation.
$$\begin{aligned} 1+B &= 1 \\ B &= 0 \end{aligned}$$

Substitute $A=1$ and $B=0$ into the third equation.
$$\begin{aligned} 2(1)+0+D &= 1 \\ D &= -1 \end{aligned}$$

Substitute $C = 1$ into the fourth equation.

$$1 + E = -1$$
$$E = -2$$

Now we have solved for all of the unknowns on the right side of the equal sign. We have $A = 1$, $B = 0$, $C = 1$, $D = -1$, and $E = -2$. We can write the decomposition as follows:

$$\frac{x^4 + x^3 + x^2 - x + 1}{x(x^2+1)^2} = \frac{1}{x} + \frac{1}{(x^2+1)} - \frac{x+2}{(x^2+1)^2}$$

**Exercise 9.3.4**

Find the partial fraction decomposition of the expression with a repeated irreducible quadratic factor.

$$\frac{x^3 - 4x^2 + 9x - 5}{(x^2 - 2x + 3)^2}$$

**Answer**

$$\frac{x-2}{x^2-2x+3} + \frac{2x+1}{(x^2-2x+3)^2}$$

**Media**

Access these online resources for additional instruction and practice with partial fractions.

- Partial Fraction Decomposition
- Partial Fraction Decomposition With Repeated Linear Factors
- Partial Fraction Decomposition With Linear and Quadratic Factors

## Key Concepts

- Decompose $\frac{P(x)}{Q(x)}$ by writing the partial fractions as

  $$\frac{A}{a_1 x + b_1} + \frac{B}{a_2 x + b_2}.$$

  Solve by clearing the fractions, expanding the right side, collecting like terms, and setting corresponding coefficients equal to each other, then setting up and solving a system of equations (see Example 9.3.1).
- The decomposition of $\frac{P(x)}{Q(x)}$ with repeated linear factors must account for the factors of the denominator in increasing powers (see Example 9.3.2).
- The decomposition of $\frac{P(x)}{Q(x)}$ with a nonrepeated irreducible quadratic factor needs a linear numerator over the quadratic factor, as in $\frac{A}{x} + \frac{Bx + C}{(ax^2 + bx + c)}$ (see Example 9.3.3).
- In the decomposition of $\frac{P(x)}{Q(x)}$, where $Q(x)$ has a repeated irreducible quadratic factor, when the irreducible quadratic factors are repeated, powers of the denominator factors must be represented in increasing powers as

  $$\frac{A_1 x + B_1}{ax^2 + bx + c} + \frac{A_2 x + B_2}{(ax^2 + bx + c)^2} + \cdots + \frac{A_n x + B_n}{(ax^2 + bx + c)^n}$$

  See Example 9.3.4.

This page titled 9.3: Partial Fractions is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.4: Partial Fractions** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.3.1: Partial Fractions (Exercises)

For the following exercises, decompose into partial fractions.

31. $\frac{-2x+6}{x^2+3x+2}$
32. $\frac{10x+2}{4x^2+4x+1}$
33. $\frac{7x+20}{x^2+10x+25}\backslash$
34. $\frac{x-18}{x^2-12x+36}$
35. $\frac{-x^2+36x+70}{x^3-125}$
36. $\frac{-5x^2+6x-2}{x^3+27}$
37. $\frac{x^3-4x^2+3x+11}{(x^2-2)^2}$
38. $\frac{4x^4-2x^3+22x^2-6x+48}{x(x^2+4)^2}$

This page titled 9.3.1: Partial Fractions (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.4E: Partial Fractions (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.4: Matrices and Matrix Operations

**Learning Objectives**

- Find the sum and difference of two matrices.
- Find scalar multiples of a matrix.
- Find the product of two matrices.

Two club soccer teams, the Wildcats and the Mud Cats, are hoping to obtain new equipment for an upcoming season. Table 9.4.1 shows the needs of both teams.

Table 9.4.1

| | Wildcats | Mud Cats |
|---|---|---|
| Goals | 6 | 10 |
| Balls | 30 | 24 |
| Jerseys | 14 | 20 |

A goal costs $300; a ball costs $10; and a jersey costs $30. How can we find the total cost for the equipment needed for each team? In this section, we discover a method in which the data in the soccer equipment table can be displayed and used for calculating other information. Then, we will be able to calculate the cost of the equipment.



Figure 9.4.1

## Finding the Sum and Difference of Two Matrices

To solve a problem like the one described for the soccer teams, we can use a matrix, which is a rectangular array of numbers. A row in a matrix is a set of numbers that are aligned horizontally. A column in a matrix is a set of numbers that are aligned vertically. Each number is an entry, sometimes called an element, of the matrix. Matrices (plural) are enclosed in [ ] or ( ), and are usually named with capital letters. For example, three matrices named $A$, $B$, and $C$ are shown below.

$$A = \begin{bmatrix} 1 & 2 \\ 3 & 4 \end{bmatrix}$$

$$B = \begin{bmatrix} 1 & 2 & 7 \\ 0 & -5 & 6 \\ 7 & 8 & 2 \end{bmatrix}$$

$$C = \begin{bmatrix} -1 & 3 \\ 0 & 2 \\ 3 & 1 \end{bmatrix}$$

A matrix is often referred to by its size or dimensions: $m \times n$ indicating $m$ rows and $n$ columns. Matrix entries are defined first by row and then by column. For example, to locate the entry in matrix $A$ identified as $a_{ij}$,we look for the entry in row $i$,column $j$. In matrix $A$, shown below, the entry in row 2, column 3 is $a_{23}$.

$$A = \begin{bmatrix} a_{11} & a_{12} & a_{13} \\ a_{21} & a_{22} & a_{23} \\ a_{31} & a_{32} & a_{33} \end{bmatrix}$$

- A **square matrix** is a matrix with dimensions $n \times n$, meaning that it has the same number of rows as columns. The $3 \times 3$ matrix above is an example of a square matrix.
- A **row matrix** is a matrix consisting of one row with dimensions $1 \times n$.

$$\begin{bmatrix} a_{11} & a_{12} & a_{13} \end{bmatrix}$$

- A **column matrix** is a matrix consisting of one column with dimensions $m \times 1$.

$$\begin{bmatrix} a_{11} \\ a_{21} \\ a_{31} \end{bmatrix}$$

A matrix may be used to represent a system of equations. In these cases, the numbers represent the coefficients of the variables in the system. Matrices often make solving systems of equations easier because they are not encumbered with variables. We will investigate this idea further in the next section, but first we will look at basic **matrix operations**.

**Definition: MATRICES**

A *matrix* is a rectangular array of numbers that is usually named by a capital letter: $A$, $B$, $C$,and so on. Each entry in a matrix is referred to as $a_{ij}$,such that $i$ represents the row and $j$ represents the column. Matrices are often referred to by their dimensions: $m \times n$ indicating $m$ rows and $n$ columns.

**Example 9.4.1: Finding the Dimensions of the Given Matrix and Locating Entries**

Given matrix $A$:

a. What are the dimensions of matrix $A$?
b. What are the entries at $a_{31}$ and $a_{22}$?

$$A = \begin{bmatrix} 2 & 1 & 0 \\ 2 & 4 & 7 \\ 3 & 1 & -2 \end{bmatrix}$$

**Solution**

a. The dimensions are $3 \times 3$ because there are three rows and three columns.
b. Entry $a_{31}$ is the number at row 3, column 1, which is 3. The entry $a_{22}$ is the number at row 2, column 2, which is 4. Remember, the row comes first, then the column.

### Adding and Subtracting Matrices

We use matrices to list data or to represent systems. Because the entries are numbers, we can perform operations on matrices. We add or subtract matrices by adding or subtracting corresponding entries. To do this, the entries must correspond. Therefore, *addition and subtraction of matrices is only possible when the matrices have the same dimensions*. We can add or subtract a $3 \times 3$ matrix and another $3 \times 3$ matrix, but we cannot add or subtract a $2 \times 3$ matrix and a $3 \times 3$ matrix because some entries in one matrix will not have a corresponding entry in the other matrix.

**ADDING AND SUBTRACTING MATRICES**

Given matrices $A$ and $B$ of like dimensions, addition and subtraction of $A$ and $B$ will produce matrix $C$ or matrix $D$ of the same dimension.

$$A+B=C \tag{9.4.1}$$

such that $a_{ij}+b_{ij}=c_{ij}$

$$A-B=D \tag{9.4.2}$$

such that $a_{ij}-b_{ij}=d_{ij}$

Matrix addition is *commutative*.

$$A+B=B+A \tag{9.4.3}$$

It is also *associative*.

$$(A+B)+C=A+(B+C) \tag{9.4.4}$$

### Example 9.4.2A: Finding the Sum of Matrices

Find the sum of $A$ and $B$, given

$$A=\begin{bmatrix} a & b \\ c & d \end{bmatrix}$$

and

$$B=\begin{bmatrix} e & f \\ g & h \end{bmatrix}$$

**Solution**

Add corresponding entries.

$$\begin{aligned} A+B &= \begin{bmatrix} a & b \\ c & d \end{bmatrix}+\begin{bmatrix} e & f \\ g & h \end{bmatrix} \\ &= \begin{bmatrix} a+e & b+f \\ c+g & d+h \end{bmatrix} \end{aligned}$$

### Example 9.4.2B: Adding Matrix $A$ and Matrix $B$

Find the sum of $A$ and $B$.

$$A=\begin{bmatrix} 4 & 1 \\ 3 & 2 \end{bmatrix}$$

and

$$B=\begin{bmatrix} 5 & 9 \\ 0 & 7 \end{bmatrix}$$

**Solution**

Add corresponding entries. Add the entry in row 1, column 1, $a_{11}$, of matrix $A$ to the entry in row 1, column 1, $b_{11}$, of $B$. Continue the pattern until all entries have been added.

$$\begin{aligned} A+B &= \begin{bmatrix} 4 & 1 \\ 3 & 2 \end{bmatrix}+\begin{bmatrix} 5 & 9 \\ 0 & 7 \end{bmatrix} \\ &= \begin{bmatrix} 4+5 & 1+9 \\ 3+0 & 2+7 \end{bmatrix} \\ &= \begin{bmatrix} 9 & 10 \\ 3 & 9 \end{bmatrix} \end{aligned}$$

### Example 9.4.2C: Finding the Difference of Two Matrices

Find the difference of $A$ and $B$.

$$A=\begin{bmatrix}-2 & 3\\ 0 & 1\end{bmatrix} \text{ and } B=\begin{bmatrix}8 & 1\\ 5 & 4\end{bmatrix}$$

**Solution**

We subtract the corresponding entries of each matrix.

$$\begin{aligned} A-B &= \begin{bmatrix}-2 & 3\\ 0 & 1\end{bmatrix}-\begin{bmatrix}8 & 1\\ 5 & 4\end{bmatrix}\\ &= \begin{bmatrix}-2-8 & 3-1\\ 0-5 & 1-4\end{bmatrix}\\ &= \begin{bmatrix}-10 & 2\\ -5 & -3\end{bmatrix}\end{aligned}$$

### Example 9.4.2D: Finding the Sum and Difference of Two 3 x 3 Matrices

Given $A$ and $B$:

a. Find the sum.
b. Find the difference.

$$A=\begin{bmatrix}2 & -10 & -2\\ 14 & 12 & 10\\ 4 & -2 & 2\end{bmatrix}$$

and

$$B=\begin{bmatrix}6 & 10 & -2\\ 0 & -12 & -4\\ -5 & 2 & -2\end{bmatrix}$$

**Solution**

a. Add the corresponding entries.

$$\begin{aligned} A+B &= \begin{bmatrix}2 & -10 & -2\\ 14 & 12 & 10\\ 4 & -2 & 2\end{bmatrix}+\begin{bmatrix}6 & 10 & -2\\ 0 & -12 & -4\\ -5 & 2 & -2\end{bmatrix}\\ &= \begin{bmatrix}2+6 & -10+10 & -2-2\\ 14+0 & 12-12 & 10-4\\ 4-5 & -2+2 & 2-2\end{bmatrix}\\ &= \begin{bmatrix}8 & 0 & -4\\ 14 & 0 & 6\\ -1 & 0 & 0\end{bmatrix}\end{aligned}$$

b. Subtract the corresponding entries.

$$A-B=\begin{bmatrix}2&-10&-2\\14&12&10\\4&-2&2\end{bmatrix}-\begin{bmatrix}6&10&-2\\0&-12&-4\\-5&2&-2\end{bmatrix}$$
$$=\begin{bmatrix}2-6&-10-10&-2+2\\14-0&12+12&10+4\\4+5&-2-2&2+2\end{bmatrix}$$
$$=\begin{bmatrix}-4&-20&0\\14&24&14\\9&-4&4\end{bmatrix}$$

**? Exercise 9.4.1**

Add matrix $A$ and matrix $B$.

$$A=\begin{bmatrix}2&6\\1&0\\1&-3\end{bmatrix}$$

and

$$B=\begin{bmatrix}3&-2\\1&5\\-4&3\end{bmatrix}$$

**Answer**

$$A+B=\begin{bmatrix}2&6\\1&0\\1&-3\end{bmatrix}+\begin{bmatrix}3&-2\\1&5\\-4&3\end{bmatrix}$$
$$=\begin{bmatrix}2+3&6+(-2)\\1+1&0+5\\1+(-4)&-3+3\end{bmatrix}$$
$$=\begin{bmatrix}5&4\\2&5\\-3&0\end{bmatrix}$$

## Finding Scalar Multiples of a Matrix

Besides adding and subtracting whole matrices, there are many situations in which we need to multiply a matrix by a constant called a scalar. Recall that a scalar is a real number quantity that has magnitude, but not direction. For example, time, temperature, and distance are scalar quantities. The process of scalar multiplication involves multiplying each entry in a matrix by a scalar. A scalar multiple is any entry of a matrix that results from scalar multiplication.

Consider a real-world scenario in which a university needs to add to its inventory of computers, computer tables, and chairs in two of the campus labs due to increased enrollment. They estimate that 15 more equipment is needed in both labs. The school's current inventory is displayed in Table 9.4.2.

Table 9.4.2

| | Lab A | Lab B |
|---|---|---|
| **Computers** | 15 | 27 |
| **Computer Tables** | 16 | 34 |
| **Chairs** | 16 | 34 |

Converting the data to a matrix, we have

$$C_{2013} = \begin{bmatrix} 15 & 27 \\ 16 & 34 \\ 16 & 34 \end{bmatrix}$$

To calculate how much computer equipment will be needed, we multiply all entries in matrix $C$ by $0.15$.

$$(0.15)C_{2013} = \begin{bmatrix} (0.15)15 & (0.15)27 \\ (0.15)16 & (0.15)34 \\ (0.15)16 & (0.15)34 \end{bmatrix} = \begin{bmatrix} 2.25 & 4.05 \\ 2.4 & 5.1 \\ 2.4 & 5.1 \end{bmatrix}$$

We must round up to the next integer, so the amount of new equipment needed is

$$\begin{bmatrix} 3 & 5 \\ 3 & 6 \\ 3 & 6 \end{bmatrix}$$

Adding the two matrices as shown below, we see the new inventory amounts.

$$\begin{bmatrix} 15 & 27 \\ 16 & 34 \\ 16 & 34 \end{bmatrix} + \begin{bmatrix} 3 & 5 \\ 3 & 6 \\ 3 & 6 \end{bmatrix} = \begin{bmatrix} 18 & 32 \\ 19 & 40 \\ 19 & 40 \end{bmatrix}$$

This means

$$C_{2014} = \begin{bmatrix} 18 & 32 \\ 19 & 40 \\ 19 & 40 \end{bmatrix}$$

Thus, Lab A will have 18 computers, 19 computer tables, and 19 chairs; Lab B will have 32 computers, 40 computer tables, and 40 chairs.

### SCALAR MULTIPLICATION

Scalar multiplication involves finding the product of a constant by each entry in the matrix. Given

$$A = \begin{bmatrix} a_{11} & a_{12} \\ a_{21} & a_{22} \end{bmatrix}$$

the scalar multiple $cA$ is

$$cA = c\begin{bmatrix} a_{11} & a_{12} \\ a_{21} & a_{22} \end{bmatrix}$$
$$= \begin{bmatrix} ca_{11} & ca_{12} \\ ca_{21} & ca_{22} \end{bmatrix}$$

Scalar multiplication is distributive. For the matrices $A$, $B$,and $C$ with scalars $a$ and $b$,

$$a(A+B) = aA + aB \tag{9.4.5}$$
$$(a+b)A = aA + bA \tag{9.4.6}$$

### Example 9.4.3: Multiplying the Matrix by a Scalar

Multiply matrix $A$ by the scalar $3$.

$$A = \begin{bmatrix} 8 & 1 \\ 5 & 4 \end{bmatrix}$$

**Solution**

Multiply each entry in $A$ by the scalar 3.

$$\begin{aligned} 3A &= 3\begin{bmatrix} 8 & 1 \\ 5 & 4 \end{bmatrix} \\ &= \begin{bmatrix} 3\cdot 8 & 3\cdot 1 \\ 3\cdot 5 & 3\cdot 4 \end{bmatrix} \\ &= \begin{bmatrix} 24 & 3 \\ 15 & 12 \end{bmatrix} \end{aligned}$$

**Exercise 9.4.2**

Given matrix $B$, find $-2B$ where

$$B = \begin{bmatrix} 4 & 1 \\ 3 & 2 \end{bmatrix}$$

**Answer**

$$-2B = \begin{bmatrix} -8 & -2 \\ -6 & -4 \end{bmatrix}$$

**Example 9.4.4: Finding the Sum of Scalar Multiples**

Find the sum $3A + 2B$.

$$A = \begin{bmatrix} 1 & -2 & 0 \\ 0 & -1 & 2 \\ 4 & 3 & -6 \end{bmatrix}$$

and

$$B = \begin{bmatrix} -1 & 2 & 1 \\ 0 & -3 & 2 \\ 0 & 1 & -4 \end{bmatrix}$$

**Solution**

First, find $3A$, then $2B$.

$$\begin{aligned} 3A &= \begin{bmatrix} 3\cdot 1 & 3(-2) & 3\cdot 0 \\ 3\cdot 0 & 3(-1) & 3\cdot 2 \\ 3\cdot 4 & 3\cdot 3 & 3(-6) \end{bmatrix} \\ &= \begin{bmatrix} 3 & -6 & 0 \\ 0 & -3 & 6 \\ 12 & 9 & -18 \end{bmatrix} \end{aligned}$$

$$\begin{aligned} 2B &= \begin{bmatrix} 2(-1) & 2\cdot 2 & 2\cdot 1 \\ 2\cdot 0 & 2(-3) & 2\cdot 2 \\ 2\cdot 0 & 2\cdot 1 & 2(-4) \end{bmatrix} \\ &= \begin{bmatrix} -2 & 4 & 2 \\ 0 & -6 & 4 \\ 0 & 2 & -8 \end{bmatrix} \end{aligned}$$

Now, add $3A + 2B$.

$$3A+2B=\begin{bmatrix}3&-6&0\\0&-3&6\\12&9&-18\end{bmatrix}+\begin{bmatrix}-2&4&2\\0&-6&4\\0&2&-8\end{bmatrix}$$
$$=\begin{bmatrix}3-2&-6+4&0+2\\0+0&-3-6&6+4\\12+0&9+2&-18-8\end{bmatrix}$$
$$=\begin{bmatrix}1&-2&2\\0&-9&10\\12&11&-26\end{bmatrix}$$

## Finding the Product of Two Matrices

In addition to multiplying a matrix by a scalar, we can multiply two matrices. Finding the product of two matrices is only possible when the inner dimensions are the same, meaning that the number of columns of the first matrix is equal to the number of rows of the second matrix. If $A$ is an $m\times r$ matrix and $B$ is an $r\times n$ matrix, then the product matrix $AB$ is an $m\times n$ matrix. For example, the product $AB$ is possible because the number of columns in $A$ is the same as the number of rows in $B$. If the inner dimensions do not match, the product is not defined.

$$\underset{2\times 3}{A}\quad\cdot\quad\underbrace{\underset{3\times 3}{B}}_{\text{same}}$$

We multiply entries of $A$ with entries of $B$ according to a specific pattern as outlined below. The process of **matrix multiplication** becomes clearer when working a problem with real numbers.

To obtain the entries in row $i$ of $AB$, we multiply the entries in row $i$ of $A$ by column $j$ in $B$ and add. For example, given matrices $A$ and $B$, where the dimensions of $A$ are $2\times 3$ and the dimensions of $B$ are $3\times 3$ ,the product of $AB$ will be a $2\times 3$ matrix.

$$A=\begin{bmatrix}a_{11}&a_{12}&a_{13}\\a_{21}&a_{22}&a_{23}\end{bmatrix}$$

and

$$B=\begin{bmatrix}b_{11}&b_{12}&b_{13}\\b_{21}&b_{22}&b_{23}\\b_{31}&b_{32}&b_{33}\end{bmatrix}$$

Multiply and add as follows to obtain the first entry of the product matrix $AB$.

1. To obtain the entry in row 1, column 1 of $AB$,multiply the first row in $A$ by the first column in $B$,and add.

$$\begin{bmatrix}a_{11}&a_{12}&a_{13}\end{bmatrix}\cdot\begin{bmatrix}b_{11}\\b_{21}\\b_{31}\end{bmatrix}=a_{11}\cdot b_{11}+a_{12}\cdot b_{21}+a_{13}\cdot b_{31}$$

2. To obtain the entry in row 1, column 2 of $AB$,multiply the first row of $A$ by the second column in $B$,and add.

$$\begin{bmatrix}a_{11}&a_{12}&a_{13}\end{bmatrix}\cdot\begin{bmatrix}b_{12}\\b_{22}\\b_{32}\end{bmatrix}=a_{11}\cdot b_{12}+a_{12}\cdot b_{22}+a_{13}\cdot b_{32}$$

3. To obtain the entry in row 1, column 3 of $AB$,multiply the first row of $A$ by the third column in $B$,and add.

$$\begin{bmatrix}a_{11}&a_{12}&a_{13}\end{bmatrix}\cdot\begin{bmatrix}b_{13}\\b_{23}\\b_{33}\end{bmatrix}=a_{11}\cdot b_{13}+a_{12}\cdot b_{23}+a_{13}\cdot b_{33}$$

We proceed the same way to obtain the second row of $AB$. In other words, row 2 of $A$ times column 1 of $B$; row 2 of $A$ times column 2 of $B$; row 2 of $A$ times column 3 of $B$. When complete, the product matrix will be

$$AB = \begin{bmatrix} a_{11} \cdot b_{11} + a_{12} \cdot b_{21} + a_{13} \cdot b_{31} & a_{11} \cdot b_{12} + a_{12} \cdot b_{22} + a_{13} \cdot b_{32} & a_{11} \cdot b_{13} + a_{12} \cdot b_{23} + a_{13} \cdot b_{33} \\ a_{21} \cdot b_{11} + a_{22} \cdot b_{21} + a_{23} \cdot b_{31} & a_{21} \cdot b_{12} + a_{22} \cdot b_{22} + a_{23} \cdot b_{32} & a_{21} \cdot b_{13} + a_{22} \cdot b_{23} + a_{23} \cdot b_{33} \end{bmatrix}$$

## PROPERTIES OF MATRIX MULTIPLICATION

For the matrice $A$, $B$,and $C$ the following properties hold.

- Matrix multiplication is *associative*:

$$(AB)C = A(BC). \tag{9.4.7}$$

- Matrix multiplication is *distributive*:

$$C(A+B) = CA + CB \tag{9.4.8}$$

$$(A+B)C = AC + BC. \tag{9.4.9}$$

Note that matrix multiplication is not commutative.

## Example 9.4.5A: Multiplying Two Matrices

Multiply matrix $A$ and matrix $B$.

$$A = \begin{bmatrix} 1 & 2 \\ 3 & 4 \end{bmatrix}$$

and

$$B = \begin{bmatrix} 5 & 6 \\ 7 & 8 \end{bmatrix}$$

**Solution**

First, we check the dimensions of the matrices. Matrix $A$ has dimensions $2 \times 2$ and matrix $B$ has dimensions $2 \times 2$. The inner dimensions are the same so we can perform the multiplication. The product will have the dimensions $2 \times 2$.

We perform the operations outlined previously.

$$\begin{aligned} AB &= \begin{bmatrix} 1 & 2 \\ 3 & 4 \end{bmatrix} \cdot \begin{bmatrix} 5 & 6 \\ 7 & 8 \end{bmatrix} \\ &= \begin{bmatrix} 1(5) + 2(7) & 1(6) + 2(8) \\ 3(5) + 4(7) & 3(6) + 4(8) \end{bmatrix} \\ &= \begin{bmatrix} 19 & 22 \\ 43 & 50 \end{bmatrix} \end{aligned}$$

## Example 9.4.5B: Multiplying Two Matrices

Given $A$ and $B$:

a. Find $AB$.
b. Find $BA$.

$$A = \begin{bmatrix} -1 & 2 & 3 \\ 4 & 0 & 5 \end{bmatrix}$$

and

$$B = \begin{bmatrix} 5 & -1 \\ -4 & 0 \\ 2 & 3 \end{bmatrix}$$

**Solution**

a. As the dimensions of $A$ are $2 \times 3$ and the dimensions of $B$ are $3 \times 2$,these matrices can be multiplied together because the number of columns in $A$ matches the number of rows in $B$. The resulting product will be a $2 \times 2$ matrix, the number of rows in $A$ by the number of columns in $B$.

$$\begin{aligned} AB &= \begin{bmatrix} -1 & 2 & 3 \\ 4 & 0 & 5 \end{bmatrix} \begin{bmatrix} 5 & -1 \\ -4 & 0 \\ 2 & 3 \end{bmatrix} \\ &= \begin{bmatrix} -1(5)+2(-4)+3(2) & -1(-1)+2(0)+3(3) \\ 4(5)+0(-4)+5(2) & 4(-1)+0(0)+5(3) \end{bmatrix} \\ &= \begin{bmatrix} -7 & 10 \\ 30 & 11 \end{bmatrix} \end{aligned}$$

b. The dimensions of $B$ are $3 \times 2$ and the dimensions of $A$ are $2 \times 3$. The inner dimensions match so the product is defined and will be a $3 \times 3$ matrix.

$$\begin{aligned} BA &= \begin{bmatrix} 5 & -1 \\ -4 & 0 \\ 2 & 3 \end{bmatrix} \begin{bmatrix} -1 & 2 & 3 \\ 4 & 0 & 5 \end{bmatrix} \\ &= \begin{bmatrix} 5(-1)+-1(4) & 5(2)+-1(0) & 5(3)+-1(5) \\ -4(-1)+0(4) & -4(2)+0(0) & -4(3)+0(5) \\ 2(-1)+3(4) & 2(2)+3(0) & 2(3)+3(5) \end{bmatrix} \\ &= \begin{bmatrix} -9 & 10 & 10 \\ 4 & -8 & -12 \\ 10 & 4 & 21 \end{bmatrix} \end{aligned}$$

**Analysis**

Notice that the products $AB$ and $BA$ are not equal.

$$AB = \begin{bmatrix} -7 & 10 \\ 30 & 11 \end{bmatrix} \neq \begin{bmatrix} -9 & 10 & 10 \\ 4 & -8 & -12 \\ 10 & 4 & 21 \end{bmatrix} = BA$$

This illustrates the fact that matrix multiplication is **not** commutative.

**Q&A: Is it possible for AB to be defined but not BA?**

*Yes, consider a matrix $A$ with dimension $3 \times 4$ and matrix $B$ with dimension $4 \times 2$. For the product $AB$ the inner dimensions are $4$ and the product is defined, but for the product $BA$ the inner dimensions are $2$ and $3$ so the product is undefined.*

**Example 9.4.6: Using Matrices in Real-World Problems**

Let's return to the problem presented at the opening of this section. We have Table 9.4.3, representing the equipment needs of two soccer teams.

Table 9.4.3

| | Wildcats | Mud Cats |
|---|---|---|
| **Goals** | 6 | 10 |

| | Wildcats | Mud Cats |
|---|---|---|
| **Balls** | 30 | 24 |
| **Jerseys** | 14 | 20 |

We are also given the prices of the equipment, as shown in Table 9.4.4.

Table 9.4.4

| | |
|---|---|
| **Goal** | $300 |
| **Ball** | $10 |
| **Jersey** | $30 |

We will convert the data to matrices. Thus, the equipment need matrix is written as

$$E = \begin{bmatrix} 6 & 10 \\ 30 & 24 \\ 14 & 20 \end{bmatrix}$$

The cost matrix is written as

$$C = [300 \quad 10 \quad 30]$$

We perform matrix multiplication to obtain costs for the equipment.

$$\begin{aligned} CE &= [300 \quad 10 \quad 30] \cdot \begin{bmatrix} 6 & 10 \\ 30 & 24 \\ 14 & 20 \end{bmatrix} \\ &= [\,300(6)+10(30)+30(14) \quad 300(10)+10(24)+30(20)\,] \\ &= [2,520 \quad 3,840] \end{aligned}$$

The total cost for equipment for the Wildcats is $\$2,520$, and the total cost for equipment for the Mud Cats is $\$3,840$.

**How to: Given a matrix operation, evaluate using a calculator**

1. Save each matrix as a matrix variable $[A], [B], [C], \ldots$
2. Enter the operation into the calculator, calling up each matrix variable as needed.
3. If the operation is defined, the calculator will present the solution matrix; if the operation is undefined, it will display an error message.

**Example 9.4.7: Using a Calculator to Perform Matrix Operations**

Find $AB - C$ given

$$A = \begin{bmatrix} -15 & 25 & 32 \\ 41 & -7 & -28 \\ 10 & 34 & -2 \end{bmatrix}, B = \begin{bmatrix} 45 & 21 & -37 \\ -24 & 52 & 19 \\ 6 & -48 & -31 \end{bmatrix}, \text{ and } C = \begin{bmatrix} -100 & -89 & -98 \\ 25 & -56 & 74 \\ -67 & 42 & -75 \end{bmatrix}$$

**Solution**

On the matrix page of the calculator, we enter matrix $A$ above as the matrix variable $[A]$, matrix $B$ above as the matrix variable $[B]$, and matrix $C$ above as the matrix variable $[C]$.

On the home screen of the calculator, we type in the problem and call up each matrix variable as needed.

$$[A] \times [B] - [C]$$

The calculator gives us the following matrix.

$$\begin{bmatrix} -983 & -462 & 136 \\ 1,820 & 1,897 & -856 \\ -311 & 2,032 & 413 \end{bmatrix}$$

**Media**

Access these online resources for additional instruction and practice with matrices and matrix operations.

- Dimensions of a Matrix
- Matrix Addition and Subtraction
- Matrix Operations
- Matrix Multiplication

## Key Concepts

- A matrix is a rectangular array of numbers. Entries are arranged in rows and columns.
- The dimensions of a matrix refer to the number of rows and the number of columns. A $3 \times 2$ matrix has three rows and two columns. See Example $9.4.1$.
- We add and subtract matrices of equal dimensions by adding and subtracting corresponding entries of each matrix. See Example $9.4.2$, Example $9.4.3$, Example $9.4.4$, and Example $9.4.5$.
- Scalar multiplication involves multiplying each entry in a matrix by a constant. See Example $9.4.6$.
- Scalar multiplication is often required before addition or subtraction can occur. See Example $9.4.7$.
- Multiplying matrices is possible when inner dimensions are the same—the number of columns in the first matrix must match the number of rows in the second.
- The product of two matrices, $A$ and $B$,is obtained by multiplying each entry in row 1 of $A$ by each entry in column 1 of $B$; then multiply each entry of row 1 of $A$ by each entry in columns 2 of $B$,and so on. See Example $9.4.8$ and Example $9.4.9$.
- Many real-world problems can often be solved using matrices. See Example $9.4.10$.
- We can use a calculator to perform matrix operations after saving each matrix as a matrix variable. See Example $9.4.11$.

This page titled 9.4: Matrices and Matrix Operations is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.5: Matrices and Matrix Operations** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.4E: Matrices and Matrix Operations (Exercises)

For the following exercises, perform the requested operations on the given matrices.

$$A=\begin{bmatrix}4 & -2\\ 1 & 3\end{bmatrix}, B=\begin{bmatrix}6 & 7 & -3\\ 11 & -2 & 4\end{bmatrix}, C=\begin{bmatrix}6 & 7\\ 11 & -2\\ 14 & 0\end{bmatrix}, D=\begin{bmatrix}1 & -4 & 9\\ 10 & 5 & -7\\ 2 & 8 & 5\end{bmatrix}, E=\begin{bmatrix}7 & -14 & 3\\ 2 & -1 & 3\\ 0 & 1 & 9\end{bmatrix} \quad (9.4E.1)$$

39. $-4A$
40. $10D-6E$
41. $B+C$
42. $AB$
43. $BA$
44. $BC$
45. $CB$
46. $DE$
47. $ED$
48. $EC$
49. $CE$
50. $A^3$

This page titled 9.4E: Matrices and Matrix Operations (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.5E: Matrices and Matrix Operations (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.5: Solving Systems with Inverses

**Learning Objectives**

- Find the inverse of a matrix.
- Solve a system of linear equations using an inverse matrix

Nancy plans to invest $\$10,500$ into two different bonds to spread out her risk. The first bond has an annual return of 10, and the second bond has an annual return of 6. To receive an 8.5 return from the two bonds, how much should Nancy invest in each bond? What is the best method to solve this problem? There are several ways we can solve this problem. As we have seen in previous sections, systems of equations and matrices are useful in solving real-world problems involving finance. After studying this section, we will have the tools to solve the bond problem using the inverse of a matrix.

## Finding the Inverse of a Matrix

We know that the multiplicative inverse of a real number $a$ is $a^{-1}$, so

$$aa^{-1} = a^{-1}a = \left(\frac{1}{a}\right)a = 1 \tag{9.5.1}$$

For example, consider the scalar multiplication situation

$$2^{-1} = \frac{1}{2}$$

therefore from Equation 9.5.1

$$\left(\frac{1}{2}\right)2 = 1.$$

The **multiplicative inverse of a matrix** is similar in concept, except that the product of matrix $A$ and its inverse $A^{-1}$ equals the **identity matrix.** The identity matrix is a square matrix containing ones down the main diagonal and zeros everywhere else. We identify identity matrices by $I_n$ where $n$ represents the dimension of the matrix. Equations 9.5.2 and 9.5.3 are the identity matrices for a $2 \times 2$ matrix and a $3 \times 3$ matrix, respectively:

$$I_2 = \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix} \tag{9.5.2}$$

$$I_3 = \begin{bmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 1 \end{bmatrix} \tag{9.5.3}$$

The identity matrix acts as a 1 in matrix algebra. For example,

$$AI = IA = A$$

A matrix that has a multiplicative inverse has the properties

$$AA^{-1} = I \tag{9.5.4}$$

$$A^{-1}A = I \tag{9.5.5}$$

A matrix that has a multiplicative inverse is called an **invertible matrix**. Only a square matrix may have a multiplicative inverse, as the reversibility,

$$AA^{-1} = A^{-1}A = I \tag{9.5.6}$$

is a requirement. Not all square matrices have an inverse, but if $A$ is invertible, then $A^{-1}$ is unique. We will look at two methods for finding the inverse of a $2 \times 2$ matrix and a third method that can be used on both $2 \times 2$ and $3 \times 3$ matrices.

### Definitions: THE IDENTITY MATRIX AND MULTIPLICATIVE INVERSE

The *identity matrix*, $I_n$, is a square matrix containing ones down the main diagonal and zeros everywhere else.

$$I_2 = \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix}$$

as for the $2 \times 2$ identity matrix

$$I_3 = \begin{bmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 1 \end{bmatrix}$$

as for the $3 \times 3$ identity matrix

If $A$ is an $n \times n$ matrix and $B$ is an $n \times n$ matrix such that $AB = BA = I_n$ , then $B = A - 1$ , the **multiplicative inverse of a matrix $A$.**

### Example 9.5.1: Showing That the Identity Matrix Acts as a 1

Given matrix $A$, show that $AI = IA = A$ .

$$A = \begin{bmatrix} 3 & 4 \\ -2 & 5 \end{bmatrix}$$

**Solution**

Use matrix multiplication to show that the product of $A$ and the identity matric is equal to the product of the identity matrix and $A$.

$$\begin{aligned} AI &= \begin{bmatrix} 3 & 4 \\ -2 & 5 \end{bmatrix} \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix} \\ &= \begin{bmatrix} 3 \cdot 1 + 4 \cdot 0 & 3 \cdot 0 + 4 \cdot 1 \\ -2 \cdot 1 + 5 \cdot 0 & -2 \cdot 0 + 5 \cdot 1 \end{bmatrix} \\ &= \begin{bmatrix} 3 & 4 \\ -2 & 5 \end{bmatrix} \end{aligned}$$

$$\begin{aligned} AI &= \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix} \begin{bmatrix} 3 & 4 \\ -2 & 5 \end{bmatrix} \\ &= \begin{bmatrix} 1 \cdot 3 + 0 \cdot (-2) & 1 \cdot 4 + 0 \cdot 5 \\ 0 \cdot 3 + 1 \cdot (-2) & 0 \cdot 4 + 1 \cdot 5 \end{bmatrix} \\ &= \begin{bmatrix} 3 & 4 \\ -2 & 5 \end{bmatrix} \end{aligned}$$

### How to: Given two matrices, show that one is the multiplicative inverse of the other

- Given matrix $A$ of order $n \times n$ and matrix $B$ of order $n \times n$ multiply $AB$.
- If $AB = I$ , then find the product $BA$. If $BA = I$ , then $B = A^{-1}$ and $A = B^{-1}$ .

### Example 9.5.2: Showing That Matrix $A$ Is the Multiplicative Inverse of Matrix $B$

Show that the given matrices are multiplicative inverses of each other.

$$A = \begin{bmatrix} 1 & 5 \\ -2 & -9 \end{bmatrix}$$

and

$$B = \begin{bmatrix} -9 & -5 \\ 2 & 1 \end{bmatrix}$$

**Solution**

Multiply $AB$ and $BA$. If both products equal the identity, then the two matrices are inverses of each other.

$$\begin{aligned} AB &= \begin{bmatrix} 1 & 5 \\ -2 & -9 \end{bmatrix} \cdot \begin{bmatrix} -9 & -5 \\ 2 & 1 \end{bmatrix} \\ &= \begin{bmatrix} 1(-9)+5(2) & 1(-5)+5(1) \\ -2(-9)-9(2) & -2(-5)-9(1) \end{bmatrix} \\ &= \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix} \end{aligned}$$

and

$$\begin{aligned} BA &= \begin{bmatrix} -9 & -5 \\ 2 & 1 \end{bmatrix} \cdot \begin{bmatrix} 1 & 5 \\ -2 & -9 \end{bmatrix} \\ &= \begin{bmatrix} -9(1)-5(-2) & -9(5)-5(-9) \\ 2(1)+1(-2) & 2(-5)+1(-9) \end{bmatrix} \\ &= \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix} \end{aligned}$$

$A$ and $B$ are inverses of each other.

**? Exercise 9.5.1**

Show that the following two matrices are inverses of each other.

$$A = \begin{bmatrix} 1 & 4 \\ -1 & -3 \end{bmatrix}$$

and

$$B = \begin{bmatrix} -3 & -4 \\ 1 & 1 \end{bmatrix}$$

**Answer**

$$\begin{aligned} AB &= \begin{bmatrix} 1 & 4 \\ -1 & -3 \end{bmatrix} \begin{bmatrix} -3 & -4 \\ 1 & 1 \end{bmatrix} \\ &= \begin{bmatrix} 1(-3)+4(1) & 1(-4)+4(1) \\ -1(-3)+-3(1) & -1(-4)+-3(1) \end{bmatrix} \\ &= \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix} \end{aligned}$$

$$\begin{aligned} BA &= \begin{bmatrix} -3 & -4 \\ 1 & 1 \end{bmatrix} \begin{bmatrix} 1 & 4 \\ -1 & -3 \end{bmatrix} \\ &= \begin{bmatrix} -3(1)+-4(-1) & -3(4)+-4(-3) \\ 1(1)+1(-1) & 1(4)+1(-3) \end{bmatrix} \\ &= \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix} \end{aligned}$$

## Finding the Multiplicative Inverse Using Matrix Multiplication

We can now determine whether two matrices are inverses, but how would we find the inverse of a given matrix? Since we know that the product of a matrix and its inverse is the identity matrix, we can find the inverse of a matrix by setting up an equation using **matrix multiplication**.

### Example 9.5.3: Finding the Multiplicative Inverse Using Matrix Multiplication

Use matrix multiplication to find the inverse of the given matrix.

$$A=\begin{bmatrix}1 & -2\\ 2 & -3\end{bmatrix}$$

**Solution**

For this method, we multiply $A$ by a matrix containing unknown constants and set it equal to the identity.

$$\begin{bmatrix}1 & -2\\ 2 & -3\end{bmatrix}\begin{bmatrix}a & b\\ c & d\end{bmatrix}=\begin{bmatrix}1 & 0\\ 0 & 1\end{bmatrix}$$

Find the product of the two matrices on the left side of the equal sign.

$$\begin{bmatrix}1 & -2\\ 2 & -3\end{bmatrix}\begin{bmatrix}a & b\\ c & d\end{bmatrix}=\begin{bmatrix}1a-2c & 1b-2d\\ 2a-3c & 2b-3d\end{bmatrix}$$

Next, set up a system of equations with the entry in row 1, column 1 of the new matrix equal to the first entry of the identity, 1. Set the entry in row 2, column 1 of the new matrix equal to the corresponding entry of the identity, which is 0.

$$1a-2c=1\ R_1$$

$$2a-3c=0\ R_2$$

Using row operations, multiply and add as follows: $(-2)R_1+R_2\rightarrow R_2$ . Add the equations, and solve for $c$.

$$\begin{aligned}1a-2c&=1\\ 0+1c&=-2\\ c&=-2\end{aligned}$$

Back-substitute to solve for $a$.

$$\begin{aligned}a-2(-2)&=1\\ a+4&=1\\ a&=-3\end{aligned}$$

Write another system of equations setting the entry in row 1, column 2 of the new matrix equal to the corresponding entry of the identity, 0. Set the entry in row 2, column 2 equal to the corresponding entry of the identity.

$$1b-2d=0\ R_1$$

$$2b-3d=1\ R_2$$

Using row operations, multiply and add as follows: $(-2)R_1+R_2=R_2$ . Add the two equations and solve for $d$.

$$\begin{aligned}1b-2d&=0\\ 0+1d&=1\\ d&=1\end{aligned}$$

Once more, back-substitute and solve for $b$.

$$b-2(1)=0$$
$$b-2=0$$
$$b=2$$
$$A^{-1}=\begin{bmatrix}-3 & 2\\ -2 & 1\end{bmatrix}$$

## Finding the Multiplicative Inverse by Augmenting with the Identity

Another way to find the **multiplicative inverse** is by augmenting with the identity. When matrix $A$ is transformed into $I$, the augmented matrix $I$ transforms into $A^{-1}$.

For example, given

$$A=\begin{bmatrix}2 & 1\\ 5 & 3\end{bmatrix}$$

augment $A$ with the identity

$$\left[\begin{array}{cc|cc}2 & 1 & 1 & 0\\ 5 & 3 & 0 & 1\end{array}\right]$$

Perform row operations with the goal of turning A into the identity.

1. Switch row 1 and row 2.

$$\left[\begin{array}{cc|cc}5 & 3 & 0 & 1\\ 2 & 1 & 1 & 0\end{array}\right]$$

2. Multiply row 2 by −2 and add to row 1.

$$\left[\begin{array}{cc|cc}1 & 1 & -2 & 1\\ 2 & 1 & 1 & 0\end{array}\right]$$

3. Multiply row 1 by −2 and add to row 2.

$$\left[\begin{array}{cc|cc}1 & 1 & -2 & 1\\ 0 & -1 & 5 & -2\end{array}\right]$$

4. Add row 2 to row 1.

$$\left[\begin{array}{cc|cc}1 & 0 & 3 & -1\\ 0 & -1 & 5 & -2\end{array}\right]$$

5. Multiply row 2 by−1. −1.

$$\left[\begin{array}{cc|cc}1 & 0 & 3 & -1\\ 0 & 1 & -5 & 2\end{array}\right]$$

The matrix we have found is $A^{-1}$.

$$A^{-1}=\begin{bmatrix}3 & -1\\ -5 & 2\end{bmatrix}$$

## Finding the Multiplicative Inverse of $2\times 2$ Matrices Using a Formula

When we need to find the **multiplicative inverse** of a $2\times 2$ matrix, we can use a special formula instead of using matrix multiplication or augmenting with the identity.

If $A$ is a $2\times 2$ matrix, such as

$$A = \begin{bmatrix} a & b \\ c & d \end{bmatrix}$$

the multiplicative inverse of $A$ is given by the formula

$$A^{-1} = \frac{1}{ad - bc} \begin{bmatrix} d & -b \\ -c & a \end{bmatrix}$$

where $ad - bc \neq 0$ . If $ad - bc = 0$ , then $A$ has no inverse.

### Example 9.5.4: Using the Formula to Find the Multiplicative Inverse of Matrix $A$

Use the formula to find the multiplicative inverse of

$$A = \begin{bmatrix} 1 & -2 \\ 2 & -3 \end{bmatrix}$$

**Solution**

We can check that our formula works by using one of the other methods to calculate the inverse. Let's augment $A$ with the identity.

$$\left[\begin{array}{cc|cc} 1 & -2 & 1 & 0 \\ 2 & -3 & 0 & 1 \end{array}\right]$$

Perform row operations with the goal of turning $A$ into the identity.

1. Multiply row 1 by $-2$ and add to row 2.

$$\left[\begin{array}{cc|cc} 1 & -2 & 1 & 0 \\ 0 & 1 & -2 & 1 \end{array}\right]$$

2. Multiply row 1 by 2 and add to row 1.

$$\left[\begin{array}{cc|cc} 1 & 0 & -3 & 2 \\ 0 & 1 & -2 & 1 \end{array}\right]$$

So, we have verified our original solution.

$$A^{-1} = \begin{bmatrix} -3 & 2 \\ -2 & 1 \end{bmatrix}$$

### Exercise 9.5.2

Use the formula to find the inverse of matrix $A$. Verify your answer by augmenting with the identity matrix.

$$A = \begin{bmatrix} 1 & -1 \\ 2 & 3 \end{bmatrix}$$

**Answer**

$$A^{-1} = \begin{bmatrix} \frac{3}{5} & \frac{1}{5} \\ -\frac{2}{5} & \frac{1}{5} \end{bmatrix}$$

### Example 9.5.5: Finding the Inverse of the Matrix, If It Exists

Find the inverse, if it exists, of the given matrix.

$$A = \begin{bmatrix} 3 & 6 \\ 1 & 2 \end{bmatrix}$$

**Solution**

We will use the method of augmenting with the identity.

$$\left[\begin{array}{cc|cc} 3 & 6 & 1 & 0 \\ 1 & 3 & 0 & 1 \end{array}\right]$$

1. Switch row 1 and row 2.

$$\left[\begin{array}{cc|cc} 1 & 3 & 0 & 1 \\ 3 & 6 & 1 & 0 \end{array}\right]$$

2. Multiply row 1 by $-3$ and add it to row 2.

$$\left[\begin{array}{cc|cc} 1 & 2 & 1 & 0 \\ 0 & 0 & -3 & 1 \end{array}\right]$$

3. There is nothing further we can do. The zeros in row 2 indicate that this matrix has no inverse.

### Finding the Multiplicative Inverse of $3 \times 3$ Matrices

Unfortunately, we do not have a formula similar to the one for a $2 \times 2$ matrix to find the inverse of a $3 \times 3$ matrix. Instead, we will augment the original matrix with the identity matrix and use row operations to obtain the inverse.

Given a $3 \times 3$ matrix

$$A = \begin{bmatrix} 2 & 3 & 1 \\ 3 & 3 & 1 \\ 2 & 4 & 1 \end{bmatrix}$$

augment $A$ with the identity matrix

$$A \,\big|\, I \;=\; \left[\begin{array}{ccc|ccc} 2 & 3 & 1 & 1 & 0 & 0 \\ 3 & 3 & 1 & 0 & 1 & 0 \\ 2 & 4 & 1 & 0 & 0 & 1 \end{array}\right]$$

To begin, we write the **augmented matrix** with the identity on the right and $A$ on the left. Performing elementary **row operations** so that the **identity matrix** appears on the left, we will obtain the **inverse matrix** on the right. We will find the inverse of this matrix in the next example.

### How to: Given a $3 \times 3$ matrix, find the inverse

1. Write the original matrix augmented with the identity matrix on the right.
2. Use elementary row operations so that the identity appears on the left.
3. What is obtained on the right is the inverse of the original matrix.
4. Use matrix multiplication to show that $AA^{-1} = I$ and $A^{-1}A = I$.

## Example 9.5.6: Finding the Inverse of a $3 \times 3$ Matrix

Given the $3 \times 3$ matrix $A$, find the inverse.

$$A = \begin{bmatrix} 2 & 3 & 1 \\ 3 & 3 & 1 \\ 2 & 4 & 1 \end{bmatrix}$$

**Solution**

Augment $A$ with the identity matrix, and then begin row operations until the identity matrix replaces $A$. The matrix on the right will be the inverse of $A$.

$$\left[\begin{array}{ccc|ccc} 2 & 3 & 1 & 1 & 0 & 0 \\ 3 & 3 & 1 & 0 & 1 & 0 \\ 2 & 4 & 1 & 0 & 0 & 1 \end{array}\right] \xrightarrow{\text{Interchange } R_2 \text{ and } R_1} \left[\begin{array}{ccc|ccc} 3 & 3 & 1 & 0 & 1 & 0 \\ 2 & 3 & 1 & 1 & 0 & 0 \\ 2 & 4 & 1 & 0 & 0 & 1 \end{array}\right]$$

$$-R_2 + R_1 = R_1 \rightarrow \left[\begin{array}{ccc|ccc} 1 & 0 & 0 & -1 & 1 & 0 \\ 2 & 3 & 1 & 1 & 0 & 0 \\ 2 & 4 & 1 & 0 & 0 & 1 \end{array}\right]$$

$$-R_2 + R_3 = R_3 \rightarrow \left[\begin{array}{ccc|ccc} 1 & 0 & 0 & -1 & 1 & 0 \\ 2 & 3 & 1 & 1 & 0 & 0 \\ 0 & 1 & 0 & -1 & 0 & 1 \end{array}\right]$$

$$R_2 \leftrightarrow R_3 \rightarrow \left[\begin{array}{ccc|ccc} 1 & 0 & 0 & -1 & 1 & 0 \\ 0 & 1 & 0 & -1 & 0 & 1 \\ 2 & 3 & 1 & 1 & 0 & 0 \end{array}\right]$$

$$-2R_1 + R_3 = R_3 \rightarrow \left[\begin{array}{ccc|ccc} 1 & 0 & 0 & -1 & 1 & 0 \\ 0 & 1 & 0 & -1 & 0 & 1 \\ 0 & 3 & 1 & 3 & -2 & 0 \end{array}\right]$$

$$-3R_2 + R_3 = R_3 \rightarrow \left[\begin{array}{ccc|ccc} 1 & 0 & 0 & -1 & 1 & 0 \\ 0 & 1 & 0 & -1 & 0 & 1 \\ 0 & 0 & 1 & 6 & -2 & -3 \end{array}\right]$$

Thus,

$$A^{-1} = B = \begin{bmatrix} -1 & 1 & 0 \\ -1 & 0 & 1 \\ 6 & -2 & -3 \end{bmatrix}$$

**Analysis**

To prove that $B = A^{-1}$, let's multiply the two matrices together to see if the product equals the identity, if $AA^{-1} = I$ and $A^{-1}A = I$.

$$AA^{-1} = \begin{bmatrix} 2 & 3 & 1 \\ 3 & 3 & 1 \\ 2 & 4 & 1 \end{bmatrix} \begin{bmatrix} -1 & 1 & 0 \\ -1 & 0 & 1 \\ 6 & -2 & -3 \end{bmatrix}$$

$$= \begin{bmatrix} 2(-1)+3(-1)+1(6) & 2(1)+3(0)+1(-2) & 2(0)+3(1)+1(-3) \\ 3(-1)+3(-1)+1(6) & 3(1)+3(0)+1(-2) & 3(0)+3(1)+1(-3) \\ 2(-1)+4(-1)+1(6) & 2(1)+4(0)+1(-2) & 2(0)+4(1)+1(-3) \end{bmatrix}$$

$$= \begin{bmatrix} 1 & 0 & 0 & 0 & 1 & 0 \\ 0 & 0 & 1 & & & \end{bmatrix}$$

$$A^{-1}A = \begin{bmatrix} -1 & 1 & 0 \\ -1 & 0 & 1 \\ 6 & -2 & -3 \end{bmatrix} \begin{bmatrix} & 2 & 31 \\ 3 & 3 & 1 \\ 2 & 4 & 1 \end{bmatrix}$$

$$= \begin{bmatrix} -1(2)+1(3)+0(2) & -1(3)+1(3)+0(4) & -1(1)+1(1)+0(1) \\ -1(2)+0(3)+1(2) & -1(3)+0(3)+1(4) & -1(1)+0(1)+1(1) \\ 6(2)+-2(3)+-3(2) & 6(3)+-2(3)+-3(4) & 6(1)+-2(1)+-3(1) \end{bmatrix}$$

$$= \begin{bmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 1 \end{bmatrix}$$

**? Exercise 9.5.3**

Find the inverse of the $3 \times 3$ matrix.

$$A = \begin{bmatrix} 2 & -17 & 11 \\ -1 & 11 & -7 \\ 0 & 3 & -2 \end{bmatrix}$$

**Answer**

$$A^{-1} = \begin{bmatrix} 1 & 1 & 2 \\ 2 & 4 & -3 \\ 3 & 6 & -5 \end{bmatrix}$$

## Solving a System of Linear Equations Using the Inverse of a Matrix

Solving a system of linear equations using the inverse of a matrix requires the definition of two new matrices: $X$ is the matrix representing the variables of the system, and $B$ is the matrix representing the constants. Using **matrix multiplication**, we may define a system of equations with the same number of equations as variables as

$$AX = B$$

To solve a system of linear equations using an inverse matrix, let $A$ be the coefficient matrix, let $X$ be the variable matrix, and let $B$ be the constant matrix. Thus, we want to solve a system $AX = B$. For example, look at the following system of equations.

$$a_1x + b_1y = c_1$$

$$a_2x + b_2y = c_2$$

From this system, the coefficient matrix is

$$A = \begin{bmatrix} a_1 & b_1 \\ a_2 & b_2 \end{bmatrix}$$

The variable matrix is

$$X = \begin{bmatrix} x \\ y \end{bmatrix}$$

And the constant matrix is

$$B = \begin{bmatrix} c_1 \\ c_2 \end{bmatrix}$$

Then $AX = B$ looks like

$$\begin{bmatrix} a_1 & b_1 \\ a_2 & b_2 \end{bmatrix} \begin{bmatrix} x \\ y \end{bmatrix} = \begin{bmatrix} c_1 \\ c_2 \end{bmatrix}$$

Recall the discussion earlier in this section regarding multiplying a real number by its inverse, $(2^{-1})2 = \left(\frac{1}{2}\right) 2 = 1$. To solve a single linear equation $ax = b$ for $x$, we would simply multiply both sides of the equation by the multiplicative inverse (reciprocal) of $a$. Thus,

$$\begin{aligned} ax &= b \\ \left(\frac{1}{a}\right) ax &= \left(\frac{1}{a}\right) b \\ \left(a^{-1}\right) ax &= \left(a^{-1}\right) b \\ \left[\left(a^{-1}\right) a\right] x &= \left(a^{-1}\right) b \\ 1x &= \left(a^{-1}\right) b \\ x &= \left(a^{-1}\right) b \end{aligned}$$

The only difference between a solving a linear equation and a system of equations written in matrix form is that finding the inverse of a matrix is more complicated, and matrix multiplication is a longer process. However, the goal is the same—to isolate the variable.

We will investigate this idea in detail, but it is helpful to begin with a $2 \times 2$ system and then move on to a $3 \times 3$ system.

### SOLVING A SYSTEM OF EQUATIONS USING THE INVERSE OF A MATRIX

Given a system of equations, write the coefficient matrix $A$, the variable matrix $X$, and the constant matrix $B$. Then

$$AX = B$$

Multiply both sides by the inverse of $A$ to obtain the solution.

$$\begin{aligned} \left(A^{-1}\right) AX &= \left(A^{-1}\right) B \\ \left[\left(A^{-1}\right) A\right] X &= \left(A^{-1}\right) B \\ IX &= \left(A^{-1}\right) B \\ X &= \left(A^{-1}\right) B \end{aligned}$$

### Q&A: If the coefficient matrix does not have an inverse, does that mean the system has no solution?

*No, if the coefficient matrix is not invertible, the system could be inconsistent and have no solution, or be dependent and have infinitely many solutions.*

### Example 9.5.7: Solving a $2 \times 2$ System Using the Inverse of a Matrix

Solve the given system of equations using the inverse of a matrix.

$$\begin{aligned} 3x+8y &= 5 \\ 4x+11y &= 7 \end{aligned}$$

**Solution**

Write the system in terms of a coefficient matrix, a variable matrix, and a constant matrix.

$$A = \begin{bmatrix} 3 & 8 \\ 4 & 11 \end{bmatrix}, X = \begin{bmatrix} x \\ y \end{bmatrix}, B = \begin{bmatrix} 5 \\ 7 \end{bmatrix}$$

Then

$$\begin{bmatrix} 3 & 8 \\ 4 & 11 \end{bmatrix} \begin{bmatrix} x \\ y \end{bmatrix} = \begin{bmatrix} 5 \\ 7 \end{bmatrix}$$

First, we need to calculate $A^{-1}$. Using the formula to calculate the inverse of a 2 by 2 matrix, we have:

$$\begin{aligned} A^{-1} &= \frac{1}{ad-bc} \begin{bmatrix} d & -b \\ -c & a \end{bmatrix} \\ &= \frac{1}{3(11)-8(4)} \begin{bmatrix} 11 & -8 \\ -4 & 3 \end{bmatrix} \\ &= \frac{1}{1} \begin{bmatrix} 11 & -8 \\ -4 & 3 \end{bmatrix} \end{aligned}$$

So,

$$A^{-1} = \begin{bmatrix} 11 & -8 \\ -4 & 3 \end{bmatrix}$$

Now we are ready to solve. Multiply both sides of the equation by $A^{-1}$.

$$\begin{aligned} \left(A^{-1}\right) AX &= \left(A^{-1}\right) B \\ \begin{bmatrix} 11 & -8 \\ -4 & 3 \end{bmatrix} \begin{bmatrix} 3 & 8 \\ 4 & 11 \end{bmatrix} \begin{bmatrix} x \\ y \end{bmatrix} &= \begin{bmatrix} 11 & -8 \\ -4 & 3 \end{bmatrix} \begin{bmatrix} 5 \\ 7 \end{bmatrix} \\ \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix} \begin{bmatrix} x \\ y \end{bmatrix} &= \begin{bmatrix} 11(5)+(-8)7 \\ -4(5)+3(7) \end{bmatrix} \\ \begin{bmatrix} x \\ y \end{bmatrix} &= \begin{bmatrix} -1 \\ 1 \end{bmatrix} \end{aligned}$$

The solution is $(-1, 1)$.

### Q&A: Can we solve for $X$ by finding the product $BA^{-1}$?

*No, recall that matrix multiplication is not commutative, so $A^{-1}B \neq BA^{-1}$. Consider our steps for solving the matrix equation.*

$$\begin{aligned} \left(A^{-1}\right) AX &= \left(A^{-1}\right) B \\ \left[\left(A^{-1}\right) A\right] X &= \left(A^{-1}\right) B \\ IX &= \left(A^{-1}\right) B \\ X &= \left(A^{-1}\right) B \end{aligned}$$

*Notice in the first step we multiplied both sides of the equation by $A^{-1}$, but the $A^{-1}$ was to the left of $A$ on the left side and to the left of $B$ on the right side. Because matrix multiplication is not commutative, order matters.*

### Example 9.5.8: Solving a 3 × 3 System Using the Inverse of a Matrix

Solve the following system using the inverse of a matrix.

$$\begin{aligned} 5x+15y+56z &= 35 \\ -4x-11y-41z &= -26 \\ -x-3y-11z &= -7 \end{aligned}$$

**Solution**

Write the equation $AX = B$.

$$\begin{bmatrix} 5 & 15 & 56 \\ -4 & -11 & -41 \\ -1 & -3 & -11 \end{bmatrix} \begin{bmatrix} x \\ y \\ z \end{bmatrix} = \begin{bmatrix} 35 \\ -26 \\ -7 \end{bmatrix}$$

First, we will find the inverse of $A$ by augmenting with the identity.

$$\left[\begin{array}{ccc|ccc} 5 & 15 & 56 & 1 & 0 & 0 \\ -4 & -11 & -41 & 0 & 1 & 0 \\ -1 & -3 & -11 & 0 & 0 & 1 \end{array}\right]$$

Multiply row 1 by $\frac{1}{5}$.

$$\left[\begin{array}{ccc|ccc} 1 & 3 & \frac{56}{5} & \frac{1}{5} & 0 & 0 \\ -4 & -11 & -41 & 0 & 1 & 0 \\ -1 & -3 & -11 & 0 & 0 & 1 \end{array}\right]$$

Multiply row 1 by 4 and add to row 2.

$$\left[\begin{array}{ccc|ccc} 1 & 3 & \frac{56}{5} & \frac{1}{5} & 0 & 0 \\ 0 & 1 & \frac{19}{5} & \frac{4}{5} & 1 & 0 \\ -1 & -3 & -11 & 0 & 0 & 1 \end{array}\right]$$

Add row 1 to row 3.

$$\left[\begin{array}{ccc|ccc} 1 & 3 & \frac{56}{5} & \frac{1}{5} & 0 & 0 \\ 0 & 1 & \frac{19}{5} & \frac{4}{5} & 1 & 0 \\ 0 & 0 & \frac{1}{5} & \frac{1}{5} & 0 & 1 \end{array}\right]$$

Multiply row 2 by $-3$ and add to row 1.

$$\left[\begin{array}{ccc|ccc} 1 & 0 & -\frac{1}{5} & -\frac{11}{5} & -3 & 0 \\ 0 & 1 & \frac{19}{5} & \frac{4}{5} & 1 & 0 \\ 0 & 0 & \frac{1}{5} & \frac{1}{5} & 0 & 1 \end{array}\right]$$

Multiply row 3 by 5.

$$\left[\begin{array}{ccc|ccc} 1 & 0 & -\frac{1}{5} & -\frac{11}{5} & -3 & 0 \\ 0 & 1 & \frac{19}{5} & \frac{4}{5} & 1 & 0 \\ 0 & 0 & 1 & 1 & 0 & 5 \end{array}\right]$$

Multiply row 3 by $\frac{1}{5}$ and add to row 1.

$$\left[\begin{array}{ccc|ccc} 1 & 0 & 0 & -2 & -3 & 1 \\ 0 & 1 & \frac{19}{5} & \frac{4}{5} & 1 & 0 \\ 0 & 0 & 1 & 1 & 0 & 5 \end{array}\right]$$

Multiply row 3 by $-\frac{19}{5}$ and add to row 2.

$$\left[\begin{array}{ccc|ccc} 1 & 0 & 0 & -2 & -3 & 1 \\ 0 & 1 & 0 & -3 & 1 & -19 \\ 0 & 0 & 1 & 1 & 0 & 5 \end{array}\right]$$

So,

$$A^{-1} = \begin{bmatrix} -2 & -3 & 1 \\ -3 & 1 & -19 \\ 1 & 0 & 5 \end{bmatrix}$$

Multiply both sides of the equation by $A^{-1}$. We want $A^{-1}AX = A^{-1}B$:

$$\begin{bmatrix} -2 & -3 & 1 \\ -3 & 1 & -19 \\ 1 & 0 & 5 \end{bmatrix} \begin{bmatrix} 5 & 15 & 56 \\ -4 & -11 & -41 \\ -1 & -3 & -11 \end{bmatrix} \begin{bmatrix} x \\ y \\ z \end{bmatrix} = \begin{bmatrix} -2 & -3 & 1 \\ -3 & 1 & -19 \\ 1 & 0 & 5 \end{bmatrix} \begin{bmatrix} 35 \\ -26 \\ -7 \end{bmatrix}$$

Thus,

$$A^{-1}B = \begin{bmatrix} -70+78-7 \\ -105-26+133 \\ 35+0-35 \end{bmatrix} = \begin{bmatrix} 1 \\ 2 \\ 0 \end{bmatrix}$$

The solution is $(1, 2, 0)$.

**? Exercise 9.5.4**

Solve the system using the inverse of the coefficient matrix.

$$\begin{aligned} 2x - 17y + 11z &= 0 \\ -x + 11y - 7z &= 8 \\ 3y - 2z &= -2 \end{aligned}$$

**Answer**

$$X = \begin{bmatrix} 4 \\ 38 \\ 58 \end{bmatrix}$$

### How to: Given a system of equations, solve with matrix inverses using a calculator

1. Save the coefficient matrix and the constant matrix as matrix variables $[A]$ and $[B]$.
2. Enter the multiplication into the calculator, calling up each matrix variable as needed.
3. If the coefficient matrix is invertible, the calculator will present the solution matrix; if the coefficient matrix is not invertible, the calculator will present an error message.

### Example 9.5.9: Using a Calculator to Solve a System of Equations with Matrix Inverses

Solve the system of equations with matrix inverses using a calculator

$$\begin{aligned} 2x+3y+z &= 32 \\ 3x+3y+z &= -27 \\ 2x+4y+z &= -2 \end{aligned}$$

**Solution**

On the matrix page of the calculator, enter the coefficient matrix as the matrix variable $[A]$, and enter the constant matrix as the matrix variable $[B]$.

$$[A] = \begin{bmatrix} 2 & 3 & 1 \\ 3 & 3 & 1 \\ 2 & 4 & 1 \end{bmatrix}, [B] = \begin{bmatrix} 32 \\ -27 \\ -2 \end{bmatrix}$$

On the home screen of the calculator, type in the multiplication to solve for $X$, calling up each matrix variable as needed.

$$[A]^{-1} \times [B]$$

Evaluate the expression.

$$\begin{bmatrix} -59 \\ -34 \\ 252 \end{bmatrix}$$

### Media

Access these online resources for additional instruction and practice with solving systems with inverses.

- The Identity Matrix
- Determining Inverse Matrices
- Using a Matrix Equation to Solve a System of Equations

## Key Equations

| | |
|---|---|
| Identity matrix for a $2 \times 2$ matrix | $I_2 = \begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix}$ |
| Identity matrix for a $3 \times 3$ matrix | $I_3 = \begin{bmatrix} 1 & 0 & 0 \\ 0 & 1 & 0 \\ 0 & 0 & 1 \end{bmatrix}$ |

| | |
|---|---|
| Multiplicative inverse of a $2 \times 2$ matrix | $A^{-1} = \frac{1}{ad-bc}\begin{bmatrix} d & -b \\ -c & a \end{bmatrix}$, where $ad - bc \neq 0$ |

## Key Concepts

- An identity matrix has the property $AI = IA = A$ . See Example $9.5.1$.
- An invertible matrix has the property $AA^{-1} = A^{-1}A = I$ . See Example $9.5.2$.
- Use matrix multiplication and the identity to find the inverse of a $2 \times 2$ matrix. See Example $9.5.3$.
- The multiplicative inverse can be found using a formula. See Example $9.5.4$.
- Another method of finding the inverse is by augmenting with the identity. See Example $9.5.5$.
- We can augment a $3 \times 3$ matrix with the identity on the right and use row operations to turn the original matrix into the identity, and the matrix on the right becomes the inverse. See Example $9.5.6$.
- Write the system of equations as $AX = B$, and multiply both sides by the inverse of $A$: $A^{-1}AX = A^{-1}B$. See Example $9.5.7$ and Example $9.5.8$.
- We can also use a calculator to solve a system of equations with matrix inverses. See Example $9.5.9$.

---

This page titled 9.5: Solving Systems with Inverses is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.7: Solving Systems with Inverses** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.5E: Solving Systems with Inverses (Exercises)

For the following exercises, find the inverse of the matrix.

61. $\begin{bmatrix} -0.2 & 1.4 \\ 1.2 & -0.4 \end{bmatrix}$

62. $\begin{bmatrix} \frac{1}{2} & -\frac{1}{2} \\ -\frac{1}{4} & \frac{3}{4} \end{bmatrix}$

63. $\begin{bmatrix} 12 & 9 & -6 \\ -1 & 3 & 2 \\ -4 & -3 & 2 \end{bmatrix}$

64. $\begin{bmatrix} 2 & 1 & 3 \\ 1 & 2 & 3 \\ 3 & 2 & 1 \end{bmatrix}$

For the following exercises, find the solutions by computing the inverse of the matrix.

65.
$0.3x - 0.1y = -10$
$-0.1x + 0.3y = 14$

66.
$0.4x - 0.2y = -0.6$
$-0.1x + 0.05y = 0.3$

67.

$$\begin{aligned} 4x + 3y - 3z &= -4.3 \\ 5x - 4y - z &= -6.1 \\ x + z &= -0.7 \end{aligned} \tag{9.5E.1}$$

68

$-2x - 3y_2z = 3$

$-x + 2y + 4z = -5$

$-2y + 5z = -3$

For the following exercises, write a system of equations to solve each problem. Solve the system of equations.

69. Students were asked to bring their favorite fruit to class. $90\%$ of the fruits consisted of banana, apple, and oranges. If oranges were half as popular as bananas and apples were $5\%$ more popular than bananas, what are the percentages of each individual fruit?

70. A sorority held a bake sale to raise money and sold brownies and chocolate chip cookies. They priced the brownies at $\$2$ and the chocolate chip cookies at $\$1$. They raised $\$250$ and sold 175 items. How many brownies and how many cookies were sold? ?

This page titled 9.5E: Solving Systems with Inverses (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.7E: Solving Systems with Inverses (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.6: Solving Systems with Cramer's Rule

**Learning Objectives**

- Evaluate 2 × 2 determinants.
- Use Cramer's Rule to solve a system of equations in two variables.
- Evaluate 3 × 3 determinants.
- Use Cramer's Rule to solve a system of three equations in three variables.
- Know the properties of determinants.

We have learned how to solve systems of equations in two variables and three variables, and by multiple methods: substitution, addition, Gaussian elimination, using the inverse of a matrix, and graphing. Some of these methods are easier to apply than others and are more appropriate in certain situations. In this section, we will study two more strategies for solving systems of equations.

## Evaluating the Determinant of a 2 × 2 Matrix

A determinant is a real number that can be very useful in mathematics because it has multiple applications, such as calculating area, volume, and other quantities. Here, we will use determinants to reveal whether a matrix is invertible by using the entries of a square matrix to determine whether there is a solution to the system of equations. Perhaps one of the more interesting applications, however, is their use in cryptography. Secure signals or messages are sometimes sent encoded in a matrix. The data can only be decrypted with an invertible matrix and the determinant. For our purposes, we focus on the determinant as an indication of the invertibility of the matrix. Calculating the determinant of a matrix involves following the specific patterns that are outlined in this section.

**FIND THE DETERMINANT OF A 2 × 2 MATRIX**

The *determinant* of a 2 × 2 matrix, given

$$A = \begin{bmatrix} a & b \\ c & d \end{bmatrix}$$

is defined as

$$\det(A) = \begin{vmatrix} a & b \\ c & d \end{vmatrix} = ad - cb$$

Notice the change in notation. There are several ways to indicate the determinant, including $\det(A)$ and replacing the brackets in a matrix with straight lines, $|A|$.

**Example 9.6.1: Finding the Determinant of a 2 × 2 Matrix**

Find the determinant of the given matrix.

$$A = \begin{bmatrix} 5 & 2 \\ -6 & 3 \end{bmatrix}$$

**Solution**

$$\begin{aligned} \det(A) &= \begin{vmatrix} 5 & 2 \\ -6 & 3 \end{vmatrix} \\ &= 5(3) - (-6)(2) \\ &= 27 \end{aligned}$$

## Using Cramer's Rule to Solve a System of Two Equations in Two Variables

We will now introduce a final method for solving systems of equations that uses determinants. Known as **Cramer's Rule**, this technique dates back to the middle of the 18th century and is named for its innovator, the Swiss mathematician Gabriel Cramer (1704-1752), who introduced it in 1750 in *Introduction à l'Analyse des lignes Courbes algébriques*. Cramer's Rule is a viable and

efficient method for finding solutions to systems with an arbitrary number of unknowns, provided that we have the same number of equations as unknowns.

Cramer's Rule will give us the unique solution to a system of equations, if it exists. However, if the system has no solution or an infinite number of solutions, this will be indicated by a determinant of zero. To find out if the system is inconsistent or dependent, another method, such as elimination, will have to be used.

To understand Cramer's Rule, let's look closely at how we solve systems of linear equations using basic row operations. Consider a system of two equations in two variables.

$$a_1x+b_1y=c_1 (1) \tag{9.6.1}$$
$$a_2x+b_2y=c_2 (2) \tag{9.6.2}$$

We eliminate one variable using row operations and solve for the other. Say that we wish to solve for $x$. If Equation 9.6.2 is multiplied by the opposite of the coefficient of $y$ in Equation 9.6.1, Equation 9.6.1 is multiplied by the coefficient of $y$ in Equation 9.6.2, and we add the two equations, the variable $y$ will be eliminated.

$$\begin{array}{rll} b_2a_1x+b_2b_1y=b_2c_1 & & \text{Multiply } R_1 \text{ by } b_2 \\ \underline{-b_1a_2x-b_1b_2y=-b_1c_2} & & \text{Multiply } R_2 \text{ by } -b_1 \\ b_2a_1x-b_1a_2x=b_2c_1-b_1c_2 & & \end{array}$$

Now, solve for $x$.

$$\begin{aligned} b_2a_1x-b_1a_2x &= b_2c_1-b_1c_2 \\ x(b_2a_1-b_1a_2) &= b_2c_1-b_1c_2 \end{aligned}$$
$$x=\frac{b_2c_1-b_1c_2}{b_2a_1-b_1a_2}=\frac{\begin{bmatrix} c_1 & b_1 \\ c_2 & b_2 \end{bmatrix}}{\begin{bmatrix} a_1 & b_1 \\ a_2 & b_2 \end{bmatrix}}$$

Similarly, to solve for $y$,we will eliminate $x$.

$$\begin{array}{rll} a_2a_1x+a_2b_1y=a_2c_1 & & \text{Multiply } R_1 \text{ by } a_2 \\ \underline{-a_1a_2x-a_1b_2y=-a_1c_2} & & \text{Multiply } R_2 \text{ by } -a_1 \\ a_2b_1y-a_1b_2y=a_2c_1-a_1c_2 & & \end{array}$$

Solving for $y$ gives

$$\begin{aligned} a_2b_1y-a_1b_2y &= a_2c_1-a_1c_2 \\ y(a_2b_1-a_1b_2) &= a_2c_1-a_1c_2 \end{aligned}$$
$$y=\frac{a_2c_1-a_1c_2}{a_2b_1-a_1b_2}=\frac{a_1c_2-a_2c_1}{a_1b_2-a_2b_1}=\frac{\begin{bmatrix} a_1 & c_1 \\ a_2 & c_2 \end{bmatrix}}{\begin{bmatrix} a_1 & b_1 \\ a_2 & b_2 \end{bmatrix}}$$

Notice that the denominator for both $x$ and $y$ is the determinant of the coefficient matrix.

We can use these formulas to solve for $x$ and $y$, but Cramer's Rule also introduces new notation:

- $D$:determinant of the coefficient matrix
- $D_x$:determinant of the numerator in the solution of $x$

$$x=\frac{D_x}{D} \tag{9.6.3}$$

- $D_y$:determinant of the numerator in the solution of $y$

$$y=\frac{D_y}{D} \tag{9.6.4}$$

The key to Cramer's Rule is replacing the variable column of interest with the constant column and calculating the determinants. We can then express $x$ and $y$ as a quotient of two determinants.

### CRAMER'S RULE FOR $2 \times 2$ SYSTEMS

Cramer's Rule is a method that uses determinants to solve systems of equations that have the same number of equations as variables.

Consider a system of two linear equations in two variables.

$$\begin{aligned} a_1x + b_1y &= c_1 \\ a_2x + b_2y &= c_2 \end{aligned}$$

The solution using Cramer's Rule is given as

$$x = \frac{D_x}{D} = \frac{\begin{bmatrix} c_1 & b_1 \\ c_2 & b_2 \end{bmatrix}}{\begin{bmatrix} a_1 & b_1 \\ a_2 & b_2 \end{bmatrix}}, D \neq 0 \tag{9.6.5}$$

$$y = \frac{D_y}{D} = \frac{\begin{bmatrix} a_1 & c_1 \\ a_2 & c_2 \end{bmatrix}}{\begin{bmatrix} a_1 & b_1 \\ a_2 & b_2 \end{bmatrix}}, D \neq 0 \tag{9.6.6}$$

If we are solving for $x$, the $x$ column is replaced with the constant column. If we are solving for $y$, the $y$ column is replaced with the constant column.

### Example 9.6.2: Using Cramer's Rule to Solve a $2 \times 2$ System

Solve the following $2 \times 2$ system using Cramer's Rule.

$$\begin{aligned} 12x + 3y &= 15 \\ 2x - 3y &= 13 \end{aligned}$$

**Solution**

Solve for $x$.

$$\begin{aligned} x &= \frac{D_x}{D} \\ &= \frac{\begin{bmatrix} 15 & 3 \\ 13 & -3 \end{bmatrix}}{\begin{bmatrix} 12 & 3 \\ 2 & -3 \end{bmatrix}} \\ &= \frac{-45 - 39}{-36 - 6} \\ &= \frac{-84}{-42} \\ &= 2 \end{aligned}$$

Solve for $y$.

$$
\begin{aligned}
y &= \frac{D_y}{D} \\
&= \frac{\begin{bmatrix} 12 & 15 \\ 2 & 13 \end{bmatrix}}{\begin{bmatrix} 12 & 3 \\ 2 & -3 \end{bmatrix}} \\
&= \frac{156-30}{-36-6} \\
&= -\frac{126}{42} \\
&= -3
\end{aligned}
$$

The solution is $(2, -3)$.

**? Exercise 9.6.1**

Use Cramer's Rule to solve the $2 \times 2$ system of equations.

$$
\begin{aligned}
x + 2y &= -11 \\
-2x + y &= -13
\end{aligned}
$$

**Answer**

$(3, -7)$

## Evaluating the Determinant of a 3 × 3 Matrix

Finding the determinant of a 2×2 matrix is straightforward, but finding the determinant of a 3×3 matrix is more complicated. One method is to augment the 3×3 matrix with a repetition of the first two columns, giving a 3×5 matrix. Then we calculate the sum of the products of entries *down* each of the three diagonals (upper left to lower right), and subtract the products of entries *up* each of the three diagonals (lower left to upper right). This is more easily understood with a visual and an example.

Find the determinant of the 3×3 matrix.

$$
A = \begin{bmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{bmatrix}
$$

1. Augment $A$ with the first two columns.

$$
\det(A) = \left| \begin{array}{ccc|cc} a_1 & b_1 & c_1 & a_1 & b_1 \\ a_2 & b_2 & c_2 & a_2 & b_2 \\ a_3 & b_3 & c_3 & a_3 & b_3 \end{array} \right|
$$

2. From upper left to lower right: Multiply the entries down the first diagonal. Add the result to the product of entries down the second diagonal. Add this result to the product of the entries down the third diagonal.
3. From lower left to upper right: Subtract the product of entries up the first diagonal. From this result subtract the product of entries up the second diagonal. From this result, subtract the product of entries up the third diagonal.

$$
\det(A) = \left| \begin{array}{ccc|cc} a_1 & b_1 & c_1 & a_1 & b_1 \\ a_2 & b_2 & c_2 & a_2 & b_2 \\ a_3 & b_3 & c_3 & a_3 & b_3 \end{array} \right|
$$

The algebra is as follows:

$$
|A| = a_1b_2c_3 + b_1c_2a_3 + c_1a_2b_3 - a_3b_2c_1 - b_3c_2a_1 - c_3a_2b_1
$$

**Example 9.6.3: Finding the Determinant of a 3 × 3 Matrix**

Find the determinant of the $3 \times 3$ matrix given

$$A = \begin{bmatrix} 0 & 2 & 1 \\ 3 & -1 & 1 \\ 4 & 0 & 1 \end{bmatrix}$$

**Solution**

Augment the matrix with the first two columns and then follow the formula. Thus,

$$\begin{aligned} |A| &= \left| \begin{array}{ccc|cc} 0 & 2 & 1 & 0 & 2 \\ 3 & -1 & 1 & 3 & -1 \\ 4 & 0 & 1 & 4 & 0 \end{array} \right| \\ &= 0(-1)(1) + 2(1)(4) + 1(3)(0) - 4(-1)(1) - 0(1)(0) - 1(3)(2) \\ &= 0 + 8 + 0 + 4 - 0 - 6 \\ &= 6 \end{aligned}$$

**Exercise 9.6.2**

Find the determinant of the 3 × 3 matrix.

$$\det(A) = \begin{vmatrix} 1 & -3 & 7 \\ 1 & 1 & 1 \\ 1 & -2 & 3 \end{vmatrix}$$

**Answer**

$-10$

**Q&A: Can we use the same method to find the determinant of a larger matrix?**

*No, this method only works for 2 × 2 and 3 × 3 matrices. For larger matrices it is best to use a graphing utility or computer software.*

## Using Cramer's Rule to Solve a System of Three Equations in Three Variables

Now that we can find the determinant of a $3 \times 3$ matrix, we can apply Cramer's Rule to solve a system of three equations in three variables. Cramer's Rule is straightforward, following a pattern consistent with Cramer's Rule for $2 \times 2$ matrices. As the order of the matrix increases to $3 \times 3$, however, there are many more calculations required.

When we calculate the determinant to be zero, Cramer's Rule gives no indication as to whether the system has no solution or an infinite number of solutions. To find out, we have to perform elimination on the system.

Consider a $3 \times 3$ system of equations.

$$a_1 x + b_1 y + c_1 z = d_1 \tag{9.6.7}$$
$$a_2 x + b_2 y + c_2 z = d_2 \tag{9.6.8}$$
$$a_3 x + b_3 y + c_3 z = d_3 \tag{9.6.9}$$

$$x = \frac{D_x}{D}, y = \frac{D_y}{D}, z = \frac{D_z}{D}, D \neq 0$$

where

$$D = \begin{vmatrix} a_1 & b_1 & c_1 \\ a_2 & b_2 & c_2 \\ a_3 & b_3 & c_3 \end{vmatrix}, D_x = \begin{vmatrix} d_1 & b_1 & c_1 \\ d_2 & b_2 & c_2 \\ d_3 & b_3 & c_3 \end{vmatrix}, D_y = \begin{vmatrix} a_1 & d_1 & c_1 \\ a_2 & d_2 & c_2 \\ a_3 & d_3 & c_3 \end{vmatrix}, D_z = \begin{vmatrix} a_1 & b_1 & d_1 \\ a_2 & b_2 & d_2 \\ a_3 & b_3 & d_3 \end{vmatrix} \tag{9.6.10}$$

If we are writing the determinant $D_x$,we replace the $x$ column with the constant column. If we are writing the determinant $D_y$,we replace they y column with the constant column. If we are writing the determinant $D_z$,we replace the $z$ column with the constant column. Always check the answer.

### Example 9.6.4: Solving a $3 \times 3$ System Using Cramer's Rule

Find the solution to the given $3 \times 3$ system using Cramer's Rule.

$$\begin{aligned} x+y-z &= 6 \\ 3x-2y+z &= -5 \\ x+3y-2z &= 14 \end{aligned}$$

**Solution**

Use Cramer's Rule.

$$D = \begin{vmatrix} 1 & 1 & -1 \\ 3 & -2 & 1 \\ 1 & 3 & -2 \end{vmatrix}, D_x = \begin{vmatrix} 6 & 1 & -1 \\ -5 & -2 & 1 \\ 14 & 3 & -2 \end{vmatrix}, D_y = \begin{vmatrix} 1 & 6 & -1 \\ 3 & -5 & 1 \\ 1 & 14 & -2 \end{vmatrix}, D_z = \begin{vmatrix} 1 & 1 & 6 \\ 3 & -2 & -5 \\ 1 & 3 & 14 \end{vmatrix}$$

Then,

$$\begin{aligned} x = \frac{D_x}{D} &= \frac{-3}{-3} = 1 \\ y = \frac{D_y}{D} &= \frac{-9}{-3} = 3 \\ z = \frac{D_z}{D} &= \frac{6}{-3} = -2 \end{aligned}$$

The solution is $(1, 3, -2)$.

### Exercise 9.6.3

Use Cramer's Rule to solve the $3 \times 3$ matrix.

$$\begin{aligned} x-3y+7z &= 13 \\ x+y+z &= 1 \\ x-2y+3z &= 4 \end{aligned}$$

**Answer**

$$\left(-2, \frac{3}{5}, \frac{12}{5}\right)$$

### Example 9.6.5A: Using Cramer's Rule to Solve an Inconsistent System

Solve the system of equations using Cramer's Rule.

$$3x-2y = 4 \tag{9.6.11}$$
$$6x-4y = 0 \tag{9.6.12}$$

**Solution**

We begin by finding the determinants $D$, $D_x$,and $D_y$.

$$D = \begin{vmatrix} 3 & -2 \\ 6 & -4 \end{vmatrix} = 3(-4) - 6(-2) = 0$$

We know that a determinant of zero means that either the system has no solution or it has an infinite number of solutions. To see which one, we use the process of elimination. Our goal is to eliminate one of the variables.

1. Multiply Equation 9.6.11 by $-2$.

2. Add the result to Equation 9.6.12.

$$\begin{aligned} -6x+4y &= -8 \\ \underline{6x-4y} &= \underline{0} \\ 0 &= -8 \end{aligned}$$

We obtain the equation $0=-8$, which is false. Therefore, the system has no solution. Graphing the system reveals two parallel lines. See Figure 9.6.1.





Figure 9.6.1

## Example 9.6.5B: Use Cramer's Rule to Solve a Dependent System

Solve the system with an infinite number of solutions.

$$x-2y+3z=0 \quad (9.6.13)$$
$$3x+y-2z=0 \quad (9.6.14)$$
$$2x-4y+6z=0 \quad (9.6.15)$$

### Solution

Let's find the determinant first. Set up a matrix augmented by the first two columns.

$$\left|\begin{array}{ccc|cc} 1 & -2 & 3 & 1 & -2 \\ 3 & 1 & -2 & 3 & 1 \\ 2 & -4 & 6 & 2 & -4 \end{array}\right|$$

Then,

$$1(1)(6)+(-2)(-2)(2)+3(3)(-4)-2(1)(3)-(-4)(-2)(1)-6(3)(-2)=0$$

As the determinant equals zero, there is either no solution or an infinite number of solutions. We have to perform elimination to find out.

1. Multiply Equation 9.6.13 by $-2$ and add the result to Equation 9.6.15:

$$\begin{aligned} -2x+4y-6x &= 0 \\ \underline{2x-4y+6z} &= \underline{0} \\ 0 &= 0 \end{aligned}$$

2. Obtaining an answer of $0=0$, a statement that is always true, means that the system has an infinite number of solutions. Graphing the system, we can see that two of the planes are the same and they both intersect the third plane on a line. See Figure 9.6.2.





Figure 9.6.2

## Understanding Properties of Determinants

There are many properties of determinants. Listed here are some properties that may be helpful in calculating the determinant of a matrix.

**PROPERTIES OF DETERMINANTS**

1. If the matrix is in upper triangular form, the determinant equals the product of entries down the main diagonal.
2. When two rows are interchanged, the determinant changes sign.
3. If either two rows or two columns are identical, the determinant equals zero.
4. If a matrix contains either a row of zeros or a column of zeros, the determinant equals zero.
5. The determinant of an inverse matrix $A^{-1}$ is the reciprocal of the determinant of the matrix $A$.
6. If any row or column is multiplied by a constant, the determinant is multiplied by the same factor.

**Example 9.6.6: Illustrating Properties of Determinants**

Illustrate each of the properties of determinants.

**Solution**

Property 1 states that if the matrix is in upper triangular form, the determinant is the product of the entries down the main diagonal.

$$A = \begin{bmatrix} 1 & 2 & 3 \\ 0 & 2 & 1 \\ 0 & 0 & -1 \end{bmatrix}$$

Augment $A$ with the first two columns.

$$A = \left[\begin{array}{ccc|cc} 1 & 2 & 3 & 1 & 2 \\ 0 & 2 & 1 & 0 & 2 \\ 0 & 0 & -1 & 0 & 0 \end{array}\right]$$

Then

$$\begin{aligned} \det(A) &= 1(2)(-1)+2(1)(0)+3(0)(0)-0(2)(3)-0(1)(1)+1(0)(2) \\ &= -2 \end{aligned}$$

Property 2 states that interchanging rows changes the sign. Given

$$\begin{aligned} A &= \begin{bmatrix} -1 & 5 \\ 4 & -3 \end{bmatrix} \\ \det(A) &= (-1)(-3)-(4)(5) \\ &= 3-20 \\ &= -17 \end{aligned}$$

$$\begin{aligned} B &= \begin{bmatrix} 4 & -3 \\ -1 & 5 \end{bmatrix} \\ \det(B) &= (4)(5)-(-1)(-3) \\ &= 20-3 \\ &= 17 \end{aligned}$$

Property 3 states that if two rows or two columns are identical, the determinant equals zero.

$$\begin{aligned} A &= \left[\begin{array}{ccc|cc} 1 & 2 & 2 & 1 & 2 \\ 2 & 2 & 2 & 2 & 2 \\ -1 & 2 & 2 & -1 & 2 \end{array}\right] \\ \det(A) &= 1(2)(2)+2(2)(-1)+2(2)(2)+1(2)(2)-2(2)(1)-2(2)(2) \\ &= 4-4+8+4-4-8 \\ &= 0 \end{aligned}$$

Property 4 states that if a row or column equals zero, the determinant equals zero. Thus,

$$\begin{aligned} A &= \begin{bmatrix} 1 & 2 \\ 0 & 0 \end{bmatrix} \\ \det(A) &= 1(0)-2(0) \\ &= 0 \end{aligned}$$

Property 5 states that the determinant of an inverse matrix $A^{-1}$ is the reciprocal of the determinant $A$. Thus,

$$\begin{aligned} A &= \begin{bmatrix} 1 & 2 \\ 3 & 4 \end{bmatrix} \\ \det(A) &= 1(4)-3(2) \\ &= -2 \end{aligned}$$

$$\begin{aligned} A^{-1} &= \begin{bmatrix} -2 & 1 \\ \frac{3}{2} & -\frac{1}{2} \end{bmatrix} \\ \det(A^{-1}) &= -2\left(-\frac{1}{2}\right)-\frac{3}{2}(1) \\ &= -\frac{1}{2} \end{aligned}$$

Property 6 states that if any row or column of a matrix is multiplied by a constant, the determinant is multiplied by the same factor. Thus,

$$\begin{aligned} A &= \begin{bmatrix} 1 & 2 \\ 3 & 4 \end{bmatrix} \\ \det(A) &= 1(4)-2(3) \\ &= -2 \end{aligned}$$

$$\begin{aligned} B &= \begin{bmatrix} 2(1) & 2(2) \\ 3 & 4 \end{bmatrix} \\ \det(B) &= 2(4)-3(4) \\ &= -4 \end{aligned}$$

### Example 9.6.7: Using Cramer's Rule and Determinant Properties to Solve a System

Find the solution to the given $3\times 3$ system.

$$2x+4y+4z = 2 \tag{9.6.16}$$
$$3x+7y+7z = -5 \tag{9.6.17}$$
$$x+2y+2z = 4 \tag{9.6.18}$$

**Solution**

Using Cramer's Rule, we have

$$D = \begin{bmatrix} 2 & 4 & 4 \\ 3 & 7 & 7 \\ 1 & 2 & 2 \end{bmatrix}$$

Notice that the second and third columns are identical. According to Property 3, the determinant will be zero, so there is either no solution or an infinite number of solutions. We have to perform elimination to find out.

1. Multiply Equation 9.6.18 by $-2$ and add the result to Equation 9.6.16.

$$\begin{aligned} -2x - 4y - 4x &= -8 \\ 2x + 4y + 4z &= 2 \\ 0 &= -6 \end{aligned}$$

Obtaining a statement that is a contradiction means that the system has no solution.

**Media**

Access these online resources for additional instruction and practice with Cramer's Rule.

- Solve a System of Two Equations Using Cramer's Rule
- Solve a Systems of Three Equations using Cramer's Rule

## Key Concepts

- The determinant for $\begin{bmatrix} a & b \\ c & d \end{bmatrix}$ is $ad - bc$. See Example 9.6.1.
- Cramer's Rule replaces a variable column with the constant column. Solutions are $x = \frac{D_x}{D}$, $y = \frac{D_y}{D}$. See Example 9.6.2.
- To find the determinant of a $3 \times 3$ matrix, augment with the first two columns. Add the three diagonal entries (upper left to lower right) and subtract the three diagonal entries (lower left to upper right). See Example 9.6.3.
- To solve a system of three equations in three variables using Cramer's Rule, replace a variable column with the constant column for each desired solution: $x = \frac{D_x}{D}$, $y = \frac{D_y}{D}$, $z = \frac{D_z}{D}$. See Example 9.6.4.
- Cramer's Rule is also useful for finding the solution of a system of equations with no solution or infinite solutions. See Example 9.6.5 and Example 9.6.6.
- Certain properties of determinants are useful for solving problems. For example:
  - If the matrix is in upper triangular form, the determinant equals the product of entries down the main diagonal.
  - When two rows are interchanged, the determinant changes sign.
  - If either two rows or two columns are identical, the determinant equals zero.
  - If a matrix contains either a row of zeros or a column of zeros, the determinant equals zero.
  - The determinant of an inverse matrix $A^{-1}$ is the reciprocal of the determinant of the matrix $A$.
  - If any row or column is multiplied by a constant, the determinant is multiplied by the same factor. See Example 9.6.7 and Example 9.6.8.

This page titled 9.6: Solving Systems with Cramer's Rule is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.8: Solving Systems with Cramer's Rule** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.6E: Solving Systems with Cramer's Rule (Exercises)

For the following exercises, find the determinant.

71. $\begin{vmatrix} 100 & 0 \\ 0 & 0 \end{vmatrix}$

72. $\begin{vmatrix} 0.2 & -0.6 \\ 0.7 & -1.1 \end{vmatrix}$

73. $\begin{vmatrix} -1 & 4 & 3 \\ 0 & 2 & 3 \\ 0 & 0 & -3 \end{vmatrix}$

74. $\begin{vmatrix} \sqrt{2} & 0 & 0 \\ 0 & \sqrt{2} & 0 \\ 0 & 0 & \sqrt{2} \end{vmatrix}$

For the following exercises, use Cramer's Rule to solve the linear systems of equations.

75.

$4x-2y=23$
$-5x-10y=-35$

76 .

$0.2x-0.1y=0$

$-0.3x+0.3y=2.5$

77 .

$-0.5x+0.1y=0.3$
$-0.25x+0.05y=0.15$

78.

$x+6y+3z=4$

$2x+y+2z=3$
$3x-2y+z=0$

79.

$4x-3y+5z=-\frac{5}{2}$

$7x-9y-3z=\frac{3}{2}$
$x-5y-5z=\frac{5}{2}$

80.

$\frac{3}{10}x-\frac{1}{5}y-\frac{3}{10}z=-\frac{1}{50}$
$\frac{1}{10}x-\frac{1}{10}y-\frac{1}{2}z=-\frac{9}{50}$
$\frac{2}{5}x-\frac{1}{2}y-\frac{3}{5}z=-\frac{1}{5}$

This page titled 9.6E: Solving Systems with Cramer's Rule (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **11.8E: Solving Systems with Cramer's Rule (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.7: Rotation of Axes

**Learning Objectives**

- Identify nondegenerate conic sections given their general form equations.
- Use rotation of axes formulas.
- Write equations of rotated conics in standard form.
- Identify conics without rotating axes.

As we have seen, conic sections are formed when a plane intersects two right circular cones aligned tip to tip and extending infinitely far in opposite directions, which we also call a *cone*. The way in which we slice the cone will determine the type of conic section formed at the intersection. A circle is formed by slicing a cone with a plane perpendicular to the axis of symmetry of the cone. An ellipse is formed by slicing a single cone with a slanted plane not perpendicular to the axis of symmetry. A parabola is formed by slicing the plane through the top or bottom of the double-cone, whereas a hyperbola is formed when the plane slices both the top and bottom of the cone (Figure 9.7.1).





***Figure* 9.7.1:** *The nondegenerate conic sections*

Ellipses, circles, hyperbolas, and parabolas are sometimes called the nondegenerate conic sections, in contrast to the degenerate conic sections, which are shown in Figure 9.7.2. A degenerate conic results when a plane intersects the double cone and passes through the apex. Depending on the angle of the plane, three types of degenerate conic sections are possible: a point, a line, or two intersecting lines.





***Figure* 9.7.2:** *Degenerate conic sections*

## Identifying Nondegenerate Conics in General Form

In previous sections of this chapter, we have focused on the standard form equations for nondegenerate conic sections. In this section, we will shift our focus to the general form equation, which can be used for any conic. The general form is set equal to zero, and the terms and coefficients are given in a particular order, as shown below.

$$Ax^2+Bxy+Cy^2+Dx+Ey+F=0$$

where $A$, $B$, and $C$ are not all zero. We can use the values of the coefficients to identify which type conic is represented by a given equation.

You may notice that the general form equation has an $xy$ term that we have not seen in any of the standard form equations. As we will discuss later, the $xy$ term rotates the conic whenever $B$ is not equal to zero.

**Table 9.7.1**

| Conic Sections | Example |
|---|---|
| ellipse | $4x^2+9y^2=1$ |
| circle | $4x^2+4y^2=1$ |
| hyperbola | $4x^2-9y^2=1$ |
| parabola | $4x^2=9y$ or $4y^2=9x$ |

| Conic Sections | Example |
|---|---|
| one line | $4x+9y=1$ |
| intersecting lines | $(x-4)(y+4)=0$ |
| parallel lines | $(x-4)(x-9)=0$ |
| a point | $4x^2+4y^2=0$ |
| no graph | $4x^2+4y^2=-1$ |

## GENERAL FORM OF CONIC SECTIONS

A *conic section* has the general form

$$Ax^2+Bxy+Cy^2+Dx+Ey+F=0 \tag{9.7.1}$$

where $A$, $B$, and $C$ are not all zero. Table 9.7.2 summarizes the different conic sections where $B=0$, and $A$ and $C$ are nonzero real numbers. This indicates that the conic has not been rotated.

**Table 9.7.2**

| | |
|---|---|
| ellipse | $Ax^2+Cy^2+Dx+Ey+F=0$ , $A\neq C$ and $AC>0$ |
| circle | $Ax^2+Cy^2+Dx+Ey+F=0$ , $A=C$ |
| hyperbola | $Ax^2-Cy^2+Dx+Ey+F=0$ or $-Ax^2+Cy^2+Dx+Ey+F=0$ , where $A$ and $C$ are positive |
| parabola | $Ax^2+Dx+Ey+F=0$ or $Cy^2+Dx+Ey+F=0$ |

## How to: Given the equation of a conic, identify the type of conic

1. Rewrite the equation in the general form (Equation 9.7.1), $Ax^2+Bxy+Cy^2+Dx+Ey+F=0$
2. Identify the values of $A$ and $C$ from the general form.
   - If $A$ and $C$ are nonzero, have the same sign, and are not equal to each other, then the graph may be an ellipse.
   - If $A$ and $C$ are equal and nonzero and have the same sign, then the graph may be a circle.
   - If $A$ and $C$ are nonzero and have opposite signs, then the graph may be a hyperbola.
   - If either $A$ or $C$ is zero, then the graph may be a parabola.

If $B=0$, the conic section will have a vertical and/or horizontal axes. If $B$ does not equal 0, as shown below, the conic section is rotated. Notice the phrase "may be" in the definitions. That is because the equation may not represent a conic section at all, depending on the values of $A$, $B$, $C$, $D$, $E$, and $F$. For example, the degenerate case of a circle or an ellipse is a point:

$$Ax^2+By^2=0, \tag{9.7.2}$$

when $A$ and $B$ have the same sign.

The degenerate case of a hyperbola is two intersecting straight lines: $Ax^2+By^2=0$ , when $A$ and $B$ have opposite signs.

On the other hand, the equation, $Ax^2+By^2+1=0$ , when $A$ and $B$ are positive does not represent a graph at all, since there are no real ordered pairs which satisfy it.

## Example 9.7.1: Identifying a Conic from Its General Form

Identify the graph of each of the following nondegenerate conic sections.

a. $4x^2-9y^2+36x+36y-125=0$
b. $9y^2+16x+36y-10=0$
c. $3x^2+3y^2-2x-6y-4=0$
d. $-25x^2-4y^2+100x+16y+20=0$

**Solution**

1. Rewriting the general form (Equation 9.7.1), we have

$$\begin{aligned} Ax^2+Bxy+Cy^2+Dx+Ey+F &= 0 \\ 4x^2+0xy+(-9)y^2+36x+36y+(-125) &= 0 \end{aligned}$$

   with $A=4$ and $C=-9$, so we observe that $A$ and $C$ have opposite signs. The graph of this equation is a hyperbola.
2. Rewriting the general form (Equation 9.7.1), we have

$$\begin{aligned} Ax^2+Bxy+Cy^2+Dx+Ey+F &= 0 \\ 0x^2+0xy+9y^2+16x+36y+(-10) &= 0 \end{aligned}$$

   with $A=0$ and $C=9$. We can determine that the equation is a parabola, since $A$ is zero.
3. Rewriting the general form (Equation 9.7.1), we have

$$\begin{aligned} Ax^2+Bxy+Cy^2+Dx+Ey+F &= 0 \\ 3x^2+0xy+3y^2+(-2)x+(-6)y+(-4) &= 0 \end{aligned}$$

   with $A=3$ and $C=3$. Because $A=C$, the graph of this equation is a circle.
4. Rewriting the general form (Equation 9.7.1), we have

$$\begin{aligned} Ax^2+Bxy+Cy^2+Dx+Ey+F &= 0 \\ (-25)x^2+0xy+(-4)y^2+100x+16y+20 &= 0 \end{aligned}$$

   with $A=-25$ and $C=-4$. Because $AC>0$ and $A\neq C$, the graph of this equation is an ellipse.

## Exercise 9.7.1

Identify the graph of each of the following nondegenerate conic sections.

a. $16y^2-x^2+x-4y-9=0$
b. $16x^2+4y^2+16x+49y-81=0$

**Answer a**

hyperbola

**Answer b**

ellipse

### Finding a New Representation of the Given Equation after Rotating through a Given Angle

Until now, we have looked at equations of conic sections without an $xy$ term, which aligns the graphs with the *x*- and *y*-axes. When we add an $xy$ term, we are rotating the conic about the origin. If the *x*- and *y*-axes are rotated through an angle, say $\theta$,then every point on the plane may be thought of as having two representations: $(x, y)$ on the Cartesian plane with the original *x*-axis and *y*-axis, and $(x', y')$ on the new plane defined by the new, rotated axes, called the *x*′-axis and *y*′-axis (Figure 9.7.3).





***Figure* 9.7.3:** *The graph of the rotated ellipse* $x^2 + y^2 - xy - 15 = 0$

We will find the relationships between $x$ and $y$ on the Cartesian plane with $x'$ and $y'$ on the new rotated plane (Figure 9.7.4).





***Figure* 9.7.4:** *The Cartesian plane with* $x$*- and* $y$*-axes and the resulting* $x'-$ *and* $y'-$*axes formed by a rotation by an angle* $\theta$*.*

The original coordinate *x*- and *y*-axes have unit vectors $\hat{i}$ and $\hat{j}$. The rotated coordinate axes have unit vectors $\hat{i}'$ and $\hat{j}'$.The angle $\theta$ is known as the angle of rotation (Figure 9.7.5). We may write the new unit vectors in terms of the original ones.

$$\hat{i}' = \cos\theta\hat{i} + \sin\theta\hat{j} \tag{9.7.3}$$

$$\hat{j}' = -\sin\theta\hat{i} + \cos\theta\hat{j} \tag{9.7.4}$$





***Figure* 9.7.5:** *Relationship between the old and new coordinate planes.*

Consider a vector $\vec{u}$ in the new coordinate plane. It may be represented in terms of its coordinate axes.

$$\begin{aligned}
\vec{u} &= x'i' + y'j' \\
&= x'(i\cos\theta + j\sin\theta) + y'(-i\sin\theta + j\cos\theta) && \text{Substitute.} \\
&= ix'\cos\theta + jx'\sin\theta - iy'\sin\theta + jy'\cos\theta && \text{Distribute.} \\
&= ix'\cos\theta - iy'\sin\theta + jx'\sin\theta + jy'\cos\theta && \text{Apply commutative property.} \\
&= (x'\cos\theta - y'\sin\theta)i + (x'\sin\theta + y'\cos\theta)j && \text{Factor by grouping.}
\end{aligned}$$

Because $\vec{u} = x'i' + y'j'$, we have representations of $x$ and $y$ in terms of the new coordinate system.

$$x = x'\cos\theta - y'\sin\theta$$

and

$$y = x'\sin\theta + y'\cos\theta$$

### EQUATIONS OF ROTATION

If a point $(x, y)$ on the Cartesian plane is represented on a new coordinate plane where the axes of rotation are formed by rotating an angle $\theta$ from the positive $x$-axis, then the coordinates of the point with respect to the new axes are $(x', y')$. We can use the following equations of rotation to define the relationship between $(x, y)$ and $(x', y')$:

$$x = x' \cos\theta - y' \sin\theta \tag{9.7.5}$$

and

$$y = x' \sin\theta + y' \cos\theta \tag{9.7.6}$$

### How to: Given the equation of a conic, find a new representation after rotating through an angle

1. Find $x$ and $y$ where $x = x' \cos\theta - y' \sin\theta$ and $y = x' \sin\theta + y' \cos\theta$ .
2. Substitute the expression for $x$ and $y$ into in the given equation, then simplify.
3. Write the equations with $x'$ and $y'$ in standard form.

### Example 9.7.2: Finding a New Representation of an Equation after Rotating through a Given Angle

Find a new representation of the equation $2x^2 - xy + 2y^2 - 30 = 0$ after rotating through an angle of $\theta = 45^\circ$.

**Solution**

Find $x$ and $y$, where $x = x' \cos\theta - y' \sin\theta$ and $y = x' \sin\theta + y' \cos\theta$ .

Because $\theta = 45^\circ$,

$$\begin{aligned} x &= x' \cos(45^\circ) - y' \sin(45^\circ) \\ x &= x' \left(\frac{1}{\sqrt{2}}\right) - y' \left(\frac{1}{\sqrt{2}}\right) \\ x &= \frac{x' - y'}{\sqrt{2}} \end{aligned}$$

and

$$\begin{aligned} y &= x' \sin(45^\circ) + y' \cos(45^\circ) \\ y &= x' \left(\frac{1}{\sqrt{2}}\right) + y' \left(\frac{1}{\sqrt{2}}\right) \\ y &= \frac{x' + y'}{\sqrt{2}} \end{aligned}$$

Substitute $x = x' \cos\theta - y' \sin\theta$ and $y = x' \sin\theta + y' \cos\theta$ into $2x^2 - xy + 2y^2 - 30 = 0$ .

$$2\left(\frac{x' - y'}{\sqrt{2}}\right)^2 - \left(\frac{x' - y'}{\sqrt{2}}\right)\left(\frac{x' + y'}{\sqrt{2}}\right) + 2\left(\frac{x' + y'}{\sqrt{2}}\right)^2 - 30 = 0$$

**Simplify**.

$$2\frac{(x' - y')(x' - y')}{2} - \frac{(x' - y')(x' + y')}{2} + 2\frac{(x' + y')(x' + y')}{2} - 30 = 0 \quad \text{FOIL method}$$

$$x'^2 - 2x'y' + y'^2 - \frac{(x'^2 - y'^2)}{2} + x'^2 + 2x'y' + y'^2 - 30 = 0 \quad \text{Combine like terms.}$$

$$2x'^2 + 2y'^2 - \frac{(x'^2 - y'^2)}{2} = 30 \quad \text{Combine like terms.}$$

$$2(2x'^2 + 2y'^2 - \frac{(x'^2 - y'^2)}{2}) = 2(30) \quad \text{Multiply both sides by 2.}$$

$$4x'^2 + 4y'^2 - (x'^2 - y'^2) = 60 \quad \text{Simplify.}$$


$$4x'^2 + 4y'^2 - x'^2 + y'2 = 60 \quad \text{Distribute.}$$

$$\frac{3x'^2}{60} + \frac{5y'^2}{60} = \frac{60}{60} \quad \text{Set equal to 1.}$$

Write the equations with $x'$ and $y'$ in the standard form.

$$\frac{x'^2}{20} + \frac{y'^2}{12} = 1$$

This equation is an ellipse. Figure 9.7.6 shows the graph.





https://math.libretexts.org/@go/page/96345

*Figure* 9.7.6

## Writing Equations of Rotated Conics in Standard Form

Now that we can find the standard form of a conic when we are given an angle of rotation, we will learn how to transform the equation of a conic given in the form $Ax^2+Bxy+Cy^2+Dx+Ey+F=0$ into standard form by rotating the axes. To do so, we will rewrite the general form as an equation in the $x'$ and $y'$ coordinate system without the $x'y'$ term, by rotating the axes by a measure of $\theta$ that satisfies

$$\cot(2\theta)=\frac{A-C}{B} \tag{9.7.7}$$

We have learned already that any conic may be represented by the second degree equation

$$Ax^2+Bxy+Cy^2+Dx+Ey+F=0$$

where $A$, $B$,and $C$ are not all zero. However, if $B\neq 0$, then we have an $xy$ term that prevents us from rewriting the equation in standard form. To eliminate it, we can rotate the axes by an acute angle $\theta$ where $\cot(2\theta)=\frac{A-C}{B}$.

- If $\cot(2\theta)>0$, then $2\theta$ is in the first quadrant, and $\theta$ is between $(0^\circ, 45^\circ)$.
- If $\cot(2\theta)<0$, then $2\theta$ is in the second quadrant, and $\theta$ is between $(45^\circ, 90^\circ)$.
- If $A=C$, then $\theta=45^\circ$.

**How to: Given an equation for a conic in the $x'y'$ system, rewrite the equation without the $x'y'$ term in terms of $x'$ and $y'$,where the $x'$ and $y'$ axes are rotations of the standard axes by $\theta$ degrees**

1. Find $\cot(2\theta)$.
2. Find $\sin\theta$ and $\cos\theta$.
3. Substitute $\sin\theta$ and $\cos\theta$ into $x=x'\cos\theta-y'\sin\theta$ and $y=x'\sin\theta+y'\cos\theta$.
4. Substitute the expression for $x$ and $y$ into in the given equation, and then simplify.
5. Write the equations with $x'$ and $y'$ in the standard form with respect to the rotated axes.

**Example 9.7.3: Rewriting an Equation with respect to the $x'$ and $y'$ axes without the $x'y'$ Term**

Rewrite the equation $8x^2-12xy+17y^2=20$ in the $x'y'$ system without an $x'y'$ term.

**Solution**

First, we find $\cot(2\theta)$.

$$8x^2-12xy+17y^2=20 \rightarrow A=8,\ B=-12 \text{ and } C=17$$





*Figure* 9.7.7

From Figure 9.7.7:

$$\cot(2\theta)=\frac{A-C}{B}=\frac{8-17}{-12}$$
$$=\frac{-9}{-12}=\frac{3}{4}$$
$$\cot(2\theta)=\frac{3}{4}=\frac{\text{adjacent}}{\text{opposite}}$$

So the hypotenuse is

$$3^2+4^2=h^2$$
$$9+16=h^2$$
$$25=h^2$$
$$h=5$$

Next, we find $\sin\theta$ and $\cos\theta$.

$$\sin\theta=\sqrt{\frac{1-\cos(2\theta)}{2}}=\sqrt{\frac{1-\frac{3}{5}}{2}}=\sqrt{\frac{\frac{5}{5}-\frac{3}{5}}{2}}=\sqrt{\frac{5-3}{5}\cdot\frac{1}{2}}=\sqrt{\frac{2}{10}}=\sqrt{\frac{1}{5}}$$
$$\sin\theta=\frac{1}{\sqrt{5}}$$
$$\cos\theta=\sqrt{\frac{1+\cos(2\theta)}{2}}=\sqrt{\frac{1+\frac{3}{5}}{2}}=\sqrt{\frac{\frac{5}{5}+\frac{3}{5}}{2}}=\sqrt{\frac{5+3}{5}\cdot\frac{1}{2}}=\sqrt{\frac{8}{10}}=\sqrt{\frac{4}{5}}$$
$$\cos\theta=\frac{2}{\sqrt{5}}$$

Substitute the values of $\sin\theta$ and $\cos\theta$ into $x=x'\cos\theta-y'\sin\theta$ and $y=x'\sin\theta+y'\cos\theta$.

$$\begin{aligned} x &= x'\cos\theta - y'\sin\theta \\ &= x'\left(\frac{2}{\sqrt{5}}\right) - y'\left(\frac{1}{\sqrt{5}}\right) \\ &= \frac{2x'-y'}{\sqrt{5}} \end{aligned}$$

and

$$\begin{aligned} y &= x'\sin\theta + y'\cos\theta \\ &= x'\left(\frac{1}{\sqrt{5}}\right) + y'\left(\frac{2}{\sqrt{5}}\right) \\ &= \frac{x'+2y'}{\sqrt{5}} \end{aligned}$$

Substitute the expressions for $x$ and $y$ into in the given equation, and then simplify.

$$8\left(\frac{2x'-y'}{\sqrt{5}}\right)^2 - 12\left(\frac{2x'-y'}{\sqrt{5}}\right)\left(\frac{x'+2y'}{\sqrt{5}}\right) + 17\left(\frac{x'+2y'}{\sqrt{5}}\right)^2 = 20$$

$$8\left(\frac{(2x'-y')(2x'-y')}{5}\right) - 12\left(\frac{(2x'-y')(x'+2y')}{5}\right) + 17\left(\frac{(x'+2y')(x'+2y')}{5}\right) = 20$$

$$8(4x'^2 - 4x'y' + y'^2) - 12(2x'^2 + 3x'y' - 2y'^2) + 17(x'^2 + 4x'y' + 4y'^2) = 100$$

$$32x'^2 - 32x'y' + 8y'^2 - 24x'^2 - 36x'y' + 24y'^2 + 17x'^2 + 68x'y' + 68y'^2 = 100$$

$$25x'^2 + 100y'^2 = 100$$

$$\frac{25}{100}x'^2 + \frac{100}{100}y'^2 = \frac{100}{100}$$

Write the equations with $x'$ and $y'$ in the standard form with respect to the new coordinate system.

$$\frac{x'^2}{4} + \frac{y'^2}{1} = 1$$

Figure 9.7.8 shows the graph of the ellipse.





***Figure* 9.7.8**

**? Exercise 9.7.2**

Rewrite the $13x^2 - 6\sqrt{3}xy + 7y^2 = 16$ in the $x'y'$ system without the $x'y'$ term.

**Answer**

$\frac{x'^2}{4} + \frac{y'^2}{1} = 1$

**✓ Example 9.7.4 :Graphing an Equation That Has No $x'y'$ Terms**

Graph the following equation relative to the $x'y'$ system:

$$x^2 + 12xy - 4y^2 = 30$$

**Solution**

First, we find $\cot(2\theta)$.

$$x^2 + 12xy - 4y^2 = 20 \rightarrow A = 1\ ,\ B = 12, \text{and } C = -4$$

$$\cot(2\theta) = \frac{A-C}{B}$$

$$\cot(2\theta) = \frac{1-(-4)}{12}$$

$$\cot(2\theta) = \frac{5}{12}$$

Because $\cot(2\theta) = \frac{5}{12}$, we can draw a reference triangle as in Figure 9.7.9.





***Figure* 9.7.9**

$$\cot(2\theta) = \frac{5}{12} = \frac{adjacent}{opposite}$$

Thus, the hypotenuse is

$$\begin{aligned} 5^2 + 12^2 &= h^2 \\ 25 + 144 &= h^2 \\ 169 &= h^2 \\ h &= 13 \end{aligned}$$

Next, we find $\sin\theta$ and $\cos\theta$. We will use half-angle identities.

$$\sin\theta = \sqrt{\frac{1-\cos(2\theta)}{2}} = \sqrt{\frac{1-\frac{5}{13}}{2}} = \sqrt{\frac{\frac{13}{13}-\frac{5}{13}}{2}} = \sqrt{\frac{8}{13}\cdot\frac{1}{2}} = \frac{2}{\sqrt{13}}$$

$$\cos\theta = \sqrt{\frac{1+\cos(2\theta)}{2}} = \sqrt{\frac{1+\frac{5}{13}}{2}} = \sqrt{\frac{\frac{13}{13}+\frac{5}{13}}{2}} = \sqrt{\frac{18}{13}\cdot\frac{1}{2}} = \frac{3}{\sqrt{13}}$$

Now we find $x$ and $y$.

$$\begin{aligned} x &= x'\cos\theta - y'\sin\theta \\ x &= x'\left(\frac{3}{\sqrt{13}}\right) - y'\left(\frac{2}{\sqrt{13}}\right) \\ x &= \frac{3x'-2y'}{\sqrt{13}} \end{aligned}$$

and

$$\begin{aligned} y &= x'\sin\theta + y'\cos\theta \\ y &= x'\left(\frac{2}{\sqrt{13}}\right) + y'\left(\frac{3}{\sqrt{13}}\right) \\ y &= \frac{2x'+3y'}{\sqrt{13}} \end{aligned}$$

Now we substitute $x = \frac{3x'-2y'}{\sqrt{13}}$ and $y = \frac{2x'+3y'}{\sqrt{13}}$ into $x^2 + 12xy - 4y^2 = 30$.

$$\left(\frac{3x'-2y'}{\sqrt{13}}\right)^2 + 12\left(\frac{3x'-2y'}{\sqrt{13}}\right)\left(\frac{2x'+3y'}{\sqrt{13}}\right) - 4\left(\frac{2x'+3y'}{\sqrt{13}}\right)^2 = 30$$

$$\left(\frac{1}{13}\right)\left[(3x'-2y')^2 + 12(3x'-2y')(2x'+3y') - 4(2x'+3y')^2\right] = 30 \quad \text{Factor.}$$

$$\left(\frac{1}{13}\right)\left[9x'^2 - 12x'y' + 4y'^2 + 12(6x'^2 + 5x'y' - 6y'^2) - 4(4x'^2 + 12x'y' + 9y'^2)\right] = 30 \quad \text{Multiply.}$$

$$\left(\frac{1}{13}\right)\left[9x'^2 - 12x'y' + 4y'^2 + 72x'^2 + 60x'y' - 72y'^2 - 16x'^2 - 48x'y' - 36y'^2\right] = 30 \quad \text{Distribute.}$$

$$\left(\frac{1}{13}\right)\left[65x'^2 - 104y'^2\right] = 30 \quad \text{Combine like terms.}$$

$$65x'^2 - 104y'^2 = 390 \quad \text{Multiply.}$$

$$\frac{x'^2}{6} - \frac{4y'^2}{15} = 1 \quad \text{Divide by 390.}$$

Figure 9.7.10 shows the graph of the hyperbola $\frac{x'^2}{6} - \frac{4y'^2}{15} = 1$





***Figure* 9.7.10**

## Identifying Conics without Rotating Axes

Now we have come full circle. How do we identify the type of conic described by an equation? What happens when the axes are rotated? Recall, the general form of a conic is

$$Ax^2+Bxy+Cy^2+Dx+Ey+F=0$$

If we apply the rotation formulas to this equation we get the form

$$A'x'^2+B'x'y'+C'y'^2+D'x'+E'y'+F'=0$$

It may be shown that

$$B^2-4AC=B'^2-4A'C'$$

The expression does not vary after rotation, so we call the expression *invariant*. The discriminant, $B^2-4AC$, is invariant and remains unchanged after rotation. Because the discriminant remains unchanged, observing the discriminant enables us to identify the conic section.

### HOWTO: USING THE DISCRIMINANT TO IDENTIFY A CONIC

If the equation

$$Ax^2+Bxy+Cy^2+Dx+Ey+F=0 \tag{9.7.8}$$

is transformed by rotating axes into the equation

$$A'x'^2+B'x'y'+C'y'^2+D'x'+E'y'+F'=0 \tag{9.7.9}$$

then

$$B^2-4AC=B'^2-4A'C' \tag{9.7.10}$$

The equation $Ax^2+Bxy+Cy^2+Dx+Ey+F=0$ is an ellipse, a parabola, or a hyperbola, or a degenerate case of one of these. If the discriminant, $B^2-4AC$, is

- $<0$, the conic section is an ellipse
- $=0$, the conic section is a parabola
- $>0$, the conic section is a hyperbola

### Example 9.7.5: Identifying the Conic without Rotating Axes

Identify the conic for each of the following without rotating axes.

a. $5x^2+2\sqrt{3}xy+2y^2-5=0$
b. $5x^2+2\sqrt{3}xy+12y^2-5=0$

**Solution**

a. Let's begin by determining $A$, $B$, and $C$.

$$\underbrace{5}_{A}x^2+\underbrace{2\sqrt{3}}_{B}xy+\underbrace{2}_{C}y^2-5=0$$

Now, we find the discriminant.

$$\begin{aligned}B^2-4AC&=(2\sqrt{3})^2-4(5)(2)\\&=4(3)-40\\&=12-40\\&=-28<0\end{aligned}$$

Therefore, $5x^2+2\sqrt{3}xy+2y^2-5=0$ represents an ellipse.

b. Again, let's begin by determining $A$,$B$, and $C$.

$$\underbrace{5}_{A}x^2+\underbrace{2\sqrt{3}}_{B}xy+\underbrace{12}_{C}y^2-5=0$$

Now, we find the discriminant.

$$\begin{aligned}B^2-4AC&=(2\sqrt{3})^2-4(5)(12)\\&=4(3)-240\\&=12-240\\&=-228<0\end{aligned}$$

Therefore, $5x^2+2\sqrt{3}xy+12y^2-5=0$ represents an ellipse.

**? Exercise 9.7.3**

Identify the conic for each of the following without rotating axes.

a. $x^2 - 9xy + 3y^2 - 12 = 0$
b. $10x^2 - 9xy + 4y^2 - 4 = 0$

**Answer a**

hyperbola

**Answer b**

ellipse

## Key Equations

| | |
|---|---|
| General Form equation of a conic section | $Ax^2 + Bxy + Cy^2 + Dx + Ey + F = 0$ |
| Rotation of a conic section | $x = x' \cos\theta - y' \sin\theta$<br>$y = x' \sin\theta + y' \cos\theta$ |
| Angle of rotation | $\theta$, where $\cot(2\theta) = \dfrac{A - C}{B}$ |

## Key Concepts

- Four basic shapes can result from the intersection of a plane with a pair of right circular cones connected tail to tail. They include an ellipse, a circle, a hyperbola, and a parabola.
- A nondegenerate conic section has the general form $Ax^2 + Bxy + Cy^2 + Dx + Ey + F = 0$ where $A$, $B$ and $C$ are not all zero. The values of $A$, $B$, and $C$ determine the type of conic. See Example $9.7.1$.
- Equations of conic sections with an $xy$ term have been rotated about the origin. See Example $9.7.2$.
- The general form can be transformed into an equation in the $x'$ and $y'$ coordinate system without the $x'y'$ term. See Example $9.7.3$ and Example $9.7.4$.
- An expression is described as invariant if it remains unchanged after rotating. Because the discriminant is invariant, observing it enables us to identify the conic section. See Example $9.7.5$.

This page titled 9.7: Rotation of Axes is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **12.4: Rotation of Axes** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.7E: Rotation of Axes (Exercises)

For the following exercises, determine which of the conic sections is represented.

33. $16x^2+24xy+9y^2+24x-60y-60=0$

34. $4x^2+14xy+5y^2+18x-6y+30=0$

35. $4x^2+xy+2y^2+8x-26y+9=0$

For the following exercises, determine the angle $\theta$ that will eliminate the $xy$ term, and write the corresponding equation without the $xy$ term.

36. $x^2+4xy-2y^2-6=0$

37. $x^2-xy+y^2-6=0$

For the following exercises, graph the equation relative to the $x'y'$ system in which the equation has no $x'y'$ term.

38. $9x^2-24xy+16y^2-80x-60y+100=0$

39. $x^2-xy+y^2-2=0$

40. $6x^2+24xy-y^2-12x+26y+11=0$

This page titled 9.7E: Rotation of Axes (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **12.4E: Rotation of Axes (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.8: Conic Sections in Polar Coordinates

**Learning Objectives**

- Identify a conic in polar form.
- Graph the polar equations of conics.
- Define conics in terms of a focus and a directrix.

Most of us are familiar with orbital motion, such as the motion of a planet around the sun or an electron around an atomic nucleus. Within the planetary system, orbits of planets, asteroids, and comets around a larger celestial body are often elliptical. Comets, however, may take on a parabolic or hyperbolic orbit instead. And, in reality, the characteristics of the planets' orbits may vary over time. Each orbit is tied to the location of the celestial body being orbited and the distance and direction of the planet or other object from that body. As a result, we tend to use polar coordinates to represent these orbits.




Figure 9.8.1: Planets orbiting the sun follow elliptical paths. (credit: NASA Blueshift, Flickr)

In an elliptical orbit, the **periapsis** is the point at which the two objects are closest, and the **apoapsis** is the point at which they are farthest apart. Generally, the velocity of the orbiting body tends to increase as it approaches the periapsis and decrease as it approaches the apoapsis. Some objects reach an escape velocity, which results in an infinite orbit. These bodies exhibit either a parabolic or a hyperbolic orbit about a body; the orbiting body breaks free of the celestial body's gravitational pull and fires off into space. Each of these orbits can be modeled by a conic section in the polar coordinate system.

## Identifying a Conic in Polar Form

Any conic may be determined by three characteristics: a single **focus**, a fixed line called the **directrix**, and the ratio of the distances of each to a point on the graph. Consider the **parabola** $x = 2 + y^2$ shown in Figure 9.8.2.





Figure 9.8.2

We previously learned how a parabola is defined by the focus (a fixed point) and the directrix (a fixed line). In this section, we will learn how to define any conic in the polar coordinate system in terms of a fixed point, the focus $P(r, \theta)$ at the pole, and a line, the directrix, which is perpendicular to the polar axis.

If $F$ is a fixed point, the focus, and $D$ is a fixed line, the directrix, then we can let $e$ be a fixed positive number, called the **eccentricity**, which we can define as the ratio of the distances from a point on the graph to the focus and the point on the graph to the directrix. Then the set of all points $P$ such that $e = \dfrac{PF}{PD}$ is a conic. In other words, we can define a conic as the set of all points $P$ with the property that the ratio of the distance from $P$ to $F$ to the distance from $P$ to $D$ is equal to the constant $e$.

For a conic with eccentricity $e$,

- if $0 \le e < 1$, the conic is an ellipse
- if $e = 1$, the conic is a parabola
- if $e > 1$, the conic is an hyperbola

With this definition, we may now define a conic in terms of the directrix, $x = \pm p$, the eccentricity $e$, and the angle $\theta$. Thus, each conic may be written as a **polar equation**, an equation written in terms of $r$ and $\theta$.

### THE POLAR EQUATION FOR A CONIC

For a conic with a focus at the origin, if the directrix is $x = \pm p$, where $p$ is a positive real number, and the eccentricity is a positive real number $e$, the conic has a polar equation

$$r = \frac{ep}{1 \pm e\cos\theta} \tag{9.8.1}$$

For a conic with a focus at the origin, if the directrix is $y = \pm p$, where $p$ is a positive real number, and the eccentricity is a positive real number $e$, the conic has a polar equation

$$r = \frac{ep}{1 \pm e\sin\theta} \tag{9.8.2}$$

### How to: Given the polar equation for a conic, identify the type of conic, the directrix, and the eccentricity.

1. Multiply the numerator and denominator by the reciprocal of the constant in the denominator to rewrite the equation in standard form.
2. Identify the eccentricity $e$ as the coefficient of the trigonometric function in the denominator.
3. Compare $e$ with 1 to determine the shape of the conic.
4. Determine the directrix as $x = p$ if cosine is in the denominator and $y = p$ if sine is in the denominator. Set $ep$ equal to the numerator in standard form to solve for $x$ or $y$.

### Example 9.8.1: Identifying a Conic Given the Polar Form

For each of the following equations, identify the conic with focus at the origin, the directrix, and the eccentricity.

a. $r = \dfrac{6}{3 + 2\sin\theta}$

b. $r = \dfrac{12}{4 + 5\cos\theta}$

c. $r = \dfrac{7}{2 - 2\sin\theta}$

**Solution**

For each of the three conics, we will rewrite the equation in standard form. Standard form has a 1 as the constant in the denominator. Therefore, in all three parts, the first step will be to multiply the numerator and denominator by the reciprocal of the constant of the original equation, $\dfrac{1}{c}$, where $c$ is that constant.

a. Multiply the numerator and denominator by $\dfrac{1}{3}$.

$$r=\frac{6}{3+2\sin\theta}\cdot\frac{\left(\frac{1}{3}\right)}{\left(\frac{1}{3}\right)}=\frac{6\left(\frac{1}{3}\right)}{3\left(\frac{1}{3}\right)+2\left(\frac{1}{3}\right)\sin\theta}=\frac{2}{1+\frac{2}{3}\sin\theta}$$

Because $\sin\theta$ is in the denominator, the directrix is $y=p$. Comparing to standard form, note that $e=\frac{2}{3}$ .Therefore, from the numerator,

$$\begin{aligned}2&=ep\\2&=\frac{2}{3}p\\\left(\frac{3}{2}\right)2&=\left(\frac{3}{2}\right)\frac{2}{3}p\\3&=p\end{aligned}$$

Since $e<1$ , the conic is an **ellipse**. The eccentricity is $e=\frac{2}{3}$ and the directrix is $y=3$.

b. Multiply the numerator and denominator by $\frac{1}{4}$.

$$\begin{aligned}r&=\frac{12}{4+5\cos\theta}\cdot\frac{\left(\frac{1}{4}\right)}{\left(\frac{1}{4}\right)}\\r&=\frac{12\left(\frac{1}{4}\right)}{4\left(\frac{1}{4}\right)+5\left(\frac{1}{4}\right)\cos\theta}\\r&=\frac{3}{1+\frac{5}{4}\cos\theta}\end{aligned}$$

Because $\cos\theta$ is in the denominator, the directrix is $x=p$. Comparing to standard form, $e=\frac{5}{4}$ . Therefore, from the numerator,

$$\begin{aligned}3&=ep\\3&=\frac{5}{4}p\\\left(\frac{4}{5}\right)3&=\left(\frac{4}{5}\right)\frac{5}{4}p\\\frac{12}{5}&=p\end{aligned}$$

Since $e>1$ , the conic is a **hyperbola**. The eccentricity is $e=\frac{5}{4}$ and the directrix is $x=\frac{12}{5}=2.4$.

c. Multiply the numerator and denominator by $\frac{1}{2}$.

$$r=\frac{7}{2-2\sin\theta}\cdot\frac{\left(\frac{1}{2}\right)}{\left(\frac{1}{2}\right)}$$

$$r=\frac{7\left(\frac{1}{2}\right)}{2\left(\frac{1}{2}\right)-2\left(\frac{1}{2}\right)\sin\theta}$$

$$r=\frac{\frac{7}{2}}{1-\sin\theta}$$

Because sine is in the denominator, the directrix is $y=-p$. Comparing to standard form, $e=1$. Therefore, from the numerator,

$$\frac{7}{2}=ep$$
$$\frac{7}{2}=(1)p$$
$$\frac{7}{2}=p$$

Because $e=1$, the conic is a parabola. The eccentricity is $e=1$ and the directrix is $y=-\frac{7}{2}=-3.5$.

**Exercise 9.8.1**

Identify the conic with focus at the origin, the directrix, and the eccentricity for $r=\frac{2}{3-\cos\theta}$.

**Answer**

ellipse; $e=\frac{1}{3}$; $x=-2$

## Graphing the Polar Equations of Conics

When graphing in Cartesian coordinates, each conic section has a unique equation. This is not the case when graphing in polar coordinates. We must use the eccentricity of a conic section to determine which type of curve to graph, and then determine its specific characteristics. The first step is to rewrite the conic in standard form as we have done in the previous example. In other words, we need to rewrite the equation so that the denominator begins with 1. This enables us to determine $e$ and, therefore, the shape of the curve. The next step is to substitute values for $\theta$ and solve for $r$ to plot a few key points. Setting $\theta$ equal to $0$, $\frac{\pi}{2}$, $\pi$, and $\frac{3\pi}{2}$ provides the vertices so we can create a rough sketch of the graph.

**Example 9.8.2A: Graphing a Parabola in Polar Form**

Graph $r=\frac{5}{3+3\cos\theta}$.

**Solution**

First, we rewrite the conic in standard form by multiplying the numerator and denominator by the reciprocal of 3, which is $\frac{1}{3}$.

$$r = \frac{5}{3+3\cos\theta} = \frac{5\left(\frac{1}{3}\right)}{3\left(\frac{1}{3}\right)+3\left(\frac{1}{3}\right)\cos\theta}$$

$$r = \frac{\frac{5}{3}}{1+\cos\theta}$$

Because $e = 1$ ,we will graph a **parabola** with a focus at the origin. The function has a $\cos\theta$, and there is an addition sign in the denominator, so the directrix is $x = p$.

$$\frac{5}{3} = ep$$
$$\frac{5}{3} = (1)p$$
$$\frac{5}{3} = p$$

The directrix is $x = \frac{5}{3}$.

Plotting a few key points as in Table 9.8.1 will enable us to see the vertices. See Figure 9.8.3.

Table 9.8.1

| | A | B | C | D |
|---|---|---|---|---|
| $\theta$ | $0$ | $\frac{\pi}{2}$ | $\pi$ | $\frac{3\pi}{2}$ |
| $r = \frac{5}{3+3\cos\theta}$ | $\frac{5}{6} \approx 0.83$ | $\frac{5}{3} \approx 1.67$ | undefined | $\frac{5}{3} \approx 1.67$ |





Figure 9.8.3

We can check our result with a graphing utility. See Figure 9.8.4.





Figure 9.8.4

**Example 9.8.2B: Graphing a Hyperbola in Polar Form**

Graph $r = \dfrac{8}{2 - 3\sin\theta}$.

**Solution**

First, we rewrite the conic in standard form by multiplying the numerator and denominator by the reciprocal of 2, which is $\frac{1}{2}$.

$$r = \frac{8}{2 - 3\sin\theta} = \frac{8\left(\frac{1}{2}\right)}{2\left(\frac{1}{2}\right) - 3\left(\frac{1}{2}\right)\sin\theta}$$

$$r = \frac{4}{1 - \frac{3}{2}\sin\theta}$$

Because $e = \frac{3}{2}$, $e > 1$, so we will graph a hyperbola with a focus at the origin. The function has a $\sin\theta$ term and there is a subtraction sign in the denominator, so the directrix is $y = -p$.

$$4 = ep$$
$$4 = \left(\frac{3}{2}\right)p$$
$$4\left(\frac{2}{3}\right) = p$$
$$\frac{8}{3} = p$$

The directrix is $y = -\frac{8}{3}$.

Plotting a few key points as in Table 9.8.2 will enable us to see the vertices. See Figure 9.8.5.

Table 9.8.2

| | A | B | C | D |
|---|---|---|---|---|
| $\theta$ | 0 | $\frac{\pi}{2}$ | $\pi$ | $\frac{3\pi}{2}$ |
| $r = \frac{8}{2 - 3\sin\theta}$ | 4 | $-8$ | 4 | $\frac{8}{5} = 1.6$ |





Figure 9.8.5

## Example 9.8.2C: Graphing an Ellipse in Polar Form

Graph $r = \dfrac{10}{5 - 4\cos\theta}$.

### Solution

First, we rewrite the conic in standard form by multiplying the numerator and denominator by the reciprocal of 5, which is $\frac{1}{5}$.

$$r = \frac{10}{5 - 4\cos\theta} = \frac{10\left(\frac{1}{5}\right)}{5\left(\frac{1}{5}\right) - 4\left(\frac{1}{5}\right)\cos\theta}$$

$$r = \frac{2}{1 - \frac{4}{5}\cos\theta}$$

Because $e = \frac{4}{5}$, $e < 1$, so we will graph an **ellipse** with a **focus** at the origin. The function has a $\cos\theta$, and there is a subtraction sign in the denominator, so the **directrix** is $x = -p$.

$$2 = ep$$
$$2 = \left(\frac{4}{5}\right)p$$
$$2\left(\frac{5}{4}\right) = p$$
$$\frac{5}{2} = p$$

The directrix is $x = -\frac{5}{2}$.

Plotting a few key points as in Table 9.8.3 will enable us to see the vertices. See Figure 9.8.6.

Table 9.8.3

| | A | B | C | D |
|---|---|---|---|---|
| $\theta$ | 0 | $\frac{\pi}{2}$ | $\pi$ | $\frac{3\pi}{2}$ |

| | A | B | C | D |
|---|---|---|---|---|
| $r = \dfrac{10}{5 - 4\cos\theta}$ | 10 | 2 | $\dfrac{10}{9} \approx 1.1$ | 2 |





Figure 9.8.6

**Analysis**

We can check our result using a graphing utility. See Figure 9.8.7.




Figure 9.8.6: $r = \dfrac{10}{5 - 4\cos\theta}$ graphed on a viewing window of $[-3, 12, 1]$ by $[-4, 4, 1]$, $\theta min = 0$ and $\theta max = 2\pi$.

**? Exercise 9.8.2**

Graph $r = \dfrac{2}{4 - \cos\theta}$.

**Answer**





Figure 9.8.7

## Defining Conics in Terms of a Focus and a Directrix

So far we have been using polar equations of conics to describe and graph the curve. Now we will work in reverse; we will use information about the origin, eccentricity, and directrix to determine the polar equation.

**How to: Given the focus, eccentricity, and directrix of a conic, determine the polar equation**

1. Determine whether the directrix is horizontal or vertical. If the directrix is given in terms of $y$, we use the general polar form in terms of sine. If the directrix is given in terms of $x$, we use the general polar form in terms of cosine.
2. Determine the sign in the denominator. If $p < 0$, use subtraction. If $p > 0$, use addition.
3. Write the coefficient of the trigonometric function as the given eccentricity.
4. Write the absolute value of $p$ in the numerator, and simplify the equation.

**Example $9.8.3A$: Finding the Polar Form of a Vertical Conic Given a Focus at the Origin and the Eccentricity and Directrix**

Find the polar form of the conic given a focus at the origin, $e = 3$ and directrix $y = -2$.

**Solution**

The directrix is $y = -p$, so we know the trigonometric function in the denominator is sine.

Because $y = -2, -2 < 0$, so we know there is a subtraction sign in the denominator. We use the standard form of

$$r = \frac{ep}{1 - e\sin\theta}$$

and $e = 3$ and $|-2| = 2 = p$.

Therefore,

$$r = \frac{(3)(2)}{1 - 3\sin\theta}$$
$$r = \frac{6}{1 - 3\sin\theta}$$

**Example $9.8.3B$: Finding the Polar Form of a Horizontal Conic Given a Focus at the Origin and the Eccentricity and Directrix**

Find the polar form of a conic given a focus at the origin, $e = \frac{3}{5}$, and directrix $x = 4$.

**Solution**

Because the directrix is $x = p$, we know the function in the denominator is cosine. Because $x = 4$, $4 > 0$, so we know there is an addition sign in the denominator. We use the standard form of

$$r = \frac{ep}{1 + e\cos\theta}$$

and $e = \frac{3}{5}$ and $|4| = 4 = p$.

Therefore,

$$r = \frac{\left(\frac{3}{5}\right)(4)}{1 + \frac{3}{5}\cos\theta}$$

$$r = \frac{\frac{12}{5}}{1 + \frac{3}{5}\cos\theta}$$

$$r = \frac{\frac{12}{5}}{1\left(\frac{5}{5}\right) + \frac{3}{5}\cos\theta}$$

$$r = \frac{\frac{12}{5}}{\frac{5}{5} + \frac{3}{5}\cos\theta}$$

$$r = \frac{12}{5} \cdot \frac{5}{5 + 3\cos\theta}$$

$$r = \frac{12}{5 + 3\cos\theta}$$

**Exercise 9.8.3**

Find the polar form of the conic given a focus at the origin, $e = 1$, and directrix $x = -1$.

**Answer**

$$r = \frac{1}{1 - \cos\theta}$$

**Example 9.8.4: Converting a Conic in Polar Form to Rectangular Form**

Convert the conic $r = \frac{1}{5 - 5\sin\theta}$ to rectangular form.

**Solution**

We will rearrange the formula to use the identities $r = \sqrt{x^2 + y^2}$, $x = r\cos\theta$,and $y = r\sin\theta$.

$$
\begin{aligned}
r &= \frac{1}{5-5\sin\theta} \\
r\cdot(5-5\sin\theta) &= \frac{1}{5-5\sin\theta}\cdot(5-5\sin\theta) && \text{Eliminate the fraction.} \\
5r-5r\sin\theta &= 1 && \text{Distribute.} \\
5r &= 1+5r\sin\theta && \text{Isolate } 5r. \\
25r^2 &= (1+5r\sin\theta)^2 && \text{Square both sides.} \\
25(x^2+y^2) &= (1+5y)^2 && \text{Substitute } r=\sqrt{x^2+y^2} \text{ and } y=r\sin\theta. \\
25x^2+25y^2 &= 1+10y+25y^2 && \text{Distribute and use FOIL.} \\
25x^2-10y &= 1 && \text{Rearrange terms and set equal to 1.}
\end{aligned}
$$

**Exercise 9.8.4**

Convert the conic $r=\dfrac{2}{1+2\cos\theta}$ to rectangular form.

**Answer**

$4-8x+3x^2-y^2=0$

**Media**

Access these online resources for additional instruction and practice with conics in polar coordinates.

- Polar Equations of Conic Sections
- Graphing Polar Equations of Conics - 1
- Graphing Polar Equations of Conics - 2

Visit this website for additional practice questions from Learningpod.

## Key Concepts

- Any conic may be determined by a single focus, the corresponding eccentricity, and the directrix. We can also define a conic in terms of a fixed point, the focus $P(r,\theta)$ at the pole, and a line, the directrix, which is perpendicular to the polar axis.
- A conic is the set of all points $e=\dfrac{PF}{PD}$, where eccentricity $e$ is a positive real number. Each conic may be written in terms of its polar equation. See Example 9.8.1.
- The polar equations of conics can be graphed. See Example 9.8.2, Example 9.8.3, and Example 9.8.4.
- Conics can be defined in terms of a focus, a directrix, and eccentricity. See Example 9.8.5 and Example 9.8.6.
- We can use the identities $r=\sqrt{x^2+y^2}$, $x=r\cos\theta$, and $y=r\sin\theta$ to convert the equation for a conic from polar to rectangular form. See Example 9.8.7.

This page titled 9.8: Conic Sections in Polar Coordinates is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **12.5: Conic Sections in Polar Coordinates** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.8E: Conic Sections in Polar Coordinates (Exercises)

For the following exercises, given the polar equation of the conic with focus at the origin, identify the eccentricity and directrix.

41. $r = \frac{10}{1-5\cos\theta}$

42. $r = \frac{6}{3+2\cos\theta}$

43. $r = \frac{1}{4+3\sin\theta}$

44. $r = \frac{3}{5-5}\sin\theta$

For the following exercises, graph the conic given in polar form. If it is a parabola, label the vertex, focus, and directrix. If it is an ellipse or a hyperbola, label the vertices and foci.

45. $r = \frac{3}{1-\sin\theta}$

46. $r = \frac{8}{4+3}\sin\theta$

47. $r = \frac{10}{4+5\cos\theta}$

48. $r = \frac{9}{3-6\cos\theta}$

For the following exercises, given information about the graph of a conic with focus at the origin, find the equation in polar form.

49. Directrix is $x = 3$ and eccentricity $e = 1$

50. Directrix is $y = -2$ and eccentricity $e = 4$

This page titled 9.8E: Conic Sections in Polar Coordinates (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **12.5E: Conic Sections in Polar Coordinates (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.9: Counting Principles

**Learning Objectives**

- Solve counting problems using the Addition Principle.
- Solve counting problems using the Multiplication Principle.
- Solve counting problems using permutations involving n distinct objects.
- Solve counting problems using combinations.
- Find the number of subsets of a given set.
- Solve counting problems using permutations involving n non-distinct objects.

A new company sells customizable cases for tablets and smartphones. Each case comes in a variety of colors and can be personalized for an additional fee with images or a monogram. A customer can choose not to personalize or could choose to have one, two, or three images or a monogram. The customer can choose the order of the images and the letters in the monogram. The company is working with an agency to develop a marketing campaign with a focus on the huge number of options they offer. Counting the possibilities is challenging!

We encounter a wide variety of counting problems every day. There is a branch of mathematics devoted to the study of counting problems such as this one. Other applications of counting include secure passwords, horse racing outcomes, and college scheduling choices. We will examine this type of mathematics in this section.

## Using the Addition Principle

The company that sells customizable cases offers cases for tablets and smartphones. There are 3 supported tablet models and 5 supported smartphone models. The **Addition Principle** tells us that we can add the number of tablet options to the number of smartphone options to find the total number of options. By the Addition Principle, there are 8 total options, as we can see in Figure 9.9.1.




Figure 9.9.1

**THE ADDITION PRINCIPLE**

According to the *Addition Principle*, if one event can occur in $m$ ways and a second event with no common outcomes can occur in $n$ ways, then the first *or* second event can occur in $m+n$ ways.

**Example 9.9.1: Using the Addition Principle**

There are 2 vegetarian entrée options and 5 meat entrée options on a dinner menu. What is the total number of entrée options?

**Solution**

We can add the number of vegetarian options to the number of meat options to find the total number of entrée options.

The addition of the type of options for an entree.

There are 7 total options.

**Exercise 9.9.1**

A student is shopping for a new computer. He is deciding among 3 desktop computers and 4 laptop computers. What is the total number of computer options?

**Answer**

7

## Using the Multiplication Principle

The **Multiplication Principle** applies when we are making more than one selection. Suppose we are choosing an appetizer, an entrée, and a dessert. If there are 2 appetizer options, 3 entrée options, and 2 dessert options on a fixed-price dinner menu, there are a total of 12 possible choices of one each as shown in the tree diagram in Figure 9.9.2.





Figure 9.9.2

The possible choices are:

1. soup, chicken, cake
2. soup, chicken, pudding
3. soup, fish, cake
4. soup, fish, pudding
5. soup, steak, cake
6. soup, steak, pudding

7. salad, chicken, cake
8. salad, chicken, pudding
9. salad, fish, cake
10. salad, fish, pudding
11. salad, steak, cake
12. salad, steak, pudding We can also find the total number of possible dinners by multiplying.

We could also conclude that there are 12 possible dinner choices simply by applying the Multiplication Principle.

$$\#\text{of appetizer options} \times \#\text{of entree options} \times \#\text{of dessert options}$$

$$2 \times 3 \times 2 = 12$$

**THE MULTIPLICATION PRINCIPLE**

According to the Multiplication Principle, if one event can occur in $m$ ways and a second event can occur in $n$ ways after the first event has occurred, then the two events can occur in $m \times n$ ways. This is also known as the Fundamental Counting Principle.

**Example 9.9.2: Using the Multiplication Principle**

Diane packed 2 skirts, 4 blouses, and a sweater for her business trip. She will need to choose a skirt and a blouse for each outfit and decide whether to wear the sweater. Use the Multiplication Principle to find the total number of possible outfits.

**Solution**

To find the total number of outfits, find the product of the number of skirt options, the number of blouse options, and the number of sweater options.

| # of skirt options | × | # of blouse options | × | # of sweater options | |
|---|---|---|---|---|---|
| 2 | × | 4 | × | 2 | = 16 |

There are 16 possible outfits.

**Exercise 9.9.2**

A restaurant offers a breakfast special that includes a breakfast sandwich, a side dish, and a beverage. There are 3 types of breakfast sandwiches, 4 side dish options, and 5 beverage choices. Find the total number of possible breakfast specials.

**Answer**

There are 60 possible breakfast specials.

## Finding the Number of Permutations of $n$ Distinct Objects

The Multiplication Principle can be used to solve a variety of problem types. One type of problem involves placing objects in order. We arrange letters into words and digits into numbers, line up for photographs, decorate rooms, and more. An ordering of objects is called a permutation.

### Finding the Number of Permutations of $n$ Distinct Objects Using the Multiplication Principle

To solve permutation problems, it is often helpful to draw line segments for each option. That enables us to determine the number of each option so we can multiply. For instance, suppose we have four paintings, and we want to find the number of ways we can hang three of the paintings in order on the wall. We can draw three lines to represent the three places on the wall.

$$\_\_\_\_ \times \_\_\_\_ \times \_\_\_\_$$

There are four options for the first place, so we write a 4 on the first line.

$$4 \times \_\_\_\_ \times \_\_\_\_$$

After the first place has been filled, there are three options for the second place so we write a 3 on the second line.

$$4 \times 3 \times \_\_\_\_$$

After the second place has been filled, there are two options for the third place so we write a 2 on the third line. Finally, we find the product.

$$4 \times 3 \times 2 = 24$$

There are 24 possible permutations of the paintings.

**How to: Given $n$ distinct options, determine how many permutations there are.**

1. Determine how many options there are for the first situation.
2. Determine how many options are left for the second situation.
3. Continue until all of the spots are filled.
4. Multiply the numbers together.

**Example 9.9.3: Finding the Number of Permutations Using the Multiplication Principle**

At a swimming competition, nine swimmers compete in a race.

a. How many ways can they place first, second, and third?
b. How many ways can they place first, second, and third if a swimmer named Ariel wins first place? (Assume there is only one contestant named Ariel.)
c. How many ways can all nine swimmers line up for a photo?

**Solution**

a. Draw lines for each place.

| options for 1st place | × | options for 2nd place | × | options for 3rd place |
|---|---|---|---|---|

There are 9 options for first place. Once someone has won first place, there are 8 remaining options for second place. Once first and second place have been won, there are 7 remaining options for third place.

| 9 | × | 8 | × | 7 | = 504 |
|---|---|---|---|---|---|

Multiply to find that there are 504 ways for the swimmers to place.

b. Draw lines for describing each place.

options for 1st place × options for 2nd place × options for 3rd place

We know Ariel must win first place, so there is only 1 option for first place. There are 8 remaining options for second place, and then 7 remaining options for third place.

1 × 8 × 7 = 56

Multiply to find that there are 56 ways for the swimmers to place if Ariel wins first.

c. Draw lines for describing each place in the photo.

____ × ____ × ____ × ____ × ____ × ____ × ____ × ____ × ____

There are 9 choices for the first spot, then 8 for the second, 7 for the third, 6 for the fourth, and so on until only 1 person remains for the last spot.

9 × 8 × 7 × 6 × 5 × 4 × 3 × 2 × 1 = 362,880

There are $362,880$ possible permutations for the swimmers to line up.

**Analysis**

Note that in part c, we found there were $9!$ ways for 9 people to line up. The number of permutations of $n$ distinct objects can always be found by $n!$.

**? Exercise 9.9.3A**

A family of five is having portraits taken. Use the Multiplication Principle to find the following:

a. How many ways can the family line up for the portrait?
b. How many ways can the photographer line up 3 family members?
c. How many ways can the family line up for the portrait if the parents are required to stand on each end?

**Answer a**

120

**Answer b**

60

**Answer c**

12

### Finding the Number of Permutations of *n* Distinct Objects Using a Formula

For some permutation problems, it is inconvenient to use the Multiplication Principle because there are so many numbers to multiply. Fortunately, we can solve these problems using a formula. Before we learn the formula, let's look at two common notations for permutations. If we have a set of $n$ objects and we want to choose $r$ objects from the set in order, we write $P(n,r)$. Another way to write this is ${}_nP_r$, a notation commonly seen on computers and calculators. To calculate $P(n,r)$, we begin by finding $n!$, the number of ways to line up all nn objects. We then divide by $(n-r)!$ to cancel out the $(n-r)$ items that we do not wish to line up.

Let's see how this works with a simple example. Imagine a club of six people. They need to elect a president, a vice president, and a treasurer. Six people can be elected president, any one of the five remaining people can be elected vice president, and any of the remaining four people could be elected treasurer. The number of ways this may be done is $6\times5\times4=120$ . Using factorials, we get the same result.

$$\frac{6!}{3!}=\frac{6\cdot5\cdot4\cdot3!}{3!}=6\cdot5\cdot4=120$$

There are 120 ways to select 3 officers in order from a club with 6 members. We refer to this as a permutation of 6 taken 3 at a time. The general formula is as follows.

$$P(n,r)=\frac{n!}{(n-r)!} \tag{9.9.1}$$

Note that the formula stills works if we are choosing all $n$ objects and placing them in order. In that case we would be dividing by $(n-n)!$ or $0!$, which we said earlier is equal to 1. So the number of permutations of $n$ objects taken $n$ at a time is $\frac{n!}{1}$ or just $n!$.

**Note: FORMULA FOR PERMUTATIONS OF *N* DISTINCT OBJECTS**

Given $n$ distinct objects, the number of ways to select $r$ objects from the set in order is

$$P(n,r)=\frac{n!}{(n-r)!} \tag{9.9.2}$$

**How to: Given a word problem, evaluate the possible permutations.**

1. Identify $n$ from the given information.
2. Identify $r$ from the given information.
3. Replace $n$ and $r$ in the formula with the given values.
4. Evaluate.

**Example 9.9.4: Finding the Number of Permutations Using the Formula**

A professor is creating an exam of 9 questions from a test bank of 12 questions. How many ways can she select and arrange the questions?

**Solution**

Substitute $n=12$ and $r=9$ into the permutation formula and simplify.

$$\begin{aligned}P(n,r)&=\frac{n!}{(n-r)!}\\P(12,9)&=\frac{12!}{(12-9)!}\\&=\frac{12!}{3!}\\&=79,833,600\end{aligned}$$

There are $79,833,600$possible permutations of exam questions!

**Analysis**

We can also use a calculator to find permutations. For this problem, we would enter $12$, press the $nP_r$ function, enter $9$, and then press the equal sign. The $nP_r$ function may be located under the MATH menu with probability commands.

**Q&A**

**Could we have solved the example above using the Multiplication Principle?**

Yes. We could have multiplied $15 \cdot 14 \cdot 13 \cdot 12 \cdot 11 \cdot 10 \cdot 9 \cdot 8 \cdot 7 \cdot 6 \cdot 5 \cdot 4$ to find the same answer.

**Exercise $9.9.4A$**

A play has a cast of $7$ actors preparing to make their curtain call. Use the permutation formula to find the following.

How many ways can the $7$ actors line up?

**Answer**

$P(7,7) = 5,040$

**Exercise $9.9.4B$**

How many ways can $5$ of the $7$ actors be chosen to line up?

**Answer**

$P(7,5) = 2,520$

### Find the Number of Combinations Using the Formula

So far, we have looked at problems asking us to put objects in order. There are many problems in which we want to select a few objects from a group of objects, but we do not care about the order. When we are selecting objects and the order does not matter, we are dealing with **combinations**. A selection of $r$ objects from a set of $n$ objects where the order does not matter can be written as $C(n,r)$. Just as with permutations, $C(n,r)$ can also be written as $nC_r$. In this case, the general formula is as follows.

$$C(n,r) = \frac{n!}{r!(n-r)!} \tag{9.9.3}$$

An earlier problem considered choosing $3$ of $4$ possible paintings to hang on a wall. We found that there were $24$ ways to select $3$ of the $4$ paintings in order. But what if we did not care about the order? We would expect a smaller number because selecting paintings $1, 2, 3$ would be the same as selecting paintings $2, 3, 1$. To find the number of ways to select $3$ of the $4$ paintings, disregarding the order of the paintings, divide the number of permutations by the number of ways to order $3$ paintings. There are $3! = 3 \cdot 2 \cdot 1 = 6$ ways to order $3$ paintings. There are $\frac{24}{6}$, or $4$ ways to select $3$ of the $4$ paintings. This number makes sense because every time we are selecting $3$ paintings, we are *not* selecting $1$ painting. There are $4$ paintings we could choose *not* to select, so there are $4$ ways to select $3$ of the $4$ paintings.

**Note: FORMULA FOR COMBINATIONS OF *N* DISTINCT OBJECTS**

Given $n$ distinct objects, the number of ways to select $r$ objects from the set is

$$C(n,r) = \frac{n!}{r!(n-r)!} \tag{9.9.4}$$

**How to: Given a number of options, determine the possible number of combinations.**

1. Identify $n$ from the given information.
2. Identify $r$ from the given information.
3. Replace $n$ and $r$ in the formula with the given values.
4. Evaluate.

**Example $9.9.5$: Finding the Number of Combinations Using the Formula**

A fast food restaurant offers five side dish options. Your meal comes with two side dishes.

a. How many ways can you select your side dishes?
b. How many ways can you select $3$ side dishes?

**Solution**

a. We want to choose $2$ side dishes from $5$ options.

$$C(5,2) = \frac{5!}{2!(5-2)!} = 10$$

b. We want to choose $3$ side dishes from $5$ options.

$$C(5,3) = \frac{5!}{3!(5-3)!} = 10$$

**Analysis**

We can also use a graphing calculator to find combinations. Enter $5$, then press $nC_r$, enter $3$, and then press the equal sign. The $nC_r$, function may be located under the MATH menu with probability commands.

**Q&A**

**Is it a coincidence that parts (a) and (b) in the example above have the same answers?**

No. When we choose r objects from n objects, we are **not** choosing $(n-r)$ objects. Therefore, $C(n,r) = C(n,n-r)$.

**Exercise 9.9.5**

An ice cream shop offers 10 flavors of ice cream. How many ways are there to choose 3 flavors for a banana split?

**Answer**

$C(10,3)=120$

### Finding the Number of Subsets of a Set

We have looked only at combination problems in which we chose exactly rr objects. In some problems, we want to consider choosing every possible number of objects. Consider, for example, a pizza restaurant that offers 5 toppings. Any number of toppings can be ordered. How many different pizzas are possible?

To answer this question, we need to consider pizzas with any number of toppings. There is $C(5,0)=1$ way to order a pizza with no toppings. There are $C(5,1)=5$ ways to order a pizza with exactly one topping. If we continue this process, we get

$$C(5,0)+C(5,1)+C(5,2)+C(5,3)+C(5,4)+C(5,5)=32$$

There are 32 possible pizzas. This result is equal to $2^5$.

We are presented with a sequence of choices. For each of the nn objects we have two choices: include it in the subset or not. So for the whole subset we have made nn choices, each with two options. So there are a total of $2\cdot 2\cdot 2\cdot\ldots\cdot 2$ possible resulting subsets, all the way from the empty subset, which we obtain when we say "no" each time, to the original set itself, which we obtain when we say "yes" each time.

**Note: FORMULA FOR THE NUMBER OF SUBSETS OF A SET**

A set containing $n$ distinct objects has $2^n$ subsets.

**Example 9.9.6: Finding the Number of Subsets of a Set**

A restaurant offers butter, cheese, chives, and sour cream as toppings for a baked potato. How many different ways are there to order a potato?

**Solution**

We are looking for the number of subsets of a set with 4 objects. Substitute $n=4$ into the formula.

$$\begin{aligned}2^n &= 2^4\\ &= 16\end{aligned}$$

There are 16 possible ways to order a potato.

**Exercise 9.9.6**

A sundae bar at a wedding has 6 toppings to choose from. Any number of toppings can be chosen. How many different sundaes are possible?

**Answer**

64 sundaes

### Finding the Number of Permutations of *n* Non-Distinct Objects

We have studied permutations where all of the objects involved were distinct. What happens if some of the objects are indistinguishable? For example, suppose there is a sheet of 12 stickers. If all of the stickers were distinct, there would be 12! ways to order the stickers. However, 4 of the stickers are identical stars, and 3 are identical moons. Because all of the objects are not distinct, many of the 12! permutations we counted are duplicates. The general formula for this situation is as follows.

$$\frac{n!}{r_1!r_2!\ldots r_k!} \tag{9.9.5}$$

In this example, we need to divide by the number of ways to order the 4 stars and the ways to order the 3 moons to find the number of unique permutations of the stickers. There are 4! ways to order the stars and 3! ways to order the moon.

$$\frac{12!}{4!3!}=3,326,400$$

There are $3,326,400$ways to order the sheet of stickers.

**Note: FORMULA FOR FINDING THE NUMBER OF PERMUTATIONS OF $N$ NON-DISTINCT OBJECTS**

If there are nn elements in a set and $r_1$ are alike, $r_2$ are alike, $r_3$ are alike, and so on through $r_k$, the number of permutations can be found by

$$\frac{n!}{r_1!r_2!\ldots r_k!} \tag{9.9.6}$$

**Example 9.9.7: Finding the Number of Permutations of $n$ Non-Distinct Objects**

Find the number of rearrangements of the letters in the word DISTINCT.

**Solution**

There are 8 letters. Both $I$ and $T$ are repeated 2 times. Substitute $n=8$, $r_1=2$, and $r_2=2$ into the formula.

$$\frac{8!}{2!2!}=10,080$$

There are $10,080$arrangements.

**Exercise 9.9.7**

Find the number of rearrangements of the letters in the word CARRIER.

**Answer**

840

Media

Access these online resources for additional instruction and practice with combinations and permutations.

- Combinations
- Permutations

## Key Equations

| | |
|---|---|
| number of permutations of $n$ distinct objects taken $r$ at a time | $P(n,r)=\frac{n!}{(n-r)!}$ |
| number of combinations of $n$ distinct objects taken $r$ at a time | $C(n,r)=\frac{n!}{r!(n-r)!}$ |
| number of permutations of $n$ non-distinct objects | $\frac{n!}{r1!r2!\ldots rk!}$ |

## Key Concepts

- If one event can occur in $m$ ways and a second event with no common outcomes can occur in $n$ ways, then the first or second event can occur in $m+n$ ways. See Example $9.9.1$.
- If one event can occur in $m$ ways and a second event can occur in $n$ ways after the first event has occurred, then the two events can occur in $m\times n$ ways. See Example $9.9.2$.
- A permutation is an ordering of $n$ objects.
- If we have a set of $n$ objects and we want to choose $r$ objects from the set in order, we write $P(n,r)$.
- Permutation problems can be solved using the Multiplication Principle or the formula for $P(n,r)$. See Example $9.9.3$ and Example $9.9.4$.
- A selection of objects where the order does not matter is a combination.
- Given $n$ distinct objects, the number of ways to select $r$ objects from the set is $C(n,r)$ and can be found using a formula. See Example $9.9.5$.
- A set containing $n$ distinct objects has $2n$ subsets. See Example $9.9.6$.
- For counting problems involving non-distinct objects, we need to divide to avoid counting duplicate permutations. See Example $9.9.7$.

## Contributors and Attributions

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.

This page titled 9.9: Counting Principles is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.5: Counting Principles** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.9E: Counting Principles (Exercises)

31. How many ways are there to choose a number from the set \{-10,-6,4,10,12,18,24,32\} that is divisible by either 4 or 6?

32. In a group of 20 musicians, 12 play piano, 7 play trumpet, and 2 play both piano and trumpet. How many musicians play either piano or trumpet?

33. How many ways are there to construct a 4 -digit code if numbers can be repeated?

34. A palette of water color paints has 3 shades of green, 3 shades of blue, 2 shades of red, 2 shades of yellow, and 1 shade of black. How many ways are there to choose one shade of each color?

35. Calculate $P(18,4)$.

36. In a group of 5 freshman, 10 sophomores, 3 juniors, and 2 seniors, how many ways can a president, vice president, and treasurer be elected?

37. Calculate $C(15,6)$.

38. A coffee shop has 7 Guatemalan roasts, 4 Cuban roasts, and 10 Costa Rican roasts. How many ways can the shop choose 2 Guatemalan, 2 Cuban, and 3 Costa Rican roasts for a coffee tasting event?

39. How many subsets does the set $\{1,3,5,\ldots,99\}$have?

40. A day spa charges a basic day rate that includes use of a sauna, pool, and showers. For an extra charge, guests can choose from the following additional services: massage, body scrub, manicure, pedicure, facial, and straight-razor shave. How many ways are there to order additional services at the day spa?

41. How many distinct ways can the word DEADWOOD be arranged?

42. How many distinct rearrangements of the letters of the word DEADWOOD are there if the arrangement must begin and end with the letter D?

This page titled 9.9E: Counting Principles (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.5E: Counting Principles (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.10: Binomial Theorem

**Learning Objectives**

- Apply the Binomial Theorem.

A polynomial with two terms is called a binomial. We have already learned to multiply binomials and to raise binomials to powers, but raising a binomial to a high power can be tedious and time-consuming. In this section, we will discuss a shortcut that will allow us to find $(x+y)^n$ without multiplying the binomial by itself $n$ times.

## Identifying Binomial Coefficients

In the shortcut to finding $(x+y)^n$, we will need to use combinations to find the coefficients that will appear in the expansion of the binomial. In this case, we use the notation $\binom{n}{r}$ instead of $C(n,r)$, but it can be calculated in the same way. So

$$\binom{n}{r} = C(n,r) = \frac{n!}{r!(n-r)!} \tag{9.10.1}$$

The combination $\binom{n}{r}$ is called a *binomial coefficient*. An example of a binomial coefficient is:

$$\binom{5}{2} = C(5,2) = 10$$

**Definition: BINOMIAL COEFFICIENTS**

If $n$ and $r$ are integers greater than or equal to 0 with $n \geq r$, then the *binomial coefficient* is

$$\binom{n}{r} = C(n,r) = \frac{n!}{r!(n-r)!} \tag{9.10.2}$$

**Q&A: Is a binomial coefficient always a whole number?**

*Yes. Just as the number of combinations must always be a whole number, a binomial coefficient will always be a whole number.*

**Example 9.10.1: Finding Binomial Coefficients**

Find each binomial coefficient.

a. $\binom{5}{3}$
b. $\binom{9}{2}$
c. $\binom{9}{7}$

**Solution**

Use the Equation 9.10.2 to calculate each binomial coefficient. You can also use the $nC_r$ function on your calculator.

a. $\binom{5}{3} = \frac{5!}{3!(5-3)!} = \frac{5 \cdot 4 \cdot 3!}{3!2!} = 10$
b. $\binom{9}{2} = \frac{9!}{2!(9-2)!} = \frac{9 \cdot 8 \cdot 7!}{2!7!} = 36$
c. $\binom{9}{7} = \frac{9!}{7!(9-7)!} = \frac{9 \cdot 8 \cdot 7!}{7!2!} = 36$

**Analysis**

Notice that we obtained the same result for parts (b) and (c). If you look closely at the solution for these two parts, you will see that you end up with the same two factorials in the denominator, but the order is reversed, just as with combinations.

$$\binom{n}{r} = \binom{n}{n-r}$$

**Exercise 9.10.1**

Find each binomial coefficient.

a. $\binom{7}{3}$
b. $\binom{11}{4}$

**Answer a**

35

**Answer b**

33

## Using the Binomial Theorem

When we expand $(x+y)^n$ by multiplying, the result is called a binomial expansion, and it includes binomial coefficients. If we wanted to expand $(x+y)^{52}$, we might multiply $(x+y)$ by itself fifty-two times. This could take hours! If we examine some simple binomial expansions, we can find patterns that will lead us to a shortcut for finding more complicated binomial expansions.

$$(x+y)^2 = x^2+2xy+y^2$$
$$(x+y)^3 = x^3+3x^2y+3xy^2+y^3$$
$$(x+y)^4 = x^4+4x^3y+6x^2y^2+4xy^3+y^4$$

First, let's examine the exponents. With each successive term, the exponent for $x$ decreases and the exponent for $y$ increases. The sum of the two exponents is $n$ for each term.

Next, let's examine the coefficients. Notice that the coefficients increase and then decrease in a symmetrical pattern. The coefficients follow a pattern:

$$\binom{n}{0}, \binom{n}{1}, \binom{n}{2}, ..., \binom{n}{n}.$$

These patterns lead us to the **Binomial Theorem**, which can be used to expand any binomial.

$$(x+y)^n = \sum_{k=0}^{n} \binom{n}{k} x^{n-k}y^k$$
$$= x^n + \binom{n}{1}x^{n-1}y + \binom{n}{2}x^{n-2}y^2 + \ldots + \binom{n}{n-1}xy^{n-1} + y^n$$

Another way to see the coefficients is to examine the expansion of a binomial in general form, $x+y$, to successive powers 1, 2, 3, and 4.

$$(x+y)^1 = x+y$$
$$(x+y)^2 = x^2+2xy+y^2$$
$$(x+y)^3 = x^3+3x^2y+3xy^2+y^3$$
$$(x+y)^4 = x^4+4x^3y+6x^2y^2+4xy^3+y^4$$

Can you guess the next expansion for the binomial $(x+y)^5$?





***Figure* 9.10.1**

See Figure 9.10.1, which illustrates the following:

- There are $n+1$ terms in the expansion of $(x+y)^n$.
- The degree (or sum of the exponents) for each term is $n$.
- The powers on $x$ begin with $n$ and decrease to 0.
- The powers on $y$ begin with 0 and increase to $n$.
- The coefficients are symmetric.

To determine the expansion on $(x+y)^5$, we see $n=5$, thus, there will be $5+1=6$ terms. Each term has a combined degree of 5. In descending order for powers of $x$, the pattern is as follows:

- Introduce $x^5$, and then for each successive term reduce the exponent on $x$ by 1 until $x^0=1$ is reached.
- Introduce $y^0=1$, and then increase the exponent on yy by 1 until $y^5$ is reached.

$$x^5, x^4y, x^3y^2, x^2y^3, xy^4, y^5$$

The next expansion would be

$$(x+y)^5 = x^5+5x^4y+10x^3y^2+10x^2y^3+5xy^4+y^5$$

But where do those coefficients come from? The binomial coefficients are symmetric. We can see these coefficients in an array known as Pascal's Triangle, shown in Figure 9.10.2





***Figure* 9.10.2**

To generate Pascal's Triangle, we start by writing a 1. In the row below, row 2, we write two $1's$. In the 3rd row, flank the ends of the rows with $1's$, and add $1+1$ to find the middle number, 2. In the $n^{th}$ row, flank the ends of the row with $1's$. Each element in the triangle is the sum of the two elements immediately above it.

To see the connection between Pascal's Triangle and binomial coefficients, let us revisit the expansion of the binomials in general form.

$$
\begin{array}{ccccccccccc}
 & & & & 1 & & & & & \longrightarrow & (x+y)^0 = 1 \\
 & & & 1 & & 1 & & & & \longrightarrow & (x+y)^1 = x+y \\
 & & 1 & & 2 & & 1 & & & \longrightarrow & (x+y)^2 = x^2+2xy+y^2 \\
 & 1 & & 3 & & 3 & & 1 & & \longrightarrow & (x+y)^3 = x^3+3x^2y+3xy^2+y^3 \\
1 & & 4 & & 6 & & 4 & & 1 & \longrightarrow & (x+y)^4 = x^4+4x^3y+6x^2y^2+4xy^3+y^4 \\
1 & & 5 & & 10 & & 10 & & 5 & \longrightarrow & (x+y)^5 = x^5+5x^4y+10x^3y^2+10x^2y^3+5xy^4+y^5
\end{array}
$$

**THE BINOMIAL THEOREM**

The *Binomial Theorem* is a formula that can be used to expand any binomial.

$$(x+y)^n = \sum_{k=0}^{n} \binom{n}{k} x^{n-k}y^k = x^n + \binom{n}{1}x^{n-1}y + \binom{n}{2}x^{n-2}y^2 + \ldots + \binom{n}{n-1}xy^{n-1} + y^n \tag{9.10.3}$$

**How to: Given a binomial, write it in expanded form.**

1. Determine the value of $n$ according to the exponent.
2. Evaluate the $k=0$ through $k=n$ using the Binomial Theorem formula.
3. Simplify.

**Example 9.10.2: Expanding a Binomial**

Write in expanded form.

a. $(x+y)^5$
b. $(3x-y)^4$

**Solution**

a. Substitute $n=5$ into the formula. Evaluate the $k=0$ through $k=5$ terms. Simplify.

$$\begin{aligned}(x+y)^5 &= \binom{5}{0}x^5y^0 + \binom{5}{1}x^4y^1 + \binom{5}{2}x^3y^2 + \binom{5}{3}x^2y^3 + \binom{5}{4}x^1y^4 + \binom{5}{5}x^0y^5 \\ (x+y)^5 &= x^5 + 5x^4y + 10x^3y^2 + 10x^2y^3 + 5xy^4 + y^5\end{aligned}$$

b. Substitute $n=4$ into the formula. Evaluate the $k=0$ through $k=4$ terms. Notice that $3x$ is in the place that was occupied by $x$ and that $-y$ is in the place that was occupied by $y$. So we substitute them. Simplify.

$$\begin{aligned}(3x-y)^4 &= \binom{4}{0}(3x)^4(-y)^0 + \binom{4}{1}(3x)^3(-y)^1 + \binom{4}{2}(3x)^2(-y)^2 + \binom{4}{3}(3x)^1(-y)^3 + \binom{4}{4}(3x)^0(-y)^4 \\ (3x-y)^4 &= 81x^4 - 108x^3y + 54x^2y^2 - 12xy^3 + y^4\end{aligned}$$

**Analysis**

Notice the alternating signs in part b. This happens because $(-y)$ raised to odd powers is negative, but $(-y)$ raised to even powers is positive. This will occur whenever the binomial contains a subtraction sign.

**Exercise 9.10.2**

Write in expanded form.

a. $(x-y)^5$
b. $(2x+5y)^3$

**Answer a**

$x^5 - 5x^4y + 10x^3y^2 - 10x^2y^3 + 5xy^4 - y^5$

**Answer b**

$8x^3 + 60x^2y + 150xy^2 + 125y^3$

## Using the Binomial Theorem to Find a Single Term

Expanding a binomial with a high exponent such as $(x+2y)^{16}$ can be a lengthy process. Sometimes we are interested only in a certain term of a binomial expansion. We do not need to fully expand a binomial to find a single specific term.

Note the pattern of coefficients in the expansion of $(x+y)^5$.

$$(x+y)^5 = x^5 + \binom{5}{1}x^4y + \binom{5}{2}x^3y^2 + \binom{5}{3}x^2y^3 + \binom{5}{4}xy^4 + y^5$$

The second term is $\binom{5}{1}x^4y$. The third term is $\binom{5}{2}x^3y^2$. We can generalize this result.

**THE $(R+1)$TH TERM OF A BINOMIAL EXPANSION**

The $(r+1)$th term of the binomial expansion of $(x+y)^n$ is:

$$\binom{n}{r}x^{n-r}y^r \tag{9.10.4}$$

**How to: Given a binomial, write a specific term without fully expanding.**

1. Determine the value of nn according to the exponent.
2. Determine $(r+1)$.
3. Determine $r$.
4. Replace $r$ in the formula for the $(r+1)$th term of the binomial expansion.

**Example 9.10.3: Writing a Given Term of a Binomial Expansion**

Find the tenth term of $(x+2y)^{16}$ without fully expanding the binomial.

**Solution**

Because we are looking for the tenth term, $r+1=10$, we will use $r=9$ in our calculations and Equation 9.10.4.

$$\binom{16}{9}x^{16-9}(2y)^9 = 5,857,280x^7y^9$$

**Exercise 9.10.3**

Find the sixth term of $(3x-y)^9$ without fully expanding the binomial.

**Answer**

$-10,206x^4y^5$

**Media**

Access these online resources for additional instruction and practice with binomial expansion.

- The Binomial Theorem
- Binomial Theorem Example

## Key Equations

| | |
|---|---|
| Binomial Theorem | $(x+y)^n = \sum_{k=0}^{n}\binom{n}{k}x^{n-k}y^k$ |
| $(r+1)$ th term of a binomial expansion | $\binom{n}{r}x^{n-r}y^r$ |

## Key Concepts

- $\binom{n}{r}$ is called a binomial coefficient and is equal to $C(n,r)$. See Example 9.10.1.
- The Binomial Theorem allows us to expand binomials without multiplying. See Example 9.10.2.
- We can find a given term of a binomial expansion without fully expanding the binomial. See Example 9.10.3.

## Contributors and Attributions

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.

This page titled 9.10: Binomial Theorem is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.6: Binomial Theorem** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.10E: Binomial Theorem (Exercises)

43. Evaluate the binomial coefficient $\binom{23}{8}$.

44. Use the Binomial Theorem to expand $\left(3x+\frac{1}{2}y\right)^6$.

45. Use the Binomial Theorem to write the first three terms of $(2a+b)^{17}$.

46. Find the fourth term of $\left(3a^2-2b\right)^{11}$ without fully expanding the binomial.

---

This page titled 9.10E: Binomial Theorem (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.6E: Binomial Theorem (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.11: Probability

**Learning Objectives**

- Construct probability models.
- Compute probabilities of equally likely outcomes.
- Compute probabilities of the union of two events.
- Use the complement rule to find probabilities.
- Compute probability using counting theory.

Residents of the Southeastern United States are all too familiar with charts, known as spaghetti models, such as the one in Figure 9.11.1. They combine a collection of weather data to predict the most likely path of a hurricane. Each colored line represents one possible path. The group of squiggly lines can begin to resemble strands of spaghetti, hence the name. In this section, we will investigate methods for making these types of predictions.




***Figure* 9.11.1 :** *An example of a "spaghetti model," which can be used to predict possible paths of a tropical storm.*[1]

## Constructing Probability Models

Suppose we roll a six-sided number cube. Rolling a number cube is an example of an **experiment**, or an activity with an observable result. The numbers on the cube are possible results, or **outcomes**, of this experiment. The set of all possible outcomes of an experiment is called the **sample space** of the experiment. The sample space for this experiment is $\{1, 2, 3, 4, 5, 6\}$ An **event** is any subset of a sample space.

The likelihood of an event is known as probability. The probability of an event pp is a number that always satisfies $0 \le p \le 1$, where $0$ indicates an impossible event and $1$ indicates a certain event. A probability model is a mathematical description of an experiment listing all possible outcomes and their associated probabilities. For instance, if there is a $1\%$ chance of winning a raffle and a $99\%$ chance of losing the raffle, a probability model would look much like Table 9.11.1.

Table 9.11.1

| Outcome | Probability |
|---|---|
| Winning the raffle | 1% |
| Losing the raffle | 99% |

The sum of the probabilities listed in a probability model must equal $1$, or $100\%$.

**How to: Given a probability event where each event is equally likely, construct a probability model.**

1. Identify every outcome.
2. Determine the total number of possible outcomes.
3. Compare each outcome to the total number of possible outcomes.

**Example 9.11.1: Constructing a Probability Model**

Construct a probability model for rolling a single, fair die, with the event being the number shown on the die.

**Solution**

Begin by making a list of all possible outcomes for the experiment. The possible outcomes are the numbers that can be rolled: $1$, $2$, $3$, $4$, $5$, and $6$. There are six possible outcomes that make up the sample space.

Assign probabilities to each outcome in the sample space by determining a ratio of the outcome to the number of possible outcomes. There is one of each of the six numbers on the cube, and there is no reason to think that any particular face is more likely to show up than any other one, so the probability of rolling any number is $16$.

**Table 9.11.2**

| **Outcome** | Roll of 1 | Roll of 2 | Roll of 3 | Roll of 4 | Roll of 5 | Roll of 6 |
|---|---|---|---|---|---|---|
| **Probability** | $\frac{1}{6}$ | $\frac{1}{6}$ | $\frac{1}{6}$ | $\frac{1}{6}$ | $\frac{1}{6}$ | $\frac{1}{6}$ |

**Q&A: Do probabilities always have to be expressed as fractions?**

*No. Probabilities can be expressed as fractions, decimals, or percents. Probability must always be a number between $0$ and $1$, inclusive of $0$ and $1$.*

## Computing Probabilities of Equally Likely Outcomes

Let $S$ be a sample space for an experiment. When investigating probability, an event is any subset of $S$. When the outcomes of an experiment are all equally likely, we can find the probability of an event by dividing the number of outcomes in the event by the total number of outcomes in $S$. Suppose a number cube is rolled, and we are interested in finding the probability of the event "rolling a number less than or equal to 4." There are 4 possible outcomes in the event and 6 possible outcomes in $S$, so the probability of the event is $\frac{4}{6} = \frac{2}{3}$.

**COMPUTING THE PROBABILITY OF AN EVENT WITH EQUALLY LIKELY OUTCOMES**

The probability of an event $E$ in an experiment with sample space $S$ with equally likely outcomes is given by

$$P(E) = \frac{\text{number of elements in } E}{\text{number of elements in } S} = \frac{n(E)}{n(S)} \tag{9.11.1}$$

$E$ is a subset of $S$, so it is always true that $0 \le P(E) \le 1$ .

**Example 9.11.2: Computing the Probability of an Event with Equally Likely Outcomes**

A number cube is rolled. Find the probability of rolling an odd number.

**Solution**

The event "rolling an odd number" contains three outcomes. There are 6 equally likely outcomes in the sample space. Divide to find the probability of the event.

$$P(E) = \frac{3}{6} = \frac{1}{2}$$

**Exercise 9.11.1**

A number cube is rolled. Find the probability of rolling a number greater than 2.

**Answer**

$\frac{2}{3}$

### Computing the Probability of the Union of Two Events

We are often interested in finding the probability that one of multiple events occurs. Suppose we are playing a card game, and we will win if the next card drawn is either a heart or a king. We would be interested in finding the probability of the next card being a heart or a king. The union of two events $E$ and $F$,written $E \cup F$ , is the event that occurs if either or both events occur.

$$P(E \cup F) = P(E) + P(F) - P(E \cap F) \tag{9.11.2}$$

Suppose the spinner in Figure 9.11.2is spun. We want to find the probability of spinning orange or spinning a $b$.





***Figure* 9.11.2:** *A pie chart with six options.*

There are a total of 6 sections, and 3 of them are orange. So the probability of spinning orange is $\frac{3}{6} = \frac{1}{2}$ . There are a total of 6 sections, and 2 of them have a $b$. So the probability of spinning a $b$ is $\frac{2}{6} = \frac{1}{3}$ . If we added these two probabilities, we would be counting the sector that is both orange and a $b$ twice. To find the probability of spinning an orange or a $b$, we need to subtract the probability that the sector is both orange and has a $b$.

$$\frac{1}{2} + \frac{1}{3} - \frac{1}{6} = \frac{2}{3}$$

The probability of spinning orange or a $b$ is $\frac{2}{3}$.

**PROBABILITY OF THE UNION OF TWO EVENTS**

The *probability of the union of two events* $E$ and $F$ (written $E \cup F$ ) equals the sum of the probability of $E$ and the probability of $F$ minus the probability of $E$ and $F$ occurring together (which is called the intersection of $E$ and $F$ and is written as $E \cap F$ ).

$$P(E \cup F) = P(E) + P(F) - P(E \cap F) \tag{9.11.3}$$

**Example 9.11.3: Computing the Probability of the Union of Two Events**

A card is drawn from a standard deck. Find the probability of drawing a heart or a 7.

**Solution**

A standard deck contains an equal number of hearts, diamonds, clubs, and spades. So the probability of drawing a heart is $\frac{1}{4}$. There are four $7s$ in a standard deck, and there are a total of 52 cards. So the probability of drawing a 7 is $\frac{1}{13}$.

The only card in the deck that is both a heart and a 7 is the 7 of hearts, so the probability of drawing both a heart and a 7 is $\frac{1}{52}$. Substitute $P(H) = \frac{1}{4}$, $P(7) = \frac{1}{13}$, and $P(H \cap 7) = \frac{1}{52}$ into the formula.

$$\begin{aligned} P(E \cup F) &= P(E) + P(F) - P(E \cap F) \\ &= \frac{1}{4} + \frac{1}{13} - \frac{1}{52} \\ &= \frac{4}{13} \end{aligned}$$

The probability of drawing a heart or a 7 is $\frac{4}{13}$.

**Exercise 9.11.2**

A card is drawn from a standard deck. Find the probability of drawing a red card or an ace.

**Answer**

$\frac{7}{13}$

### Computing the Probability of Mutually Exclusive Events

Suppose the spinner in Figure 9.11.2 is spun again, but this time we are interested in the probability of spinning an orange or a $d$. There are no sectors that are both orange and contain a $d$, so these two events have no outcomes in common. Events are said to be mutually exclusive events when they have no outcomes in common. Because there is no overlap, there is nothing to subtract, so the general formula is

$$P(E \cap F) = P(E) + P(F) \tag{9.11.4}$$

Notice that with mutually exclusive events, the intersection of $E$ and $F$ is the empty set. The probability of spinning an orange is $\frac{3}{6} = \frac{1}{2}$ and the probability of spinning a $d$ is $\frac{1}{6}$. We can find the probability of spinning an orange or a $d$ simply by adding the two probabilities.

$$\begin{aligned} P(E \cap F) &= P(E) + P(F) \\ &= \frac{1}{2} + \frac{1}{6} \\ &= \frac{2}{3} \end{aligned}$$

The probability of spinning an orange or a $d$ is $\frac{2}{3}$.

**PROBABILITY OF THE UNION OF MUTUALLY EXCLUSIVE EVENTS**

The *probability of the union of two mutually exclusive* events $E$ and $F$ is given by

$$P(E \cap F) = P(E) + P(F) \tag{9.11.5}$$

**How to: Given a set of events, compute the probability of the union of mutually exclusive events.**

1. Determine the total number of outcomes for the first event.
2. Find the probability of the first event.
3. Determine the total number of outcomes for the second event.
4. Find the probability of the second event.
5. Add the probabilities.

**Example 9.11.4: Computing the Probability of the Union of Mutually Exclusive Events**

A card is drawn from a standard deck. Find the probability of drawing a heart or a spade.

**Solution**

The events "drawing a heart" and "drawing a spade" are mutually exclusive because they cannot occur at the same time. The probability of drawing a heart is $\frac{1}{4}$, and the probability of drawing a spade is also $\frac{1}{4}$, so the probability of drawing a heart or a spade is

$$\frac{1}{4} + \frac{1}{4} = \frac{1}{2}$$

**Exercise 9.11.3**

A card is drawn from a standard deck. Find the probability of drawing an ace or a king.

**Answer**

$\frac{2}{13}$

### Using the Complement Rule to Compute Probabilities

We have discussed how to calculate the probability that an event will happen. Sometimes, we are interested in finding the probability that an event will *not* happen. The **complement of an event** $E$, denoted $E'$, is the set of outcomes in the sample space that are not in $E$. For example, suppose we are interested in the probability that a horse will lose a race. If event $W$ is the horse winning the race, then the complement of event $W$ is the horse losing the race.

To find the probability that the horse loses the race, we need to use the fact that the sum of all probabilities in a probability model must be 1.

$$P(E') = 1 - P(E) \tag{9.11.6}$$

The probability of the horse winning added to the probability of the horse losing must be equal to 1. Therefore, if the probability of the horse winning the race is $\frac{1}{9}$, the probability of the horse losing the race is simply

$$1 - \frac{1}{9} = \frac{8}{9}$$

**THE COMPLEMENT RULE**

The probability that the complement of an event will occur is given by

$$P(E') = 1 - P(E) \tag{9.11.7}$$

### Example 9.11.5: Using the Complement Rule to Calculate Probabilities

Two six-sided number cubes are rolled.

a. Find the probability that the sum of the numbers rolled is less than or equal to 3.
b. Find the probability that the sum of the numbers rolled is greater than 3.

**Solution**

The first step is to identify the sample space, which consists of all the possible outcomes. There are two number cubes, and each number cube has six possible outcomes. Using the Multiplication Principle, we find that there are $6 \times 6$, or 36 total possible outcomes. So, for example, $1-1$ represents a 1 rolled on each number cube.

| | | | | | |
|---|---|---|---|---|---|
| $1-1$ | $1-2$ | $1-3$ | $1-4$ | $1-5$ | $1-6$ |
| $2-1$ | $2-2$ | $2-3$ | $2-4$ | $2-5$ | $2-6$ |
| $3-1$ | $3-2$ | $3-3$ | $3-4$ | $3-5$ | $3-6$ |
| $4-1$ | $4-2$ | $4-3$ | $4-4$ | $4-5$ | $4-6$ |
| $5-1$ | $5-2$ | $5-3$ | $5-4$ | $5-5$ | $5-6$ |
| $6-1$ | $6-2$ | $6-3$ | $6-4$ | $6-5$ | $6-6$ |

a. We need to count the number of ways to roll a sum of 3 or less. These would include the following outcomes: $1-1$, $1-2$, and $2-1$. So there are only three ways to roll a sum of 3 or less. The probability is

$$\frac{3}{36} = \frac{1}{12}$$

b. Rather than listing all the possibilities, we can use the Complement Rule. Because we have already found the probability of the complement of this event, we can simply subtract that probability from 1 to find the probability that the sum of the numbers rolled is greater than 3.

$$\begin{aligned} P(E') &= 1 - P(E) \\ &= 1 - \frac{1}{12} \\ &= \frac{11}{12} \end{aligned}$$

### Exercise 9.11.4:

Two number cubes are rolled. Use the Complement Rule to find the probability that the sum is less than 10.

**Answer**

$\frac{5}{6}$

## Computing Probability Using Counting Theory

Many interesting probability problems involve counting principles, permutations, and combinations. In these problems, we will use permutations and combinations to find the number of elements in events and sample spaces. These problems can be complicated, but they can be made easier by breaking them down into smaller counting problems.

Assume, for example, that a store has 8 cellular phones and that 3 of those are defective. We might want to find the probability that a couple purchasing 2 phones receives 2 phones that are not defective. To solve this problem, we need to calculate all of the ways to select 2 phones that are not defective as well as all of the ways to select 2 phones. There are 5 phones that are not defective, so there are $C(5,2)$ ways to select 2 phones that are not defective. There are 8 phones, so there are $C(8,2)$ ways to select 2 phones. The probability of selecting 2 phones that are not defective is:

$$\begin{aligned} \frac{\text{ways to select 2 phones that are not defective}}{\text{ways to select 2 phones}} &= \frac{C(5,2)}{C(8,2)} \\ &= \frac{10}{28} \\ &= \frac{5}{14} \end{aligned}$$

### Example 9.11.5: Computing Probability Using Counting Theory

A child randomly selects 5 toys from a bin containing 3 bunnies, 5 dogs, and 6 bears.

a. Find the probability that only bears are chosen.
b. Find the probability that 2 bears and 3 dogs are chosen.
c. Find the probability that at least 2 dogs are chosen.

**Solution**

a. We need to count the number of ways to choose only bears and the total number of possible ways to select 5 toys. There are 6 bears, so there are $C(6,5)$ ways to choose 5 bears. There are 14 toys, so there are $C(14,5)$ ways to choose any 5 toys.

$$\frac{C(6,5)}{C(14,5)} = \frac{6}{2,002} = \frac{3}{1,001}$$

b. We need to count the number of ways to choose 2 bears and 3 dogs and the total number of possible ways to select 5 toys. There are 6 bears, so there are $C(6,2)$ ways to choose 2 bears. There are 5 dogs, so there are $C(5,3)$ ways to choose 3 dogs. Since we are choosing both bears and dogs at the same time, we will use the Multiplication Principle. There are $C(6,2) \cdot C(5,3)$ ways to choose 2 bears and 3 dogs. We can use this result to find the probability.

$$\frac{C(6,2)C(5,3)}{C(14,5)} = \frac{15 \cdot 10}{2,002} = \frac{75}{1,001}$$

c. It is often easiest to solve "at least" problems using the Complement Rule. We will begin by finding the probability that fewer than 2 dogs are chosen. If less than 2 dogs are chosen, then either no dogs could be chosen, or 1 dog could be chosen.

When no dogs are chosen, all 5 toys come from the 9 toys that are not dogs. There are $C(9,5)$ ways to choose toys from the 9 toys that are not dogs. Since there are 14 toys, there are $C(14,5)$ ways to choose the 5 toys from all of the toys.

$$\frac{C(9,5)}{C(14,5)} = \frac{63}{1,001}$$

If there is 1 dog chosen, then 4 toys must come from the 9 toys that are not dogs, and 1 must come from the 5 dogs. Since we are choosing both dogs and other toys at the same time, we will use the Multiplication Principle. There are $C(5,1)\cdot C(9,4)$ ways to choose 1 dog and 1 other toy.

$$\frac{C(5,1)C(9,4)}{C(14,5)}=\frac{5\cdot 126}{2,002}=\frac{315}{1,001}$$

Because these events would not occur together and are therefore mutually exclusive, we add the probabilities to find the probability that fewer than 2 dogs are chosen.

$$\frac{63}{1,001}+\frac{315}{1,001}=\frac{378}{1,001}$$

We then subtract that probability from 1 to find the probability that at least 2 dogs are chosen.

$$1-\frac{378}{1,001}=\frac{623}{1,001}$$

**? Exercise 9.11.5**

A child randomly selects 3 gumballs from a container holding 4 purple gumballs, 8 yellow gumballs, and 2 green gumballs.

a. Find the probability that all 3 gumballs selected are purple.
b. Find the probability that no yellow gumballs are selected.
c. Find the probability that at least 1 yellow gumball is selected.

**Answer**

$\frac{1}{91}$

**Answer**

$\frac{5}{91}$

**Answer**

$\frac{86}{91}$

**Media**

Access these online resources for additional instruction and practice with probability.

- Introduction to Probability
- Determining Probability

Visit this website for additional practice questions from Learningpod.

## Key Equations

| | |
|---|---|
| probability of an event with equally likely outcomes | $P(E)=\frac{n(E)}{n(S)}$ |
| probability of the union of two events | $P(E\cup F)=P(E)+P(F)-P(E\cap F)$ |
| probability of the union of mutually exclusive events | $P(E\cup F)=P(E)+P(F)$ |
| probability of the complement of an event | $P(E')=1-P(E)$ |

## Key Concepts

- Probability is always a number between 0 and 1, where 0 means an event is impossible and 1 means an event is certain.
- The probabilities in a probability model must sum to 1. See Example 9.11.1
- When the outcomes of an experiment are all equally likely, we can find the probability of an event by dividing the number of outcomes in the event by the total number of outcomes in the sample space for the experiment. See Example 9.11.2
- To find the probability of the union of two events, we add the probabilities of the two events and subtract the probability that both events occur simultaneously. See Example 9.11.3
- To find the probability of the union of two mutually exclusive events, we add the probabilities of each of the events. See Example 9.11.4
- The probability of the complement of an event is the difference between 1 and the probability that the event occurs. See Example 9.11.5
- In some probability problems, we need to use permutations and combinations to find the number of elements in events and sample spaces. See Example 9.11.6

## Contributors and Attributions

- Jay Abramson (Arizona State University) with contributing authors. Textbook content produced by OpenStax College is licensed under a Creative Commons Attribution License 4.0 license. Download for free at https://openstax.org/details/books/precalculus.

This page titled 9.11: Probability is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.7: Probability** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# 9.11E: Probability (Exercises)

For the following exercises, assume two die are rolled.

47. Construct a table showing the sample space.

48. What is the probability that a roll includes a 2?

49. What is the probability of rolling a pair?

50. What is the probability that a roll includes a 2 or results in a pair?

51. What is the probability that a roll doesn't include a 2 or result in a pair?

52. What is the probability of rolling a 5 or a 6?

53. What is the probability that a roll includes neither a 5 nor a 6?

For the following exercises, use the following data: An elementary school survey found that 350 of the 500 students preferred soda to milk. Suppose 8 children from the school are attending a birthday party. (Show calculations and round to the nearest tenth of a percent.)

54. What is the percent chance that all the children attending the party prefer soda?

55. What is the percent chance that at least one of the children attending the party prefers milk?

56. What is the percent chance that exactly 3 of the children attending the party prefer soda?

57. What is the percent chance that exactly 3 of the children attending the party prefer milk?

This page titled 9.11E: Probability (Exercises) is shared under a CC BY 4.0 license and was authored, remixed, and/or curated by OpenStax via source content that was edited to the style and standards of the LibreTexts platform.

- **13.7E: Probability (Exercises)** by OpenStax is licensed CC BY 4.0. Original source: https://openstax.org/details/books/precalculus.

# Index


## A

A system of linear equations
6.2: Systems of Linear Equations - Two Variables
absolute value equation
3.8: Absolute Value Functions
absolute value equations
2.6: Other Types of Equations
Absolute Value Function
2.8.1: Linear Inequalities
Absolute Value Inequalities
2.8.1: Linear Inequalities
absolute value inequality
3.8: Absolute Value Functions
addition principle
9.9: Counting Principles
algebraic expression
1.2: Real Numbers - Algebra Essentials
annual percentage interest (APR)
8.5: Series and Their Notations
Annuity Problems
8.5: Series and Their Notations
arithmetic sequence
8.3: Arithmetic Sequences
8.5: Series and Their Notations
arithmetic series
8.5: Series and Their Notations
associative property of addition
1.2: Real Numbers - Algebra Essentials
associative property of multiplication
1.2: Real Numbers - Algebra Essentials
augmented matrix
6.5: Solving Systems with Gaussian Elimination
average rate of change
3.4: Rates of Change and Behavior of Graphs
axis of symmetry
4.2: Quadratic Functions

## B

base
1.2: Real Numbers - Algebra Essentials
binomial coefficients
9.10: Binomial Theorem
binomial theorem
9.10: Binomial Theorem

## C

coefficient
4.3: Power Functions and Polynomial Functions
combinations
9.9: Counting Principles
common difference
8.3: Arithmetic Sequences
8.5: Series and Their Notations
common logarithms
5.4: Logarithmic Functions
common ratio
8.4: Geometric Sequences
8.5: Series and Their Notations
commutative property of addition
1.2: Real Numbers - Algebra Essentials
complement rule
9.11: Probability
completing the square
2.5: Quadratic Equations
complex number
2.4: Complex Numbers
complex plane
2.4: Complex Numbers
Complex rational expressions
1.7: Rational Expressions
composite function
3.6: Composition of Functions
Compound Inequalities
2.8.1: Linear Inequalities
compression
5.3: Graphs of Exponential Functions
conditional equation
2.3: Linear Equations in One Variable
conics in polar form
9.8: Conic Sections in Polar Coordinates
constant
1.2: Real Numbers - Algebra Essentials
constant ratio
9.2: Modeling Using Variation
Continuous decay model
5.2: Exponential Functions
continuous function
4.3: Power Functions and Polynomial Functions
Continuous growth model
5.2: Exponential Functions
correlation coefficient
3.5.5: Fitting Linear Models to Data
3.5.E: Linear Functions(Exercises)
3.5.R: Linear Functions(Review)
Counting Theory
9.11: Probability
Cramer's Rule
9.6: Solving Systems with Cramer's Rule

## D

decreasing linear function
3.5.2: Linear Functions
degenerate conic sections
9.7: Rotation of Axes
degree
4.3: Power Functions and Polynomial Functions
degree of a polynomial
1.5: Polynomials
dependent system
6.2: Systems of Linear Equations - Two Variables
dependent variable
3.2: Functions and Function Notation
Descartes' Rule of Signs
4.6: Zeros of Polynomial Functions
determinants
9.6: Solving Systems with Cramer's Rule
Difference of Cubes
1.6: Factoring Polynomials
Difference of Squares
1.5: Polynomials
1.6: Factoring Polynomials
Dimensions of a Matrix
9.4: Matrices and Matrix Operations
direct variation
9.2: Modeling Using Variation
directrix
9.8: Conic Sections in Polar Coordinates
discriminant
2.5: Quadratic Equations
distance formula
2.2: The Rectangular Coordinate Systems and Graphs
distributive property
1.2: Real Numbers - Algebra Essentials
division algorithm
4.5: Dividing Polynomials
domain
3.2: Functions and Function Notation
domain of a logarithmic function
5.5: Graphs of Logarithmic Functions

## E

eccentricity
9.8: Conic Sections in Polar Coordinates
ellipses
7.3: The Ellipse
end behavior
4.3: Power Functions and Polynomial Functions
equation
1.2: Real Numbers - Algebra Essentials
equation in two variables
2.2: The Rectangular Coordinate Systems and Graphs
even function
3.7: Transformation of Functions
exponent
1.2: Real Numbers - Algebra Essentials
exponential equations
5.4: Logarithmic Functions
5.7: Exponential and Logarithmic Equations
exponential function
5.8: Exponential and Logarithmic Models
exponential model
5.2: Exponential Functions
Exponential Notation
1.2: Real Numbers - Algebra Essentials
1.3: Exponents and Scientific Notation
exponential regression
5.9: Fitting Exponential Models to Data
exponentials
5.2: Exponential Functions
extrapolation
3.5.5: Fitting Linear Models to Data
3.5.E: Linear Functions(Exercises)
3.5.R: Linear Functions(Review)
extrema
3.4: Rates of Change and Behavior of Graphs

## F

Factor Theorem
4.6: Zeros of Polynomial Functions
foci
7.3: The Ellipse

focus
9.8: Conic Sections in Polar Coordinates
FOIL
1.5: Polynomials
formula
1.2: Real Numbers - Algebra Essentials
function
3.2: Functions and Function Notation
Fundamental Theorem of Algebra
4.6: Zeros of Polynomial Functions

G
Gaussian elimination
6.5: Solving Systems with Gaussian Elimination
general form of a quadratic function
4.2: Quadratic Functions
Geometric Sequences
8.4: Geometric Sequences
global maximum
4.4: Graphs of Polynomial Functions
global minimum
4.4: Graphs of Polynomial Functions
Graph an Ellipse with Center at the Origin
7.3: The Ellipse
Graph an Ellipse with Center Not at the Origin
7.3: The Ellipse
graph in two variables
2.2: The Rectangular Coordinate Systems and Graphs
Graphing Hyperbolas Centered at the Origin
7.4: The Hyperbola
Graphing Hyperbolas Not Centered at the Origin
7.4: The Hyperbola
Graphing Reflections
5.3: Graphs of Exponential Functions
greatest common factor
1.6: Factoring Polynomials
grouping method
2.5: Quadratic Equations

H
Heaviside method
9.3: Partial Fractions
horizontal asymptote
4.7: Rational Functions
horizontal compression
3.7: Transformation of Functions
horizontal line
2.3: Linear Equations in One Variable
3.5.3: Graphs of Linear Functions
horizontal line test
3.2: Functions and Function Notation
horizontal reflection
3.7: Transformation of Functions
horizontal shift
3.7: Transformation of Functions
horizontal stretch
3.7: Transformation of Functions
Hyperbolas
7.4: The Hyperbola

I
identity equation
2.3: Linear Equations in One Variable
identity matrix
9.5: Solving Systems with Inverses
identity property of addition
1.2: Real Numbers - Algebra Essentials
identity property of multiplication
1.2: Real Numbers - Algebra Essentials
imaginary axis
2.4: Complex Numbers
inconsistent equation
2.3: Linear Equations in One Variable
inconsistent system
6.2: Systems of Linear Equations - Two Variables
increasing linear function
3.5.2: Linear Functions
independent system
6.2: Systems of Linear Equations - Two Variables
independent variable
3.2: Functions and Function Notation
inequalities
6.4: Systems of Nonlinear Equations and Inequalities - Two Variables
infinite sequence
8.2: Sequences and Their Notations
infinite series
8.5: Series and Their Notations
input
3.2: Functions and Function Notation
integers
1.2: Real Numbers - Algebra Essentials
intercepts
2.2: The Rectangular Coordinate Systems and Graphs
Intermediate Value Theorem
4.4: Graphs of Polynomial Functions
interpolation
3.5.5: Fitting Linear Models to Data
3.5.E: Linear Functions(Exercises)
3.5.R: Linear Functions(Review)
Interval Notation
2.8.1: Linear Inequalities
3.3: Domain and Range
inverse
3.9: Inverse Functions
inverse function
3.9: Inverse Functions
inverse of a matrix
9.5: Solving Systems with Inverses
inverse of a quadratic function
9.1: Inverses and Radical Functions
inverse property of addition
1.2: Real Numbers - Algebra Essentials
inverse property of multiplication
1.2: Real Numbers - Algebra Essentials
inverse variation
9.2: Modeling Using Variation
invertible
9.1: Inverses and Radical Functions
irrational numbers
1.2: Real Numbers - Algebra Essentials

J
joint variation
9.2: Modeling Using Variation

L
leading coefficient
4.3: Power Functions and Polynomial Functions
least common denominator
2.3: Linear Equations in One Variable
least squares regression line
3.5.5: Fitting Linear Models to Data
3.5.E: Linear Functions(Exercises)
3.5.R: Linear Functions(Review)
Line of Best Fit
3.5.5: Fitting Linear Models to Data
3.5.E: Linear Functions(Exercises)
3.5.R: Linear Functions(Review)
linear equation
2.7.1: Models and Applications
Linear Factorization Theorem
4.6: Zeros of Polynomial Functions
linear function
3.5.2: Linear Functions
3.5.4: Modeling with Linear Functions
linear model
3.5.4: Modeling with Linear Functions
local extrema
3.4: Rates of Change and Behavior of Graphs
local maximum
3.4: Rates of Change and Behavior of Graphs
local minimum
3.4: Rates of Change and Behavior of Graphs
logarithmic equations
5.4: Logarithmic Functions
Logarithmic Function
5.4: Logarithmic Functions
logarithmic functions
5.5: Graphs of Logarithmic Functions
logarithmic regression
5.9: Fitting Exponential Models to Data
logistic growth functions
5.8: Exponential and Logarithmic Models
logistic regression
5.9: Fitting Exponential Models to Data

M
major axis
7.3: The Ellipse
Mandelbrot set
2.4: Complex Numbers
matrix addition
9.4: Matrices and Matrix Operations
matrix multiplication
9.4: Matrices and Matrix Operations
9.5: Solving Systems with Inverses
Matrix Subtraction
9.4: Matrices and Matrix Operations
maxima
3.4: Rates of Change and Behavior of Graphs
maximum
4.4: Graphs of Polynomial Functions
Midpoint Formula
2.2: The Rectangular Coordinate Systems and Graphs

minima
3.4: Rates of Change and Behavior of Graphs
minimum
4.4: Graphs of Polynomial Functions
minor axis
7.3: The Ellipse
model breakdown
3.5.5: Fitting Linear Models to Data
3.5.E: Linear Functions(Exercises)
3.5.R: Linear Functions(Review)
multiplication principle
9.9: Counting Principles
multiplicity
4.4: Graphs of Polynomial Functions

## N

natural logarithms.
5.4: Logarithmic Functions
natural numbers
1.2: Real Numbers - Algebra Essentials
negative numbers
1.2: Real Numbers - Algebra Essentials
Negative rule
1.3: Exponents and Scientific Notation
Newton’s Law of Cooling
5.8: Exponential and Logarithmic Models
nondegenerate conic sections
9.7: Rotation of Axes
nonlinear systems
6.4: Systems of Nonlinear Equations and Inequalities - Two Variables

## O

odd function
3.7: Transformation of Functions
order of operations
1.2: Real Numbers - Algebra Essentials
output
3.2: Functions and Function Notation

## P

parabola
7.2: The Parabola
Parabola with Horizontal Axis
7.2: The Parabola
Parabola with Vertical Axis
7.2: The Parabola
Parallel Line
3.5.3: Graphs of Linear Functions
partial fraction decomposition
9.3: Partial Fractions
partial fractions
9.3: Partial Fractions
Pascal's Triangle
9.10: Binomial Theorem
perfect square trinomial
1.6: Factoring Polynomials
Perfect square trinomials
1.5: Polynomials
permutations
9.9: Counting Principles
perpendicular lines
3.5.3: Graphs of Linear Functions
pH scale
5.6: Logarithmic Properties
piecewise function
3.3: Domain and Range
8.2: Sequences and Their Notations
polynomial
1.5: Polynomials
polynomial function
4.3: Power Functions and Polynomial Functions
population growth
5.7: Exponential and Logarithmic Equations
power function
4.3: Power Functions and Polynomial Functions
Power of a product rule
1.3: Exponents and Scientific Notation
Power of a quotient rule
1.3: Exponents and Scientific Notation
power rule
1.3: Exponents and Scientific Notation
5.6: Logarithmic Properties
power rule for logarithms
5.6: Logarithmic Properties
principal square root
1.4: Radicals and Rational Expressions
probability
9.11: Probability
Probability of Mutually Exclusive Events
9.11: Probability
Probability of the Union of Two Events
9.11: Probability
product rule
1.3: Exponents and Scientific Notation
5.6: Logarithmic Properties
product rule of logarithms
5.6: Logarithmic Properties
properties of exponents
1.3: Exponents and Scientific Notation
Pythagorean Theorem
2.2: The Rectangular Coordinate Systems and Graphs
2.5: Quadratic Equations

## Q

quadratic equations
2.5: Quadratic Equations
quadratic formula
2.5: Quadratic Equations
quotient rule
1.3: Exponents and Scientific Notation
5.6: Logarithmic Properties
quotient rule of logarithms
5.6: Logarithmic Properties

## R

radical expressions
1.4: Radicals and Rational Expressions
radicals
1.4: Radicals and Rational Expressions
range
3.2: Functions and Function Notation
rate of change
3.4: Rates of Change and Behavior of Graphs
Rational Exponents
1.4: Radicals and Rational Expressions
2.6: Other Types of Equations
Rational expressions
1.7: Rational Expressions
rational function’s end behavior
4.7: Rational Functions
rational numbers
1.2: Real Numbers - Algebra Essentials
Rational Zero Theorem
4.6: Zeros of Polynomial Functions
real number line
1.2: Real Numbers - Algebra Essentials
real numbers
1.2: Real Numbers - Algebra Essentials
recurrence relation
8.4: Geometric Sequences
regression
3.5.5: Fitting Linear Models to Data
3.5.E: Linear Functions(Exercises)
3.5.R: Linear Functions(Review)
5.9: Fitting Exponential Models to Data
relation
3.2: Functions and Function Notation
Remainder Theorem
4.6: Zeros of Polynomial Functions
removable discontinuity
4.7: Rational Functions
rotation of a conic section
9.7: Rotation of Axes
Rotation of Axes
9.7: Rotation of Axes
row operations
6.5: Solving Systems with Gaussian Elimination

## S

scatter plot
3.5.5: Fitting Linear Models to Data
3.5.E: Linear Functions(Exercises)
3.5.R: Linear Functions(Review)
scientific notation
1.3: Exponents and Scientific Notation
sequences
8.2: Sequences and Their Notations
sigma notation
8.5: Series and Their Notations
slope
2.3: Linear Equations in One Variable
3.5.2: Linear Functions
smooth curve
4.3: Power Functions and Polynomial Functions
solution set
6.3: Systems of Linear Equations with Three Variables
spaghetti models
9.11: Probability
square root function
2.4: Complex Numbers
9.1: Inverses and Radical Functions
standard form of a parabola
7.2: The Parabola
standard form of a quadratic function
4.2: Quadratic Functions
stretch
5.3: Graphs of Exponential Functions
substitution method
6.2: Systems of Linear Equations - Two Variables

Sum of Cubes
1.6: Factoring Polynomials
synthetic division
4.5: Dividing Polynomials

T
tabular function
3.9: Inverse Functions
term of a polynomial function
4.3: Power Functions and Polynomial Functions
the grouping method
2.5: Quadratic Equations
the quadratic formula
2.5: Quadratic Equations
translations of the exponential function
5.3: Graphs of Exponential Functions
turning point
4.3: Power Functions and Polynomial Functions

V
variable
1.2: Real Numbers - Algebra Essentials
vertex
4.2: Quadratic Functions
vertex form of a quadratic function
4.2: Quadratic Functions
vertical asymptotes
4.7: Rational Functions
vertical compression
3.7: Transformation of Functions
vertical line
2.3: Linear Equations in One Variable
3.5.3: Graphs of Linear Functions
vertical line test
3.2: Functions and Function Notation
vertical reflection
3.7: Transformation of Functions
vertical shift
3.7: Transformation of Functions
5.3: Graphs of Exponential Functions
vertical stretch
3.7: Transformation of Functions

W
whispering chamber
7.3: The Ellipse
whole numbers
1.2: Real Numbers - Algebra Essentials

Z
Zero exponent rule
1.3: Exponents and Scientific Notation
zeros
4.2: Quadratic Functions

# Glossary

**Sample Word 1** | Sample Definition 1

# Detailed Licensing

## Overview

**Title:** Book: College Algebra

**Webpages:** 161

**All licenses found:**

- CC BY 4.0: 91.3% (147 pages)
- Undeclared: 8.7% (14 pages)

## By Page


- Book: College Algebra - *CC BY 4.0*
  - Front Matter - *Undeclared*
    - TitlePage - *Undeclared*
    - InfoPage - *Undeclared*
    - Table of Contents - *Undeclared*
    - Licensing - *Undeclared*
  - 1: Prerequisites - *CC BY 4.0*
    - 1.1: Prelude to Prerequisites - *CC BY 4.0*
    - 1.2: Real Numbers - Algebra Essentials - *CC BY 4.0*
      - 1.2E: Real Numbers - Algebra Essentials (Exercises) - *CC BY 4.0*
    - 1.3: Exponents and Scientific Notation - *CC BY 4.0*
      - 1.3E: Exponents and Scientific Notation (Exercises) - *CC BY 4.0*
    - 1.4: Radicals and Rational Expressions - *CC BY 4.0*
      - 1.4E: Radicals and Rational Expressions (Exercise) - *CC BY 4.0*
    - 1.5: Polynomials - *CC BY 4.0*
      - 1.5E: Polynomials (Exercises) - *CC BY 4.0*
    - 1.6: Factoring Polynomials - *CC BY 4.0*
      - 1.6E: Factoring Polynomials (Exercises) - *CC BY 4.0*
    - 1.7: Rational Expressions - *CC BY 4.0*
      - 1.7E: Rational Expressions (Exercises) - *CC BY 4.0*
  - 2: Equations and Inequalities - *CC BY 4.0*
    - 2.1: Prelude to Equations and Inequalities - *CC BY 4.0*
    - 2.2: The Rectangular Coordinate Systems and Graphs - *CC BY 4.0*
      - 2.2E: The Rectangular Coordinate Systems and Graphs (Exercises) - *CC BY 4.0*
    - 2.3: Linear Equations in One Variable - *CC BY 4.0*
      - 2.3E: Linear Equations in One Variable (Exercises) - *CC BY 4.0*
    - 2.4: Complex Numbers - *CC BY 4.0*
      - 2.4E: Complex Numbers (Exercises) - *CC BY 4.0*
    - 2.5: Quadratic Equations - *CC BY 4.0*
      - 2.5E: Quadratic Equations (Exercises) - *CC BY 4.0*
    - 2.6: Other Types of Equations - *CC BY 4.0*
      - 2.6E: Other Types of Equations (Exercises) - *CC BY 4.0*
    - 2.7: Modeling with Equations - *Undeclared*
      - 2.7.1: Models and Applications - *CC BY 4.0*
        - 2.7.1E: Models and Applications (Exercises) - *CC BY 4.0*
      - 2.7.2: Solve Mixture and Uniform Motion Applications - *CC BY 4.0*
        - 2.7.2E: Exercises - *CC BY 4.0*
      - 2.7.3: Solve Applications with Rational Equations - *CC BY 4.0*
        - 2.7.3E: Exercises - *CC BY 4.0*
    - 2.8: Linear and Absolute Value Inequalities - *Undeclared*
      - 2.8.1: Linear Inequalities - *CC BY 4.0*
        - 2.8.1E: Exercises - *CC BY 4.0*
      - 2.8.2: Solve Absolute Value Inequalities - *CC BY 4.0*
        - 2.8.2E: Exercises - *CC BY 4.0*
      - 2.8E: Linear Inequalities and Absolute Value Inequalities (Exercises) - *CC BY 4.0*
  - 3: Functions - *CC BY 4.0*
    - 3.1: Prelude to Functions - *CC BY 4.0*
    - 3.2: Functions and Function Notation - *CC BY 4.0*
      - 3.2E: Functions and Function Notation (Exercises) - *CC BY 4.0*
    - 3.3: Domain and Range - *CC BY 4.0*
      - 3.3E: Domain and Range (Exercises) - *CC BY 4.0*
    - 3.4: Rates of Change and Behavior of Graphs - *CC BY 4.0*

- 3.4E: Rates of Change and Behavior of Graphs (Exercises) - *CC BY 4.0*
- 3.5: Linear Functions - *CC BY 4.0*
  - 3.5.1: Prelude to Linear Functions - *CC BY 4.0*
  - 3.5.2: Linear Functions - *CC BY 4.0*
  - 3.5.3: Graphs of Linear Functions - *CC BY 4.0*
  - 3.5.4: Modeling with Linear Functions - *CC BY 4.0*
  - 3.5.5: Fitting Linear Models to Data - *CC BY 4.0*
  - 3.5.E: Linear Functions(Exercises) - *CC BY 4.0*
  - 3.5.R: Linear Functions(Review) - *CC BY 4.0*
- 3.6: Composition of Functions - *CC BY 4.0*
  - 3.6E: Composition of Functions (Exercises) - *CC BY 4.0*
- 3.7: Transformation of Functions - *CC BY 4.0*
  - 3.7E: Transformation of Functions (Exercises) - *CC BY 4.0*
- 3.8: Absolute Value Functions - *CC BY 4.0*
  - 3.8E: Absolute Value Functions (Exercises) - *CC BY 4.0*
- 3.9: Inverse Functions - *CC BY 4.0*
  - 3.9E: Inverse Functions (Exercises) - *CC BY 4.0*

4: Polynomial and Rational Functions - *CC BY 4.0*
- 4.1: Prelude to Polynomial and Rational Functions - *CC BY 4.0*
- 4.2: Quadratic Functions - *CC BY 4.0*
  - 4.2E: Quadratic Functions (Exercises) - *CC BY 4.0*
- 4.3: Power Functions and Polynomial Functions - *CC BY 4.0*
  - 4.3E: Power Functions and Polynomial Functions (Exercises) - *CC BY 4.0*
- 4.4: Graphs of Polynomial Functions - *CC BY 4.0*
  - 4.4E: Graphs of Polynomial Functions (Exercises) - *CC BY 4.0*
- 4.5: Dividing Polynomials - *CC BY 4.0*
  - 4.5E: Dividing Polynomials (Exercises) - *CC BY 4.0*
- 4.6: Zeros of Polynomial Functions - *CC BY 4.0*
  - 4.6E: Zeros of Polynomial Functions (Exercises) - *CC BY 4.0*
- 4.7: Rational Functions - *CC BY 4.0*
  - 4.7E: Rational Functions (Exercises) - *CC BY 4.0*
- 4.8: Non-linear Inequalities - *Undeclared*
  - 4.8.1: Solve Quadratic Inequalities - *Undeclared*
    - 4.8.1E: Exercises - *CC BY 4.0*
  - 4.8.2: Solve Rational Inequalities - *CC BY 4.0*
    - 4.8.2E: Exercises - *CC BY 4.0*

5: Exponential and Logarithmic Functions - *CC BY 4.0*
- 5.1: Prelude to Exponential and Logarithmic Functions - *CC BY 4.0*
- 5.2: Exponential Functions - *CC BY 4.0*
  - 5.2E: Exponential Functions (Exercises) - *CC BY 4.0*
- 5.3: Graphs of Exponential Functions - *CC BY 4.0*
  - 5.3E: Graphs of Exponential Functions (Exercises) - *CC BY 4.0*
- 5.4: Logarithmic Functions - *CC BY 4.0*
  - 5.4E: Logarithmic Functions (Exercises) - *CC BY 4.0*
- 5.5: Graphs of Logarithmic Functions - *CC BY 4.0*
  - 5.5E: Graphs of Logarithmic Functions (Exercises) - *CC BY 4.0*
- 5.6: Logarithmic Properties - *CC BY 4.0*
  - 5.6E: Logarithmic Properties (Exercises) - *CC BY 4.0*
- 5.7: Exponential and Logarithmic Equations - *CC BY 4.0*
  - 5.7E: Exponential and Logarithmic Equations (Exercises) - *CC BY 4.0*
- 5.8: Exponential and Logarithmic Models - *CC BY 4.0*
  - 5.8E: Exponential and Logarithmic Models (Exercises) - *CC BY 4.0*
- 5.9: Fitting Exponential Models to Data - *CC BY 4.0*
  - 5.9E: Fitting Exponential Models to Data (Exercises) - *CC BY 4.0*

6: Systems of Equations and Inequalities - *CC BY 4.0*
- 6.1: Prelude to Systems of Equations and Inequalities - *CC BY 4.0*
- 6.2: Systems of Linear Equations - Two Variables - *CC BY 4.0*
  - 6.2E: Systems of Linear Equations - Two Variables (Exercises) - *CC BY 4.0*
- 6.3: Systems of Linear Equations with Three Variables - *CC BY 4.0*
  - 6.3E: Systems of Linear Equations with Three Variables (Exercises) - *CC BY 4.0*
- 6.4: Systems of Nonlinear Equations and Inequalities - Two Variables - *CC BY 4.0*
  - 6.4E: Systems of Nonlinear Equations and Inequalities - Two Variables (Exercises) - *CC BY 4.0*
- 6.5: Solving Systems with Gaussian Elimination - *CC BY 4.0*

- 6.5E: Solving Systems with Gaussian Elimination (Exercises) - *CC BY 4.0*

- 7: Analytic Geometry - *CC BY 4.0*
  - 7.1: Prelude to Analytic Geometry - *CC BY 4.0*
  - 7.2: The Parabola - *CC BY 4.0*
    - 7.2E: The Parabola (Exercises) - *CC BY 4.0*
  - 7.3: The Ellipse - *CC BY 4.0*
    - 7.3E: The Ellipse (Exercises) - *CC BY 4.0*
  - 7.4: The Hyperbola - *CC BY 4.0*
    - 7.4E: The Hyperbola (Exercises) - *CC BY 4.0*
- 8: Sequences, Probability, and Counting Theory - *CC BY 4.0*
  - 8.1: Prelude to Sequences, Probability and Counting Theory - *CC BY 4.0*
  - 8.2: Sequences and Their Notations - *CC BY 4.0*
    - 8.2E: Sequences and Their Notations (Exercises) - *CC BY 4.0*
  - 8.3: Arithmetic Sequences - *CC BY 4.0*
    - 8.3E: Arithmetic Sequences (Exercises) - *CC BY 4.0*
  - 8.4: Geometric Sequences - *CC BY 4.0*
    - 8.4E: Geometric Sequences (Exercises) - *CC BY 4.0*
  - 8.5: Series and Their Notations - *CC BY 4.0*
    - 8.5E: Series and Their Notations (Exercises) - *CC BY 4.0*
- 9: Additional Topics for Ch 4, 6, 7 and 8 - *Undeclared*
  - 9.1: Inverses and Radical Functions - *CC BY 4.0*
    - 9.1.1: Inverses and Radical Functions (Exercises) - *CC BY 4.0*
  - 9.2: Modeling Using Variation - *CC BY 4.0*
    - 9.2E: Modeling Using Variation (Exercises) - *CC BY 4.0*
  - 9.3: Partial Fractions - *CC BY 4.0*
    - 9.3.1: Partial Fractions (Exercises) - *CC BY 4.0*
  - 9.4: Matrices and Matrix Operations - *CC BY 4.0*
    - 9.4E: Matrices and Matrix Operations (Exercises) - *CC BY 4.0*
  - 9.5: Solving Systems with Inverses - *CC BY 4.0*
    - 9.5E: Solving Systems with Inverses (Exercises) - *CC BY 4.0*
  - 9.6: Solving Systems with Cramer's Rule - *CC BY 4.0*
    - 9.6E: Solving Systems with Cramer's Rule (Exercises) - *CC BY 4.0*
  - 9.7: Rotation of Axes - *CC BY 4.0*
    - 9.7E: Rotation of Axes (Exercises) - *CC BY 4.0*
  - 9.8: Conic Sections in Polar Coordinates - *CC BY 4.0*
    - 9.8E: Conic Sections in Polar Coordinates (Exercises) - *CC BY 4.0*
  - 9.9: Counting Principles - *CC BY 4.0*
    - 9.9E: Counting Principles (Exercises) - *CC BY 4.0*
  - 9.10: Binomial Theorem - *CC BY 4.0*
    - 9.10E: Binomial Theorem (Exercises) - *CC BY 4.0*
  - 9.11: Probability - *CC BY 4.0*
    - 9.11E: Probability (Exercises) - *CC BY 4.0*
- Back Matter - *Undeclared*
  - Index - *Undeclared*
  - Glossary - *Undeclared*
  - Detailed Licensing - *Undeclared*